CERTIFIED MAIL – RETURN RECEIPT REQUESTED

October 8, 2026

Jason Sanchez, Receiver
Yah-ta-hey Water and Sanitation District
P.O. Box 4128
Yahtahey, New Mexico 87375

RE: Draft Discharge Permit Renewal, DP-792, Yah-ta-hey Water and Sanitation District

Dear Jason Sanchez:

The New Mexico Environment Department (NMED) hereby provides notice to you of the proposed approval of Ground Water Discharge Permit Renewal, DP-792, (copy enclosed), pursuant to Subsection H of 20.6.2.3108 NMAC. NMED will publish notice of the availability of the draft Discharge Permit in the near future for public review and comment and will forward a copy of that notice to you.

Prior to making a final ruling on the proposed Discharge Permit, NMED will allow 30 days from the date the public notice is published in the newspaper for any interested party, including the Discharge Permit applicant, i.e., yourself, to submit written comments and/or a request a public hearing. A hearing request shall set forth the reasons why a hearing is requested. NMED will hold a hearing in response to a timely hearing request if the NMED Secretary determines there is substantial public interest in the proposed Discharge Permit.

Please review the enclosed draft Discharge Permit carefully. Please be aware that this Discharge Permit may contain conditions that require the permittee to implement operational, monitoring or closure actions by a specified deadline.

Please submit written comments or a request for hearing to my attention at the address below, via email to deborah.carpenter@env.nm.gov or to pps.general@env.nm.gov, or directly into the NMED Public Comment Portal at https://nmed.commentinput.com/comment/search. If NMED does not receive written comments or a request for hearing during the public comment period, the draft Discharge Permit will become final.

Thank you for your cooperation during the review process. Feel free to contact me with any questions at (505) 531-7430.

Sincerely,

Deborah Carpenter
Digitally signed by Deborah Carpenter
Date: 2026.10.08 16:42:11 -06'00'

Deborah Carpenter, Senior Water Resource Professional

Encl: Draft Discharge Permit Renewal, DP-792

cc: Brian Bennon, UOCP Program Manager
Damon Reyes, EHB District 1 Manager
Teresa Stephens, Facility Operator

NEW MEXICO
ENVIRONMENT DEPARTMENT
Ground Water Quality Bureau
1190 Saint Francis Drive / PO Box 5469
Santa Fe, NM 87502-5469
Phone (505) 827-2900 Fax (505) 827-2965
www.env.nm.gov

Draft: October 2026

GROUND WATER QUALITY BUREAU
DISCHARGE PERMIT
Issued under 20.6.2 NMAC

Facility Name:	Yah-ta-hey Water and Sanitation District
Discharge Permit Number:	DP-792
Facility Location:	End of South La Bah Drive, 0.9 miles southeast of the intersection of Routes 491 and 264 Yahtahey, New Mexico 87375
County:	McKinley
Permittee: Mailing Address:	Yah-ta-hey Water and Sanitation District P.O. Box 4128 Yah-ta-hey, New Mexico 87375
Facility Contact: Telephone Number/Email:	Jason Sanchez 505-339-1158 / jason.sanchez@pinnbank.com
Permitting Action:	Renewal
Permit Issuance Date:	DATE
Permit Expiration Date:	
NMED Permit Contact: Telephone Number/Email:	Deborah Carpenter 505-531-7430 / deborah.carpenter@env.nm.gov or 505-827-2900 / pps.general@env.nm.gov

JUSTIN D. BALL
Chief, Ground Water Quality Bureau
New Mexico Environment Department

draft

TABLE OF CONTENTS

I. INTRODUCTION 1

II. FINDINGS 3

III. AUTHORIZATION TO DISCHARGE 3

IV. CONDITIONS 3

A. OPERATIONAL PLAN 3

Operational Actions with Implementation Deadlines 4

Operating Conditions 6

B. MONITORING AND REPORTING 8

Due Dates for Monitoring Reports 8

Groundwater Monitoring Conditions 8

Facility Monitoring Conditions 12

C. CONTINGENCY PLAN 12

D. CLOSURE PLA 17

Closure Actions with Implementation Deadlines 17

Permanent Facility Closure Conditions 20

E. GENERAL TERMS AND CONDITIONS 22

ATTACHMENTS

Discharge Permit Summary
Groundwater Discharge Permit Guidance for Synthetically Lined Lagoons – Liner Material and Site Preparation, Revision 0.0, May 2007
New Mexico Environment Department Ground Water Quality Bureau Monitoring Well Construction and Abandonment Guidelines, Revision 1.1, March 2011 (Monitoring Well Guidance)
New Mexico Environment Department – Ground Water Quality Bureau Guidance: How to Sample a Monitoring Well
Groundwater Monitoring Worksheet and Reference Chart

draft

I. INTRODUCTION

The New Mexico Environment Department (NMED) issues this groundwater discharge permit Renewal (Discharge Permit or DP-792) to the Yah-ta-hey Water and Sanitation District (Permittee) pursuant to the New Mexico Water Quality Act (WQA), NMSA 1978 §§74-6-1 through 74-6-17, and the New Mexico Water Quality Control Commission (WQCC) Ground and Surface Water Protection Regulations, 20.6.2 NMAC.

NMED's purpose in issuing this Discharge Permit, and in imposing the requirements and conditions specified herein, is to control the discharge of water contaminants from Yah-ta-hey Water and Sanitation District Wastewater Treatment Facility (Facility) in order to protect groundwater and those segments of surface water gaining from groundwater inflow for present and potential future use as domestic and agricultural water supply and other uses, and to protect public health. It is NMED's determination in issuing this Discharge Permit that the Permittee has met the requirements of Subsection C of 20.6.2.3109 NMAC. The Permittee is responsible for complying with the terms and conditions of this Discharge Permit pursuant to Section 20.6.2.3104 NMAC; failure to do so may result in enforcement action by NMED (20.6.2.1220 NMAC).

Described below are the activities that produce the discharge, the location of the discharge, and the quantity, quality, and flow characteristics.

The Facility discharges up to 37,190 gallons per day (gpd) of domestic wastewater to a synthetically lined treatment impoundment followed by four unlined impoundments for disposal by evaporation.

Data collected from an on-site monitoring well document groundwater contamination attributed to one or more sources at this Facility. The on-site monitoring well has exceedances of groundwater quality standards for nitrates according to the criteria of Sections 20.6.2.3101 and 20.6.2.3103 NMAC. This Discharge Permit contains requirements, actions and/or contingencies intended to address the source(s) of documented groundwater contamination.

Discharge Permit Location Information:

Physical Address	End of South La Bah Road, approx. 0.9 miles southeast of the intersection of Routes 491 and 264
Nearest Town/City	Yah-ta-hey
Section, Township, Range	Section 13, Township 16 North, Range 19 West
County	McKinley
Depth to Groundwater	38 feet
Pre-Discharge TDS	1990 mg/L

Discharge Permit Issuance History:

draft

Original Permit Issuance	April 1996
Permit Renewal	February 2002
Permit Renewal	June 2018

The application (i.e., discharge plan) associated with this Discharge Permit consists of the materials submitted by the Permittee dated December 4, 2023, and materials contained in the administrative record prior to the issuance of this Discharge Permit.

The Permittee shall manage the discharge in accordance with all conditions and requirements of this Discharge Permit.

NMED reserves the right to require a Discharge Permit modification in the event NMED determines that the Permittee is or may be violating, or is likely to violate in the future, the requirements of 20.6.2 NMAC or the standards of Section 20.6.2.3103 NMAC. NMED reserves this right pursuant to Section 20.6.2.3109 NMAC. An NMED requirement to modify the Discharge Permit may result from a determination by the department that structural controls and/or management practices approved under this Discharge Permit are insufficiently protective of groundwater quality and human health. NMED reserves the right to require the Permittee to implement abatement of water pollution and remediate groundwater quality.

NMED issuance of this Discharge Permit does not relieve the Permittee of the responsibility to comply with the WQA, WQCC Regulations, and any other applicable federal, state and/or local laws and regulations, such as zoning requirements and nuisance ordinances.

This Discharge Permit may use the following acronyms and abbreviations.

Abbreviation	Explanation		Abbreviation	Explanation
BOD_5	biochemical oxygen demand (5-day)		NMED	New Mexico Environment Department
CAP	Corrective Action Plan		NMSA	New Mexico Statutes Annotated
CFR	Code of Federal Regulations		NO_3-N	nitrate-nitrogen
CFU	colony forming unit		NTU	nephelometric turbidity units
Cl	chloride		QA/QC	Quality Assurance/Quality Control
EPA	United States Environmental Protection Agency		TDS	total dissolved solids
Gpd	gallons per day		TKN	total Kjeldahl nitrogen
LAA	land application area		total nitrogen	= TKN + NO_3-N
LADS	Land Application Data Sheet(s)		TRC	total residual chlorine
mg/L	milligrams per liter		TSS	total suspended solids
mL	milliliters		WQA	New Mexico Water Quality Act

draft

Abbreviation	Explanation		Abbreviation	Explanation
MPN	most probable number		WQCC	Water Quality Control Commission
NMAC	New Mexico Administrative Code		WWTF	Wastewater Treatment Facility

II. FINDINGS

In issuing this Discharge Permit, NMED finds the following.

1. The Permittee is discharging effluent or leachate from the Facility so that such effluent or leachate may move into groundwater of the State of New Mexico that has an existing concentration of 10,000 mg/L or less of TDS, within the meaning of Subsection A of 20.6.2.3101 NMAC, without exceeding standards of 20.6.2.3103 NMAC for any water contaminant.

2. The Permittee is discharging effluent or leachate from the Facility directly or indirectly into groundwater pursuant to this Discharge Permit and Sections 20.6.2.3000 through 20.6.2.3114 NMAC.

3. The discharge from this Facility has the potential to contain water contaminants or toxic pollutants elevated above the standards of Section 20.6.2.3103 NMAC and is not subject to the exemption at Subsection 20.6.2.3105 NMAC.

III. AUTHORIZATION TO DISCHARGE

The Permittee is responsible for ensuring that discharges authorized by this Discharge Permit are consistent with the terms and conditions herein pursuant to 20.6.2.3104 NMAC.

This Discharge Permit authorizes the Permittee to discharge domestic wastewater up to 37,190 gallons per day (gpd) of domestic wastewater. This Discharge Permit authorizes the Permittee to discharge to a synthetically lined and unlined impoundment system for disposal by evaporation.

[20.6.2.3104 NMAC, Subsection C of 20.6.2.3106 NMAC, Subsection D of 20.6.2.3109 NMAC]

IV. CONDITIONS

NMED issues this Discharge Permit for the discharge of water contaminants subject to the following conditions.

A. OPERATIONAL PLAN

draft

#	Terms and Conditions
1.	The Permittee shall implement the following operational plan to ensure compliance with Title 20, Chapter 6, Parts 2 and 4 NMAC. [Subsection C of 20.6.2.3109 NMAC]
2.	The Permittee shall operate in a manner that does not violate standards and requirements of Sections 20.6.2.3101 and 20.6.2.3103 NMAC. [20.6.2.3101 NMAC, 20.6.2.3103 NMAC, Subsection C of 20.6.2.3109 NMAC]

Operational Actions with Implementation Deadlines

#	Terms and Conditions
3.	During the development of construction plans and specifications for the proposed synthetic re-lining of the Facultative Impoundment, the Permittee shall submit construction plans and specifications at 50% and 95%, or equivalent, level of design to NMED for review for Discharge Permit compliance and comment. [Subsections A and C of 20.6.2.1202 NMAC, Subsection C of 20.6.2.3106 NMAC, Subsection C of 20.6.2.3107 NMAC, NMSA 1978, §§ 61-23-1 through 61-23-32]
4.	Within two years following the issuance date of this Discharge Permit (**by DATE**), the Permittee shall submit final construction plans and specifications for the synthetic re-lining of the Facultative Impoundment for NMED's review. The construction plans and specifications shall bear the seal and signature of a licensed New Mexico professional engineer (pursuant to New Mexico Engineering and Surveying Practice Act and the rules promulgated under that authority) and shall include the supporting design calculations. The submitted documentation shall include the following elements. a) Details for the construction of the Facultative Impoundment and a liner consistent with the attachment titled *Groundwater Discharge Permit Guidance for Synthetically Lined Lagoons – Liner Material and Site Preparation*, Revision 0.0, May 2007. b) Evaporative impoundment capacity and evaporative potential design calculations. The Permittee shall design the impoundment to dispose of the permitted discharge volume by evaporation while preserving two feet of freeboard. Design calculations may consider seasonal discharge patterns. c) Wastewater system component(s) design, e.g., lift stations, valves, transfer lines, process units and associated details; whether new for the new system, retrofitted for the new system, or proposed for abandonment.

draft

#	Terms and Conditions
	d) Flow meter design detail - Flow meters to measure the volume of wastewater discharged to the Facultative Impoundment. e) Specifications for all equipment, materials and installation procedures the Permittee will use in the construction of the wastewater system. f) Fences design detail around the Facultative Impoundment. Prior to constructing the Facultative Impoundment and its associated components, the Permittee shall obtain written verification from NMED that the plans and specifications meet the requirements of this Discharge Permit. [Subsections A and C of 20.6.2.1202 NMAC, Subsection C of 20.6.2.3106 NMAC, Subsection C of 20.6.2.3107 NMAC, NMSA 1978, §§ 61-23-1 through 61-23-32]
5.	Within three years following the issuance date of this Discharge Permit (**by DATE**), the Permittee shall complete the synthetic re-lining of the Facultative Impoundment in accordance with the final construction plans and specifications required by this Discharge Permit. The Permittee shall notify NMED at least five working days prior to commencement of construction to allow NMED personnel to be onsite for inspection. [Subsections A and C of 20.6.2.1202 NMAC, Subsection C of 20.6.2.3109 NMAC, NMSA 1978, §§ 61-23-1 through 61-23-32]
6.	Within 30 days of completion of the synthetic re-lining of the Facultative Impoundment, the Permittee shall submit record drawings to NMED that bear the seal and signature of a licensed New Mexico professional engineer (pursuant to the New Mexico Engineering and Surveying Practice Act and the rules promulgated under that authority) for the synthetically re-lined Facultative Impoundment. [Subsections A and C of 20.6.2.1202 NMAC, Subsection C of 20.6.2.3109 NMAC, NMSA 1978, §§ 61-23-1 through 61-23-32]
7.	Within 180 days following the issuance date of this Discharge Permit (**by DATE**), the Permittee shall measure the thickness of the settled solids in the Facultative Impoundment. The Permittee shall report the results of the solids thickness measurements to NMED in the next required periodic monitoring report. The Permittee shall measure the thickness of settled solids in accordance with the following procedure. a) The division of the total surface area of the treatment impoundment into nine equal sub-areas. b) One measurement (to the nearest half foot) using a settled solids measurement device (e.g., core sampler) per sub-area.

draft

#	Terms and Conditions
	c) Calculation of the average of the nine measurements. In the event that the measured settled solids exceed one-third of the maximum liquid depth in the impoundment, the Permittee shall implement the Contingency Plan set forth in this Discharge Permit. [Subsection A of 20.6.2.3107 NMAC, Subsection C of 20.6.2.3109 NMAC]

Operating Conditions

#	Terms and Conditions
8.	The Permittee shall maintain fences around the Facility to restrict unauthorized access by the general public and animals. The fences shall consist of a minimum of six-foot chain link or field fencing and locking gates. The Permittee shall maintain the fences to serve the stated purpose throughout the term of this Discharge Permit. [Subsections B and C of 20.6.2.3109 NMAC, NMSA 1978, § 74-6-5.D]
9.	The Permittee shall maintain signs indicating that the wastewater at the Facility is not potable. The Permittee shall post signs at the Facility entrance and other areas where there is potential for public contact with wastewater. The Permittee shall print signs in English and Spanish and shall ensure the signs remain visible and legible for the term of this Discharge Permit. [Subsections B and C of 20.6.2.3109 NMAC, NMSA 1978, § 74-6-5.D]
10.	The Permittee shall maintain the impoundments and the impoundment liners to avoid conditions that could affect the liner or the structural integrity of the impoundments. Characterization of such conditions may include the following: • erosion damage; • animal burrows or other damage; • the presence of vegetation including aquatic plants, weeds, woody shrubs or trees growing within five feet of the top inside edge of a sub-grade impoundment, within five feet of the toe of the outside berm of an above-grade impoundment, or within the impoundment itself; • the presence of large debris or large quantities of debris in the impoundment; • evidence of seepage; or • evidence of berm subsidence.

draft

#	Terms and Conditions
	The Permittee shall routinely control vegetation growing around the impoundments by mechanical removal that is protective of the impoundment liner. The Permittee shall visually inspect the impoundments and surrounding berms on a monthly basis to ensure proper maintenance. In the event that inspection reveals any evidence of damage that threatens the structural integrity of an impoundment berm or liner, or that may result in an unauthorized discharge, the Permittee shall implement the Contingency Plan set forth in this Discharge Permit. The Permittee shall create and maintain a log of all impoundment inspections which describes the date of the inspection, any findings and repairs and the name of the person responsible for the inspection. The Permittee shall make the log available to NMED upon request. [Subsection A of 20.6.2.3107 NMAC, Subsection C of 20.6.2.3109 NMAC]
11.	The Permittee shall preserve a minimum of two feet of freeboard, i.e., the distance between the highest calculated liquid level in the impoundments and the liquid level which would result in the release of stored liquid from the impoundments. In the event that the Permittee determines that it cannot preserve two feet of freeboard in the impoundments, the Permittee shall implement the Contingency Plan set forth in this Discharge Permit. [Subsection A of 20.6.2.3107 NMAC, Subsection C of 20.6.2.3109 NMAC]
12.	The Permittee shall inspect and clean the lift stations as needed to prevent pump failure. The Permittee shall maintain a record of lift station inspections, repairs, and cleanings. The Permittee shall make the record available to NMED upon request. [Subsection A of 20.6.2.3107 NMAC, Subsection C of 20.6.2.3109 NMAC]
13.	The Permittee shall utilize operators, certified by the State of New Mexico at the appropriate level pursuant to 20.7.4 NMAC, to operate the wastewater collection, treatment, and disposal systems. A certified operator or a direct supervisee of a certified operator shall perform the operations and maintenance of all or any part of the wastewater system. The Permittee shall notify the NMED within 24 hours if at any time the Permittee no longer has a certified operator maintaining the system.

draft

#	Terms and Conditions
	[Subsection C of 20.6.2.3109 NMAC, 20.7.4 NMAC]

B. MONITORING AND REPORTING

#	Terms and Conditions
14.	The Permittee shall conduct the monitoring, reporting, and other requirements listed below in accordance with the monitoring requirements of this Discharge Permit. [Subsection A of 20.6.2.3107 NMAC, Subsection C of 20.6.2.3109 NMAC]
15.	METHODOLOGY – Unless otherwise specified by this Discharge Permit, or approved in writing by NMED, the Permittee shall use sampling and analytical techniques that conform with the references listed in Subsection B of 20.6.2.3107 NMAC. [Subsection B of 20.6.2.3107 NMAC]

Due Dates for Monitoring Reports

#	Terms and Conditions
16.	Quarterly monitoring - The Permittee shall perform monitoring and other Permit required actions during the following periods and shall submit quarterly reports to NMED by the following due dates: • January 1st through March 31st – **due by May 1st;** • April 1st through June 30th – **due by August 1st;** • July 1st through September 30th – **due by November 1st; and** • October 1st through December 31st – **due by February 1st.** [Subsection A of 20.6.2.3107 NMAC]

Monitoring Actions with Implementation Deadlines

17.	At least 60 days prior to monitoring well installation, the Permittee shall submit a written groundwater monitoring well location proposal for NMED review and approval. The proposal shall designate the installation locations of the monitoring well required by this Discharge Permit. The proposal shall include, at a minimum, the following information. a) A map showing the proposed location of the monitoring well in relation to the boundary of the source it is intended to monitor. b) A written description of the specific location proposed for the monitoring well including the distance (in feet) and direction of the monitoring well from the edge of

draft

	the source it is intended to monitor and the latitude and longitude coordinates for each well in decimal format. Examples include: 35 feet north-northwest of the northern berm of the synthetically lined impoundment and 35.898306 and -107.281519; 45 feet due south of the leach field and 35.898306 and -107.281519; and 30 feet southeast of the reuse area and 35.898306 and -107.281519. c) A statement describing the groundwater flow direction beneath the Facility, and documentation and/or data supporting the determination. The Permittee must have NMED's approval of all monitoring well locations prior to their installation. [Subsection A of 20.6.2.3107 NMAC]
18.	Within 60 days of completing impoundment rehabilitation (**by DATE**), the Permittee shall install the following new monitoring well. a) One monitoring well (MW-TBD) located at an alternate location from MW-S and 20 to 50 feet hydrologically downgradient of Evaporative Impoundments. The Permittee shall complete the well in accordance with the attached Monitoring Well Guidance. The Permittee shall affix a permanent label with the well identification number above. Unless otherwise noted in this Discharge Permit, the requirement to install a monitoring well downgradient of a source is <u>not</u> contingent upon construction of the Facility, or discharge of wastewater from the Facility. [Subsection A of 20.6.2.3107 NMAC]
19.	Within 60 days following monitoring well installation (**by DATE**), the Permittee shall perform a professional survey of all groundwater monitoring wells approved by NMED for Discharge Permit monitoring purposes. The survey shall be tied or referenced to a U.S. Geological Survey (USGS) or other permanent benchmark. Survey data shall include northing, easting and elevation to the nearest one-hundredth of a foot or shall be in accordance with the "Minimum Standards for Surveying in New Mexico" (12.8.2 NMAC). The survey shall bear the seal and signature of a licensed New Mexico professional surveyor (pursuant to the New Mexico Engineering and Surveying Practice Act and the rules promulgated under that authority). The Permittee shall utilize the survey to establish an elevation at the top-of-casing, with a permanent marking indicating the point of elevation.

draft

	The Permittee shall measure the depth-to-most-shallow groundwater to the nearest one-hundredth of a foot in all surveyed wells and referenced to mean sea level, and the data shall be used to develop a groundwater elevation contour, i.e., potentiometric surface, map showing the location of all monitoring wells and the direction and gradient of groundwater flow in the uppermost aquifer below the Facility. The Permittee shall submit the survey data and groundwater elevation contour map to NMED within 30 days of survey completion. [Subsection A of 20.6.2.3107 NMAC, NMSA 1978, §§ 61-23-1 through 61-23-32]

Groundwater Monitoring Conditions

#	Terms and Conditions
20.	The Permittee shall perform quarterly groundwater sampling in the following groundwater monitoring wells and analyze the samples for TKN, NO_3-N, TDS, and Cl. • MW-N, located hydrologically upgradient of the Facility, approximately 30 feet north of the Facultative Impoundment (35.623333, -108.79722 • MW-S, located hydrologically downgradient of Evaporative Impoundment 3 in the southwest corner of the Facility (35.619881, -108.798056). • MW-E, located hydrologically downgradient of the Abandoned Impoundment in the northeast corner of the Facility (35.623056, -108.793611). • MW-TBD, to be located at an alternate location from MW-S and hydrologically downgradient 20-50 feet from the Evaporative Impoundments. The Permittee shall perform groundwater sample collection, preservation, transport, and analysis according to the following procedures. • Measure the depth-to-most-shallow groundwater from the top of the well casing to the nearest one-hundredth of a foot. • Purge three well volumes of water from the well prior to sample collection. • Obtain samples from the well for analysis. • Properly prepare, preserve, and transport samples. • Analyze samples in accordance with the methods authorized in this Discharge Permit. • The Permittee shall submit the depth-to-most-shallow groundwater measurements and the laboratory analytical data results including the laboratory QA/QC summary report and Chain of Custody for each well, and a Facility layout map showing the location and number of each well to NMED in the monitoring reports due by • January 1st through March 31st – **due by May 1st;**

draft

#	Terms and Conditions
	• April 1st through June 30th – **due by August 1st;** • July 1st through September 30th – **due by November 1st; and** • October 1st through December 31st – **due by February 1st.** [Subsection A of 20.6.2.3107 NMAC]
21.	The Permittee shall develop a groundwater elevation contour map, i.e., potentiometric surface map, on a quarterly basis using the top of casing elevation data from the monitoring well survey and the most recent depth-to-most-shallow groundwater measurements, referenced to mean sea level, obtained during the groundwater sampling required by this Discharge Permit. The groundwater elevation contour map shall depict the groundwater flow direction based on the groundwater elevation contours. The Permittee shall estimate groundwater elevations between monitoring well locations using common interpolation methods. The Permittee shall use a contour interval appropriate to the data but shall not be greater than two feet. Groundwater elevation contour maps shall use arrows to depict the groundwater flow direction based on the orientation of the groundwater elevation contours and shall locate and identify each monitoring well and contaminant source. The Permittee shall submit to NMED a groundwater elevation contour map in the quarterly monitoring reports. • January 1st through March 31st – **due by May 1st;** • April 1st through June 30th – **due by August 1st;** • July 1st through September 30th – **due by November 1st; and** • October 1st through December 31st – **due by February 1st.** [Subsection A of 20.6.2.3107 NMAC]
19.	NMED shall have the option to perform downhole inspections of all groundwater monitoring wells identified in this Discharge Permit. NMED shall establish the inspection date and notify the Permittee. The Permittee shall remove any existing dedicated pumps at least 48 hours prior to NMED inspection to allow adequate settling time of sediment agitated from pump removal. Should the Permittee decide to install a pump in a monitoring well without a dedicated pump, the Permittee shall notify NMED at least 90 days prior to pump installation so that NMED can schedule a downhole well inspection prior to pump placement. [Subsections A and D of 20.6.2.3107 NMAC]

draft

Facility Monitoring Conditions

#	Terms and Conditions
22.	The Permittee shall on a monthly basis measure the volume of wastewater discharged to the evaporative impoundment system. To determine the discharge volume, the Permittee shall obtain readings from a totalizing flow meter located west of Lift Station 3 on the discharge line on a monthly basis and calculate the monthly and average daily volume discharged to the impoundment system. The Permittee shall submit calendar monthly meter readings, calculated monthly discharge volumes, and average daily discharge volumes to NMED in the quarterly monitoring reports. [Subsection A of 20.6.2.3107 NMAC, Subsections C and H of 20.6.2.3109 NMAC]
23.	The Permittee shall collect a composite wastewater sample on a semi-annual basis (once every six months) from the Facultative Impoundment. The composite sample shall consist of a minimum of six equal aliquots collected equidistantly around the entire perimeter of the evaporative impoundment and thoroughly mixed. The Permittee shall analyze the composite sample for: • TKN; • NO_3-N; • TDS; and • Cl. The Permittee shall ensure the sample is properly prepared, preserved, transported, and analyzed in accordance with the methods authorized in this Discharge Permit. The Permittee shall submit the laboratory analytical data results, including the QA/QC summary and Chain of Custody, to NMED in the quarterly monitoring reports. [Subsection A of 20.6.2.3107 NMAC, Subsections C and H of 20.6.2.3109 NMAC]

C. CONTINGENCY PLAN

#	Terms and Conditions
24.	In the event that groundwater monitoring indicates that groundwater exceeds a standard identified in Section 20.6.2.3103 NMAC in a monitoring well with no previous exceedances of the chemical constituent at the date of issuance of this Discharge Permit, the Permittee shall collect a confirmatory sample from the monitoring well within 15 days of receipt of the initial sampling results to confirm the initial sampling results.

draft

#	Terms and Conditions
	Within 60 days of confirmation of groundwater contamination, the Permittee shall submit to NMED a Corrective Action Plan (CAP) that proposes, at a minimum, contaminant source control measures and an implementation schedule. The Permittee shall implement the CAP as approved by NMED. This condition shall apply until the Permittee completes groundwater monitoring for a minimum of eight (8) consecutive quarterly samples demonstrating groundwater does not exceed the standards of Section 20.6.2.3103 NMAC. Violation of the groundwater standard beyond 180 days after the confirmation of groundwater contamination may cause NMED to require the Permittee to abate water pollution consistent with the requirements and provisions of Section 20.6.2.4101, Section 20.6.2.4103, Subsections C and E of 20.6.2.4106, Section 20.6.2.4107, Section 20.6.2.4108 and Section 20.6.2.4112 NMAC. [20.6.2.3103 NMAC, Subsection A of 20.6.2.3107 NMAC, Subsection E of 20.6.2.3109 NMAC]
25.	In the event that information available to NMED indicates that a well is not constructed in a manner consistent with the attached Monitoring Well Guidance, contains insufficient water to effectively monitor groundwater quality, or is otherwise not completed in a manner that is protective of groundwater quality, the Permittee shall install a replacement well(s) within 120 days following notification from NMED. The Permittee shall survey the replacement monitoring well(s) within 30 days following well completion. The Permittee shall install replacement well(s) at locations approved by NMED prior to installation and shall complete replacement well(s) in accordance with the attached Monitoring Well Guidance. The Permittee shall submit well construction and lithologic logs, survey data, and a groundwater elevation contour map to NMED within 60 days following well completion. The Permittee shall properly plug and abandon monitoring well(s) requiring replacement upon completion of the replacement monitoring well(s). The Permittee shall complete the well plugging and abandonment, and shall document the abandonment procedures, in accordance with the attached Monitoring Well Guidance and all applicable local, state, and federal regulations. The Permittee shall submit a copy of the well abandonment documentation to NMED within 60 days following the replacement well(s) completion.

draft

#	Terms and Conditions
	[Subsection A of 20.6.2.3107 NMAC]
26.	In the event that groundwater flow information obtained pursuant to this Discharge Permit indicates that a monitoring well is not appropriately located, e.g., hydrologically downgradient of the discharge location it is intended to monitor, the Permittee shall install a replacement well within 120 days following notification from NMED. The Permittee shall survey the replacement monitoring well within 30 days following well completion. The Permittee shall install the replacement well at the location approved by NMED prior to installation and shall complete the replacement well in accordance with the attached Monitoring Well Guidance. The Permittee shall submit construction and lithologic logs, survey data and a groundwater elevation contour map within 60 days following well completion. The Permittee shall properly plug and abandon a monitoring well requiring replacement upon completion of the replacement monitoring well. The Permittee shall complete the well plugging and abandonment, and shall document the abandonment procedures, in accordance with the attached Monitoring Well Guidance and all applicable local, state, and federal regulations. The Permittee shall submit a copy of the well abandonment documentation to NMED within 60 days following the replacement well completion. [Subsection A of 20.6.2.3107 NMAC]
27.	In the event that the Facility exceeds the authorized discharge volume set in this Discharge Permit, the Permittee shall initiate the following Contingency Plan. <u>Contingency Plan</u> a) Notify NMED within seven days of the discovery of the discharge volume exceedance that the Facility exceeded the authorized discharge volume. b) The Permittee shall conduct a physical inspection of the discharge system, i.e., inflow and infiltration issues, collection system failures, etc., and the volume measuring device/method to detect abnormalities and report the findings to NMED within 30 days of the discovery of the discharge volume exceedance. The Permittee shall correct any abnormalities detected with NMED's concurrence. c) If the Permittee does not detect any abnormalities and with NMED's concurrence, the Permittee shall submit a discharge permit modification for the increase in discharge quantity to NMED within 90 days of the discovery of the discharge volume exceedance. The discharge permit modification must include demonstration that the

draft

#	Terms and Conditions
	volume increase is sufficient for the design capacity or plans and specifications to upgrade the system to accommodate the discharge volume increase. [Subsection A of 20.6.2.3107 NMAC]
28.	In the event that an inspection reveals significant damage has occurred or is likely to affect the structural integrity of an impoundment or liner or their ability to contain contaminants, the Permittee shall propose the repair or replacement by submitting a CAP to NMED for approval. The Permittee shall submit the CAP to NMED within 30 days after discovery of the damage or following notification from NMED that significant damage is evident. The Permittee shall ensure the CAP includes a schedule for completion of corrective actions. The Permittee shall initiate implementation of the CAP following approval by NMED. [Subsection A of 20.6.2.3107 NMAC, Subsection C of 20.6.2.3109 NMAC]
29.	In the event that an impoundment cannot preserve a minimum of two feet of freeboard, the Permittee shall take actions to restore the required freeboard as authorized by this Discharge Permit and all applicable local, state, and federal regulations. In the event that two feet of freeboard cannot be restored within a period of 72 hours following discovery, the Permittee shall propose actions to restore two feet of freeboard by submitting a short-term CAP to NMED for approval. Examples of short-term corrective actions include the pumping and hauling of excess wastewater from the impoundment or reducing the volume of wastewater discharged to the impoundment. The Permittee shall ensure the CAP includes a schedule for completion of corrective actions. The Permittee shall submit the CAP within 15 days following the date the Permittee or the NMED discover the exceedance. The Permittee shall implement the CAP following NMED approval. In the event that the short-term corrective actions fail to restore two feet of freeboard, the Permittee shall submit to NMED a proposal for permanent corrective actions in a long-term CAP. The Permittee shall submit the long-term CAP within 90 days following failure of the short-term CAP. Examples of corrective actions include the installation of an additional storage impoundment or a significant and permanent reduction in the volume of wastewater discharged to the impoundment. The Permittee shall ensure the long-term CAP includes a schedule for completion of corrective actions. The Permittee shall implement the CAP following NMED approval. [Subsection A of 20.6.2.3107 NMAC]

draft

#	Terms and Conditions
30.	In the event the average solids accumulation exceeds one-third of the maximum liquid depth in the impoundments, the Permittee shall propose a plan for the removal and disposal of the solids. The Permittee shall submit the solids removal and disposal plan to NMED for approval within 120 days following discovery and include the following information. a) A method for removing the solids to a depth of less than six inches throughout the treatment impoundment in a manner that is protective of the impoundment liner. b) A description of how the Permittee will contain, transport, and dispose of the solids in accordance with all local, state, and federal regulations, including 40 CFR Part 503. c) A schedule for completion of the solids removal and disposal project. The Permittee shall initiate implementation of the plan following approval by NMED. [Subsection A of 20.6.2.3107 NMAC, Subsection C of 20.6.2.3109 NMAC]
31.	In the event that a release occurs that is not authorized under this Discharge Permit (commonly known as a "spill"), the Permittee shall take measures to mitigate damage from the unauthorized discharge and initiate the notifications and corrective actions required in Section 20.6.2.1203 NMAC and summarized below. A release is defined as such quantity as may with reasonable probability injure or be detrimental to human health, animal or plant life, or property, or unreasonably interfere with the public welfare or the use of property. Within 24 hours following discovery of the unauthorized discharge, the Permittee shall verbally notify NMED and provide the following information. a) The name, address, and telephone number of the person or persons in charge of the Facility, as well as of the owner and/or operator of the Facility. b) The name and address of the Facility. c) The date, time, location, and duration of the unauthorized discharge. d) The source and cause of unauthorized discharge. e) A description of the unauthorized discharge, including its estimated chemical composition. f) The estimated volume of the unauthorized discharge. g) Any actions taken to mitigate immediate damage from the unauthorized discharge. Within one week following discovery of the unauthorized discharge, the Permittee shall submit written notification to NMED providing the information listed above and any pertinent updates. Within 15 days following discovery of the unauthorized discharge, the Permittee shall submit a CAP to NMED describing any corrective actions previously taken and corrective

draft

#	Terms and Conditions
	actions to be taken relative to the unauthorized discharge. The CAP shall include the following information. a) A description of proposed actions to mitigate damage from the unauthorized discharge. b) A description of proposed actions to prevent future unauthorized discharges of this nature. c) A schedule for completion of proposed actions. In the event that the unauthorized discharge causes or may with reasonable probability cause water pollution in excess of the standards and requirements of Section 20.6.2.4103 NMAC, and the water pollution will not be abated within 180 days after notice is required to be given pursuant to Paragraph (1) of Subsection A of 20.6.2.1203 NMAC, NMED may require the Permittee to abate water pollution pursuant to Sections 20.6.2.4000 through 20.6.2.4115 NMAC. The Permittee shall not construe anything in this condition as relieving them of the obligation to comply with all requirements of Section 20.6.2.1203 NMAC. [20.6.2.1203 NMAC]
32.	In the event that NMED or the Permittee identifies any failures of the discharge plan, i.e., the application, or this Discharge Permit not specifically noted herein, NMED may require the Permittee to submit a CAP and a schedule for completion of corrective actions to address the failure(s). Additionally, NMED may require a discharge permit modification to achieve compliance with 20.6.2 NMAC. [Subsection A of 20.6.2.3107 NMAC, Subsection E of 20.6.2.3109 NMAC]

D. CLOSURE PLAN

Closure Actions with Implementation Deadlines

#	Terms and Conditions
33.	Within 3 years of the issuance date of this Discharge Permit (by DATE), the Permittee shall commence the following closure measures on the Retired Impoundment. The Permittee shall submit a sludge removal and disposal plan, which includes soil sampling to characterize potential releases (if applicable), to NMED for approval. The sludge removal and disposal plan shall include the following information.

draft

#	Terms and Conditions
	a) The estimated volume and dry weight of sludge planned to be removed and disposed of, including measurements and calculations. b) Laboratory analytical data results for samples of the sludge taken from the impoundment for TKN, NO_3-N, percent total solids, and any other parameters tested (reported in mg/kg, dry weight basis). c) The method(s) of sludge *removal* from the impoundment. d) The method(s) of *disposal* for all of the sludge (and its contents) removed from the impoundment. The method(s) shall comply with all local, state and federal regulations, including 40 CFR Part 503. *Note: A proposal that includes the surface disposal of sludge may be subject to Groundwater Discharge Permitting requirements pursuant to 20.6.2.3104 NMAC that are separate from the requirements of this Discharge Permit*. The methods and extent of soil sampling to assess any potential releases associated with the impoundment (if applicable). Within <u>one year</u> following completion of the sludge removal and disposal, the Permittee shall complete the following closure measures. a) Remove all lines leading to and from the impoundment or permanently plug and abandon the lines in place. b) Remove or demolish any other wastewater system components and re-grade area with suitable fill to blend with surface topography, promote positive drainage and prevent ponding. c) Characterize, remove, and dispose of all solids from the impoundments in accordance with local, state, and federal regulations, and maintain a record of solids transported for off-site disposal, including the volume of solids transported and the disposal location. d) Sample soil below the liners, assess the impact, report that assessment to NMED, and mitigate the impacts following NMED approval. e) Fill the impoundment(s) with suitable fill. f) Re-grade the impoundment site and the locations of ancillary equipment, e.g., influent piping, to blend with surface topography, promote positive drainage and prevent ponding. The Permittee shall continue groundwater monitoring until the Permittee meets the requirements of this condition met and groundwater monitoring confirms for a minimum of eight consecutive quarterly groundwater sampling events that groundwater does not exceed the standards of Section 20.6.2.3103 NMAC. This period is referred to as “post-closure.” If at any time monitoring results show an exceedance of a groundwater quality standard

draft

#	Terms and Conditions
	in Section 20.6.2.3103 NMAC, the Permittee shall implement the Contingency Plan required by this Discharge Permit. Following notification from NMED that the Permittee may cease post-closure monitoring, the Permittee shall plug and abandon the monitoring well(s) in accordance with the attached Monitoring Well Guidance. When the Permittee has met all closure and post-closure requirements and verified appropriate actions with date stamped photographic evidence or an associated NMED inspection, the Permittee may submit to NMED a written request, including photographic evidence, for termination of the Discharge Permit. [Subsection A of 20.6.2.3107 NMAC, Subsection D of 20.6.2.4103 NMAC, 40 CFR Part 503]
34.	Within 3 years of the issuance date of this Discharge Permit (by DATE), the Permittee shall commence the following closure measures on the Facultative Impoundment for re-lining of the Facultative Impoundment. a) Cease discharging to the impoundment. b) Temporarily plug all lines leading to and from the impoundment. c) Drain wastewater from the impoundment and any other wastewater system components and dispose of it in accordance with all local, state and federal regulations, or evaporate remaining wastewater from the impoundment. Drain wastewater from the impoundment and any other wastewater system components and dispose of it in accordance with all local, state and federal regulations, or evaporate remaining wastewater from the impoundment. Within <u>90 days</u> of ceasing to discharge to the impoundment, the Permittee shall submit a sludge removal and disposal plan, which includes soil sampling to characterize potential releases (if applicable), to NMED for approval. The sludge removal and disposal plan shall include the following information. e) The estimated volume and dry weight of sludge planned to be removed and disposed of, including measurements and calculations. f) Laboratory analytical data results for samples of the sludge taken from the impoundment for TKN, NO_3-N, percent total solids, and any other parameters tested (reported in mg/kg, dry weight basis). g) The method(s) of sludge *removal* from the impoundment.

draft

#	Terms and Conditions
	h) The method(s) of *disposal* for all of the sludge (and its contents) removed from the impoundment. The method(s) shall comply with all local, state and federal regulations, including 40 CFR Part 503. *Note: A proposal that includes the surface disposal of sludge may be subject to Groundwater Discharge Permitting requirements pursuant to 20.6.2.3104 NMAC that are separate from the requirements of this Discharge Permit*. i) The methods and extent of soil sampling to assess any potential releases associated with the impoundment(s) (if applicable). j) A schedule for completion of sludge removal and disposal not to exceed two years from the date discharge to the impoundment ceased. The Permittee shall initiate implementation of the plan within 30 days following approval by NMED. Following completion of the sludge removal and disposal, the Permittee shall complete re-lining of the impoundment and return the impoundment to service in accordance with the requirements of this Discharge Permit. [Subsection A of 20.6.2.3107 NMAC, Subsection D of 20.6.2.4103 NMAC, 40 CFR Part 503]

Permanent Facility Closure Conditions

#	Terms and Conditions
35.	The Permittee shall perform the following closure measures in the event the Facility, or a component thereof, is proposed to be permanently closed. Within 60 days of ceasing to discharge to the impoundment(s), the Permittee shall plug the impoundment influent lines so that a discharge can no longer occur. Within 60 days of ceasing to discharge to the impoundment(s), the Permittee shall evaporate or drain all wastewater from the impoundment and any other wastewater system component and dispose of it in accordance with all local, state, and federal regulations. Within 90 days of ceasing to discharge to the impoundment(s), the Permittee shall submit a sludge removal and disposal plan, which includes soil sampling to characterize potential releases, to NMED for approval. The Permittee shall implement the plan within

draft

#	Terms and Conditions
	30 days following approval by NMED. The sludge removal and disposal plan shall include the following information. g) The estimated volume and dry weight of sludge planned for removal and disposal, including measurements and calculations. h) Analytical results for samples of the sludge taken from the impoundment for TKN, NO_3-N, percent total solids, and any other parameters tested (reported in mg/kg, dry weight basis). i) The method of sludge *removal* from the impoundment. j) The method of *disposal* for all the sludge (and its contents) removed from the impoundment(s). The method shall comply with all local, state and federal regulations, including 40 CFR Part 503. *Note: A proposal that includes the surface disposal of sludge may be subject to Groundwater Discharge Permitting requirements pursuant to 20.6.2.3104 NMAC that are separate from the requirements of this Discharge Permit*. k) The methods and extent of soil sampling to assess any potential releases associated with the impoundment(s). l) A schedule for completion of sludge removal and disposal not to exceed two years from the date discharge to the impoundment(s) ceased. Within <u>one year</u> following completion of the sludge removal and disposal, the Permittee shall complete the following closure measures. m) Remove all lines leading to and from the impoundment(s) or permanently plug and abandon the lines in place. n) Remove or demolish any other wastewater system components and re-grade area with suitable fill to blend with surface topography, promote positive drainage and prevent ponding. o) Characterize, remove, and dispose of all solids from the impoundments in accordance with local, state, and federal regulations, and maintain a record of solids transported for off-site disposal, including the volume of solids transported and the disposal location. p) Remove and dispose of the impoundment liners at a solid waste facility. q) Sample soil below the liners, assess the impact, report that assessment to NMED, and mitigate the impacts following NMED approval. r) Fill the impoundment(s) with suitable fill. s) Re-grade the impoundment site and the locations of ancillary equipment, e.g., influent piping, to blend with surface topography, promote positive drainage and prevent ponding. The Permittee shall continue groundwater monitoring until the Permittee meets the requirements of this condition met and groundwater monitoring confirms for a minimum

draft

#	Terms and Conditions
	of eight consecutive quarterly groundwater sampling events that groundwater does not exceed the standards of Section 20.6.2.3103 NMAC. This period is referred to as "post-closure." If at any time monitoring results show an exceedance of a groundwater quality standard in Section 20.6.2.3103 NMAC, the Permittee shall implement the Contingency Plan required by this Discharge Permit. Following notification from NMED that the Permittee may cease post-closure monitoring, the Permittee shall plug and abandon the monitoring well(s) in accordance with the attached Monitoring Well Guidance. When the Permittee has met all closure and post-closure requirements and verified appropriate actions with date stamped photographic evidence or an associated NMED inspection, the Permittee may submit to NMED a written request, including photographic evidence, for termination of the Discharge Permit. [Subsection A of 20.6.2.3107 NMAC, Subsection D of 20.6.2.4103 NMAC, 40 CFR Part 503]

E. GENERAL TERMS AND CONDITIONS

#	Terms and Conditions
36.	RECORD KEEPING - The Permittee shall maintain a written record of the following: • Information and data used to complete the application for this Discharge Permit; • Information, data, and documents demonstrating completion of closure activities; • Any releases (commonly known as "spills") not authorized under this Discharge Permit and reports submitted pursuant to 20.6.2.1203 NMAC; • The operation, maintenance, and repair of all facilities/equipment used to treat, store or dispose of wastewater; • Facility record drawings (plans and specifications) showing the actual construction of the Facility and bear the seal and signature of a licensed New Mexico professional engineer; • Copies of logs, inspection reports, and monitoring reports completed and/or submitted to NMED pursuant to this Discharge Permit; • The volume of wastewater or other wastes discharged pursuant to this Discharge Permit; • Groundwater quality and wastewater quality data collected pursuant to this Discharge Permit;

draft

#	Terms and Conditions
	• Copies of construction records (well log) for all sampled groundwater monitoring wells pursuant to this Discharge Permit; • The maintenance, repair, replacement or calibration of any monitoring equipment or flow measurement devices required by this Discharge Permit; and • Data and information related to field measurements, sampling, and analysis conducted pursuant to this Discharge Permit, including: o the dates, location and times of sampling or field measurements; o the name and job title of the individuals who performed each sample collection or field measurement; o the sample analysis date of each sample; o the name and address of the laboratory, and the name of the signatory authority for the laboratory analysis; o the analytical technique or method used to analyze each sample or collect each field measurement; o the results of each analysis or field measurement, including raw data; o the results of any split, spiked, duplicate or repeat sample; and o a copy of the laboratory analysis chain-of-custody as well as a description of the quality assurance and quality control procedures used. The Permittee shall maintain the written record at a location accessible to NMED during a Facility inspection for a minimum of five years. The Permittee shall make the record available to NMED upon request. [Subsections A and D of 20.6.2.3107 NMAC]
37.	SUBMITTALS – The Permittee shall submit both a paper copy and an electronic copy of all notification and reporting documents required by this Discharge Permit, e.g., monitoring reports. The Permittee shall submit paper and electronic documents to the NMED Permit Contact identified on the Permit cover page. [Subsection A of 20.6.2.3107 NMAC]
38.	INSPECTION and ENTRY – The Permittee shall allow NMED to inspect the Facility and its operations that are subject to this Discharge Permit and the WQCC regulations. NMED may upon presentation of proper credentials, enter at reasonable times upon or through any premises in which a water contaminant source is located or in which any maintained records required by this Discharge Permit, the regulations of the federal government, or the WQCC are located. The Permittee shall allow NMED to have access to and reproduce for their use any copy of the records, and to perform assessments, sampling or monitoring during an inspection

draft

#	Terms and Conditions
	for the purpose of evaluating compliance with this Discharge Permit and the WQCC regulations. No person shall construe anything in this Discharge Permit as limiting in any way the inspection and entry authority of NMED under the WQA, the WQCC Regulations, or any other local, state or federal regulations. [Subsection D of 20.6.2.3107 NMAC, NMSA 1978, §§ 74-6-9.B and 74-6-9.E]
39.	DUTY to PROVIDE INFORMATION - The Permittee shall, upon NMED's request, allow for NMED's inspection/duplication of records required by this Discharge Permit and/or furnish to NMED copies of such records. [Subsection D of 20.6.2.3107 NMAC]
40.	MODIFICATIONS and/or AMENDMENTS – In the event the Permittee proposes a change to the Facility or the Facility's discharge that would result in a change in the volume discharged; the location of the discharge; or in the amount or character of water contaminants received, treated or discharged by the Facility, the Permittee shall notify NMED prior to implementing such changes. The Permittee shall obtain NMED's approval (which may require modification of this Discharge Permit) prior to implementing such changes. [Subsection C of 20.6.2.3107 NMAC, Subsections E and G of 20.6.2.3109 NMAC]
41.	PLANS and SPECIFICATIONS – In the event the Permittee proposes to construct a wastewater system or change a process unit of an existing system such that the quantity or quality of the discharge will change substantially from that authorized by this Discharge Permit, the Permittee shall submit construction plans and specifications of the proposed system or process unit to NMED for approval prior to the commencement of construction. In the event the Permittee implements changes to the wastewater system authorized by this Discharge Permit that result in only a minor effect on the character of the discharge, the Permittee shall report such changes (including the submission of record drawings where applicable) to NMED prior to implementation. [Subsections A and C of 20.6.2.1202 NMAC, NMSA 1978, §§ 61-23-1 through 61-23-32]
42.	CIVIL PENALTIES - Any violation of the requirements and conditions of this Discharge Permit, including any failure to allow NMED staff to enter and inspect records or facilities, or any refusal or failure to provide NMED with records or information, may subject the

draft

#	Terms and Conditions
	Permittee to a civil enforcement action. Pursuant to WQA 74-6-10(A) and (B), such action may include a compliance order requiring compliance immediately or in a specified time, assessing a civil penalty, modifying or terminating the Discharge Permit, or any combination of the foregoing; or an action in district court seeking injunctive relief, civil penalties, or both. Pursuant to WQA 74-6-10(C) and 74-6-10.1, civil penalties of up to $15,000 per day of noncompliance may be assessed for each violation of the WQA 74-6-5, the WQCC Regulations, or this Discharge Permit, and civil penalties of up to $10,000 per day of noncompliance may be assessed for each violation of any other provision of the WQA, or any regulation, standard, or order adopted pursuant to such other provision. In any action to enforce this Discharge Permit, the Permittee waives any objection to the admissibility as evidence of any data generated pursuant to this Discharge Permit. [20.6.2.1220 NMAC, NMSA 1978, §§ 74-6-10 and 74-6-10.1]
43.	CRIMINAL PENALTIES – No person shall: • Make any false material statement, representation, certification or omission of material fact in an application, record, report, plan or other document filed, submitted or maintained under the WQA; • Falsify, tamper with or render inaccurate any monitoring device, method or record maintained under the WQA; or • Fail to monitor, sample or report as required by a permit issued pursuant to a state or federal law or regulation. Any person who knowingly violates or knowingly causes or allows another person to violate the requirements of this condition is guilty of a fourth-degree felony and shall be sentenced in accordance with the provisions of NMSA 1978, § 31-18-15. Any person who is convicted of a second or subsequent violation of the requirements of this condition is guilty of a third-degree felony and shall be sentenced in accordance with the provisions of NMSA 1978, § 31-18-15. Any person who knowingly violates the requirements of this condition or knowingly causes another person to violate the requirements of this condition and thereby causes a substantial adverse environmental impact is guilty of a third-degree felony and shall be sentenced in accordance with the provisions of NMSA 1978, § 31-18-15. Any person who knowingly violates the requirements of this condition and knows at the time of the violation that he is creating a substantial danger of death or serious bodily injury to any other person is guilty of a second degree felony and shall be sentenced in accordance with the provisions of NMSA 1978, § 31-18-15. [20.6.2.1220 NMAC, NMSA 1978, §§ 74-6-10.2.A through 74-6-10.2.F]
44.	COMPLIANCE with OTHER LAWS - Nothing in this Discharge Permit shall be construed in any way as relieving the Permittee of the obligation to comply with any other applicable

draft

#	Terms and Conditions
	federal, state, and/or local laws, regulations, zoning requirements, nuisance ordinances, permits or orders. [NMSA 1978, § 74-6-5.L]
45.	RIGHT to APPEAL - The Permittee may file a petition for review before the WQCC on this Discharge Permit. Such petition shall be in writing to the WQCC within thirty days of the receipt of postal notice of this Discharge Permit and shall include a statement of the issues raised and the relief sought. Unless the Permittee files a timely petition for review, the decision of NMED shall be final and not subject to judicial review. [20.6.2.3112 NMAC, NMSA 1978, § 74-6-5.O]
46.	TRANSFER of DISCHARGE PERMIT - Prior to the transfer of any ownership, control, or possession of this Facility or any portion thereof, the Permittee shall: • Notify the proposed transferee in writing of the existence of this Discharge Permit; • Include a copy of this Discharge Permit with the notice; and • Deliver or send by certified mail to NMED a copy of the notification and proof that the proposed transferee has received such notification. The Permittee shall continue to be responsible for any discharge from the Facility, until both ownership and possession of the Facility have been transferred to the transferee. [20.6.2.3111 NMAC]
47.	PERMIT FEES – The Permittee shall be aware that the payment of permit fees is due at the time of Discharge Permit approval. The Permittee may pay the permit fees in a single payment or they may pay the fee in equal installments on a yearly basis over the term of the Discharge Permit. The Permittee shall remit single payments to NMED no later than 30 days after the Discharge Permit issuance date. The Permittee shall remit initial installment payments to NMED no later than 30 days after the Discharge Permit issuance date; with subsequent installment payments remitted to NMED no later than the anniversary of the Discharge Permit issuance date. Permit fees are associated with <u>issuance</u> of this Discharge Permit. No person shall construe anything in this Discharge Permit as relieving the Permittee of the obligation to pay all permit fees assessed by NMED. A Permittee that ceases discharging or does not commence discharging from the Facility during the term of the Discharge Permit shall pay all permit fees assessed by NMED. NMED shall suspend or terminate an approved Discharge Permit if the Permittee fails to remit an installment payment by its due date.

draft

#	Terms and Conditions
	[Subsection F of 20.6.2.3114 NMAC, NMSA 1978, § 74-6-5.K]

draft

New Mexico Environment Department Ground Water Quality Bureau
Discharge Permit Summary

Facility Information

Facility Name Yah-ta-hey Water and Sanitation District
Discharge Permit Number DP-792

Legally Responsible Party

Jason Sanchez, Receiver
Yah-ta-hey water and Sanitation District
P.O. Box 4120
Yahtahey, New Mexico 87375
(505) 399-1158

Treatment, Disposal and Site Information

Primary Waste Type Domestic
Facility Type Municipal

Treatment Methods

Type	Designation	Description & Comments
Impoundment	Facultative Impoundment	Synthetically lined Facultative Impoundment (approx. 2.75 acres) located west of the Retired Impoundment at 35.622939, -108.797152.
Impoundment	Evaporative Impoundment 1	Unlined impoundment (approx. 1.15 acres), located south of Facultative Impoundment at 35.622162, -108.797441.
Impoundment	Evaporative Impoundment 2	Unlined impoundment (approx. 0.75 acres) located south of Evaporative Impoundment 1 at 35.621681, -108.797410.
Impoundment	Evaporative Impoundment 3	Unlined impoundment (approx. 1.67 acres) located south of Evaporative Impoundment 2 at 35.621089, -108.797456
Impoundment	Evaporative Impoundment 4	Unlined impoundment (approx. 2.0 acres) located south of Evaporative Impoundment 3 at 35.620250, -108.797410
Impoundment	Retired Impoundment	Unlined impoundment (approx. 1.25 acres) located east of Facultative Impoundment at 35.622963, -108.795134. To be properly closed out during this permit term.
Lift Station	Lift Station 1	Approximately 20,000 gallons and concrete construction with dual pumps. 450 feet northeast corner of North Labah and Tso Drives (35.634243, -108.788398)
Lift Station	Lift Station 2	Approximately 20,000 gallons and concrete construction with dual pumps. North end of South Labah Drive (35.629819, -108.78854)
Lift Station	Lift Station 3	Approximately 15,000 gallons and concrete construction with dual pumps. South end of South Labah Drive and lagoon access road (35.623273, -108.788086)

Flow Metering Locations

Type	Designation	Description & Comments
Totalizing meter	Discharge Meter	Badger flow meter located west of Lift Station 3 on the discharge line.

draft

Ground Water Monitoring Locations

Type	Designation	Description & Comments
Monitoring Well	MW-N	MW-N, located hydrologically upgradient of the Facility, approximately 30 feet north of the synthetically lined Facultative Impoundment (35.623333, -108.797222).
Monitoring Well	MW-S	MW-S, located hydrologically downgradient of Evaporative Impoundment 3 in the southwest corner of the Facility (35.619881, -108.798056).
Monitoring Well	MW-E	MW-E, located hydrologically upgradient of the Abandoned Impoundment in the northeast corner of the Facility (35.623056, -108.793611).
Monitoring Well	MW-TBD	MW-TBD, to be located downgradient of the Evaporative Impoundments.

Depth-to-Ground Water 38 feet
Total Dissolved Solids (TDS) 1,990 mg/L

Permit Information

Original Permit Issued **April 15, 1996**
Permit Renewal **February 1, 2002**
Permit Renewal and Modification **June 29, 2018**

Current Action **Renewal**
Application Received December 4, 2023
Public Notice Published [not yet published]
Permit Issued (Issuance Date) [issuance date]
Permitted Discharge Volume 31,190 gallons per day

NMED Contact Information

Mailing Address
Ground Water Quality Bureau
P.O. Box 5469
Santa Fe, New Mexico 87502-5469

GWQB Telephone Number (505) 827-2900

NMED Lead Staff Deborah Carpenter
Lead Staff Telephone Number (505) 531-7430
Lead Staff Email deborah.carpenter@env.nm.gov or pps.general@env.nm.gov

draft

New Mexico Environment Department Ground Water Quality Bureau
Discharge Permit Renewal

Summary of Permit Conditions Requiring Action

Yah-ta-Hey Water and Sanitation District, DP-792

Effective Date:

A. ONE-TIME REQUIRED ACTIONS

#	Description of Required Action	Due Date
1.	Submit final construction plans and specifications for the proposed re-lining of the Facultative Impoundment.	Within 2 years following the issuance date of this Discharge Permit (**by DATE**).
2.	Complete the synthetic re-lining of the Facultative Impoundment in accordance with the final construction plans and specifications required by this Discharge Permit.	Within 3 years following the issuance date of this Discharge Permit (**by DATE**).
3.	Measure the thickness of the settled solids in the Facultative Impoundment and report the results of the solids thickness measurements to NMED.	Within 180 days following the issuance date of this Discharge Permit (**by DATE**).
4.	Complete closure of Retired Impoundment	Within 3 years following the issuance date of this Discharge Permit (**by DATE**).
5.	Submit a written monitoring well location proposal for review and approval by NMED.	At least 60 days prior to monitoring well installation.
6.	Install new monitoring well.	Within 60 days of completing impoundment rehabilitation.
7.	Survey all wells approved by NMED for Discharge Permit monitoring purposes to a U.S. Geological Survey (USGS) or other permanent benchmark.	Within 60 days of monitoring well completion.

B. RECURRING REQUIRED ACTIONS

#	Description of Required Action	Frequency	Reporting Due Dates
4.	Inspect the lift stations and clean as needed to prevent pump failure.	Quarterly	1st of February, May, August and November
5.	Conduct groundwater sampling in the following monitoring wells MW-N, MW-S, MW-E, and analyze the samples for TKN, NO_3-N, TDS and Cl.		Quarterly

Summary of Permit Conditions Requiring Action

	Depth-to-most-shallow groundwater measurements, analytical results, including the laboratory QA/QC summary report, and a facility layout map showing the location and number of each well.		——————— Quarterly
6.	Develop a groundwater elevation contour map. ——————————— Depth-to-most-shallow groundwater measurements, referenced to mean sea level, obtained from the groundwater monitoring wells.		Quarterly ——————— Quarterly
7.	Submit the record of the monthly operating time for the pump(s), pumping rate and estimated monthly and average daily influent volume.	Monthly	1st of February and August
8.	Submit the monthly meter readings and calculated monthly and average daily discharge volumes.	Monthly	Quarterly
9.	Measure the monthly volume of wastewater discharged to the evaporative impoundment system.	Monthly	Quarterly
10.	Collect a composite wastewater sample from the Facultative Impoundment and analyze for TKN, NO_3-N, TDS and CL.	Semi-annual basis (once every six months)	1st of February and August

NOTE: This document is intended as a reminder only. See Discharge Permit for full requirement details.

Submit reports electronically to:

pps.general@env.nm.gov OR Deborah.carpenter@env.nm.gov

NMED Ground Water Quality Bureau
P.O. Box 5469
Santa Fe, New Mexico 87502-5469

draft