6-16-2008 3

00001

Inspection Report
Ground Water Quality Bureau

Start Date: 06/16/2008 06:30 PM **End Date:** 06/16/2008 08:00 PM

Facility Information
Facility Name: Copper Flat Mine, DP-1
Contact: unknown
Type of Operation: Mining
Location: Hillsboro

Inspector(s): Kurt Vollbrecht (NMED), James Hollen (MMD)

Inspection Summary
Purpose: Facility Inspection (GWB)

Activities
Samples Taken: Yes

Observations and Information Obtained

We arrived at the site at approximately 6:30 PM on the way to Silver City. Access to the site was thru well established roads with no gates to prevent access. The pit lake is on the west edge of the site. The tailings impoundment was visible but fairly well vegetated. There are some regarded waste rock piles, and some that have not been reclaimed. We did not spend time investigating the status of waste rock piles but instead drove thru to the pit lake. In general the site is pretty clean.

Arriving at the pit lake there were four deer noted at the shoreline. There is evidence of deer, possibly elk, cattle, and coyote tracks around the lake. One cow was noted on the shore, and a rancher has placed salt blocks to lead livestock to the lake.

The lake is a deep blue color with significant sulfate precipitates along the shoreline and at depth in the lake. The lake level appears to have dropped about 2' based on the "bath tub" ring present. We tested pH (pH strips) at several locations and found the pH to be in the 4 to 4.5 range.

Samples were collected from two locations for analysis. One sample was collected along the NW shore and another from the east shore near the "ramp". Samples will be analyzed for total metals, dissolved metals, and general chemistry.

Russ Macrae with the USFWS had visited the site recently and sent an email speculating on ownership of the site. This should be investigated further and a compliance letter sent to the responsible party.

06/16/2008 18:54


06/16/2008 19:04


06/16/2008 18:54

06/16/2008 19:01

06/16/2008 19:18

06/16/2008 19:05

06/16/2008 19:19

Add to Company Profile

Set Company Alert

Stay in the know. Sign up to receive email alert notification when new information about Hydro Resources Corporation is available.

Set Company Alert

Looking for reports & articles on Hydro Resources Corporation?

Manta also provides financial reports, credit reports, news articles, and market research reports on Hydro Resources Corporation.

View Reports & Articles

Copyright 2008 Dun and Bradstreet, Inc. All Rights Reserved

7/10/08

Privacy Policy | Refund Policy | Contact Us | Advertise | Local Ads | Terms & Conditions | Site Map | Manta

Copyright © 2008, ECNext, Inc. All Rights Reserved.

KMV called ... @ 10:00 Am.

- Sole Responsible Party (George Lotspeich)
  - Explained Concerns
    - Previous GW Cont. associated w/ Tailings
    - Unknown condition of wells now
    - Pit lake exceedences 2004
    - Sampled Recently (George would like to see results)
    - Potential For Further GW Cont.
- Require abatement or closure?
- letter or Meeting (or both)
- Understand he never operated but since he bought the property he has assumed the liability

NEW MEXICO
ENVIRONMENT DEPARTMENT

Ground Water Quality Bureau

1190 St. Francis Drive
P.O. Box 26110, Santa Fe, NM 87502
Phone (505) 827-2918 Fax (505) 827-2965
www.nmenv.state.nm.us
William C. Olson, Bureau Chief

BILL RICHARDSON
Governor
DIANE DENISH
Lieutenant Governor

RON CURRY
Secretary
JON GOLDSTEIN

CERTIFIED MAIL – RETURN RECEIPT REQUESTED

August 20, 2008

George Lotspeich, President
Hydro Resources Corporation
4011 Mesa Verde Ave. NE
Albuquerque, NM 87110

Re: Abatement Plan Required at Copper Flat Mine Site, DP-1

Dear Mr. Lotspeich:

Pursuant to the New Mexico Water Quality Control Commission (WQCC) Regulations Sections 20.6.2.1203.A(9), 20.6.2.4104 and 20.6.2.4106.A NMAC, the New Mexico Environment Department (NMED) hereby provides notification that you, George Lotspeich and Hydro Resources Corporation (HRC) as a "responsible person", as defined in WQCC regulation 20.6.2.7.00 NMAC, are required to submit an abatement plan for the Copper Flat Mine site, located approximately 6 miles northeast of Hillsboro, New Mexico. The May 1997 Alta Gold submittal entitled "Copper Flat Mine Project Monitoring Plans" lists historical ground water exceedences of WQCC standards through 1994. Additional ground water sampling in 1997 and 1998 confirmed that standards set forth in WQCC regulation 20.6.2.4103 NMAC have been exceeded. Sampling the water quality of the pit lake at Copper Flat in 2004 indicates the pit lake water also exceeds WQCC standards for sulfate, total dissolved solids, chloride, manganese and uranium. Additional sampling of the pit lake was conducted in June 2008. Although analytical data is not yet available from this recent sampling event the field pH was measured at approximately 4.5 which is below the acceptable range of 6 to 9. Field observations indicate high concentrations of sulfate and total dissolved solids.

Within 60 days of receipt of this letter, HRC shall submit to NMED an abatement plan proposal for a Stage 1 Abatement Plan to characterize ground and surface water contamination at the Copper Flat Mine site.

The purpose of the Stage 1 Abatement Plan is to define site conditions and provide the data necessary to select and design an effective abatement alternative. WQCC regulation

20.6.2.4106.C NMAC describes the information that may be required for a Stage 1 Abatement Plan. HRC's abatement plan proposal must include an adequate investigation for the definition of extent and magnitude of ground and surface water contamination as well as characterization of the hydrogeology of the site.

For your reference, a current copy (effective July 16, 2006) of the WQCC Regulations, 20.6.2 NMAC is enclosed.

Please contact Kurt Vollbrecht at 505-827-0195 with any questions.

Sincerely,

William C. Olson, Chief
Ground Water Quality Bureau

Enc.: WQCC Regulations 20.6.2 NMAC

cc: Mary Ann Menetrey, Program Manager, GWQB-MECS
Karen Garcia, Chief, Mine Reclamation Bureau
Russell MacRae, U.S. Fish and Wildlife Service, 2105 Osuna NE, Abq., Nm 87113

12-15-2008 5

NEW MEXICO
ENVIRONMENT DEPARTMENT

Ground Water Quality Bureau

1190 St. Francis Drive
P.O. Box 26110, Santa Fe, NM 87502
Phone (505) 827-2918 Fax (505) 827-2965
www.nmenv.state.nm.us
William C. Olson, Bureau Chief

BILL RICHARDSON
Governor
DIANE DENISH
Lieutenant Governor

RON CURRY
Secretary
JON GOLDSTEIN
Deputy Secretary

12/15/08

George,

Here is a copy of Kurt's letter.

I'll call again when I have more information. Thank you.

Greg Huey

phone: (505) 827-1046

NEW MEXICO
ENVIRONMENT DEPARTMENT

Ground Water Quality Bureau

1190 St. Francis Drive
P.O. Box 26110, Santa Fe, NM 87502
Phone (505) 827-2918 Fax (505) 827-2965
www.nmenv.state.nm.us
William C. Olson, Bureau Chief

BILL RICHARDSON
Governor
DIANE DENISH
Lieutenant Governor

RON CURRY
Secretary
JON GOLDSTEIN
Deputy Secretary

CERTIFIED MAIL – RETURN RECEIPT REQUESTED

August 20, 2008

George Lotspeich, President
Hydro Resources Corporation
4011 Mesa Verde Ave. NE
Albuquerque, NM 87110

Re: Abatement Plan Required at Copper Flat Mine Site, DP-1

Dear Mr. Lotspeich:

Pursuant to the New Mexico Water Quality Control Commission (WQCC) Regulations Sections 20.6.2.1203.A(9), 20.6.2.4104 and 20.6.2.4106.A NMAC, the New Mexico Environment Department (NMED) hereby provides notification that you, George Lotspeich and Hydro Resources Corporation (HRC) as a "responsible person", as defined in WQCC regulation 20.6.2.7.00 NMAC, are required to submit an abatement plan for the Copper Flat Mine site, located approximately 6 miles northeast of Hillsboro, New Mexico. The May 1997 Alta Gold submittal entitled "Copper Flat Mine Project Monitoring Plans" lists historical ground water exceedences of WQCC standards through 1994. Additional ground water sampling in 1997 and 1998 confirmed that standards set forth in WQCC regulation 20.6.2.4103 NMAC have been exceeded. Sampling the water quality of the pit lake at Copper Flat in 2004 indicates the pit lake water also exceeds WQCC standards for sulfate, total dissolved solids, chloride, manganese and uranium. Additional sampling of the pit lake was conducted in June 2008. Although analytical data is not yet available from this recent sampling event the field pH was measured at approximately 4.5 which is below the acceptable range of 6 to 9. Field observations indicate high concentrations of sulfate and total dissolved solids.

Within 60 days of receipt of this letter, HRC shall submit to NMED an abatement plan proposal for a Stage 1 Abatement Plan to characterize ground and surface water contamination at the Copper Flat Mine site.

The purpose of the Stage 1 Abatement Plan is to define site conditions and provide the data necessary to select and design an effective abatement alternative. WQCC regulation

20.6.2.4106.C NMAC describes the information that may be required for a Stage 1 Abatement Plan. HRC's abatement plan proposal must include an adequate investigation for the definition of extent and magnitude of ground and surface water contamination as well as characterization of the hydrogeology of the site.

For your reference, a current copy (effective July 16, 2006) of the WQCC Regulations, 20.6.2 NMAC is enclosed.

Please contact Kurt Vollbrecht at 505-827-0195 with any questions.

Sincerely,

William C. Olson, Chief
Ground Water Quality Bureau

Enc.: WQCC Regulations 20.6.2 NMAC

cc: Mary Ann Menetrey, Program Manager, GWQB-MECS
Karen Garcia, Chief, Mine Reclamation Bureau
Russell MacRae, U.S. Fish and Wildlife Service, 2105 Osuna NE, Abq., Nm 87113

3-18-2009

NEW MEXICO
ENVIRONMENT DEPARTMENT

Ground Water Quality Bureau

1190 St. Francis Drive, P.O. Box 5469
Santa Fe, New Mexico 87502-5469
Phone (505) 827-2900 Fax (505) 827-2965
www.nmenv.state.nm.us

BILL RICHARDSON
Governor
DIANE DENISH
Lieutenant Governor

RON CURRY
Secretary
JON GOLDSTEIN
Deputy Secretary

CERTIFIED MAIL – RETURN RECEIPT REQUESTI

March 18, 2009

George Lotspeich, President
Hydro Resources Corporation
4011 Mesa Verde Avenue, NE
Albuquerque, NM 87110

RE: Copper Flat Mine Site Information

Dear Mr. Lotspeich:

Thank you for meeting with the New Mexico Environment Department (NMED) regarding the Copper Flat Mine Site Stage 1 Abatement Plan on February 25, 2009. Your cooperation with this project is greatly appreciated.

I've reviewed and inventoried the reports available through NMED. These files are available for review at the NMED Ground Water Quality Bureau Santa Fe offices and include the following:

- Hydrology Impact Evaluation, 1996
- Baseline Data, Volume 1. Copper Flat Project, 1995
- Copper Flat Mine-Mine Permit Application, volumes 1-4, 1996
- Copper Flat Mine Project Monitoring Plans, 1996
- Appendices-volume II of II, Copper Flat Project Soil Cover Modeling Study, 1996 (I cannot locate volume I of II)
- Environmental Impact Statement, Copper Flat Project, 1995
- Response to Closure Plan Comments, Copper Flat Project, 1996
- Final Geotechnical and Design Development Report, Tailings Dam and Disposal Area, Copper Flat Project, 1981

In addition, eight water quality samples were collected from the Pit Lake and submitted for analysis by NMED on 12/09/2004 and 06/16/2008. Copies of the results are attached for your records.

The first step in initiating a Stage 1 Abatement Plan as described in WQCC Regulation 20.6.2.4106 NMAC (page 26) will be to walk the property and identify existing monitoring wells that may be used to collect water quality samples for the assessment of ground water at the site. I have March 24th scheduled to meet you in Hillsborough at 10:30 to conduct that inspection.

Following sample collection and results analysis, NMED and Hydro Resources Corporation will cooperate in the development of an appropriate Stage 1 Abatement Plan for the facility.

Please contact me at (505) 827-1046 with any questions you may have.

Regards,

Greg Huey
Ground Water Quality Bureau

Enc.: Water Quality Sample Reports

11-30-2009

7

NEW MEXICO
ENVIRONMENT DEPARTMENT

Ground Water Quality Bureau

1190 St. Francis Drive, P.O. Box 5469
Santa Fe, New Mexico 87502
Phone (505) 827-2900 Fax (505) 827-2965
www.nmenv.state.nm.us

BILL RICHARDSON
Governor
DIANE DENISH
Lieutenant Governor

RON CURRY
Secretary
JON GOLDSTEIN
Deputy Secretary

CERTIFIED MAIL – RETURN RECEIPT REQUESTED

DATE: November 30, 2009

TO: Holland Shepherd, Program Manager, Mining Act Reclamation Program

FROM: Greg Huey, Ground Water Quality Bureau
Neal Schaeffer, Surface Water Quality Bureau

THROUGH: Kurt Vollbrecht, NMED Mining Act Team Leader

RE: New Mexico Copper Corporation, Copper Flat Exploration Project, Minimal Impact Exploration Project Permit Application, Permit No. SI022EM

The New Mexico Environment Department (NMED) received the Copper Flat Exploration Project Minimal Impact Exploration Permit Application from the Mining Act Reclamation Program (MARP) on November 10, 2009. MARP requested that the application be reviewed and all comments returned within 20 days of receipt. A site inspection was conducted on November 17, 2009 and comments were submitted prior to the November 30, 2009 deadline.

Pursuant to Subpart 302.G of the New Mexico Mining Act Rules (NMMA), the NMED Air Quality Bureau, Surface Water Quality Bureau and Ground Water Quality Bureau have reviewed the Copper Flat Exploration Minimal Impact Exploration Project Permit Application. The Surface Water Quality Bureau and Ground Water Quality Bureau are submitting comments jointly in this memorandum. Air Quality Bureau comments are provided under a separate memorandum.

Site Location and Description

The proposed Copper Flat Exploration Project is located in Township 15S, Range 7W of Section 26, Sierra County, NM. Hydro Resources Corporation, Cu Flat LLC and GCM, Inc. of Albuquerque, NM are the joint owners of surface and mineral rights to the property.

The total proposed exploration disturbance is less than 5 acres. Depth to ground water is estimated to be 30 feet.

Three drill sites are proposed, with two drill holes per site to a depth of 600 feet. No access roads or drill pad construction will be necessary, as the drill sites are within a previously excavated and graded bedrock bench remaining from a previous mining operation.

Drilling mud and additives are to be stored in metal tanks during the operational phase. The proposal calls for the disposal of drilling mud and additives into drilling holes after drilling is completed. It is then proposed that the drill holes are to be plugged with drilling mud from total depth to ten feet below ground surface and completed with a cement plug from ten feet below ground surface to the existing ground surface.

Permit Application Requirements and Minimal Impact Status

The permit application states that bore holes will be plugged with drilling mud. According to the New Mexico Office of the State Engineer requirements and New Mexico Mining Act Rules, drill holes must be plugged from the bottom of the hole to the land surface with cement or high density bentonite clay, with the top ten feet of the hole plugged with cement. Drilling mud is not a satisfactory bore hole abandonment material.

New Mexico Mining Act Rules prohibit disposal of drill cuttings, drill mud or additives into excavated drill holes. NMMA §19.10.3.K provides guidance for construction and reclamation of pits for drill waste disposal.

In general, the following measures should be implemented at exploration drill sites to provide for protection of surface and ground water quality:

- A minimum setback from surface water of 100 feet must be maintained for all drill pads and associated activities.

- All exploration activities need to implement Best Management Practices in a manner that prevents direct impacts to surface water and watercourses (ephemeral, intermittent and perennial). For surface disturbances during exploration and reclamation activities, the operator must commit to implementing erosion control measures that are designed, constructed and maintained using professionally recognized standards (e.g. Natural Resource Conservation Service Standards or the Bureau of Land Management "Gold Book").

- All heavy equipment used in the project area must be pressure washed and/or steam cleaned before the start of the project and inspected daily for leaks. A written log of inspections and maintenance should be completed.

- Appropriate spill clean-up materials, such as absorbent pads, must be available on-site at all times during drilling activities to address potential spills.

- Spills must be reported immediately to the NMED as required by the New Mexico Water Quality Control Commission Regulations (20.6.2.1203 NMAC). For non-emergencies

during normal business hours, call (505) 428-2500. For non-emergencies after hours, call (866) 428-6535 or (505) 428-6535 (voice mail, twenty-four hours a day). For emergencies only, call (505) 827-9329 twenty-four hours a day (NM Dept of Public Safety).

- The applicant must contain any water produced from the exploration holes at the drill site. Discharge of this water or any drilling fluids to any watercourse may be a violation of the Clean Water Act. All drilling cores should be collected and disposed of properly.

- This project may require coverage under a Clean Water Act §402 permit, such as for construction or industrial storm water, or for an NPDES process wastewater discharge. Failure to receive and implement proper permit coverage would be a violation of the Clean Water Act. A Construction General Permit, Notice of Intent (NOI), Fact Sheet, and Federal Register notice can be downloaded at http//cfpub.epa.gov/npdes/stormwater/cgp.cfm. The Industrial General Permit, NOI, Fact Sheet, and Federal Register notice can be downloaded at http://cfpub.epa.gov/npdes/stormwater/msgp.cfm. If you have questions about this coverage, please contact Rich Powell, NMED SWQB, at (505) 827-2798.

- The applicant should consult with the USACE to verify whether the proposed activity will require Clean Water Act §404 permitting.

- Boreholes must be abandoned in accordance with the New Mexico Office of the State Engineer requirements and New Mexico Mining Act Rules, including complete plugging from the bottom of the hole to the land surface with cement or high density bentonite clay.

NMED finds the proposed exploration activities are likely to have a minimal environmental impact if operated and reclaimed in accordance with the approved permit and requirements listed above.

cc: William C. Olson, Bureau Chief, GWQB
Glenn Saums, Acting Chief, SWQB
Rachel Jankowitz, NMDGF
Mary Ann Menetrey, GWQB-MECS
Charles Thomas, Bureau Chief, EMNRD-MMD

5-5-2010

NEW MEXICO
ENVIRONMENT DEPARTMENT

Ground Water Quality Bureau

PUBLIC RECORDS RELEASE FORM

* Please complete this form for each facility requested.

Pre-Review

~~Greg Hoeg~~ Cindy Ardito (Intera)

Reviewers Name: ~~[redacted]~~ **Facility requested:** Copper Flat mine **DP#** 01

Number of files given out: **C-** 1-5 **M-** 1-3 **Maps, designs, etc.:** —

Records Inspection (On-site)

Date: 5-5-10 **Time:** 10:20 am/pm **Company:** INTERA **Phone #:** 8246-1600

Name: Cindy Ardito **Signature:** [signature]

I acknowledge I have read and agree to the attached Notice of Right to Inspect Public Records

Copy Service (Off-site)

Records Check-Out:

Date: 5/12/10 **Time:** 4:35 am/pm **Company:** Paper Tiger **Phone #:** _____

Name: _____ **Signature:** _____

I acknowledge I have read and agree to the attached Notice of Right to Inspect Public Records

Estimated date of return: 5/14/10

Records Check-In:

Date: 5/14/10 **Time:** 4:35 am/pm **Company:** Paper Tiger **Phone #:** _____

Name: _____ **Signature:** _____

Post-Review

Reviewers Name: Cindy Ardito **Facility requested:** Cu Flat **DP#** 1

Number of files given out: **C-** 1-5 **M-** 1-3 **Maps, designs, etc.:** —

Documents returned in good condition (circle)? Yes/No

COPY

COPY

NEW MEXICO ENVIRONMENT DEPARTMENT
INSPECTION OF PUBLIC RECORDS ACT PRIVATE COPY FACILITY AUTHORIZATION

1. Requestor's name: Cynthia Ardito, Intera Inc.
2. Requestor's email: cardito@intera.com
3. Requestor's address: 6000 uptown Blvd, NE Suite 100, Albuquerque 87110
4. Requestor's telephone: (505) 379-7330
5. Private copy facility's name: _____
6. Private copy facility's address: _____
7. Private copy facility's telephone: (_____) Paper Tiger
8. Documents/files/records to be copied: DP-01 Copper Flat Mine
   Monitoring FILES 1-3
   Correspondence FILES 1-6
9. Date documents/files/records provided to private copy facility: _____
10. Department personnel authorizing release: Pat Hurley (MECS)
11. Date documents/files/records to be returned to Department: _____

DOCUMENTS SHALL BE RETURNED TO THE DEPARTMENT WITHIN 24 HOURS OF RELEASE.

THE PRIVATE COPY FACILITY SHALL NOT RELEASE ANY DEPARTMENT DOCUMENTS/FILES/RECORDS TO THE REQUESTOR OR TO ANY OTHER PERSON OR ENTITY OTHER THAN DEPARTMENT PERSONNEL.

THE PRIVATE COPY FACILITY SHALL NOT TAMPER WITH OR ALTER ANY DEPARTMENT DOCUMENTS/FILES/RECORDS, NMSA 1978, § 30-26-1, AND SHALL ACCURATELY TRACK THE DOCUMENTS/FILES/RECORDS IN ITS POSSESSION.

5/12/10 4:35 pm
Authorized signature for private copy facility
Print name: _____

Date documents returned: 5/14/10 4:40pm
Received by: Dana S

New Mexico Copper Corporation

September 3, 2010

Mr. Chris Eustice
Senior Environmental Engineer
Mining Act Reclamation Program
Mining and Mineral Division
1220 South St. Francis Drive
Santa Fe, New Mexico 87505

Dear Mr. Eustice;

On behalf of New Mexico Copper Corporation (NMCC), please accept the enclosed Sampling and Analysis Plan (SAP) for the proposed Copper Flat Mine located approximately 6 miles east of Hillsboro, New Mexico. The SAP has been prepared in accordance to the New Mexico Administrative Code (NMAC) 19.10.6.602.D and the August 2010 Guidance Document for Part 6, New Mining Operation Permitting Under the New Mexico Mining Act.

Also enclosed is a $5,000 check to address the base mine permit application fee.

I, Jon Steven Raugust, certify that I have personally examined and am familiar with the information submitted herein, and based on my inquiry of those individuals responsible for obtaining the information; I believe the submitted information is true, accurate, and complete.

Please contact me at 505.382.5770 or by email at steve.raugust@gmail.com if you have any questions or comments regarding NMCC's Copper Flat Mine Project.

Respectfully,

J. Steven Raugust, P.G.
Project Manager

Cc: Barrret Sleeman, P.Eng., CEO, New Mexico Copper Corporation

Enclosures:

1. Sampling and Analysis Plan for the Copper Flat Mine Project (6 hard copy, 1 electronic copy)
2. One check for $5,000.

2425 San Pedro, NE, Suite 200
Albuquerque, New Mexico 87110

505.382.5770

Sampling and Analysis Plan
for
Copper Flat Mine

September 2010

Prepared for:
New Mexico Copper Corporation

Submitted to:
Mining and Minerals Division
New Mexico Energy, Minerals and Natural Resources Department

Prepared by:

INTERA

with support from Parametrix and Class One Technical Services

00026

Table of Contents

Acronyms and Abbreviations **1**

1 Introduction to the Copper Flat Sampling and Analysis Plan **1-1**

1.1 Background 1-1
1.2 Applicant Information and General Plan 1-1
1.2.1 Name of Permit Applicant 1-1
1.2.2 Map of Proposed Site 1-1
1.2.3 Surface Ownership Map with Mineral Estates at the Proposed Site 1-2
1.2.4 List of Surface Owners 1-2
1.2.5 Access Agreements 1-2
1.2.6 Contact Information for Surface Owners 1-2
1.2.7 Statement of U.S.-Based Mining Operations Directly Controlled by Applicant, Owner, or Operator 1-3
1.2.8 Contact Information for the Applicant's Designated Agent 1-3
1.3 Sampling and Analysis Plan 1-3
1.4 Summary of Historical Mining Operations 1-4
1.4.1 Mining History 1-4
1.4.2 Surface Features of the Copper Flat Mine 1-5
1.4.3 Historical Investigations 1-5
1.5 Description of Proposed Mining Operations 1-6
1.6 References 1-7

2 Climatological Factors **2-1**

2.1 Introduction and Background 2-1
2.2 Sampling Objectives 2-2
2.2.1 Meteorological 2-2
2.2.2 Air Quality – Particulate (PM10) 2-2
2.3 Sampling Frequency 2-3
2.3.1 Meteorological Station 2-3
2.3.2 Air Quality Station 2-3
2.4 List of Data to Be Collected 2-3
2.4.1 Meteorological 2-3
2.4.2 Particulate (PM10) 2-3
2.5 Methods of Collection 2-3
2.5.1 Meteorological Monitoring 2-3
2.5.2 Air Quality Monitoring 2-4
2.6 Parameters to be Analyzed 2-4
2.6.1 Meteorological Parameters 2-4
2.6.2 Air Quality Parameters 2-4

2.7 Maps Showing Proposed Sampling Locations 2-4
2.8 Laboratory and Field Quality Assurance Plans 2-5
2.8.1 General 2-5
2.8.2 Quality Assurance Procedures for Meteorological Station 2-5
2.8.3 Quality Assurance Procedures for Air Quality Station 2-14
2.9 Discussion in Support of Proposal 2-14
2.9.1 Total Suspended Particulates 2-14
2.9.2 Particulate Matter Less than 10 Micrometers 2-14
2.10 References 2-15

3 Topography 3-1
3.1 Introduction and Background 3-1
3.2 Sampling Objectives 3-1
3.3 List of Data to be Collected 3-1
3.4 Methods of Collection 3-1
3.5 Parameters to be Analyzed 3-2
3.6 Maps Providing Sampling Locations 3-2
3.7 Sampling Frequency 3-2
3.8 Laboratory and Field Quality Assurance Plan 3-2

4 Vegetation 4-1
4.1 Introduction and Background 4-1
4.2 Sampling Objectives 4-1
4.3 Sampling Frequency 4-2
4.4 List of Data to be Collected 4-2
4.5 Methods of Collection 4-2
4.5.1 Site Stratification 4-2
4.5.2 Plant Species Inventory 4-3
4.5.3 Rare, Threatened, or Endangered Plant Species 4-3
4.5.4 Noxious Weeds 4-4
4.5.5 Sampling Methodology 4-4
4.6 Parameters to be Analyzed 4-6
4.7 Maps Showing Proposed Sampling Locations 4-6
4.8 Laboratory and Field Quality Assurance Plans 4-6
4.8.1 Personnel 4-6
4.8.2 Sampling Protocol 4-6
4.8.3 Data Quality Assurance and Quality Control 4-7
4.9 Discussion in Support of Sampling Proposal 4-7
4.10 References 4-7

5 Wildlife 5-1
5.1 Introduction and Background 5-1
5.2 Sampling Objectives 5-1

5.3 Sampling Frequency 5-2
5.4 List of Data to be Collected 5-2
5.5 Methods of Collection 5-2
5.6 Parameters to be Analyzed 5-2
5.7 Maps Showing Proposed Sampling Locations 5-3
5.8 Laboratory and Field Quality Assurance Plans 5-3
5.9 Discussion in Support of Sampling Proposal 5-3
5.10 Resources 5-3
5.11 References 5-4

6 Topsoil Survey and Sampling 6-1
6.1 Background and General Description of Topsoil 6-1
6.2 Sampling Objectives 6-1
6.3 Sampling Frequency 6-2
6.4 List of Data to Be Collected 6-2
6.5 Methods of Collection 6-2
6.5.1 Sampling Methods 6-3
6.6 Parameters to Be Analyzed 6-5
6.7 Maps Showing Proposed Sampling Locations 6-6
6.8 Laboratory and Field Quality Assurance Plans 6-6
6.9 Discussion in Support of Proposal 6-6
6.10 References 6-6

7 Geology 7-1
7.1 Regional Geologic Setting 7-1
7.2 Geology of Copper Flat Mine Site 7-1
7.2.1 Stratigraphy 7-1
7.2.2 Structure 7-2
7.3 Description of the Ore Body 7-3
7.3.1 Structure and Model 7-3
7.3.2 Mineralization 7-4
7.4 Geochemical Sampling 7-5
7.4.1 Step 1: Data Review and Material Type Delineation 7-5
7.4.2 Step 2: Sample Interval Selection 7-6
7.4.3 Step 3: Sample Collection and Field Screening 7-6
7.4.4 Step 4: Geochemical Test Work 7-7
7.4.5 Step 5: Kinetic Testing Program 7-7
7.4.6 Step 6: Data Validation and Compilation 7-7
7.5 References 7-8

8 Surface Water 8-1
8.1 Surface Water Characteristics of Site and Vicinity 8-1
8.2 Historical Data 8-2

8.3 Sampling Objectives 8-3
8.4 Sampling Frequency 8-3
8.5 List of Data To Be Collected 8-4
8.6 Methods of Collection 8-4
8.6.1 Surface Water Samples from Springs and Drainages 8-4
8.6.2 Pit Lake Sampling 8-7
8.7 Parameters to Be Analyzed 8-8
8.8 Maps Showing Proposed Sampling Locations 8-8
8.9 Laboratory and Field Quality Assurance Plans 8-9
8.10 Discussion in Support of Proposal 8-9
8.11 References 8-9

9 Groundwater 9-1
9.1 Regional Hydrogeology 9-1
9.1.1 Hydrogeology of the Permit Area 9-2
9.1.2 Aquifer Characteristics in the Permit Area 9-2
9.1.3 Existing Baseline Groundwater Information 9-5
9.1.4 NMED Stage 1 Abatement Plan Requirements 9-6
9.1.5 Statistical Analysis of Existing Baseline Data 9-7
9.2 Sampling Objectives 9-8
9.3 Sampling Frequency 9-8
9.4 List of Data to Be Collected 9-9
9.4.1 Groundwater Quality Parameters 9-9
9.4.2 Aquifer Parameters 9-9
9.5 Methods of Collection 9-9
9.5.1 Water Level and Total Depth Measurements SOP 9-9
9.5.2 Monitoring Well Sampling for Groundwater SOP 9-11
9.5.3 Aquifer Testing and Analysis SOP 9-17
9.5.4 Monitoring Well Installation 9-21
9.6 Parameters to be Analyzed 9-21
9.7 Maps Showing Proposed Sampling Locations 9-21
9.8 Laboratory and Field Quality Assurance Plans 9-21
9.9 Discussion in Support of Proposal 9-22
9.10 References 9-24

10 Historical and Cultural Properties Survey 10-1
10.1 Introduction and Background 10-1
10.2 Sampling Objectives 10-2
10.3 Sampling Frequency 10-3
10.4 List of Data to be Collected 10-3
10.5 Methods of Collection 10-3
10.5.1 Site Definition 10-3
10.5.2 Site Recording 10-4

10.5.3 Isolated Manifestation Recording 10-5
10.5.4 Mapping 10-5
10.5.5 Historical Cultural Properties 10-5
10.6 Parameters to be Analyzed 10-6
10.7 Map Showing Proposed Sampling Locations 10-6
10.8 Laboratory and Field Quality Assurance Plans 10-6
10.9 Discussion in Support of Sampling Proposal 10-6
10.10 References 10-7

11 Present and Historical Land Use 11-1
11.1 Present Land Use 11-1
11.1.1 Land Ownership and Status 11-1
11.1.2 Land Planning and Regional Land Use 11-2
11.1.3 Current Land Use and Structures at Site 11-2
11.1.4 Access, Rights of Way, and Water Rights 11-2
11.2 Environmental Liabilities and Permits 11-3
11.3 Pertinent Historical Land Use 11-3
11.4 References 11-5

List of Figures

Figure 1-1 Site Location
Figure 1-2 Proposed Copper Flat Permit Area with Topography
Figure 1-3 Proposed Copper Flat Permit Area with Air Photography
Figure 1-4 Proposed Copper Flat Permit Area with Land Ownership and Claims
Figure 1-5 Proposed Copper Flat Permit Area with the Pit, Three Waste Piles, a Tailings Impoundment Area, and a Plant-Facilities Area
Figure 2-1 Topographic Map Showing the Locations of the Proposed Particulate (PM_{10}) and Meteorological Monitoring Stations
Figure 3-1 Topographic Map of the Site and Surrounding Area
Figure 3-2 Aerial Photograph of the Site
Figure 3-3 Topographical Map with Boundary
Figure 4-1 Graphical Depiction of the Strata Recommended for Vegetation Sampling and Analysis
Figure 4-2 Map of the Proposed Vegetation Transect Sampling Locations and Site Strata
Figure 5-1 Map of the Proposed Wildlife Transects and Site Strata
Figure 6-1 Topsoil Sampling Locations
Figure 7-1 Regional Surface Geology
Figure 7-2 Schematic Geologic Cross Section (A-A')
Figure 7-3 Geologic Structural Features of the Region
Figure 7-4 Geologic Schematic of the Hillsboro Mining District, New Mexico
Figure 7-5 Locations of Geologic Samples
Figure 8-1 Proposed Surface Water Sampling Locations
Figure 8-2 Proposed Parallel Profiles for Pit Lake Survey
Figure 9-1 Lower Rio Grande Basin

Figure 9-2 Conceptual Model of Groundwater Flow System
Figure 9-3 Spring and Stream Locations
Figure 9-4 Water Level Contours
Figure 9-5 Water Level Map of Copper Flat Pit Area
Figure 9-6 Conceptual Model of Pit Lake Monitoring Well Relationship with Water Quality Reports
Figure 9-7 Conceptual Design, Tailings Seepage Control
Figure 9-8 Schematic Geologic Cross Section (A-A')
Figure 9-9 Regional Groundwater Well Locations
Figure 9-10 Proposed Monitoring Well Program
Figure 9-11 Wells Sampled in January 2010
Figure 10-1 Aerial Photograph Showing the Proposed Survey Area for Cultural Resources Investigation
Figure 11-1 Land Ownership Status
Figure 11-2 Noncontiguous Mill Site Claims
Figure 11-3 Aerial View to the West at Copper Flat Mine, 1982
Figure 11-4 Aerial View to the East at Copper Flat Mine, 1982
Figure 11-5 Proposed Copper Flat Permit Area with Air Photography

List of Tables

Table 2-1 Meteorological Data to be Collected
Table 2-2 Summary of Meteorological Audit Criteria
Table 4-1 List of the Current Data Needs Addressed in this Report
Table 4-2 List of Vegetation Attributes, Data Sources, and Proposed Analysis Processes
Table 6-1 Topsoil Data Needs
Table 6-2 Soil Characteristics and Methods Used
Table 7-1 Stratigraphy of the Copper Flat Area
Table 7-2 Proposed Analytical Parameters with Method Reporting Limits
Table 8-1 Historical Flow and Water Quality Parameters
Table 8-2 Proposed Surface Water Monitoring Locations (as shown on Figure 8-1) with Method of Measurement and Frequency of Collection
Table 8-3 Surface Water Resources Data Needs
Table 8-4 Analytical Parameters and Analysis Methods for Surface Water and Sediment Samples
Table 9-1 Groundwater Sampling and Data Analysis Plan
Table 9-2 Proposed Monitoring Wells for Water Quality Sampling and Water Level Measurements
Table 9-3 Analytical Parameters and Analysis Methods for Groundwater Samples
Table 9-4 Groundwater System Characteristics (from SRK, 1995)
Table 11-1 Permits and Approvals Required for the Copper Flat Mine

List of Attachments

Attachment 1: Quality Assurance Project Plan
Attachment 2: Access Agreement

Acronyms and Abbreviations

ABA	acid base accounting
Alta Gold	Alta Gold Company
amsl	above mean sea level
APE	area of potential effects
AWRM	Active Water Resource Management
bgs	below ground surface
BLM	U.S. Bureau of Land Management
cc	cubic centimeter
CFQM	Copper Flat Quartz Monzonite
CFR	Code of Federal Regulations
cfs	cubic feet per second
cm	centimeter
CRMD	New Mexico State University Cultural Resources Management Division
CTS	Class One Technical Services
^{O}F	degrees Fahrenheit
DTW	depth to water
DVM	digital volt meter
EA	Environmental Assessment
EIS	Environmental Impact Statement
EMNRD	New Mexico Energy, Minerals and Natural Resources Department
EPA	U.S. Environmental Protection Agency
ESD	Ecological Site Description
ft	feet
GIS	Geographic Information System
Gold Express	Gold Express Corporation
gpm	gallons per minute
GPS	Global Positioning System
HCPI	New Mexico Historic Cultural Properties Inventory
HSR	Human Systems Research, Inc.
HSU	hydrostratigraphic unit
IM	isolated manifestation
INTERA	INTERA, Incorporated
JFD	joint frequency distribution
Km	kilometer
kV	Kilovolt
l/min	liters per minute
LA	Laboratory of Anthropology
LOG	lognormal
LRGB	Lower Rio Grande Underground Water Basin
m	meter
Ma	million years ago
mb	millibars
mg/L	milligrams per liter
ml	milliliter

mm	millimeter
MMD	New Mexico Mining and Minerals Division
MSF	Middle Santa Fe Group hydrostratigraphic unit
Mst	million standard tons
MVA	Megavolt-ampere
MWMP	Meteoric Water Mobility Procedure
NAD	North American Datum
NAG	Net Acid Generation
NELAP	National Environmental Laboratory Accreditation Program
NHPA	National Historic Preservation Act
NIST	National Institute of Standards and Technology
NMAAQS	New Mexico Ambient Air Quality Standards
NMAC	New Mexico Administrative Code
NMCC	New Mexico Copper Corporation
NMCRIS	New Mexico Cultural Resources Information System
NMED	New Mexico Environment Department
NMED GWQB	New Mexico Environment Department Groundwater Quality Bureau
NMED SWQB	New Mexico Environment Department Surface Water Quality Bureau
NMSRCP	New Mexico State Register of Cultural Properties
NORM	normal
NP	nonparametric
NPS	National Park Service
NRCS	Natural Resources Conservation Service
NRHP	National Register of Historic Places
OSE	New Mexico Office of the State Engineer
oz	ounce
PFEIS	Preliminary Final Environmental Impact Statement
$PM_{[x]}$	particulate matter less than [x] micrometers
PSD	prevention of significant deterioration
QA/QC	quality assurance/quality control
QAPP	Quality Assurance Project Plan
Quintana	Quintana Minerals Corporation
R	range
RAM	random access memory
RH	relative humidity
Rio Gold	Rio Gold Mining Ltd
ROW	right-of-way
rpm	revolutions per minute
SAP	Sampling and Analysis Plan
SCS	Soil Conservation Service
SHPO	New Mexico State Historic Preservation Officer
Site	Copper Flat Mine Permit Area
SOP	standard operating procedure
SRK	Steffen Robertson and Kirsten, Inc.
st	standard ton
S-W	Shannon-Weiner Index
T	township

TD	total depth
TDS	total dissolved solids
Tenneco	Tenneco Minerals
TSP	total suspended particulates
TSS	total suspended solids
$\mu g/m^3$	micrograms per cubic meter
USBR	U.S. Bureau of Reclamation
USF	Upper Santa Fe Group hydrostratigraphic unit
USGS	U.S. Geological Survey
UTM	Universal Transverse Mercator
VOA	volatile organic analysis
WQCC	New Mexico Water Quality Control Commission

Table of Contents

1 Introduction to the Copper Flat Sampling and Analysis Plan 1-1

1.1 Background 1-1

1.2 Applicant Information and General Plan 1-1

1.2.1 Name of Permit Applicant 1-1
1.2.2 Map of Proposed Site 1-1
1.2.3 Surface Ownership Map with Mineral Estates at the Proposed Site 1-2
1.2.4 List of Surface Owners 1-2
1.2.5 Access Agreements 1-2
1.2.6 Contact Information for Surface Owners 1-2
1.2.7 Statement of U.S.-Based Mining Operations Directly Controlled by Applicant, Owner, or Operator 1-3
1.2.8 Contact Information for the Applicant's Designated Agent 1-3

1.3 Sampling and Analysis Plan 1-3

1.4 Summary of Historical Mining Operations 1-4

1.4.1 Mining History 1-4
1.4.2 Surface Features of the Copper Flat Mine 1-5
1.4.3 Historical Investigations 1-5

1.5 Description of Proposed Mining Operations 1-6

1.6 References 1-7

List of Figures

Figure 1-1 Site Location
Figure 1-2 Proposed Copper Flat Permit Area with Topography
Figure 1-3 Proposed Copper Flat Permit Area with Air Photography
Figure 1-4 Proposed Copper Flat Permit Area with Land Ownership and Claims
Figure 1-5 Proposed Copper Flat Permit Area with the Pit, Three Waste Piles, a Tailings Impoundment Area, and a Plant-Facilities Area

1 Introduction to the Copper Flat Sampling and Analysis Plan

1.1 Background

The New Mexico Copper Corporation (NMCC) plans to re-open the Copper Flat Mine, a porphyry copper/molybdenum/gold deposit located in the Hillsboro Mining District in South Central New Mexico, in Sierra County. The Cooper Flat Mine is approximately 20 miles southwest from Truth or Consequences, New Mexico and approximately 5 miles northeast of Hillsboro, New Mexico (Figure 1-1). The proposed mining operation is located in Sections 30 and 31, Township 15 South, Range 5 West (T15S, R5W); Sections 30 and 31, T15S, R6W; Sections 23 through 27 and 34 through 36, T15S, R7W; Section 6, T16S, R6W; and Section 2, T16S, R7W (all with reference to the New Mexico Principal Meridian) in Sierra County, New Mexico. The mineralized zone is centered at approximately latitude 32.970300, longitude −107.533527.

Baseline data has been collected at the Copper Flat project starting in the late 1970s by Quintana, followed by Rio Gold Mining Ltd (Rio Gold), Gold Express, and Alta Gold Company (Alta Gold). This data is relevant and provides insights for future permitting activities. The Copper Flat Mine was first permitted by Quintana Minerals (Quintana) during the 1980s. In 1992, a new plan of operations was submitted and an environmental assessment (EA) was begun by Gold Express, but the operation was never restarted. Alta Gold acquired the property in the mid-1990s and reinitiated the permitting and approvals process, collecting significant baseline data and submitting applications for all major state and federal permits. Alta Gold declared bankruptcy in early 1999, but not before a draft environmental impact statement (DEIS, 1996) and preliminary final EIS (PFEIS, 1999) had been prepared and the associated public comments received; a public hearing had also been held on the New Mexico Mining Act Permit and the New Mexico Groundwater Discharge Permit. However, no final permits had been issued and there had been no opportunity for appeals or litigation regarding the operation. Figures 1-2 and 1-3 illustrate the Site permit boundary with topography and the 2009 aerial photo, respectively.

For the purposes of this sampling and analysis plan (SAP), the permit area is defined as the Site as illustrated on Figure 1-2. The Copper Flat project is composed of approximately 3,304.75 acres in contiguous and noncontiguous lands that include patented and unpatented mining claims (lode, placer, and mill site), and fee parcels. The acreage inside the Site permit boundary is 2,190 acres. NMCC will mine copper ore by open pit extraction methods in the area. Molybdenum, gold and silver will be recovered as byproducts.

The following sections provide an overview of the requirements and content of this SAP, a summary of previous mining activity and investigations, and a description of the proposed mining operations, which provide a basis for understanding the baseline data gathering needs related to the planned mine construction and operations. A mine plan will be submitted at a later date with the mine permit application to detail the construction and operation of the mine.

1.2 Applicant Information and General Plan

1.2.1 Name of Permit Applicant

New Mexico Copper Corporation, a New Mexico corporation.

1.2.2 Map of Proposed Site

Figures 1-2 and 1-3 present the Site permit boundary on a topographic map and a 2009 aerial photograph, respectively.

1.2.3 Surface Ownership Map with Mineral Estates at the Proposed Site

Figure 1.4 presents the map of all known owners of surface and mineral estates within the proposed permit area as of September 1, 2010. This map has been prepared by a qualified mineral title specialist working in collaboration with NMCC's legal counsel, Mark K. Adams of Rodey, Dickason, Sloan, and Robb, PA. This land ownership map is preliminary and subject to update and revision as continued title research is performed and evaluated. The final land ownership map will be submitted with the Phase II Permit Application Package.

1.2.4 List of Surface Owners

According to the 2010 property tax schedule of the Sierra County Assessor, Hydro Resources Corporation (Hydro) and Cu Flat, LLC (Cu Flat) own all of the fee lands within the permit area except as follows:

- Edgar E. Greer ("Greer") owns the fee surface estate in the lands within the permit area in Sections 30 and 31, Township 15 South, Range 6 West, and has contracted to sell his fee surface estate to Ryan G. and Wendy M. Fancher (the "Fanchers"). The mineral estate in such lands is owned by the United States and is subject to unpatented mining claims owned by Hydro and GCM, Inc. (GCM).
- Greer owns the fee surface and mineral estates in the Cincinnati, Graf Von Luxenburg, and Prosper patented mining claims in Sections 25 and 36, Township 15 South, Range 7 West, and has contracted to sell such claims to the Fanchers.
- The non-fee lands within the permit area are owned by the United States. All such lands are subject to unpatented mining claims owned by Hydro and GCM.

All of the fee lands and unpatented mining claims within the permit area owned by Hydro, Cu Flat, and GCM are subject to the Option and Purchase Agreement described in 1.2.5 below.

1.2.5 Access Agreements

The Applicant has the right to enter the proposed permit area and conduct mining and reclamation operations on all lands on which such operations will be conducted or cause disturbance under an Option and Purchase Agreement dated July 23, 2009 by and between Applicant, as Optionee, and Hydro, Cu Flat, GCM, as Optionor. The Option and Purchase Agreement has been amended by a First Amendment dated January 20, 2010, a Second Amendment dated April 1, 2010, a Third Amendment and Supplemental Memorandum dated May 28, 2010, and a Fourth Amendment dated August 2, 2010. This agreement and associated amendments are presented in Attachment 2, Access Agreements.

With respect to the Edgar E. Greer lands within the permit boundary and under contract to Ryan and Wendy Fancher, NMCC has initiated formal negotiations with Ryan and Wendy Fancher for use of the fee surface and mineral estates described in Section 1.2.4. There has been a history of land arrangements with Edgar E. Greer with previous mining companies (Quintana Minerals and Alta Gold), however, these negotiations are expected proceed in parallel with the collection of the baseline data and be concluded prior to the submittal of the Permit Application Package.

1.2.6 Contact Information for Surface Owners

The Applicant owns and controls the entire interest in the proposed Copper Flat operation. The Applicant's address is 2425 San Pedro, NE, Suite 200, Albuquerque, New Mexico 87110, and its telephone number is 505-382-5770. THEMAC Resources Group Limited (THEMAC), a Yukon corporation, owns and controls all of the Applicant's shares. THEMAC's address is Suite 2000, 1066 West Hastings Street, Vancouver, British Columbia, Canada, V6E 3X2, and its telephone number is (+1) 604-495-6723.

1.2.7 Statement of U.S.-Based Mining Operations Directly Controlled by Applicant, Owner, or Operator

Neither NMCC nor THEMAC owns, operates, or directly controls any mining operation in the United States.

1.2.8 Contact Information for the Applicant's Designated Agent

Barrett E.G. Sleeman, President and Chief Executive Officer, THEMAC Resources Group Limited, Suite 2000, 1066 West Hastings Street, Vancouver, British Columbia, Canada, V6E 3X2, (+1) 604-495-6723, barrettsleeman@hotmail.com.

1.3 Sampling and Analysis Plan

The permitting of new non-coal mines is governed by 19.10.6 NMAC (New Mexico Administrative Code). This SAP is submitted to the New Mexico Energy, Minerals and Natural Resources Department (EMNRD) Mining and Minerals Division (MMD) by NMCC as the first phase in the mine permitting process. The second phase will be submittal of the baseline characterization report and the mine permit application.

The SAP provides the sampling and analysis procedures for the data to be included in the baseline characterization report described in Paragraph (13) of Subsection D of 19.10.6.602 NMAC. As described in Part 6, baseline data include the (1) hydrological, (2) geological, (3) mineralogical, (4) ecological, and (5) cultural components within the proposed Site and the area outside of the Site that will be affected by the proposed mining activity at the Copper Flat Mine.

Pursuant to Paragraph (13) of Subsection D of 19.10.6.602 NMAC, this SAP must contain seven data subcategories, which are further described in Tables 1 and 2 of the MMD draft guidance document (MMD, 2010). These subcategories and their location in this SAP are listed below.

- Climatological factors (Section 2)
- Vegetation survey (Section 4)
- Wildlife survey (Section 5)
- Topsoil survey/sampling (Section 6)
- Surface water sampling (Section 8)
- Groundwater sampling (Section 9)
- Historic and cultural properties survey (Section 10)

An eighth subcategory, radiological survey, is not required for non-uranium mines.

This SAP presents the data requirements identified for each subcategory and describes how these will be addressed, summarizes the sampling objectives, and describes the data collection methods for each subcategory or medium. Specifically, in accordance with Subparagraph (a) of Paragraph (12) of Subsection D of 19.10.6.602 NMAC, the following information is discussed for each of the seven subcategories:

- Sampling objectives
- Sampling frequency (in accordance with Table 2 of the 2010 MMD guidance for new mining operations)
- A list of data to be collected
- Methods of collection
- Parameters to be analyzed (as outlined in Table 1 of the 2010 MMD guidance)
- Maps showing proposed sampling locations

- Laboratory and field quality assurance plans
- A brief discussion supporting the proposed sampling plan and/or use of historical data

Where the methods of collection require the use of a Global Positioning System (GPS) receiver to record site features (e.g., discrete sampling locations, transect locations, surface drainage features, weather station locations, cultural resource locations, etc.), those data will be verified by reference to landscape features and landmarks shown on USGS quadrangle maps. All GPS data will then be differentially corrected for sub-meter accuracy. Shapefiles of these features will be created using a geographic information system (GIS) compatible with ArcGIS. The shapefiles and GPS data will be presented in a baseline summary report in both hard-copy format as report figures and digital format as Microsoft Excel tables and/or ESRI shapefiles.

The following additional information is included in this SAP:

- An overview of major topographic features and topographic maps at a scale of 1-inch equals 2000 feet (1:24,000) (Section 3 and throughout document)
- Conceptual mine layout for proposed operations (Section 1.5)
- Mine operation description (Section 1.5)
- General geology, ore body description, and geologic sampling (Section 7)
- Land use information (Section 11)
- Maps to illustrate all proposed sampling locations (at end of Sections 2, 4, 5, 6, 8, 9, and 10)

Extensive site characterization activities have been performed at the Copper Flat Mine as a result of previous mining activities and attempts to re-open the mine. This SAP presents the historical data that will be incorporated into the baseline characterization report along with procedures for acquiring new data that will be collected to fill data gaps and meet the requirements of 19.10.6 NMAC. All new data collection will be performed in compliance with the procedures defined in this SAP and the Quality Assurance Project Plan included as Attachment 1.

1.4 Summary of Historical Mining Operations

The following history of the Copper Flat Mine and the overview of previous investigations and sampling programs were summarized from BLM (1999), Raugust (2003), and SRK (2010). The results of previous sampling programs are discussed in the applicable sections of this SAP, as relevant.

1.4.1 Mining History

Mining activities in the Hillsboro Mining District, including gold mining from both placer and vein deposits, began in 1877. From 1877 to 1893, numerous shafts and adits were developed along veins that radiate to the southwest and northeast from Copper Flat. Placer workings were developed along most of the major creeks that drain to the east and southwest from Black and Animas Peaks. Between 1911 and 1931, underground deposits were further developed; approximately 65 percent of the $7 million of ore produced from the district before 1931 came from underground veins (BLM, 1999). Placer mining increased after 1932 until World War II; small-scale placer mining continues in the area today (Hedlund, 1985; McLemore, 2003 as cited in Raugust, 2003).

Copper exploration began in the area in the 1950s and continued through the early 1970s. Quintana Minerals Corporation (Quintana) leased the property in 1974 and defined reserves sufficient for mine development through an extensive drilling and sampling program. The Copper Flat Partnership, Ltd., with Quintana acting as mine operator, developed and operated an open pit copper mine at the Copper Flat location in 1982 that included a 15,000 ton-per-day flotation mill and a tailings impoundment. Poor economic conditions led to the

termination of mining after only 3 months of operation, although the mine remained on a maintenance status until 1986, at which point the facilities were dismantled and the Site was partially reclaimed (BLM, 1999). The mine produced 7.4 million pounds of copper, approximately 2,300 ounces of gold, and nearly 56,000 ounces of silver during its 3-month operational life (Hedlund, 1985). During the 1990s, several companies submitted plans to reopen the Copper Flat operation; however, none of the plans were realized. No mining activities have occurred at Copper Flat since 1982. More detail about copper exploration activities can be found in Section 11.3.

1.4.2 Surface Features of the Copper Flat Mine

Activity at the Copper Flat Mine in 1982 disturbed 358 acres of BLM-managed public lands and 331 acres of private lands (Figure 1-2). Surface features of the Copper Flat Mine include the following:

- A pit lake that covers approximately 12.8 acres and is about 40 feet (ft) deep.
- Overburden rock storage piles (disposal areas) to the north, west, south, and east of the pit.
- Former mine and mill areas including an unpaved but maintained road from NM Highway 152 to the mill area and a primitive road to the pit area, a 115-kilovolt power line, and a 20-inch welded steel water line.
- A previously state approved and permitted diversion channel re-routing Grayback Arroyo around the mine site.
- A tailings impoundment area, which is dammed by a 6,600-ft-long dam with a maximum crest height of 60 ft, and which includes at least 1.2 million tons of tailings over a 60-acre area (SRK, 1995).

1.4.3 Historical Investigations

A number of investigations and sampling programs have been undertaken at Copper Flat in the past 30 years; several of these provide valuable sources of baseline data as these were related to various permitting processes including EAs and a Draft EIS in 1996 and a Preliminary Final EIS in 1999. For example, in the 8-year period before the 1982 operations began, Quintana collected baseline data at the Site related to climate, soils, vegetation, wildlife, surface water, groundwater, and archeology (Glover, 1977). The geology, mining history, and mineral deposits associated with Copper Flat were described by Hedlund in 1985; the results of a later field investigation that included sampling, water supply information, and ore reserves were documented by Dunn (1992). Aquifer testing was performed as early as the late 1970s and early 1980s, as well as again related to Alta Gold's PFEIS processes in the late 1990s. At least two environmental assessments and one environmental impact statement were prepared for the Site during the 1990s (Raugust, 2003). A number of reports were prepared for Alta Gold in the late 1990s related to the DEIS process; these reports included but are not limited to those summarized by SRK, Adrian Brown Consultants, and ENSR; an independent evaluation was also prepared by Daniel B. Stephens & Associates, Inc. in 1997 (Raugust, 2003). During 2009 and early 2010, a Copper Flat drilling program was undertaken by NMCC to verify the historical Alta Gold data and to expand and refine the existing resources at Copper Flat (SRK, 2010).

Many of these previous investigations have sampled for vegetation, wildlife, soil, potential acid rock drainage, climate and air quality, surface water and groundwater at or near the Site. Between 1989 and 1998, the pit lake was sampled 65 times by various investigators (BLM, 1999). Samples were typically analyzed for pH, major cations and anions, and metals (Raugust, 2003). Attempts were made to measure the flow at local springs and seeps in the 1990s and surface water sampling of creeks began before the 1982 mining operations and continued sporadically until the late 1990s. Before 1996, only one well was available at the Site for groundwater sampling; two additional wells were drilled during 1996 and used for subsequent sampling in the late 1990s (Raugust, 2003). Groundwater samples have also been taken from wells downgradient of the tailings impoundment dam.

Characterization of waste rock from outcrop and storage piles was undertaken in 1994 and again in 1997 to assess existing geochemical characteristics and potential for future acid generation (Raugust, 2003).Test borings in the tailings impoundment area have also been undertaken to investigate the nature of near-surface material and its suitability as borrow material (Raugust, 2003).

1.5 Description of Proposed Mining Operations

A preliminary economic assessment (PEA) was conducted by SRK Engineers and Scientists (SRK 2010) to satisfy the Canadian Securities Administrators National Instrument 43-101. The PEA provides a preliminary overview of the Copper Flat mineral resources and operational mining activities. Mining operations at the Copper Flat deposit will be characterized by a low stripping ratio pit (strip ratio of 0.38, waste to minable resource), with the mining of disseminated porphyry mineralization situated in a moderately mountainous region. The pit was previously pre-stripped of waste prior to ore production when the mine was briefly operated in 1982. The various water diversion structures previously constructed around the pit area are still in place and will be used. Figure 1-5 illustrates the pit, three waste piles, a tailings impoundment area, and a plant-facilities area between the pit to the west and the tailings impoundment to the east.

The preliminary pit design was determined to be approximately 2,500 ft (east-west), 2,500 ft (North-South), and 900 ft deep. The pit design was broken into three phases for scheduling purposes, with 80-foot-wide ramps, 30-foot bench heights, and a maximum haul road grade of 10 percent.

Open pit mining will be conducted using conventional diesel-powered equipment, a combination of blast-hole drills, hydraulic face shovels, rubber-tired wheel loaders, and off-highway haul trucks. Support equipment such as graders, track dozers, and a water truck will aid in the mining of the mineral resources and waste.

Indicated and Inferred mineral resources were considered for all optimization and production scheduling analyses and were based on an internal cut-off grade of 0.14% Cu. (The internal cut-off grade is based on process and general and administrative [G&A] operating costs.) The PEA report includes the Inferred mineral resources that are considered too speculative geologically to have economic considerations applied to them that would enable them to be categorized as mineral reserves.

A variable cut-off grade strategy, with elevated cut-off grades for the first 14 years of production, increased the mill feed head grades in those years and provided over three years of low-grade stockpile processing after the pit mining operations ended.

Existing infrastructure in preservation includes items such as the primary access road, water systems, electrical power distribution, and the concentrate load-out facility. Where possible, existing serviceable items were presumed to be re-used or upgraded; otherwise new construction will be assumed.

The primary items that were assumed to be re-usable include the mine access road, the water well field, the primary freshwater pipeline, the main electrical substation at I-25, the 115kV power transmission lines, the 25kV power line to the well field, the reclaim tunnel, and the access cutting from the mill site to the tailings area.

Access to the mine site includes approximately 3 miles of all-weather gravel road, which will require re-grading in addition to some widening and work at key points.

The milling and process system will receive fresh water from a series of previously existing wells located about 8 miles east of the site. Additionally, the previously used 20-inch diameter pipeline was left in place. It was assumed that the wells will be uncapped and refitted with new pumps for current use, and that the pipeline will be in serviceable condition and can also be re-used. It was also assumed that the well field and pipeline pump stations powered via a 25kV power line can be reconnected and re-used.

Electrical power in the county is provided by Sierra Electric Co-op. A high-voltage substation is still in existence near Caballo, 13 miles to the east of the Site. This substation supplies a 115kV transmission line to the Site that is currently not live, as well as low-voltage distribution lines to the town of Hillsboro. The 115kV transmission line can be accessed for site power.

A new substation will need to be constructed at the Site. An emergency generator allowance was also included as backup power would be required in the event of power loss to maintain critical systems and to aid in a controlled shut down. NMCC is analyzing the viability of solar power generation to offset the mine's energy demand, along with other energy and water conservation measures.

Product concentrate will be produced on site, and the resulting dried bulk copper concentrate and bagged molybdenum concentrates will need to be shipped to other facilities. An on-site concentrate load-out facility will be required, and two possible off-site load-out facility locations have been identified. The off-site load-out facility would essentially be a fenced-in area adjacent to a new rail siding that has truck off-loading and railcar loading capabilities.

The copper concentrate will be transported via railcar to a smelter facility, such as the Freeport-McMoRan Miami Operation. Molybdenum product would be transported from the mill in "super sacks." A truck scale and scale house will be needed to weigh the copper concentrate and molybdenum concentrate trucks leaving the site en route to the load-out facility (SRK, 2010).

1.6 References

Bureau of Land Management (BLM), 1999, Preliminary final environmental impact statement, Copper Flat project: Las Cruces, N. Mex., U.S. Department of the Interior, 491 p. Prepared by ENSR, Fort Collins, Colo.

Dunn, P.G., 1992, Development geology of the Copper Flat porphyry copper deposit, Case study *in* SME Mining Engineering Handbook: Littleton, Colo., Society for Mining, Metallurgy, and Exploration, Inc.

Hedlund, 1985, Economic geology of some selected mines in the Hillsboro and San Lorenzo quadrangles, Grant and Sierra Counties, New Mexico: U.S. Geological Survey Open File Report 85-0456.

Glover, F.A., 1977, Environmental assessment report, Copper Flat mine development, Copper Flat, New Mexico.

McLemore, V.T., 2003, Personal Communication: Socorro, N. Mex., New Mexico Bureau of Geology and Mineral Resources.

Mining and Minerals Division (MMD), State of New Mexico, 2010, Guidance Document for Part 6 New Mining Operations Permitting under the New Mexico Mining Act, New Mexico Administrative Code Title 19, Chapter 10, Part 6, Draft for Review: New Mexico Energy Minerals and Natural Resources Department, Mining Act Reclamation Program, Santa Fe, New Mexico.

Raugust, J.S., 2003, The natural defenses of Copper Flat Sierra County, New Mexico: New Mexico Bureau of Geology and Mineral Resources Open-File Report 475, Socorro, N. Mex., New Mexico Institute of Mining and Technology.

Steffen, Robertson and Kirsten, Inc. (SRK), 1995, Copper Flat Mine, hydrological studies: Reno, Nev.

SRK Consulting, 2010, NI-43-101 Preliminary Assessment, THEMAC Resources Group Limited, Copper Flat Project, Sierra County, New Mexico: Lakewood, Colo. Prepared by SRK Consulting for THEMAC Resource Group Limited, June 30, 2010.

Figures



0 6 12 24

Miles

Imagery Information:
-Landsat Imagery from
University of Maryland NLCD

Legend

- City/Town
- Site Location
- Road



Figure 1-1
Site Location
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\1_introduction\1-1_SiteLocationMap.mxd 07/22/2010



Mine Boundary:
Tom Van Bebber
Imagery Information:
-USGS 7.5-Minutes Quads; Skute Stone Arroyo & Hillsboro
Projection Information:
-New Mexico State Plane West, NAD 1927

Legend

Proposed Mine Permit Boundary

Figure 1-2
Proposed Copper Flat Permit Area with Topography
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\1_introduction\1-2_proposed-permit_topo.mxd 08/30/2010

N
W E
S

0 1,000 2,000 4,000 6,000

Feet

Mine Boundary:
Tom Van Bebber
Imagery Information:
-USGS 7.5-Minutes County DOQQ
mosaic Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

Legend

Proposed Mine Permit Boundary

Figure 1-3
Proposed Copper Flat Permit Area with Air Photography

New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\1_introduction\1-2_proposed-permit_photo.mxd 08/30/2010



Figure 1-4
Proposed Copper Flat Permit Area with Land Ownership and Claims

New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\1-Interduction\1-4_claim-map.mxd 09/02/2010



N
W E
S

0 1,000 2,000 4,000 6,000

Feet

Mine Boundary:
Tom Reynolds
Disturbed areas/mine facilities: SRK, 2010
Imagery Information:
-USGS 7.5-Minutes County DOQQ
mosaic Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

Legend

- Proposed Mine Permit Boundary
- Proposed Mine Facility
- Waste Rock
- Topsoil Stockpile
- Tailings
- Stockpile
- Pit
- Haul Road
- Diversion
- Ancillary
- Access Road

Figure 1-5
Proposed Copper Flat Permit Area with the Pit, Three Waste Piles, a Tailings Impoundment Area, and a Plant-Facilities Area

New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\1_introduction\1-5_proposed-permit_disturbed.mxd 09/07/2010

Table of Contents

2 Climatological Factors 2-1
2.1 Introduction and Background 2-1
2.2 Sampling Objectives 2-2
2.2.1 Meteorological 2-2
2.2.2 Air Quality – Particulate (PM_{10}) 2-2
2.3 Sampling Frequency 2-3
2.3.1 Meteorological Station 2-3
2.3.2 Air Quality Station 2-3
2.4 List of Data to Be Collected 2-3
2.4.1 Meteorological 2-3
2.4.2 Particulate (PM_{10}) 2-3
2.5 Methods of Collection 2-3
2.5.1 Meteorological Monitoring 2-3
2.5.2 Air Quality Monitoring 2-4
2.6 Parameters to be Analyzed 2-4
2.6.1 Meteorological Parameters 2-4
2.6.2 Air Quality Parameters 2-4
2.7 Maps Showing Proposed Sampling Locations 2-4
2.8 Laboratory and Field Quality Assurance Plans 2-5
2.8.1 General 2-5
2.8.2 Quality Assurance Procedures for Meteorological Station 2-5
2.8.3 Quality Assurance Procedures for Air Quality Station 2-14
2.9 Discussion in Support of Proposal 2-14
2.9.1 Total Suspended Particulates 2-14
2.9.2 Particulate Matter Less than 10 Micrometers 2-14
2.10 References 2-15

List of Figures

Figure 2-1 Topographic Map Showing the Locations of the Proposed Particulate (PM_{10}) and Meteorological Monitoring Stations

List of Tables

Table 2-1 Meteorological Data to be Collected
Table 2-2 Summary of Meteorological Audit Criteria

2 Climatological Factors

2.1 Introduction and Background

The Copper Flat Mine Permit Area (Site) lies within the belt of mid-latitude westerlies where the prevailing wind direction is from the west. Winds at the Truth or Consequences, New Mexico, airport, located about 30 miles northeast of the Site, are generally from the northwest; however, the Black Range and foothills cause local variations in the winds. At Copper Flat, the wind direction is predominantly west to east, and secondarily north to south. Local wind speeds average about 10 to 15 miles per hour, although winds in excess of 50 miles per hour may occur at times. Temperature inversions are rare at Copper Flat, but are more common farther east along the Rio Grande valley, especially during the winter months. Vertical air dilution is generally good because of the area's high surface temperatures, creating strong daytime thermal mixing. Thermal mixing and moderate winds generally tend to suppress occasional nighttime inversions. The presence of higher winds and the lack of inversions contribute to a relatively clean atmosphere at the Site since any pollutants are readily mixed and dispersed (BLM, 1999).

Temperature data for the Site show a wide diurnal and seasonal variability, which is typical of dry climates. The warmest temperatures occur in June and July and the coldest temperatures usually occur in December and January. In spring and fall, daily maximum temperatures are moderate, typically averaging 65 to 85 degrees Fahrenheit (°F). Nights are cooler, with low temperatures averaging 32 to 50°F. Winter temperatures are frequently below freezing at night, but can be above 50°F during the day. During summer, temperatures can approach 100°F during the day. Daily temperature fluctuations of 30°F are common throughout the year (BLM, 1999).

Precipitation at the Site averages about 13 inches per year (ranging from nearly 3 inches in 1956 to over 20 inches in 1986). As much as half of the annual precipitation occurs in the form of intense thunderstorms during July, August, and September, when moist air enters the region from the Gulf of Mexico. Summer thunderstorms can result in heavy rainfall and flash floods. Average monthly precipitation in January through June is typically 0.50 inch or less. Snowfall is possible from October through April, but most likely (greater than 1 inch) between December through February (BLM, 1996).

Evaporation exceeds precipitation in southwestern New Mexico. Pan evaporation data, the most commonly collected data, are correlated with lake evaporation (i.e., free water surface evaporation) to predict evaporation from reservoirs and lakes. Lake evaporation at the Site is estimated to be approximately 58 to 65 inches per year, and pan evaporation is estimated to be approximately 80 to 90 inches per year (SRK, 1995).

Prior to the preparation of this Section, two reports from Alta Gold Company baseline meteorological data were reviewed by a subcontractor on behalf of NMCC to collect baseline meteorological data and conduct PM_{10} ambient air monitoring. These reports were prepared for Alta Gold Company by their air quality subcontractors, Air Sciences Inc. (Air Sciences) and present the meteorological protocols used by Air Sciences, including a letter from the New Mexico Air Quality Bureau approving the protocols. They also present the baseline air conditions for six months of on-site data (collected from August 19 to February 20, 1995), and six months of complimentary Truth or Consequences data (collected from February 21 to August 18, 1964), which was used for air dispersion modeling. On July 9, 2010, NMCC and the subcontractor visited the New Mexico Air Quality Bureau to meet with David Heath of the air modeling group, and Norma Perez and Kathy Primm, Environmental and Permit Specialists, respectively, to describe the air monitoring protocols the subcontractor would use, and to discuss the location of the on-site meteorological tower, which is the same location used by Alta Gold in 1994 and 1995. No objections were noted to either the protocols or the tower location (Air Sciences, 1995a and 1995b).

2.2 Sampling Objectives

2.2.1 Meteorological

The monitoring program will operate as a single station for a minimum of one year. The purpose of the monitoring program will be to collect baseline climatological data representative of the Site that satisfies the criteria of the New Mexico Surface Mining Act and the U.S. Environmental Protection Agency (EPA) on-site meteorological program guidance for dispersion modeling (EPA, 1987). The meteorological data will provide input to characterize the following climatological factors on a quarterly and annual basis:

- Wind direction
- Wind speed
- Temperature
- Precipitation
- Relative humidity
- Barometric pressure
- Net radiation
- Evapotranspiration

Additionally, the meteorological data will support the particulate (PM_{10}) air monitoring program to help determine sources of airborne particulate matter and to aid in the validation of monitored data.

The data capture goal will be 90 percent or greater for each meteorological parameter.

2.2.2 Air Quality – Particulate (PM_{10})

Title 19, Part 6 of the New Mexico Surface Mining Act requires the mine permittee to maintain all environmental permits and to be in compliance with other state or federal laws, regulations, or standards. Other applicable ambient air quality laws, regulations, and standards include those promulgated by the New Mexico Environment Department's Air Quality Bureau and the Environmental Protection Agency.

Federal and New Mexico Ambient Air Quality Standards (NMAAQS) exist for three categories of particulate. The categories and standards are as follows:

- Total suspended particulates (TSP) (20.2.3.109 NMAC)
  - 24-hour average: 150 micrograms per cubic meter ($\mu g/m^3$)
  - Annual geometric mean: 60 $\mu g/m^3$
- Particulate matter less than 10 micrometers (PM_{10}) (40 CFR 50.6(a))
  - 24-hour average: 150 $\mu g/m^3$
- Particulate matter less than 2.5 micrometers ($PM_{2.5}$) (40 CFR 50.7(a))
  - 24-hour average: 35 $\mu g/m^3$
  - Annual average: 15 $\mu g/m^3$

Fugitive dust from material hauling and conveying, stockpiles, and tailings impoundments may contribute air emissions of particulate matter categorized as PM_{10} and TSP. Currently, no monitored data exists characterizing the local ambient air quality particulate concentrations in the vicinity of the Site. Based on the need to

determine current background concentrations and to address potential public concern over future air quality impacts, NMCC recommends PM_{10} monitoring at two locations.

PM_{10} monitoring will demonstrate compliance with the NMAAQS health-based standard and help characterize TSP episodes to address the New Mexico standards for nuisance dust and soiling. The PM_{10} monitoring program will follow EPA guidelines for methodology and quality assurance, and will use samplers with equivalence method designation.

The validated data capture goal is 75 percent based on quarterly and annual report periods.

Surface mining and milling for copper are not considered significant sources for $PM_{2.5}$ emissions. Monitoring for this parameter is not recommended due to potential emissions below significant thresholds.

2.3 Sampling Frequency

2.3.1 Meteorological Station

Meteorological sensors are to be scanned once each second. The data are compiled as averages and totals at hourly and 15-minute intervals.

2.3.2 Air Quality Station

PM_{10} samples will be taken once every 6 days. Each scheduled sample will run for a period of 24 hours from midnight to midnight of the scheduled sample date.

2.4 List of Data to Be Collected

2.4.1 Meteorological

Meteorological data will be output hourly; averages and totals will be output every 15 minutes. See Table 2-1 for the meteorological data that will be collected and the instruments that will be used.

2.4.2 Particulate (PM_{10})

In addition to collecting 24-hour average particulate matter as PM_{10}, the following supporting data will be collected:

- Flow rate in liters per minute
- Fluctuation of flow rate
- Average ambient temperature
- Average ambient pressure
- Total run time in minutes
- Total volume of air sampled

2.5 Methods of Collection

2.5.1 Meteorological Monitoring

Data will be collected and stored on a Campbell Scientific CR1000 datalogger. The datalogger will interface with a digital cellular modem allowing daily data downloads to a remote PC and monitoring of real-time

meteorological conditions. The datalogger will have the capacity to store approximately 2 months of data on-site.

2.5.2 Air Quality Monitoring

Each sample filter will be collected manually following the end of the sample period and prior to the next scheduled sample. Filters will be labeled with individual serial numbers and tracked with chain-of-custody forms between the field and laboratory. The laboratory will ship pre-exposed filters to the field in individual glassine envelopes. No later than two days following the end of sample period, a field technician will place the exposed filters into the original glassine envelope and return the filters via express mail.

The designated PM_{10} sampler is a model PQ200 manufactured by BGI corporation. The sampler flow controller will maintain flow rate at 16.7 liters per minute. The processor will output hourly and daily values for average ambient temperature and pressure, flow rate, pressure drop, and error alarms. The data log will be downloaded onto a field PC at the time of each filter change.

2.6 Parameters to be Analyzed

2.6.1 Meteorological Parameters

The meteorological tower will report hourly and 15-minute averages for the following parameters:

- Horizontal wind direction
- Horizontal wind speed
- Sigma theta of the wind direction
- Temperature at 10 meters (T10)
- Temperature at 2 meters (T2)
- Delta temperature as T10 minus T2
- Relative humidity
- Barometric pressure
- Net radiation
- Pan evaporation

In addition, the meteorological tower will report hourly and 15-minute totals for precipitation and evaporation.

2.6.2 Air Quality Parameters

PM_{10} will be calculated as a 24-hour average using standard conditions of temperature and pressure to determine flow rates for each sample. The standardized temperature and pressure will be used in combination with net weight gain on the filter to determine the final PM_{10} concentration in $\mu g/m^3$.

2.7 Maps Showing Proposed Sampling Locations

The map provided in Figure 2-1 plots the locations of the proposed particulate (PM_{10}) and meteorological monitoring stations. The air monitoring stations are designated as Site 1 and Site 2. Site 1 consists of one 10-meter meteorological tower and one PM_{10} monitor. Site 2 consists of a single PM_{10} monitor.

The air monitoring site coordinates are as follows:

- Site 1 – 0264721 meters E; 3650403 meters N; Elevation at 5,402 feet
- Site 2 – 0262618 meters E; 3651000 meters N; Elevation at 5,596 feet
- Mill Site – 0264363 meters E; 3650403 meters N; Elevation at 5,457 feet

All coordinates are expressed as Universal Transverse Mercator (UTM) coordinates in the NAD 83 mode.

2.8 Laboratory and Field Quality Assurance Plans

2.8.1 General

2.8.1.1 Data Validation and Reporting

All data will be reviewed by a senior air quality professional retained by NMCC as it is received from the field. Any problems detected during the data review will be immediately communicated to the field technicians and then to the data reduction specialists. Data reduction specialists will compile the data on a monthly basis and produce monthly engineering units, math reports, and data capture summaries of the validated data. A senior air quality professional will prepare an operations summary for each month. The individual monthly reports and summaries will be compiled into an annual database from which an annual report will be produced. PM_{10} data will be reported monthly and quarterly as specified by EPA guidelines and federal regulations.

All procedures for calculation and reporting of data capture and determination of compliance will be performed in accordance with the following, as appropriate:

- Paragraph 13 of Subsection D of 19.10.6.602 NMAC
- Instruction manual for the PQ200 air sampler version 1.83 (BGI, 2007)
- 40 CFR 50, Appendices H, J, and K to Part 50
- 40 CFR 58, Appendix B to Part 58
- EPA *On-Site Meteorological Program Guidance for Regulatory Modeling Applications, Quality Assurance Handbook for Air Pollution Measurement Systems,* Volume II: Ambient Air Specific Methods (Appendix D); and *Quality Assurance Handbook for Air Pollution Measurement Systems,* Volume IV: Meteorological Measurements (EPA 1987, 2008a, 2008b).

2.8.1.2 Quality Assurance/Quality Control

The quality assurance audits will be conducted with personnel and equipment completely independent from the routine field operators and their chain of supervision. Audits of the particulate samplers will be performed every six months, with a total of two proposed for the first year. Monthly flow checks will be performed by the on-site technician. The tower-based meteorological sensors will be audited every six months, with a total of two audits scheduled for the first year. Problems encountered during the audits will be corrected at the time of the audit or immediately referred to the station operator. All audit results will be summarized in a separate report to be issued following each field visit.

All audit procedures and equipment will conform to the federal regulations and guidelines listed in the previous section.

2.8.2 Quality Assurance Procedures for Meteorological Station

The field quality assurance procedures and schedule for the meteorological tower are provided below:

Procedure	Schedule
Perform general station check/visit	2 times per month
Review data on a real time basis	Daily
Audit meteorological tower instruments	Biannually
Check operation of meteorological sensors	Each visit
Check datalogger output against ambient conditions	Each visit
Ship data to Albuquerque (field logs)	1 time per month
Review data (field)	Each visit
Review data (home office)	Daily
Maintain documentation of all field activities	Each visit

The station operator will document the findings and actions taken during each station check on pre-printed and bound station log forms. A guidance document outlining the procedures and required corrective actions, if applicable to maintain properly functioning instruments will accompany the station logbook.

Below is a summary of the meteorological field audit procedures to be followed by all air quality personnel. Although characterized as a summary, the procedures described follow the intent of the published EPA QA/QC guidelines and satisfy the project monitoring obligations. The general guidelines to follow in preparation for a field performance audit are as follows:

1. List all parameters to be audited. Include calculated parameters (e.g., delta T, temp. lapse, sigma theta).
2. List the model type(s) for all sensors to be audited.
3. Compare the standard procedures below with the parameter/sensor model to be audited and prepare an equipment list and an information list.
    a. The equipment list should include:
        i. Actual test equipment.
        ii. Tools and spare parts.
        iii. A computer interface (lap top, keyboard, etc).
    b. The information list should include (most of the information in the first five items can be found in the field quality assurance binders and reports from previous audits):
        i. Expected sensor output values.
        ii. Calibration factors for tower sensors and audit instrumentation (e.g., net radiation).
        iii. Programs and software (LoggerNet, copies of the datalogger program and channel outputs, an audit assistant spreadsheet, and look-up tables).
        iv. Wiring diagrams for the datalogger and other connections, if available.
        v. General data points and results from the previous audit, if available.

vi. Instruction manuals, including Campbell Scientific CR1000, Raven modem, and sensor manuals as required.

vii. A field quality assurance binder.

4. Pack-up, review the checklist, and leave.

Each meteorological sensor is evaluated based on the comparison of performance against EPA guidelines and manufacturer specifications. If any performance values are outside the recommended ranges, the results are immediately reported to field personnel so that any field repair and/or recalibrations can be performed expeditiously. The baseline summary report will include these results for documentation purposes.

Each meteorological sensor is calibrated using procedures specifically designed to test its accuracy of response. General descriptions are given below. These procedures reflect the requirements described in the *Quality Assurance Handbook for Air Pollution Measurement Systems* (EPA, 2008b). Upon arrival at the Site, each variable is observed for reasonableness. Next, the audit manipulations to each sensor are conducted. The datalogger outputs are recorded and compared to the audit input values. If the bias between the audit and Site values exceeds the prescribed limits described below, the appropriate troubleshooting is conducted to determine the cause of the discrepancy. At the conclusion of the audit, the sensors are put back on line and are again checked for reasonableness.

See Table 2-2 for a summary of meteorological audit criteria.

2.8.2.1 Sensor Heights

During the Site visit, the height of each sensor above ground is measured with a standard tape measure or using trigonometric methods and a surveyor's transit. The measured heights are then compared to those stated in the air monitoring program plan.

2.8.2.2 Wind Direction

Vane Calibration. Two factors must be checked to assure the wind vane is accurately measuring the wind direction: the azimuth as stated on the wind vane (orientation) and the ability of the wind vane to measure winds from all directions.

The preferred method for checking the wind vane orientation marker's stated azimuth is the solar azimuth angle technique, which is used to determine a known direction (solar azimuth). This measurement is made using a surveyor's transit mounted either on a field tripod or directly onto the wind direction sensor mounting plate. A measurement to a local topographical marker is then taken and the difference between that value and the known solar azimuth is used to determine a calculated azimuth angle for the reference marker. The resultant azimuth for the reference marker is used in a like manner to determine the orientation of the sensor crossarm (ideally set at 180 degrees). The solar azimuth check is normally done only once to establish a known direction for measurement of the orientation of the reference marker. A minimum of three bearings will be taken for this test. If the solar azimuth angle technique cannot be used, the azimuth angles will be measured with compass bearings.

A substitute (and second preference) for using the solar angle method is to measure the reference point azimuths from a topographic map. The sensor outputs, when aligned to the chosen reference points, are compared to the azimuths determined from the topographic map. This methodology requires accurate interpretation of the angles from the topographic map and knowledge that the chosen reference points are

visible from the tower site. Additionally, at least one of the reference points needs to be greater than 10 kilometers from the tower site.

Regardless of which azimuth determination technique is used, the following should be adhered to by the field staff:

1. Select reference points with as great a distance possible from the tower site. The preferred approach is to have at least one point that is a minimum of 10 kilometers distant. If points of this distance are not available, extra care must be taken during the visual alignments.
2. Always prepare the basic field data before leaving for the Site (solar angle tables, azimuth to reference points, etc.).
3. Complete all preliminary data on the audit log forms. This data includes calibration constants of all audit instrumentation (as applicable) and expected output values for each test (as applicable).
4. Always run an equipment checklist prior to leaving for the Site. The content of the equipment list depends on the methodologies to be used.

The ability of the wind sensor to measure winds from any direction is tested by visually aligning the sensor with the reference markers established above, recording the output from the datalogger, and comparing the previously determined azimuths. To ensure accuracy, the wind vane is aligned with the crossarm and the corresponding output is recorded.

Sensor Linearity and Overall Accuracy. Sensor linearity is checked by removing the wind vane and replacing it with a protractor and angle fixture. Wind direction readings will be taken at 30 degree intervals for a total of 12 readings. This is the preferred method.

In the event a calibrated protractor is not available for a given type of sensor, the linearity will be checked by approximating 45 or 90 degree turns. A volt or ohm meter may be also be used for the alignments. As with the calibrated protractor, readings will be taken at approximately 30 degree intervals.

Sigma Theta Test. The wind direction sigma theta check is a test of the datalogger sigma theta calculation. Any system errors attributable to the program algorithm and/or the signal from the sensors are detected in the outputs at the datalogger. The theta test is conducted by fixing the wind vane at a given direction for a given period of time and then moving the vane approximately 30 degrees and leaving it at this setting for the same time period. The time interval is selected to correspond to one averaging period of the datalogger. During the selected time interval, the wind speed sensor is held stationary to prevent the vector averaging routine from interfering with the sigma theta audit. Sigma theta, average wind direction, and average wind speed are recorded from the datalogger and compared to the expected values.

The following items are important to ensure the accuracy of this test:

1. Ensure that the theta test corresponds to the averaging interval on the datalogger. Most systems calculate the sigma theta over a sub-interval period of either 10 or 15 minutes. Whenever a sub-interval period is in use, the averaging period of the datalogger (i.e., final output instruction) must be modified to correspond to this interval. Remember to always reset all changes made to the program before proceeding to the next audit parameter.
2. Synchronize the timing for the test to the datalogger clock, not necessarily with the auditor's watch. Repositioning of the wind vane (for the second half of the averaging interval) must occur as closely as

possible to the midpoint of the time interval. For example, the wind vane will be moved after 5 minutes for a 10-minute test and after 7.5 minutes for a 15-minute test.

3. Always record start and end values for time, wind directions, wind speeds, and protractor settings (when applicable).
4. Perform the sigma theta test on each datalogger within a monitoring network. On towers with multiple levels of sigma theta, perform the test on the level of the most significant interest.

Starting Threshold Torque. The wind vane's starting threshold torque is measured using a National Institute of Standards and Technology (NIST)-calibrated torque gauge. The gauge is applied to the wind vane shaft at the center of rotation and a constant force is applied. The test is repeated six to eight times beginning at different points for a 360-degree rotation. The value recorded is the highest value observed during the test.

If a calibrated torque watch is not available, the Jonard leaf torque gauge must be employed. This method requires a ruler (capable of measuring 10 centimeters [cm]) and a protected area where the sensor can be set up and leveled free from any air disturbance.

A manual, qualified, bearing check is acceptable only in combination with the above procedures for the purpose of a QA audit.

2.8.2.3 Horizontal Wind Speed

Sensor Calibration. The sensor is audited by removing the anemometer cups and applying a constant rate of rotation in the normal direction of spin using synchronous motors. This is done by connecting the motor shaft to the anemometer shaft using a non-rigid, non-slip connector. Using the anemometer specifications, revolutions per minute (rpm) are converted to wind speed and compared to the resulting instantaneous datalogger outputs. The following precautions will be taken during the calibration procedure:

1. Avoid applying excessive pressure to the sensor shaft during the motor test. Excessive pressure will slow the rate of rotation.
2. Be certain all connections between the motor shaft and the sensor shaft are secure. Slippage can cause erroneous readings on the sensor.
3. Always have the expected output values and audit criteria recorded on the audit log.

Starting Threshold Torque. The starting threshold torque measurement of the anemometer shaft follows the same procedure as that described for the horizontal wind vane. Due to the lower resistance, a more sensitive torque watch is used.

2.8.2.4 Temperature

The tower-mounted temperature sensor is audited by collocation at three points with an NIST-traceable thermometer in constant temperature water baths. The field thermometer has a range of at least -1° to 51°C in 0.1°C graduations and will be certified by comparison to an NIST-certified thermometer. The tests are conducted in the following temperature ranges: 0° to 5°C, 20° to 30°C, and 40° to 50°C. The equilibrated thermometer reading is compared to the datalogger output. Finally, the aspirator is checked for proper ventilation by inspecting operation of the fans, if applicable, and checking the air pathway for obstructions.

Occasionally, a water bath test is not possible. In this instance, the temperature probes will be audited by collocation with the NIST thermometer. The field (NIST) thermometer is to be collocated, under ambient

conditions, in proximity to the tower sensor. If possible, the temperature probe will be placed inside the aspirator shield. Be certain not to contact any nearby surfaces with the field probe while conducting this test and keep in mind the following considerations:

1. In addition to recording readings from the field thermometer and individual tower probes, record the delta temperature and temperature lapse values, as calculated by the datalogger, simultaneously for each of the three water baths.
2. Note that small temperature differences within the water bath tests can induce large differences in the measured lapse rates. The passing criterion is 0.1°C.

2.8.2.5 Precipitation

The precipitation gauges are audited using a 100–milliliter (ml) graduated buret (within 1 percent accuracy). Two types of tests are conducted: a 10-tip test and a bucket test. The 10-tip test is conducted before disturbing the outer housing of the gauge. To conduct the 10-tip test, the buret is opened to deliver water at the approximate rate of 5 seconds per cubic centimeter (cc) of water and allowed to flow until ten tips are identified. The delivered amount of water is converted to equivalent inches of precipitation and the result compared to the datalogger output. During the 10-tip test, it is important that the bucket does not overflow on the final tip (the tenth tip). Carefully monitor the flow rate following the ninth tip and quickly close the stop cock on the final tip of the bucket. The error introduced at this point can be minimized with careful control of the water flow rate and should not have a significant effect on the 10-tip average.

In the bucket test, water is delivered until the bucket tips one time. The delivered water is compared to the theoretical amount of precipitation needed for 0.01 inch of rain in each bucket. The bucket test is repeated at least three times for each bucket. Following the bucket tip tests, the sensor is checked for level and cleanliness.

2.8.2.6 Barometric Pressure

The barometric pressure sensors will be calibrated according to manufacturer specifications. The sensor output will be checked by collocation with an aneroid or digital portable barometer. The portable barometer will be calibrated to an NIST-traceable mercury barometer immediately before the team leaves for the field. The mercury barometer and documentation of the certifications will be located at the NMCC Albuquerque office.

2.8.2.7 Relative Humidity

The relative humidity sensors are audited by collocation under ambient conditions using an aspirated psychrometer or digital relative humidity (RH) meter. Both thermometers used in the psychrometer are certified using the procedures cited above for temperature. The equilibrated dry bulb and wet bulb thermometer readings and the datalogger output values are recorded. The audit relative humidity value is calculated from formulas contained in the Smithsonian Meteorological Tables, corrected for the measured ambient barometric pressure. The audit relative humidity is compared to the datalogger output and the result is considered satisfactory if the difference between the two is ±3 percent RH or less.

When conducting the relative humidity audit, it is important that the following considerations be observed:

1. Position the tower sensor as close to the inlet to the psychrometer thermometers as possible.
2. Be certain to shield the tower sensor and the psychrometer from direct sunlight.
3. Allow 2 or 3 minutes for the psychrometer to stabilize at the beginning of the test.

4. Perform at least two tests, preferably three.

2.8.2.8 Net Radiation

The net radiation audit is accomplished through collocation of an audit pyranometer with the tower pyranometer. The mounting of the audit sensor should closely match that of the tower sensor, accounting for elevation, sun exposure, and level. The audit sensor should be of nearly identical spectral response as that of the tower sensor.

Readings from the two sensors can either be taken as discrete points over a pre-determined time interval or as an extended time average. Discrete readings should be taken over a minimum period of 2 hours with as many as 15 to 20 values distributed over the time interval. Extended averages can be taken with an independent volt meter (capable of collecting average data) over a minimum period of one hour. The following considerations apply:

1. Ensure that discrete readings of the audit and tower sensors are closely synchronized in time.
2. Start the extended averaging period on the digital volt meter (DVM) at the beginning of the corresponding period on the tower datalogger (hourly, 15 minutes, etc.).

2.8.2.9 Station Locations and Orientation

During the field portion of the audit activities, the integrity of the station reference marker is checked by determining the azimuth angle with respect to true north and comparing that value to the value used by the station operator for the meteorological tower. This is accomplished by field measurement of the solar azimuth using a leveled surveyor's transit. The solar azimuth angle is previously calculated from a computer program and available to the auditor in tables at 5-minute intervals. Once the known azimuth angle of the sun is established, it is used to determine the azimuth of station reference marker(s). These values are compared to values determined by the station operator using other orientation methods.

2.8.2.10 Station Sampling Environs

Part of the system audit is to document instrument fetch and local effects on data. The Site area obstructions, field of view, and local topography are examined. Nearby obstructions are located on the azimuth scale, heights are determined (when possible), and the distance from the tower is measured. All local environs data are evaluated, compared to regulatory guidance, and submitted with the audit report for inclusion in Site documentation files.

Meteorological Data Validation Criteria. The following criteria will be used in preparing the quarterly summaries for the Copper Flat meteorological data for this report:

1. Temperature Summaries (10-m temperature, 2-m temperature, delta temperature, and temperature lapse rate)

   The mean, maximum, and minimum temperatures (in degrees Celsius) are reported for each day in the quarter. The maxima and the minima are based on 1-hour averages. For a 24-hour mean value to be valid, at least 18 hourly values must have been recorded during the 24-hour period. If less than 18 hours of valid data are available, the mean is calculated, but data may not be representative and should be used with care. Similarly, maxima and minima are included for these periods. Even though some data may have been available on these days, the maxima and minima may be misleading if the missing data was for the hottest or coldest part of the day.

For each month in the quarter, the mean temperature for the month is calculated from all of the hourly data, including the data from the days that did not have sufficient data to calculate a 24-hour mean. Monthly averages are calculated for months with less than 4 valid 24-hour means. The monthly maximum and minimum are also reported. Although 4 days of valid data are considered enough to report a mean, means for months with less than 18 days of valid data may not be representative and should be used with care.

A quarterly mean, maximum, and minimum are reported if there is at least one valid month of data in the quarter. However, these values may not be truly representative of the entire quarter if significant amounts of data are missing. The validity of the quarterly values depends on their intended use, and care should be taken with quarters with low data capture.

2. Wind Speed Summary

   The 24-hour mean wind speed and the maximum hourly wind speed are reported for each day of each month (in meters per second). The criterion for a valid 24-hour means is the same as that described above for mean temperatures.

   The monthly mean wind speed and the maximum wind speed are also reported. The criteria for determining the monthly values are the same as those described above for monthly temperature values. Likewise, the mean for the entire quarter and the maximum hourly value in the quarter are reported, using the criteria described above for quarterly temperature values.

3. Wind Data Summary

   The wind data summary report gives a joint frequency distribution (JFD) for wind direction and wind speed. Wind direction is divided into 16 sectors, each representing 22.5 degrees. The north sector covers 348.75 degrees to 11.25 degrees (i.e., its axis of symmetry is zero degrees). Wind speeds are divided into 8 categories. The data in each wind speed/wind direction category are given as a fraction of the total month to the nearest 1 percent. The total fraction for each wind direction sector and each wind speed category is also given.

   A quarterly JFD is printed if at least one valid month of data existed in the quarter. However, the quarterly JFD may not be truly representative of the full quarter if only one month of data is available.

4. Precipitation Summary

   The total daily precipitation in inches is reported for each day in the quarter, along with a running precipitation total beginning on the first day of the quarter. Daily precipitation is reported if at least one hour of data is available during that day.

   The total quarterly precipitation is reported along with the total number of hours during which precipitation occurred. A quarterly precipitation value is reported if there is any valid precipitation data during the quarter. Care must be taken when using quarterly precipitation values if there were significant missing data during the quarter.

5. Relative Humidity Summaries

   The daily mean, maximum, and minimum relative humidity (in percent) are reported for each day in the quarter. The maxima and minima are based on 1-hour averages. For a 24-hour mean value to be valid, at least 18 hourly values must have been recorded during the 24-hour period. If less than 18 hours of valid data are available, the mean is calculated, but data may not be representative and should be used with

care. Similarly, maxima and minima are included for these periods. However, the maxima and minima may be misleading if the missing data were for the hottest or coldest part of the day.

The monthly mean relative humidity is calculated from all of the hourly data, including that from the days without sufficient data to calculate a 24-hour mean. Monthly averages are calculated for months with less than 4 valid 24-hour means in the month. The monthly maximum and minimum are also reported. Although 4 valid days are considered sufficient to report a mean, monthly means based on less than 18 days of valid data may not be representative and should be used with care.

A quarterly mean, maximum, and minimum are reported if there is at least one valid month of data in the quarter. However, these values may not be truly representative of the entire quarter if significant amounts of data are missing.

6. Data Capture Summary

   The percent of valid data, based on hourly values, is reported for each month and each parameter; the average data capture for the entire month is also reported. In addition, the percent of valid data for the quarter for each parameter and the average data capture for the quarter are provided.

7. Barometric Pressure Summary

   Barometric pressure is provided in millibars and represents the actual Site pressures; these data have not been “corrected” to sea level as is typically done with National Weather Service data. The reporting requirements for valid averages, maxima, and minima are the same as those for temperature and relative humidity summaries.

8. Net Radiation Summary

   The maximum net radiation in watts per square meter is reported for each day in the quarter. The maxima are based on 1-hour averages.

9. Evaporation Summary

   The total, minimum, and maximum evaporation values are reported in inches for each day of the quarter. Minima and maxima are based on 1-hour averages. Positive values indicate evaporation, or loss of water from the evaporation pan, whereas negative values indicate precipitation or addition of water to the evaporation pan for other reasons.

   For a 24-hour total value to be valid, at least 18 hourly values must have been recorded during the 24-hour period. If less than 18 hours of valid data are available, the total is calculated, but data may not be representative and should be used with care. Similarly, the maximum and minimum are included for these periods, but may be misleading if the missing data occurred in the hottest or coldest part of the day or during a precipitation event.

   The total monthly evaporation is calculated from all the hourly data for each month in the quarter, including the data from days with insufficient data to calculate a 24-hour total. The monthly maximum and minimum are reported as well.

   Validated data includes natural precipitation events. Scheduled and manual re-filling events are removed from the reported data set.

2.8.3 Quality Assurance Procedures for Air Quality Station

The field quality assurance procedures and schedule for the air quality station are provided below (EPA, 2008a):

Procedure	Schedule
Change particulate filters	Every 6 days
General station check/visit	At each visit
Flow rate check particulate samplers (PM_{10})	Monthly
Audit flow check of particulate samplers	Every 6 months

During monthly sampler flow checks, the flow rate is adjusted to be within 4 percent of 16.67 liters per minute (l/min) under ambient conditions. Ambient temperature and pressure taken at the time of the flow checks/adjustments are used to calculate a correction factor. The correction factor is used to calculate actual flow rates (Q_{ACT}).

Actual flow rates are converted into standard flow rates (Q_{STD}) at standard temperature (298°K) and pressure (760 mm Hg). The filter weight gain is determined to be the difference between the unexposed filter weight and the exposed filter weight. Both Q_{ACT} and Q_{STD} together with net weight gain are used to determine the 24-hour particulate concentration in micrograms per cubic meter ($\mu g/m^3$).

2.9 Discussion in Support of Proposal

2.9.1 Total Suspended Particulates

Currently no NMAAQS exists for TSP. However, the state of New Mexico retains a TSP ambient air quality standard for nuisance dust and overall welfare type of impacts. Given the lack of residences and restricted public access to the mine areas, NMCC does not anticipate nuisance dust to be a significant problem, at least for the near term of the project. However, the project recognizes potential public concern for TSP impacts. NMCC proposes to use PM_{10} monitoring, as described in the following section, to estimate TSP concentrations based on monitored PM_{10} values.

2.9.2 Particulate Matter Less than 10 Micrometers

In 1987, the EPA adopted PM_{10} as the NMAAQS for particulate matter, replacing TSP. Since that date, PM_{10} has been one of the particulate matter health standards at the federal and state levels. PM_{10} has potential local impacts due to releases from the ground level and elevated stack sources. A review of the New Mexico Energy, Minerals and Natural Resources Department (EMNRD) Mining and Minerals Division (MMD) regulations (Title 19, Part 6) revealed no specific requirement for an air quality monitoring plan to protect the environment. Additionally, a survey of several non-coal mines in New Mexico revealed no requirements for particulate monitoring.

Fugitive dust from material hauling and conveying, stockpiles, and tailings impoundments may contribute air emissions of particulate matter categorized as PM_{10} and TSP. Currently, no monitoring data exists characterizing the local ambient air quality particulate concentrations in the vicinity of the Site. Based on the need to determine current background concentrations and potential public concern of future air quality impacts, NMCC recommends PM_{10} monitoring at two locations.

PM_{10} monitoring will demonstrate compliance with the NMAAQS health-based standard and help characterize TSP episodes to address the New Mexico standards for nuisance dust and soiling. The PM_{10} monitoring program

will follow EPA guidelines for methodology and quality assurance, and will use samplers with equivalence method designation.

NMCC proposes using the PQ200 low-volume (16.67 l/min) sampler manufactured by BGI. The sampler uses a 47-mm Teflon filter and is powered by a 100-amp hour gel cell lead acid battery. It uses a photovoltaic panel for charging. The sampler has EPA equivalence method designation for both PM_{10} and $PM_{2.5}$.

2.10 References

Air Sciences Inc., 1995a, Meteorological data report, Copper Flat project, November 1, 1994 – January 31, 1995, prepared for Alta Gold Company, Truth or Consequences, New Mexico: Lakewood, Colo., Air Sciences, Inc.

——— 1995b, Baseline meteorology report, Copper Flat project, Alta Gold: Lakewood, Colo., Air Sciences, Inc.

BGI, June 2007, PQ200 & PQ200A air sampler instruction manual, $PM_{2.5}$ Designation RFPS-0498-116, PM_{10} Designation RFPS-1298-125, version 1.83: Waltham, MA, BGI Incorporated.

Bureau of Land Management (BLM), March 1996, Draft environmental impact statement, Copper Flat project: Las Cruces, N. Mex., U.S. Department of the Interior. Prepared by ENSR, Fort Collins, Colo.

——— BLM, 1999, Preliminary final environmental impact statement, Copper Flat project: Las Cruces, N. Mex., U.S. Department of the Interior, 491 p. Prepared by ENSR, Fort Collins, Colo.

Environmental Protection Agency (EPA), 1987, On-site meteorological program guidance for regulatory modeling applications, EPA document EPA-450/4-87-013.

——— 2008a, Quality assurance handbook for air pollution measurement systems, volume II: ambient air specific methods (appendix D), EPA document EPA-454/B-08-003.

——— 2008b, Quality assurance handbook for air pollution measurement systems, volume IV: meteorological measurements, EPA document EPA/454/B-08-002.

Steffen Robertson and Kirsten (U.S.), Inc. (SRK), 1995, Copper Flat Mine, hydrogeological studies: Reno, Nev.

Figure



Sample Locations:
Class One Technical Services
Mine Boundary:
Tom Van Bebber
Imagery Information:
-USGS 7.5-Minutes Quads; Skute Stone Arroyo & Hillsboro
Projection Information:
-New Mexico State Plane West, NAD 1927

Legend

Proposed Mine Permit Boundary

Figure 2-1
Topographic Map Showing the Locations of the Proposed Particulate (PM_{10}) and Meteorological Monitoring Stations

New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\2_climatological\2-1_air-met_monitoring.mxd 08/30/2010

Tables

Table 2-1

Meteorological Data to be Collected

Parameter	Tower Level (m above ground surface)			Equipment Manufacturer and Model
	0	2	10	
Horizontal Wind Direction			X	Climatronics F460
Horizontal Wind Speed			X	Climatronics F460
Ambient Temperature		X	X	Climatronics 100093 Motor Aspirated
Temperature Lapse (2–10 m)		X	X	Climatronics 100093 Motor Aspirated
Pan Evaporation	X			NovaLynx
Relative Humidity		X		Climatronics 100098 Motor Aspirated
Net Radiation		X		Kipp and Zonen
Precipitation	X			Climatronics Tipping Bucket
Barometric Pressure		X		Setra

Table 2-2

Summary of Meteorological Audit Criteria

Parameter Tested	Acceptable EPA Deviation or Satisfactory Criteria
Wind Direction	
Vane Orientation	± 5° from reference
Sensor Linearity	±3° at any of the 12 points checked
Starting Torque	See manufacturer specifications
Horizontal Wind Speed	
Sensor Calibration	± 0.25 m/s at speeds < 5 m/s 5% at speeds > 5 m/s (max. error 2.5 m/s)
Starting Torque	See manufacturer specifications
Temperature	± 0.5°C at all 3 points checked
Temp. Lapse	± 0.1°C
Precipitation	± 10% difference
Barometric Pressure	± 10.2 millibars (mb)
Relative Humidity	± 3%
Net Radiation	± 5% difference
Evaporation	± 10% difference

Table of Contents

3 Topography 3-1
3.1 Introduction and Background 3-1
3.2 Sampling Objectives 3-1
3.3 List of Data to be Collected 3-1
3.4 Methods of Collection 3-1
3.5 Parameters to be Analyzed 3-2
3.6 Maps Providing Sampling Locations 3-2
3.7 Sampling Frequency 3-2
3.8 Laboratory and Field Quality Assurance Plan 3-2

List of Figures

Figure 3-1 Topographic Map of the Site and Surrounding Area
Figure 3-2 Aerial Photograph of the Site
Figure 3-3 Topographical Map with Boundary

3 Topography

3.1 Introduction and Background

A topographic map of the Copper Flat Mine Permit Area (Site) and the surrounding area at a scale of 1:24,000 (where 1 inch equals 2,000 feet) is shown in Figures 3-1, 3-2, and 3-3. Off-site sampling locations are shown in the respective sections of this SAP at the appropriate scale. In addition to topography, these figures show:

- The boundaries of the Site.
- Various manmade features not enumerated herein.
- Proposed sampling locations for soil characterization analysis.
- Surface water features.
- Groundwater wells.
- Air monitoring stations.
- Weather stations.
- Wildlife and vegetation transects.
- Paved and dirt roads.
- A conceptual mine layout showing the basics of the proposed mining operation, including the proposed locations of all surface features such as structures, stockpiles, tailings, pits, adits, shafts, etc.

An aerial photograph covering the same area as Figure 3-1 is presented in Figure 3-2, illustrating the site boundary, disturbances from previous mining and mineral development activities, including roads, pit, waste dumps, tailings, diversion channel, scraped and developed plant facilities areas, and other disturbed lands.

3.2 Sampling Objectives

The objective of the proposed data collection is to verify the existence, condition, and use of features within and immediately around the Site in advance of mining in order to supplement existing topographic data. This baseline data will assist in the design of the facility and the reclamation and replacement of features.

3.3 List of Data to be Collected

No topographic data other than the global positioning system (GPS) data collected for sampling locations, as described in each individual resources section of this SAP, will be collected. Existing USGS topographic maps and publicly available aerial photography will be used to display the sampling points collected in the field within the context of the Site or project area.

3.4 Methods of Collection

Field surveys will be conducted across the Site and samples will be collected at locations up to 9.2 miles from the Site to establish the existence and location of the features enumerated in Section 3.1 by means of a Global Positioning System (GPS) unit. The surveys will be conducted concurrently with other field work.

Site topography is considered to be well established by U.S. Geological Survey (USGS) topographic maps, and will be verified by comparison between topographic maps and current aerial photographs.

3.5 Parameters to be Analyzed

The parameters to be analyzed are the Site baseline topography and locations of existing manmade features.

3.6 Maps Providing Sampling Locations

See Figure 3-1, 3-3, and 3-4 for a topographic map and manmade features up to 9.2 miles from the Site. See Figure 3-2 for an aerial photographic perspective. Off-site sampling locations are shown in figures included in the respective sections of this SAP.

3.7 Sampling Frequency

Field surveys to verify manmade features will be performed concurrent with other field activities during 2010 and 2011.

3.8 Laboratory and Field Quality Assurance Plan

There are no analytical laboratory requirements for topographical field work. New Mexico Copper Corporation (NMCC) may utilize subcontractors to assist with gathering updated information about the baseline topographic condition of the Site. Licensed field surveyors and aerial photographers will be selected based on their qualifications and certifications. Subcontractors and in-house personnel will follow quality assurance/quality control procedures as described in the Quality Assurance Project Plan. The NMCC Task Manager or designee will select a coordinate system consistent with state requirements in order to relate all base maps and surface features to the same system. Field Leaders will verify the existence and location of manmade features as they walk the Site for other data collection activities. If necessary, the features or objects will be tied to the nearest benchmark. Digitized aerial photographs and derived contours will be used for design, baseline data presentation, and baseline conditions for reclamation and re-vegetation.

Figures



Mine Boundary:
Tom Reynolds
Facilities:
SRK, 2010
Imagery Information:
-USGS 7.5-Minutes Quads; Skute Stone Arroyo & Hillsboro
Projection Information:
-New Mexico State Plane West, NAD 1927

Legend

- Proposed Mine Permit Boundary
- Proposed Mine Facilities

Figure 3-1
Topographic Map of the Site and Surrounding Area
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\3_topography\3-1_site-area_topo.mxd 09/03/2010

N
W E
S

0 1,000 2,000 4,000 6,000

Feet

Mine Boundary:
Tom Reynolds
Facilities:
SRK, 2010
Imagery Information:
-USGS 7.5-Minutes County DOQQ
mosaic Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

Legend

- Proposed Mine Permit Boundary
- Proposed Mine Facilities

Figure 3-2
Aerial Photograph of the Site
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\3_topography\3-2_site-area_aerial.mxd 09/03/2010



0 1,000 2,000 4,000

Feet

N

W E

S

Mine Boundary:
Tom Reynolds
Sample Locations:
SRK, 2010
Imagery Information:
-USGS 7.5-Minutes Quads; Skute Stone Arroyo & Hillsboro
Projection Information:
-New Mexico State Plane West, NAD 1927

Legend

- Proposed Mine Permit Boundary
- Proposed Mine Facility
- Proposed Sampling Locations
  - Vegetation Transect
  - Geologic Sample
  - Climate & Air Quality Sample
  - Monitoring Well
  - Surface Water Sample
- Cultural Resources Survey
- Wildlife/Soil Transect

Figure 3-3
Topographical Map with Boundary

New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\3_topography\3-3_sample-locations.mxd 09/03/2010

Table of Contents

4 Vegetation 4-1
4.1 Introduction and Background 4-1
4.2 Sampling Objectives 4-1
4.3 Sampling Frequency 4-2
4.4 List of Data to be Collected 4-2
4.5 Methods of Collection 4-2
4.5.1 Site Stratification 4-2
4.5.2 Plant Species Inventory 4-3
4.5.3 Rare, Threatened, or Endangered Plant Species 4-3
4.5.4 Noxious Weeds 4-4
4.5.5 Sampling Methodology 4-4
4.6 Parameters to be Analyzed 4-6
4.7 Maps Showing Proposed Sampling Locations 4-6
4.8 Laboratory and Field Quality Assurance Plans 4-6
4.8.1 Personnel 4-6
4.8.2 Sampling Protocol 4-6
4.8.3 Data Quality Assurance and Quality Control 4-7
4.9 Discussion in Support of Sampling Proposal 4-7
4.10 References 4-7

List of Figures

Figure 4-1 Graphical Depiction of the Strata Recommended for Vegetation Sampling and Analysis
Figure 4-2 Map of the Proposed Vegetation Transect Sampling Locations and Site Strata

List of Tables

Table 4-1 List of the Current Data Needs Addressed in this Report
Table 4-2 List of Vegetation Attributes, Data Sources, and Proposed Analysis Processes

4 Vegetation

4.1 Introduction and Background

Mining activities and infrastructure constructed by the Copper Flat Partnership, ca. 1982, combined with previous mining-related activities, have contributed to the disturbance of approximately 690 acres within the Copper Flat Mine Permit Area (Site) (BLM, 1999); 358 acres is on public lands and 331 acres is estimated on private lands (according to disturbance acreages listed in BLM, 1999). New calculations by Parametrix total a total disturbed area of 965 acres for the Site, based on digitizing high resolution 2009 aerial photography (Figure 4-2). The Site was reclaimed in 1986, although it appears that only relatively small portions of the Site were actively revegetated. Baseline data has been collected at the Copper Flat project starting in the late 1970s by Quintana, followed by Rio Gold Mining Ltd (Rio Gold), Gold Express, and Alta Gold (related to the 1999 PFEIS). These data are relevant and provide insights for future permitting activity. Information from these previous baseline surveys have been researched and utilized to augment this current sampling process where appropriate.

The history of repeated disturbance at this Site has dramatically impacted vegetation communities. Current vegetation community distribution in the mined areas is more strongly correlated with previous land use than with the biotic or abiotic factors that typically render the distribution of vegetation types or vegetation potential. Given this, the "baseline" vegetation condition for portions of the Site include tailings piles, a tailings dam, barren areas, waste dumps, various roads, diversion channel, pits and pit lake, and other disturbed areas. However, relatively undisturbed areas are also still present within the permit boundary (Figure 4-2).

Biologists surveyed the Copper Flat permit area in April 2010 to assess the relative abundance of individual plant species and perform a preliminary inventory (Parametrix, 2010). During this visit, a total 93 plant species were observed. Additionally, 18 vegetation transects (six each in the control, tailings dam, and tailings piles) were completed to provide a basis for determining vegetation sampling adequacy. The statistical analysis revealed that the data collection methods proposed in this report should achieve the intended sampling objectives for evaluating the important vegetation attributes as outlined in New Mexico Energy, Minerals and Natural Resources Department (EMNRD) Mining and Minerals Division (MMD) guidance documentation (MMD, 2010).

4.2 Sampling Objectives

The proposed sampling and analysis approach intends to capture the current vegetation condition throughout the permit area to meet the following sampling objectives:

1. Delineate a current vegetation map stratified according to disturbance history and Ecological Site Description.
2. Describe specific vegetation attributes for plant communities delineated within the permit area through quantitative measurements of:
   - Basal vegetation cover by species and ground cover.
   - Aerial vegetation cover by species.
   - Woody plant density.
   - Herbaceous productivity.
   - Plant species richness and diversity.
3. Complete a plant species inventory.
4. Perform a threatened or endangered species survey.

4.3 Sampling Frequency

The growing season for warm season (C4) grass species is typically April through August in New Mexico. Since biomass production rates typically increase with precipitation, quantitative data collection transects will be performed during the late summer following monsoons to accurately capture annual biomass production. This time period is also representative of peak vegetation cover during most years and is considered a favorable period to identify many plant species. Plant cover (especially by annuals) can be greatly reduced after the first frost.

As previously mentioned, an additional plant inventory will be performed during the late summer/early fall. The spring survey was completed in April 2010.

4.4 List of Data to be Collected

A vegetation survey was completed at the Site during 1996 (SRK, 1997) in support of Alta Gold Company's proposal to re-open the Copper Flat Project. The survey employed a modified Parker Three-Step method to characterize vegetation composition, density, and biomass production of native perennial plants. The Parker Three-Step method uses a cluster of three transects in a stratum to characterize the desired vegetation attributes. Unfortunately, the original datasheets or data summaries by cluster are no longer available from this effort. The only information currently available pertains to the dominant native species encountered at each cluster. A recent effort to relocate metal stakes marking the 1996 transects was also unsuccessful. Consequently, the previous information cannot be incorporated into the current vegetation assessment for trend analysis or other purposes. Information collected during the April 2010 preliminary vegetation assessment (Parametrix, 2010) will be incorporated into future work, primarily to supplement the plant inventory, and was also used as a basis for estimating sample adequacy for this plan.

In order to meet the sampling objectives, several additional data needs have been identified and are summarized in Table 4-1.

4.5 Methods of Collection

4.5.1 Site Stratification

The permit area lies within the transition zone between Chihuahuan Desert Scrub and the Desert Grassland Ecotone according to Dick-Peddie (1999). Though the entire permit boundary technically lies within the Chihuahuan Desert Scrub type, the delineation line between these two types is only about 200 meters (m) west of the permit boundary. Two Natural Resources Conservation Service (NRCS) Major Land Resources Areas actually converge within the permit area. Much of the western half is considered Mogollon Transitions (Interior Chaparral – Woodlands/Grassland subclass), while the eastern half is predominantly characterized as Southern Desertic Basins, Plains, and Mountains (Chihuahuan Desert Shrubs subclass) (NRCS, 2007). The convergence of two landscape scale vegetation classes under both sources (NRCS, 2007 and Dick-Peddie, 1999) may create a relatively unique ecotone at Copper Flat.

The permit area will be stratified according to existing disturbance, proposed disturbance, and NRCS Ecological Site Description (ESD). This stratification serves as an initial vegetation map and also facilitates a stratified-random sampling design for field data collection. Figure 4-1 outlines a process for stratifying the Site and the total number of transects in each stratum. As already mentioned, previous mining activities have significantly impacted vegetation in portions of Copper Flat. Statistical analyses of the data collected during the 2010 preliminary assessment found significant differences in shrub density, grass cover, and species diversity among the tailings dam, tailings piles, and control areas. In consideration, the disturbed areas will be stratified

according to whether the area is a tailings pile, pit, or tailings dam. Some areas (namely previous mining pits) are void of vegetation altogether but reflect the pre-mining vegetation condition in these areas under the current permit application. Consequently, this stratum will also be included in sampling.

Two ESDs are delineated in the permit area, Gravelly and Hills. ESD delineations will form the basis for stratifying currently undisturbed portions of the Site. Some of these areas may become waste rock areas, tailings impoundments, etc. during proposed future mining. The areas that are planned to be disturbed during future mining will be isolated as a separate stratum by ESD during sampling. Meanwhile, areas currently undisturbed where future disturbance is *not* proposed will be sampled and will serve as a control. Transects occurring in the control area will be permanently marked with a survey nail and whisker on both sides of the transect tape.

The ESDs described at Copper Flat include Gravelly (R042XB010NM) and Hills (R038XB102NM). The Gravelly ESD in this portion of New Mexico has been particularly susceptible to desertification and creosote (*Larrea tridentata*) expansion or invasion. Most of the undisturbed Gravelly portions of Copper Flat are still in a shrub savanna condition with diverse grasses, consistent with the historical climax plant community typified for this area. In fact, creosote was not observed at the Site during the preliminary site assessment. Undisturbed portions of the Hills ESD at Copper Flat also match a historical climax condition relatively well. These areas are dominated by sideoats grama (*Bouteloua curtipendula*) and other mixed grasses with well distributed shrubs. Establishing permanent control transects in these areas will assist in monitoring vegetation community change irrespective of mining disturbance in the permit area.

ESD delineations will be particularly useful since it can be difficult to delineate unique vegetation types in grasslands or scrub shrub communities that appear relatively homogenous on the surface (NRCS, 2010). ESDs are also useful for gauging vegetation potential, describing the seral state of the current community, and defining typical plant community transitions under disturbance or climatic conditions (such as drought). Data comprising an ESD is presented in four major categories (NRCS, 2010):

- Site Characteristics: Identifies the Site and describes the physiographic, climate, soil, and water features associated with the Site.
- Plant Communities: Describes the ecological dynamics and the common plant communities comprising the various vegetation states of the Site. The disturbances that can cause a shift from one state to another are also described.
- Site Interpretations: Provides interpretive information pertinent to the use and management of the Site and its related resources.
- Supporting Information: Provides sources of information and data used in developing the Site description and the relationship of the Site to other ecological sites.

4.5.2 Plant Species Inventory

A preliminary plant species list was compiled in April 2010. This list will serve as a spring inventory for the Site. An additional late summer/early fall inventory will be completed in the permit area during September 2010. The intent of these surveys is to capture a complete plant species list at the Site, including fall or spring annuals and species that can be difficult to definitively identify outside of their flowering and/or fruiting period.

4.5.3 Rare, Threatened, or Endangered Plant Species

Inventories will pay particular attention to the presence or absence of agency-,state-, or federally regulated rare, threatened, or endangered species. Field botanists will research documented nearby locations and habitat requirements of species of concern before completing the inventory. If a species of concern is encountered, a

Global Positioning System (GPS) file will be recorded. Species closely resembling a species of concern will be photographed and/or collected following the discretion of the field botanist and appropriate regulations. No species of concern were observed during the April 2010 preliminary assessment.

4.5.4 Noxious Weeds

If state- or federally listed noxious weeds are encountered, the specific location will be documented with a GPS receiver. Noxious weeds were not observed during the preliminary site assessment.

4.5.5 Sampling Methodology

This section describes the sampling methodology proposed for collecting quantitative vegetation data at Copper Flat. A map (supplied by New Mexico Copper Corporation and Steffen Robertson and Kirsten [SRK]) of the lands previously disturbed and proposed disturbance was used in determining the intensity of sampling and the distribution of transects. Sampling adequacy was based on recommendations from the preliminary site assessment (Parametrix, 2010).

4.5.5.1 Transect Distribution

A stratified-random sampling approach will be used to characterize the current vegetation condition throughout the Site. The total number of transects per stratum was determined by reviewing the results of sampling adequacy calculations following the preliminary site assessment (Parametrix, 2010) and weighting the sample size according to total acreage of the stratum. Sample adequacy is a statistical measure used as a means to assist with determining the sample size that is required to statistically evaluate specific monitoring objectives. According to the preliminary assessment (Parametrix, 2010), the transect number needs to be increased to six (a minimum of ten is recommended in this report), and the transect length should be extended to 50 m. Both of these recommendations are captured in the sampling design proposed in this report. Further dividing “control” areas by Ecological Site Description may also help to reduce variability between the ESDs.

Figures 4-1 and 4-2 articulate how the Site will be stratified for random plot generation. The proposed mine permit boundary is just under 2,200 acres. Of this, the total combined acreage of existing disturbance is approximately 965 acres (Figure 4-2). A sample size of 93 transects is recommended within the permit boundary. See Figures 4-1 and 4-2 for the total number of transects per stratum and the overall transect distribution at the Site.

Transect locations were randomly selected using the random point generation function within Hawth’s Analysis Tools ArcGIS plug-in. During this process, the required number of random transects was placed in each stratum. A 40-m buffer was enforced at transition lines between strata and also between individual transects to reduce cross sampling. The resulting geographic coordinates will be transferred to a GPS receiver for field navigation to the target locations. If field conditions do not match the stratum intended, the transect will be moved to a nearby location in the target stratum. After arriving at the sample point, personnel will take a digital photograph in the transect location, and then stretch a transect tape to record quantitative information specific to characterizing cover, production, density, and diversity at each individual stratum.

4.5.5.2 Cover

At the beginning point of each transect, a 50-m tape will be stretched along the ground towards a random direction determined by spinning the compass dial without looking. Cover will be measured with a laser device at stations along the transect using the point-intercept method. The device consists of two green-light laser pointers fixed to a piece of angled aluminum beam and mounted on a camera tripod. Each laser produces a

point of light 1 to 2 millimeters (mm) in diameter. Readings will be taken to the right and left of the tape 1 m apart along the entire 50-m tape, resulting in a total of 100 points recorded along each transect.

Both aerial vegetation cover and ground cover will be recorded at each sample point. Aerial cover will be recorded by species. In situations where multiple species are intersected by the laser, both species will be recorded. A single species will not be recorded more than once at the same point. Ground cover will also be determined at each sample point according to whether basal vegetation, litter, bare soil, downed wood, or various rock categories (i.e., cobble, gravel, rock, bedrock, etc., separated by size) are intersected at the ground surface.

4.5.5.3 Biomass Production

Production will be assessed by clipping all herbaceous vegetation within 1-m² quadrats placed at 25-m intervals along the transect. Vegetation from the current growing season will be clipped and stored in labeled paper bags by species and transect. Care will be taken to remove and discard vegetation from the previous growing season (which is usually gray and sometimes partially blackened). When a large shrub covers more than 75 percent of the quadrat area, these shrubs will be clipped within a 0.25 m² quadrat nested inside the 1-m² quadrat.

Biomass collections will then be air-dried at room temperature for six to ten weeks. Samples will be weighed regularly during the drying process to monitor when weight loss stops (i.e., the samples are air dry). Following drying, sample bags will be weighed on an Ohaus Scout II electronic balance to the nearest 0.1 gram.

4.5.5.4 Woody plant density

Woody plant density will be determined on belt transects 2 m wide by 50 m long (100 m²) nested along the sample transect. Field personnel will tally all woody plants rooted within the belt by species. Multi-stemmed shrubs will be considered one individual plant if they appear to emerge from a single root crown.

4.5.5.5 Diversity

While the point-intercept method accurately quantifies cover (Elzinga et al., 1998 and sources within) along a transect, this method sometimes neglects incidental or less common species (sources within Elzinga et al., 1998). To alleviate this limitation, a complete list of herbaceous species encountered along the 2-m belt transect (as described in the *Woody plant density* section above) will be compiled. This information will be used to supplement species diversity information recorded from point-intercept.

There are a variety of measures that assess plant species diversity. Measures can be used to describe species richness, species evenness, and/or the structural complexity of a community. Species richness is simply the total number of species that occur within a transect, stratum, or the entire Site. Species evenness expresses how evenly or unevenly species are distributed within the plant community. Evenness can be expressed as the proportion or percentage that each species represents of the whole (sum of all species).

The Shannon-Weiner (S-W) Index is one commonly used measure of species diversity (Krebs, 1989, and Shannon, 1948). Both species richness and species evenness are factors in this index. The greater the number of species, the higher the index value becomes. In addition, the more evenly matched species are with each other with respect to quantities (whether the quantity is cover, production, or other parameter), the higher the index value. In other words, if certain species are too dominant, the index value decreases. If the species have relatively similar dominances, the index value will go up. Statistically, the index is monitoring the probability of whether the next sample will contain the same species as the previous sample or whether the next sample will be a new species (Krebs, 1989, and Shannon, 1948). The S-W equation is given below (Krebs, 1989, and Shannon, 1948):

$$H = -\sum_{i=1}^{s} (p_i) \log_2 (p_i)$$

where:

H is the diversity index

Σ means to sum the values for each species

i refers to the ith species

s refers to the total number of species

pi is the proportion of individuals of the total sample (in this case, cover) belonging to the ith species

log2 is the same as the natural log or ln

The absolute plant covers recorded by the point method are converted to relative covers by lifeform (grass, forb, shrub, annual), by perennials, and by all live vegetation (perennials and annuals). In this manner, the relative perennial cover contributions can be compared to the defined values.

4.6 Parameters to be Analyzed

Analysis parameters were designed to measure standard vegetation attributes and also meet the requirements of MMD guidance documents (MMD, 2010). Specific parameters are listed in Table 4-2.

4.7 Maps Showing Proposed Sampling Locations

As previously mentioned, a stratified-random sampling approach will be used to characterize the baseline vegetation at the Site. Figure 4-2 displays the proposed sampling locations randomly plotted in ArcGIS and the preliminary Site strata.

4.8 Laboratory and Field Quality Assurance Plans

4.8.1 Personnel

The approach recommended within this proposal describes a relatively standard, replicable process that can be applied to the Copper Flat permit area to describe and assess existing vegetation. Quantitative field data collection and plant species inventories will only be completed by trained field botanists with a minimum of a Bachelors of Science in Botany or related qualifications, and five years of regional field experience. Each of the botanists will be accompanied by a field technician for recording data and assisting with transect set-up. All staff will also be trained in use of GPS field devices. Names and resumes of field botanists completing field data collection and data analysis will be available for inclusion in annual reports and survey memoranda.

4.8.2 Sampling Protocol

Specific sampling protocols in this report have been reviewed by senior scientists with extensive experience completing vegetation surveys on rangeland and mine lands. This plan will be independently evaluated again before field data collection is initiated.

4.8.3 Data Quality Assurance and Quality Control

A single field crew chief will be assigned to ensure data collection is consistent between crews. This individual will review a sub-set of the field forms following each field day. Formalized data collection training will also be completed prior to field sampling. All field botanists will be familiar with plant systematics and techniques to identify plants using taxonomic keys. Plant species not readily identifiable in the field will be collected and preserved for identification at the University of New Mexico Herbarium.

Vegetation material produced during the previous growing season will be discarded before placing samples into a paper bag. Rocks, soil, and/or litter will not be placed into sample bags. Biomass production will only be calculated as an actual dry-weight sample. No double sampling or estimations will occur.

Field data entered into an electronic format such as MS Excel or Access will be evaluated for integrity, consistency, and completeness before data analysis. Oversights or incorrect entries will be corrected. A sub-set of the field forms will be compared to the electronic version for an accuracy assessment. If significant differences are identified, a thorough re-evaluation of each of the forms will be completed.

4.9 Discussion in Support of Sampling Proposal

The approach recommended in this report conforms to agency sampling guidelines and objectives (MMD, 2010) and provides a methodology for accurately measuring and characterizing current vegetation at Copper Flat. This information will be used to document baseline vegetation before mining operations continue, and will also provide long-term monitoring locations in undisturbed portions of the permit area that may be useful in the future for gauging reclamation success and climatic or other disturbance-driven changes to vegetation in the permit area.

4.10 References

Bureau of Land Management (BLM), 1999, Preliminary final environmental impact statement: Copper Flat project: Las Cruces, N. Mex. U.S. Department of the Interior, 491 p.

Dick-Peddie, W.A., 1999, New Mexico vegetation: past, present, and future: Albuquerque, N. Mex., University of New Mexico Press, 280 p.

Elzinga, C.L., Salzer, D.W., and Willoughby, J.W., 1998, Measuring and monitoring plant populations: Bureau of Land Management Technical Reference 1730-1, 492 p.

Krebs, Charles, 1989, Ecological methodology: New York, HarperCollins.

Natural Resources Conservation Service (NRCS), 2007, Reference sheet for Gravelly R042XB010NM, available online at: http://www.nm.nrcs.usda.gov/technical/fotg/section-2/esd/1983mlramap/sd-2/sd-2gravelly.pdf.

——— 2010, Ecological site descriptions, available online at: http://esis.sc.egov.usda.gov/ESIS/About.aspx.

Mining and Minerals Division (MMD), State of New Mexico, 2010, Guidance Document for Part 6 New Mining Operations Permitting under the New Mexico Mining Act, New Mexico Administrative Code Title 19, Chapter 10, Part 6, Draft for Review: New Mexico Energy Minerals and Natural Resources Department, Mining Act Reclamation Program, Santa Fe, New Mexico.

Parametrix, Inc., 2010, Technical memorandum: Preliminary vegetation survey results, Copper Flat Mine: Parametrix Project 563-6671-001.

Shannon, C.E., 1948, A mathematical theory of communication: Bell System Technical Journal 27, p. 379–423 and 623–656.

Steffen Robertson and Kirsten, Inc. (SRK), Southwest Rangeland Services, and Adrian Brown, 1997, Copper Flat Mine project monitoring plans: SRK Project 68607.

Figures



Figure 4-1
Graphical Depiction of the Strata Recommended for Vegetation Sampling and Analysis

New Mexico Copper Corporation



0 1,000 2,000 4,000 6,000

Feet

N
W E
S

Mine Boundary:
Tom Van Bebber
Strata/transects:
Parametrix
Imagery Information:
-USGS 7.5-Minutes County DOQQ mosaic
Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

Legend

- Proposed Mine Permit Boundary
- Preliminary Transect Locations
- Access Road
- Baseline No Proposed Disturbance - Gravelly
- Baseline No Proposed Disturbance - Hills
- Baseline Proposed Disturbance - Gravelly
- Baseline Proposed Disturbance - Hills
- Pit
- Pit Lake
- Saltcedar
- Tailings Dam
- Tailings Pile

Figure 4-2
Map of the Proposed Vegetation Transect Sampling Locations and Site Strata

New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\4_vegetation\4-2_veg_strata_sample.mxd 08/30/2010

Tables

Table 4-1

List of the Current Data Needs Addressed in this Report

Data Needs	Plan to Address Data Needs
Vegetation map	A vegetation map will be initially stratified according to the Ecological Site Description and existing disturbance. This source will then be updated based on field observations and further review of aerial photography during quantitative vegetation assessment.
Vegetation survey data	Quantitative assessments of vegetation cover, diversity of plant life form, productivity, and woody plant density will be completed per Mining and Minerals Division Guidance document requirements (MMD, 2010).
Complete plant species inventory	Plant species observed during the April 2010 assessment will be supplemented by additional inventories completed during late summer/early fall per Mining and Minerals Division Guidance document requirements (MMD, 2010).

Table 4-2

List of Vegetation Attributes, Data Sources, and Proposed Analysis Processes

Vegetation Attribute	Source Used for Analysis	Analysis Process
Acreage of existing vegetation community	Vegetation map	Total acreage calculated in ESRI ArcGIS for individual vegetation types in the permit boundary.
Aerial vegetation cover	Quantitative vegetation transects	Parameter calculated from vegetation transects. Results summarized by species and life forms as a weighted average for the Site and also by stratum.
Ground cover	Quantitative vegetation transects	Parameter calculated from vegetation transects. Individual ground cover attributes include basal vegetation (by species, life form, or in total), rock, cobble, gravel, litter, downed wood, and bare soil. Results summarized as a weighted average for the Site and also by stratum.
Species richness and diversity	Plant species inventory and quantitative vegetation transects	Parameter calculated from vegetation transects to summarize diversity by stratum as recorded during this effort. Analysis will employ simply summing the total number of species encountered and Shannon-Weiner Index calculations. Diversity for entire Site supplemented by information collected during the plant species inventory.
Diversity of plant life form	Plant species inventory and quantitative vegetation transects	See description for species richness above. Results also summarized by life form.
Biomass production	Quantitative vegetation transects	Parameter calculated from vegetation transects. Annual production of native grasses summarized by species and in total as a weighted average for the Site and also by stratum.
Woody vegetation density	Quantitative vegetation transects	Parameter calculated from vegetation transects. Results summarized by species and life forms as a weighted average for the Site and also by stratum.

Table of Contents

5 Wildlife 5-1
5.1 Introduction and Background 5-1
5.2 Sampling Objectives 5-1
5.3 Sampling Frequency 5-2
5.4 List of Data to be Collected 5-2
5.5 Methods of Collection 5-2
5.6 Parameters to be Analyzed 5-2
5.7 Maps Showing Proposed Sampling Locations 5-3
5.8 Laboratory and Field Quality Assurance Plans 5-3
5.9 Discussion in Support of Sampling Proposal 5-3
5.10 Resources 5-3
5.11 References 5-4

List of Figures

Figure 5-1 Map of the Proposed Wildlife Transects and Site Strata

5 Wildlife

5.1 Introduction and Background

Baseline data has been collected at the Copper Flat project starting in the late 1970s by Quintana, followed by Rio Gold Mining Ltd (Rio Gold), Gold Express, and Alta Gold (related to the 1999 PFEIS). These data are relevant and provide insights for future permitting activity. The previously completed wildlife surveys and studies have been reviewed (SRK, 1997, and BLM, 1999). Relevant information from these previous baseline surveys have been researched and utilized to augment this current sampling process where appropriate. The Chihuahuan desert is a harsh environment home to many birds, reptiles, and mammals. While the actual wildlife diversity is much greater than the list below, some of the more common species are:

- black-chinned sparrow (*Spizella atrogularis*)
- brown thrasher (*Toxostoma rufum*)
- cactus wren (*Campylorhynchus brunneicapillus*)
- roadrunner (*Geococcyx californianus*)
- whiptail lizard (*Cnemidophorus* sp.)
- kangaroo rat (*Dipodomys* sp.)
- western diamondback rattlesnake (*Crotalus atrox*)
- jackrabbit (*Lepus californicus*)
- pronghorn antelope (*Antilocapra americana*)
- and coyote (*Canis latrans*)

Biologists surveyed the Copper Flat permit area on April 15, 2010, to identify migratory bird nests and sensitive habitat areas. This survey was conducted using methods required to fulfill Migratory Bird Treaty Act requirements for the proposed mining activities. During the field survey, numerous bird nests were observed. The most common nests found were cactus wren and brown thrasher nests. These birds build stick and grass nests in cholla cactus (*Opuntia imbricata*) and were common in the tailings pond area as well as around the existing pit.

5.2 Sampling Objectives

The sampling objectives for this project are:

1. Delineate and map current habitat, including disturbed areas.
2. Describe wildlife use of the area through measurements of:
    a. Big game fecal pellet group counts for deer, elk, and antelope.
    b. Call counts for birds and amphibians.
    c. Trend routes for mammals.
    d. Visual sighting transects for birds, mammals, and reptiles.
3. Complete a bird species inventory.

4. Complete a threatened or endangered species survey by comparing known records and habitat requirements with current field conditions to determine the likelihood of occurrence of all federal and state listed wildlife species.
5. Develop a list of species encountered during surveys or deemed likely to occur within the permit area. Species encountered will be given an estimate of relative abundance in the permit area.
6. Determine species distribution by habitat and season. Certain animals, especially birds, use specific habitats during different times of the year.
7. Enumerate other key habitat areas observed (e.g., cliffs, talus slopes, ponds, springs, known nests).

5.3 Sampling Frequency

Wildlife presence and activity surveys will occur twice per year. One survey will be conducted in December or January for overwintering birds (MMD 2010). Another survey will be conducted in late May or June during peak breeding season. Other groups of animals such as mammals, reptiles, and amphibians will also be recorded during the May/June surveys. Habitat features and characteristics will be noted during spring surveys.

5.4 List of Data to be Collected

Data to be collected will include:

1. Counts (sightings) of the various wildlife species including birds, reptiles, amphibians, and mammals.
2. Record signs of species (i.e. scat, feathers, burrows, bones, etc.).
3. Frequency—the number of transects and/or surveys a particular species is encountered.
4. Record key habitat features and characteristics suitable to various wildlife.
5. Survey for threatened or endangered species, including sightings, signs, and potential habitat encountered.

5.5 Methods of Collection

Data will be collected through visual/pedestrian transect surveys to identify nests, burrows, fecal pellets, and other pertinent signs of wildlife. These transects will consist of parallel lines spaced between 100 to 300 meters apart and oriented to capture the entire sampling unit. Smaller sampling units or strata, such as the tailings dam and pit will be surveyed with a closer transect spacing (approximately 100 meters). In larger sampling strata, such as the tailings pile and undisturbed areas, transect spacing will be greater (between 200 to 300 meters). As deemed necessary, these surveys will also be conducted during late evening and early morning to identify potential diurnally active animals and bat roosts, through direct observation or by listening for calls. Some of these wildlife surveys may include "time-constraint" surveys. A “time-constraint” technique uses a controlled or closely monitored amount of time to walk a transect line or survey area to record the total number of occurrences of particular species, such as a horned lizard for example. Such surveys are completed at specific times of the day when target species are more active.

5.6 Parameters to be Analyzed

Parameters to be analyzed include:

1. Bird nest density and distribution.

2. Density of observed avian species.
3. Relative abundance and distribution by habitat and season.
4. Density and distribution of wildlife indicators (e.g. fecal pellet counts) and occurrences (sightings) of wildlife.
5. Acreages and maps of key habitat areas for various wildlife species.
6. Threatened and endangered species survey results.

These parameters will be summarized and evaluated by individual species. Mobile or transient species, referring to those species without fixed habitat needs (such as those without nests or burrows) will similarly be tabulated and analyzed to determine abundance and frequency of occurrence.

5.7 Maps Showing Proposed Sampling Locations

Figure 5.1 shows a map of the sampling areas. These same areas will be surveyed for wildlife activity using the walking transects described above (Section 5.5). Transect spacing will vary as described based on the size of the sampling areas.

5.8 Laboratory and Field Quality Assurance Plans

Biologists will have a minimum of a BA/BS in Biology and five to ten years of field experience conducting a wide variety of animal surveys ranging from reptiles and amphibians, to birds, mammals, insects, and other invertebrates. This includes experience in recognizing and identifying signs of wildlife. All findings and results will be reviewed by senior scientists.

5.9 Discussion in Support of Sampling Proposal

Most of the protocol specific surveys for wildlife involve threatened and endangered species, or species with a "sensitive" status. Although our surveys will assess for the potential occurrence of threatened, endangered, or sensitive species, we are not anticipating that these will occur. Consequently, much of the sampling and analysis plan for wildlife is of a generalized nature. The intent of the sampling and analysis plan for wildlife is to obtain general or basic information on species presence and habitat use within the permitted area of the mine. All qualitative information will be included in the findings. Some of the information gathered will be of a quantitative nature and thus serve as a basis in which to monitor trends in wildlife use of these areas. The sampling approach will be revised if threatened, endangered, or sensitive species are suspected to occur

5.10 Resources

Adams, R.A., 2003, Bats of the Rocky Mountain West: natural history, ecology, and conservation: Boulder, Colo., University Press of Colorado.

Baicich, P.J., and Harrison, C.J., 2005, Nests, eggs, and nestlings of North American birds: Princeton, N.J., Princeton University Press.

Borror, D.J., and White, Richard, 1970, Peterson field guide to insects: New York, Houghton Mifflin Company.

Christman, B.C., 2003, A partial field guide to frogs and toads of the Gila National Forest: Albuquerque, N. Mex., Museum of Southwestern Biology, University of New Mexico.

Cartron, J.E., Lightfoot, D.C., Mygatt, J.E., Brantley, S.L., and Lowrey, T.K., 2008, A field guide to the plants and animals of the Middle Rio Grande Bosque: Albuquerque, N. Mex., University of New Mexico Press.

Degenhardt, W.G., Painter, C.W., and Price, A.H., Amphibians and reptiles of New Mexico: Albuquerque, N. Mex., University of New Mexico Press.

Elbroch, Mark, 2003, Mammal tracks and sign: Mechanicsburg, Pa., Stackpole Books.

Findley, J.S., Harris, A.H., Wilson, D.E., and Jones, Clyde, 1975, Mammals of New Mexico: Albuquerque, N. Mex., University of New Mexico Press.

Harley, G.T., 1934, The geology and ore deposits of Sierra County, New Mexico: Socorro, N. Mex., New Mexico School of Mines Bulletin 10.

Harrison, H.H., 1979, Western bird nests, Peterson field guides: New York, Houghton Mifflin Company.

Mining and Minerals Division (MMD), State of New Mexico, 2010, Guidance Document for Part 6 New Mining Operations Permitting under the New Mexico Mining Act, New Mexico Administrative Code Title 19, Chapter 10, Part 6, Draft for Review: New Mexico Energy Minerals and Natural Resources Department, Mining Act Reclamation Program, Santa Fe, New Mexico.

Peterson, R.T., 1990, Western birds, Peterson field guides: New York: Houghton Mifflin Company.

Zimmerman, D.A., and Zimmerman, M.A., 1997, New Mexico bird finding guide: Albuquerque, N. Mex., The New Mexico Ornithological Society.

5.11 References

Bureau of Land Management (BLM), 1999, Preliminary final environmental impact statement: Copper Flat project: Las Cruces, N. Mex. U.S. Department of the Interior, 491 p. Prepared by ENSR, Fort Collins, Colo.

Mining and Minerals Division (MMD), State of New Mexico, 2010, Guidance Document for Part 6 New Mining Operations Permitting under the New Mexico Mining Act, New Mexico Administrative Code Title 19, Chapter 10, Part 6, Draft for Review: New Mexico Energy Minerals and Natural Resources Department, Mining Act Reclamation Program, Santa Fe, New Mexico.

Steffen Robertson and Kirsten, Inc. (SRK), Southwest Rangeland Services, and Adrian Brown, 1997, Copper Flat Mine project monitoring plans: SRK Project 68607.

Figure



0 1,000 2,000 4,000 6,000

Feet

N
W E
S

Mine Boundary:
Tom Van Bebber
Strata/transects:
Parametrix
Imagery Information:
-USGS 7.5-Minutes County DOQQ mosaic
Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

Legend

- Proposed Mine Permit Boundary
- Proposed Wildlife Transect Survey Locations
- Access Road
- Baseline No Proposed Disturbance - Gravelly
- Baseline No Proposed Disturbance - Hills
- Baseline Proposed Disturbance - Gravelly
- Baseline Proposed Disturbance - Hills
- Pit
- Pit Lake
- Saltcedar
- Tailings Dam
- Tailings Pile

Figure 5-1
Map of the Proposed Wildlife Transects and Site Strata
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\5_wildlife\5-1_wildlife-transect.mxd 08/30/2010

Table of Contents

6 Topsoil Survey and Sampling 6-1
6.1 Background and General Description of Topsoil 6-1
6.2 Sampling Objectives 6-1
6.3 Sampling Frequency 6-2
6.4 List of Data to Be Collected 6-2
6.5 Methods of Collection 6-2
6.5.1 Sampling Methods 6-3
6.6 Parameters to Be Analyzed 6-5
6.7 Maps Showing Proposed Sampling Locations 6-6
6.8 Laboratory and Field Quality Assurance Plans 6-6
6.9 Discussion in Support of Proposal 6-6
6.10 References 6-6

List of Figures

Figure 6-1 Topsoil Sampling Locations

List of Tables

Table 6-1 Topsoil Data Needs
Table 6-2 Soil Characteristics and Methods Used

6 Topsoil Survey and Sampling

6.1 Background and General Description of Topsoil

A successful reclamation program is dependent, in part, upon the quantity and quality of soil available for use during the reclamation process. New Mexico Copper Corporation (NMCC) assessed the quantity and suitability of topsoil present at the Copper Flat Mine Permit Area (Site) in two ways. First, NMCC reviewed current literature concerning soil characteristics, and second, NMCC determined site-specific soil characteristics. The findings are summarized in this section of the SAP. In addition, baseline soil surveys were completed on the project area as recently as the late 1990s, and are briefly summarized and referenced in the PFEIS (BLM, 1999).

The term "topsoil" refers to the A master soil horizon (Soil Survey Staff, 1999), which is the uppermost mineral horizon that contains organic matter and can be salvaged from the areas to be disturbed and is capable of supporting vegetation, or other soil material capable of supporting vegetation. This material is often referred to as "suitable top dressing." NMCC has reviewed previous literature describing the results of soil surveys completed at the Site (BLM, 1999) and is aware that the presence of an A master soil horizon across the Site is limited. The purpose of the soil survey and sampling proposed in this section of the SAP is to evaluate the presence of suitable top dressing. However, in the interest of conforming to the requirements of the Mine Act regulations, the term "topsoil" will be used throughout this section to refer to suitable top dressing.

General information about the soils present at the Site was obtained from a Soil Conservation Service (SCS) survey completed by Neher (1984). The SCS (now the Natural Resources Conservation Service) mapped two major soil types that occur in the Copper Flat area:

1. The Luzena-Rock Outcrop association
2. The Scholle-Ildelfonso association

Figure 6-1 shows the boundary of the two soil types found in the proposed mine area along with the proposed operational areas within the proposed mine permit boundary. All but the easternmost portion of the proposed Site is mapped as Luzena-Rock Outcrop association, which is typically present on the steeper slopes of hills and mountains. These soils are typically shallow, very gravelly and cobbly loams and clay loams. The Scholle-Ildelfonso association occurs on more gentle slopes of the piedmonts and mountain toes and is deep, well-drained, and formed in mixed alluvium. The resulting soil texture in these areas is primarily gravely loams and gravelly clay loams (SRK, 1996).

The soils are thin and of low productive capacity. The soil textures are primarily gravelly loams and gravelly clay loams and are subject to continuing wind and water erosion. Along with the natural erosion, much of the Copper Flat landscape has been severely disturbed by historical placer mining and the 1982 mining operation. Over 63 percent of the areas targeted by the proposed operation were disturbed during the 1982 operation. Soils were replaced in the north cell of the tailings impoundment and over a portion of the plant site during 1986. Much of the remaining 1982 operational area remains disturbed and unvegetated (SRK, 1996).

6.2 Sampling Objectives

The objectives of soil sampling plan are:

- To determine the suitability of in-place soils in areas of proposed disturbance for use as a topsoil material during reclamation. Suitability parameters will be defined. Two key parameters for a topsoil source are soil texture and coarse fragment content because these are the most difficult parameters to amend. Also critical, particularly for soils in the southwestern United States, are soil salinity and sodicity.

Salt and sodium concentrations in soils affect plant growth and soil infiltration characteristics, and are also difficult to amend. Other soil characteristics that are important in reclamation, but which can more easily be amended, are organic matter content, macronutrient concentrations, and micronutrient concentrations.

- To determine the volume of suitable material present and calculate the amount of topsoil that must be obtained from a borrow source to complete Site reclamation.

6.3 Sampling Frequency

In accordance with 19.10.6.602 of the New Mexico Administrative Code (NMAC), there will be one sampling event for topsoil characterization during the 12-month baseline data collection period.

6.4 List of Data to Be Collected

Table 6-1 shows the four data requirements identified for topsoil and the plans for addressing these requirements. NMCC proposes to satisfy the data requirements by characterizing soils in areas that will be disturbed by proposed mining operations and that may be used as topsoil borrow sources. Figure 6-1 shows the proposed mining disturbance areas.

6.5 Methods of Collection

First order (order 1) pedestrian soil surveys will be conducted by a qualified soils scientist within each of the disturbed areas shown on Figure 6-1 to delineate topsoil. First order soil surveys have delineations of 1 hectare (2.5 acres) or less, depending on scale; typically show phases of soil series and miscellaneous areas as components of map units; and typically display results at a scale of 1:15,840 or larger (Soil Survey Division Staff, 1993). Surveys will be conducted by walking along parallel transects defined within the boundary of each disturbed area. The total number of transects per disturbed area will be randomly selected using the random point generation function within Hawth's Analysis Tools ArcGIS plug-in. During this process, the required number of random transects will be placed in each disturbed area. The resulting geographic coordinates will be transferred to a Global Positioning System (GPS) receiver with a horizontal accuracy≤3m for field navigation to the target locations. If field conditions do not match the stratum intended, the transect will be moved to a nearby location within the disturbed area. While walking along each transect, the soils scientist will delineate the boundaries for topsoil by making visual observations of surface soils and confirming those observations with hand-auger holes. Topography, vegetative cover, slope and aspect will all be used to guide the decisions. Boundaries recorded in the GPS receiver will later be downloaded and imported into an ESRI geographic information system (GIS) as a shapefile.

Soil samples will be collected from topsoil within the disturbed areas using a hand auger, shovel, mechanized geoprobe (if permitted), or other means necessary to retrieve samples until bedrock or a hardened surface is reached. A total of six samples will be taken: three from the tailings impoundment and one each from the North, West, and East Waste Rock disposal areas (Figure 6-1). It is anticipated that at each sample location, a soil subsample will be collected at three different depth intervals in the topsoil. The subsamples from each location will be collected and mixed to form a composite sample. Typically, the soil scientist will estimate soil texture visually at 6-inch intervals within the top 2 feet (ft). Below 2 ft, texture will be estimated at 1-ft intervals. Soil features, such as color, presence of calcium carbonates, salt accumulation, volume of coarse fragments, and depth to bedrock or rocky layer, will also be noted. For mapping purposes, the location of the subsample will be documented with a GPS receiver.

Soil samples will be air-dried before submission to the laboratory. Sample handling and chain-of-custody procedures will be followed for the preparation of soil samples for shipment to the off-site analytical laboratory.

6.5.1 Sampling Methods

The sampling methods described below may be used for obtaining the necessary soil samples. The surface soil sample collection procedures discussed in 6.5.1.1 may be used if the soil sampling location is not below a water surface. The procedures discussed in 6.5.1.2 may be used if the soil sampling location is below a water surface.

The following equipment will be assembled before surface-soil sampling begins:

- Coolers
- Sample containers and laboratory-supplied preservatives (if needed)
- Sample labels
- Personal protective equipment
- Custody seals
- Waterproof pens
- Appropriate sampling equipment
- Acetate sleeves (if needed)
- Personnel/equipment decontamination supplies
- Field logbook
- Sample control logs
- Chain-of-custody forms

All sampling equipment will be cleaned before use.

6.5.1.1 Surface Soil Sample Collection Procedure (Dry)

The following procedure will be used for collecting surface soil samples for chemical analysis.

1. If necessary, use a shovel to remove vegetation from the sampling point.
2. Use any of the following three methods to obtain representative samples from the intervals of interest:
    a. Soil samples may be collected using a hydraulic soil sampler or a hand-driven soil sampler, both with acetate sleeves. These samples will be extruded from the acetate sleeve or else the sleeve will be cut to segregate the sample interval of interest.

       Cap the acetate sleeves as quickly as possible and send them intact to the laboratory so that the interval of interest can be tested with a minimum loss of volatile components.

    b. A pit may be excavated with a clean shovel to expose a soil profile, which is a vertical cut in the soils that exposes the genetic layers or horizons. Because the soil samples will be analyzed for metals, samples will not be collected from the surface that was in contact with the shovel. Instead, the surface will be scraped with a clean, non-metal trowel before collection. Soil samples may be collected using a clean, stainless-steel trowel or an appropriate disposable trowel to remove equal portions of the soil from the surface or near the surface to the base of the interval of interest.

    c. Soil samples may be collected using a clean, stainless-steel hand auger. Note the sampling depth. Use a non-metal trowel, spatula, or knife to assist in removing the sample for placement in the sample container.
3. Remove obvious rock material from each sample.

4. Place each sample in a clean, labeled sample container and cap securely as quickly as possible. Ensure that neither the sample nor its container comes into contact with any contaminated surfaces.
5. Provide complete information when filling out the sample label. Labels must include the following information:
   - Project name and/or number
   - Field sample number
   - Depth interval (if applicable)
   - Initials of collector
   - Date and time of collection
   - Sample type and preservative (if any)
6. Immediately place the sealed and labeled sample container in a cooler containing double-bagged ice or frozen ice packs. Store at <4°C, if required. (The use of protective packaging will be dictated by the mode of transport.)
7. Record the sampling data on the sample control log and in the field logbook, as appropriate.
8. Decontaminate the sampling equipment before collecting the next sample. If possible, have a sufficient quantity of clean, decontaminated equipment available so that each sample can be taken with separate equipment and all sampling tools can be decontaminated periodically or at the end of the sampling effort rather than between each sampling event.
9. Complete a chain-of-custody form for laboratory shipment.
10. Place custody seals across the shipping container lids so that the shipping containers cannot be opened without breaking the custody seals. Custody seals must contain the following information:
    - Collector's signature or initials
    - Date of shipping
11. Ship sample containers to the laboratory for analysis within 24 hours of sample collection, carefully observing all minimum holding time requirements for degradable constituents.

The chain-of-custody form, sample control logs, and field logbook must be completed in accordance with the procedures set forth in the Quality Assurance Project Plan (Attachment 1).

6.5.1.2 Sampling Beneath a Water Surface

The following sampling methods may be used if the soil sampling location is below a water surface.

6.5.1.2.1 Sampling with a Trowel

Sediment samples can be collected using a stainless steel or disposable trowel provided the water depth is very shallow (e.g., a few centimeters). A stainless steel trowel or scoop is recommended because of its inert nature. Single grab samples may be collected or, if the area in question is large, a grid can be used and multiple samples can be collected and composited. The sample collection procedure is as follows:

1. Label all bottles. Fill out all information except the sampler's name/initials and the actual date and time. Sort bottles according to the sampling locations.
2. Note the sampling location in the logbook, measuring distances and direction from stationary landmarks. If possible, photograph the location.

3. Record the date, time, and sampler's name/initials on all sample containers and on the sample control log. Cover all container labels with wide transparent waterproof tape to ensure label integrity.
4. Insert the trowel into the sediment and begin to remove material. Avoid collecting large rocks or plant roots as much as possible.
5. Decontaminate the sampling equipment before collecting the next sample by cleaning the equipment with warm water and Liquinox, then rinsing again with warm water. If possible, have a sufficient quantity of clean, decontaminated trowels available so that each of the sediment samples can be taken with a separate trowel and decontamination can be performed on all the trowels at the end of the sampling effort rather than between each sampling event.
6. Store and transport at <4°C, if required, and place custody seals on the cooler lid so that the cooler cannot be opened without breaking the seals.

6.5.1.2.2 Sampling with a Hand Corer

A hand corer is essentially the same type of thin-wall sampler that is used for collecting surface soil samples. It has a handle to facilitate driving the corer into the sediment and a check valve on the top to prevent sample washout during retrieval through an overlying water layer.

Hand corers can be used for the same situations and with the same materials as trowels (see previous section). The advantage of a hand corer is the ability to collect an undisturbed sample that can profile any stratification in the sample as a result of changes in the deposition. Some hand corers can be fitted with extension handles that allow collection of sediment samples in water of moderate depth (6 ft). Most corers can be fitted with liners of brass, polycarbonate plastic, or Teflon. The appropriate liner can be chosen to match the type of contamination expected in the sample and the intended analytical procedures.

The sample collection procedure using a hand corer is as follows:

1. Label all bottles. Fill out all information except the sampler's name/initials and the actual date and time. Sort bottles into sets: one per sampling location, with additional sets as needed for blanks and duplicates.
2. Note the location of the sample in the logbook, measuring distances and direction from stationary landmarks. If possible, photograph the location.
3. Record the date, time, and sampler's name/initials on all sample containers and on the sample control log. Cover all container labels with wide transparent waterproof tape to ensure label integrity.
4. Force the corer into the sediment with a smooth, continuous motion.
5. Twist the corer and withdraw in a single smooth motion.
6. Decontaminate the sampling equipment before collecting the next sample.
7. Store and transport at <4°C, if required, and place custody seals on the cooler lid so that the cooler cannot be opened without breaking the seals.

6.6 Parameters to Be Analyzed

Soil samples will be collected and analyzed at a soil testing laboratory accredited by the National Environmental Laboratory Accreditation Program (NELAP) and the New Mexico Environment Department (NMED) for the soil characteristics summarized in Table 6-2. While performing the field sampling, the New Mexico Copper

Corporation (NMCC) representative will measure pH and electrical conductivity as necessary in order to "field-calibrate" for these parameters. Rock fragments will be removed from samples in the field and will be estimated by percentage by the soils scientist. In addition to the analyses outlined in Table 6-2, measurements of electrical conductivity, saturation percentage, and salinity will be collected following USDA guidelines (U.S. Salinity Laboratory Staff, 1954). Sodium adsorption ratio, a measure of the sodicity of the soil, will be calculated from the parameters of paste calcium, magnesium, and sodium in units of milliequivalents per liter.

6.7 Maps Showing Proposed Sampling Locations

A total of six samples will be taken: three from the tailings impoundment and one each from the North, West, and East Waste Rock disposal areas. Figure 6-1 shows the general boundaries of these locations at the Site.

6.8 Laboratory and Field Quality Assurance Plans

Sampling will be conducted in accordance with the sampling procedures described above. Soil sampling will be conducted by a qualified NMCC representative, who will document the sample location on a map, take a GPS reading, and record observations in a logbook. Sample handling and chain-of-custody procedures will be followed to prepare soil samples for shipment to the off-site analytical laboratory. Laboratory analyses will be conducted in accordance with methods described in *Methods of Soil Analysis, Parts 1 and 2* (Klute, 1986, and Weaver, 1994, respectively). NMCC will select a laboratory that operates under a quality program and has expertise and experience with the approved soil analytical methods.

6.9 Discussion in Support of Proposal

The proposed data collection will allow the characterization and establishment of baseline topsoil conditions across the Site in advance of mining and will supplement existing topsoil data. A deficit in volume of topsoil for Site reclamation is expected. The topsoil required to compensate for the deficit is expected to be obtained from within the tailings impoundment area (SRK, 1996).

6.10 References

Bureau of Land Management (BLM), 1999, Preliminary final environmental impact statement, Copper Flat project: Las Cruces, N. Mex., U.S. Department of the Interior, 491 p. Prepared by ENSR, Fort Collins, Colo.

Klute, Arnold, ed., 1986, Methods of soil analysis, Pt. 1, Physical and mineralogical methods (2d ed.): Madison, Wis., American Society of Agronomy, Inc., Soil Science Society of America, Inc., 1358 p.

Neher, R.E., 1984, Soil survey of Sierra County area, New Mexico: Washington, DC, U.S. Department of Agriculture, Soil Conservation Service, 80 p.

Plumb, R.H., Jr. 1981. Procedures for handling and chemical analysis of sediment and water samples, Technical Report EPA/CE-81-1, U.S. Environmental Protection Agency/Corps of Engineers Technical Committee on Criteria for Dredged and Fill Material. U.S. Army Engineer Waterways Experiment Station, Vicksburg, Miss.

Soil Survey Division Staff, 1993, Soil survey manual, Soil Conservation Service, U.S. Department of Agriculture Handbook 18.

Soil Survey Staff, 1999, Soil taxonomy, a basic system of soil classification for making and interpreting soil surveys (2d ed.): Washington, D.C., U.S. Department of Agriculture Natural Resources Conservation Service Agriculture Handbook 436, U.S. Government Printing Office.

Steffen Robertson and Kirsten (SRK), 1996, Copper Flat Mine, Mining permit application, v. 1, p. 2-12.

U.S. Salinity Laboratory Staff, 1954, Chapter 2 – Determination of the properties of saline and alkali soils, *In* Diagnosis and improvement of saline and alkali soils, Agriculture Handbook No. 60, United States Department of Agriculture, 27 p.

Weaver, R.W., ed., 1994, Methods of soil analysis, Pt. 2, Chemical and microbiological properties: Madison, Wis., Soil Science Society of America, Inc., 1692 p.

Figure



N
W E
S

0 1,000 2,000 4,000 6,000

Feet

Mine Boundary:
Tom Reynolds
Disturbed areas/mine facilities: SRK, 2010
Imagery Information:
-USGS 7.5-Minutes County DOQQ
mosaic Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

Legend

- Proposed Mine Permit Boundary
- Proposed Mine Facility
- Scholle-Ildefonso/Lusena-Rock soil boundary
- Waste Rock
- Topsoil Stockpile
- Tailings
- Stockpile
- Pit
- Haul Road
- Diversion
- Ancillary
- Access Road

Figure 6-1
Topsoil Sampling Locations

New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\6_Topsoil\6-1_topsoil_sample_locs.mxd 09/03/2010

Tables

Table 6-1
Topsoil Data Needs

Data Need	Plan to Address Data Need
Determine accurate soil depths in areas to be disturbed to ensure proper topsoil volume calculation.	Measure soil depths in areas where planned disturbances will take place (locations will be entered into a GPS unit).
Determine suitability of stripped material for use as topsoil during reclamation.	Send soil samples to a laboratory for analysis to determine characteristics and suitability as topsoil.
Determine need for additional topsoil.	Estimate the available topsoil based on the results of the soil survey and calculate topsoil deficit by subtracting the available topsoil from the topsoil needed. Any topsoil deficit will be addressed identifying additional on-site borrow areas or other potential borrow sources in the immediate vicinity of the mine.
Sample and characterize any material needed from borrow pits to complete reclamation efforts.	Conduct soil characterization and analysis on soils that may be used as a borrow source.

Table 6-2

Soil Characteristics and Methods Used

(Sampling requires 125 ml/4 oz wide mouth glass jar.)

Analytical Parameter	Analysis Method	Lab Detection Limit for Sediments (mg/kg unless noted)
Nitrate-nitrite	EPA Method 353.2	0.05
Phosphorous	EPA Method 365.2	2.5
Arsenic	EPA Method 200.7	1.0
Boron	EPA Method 200.7	2.0
Cadmium	EPA Method 200.7	0.1
Calcium	EPA Method 200.7	5.0
Copper	EPA Method 200.7	0.2
Iron	EPA Method 200.7	1.0
Lead	EPA Method 200.8	0.25
Magnesium	EPA Method 200.7	5.0
Manganese	EPA Method 200.7	0.1
Mercury	M7471A CVAA	0.03
Molybdenum	EPA Method 200.7	0.4
Nickel	EPA Method 200.7	0.5
Potassium	M6010C ICP	10
Selenium	EPA Method 200.7	1.0
Sodium	EPA Method 200.7	5.0
Zinc	EPA Method 200.7	0.25
pH	EPA Method 150.1	NA
Grain size	Plumb, 1981	NA

Table of Contents

7 Geology 7-1
7.1 Regional Geologic Setting 7-1
7.2 Geology of Copper Flat Mine Site 7-1
7.2.1 Stratigraphy 7-1
7.2.2 Structure 7-2
7.3 Description of the Ore Body 7-3
7.3.1 Structure and Model 7-3
7.3.2 Mineralization 7-4
7.4 Geochemical Sampling 7-5
7.4.1 Step 1: Data Review and Material Type Delineation 7-5
7.4.2 Step 2: Sample Interval Selection 7-6
7.4.3 Step 3: Sample Collection and Field Screening 7-6
7.4.4 Step 4: Geochemical Test Work 7-7
7.4.5 Step 5: Kinetic Testing Program 7-7
7.4.6 Step 6: Data Validation and Compilation 7-7
7.5 References 7-8

List of Figures

Figure 7-1 Regional Surface Geology
Figure 7-2 Schematic Geologic Cross Section (A-A')
Figure 7-3 Geologic Structural Features of the Region
Figure 7-4 Geologic Schematic of the Hillsboro Mining District, New Mexico
Figure 7-5 Locations of Geologic Samples

List of Tables

Table 7-1 Stratigraphy of the Copper Flat Area
Table 7-2 Proposed Analytical Parameters with Method Reporting Limits

7 Geology

This section provides an overview of the regional and local stratigraphy and structural geology, as well as the mineralization at the Copper Flat Mine Permit Area (Site). The information has been summarized primarily from the BLM Preliminary Final Environmental Impact Statement (PFEIS) for Copper Flat (1999), Raugust (2003), and SRK (2010).

7.1 Regional Geologic Setting

The Copper Flat Mine lies within the Mexican Highlands portion of the Basin and Range Physiographic Province. It is located in the Hillsboro Mining District in the Las Animas Hills, which are part of the Animas Uplift, a horst on the western edge of the Rio Grande valley (Raugust, 2003). The Animas Uplift is separated from the Rio Grande by nearly 20 miles of Santa Fe Group alluvial sediments, referred to as the Palomas Basin of the Rio Grande valley. To the west of the Animas Uplift is the Warm Springs valley, a graben that parallels the Rio Grande valley (BLM, 1999; Raugust, 2003). Further west, the Black Mountains form the backbone of the Continental Divide, rising to about 9,000 feet above mean sea level (amsl). The surface geology of the Copper Flat region is shown in Figure 7-1, and a schematic geologic cross section is shown in Figure 7-2.

Basement rocks in the area consist of Precambrian granite and Paleozoic and Mesozoic sandstones, shales, limestones, and evaporites. Sedimentary units that crop out within the Animas Uplift include the Ordovician Montoya Limestone, the Silurian Fusselman Dolomite, and the Devonian Percha Shale. The Cretaceous-age Laramide orogeny, which was characterized by the intrusion of magma associated with the subduction of the Farallon plate beneath the North American plate, affected this region between 75 and 50 million years ago (Ma). Volcanic activity during the late Cretaceous and Tertiary periods resulted in localized flows, dikes, and intrusive bodies, some of which were associated with the development of the nearby Tertiary Emory and Good Sight-Cedar Hills cauldrons (Figure 7-3); later basaltic flows resulted from the tectonic activity associated with the formation of the Rio Grande rift. Tertiary and Quaternary alluvial sediments of the Santa Fe Group and more recent valley fill overlie the older Paleozoic and Mesozoic units in the area. The regional stratigraphy of the lower Rio Grande Valley is summarized in Table 7-1 (BLM, 1999).

The geologic structure of the region is characterized by block and rift faulting (Figure 7-3). The Tertiary cauldrons associated with the earlier block faulting formed between 35 and 45 Ma. Rift faulting and associated north-south block faulting associated with continental extension and the formation of the Rio Grande rift began approximately 25 to 30 Ma. The Las Animas Hills are bounded by faults associated with rifting (Dunn, 1982). Continental extension continues to the present, as evidenced by north-south trending grabens represented by the Rio Grande and Warm Springs valleys.

7.2 Geology of Copper Flat Mine Site

7.2.1 Stratigraphy

As shown in Figure 7-4, the dominant geologic feature of the Animas Hills and Hillsboro district is the Copper Flat strato-volcano, a circular body of Cretaceous andesite that is 4 miles in diameter (Raugust, 2003). The andesite is generally fine-grained with phenocrysts of plagioclase (andesine) and amphibole in a groundmass of plagioclase and potassium feldspar and rare quartz. Some agglomerates or flow breccias are locally present, but the andesite is generally massive. Magnetite is a common association with the mafic phenocrysts, and accessory apatite is found in nearly every thin section (Dunn, 1984).

The strato-volcano is eroded to form a topographic low; the total depth of erosion is uncertain (SRK, 2010). To the east of the Site, this andesite body is in fault contact with Santa Fe Group sediments, which are at least

2,000 feet (ft) thick in the area. Near-vertical faults characterize the contacts on the remaining perimeter of the andesite body; these faults juxtapose the andesite with Paleozoic sedimentary rocks. Drill holes indicate the andesite is more than 3,000 ft thick. This feature, combined with the concentric fault pattern, indicate that the local geology represents a deeply eroded Cretaceous-age volcanic complex (Dunn, 1982).

The core of the volcanic complex is a Cretaceous-age quartz monzonite stock that intruded into the center of the andesite body. Known as the Copper Flat Quartz Monzonite (CFQM), this irregular-shaped stock underlies a surface area of approximately 0.25 square miles and has been dated to approximately 75 million years before present (Raugust, 2003; BLM, 1999; and McLemore et al., 2000). The monzonite crops out in only a few isolated areas, and the andesite at these contacts shows no obvious signs of contact metamorphism (Dunn, 1984). The CFQM is a medium- to coarse-grained, holocrystalline porphyry composed primarily of potassium feldspar, plagioclase, hornblende, and biotite; trace amounts of magnetite, apatite, zircon, and rutile are also present, along with localized mineralized zones containing pyrite, chalcopyrite, and molybdenite (McLemore et al., 2000). About 15 percent of the monzonite is quartz, which occurs both as small phenocrysts and as part of the groundmass; however, quartz is absent in some parts of the stock (Dunn, 1984).

Numerous dikes, mostly latite, radiate from the CFQM stock, some nearly a mile in length. Most of the dikes trend to the northeast or northwest and represent late stage differentiation of the CFQM stock (Raugust, 2003). Immediately south of the quartz monzonite, the andesite is coarse-grained, perhaps indicating a shallow intrusive phase. An irregular mass of andesite breccia along the northwestern contact of the quartz monzonite contains potassium feldspar phenocrysts and andesitic rock fragments in a matrix of sericite with minor quartz; this may represent a pyroclastic unit. Magnetite, chlorite, epidote, and accessory apatite are also present in the andesite breccia (Dunn, 1984).

The southwestern edge of the andesite body was intruded by the Warm Springs Quartz Monzonite pluton, which dates to approximately 73 Ma (Hedlund, 1974). Unlike the CFQM and the andesite, this monzonite body is not cut by the latite dikes (SRK, 2010), indicating that the dikes were emplaced prior to the Warm Springs Quartz Monzonite.

The Sugarlump Tuff (35 Ma) and the Kneeling Nun Tuff (34 Ma) unconformably overlie the local andesite flows. These tuffs erupted from the Emory caldera, and indicate that the Copper Flat volcanic/intrusive complex was buried during the Oligocene and exhumed during Miocene uplift (around 21.7 ±3.6 Ma) (Kelley and Chapin, 1997). Both the andesite and the quartz monzonite intrusions are cut by black, scoriaceous basalt dikes. These dikes remain unaltered, and appear to be associated with locally abundant Pliocene alkali basalt flows from around 4 Ma (Seager et al., 1984).

7.2.2 Structure

Three principal structural zones are present at the Site and surrounding area, the most prominent of which is a northeast-striking fault trend that includes the Hunter and parallel faults. In addition, west-northwest striking zones of structural weakness are marked by the Patten and Greer faults, and east-northeast striking zones are marked by the Olympia and Lewellyn faults. All faults have a near-vertical dip; the Hunter fault system dips 80°W, and both the Olympia and Lewellyn fault systems dip between 80°S and 90°S (SRK, 2010; Dunn, 1984). These three major fault zones appear to have been established prior to the emplacement of the CFQM and controlled subsequent igneous events and mineralization (SRK, 2010).

The CFQM emplacement is largely controlled by the three structural zones. The southern contact parallels and is cut by the Greer fault, although the contact is cut by the fault, and the southeastern and northwestern contacts are roughly parallel to the Olympia and Lewellyn faults, respectively. The elongate neck of the stock parallels the Hunter fault system. Whether there was movement along the fault zones before the emplacement of the stock has not been determined (SRK, 2010; Dunn, 1984).

Although the latite dikes strike in all the three principal fracture directions, most of the dikes strike northeast. A narrow zone of fault gouge commonly occurs along the contact between the dikes and the andesite, with the mineralization post-dating fault movement (Harley, 1934). The northeast fault zones contain a high proportion of wet gouge, often with no recognizable rock fragments. Underground exposures of the Hunter fault zone (in previously existing mine workings) material has the same consistency as wet concrete and has been observed to flow in underground headings. However, the material in the east-northeast fault zones contains only highly broken rock and little obvious gouge. The width of the fault zones in both systems varies along strike from less than a foot to nearly 25 ft in the Patten fault east of the Project. Despite intense brecciation, the total displacement along the faults does not appear to exceed a few tens of feet (Dunn, 1984). At the western edge of the Site, a younger porphyritic dike was emplaced in a fault that had offset an early latite dike, indicating that fault movement occurred during the time that dikes were being emplaced (Dunn, 1984).

Post-dike movement is evident in all the three principal fault zones, and both the Hunter and Patten fault systems show signs of definite post-mineral movement. Fault movement has smeared sulfide deposits and offset the breccia pipe as well as the zones within the breccia pipe. Post-mineral movement along faults has resulted in wide, strongly brecciated fault zones. Some of the post-mineral dikes have been emplaced within these fault zones (SRK, 2010; Dunn, 1984).

NMCC has mapped the pit area and diversion cuts in detail at 1 inch:40 ft (1:480) and has examined the pre- and post-mineral stress orientations in the andesites and CFQM. Findings indicate no significant difference in the stress fields before and after mineralization (SRK, 2010).

7.3 Description of the Ore Body

Copper Flat is an alkalic copper-gold mineralized breccia pipe, associated with and genetically-linked to an alkalic porphyry system. Copper Flat is situated along the eastern edge of the Cretaceous Arizona-Sonora-New Mexico porphyry copper belt, and, along with Tyrone, New Mexico, forms a linear mineralized feature known as the Santa Rita lineament (SRK, 2010; McLemore et al., 2000). Copper Flat is the easternmost and one of the oldest known porphyry deposits in the southwestern U.S. (Hedlund, 1974; Dunn, 1982; Titley, 1982). Analogous deposits include Terrane Metal's Mount Milligan, British Colombia deposit and the Continental breccia pipe located in the Central Mining district of New Mexico (SRK, 2010).

7.3.1 Structure and Model

Mineralization at the Site is concentrated in a breccia pipe within the CFQM stock (Raugust, 2003; BLM, 1999). The eastern portion of the breccia pipe is outside the outline of the main mineralization; however, the rest of the breccia pipe is higher grade than the surrounding CFQM, hosting nearly half of the copper at the Site, but only about one-third of the total resource tonnage (SRK, 2010). Drillholes spaced approximately 100 ft apart within the center of the deposit indicate the breccia pipe occurs as a single, continuous body, approximately 1,300 ft long by approximately 600 ft wide at the surface with the long axis perpendicular to the predominant northeast fracture direction. It is exposed in only a few places, but extends vertically to over 1,000 ft; veins of coarse pegmatitic material have been found at approximately 1,700 ft below ground surface (bgs) in one drillhole (Dunn, 1984).

Mineralized polymetallic quartz veins, commonly associated with the dikes that radiate outward from the central stock, have been the target of historical mining activities in the Hillsboro district. The breccia pipe zone has been cut by numerous, randomly oriented, irregular veins that are thicker and coarser grained than the narrow fracture-controlled veinlets in the surrounding stock.

Mineralization appears to have been contemporaneous with pipe formation (SRK, 2010). The lack of rock flour or gouge in the matrix suggests that brecciation was not the result of tectonic movement, while the apparent

lack of appreciable movement between the fragments and the gradational contact between the breccia and the zone of stockwork veining indicate that an explosive mechanism was not the source of the brecciation. Likewise, the process of mineralization stoping described by Locke (1926), which would have resulted in appreciable downward movement and mixing of the fragments, is not supported by field observations. Thus the mechanism responsible for the formation of the Copper Flat mineralized breccia pipe appears to be autobrecciation resulting from retrograde boiling, a phenomenon that occurs when the pressure of the mineralizing hydrothermal fluid exceeds the confining pressure (Phillips, 1973). The matrix of the breccia, the irregular veins in the surrounding crackle breccias, and the open space filling in the breccias consist of hydrothermal minerals and part of the second stage mineralization occurred as replacement, which modified the original breccia texture (SRK, 2010).

Unlike most deposits in the southwestern U.S., Copper Flat shows very little supergene enrichment or the symmetrical and telescoped zoning of alteration types that is considered typical of most porphyry copper deposits. Instead, hypogene mineralization and alteration, including the formation of the breccia pipe, was the result of the final crystallization of the CFQM melt and related dikes (SRK, 2010).

The current model used by NMCC for further exploration at the Site is based on Richards (2003), who interprets the area as an eroded volcano. According to this model, mineralization occurred at similar depths to that found at El Teniente in Chile; since the Copper Flat breccia pipe now crops out at the surface, this assumption indicates that approximately 0.5 to 2 kilometers (km) of volcanic rocks have been eroded from the central zone of mineralization. Fluid inclusion work by Norman et al. (1989) and McLemore et al. (2000) suggest that the breccia pipe and veins formed at a depth of 1 to 2 km bgs and at temperatures ranging from 226° to 360°C.

7.3.2 Mineralization

During the early mining days, a 20- to 50-foot leached oxide zone existed over the ore body, but this material was stripped during the mining activities that occurred in the early 1980s. Most of the remaining ore is unoxidized and consists primarily of chalcopyrite and pyrite with some molybdenite and traces of galena and sphalerite. Appreciable amounts of silver and gold are also present (BLM, 1999; SRK, 2010). The proven and probable reserves are estimated at more than 50 million tons of ore with 0.45 percent copper (Hydro Resources, 2002).

The breccia consists largely of fragments of mineralized CFQM, with locally abundant mineralized latite where dikes exposed in the CFQM projected into the brecciated zone. Andesite occurs only as mixed fragments partially in contact with intrusive CFQM and appears to represent the brecciation of andesite xenoliths in the CFQM (Dunn, 1984). The matrix contains varying proportions of quartz, biotite (phlogopite), potassium feldspar, pyrite, and chalcopyrite, with magnetite, molybdenite, fluorite, anhydrite, and calcite locally common. Apatite is a common accessory mineral. Much of the quartz-feldspar matrix has a pegmatitic texture. Breccia fragments are rimmed with either biotite or potassium feldspar, and the quartz and sulfide minerals have generally formed in the center of the matrix (Dunn, 1984).

The andesite in contact with the CFQM, dikes, and veins is typically altered into one of three types of mineral assemblages: biotite-potassic, potassic, or sericitic alteration (Fowler, 1982). The highest copper grades are associated with the biotite-potassic alteration, which is characterized by hydrothermal biotite, potassium feldspar, quartz, and pyrite, and which occurs in veinlets and as replacement assemblages in the monzonite (McLemore et al., 2000).

The total sulfide content ranges from 1 percent (by volume) in the eastern part of the breccia pipe and the surrounding CFQM to 5 percent in the CFQM to the south and west (SRK, 2010). Sulfide content is highly variable within the breccia, with portions containing as much as 20 percent sulfide minerals. Sulfide mineralization is

restricted to the CFQM and breccia pipe, and drops abruptly at the andesite contact. Minor pyrite mineralization extends into the andesite along the pre-mineral dikes (SRK, 2010; Dunn, 1984).

Pyrite and chalcopyrite are disseminated within the CFQM and also occur along fracture-controlled veinlets and as disseminations associated with mafic minerals. Typically, pyrite is more abundant than chalcopyrite in two areas (SRK, 2010):

- A narrow zone that surrounds and overlies the western end of the breccia pipe, which has the highest grade CFQM mineralization, characterized by abundant chalcopyrite in quartz-sulfide veinlets.
- Outcrops to the southeast of the breccia and south of Grayback Wash, where disseminated chalcopyrite is present with no associated pyrite.

Molybdenite occurs occasionally in quartz veins or as thin coatings on fractures. Minor sphalerite and galena are present in both carbonate and quartz veinlets in the CFQM stock (Dunn, 1984).

7.4 Geochemical Sampling

NMCC has hired a contractor to conduct geologic sampling to address the potential for geologic strata to create acid rock drainage, or degradation of the surface or groundwater quality, or cause a hindrance to reclamation. NMCC proposes the use of the following geochemical characterization program at Copper Flat.

An assessment of waste rock geochemistry is proposed to predict the potential geochemical reactivity of waste rock that will be exposed during the proposed mining operation, and to provide input into a future pit lake hydrogeochemical model. This assessment will also include characterization of ore-grade materials that will be processed and deposited as tailings in the tailings impoundment.

The material characterization described in this program will address mineralogy, bulk geochemical characteristics, and the potential of the waste rock and processed ore (tailings) to generate acid or net neutral drainage, as well as a prediction of future water quality that would result from precipitation contacting the material, and what influence this may have on groundwater, surface water, and pit lake quality at the site. As appropriate, the assessment may identify waste rock management measures that would mitigate or reduce future liabilities.

NMCC proposes a phased approach that will ensure that the geologic sampling program applied addresses all the regulatory objectives and requirements. The following is a general breakdown of each step.

7.4.1 Step 1: Data Review and Material Type Delineation

NMCC's contractor will review all data available from the previous and current exploration drilling programs, including the drill hole database, drill logs, assay data, and bulk element geochemistry. From this review, the main rock types, alteration types, and oxidation states identified by SRK in the late 1990's will be reviewed and modified as needed. The combination of these parameters will be used to define material types for the project that will be the focus of the characterization program.

The block model and proposed pit outlines prepared by NMCC and its contractor will also be reviewed to identify ore and waste zones within the proposed pit boundaries and ensure that the proposed sample suite is spatially representative (both vertically and horizontally) of waste rock and ore. The estimated tonnages of the waste rock and ore material types will be obtained from the block model in order to define the number of samples required to characterize each material type. The sampling program will focus on the main material types with more samples being collected from the material types with the greatest predicted tonnage. This characterization will include both ore- and waste-grade material.

7.4.2 Step 2: Sample Interval Selection

Several types of geologic material are available from the exploration drill programs for sampling including coarse rejects and half-split core from the core and rotary drilling. However, the core will be the preferred sample material. The half-split core material is currently being stored on-site in a sheltered area and oxidation of this material from weather is anticipated to be minor. A significant amount of the core material from the mineralized zones may have been mostly consumed for metallurgical testing; however, half-split core material should be available for most of the waste intervals. Therefore, the half-split core material from the waste intervals has been identified as the best material available for geochemical testing and will be targeted in the waste rock characterization portion of this sampling program. In addition, exploration drilling is currently ongoing in the expansion areas. This drilling presents an opportunity to collect additional samples for geochemical testing from rotary and core holes, provided the coarse rejects are properly stored prior to sample collection.

In the late 1990s, SRK collected 46 samples for Acid Base Accounting (ABA) testing, 59 for Net Acid Generation (NAG) testing, 1 for short-term leach testing, and 5 for humidity cell kinetic tests. In addition, 14 samples were collected from the historic tailings impoundment for static test analysis, and approximately 130 samples of waste rock and pit walls were collected for field NAG test and paste chemistry. These samples were characterized by lithology, alteration, oxidation, and absence/presence of sulfides. Samples were generated by collecting material from consecutive intervals within the same drill hole, and each sample consisted of a single material type as defined by rock type, alteration type, and oxidation state. These samples were submitted to certified laboratories in Reno, Nevada for sample preparation and laboratory testing.

Additional samples will be required for waste rock characterization in order to create a sample database that is vertically and horizontally representative of waste rock associated with the current project. In addition, ore-grade samples will need to be collected. Following the data review and development of estimated waste rock and ore volumes in Step 1, NMCC's contractor will select sample intervals from exploration drill holes to fill the identified data gaps.

NMCC's approach to sample selection is designed to ensure that samples with the end-member reactivity are sufficiently sampled to provide a comprehensive and representative understanding of the full range of geochemical characteristics for each of the material types. To this end, NMCC's contractor will focus on understanding the geological controls on the geochemical behavior of the different materials as the basis for sample selection. As additional mineralogical and geochemical data become available through sample analysis, these data will be combined with the previous data to define subsequent sample sets.

7.4.3 Step 3: Sample Collection and Field Screening

Samples will be collected by qualified geologists from consecutive intervals within the same drill hole and each sample will consist of a single material type as defined by rock type, alteration type, and oxidation state.

Once the main material types are delineated and sampled, a number of field tests can be performed to assess broad geochemical behavior of the identified material types and confirm the geological classification of the materials. Because these tests are inexpensive and quick, a significant amount of data can be collected quickly with minimal cost. By using the field screening to define a representative sample set, the "representativeness" of the sample set is more defensible and the number of samples selected for the more expensive static test suite can be minimized. This is in contrast to another commonly applied approach of selecting a set number of samples based on the predicted amount of waste rock, which usually results in an unnecessarily large sample set. This method also allows us to focus on materials that the initial geological work and testing indicate may be of concern, or which demonstrate an uncertain or highly variable geochemical behavior.

7.4.4 Step 4: Geochemical Test Work

Based on the geologic logging and field screening, a representative number of larger samples will be selected for standard static testing, including: multi-element analyses, acid base accounting (ABA) with sulfur speciation, Meteoric Water Mobility Procedure (MWMP), and Net Acid Generation (NAG). These static tests are intended to define the potential of a material to generate acid, buffer acid, and/or leach constituents under field conditions.

Based on the results of the field work and static testing, samples of material with an uncertain acid generation potential or leaching characteristics may be selected for kinetic testing. Because the static test work assumes that all minerals that have the potential to generate acid, buffer acid, or leach metals will react completely, they can only define the chemical/mineralogical potential of the rock and do not take into account reaction rates that will ultimately control whether the material will actually generate acid, buffer acid, or leach metals under field conditions.

The samples collected in Step 3 will be submitted to a certified laboratory for sample preparation and the first phase of static testing at Nevada certified laboratories as follows:

1. Whole rock analysis using four-acid digest and ICP analysis to determine total metal and metalloid chemistry for 48 elements (ALS Chemex Method ME-MS61).
2. ABA using the modified Sobek method (Memorandum No. 96-79) with sulfur speciation.
3. NAG test reporting final NAG pH and final NAG value after a two-stage hydrogen peroxide digest.
4. MWMP (ASTM D5744-96) with geochemical analysis of the leachate for applicable constituents.

This work will be supervised by NMCC's contractor at McClelland Laboratories of Sparks, Nevada with analysis by Western Environmental Testing Laboratory (WETLab) of Sparks, Nevada; ALS Chemex of Reno, Nevada; and SVL Laboratories of Kellogg, Idaho.

The first phase of geochemical testing will be completed to assess the range of reactivity of each of the material types and the results will be used to select samples for MWMP testing with geochemical analysis of the leachate for applicable constituents (Table 7-2). Samples demonstrating end-member reactivity, as determined from the first phase of static laboratory testing, will be selected for MWMP testing to provide a comprehensive and representative understanding of the leaching characteristics of the different material types associated with the Copper Flat deposit. It is estimated that 80 samples will be selected for static testing (Figure 7-5), of which 40 samples would be selected for MWMP testing. Mineralogical analysis will also be completed on about 20 samples to provide a better understanding of the influence geologic controls have on the geochemical behavior of the waste rock and ore.

As the additional MWMP and mineralogical data become available, they will be combined with the previous dataset to refine the preliminary geochemical predictions for each material type.

7.4.5 Step 5: Kinetic Testing Program

Based on the results of the static testing described above, any material types that exhibit uncertain or highly variable geochemical behavior will require further characterization using kinetic test methods to determine the rates and character of longer-term leaching. Based on the results of previous static testing and interpretation, representative samples will be selected for kinetic test work. Although the number of samples that will require kinetic testing will be based on the static test results, it is estimated that about 20 samples will be selected from the static test database for humidity cell testing (ASTM D-5744-96-7).

7.4.6 Step 6: Data Validation and Compilation

The geochemical data will be reviewed as it is received to ensure the quality of data and consistency in analyses. NMCC's contractor will then verify the quality of all data and confirm that no anomalies are related to laboratory

error prior to interpretation and reporting. At a minimum, NMCC's contractor will utilize their internal standard data validation procedures, although guidance from other sources may also be considered (e.g., U.S. Environmental Protection Agency). All geochemical data collected as part of the static testing program will be compiled into a single database for evaluation.

7.5 References

Bureau of Land Management (BLM), 1999, Preliminary final environmental impact statement, Copper Flat project: Las Cruces, N. Mex., U.S. Department of the Interior, 491 p. Prepared by ENSR, Fort Collins, Colo.

Dunn, P.G., 1982, Geology of the Copper Flat porphyry copper deposit, Hillsboro, Sierra County, New Mexico *in* Advances in geology of the porphyry copper deposits, southwestern North America: Tucson, Ariz., University of Arizona Press, p. 313-325.

Dunn, P., 1984, Geologic studies during the development of the Copper Flat porphyry deposit: Mining Engineering, February, 1984, pg.151.

Fowler, L.L., 1982, Brecciation, alteration, and mineralization at the Copper Flat porphyry copper deposit, Hillsboro, New Mexico: University of Arizona, Tucson, M.S. thesis, 133 p.

Harley, G.T., 1934, The geology and ore deposits of Sierra County: New Mexico Bureau of Mines and Mineral Resources, Bulletin 10, 220 p.

Hedlund, D.C., 1974, Age and structural setting of base-metal mineralization in the Hillsboro-San Lorenzo area, southwestern New Mexico *in* Siemers, C.R., Woodward, L.A., and Callender, J.F., eds., Silver Anniversary Guidebook; Ghost Ranch; North-Central New Mexico: New Mexico Geological Society Guidebook 25, p. 378–379.

Hydro Resources, Inc., 2002, Copper Flat: Albuquerque, N. Mex., Hydro Resources, Inc.

Kelley, S.A., and Chapin, C.E., 1997, Cooling histories of mountain ranges in the southern Rio Grande rift based on apatite fission-track analysis—A reconnaissance survey: New Mexico Geology, v. 19, no. 1, p. 1–14.

Locke, Augustus, 1926, The formation of certain ore bodies by mineralization stoping: Economic Geology, v.21, p. 431-453.

McLemore, V.T., Munroe, E.A., Heizler, M.T., McKee, C., 2000, Geology and evolution of the mineral deposits in the Hillsboro District, Sierra County, New Mexico *in* Geology and Ore Deposits 2000, The Great Basin and Beyond: Geological Society of Nevada, Program with abstracts, p. 63

Norman, D.I., Kyle, P.R., and Baron, C., 1989, Analysis of trace elements including rare earth elements in fluid inclusion liquids: Economic Geology, v.84, p. 162-166.

Phillips, W.J., 1973, Mechanical effects of retrograde boiling and its probable importance in the formation of some porphyry ore deposits: Institution of Mining Metallurgy Transactions, Sec. B, v. 82, p. 90-98.

Raugust, J.S., 2003, The natural defenses of Copper Flat, Sierra County, New Mexico: New Mexico Bureau of Geology and Mineral Resources Open-file report 475, Socorro, N. Mex., New Mexico Institute of Mining and Technology.

Richards, J.P., 2003, Tectono-magmatic precursors for geophysical data over a copper gold porphyry Cu-(Mo-Au) deposit formation, *in* Journal of Economic Geology, v. 96, p. 1419–1431

Seager, W.R., Shafiqullah, M., Hawley, J.W., and Marvin, R.F., 1984, New K-Ar dates from basalts and the evolution of the southern Rio Grande rift: Geological Society of America Bulletin, v. 95, p. 87–99.

SRK Consulting, 2010, NI-43-101 Preliminary Assessment, THEMAC Resources Group Limited, Copper Flat Project, Sierra County, New Mexico: Lakewood, Colo. Prepared by SRK Consulting for THEMAC Resource Group Limited, June 30, 2010.

Titley, S.R., 1982, Geologic setting of porphyry copper deposits, southeastern Arizona, *in* Titley, S.R., ed., Advances in geology of the porphyry copper deposits, pp 37-58.

Figures



STRATIGRAPHY

TERTIARY - QUATERNARY	CRETACEOUS	PALEOZOIC AND PRECAMBRIAN
Quaternary Alluvium (Qvy+Qvo)	Late Cretaceous – Silicic Intrusives (Kli)	Paleozoic Siliclastic and Carbonate Sedimentary Rocks (pC through PM)
Tertiary Volcanics (TQb+Tv)	Cretaceous Latite – Andesite Intrusives (Kql+Kd+Kis)	
Tertiary Santa Fe Group (Tsfp+Tsf)	Andesite rocks near Copper Flat (Ka)	

LEGEND

NORMAL FAULT, BALL ON DOWNTHROWN SIDE; DASHED WHERE INFERRED, DOTTED WHERE BURIED.

CONTACT

A A' CROSS SECTION LOCATION

NORTH

0 5,825 11,650

FEET

SOURCES:
(1) HARLEY (1934)
(2) SEAGER ET AL. (1982)
(3) HEDLUND (1977)
(4) ALMINAS ET AL. (1978)

(see Figure 7-2 for cross section detail)

INTERA

from BLM, 1999

Figure 7-1
Regional Surface Geology
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\7_geology\7-1_general_surface_geology.mxd 07/22/2010

A

A'



LEGEND:

QUATERNARY
- Qvy
- Qvo
- Stream Alluvium

TERTIARY
- Tsfp
- Tsfp Clay
- Palomas Formation
- Tsf – Rincon Valley Formation
- Tv – Tertiary Volcanics

CRETACEOUS
- Ka
- Kis
- Volcanics and Intrusives

PALEOZOIC
- Bedrock Carbonate and Clastic Rocks

SOURCES:
(1) HARLEY (1934)
(2) SEAGER ET AL. (1982)
(3) HEDLUND (1977)
(4) ALMINAS ET AL. (1975)

SCALE IN FEET
1500 VERTICAL 0'
6000 HORIZONTAL 0'

(see Figure 7-1 for cross section location)

from BLM, 1999

Figure 7-2
Schematic Geologic Cross Section (A-A')
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\7_geology\7-2_cross-sectionAA.mxd 07/16/2010



from BLM, 1999

Figure 7-3
Geologic Structural Features of the Region
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\7_geology\7-3_geology_hillsboro.mxd 07/16/2010



from McLemore et al., 2000; Dunn, 1982; Hedlund, 1985

Figure 7-4
Geologic Schematic of the Hillsboro Mining District, New Mexico
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\7_geology\7-4_geology_hillsboro.mxd 07/16/2010



Mine Boundary:
Tom Reynolds
Samples:
SRK, 2010
Imagery Information:
-USGS 7.5-Minutes County DOQQ
mosaic Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

Figure 7-5
Locations of
Geologic Samples

New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\7_geology\7-5_sample-locations.mxd 09/03/2010

Tables

Table 7-1
Stratigraphy of the Copper Flat Area

Age	Geologic Unit		Thickness (ft)
Cenozoic 0–65 million years ago (Ma)	Pleistocene and Holocene valley alluvium		10–70
	Pleistocene river, arroyo, and fan deposits		50–100
	Pliocene basalt flows, dikes, and plugs		50–200
	Upper Santa Fe Group fanglomerates (Palomas Formation)		300–100
	Santa Fe Group, Rincon Formation		1000–2000
	Tertiary volcanics		1000
Mesozoic 65–225 Ma	Quartz latite dikes Intermediate composition intrusive Late Cretaceous andesite dikes Late Cretaceous silicic intrusives	**Copper Flat volcanic and intrusive (mineralization associated with emplacement)**	>3000
	Sandstone		
	Mancos Shale (not exposed)		300–400
	Dakota Sandstone (not exposed)		100–200
Paleozoic 225–570 Ma	Manazano Group sedimentary rocks. Abo Sandstone, Yeso Formation shales, sandstones, and gypsum deposits, and San Andres Limestone. Not exposed west of Rio Grande at Site.		1000–2000
	Pennsylvanian carbonate rocks including Syrena, Oswaldo, and Magdalena Groups, minor conglomeratic sandstone and cherty massive limestone.		400–1000
	Devonian and Mississippian carbonate rocks (Kelly Limestone, Lake Valley Limestone, Caballero Formation) and Percha Shale.		200–500
	Ordovician Montoya Group and Fusselman Dolomite.		250–600
	Cambrian-Ordovician Bliss Sandstone and El Paso Group Limestone.		500–700
Precambrian 570–1,500 Ma	Precambrian massive granite		

Source: BLM, 1999, Tables 3-1 and 3-2

Table 7-2

Proposed Analytical Parameters with Method Reporting Limits

Parameter	Method	Method Reporting Limit
Alkalinity, CaCO3 (Acidity)	SM 2320B	1
CO3, CaCO3	SM 2320B	1
HCO3	SM 2320B	1
Aluminum	EPA 200.7	0.045
Antimony	EPA 200.8	0.0025
Arsenic	EPA 200.8	0.005
Barium	EPA 200.7	0.01
Beryllium	EPA 200.7	0.001
Bismuth	EPA 200.7	0.1
Boron	EPA 200.7	0.1
Cadmium	EPA 200.8	0.001
Calcium	EPA 200.7	0.5
Chloride	EPA 300.0	1
Chromium	EPA 200.7	0.005
Cobalt	EPA 200.7	0.01
Copper	EPA 200.8	0.05
Fluoride	EPA 300.0	0.1
Gallium	EPA 200.7	0.1
Iron	EPA 200.7	0.01
Lead	EPA 200.8	0.01
Lithium	EPA 200.7	0.1
Magnesium	EPA 200.7	0.5
Manganese	EPA 200.7	0.005
Mercury	EPA 200.8	0.0001
Molybdenum	EPA 200.7	0.01
Nickel	EPA 200.7	0.01
Nitrate as N	EPA 300.0	1
Nitrite as N	EPA 300.0	1
pH (s.u.)	SM 4500-H+ B	--

Parameter	Method	Method Reporting Limit
Phosphorus	EPA 200.7	0.5
Potassium	EPA 200.7	0.5
Scandium	EPA 200.7	0.1
Selenium	EPA 200.8	0.005
Silver	EPA 200.7	0.005
Sodium	EPA 200.7	0.5
Strontium	EPA 200.7	0.1
Sulfate	EPA 300.0	1
Thallium	EPA 200.8	0.001
Tin	EPA 200.7	0.1
Titanium	EPA 200.7	0.1
Total Dissolved Solids	SM 2540C	10
Uranium	EPA 200.8	0.002
Vanadium	EPA 200.7	0.01
Zinc	EPA 200.7	0.01

Table of Contents

8 Surface Water 8-1
8.1 Surface Water Characteristics of Site and Vicinity 8-1
8.2 Historical Data 8-2
8.3 Sampling Objectives 8-3
8.4 Sampling Frequency 8-3
8.5 List of Data to Be Collected 8-4
8.6 Methods of Collection 8-4
8.6.1 Surface Water Samples from Springs and Drainages 8-4
8.6.2 Pit Lake Sampling 8-7
8.7 Parameters to Be Analyzed 8-8
8.8 Maps Showing Proposed Sampling Locations 8-8
8.9 Laboratory and Field Quality Assurance Plans 8-9
8.10 Discussion in Support of Proposal 8-9
8.11 References 8-9

List of Figures

Figure 8-1 Proposed Surface Water Sampling Locations
Figure 8-2 Proposed Parallel Profiles for Pit Lake Survey

List of Tables

Table 8-1 Historical Flow and Water Quality Parameters
Table 8-2 Proposed Surface Water Monitoring Locations (as shown on Figure 8-1) with Method of Measurement and Frequency of Collection
Table 8-3 Surface Water Resources Data Needs
Table 8-4 Analytical Parameters and Analysis Methods for Surface Water and Sediment Samples

8 Surface Water

The Copper Flat area falls within the Lower Rio Grande watershed, as defined by the New Mexico Water Quality Control Commission (WQCC). This watershed includes approximately 5,000 square miles in Catron, Socorro, Sierra, and Doña Ana Counties and is dominated by the Rio Grande and its tributaries as well as the two large reservoirs of Elephant Butte and Caballo. Numerous ephemeral tributaries feed into the Rio Grande from the west, but none contribute perennial flow to the Rio Grande.

Subsection 8.1 provides background information about surface water resources in the vicinity of the Copper Flat Mine Permit Area (Site), and Subsection 8.2 summarizes resources for pertinent historical data related to surface water sampling. The rest of this section focuses on the proposed sampling plan for surface water at the Site. Surface water baseline studies have been completed in the project area since the 1960s, and relevant information and data are referenced in subsequent sub-sections throughout Section 8.

8.1 Surface Water Characteristics of Site and Vicinity

The Site is drained by ephemeral streams (arroyos) within the Greenhorn Arroyo drainage basin, a 6th level sub-watershed defined by the Hydrologic Unit classification system (Seaber et al., 1987) that drains 29,414 acres of land on the eastern slope of the Animas Uplift to a single outlet into the Rio Grande (Figure 8-1). Flows within the Greenhorn Arroyo drainage basin are ephemeral, as they only occur in direct response to precipitation. As a result, this drainage, similar to others in the region, does not contribute any perennial surface water flow to the Rio Grande.

Numerous arroyos contribute to the trunk channel of Greenhorn Arroyo. Of these, Grayback Arroyo is the primary drainage through the Site. Grayback Arroyo originates west of the Site and drains eastward along the Site axis until it converges with the trunk channel of Greenhorn Arroyo approximately 8 miles east of the Site boundary (Figure 8-1). In pre-mining times, Grayback Arroyo drained directly through the mine area, but was later re-routed around the southern perimeter of the mine area for flood control purposes (Raugust, 2003). Newcomer and Finch (1993) measured flow rates in Grayback Arroyo of 12.5 gallons per minute (gpm) in March 1993 at a point east of the pit and former plant site. Three seeps have been identified along Grayback Arroyo (BLM, 1999). One seep with riparian vegetation is located near a buried storm water collection pond, a second is located downstream from the first seep and supports a small cottonwood/willow stand, and the third is south of the operations area (Figure 8-1).

Two creeks drain basins directly to the north and south of the Greenhorn Arroyo drainage basin: Las Animas Creek in the north and Percha Creek to the south (Figure 8-1). Both Las Animas and Percha Creeks have ephemeral, intermittent, and perennial reaches. Streamflow in Las Animas Creek varies from perennial to intermittent from the area near sampling site MAS (Figure 8-1) to Caballo Reservoir (BLM, 1999). For example, Davie and Spiegel (1967) show flow rates ranging from about 450 to 900 gpm in the upper reach (T14S R7W, Sections 34 through 36, near sampling sites LAC-A and LAC-B in Figure 8-1) and middle reach (within T15S R5W) of the creek; according to Davie and Spiegel, these reaches are “losing reaches” of the creek. Streamflow in Percha Creek is intermittent in the Hillsboro reach and perennial in the area known as the Percha Box, a steep-walled reach of the drainage that has incised into Paleozoic bedrock (BLM, 1996) (Figure 8-1). SRK (1995) reported measurable streamflows just east of the Percha Box of roughly 200 to 250 gpm. This was the only reach of Percha Creek with measurable flows during the SRK sampling period. Though both Las Animas Creek and Percha Creek have perennial reaches, neither creek contributes perennial flow to the Lower Rio Grande Basin.

Two springs are located within the Greenhorn Arroyo drainage basin to the north and west of the Site (Figure 8-1). Other unnamed seeps occur in the pit walls surrounding the pit lake after precipitation events;

these are likely the result of fractured flow through the bedrock exposed in the pit wall. Several springs in the Percha Creek basin and one in the Las Animas Creek basin have been identified for sampling, but have been studied less than those within the Greenhorn Arroyo basin. As a result, there is little information on their flow rates or quality, although Newcomer and Finch (1993) did attempt to measure flow.

The open pit that was mined during the early 1980s now contains a lake. Since 1989, the pit lake has been sampled for water quality approximately 65 times at various locations and depths, including samples collected by past operators of the mine, state regulatory agencies, and academic researchers studying the mine (BLM, 1999). For the proposed operations, the New Mexico Copper Corporation (NMCC) would consume the pit lake waters for mine operations and dust suppression. If necessary, pit water could be temporarily stored in a reservoir in the plant area (SRK, 2010a).

Mine water from milling operations would be discharged into an evaporation pond or re-used for several purposes: (1) plant processing streams, (2) the tailings facility with pump-back to the plant, and/or (3) dust control (SRK, 2010a). Both a National Pollution Discharge Elimination System permit and a New Mexico Environment Department (NMED) groundwater discharge permit are required for NMCC to discharge mine water. In preparation for both permits, NMCC will characterize the water quality of the mine discharge through scheduled gauging and sampling of discharge. In addition, NMCC will design a storm water management system to manage discharge for the proposed facilities. Mine water discharge is not expected to reach the Lower Rio Grande or any lake, spring, reservoir, riparian, or wetland areas.

8.2 Historical Data

Existing surface water data relevant to the NMCC sampling plan are discussed in this section and are summarized in Table 8-1. Surface water at the Site was most recently investigated by ABC (1996), who collected flow and water quality from Percha Creek and Las Animas Creek. Newcomer et al. (1993) performed a hydrologic assessment of the Greenhorn Arroyo drainage basin, measuring flow and water quality along Grayback Arroyo and at a number of seeps and springs. The oldest known surface water investigation at the Site was performed by Davie and Spiegel (1967), who collected flow data for Las Animas Creek. In addition, the surface water chemistry of Grayback Arroyo was initially investigated in 1977 at three locations as part of an environmental assessment prepared by the BLM in response to an application by Quintana Minerals Corporation for an open pit copper mine at the Site (BLM, 1978). The three locations sampled in 1977 generally correspond to the sampling locations proposed in Figure 8-1, with one location upstream of the permit boundary, one within the Site approximately 300 yards from the mine rim, and a third located where the arroyo leaves the Site (BLM, 1978). Water samples were collected in January, March, and July of 1977. Results of these investigations were compiled by Raugust (2003) and are also summarized in the Bureau of Land Management's (BLM) preliminary final environmental impact statement (PFEIS) for Copper Flat (1999).

Spring and seep flow rates are infrequently reported in the available literature for the Site and surrounding areas. Several springs and seeps have been identified within the Greenhorn Arroyo drainage basin. Two springs, identified as BG and BG-2, are located to the north and west of the Site (Figure 8-1) and several unnamed seeps occur in the walls surrounding the pit lake. BG and BG-2 were judged by Newcomer et al. (1993) to be ephemeral. The seeps along the pit walls are observed to flow in response to precipitation events, and, as mentioned above, are likely the result of fractured flow through the bedrock exposed in the pit wall. All known springs and seeps in the Greenhorn Arroyo drainage basin are upgradient of the proposed mine water discharge location. Other seeps and springs shown in Figure 8-1 have not been measured in the past and thus have no associated historical flow information.

The 12.8-acre lake that has formed in the existing pit (Figure 8-2) is estimated to be about 40 ft deep, based on a pit bottom elevation of 5,380 ft above mean sea level (amsl) and water level elevation of 5,420 ft amsl as measured in 1986 (SRK, 2010b). The water quality of the pit lake has been sampled over 65 times at various depths and locations since the initial samples were collected on April 13, 1989, by the New Mexico Environment Improvement Board (Raugust, 2003); the latest samples were collected in January 2010. Raugust (2003) concluded that the collective data show several trends in the variability of water quality over time, mainly that evapoconcentration and buffering processes are influencing the quality of the lake water. Pit water has historically exceeded the WQCC standards for sulfate, chloride, TDS, manganese, and uranium (20.6.2.4103 of the New Mexico Administrative Code) and has, at times, dropped below the acceptable pH range of 6 to 9.

Other key studies that discuss the water quality are summarized in SRK (1997) and include hydrogeologic and hydrogeochemical studies (SRK, 1995), post-closure pit water balance model calculations (SRK, 1997), water quality and host-rock geochemical studies (SRK, 1997), and post-hearing submittals that followed the 1997 New Mexico Mine Permit public hearing.

Evaluating these existing historical data is essential to completing a comprehensive Baseline Characterization Report. The statistical analysis method proposed to evaluate these historical volumetric flow and water quality data as baseline characterization data is discussed in detail in Section 9.1.5 of the SAP (see Section 9 – Groundwater). This statistical analysis will be used to justify the use of historical data, per the New Mexico Energy, Minerals and Natural Resources Department (EMNRD) Mining and Minerals Division (MMD) draft Guidance Document for Part 6 New Mining Operations Permitting under the New Mexico Mining Act (MMD Guidance Document). Additionally, statistical analysis will be used to determine if the current baseline data are significantly different from existing baseline data where temporal data are available for the monitoring wells.

8.3 Sampling Objectives

The objective of sampling surface water is to characterize the volumetric flow and water quality of seeps, springs, streams, and the pit lake. Table 8-2 lists the frequency, location, and method for the proposed sampling program.

This information will be used for the following purposes:

1. Develop the discharge plan application for water produced during dewatering.
2. Further describe the seasonal variations in surface water quantity and quality in the vicinity of the Site.
3. Determine the likely impacts on the hydrologic regime, such as the quality and quantity of surface water systems in the vicinity, including dissolved and suspended solids under seasonal conditions.

Sources that could affect surface water quality include the disposal of mill tailings, acid rock drainage from mine stock piles, and erosion associated with reduced land cover and increased land disturbance. Dewatering activities associated with the pit as well as groundwater development for mine operations could affect surface water quantity. This plan outlines how, when, and where data will be collected to characterize baseline conditions in support of mitigating impacts to surface water quality and quantity.

8.4 Sampling Frequency

Perennial streams, springs, and the pit lake will be sampled four times over a 12-month period. Ephemeral or intermittent streams, springs and seeps will be sampled during opportunistic sampling events after precipitation events. The frequency of samples by location is presented in Table 8-2.

8.5 List of Data to Be Collected

A variety of data needs are associated with surface water. These needs are provided in Table 8-3 along with a plan for how each need will be addressed through this sampling and analysis plan.

8.6 Methods of Collection

In general, the methods used to collect surface water samples will follow the standard operating procedures defined by the NMED Surface Water Quality Bureau (SWQB) (2007) for streamflow measurement and water quality sampling, as described below. Methods deviate from NMED standard operating procedures for sampling volumetric flow and water quality from springs and seeps and water quality and sediment in the pit lake, as described in Section 8.6.2.

8.6.1 Surface Water Samples from Springs and Drainages

8.6.1.1 Volumetric Flow Measurements

Streams. Streamflow measurements will be made using classical techniques for open-channel flow. For reaches with perennial flow (Table 8-2), volumetric flow will be measured using a flow meter such as the Marsh-McBirney Flo-Mate™ 2000, which is designed for characterizing open-channel flow; a top-setting wading rod; and a tape measure or tagline. Assembly, calibration, and operation of the flow meter will follow the procedures described in NMED SWQB (2007). At each stream location listed in Table 8-2 that does not have an auto-sampler installed, a sampling station will be established by identifying (as close to the designated location as possible) a straight reach of the stream where the streambed is uniform and relatively free boulders and aquatic vegetation. The width of the stream will be measured using a tape measure, then subdivided so that each stream section between vertical profiles will contain no more than 10% of discharge (e.g., if the stream is <5-ft wide, vertical profiles would be 0.5 ft apart). Following procedures in NMED SWQB (2007), if the stream depth is greater than 2.5 ft, stream velocity will be measured at 20 percent, 60 percent, and 80 percent of the total depth of the stream at each profile location along the cross-section. If stream depth is more than 0.15 ft but less than 2.5 ft, the velocity measurement will be taken at a depth that is equal to 60 percent of the total depth when measured from the surface of the water (NMED SWQB, 2007). Following the same NMED SWQB procedures, if the stream is less than 0.15 ft deep, flow will be measured using the equation $0.9 \times Umax$, where $Umax$ is the maximum velocity recorded throughout the entire flow (Marsh-McBirney, 1990). Once measurements have been recorded, flow will be calculated in the field and recorded in the field book.

Given the unpredictable nature of flow in intermittent and ephemeral reaches of streams, streamflow in many of these locations will be recorded using deployed, portable, automatic sampling devices (auto-samplers). An auto-sampler, such as the Global Water FSS Flow Sampling System (or similar), will be installed to collect streamflow during periods in which there is measurable flow. A datalogger will record flow measurements in the unit's random access memory (RAM) and will be available for download onto a laptop computer following the storm event. Five auto-samplers will be installed within and in the vicinity of the Site, three within Greyback Arroyo, one in Percha Creek, and one in Las Animas Creek, as listed in Table 8-2 and shown in Figure 8-1.

Sites were selected for flow measurement following methods presented in NMED SWQB (2010). Established monitoring stations with historical data on each watershed were selected to examine trends in water flow. These include stream sampling stations listed in Table 8-2. Grayback Arroyo SWQ-1, SWQ-2, and SWQ-3 all have historical measurements for streamflow, but the data are sparse because auto-samplers were not installed and measurements were made by hand. These stations, however, are well positioned for the purposes of characterizing upstream, on-site, and downstream conditions because Site SWQ-1 is located upstream of the

Site, SWQ-2 is located within the Site, and SWQ-3 is located downstream of the portion of the Site that has been most disturbed by mining activities and still exhibits ephemeral flow. SWQ-1 is proposed as a reference site, as the water quality at this location has received the least amount of impact from past mining activities and the geology, gradient, and precipitation characteristics of SWQ-1 are similar to the sampling locations within and downstream of the Site, which have been more impacted by past mining operations and are likely to be more affected by the proposed NMCC mining operation. The selection of locations for the installation of auto-samplers in Percha and Las Animas Creeks was based on the criteria for site selection defined in NMED SWQB (2010), and reflects the fact that past measurements at these locations demonstrates that flow has occurred historically within the given reach.

Springs and Seeps. Volumetric flow from springs and seeps can be measured with a portable V-notch weir box or adjustable flume, if sufficient flow exists and channel conditions are appropriate. The V-notch weir box operates under the principle that discharge is related to the height of the water above the bottom of the V-shaped notch; the shape ensures that a small change in the discharge will effect a large change in the height of the water. Flow can be calculated from measurement methods defined for V-notch weirs by the U.S. Bureau of Reclamation (USBR, 2001).

If flows are insufficient for the use of a flume or V-notch weir (e.g., <0.1 cfs [44.8 gpm]), volumetric flow will be estimated using the "timed fill" method, as described by NMED SWQB (2007). This method uses a stopwatch to measure the time it takes to fill a 5-gallon bucket by diverting the entire flow of the spring or seep into the bucket below a weir or waterfall (NMED SWQB, 2007). To calculate flow using this procedure, 5 gallons per unit time may be converted to cfs using the following equation:

$$5 \text{ g} = 0.6684 \text{ ft}^3, \text{ thus } 440.6684/\text{elapsed time (seconds)} = \text{cfs}$$

8.6.1.2 Water Quality Sampling

Streams. Individual samples collected over a period of 15 minutes or less (i.e., grab samples) will be collected by the auto-samplers installed in Grayback Arroyo, Percha Creek, and Las Animas Creek at the locations listed in Table 8-2. Each sample will represent water quality conditions at the time the sample was collected. The auto-sampler consists of a 2.5-gallon polyethylene sample bottle, a peristaltic sampling pump, a pickup hose, a circuit board controller, a rechargeable gel cell battery, and a battery charger. With the exception of the pickup hose, the components are housed in a waterproof case mounted aboveground next to the sampling location, which is outside of the ordinary high water mark of channel.

Once the sample is collected, a radio unit in the sampler will communicate to a receiver installed in the meteorological tower (see Section 2), which will in turn notify the NMCC surface water lead via telemetry that a surface water sample has been collected. The sample will be retrieved by on-site mine staff, placed in a laboratory-provided sample container, and shipped overnight to the designated laboratory for analysis. All equipment preparation and cleaning, sample collection, and sample preservation will follow the standard operating procedures defined by NMED (NMED SWQB, 2007).

Springs and Seeps. During quarterly measurements of flow from seeps and springs, water quality samples will be collected using non-isokinetic, open-mouth samplers following U.S. Geological Survey protocols for sample equipment selection described in Lane et al. (2003). Methods will follow the 2007 NMED/SWQB Standard Operating Procedures for Data Collection, §7.3 Routine Water Chemistry Sampling.

Samples will be collected in clean polyethylene Cubitainer® containers. Where water flows at sufficient depth, samples will be collected by immersing the container by hand or by rod beneath the surface. Otherwise, water will be collected in a plastic bucket or disposable bailer held with nylon rope or twine, if necessary. Care will be taken to avoid contamination with debris from the rope or twine and the sampling area. Buckets and bailers will

be rinsed three times with source water and sampling personnel will rinse their hands with source water before collecting samples. Samples will be collected immediately following rinsing. Buckets will be rinsed with spring water following use and cleaned with Liquinox and warm water prior to the next use.

Water will be transferred from the collection vessel to the sample container with a peristaltic pump or syringe, filtering as appropriate. Dissolved concentration samples will be filtered; total concentration samples will not be filtered. All samples for dissolved constituent analytes will be filtered with a 0.45-micron pore-size disposable in-line filter cartridge. Filters will be rinsed with sample water according to the manufacturer's recommendations prior to sampling.

Every effort will be made to take sonde readings in flowing water. When this is not possible, sonde readings will be made from the bucket or bailer after the sample has been collected and a note to this effect will be made on the field sheet.

8.6.1.3 Sediment Sampling in Streams

Sediment samples will be collected at each of the surface water sampling locations identified in Table 8-2. Sample collection methodology will depend on sample location. Field personnel will visit the locations and determine the best approach for ensuring collection of samples based on field reconnaissance. The objective in selecting a sample site is to obtain recently deposited fine sediment. Depositional zones include areas on the inside bend of a stream; areas downstream from obstacles such as boulders, islands, or sand bars; or simply shallow waters near the shore. Where possible, fine-grained surficial sediments will be obtained from several depositional zones that represent various flow regimes within a stream reach, and will be composited to yield a sample representing average conditions. However, depositional zones on small, ephemeral drainages may be limited in size, necessitating that a single zone be regarded as representative.

Samples will be collected following NMED SWQB Standard Operating Procedures for Data Collection (NMED SWQB, 2007), as follows:

1. Samples will be collected in a plastic or Nalgene® jar.
2. The sample will be composited from several representative depositional zones into an appropriate mixing container after decanting any excess water over the back of the scoop.
3. The sample will be mixed well.
4. An aliquot of the mixed material will be transferred to the final, labeled sample container (a 4-ounce, wide-mouthed glass jar) and placed on ice for transport to the analytical facility. If shipment cannot be accomplished in a timely manner, the sample will be frozen prior to shipment. (Sediment samples are not preserved.)

If water and sediment samples are to be collected at the same location, water samples will be collected (1) before collecting sediment samples, as sampling sediment will disturb the stream, and (2) downstream of sediment samples, as water sampling may disturb representative depositional zones. Personnel collecting samples will employ proper sample handling techniques, including wearing latex or nitrile gloves, avoiding hand contact with contaminating surfaces, and minimizing the number of sample handling steps. Sample containers will be covered while being moved to minimize the atmospheric input. All sample collection equipment will be rinsed as soon as possible after use and thoroughly rinsed with ambient water at each new sampling station before collecting a sample. Equipment used will be inert with respect to the analytes to be collected.

8.6.2 Pit Lake Sampling

8.6.2.1 Water Sampling

Lake water from a sampling station located at the deepest point in the lake will be sampled four times within a 12-month period, with one set of samples collected during each season. Only one sampling station is proposed, as the size of the lake is less than 100 acres, which is typically the threshold for establishing additional sampling stations (see Section 2.0 of NMED SWQB, 2010). The deepest point of the lake will be identified by surveying the lake bathymetry along predetermined parallel depth profiles. These parallel profiles will be spaced to provide adequate coverage with the addition of two tie lines perpendicular to the profiles to ensure consistency in the interpretation of water depth between each profile. Given the size of the pit lake, 5 profiles and 2 tie lines are proposed, as shown in Figure 8-2. The depth along each profile will be measured using a portable acoustic transducer tethered to the side of the boat 2 inches below the water surface. Each predetermined profile will be pre-loaded into a global positioning system (GPS) with horizontal accuracy of ±3 meters (9.8 ft) to ensure that depth measurements follow the proposed profile lines in the field.

During each of the four quarterly sampling events, vertical profiles of temperature, pH, oxygen/reduction potential, dissolved oxygen, and conductivity will be measured at a resolution of up to every 12 inches. These profiles will be used to define seasonal trends in the water column and the discrete depths at which surface water quality samples should be collected.

Based on the results from the vertical profile, a surface water sample will be collected from up to three depths at the deepest point within the lake. These three samples, taken quarterly, are needed to determine whether the lake is either thermally or chemically stratified and to support geochemical modeling of the pit lake system. If the vertical temperature profile shows that no thermocline present in the lake (i.e., there is less than 1^{o}C difference between the temperature of the surface and bottom of the lake), then three water-quality samples will be collected from within the euphotic zone. The euphotic zone is defined as the depth of light extinction, which will be measured by lowering a secchi disk into the water and measuring the depth below water at which the disk is no longer visible through a secchi disk viewer. Following the NMED SWQB (2007) procedures for sampling lakes, 5-liter samples from the top, middle, and bottom of the euphotic zone will be collected for the water quality analyses listed in Table 8-4; a rinsed Kemmerer® water bottle will be used for sample collection. The 5-liter samples will be composited in a 5-gallon, acid-washed container. If a thermocline is present (i.e., if there is greater than 1°C difference between the surface and bottom temperatures of the lake), 5-liter samples will be taken from the top, middle, and bottom of the entire water column instead of just the euphotic zone. The 5-liter samples will then be composited in a 5-gallon, acid-washed container.

Each 5-liter water-quality sample will be collected using a Wildco® discrete-depth sampler that is capable of collecting a continuous column of water from a desired depth. A 5-gallon Cubitainer® will be filled with water from each of the three samples to create a composited sample. Following NMED SWQB (2007) sampling protocols for lakes, all water quality samples will be poured off from the composited sample into their respective containers, which will be either individually rinsed, 1-liter Cubitainers® or other containers as prescribed by the analysis to be performed. Dissolved nutrient and metal samples will be filtered prior to being poured into individually rinsed, 1-liter Cubitainers®. After the composited sample is divided into individual containers, the samples for total and dissolved nutrients will be preserved in the field with 2 milliliters (ml) of concentrated sulfuric acid per liter of sample water (to reduce pH to < 2). Samples for total and dissolved metal analyses are preserved with 5 ml of concentrated nitric acid per liter of sample water (to reduce pH to <2). Samples for cyanide are preserved with 8 to 10 tablets of NaOH per liter of sample water (to increase pH to >12).

8.6.2.2 Sediment Sampling

A core of recently deposited fine-grained sediment will be collected from the lake during the first sampling event using a Glew Corer (Glew, 1988; Glew et al., 2001), a gravity-driven coring device composed of cylindrical aluminum alloy and a Teflon body with a nominal diameter of 2.8 inches. The upper part (core body) houses the closing piston, release mechanism, and captive float. The float relays the motion of the messenger to the trigger and gives the corer vertical stability in the water. The core body caries a sleeve and clamping device that secures a 2.5-inch diameter Lexan-core tube capable of collecting up to 24 inches of undisturbed sediment. The Glew Corer is specially designed to collect undisturbed samples from the sediment-water interface where the bed material is loosely consolidated. In contrast to other sediment sampling devices, the flow of water through the Glew Corer is not impeded because the design of the coring device allows water to pass freely through the device with little resistance. As a result, the Glew Corer eliminates the hydraulic pressure that normally forms ahead of other devices. This hydraulic pressure can cause the top sediment to blow out when the device is lowered to the sediment-water interface, which results in sample loss even before the sample is collected by the device.

The sediment sample will be collected from a boat held in position over the deepest point in the lake by at least three anchors. The corer will be assembled and tested according to Glew et al. (2001). First, the messenger weight and Lexan core tube will be attached to the line and core body, respectively. The core tube will be attached flush with the core body to ensure there is a tight seal. Once assembled, the corer will be lowered slowly from the side of the boat approximately 1 to 2 ft above the sediment-water interface. Holding the messenger weight in one hand, the corer will penetrate the sediment by letting the rope slide through the other hand. Once the corer has penetrated the sediment, the messenger weight will be dropped to trigger the closing piston. The corer will then be lifted by hand to a level where the bottom of the core tube remains just the water surface. A rubber stopper will be inserted by a gloved hand into the bottom of the core tube before the core tube is lifted above the water surface.

Once the corer is on the boat, the piston sealer will be lifted from the core body and the tube removed by unscrewing the band clamp that holds the core tube onto the corer. Holding the core tube upright, the core body will be detached from the tube and capped immediately before bringing the core back to shore. On shore, core samples will be extruded from core tubes into sampling jars in the field using an extruding device specifically designed for the Glew Corer (see Glew, 1988 and Glew et al., 2001). The extruding device will push the sediment through the top of the core tube and into sampling jars provided by the laboratory. The sample extruded from the core tube will be homogenized and then sub-sampled into a container submitted to a laboratory for analysis for the parameters listed in Table 8-4. The sediment sample will be collected only after the required water sample has been collected to avoid disturbing or suspending sediment that would contaminate the surface water sample.

8.7 Parameters to Be Analyzed

During the year of sampling, 12 water quality samples from the pit lake (1 sample site x 3 sample depths x 4 quarterly sampling events) will be collected. The samples will be analyzed for the suite of parameters and methods provided in Table 8-4. Additionally, it is assumed that the streams, seeps, and springs listed in Table 8-2 will be analyzed for the same suite of parameters.

8.8 Maps Showing Proposed Sampling Locations

Locations for proposed sampling locations for streams and springs are shown in Figure 8-1. These locations were selected by NMCC because they were sampled in the past (e.g., SWQ series in Grayback Arroyo, PC series in

Percha Creek, and select sites within the LAC series along Las Animas Creek) or represent an area of interest where volumetric flow or water quality data would be of importance to understanding regional characteristics of surface water quality and quantity. The water quality and sediment samples collected from the deepest point in the lake will be based on the results of the depth profiles shown in Figure 8-2.

8.9 Laboratory and Field Quality Assurance Plans

Data collected to characterize the water quality and flow of surface water resources discussed in this section of the Sampling and Analysis Plan will conform to the NMCC Quality Assurance Project Plan (Attachment 1) with respect to field methods, sampling procedures, and recording of field notes. If procedures for sampling or analysis are not specifically defined in Attachment 1, by the sampling method, or by the analytical method, the NMED SWQB (2007) protocols for field data sampling, equipment calibration and cleaning, sample containment and handling, and photographic documentation will be followed as appropriate and/or applicable to the site conditions.

The samples for chemical analysis will be properly preserved and field filtered, if necessary, before shipment to an analytical laboratory certified by the U.S. Environmental Protection Agency. All samples will be shipped within the holding times defined by the analytical method to be used. In addition, containers specific to a given analytical method will be used as appropriate. To provide quality control, duplicates and/or equipment blanks will be collected/used. Analytical results will be stored in a project database that will be provided to the New Mexico Mining and Minerals Division electronically as well as in hard-copy as an attachment to the Baseline Summary Report.

8.10 Discussion in Support of Proposal

The existing water quality and flow data for surface water within and in the vicinity of the Site will be bolstered by the new data collected as outlined in this section of the Sampling and Analysis Plan. New data will establish baseline conditions in that they will represent the nature of flow and quality of surface water and sediment prior to any operations or activities by NMCC. These data will also help guide future planning and designing decisions with regard to mine water discharge.

8.11 References

Adrian Brown Consultants (ABC), 1996, Appendix F of Copper Flat project hydrology impact evaluation report.

——— 1997, Copper Flat hydrology impact evaluation post-hearing submittal exhibits, including revised appendices O, F, and L: Report 1356A.970326.

Bureau of Land Management (BLM), 1978, Environmental assessment record on Quintana Minerals Corporation's proposed open pit copper mine at Copper Flat, Sierra County, New Mexico: Las Cruces, N. Mex., 170 p.

——— 1996, Draft environmental impact statement (DEIS), Copper Flat Project: Las Cruces, N. Mex., U.S. Department of the Interior. Prepared by ENSR, Fort Collins, Colo.

——— 1999, Preliminary final environmental impact statement, Copper Flat project: Las Cruces, N. Mex., U.S. Department of the Interior, 491 p. Prepared by ENSR, Fort Collins, Colo.

Davie, W., Jr., and Spiegel, Z., 1967, Las Animas Creek hydrographic survey report, geology and water resources of Las Animas Creek and vicinity, Sierra County, New Mexico: New Mexico State Engineering Report.

Glew, J.R., 1988, A portable extruding device for close interval sectioning of unconsolidated core samples: Journal of Paleolimnology, v. 1, p. 235-139.

Glew, J.R., Smol, J.P. and Last, W.M., 2001, Sediment core collection and extrusion, *in*: Last, W.M. and Smol, J.P., eds., Tracking environmental change using lake sediments, Vol 1: Basin analysis, coring, and chronological techniques: Dordrecht, Kluwer Academic Publishers, p. 73-105.

Lane, S.L., Flanagan, S., and Wilde, F.D., 2003, Selection of equipment for water sampling (ver. 2.0): U.S. Geological Survey Techniques of Water-Resources Investigations, book 9, chap. A2, accessed July 2010 [http://pubs.water.usgs.gov/twri9A2/].

Marsh-McBirney, 1990, Flo-Mate™ 2000 portable flowmeter instruction manual.

Newcomer, R.W., and Finch, S.T., 1993, Water quality and impacts of proposed mine and mill, Copper Flat Mine site, Sierra County, New Mexico, 30 p. Prepared for Gold Express Corporation.

Newcomer, R. W. Jr., Shomaker, J.W., and Finch, S.T., Jr., 1993, Hydrologic assessment, Copper Flat project, Sierra County, New Mexico. Prepared for Gold Express Corporation.

New Mexico Environment Department Groundwater Quality Bureau (NMED GWQB), 2008, Letter to Mr. George Lotspeich regarding Abatement plan required at Copper Flat Mine site, DP-1, August 20, 2 p.

NMED Surface Water Quality Bureau (NMED SWQB), 2007, The 2007 NMED/SWQB standard operating procedures for data collection, July 26, 186 p.

——— 2010, Quality assurance project plan for water quality management, revision 0, April, 80 p.

Raugust, J.S., 2003, The natural defenses of Copper Flat, Sierra County, New Mexico: New Mexico Bureau of Geology and Mineral Resources Open-File report 475, Socorro, N. Mex., New Mexico Institute of Mining and Technology.

Steffen Robertson and Kirsten (U.S.), Inc. (SRK), 1995, Copper Flat Mine hydrogeological studies. Copper Flat, New Mexico: Steffen Robertson and Kirsten, Inc.

——— 1997, Copper Flat Mine compilation of pit lake studies, prepared by SRK for Alta Gold Co., October 1997, 76 p.

———2010a, Preliminary draft Copper Flat plan of operations, New Mexico Copper Corporation: SRK Consulting, Reno, Nevada.

——— 2010b, NI-43-101 Preliminary assessment, THEMAC Resources Group Limited, Copper Flat project, Sierra County, New Mexico: Lakewood, Colo. Prepared by SRK Consulting for THEMAC Resource Group Limited, June 30, 2010.

Seaber, P.R., Kapinos, F.P., and Knapp, G.L., 1987, Hydrologic unit maps: U.S. Geological Survey Water-Supply Paper 2294, 63 p.

U.S. Bureau of Reclamation (USBR), 2001, Weirs, Chapter 7 *in* Water measurement manual, a water resources technical publication (3d ed.): U.S. Department of the Interior, Bureau of Reclamation, 2001 revised reprint edition, variously paged.

Wilson, C.A., Orr, C.A., White, R.R., and Roybal, R.G., 1981, Water resources of the Rincon and Mesilla valleys and adjacent areas: New Mexico State Engineering Report No. 43.

Figures



N
W E
S

Watersheds:
USGS Hydrologic Unit Map
Mine Boundary:
Tom Van Bebber
Imagery Information:
-USGS 7.5-Minutes County DOQQ mosaic
Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

0 3,500 7,000 14,000 21,000
Feet

Legend

- Stream Sample
- Spring Sample
- Proposed Mine Permit Boundary

Watersheds
- Caballo
- El Paso-Las Cruces
- Sub-Watershed

Figure 8-1
Proposed Surface Water Sampling Locations
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\8-SurfaceWater\8-1_surface_wtr_locations.mxd 08/31/2010

0 50 100 200

Feet

Imagery Information:
-USGS 7.5-Minutes County DOQQ mosaic
Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

Legend

Profile Line

Figure 8-2
Proposed Parallel Profiles for Pit Lake Survey

New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\9_groundwater\9-1_LRG_basins.mxd 07/30/2010

Tables

Table 8-1
Historical Flow and Water Quality Parameters

Location	Date	Description	Flow (cfs)	pH	Conductivity (µS/cm)	Temperature (°C)
Las Animas Creek	1967	Upper Reach	1.0 – 2.0	NM	NM	NM
Las Animas Creek	1967	Middle Reach	1.0 – 1.5	NM	NM	NM
Las Animas Creek	1996	LAC-E	0.546	8.2	400	17
Percha Box	1996	1200’ u/s of Box entry	Dry	NA	NA	NA
Percha Box	1996	700’ u/s of Box entry	0	8.1	600	32
Percha Box	1996	400’ u/s of Box entry	Dry	NA	NA	NA
Percha Box	1996	Box entry	0.265	7.7	500	23
Percha Box	1996	1500’ d/s of Box entry	0.446	8.2	500	23
Percha Box	1996	Box exit	1.02	8.4	400	25
Percha Box	1996	2400’ d/s of Box exit	0	9.3	400	32
Percha Box	1996	2500’ d/s of Box exit	Dry	NA	NA	NA
Percha Box	1996	5000’ d/s of Box exit	0.394	9.0	400	28
Percha Box	1996	5400’ d/s of Box exit	0	9.0	400	32
Percha Box	1996	5500’ d/s of Box exit	Dry	NA	NA	NA
Percha Box	1996	3 miles d/s of Box exit	Dry	NA	NA	NA
Percha Box	1996	5 miles d/s of Box exit	Dry	NA	NA	NA
Grayback Arroyo	4/1/93	SWQ-1	1 – 2	8.3	1150	NM
Grayback Arroyo	5/7/93	SWQ-1	Dry	NA	NA	NA
Grayback Arroyo	3/31/93	SWQ-2	< 1	7.7	3150	NM
Grayback Arroyo	3/31/93	SWQ-3	12.5	8.1	3330	NM
Spring/Seep	4/1/93	BG	1 – 2	8.2	1090	NM
Spring/Seep	5/7/93	BG	Dry	NA	NA	NA
Spring/Seep	4/1/93	BG-2	< 1	8.2	1030	NM
Spring/Seep	5/7/93	BG-2	< 1	NM	NM	NM
Spring/Seep	1997	PW-2	NM	8.16	NM	NM
Spring/Seep	1967	WS	0.8	NM	NM	81.5
Spring/Seep	4/2/93	WS	0.00735	8.5	1980	NM

Notes:

Box = Percha Box
u/s = upstream
d/s = downstream
NA = no water present for sampling
NM = parameter not measured or not available

Table 8-2

Proposed Surface Water Monitoring Locations (shown on Figure 8-1) with Method of Measurement and Frequency of Collection

Sample Location	Location Type	Likely Flow Type	Description of Location	Quarterly or Opportunistic Flow Measurement	Method of Collection	Quarterly Water Quality Sample
LAC-A	Stream	Perennial	Las Animas Creek u/s of North Warm Spring (NWS)	Quarterly	Flow meter	
LAC-B	Stream	Perennial	Las Animas Creek d/s of North Warm Spring	Quarterly	Flow meter	
LAC-C	Stream	Intermittent	Las Animas Creek d/s of Meyers Animas Spring (MAS)	Opportunistic	Auto sampler	X
LAC-D	Stream	Intermittent	Las Animas Creek at site previously named STA8	Quarterly	Flow meter	
LAC-E	Stream	Intermittent	Las Animas Creek at site previously named LAC-1	Quarterly	Flow meter	
SWQ-1	Stream	Ephemeral	Grayback Arroyo at site previously named GA-A	Opportunistic	Auto sampler	X
SWQ-2	Stream	Ephemeral	Grayback Arroyo at site previously named GA-B	Opportunistic	Auto sampler	X
SWQ-3	Stream	Ephemeral	Grayback Arroyo at site previously named GA-C	Opportunistic	Auto sampler	X
PC-A	Stream	Intermittent	Percha Creek u/s of Warm Springs Canyon	Quarterly	Flow meter	
PC-B	Stream	Intermittent	Percha Creek u/s of Percha Box	Quarterly	Flow meter	
PC-C	Stream	Perennial	Percha Creek in Percha Box	Opportunistic	Auto sampler	X
PC-D	Stream	Ephemeral	Percha Creek in Sec. 21 T16S R5W	Quarterly	Flow meter	
WSC-A	Stream	Ephemeral	Upper Warm Springs Canyon	Quarterly	Flow meter	
CSC-A	Stream	Ephemeral	Upper Cold Springs Canyon	Quarterly	Flow meter	
NWS	Stream	Perennial	North Warm Spring on Las Animas Creek	Quarterly	Flow meter	
WS	Spring	Ephemeral	Warm Spring	Quarterly	Weir	
BG	Spring	Ephemeral	BG Spring	Quarterly	Weir	X
BG-2	Spring	Ephemeral	BG-2 Spring	Quarterly	Weir	X
PWS	Spring	Ephemeral	Paxton Well Spring	Quarterly	Weir	
MAS	Spring	Ephemeral	Meyers Animas Spring	Quarterly	Weir	X
CSCS-A	Spring	Ephemeral	Cold Spring Canyon spring	Quarterly	Weir	
WSCS-A	Spring	Ephemeral	Warm Spring Canyon spring #1	Quarterly	Weir	X
WSCS-B	Spring	Ephemeral	Warm Spring Canyon spring #2	Quarterly	Weir	X

Table 8-3
Surface Water Resources Data Needs

Data Need	Plan to Address Data Need
Nature of flow and water quality in Grayback Arroyo	Three sampling stations are proposed to characterize streamflow and water quality by collecting opportunistic samples and measurements during storm events. Sites are proposed upstream, within, and downstream of the mine operations at sites that have been sampled in the past. Installation of auto-samplers along this ephemeral reach will enable opportunistic sampling.
Nature of flow and water quality in Percha Creek	Three sampling stations along perennial, intermittent and ephemeral reaches are proposed to characterize streamflow and water quality by collecting quarterly samples and measurements and a fourth sampling station on an intermittent reach is proposed to characterize streamflow and water quality opportunistically. Sites are proposed upstream, within, and downstream of the Percha Box at locations that have been sampled in the past. Installation of an auto-sampler along the intermittent reach will enable opportunistic sampling.
Nature of flow and water quality in Las Animas Creek	Four sampling stations along perennial and intermittent reaches are proposed to characterize streamflow and water quality by collecting quarterly samples and measurements and a fifth sampling station on an intermittent reach is proposed to characterize streamflow and water quality opportunistically. Sites are proposed in the upper, middle, and lower reaches of Las Animas Creek at sites that have been sampled in the past. Installation of an auto-sampler along the intermittent reach will enable opportunistic sampling.
Potential of mine discharge to have a significant, quantifiable effect on intermittent or perennial flow	Opportunistic streamflow and water quality samples collected at three sites Grayback Arroyo.
Seasonal variability in water quality conditions in the pit lake, including stratification	High-resolution, vertical profiles of water quality coupled with discrete-depth samples taken from the epilimnion, metalimnion, and hypolimnion (if present) on a quarterly basis.
Geochemical characteristics of sediment	Sediment samples will be collected concurrently with surface water samples collected from perennial reaches of streams and from the pit lake. The list of sediment parameters to be analyzed is presented in Table 8-4.
Nature of flows from springs and seeps	Eight springs are proposed to characterize spring flow and water quality by collecting quarterly water samples and measurements. Sites are proposed within the Greenhorn Arroyo drainage basin, Percha Creek drainage basin, and Las Animas Creek drainage basin.

Table 8-4

Analytical Parameters and Analysis Methods for Surface Water and Sediment Samples

(Sediment samples will be prepared using EPA Method 1312-SPLP, Synthetic Precipitation Leaching Procedure, to determine the concentrations of water-soluble constituents in the sediments.)

Analytical Parameter	Analysis Method for Water	Lab Detection Limit (mg/L unless noted)	Analysis Method for Sediment	Lab Detection Limit for Sediments (mg/kg unless noted)
Anions				
Fluoride	EPA Method 300.0	0.1	NA	NA
Chloride	EPA Method 300.0	0.1	NA	NA
Nitrogen, Nitrite (as N)	EPA Method 300.0	0.1	NA	NA
Nitrogen, Nitrate (as N)	EPA Method 300.0	0.1	NA	NA
Nitrogen, Ammonia (as N)[§]	EPA Method 300.0	0.1	NA	NA
Sulfate	EPA Method 300.0	0.5	NA	NA
Dissolved Metals				
Aluminum	EPA Method 200.7	0.02	EPA Method 200.7	1.0
Antimony	EPA Method 200.8	0.005	EPA Method 200.8	0.25
Arsenic	EPA Method 200.8	0.02	EPA Method 200.8	1.0
Barium	EPA Method 200.7	0.002	EPA Method 200.7	0.1
Beryllium	EPA Method 200.7	0.002	EPA Method 200.7	0.1
Boron	EPA Method 200.7	0.04	EPA Method 200.7	2.0
Cadmium	EPA Method 200.7	0.002	EPA Method 200.7	0.1
Calcium	EPA Method 200.7	0.50	EPA Method 200.7	5.0
Chromium	EPA Method 200.7	0.006	EPA Method 200.7	0.3
Cobalt	EPA Method 200.7	0.006	EPA Method 200.7	0.3
Copper	EPA Method 200.7	0.0003	EPA Method 200.7	0.2
Iron	EPA Method 200.7	0.02	EPA Method 200.7	1.0
Lead	EPA Method 200.7	0.005	EPA Method 200.7	0.25
Magnesium	EPA Method 200.7	0.50	EPA Method 200.7	5.0
Manganese	EPA Method 200.7	0.002	EPA Method 200.7	0.1
Mercury	EPA Method 7470 CVAA	0.0002	M7471A CVAA	0.03
Molybdenum	EPA Method 200.7	0.008	EPA Method 200.7	0.4
Nickel	EPA Method 200.7	0.01	EPA Method 200.7	0.5
Potassium	EPA Method 200.7	1.0	EPA Method 200.7	10
Selenium	EPA Method 200.8	0.02	EPA Method 200.8	1.0
Silicon	EPA Method 200.7	0.08	EPA Method 200.7	4.0
Silver	EPA Method 200.7	0.005	EPA Method 200.7	0.25

Analytical Parameter	Analysis Method for Water	Lab Detection Limit (mg/L unless noted)	Analysis Method for Sediment	Lab Detection Limit for Sediments (mg/kg unless noted)
Sodium	EPA Method 200.7	0.5	EPA Method 200.7	5.0
Thallium	EPA Method 200.7	0.01	EPA Method 200.7	0.5
Titanium	EPA Method 200.7	0.005	EPA Method 200.7	0.25
Uranium	EPA Method 200.8	0.01	EPA Method 200.8	0.5
Vanadium	EPA Method 200.7	0.005	EPA Method 200.7	0.25
Zinc	EPA Method 200.7	0.005	EPA Method 200.7	0.25
Solids				
Total Suspended Solids (TSS)	SM 2540D	1.0 µg/L	NA	NA
Total Dissolved Solids (TDS)	SM 2540C	10	NA	NA
Percent Solids	NA	NA	CLPSOW290 Part F, D-98	NA
Alkalinity				
Alkalinity, total (as $CaCO_3$)	SM 2320B	20	NA	NA
Carbonate	SM 2320B	20	NA	NA
Bicarbonate	SM 2320B	20	NA	NA
Other				
pH	150.1	12.45	NA	NA
Specific Conductance	120.1	0.01 µS/cm	NA	NA
Cyanide	Kelada-01	0.005	M9012A	0.5
Temperature[§]	EPA Method 170.1	ND	NA	NA
Dissolved Oxygen[§]	EPA Method 360.1	ND	NA	NA

Notes:

NA = not applicable as sample will not be analyzed for a given parameter
ND = not determined or dependent on the instrument
§ = run for pit lake sample only and not run for samples from stream, spring, or seep

Table of Contents

9 Groundwater 9-1
9.1 Regional Hydrogeology 9-1
9.1.1 Hydrogeology of the Permit Area 9-2
9.1.2 Aquifer Characteristics in the Permit Area 9-2
9.1.3 Existing Baseline Groundwater Information 9-5
9.1.4 NMED Stage 1 Abatement Plan Requirements 9-6
9.1.5 Statistical Analysis of Existing Baseline Data 9-7
9.2 Sampling Objectives 9-8
9.3 Sampling Frequency 9-8
9.4 List of Data to Be Collected 9-9
9.4.1 Groundwater Quality Parameters 9-9
9.4.2 Aquifer Parameters 9-9
9.5 Methods of Collection 9-9
9.5.1 Water Level and Total Depth Measurements SOP 9-9
9.5.2 Monitoring Well Sampling for Groundwater SOP 9-11
9.5.3 Aquifer Testing and Analysis SOP 9-17
9.5.4 Monitoring Well Installation 9-21
9.6 Parameters to be Analyzed 9-21
9.7 Maps Showing Proposed Sampling Locations 9-21
9.8 Laboratory and Field Quality Assurance Plans 9-21
9.9 Discussion in Support of Proposal 9-22
9.10 References 9-24

List of Figures

Figure 9-1 Lower Rio Grande Basin
Figure 9-2 Conceptual Model of Groundwater Flow System
Figure 9-3 Spring and Stream Locations
Figure 9-4 Water Level Contours
Figure 9-5 Water Level Map of Copper Flat Pit Area
Figure 9-6 Conceptual Model of Pit Lake Monitoring Well Relationship with Water Quality Reports
Figure 9-7 Conceptual Design, Tailings Seepage Control
Figure 9-8 Schematic Geologic Cross Section (A-A')
Figure 9-9 Regional Groundwater Well Locations
Figure 9-10 Proposed Monitoring Well Program
Figure 9-11 Wells Sampled in January 2010

List of Tables

Table 9-1 Groundwater Sampling and Data Analysis Plan
Table 9-2 Proposed Monitoring Wells for Water Quality Sampling and Water Level Measurements
Table 9-3 Analytical Parameters and Analysis Methods for Groundwater Samples
Table 9-4 Groundwater System Characteristics (from SRK, 1995)

9 Groundwater

Groundwater is a major supply of water for domestic and agricultural use in southern New Mexico. The high evaporation rate during the long, hot summers coupled with low average annual precipitation in the area result in surface waters being an unreliable source of water on a year-round basis. The Rio Grande is the only significant surface water resource in the Copper Flat Mine Permit Area (Site). Intermittent streams that feed the Rio Grande, such as Las Animas Creek and Percha Creek in the Site area, are local sources of water for at least part of the year. The river and associated shallow alluvial deposits of its inner valley also served as the ultimate discharge zone for pre-development groundwater flow from the adjacent Greenhorn Arroyo, Las Animas Creek, and Percha Creek drainage basins (Hawley et al., 2005, Wilson et al. 1981). Additional water comes from shallow domestic and agricultural wells. This section provides a description of the regional and local groundwater along with a proposed sampling and analysis approach to characterizing baseline conditions of groundwater resources. Baseline studies have been completed in the project area since the 1960s, and relevant information and data are referenced in subsequent sub-sections throughout Section 9.

9.1 Regional Hydrogeology

The Site is located in the Lower Rio Grande Underground Water Basin (LRGB), which extends from Elephant Butte Dam to the Texas Border near El Paso and is one of New Mexico's principal agricultural regions (Figure 9-1). The LRGB was declared by the NM State Engineer on September 11, 1980. In doing so, the underground waters of the LRGB are administered by the State Engineer. In response to drought conditions in New Mexico, the Office of the State Engineer (OSE) designated the LRGB for Active Water Resource Management (AWRM) in 2004, emplacing additional restrictions on groundwater development. In addition, a water master district that encompasses Hot Springs, Las Animas Creek, and LRGB Underground Water Basins was created to assist with water administration in the region.

Groundwater in the LRGB generally flows from the highlands on either side of the basin through bedrock and valley alluvium to the center of the basin and to the Rio Grande. Figure 9-2 illustrates the conceptual model of groundwater flow at the Site. The bedrock aquifer in the Paleozoic sedimentary rocks are recharged by rainfall and snowmelt through bedrock faults and bedding planes exposed in the highlands west of the site. This water generally flows along a hydraulic gradient toward the approximate center of the Rio Grande Valley. Occasionally, this deep regional flow discharges at the ground surface as springs along faults where the Paleozoic bedrock crops out within the valley. This occurs in at several locations within the Las Animas Creek and Percha Creek drainage basins (Figure 9-3). The water table elevation near the existing pit lies at approximately 5,450 to 5,500 feet (ft) above mean sea level (amsl). Groundwater near Caballo Reservoir lies at about 4,200 ft amsl, indicating a drop of 1,300 ft over approximately 14 to 15 miles.

Valley alluvium is generally recharged by precipitation along mountain fronts where the alluvial fans are exposed and by streams that flow out of the highlands and lose water to the alluvium as they flow toward the Rio Grande. Many intermittent streams in the area are "losing streams" over at least part of their courses and provide recharge to the alluvial groundwater system. This alluvial groundwater then flows downgradient to the Rio Grande. Most areas within the LRGB that have not been significantly disturbed by human activity are in hydraulic equilibrium. That is, water coming into the system by precipitation recharge is balanced by outflow to major streams, evapotranspiration, and interbasin flow.

9.1.1 Hydrogeology of the Permit Area

Three aquifers exist in the Site area, as shown schematically on Figure 9-2. The deepest aquifer is the crystalline bedrock aquifer that receives water from the highlands to the west of Animas Peak and carries this water along bedding planes, faults, and solution cavities toward the center of the LRGB. The crystalline bedrock aquifer consists of Cretaceous andesite and monzonite breccias underlain by Paleozoic rocks in the Animas Uplift area, Tertiary volcanic rocks to the west of the pit lake in the graben associated with the Animas uplift, and Paleozoic sedimentary rocks to the east of the pit lake area in the Palomas Basin (see Section 7.0). The Santa Fe Group aquifer system, which consists of interbedded sandstones, silts, and clays, overlies the Paleozoic bedrock units to the east of the pit lake area within the Palomas Basin. This aquifer system receives water from precipitation and from the losing reaches of streams. The uppermost aquifer at the Site is the Quaternary alluvial aquifer along Las Animas and Percha Creeks (Figure 9-2). This alluvium is up to 40-ft thick in the Las Animas Creek area and carries water that is in hydraulic equilibrium with the water flowing in Las Animas Creek (BLM, 1999). The Percha Creek alluvial aquifer is less studied than the Las Animas Creek alluvial aquifer, and as a result, less historical data about its aquifer characteristics are available. The aquifers of greatest importance in terms of water supply in the area are within the Palomas Basin to the east of the pit lake and include the intermediate Santa Fe Group aquifer system and the alluvial aquifer associated with Las Animas Creek.

Figure 9-4 from the Adrian Brown Consultants (ABC) (1998b) presents a piezometric contour map showing the general configuration of groundwater level elevations at the Site as interpreted at that time. Groundwater levels near the existing pit are approximately 5,450 ft amsl, and at Caballo Reservoir, the levels are about 4,200 ft amsl. The map indicates that groundwater flow is generally to the east toward Caballo Reservoir. Hydraulic gradients are relatively large (closely spaced contours) in the western portion of the Site, reflecting lower transmissivity in the bedrock aquifer and in the western portion of the Palomas Basin in the Santa Fe Group aquifer system. The wider spacing of contours in the eastern portion of the Site suggests that transmissivity of the Santa Fe Group aquifer increases toward Caballo reservoir. The widest spacing of contours (highest transmissivity) appears to occur in the area of the groundwater production wellfield (wells PW-1, 2, 3, and 4 on Figure 9-4). This area coincides with an interpreted graben structure (see Section 7), which reflects an increased thickness of the Santa Fe Group in this area.

9.1.2 Aquifer Characteristics in the Permit Area

9.1.2.1 Crystalline Bedrock Aquifer Characteristics

Groundwater within the mining district and the area of the present open pit occurs in andesitic volcanic rocks and quartz monzonite breccia intrusive rocks (Figure 9-2). The current pit lake was reported by SRK (1997) to be at an elevation of 5,442 ft amsl, which is about 50 to 100 ft below the pre-mining ground elevation (5,500 to 5,540 ft amsl reported in the Preliminary Final Environmental Impact Statement (PFEIS) (BLM, 1999). Groundwater levels measured in the pit and tailings areas as of 1997 are shown on Figure 9-5. Newcomer et al. (1993) reported a pre-mining (1981) water level of 5,370 ft amsl in well GWQ-5, which is approximately 4,000 ft east-southeast from the pit and within the old plant site area. These authors also reported a water level of 5,360 ft amsl in the Hillscher West well (GWQ-6), which lies approximately 2,500 ft southeast from well GWQ-5. These limited groundwater elevation data suggest that the groundwater gradient in the andesitic volcanic rocks may be to the east or southeast from the current pit lake area as shown on Figure 9-5. Within 500 ft of the pit lake (see Figure 9-6, however, groundwater gradients are toward the pit lake, which may act as a local evaporative sink (BLM, 1999).

In January 2010, NMCC resurveyed the pit lake and as many of the groundwater monitoring wells established for the PFEIS as could be located. The pit lake elevation was 5,444 ft amsl in January 2010, revealing that the pit lake elevation remains below the pre-mining water level elevation of 5,500 to 5,540 ft amsl.

9.1.2.2 Santa Fe Group Aquifer System

Overview

Overlying the crystalline bedrock aquifer at the Site is the Santa Fe Group aquifer system, a system that is locally represented by two hydrostratigraphic units (HSUs): (1) the Upper Santa Fe Group hydrostratigraphic unit (USF), and (2) the Middle Santa Fe Group hydrostratigraphic unit (MSF). As defined by Hawley and Kennedy (2004), these hydrostratigraphic units are mappable bodies of basin and valley fill that are grouped according to genesis and position in both lithostratigraphic and chronostratigraphic sequences. Informally, these HSUs comprise the major basin-fill aquifer zones, and correspond roughly to the upper (Palomas) and middle (Rincon valley) lithostratigraphic subdivisions of the Santa Fe Group used in local and regional geologic mapping (Hawley and Kennedy, 2004).

The Santa Fe Group is composed chiefly of coalescing alluvial fan deposits that are discontinuous and locally heterogeneous with inter-bedded sandstones, silts, and clays of varying percentages. The Upper Santa Fe Group Palomas Formation (Lozinsky and Hawley, 1986) represents the USF at the Site. This formation grades eastward from the Animas Uplift from coarse alluvial fan material to braided-stream and deltaic sands and silts to clays near the Rio Grande. The interfingering with clays begins approximately 3 to 5 miles west of the current position of the Rio Grande and is responsible for the flowing wells common in this part of the Site (Murray, 1959; Figure 9-2). A basalt flow dated at 4.2 million years before present caps the Palomas Formation gravels near Copper Flat (Seager et al., 1984).

The Middle Santa Fe Group Rincon Valley Formation (Seager and Hawley, 1973) is exposed near Hillsboro, New Mexico, where the reddish-brown clays and clayey silts characteristic of this basal unit are interbedded with basalts dated at 28 million years before present (Seager et al., 1984). The Rincon Valley Formation represents the MSF at the Site and generally contains water, but the yield is low due to the low hydraulic conductivity of the clays. The Rincon Valley Formation lacustrine red clays underlie the Palomas Formation and thicken southward toward Hatch, New Mexico, and the Rincon Basin (Wilson et al., 1981).

Tailings Dam Vicinity

The present tailings impoundment facility overlies the old placer workings of Greyback Arroyo and Hunkidori Gulch (Figure 9-3). A study of these placer workings by Segerstrom and Antweiler (1975) showed that the placers were found in paleo-stream terrace alluvium approximately 25 to 30 ft thick that is underlain by a calcium carbonate horizon and reddish-brown clay. SRK (1995) and SHB (1980) confirmed and expanded the areal extent of this reddish-brown clay layer and determined that the top of the Palomas Formation is stratigraphically below the red clay layer. According to the studies completed by SRK and SHB, the clay layer and the 25 to 30 ft of paleo-stream terrace gravels that lie above the clay, have acted to prevent downward migration of water draining from the eastern half of the existing tailings. This clay layer has enabled a mound of water beneath the tailings impoundment to develop and was determined by SRK and SHB to extend eastward beyond the tailings dam. This mounding of water, due to drainage of the tailings, became evident in some tailings dam monitor wells completed above the clay layer. The central and western sections of the existing tailings facility appear to communicate hydrologically with the USF that lies beneath the tailings area because the clay zone thins and disappears in this area, as shown in Figure 9-7.

The thickness of the Palomas Formation increases locally over a graben structure (labeled Dutch Gulch in Figure 9-8), which is reflected in higher transmissivity and relatively low hydraulic gradients in the USF. Based on a 7-day aquifer pumping test (ABC, 1996), the transmissivity of the USF in the tailings dam area is about 187 ft^2/day. East of the tailings area (see Figure 9-8) is a 10- to 30-foot thick clayey sand and gravel layer, underlain by a 25- to 100-foot-thick clay layer, which in turn is underlain by a silty sand and gravel layer (SRK, 1995). The lower silty sand and gravel layer is considered by ABC (1996) to be the USF and, based on drilling information, has a thickness of at least 200 ft. The hydraulic gradient in this area is about 30 ft per mile.

East of the graben structure, labeled as Dutch Gulch in Figure 9-8, the Palomas Formation (labeled Tsfp) thins and is interpreted to have significantly reduced transmissivity. The hydraulic gradient in this area ranges from about 130 to 330 ft/mile. The contact between the Palomas Formation and the underlying Rincon Valley Formation clay unit (labeled Tsf in Figure 9-8) is a highly irregular depositional contact. Locally, the Palomas Formation (USF) may be unsaturated, with the water table existing in the underlying Rincon Valley Formation (MSF) (BLM, 1999).

Production Wellfield Vicinity

Farther to the east, the hydraulic gradient decreases from 330 ft/mile to about 34 ft/mile in the vicinity of the production wellfield (identified as PW wells on Figure 9-9). This suggests a progressive increase in transmissivity toward the area of the production wellfield. A graben structure below the production wellfield locally increases the thickness of the Palomas Formation to as much as 1,000 ft (Figure 9-8). The transmissivity of the USF in the production wellfield area ranges from about 2,675 to 5,750 ft^2/day (SRK, 1995). Farther to the east, towards Caballo Reservoir, sands and gravels in the Palomas Formation are interbedded with clays of the ancient Rio Grande. As a consequence, the transmissivity decreases slightly and the hydraulic gradient Increases to 45 ft/mile. In this area, the USF appears to be confined, leading to artesian flow in wells along the lower reaches of both Las Animas Creek and Percha Creek.

Although the Palomas Formation is described as “sand and gravel” (Davie and Spiegel, 1967), there exist numerous discontinuous clay layers within the sequence. This causes the bulk vertical hydraulic conductivity of the USF to be much lower than the horizontal conductivity. As a consequence, groundwater in deeper portions of the USF can be semiconfined, leading to relatively high vertical hydraulic gradients. The low vertical hydraulic conductivity has two important effects on the groundwater flow system. First, within about 4 miles of Caballo Reservoir, confinement of groundwater is sufficient to create artesian conditions in deeper portions of the USF. Wells drilled to these depths have groundwater levels aboveground surface and produce flowing wells, the locations of which are shown on Figure 9-9. Flow rates for uncapped wells range between a few gallons per minute (gpm) to as high as 40 gpm.

The second effect of low vertical conductivity is to reduce downward leakage between the Quaternary alluvial aquifer in the Las Animas Creek drainage basin and the underlying USF. At the location of monitoring wells MW-9, 10, and 11, north of the production wellfield, the groundwater level in the USF is some 58 ft lower than the water level in the overlying Quaternary alluvial aquifer (ABC, 1996). This results in a downward vertical hydraulic gradient from the Quaternary alluvial aquifer in the vicinity of Las Animas Creek drainage basin to the USF approaching 1 ft/ft. Such downward gradients are interpreted to occur along a substantial length of Las Animas Creek (ABC, 1996). In spite of these gradients, the amount of surface water loss from the Quaternary alluvial aquifer in the Las Animas Creek drainage basin is not significant; suggesting that vertical hydraulic conductivity in the USF is relatively low. Analytical calculations (ABC, 1997) suggest that if the vertical conductivity were much greater than 1 ft/year (10^{-6} cm/second), the Las Animas surface water system would lose essentially all of its water and become an intermittent stream, which clearly does not occur.

The hydraulic connection between the USF and the alluvial aquifer of the Rio Grande has not been evaluated, but groundwater gradients at the Site strongly suggest that water flows from the Palomas Formation to the floodplain alluvium of the Rio Grande.

An aquifer pumping test conducted at the locations of monitor wells MW-9, 10, and 11 suggests that the vertical conductivity of the USF is low in this area (ABC, 1997). Pumping of the wells screened in the USF at this location did not affect a well screened in the Quaternary alluvial aquifer in the Las Animas Creek drainage basin, even though the well screened in the USF had 22 ft of drawdown. Also, monitoring of water levels along Las Animas Creek by Alta (Goff, 1998) for wells screened in both aquifers showed that fluctuations in water levels observed in shallow wells (those screened in the Quaternary alluvial aquifer) are not mirrored in the deeper wells (wells screened in the USF). These data are presented in Table A2-10 of the PFEIS (BLM, 1999).

9.1.2.3 Quaternary Alluvial Aquifer

The uppermost aquifer at the Site is the Quaternary alluvial aquifer, which is composed of channel and floodplain gravels, sands, and silts. Locally, these units are generally 30 to 50 ft thick near the mouths of Las Animas and Percha Creeks (Davie and Spiegel, 1967). Cores from monitoring wells drilled along Las Animas Creek indicate that upper alluvial gravels extend from the surface to a depth of approximately 20 to 60 ft depending on the location along the creek (BLM, 1999). There are fewer data available for the thickness of these deposits in and along Percha Creek.

The Las Animas alluvial aquifer consists of local alluvial deposits adjacent to and underlying Las Animas Creek. Groundwater in this narrow, sinuous aquifer is in direct hydraulic communication with Las Animas Creek surface water. Surface water in the creek and groundwater in the aquifer form a single surface-to-groundwater flow system. Surface water flow from one location to the next may be related, in part, to the proportion of total system flow being carried by the aquifer at each location. Along its course, the Las Animas alluvial aquifer receives recharge by rainfall infiltration. Discharge from the aquifer occurs through evaporation and evapotranspiration from riparian vegetation and existing well pumping. Between the Saladone well and an area of the Lower Animas Artesian well (Figure 9-8), the aquifer loses water to the underlying Palomas Basin alluvial aquifer by slow downward seepage. The total flow rate for surface flow plus flow in the alluvium of the creek drops from around 1,800 to 1,900 gpm to around 1,100 gpm, a loss of 800 gpm over the 8-mile stretch of creek bed. The loss is consistent with slow downward seepage of water at a rate of around 1 foot/year (ABC, 1997). This is the approximate saturated hydraulic conductivity of clay. In the area of the Lower Animas Artesian (Figure 9-9) the Las Animas surface/groundwater system may receive recharge from the USF. At Caballo Reservoir, all water in the Las Animas surface/groundwater system discharges to the reservoir. The nature of artesian conditions in the Percha Creek drainage basin have not been studied in as much detail, and therefore less historical data are available.

Upstream of the artesian wells, Las Animas Creek, the alluvial aquifer can be “perched” above the water table in the Santa Fe Group aquifer system by 20 to 60 ft of unsaturated to partially saturated alluvial sediments (SRK, 1995; ABC, 1997). The alluvial aquifer along Las Animas Creek in the lower reaches loses water to the Santa Fe Group aquifer system by slow downward seepage. The upper reach of Las Animas Creek near the Saladone Well (Figure 9-9) also may be perched above the intermediate aquifer (Minton, 1961).

9.1.3 Existing Baseline Groundwater Information

A wealth of groundwater data are available for the Site because the mine was active in the past and was characterized by previous operators that either mined the Site or worked on permit applications to mine the Site. These historical data will be used in conjunction with the baseline groundwater quality data that will be

collected under the procedures set forth in this SAP to provide as thorough an understanding as possible of groundwater quality conditions prior to the re-initiation of mining at Copper Flat. Key resources that contain data to be used for the baseline groundwater analysis include: Groundwater monitoring well exceedences provided by SRK (2010); the PFEIS (BLM, 1999); the Hydrologic Assessment, Copper Flat Project Sierra County, New Mexico (Newcomer et. al, 1993); and The Natural Defenses of Copper Flat, Sierra County, New Mexico (Raugust, 2003). A brief summary of the data available in these key reports follows.

The PFEIS (BLM, 1999) provides a summary of groundwater quality data. Summary tables for key wells and key constituents are provided in Table 9-2. The wells identified in this study are illustrated in Figure 9-9. The PFEIS (BLM, 1999) concluded that groundwater quality at the Site was good and generally useable for domestic and agricultural purposes. This document also concluded that past mining in the Hillsboro District, the Copper Flat Mine tailings facility drainage, and the presence of an oxidized sulfide-bearing ore body have impacted groundwater within and immediately adjacent to the area of past mining, resulting in elevated total dissolved solids (TDS) and sulfate that exceed New Mexico Water Quality Control Commission (WQCC) Standards. These impacts were found to be localized within the immediate vicinity of the mine features or associated with wells completed in the ore body.

Newcomer et al. (1993) determined that the quality of groundwater at the Site has changed little since the early 1980s and probably since the 1800s. The authors found that there have been some increases in TDS and sulfate in some wells along Grayback Arroyo below the mine site and down-gradient of the tailings dam, associated with mining and milling activities in the 1980s. Newcomer et al. (1993) determined that the only constituents exceeding the WQCC Standards were barium from a spring sample, and, cadmium and fluoride from a pit lake water sample.

Raugust (2003) compiled historical groundwater data and summarized groundwater quality conditions and, based on his data compilation and analysis, concluded:

- Groundwater pH measurements both up and downgradient of the pit lake range from 7 to 8.2.
- TDS and sulfate values are less than WQCC standards in the wells evaluated for this analysis; however, samples downgradient of the mine have increased gradually over time and are approaching the standards for TDS.
- Historical sampling of well GWQ-5, located east and downgradient of the pit lake, indicates that water quality in the vicinity of the pit lake may have been affected naturally by the presence of the ore body prior to mining in 1982.
- The groundwater upgradient of the mine pit lake is high quality with relatively high proportions of chloride and sulfate. Groundwater downgradient of the pit lake shows relatively higher proportions of bicarbonate and calcium and relatively lower proportions of sulfates.
- Pre-Quintana mining (June 15, 1981) groundwater data collected from wells downgradient of the pit lake show similar anions and cation distributions to post-Quintana mining activities (1996 and 1998). This indicates that groundwater quality downgradient of the ore body reflects the natural weathering of the Copper Flat porphyry system.

9.1.4 NMED Stage 1 Abatement Plan Requirements

On August 20, 2008, the NMED sent a letter to the site owner at that time requiring a Stage 1 Abatement Plan (20.6.2.4101 NMAC). The purpose of the Stage 1 Abatement Plan is to provide the data necessary to select and design an effective abatement alternative. The requirements for the Stage 1 Abatement Plan are described in 20.6.2.4106 NMAC. The abatement plan proposal must include an investigation to define the extent and magnitude of any existing groundwater and surface water contamination and to characterize the hydrogeology

of the site. These requirements are similar to the EMNRD requirements for completing a Baseline Characterization Report, and these efforts will be conducted in parallel; therefore, the surface water and groundwater requirements of this SAP are relevant to both characterization efforts.

NMCC's meetings with the NMED concerning the abatement requirements have revealed the following key concerns on the part of the NMED:

- Groundwater impacts from the existing unlined tailings impoundment have been documented, but have not been fully characterized.
- Samples of pit lake water quality reveal exceedances of WQCC standards, and NMED is concerned about migration of this water away from the pit, causing additional groundwater impacts as well as ongoing contact with wildlife.
- Acid leaching could be occurring due to ongoing ore exposure.

9.1.5 Statistical Analysis of Existing Baseline Data

As discussed in this section, enormous amounts of surface water and groundwater data exist for this Site. These existing baseline data are essential to completing a comprehensive Baseline Characterization Report. As discussed in the EMNRD Mining and Minerals Division (MMD) draft, Guidance Document for Part 6 New Mining Operations Permitting under the New Mexico Mining Act (MMD Guidance Document), "If historic data and information are used as part of the baseline data, the SAP will include supporting material to justify the use of this historic data." As discussed in the previous subsection, baseline data collection has been initiated at the Site. The following sections describe how these data will be collected to maintain compliance with the referenced MMD Guidance. To justify the incorporation of the existing baseline data, statistical analysis will be used to determine if the current baseline data are significantly different from existing baseline data. This subsection describes a proposed approach that may be utilized to answer this question.

To statistically evaluate and compare new and existing baseline data, an Access database will be utilized to incorporate data from the sources listed above, as well as from other key sources that are identified during the baseline characterization program. Standardized queries will be used to easily select common location and parameter combinations.

The database will include the following data-entry features:

- A data qualifier to be applied at the time of data entry. This qualifier will be based primarily on the existence of supporting documentation and the indication that the data have been previously validated.
- Fields for entry of chemical parameters and other significant data, including:
  - Well identification (ID)
  - Parameter
  - Result
  - Units
  - Detection limit
  - Method
  - Non-detect qualifier used
  - Date of collection or analysis
  - Laboratory performing analysis
  - Analytical laboratory data qualifier

- Descriptive summary statistics for the compiled existing baseline dataset and a dataset based on data collected from the current baseline monitoring well network, including:
  - Chemical name
  - Number of detections
  - Number of samples
  - Arithmetic mean
  - Geometric mean (the backtransformed mean of the logtransformed data)
  - Standard deviation
  - Arithmetic mean plus two standard deviations
  - 95-percent upper confidence limit on the arithmetic mean (likely upper value of the arithmetic mean)
  - Minimum reported concentration
  - Maximum reported concentration

Descriptive summary statistics will be calculated separately for each historical data set identified and then a historical data set will be developed to represent existing baseline data. These data will be compared to summary descriptive statistics developed for the current baseline monitoring well network. If possible, the historical data set will be classified into pre-mining, mining, and post-mining periods and summary descriptive statistics will be developed for each classification.

Summary descriptive statistics will be developed for any populations identified by the methods described above. Each historical population identified will be separately compared to current baseline data and an interpretive evaluation of the historical and current datasets will be completed.

9.2 Sampling Objectives

The objectives of the baseline groundwater characterization program are as follows:

- Obtain necessary data to evaluate quantity and quality of all aquifers at the Site that could be impacted by mining activities.
- Address data gaps identified during evaluation of the DEIS (BLM, 1996).
- Meet the requirements set forth in the regulations in NMAC Title 19, Chapter 10, Part 6.
- Meet the guidelines set forth in MMD's draft Guidance Document for Part 6 New Mining Operations Permitting under the New Mexico Mining Act.

See Table 9-1 for the activities proposed to meet these objectives.

9.3 Sampling Frequency

The MMD Guidance Document requires a minimum of two sampling events over the required 12-month period for baseline groundwater quality sampling. Quarterly groundwater quality sampling will be necessary to address NMED's Stage 1 Abatement and Discharge Plan requirements; therefore, the baseline groundwater quality sampling will be performed for a minimum of four quarters. Additionally, water levels will be obtained on a quarterly basis to evaluate baseline seasonal fluctuations. Table 9-2 provides the current list of groundwater monitoring wells and the sampling frequency for water quality and water level measurements. The locations for these proposed wells are shown in Figure 9-10. NMCC proposes a phased approach to water quality sampling,

where water quality samples will be collected initially from the wells identified in Table 9-2 for water quality sampling, then reduced to a subset of ten wells based on the analytical results and consultation with the MMD.

9.4 List of Data to Be Collected

The two categories of data to be collected for baseline groundwater characterization are groundwater quality and aquifer parameters. Further discussion of these datasets is included in the following subsections.

9.4.1 Groundwater Quality Parameters

The MMD Guidance lists specific groundwater quality parameters that are recommended to comply with the baseline characterization requirements. Table 9-3 shows the list of parameters to be analyzed for and the associated analysis methods and laboratory detection limits.

9.4.2 Aquifer Parameters

Water level measurements will be taken from all wells in the monitoring well network on a quarterly basis during the baseline characterization phase to evaluate the pre-mining potentiometric surface (i.e., steady-state condition). This potentiometric surface will form the basis for future modeling required to evaluate potential impacts from mine dewatering and production well pumping. Based on comments made during Alta Gold's permit application phase, the need to install additional monitoring wells for water level measurement, particularly outside the permit area, will be evaluated (DBS&A, 1998).

In addition to water level monitoring, groundwater modeling requires hydraulic parameter data, specifically, hydraulic conductivity, transmissivity, and storativity for the key aquifers. Several pumping tests have been performed in the tailings dam, production well, and the Las Animas Creek areas to evaluate the aquifer characteristics (Greene and Halpenny, 1976; Atkins, 1992; ABC, 1996b; and ABC, 1998). The details and analytical results of these tests are summarized by SRK (1995) and in Table 9-4. The existing data and recommendations will be evaluated during the baseline characterization phase, and a determination will be made as to the adequacy of the existing data to support the hydrologic impact analysis. If necessary, additional aquifer tests may be completed.

9.5 Methods of Collection

As discussed in the previous sections, three major categories of data will be collected for the baseline groundwater characterization:

1. Well information (water levels and total depth)
2. Groundwater quality samples for general chemistry and metals
3. Aquifer parameters (hydraulic conductivity, transmissivity and storativity)

The following sections provide general Standard Operating Procedures (SOPs) for water level and total depth measurements, groundwater sampling, and aquifer testing. Procedures will be modified as necessary to conform to site-specific requirements. Additionally, if new wells are added to the monitoring well network, they will be constructed in compliance with the NMED Monitor Well Construction Guidelines.

9.5.1 Water Level and Total Depth Measurements SOP

This SOP is concerned with the measurement of water levels in monitoring wells and the total depth of wells. Step-by-step procedures are outlined in the following sections.

9.5.1.1 Groundwater Level Measurement

If necessary, a plastic sheet can be placed around the well, creating a clean surface onto which the measurement and sampling equipment can be positioned. Do not place meters, tools, equipment, etc., on the sheet unless they have been cleaned first. After unlocking and/or opening a monitoring well, water level measurements will be made using an electric water level meter.

Equipment

- Socket wrenches and/or open-end wrenches
- Screw driver
- Key or combination for monitoring well lock
- Electric water level meter
- Decontamination equipment (buckets, brushes, Alconox™, distilled or deionized water, brushes, and paper towels)
- Safety equipment (sample gloves and other Personal Protective Equipment [PPE] as required for the job)
- Air monitoring equipment as required

Groundwater Level Measurement Procedures

- Unlock and/or open the monitoring well.
- Check for the measuring point at the top of the well. The measuring-point location should be clearly marked on the innermost casing or identified in previous sample-collection records. If no measuring point can be determined, a measuring point should be established. Typically, the top (i.e., the highest point or the north-facing point) of the innermost well casing will be used as the measuring point. The measuring-point location should be described on the monitoring-well gauging data form and should be the same point used for all subsequent sampling efforts.
- Obtain a water level measurement by lowering the probe of the electric water level meter into the monitoring well. Take care that the probe and electric line hang freely in the monitoring well and do not adhere to the wall of the well casing. Lower the probe into the well until the sound and light (if present) on the meter are activated. At this time, the precise measurement should be determined (to a hundredth of a foot) by repeatedly raising and lowering the tape to converge on the exact measurement. The water level measurement should be entered on an appropriate field form (i.e., monitoring-well gauging data form).
- Verify that the water level measurement is indicative of a static water level. The initial water level measurement may not be indicative of static conditions if groundwater pumping recently occured in this vicinity or if the well is screened in a confined aquifer and the well casing does not have a vent hole permitting equilibrium with the atmosphere. A second water level measurement a few minutes after the initial measurement can be used to verify static water level conditions.
- Decontaminate the electric water level meter after use. Generally only the probe and the portion of the tape that enters the well will be cleaned. Ensure that the measuring tape is not placed directly on the ground surface.

9.5.1.2 Total Depth Measurement

If necessary, a plastic sheet can be placed around the well, creating a clean surface on which the measurement equipment can be positioned. Do not place tools, equipment, etc., on the sheet unless they have been cleaned first. Total-depth measurements will be made using a stainless-steel weighted tape.

Equipment

- Socket wrenches and/or open-end wrenches
- Screw driver
- Key or combination for monitoring well lock
- Stainless steel weighted tape
- Decontamination equipment (buckets, brushes, Alconox™, distilled or deionized water, brushes, and paper towels)
- Safety equipment (sample gloves and other PPE as required for job)
- Air monitoring equipments as required

Total Depth Measurement Procedures

- Unlock and/or open the monitoring well.
- Monitor the atmosphere at the wellhead.
- Check for the measuring point of the well. The measuring-point location should be clearly marked on the innermost casing or identified in previous sample-collection records. If no measuring point can be determined, a measuring point should be established. Typically, the top (i.e., the highest point or the north-facing point) of the innermost well casing will be used as the measuring point. The measuring-point location should be described on the water level data form and should be the same point used for all subsequent sampling efforts.
- Obtain a total-depth measurement by lowering a weighted calibrated tape into the monitoring well. Take care that the weighted tape hangs freely in the monitoring well and does not adhere to the wall of the well casing. Lower the weighted tape into the well until the bottom of the well is reached. This can be determined when the weight can no longer be felt and there is slack in the tape. A precise measurement of the total depth of the well should be determined (to a hundredth of a foot) by repeatedly raising and lowering the tape to determine the exact measurement and then adding the probe tip length (e.g., 0.10 ft) that extends below the 0.00-foot mark on the tape/probe. The total-depth measurement and condition of the well bottom (i.e., hard, soft) should be entered on an appropriate field form or field logbook (i.e., water level data form).
- Decontaminate the measurement device after each use. Generally only the portion of the tape that enters the well will be cleaned. Ensure that the measuring tape is not placed directly on the ground surface.

9.5.2 Monitoring Well Sampling for Groundwater SOP

This SOP is concerned with the collection of valid and representative samples from groundwater monitoring wells. Groundwater samples are collected and analyzed to determine the presence, absence, or quantity of various contaminants as part of site characterization, remediation, and/or monitoring activities.

9.5.2.1 Equipment

The following list identifies the types of equipment that may be used for a range of groundwater sampling applications. A project-specific equipment list will be selected from this list based on project objectives and well conditions.

- Bailer with rope or string
- Pump with tubing and power source
- pH meter

- Specific conductance meter
- Temperature meter
- Dissolved oxygen meter
- eH (ORP) meter
- Turbidity meter
- Flow-through cell
- Water level measurement equipment
- Water sampling data form
- Filtration apparatus (project-dependent)
- Personal protective equipment
- Decontamination equipment
- Permanent pens
- Field logbook
- Sample coolers
- Sample containers and laboratory-supplied preservatives (if any)
- Sample labels
- Custody seals (if required by Sampling & Analysis Plan/Work Plan)
- Chain-of-custody forms
- Sample control logs

9.5.2.2 Well Purging

Prior to sample collection, purging must be performed for all groundwater monitoring wells to remove stagnant water from within the well casing and/or to ensure that a representative sample is obtained.

Standard Well Purging. Monitoring wells will be purged of at least three well casing volumes (moderate- to high-yield formations) or at least one well casing volume for low-yield formations unless micropurge methodology is followed (method described below). To determine the volume of water to be removed, the first step is to measure the depth to water (DTW) and the total depth (TD) of the well casing using the procedures described as outlined in Section 9.5.1. DTW measurements should be made within 48-hours of purging and sampling wells. Once these measurements have been obtained, the well casing volume is determined using the following equation:

$$V_{WC} = \frac{\pi D^2 h}{4}$$

where: V_{WC} (ft^3) = well casing volume

D (ft) = internal diameter of the well casing

h (ft) = length of the water column in the well casing (TD-DTW)

As a conservative measure or because of project-specific requirements, total well volumes may be required for purging rather than well casing volumes. Total well volume differs from well casing volume in that it includes the volume of water in the filter pack. Total well volume is calculated using the equation:

$$\text{Total Well Volume} = V_{FP} + V_{WC}$$

where: V_{FP} = volume of water in the filter pack

The volume of water in the filter pack is determined by calculating the volume of the water in the borehole less the well casing volume. Compensation for the porosity of the filter pack is included in the equation, and this relationship is expressed as follows:

$$V_{FP} = \left[\frac{\pi D^2 h}{4} - V_{WC} \right] (n)$$

where: V_{FP} (ft^3) = filter pack volume

D (ft) = diameter of the borehole

h (ft) = lesser of (a) length of filter pack, or (b) length of water column in the casing

n = filter pack porosity (assume 30 percent)

V_{WC} (ft^3) = well casing volume

Useful conversions: 1 ft^3 = 7.48 gal

1 gal = 0.134 ft^3

Indicator parameters (pH, temperature, and conductivity) will be monitored and recorded during purging. Generally, well purging will continue until the pH is within 0.2 standard units, temperature is within 1° C, and electrolytic conductivity is within 10 percent in three consecutive measurements.

Low-yield wells are considered purged after a minimum of one well volume is removed. If possible, low-yield wells should be purged at a rate slow enough so as not to purge the well dry. If a well is purged dry, the well should be sampled as soon as it has recovered enough to have sufficient water volume for the sample. The time between purging and sampling should not exceed 24 hours.

For medium or high-yield wells, samples should be collected within two hours of purging if possible. Under no circumstances should there be more than 24 hours between purging and sampling.

Please note that purging and sampling of a well can be done within 12 hours of well installation (i.e., just after well development), if necessary. However, the greater the time lapse between well installation and well sampling, the more representative the sample will be of formation water. It is recommended that, when project schedules and budget allow, wells should be allowed to stand for 24 hours or greater prior to purging and sampling.

Micropurging. Micropurging is an alternate method for purging wells that is distinctly different from the above-mentioned purging methodology. With micropurging, also referred to as low-flow purging, water is withdrawn directly from the screened interval at low enough pumping rates to ensure that the water sampled is formation water just recently entering the screen. As with traditional sampling, the groundwater is not sampled until the water-quality parameters (pH, temperature, and conductivity) have stabilized. Micropurging does not require a certain volume of water to be evacuated from the well. The intake point of the pump or tubing should to be close to the middle of the screen, so the monitoring-well construction details must be known. Micropurging criteria include the following:

- The intake point of the pump or tubing is in the center of the screen.
- Return water is clear and free of debris and has evacuated all major air bubbles in the tubing and flow-through cell.
- The pumping rate does not exceed 1 liter per minute (L/min) (0.1 to 0.5 L/min is usually optimum).
- Drawdown in the well is minimized and does not exceed 10 percent of the screen length.

- Three consecutive measurements of pH, temperature, conductivity, redox potential, and dissolved oxygen have been taken and show changes in value no more than 0.1 for pH, 1°C for temperature, 3 percent for conductivity, 10 millivolts for redox potential, and 10 percent for dissolved oxygen.

9.5.2.3 Well-Purging Methods

Monitoring wells may be developed using either bailers or pumps. It is not recommended that bailers be used for purging, although in many cases bailing may be the most practical method.

Four general types of equipment are used for well purging:

1. Grab samplers (including bailers, Kemmerer samplers, and syringe samplers)
2. Suction-lift pumps (including peristaltic pumps, surface centrifugal pumps, and vacuum pumps)
3. Electric submersible pumps (including centrifugal submersible pumps, helical rotor pumps, and gear pumps)
4. Positive displacement pumps (including gas–drive pumps, piston pumps, inertial lift pumps, and bladder pumps)

Once the type of pump or bailer is selected, the purge rate should be set low enough to avoid turbulent flow that causes entrainment of fines in the sand pack (over development of the well) and potentially causes stripping of volatile organic compounds. As a rule of thumb, the purge rate should not exceed the pumping rate or bailing rate used for well development. In addition, the purge rate should not exceed the recovery rate for the well. Typically, purging rates should not exceed 0.2 to 0.3 L/min.

Bailing. In many cases, bailing is the most convenient method for well purging and sampling. Bailers are constructed using a variety of materials such as PVC, stainless steel, polyethylene, and Teflon®. Care must be taken to select a specific type of bailer that suits a study's particular needs. Teflon® bailers are generally the most "inert," while PVC bailers are less expensive and sufficiently resistant to small-term exposure to most common contaminants. Bailers that are not chemically inert and easily decontaminated should not be used to purge and/or sample more than one well. Typically, a bailer can be dedicated to one well and can be hung in the well for subsequent purging and sampling events Disposable bailers, usually made of polyethylene, are sometimes more practical to use when decontamination time, expense, and the number of sampling events are considered.

Bailing presents three potential problems with well purging and sampling. First, increased suspended solids may be present in samples as a result of the turbulence caused by raising and lowering the bailer through the water column. High solids concentrations may require that total suspended solids (TSS) and the chemical character of the solids be evaluated during sample analyses. In addition, rapid bailing could cause the stripping of volatile organic compounds from the groundwater as a result of bailer agitation and/or groundwater cascading down the sides of the well screen.

Second, bailing may not be practical for wells that require that more than 20 gallons be removed during purging or for wells that are deeper than 50 ft below ground surface. Such bailing conditions mandate that long periods be spent during purging and sample collection, or that centrifugal pumps be used.

Third, bailing typically withdraws water from the top of the water column in the well and this water has already been exposed to the atmosphere. Exposure to the atmosphere can cause volatilization and reactions with carbon dioxide which cause subsequent lowering of the water's pH.

Suction-Lift Pumps. Suction-lift pumps are used to purge and sample groundwater from less than 30 ft below ground surface. Suction–lift pumps include peristaltic pumps, surface centrifugal pumps, and vacuum pumps. Vacuum pumps and surface centrifugal pumps (to a lesser extent) are not as appropriate as peristaltic pumps when collecting volatile-sensitive water samples.

Electric Submersible Pumps. Electric submersible pumps are commonly used to purge and sample groundwater from a variety of depths. Electric submersible pumps include centrifugal submersible pumps, helical rotor pumps, and gear pumps. The centrifugal submersible pumps are most commonly used, yet cause considerable water agitation due to the movement of the impeller(s). The gear pumps are the best-suited electric submersible pumps for groundwater purging and sampling and one of the best overall pumps for minimizing volatilization of groundwater samples.

Positive Displacement Pumps. Positive displacement pumps are widely available pumps often useful for groundwater purging and sampling. Positive displacement pumps include gas-drive pumps, piston pumps, inertial-lift pumps, and bladder pumps. The bladder pump is generally considered the best overall type of pump to collect groundwater samples for inorganic and/or organic analyses. Inertial lift pumps are ideal for well development, but should not be used to collect volatile-sensitive groundwater samples.

9.5.2.4 Purging and Sample-Collection Procedures — Method Specific

Once purging is complete, samples can be collected with either bailers or pumps. In many cases, a well may be purged using a pump and sampled using a bailer. This section discusses specific procedures for collecting samples using bailers and pumps.

Bailer Sampling. Obtain a decontaminated or new bailer and rope or cord made out of nylon, polypropylene, or other equivalent material. Tie a bowline knot or equivalent through the bailer loop. Test the knot for security and the bailer itself to ensure that all parts are intact before inserting the bailer into the well. Remove the protective wrapping from the bailer. Lower the bailer to the bottom of the monitoring well and cut the cord at a proper length. Bailer rope should never touch the ground surface at any time during purging and sampling.

Raise the bailer by grasping a section of cord using each hand alternately in a “windmill” action. This method requires the sampler’s hands to be kept approximately 2 to 3 ft apart and the bailer rope to be alternately looped onto or off each hand as the bailer is raised and lowered. Alternate methods may be used to raise the bailer including use of a reel or a plastic-lined bucket into which the rope is manually fed. Bailed groundwater is poured from the bailer into a graduated container to measure the purged water volume.

For slowly recharging wells, the bailer is generally lowered to the bottom of the monitoring well and withdrawn slowly through the entire water column. If possible, the water should be bailed at a rate slow enough so that it does not cascade down the sides of the well screen, which causes stripping of volatile organic compounds. Groundwater should be allowed to recover to 70 percent or greater of its static volume before a sample is collected.

Typically, water samples should be collected at or near the midpoint of the well screen. To collect a groundwater sample using a bailer, slowly lower the bailer into the water column, allowing the bailer to fill slowly from the bottom. Once the bailer has been lowered to approximately the mid-point of the screen, slowly raise the bailer to minimize creating turbulence in the well and minimize drawing fine-grained sediment into the well. Gently empty water directly from the full bailer into sample containers, taking care not to allow contact between the bailer and the sample container.

Pump Sampling. When selecting the appropriate pump to use for purging and sampling a well, there are two criteria that must be considered. First, the construction material of the pump and tubing should not contain

materials that interact with the constituents of interest and/or contain constituents that may cause the sample to have a false positive analysis. Second, if the sample is to be analyzed for volatile organic compounds, a pump that minimizes sample agitation and subsequent volatilization should be used. As noted previously, the most appropriate pumps under these conditions are the gear pump or the bladder pump.

Prior to inserting a pump into a monitoring well, it should be thoroughly decontaminated by pumping an Alconox™ or equivalent potable water mixture through the pump followed by pumping potable water, followed by a distilled or deionized water rinse. Tubing should be dedicated to a single well and should not be re-used.

During the collection of samples, the pumping rate should be approximately 0.1 L/min. If a greater pumping rate is used for purging, the pumping rate should be reduced during sampling. Groundwater should be pumped directly into the sample containers.

9.5.2.5 Sample Collection Procedures — Method Independent

The following are method-independent sample collection procedures:

- Collect samples intended for volatile organic analysis (VOA) first.
- Fill sample containers quickly and smoothly to avoid agitation, aeration, and loss of volatile components.
- To further avoid loss of volatile components, completely fill samples so that no headspace is present and cap securely with a Teflon®-lined lid.
- Collect samples for semivolatile, metal, or other analyses in the proper sample containers.
- Collect duplicate samples when QA/QC samples are needed for VOA. VOA samples typically consist of two sample vials, referred to as the sample set. Alternating between the primary sample set and the replicate sample set, completely fill each vial and cap immediately in the order shown below:
  - Fill vial #1 - primary sample set
  - Fill vial #1 - replicate sample set
  - Fill vial #2 - primary sample set
  - Fill vial #2 - replicate sample set
- Collect duplicate samples when QA/QC samples are required for sample analyses other than VOA by alternately filling the sample containers as in the VOA procedure, but fill containers incrementally instead of completely, continuing the filling procedure until the sample containers are full.
- Label all sample containers with the following information:
  - Project name and/or number
  - Field sample number
  - Depth interval (if applicable)
  - Initials of collector
  - Date and time of collection
  - Sample type and preservative (if any)

  Replicate and duplicate sample labels require only project name and/or number, field sample number, and sample type and preservative (if any).
- Place samples in coolers as soon as possible and, if required, store and transport them at <4°C (39°F), using frozen ice packs or double-bagged ice.
- Use protective packaging as dictated by the mode of transport.

- Record sample information in the field logbook and on the sample control log as soon as possible after sample collection, in accordance with the procedures set forth in the Quality Assurance Project Plan.
- Complete chain-of-custody forms and placed them in the cooler for shipment to the laboratory.
- If required by the SAP, place custody seals across cooler lids so that coolers cannot be opened without breaking the custody seal. Include the following information on the custody seals:
  - Collector's signature or initials
  - Date of sampling
- Ship samples to the laboratory for analysis, carefully observing all minimum holding-time requirements for degradable constituents.
- Set up a decontamination station near the sampling location to decontaminate equipment that will be reused at the next sampling location.

9.5.3 Aquifer Testing and Analysis SOP

All monitoring wells added to the monitoring well network will be installed and completed in accordance with the NMED Monitor Well Construction Guideline.

9.5.3.1 General

An aquifer test or "pumping test" is used to determine the hydraulic properties of an aquifer by pumping one well for a specified length of time while collecting periodic water level measurements. Aquifer properties that can potentially be estimated using a pumping test include transmissivity (i.e., hydraulic conductivity multiplied by aquifer thickness), horizontal or vertical hydraulic conductivity, coefficient of storage, specific yield, and confining layer leakage. The two types of pumping tests most useful in determine aquifer hydraulic properties are the constant rate pumping test and the step-drawdown pumping test. The latter is best suited to determining the well's reduction in specific capacity (i.e., specific yield per unit of drawdown) with increasing yields, while the former is the most widely used pumping test in determining the transmissivity and storage values for an aquifer.

A pumping test can be performed using only the pumping well; however, specific information such as aquifer storage will not be obtainable. The use of observation wells in obtaining additional drawdown and/or recovery data over time is recommended whenever possible, especially when information on aquifer storage, anisotropy, vertical leakage, or the distance to a recharge or no-flow (i.e., barrier) boundary is needed.

In comparison to a slug test, a pumping test is representative of a much larger area and is therefore a better estimation of the hydraulic parameters of an aquifer. Conversely, a pumping test requires a greater commitment of resources (time, money, and equipment) and produces large volumes of water that usually need to be containerized during the test.

Several analytical solution methods are available. Two of the most widely used are the Theis (1935) equation and the Cooper and Jacob (1946) equation (often referred to as the Jacob straight-line method). A multitude of pumping test analysis software is available, though users are cautioned to be sure to understand all model or spreadsheet inputs as well as the assumptions of the governing equations. Far more extensive information on the design and analysis of pumping tests is covered in texts including, to name a few, Driscoll (1986), Kruseman and de Ridder (1991), Dawson and Istok (1991), Osborne (1993), and Fetter (1988).

Analyses of pumping tests require the following assumptions:

- The water-bearing formation is homogeneous, isotropic, uniform in thickness, and infinite in areal extent.
- The formation receives no recharge from any source.
- The pumping well (i.e., the screened section) is fully penetrating the entire thickness of the water-bearing formation.
- The water removed from storage is discharged instantaneously when the head is lowered.
- The pumping well is 100 percent efficient.
- All water removed from the well comes from aquifer storage.
- Laminar flow exists throughout the well and aquifer.
- The water table or potentiometric surface has no slope.

In reality, most pumping tests violate many of the above-mentioned assumptions to some degree or another. However, it is important to take all feasible measures to limit the extent of these violations whenever possible, and discussing these assumptions and any possible violations to them is important to any pumping test report.

Design Considerations. Prior to performing an aquifer pumping test, all available site and regional hydrogeologic information should be assembled and evaluated. If retrievable, such data should include groundwater flow direction(s), hydraulic gradients, other geohydraulic properties, site stratigraphy, well construction details, regional water level trends, and the performance of other pumping wells in the vicinity of the test area. This information is used to select test duration, proposed pumping rates, and pumping well and equipment dimensions.

The precise location of an aquifer test is chosen to be representative of the area under study. In addition, the location is selected on the basis of numerous other criteria, including:

- The size of the investigation area.
- Uniformity and homogeneity of the aquifer.
- Distribution of contaminant sources and dissolved contaminant plumes.
- The location of known or suspected recharge or barrier boundary conditions.
- The availability of pumping and/or observation wells of appropriate dimension and screened at the desired depth.
- Requirements for handling discharge.

The dimensions and screened interval of the pumping well must be appropriate for the tested aquifer. For example, the diameter of the well must be sufficient to accommodate pumping equipment capable of sustaining the desired flow rate at the given water depth. In addition, if testing a confined aquifer that is relatively thin, the pumping well should be screened for the entire thickness of the aquifer. For an unconfined aquifer, the wells should be screened at least in the bottom one- to two-thirds of the saturated zone and they may be screened throughout the entire thickness of the saturated zone.

Any number of observation wells may be used. The number chosen is contingent upon both cost and the need to obtain the maximum amount of accurate and reliable data. If at least three observation wells are to be installed and there is a known boundary condition, the wells should be configured such that water levels can be monitored both perpendicular and parallel to the boundary, with the pumping well at the intersection of the two well lines. If two observation wells are to be installed, they should be placed in a triangular pattern, non–equidistant from the pumping well. If observation wells are placed at 90° angles from the pumping well, radial anisotropy can be easily calculated. When observation wells are installed for aquifer testing purposes, they should be located at distances and depths appropriate for the planned method for analysis of the aquifer test

data. Observation well spacing should be determined based upon expected drawdown conditions that are the result of the studies of geohydraulic properties, proposed pumping test duration, and proposed pumping rate.

Equipment. The equipment necessary to conduct a pumping test includes:

- A pump (suited for site conditions and requirements of the test)
- Water level measuring devices (pressure transducers and/or electronic water level indicators) accurate to at least 0.01 ft
- A flow meter with totalizer (something as simple as a graduated bucket can also suffice, especially as backup)
- A digital watch with stopwatch function (used to keep time and to help determine discharge rate when using graduated containers)
- An electrical source (generator or electrical receptacle on site)
- An electronic data recorder programmed to suitable data collection intervals)
- A barometer
- Water quality meter(s) for noting changes as a function of capture zone
- Hose or pipe to route pumped water away from the test area
- A gate valve
- An adequately sized tank/container for storing water
- A portable computer for preliminary analysis of data (optional)
- Field forms and logbook
- Pen and paper
- Backup equipment if feasible

Pumping equipment should conform to the size of the well and be capable of delivering the estimated range of pumping rates. The selection of flow meter, gate valve, and water transfer lines should be based on anticipated rates of water discharge. Both the discharge rate and test duration should be considered when selecting a tank for storing discharge water if the water cannot be released directly to the ground, sanitary sewer, storm sewer, or nearby water treatment facility.

Pumping-Test Preperations. If feasible for the site, slug tests or preliminary pumping tests (constant-rate or step drawdown) should be performed on the pumping well prior to the actual test. The preliminary pumping should determine the maximum drawdown in the well, and the proper pumping rate should be determined by step drawdown testing. If the discharge rate varied by less than 5 percent (i.e., a constant-rate-pumping test), the time versus drawdown data from the pumping well can be used to estimate aquifer transmissivity. The preliminary pumping will also provide redevelopment of the pumping well by removing fines from the adjacent formation and from the filter pack. Redevelopment of the pumping well will improve well efficiency during the pumping test and thus will allow for a better estimation of the aquifer's hydraulic properties. The aquifer should then be given time to recover before the actual pumping test begins (as a rule–of–thumb, one day). A record should be maintained in the field logbook to track when pumping and discharge of other wells in the area occurs and whether the wells' radii of influence intersect the cone of depression of the test well.

Barometric changes may affect water levels in wells, particularly in semiconfined and confined aquifers. Therefore, it is advisable to monitor (perhaps hourly) the barometric pressure and water levels in key wells at least 24 hours (if possible) prior to performing a pumping test. If a groundwater fluctuation trend is apparent, the barometric pressure should be used to develop curves depicting the change in water level versus time. These curves should be used to correct the water levels observed during the pumping test. Groundwater levels and barometric pressures in the background should continue to be recorded throughout the duration of the

test. If dataloggers with transducers are used, backup field measurements should be collected in case of datalogger malfunction. All measurements and observations should be recorded in a field logbook or on appropriate field forms.

All equipment should receive calibration, function checks, and fresh or charged batteries if needed.

Conducting the Pumping Test. Prior to the start of the pumping test, the following checks should be made:

- Ensure all piping, valves, and flow meters are properly installed.
- Ensure that all containers are in place to capture all pumped water.
- Ensure that the energy needs (batteries, electricity, or gas) for all equipment are provided, including backup energy sources for key equipment.
- Verify all equipment is present and place it at locations where it will be most needed.
- Verify the pump intake is located at the proper interval in the pumping well.
- Verify all transducers are placed at the proper depth and are properly secured so they will not move or be susceptible to contact from site personnel.
- Verify the datalogger is properly programmed to record (typically logarithmically).
- Lower electronic water level tapes to just above the water levels inside each well.
- Warm up all equipment (such as a generator) that perform better after initial operations.
- Ensure all personnel and field forms are in their start-of-test locations.

Immediately prior to starting the pump, the water levels should be measured and recorded for all wells to determine the static-water levels upon which all drawdowns will be based. Dataloggers should be reset for each well to a starting water level of 0.00 foot. At this time, a pumping test is initiated by starting the datalogger and then starting the pump. The datalogger needs to be started at least a split second before the pumping begins. Immediately afterwards, the time that pumping started needs to be recorded along with water level readings, especially at or near the pumping well. A suggested schedule for recording water level measurements made by hand is as follows:

- 0 to 10 minutes – 0.5, 1.0, 1.5, 2.0, 2.5, 3.0, 4.0, 5.0, 6.0, 7.0, 8.0, 9.0, and 10 minutes (It is important in the early part of the test to record with maximum accuracy the time at which readings are taken.)
- 10 to 100 minutes – 10, 15, 20, 25, 30, 40, 50, 60, 70, 80, 90, and 100 minutes
- 120 minutes to end of test – every 1 hour (60 minutes)

At least 10 measurements of drawdown for each log cycle of time should be made both in the test well and the observation wells. Dataloggers can be set to record in log time, which is very useful for data analysis. When logging data by hand, there should initially be sufficient field personnel to station one person at each well used in the pumping test. After the first two hours of pumping, two people are usually sufficient to complete most simplistic tests. It is advisable for at least one field member to have experience in the performance of pumping tests, and for all field personnel to have a basic familiarity with conducting the test and gathering data.

The discharge rate should be measured frequently throughout the test with a flow meter equipped with a totalizer and controlled to maintain a constant pump. This can be achieved, in part, by using a control valve. If used properly, the flow control valve can be pre-set for the test and will not have to be adjusted during pumping. When the pumping is complete, the total gallons pumped are divided by the time of pumping to obtain the average discharge rate for the test.

For a confined aquifer, if possible, the water level in the pumping well should not be allowed to fall below the bottom of the upper confining stratum during a pumping test. The pitch or rhythm of the pump or generator

provides a check on performance. If there is a sudden change in pitch, the discharge should be checked immediately and proper adjustments to the control valve or the generator engine speed should be made, if necessary. Do not allow the pump to break suction during the test. If the pump stops working during the test, make necessary adjustments and restart the test after the well has stabilized.

Water pumped from an aquifer during a pumping test should be disposed of in such a manner as to not allow the aquifer to recharge during the test. This means that the water must be piped away from the well and associated observation wells. Also, if contaminated water is pumped during the test, the water must be stored and treated or disposed of according to project specifications. The discharge water may be temporarily stored in drums; a lined, bermed area; or tanks. If necessary, it should be transported and staged in a designated secure area.

Field personnel should be aware that electronic equipment sometimes fails in the field. It is a good idea to record key data in the field logbook or on field forms as the data are produced. That way, the data are not lost should the equipment fail.

The total pumping time for a test depends on the type of aquifer and degree of accuracy desired. Economizing on the duration of pumping may yield less reliable results. It is always recommended to pump long enough to ensure the cone of depression achieves a stabilized condition. The cone of depression will continue to expand at an ever-decreasing rate until recharge of the aquifer equals the pumping rate, and a steady-state condition is established. The time required for steady-state flow to occur varies considerably from site to site. If steady-state conditions cannot be achieved in a reasonable time frame for the project, consider a test duration of at least 24 hours. A longer duration of pumping may reveal the presence of boundary conditions or delayed yield.

Use of portable computers allows time/drawdown plots to be made in the field. If dataloggers are used to monitor water levels, the electronic data can be reviewed by scrolling with the datalogger screen or via a portable computer. It is advisable to download the water level data before transporting the datalogger from the site.

9.5.4 Monitoring Well Installation

If additional monitoring wells are required, SOPs for Monitoring-Well Installation and Hollow-Stem Auger Drilling will be followed. These SOPs will be submitted to the MMD prior to installation of additional wells and will meet state requirements for well installation.

9.6 Parameters to be Analyzed

See Table 9-3 for analytical parameters and analysis methods.

9.7 Maps Showing Proposed Sampling Locations

Figure 9-10 illustrates the current groundwater monitoring network for the baseline characterization study. This network has grown from the initial sampling program conducted in January 2010 (Figure 9-11). The wells have been categorized according to the aquifer being monitored (i.e., Quaternary alluvial aquifer, Santa Fe Group aquifer, or Bedrock aquifer) if known.

9.8 Laboratory and Field Quality Assurance Plans

The groundwater sample and data collection will be conducted in accordance with the Quality Assurance Project Plan (QAPP) (see Attachment 1) and the procedures for sampling and recording observations in a logbook. The samples will be properly preserved and sent to an accredited analytical laboratory. Water samples will be

collected from Site wells and private wells. Fieldwork to determine which of these wells exist and can be sampled and measured is subject to owner approval. Comments made by the well users visited will be recorded in the logbook.

The parameters of pH, temperature, dissolved oxygen, turbidity, and specific conductivity will be measured in the field at the time of collection for each well. The field instruments will be calibrated by the manufacturer with calibration checks conducted by the user. The calibration certificates will be filed and the field checks will be recorded in the logbook. Groundwater quality control samples will include random duplicate samples.

The Field Leader for the aquifer pump test will be experienced and the field members will be trained to the procedures. The procedures to be used have been developed by professionals in groundwater hydrology. The instruments used for pump tests will be calibrated by the manufacturer. A calibration certificate will be retained as a record. The main instruments used for the pump test are the pressure transducers, E-tape, vented cable, and barometric pressure gage. A preliminary step drawdown test a few days prior to the pump test will afford the field hydrologists a chance to verify that the meter, discharge system, transducers, and generator are working properly.

Water level measurements will be monitored manually with an E-tape as a check on transducer measurements and to ensure that a back-up set of data are available in case of transducer failure. The E-tape and transducers will be compared several times before the pump test to determine the difference in readings. This difference will be recorded. During and after the pump test, several more checks will be made to compare the reading differences. The differences are typically minimal (inches), but will be used as an adjustment for the data interpretation. A similar comparison will be noted for the vented cable and the barometric pressure gage readings. Prior to installation, the transducer probe and cable will be inspected for damage, un-kinked, and cleaned.

The transducer data will be downloaded to a laptop computer on a regular basis. E-tape comparison readings will be taken, often during the initial pumping and again during the initial recovery period and numerous times during the days of pumping. For safety reasons, at least two people will be on-Site during the entire pumping portion of the test.

Personnel will maintain a field logbook in which are recorded weather, field conditions, nearby pumping wells, and any circumstances which influence test results or would be useful to know during interpretation of test results.

9.9 Discussion in Support of Proposal

The main objective of the proposed groundwater data collection program is to obtain the data necessary to determine potential impacts of mining activities, including mine dewatering, on local and regional groundwater systems. As this Site has been mined before and has been through several permitting cycles, historical data will play an important role in the evaluation of potential impacts caused by new mining. Therefore, all impact analysis performed using data collected in accordance with this SAP will be supported by concurrent evaluation utilizing historical data where available.

The water quality sampling program will provide current water quality data for a monitoring well network that includes wells with a history of sampling. Current and historical data will be statistically evaluated to determine a range of baseline groundwater quality values for key constituents.

The water level measurement program will provide recent baseline data on local water levels. Existing aquifer pumping test data will be used to obtain hydraulic information and additional tests will be performed as necessary.

The potential impacts of groundwater withdrawals from the Bedrock and Santa Fe Group aquifer system on groundwater levels will be determined using a three-dimensional groundwater flow model. The groundwater flow model will incorporate historical data as well as data collected under this SAP. Defensible, site-specific conceptual and numerical flow models are critical to NMCC for securing the necessary permits and stakeholder acceptance for assessment of potential impacts from dewatering, pit lake evolution, and leaching from waste rock facilities and the tailings impoundment. The potential impacts on water supply wells will be evaluated with this model as well as the potential impacts of the discharge of dewatering water on the alluvial aquifers in Las Animas and Percha Creeks. The groundwater model will be calibrated under pre-development and transient conditions and will represent the most reasonable tool available for estimating impacts of dewatering and appropriation of groundwater on both a local and regional scale.

Given that the existing groundwater flow model developed for Alta Gold (ABC, 1996; ABC, 1997; ABC, 1998b) received significant criticism, NMCC will develop a revised conceptual model for groundwater flow that will be used to construct a MODFLOW numerical model which will in turn be used to assess impacts from mine operations. The revised conceptual model will be primarily based on data collected as part of this baseline characterization work, including historical data that are statistically valid.

A new numerical flow model will be constructed, calibrated, and applied to assess potential impacts from mine dewatering and from post-mining groundwater rebound. This model, which we expect will be a sub-regional scale model, will focus on an area sufficiently large enough to defensibly determine water level and flux changes on identified resources. NMCC proposes to use either MODFLOW or MODFLOW–SURFACT as the flow model code because they have been accepted by both state and federal agencies for mining impact assessments, among other uses. The geologic model from the previous flow model will serve as the foundation for a revised geologic model to be developed by NMCC in close collaboration with MMD staff. Estimates of recharge, evapotranspiration, and other boundary conditions from the previous model will also serve as a starting point for the new numerical flow model.

To assess potential impacts, NMCC will develop and calibrate numerical flow models for the sub-regional scale that represent different periods of mine activity. First, NMCC will construct and calibrate a steady state flow model that represents pre-mining conditions. A transient model that represents mining activities to the present day will be constructed from the steady state model and calibrated to available head and flux data. Potential impacts will be determined from the final transient model that simulates mine activities such as pit deepening and dewatering as well as the post-mining period's groundwater rebound. Changes in fluxes to surface water bodies and water levels will be used as the performance metrics for the impact assessment.

NMCC efforts for the groundwater impact assessment will include:

- Develop a conceptual model for groundwater flow through the site and its vicinity, including groundwater and surface interactions, and construct a water balance for the site vicinity.
- Present the conceptual model and preliminary numerical model domain to relevant agencies.
- Construct and calibrate a steady state flow model to represent pre-mining conditions.
- Construct and calibrate a transient flow model that simulates historical mine development to the present day.

- Construct and calibrate a transient flow model that estimates drawdown from proposed mine dewatering and groundwater rebound following mine reclamation as well as any potential impacts to groundwater and surface water resources.
- Present the preliminary numerical model results to the relevant agencies.

9.10 References

Adrian Brown Consultants (ABC), 1996, Copper Flat project hydrology impact evaluation report.

——— 1996b, Appendix G of Copper Flat project hydrology impact evaluation report – Tailings Dam Area Pumping Test, prepared for SRK, Report 1356A/960909.

——— 1997, Copper Flat hydrology impact evaluation post-hearing submittal exhibits, including revised appendices O, F, and L: Report 1356A.970326.

——— 1998, Copper Flat Las Animas Creek pumping test: Project 13560, prepared for Alta Gold Co.

——— 1998b, Hydrologic impact evaluation for the proposed action, Copper Flat project: Report 1356A.981219. Prepared for Alta Gold Co., December 19, 1998.

Atkins Engineering Associates, Inc. (Atkins), 1992, Engineering analysis of shallow aquifer tests for Saladone Well and Shipping Pen Well within the Ladder Ranch vicinity, 44 p. Prepared for Turner Enterprises, Incorporated, Gallatin Gateway, Montana, December 1992.

Bureau of Land Management (BLM), 1996, Draft environmental impact statement (DEIS), Copper Flat Project: Las Cruces, N. Mex., U.S. Department of the Interior. Prepared by ENSR, Fort Collins, Colo.

——— 1999, Preliminary final environmental impact statement, Copper Flat project: Las Cruces, N. Mex., U.S. Department of the Interior, 491 p. Prepared by ENSR, Fort Collins, Colo.

Cooper, H.H., Jr. and Jacob, C.E., 1946, A generalized graphical method for evaluating formation constants and summarizing well-field history: Transactions, American Geophysical Union, v. 27, p. 526-534.

Davie, W., Jr., and Spiegel, Z., 1967, Las Animas Creek hydrographic survey report, geology and water resources of Las Animas Creek and vicinity, Sierra County, New Mexico: New Mexico State Engineering Report.

Dawson, K.J., and Istok, J.D., 1991, Aquifer testing: design and analysis of pumping and slug tests: Chelsea, Mich., Lewis Publishers, 344 p.

DBS&A, 1998, Environmental Evaluation report, Copper Flat project. Prepared for the Energy, Mining and Natural Resources Department, Mining and Minerals Division, Santa Fe, New Mexico.

Driscoll, F.G., 1986, Ground water and wells (2d ed.): St. Paul, Minn., Johnson Division, 1089 p.

Fetter, C.W., 1988, Applied hydrogeology (2d ed.): Columbus, Ohio, Merrill Publishing Company, 592 p.

Goff, 1998.

Greene, D.K., and Halpenny, L.C., 1976, Report on development of ground-water supply for Quintana Minerals Corporation Copper Flat Project, Hillsboro, New Mexico: Tucson, Water Development Corporation, 32 p.

Hawley, J.W., Kennedy, J.F., Ortiz, M., and Carrasco, S., 2005, Digital Hydrogeologic Framework Model of the Rincon Valley and Adjacent areas of Dona Ana, Sierra, and Luna Counties, NM: Addendum to the Creation of a Digital Hydrogeologic Framework Model of the Mesilla Basin and Southern Jornada del

Muerto Basin, New Mexico Water Resources Research Institute, New Mexico State University, Technical Report No. 332, June 2004, 12 p.

Kruseman, G.P., and de Ridder, N.A., 1991, Analysis and evaluation of pumping test data (2d ed.): Wageningen, The Netherlands, International Institute of Land Reclamation and Improvement, 377 p.

Lozinsky, R.P. and J.W. Hawley. 1986. The Palomas Formation of south-central New Mexico -- a formal definition. New Mexico Geology. 8. 4, p: 73-82.

Minton, 1961.

Murray, C. R., 1959, Ground-water conditions in the nonthermal artesian-water basin south of Hot Springs, Sierra County, New Mexico: New Mexico State Engineering Technical Report 10.

Newcomer, R. W. Jr., Shomaker, J.W., and Finch, S.T., Jr., 1993, Hydrologic assessment, Copper Flat project, Sierra County, New Mexico. Prepared for Gold Express Corporation.

Osborne, P.S., 1993, Suggested operating procedures for aquifer pumping tests: U.S.E.P.A. Office of Research and Development and Office of Solid Waste and Emergency response, EPA/540/S-93/503, 23 p.

Raugust, J.S., 2003, The natural defenses of Copper Flat, Sierra County, New Mexico: New Mexico Bureau of Geology and Mineral Resources Open-file report 475, Socorro, N. Mex., New Mexico Institute of Mining and Technology.

Seager, W.R. and J.W. Hawley. 1973. Geology of Rincon quadrangle, New Mexico. New Mexico Bureau of Mines and Mineral Resources Bulletin 102. 56 p.

Seager, W.R., Shafiqullah, M., Hawley, J.W., and Marvin, R.F., 1984, New K-Ar dates from basalts and the evolution of the Southern Rio Grande Rift: Geological Society of America Bulletin, v. 95, p.87-99.

Segerstrom, K. and Antweiler, J.C., III, 1975, Placer-gold deposits of the Las Animas District, Sierra County, New Mexico: USGS OFR 75-206.

Sergent, Hauskins, and Beckwith (SHB), 1980, Geotechnical and design development report, tailings dam and disposal area, Quintana Minerals Corporation, Copper Flat Project, Golddust, New Mexico. Technical report prepared for Quintana Minerals.

SRK Consulting, 2010, Copper flat project, Hillsboro, New Mexico, Ground water monitoring well exceedences, Report as of January 07, 2010.

Steffen Robertson and Kirsten (U.S.), Inc. (SRK), 1995, Copper Flat Mine hydrogeological studies. Copper Flat, New Mexico: Steffen Robertson and Kirsten, Inc.

——— 1997a, Copper Flat post-hearing submittal exhibits: Steffen Robertson and Kirsten, Inc.

——— 1997b, Copper Flat Mine-Compilation of pit lake studies: Steffen Robertson and Kirsten, Inc., Project 68610. Prepared for Alta Gold Co.

Theis, C.V., 1935, The relation between the lowering of the piezometric surface and the rate and duration of discharge of a well using ground water storage: Transactions, American Geophysical Union, v. 16, p 518-524.

Wilson, C.A., Orr, C.A, White, R.R., and Roybal, R.G., 1981, Water resources of the Rincon and Mesilla Valleys and adjacent areas, New Mexico: New Mexico State Engineering Technical Report 43.

Figures



0 7.5 15 30

Miles

Basin Boundaries:
RGIS website/NMOSE
Imagery Information:
Landsat imagery from
University of Maryland NLCD

Legend

- City/Town
- Site Location
- Road
- OSE Declared Basin
  - Lower Rio Grande
  - Las Animas

Figure 9-1
Lower Rio Grande Basin
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\9_groundwater\9-1_LRG_basins.mxd 07/30/2010



from John W. Shomaker, Inc., 1993

Figure 9-2
Conceptual Model of Groundwater Flow System
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\7_geology\9-2_concep_hydrogeo.mxd 07/21/2010



N
W E
S

Watersheds:
USGS Hydrologic Unit Map
Mine Boundary:
Tom Van Bebber
Imagery Information:
-USGS 7.5-Minutes County DOQQ mosaic
Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

0 3,500 7,000 14,000 21,000
Feet

Legend

- Identified Spring
- Proposed Mine Permit Boundary

Watersheds
- Caballo
- El Paso-Las Cruces
- Sub-Watershed

Figure 9-3
Spring and Stream Locations
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\8-SurfaceWater\8-1_surface_wtr_locations.mxd 08/26/2010

00191



4300 WATER TABLE ELEVATION

NORTH

0 8,000 16,000

FEET

from ABC, 1998B

Figure 9-4
Water Level Contours
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\9_groundwater\9-4_wtr-level-contours.mxd 07/29/2010



from ABC, 1997

Figure 9-5
Water Level Map of
Copper Flat Pit Area

New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\9_groundwater\9-5_wtr-table-map.mxd 07/29/2010



	GWQ96-22		PIT LAKE		GWQ96-23	
	JULY '96	AUG '97	AUG '95	AUG '97	APR '97	AUG '97
pH	7.5	7.65	8.31	8.16	7.89	7.68
TDS	700	700	4707	5021	770	920
SO_4	250	230	3170	3100	150	410
Cu	<0.025	<0.025	<0.025	0.050	<0.025	<0.025
Fe	<0.05	<0.05	<0.025	<0.05	6.5	0.82

Figure 9-6
Conceptual Model of Pit Lake Monitoring Well Relationship with Water Quality Reports

New Mexico Copper Corporation

from SRK, 1998

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\9_groundwater\9-6_well_WQReports.mxd 07/29/2010



from SRK, 1995

Figure 9-7
Conceptual Design,
Tailings Seepage Control

New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\9_groundwater\9-7_seepage-control.mxd 07/29/2010

A

A'



LEGEND:

QUATERNARY
- Qvy
- Qvo
- Stream Alluvium

TERTIARY
- Tsfp
- Tsfp Clay
- Palomas Formation
- Tsf – Rincon Valley Formation
- Tv – Tertiary Volcanics

CRETACEOUS
- Ka
- Kis
- Volcanics and Intrusives

PALEOZOIC
- Bedrock Carbonate and Clastic Rocks

SOURCES:
(1) HARLEY (1934)
(2) SEAGER ET AL. (1982)
(3) HEDLUND (1977)
(4) ALMINAS ET AL. (1975)

SCALE IN FEET
VERTICAL: 1500 – 0'
HORIZONTAL: 6000 – 0'

(see Figure 7-1 for cross section location)

from BLM, 1999

Figure 9-8
Schematic Geologic Cross Section (A-A')
New Mexico Copper Corporation



N
W E
S

Well Locations:
SRK or OSE
Mine Boundary:
Tom Van Bebber
Imagery Information:
-USGS 7.5-Minutes County DOQQ mosaic
Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

0 3,000 6,000 12,000 18,000
Feet

Legend

- Road
- Project Well
- Proposed Mine Permit Boundary
- NM OSE Wells (Use)
  - Domestic
  - Irrigation
  - Stock

Figure 9-9
Regional Groundwater Well Locations
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\9_groundwater\9-9_Regional GWwells.mxd 09/07/2010



Well Locations:
SRK or OSE
Mine Boundary:
Tom Van Bebber
Imagery Information:
-USGS 7.5-Minutes County DOQQ mosaic
Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

0 3,000 6,000 12,000 18,000
Feet

Legend

Proposed Monitoring Well
Aquifer
- Crystalline Bedrock
- Qauternary Alluvium
- Santa Fe Group
- Unknown

- Water Level Only
- Water Level & Water Quality
- Proposed Mine Permit Boundary
- Road

Figure 9-10
Proposed Monitoring Well Program
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\9_groundwater\9-10_ProposedGWwells.mxd 09/07/2010



N
W E
S

0 750 1,500 3,000 4,500

Feet

Mine Boundary:
Tom Van Bebber
Imagery Information:
-USGS 7.5-Minutes County DOQQ mosaic
Sierra County, 2009
Projection Information:
-Geographic, WGS 1984

Legend

Aquifer
- Crystalline Bedrock
- Qauternary Alluvium
- Santa Fe Group

- Proposed Mine Permit Boundary
- Road

Figure 9-11
Wells Sampled in January 2010
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\9_groundwater\9-11_Jan2010.mxd 09/07/2010

Tables

Table 9-1
Groundwater Sampling and Data Analysis Plan

Proposed Activity	Purpose of Activity
Perform a field verification survey of monitoring wells identified by previous investigators, measure depths to water and total depths of wells.	Confirm existing monitor well network in order to evaluate need for additional wells in key aquifers and finalize baseline monitoring well network
Install background monitoring wells in Santa Fe and alluvial aquifers.	Establish background water quality for Santa Fe Group and alluvial aquifers
Continue water level measurement and sampling of groundwater monitoring network.	Establish baseline (pre-mining) water quality and water levels for the Bedrock, Santa Fe Group, and Alluvial Aquifers
Install additional monitor wells as necessary to meet to address data gaps	Further define potential impacts from earlier mining activities and obtain additional pre-mining water levels
Determine hydraulic parameters for Bedrock, Santa Fe Group, and Alluvial aquifers	Obtain necessary input for groundwater model to evaluate drawdown from mine dewatering and production well activities

Table 9-2

Proposed Monitoring Wells for Water Quality Sampling and Water Level Measurements

Well Name	Total Depth (ft bgs)	Top of Screen (ft bgs)	Bottom of Screen (ft bgs)	Year Drilled	Diameter (inches)	Inferred Aquifer	Water Quality Sample	Water Level Measurement
Animas Station 8 Well	NA	NA	NA	NA	NA	ND		X
Delores Well	NA	NA	NA	1932	NA	ND		X
GWQ-10	121.0	NA	NA	1981	3	Santa Fe Group		X
GWQ-11	84.5	NA	NA	1981	3	Quaternary Alluvium		X
GWQ-12	130.0	NA	NA	1981	3	Santa Fe Group		X
GWQ94-13	112.0	74.0	104.5	1994	5	Santa Fe Group	X	X
GWQ94-14	158.0	127.5	157.5	1994	5	Santa Fe Group	X	X
GWQ94-15	148.0	112.0	142.0	1994	5	Santa Fe Group	X	X
GWQ94-16	45.0	25.0	45.0	1994	5	Quaternary Alluvium	X	X
GWQ94-17	158.0	120.0	150.0	1994	5	Santa Fe Group	X	X
GWQ94-18	60.0	10.0	50.0	1994	4	Quaternary Alluvium	X	X
GWQ94-19	54.0	10.0	50.0	1994	4	Quaternary Alluvium	X	X
GWQ96-22A	240.0	170.0	240.0	1996	2	Bedrock	X	X
GWQ96-23A	100.0	50.0	100.0	1996	2	Bedrock	X	X
Highway Well	NA	NA	NA	1934	NA	Santa Fe Group		X
IW-1	49.0	NA	49.0	1982	4	Quaternary Alluvium		X
IW-2	45.0	NA	45.0	1982	4	Quaternary Alluvium	X	X
IW-3	45.0	NA	45.0	1982	4	Quaternary Alluvium		X
Ladder Airstrip Well	NA	NA	NA	NA	NA	ND		X
Lower Percha Artesian	NA	NA	NA	NA	NA	ND		X
MW-1	1000.0	350.0	1000.0	1975	8	Santa Fe Group	X	X
MW-11	65.0	12.0	32.0	1994	8	Quaternary Alluvium	X	X

Well Name	Total Depth (ft bgs)	Top of Screen (ft bgs)	Bottom of Screen (ft bgs)	Year Drilled	Diameter (inches)	Inferred Aquifer	Water Quality Sample	Water Level Measurement
MW-2	1500.0	133.0	1500.0	1975	8	Santa Fe Group	X	X
MW-4	2000.0	123.0	1500.0	1975	8	Santa Fe Group	X	X
MW-5	1380.0	306.0	1000.0	1975	8	Santa Fe Group	X	X
MW-6	1112.0	310.0	1000.0	1975	8	Santa Fe Group	X	X
MW-8	1004.0	366.0	1000.0	1975	8	Santa Fe Group	X	X
MW-9	250.0	200.0	250.0	1994	8	Santa Fe Group	X	X
NP-1	115.0	NA	106.0	1981	4	Santa Fe Group	X	X
NP-2	115.0	NA	110.0	1981	4	Santa Fe Group	X	X
NP-3	109.5	NA	100.0	1981	4	Santa Fe Group	X	X
NP-4	117.0	NA	117.0	1981	4	Santa Fe Group	X	X
NP-5	44.0	24.0	39.0	1981	4	Quaternary Basalt	X	X
Saladone Well	NA	NA	NA	NA	NA	Quaternary Alluvium		X
Upper Percha Well	NA	NA	NA	NA	NA	ND		X

Notes:

NA = not available

ND = not determined

Table 9-3

Analytical Parameters and Analysis Methods for Groundwater Samples

Analytical Parameter	Analysis Method	Lab Detection Limit (mg/L unless noted)
Anions		
Fluoride	EPA Method 300.0	0.1
Chloride	EPA Method 300.0	0.1
Nitrogen, Nitrite (as N)	EPA Method 300.0	0.1
Nitrogen, Nitrate (as N)	EPA Method 300.0	0.1
Sulfate	EPA Method 300.0	0.5
Dissolved Metals		
Aluminum	EPA Method 200.7	0.02
Antimony	EPA Method 200.8	0.005
Arsenic	EPA Method 200.8	0.02
Barium	EPA Method 200.7	0.002
Beryllium	EPA Method 200.7	0.002
Boron	EPA Method 200.7	0.04
Cadmium	EPA Method 200.7	0.002
Calcium	EPA Method 200.7	0.50
Chromium	EPA Method 200.7	0.006
Cobalt	EPA Method 200.7	0.006
Copper	EPA Method 200.7	0.0003
Iron	EPA Method 200.7	0.02
Lead	EPA Method 200.7	0.005
Magnesium	EPA Method 200.7	0.50
Manganese	EPA Method 200.7	0.002
Mercury	EPA Method 7470 CVAA	0.0002
Molybdenum	EPA Method 200.7	0.008
Nickel	EPA Method 200.7	0.01
Potassium	EPA Method 200.7	1.0
Selenium	EPA Method 200.8	0.02
Silicon	EPA Method 200.7	0.08
Silver	EPA Method 200.7	0.005
Sodium	EPA Method 200.7	0.5

Analytical Parameter	Analysis Method	Lab Detection Limit (mg/L unless noted)
Thallium	EPA Method 200.7	0.01
Titanium	EPA Method 200.7	0.005
Uranium	EPA Method 200.8	0.01
Vanadium	EPA Method 200.7	0.005
Zinc	EPA Method 200.7	0.005
Solids		
Total Suspended Solids (TSS)	SM 2540D	1.0 µg/L
Total Dissolved Solids (TDS)	SM 2540C	10
Alkalinity		
Alkalinity, total (as $CaCO_3$)	SM 2320B	20
Carbonate	SM 2320B	20
Bicarbonate	SM 2320B	20
Other		
pH	150.1	12.45
Specific Conductance	120.1	0.01 µS/cm
Cyanide	Kelada-01	0.005

Note: NA = not applicable as sample will not be analyzed for a given parameter.

Table 9-4
Groundwater System Characteristics (from SRK, 1995)

Unit	Crystalline Bedrock	Santa Fe Group System	Quaternary Alluvium
Material	Rock	Alluvium	Alluvium
K_h (ft/yr)	10	1,000 – 4,000	~78,000
K_v (ft/yr)	10	1-40	~7
Porosity	2%	25%	25%
Storage Coefficient	1%	0.1 – 0.001%	0.1%
Depth of Unit	>2,000’	0 – 2,000’+	~30’
Depth to Water	0’-50’	50’-300’	~5’
Notes	Variable, fractured	Higher K to east; heterogeneous	Perched, low communication

Table of Contents

10 Historical and Cultural Properties Survey 10-1
10.1 Introduction and Background 10-1
10.2 Sampling Objectives 10-2
10.3 Sampling Frequency 10-3
10.4 List of Data to be Collected 10-3
10.5 Methods of Collection 10-3
10.5.1 Site Definition 10-3
10.5.2 Site Recording 10-4
10.5.3 Isolated Manifestation Recording 10-5
10.5.4 Mapping 10-5
10.5.5 Historical Cultural Properties 10-5
10.6 Parameters to be Analyzed 10-6
10.7 Map Showing Proposed Sampling Locations 10-6
10.8 Laboratory and Field Quality Assurance Plans 10-6
10.9 Discussion in Support of Sampling Proposal 10-6
10.10 References 10-7

List of Figures

Figure 10-1 Aerial Photograph Showing the Proposed Survey Area for Cultural Resources Investigation

10 Historical and Cultural Properties Survey

Several cultural resources surveys have been conducted at the Copper Flat Mine Permit Area (Site) since 1976. The initial surveys were conducted for the 1977 and 1978 environmental assessments (Glover, 1977; BLM, 1978). A subsequent Class III (100-percent pedestrian coverage) cultural resources survey was conducted by Mariah Associates for Gold Express in 1991 (Evaskovich and Higgins, 1991). In response to comments from the New Mexico State Historic Preservation Officer (SHPO) in August 1995, Alta contracted with Human Systems Research of Las Cruces to resurvey all of the undisturbed portions of the Project not covered by the 1991 survey. The results of this survey were filed with the SHPO in October 1995 (Sechrist and Laumbach, 1995). SHPO representatives have indicated that a new survey of the undisturbed areas may not be needed at this time. Because the most recent survey was conducted more than 10 years ago, the lead federal agency for cultural resource compliance review (Bureau of Land Management [BLM]) and SHPO will review the previous surveys for sufficiency and consistency with current standards for survey investigations. This review will also consider the probability of new sites having become exposed in the interim through processes such as dune formation or movement. If it is determined that a new pedestrian survey is not needed prior to construction, the fieldwork effort for cultural resources likely will be limited to revisiting previously recorded sites to evaluate their current condition and to reassess potential impacts to these resources from the proposed Project.

A number of prehistoric and historic sites eligible for listing in the National Register of Historic Places have been identified at the Site. Where possible, identified sites will be avoided by modifying the design of project components. For sites that might be impacted by the Project, and for which avoidance is not feasible, the New Mexico Copper Corporation (NMCC) will contract with qualified archaeologists to prepare a recovery plan to collect appropriate data and to minimize and mitigate adverse effects to cultural resources resulting from the Project. The recovery plan will be implemented following approval by the BLM and SHPO and prior to construction.

The following subsections assume that a new Class III survey of the undisturbed areas of the Project will be required. They are not applicable if it is determined that no cultural resources survey of the area is necessary at this time.

10.1 Introduction and Background

By obtaining knowledge of the local cultural history prior to conducting surveys, cultural resource specialists are better able to identify and interpret findings. Understanding the material and spatial correlates of different culture groups through time ensures that cultural items identified during survey are placed and interpreted in the proper context. The cultural-historical sequence for western Sierra County is generally described in terms of five different time periods:

- Paleoindian (9500 to 6000 B.C.)
- Archaic (6000 B.C. to A.D. 200)
- Formative (A.D. 200 to 1400)
- Protohistoric (A.D. 1400 to 1540)
- Historic (A.D. 1540 to 1960)

Paleoindian sites are poorly represented within the archaeological record for western Sierra County, probably because the basins to the east, north, and south provided better hunting grounds for the mobile hunters of this time period, whose subsistence practices were focused on now-extinct Pleistocene megafauna. However, previous archaeological research in the area has documented evidence of relatively consistent prehistoric

occupation during the Archaic and Formative periods (Evaskovich and Higgins, 1991; Laumbach and Kirkpatrick, 1983; Lekson, 1985; Sechrist and Laumbach, 1995).

The most prevalent archaeological sites in the general area are related to historical mining activities. Gold was discovered in the Hillsboro area in 1877 (Harley, 1934) and subsequent historical mining sites include test pits, shafts, stone-walled cabins, dugouts, tent bases, and abandoned settlements (Sechrist and Laumbach, 1995).

An historical Apache occupation in the area is indicated by the identification of a chipped-glass artifact during a previous survey (Bussey and Naylor, 1975) and the presence of gun-ports in a stone cabin at another site (Evaskovich and Higgins, 1991).

Four previous surveys have been conducted within the vicinity of the proposed project area:

- A reconnaissance survey of approximately 6 square miles was conducted by the New Mexico State University Cultural Resources Management Division (CRMD) in 1975 (Bussey and Naylor, 1975).
- A survey of the power line and water line corridors providing utilities to the mine, an access road, and related industrial sites was performed by the CRMD in 1977 (Breathauer and Hoyt, 1977).
- A Class III (100-percent coverage) pedestrian survey of 147 hectares (363.3 acres) on the eastern slope of Animas Peak was conducted by Evaskovich and Higgins in 1991.
- A 229-hectare (565-acre) Class III pedestrian survey of the Copper Flat area was conducted by Human Systems Research, Inc. (HSR) in 1995 (Sechrist and Laumbach, 1995).

This latter survey is of particular interest for the purposes of the current investigation, as 16 archaeological sites and 212 isolated occurrences were documented at that time. Ten of these sites are historical artifact scatters with associated mining and/or habitation features. These include one standing structure, one stone foundation, one tent camp, one mine tunnel, two locations identified as potentially containing graves, and several artifact scatters. The remaining sites consist of 4 flaked-stone artifact scatters, 1 site with evidence of both prehistoric and historic occupations, and 1 prehistoric petroglyph site. The flaked-stone artifact scatters were reported as likely representing Archaic remains based on the presence of diagnostic artifacts and the overall technological attributes of the assemblages (Sechrist and Laumbach, 1995).

NMCC expects that the sites recorded during HSR's 1995 survey will comprise the majority of the cultural resources identified during the current investigation. However, a few new sites may be discovered; these will likely be consistent in type to those previously recorded.

10.2 Sampling Objectives

Because the project area includes federally administered land and entails land modification activities, the proposed activity is subject to Section 106 of the National Historic Preservation Act (NHPA, P.L. 89-665, as amended). The NHPA requires consideration of the effects that a proposed undertaking may have on historic properties as defined by this legislation.

The purpose of the cultural resource investigation will be to locate and assess all cultural resources and historic properties within the area of potential effects (APE). The APE—and any potential sampling strategy—will be defined in consultation with the BLM and SHPO. However, surveys conducted for land-modifying undertakings are typically intensive (100-percent pedestrian coverage) and sampling is not a common strategy. That said, standard transect intervals vary between 5 and 15 meters (m) (16 and 49 feet [ft]) and may be considered a limited opportunity to increase or decrease the degree of field review. As with the definition of the APE, the width of the proposed survey intervals will be determined in consultation with the BLM and SHPO. In addition, a large percentage of the project area has been extensively disturbed by previous mining activities and the

agencies may consider a less-intensive sampling strategy (e.g., 30-m [98-ft] transects) in these areas, or may eliminate them from the survey entirely.

10.3 Sampling Frequency

As stated above, NMCC anticipates conducting an intensive pedestrian survey of the APE that will be limited to a single-episode field investigation and recording effort. Transects may vary, but are likely to be 15 m (49 ft) in width for the entire APE. This technique is the standard for all cultural resource investigations on BLM property and on lands administered by the State of New Mexico.

10.4 List of Data to be Collected

Unless otherwise directed by the BLM and SHPO, no artifacts or other cultural materials will be collected during the proposed investigation. All data will be recorded in the field and all cultural materials will be left in place.

The types of properties or data that may be encountered during the survey of the Site include, but are not limited to, archaeological sites, historical cultural properties (historical period buildings, structures, or objects over 50 years old), historical districts, and isolated manifestations (IMs). An assessment will be made for each resource as to its potential eligibility for nomination to the National Register of Historic Places (NRHP).

10.5 Methods of Collection

Prior to conducting the survey, cultural resource specialists will complete a pre-field records review of the New Mexico Cultural Resources Information System (NMCRIS) database, to obtain information about previously recorded archaeological sites and surveys in the project area and vicinity. In addition, current listings of the NRHP and the New Mexico State Register of Cultural Properties (NMSRCP) will be consulted to determine the known presence of any listed cultural properties or districts within and in the vicinity of the project area. We will also consult with the BLM Las Cruces Field Office to compare the BLM's records with the findings from the other databases.

Resource locations shown on the Hillsboro, NM (1985) and Skute Stone Arroyo, NM (1961) 7.5-minute U.S. Geological Survey (USGS) quadrangle maps will be obtained through the use of Global Positioning System (GPS) receivers. Universal Transverse Mercator (UTM) coordinates will be obtained using both North American Datum (NAD) 27 and NAD 83 projections on a Trimble GeoXM GPS receiver with a positional accuracy of less than 1 m (3.28 ft). Shapefiles of the project area will be created using a geographic information system (GIS) and uploaded to the Trimble GeoXM for cross-referencing purposes. Using ArcPad software, surveyors will follow project boundaries to ensure adequate coverage of the entire survey area. The survey will be conducted by walking parallel transects spaced 15 m (50 ft) apart throughout the entire survey corridor. The GPS-derived locations for IMs and sites will be verified by reference to landscape features and landmarks shown on the USGS quadrangles. All GPS data will then be differentially corrected for sub-meter accuracy.

10.5.1 Site Definition

The definition of a site will follow current BLM guidelines (BLM, 2005), which state that a site is a physical location of past human activities or events, and which further define IMs as sites with fewer than 10 artifacts or a single, undatable feature. Features that may have datable remains, such as deflated thermal features, are also recorded as IMs if they retain little or no integrity and have no associated artifacts.

Following BLM guidelines, sites will be further classified as to whether they are Category 1 or 2, following the current definition in the above-cited guidelines. Category 1 sites are defined as those whose significance lies

solely in their potential to yield information under NRHP eligibility Criterion D. These sites are further defined as having small numbers of artifacts (fewer than 15). In addition, they may be classified as containing few or no features (such as soil stains), with no potential for buried cultural deposits (either demonstrated through limited testing or through surface observations—such as when a given site is on bedrock). Category 2 sites are defined as all other sites not falling under the definition of Category 1 sites (BLM Manual Supplement H-8100-1, New Mexico, Oklahoma, and Texas).

10.5.2 Site Recording

All sites will be recorded on Laboratory of Anthropology (LA) Site Record forms. Previously recorded sites are updated using the same form. Supplemental analysis forms are used to record prehistoric and historic artifacts, provide adequate descriptive information for each assemblage, and assign cultural/temporal affiliation, if possible.

Cultural and temporal affiliations will be assigned to sites with diagnostic artifacts and/or features on the basis of widely accepted type descriptions. Complete projectile points and point fragments will be sketched in the field for later typological classification, or to confirm in-field classification. Personnel do not, as a general practice, sketch all diagnostic sherds in the field. Because typological classification of these artifacts is based on numerous technological attributes (e.g., paste color and texture, temper type and size, surface smoothing or polish, and use of mineral or carbon paint) that cannot be efficiently represented in a field sketch for later analysis (in contrast to the primarily morphological attributes of projectile point types), we rely instead on professional experience to conduct in-field analysis of ceramics. Our field crews use field manuals that provide ceramic type descriptions and completed ceramic analysis forms that include entries for typological classification and for various technological and design attributes for artifacts that cannot be confidently classified as to type.

To facilitate relocation, each site will be plotted on the appropriate 7.5-minute USGS quadrangle map and labeled with its LA site number. The location of IMs, site datums, and site boundaries are recorded using a Trimble GeoXM GPS receiver and plotted on the appropriate 7.5-minute USGS quadrangle. Roadcuts and other forms of disturbance are recorded with the GPS receiver at all sites that were designated as having either an eligible or undetermined status regarding inclusion in the NRHP. All GPS data are post-field processed for sub-meter accuracy. The GPS-derived locations for IMs and sites are also verified by reference to landscape features and landmarks shown on the quadrangle maps.

A planview map, drawn to scale, will be prepared for each site and include the following information:

- The assigned LA site number
- The site boundaries and datum location
- A north arrow, scale, and legend
- The location of identified features and the distribution of artifacts
- The location of temporally diagnostic artifacts
- The relationship of site boundaries and cultural remains to known project impact areas, such as roads, and to surrounding environmental features
- The location of photograph points
- The APE boundary

In addition to photographing an overview of the Site, photographs will be taken when necessary for Site documentation, such as when features are visible on sites. Photographs will be logged and their locations plotted on Site sketch maps. Drawings of features and individual diagnostic artifacts will also be produced when applicable.

A site marker will be placed at each of the newly discovered sites. The marker on each site will consist of an aluminum cap attached to a 12-inch piece of rebar. Each marker will be placed within close proximity of the site and noted on the Site planview map.

10.5.3 Isolated Manifestation Recording

Locations with fewer than 10 artifacts or a single, undatable feature are considered IMs. Features that may have datable remains, such as deflated or poorly defined thermal features, are also recorded as IMs if they retain little or no integrity and have no associated artifacts. IMs are plotted on the appropriate 7.5-minute USGS quadrangle map and verified with a GPS receiver in the same manner as described for site locations. IMs are documented on IM recording forms. Information recorded for IMs include the area (for IMs consisting of more than one artifact), artifact types, measurements, frequencies, and sketches of diagnostic artifacts.

10.5.4 Mapping

Mapping of the project area and its resources will be supported by state-of-the-art equipment, including Trimble GPS receivers with submeter accuracy and a Nikon Total Station, along with the newest software including TerraSync and ArcPad 7x. One of the advantages for this technology is that it allows us to produce archaeological site maps that are more accurate and scalable than those created through traditional methods. Using ArcGIS 9x, geo-referenced digital site data can be related to land-use plans and quickly and cost-effectively display how changes or revisions to any undertaking will affect cultural resources. These highly accurate data will be critical in ensuring that the proposed mining activities are in compliance with Section 106 of the NHPA.

At a minimum, the Universal Transverse Mercator coordinates of all IMs, site datums, features, selected artifacts, and site boundaries will be recorded using a handheld Trimble GPS receiver. All spatial data and descriptive information will be stored on the Trimble unit using TerraSync software and data dictionaries produced with Pathfinder Office software. These files are easily copied to desktop computers in the lab where Site maps and Site plans will be generated using ArcGIS 9x. As directed, all data will be provided in applicable GPS-derived shapefiles. All data distribution and management will be in accordance with applicable regulations such as those found in the BLM Manual (2005), Section 304 of the NHPA, Executive Order 13007, and 43 CFR 7.18.

10.5.5 Historical Cultural Properties

In-use historical buildings, structures, and objects will be recorded using the New Mexico Historic Cultural Properties Inventory (HCPI) form. Each building or structure will be photographed and its location recorded with the GPS receiver. Form 1 of the HCPI will be completed for all historical buildings. Form 2 will be completed only for historical buildings that are recommended as being eligible to the NRHP. Acequias will be recorded on the Historic Water Delivery System Inventory Form. These resources will be photographed and their locations recorded with the GPS receiver.

The APE will be evaluated for potential districts and/or landscapes before, during, and after fieldwork using standards outlined in the New Mexico Register (Volume XVI, Issue Number 15, August 15, 2005) and the National Park Service (NPS) National Register Bulletin 30 (McClelland et al., 1999). Other materials used to guide the identification of districts and landscapes include NPS Preservation Brief 36 (Birnbaum, 1994) and the Historic Transportation Corridors thematic issue of Cultural Resource Management (Reilly, 1993). These documents, developed primarily by the NPS, define “landscape,” as a site or a district (36 CFR 60.2) in contrast to terms related to eligibility for the NRHP.

As suggested by the NPS in Bulletin 30 (McClelland et al., 1999), researchers define any potential landscape through their choices of historical contexts, period or periods of significance, potential boundaries, and

contributing or non-contributing elements. Defined landscapes are more difficult to characterize than buildings or structures with readily definable physical features and boundaries. However, many landscapes do have tangible features and landscape characteristics resulting from human use.

10.6 Parameters to be Analyzed

All cultural resources encountered during the investigation will be evaluated in terms of their eligibility for listing in the NRHP, using the implementing regulations provided in 36 CFR Part 60.4. Furthermore, project-specific treatment recommendations will be provided for all NRHP-eligible cultural resources that may be subject to adverse effects from the proposed undertaking. Traditional cultural properties will be evaluated following guidance provided in National Register Bulletin 38 (Parker and King, 1998). Human remains and associated funerary objects will be treated in accordance with the Native American Graves Protection and Repatriation Act. All assessments will be conducted in close consultation with the BLM, SHPO, and other appropriate consulting parties.

In most cases, the treatment recommendations for cultural resources will include the following statement:

It is recommended that all project-related activities avoid any cultural resources determined to be eligible for inclusion in the NRHP. If total avoidance is feasible, subject to consultation and comment, the proposed undertaking will have no effect on the documented cultural resources. If complete avoidance is not possible, but the undertaking only affects portions of the sites that lack integrity, the proposed undertaking should have no adverse effect on the qualities that qualify the resources for inclusion in the NRHP. However, if avoidance of potentially intact portions of the site areas is not feasible, then one of two actions is recommended to minimize and mitigate potential adverse effects: (1) The project proponent should prepare a testing and data recovery plan per the New Mexico Administrative Code (NMAC) 4.10.8 and to the standards within NMAC 4.10.16, or (2) the project proponent should prepare a monitoring plan prior to construction per NMAC 4.10.17.11. Either plan should be implemented per agency standards, the NMAC, and in consultation with the SHPO and the Cultural Properties Review Committee (if warranted).

10.7 Map Showing Proposed Sampling Locations

Figure 10-1 illustrates the extent of the mine property. All shaded (yellow) areas will be recommended as the APE—and thus the extent of field investigations, should the BLM and SHPO determine that a survey is required.

10.8 Laboratory and Field Quality Assurance Plans

Accurate work and timely deliverables will be provided. Reporting will follow the standards in BLM manual H-8100-1, Chapter 1.B.1 and Appendix 2 (2005). In addition, work will be performed in compliance with all aspects of the NMAC, including NMAC 4.10.15.

10.9 Discussion in Support of Sampling Proposal

As stated earlier, sampling is not considered a standard strategy for cultural resource investigations in New Mexico. That said, the extent of recent disturbance at the Site may allow for a reduction in the size of the APE defined by the lead and consulting agencies, or a waiver of the requirement to conduct survey. However, within any area that is determined to require survey, NMCC anticipates using a standard 15-m (49-ft) transect interval, which is otherwise defined as an intensive Class III survey. Any modification to the APE, the survey parameters, or the data collection efforts will be the result of consultation with the BLM and the SHPO.

10.10 References

Birnbaum, C.A., 1994, Protecting cultural landscapes: Planning, treatment, and management of historic landscapes: National Park Service Preservation Brief 36, 20 p.

Breathauer, D., and Hoyt, M., 1977, An archaeological survey of two proposed powerlines, a waterline, and access road, and related industrial sites near Hillsboro, New Mexico: Cultural Resources Management Division Report 159.

Bureau of Land Management (BLM), 1978, Environmental assessment record on Quintana Minerals Corporation's proposed open pit copper mine at Copper Flat, Sierra County, New Mexico: Las Cruces, N. Mex., p. 75-81.

——— 2005, Procedures for performing cultural resource fieldwork on public lands in the area of New Mexico BLM responsibilities, BLM Manual Supplement H-8100-1, New Mexico, Oklahoma, and Texas: Santa Fe, New Mexico State Office, 164 p.

——— 1999, Preliminary final environmental impact statement: Copper Flat project: Las Cruces, N. Mex. U.S. Department of the Interior, 491 p. Prepared by ENSR, Fort Collins, Colo.

Bussey, S.D., and Naylor, B.J., 1975, An archaeological reconnaissance near Hillsboro, New Mexico: Cultural Resources Management Division Report 24.

Evaskovich, J., and Higgins, H., 1991, A class III cultural resources inventory for a proposed copper mine expansion: Albuquerque, N. Mex., Mariah and Associates, Inc.

Glover, F.A., 1977, Environmental assessment report, Copper Flat Mine development, Copper Flat, New Mexico.

Harley, G.T., 1934, The geology and ore deposits of Sierra County, New Mexico: Socorro, N. Mex., New Mexico School of Mines Bulletin 10.

Laumbach, K.W., and Kirkpatrick, D.T., 1983, The Black Range survey: a 2% archaeological sample of state lands in western Sierra County, New Mexico: Cultural Resources Management Division Report 566.

Lekson, S.H., 1985, Archaeological reconnaissance of the Rio Grande Valley, Sierra County, New Mexico: Report submitted to the State Historic Preservation Division, Santa Fe, New Mexico.

McClelland, L.F., Keller, J.T., Keller, G.P., and Melnick, R.Z., rev. 1999, Guidelines for evaluating and documenting rural historic landscapes: National Park Service, National Register Bulletin 30.

Parker, P.L., and King, T. F., 1998 (rev.), Guidelines for evaluating and documenting traditional cultural properties: National Park Service National Register Bulletin 36, 28 p.

Reilly, M. (issue consultant), 1993, Historic Transportation Corridors: A new and dynamic element of historic preservation: CRM 16, no.11, 60 p.

Sechrist, M., and Laumbach, K.W., 1995, Archaeological survey of areas in the Copper Flat project area near Hillsboro, Sierra County, New Mexico: Human Systems Research, Inc. Report 9523.

Figure



N
W E
S

0 1,000 2,000 4,000 6,000
Feet

Mine Boundary:
Tom Van Bebber
Survey:
Parametrix
Imagery Information:
-USGS 7.5-Minutes County DOQQ mosaic
Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

Legend

- Proposed Mine Permit Boundary
- Proposed Cultural Resources Survey Area

Figure 10-1
Aerial Photograph Showing the Proposed Survey Area for Cultural Resources Investigation

New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\10_10_Cultural Resources\10-1_culturalSurvey.mxd 08/31/2010

Table of Contents

11 Present and Historical Land Use 11-1
11.1 Present Land Use 11-1
11.1.1 Land Ownership and Status 11-1
11.1.2 Land Planning and Regional Land Use 11-2
11.1.3 Current Land Use and Structures at Site 11-2
11.1.4 Access, Rights of Way, and Water Rights 11-2
11.2 Environmental Liabilities and Permits 11-3
11.3 Pertinent Historical Land Use 11-3
11.4 References 11-5

List of Figures

Figure 11-1 Land Ownership Status
Figure 11-2 Noncontiguous Mill Site Claims
Figure 11-3 Aerial View to the West at Copper Flat Mine, 1982
Figure 11-4 Aerial View to the East at Copper Flat Mine, 1982
Figure 11-5 Proposed Copper Flat Permit Area with Air Photography

List of Tables

Table 11-1 Permits and Approvals Required for the Copper Flat Mine

11 Present and Historical Land Use

The information in this section is summarized primarily from SRK Consulting (2010) and the U.S. Bureau of Land Management (BLM) (1999). An online review of BLM Master Title Plats and land status on GeoCommunicator, the National Integrated Land System (http://www.geocommunicator.gov/GeoComm/index.shtm) was also performed to check the current status of rights of way (ROW) and other activities on BLM lands.

The Copper Flat Mine Permit Area (Site) and associated noncontiguous mill site claims are located between the communities of Caballo and Hillsboro, north of NM State Highway 152 and south of Animas Peak. It is covered by the Hillsboro 15-minute U.S. Geological Survey (USGS) quadrangle and occupies parts of Sections 30 and 31, Township 15 South, Range 5 West (T15S, R5W); Sections 30 and 31, T15S, R6W; Sections 23 through 27 and 34 through 36, T15S, R7W; Section 6, T16S, R6W; and Section 2, T16S, R7W (all with reference to the New Mexico Principal Meridian). Some of the noncontiguous mill site claims are outside the permit boundary and are associated with water rights and water wells approximately 8 miles east of the Site. The center of the mineralized zone is at approximately latitude 32.970300, longitude −107.533527.

11.1 Present Land Use

11.1.1 Land Ownership and Status

According to the 2010 property tax schedule of the Sierra County Assessor, Hydro Resources Corporation (Hydro) and Cu Flat, LLC (Cu Flat) own all of the fee lands within the permit area except as follows:

- Edgar E. Greer (“Greer”) owns the fee surface estate in the lands within the permit area in Sections 30 and 31, Township 15 South, Range 6 West, and has contracted to sell his fee surface estate to Ryan G. and Wendy M. Fancher (the “Fanchers”). The mineral estate in such lands is owned by the United States and is subject to unpatented mining claims owned by Hydro and GCM, Inc. (GCM).
- Greer owns the fee surface and mineral estates in the Cincinnati, Graf Von Luxenburg, and Prosper patented mining claims in Sections 25 and 36, Township 15 South, Range 7 West, and has contracted to sell such claims to the Fanchers.
- The non-fee lands within the permit area are owned by the United States. All such lands are subject to unpatented mining claims owned by Hydro and GCM.

All of the fee lands and unpatented mining claims within the permit area owned by Hydro, Cu Flat, and GCM are subject to the Option and Purchase Agreement described in Section 1.2.5.

NMCC holds an exclusive option to acquire the Copper Flat properties under an Option and Purchase Agreement effective July 23, 2009 (amended on January 10, 2010; April 1, 2010; May 28, 2010; and August 2, 2010). All option payments to date have been made; an additional payment is due in September 2010, and the final payment is to be made in 2011. The Agreement specifies that after its option is exercised NMCC will pay quarterly royalties to Hydro Resources and GCM. The lands covered by the Agreement are not subject to any other royalties, payment obligations, other agreements or encumbrances, or to any back-in rights. However, NMCC must pay New Mexico property taxes on fee and producing the Copper Flat properties and pay the U.S. fees required to maintain the unpatented mining claims and mill sites.

Figure 11-1 shows the property ownership of the Site as of June 23, 2010. Hydro Resources owns the surface and mineral estates the patented mining claims subject to the Option and Purchase Order Agreement. In addition to the surface and mineral estates shown in Figure 11-1, noncontiguous mill site claims located east of the Site that are owned by Hydro Resources and subject to the Option and Purchase agreement are shown in

Figure 11-2. Cu Flat, another of the optioners, owns the surface and mineral estates in the parcels of other fee land included in the Copper Flat property and the surface estate in three other parcels of other fee land. Hydro Resources has title to the surface rights in 132 unpatented mining claims included in the Copper Flat Property and in nine unpatented mill sites outside the permit boundary. Hydro Resources owns an undivided two-thirds interest in the surface rights as well as in the mining rights in 44 unpatented mining claims included in the Copper Flat Property, and GCM, also a vendor to NMCC, owns an undivided one-third interest in the surface and mining rights in those 44 claims. The United States has retained rights to manage and dispose of plant resources and to manage other non-mineral surface resources on the unpatented mining claims.

State lands would not be directly affected by the operation, although a portion of the mine access road in T15S, R6W, Section 32, passes through State Trust lands. Several sections of State land also exist south of the tailings impoundment dam (T16S, R6W, Section 6) and to the west and east of the existing well field (T15S, R6W, Section 36, and T15S, R5W, Section 32, respectively).

Lands adjacent to the Site include federal, state, and private property. Although there are several nearby placer claims held by rock clubs for recreational collecting, there are no known adjacent properties with mineralization similar to that of the Copper Flat Mine.

11.1.2 Land Planning and Regional Land Use

Historically, most of Sierra County has been used for mining, ranching, agriculture, and tourism. The public lands on which the unpatented mining claims and mill sites located at the Copper Flat Site are managed by BLM's Las Cruces Field Office. BLM manages public lands for multiple uses including recreation, range, forestry, mineral extraction and processing, watershed, fish and wildlife habitat, wilderness, and natural, scenic, scientific, and historical values. The current operational land use plan for this region is the 1986 White Sands Resource Management Plan, which covers all BLM-administered lands in Sierra and Otero counties; a new plan, the TriCounty Resource Management Plan, is expected to be approved in early 2011. The White Sands Resource Management Plan identifies the Copper Flat Mine as a mineral resource and recognizes that it could again become a producing mine, although no mining has occurred at the Site since 1982.

The town of Hillsboro, located approximately 5 miles southwest of the Site, has around 100 homes as well as several restaurants, other businesses, and government buildings. Truth or Consequences, approximately 20 miles northeast of the Site, has a population of about 8,000 and is the county seat. Few residences lie within 5 miles of the Copper Flat Mine: the Coalson and Clark ranches are located about 4 miles southeast of the Site and the Golddust Ranch is about 0.1 mile south of the mine and north of Highway 152 (formerly used as Quintana's Site headquarters).

11.1.3 Current Land Use and Structures at Site

Livestock grazing is the primary ongoing land use in the area of the Site. BLM grazing allotments 16040 and 10679 cover the Site, and livestock grazing is permitted in areas adjacent to the Site.

Except for a small viewing structure and a sample storage building, no buildings currently exist on the Site. A state and federally approved water diversion channel exists around the Site area. A 370-acre tailings pond exists at the Site along with two decant towers. Three dumps that were used for waste rock during the 1982 operation of the mine are located near the perimeter of the pit.

11.1.4 Access, Rights of Way, and Water Rights

The Site is accessed from I-25 by 10 miles of paved highway (NM State Highway 152) and about 3 miles of all-weather gravel road. The mine road is gated near the former mine entrance to discourage vehicular access.

Several other unimproved roads provide access to portions of the Site; however, the tailings area is fenced to limit movement of people and cattle.

Electric power in the area is supplied by Sierra Electric Co-op. An existing 115-kilovolt (kV) transmission line is located in a utility corridor that parallels State Highway 152 from the Caballo switching station to the Site. The original mine operation included a 20-megavolt-ampere (MVA) transformer that stepped the power down to 4.16 kV. A 25-kV power line exists that could be used to carry power from the Site to the water well field previously used for the mine (about 8 miles east of the Site). A 20-inch diameter waterline runs from this well field to the Site. This pipeline has no current ROW agreement, having been abandoned by the former owner, Gold Express Corporation (Gold Express). BLM now owns this line; use rights are currently being negotiated. When Hydro Resources reacquired the Site in 2001, 1,019 acre-feet of water rights were also conveyed. If NMCC exercises its option to acquire the Site, these rights will be transferred to NMCC for use at the mine. Many thousands of acre-feet of additional water rights in the area are owned by third parties; negotiations have been initiated by NMCC to acquire some of these rights (SRK, 2010).

11.2 Environmental Liabilities and Permits

The Copper Flat Mine was first permitted by Quintana Minerals (Quintana) during the 1980s. In 1992, a new plan of operations was submitted to BLM and an environmental assessment (EA) was begun by Gold Express, but the operation was never restarted. Alta Gold Company (Alta Gold) acquired the property in the mid-1990s and reinitiated the permitting and approvals process, collecting significant baseline data and submitting applications for all major state and federal permits. Alta Gold declared bankruptcy in early 1999, but not before a draft environmental impact statement (EIS) had been prepared and the associated public comments received; a public hearing had also been held on Alta Gold's application for a the New Mexico Mining Act Permit and a New Mexico Groundwater Discharge Permit. However, no final permits were issued.

Baseline data collected by Alta Gold, Gold Express, Rio Gold Mining Ltd (Rio Gold), and Quintana is relevant and provides insights for future permitting activity. Five major permits or approvals are needed:

- BLM plan of operation, and subsequent EIS approval
- New Mexico groundwater discharge permit
- New Mexico mining permit
- New Mexico air quality permit
- New Mexico permit for dam construction and operations

These and other permits/approvals are listed in Table 11-1.

11.3 Pertinent Historical Land Use

Ore was first discovered in the Hillsboro district in April 1877, and the town of Hillsboro was established that same year. A number of mining claims were patented for the Site between 1892 and the 1940s; these now form most of the private land occupied by the Copper Flat mine.

In 1952, Newmont began exploration in the district for porphyry copper mineralization by drilling nearly 3,599 ft in six angle holes into the Copper Flat Quartz Monzonite (CFQM) (Kuellmer, 1955). Bear Creek drilled another 9,300+ ft in 1958−1959 in 20 widely spaced core holes, hoping to find an enrichment blanket of secondary copper (which was not found). Both the Newmont and Bear Creek drill and assay data is available (Dunn, 1984). Porphyry copper exploration was advanced by Inspiration again in the late 1960s. Inspiration completed 30 core

drill holes by 1973, purchased the patented claims, performed metallurgical work, and completed two water wells on the property (Dunn, 1984).

In 1974, Inspiration leased the property to Quintana, which undertook a comprehensive mine development program with metallurgical work, underground drifting, bulk sampling, and drill hole composite testing (all preformed by the Colorado School of Mines Research Center). The program included detailed geologic investigations into the relationship between the breccia pipe and the quartz monzonite host rocks, as well as the relationship between host rocks and mineralization. An EA was initially prepared for state and federal agencies in 1975, but low copper prices caused the project to be shelved from late 1976 until 1979. At that time, processing methods were reviewed and semi-autogenous grinding and copper-molybdenum flotation separation became the basis for subsequent design work. Mineable reserves were estimated at 60 million standard tons (Mst) with 0.42 percent copper and 0.012 percent molybdenum, plus some gold and silver (SRK, 2010).

With Quintana as the overall project manager, the Copper Flat mine began full production in March 1982 at a rated capacity of 15,000 st a day, a waste-to-ore ratio of 1.8:1, and a cut-off grade of 0.25 percent copper. The combination of low copper prices and high interest rates on the financing loan resulted in the mine closing down just 3 months later, at the end of June. During its short operational period, the mine produced 1.48 million standard tons (Mst) of ore containing 7.4 pounds (lbs) of copper, 2,301 ounces (oz) of gold, and 55,955 oz of silver (SRK, 2010). By the end of 1985, the surface facilities equipment had been sold and the site reclaimed as required by state and federal guidelines. However, all structural foundations, power lines, water wells, and in-ground infrastructure were left in place.

Hydro Resources of Albuquerque, New Mexico, acquired the Copper Flat property, including all royalties, from Inspiration in 1989. Rio Gold and Tenneco Minerals (Tenneco) drilled six large-diameter holes in 1990. Gold Express optioned the property in 1993, and then sold it to Alta Gold in 1994 without performing any exploration or development. A preliminary final EIS for the Alta Gold mining project was issued in March 1999, but Alta Gold went bankrupt (due to financial problems with other assets) before any permits were issued. Hydro Resources reacquired all the properties in 2001 along with all royalties. Hydro Resources maintains an archive of information related to the mine, including over 14,000 sample pulps and skeleton core from the Quintana drilling programs (SRK, 2010).

In 2009 and early 2010, NMCC conducted a sample verification program that included pulp reject analysis and drilling, as part of the requirements for a NI43-101 report on the resources at Copper Flat (SRK, 2010). The program was designed to verify different aspects of the mineralization and geology of the deposit, as well as to comply with new reporting requirements. The drill holes were plugged with bentonite and capped with cement, as required by the New Mexico Energy, Minerals and Natural Resources Department (EMNRD) Mining and Minerals Division (MMD). NMCC completed seven drill holes comprising 5,046.5 ft of core. Three of the drill holes terminated prematurely due to bad ground. The drill sites were reclaimed as per MMD requirements (SRK, 2010).

Approximately 60 percent of the proposed Site has been disturbed by previous operations. Remnants of the 1982 mining operation include an open pit and pit lake, a tailings impoundment area, waste rock disposal areas, a number of buried building foundations, and ancillary facilities including decant towers, roads, power transmission lines, and waterlines (Figures 11-3 and 11-4). These features are clearly delineated on BLM geographic information system (GIS) maps and aerial photographs, and have been considered as part of the proposed plan of operations. Although some reclamation was done to the area in 1986, much of the Site remains disturbed (Figure 11-5).

11.4 References

Bureau of Land Management (BLM), 1999, Preliminary final environmental impact statement, Copper Flat project: Las Cruces, N. Mex., U.S. Department of the Interior, 491 p. Prepared by ENSR, Fort Collins, Colo.

Dunn, P., 1984, Geologic studies during the development of the Copper Flat porphyry deposit: Mining Engineering, February, 1984, p. 151.

Kuellmer, F.J., 1955, Geology of a disseminated copper deposit near Hillsboro, Sierra County, New Mexico: New Mexico Bureau of Mines and Mineral Resources Circular 34, 46 p.

SRK Consulting, 2010, NI-43-101 Preliminary assessment, THEMAC Resources Group Limited, Copper Flat project, Sierra County, New Mexico: Lakewood, Colo. Prepared by SRK Consulting for THEMAC Resource Group Limited, June 30, 2010.

Figures



N
W E
S

Mine Boundary:
John Reynolds
Claims & Feelands:
Tom Van Bebber
Imagery Information:
-USGS 7.5-Minute Quads; Skute
Stone Arroyo & Hillsboro
Projection Information:
-New Mexico State Plane West, NAD 1927

0 1,000 2,000 4,000
Feet

Legend

- Mine Permit Boundary
- Fee, Category 3a
- Fee Lands subject to Option Agreement dated July 23, 2009
- Fee Lands NOT subject to Option Agreement dated July 23, 2009

Figure 11-1
Land Ownership Status
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\11_Landuse\11-1_land-ownership.mxd 09/03/2010



Claim Boundary:
SRK, 2010
Imagery Information:
-USGS 7.5-Minutes Quads; Skute Stone Arroyo & Caballo
Projection Information:
-New Mexico State Plane West, NAD 1927

Legend

Mill Site Claims Boundary

Figure 11-2
Noncontiguous Mill Site Claims
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\11_Landuse\11-2_mill-site-claims.mxd 09/02/2010

Figure 11-3
Aerial View to the West at Copper Flat Mine, 1982

New Mexico Copper Corporation

from Hydro Resources, Inc.

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\11_Landuse\11-3_1982photo-west.mxd 09/02/2010

Figure 11-4
Aerial View to the East at Copper Flat Mine, 1982

New Mexico Copper Corporation

from Hydro Resources, Inc.

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\11_Landuse\11-4_1982photo-east.mxd 07/20/2010

N
W E
S

0 1,000 2,000 4,000 6,000

Feet

Mine Boundary:
Tom Van Bebber
Imagery Information:
-USGS 7.5-Minutes County DOQQ
mosaic Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

Legend

Proposed Mine Permit Boundary

Figure 11-5
Proposed Copper Flat Permit Area with Air Photography

New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\11_Landuse\11-5_proposed-permit_photo.mxd 09/02/2010

Table

Table 11-1

Permits and Approvals Required for the Copper Flat Mine

Permit/Approval	Approving/Granting Agency
Federal	
Plan of Operations	U.S. Bureau of Land Management
Nationwide Dredge and Fill Permit (Section 404)	U.S. Army Corps of Engineers
FCC License	Federal Communications Commission
MSHA Registration	Mining Safety and Health Administration
Stormwater Disposal Permit (National Pollutant Discharge Elimination System)	U.S. Environmental Protection Agency
State	
Mining Permit	New Mexico Energy, Mineral and Natural Resources Department-Mining Act Reclamation Bureau
Water Pollution Control Permits	New Mexico Energy, Mineral and Natural Resources Department-Mining Act Reclamation Bureau, Environmental Protection Agency
Surface Disturbance Permit (Air Quality)	New Mexico Environment Department - Air Quality Bureau
Permit to Construct (Air Quality)	New Mexico Environment Department - Air Quality Bureau
Permit to Operate (Air Quality)	New Mexico Environment Department - Air Quality Bureau
Permit to Appropriate Water	New Mexico State Engineer's Office
Permits for Dam Construction and Operations	New Mexico State Engineer's Office
Approval to Operate a Sanitary Landfill	New Mexico Environment Department-Solid Waste Bureau
Tailings Discharge	New Mexico Environment Department-Groundwater Bureau
Cultural Resources Clearance	State Historic Preservation Office

Source: SRK, 2010, Table 2.5.1.1

New Mexico Copper Corporation

Quality Assurance Project Plan

Copper Flat Mine Site

September 2010

Prepared for:
New Mexico Copper Corporation

Submitted to:
Mining and Minerals Division
New Mexico Energy, Minerals and Natural Resources Department

Prepared by:

INTERA

00233

TABLE OF CONTENTS

Abbreviations and Acronyms iii
1 Project Description and Management 1
1.1 Project Definition and Background 1
1.2 Quality Objectives and Criteria 1
1.2.1 Measurement Quality Objectives for Analytical Laboratory Data 1
1.2.2 Measurement Quality Objectives for Meteorological and Air Quality Data 3
1.2.3 Measurement Quality Objectives for Ecological Data 4
1.2.4 Measurement Quality Objectives for Cultural Resources Data 4
1.3 Project Organization 4
1.4 Special Training and Certification 4
1.4.1 Health and Safety Training 4
1.5 Documents and Records 5
1.5.1 Field Documentation 5
2 Data Generation and Acquisition 5
2.1 Sampling Design 5
2.2 Field Activities 6
2.3 Sample Handling and Custody 6
2.4 Laboratory QA/QC 7
2.5 Equipment Testing, Inspection, Maintenance, and Calibration 8
3 Inspection and Acceptance of Supplies and Consumables 8
4 Data Management 8
5 Assessment, Response Actions, and Reports to Management 9
6 Data Evaluation and Usability 9
6.1 Laboratory Data Verification 9
6.2 Laboratory Data Evaluation and Usability 10
7 Reconciliation with User Requirements 10
8 References 10

LIST OF FIGURES

Figure 1 INTERA Organizational Flow Chart
Figure 2 Parametrix Organizational Flow Chart

LIST OF TABLES

Table 1 Key Personnel and Responsibilities

Abbreviations and Acronyms

CFR	Code of Federal Regulations
COC	chain of custody
CPR	cardiopulmonary resuscitation
DQA	data quality assessment
EPA	United States Environmental Protection Agency
ER	equipment rinsate
FTL	field team leader
ID number	identification number
LCS	laboratory control sample
MDL	method detection limit
MMD	New Mexico Mining and Minerals Division
MQO	measurement quality objectives
MS	matrix spike
NMCC	New Mexico Copper Corporation
NMWQCC	New Mexico Water Quality Control Commission
OSHA	Occupational Safety and Health Administration
PARCC	precision, accuracy, representativeness, completeness, and comparability
PM	Project Manager
PPE	personal protective equipment
PRRL	project-required reporting limits
QA	quality assurance
QAPP	quality assurance project plan
QC	quality control
RPD	relative percent difference
SAP	sampling and analysis plan
Site	Copper Flat Mine Permit Area
SQL	sample quantitation limits

1 Project Description and Management

This document establishes the quality standards for products and services that have been established within the industry and through government regulations. New Mexico Copper Corporation (NMCC) and its contractors shall meet or exceed these quality standards throughout the duration of this project.

NMCC is currently initiating permitting activities for the re-opening of the Copper Flat Mine located approximately six miles northeast of Hillsboro, New Mexico, in Sierra County (Site). NMCC and its contractors will assess baseline conditions of for climate, vegetation, wildlife, topsoil, surface water, groundwater, and historical and cultural properties.

The project organizational flow chart for NMCC's geosciences and engineering contractor, INTERA Incorporated (INTERA) of Albuquerque, New Mexico, identifies key personnel and their functions (Figure 1). The INTERA Incorporated (INTERA) Program Manager, Cynthia Ardito, is responsible for project direction and quality assurance (QA) for this project. The Project Manager (PM), Peter Castiglia, is responsible for organizing and implementing field activities, project oversight, data management, and report preparation. Mr. Castiglia is also responsible for ensuring that the Quality Assurance Project Plan (QAPP) and Sampling and Analysis Plan (SAP) are appropriately developed and adhered to. The PM, Dr. John Sigda, is responsible for data analysis and modeling. Dr. Sigda will also provide technical support and will assist in data management and report preparation. INTERA's subcontractors include Class One Technical Services, Inc. of Albuquerque, New Mexico, for air quality services, and Hall Environmental Analysis Laboratories (HEAL) for analytical laboratory services. Subcontractor PMs will be responsible for QA, project oversight, data management, and coordination of field activities.

NMCC has contracted with Parametrix Incorporated of Albuquerque, New Mexico, for ecological and cultural resources services. Parametrix will be responsible for data collection for these resource areas. An organizational chart is included as Figure 2. The Parametrix PM, Mr. Jens Deichmann, is responsible for data collection and data quality. For geologic sampling, NMCC has contracted with SRK Consulting Engineers (SRK). The SRK PM is Mr. Mark Willow. The principal geochemist supporting Mr. Willow and overseeing the geologic sampling program is Dr. Robert Bowell.

1.1 Project Definition and Background

A 12-month baseline characterization of pre-mining site conditions must be completed prior to submittal of a Mine Permit Application to the New Mexico Energy, Minerals, and Natural Resources Department Mining and Minerals Division (MMD). As noted previously, this baseline characterization involves sampling, analysis, and assessment of site-specific climatic, vegetation, wildlife, soil, surface water, groundwater, and historical and cultural properties conditions. The MMD requires that a SAP be submitted for agency review. The SAP is a detailed work plan that describes how baseline data will be collected. The SAP must thoroughly describe the proposed sampling methodology and frequency, proposed data sources, and proposed sampling locations to document existing resource conditions within the permit boundary.

1.2 Quality Objectives and Criteria

The following sections present the measurement quality objectives (MQO) identified for this project.

1.2.1 Measurement Quality Objectives for Analytical Laboratory Data

All analytical results for water samples will be evaluated in accordance with precision, accuracy, representativeness, completeness, and comparability (PARCC) parameters to document the quality of the data

and promote data that are of sufficient quality to meet the project objectives. With regard to these PARCC parameters, precision and accuracy method blanks will be prepared at the frequency prescribed in the individual analytical method, or at a rate of 5 percent of the total samples if a frequency is not prescribed in the method. The subsections below describe each of the PARCC parameters and how they will be assessed for this task.

1.2.1.1 Precision

Precision is the degree of mutual agreement between individual measurements of the same property under similar conditions. Usually, combined field and laboratory precision is evaluated by collecting and analyzing field duplicates and then calculating the variance between the samples, typically as a relative percent difference (RPD).

$$RPD = \frac{|A - B|}{(A + B)} \times 100\%$$

where:

A	=	First duplicate concentration
B	=	Second duplicate concentration

Field sampling precision is evaluated by analyzing field duplicates. One duplicate groundwater sample will be collected during the initial groundwater sampling event to establish laboratory analytical precision at the onset of the investigation. The duplicate groundwater sample will be collected by completely filling two separate vials by alternating between the primary sample set and the replicate sample set in the order shown below:

- Fill vial #1 - primary sample set
- Fill vial #1 - replicate sample set
- Fill vial #2 - primary sample set
- Fill vial #2 - replicate sample set

Laboratory analytical precision is evaluated by analyzing matrix (laboratory) duplicates. Results for each laboratory duplicate pair will be used to determine the RPD in order to evaluate precision.

1.2.1.2 Accuracy

A program of sample spiking will be conducted to evaluate laboratory accuracy. This program will include analysis of matrix spike (MS), laboratory control samples (LCS) or blank spikes, and method blanks. The results for the spiked samples will be used to calculate the percent recovery for use in evaluating accuracy.

$$\text{Percent Recovery} = \frac{S - C}{T} \times 100\%$$

where:

S	=	Measured spike sample concentration
C	=	Sample concentration
T	=	True or actual concentration of the spike

Results that fall outside the accuracy goals will be further evaluated on the basis of the results of other quality control (QC) samples.

1.2.1.3 Representativeness

Representativeness expresses the degree to which sample data accurately and precisely represent: (1) the characteristics of a population, (2) variations in a parameter at a sampling point, or (3) an environmental condition that they are intended to represent.

Representativeness of data will also be promoted through the consistent application of established field and laboratory procedures. Equipment rinsate (ER) blanks and laboratory blanks will be evaluated for the presence of contaminants to aid in evaluating the representativeness of sample results. Data determined to be non-representative by comparison with existing data will be used only if accompanied by appropriate qualifiers.

1.2.1.4 Completeness

Completeness is a measure of the percentage of project-specific data that are valid. Valid data will be obtained when samples are collected and analyzed in accordance with QC procedures as outlined in this QAPP and when none of the QC criteria that affect data usability are exceeded. When all data evaluation is completed, the percent completeness value will be calculated by dividing the number of useable sample results by the total number of sample results planned for this investigation.

As discussed further in Section 8.0, completeness will also be evaluated as part of the data quality assessment process (EPA, 2000b). This evaluation will help assess whether any limitations are associated with the decisions to be made based on the data collected.

1.2.1.5 Comparability

Comparability expresses the confidence with which one data set can be compared with another. Comparability of data will be achieved by consistently following standard field and laboratory procedures and by using standard measurement units in reporting analytical data.

1.2.1.6 Detection and Quantitation Limits

The method detection limit (MDL) is the minimum concentration of an analyte that can be reliably distinguished from background noise for a specific analytical method. The quantitation limit represents the lowest concentration of an analyte that can be accurately reproduced in a sample matrix. Project-required reporting limits (PRRL) are contractually specified minimum quantitation limits for specific analytical methods and sample matrices, such as soil or water, and are typically several times the MDL to allow for matrix effects. PRRLs, which are established in the project scope of work for subcontract laboratories, are set to establish minimum criteria for laboratory performance. Actual laboratory quantitation limits may be substantially lower.

For this project, analytical methods have been selected so that the PRRL for each target analyte is below the applicable regulatory screening criteria, the New Mexico Water Quality Control Commission (NMWQCC) Standards for groundwater. Also, sample concentrations will be reported as estimated values if concentrations are less than PRRLs but greater than MDLs. The MDL for each analyte will be listed as the detection limit in the laboratory's electronic data deliverable.

1.2.2 Measurement Quality Objectives for Meteorological and Air Quality Data

Laboratory and field quality assurance procedures for meteorological and air quality data are described in detail in Section 2 of the Sampling and Analysis Plan (SAP). Please refer to Section 2.8 of this SAP for more information.

1.2.3 Measurement Quality Objectives for Ecological Data

A single field crew chief will be assigned to ensure data collection is consistent between crews. This individual will review a sub-set of the field forms following each field day. Formalized data collection training will also be completed prior to field sampling. All field botanists will be familiar with plant systematics and techniques to identify plants using taxonomic keys. Plant species not readily identifiable in the field will be collected and preserved for identification at the University of New Mexico Herbarium.

Vegetation material produced during the previous growing season will be discarded before placing samples into a paper bag. Rocks, soil, and/or litter will not be placed into sample bags. Biomass production will only be calculated as an actual dry-weight sample. No double sampling or estimations will occur.

Field data entered into an electronic format such as MS Excel or Access will be evaluated for integrity, consistency, and completeness before data analysis. Oversights or incorrect entries will be corrected. A sub-set of the field forms will be compared to the electronic version for an accuracy assessment. If significant differences are identified, a thorough re-evaluation of each of the forms will be completed.

For wildlife data, field biologists will have a minimum of a BA/BS in Biology and five to ten years of field experience conducting a wide variety of animal surveys ranging from reptiles and amphibians, to birds, mammals, insects, and other invertebrates. This includes experience in recognizing and identifying signs of wildlife. All findings and results will be reviewed by senior scientists.

1.2.4 Measurement Quality Objectives for Cultural Resources Data

Reporting will follow the standards in BLM manual H-8100-1, Chapter 1.B.1 and Appendix 2 (2005). In addition, work will be performed in compliance with all aspects of the NMAC, including NMAC 4.10.15.

1.3 Project Organization

Table 1 presents the roles and responsibilities for key personnel who will be involved in the investigation at the Site. In some cases, more than one responsibility has been assigned to one person.

1.4 Special Training and Certification

This section outlines the training and certifications required to complete the activities described in this QAPP. The following sections describe the requirements for personnel working on-site.

1.4.1 Health and Safety Training

INTERA Personnel who collect water and sediment samples from the Site are required to meet the Occupational Safety and Health Administration (OSHA) training requirements defined in Title 29 of the Code of Federal Regulations (CFR) Part 1910.120(e). These requirements include (1) 40 hours of formal off-site instruction, (2) a minimum of three days of actual on-site field experience under the supervision of a trained and experienced field supervisor, and (3) 8 hours of annual refresher training. Field personnel who directly supervise employees engaged in work at the site shall also receive at least 8 additional hours of specialized supervisor training. The supervisor training covers health and safety program requirements, training requirements, personal protective equipment (PPE) requirements, the spill containment program, and health-hazard monitoring procedures and techniques. Every member of the field team will maintain current certification in the American Red Cross “Multimedia First Aid,” and “Cardiopulmonary Resuscitation (CPR) Modular,” or equivalent.

Copies of health and safety training records, including course completion certificates for the initial and refresher health and safety training, specialized supervisor training, and first aid and CPR training, are maintained in corporate files.

1.5 Documents and Records

Documentation is critical for evaluating the success of any environmental data collection activity. The following sections discuss the requirements for documenting field activities and for preparing laboratory data packages. This section also describes reports that will be generated as a result of this project.

1.5.1 Field Documentation

Field personnel will use permanently bound field logbooks with sequentially numbered pages to record and document field activities. The logbooks will list a contract name and number, the project number, the site name, the names of subcontractors, the client, and the PM. At a minimum, the following will be recorded in the field logbook:

- Names and affiliations of all on-site personnel or visitors
- Weather conditions during the field activity
- Summary of daily activities and significant events
- Notes of conversations with coordinating officials
- References to other field logbooks or forms that contain specific information
- Discussions of problems encountered and their resolutions
- Discussions of deviations from the SAP or other governing documents
- Descriptions of all photographs taken

The field team may also use the field forms during certain sampling or data collection activities to document field activities. The same level of detail will be required for all field forms used during this investigation. Copies of the completed field forms will be stored in the project file.

2 Data Generation and Acquisition

This section describes the requirements for the following:

- Sampling Design (Section 2.1)
- Field Activities (Section 2.2)
- Sample Handling and Custody (Section 2.3)
- Laboratory Quality Assurance/Quality Control (QA/QC) (Section 2.4)
- Equipment Testing, Inspection, Maintenance, and Calibration (Section 2.5)

2.1 Sampling Design

Samples or data will be collected as outlined in the SAP. The SAP for this project is a collection of quarterly or one-time field sampling or data collection events that were prepared by NMCC and its contractors. Field activities will be implemented to optimize the time spent in the field by adhering to established scientific methods and procedures, leading coordinated field schedules, and sharing data with contractors to minimize duplication of data.

Data collected from these field activities will be used in the mine permitting process. This baseline data will also be useful in the design of mine facilities and as a reference during site reclamation activities.

2.2 Field Activities

Field activities have been broken into eight separate activities. These activities, which are outlined in the SAP, will be used to establish the baseline conditions at the Site:

- Climatological factors – The purpose of the monitoring program will be to collect baseline climatological data representative of the Site that satisfies the criteria of the New Mexico Surface Mining Act and the U.S. Environmental Protection Agency (EPA) on-site meteorological program guidance for dispersion modeling
- Vegetation survey – The purpose of the survey is to delineate current vegetation stratified according to disturbance history and to describe specific vegetation attributes for plant communities delineated within the Site. In addition, the survey will identify the presence of potential habitat for threatened and endangered species.
- Wildlife survey – Delineate and map current habitat, describe wildlife use of the area, complete a bird species inventory, complete a threatened or endangered species survey by comparing known records and habitat requirements with current field conditions to determine the likelihood of occurrence of all federal and state listed wildlife species, and determine species distribution by habitat and season.
- Soil survey and sampling – To determine the suitability of in-place soils in areas of proposed disturbance for use as a topdressing material during reclamation.
- Surface water sampling – To characterize the volumetric flow and water quality of seeps, springs, streams, and the pit lake.
- Groundwater sampling – To obtain necessary data to evaluate quantity and quality of all aquifers at the Site that could be impacted by mining activities, address data gaps identified during evaluation of the Draft EIS (BLM, 1996), meet the requirements set forth in the regulations in NMAC Title 19, Chapter 10, Part 6, and to meet the guidelines set forth in MMD's draft Guidance Document for Part 6 New Mining Operations Permitting under the New Mexico Mining Act.
- Historical and cultural properties survey – To locate and assess all cultural resources and historic properties within the area of potential effects.

2.3 Sample Handling and Custody

The following section describes sample handling procedures, including sample identification and labeling, documentation, chain of custody (COC), and shipping. This section applies to water, sediment, and geologic samples that are submitted to an analytical laboratory. Other sample handling and custody procedures for vegetation and other resources are described, where appropriate, in the SAP.

Each sample collected at the Site will be identified using a unique sample identification (ID) number. The description of the sample type and the point name will be recorded on the COC form, as well as in the field notes. Note that field duplicates and ERs will be given a unique sample ID. The association between primary, duplicate, and ER samples will be noted on the COC form.

A sample label will be affixed to each sample container. The label will be completed with the following information written in indelible ink: project name and location, sample ID number, date and time of collection,

preservative used (if applicable), collector's initials, and analysis requested. After labeling, each sample will be refrigerated or placed in a cooler containing ice.

Documentation of sample collection will be completed in permanent black or blue ink in the field logbook. All entries will be legible. The field team leader (FTL) and sampling personnel are responsible for proper documentation of all Site activities.

Standard sample custody procedures will be used to maintain and document sample integrity during collection, transportation, storage, and analysis. COC procedures provide an accurate written record that traces the possession of individual samples from the time of collection in the field to the time of acceptance at the laboratory.

The COC form will be placed in a waterproof plastic bag and taped to the inside of the shipping container used to transport the samples. The laboratory sample custodian will receive all incoming samples, sign the accompanying COC forms, and retain copies of the forms as permanent record. The laboratory sample custodian will record all pertinent information concerning the samples, including the persons delivering the samples, the date and time received, sample condition at the time of receipt (sealed, unsealed, or broken container; temperature; or other relevant remarks).

All samples will be either hand delivered or shipped to an accredited laboratory. Samples may need to be shipped to the laboratory in order to have them analyzed before the expiration of a particular sample's holding time.

2.4 Laboratory QA/QC

This section applies to water, sediment, and geologic samples submitted to accredited analytical laboratories. To ensure quality of laboratory analysis, the analytical laboratory will be required to analyze QA/QC samples as specified by the analytical methods. The laboratory will analyze method blanks, MSs, and LCSs.

Method blanks will be prepared at the frequency prescribed in the individual analytical method or at a rate of 5 percent of the total samples if a frequency is not prescribed in the method.

MSs will be analyzed at a frequency of 5 percent for soil and aqueous samples. The percent recoveries will be calculated for each of the spiked analytes and used to evaluate analytical accuracy. The RPD between spiked samples will be calculated to evaluate precision.

LCSs, or blank spikes, will be analyzed at the frequency prescribed in the analytical method or at a rate of 5 percent of the total samples if a frequency is not prescribed in the method. If percent recovery results for the LCS or blank spike are outside of the established goals, laboratory-specific protocols will be followed to gauge the usability of the data.

Sample quantitation limits (SQL), also referred to as practical quantitation limits, are PRRLs adjusted for the characteristics of individual samples. The PRRLs are chemical-specific levels that a laboratory should be able to routinely detect and quantitate in a given sample matrix. The PRRL is defined in the analytical method or in laboratory method documentation, and incorporates precision (reproducibility) assumptions for the analysis. The SQL takes into account changes in the preparation and analytical methodology that may alter the ability to detect an analyte, including changes such as use of a smaller sample aliquot or dilution of the sample extract. Physical characteristics such as sample matrix and percent moisture that may alter the ability to detect the analyte are also considered. The laboratory will calculate and report SQLs for all environmental samples.

The laboratory activities are overseen by a comprehensive quality assurance program to assure that laboratory practices and results adhere to its policies. The laboratory will provide a standard QA/QC report with all reports. This includes surrogate recoveries, spike recoveries, and method blanks.

The laboratory participates in the Wibby Environmental, third party, proficiency testing program. Wibby is accredited by A2LA and NIST/NVLAP. Results of all proficiency results are sent, by Wibby, to both the laboratory and to their accrediting authorities. The laboratory will also perform proficiency testing on a semiannual basis for all accredited tests. Water proficiencies in the water supply and water pollution studies will be performed in addition to soil proficiencies in hazardous waste pollution studies.

Proficiency results are reviewed by the laboratory manager and all personnel involved in reporting the data. Results that are marked as "check for error" and "unacceptable" are thoroughly reviewed and corrective actions are written for "unacceptable" data.

2.5 Equipment Testing, Inspection, Maintenance, and Calibration

All equipment used during the investigation will be properly tested, inspected, maintained, and calibrated. Samples collected during this investigation will be analyzed using both field and laboratory equipment. Calibration of the field equipment shall be recorded in the field logbook after each calibration event. The calibration procedure for each piece of field equipment used will be outlined in the final report.

The laboratory's QA plan and written operating procedures describing specific testing, inspection, maintenance, and calibration procedures for equipment will be followed. If required, maintenance procedures and schedules will be performed and documented.

3 Inspection and Acceptance of Supplies and Consumables

PMs have primary responsibility for identifying the types and quantities of supplies and consumables needed to complete projects and are responsible for identifying acceptance criteria for these items.

Supplies and consumables can be received either at the contractor's office or at a work site. When supplies are received at an office, the PM or FTL will sort them according to vendor, check packing slips against purchase orders, and inspect the condition of all supplies before they are accepted for use on a project. If an item does not meet the acceptance criteria, deficiencies will be noted on the packing slip and purchase order and the item will then be returned to the vendor for replacement or repair.

Procedures for receiving supplies and consumables in the field are similar. When supplies are received, the PM or FTL will inspect all items against the acceptance criteria. Any deficiencies or problems will be noted in the field logbook and deficient items will be returned for immediate replacement.

Analytical laboratories are required to provide certified clean containers for all analyses. These containers must meet EPA standards as described in *Specifications and Guidance for Obtaining Contaminant-Free Sampling Containers* (EPA, 1992).

4 Data Management

All field and analytical data collected during this investigation will be provided to MMD in the Baseline Characterization Report. Field data will be recorded in the logbook and/or field forms and will be included in the appendices. Analytical data will be summarized, tabulated, analyzed, and provided in the body of the final

report. The original laboratory data will be provided in an appendix of the final report. Some data may be presented graphically.

5 Assessment, Response Actions, and Reports to Management

NMCC and MMD will oversee collection of environmental data using the appropriate assessment and audit activities. Any problems encountered during an assessment of field investigation or laboratory activities will require appropriate corrective action to ensure that the problems are resolved. The corrective actions will be discussed with MMD and will be implemented after approval from MMD is received. NMCC will perform routine audits of their subcontractor's performance. In addition, the subcontractor's project managers will ensure that the work done under their assigned tasks complies with the QAPP and will report non compliance, problems, or other issues to NMCC in a timely manner agreed upon between NMCC and its subcontractors.

Effective management of environmental data collection requires: 1) timely assessment and review of all activities, and 2) open communication, interaction, and feedback among all project participants. NMCC and its contractors will use verbal communication with MMD oversight personnel, electronic communication, and monthly status reports to address any project-specific quality issues and to facilitate timely communication of these issues. NMCC and its contractors will develop a communications protocol to communicate with the MMD and solicit the MMD for concurrence with these communication procedures.

6 Data Evaluation and Usability

This section describes the procedures that are planned to review and evaluate field and laboratory data. This section also discusses procedures for verifying that the data are sufficient to meet MQOs for the project.

Review and evaluation of the data generated during field and laboratory activities are essential to obtaining defensible data of acceptable quality. Project team personnel will review field data to identify inconsistencies or anomalous values. Any inconsistencies discovered will be resolved as soon as possible by seeking clarification from field personnel responsible for data collection. All field personnel will be responsible for following the sampling and documentation procedures described in this SAP so that defensible and justifiable data are obtained.

Data values that are significantly different from the population are called "outliers." A systematic effort will be made to identify any outliers or errors before field personnel report the data. Outliers can result from improper sampling or measurement methodology, data transcription errors, calculation errors, or natural causes. Outliers that result from errors found during data verification will be identified and corrected; outliers that cannot be attributed to errors in sampling, measurement, transcription, or calculation will be clearly identified in project reports.

6.1 Laboratory Data Verification

Laboratory personnel will verify analytical data at the time of analysis and reporting and through subsequent reviews of the raw data for any nonconformances to the requirements of the analytical method. Laboratory personnel will make a systematic effort to identify any outliers or errors before they report the data. Outliers that result from errors found during data verification will be identified and corrected; outliers that cannot be attributed to errors in analysis, transcription, or calculation will be clearly identified in the case narrative section of the analytical data package.

6.2 Laboratory Data Evaluation and Usability

All laboratory data will be evaluated. The data evaluation strategy will not be a full data validation process, but will determine if the analytical results are within the QC limits set for the project. As part of this evaluation, the data usability will be assessed.

7 Reconciliation with User Requirements

After environmental data have been reviewed and evaluated in accordance with the procedures described in Section 7.0, the data must be further evaluated to assess whether MQOs have been met.

To the extent possible, EPA's data quality assessment (DQA) process will be followed to verify that the type, quality, and quantity of data collected are appropriate for their intended use. DQA methods and procedures are outlined in EPA's *Guidance for Data Quality Assessment, Practical Methods for Data Analysis* (EPA, 2000b). The DQA process includes five steps: (1) review the sampling objectives and sampling design, (2) conduct a preliminary data review, (3) select a statistical test, (4) verify the assumptions of the statistical test, and (5) draw conclusions from the data. In the case of water, sediment, and geologic samples, no statistical analysis is planned at this time. Statistical analyses planned for ecological and cultural resources data are defined in Sections 4, 5, and 10 of the SAP.

When the five-step DQA process is not completely followed because the sampling objectives are qualitative, data quality and data usability will be systematically assessed. This assessment will include:

- A review of the sampling design and sampling methods to verify that these were implemented as planned and are adequate to support project objectives.
- A review of project-specific data quality indicators for PARCC and project reporting limits to evaluate whether acceptance criteria have been met.
- A review of project-specific sampling objectives to assess whether they have been achieved by the data collected.
- An evaluation of any limitations associated with the decisions to be made based on the data collected (for example, if data completeness is only 90 percent compared to a project-specific completeness objective of 95 percent, the data may still be usable to support a decision, but at a lower level of confidence).

The final report for the project will discuss any potential impacts of these reviews on data usability and will clearly define any limitations associated with the data.

8 References

American Society for Testing and Materials (ASTM), 2000, Standard practice for description and identification of soils (visual-manual procedure): ASTM Standard D 2488-00.

Bureau of Land Management (BLM), 1996, Draft environmental impact statement (DEIS), Copper Flat Project: Las Cruces, N. Mex., U.S. Department of the Interior. Prepared by ENSR, Fort Collins, Colo.

Environmental Protection Agency (EPA), 1992, Specifications and guidance for obtaining contaminant-free sampling containers: Washington, DC, Office of Solid Waste and Emergency Response, EPA/A540/R-93/051. December.

———.2000a, Data quality objectives process for hazardous waste site investigations, EPA QA/G-4HW: Washington, DC, Office of Environmental Information, EPA/600/R-00/007. January.

———.2000b, Guidance for data quality assessment, practical methods for data analysis, EPA QA/G-9, QA00 Update: Washington, DC, Office of Environmental Information, EPA/600/R-96/084. July.

———.2000c, Guidance for the data quality objectives process, EPA QA/G-4: Washington, DC, Office of Environmental Information, EPA/600/R-96/055. August.

Figures



Figure 1. Project Organization



Figure 2. Parametrix Organizational Chart

Table

Table 1
INTERA Key Personnel and Responsibilities

Name	Organization	Role	Responsibilities	Contact Information
Ms. Cindy Ardito	INTERA	Program Quality Assurance (QA) Officer	Participates in development of technical approach. Reviews technical deliverables. Provides technical oversight during data collection	INTERA Inc. 6000 Uptown Blvd. NE, Suite 220 Albuquerque, NM 87110 (505) 246-1600, (505) 246-2600 FAX ext. 1206 cardito@intera.com
Mr. Peter Castiglia	INTERA	Project Manager/ Technical Lead	Responsible for overall project execution and for coordination with regulatory agencies and contractors. Actively participates in Data Quality Objective process. Provides management and technical oversight during data collection.	INTERA Inc. 6000 Uptown Blvd. NE, Suite 220 Albuquerque, NM 87110 (505) 246-1600, (505) 246-2600 FAX ext. 1217 pcastiglia@intera.com
Mr. Lee Dalton	INTERA	Field Team Leader (FTL) – Groundwater	Responsible for directing day-to-day field activities conducted by INTERA and subcontractor personnel. Verifies that field sampling and measurement procedures follow the Sampling and Analysis Plan. Provides project manager with regular reports on status of field activities.	INTERA Inc. 6000 Uptown Blvd. NE, Suite 220 Albuquerque, NM 87110 (505) 246-1600, (505) 246-2600 FAX ext. 1213 ldalton@intera.com
Mr. Justin Jayne	INTERA	Field Team Leader (FTL) – Surface Water	Responsible for directing day-to-day field activities conducted by INTERA and subcontractor personnel. Verifies that field sampling and measurement procedures follow the Sampling and Analysis Plan. Provides project manager with regular reports on status of field activities.	INTERA Inc. 6000 Uptown Blvd. NE, Suite 220 Albuquerque, NM 87110 (505) 246-1600, (505) 246-2600 FAX ext. 1220 jjayne@intera.com
Ms. Angela Persico	INTERA	On-Site Safety Officer	Responsible for implementing health and safety plan for determining appropriate site control measures and personal protection levels. Conducts safety briefings for INTERA and subcontractor personnel and site visitors. Can suspend operations that threaten health and safety.	INTERA Inc. 6000 Uptown Blvd. NE, Suite 220 Albuquerque, NM 87110 (505) 246-1600, (505) 246-2600 FAX ext. 1207 apersico@intera.com
Ms. Angela Persico Mr. Spencer Whitman Mr. Konrad Clark Ms. Annelia Tinklenberg	INTERA	Field Sampler(s)	Responsible for collecting representative samples and conducting necessary field activities specified in Sampling and Analysis Plan. Works under supervision of field team leader. Ensures proper sampling and handling procedures.	INTERA Inc. 6000 Uptown Blvd. NE, Suite 220 Albuquerque, NM 87110 (505) 246-1600, (505) 246-2600 FAX

Name	Organization	Role	Responsibilities	Contact Information
Mr. Bob Powell	Class One Technical Services, Inc.	Project Manager	Responsible for overall project execution and for coordination with regulatory agencies and contractors. Actively participates in Data Quality Objective process. Provides management and technical oversight during data collection by Class One Technical Services.	Class One Technical Services, Inc. 3500 Comanche Rd. NE Suite G Albuquerque, NM 87107 (505) 830-9680
Mr. Jens Deichmann	Parametrix	Project Manager – Ecological and Cultural Resources	Responsible for coordination with regulatory agencies and contractors. Actively participates in Data Quality Objective process. Provides management and technical oversight during data collection by Parametrix.	Parametrix Incorporated 8801 Jefferson NE; Bldg. 2 Albuquerque, NM 87113 (505) 998-5552 jdeichmann@parametrix.com
Mr. Chris Parrish	Parametrix	FTL - Cultural Resources	Responsible for directing day-to-day field activities conducted for cultural resources by Parametrix and subcontractor personnel. Verifies that field sampling and measurement procedures follow the Sampling and Analysis Plan. Provides project manager with regular reports on status of field activities.	Parametrix Incorporated 8801 Jefferson NE; Bldg. 2 Albuquerque, NM 87113 (505) 821-4700
Mr. Jim Nellessen	Parametrix	FTL – Natural Resources	Responsible for directing day-to-day field activities conducted for natural resources by Parametrix and subcontractor personnel. Verifies that field sampling and measurement procedures follow the Sampling and Analysis Plan. Provides project manager with regular reports on status of field activities.	Parametrix Incorporated 8801 Jefferson NE; Bldg. 2 Albuquerque, NM 87113 (505) 821-4700
Mr. Chad McKenna	Parametrix	Technical Lead – Geographic Information Systems (GIS)	Responsible for directing day-to-day activities conducted for GIS by Parametrix and subcontractor personnel. Verifies that GIS data collection procedures follow the Sampling and Analysis Plan. Provides project manager with regular reports on status of GIS data.	Parametrix Incorporated 8801 Jefferson NE; Bldg. 2 Albuquerque, NM 87113 (505) 821-4700
Mr. Mark Willow	SRK Consulting	Project Manager – Geologic Sampling	Responsible for coordination with regulatory agencies and contractors. Actively participates in Data Quality Objective process. Provides management and technical oversight during data collection by SRK.	SRK Consulting 250 Neil Road, Suite 300 Reno, Nevada 89502 (775) 828-6800 mwillow@srk.com
Dr. Robert Bowell	SRK Consulting	Technical Lead – Geologic Sampling	Responsible for directing day-to-day activities conducted for geologic by SRK and subcontractor personnel. Verifies that geologic data collection procedures follow the Sampling and Analysis Plan. Provides project manager with regular reports on status of geologic data collection and results.	SRK Consulting (UK) Ltd. 5th Floor, Churchill House 17 Churchill Way Cardiff, CF10 2HH, UK +44 (0) 29 2034 8150 egrbowel@srk.co.uk

11-10-2010

NEW MEXICO
ENVIRONMENT DEPARTMENT

Ground Water Quality Bureau

1190 St. Francis Drive
P.O. Box 5469, Santa Fe, NM 87502
Phone (505) 827-2918 Fax (505) 827-2965
www.nmenv.state.nm.us
William C. Olson, Bureau Chief

BILL RICHARDSON
Governor
DIANE DENISH
Lieutenant Governor

RON CURRY
Secretary
SARAH COTTRELL
Deputy Secretary

MEMORANDUM

DATE: November 10, 2010

TO: Holland Shepherd, Program Manager, Mining Act Reclamation Program

FROM: Greg Huey, NMED Ground Water Quality Bureau
David Menzie, NMED Surface Water Quality Bureau

THROUGH: Kurt Vollbrecht, NMED Mining Act Team Leader

RE: Comments on New Mexico Copper Corporation, Copper Flat Mine, Sampling and Analysis Plan, Permit no. SI027RN

The New Mexico Environment Department (NMED) received correspondence from the Mining and Minerals Division (MMD) on September 29, 2010 requesting that NMED review and provide comments on the Sampling and Analysis Plan (SAP) referenced above. MMD requested comments be submitted within 30 days of receipt in accordance with the New Mexico Mining Act Requirements. In order to facilitate a sight inspection, that deadline was extended until November 12, 2010. The NMED Surface Water Quality Bureau (SWQB) and Ground Water Quality Bureau (GWQB) have submitted comments in this memorandum jointly.

NMED SWQB Comments:

The introductory paragraph to Section 8, Surface Water, includes the statement "Numerous ephemeral tributaries feed into the Rio Grande from the west, but none contribute perennial flow to the Rio Grande." Lack of perennial flow to the Rio Grande does not negate the fact that both Las Animas Creek and Percha Creek include perennial reaches that support fisheries and water quality must be protected as required under §20.6.4.103 of the New Mexico Administrative Code (NMAC). This paragraph should be reworded to acknowledge the important contribution of these waters of the State as a natural resource.

Section 8.1, Surface Water Characteristics of Site and Vicinity: During the joint agency inspection that was conducted on October 26, 2010 (Inspection), Grayback Arroyo exhibited surface water pools and small flows along a reach of several hundred yards that did not appear to be the result of direct precipitation. In addition, there is significant riparian vegetation indicating that Grayback Arroyo

should be classified as an intermittent water of the State pursuant to §20.6.4.98 NMAC. The SAP should acknowledge this classification rather than describing Grayback Arroyo as an ephemeral channel.

Section 8.2, Historical Data: This section states that "Surface water at the Site was most recently investigated by ABC (1996), who collected flow and water quality from Percha Creek and Las Animas Creek." In 2004, the SWQB conducted a water quality survey that included Las Animas Creek and Percha Creek. These data are available from the State through a public records request.

Section 8.6.1.2, Water Quality Sampling: As observed during the Inspection, set up and placement of the automated samplers appeared adequate. SWQB staff did suggest to the applicant that stream sample collection targeting the rising limb of the hydrograph would be preferred since research indicates that the first surge of storm runoff is likely to carry the most pollutants.

Section 9 of the SAP states that the Rio Grande is the only significant surface water resource in the area. This statement is questionable since perennial reaches of the tributaries originating from the eastern side of the Black Range provide important sources of surface water to residents west of the Rio Grande and provide unique riparian and wildlife habitat year round. The SAP then states that Las Animas Creek and Percha Creek are intermittent streams. As previously discussed, these streams contain perennial reaches that support fisheries and should be acknowledged as such.

NMED GWQB Comments:

Section 7.4 of the SAP proposes to review the existing geochemical data prior to determining the locations for collection of additional samples for identification of ore and waste rock zones within the proposed pit outlines. A phased approach is proposed that will contribute to a sampling program focused on the main material types within the proposed pit outlines, with more samples being collected from the material types with the greatest predicted tonnage. NMED agrees that this phased approach is an efficient methodology for identification of geologic strata but requests that addendums to the approved SAP be submitted for agency approval at developmental intervals prior to moving forward with the proceeding stage of geochemical sampling.

Section 7.4.2 states that "exploration drilling is currently ongoing in the expansion areas." During the Inspection, a map of the proposed exploration drilling areas was discussed, but at this time no minimal impact exploration application has been submitted for NMED review. Such an application is necessary before exploratory drilling may proceed.

Section 7.4.3 mentions "a number of field tests" that may be used to determine the geochemistry of specific material types prior to moving on with standard static testing. These field tests should be identified and described in the requested addendum to the SAP for geochemical sampling.

Section 8.6.2.1 discusses using five profiles and two tie lines to determine Pit Lake depth; however, Figure 8-2 shows eight profile lines. This discrepancy should be resolved.

Section 9.1.1 cites Figure 9-2 as depicting three aquifers: the crystalline bedrock aquifer, the Santa Fe Group aquifer system, and the Quaternary alluvial aquifer. Figure 9-2 does not provide any reference to the crystalline bedrock aquifer and does not function as a "conceptual model" of the Site ground water flow system as the title suggests. This figure should be replaced with an appropriately designed diagram.

Section 9.1.2.1 states that ground water elevation data are derived from wells greater than 4,000 feet distance from the Pit Lake, but then states confidently that the ground water gradients in the area are toward the Pit Lake. The section also references Figure 9-6 as demonstrating ground water gradients toward the Pit Lake; however, the vertical scales on opposite sides of this diagram are not coordinated: the scale on the left side of the figure is approximately 80 feet to one inch, while the scale on the right side of the figure is approximately 5 feet to one inch. This gross discrepancy in scale negates the effectiveness of this figure as a tool in ground water gradient interpretation. In addition, the figure, circa 1998, shows the Pit Lake elevation at 5,436.5 ft amsl, while the text in the section reported the Pit Lake elevation at 5,442 ft amsl in 1997 and 5,444 ft amsl in 2010. The section concludes by stating that the Pit Lake elevation remains below the pre-mining **water** level elevation of 5,500 to 5,540 ft amsl. This is in contradiction to the Preliminary Environmental Impact Statement (BLM, 1999) cited previously in the section, which describes pre-mining **ground** elevation as 5,500 to 5,540 ft amsl.

Figure 9-9 shows well EIW as the closest monitoring well to the Pit Lake. However, the SAP does not include water depths in this well or Pit Lake elevations in the monitoring network. A denser monitoring well field may be necessary to delineate a local ground water divide, and the SAP should require that Pit Lake elevation measurements be taken at the same time as water level measurements in adjacent ground water monitoring wells to better define the potentiometric surface across the Site.

Statements regarding site-wide ground water levels should be re-evaluated pending a more thorough hydrological investigation.

Section 9.1.3 states that concentrations of total dissolved solids (TDS) and sulfate down-gradient of the Pit Lake have increased gradually over time and suggests that impacts to water quality in the vicinity of the Pit Lake may be naturally occurring. However, Figure 15 from Raugust (2003) shows an increase in TDS from approximately 550 mg/L to almost 1,000 mg/L between 1996 and 1998 in well GWQ-96-23A. Further review of Raugust (2003) reveals conflicting statements regarding wells in location to the Pit Lake. In the "Study Area Investigations" section, the manuscript states that

> Prior to 1996, only one well was available for sampling groundwater in the vicinity of the pit lake. This monitoring well, GWQ-4, is located approximately one-half mile east of the existing pit.

However, in the "Conclusions" section the manuscript references water quality collected from monitoring well GWQ-5 in 1981. NMED recommends that, rather than adopt conclusions from references not submitted for agency review, NMCC provide appropriate data and develop conclusions based on the analysis of those data.

Section 9.1.5 references the MMD Guidance Document for Part 6 New Mining Operations, stating that the SAP must include supporting material to justify the use of historic data. NMED requests that, regardless of justification, an inventory of all existing data be compiled and reported prior to validation and possible exclusion of these data.

Section 9.3 proposes reducing the number of wells monitored for water quality parameters after the initial four quarters of data collection. NMCC should be aware that under NMED abatement plan requirements and the discharge plan permitting process these wells will require separate evaluation by NMED prior to being removed from any approved sampling plan.

Section 9.4.2 discusses the possible need for installation of additional monitoring wells. New well drilling and installation must meet NMED and NM OSE requirements. New well locations should be proposed to NMED under a Stage One Abatement Plan and/or Discharge Plan proposal. In addition, this section references Table 9-4 for a summary of previous pumping tests and resulting aquifer characteristics. This table does not provide sufficient information to determine the source or validity of the data provided and the SAP should provide for agency review a summary of the individual aquifer tests used to compile these data prior to determination as to the adequacy of the existing data to support the hydrologic impact analysis.

Section 9.7 references Figure 9-9 to provide locations of the wells proposed for sampling in Table 9-2. Well GWQ-12 at the southern end of the tailing disposal facility is not proposed for water quality sampling. As previously stated, well EIW is also not included in the SAP. NMCC should provide justification with supporting data as to why these and other available wells are excluded from the SAP.

During the Inspection, a previously unidentified well was located adjacent to the lower Greyback Arroyo downstream of the tailing dam. It was supposed that this well may be the McCravey-Greyback well. A data review should be conducted for this well and justification for or against its inclusion in the SAP should be included. Furthermore, this well was open to the environment and efforts should be made to properly secure it with an appropriate cap.

Further review and evaluation of the SAP relative to a Ground Water Discharge Permit application and Stage One Abatement Plan may result in additional comments. At this time NMED has not received documentation regarding permitting requirements for the Copper Flat Mine pursuant to the Water Quality Control Commission Regulations (20.6.2 NMAC).

If you have any questions, please contact Greg Huey at (505) 827-1046.

cc: William C. Olson, Chief, GWQB
Marcy Leavitt, Chief, SWQB
Charles Thomas, Chief, Mine Reclamation Bureau
Mary Ann Menetrey, NMED MECS

1-18-2011

New Mexico Energy, Minerals and Natural Resources Department

Susana Martinez
Governor

Harrison H. Schmitt
Cabinet Secretary Designee

Charles Thomas
Acting Division Director
Mining and Minerals Division

7008 1300 0001 6103 4086

CERTIFIED MAIL – RETURN RECEIPT REQUESTED

January 18, 2011

Mr. Steve Raugust
New Mexico Copper Corporation
2425 San Pedro, NE, Suite 100
Albuquerque, New Mexico 87110

RE: Review and Comments on Sampling and Analysis Plan, Copper Flat Mine, New Mexico Copper Corporation, Permit No. SI027RN

Dear Mr. Raugust,

Pursuant to 19.10.6.602.D(12) NMAC, the New Mexico Mining and Minerals Division (MMD) has reviewed the submittal from New Mexico Copper Corporation (NMCC) titled, *Sampling and Analysis Plan for Copper Flat Mine* (SAP), dated September 2010, in support of a forthcoming application for a new mine, Permit No. SI027RN, for its proposed Copper Flat copper mine in Sierra County, New Mexico.

After review of the SAP and supporting information, MMD has distributed the SAP and supporting information, Pursuant to 19.10.6.602.D(12)(b) NMAC, to: the New Mexico Environment Department (NMED), the New Mexico Department of Game and Fish (NMDG&F), the New Mexico Office of the State Engineer (NMOSE), the New Mexico Department of Cultural Affairs Historic Preservation Division (NMHPD), the New Mexico State Forestry Division (NMSFD), and the Bureau of Land Management (BLM) for their (Agency) review and comments. MMD has received written comments from NMED, NMOSE, NMDG&F, and the NMHPD, as enclosed. In addition, MMD has reviewed the SAP, and supporting information, and MMD's comments are also enclosed with this letter.

The MMD and Agency review and comments have identified areas where additional information is needed in support of the SAP. Pursuant to 19.10.6.602.D.(12).(b), MMD considers the submittal and evaluation of the SAP complete. NMCC shall address the comments on the SAP in the Baseline Data Report, to be included in the permit application for the Copper Flat Mine. Pursuant to 19.10.6.602.D(12)(c) NMAC, NMCC may request a conference with MMD to discuss the comments on the SAP.

Please be aware that, depending on results of the data collected and development of the operation and reclamation plan yet to be submitted, additional sampling may be required before a permit is issued.

Additionally, please be advised that other permits, from other agencies, will be required regarding the Copper Flat Mine. The information provided by NMCC to MMD may not satisfy the requirements for the eventual approval of any additional permits. NMCC must contact the agencies responsible for those permits, including, but not limited to, the BLM, NMED and NMOSE.

Please contact me at 505-476-3437, or Chris Eustice at 505-476-3438 or at chris.eustice@state.nm.us, if you have any questions.

Sincerely,

Holland Shepherd, Program Manager
Mining Act Reclamation Program (MARP)
Mining and Minerals Division

Enclosures: NMED, Comments on NMCC's Copper Flat SAP, November 10, 2010
NMDG&F, Copper Flat SAP Comments, October 29, 2010
NMHPD, Comments on Copper Flat SAP, October 26, 2010
NMOSE, Comments for Copper Flat SAP, October 12, 2010
MMD Comments on Copper Flat SAP

cc: Chuck Thomas, Executive Manager, Mine Reclamation Bureau
Chris Eustice, Permit Lead, MARP
NMED, Kurt Vollbrecht
DCA, Michelle Ensey
OSE, Kevin Myers
BLM-Las Cruces, Mike Smith
Mine File (SI027RN)

MINING AND MINERALS DIVISION COMMENTS ON THE COPPER FLAT MINE SAMPLING AND ANALYSIS PLAN (SAP)

GENERAL COMMENTS

The SAP needs to commit to collecting appropriate baseline data in conjunction with the planned well field (water supply) and any, and all, associated utility corridor(s).

CHAPTER 1 INTRODUCTION

Figures 1-2 and 1-3 depict the Site permit boundary, but also should depict the associated well field and any related utility corridor(s).

CHAPTER 4 VEGETATION

1. Section 1.1 of the SAP lists approximately 2200 acres as being inside of the Site permit boundary, with a recommended number of 93 randomly selected vegetative transects to be conducted at the Site . MMD recommends additional attention be directed to areas of greater vegetative density and diversity, such as the Greyback Arroyo which intersects the Site from east-to-west. Greyback Arroyo has sections of intermittent wetlands and ephemeral grass/shrub areas. MMD recommends an additional two (2) vegetative transects be conducted in this arroyo region. Additionally, this may be a good area for the sampling of small mammals and reptiles.
2. Section 4.5.1 (page 4-3) of the SAP states, *Some areas (namely previous mining pits) are void of vegetation altogether but reflect the pre-mining vegetation condition in these areas under the current permit application.* NMCC needs to evaluate these areas, taking into consideration that pit areas will will be reclaimed during the reclamation phase of the mining project.

CHAPTER 5 WILDLIFE

1. Live traps, and/or pit-falls, need to be checked early in the day to avoid heat stress in the southern New Mexico climate.
2. In this environment, stick nests are relatively easy to locate in the mesquite, pinon, juniper, and other trees reminiscent of the regional vegetative community. Additionally, raptor surveys will need to be conducted in seasonally appropriate times, as well as diurnally appropriate times, to ensure that adult raptors, that are shading eggs or nestlings, are not frightened away from their nests, thereby risking eggs to be damaged or subject to related heat stresses.

CHAPTER 6 TOPSOIL SURVEY AND SAMPLING

General Comments

Objectives for the Topsoil Survey and Sampling plans are not clear to MMD. In MMD's view, the first objective of the SAP should be to verify and expand upon previous mapping efforts to provide a more detailed map of soil units. After soil units are defined, each unit, assuming that some portion occurs within an area that can be practicably salvaged, should be sampled at least once to provide an estimate of soil quality within that unit. Separate mapping and sampling efforts should lead to

estimates of salvageable and suitable soil resources for each mapping unit and a volume estimate of materials across the permit area.

Sections 6.1 and 6.2

1. Section 6.1 notes that "Over 63 percent of the areas targeted by the proposed operation were disturbed" by previous operations. Previously disturbed areas complicate the soil survey. A description of past disturbance impacts to soil seems an important component of any effort to inventory and characterize salvageable resources at the site. For example, the nature and degree of disturbance is not described in the current tailings impoundment, an area that coincides with deeper soils of the Scholle-Ildefonso association, and an area identified in Section 6.9 as a potential source of materials to meet an expected topsoil deficit at the site. Please provide a survey and sampling plan that stratifies major areas, not only by previous mapping information (NRCS), but by the nature and extent of disturbed, versus.native, undisturbed areas, as first step in the construction of a soil inventory.
2. For soils, MMD views the SAP effort as an attempt to inventory soil resources within the permit area in order to enumerate the volumes of suitable and salvageable resources among the various mapped units. Steep slopes that would prohibit safe equipment operation, other areas where salvage would be impractical, as well as unsuitable soil materials, should not be included within this inventory. Further, no assumptions should be made about what amount of soil resources will be required in reclamation. Requirements for soil volumes needed for reclamation will be determined later in the permitting process.

Section 6.5

1. MMD will require that all areas within the permit area be surveyed to provide an estimate of suitable and salvageable soil resources to provide a gross estimate of resources in areas not planned for disturbance, as well as a more refined (Order 1) estimate, supported by sampling, in areas planned for disturbance. Regolith character within soil map units should be described to at least 60 inches in depth, or until materials unsuitable for reclamation or bedrock is encountered. Where soils appear to be deeper and favorable for salvage, such as Scholle-Ildelfonso areas NE of the pit lake, the tailings area and generally along the eastern side of the permit area, additional exploration is warranted to provide a full inventory.
2. Based on the high proportion of gravel and cobble that are common across much of the permit area surface, it seems to MMD that a hand auger may provide little benefit to assess soils, except for the most shallow depths. It is likely that a hand shovel, and/or backhoe tools, may be required to assess soils, to describe "typical" pedons. An experienced soil scientist may often infer soil properties to the full depth of the profile from surface expression if he/she is familiar with soils in the area and how soil is expressed along toposequences. However, some full excavation (shovel/backhoe) will be required to confirm those estimates.
3. Described methods are not clear as to how soil mapping units will be delineated before transects are walked. Using an ArcGIS tool, *the required number of random transects will be placed in each disturbed area.* How is the "required number" of transects determined to produce an Order 1 survey? Are only previously "disturbed" areas to be surveyed, or does this term refer to areas of planned disturbance in the future? The meaning of a statement that "If field conditions do not match the stratum intended, the transect will be moved to a nearby location within the disturbed area" is not clear.

4. The SAP specifies that a total of six soil samples will be obtained. Further, these samples are described as composite samples across the full depth of a sampled profile. Since the NRCS mapping may have missed important map delineations or inclusions that may be important for salvage, this number of samples may be insufficient. Within areas planned for disturbance each mapping unit should be sampled at least once. As is described in the SAP, a high content of carbonates, or excessively high content of coarse fragments, may render a horizon as unsuitable for salvage. Therefore, MMD will not accept samples composited across the full depth of a profile. Each major horizon should be sampled discretely. The appropriate number of soil samples collected should be determined after the mapping units and important inclusions are described by the survey. Methods for description of soil horizons and properties should follow standard methods for soil survey (1993, USDA Soil Survey Manual).
5. Presently, methods to estimate soil texture are described for pre-determined intervals of depth. Visual estimates of soil texture should be limited to gravel and larger-sized fractions only. Hand textures are appropriate for fine-earth fractions. Estimates should be made per distinct pedogenic profile breaks, rather than for fixed depth intervals. Again, methods for description of soil horizons and properties should follow standard methods for soil survey (1993, USDA Soil Survey Manual).
6. Section 6.5.1.2 describes methods to conduct soil sampling where locations are found below a water surface. To MMD, it seems that few, if any, representative samples will be found in these conditions unless some sampling is anticipated in the immediate vicinity of the Grayback drainage. Please clarify.

Section 6.8 and Table 6.2.

1. Potentially conflicting methods are referred to in Section 6.8 and Table 6.2 for laboratory analysis of samples. Section 6.8 refers to more conventional methods used for soils (Methods of Soil Analysis, MOSA) that include important procedures for sample preparation, as well as instrumental analysis. Table 6.2 refers to EPA methods (e.g. 200.7) that are suitable for aqueous samples. Should MMD assume that sample preparation methods described in MOSA will be used for sample preparation and that EPA-described instrumentation will be used for analysis? Please describe sample preparation techniques (filtration, extractants, digestion, etc.) and resolve any conflicts between preparation and analytical methods.
2. Laboratory analytical suite. Please provide both total and plant-available forms of: As, B, Cd, Ca, Cu, Fe, Hg, Mg, Mn, Mo, Ni, P, K, Se, and Zn of fine-earth (<2mm) sample fractions. Soluble forms (only) are sufficient for Cl, Na and nitrate-N ions. Soluble Se should be assessed following hot-water extraction. While high SAR values are not anticipated for this area, SAR may be optionally included in the analytical suite if component ions are measured from paste extracts. The analytical suite should also include calcium carbonate percent, soil paste electrical conductivity, and total organic carbon content. The grain size analysis method proposed (Plumb, 1981) is a non-standard method that may produce results that are difficult to interpret in relation to other data sets. Please select a more standard method for grain size analysis that would utilize sieves (for USDA fine and very fine sand fractions), hydrometer or pipette, and a description of how fractions larger than (USDA, 2 mm) sand will be incorporated to depict full-range particle size description. For particle size analysis, samples containing high content of soluble salts or carbonates may require pre-treatment. USDA classification of particle size is preferred over Unified.

CHAPTER 7 GEOLOGY

1. The summary of the Copper Flat geology in the SAP is excellent and well written. However, the BDR should provide a more specific description of the objective and rational for completing additional geologic sampling to allow a thorough evaluation by MMD and other reviewers. The BDR should provide a clear description of the "professional and scientific judgment" on the part of NMCC and its contractor(s), which would allow for concurrence by MMD or other reviewers. Below is an example of the general nature of the geology section of the sampling and analysis plan:
   a. Page 7-6, paragraph 3, states "additional samples will be required for waste rock characterization in order to create a sample database that is vertically and horizontally representative of waste rock associated with the current project. In addition, ore-grade samples will need to be collected. Following the data review and development of estimated waste rock and ore volumes in Step 1, NMCC's contractor will select sample intervals from exploration drill holes to fill the identified data gaps." Since no analysis of the data gaps appears to have been performed on the historical data prior to submittal of the SAP, nor are the horizontal locations and/or vertical intervals of anticipated future samples clearly identified (see comment No.3 below), MMD is unable to assess whether this plan will result in an adequate horizontal and/or vertical sampling suite for the Baseline Data Report (BDR). The rational for selecting sample intervals must be better described and clarified in the Baseline Data Report.
2. Page 7-5, in the last paragraph, states that the estimated tonnages of waste rock and ore material types will be obtained from a block model, in order to define the number of samples required to characterize each material type, and that the sampling program will focus on the main material types with more samples being collected from the material types with the greatest predicted tonnage. However, Page 7-6, in the last paragraph, states that a field screen will be applied to define a representative sample set, in contrast to selecting a set number of samples based on the predicted amount of waste rock. The statements on these two pages appear contradictory. In the BDR, please clearly state the methodology employed to collect geologic samples and a description of the "field screening" that will be used to define the representative sample set(s).
3. Page 7-7, in the 5th paragraph, states that an estimated 80 samples will be selected for static testing. The SAP then refers the reviewer to Figure 7-5, which shows far more than 80 sampling locations. It is unclear from the description on Page 7-7 and Figure 7-5:
   a. the locations of the ~80 samples that are anticipated to be collected;
   b. the rationale as to why ~80 samples were selected as the appropriate sampling suite (see comment #2 above: was this determined from a tonnage based approach, geologic field screening approach, horizontal spacing, or some combination of these methods?);
   c. whether the samples from 1997 shown in Figure 7-5 represent historic data that already exists or whether these are locations for future laboratory analysis; and
   d. the rationale as to why these locations were selected, if this figure represents future samples to be collected (i.e. data gap in-filling?).

   The BDR should clarify the rationale of the sample locations and sample set size, and correct any inaccuracies in the associated Figures..

CHAPTER 8 SURFACE WATER

1. Section 8.6.1.3 provides a description of stream sediment sampling primarily in conjunction with co-located surface water samples, Pursuant to 602.13.g.(v), the SAP should include a plan to sample

the sediment within drainages, dry or wet, downstream (Greenhorn and Greyback Arroyo's) of the permit area to characterize baseline conditions.

2. The SAP needs to commit to collecting additional sediment samples outside the permit area sufficient to characterize the adjacent drainage systems (e.g. Percha and Los Animas Creeks).
3. To baseline characterize metals in sediment downstream of the site, the surface water drainage systems should be divided into reaches, where appropriate and sampled accordingly. Additionally, the text should provide a description of how the surface water drainages are divided or segmented, and the rational employed.
4. The SAP should include sufficient sediment sampling in adjacent watersheds (e.g. Percha and Los Animas Creeks) to characterize the respective baseline conditions.
5. A figure should be included that depicts the sediment sampling locations.
6. Figure 8.1 seems to have mislabeled the main trunk of Greenhorn Arroyo as "Greyback Arroyo," and should be checked against the text in the second paragraph of Section 8.1

CHAPTER 9 GROUNDWATER

1. The background and regional hydrogeology sections are comprehensive and informative. However, the groundwater section of the SAP is too conceptual in nature. The BDR needs to provide the specifics necessary for MMD to thoroughly evaluate the appropriateness of the plan. The plan appears to rely heavily on professional judgment, on the part of NMCC and/or its contractors, thereby making it difficult for MMD to determine whether the plan will result in a technically complete BDR. Some examples of the general nature of the groundwater sampling plan are listed below:
   a. Page 9-6, Section 9.1.4, describes NMED's concerns about groundwater impacts, and states that "groundwater impacts from the existing unlined tailing impoundment have been documented, but have not been fully characterized." Page 9-9, Section 9.5, states "...if new wells are added to the monitoring well network, they will be constructed in compliance with the NMED Monitor Well Construction Guidelines." The BDR needs to state how this will contribute to defining the baseline conditions.
   b. Page 9-9, Section 9.4.2, states that "based on comments made during Alta Gold's permit application phase, the need to install additional monitoring wells for water level measurement, particularly outside the permit area, will be evaluated."This sentence confuses the reader and needs to be better stated in the BDR
   c. Page 9-9, Section 9.4.2, also states that "the existing [historic aquifer pump test] data and recommendations will be evaluated during the baseline data characterization phase, and a determination will be made as to the adequacy of the existing data to support the hydrologic impact analysis. If necessary, additional aquifer tests may be completed." Again, the BDR should better describe how the "determination will be made as to the adequacy of the existing data to support the hydrologic impact analysis."
   d. The Standard Operating Procedures (SOP) provided in the SAP represent a general methodology and approach to be followed for various tasks, however they do not provide a substitute for specific details to allow evaluation of the adequacy of the sampling plan. For example, while it is generally good to know the SOP for an aquifer pump test, an SOP does not provide the site specific information needed to evaluate the scope of work for a pump test such as which aquifer is being tested, pumping rate (or rates for a step-test) to be utilized, test duration, locations of observation wells, etc. In MMD's opinion, it would have been more

appropriate for NMCC, and/or its contractors, to have reviewed and evaluated the historic groundwater data prior to submittal of the SAP, which would have allowed NMCC and/or its contractors to identify any data gaps that could then be described and subsequently addressed in the SAP. As currently stated in the SAP, it appears that NMCC will be relying on professional and scientific judgment to fill any groundwater data gaps identified in the future (i.e. after submittal and MMD review of the SAP), rather than providing specific details in the SAP for review and comment by MMD. The BDR should describe the "professional judgment" and the rationale of how this will identify data gaps.

2. Section 9.7 and Figure 9-10 illustrate the wells selected for the baseline sampling plan. While the overall groundwater characterization objectives are stated in Section 9.2, the rationale and objective behind selecting the wells listed in Table 9-2 needs to be described in the BDR. For example, only two wells completed within the crystalline bedrock aquifer appear to have been selected for baseline sampling, leading to several questions:
   a. why were these two wells selected as being representative of this aquifer?
   b. are there additional wells completed in the crystalline bedrock aquifer that could have been included or are these the only two completed in this aquifer?
   c. is there reason to believe that additional wells within the crystalline bedrock aquifer are not needed at this time, and if so, why? Figure 9-9 demonstrates that a plethora of wells exist in and around the Copper Flat project area. Without understanding the rationale as to why the wells shown in Figure 9-10 were selected, in lieu of other existing wells, MMD has no way of confirming that the approach proposed by NMCC will result in a technically complete BDR. In the BDR, please provide a general rationale and justification of NMCC's reasoning for selecting the wells listed in Table 9-2 for completion of the baseline sampling.
3. The SAP describes how the monitor wells at or near the toe of the tailings dam, and the Saladone Well north of Las Animas Creek, will be sampled to establish baseline conditions of the Quaternary Alluvial aquifer, but does not provide the rational of how these selected monitor wells will characterize baseline conditions. The proposed eight monitor wells located near the toe of the tailings dam are likely contaminated. NMCC should consider additional Quaternary Alluvium monitor well locations in order to avoid potentially contaminated waters related to the previous mining efforts. Additionally, some rational needs to be provided (in the the BDR) as to why the Saladone Well (or, all monitor well placements) represents baseline Alluvial aquifer conditions. Figure 9-10 and Table 2 (Section 9) do not correlate, as monitor wells GWQ94-18 and MW-11 are not located on Figure 9-10. Please be certain the BDR corrects this, and any other discrepancies.
4. These comments address the requirements of Section 19.10.6.602.(13).(g) NMAC, of the New Mexico Mining Act Rules. Additionally, any information concerning impacts to groundwater, from this project must be addressed through NMED's implementation of the New Mexico Water Quality Commission Regulations 20.6.2 NMAC. MMD will accept any information regarding this subject that has already been, or will be, provided to NMED.

Eustice, Chris, EMNRD

From: Myers, Kevin, OSE
Sent: Tuesday, October 12, 2010 12:01 PM
To: Eustice, Chris, EMNRD
Cc: Johnson, Mike S., OSE; Rappuhn, Doug H., OSE
Subject: NM OSE Comments for Copper Flat SAP - MMD permit No. SI027RN

Chris,

As discussed briefly by phone, here are NM OSE comments related to MMD permit No. SI027RN.

On September 24, 2010 MMD requested that NM OSE comment on the *Sampling and Analysis Plan for Copper Flat Mine* (SAP) dated September 2010 and prepared by INTERA for the New Mexico Copper Corporation (NMCC). The SAP is part of the documentation for a new mine operation, which the applicant proposes to be an open pit copper mine about 5 miles northeast of Hillsboro, NM. As proposed, mine dewatering would take place approximately 14 miles west of Caballo Reservoir, and ground water may be diverted from a well field about 6 miles west of Caballo Reservoir. All diversions will occur within the Lower Rio Grande Underground Water Basin and within the Grayback Arroyo, which is located between Percha and Las Animas Creeks. According to the SAP, molybdenum, gold and silver will be recovered as byproducts.

General Comments:
Overall, the SAP provides a comprehensive overview of the previous studies and details of work to be conducted. Apparently due to the large amount of existing information for some areas, the SAP proposed to complete final decisions through implementation of the plan without additional agency review. Specifically, the SAP implementation will address choices and rationale for the static and kinetic geochemical tests, aquifer tests as well as the location for any additional monitoring wells. The baseline data report may have a higher risk of being incomplete or unsatisfactory because the state agencies would not be involved in the decision process. In general, additional testing or well installation after the baseline data report submittal would take longer than if comments were addressed during the implementation of the SAP. Thus, at a minimum, NMCC should provide state agencies with a draft of these selections and rationales for review before completing the baseline data report.

The SAP mentions involvement of state agencies in the early stages of the flow model development. NM OSE would appreciate inclusion for the NMCC presentations of the conceptual model, and flow model design, calibration and results.

Specific Comments:
NMOSE Hydrology has reviewed the SAP and has the following comments:

1. Page 7-6, Section 7.4.2. Some of the testing completed in the late 1990s included waste rock, tailing and pit wall samples. NMCC should provide a justification (e.g., additional testing or other verification) that previously tested areas have not been significantly changed after an additional 10+ years of weathering.

2. Page 7-7, Sections 7.4.4 and 7.4.5. The SAP defines the number of samples to be selected without providing the distribution or rationale for selecting core samples, rock types and waste types. The SAP proposes to review the existing data before selecting the samples. NMCC should propose a draft rationale and distribution of samples for agency review prior to completing the baseline data report.

3. Page 8-3, Section 8.2. NMCC should provide a tabular summary that shows the historical concentrations measured for pit lake water quality.

4. Page 8-7, Section 8.6.2.1; and Figure 8.2. The text mentions five profiles and two tie lines, while Figure 8.2 shows eight profile lines based on its legend. NMCC should clarify the number of profile lines and tie lines for pit lake sampling.

5. Page 9-2, Section 9.1.2.1; Figure 9-5, Figure 9-6, and Table 9-2. The SAP appears to suggest that previous work pointed toward the pit lake being a hydraulic sink and recent (January 2010) lake levels are below pre-mining water levels. Figures 9-5 and 9-6 do not adequately address or justify the horizontal extent of any hydraulic discontinuity caused by the pit. For Figure 9-5 the 100-foot contour interval and basis (water levels used) do not seem appropriate for making gradient determination that are affected by water level differences of less than 20 feet. The SAP does not include the pit lake or well EIW (closest to the pit lake in Figure 9-9) in the monitoring network. A closely spaced network may be necessary to delineate a local groundwater divide, if a sink exists. NMCC should measure the pit lake level at the same time as water level measurements. NMCC should evaluate the appropriateness of the well network to delineate flow directions and extent if the pit lake is a hydraulic sink or whether the lake exhibits flow through characteristics.

6. Page 9-6, Section 9.1.3; and Figure 9-9. In the SAP, The lower left of Figure 9-9 mentions SRK or OSE mine boundary, yet it's not clear what that may mean or if a symbol should be associated with the text. NMCC should clarify whether wells represented on Figure 9-9 included any wells that may have been drilled since the 1999 BLM study. In order to have a up to date map of wells in the area with water rights, NMCC should revise the map using the online database WATERS through the Water Rights Reporting System http://nmwrrs.ose.state.nm.us/nmwrrs/index.html in conjunction with contacting the NM OSE District IV Office in Las Cruces. The contact is necessary with District IV Office for further research of nearby well records and water rights, which have not yet been fully populated into the WATERS database.

Andrea Mendoza, Acting District Supervisor

1680 Hickory Loop - Suite J
Las Cruces, NM 88004-6598
(575) 524-6161

7. Figure 9-9. An inset or additional figure is recommended to show the nearby wells that are north of the Production Wellfield (PW-1, PW-2 and PW-3). NMCC should provide well name, well type, diversion amount, location and ownership on a separate table of well information. In order to review the wells

plotted on Figure 9-9, NMCC should label individual wells on a larger format of Figure 9-9 or provide tabular information (e.g., shape file and attribute table with well names).

8. Page 9-6, Section 9.1.3; and Page 1-4, Section 1.4.1. After a cursory review of the Raugust (2003) report presented at American Society of Surface Mining conference, NMCC should review Raugust (2003) in greater detail. For example, the Raugust (2003) concludes a "slight" increase in sulfate concentrations and TDS measured at the pit lake when these parameters doubled (2,000 to 4000 and 3,000 to 6,000 mg/L, respectively) from 1989 to 1997. Raugust (2003) also mentions the "slight" increase in sulfate concentrations and TDS for a down gradient well from the pit lake, when these parameters approximately doubled or more (140 to 450 and 520 to 990 mg/L) at well 96-23A from 1989 to 1997. Doubting the water quality trend shown in the report and citing the ore body as the source of poorer water quality, Raugust (2003) states, *"...Groundwater quality down-gradient of the mine pit deteriorated with respect to sulfate and TDS from 1996 to 1998; however, more time-based sampling data would be required to ascertain whether this is a real trend or transient phenomenon.... It appears from the existing data that the ore body is likely the most significant contributor to water quality down-gradient of the pit, and that additional data would be useful in evaluating this hypothesis."* The above significant water quality trends should be evaluated further by including NMED samples with laboratory results from 2003 and 2008 as well as SAP results.

9. Pages 9-8 to 9-9, Section 9.3. After the initial minimum of four quarters of water quality and water level data collection, NMCC proposes to reduce the number of wells to ten for water quality sampling and in consultation with MMD. NMCC should note that NMED would also require consultation under discharge plan and abatement plan regulations or permit conditions. NMCC should clarify if it intends to continue water level measurements at the reduced ten wells or some larger network.

10. Page 9-9, Section 9.4.2.; and Page 9-9, Section 9.5. The SAP mentions the possibility or potential need for adding new wells. As the SAP is implemented, the new well locations would be identified. New well drilling and installation must meet NM OSE regulations 19.27.4 NMAC. Prior to the submittal of the baseline data report, NMCC should provide any proposed well locations and rationale to state agencies (e.g., MMD, NMED and NMOSE) for review.

11. Page 9-9, Section 9.4.2; Page 9-23, Section 9-9; and Table 9-4. The SAP provides a summary of previous aquifer test results in the vicinity of the proposed Copper Flat project. The table and text lack enough information to review the aquifer test results or determine how many tests were completed for each aquifer and the location. NMCC should provide a detailed summary of the individual aquifer tests including location, duration of test, type of analyses, number of tests, aquifer, etc. If additional aquifer testing is necessary, NMCC should provide a proposal for further aquifer testing for agency review prior to submittal of the baseline data report.

12. Pages 9-23 & 9-24, Section 9.9. The SAP outlines a process for developing a new numerical model using either MODFLOW or MODFLOW-SURFACT. The SAP mentions presenting the conceptual model, preliminary numerical model domain, preliminary numerical model results to relevant agencies. According to the SAP, water diversions would occur at the mine site and at a well field about eight miles east of the mine. NMCC should clarify in its conceptual model whether the model will address these diversions for mine dewatering and fresh water production.

13. Page 11-3, Section 11.2; and Table 11-1. The SAP list five major permits or approvals (BLM Plan of Operations & EIS, NMED GWQB discharge permit, MMD mining permit, NMED AQB air quality permit, NMOSE Dam Safety permit for dam construction and operations). Table 11-1 includes a NM OSE permit to appropriate water. In Table 11-1, NMCC should include a NM OSE permit for mine dewatering. NMCC should note that, for protested applications or if nearby water rights are significantly affected, the NM OSE permit to appropriate water may require a substantial effort to complete.

If you have any questions about the above, contact me.

Kevin Myers, Hydrologist
Hydrology Bureau - NM OSE
P.O. Box 25102
Santa Fe, NM 87504-5102
Ph: (505) 827-3521
Fax: (505) 476-0220

http://www.ose.state.nm.us/

NEW MEXICO
ENVIRONMENT DEPARTMENT

Ground Water Quality Bureau

1190 St. Francis Drive
P.O. Box 5469, Santa Fe, NM 87502
Phone (505) 827-2918 Fax (505) 827-2965
www.nmenv.state.nm.us
William C. Olson, Bureau Chief

BILL RICHARDSON
Governor
DIANE DENISH
Lieutenant Governor

RON CURRY
Secretary
SARAH COTTRELL
Deputy Secretary

MEMORANDUM

DATE: November 10, 2010

TO: Holland Shepherd, Program Manager, Mining Act Reclamation Program

FROM: Greg Huey, NMED Ground Water Quality Bureau
David Menzie, NMED Surface Water Quality Bureau

THROUGH: Kurt Vollbrecht, NMED Mining Act Team Leader

RE: Comments on New Mexico Copper Corporation, Copper Flat Mine, Sampling and Analysis Plan, Permit no. SI027RN

The New Mexico Environment Department (NMED) received correspondence from the Mining and Minerals Division (MMD) on September 29, 2010 requesting that NMED review and provide comments on the Sampling and Analysis Plan (SAP) referenced above. MMD requested comments be submitted within 30 days of receipt in accordance with the New Mexico Mining Act Requirements. In order to facilitate a sight inspection, that deadline was extended until November 12, 2010. The NMED Surface Water Quality Bureau (SWQB) and Ground Water Quality Bureau (GWQB) have submitted comments in this memorandum jointly.

NMED SWQB Comments:

The introductory paragraph to Section 8, Surface Water, includes the statement "Numerous ephemeral tributaries feed into the Rio Grande from the west, but none contribute perennial flow to the Rio Grande." Lack of perennial flow to the Rio Grande does not negate the fact that both Las Animas Creek and Percha Creek include perennial reaches that support fisheries and water quality must be protected as required under §20.6.4.103 of the New Mexico Administrative Code (NMAC). This paragraph should be reworded to acknowledge the important contribution of these waters of the State as a natural resource.

Section 8.1, Surface Water Characteristics of Site and Vicinity: During the joint agency inspection that was conducted on October 26, 2010 (Inspection), Grayback Arroyo exhibited surface water pools and small flows along a reach of several hundred yards that did not appear to be the result of direct precipitation. In addition, there is significant riparian vegetation indicating that Grayback Arroyo

should be classified as an intermittent water of the State pursuant to §20.6.4.98 NMAC. The SAP should acknowledge this classification rather than describing Grayback Arroyo as an ephemeral channel.

Section 8.2, Historical Data: This section states that "Surface water at the Site was most recently investigated by ABC (1996), who collected flow and water quality from Percha Creek and Las Animas Creek." In 2004, the SWQB conducted a water quality survey that included Las Animas Creek and Percha Creek. These data are available from the State through a public records request.

Section 8.6.1.2, Water Quality Sampling: As observed during the Inspection, set up and placement of the automated samplers appeared adequate. SWQB staff did suggest to the applicant that stream sample collection targeting the rising limb of the hydrograph would be preferred since research indicates that the first surge of storm runoff is likely to carry the most pollutants.

Section 9 of the SAP states that the Rio Grande is the only significant surface water resource in the area. This statement is questionable since perennial reaches of the tributaries originating from the eastern side of the Black Range provide important sources of surface water to residents west of the Rio Grande and provide unique riparian and wildlife habitat year round. The SAP then states that Las Animas Creek and Percha Creek are intermittent streams. As previously discussed, these streams contain perennial reaches that support fisheries and should be acknowledged as such.

NMED GWQB Comments:

Section 7.4 of the SAP proposes to review the existing geochemical data prior to determining the locations for collection of additional samples for identification of ore and waste rock zones within the proposed pit outlines. A phased approach is proposed that will contribute to a sampling program focused on the main material types within the proposed pit outlines, with more samples being collected from the material types with the greatest predicted tonnage. NMED agrees that this phased approach is an efficient methodology for identification of geologic strata but requests that addendums to the approved SAP be submitted for agency approval at developmental intervals prior to moving forward with the proceeding stage of geochemical sampling.

Section 7.4.2 states that "exploration drilling is currently ongoing in the expansion areas." During the Inspection, a map of the proposed exploration drilling areas was discussed, but at this time no minimal impact exploration application has been submitted for NMED review. Such an application is necessary before exploratory drilling may proceed.

Section 7.4.3 mentions "a number of field tests" that may be used to determine the geochemistry of specific material types prior to moving on with standard static testing. These field tests should be identified and described in the requested addendum to the SAP for geochemical sampling.

Section 8.6.2.1 discusses using five profiles and two tie lines to determine Pit Lake depth; however, Figure 8-2 shows eight profile lines. This discrepancy should be resolved.

Section 9.1.1 cites Figure 9-2 as depicting three aquifers: the crystalline bedrock aquifer, the Santa Fe Group aquifer system, and the Quaternary alluvial aquifer. Figure 9-2 does not provide any reference to the crystalline bedrock aquifer and does not function as a "conceptual model" of the Site ground water flow system as the title suggests. This figure should be replaced with an appropriately designed diagram.

Section 9.1.2.1 states that ground water elevation data are derived from wells greater than 4,000 feet distance from the Pit Lake, but then states confidently that the ground water gradients in the area are toward the Pit Lake. The section also references Figure 9-6 as demonstrating ground water gradients toward the Pit Lake; however, the vertical scales on opposite sides of this diagram are not coordinated: the scale on the left side of the figure is approximately 80 feet to one inch, while the scale on the right side of the figure is approximately 5 feet to one inch. This gross discrepancy in scale negates the effectiveness of this figure as a tool in ground water gradient interpretation. In addition, the figure, circa 1998, shows the Pit Lake elevation at 5,436.5 ft amsl, while the text in the section reported the Pit Lake elevation at 5,442 ft amsl in 1997 and 5,444 ft amsl in 2010. The section concludes by stating that the Pit Lake elevation remains below the pre-mining water level elevation of 5,500 to 5,540 ft amsl. This is in contradiction to the Preliminary Environmental Impact Statement (BLM, 1999) cited previously in the section, which describes pre-mining **ground** elevation as 5,500 to 5,540 ft amsl.

Figure 9-9 shows well EIW as the closest monitoring well to the Pit Lake. However, the SAP does not include water depths in this well or Pit Lake elevations in the monitoring network. A denser monitoring well field may be necessary to delineate a local ground water divide, and the SAP should require that Pit Lake elevation measurements be taken at the same time as water level measurements in adjacent ground water monitoring wells to better define the potentiometric surface across the Site.

Statements regarding site-wide ground water levels should be re-evaluated pending a more thorough hydrological investigation.

Section 9.1.3 states that concentrations of total dissolved solids (TDS) and sulfate down-gradient of the Pit Lake have increased gradually over time and suggests that impacts to water quality in the vicinity of the Pit Lake may be naturally occurring. However, Figure 15 from Raugust (2003) shows an increase in TDS from approximately 550 mg/L to almost 1,000 mg/L between 1996 and 1998 in well GWQ-96-23A. Further review of Raugust (2003) reveals conflicting statements regarding wells in location to the Pit Lake. In the "Study Area Investigations" section, the manuscript states that

> Prior to 1996, only one well was available for sampling groundwater in the vicinity of the pit lake. This monitoring well, GWQ-4, is located approximately one-half mile east of the existing pit.

However, in the "Conclusions" section the manuscript references water quality collected from monitoring well GWQ-5 in 1981. NMED recommends that, rather than adopt conclusions from references not submitted for agency review, NMCC provide appropriate data and develop conclusions based on the analysis of those data.

Section 9.1.5 references the MMD Guidance Document for Part 6 New Mining Operations, stating that the SAP must include supporting material to justify the use of historic data. NMED requests that, regardless of justification, an inventory of all existing data be compiled and reported prior to validation and possible exclusion of these data.

Section 9.3 proposes reducing the number of wells monitored for water quality parameters after the initial four quarters of data collection. NMCC should be aware that under NMED abatement plan requirements and the discharge plan permitting process these wells will require separate evaluation by NMED prior to being removed from any approved sampling plan.

Section 9.4.2 discusses the possible need for installation of additional monitoring wells. New well drilling and installation must meet NMED and NM OSE requirements. New well locations should be proposed to NMED under a Stage One Abatement Plan and/or Discharge Plan proposal. In addition, this section references Table 9-4 for a summary of previous pumping tests and resulting aquifer characteristics. This table does not provide sufficient information to determine the source or validity of the data provided and the SAP should provide for agency review a summary of the individual aquifer tests used to compile these data prior to determination as to the adequacy of the existing data to support the hydrologic impact analysis.

Section 9.7 references Figure 9-9 to provide locations of the wells proposed for sampling in Table 9-2. Well GWQ-12 at the southern end of the tailing disposal facility is not proposed for water quality sampling. As previously stated, well EIW is also not included in the SAP. NMCC should provide justification with supporting data as to why these and other available wells are excluded from the SAP.

During the Inspection, a previously unidentified well was located adjacent to the lower Greyback Arroyo downstream of the tailing dam. It was supposed that this well may be the McCravey-Greyback well. A data review should be conducted for this well and justification for or against its inclusion in the SAP should be included. Furthermore, this well was open to the environment and efforts should be made to properly secure it with an appropriate cap.

Further review and evaluation of the SAP relative to a Ground Water Discharge Permit application and Stage One Abatement Plan may result in additional comments. At this time NMED has not received documentation regarding permitting requirements for the Copper Flat Mine pursuant to the Water Quality Control Commission Regulations (20.6.2 NMAC).

If you have any questions, please contact Greg Huey at (505) 827-1046.

cc: William C. Olson, Chief, GWQB
Marcy Leavitt, Chief, SWQB
Charles Thomas, Chief, Mine Reclamation Bureau
Mary Ann Menetrey, NMED MECS

GOVERNOR
Bill Richardson

DIRECTOR AND SECRETARY
TO THE COMMISSION
Tod Stevenson

Robert S. Jenks, Deputy Director

STATE OF NEW MEXICO
DEPARTMENT OF GAME & FISH

One Wildlife Way
Post Office Box 25112
Santa Fe, NM 87504
Phone: (505) 476-8008
Fax: (505) 476-8124

Visit our website at www.wildlife.state.nm.us
For information call: 505/476-8000
To order free publications call: 1-800-862-9310

RECEIVED
NOV 03 2010
MINING & MINERALS DIVISION

STATE GAME COMMISSION

JIM McCLINTIC, Chairman
Albuquerque, NM

SANDY BUFFETT, Vice-Chairwoman
Santa Fe, NM

DR. TOM ARVAS, Commissioner
Albuquerque, NM

GARY W. FONAY, Commissioner
Hobbs, NM

KENT A. SALAZAR, Commissioner
Albuquerque, NM

M.H. "DUTCH" SALMON, Commissioner
Silver City, NM

THOMAS "DICK" SALOPEK, Commissioner
Las Cruces, NM

October 29, 2010

Chris Eustice, Permit Lead
EMNRD Mining & Minerals Division
1220 South St. Francis Drive
Santa Fe, NM 87505

Re: Copper Flat Mine Sampling and Analysis Plan, Permit SI027RN; NMDGF Project No. 13803

Dear Mr. Eustice:

In response to your letter dated 24 Sep, 2010, the New Mexico Department of Game and Fish (NMDGF) has reviewed the above referenced document. New Mexico Copper Corporation has submitted the plan in support of a new mine permit application. The project will be a copper mine and mill, located approximately five miles northeast of Hillsboro, NM. The proposed permit area includes 2,190 acres of mixed private and Bureau of Land Management surface ownership. A site visit was conducted on 26 Oct 2010. Persons present included you, Holland Shepherd, Joe Vinson and David Ennis (MMD), Rachel Jankowitz and Pat Mathis (NMDGF), Greg Huey and Dave Menzie (NMED) and Steve Raugust (NMCC). Habitat type on the project area is grass and shrubs with a prominent drainage channel (Greyback Arroyo) running from west to east through the middle. Remnants of previous mining activity include an open pit lake, roads, a drainage channel diversion around the pit and several assorted manmade structures.

The methods proposed for vegetation baseline monitoring are appropriate and sufficient. The following comments pertain to the proposed plan's vegetation type stratification:

1. The selected vegetation type stratification scheme utilizes Natural Resource Conservation Service Ecological Site Descriptions (ESD). If the delineation of the two ESDs present on site, shown in Figure 4-2, is derived from large scale mapping, the boundary should be ground-truthed, using visual observation in conjunction with soil characteristics.

2. The apparent reason for assigning undisturbed areas "planned to be disturbed in the future" to separate strata from those not planned for disturbance, is to verify the similarity between them in the undisturbed condition. If no significant difference in vegetation is discovered by initial monitoring, these data should be combined in the description of baseline pre-mining conditions.

3. Vegetation in the Greyback Arroyo is extensive and distinct enough to constitute one or more distinct monitoring strata. NMDGF recommends that arroyo vegetation be described in a quantitative or semi-quantitative manner, including both the narrow intermittent wetland sections and the ephemeral grass/shrub association on the eastern portion of the project area. Extent mapping and a comprehensive species list might be used to describe wetland areas which are too small for transect monitoring.

4. If noxious weeds are discovered, please document the extent and density of infestation, as well as the point location.

The methods proposed for wildlife baseline monitoring are appropriate, but insufficient to describe the mine site fauna. Detailed recommendations are presented in the NMDGF baseline study guideline, available on the internet at http://wildlife.state.nm.us/conservation/habitat_handbook/documents/WildlifeBaselineStudyGuidelinesand%20Appendix.pdf. A list of special status species known to occur in Sierra County is enclosed with this letter. Please consult the NM Rare Plant Technical Council website (http://nmrareplants.unm.edu/) for a county list of rare plants.

We suggest the following additions to the plan:

1. An off-site reference area should be selected for monitoring similar to that which will be conducted on the mine site. The reference area will serve to provide comparable data for the purpose of identifying and interpreting trends in wildlife usage through the mine operating and reclamation periods.

2. Most reptiles and small mammals are nocturnal. Some are difficult to identify when not in hand. Diurnal observation transects should be supplemented by a trapping or capture program to characterize the reptile and small mammal communities. State or federal permits may be required if monitoring activity is expected to involve handling of listed species

3. The proposed plan will not adequately characterize bat use of the site. Potential roosting habitat is present in rock crevices, and in existing structures or historic mine openings. The pit lake constitutes a large open water source which is likely to attract foraging bats from a wide surrounding area. The applicant should propose a bat monitoring program which utilizes acoustic detection, roost observation and/or netting. As stated above, state or federal permits may be required if monitoring activity is expected to involve handling of listed species

4. NMDGF recommends a survey for raptor nests in all suitable habitat within one mile of any potential mine-related disturbance.

5. In addition to the proposed transects, conduct focused observation of special habitat features. Those features at Copper Flat might include the pit lake and wetland locations. Surveys for amphibians would be appropriate at perennial or ephemeral aquatic locations.

6. Pellet counts and observational transects for large to medium sized animals should be conducted twice per year, to account for variation in seasonal use. Please record the sex and age class of animals observed.

The Mining Act Rules state that the SAP shall "describe the environment of the proposed permit area and, to the extent practicable, the affected area." Studies associated with the previous attempt to permit a mine at this site, in the 1990s, vary widely and are inconclusive regarding the aerial and vertical extent of groundwater drawdown that may result from pit dewatering and wellfield pumping. (for an example, refer to the BLM Draft Environmental Impact Statement dated February 1996 and the Daniel B. Stevens & Associates Environmental Evaluation Report dated February 1998). Wildlife habitat which might be affected include Las Animas Creek and its riparian zone, Percha Creek and riparian habitat in the Percha Box, Warm Springs Canyon and a number of warm- and cold-water springs and seeps in the vicinity. Monitoring of surface flow, groundwater level and water quality at these habitat features will provide most of the information needed to determine whether they are impacted by mine operations. However, biotic and ecological responses to changes in water quantity or quality may not be linear, and baseline information is not currently available. In areas where a risk of potential impact may be identified, and surface access can be obtained, the applicant should monitor and describe the characteristics of riparian vegetation and amphibian, fish and invertebrate communities, with special attention to the potential occurrence of special status species.

Thank you for the opportunity to comment on this baseline data sampling plan. If there are any questions, please contact Rachel Jankowitz at 505-476-8159, or rjankowitz@state.nm.us.

Sincerely,

Matthew Wunder, Ph.D.
Chief, Conservation Services Division

xc: Wally Murphy, Ecological Services Field Supervisor, USFWS
Pat Mathis, SW Area Habitat Specialist, NMGF
Kurt Vollbrecht, NMED Groundwater Quality Bureau

NEW MEXICO WILDLIFE OF CONCERN
SIERRA COUNTY

For complete up-dated information on federal-listed species, including plants, see the US Fish & Wildlife Service NM Ecological Services Field Office website at http://www.fws.gov/ifw2es/NewMexico/SBC.cfm. For information on state-listed plants, contact the NM Energy, Minerals and Natural Resources Department, Division of Forestry, or go to http://nmrareplants.unm.edu/. If your project is on Bureau of Land Management, contact the local BLM Field Office for information on species of particular concern. If your project is on a National Forest, contact the Forest Supervisor's office for species information.

Common Name	Scientific Name	NMGF	US FWS	critical habitat
Rio Grande Cutthroat Trout	Oncorhynchus clarki	s	SOC	
Gila Trout	Oncorhynchus gilae	T	T	
Rio Grande Chub	Gila pandora	s		
Headwater Chub	Gila nigra	E		
White Sands Pupfish	Cyprinodon tularosa	T	SOC	
Arizona Toad	Bufo microscaphus microscaphus	s		
Chiricahua Leopard Frog	Rana chiricahuensis	s	T	
Big Bend Slider	Trachemys gaigeae	s		
Brown Pelican	Pelecanus occidentalis	E		
Neotropic Cormorant	Phalacrocorax brasilianus	T		
Bald Eagle	Haliaeetus leucocephalus	T	T	
Northern Goshawk	Accipiter gentilis	s	SOC	
Common Black-Hawk	Buteogallus anthracinus	T	SOC	
Aplomado Falcon	Falco femoralis	E	Exp	
Peregrine Falcon	Falco peregrinus	T	SOC	
Mountain Plover	Charadrius montanus	s	SOC	
Least Tern	Sterna antillarum	E	E	
Black Tern	Chlidonias niger surinamensis		SOC	
Common Ground-Dove	Columbina passerina	E		
Yellow-billed Cuckoo	Coccyzus americanus	s	C	
Mexican Spotted Owl	Strix occidentalis lucida	s	T	Y
Burrowing Owl	Athene cunicularia		SOC	
Broad-billed Hummingbird	Cynanthus latirostris	T		
Lucifer Hummingbird	Calothorax lucifer	T		
Costa's Hummingbird	Calypte costae	T		
Elegant Trogon	Trogon elegans	E		
Southwestern Willow Flycatcher	Empidonax traillii extimus	E	E	Y
Thick-billed Kingbird	Tyrannus crassirostris	E		
Loggerhead Shrike	Lanius ludovicianus	s		
Bell's Vireo	Vireo bellii	T	SOC	
Gray Vireo	Vireo vicinior	T		
Baird's Sparrow	Ammodramus bairdii	T	SOC	
Varied Bunting	Passerina versicolor	T		
Western Small-footed Myotis Bat	Myotis ciliolabrum melanorhinus	s		
Yuma Myotis Bat	Myotis yumanensis yumanensis	s		
Occult Little Brown Myotis Bat	Myotis lucifugus occultus	s		
Long-legged Myotis Bat	Myotis volans interior	s		
Fringed Myotis Bat	Myotis thysanodes thysanodes	s		
Long-eared Myotis Bat	Myotis evotis evotis	s		
Pale Townsend's Big-eared Bat	Corynorhinus townsendii pallescens	s	SOC	

Gunnison's Prairie Dog	Cynomys gunnisoni	s	
Desert Pocket Gopher	Geomys arenarius	s	SOC
Pecos River Muskrat	Ondatra zibethicus ripensis	s	SOC
Mexican Gray Wolf	Canis lupus baileyi	E	Exp
Ringtail	Bassariscus astutus	s	
Common Hog-nosed Skunk	Conepatus leuconotus	s	
Desert Bighorn Sheep	Ovis canadensis mexicana	E	
Mineral Creek Mountainsnail	Oreohelix pilsbryi	T	SOC
Fairy Shrimp	Streptocephalus moorei	s	
Desert Viceroy Butterfly	Limenitis archippus obsoleta		SOC

STATE OF NEW MEXICO
DEPARTMENT OF CULTURAL AFFAIRS
HISTORIC PRESERVATION DIVISION

BATAAN MEMORIAL BUILDING
407 GALISTEO STREET, SUITE 236
SANTA FE, NEW MEXICO 87501
PHONE (505) 827-6320 FAX (505) 827-6338

BILL RICHARDSON
Governor

RECEIVED
OCT 28 2010
MINING & MINERALS DIVISION

October 26, 2010

Chris Eustice
Permit Lead
Mining Act Reclamation Program
Mining and Minerals Division
1220 South St. Francis Drive
Santa Fe, NM 87505

Re: Request for Review and Comment on the Sampling and Analysis Plan, New Mexico Copper Corporation, Copper Flat Mine, Permit No. SI027RN

Dear Mr. Eustice:

This letter is in response to sampling and analysis plan for Copper Flat Mine located in Sierra County. According to 19.10.6.602 NMAC, a sampling and analysis plan shall include a list and accompanying map indicating all sites on or eligible for listing on either the National Register of Historic Places and/or the State Registers of Cultural Properties and known cemeteries and human burials within the proposed permit area. Included in this list shall be a description of effects the proposed mining operations may have on these sites and any proposed mitigation measures.

Section 10 of the SAP, Historical and Cultural Properties Survey does not indicate whether there are cultural properties listed on or eligible for listing on either the National Register of Historic Places and/or the State Registers of Cultural Properties. However, a review of our records shows there are no historic properties listed on either the National Register of Historic Places or the State Register of Cultural Properties. The SAP does summarize the cultural resource surveys that have been conducted to date, with specific reference to a survey conducted in 1995 by Human Systems Research that recorded 16 archaeological sites and 212 isolated occurrences. Some of these sites are probably eligible for listing to the NRHP or the SRCP.

Under Section 10.2, Sampling Objectives, the SAP states that the project area includes federally administered land and the project is subject to review under Section 106 of the National Historic Preservation Act. In order to assess the effects on historic properties, a cultural resources survey is proposed although the exact survey interval and exact area to the be surveyed will be determined in consultation with the Bureau of Land Management (BLM) and the State Historic Preservation Office (SHPO). It is the SHPO's opinion that the permit

area, excluding the areas extensively disturbed by previously mining activities, should be intensively surveyed (class III). It does not appear that the 1995 Human Systems Research Survey covered the entire area so there may be a potential for additional archaeological sites to exist.

The SAP also states that a plan of operations has been submitted to the BLM. The BLM will be reviewing this project under Section 106 of the National Historic Preservation Act (NHPA). As such, they will determine the level of effort for the cultural resources survey lands under their jurisdiction. After the cultural resources survey is conducted, New Mexico Copper, in consultation with the BLM and the SHPO, will be able to determine whether the proposed mining operations will have an effect on cultural resources and determine appropriate mitigation measures if necessary.

If you have any questions regarding these comments, please do not hesitate to contact me at (505) 827-4064.

Sincerely,

Michelle M. Ensey
Archaeologist

Log: 90457
Cc/Email: Chris Parrish, Parametrix

2-3-2011

NEW MEXICO
ENVIRONMENT DEPARTMENT

Ground Water Quality Bureau

SUSANA MARTINEZ
Governor

JOHN SANCHEZ
Lieutenant Governor

P.O. Box 5469
1190 St. Francis Drive
Santa Fe, New Mexico 87502-5469
Phone (505) 827-2918 Fax (505) 827-2965
www.nmenv.state.nm.us

DAVID MARTIN
Secretary

RAJ SOLOMON, P.E.
Deputy Secretary

DATE: February 3, 2011

TO: Holland Shepherd, Program Manager, Mining Act Reclamation Program

FROM: Greg Huey, Ground Water Quality Bureau
David Menzie, Surface Water Quality Bureau

THROUGH: Kurt Vollbrecht, NMED Mining Act Team Leader

RE: New Mexico Copper Corporation, Copper Flat Exploration 2 Project, Minimal Impact Exploration Project Permit Application, Permit No. SI025EM

The New Mexico Environment Department (NMED) received the Copper Flat Exploration 2 Project Minimal Impact Exploration Permit Application from the Mining Act Reclamation Program (MARP) on January 14, 2011. MARP requested that the application be reviewed and all comments returned within 20 days of receipt. A site inspection was conducted on January 25, 2011 and comments were submitted prior to the February 3, 2011 deadline.

Pursuant to Subpart 302.G of the New Mexico Mining Act Rules (NMMA), the NMED Air Quality Bureau, Surface Water Quality Bureau and Ground Water Quality Bureau have reviewed the Copper Flat Exploration Minimal Impact Exploration 2 Project Permit Application. The Surface Water Quality Bureau and Ground Water Quality Bureau are submitting comments jointly in this memorandum. Air Quality Bureau comments are provided under a separate memorandum.

Site Location and Description

The proposed Copper Flat Exploration 2 Project is located in Township 15S, Range 7W of Section 26, Sierra County, NM. Hydro Resources Corporation, Cu Flat LLC and GCM, Inc. of Albuquerque, NM are the joint owners of surface and mineral rights to the property. The total proposed exploration disturbance is less than 5 acres. The permit states that depth to ground water at the site is between five and fifty feet and total dissolved solids concentration is <1,000 mg/L.

Forty-seven drill holes are proposed at a diameter of 3.8 inches. Forty-five of these will be to a maximum depth of 1200 feet, and two are proposed to a maximum depth of 2,000 feet. The maximum total excavation volume proposed for all holes is estimated to be 5,062 cubic feet (188 cubic yards).

Construction of pads for seventeen drill holes will not be necessary because drilling will occur on previously excavated and graded benches. Four pairs of holes will be drilled from the same drill pad; therefore, surface disturbance will only be necessary at twenty-five locations. Total drill pad construction will require 3.45 acres and new access road construction will require 1 acre for a total of 4.45 acres.

Drilling mud and additives are to be stored in metal tanks during the operational phase. The proposal calls for the disposal of drilling mud and additives into drilling holes after drilling is completed. It is then proposed that the drill holes are to be plugged with drilling mud from total depth to ten feet below ground surface and completed with a cement plug from ten feet below ground surface to the existing ground surface.

Permit Application Requirements and Minimal Impact Status

The permit application states that bore holes will be plugged with drilling mud. According to the New Mexico Office of the State Engineer requirements and New Mexico Mining Act Rules, drill holes must be plugged from the bottom of the hole to the land surface with cement or high density bentonite clay, with the top ten feet of the hole plugged with cement. Drilling mud is not an appropriate bore hole abandonment material.

New Mexico Mining Act Rules prohibit disposal of drill cuttings, drill mud or additives into excavated drill holes. NMMA §19.10.3.K provides guidance for construction and reclamation of pits for drill waste disposal.

In general, the following measures should be implemented at exploration drill sites to provide for protection of surface and ground water quality:

- A minimum setback from surface water channels of 100 feet should be maintained for all drill pads and associated activities. However, on the joint agency inspection conducted on January 25, 2011, the location for drill hole NE-C was discussed. This location is adjacent to an ephemeral wash that drains into the Open Pit Pool, and as such, the setback is not required at this location.

- All exploration activities need to implement Best Management Practices in a manner that prevents direct impacts to surface water and watercourses (ephemeral, intermittent and perennial). For surface disturbances during exploration and reclamation activities, the operator must commit to implementing erosion control measures that are designed, constructed and maintained using professionally recognized standards (e.g. Natural Resource Conservation Service Standards or the Bureau of Land Management "Gold Book").

- All heavy equipment used in the project area must be pressure washed and/or steam cleaned before the start of the project and inspected daily for leaks. A written log of inspections and maintenance should be completed.

- Appropriate spill clean-up materials, such as absorbent pads, must be available on-site at all times during drilling activities to address potential spills.

- Spills must be reported immediately to the NMED as required by the New Mexico Water Quality Control Commission Regulations (20.6.2.1203 NMAC). For non-emergencies during normal business hours, call (505) 428-2500. For non-emergencies after hours, call (866) 428-6535 or (505) 428-6535 (voice mail, twenty-four hours a day). For emergencies only, call (505) 827-9329 twenty-four hours a day (NM Dept of Public Safety).

- The applicant must contain any water produced from the exploration holes at the drill site. Discharge of this water or any drilling fluids to any watercourse may be a violation of the Clean Water Act. All drilling cores and cuttings should be collected and disposed of properly.

- This project may require coverage under a Clean Water Act §402 permit, such as for construction or industrial storm water, or for an NPDES process wastewater discharge. Failure to receive and implement proper permit coverage would be a violation of the Clean Water Act. A Construction General Permit, Notice of Intent (NOI), Fact Sheet, and Federal Register notice can be downloaded at http//cfpub.epa.gov/npdes/stormwater/cgp.cfm. The Industrial General Permit, NOI, Fact Sheet, and Federal Register notice can be downloaded at http://cfpub.epa.gov/npdes/stormwater/msgp.cfm. If you have questions about this coverage, please contact Rich Powell, NMED SWQB, at (505) 827-2798.

- The applicant should consult with the USACE to verify whether the proposed activity will require Clean Water Act §404 permitting.

- Boreholes must be abandoned in accordance with the New Mexico Office of the State Engineer requirements and New Mexico Mining Act Rules, including complete plugging from the bottom of the hole to the land surface with cement or high density bentonite clay.

NMED finds the proposed exploration activities are likely to have a minimal environmental impact if operated and reclaimed in accordance with the approved permit and requirements listed above.

cc: William C. Olson, Bureau Chief, GWQB
Marcy Leavitt, Bureau Chief, SWQB
Rachel Jankowitz, NMDGF
Mary Ann Menetrey, GWQB-MECS

2-4-2011

SURNAME
Initials/Date 2/1/2011
Initials/Date
Initials/Date 2-1-2011
Initials/Date
Initials/Date

NMNM 125986
3809 (L0310)

FEB 4 2011

CERTIFIED MAIL -- RETURN RECEIPT REQUESTED
7006 0810 0000 8915 2012

Mr. Steve Raugust
New Mexico Copper Corporation
2425 San Pedro Drive NE
Suite 100
Albuquerque, NM 87110

Dear Mr. Raugust:

On November 8, 2010, the Bureau of Land Management (BLM), Las Cruces District Office (LCDO) received your Mine Plan of Operations (MPO) for mining and mineral benefaction activities on mining claims north of Hillsboro, New Mexico, located in secs. 25, 26, 27, 35 and 36, T. 15 S., R. 7 W.; and in sec. 31, T. 15 S., R. 6 W. (New Mexico Principal Meridian) in Sierra County, New Mexico. This MPO has been assigned BLM serial number NMNM 125986; please refer to this number in future correspondence regarding this MPO.

Our review of the proposed MPO has determined that additional information is necessary for the LCDO to complete review of your proposed operation (43 CFR 3809.411(a)(2)). Please provide the following supplemental information:

1. Proposed Operating Plan (p. 3-1): Will any of the proposed placer mining occur on Federal land? If so, provide a detailed description of the proposed operation. Include a description of the area of placer operations, proposed depth of excavation, production and processing equipment requirements, access routes, sources of water, and duration of placer operations. Also provide a map of placer activity showing locations of excavation areas, waste sediment stockpiles, processing facilities and access routes. If no placer mining will occur on Federal land, describe if it will be necessary to cross Federal lands to reach the placer operations and any planned road improvements under this scenario.

2. Proposed Operating Plan (p. 3-3): Provide additional information regarding the general schedule of operations from start to closure (43 CFR 3809.401(b)(2)(vii)). Include the estimated duration of each phase of the mining operations (site preparation, production, mineral benefaction, reclamation, monitoring) during the projected 17-year mine life. At a minimum, reference Figure 5-1 in this section, the addition of a schedule in table format would also be appropriate.

3. Proposed Operating Plan (p. 3-4) states: "a detailed list of mining equipment will be provided to BLM as the mine plan is finalized." Complete this finalization so a preliminary equipment inventory can be prepared (fleet composition can be altered with a plan modification per 43 CFR 3809.430). Also include any necessary equipment not discussed in this section, such a dozers and road graders.

4. Waste-rock disposal and low grade ore stockpile (p. 3-5): Update the runoff calculations to meet regulatory requirements and design criteria. Provide additional details regarding the runoff collection system (i.e., the placement and estimated size of collection ditches, and the method by which water will be diverted into the process water system). Describe short-term (i.e., not final reclamation) BMPs to minimize sediment loading from the waste-rock piles (i.e., silt fencing, straw application, etc.).

5. Ore processing (p. 3-6): Specify the dimensions and construction of all buildings planned for the project. Specify the number and exact purpose of the ancillary buildings referred to on page 3-8 and map the locations and purposes of all buildings planned for the operation on figure 3-1 (or add a new figure with this map if you prefer).

6. Ore processing (p. 3-7): When does NMCC anticipate completing the feasibility study for in-pit crushing and conveying? Can this be incorporated into the current MPO, or will a plan modification be submitted?

7. Tailings impoundment design (p. 3-7 and Appendix D): Complete determinations regarding the source of materials for the new tailings dam and whether the existing dam will remain in place.

8. Water-supply (p 3-13): Provide the legal locations of the eight wells on BLM land proposed for use in the MPO. Also provide a map showing the location of the wells and the 20-inch pipeline (with existing valves and manholes) relative to the proposed operation.

9. Water-supply (p 3-13): Complete the planned inspection of the 20-inch pipeline to assure it will be suitable for use in the operation. If it is determined to be sufficient, provide the locations and specification of any pipeline improvements (including new valves, pumping stations, manholes, etc.) proposed for location on Federal lands (c.f. 43 CFR 3809.401(b)(2)(viii)). If it is determined that the pipeline cannot be used, describe in detail the alternative water delivery system.

10. Water-supply (p 3-14): Provide an estimate of total water use and an inventory of projected water use by activity (i.e., dust suppression, milling, floatation, etc.). Include estimated volumes of make-up water from pit de-watering and thickener overflow recycling (p. 3-8). (c.f. 43 CFR 3809.401(b)(2)(iii)).

11. Exploration activities (p. 3-18): Specify if exploration activities on Federal lands will be limited to the permits areas defined in Figures 2-1 and 3-1. If exploratory drilling is planned on Federal surface or mineral estate outside of this boundary, specify the locations of the proposed drillholes and access routes.

12. Invasive non-native species (p. 3-22): Provide details on noxious weed prevention and monitoring programs. Include information on BMPs to minimize noxious weed infestation (i.e., washing vehicles and equipment, obtaining seed and mulch from certified suppliers), monitoring strategies (including soil stockpiles), and mitigation measures if an on-site infestation is detected.

13. Reagents (p. 3-24 and Appendix E): Specify the planned retaining volume of the berm for the No. 1 diesel fuel tank and map the location of reagent mixing and storage area. Describe the construction of the reagent mixing and storage area (see #4) including the construction of the flooring. Provide details on the plastic liners (composition and thickness) and proposed depth of gravel cover for the fuel tank linings (p. 2 of Appendix E).

14. Hazardous materials management (p. 3-24 and 3-25): Specify the volumes of diesel fuel and ammonia nitrate that will be stored on site, and the number of bins, tanks, and explosive sheds that will be placed on BLM land. Complete your analysis so you may map the locations of these storage facilities.

15. Reclamation (p. 5-7): Finalize designs for the proposed waste rock facilities so BLM engineers may evaluate your proposal.

16. Reclamation (p. 5-11): Complete evaluations of tailings impoundment area to determine if the gravels and alluvial fill will be used for reclamation, impoundment construction, and/or placer operations. If material from the impoundment area will be used for reclamation on the Federal lands, describe BMPs to minimize invasive or noxious weed contamination or possible transfer of hazardous materials or contaminated soils to Federal lands.

17. Reclamation (p. 5-13): Any natural soil amendments used will have to be certified free of invasive and noxious weeds.

18. Reclamation (p. 5-14): Proposed seed mix is being evaluated by BLM wildlife and range staff and may be modified if necessary.

19. Reclamation (p. 5-14): Interim reclamation – Buildings, is this a proposal to maintain an on-site resident security guard during interruptions in operations?

20. Reclamation (p. 5-20): The reference "SRK 1995" is not listed in the bibliography, are you referring to the "Copper Flat Mine Hydrogeologic Studies" report of May 12, 1995? This report does not make a convincing argument that the pit lake level will be below hydrostatic.

21. Plant site (p. 5-23): Why is it necessary to leave foundations and footing buried on the public land? What would be the total volume of concrete left on site after operations are completed?

22. Reclamation (p. 5-25): Figure 5-3 was inadvertently omitted from the MPO.

23. Estimated reclamation cost (p. 5-25): Reclamation bonding will likely be deferred to the New Mexico Mining and Minerals Division.

Please be aware that the LCDO may require additional information or data collection if required to complete NEPA analysis for this project. Final MPO approval will occur after the BLM completes environmental review required under the National Environmental Policy Act (43 CFR 3809.411(3)(ii)) and completes consultation with the State of New Mexico to ensure your operations will be consistent with State water quality requirements (43 CFR 3809.411(3)(ix)).

Your proposed operations are also subject to regulation by the State of New Mexico. If you have not done so already, you are advised to contact the Mining and Minerals Division of the New Mexico Energy, Minerals and Natural Resources Department ((505) 476-3400) to determine what type of New Mexico State permit is required for your operation.

Please contact Michael Smith, Geologist, at (575) 525-4421, if you have any questions.

Sincerely,

EDWARD SEUM

Edward Seum
Supervisory Multi-Resources Specialist
Division of Multi-Resources

cc:
Holland Shepard
New Mexico Energy, Minerals
and Natural Resources Department
Mining and Minerals Division
1220 South St. Francis Drive
Santa Fe, NM 87505

L0310:MSmith:cp:2/1/2011:x4375:NMCopper.NM125986MPO.Ltr

2-23-2011

NEW MEXICO
ENVIRONMENT DEPARTMENT

Ground Water Quality Bureau

SUSANA MARTINEZ
Governor

JOHN SANCHEZ
Lieutenant Governor

P.O. Box 5469
1190 St. Francis Drive
Santa Fe, New Mexico 87502-5469
Phone (505) 827-2918 Fax (505) 827-2965
www.nmenv.state.nm.us



CERTIFIED MAIL – RETURN RECEIPT REQUESTED

February 23, 2011

J. Steven Raugust, PG
New Mexico Copper Corporation
2425 San Pedro Drive NE, Suite 100
Albuquerque, NM 87110

Dear Mr. Raugust,

Thank you for attending the recent meeting between the New Mexico Environment Department (NMED) and New Mexico Copper Corporation (NMCC) on February 17, 2011. In the meeting, we discussed the progress of the Copper Flat Mine Stage 1 Abatement Plan Proposal and Discharge Permit Application that are being prepared for submittal to NMED. The Copper Flat Mine site (Site) is located approximately 6 miles northeast of Hillsboro, New Mexico.

Pursuant to New Mexico Water Quality Control Commission (WQCC) Regulations Sections 20.6.2.1203.A(9), 20.6.2.4104 and 20.6.2.4106.A NMAC, NMED hereby provides notification that NMCC is a responsible person as defined in WQCC Regulations Sections 20.6.2.7.JJ and 20.6.2.7.OO NMAC and is required to submit an Abatement Plan for the Site. In addition, pursuant to WQCC Regulations Section 20.6.2.3104 NMAC, NMCC must submit a Discharge Permit Application to NMED and receive an approved Discharge Permit prior to initiation of any mining activities at the Site.

As agreed to in the meeting, NMCC will submit a Stage 1 Abatement Plan Proposal and Discharge Permit Application for the Site to NMED by March 31, 2011. Please contact Greg Huey at (505) 827-1046 with any questions or comments you may have regarding this matter.

Sincerely,

William C. Olson
Bureau Chief

cc: Mary Ann Menetrey, GWQB-MECS
Greg Huey, GWQB-MECS
Chris Eustice, MMD

3-9-2011

NEW MEXICO
ENVIRONMENT DEPARTMENT

Ground Water Quality Bureau

SUSANA MARTINEZ
Governor

JOHN SANCHEZ
Lieutenant Governor

P.O. Box 5469
1190 St. Francis Drive
Santa Fe, New Mexico 87502-5469
Phone (505) 827-2918 Fax (505) 827-2965
www.nmenv.state.nm.us

DAVID MARTIN
Secretary

RAJ SOLOMON, P.E.
Deputy Secretary

March 9, 2011

District Manager Bill Childress
Las Cruces District BLM
1800 Marquess Street
Las Cruces, NM 88005

RE: Request for Cooperating Agency Status, Environmental Impact Statement Development, New Mexico Copper Corporation's Proposed Copper Flat Mine

Dear Mr. Childress,

The New Mexico Environment Department requests Cooperating Agency status and inclusion in development of a Memorandum of Understanding for the purposes of collaborative planning and the production of an Environmental Impact Statement (EIS) for the proposed New Mexico Copper Corporation Copper Flat Mine. NMED is involved in regulation of the Copper Flat Mine through both a Ground Water Discharge Permit and a Stage I Abatement Plan pursuant to the Water Quality Control Commission Regulations 20.6.2.NMAC. Therefore, NMED has mine operational, reclamation and ground water abatement requirements that should be coordinated with any similar BLM requirements. NMED appreciates the opportunity to lend its regulatory and technical expertise to development of the EIS, and to coordinate efforts towards permitting the proposed operations in a manner that is protective of the environment.

If you have any questions please contact Greg Huey at (505) 827-1046.

Sincerely,

William C. Olson, Chief
Ground Water Quality Bureau
New Mexico Environment Department

WCO:gh

Cc: Mary Ann Menetrey, Manager, GWQB MECS
Holland Shepherd, Manager, Mining Act Reclamation Program
Mike Smith, Geologist, Bureau of Land Management, Las Cruces District Office, 1800 Marquess, Las Cruces, NM 88005
Jennifer A. Montoya, Bureau of Land Management, Las Cruces District Office, 1800 Marquess, Las Cruces, NM 88005

3-31-2011

THEMAC RESOURCES
New Mexico Copper Corporation
2425 San Pedro, NE, Suite 100
Albuquerque, New Mexico 87110

GROUND WATER
MAR 31 2011
BUREAU

March 31, 2011

Mr. Greg Huey
New Mexico Environment Department
GWQB-MECS
Harold L. Runnels Building
1190 St. Francis Drive
Santa Fe, New Mexico 87505

Re: New Mexico Copper Corporation's Application for Discharge Plan Modification for DP-001

Dear Mr. Huey,

I am pleased to attach New Mexico Copper Corporation's (NMCC's) application for discharge plan modification for DP-001, including the $100 permit fee. In order to facilitate the New Mexico Environment Department's (NMED's) review of this document, we would like to make note of the status of a few integral projects currently in progress by NMCC and its contractors.

The Plan of Operations (PoO) (Part B-1 of the discharge plan application) has been submitted to the Bureau of Land Management and is currently under review. NMCC will submit the final PoO when it becomes available.

NMED has contributed comments to NMCC's Copper Flat Sampling and Analysis Plan (SAP). Some of these comments have been addressed within the DP-001 application where possible. However, due to time constraints, some will be addressed in upcoming quarterly progress reports after discharge plan approval or in the Stage 1 Abatement Investigation Report. At our meeting on March 21, 2011, NMCC and the state agencies reviewed NMCC's strategy for addressing the SAP comments. It is our understanding from this meeting that NMED concurs with NMCC's strategy for addressing the SAP comments.

Please don't hesitate to call me if you have any questions or if I can be of further assistance. NMCC looks forward to working closely with the NMED to obtain modification of DP-001.

Sincerely,

J. Steven Raugust, PG
Project Manager
New Mexico Copper Corporation

Attachments

GROUND WATER
MAR 31 2011
BUREAU

THEMAC RESOURCES
New Mexico Copper Corporation
2425 San Pedro, NE, Suite 100
Albuquerque, New Mexico 87110

March 31, 2011

Mr. Greg Huey
New Mexico Environment Department
GWQB-MECS
Harold L. Runnels Building
1190 St. Francis Drive
Santa Fe, New Mexico 87505

Re: New Mexico Copper Corporation's Application for Discharge Plan Modification for DP-001

Dear Mr. Huey,

I am pleased to attach New Mexico Copper Corporation's (NMCC's) application for discharge plan modification for DP-001, including the $100 permit fee. In order to facilitate the New Mexico Environment Department's (NMED's) review of this document, we would like to make note of the status of a few integral projects currently in progress by NMCC and its contractors.

The Plan of Operations (PoO) (Part B-1 of the discharge plan application) has been submitted to the Bureau of Land Management and is currently under review. NMCC will submit the final PoO when it becomes available.

NMED has contributed comments to NMCC's Copper Flat Sampling and Analysis Plan (SAP). Some of these comments have been addressed within the DP-001 application where possible. However, due to time constraints, some will be addressed in upcoming quarterly progress reports after discharge plan approval or in the Stage 1 Abatement Investigation Report. At our meeting on March 21, 2011, NMCC and the state agencies reviewed NMCC's strategy for addressing the SAP comments. It is our understanding from this meeting that NMED concurs with NMCC's strategy for addressing the SAP comments.

Please don't hesitate to call me if you have any questions or if I can be of further assistance. NMCC looks forward to working closely with the NMED to obtain modification of DP-001.

Sincerely,

J. Steven Raugust, PG
Project Manager
New Mexico Copper Corporation

Attachments

3-31-2011

New Mexico Environment Department
Ground Water Quality Bureau

DP Processing Form

DP# 1 Reviewer Greg	Date	Initial

Discharge Plan Application		
❖ DP Application Received	3/31/11	ds
❖ Filing Fee Received (Amount: 100 00)	3/31/11	ds
❖ Plans and Specifications Received		

Public Notice		
❖ Public Notice 1 Published	6/1/11	ds

New Mexico Environmental Department
Ground Water Quality Bureau

Acknowledgement of Receipt

COPY

Acknowledgement of Receipt of Check/Cash

I hereby acknowledge receipt of Check No. #2068 Dated. 3/31/11
or cash, received in the amount of $ 100.00 from NM Copper Corp
for Copper Flat Mine 1 1535
(Facility Name) (DP No.) (AI ID)

Copy Made for Check Processing _____ Date _____
For Central File Activity PR02011000 1 (DP-MOD)

Submitted to ASD by: _____ Date: _____

Received in ASD by: _____ Date: _____

Filing Fee ☐ New Facility ☐ Renewal ☐

Modification ☒ Other ☐ (Explain) _____

Organization Code _____ Application FY _____

To be Deposited in the Ground Water Section Discharge Plan Fees.

Full Payment ☐ or Annual Increment ☐

BUREAU
MAR 31 2011
GROUND WATER

THIS CHECK IS DELIVERED IN CONNECTION WITH THE FOLLOWING ACCOUNT (S)

DATE		AMOUNT
TOTAL OF INVOICES		
LESS — % DISCOUNT		
LESS		
TOTAL DEDUCTIONS		
AMOUNT OF CHECK		

NEW MEXICO COPPER CORP
2425 SAN PEDRO DR NE SUITE 100
ALBUQUERQUE, NM 87110

2068
95-681/1070

DATE March 23, 2011

PAY TO THE ORDER OF NEW MEXICO ENVIRONMENT DEPT. $ 100 00

ONE HUNDRED AND 00/100 DOLLARS

Security Features Details on Back.

BANK of the WEST Coronado Office 1-800-488-2265

FOR Groundwater Discharge Permit App.

⑈002068⑈ ⑆107005813⑆ 011531008⑈

00305

INTERA Inc.
6000 Uptown Boulevard NE
Suite 220
Albuquerque, NM 87110
Telephone: 505 246 1600
Fax: 505 246 2600

March 31, 2011

Mr. Greg Huey
Ground Water Quality Bureau
Mining Environmental Compliance Section
New Mexico Environment Department
1190 St. Francis Dr.
Santa Fe, NM 87502

Re: Application for Discharge Permit Modification for the Copper Flat Mine, DP-001

Mr. Huey:

On behalf of New Mexico Copper Corporation, INTERA Incorporated (INTERA) is pleased to submit this Application for Discharge Permit Modification for the Copper Flat Mine to the New Mexico Environment Department Ground Water Quality Bureau Mining Environmental Compliance Section.

The following attachments have been included with this letter:

VOLUME 1:

PART A: ADMINISTRATIVE COMPLETENESS

Attachment A-1: Proposed Process Circuit

Attachment A-2: Stage 1 Abatement Plan

VOLUME 2:

PART B: OPERATIONAL & MONITORING PLANS

Attachment B-1: Plan of Operations

Attachment B-2: Proposed Facility Layout

Attachment B-3: Water Rights Documentation

PART C: SITE INFORMATION

Attachment C-1: Project Location Map

Attachment C-2: Regional Location Map

Attachment C-3: Topographic Maps

Attachment C-4: Flood Potential Map

Attachment C-5: Soil Survey Map

Please let us know if there is additional information that you require or if you have any questions.

Sincerely,
INTERA Inc.

Cynthia Ardito
Program Manager

File: NMC-001

Attachments

THEMAC RESOURCES
New Mexico Copper Corporation
2425 San Pedro, NE, Suite 100
Albuquerque, New Mexico 87110

March 31, 2011

Mr. Greg Huey
New Mexico Environment Department
GWQB-MECS
Harold L. Runnels Building
1190 St. Francis Drive
Santa Fe, New Mexico 87505

Re: New Mexico Copper Corporation's Application for Discharge Plan Modification for DP-001

Dear Mr. Huey,

I am pleased to attach New Mexico Copper Corporation's (NMCC's) application for discharge plan modification for DP-001, including the $100 permit fee. In order to facilitate the New Mexico Environment Department's (NMED's) review of this document, we would like to make note of the status of a few integral projects currently in progress by NMCC and its contractors.

The Plan of Operations (PoO) (Part B-1 of the discharge plan application) has been submitted to the Bureau of Land Management and is currently under review. NMCC will submit the final PoO when it becomes available.

NMED has contributed comments to NMCC's Copper Flat Sampling and Analysis Plan (SAP). Some of these comments have been addressed within the DP-001 application where possible. However, due to time constraints, some will be addressed in upcoming quarterly progress reports after discharge plan approval or in the Stage 1 Abatement Investigation Report. At our meeting on March 21, 2011, NMCC and the state agencies reviewed NMCC's strategy for addressing the SAP comments. It is our understanding from this meeting that NMED concurs with NMCC's strategy for addressing the SAP comments.

Please don't hesitate to call me if you have any questions or if I can be of further assistance. NMCC looks forward to working closely with the NMED to obtain modification of DP-001.

Sincerely,

J. Steven Raugust, PG
Project Manager
New Mexico Copper Corporation

Attachments

NEW MEXICO ENVIRONMENT DEPARTMENT
GROUND WATER QUALITY BUREAU

DISCHARGE PERMIT APPLICATION

Type of Application. Check appropriate box.

- ☐ Application for new Discharge Permit -- new facility
- ☐ Application for new Discharge Permit -- existing (unpermitted) facility
- ☐ Application for Discharge Permit Renewal
- ■ Application for Discharge Permit Modification
  "Modification" is defined as a change to the permit requirements that result from a change in the location of the discharge, a significant increase in the quantity of the discharge, or a significant change in the quality of the discharge.
- ☐ Application for Discharge Permit Renewal and Modification

For an existing Discharge Permit, please indicate: DP Number 001 Expiration date NA

Checklist of Application Components.

☐ Part A: Administrative Completeness.	*Instructions for completing the application are included on the form itself and on Supplemental Instructions for Parts A and B. You may fill out the application manually, or a Microsoft Word version may be downloaded from www.nmenv.state.nm.us (Ground Water Quality) and filled out electronically.*
☐ Part B: Operational, Monitoring, Contingency and Closure Plans, with required attachments. *Choose appropriate option*: ☐ Septic Tank System ☐ General – Various Facility Types	
☐ Part C: Site Information, with required attachments.	
☐ $100 Filing Fee, payable to the New Mexico Environment Department. *Required from all applicants.* An additional fee will be assessed prior to permit issuance. Permit fees are listed in Section 20.6.2.3114 NMAC.	

Certification. Signature must be that of the person named in Item A-3 of Part A of the application.

I certify under penalty of law that I am knowledgeable about the information contained in this application. The information is, to the best of my knowledge and belief, true, accurate and complete.

Signature: _____ Date: 3/31/2011

Printed Name: Steve Raugust

Title: Project Manager for New Mexico Copper

Send three complete copies of this application and the filing fee to:

Program Manager
Ground Water Pollution Prevention Section
New Mexico Environment Department
PO Box 5469
Santa Fe, NM 87502

Discharge Permit Application
for the
Copper Flat Mine

March 31, 2011

Prepared for:
New Mexico Copper Corporation

Prepared by:

Submitted to:
Ground Water Quality Bureau
Mining Environmental Compliance Section
New Mexico Environment Department

00312

NEW MEXICO ENVIRONMENT DEPARTMENT
GROUND WATER QUALITY BUREAU

DISCHARGE PERMIT APPLICATION

Type of Application. Check appropriate box.

- ☐ Application for new Discharge Permit -- new facility
- ☐ Application for new Discharge Permit -- existing (unpermitted) facility
- ☐ Application for Discharge Permit Renewal
- ■ Application for Discharge Permit Modification
  "Modification" is defined as a change to the permit requirements that result from a change in the location of the discharge, a significant increase in the quantity of the discharge, or a significant change in the quality of the discharge.
- ☐ Application for Discharge Permit Renewal and Modification

For an existing Discharge Permit, please indicate: DP Number 001 Expiration date NA

Checklist of Application Components.

☐ Part A: Administrative Completeness.	*Instructions for completing the application are included on the form itself and on Supplemental Instructions for Parts A and B.* *You may fill out the application manually, or a Microsoft Word version may be downloaded from www.nmenv.state.nm.us (Ground Water Quality) and filled out electronically.*
☐ Part B: Operational, Monitoring, Contingency and Closure Plans, with required attachments. *Choose appropriate option*: ☐ Septic Tank System ☐ General – Various Facility Types	
☐ Part C: Site Information, with required attachments.	
☐ $100 Filing Fee, payable to the New Mexico Environment Department. *Required from all applicants.* An additional fee will be assessed prior to permit issuance. Permit fees are listed in Section 20.6.2.3114 NMAC.	

Certification. Signature must be that of the person named in Item A-3 of Part A of the application.

I certify under penalty of law that I am knowledgeable about the information contained in this application. The information is, to the best of my knowledge and belief, true, accurate and complete.

Signature: _____ Date: _____

Printed Name: Steve Raugust

Title: Project Manager for New Mexico Copper

Send three complete copies of this application and the filing fee to:

Program Manager
Ground Water Pollution Prevention Section
New Mexico Environment Department
PO Box 5469
Santa Fe, NM 87502

GROUND WATER DISCHARGE PERMIT APPLICATION
PART A: ADMINISTRATIVE COMPLETENESS
All Facilities

A-1. **Facility Information.** See Supplemental Instructions to determine what constitutes the "facility." The physical location of the facility must be provided. If the facility does not have an address, the location can be described by road intersections, mile posts, or landmarks, as appropriate.

Facility Name: **Copper Flat Mine**

Former Names (if any): **Copper Flat Mine**

Physical address/location (*mandatory*): **Approximately 6 miles NE of Hillsboro, New Mexico in the E ½ of Section 36, T15S, R7W and W ½ of Section 31, T15S, R6W**

County: **Sierra**

Mailing address: **2425 San Pedro Dr., Suite 100**

Albuquerque, NM 87110

Contact person: **Steve Raugust**

Title: **Project Manager for New Mexico Copper**

Telephone number(s): **505-382-5770**

Fax number: _____ E-mail address: **steve.raugust@ThemacResourcesGroup.com**

A-2. **Type of Discharge and Type of Facility.** See Supplemental Instructions.

Type of discharge: ☐ Domestic ☐ Agricultural ☐ Industrial ■ Mining

Type of facility: **Copper/molybdenum/gold mine and mill.**

A-3. **Applicant Information.** The applicant is the person or entity (e.g., corporation, partnership, organization, municipality, etc.) legally responsible for the discharge and for complying with the terms of the Discharge Permit. If the applicant is an entity, then the name and title of a contact person must be provided. This application must be signed by the applicant or contact person named here.

Applicant Name: **New Mexico Copper Corporation**

Mailing address: **2425 San Pedro Dr., Suite 100**

Albuquerque, NM 87110

Contact person: **Steve Raugust**

Title: **Project Manager**

Telephone number(s): **505-382-5770**

Fax number: _____ E-mail address: **steve.raugust@ThemacResourcesGroup.com**

A-4. **Consultant Information (if applicable).** If the consultant is a company or organization, then the name and title of a contact person must be provided.

Consultant/Firm Name: **INTERA Incorporated**

Mailing address: **6000 Uptown Blvd. NE, Suite 220**

Albuquerque, NM 87110

Contact person: **Cindy Ardito**

Title: **Program Manager**

Telephone number(s): **(505) 246-1600**

Fax number: **(505) 246-2600** E-mail address: **cardito@intera.com**

A-5. **Permit Contact Information (if applicable).** If someone other the applicant listed in Item A-3 or a consultant listed in Item A-4 is a primary contact for this application and/or facility, list here.

Permit Contact Name: **(same as A-3 and A-4)**

Title:

Mailing address:

Telephone number(s):

Fax number: E-mail address:

A-6. **Ownership.**

The applicant owns (check as appropriate): ■ the facility ■ some discharge sites ☐ all discharge sites

If other parties own the facility or any of the discharge sites, attach their names and contact information.

Hydro Resources Corporation
4011 Mesa Verde Ave., NE
Albuquerque, NM 87110
505-266-2500

THEMAC Resources Group Limited (THEMAC), a Yukon corporation, owns and controls all shares of New Mexico Copper Corporation. THEMAC's address and phone number are:
Suite 2000, 1066 West Hastings Street
Vancouver, British Columbia, Canada, V6E 3X2
(+1) 604-495-6723

Edgar E. Greer owns various fee surface and mineral estates within the facility and has contracted to sell his fee surface and mineral estates to Ryan G. and Wendy M. Fancher.

The non-fee lands within the permit area are owned by the United States (Bureau of Land Management). The BLM can be contacted at the address and phone number below:
Las Cruces District Office, Bureau of Land Management
1800 Marquess Street
Las Cruces, NM 88005-3370
575-525-4300

A-7. Discharge Quantity.

Your Discharge Permit will specify a maximum discharge volume, which is typically expressed as the maximum number of gallons per day that may be treated and/or disposed of. Please indicate below the maximum discharge volume for your facility. You must show how it was determined in Part B of your application. For further explanation, see Supplemental Instructions for Part B.

Maximum discharge volume: **2,875,873** gallons per day

A-8. **Processing, Treatment, Storage and Disposal System.** Briefly describe how wastewater, sludge, etc. is processed, treated, stored, and/or disposed of at your facility. See Supplemental Instructions for examples of system components.

Attachment A-1 contains the Proposed Process Circuit (also Figure 3-5 of the PoO). Sections 3.2.1 through 3.2.3 of Attachment B-1, the Plan of Operations (PoO) describe the processing, treatment, storage and disposal systems for the Copper Flat Mine. Attachment B-2 contains the Proposed Facility Layout, which is also Figure 3-1 of the PoO.

In summary, new ore is mined from the open pit. Blasted rock from the pit is loaded and hauled to the primary crusher (processing plant), the low-grade ore stockpile, or either of four (4) waste rock piles. Processing at the plant involves a flotation process (no leaching). Tailings from the milling process will be conveyed to a lined tailings impoundment.

A-9. **Discharge Locations.** List the locations of your facility and of all components of your processing, treatment, storage and/or disposal system. Examples of components include septic tanks, lagoons, leachfields, irrigation sites, mine stockpiles, etc. Additional examples are listed in the Supplemental Instructions. Latitude and longitude are optional unless township, range and section are not available.

(Detailed designs may result in changes to this list)

Components	Township	Range	Section(s)	Latitude	Longitude
Pit-01	**15S**	**7W**	**26, 35**		
Waste Rock Pile - 01	**15S**	**7W**	**26**		
Waste Rock Pile - 02	**15S**	**7W**	**26, 27**		
Waste Rock Pile - 03	**15S**	**7W**	**26**		
Waste Rock Pile - 04	**15S**	**7W**	**25**		
Ore Stockpile-01	**15S**	**7W**	**25, 26, 35, 36**		
Tailings Impoundment - 01	**15S** **15S** **16S**	**7W** **6W** **6W**	**36** **31** **6**		
Stormwater/Settling Pond – 01	**15S**	**7W**	**36**		
Stormwater/Settling Pond - 02	**15S**	**7W**	**36**		
Septic Tank – 01	**15S**	**7W**	**35**		
Septic Leachfield - 01	**15S**	**7W**	**35**		
Septic Tank – 02	**15S**	**7W**	**35**		
Septic Leachfield - 02	**15S**	**7W**	**35**		

A-10. Discharge Quality.

Indicate the expected quality of the discharge -- wastewater, leachate, sludge, etc. -- generated, stored, treated, processed and/or discharged at your facility. List the contaminants of concern and the expected concentrations. *Not all facilities need to characterize influent quality.* See Supplemental Instructions for typical contaminants and additional guidance.

Expected or Known Contaminants	Expected or Known Contaminants Indicate units: mg/L, CFU/100 ml, etc.	
	Incoming (Influent)	Final (Effluent)
Pit-01	**N/A**	**See Sections 3.3, 4.2 and 5.2 of Attachment A-2, the Stage 1 Abatement Plan**
Waste Rock Piles	**N/A**	**See Section 5.3 of Attachment A-2, the Stage 1 Abatement Plan**
Tailings Impoundment - 01	**N/A**	**See Section 5.1 of Attachment A-2, the Stage 1 Abatement Plan**

For **new** septic tank systems, you may either fill out the chart above or simply check one of the following options:

☐ typical domestic wastewater

☐ low-strength domestic wastewater (large gray water component; e.g., laundromat, spa, etc.)

☐ high-strength domestic wastewater (low water use; e.g., RV park, low-flow toilets at campground, etc.)

A-11. Ground Water Conditions.

All applicants must provide the depth to and pre-discharge TDS concentration of the ground water that could be affected by the discharge. Refer to Supplemental Instructions for details on how to obtain these values.

Indicate the depth to the most shallow ground water beneath the discharge site. If there are multiple discharge sites, indicate the range of depths.

Depth to water (feet): **40-50 ft**

Groundwater daylights in the open pit, and elevated water levels are present under the tailings impoundment measured at 3.73 ft bgs during the Jan/Feb 2010 monitoring event.

Reference:

☐ Measurement, nearby monitoring well

☐ Measurement, nearby supply well

☐ Well log from nearby well (attach copy)

☐ Office of the State Engineer
http://www.ose.state.nm.us/

■ Report or study (give citation here and attach relevant portion):
See Section 2.3 of Attachment A-2, the Stage 1 Abatement Plan

☐ Other (describe):

Indicate pre-discharge total dissolved solids (TDS) concentration of most shallow ground water beneath the discharge site. Attach copies of analyses.

TDS (mg/L): **840 mg/L at SHB-28 in 1976**
1260 mg/L at GWQ-5 in 1981

Reference:

☐ Analysis from upgradient monitoring well

☐ Analysis from on-site supply well

☐ Analysis from shallow nearby supply well

☐ Concentration provided in previous Discharge Permit application

■ Report or study (give citation here and attach relevant portion):
See Section 3.4 and Appendix B-3 of Attachment A-2, the Stage 1 Abatement Plan

☐ Other (describe):

A-12. Public Notice. See Supplemental Instructions.

a) The public notice packet including instructions and materials should be sent to:

■ Applicant ☐ Consultant ☐ Other: _____

b) Copies of the public notice packet (excluding sign) should be sent to:

☐ Applicant ☐ Consultant ☐ Other: _____

c) The applicant is required to provide public notice of this application by placing a display ad in a newspaper of general circulation near the location of the proposed discharge. Indicate newspaper you intend to place the ad in:

Newspaper: **The Sierra County Sentinel**

d) *For new or modification applications only:* The applicant must post a sign for 30 days in a conspicuous location at or near the facility, as approved by NMED. One sign must be posted for each 640 contiguous acres or less of the discharge site. An additional notice must be posted at an off-site location conspicuous to the public. Describe the locations below where you intend to post the notices. You may also attach sketches or photographs.

At or near facility: *2 by 3 feet in size*
A sign will be posted at the road pull out on the southeast side of New Mexico Highway 152, near the Geronimo Trail Scenic Byway sign (between mile marker 55 and mile marker 56).

Off-site location: *flyer size*
A flyer will be posted at the Hillsboro, NM Post Office, located at:
300 Main St.
Hillsboro, NM 88042

Supplemental Instructions for Part A

All Facilities

Please note: Discharge Permits are required for a wide range of facilities that process, treat, store and/or dispose of wastewater, sludge, septage, leachate, contaminated soils, mine tailings, industrial waste, mine ore, waste rock, or other similar materials. For the purposes of this application form, the term "discharge" applies to any of these materials whether they are actually discharged or whether they represent only a potential discharge that could occur due to factors such as poor maintenance, improper installation, equipment failure or accidents.

A-1. Facility Information.

The "facility" may be identified as:

a) a treatment facility, such as a municipal wastewater treatment plant;
b) the source of the discharge, such as a subdivision, dairy, or waste rock pile;
c) a disposal facility or operation, such as for sludge or septage;
d) the discharge location or recipient of reclaimed wastewater for reuse, such as a golf course or cement plant;
e) a storage and/or processing facility with off-site disposal;
f) a collection of facilities, such as numerous comfort stations at a state park; or
g) a project or operation, such as a construction project or a system to distribute reclaimed wastewater throughout a city.

A-2. Type of Discharge and Type of Facility.

Characterize the type of discharge, wastewater, sludge, leachate, etc. generated, processed or received by your facility as domestic, agricultural, industrial or mining. Examples of a variety of facility types are categorized below.

Domestic Waste

"Domestic" waste contains human excreta or originates from typical residential plumbing fixtures.

- Municipal wastewater treatment plant
- Septage disposal

- Sludge disposal
- Mobile home/RV park
- Campground/park
- School/educational facility
- Restaurant
- Subdivision/apartment complex
- Unincorporated community
- Lodging/resort/spa
- Residential facility
- Commercial/shopping complex
- Laundromat
- Facility using reclaimed domestic wastewater

Agricultural Waste

- Dairy
- Food processing
- Slaughter facility
- Nursery/greenhouse
- Manufacture/processing of agricultural chemicals
- Feedlot
- Livestock truck washout

Industrial Waste

- Manufacturing
- Power plant
- Military installation
- Vehicle/equipment wash
- Mortuary
- Hydrocarbon landfarm
- Ground water remediation
- Ethanol plant
- Asphalt plant

Mining Waste

- tailing impoundment
- mine dewatering
- waste rock pile
- smelter slag
- in-situ leach
- leach piles
- pipelines
- collection ponds
- concentrator – other beneficiation

This listing is only a guide, as there can be crossover between categories. For example, a golf course might use treated industrial wastewater for irrigation. The type of facility in that case is "golf course" and the type of waste is "industrial." A mining operation may need a permit for its restroom and shower facilities. In that case, the type of facility is a "mining operation" and the type of discharge is "domestic waste."

A-7. Discharge Quantity.

Refer to the Supplemental Instructions for Part B for information on how to calculate the maximum discharge volume for your facility.

A-8 and A-9. Treatment, Storage, Disposal System.

The following are examples of treatment, storage and disposal methods:

Treatment Methods

- Septic tank
- Grease interceptor
- Oil/water separator
- Manure separator
- Wetlands
- Lagoon (indicate whether aerated and type of liner)
- Trickling filter
- Activated sludge (extended air, SBR, etc.)
- Sand filter
- Membranes
- Sludge drying bed
- Disinfection (specify type)
  - chlorination
  - UV/ozone
- Water treatment plant

Storage Methods

- Above/below ground tank
- Storage lagoon (indicate type of liner)
- Holding tank
- Pit toilet
- Stockpile
- Tailing impoundment

Disposal Methods

- Leachfield
- Infiltration gallery
- Evaporation lagoon (indicate type of liner)
- Evaporation tank
- Impoundment
- Discharge to waters of the US (NPDES permit required)
- Ongoing land application (specify type)
  - subsurface irrigation
  - sprinkler irrigation
  - flood irrigation
  - drip irrigation
  - surface spreading (solids)
  - surface injection (solids)
- Temporary uses of reclaimed wastewater

- Ongoing use of reclaimed wastewater for:
  - manufacturing
  - construction or dust control

A-9. Discharge Quality.

Untreated wastewater entering a treatment facility (also referred to as "influent") must be characterized so that the treatment process can be evaluated. It is not necessary to provide influent quality for systems providing minimal treatment prior to discharge or disposal, such as systems relying on crop uptake for treatment (e.g., dairies), septic tank – leachfield systems, storage/processing facilities or evaporative systems. The final quality of the waste or wastewater disposed of or discharged must be characterized for all facilities.

For most agricultural and domestic facilities, the contaminants of concern include nitrate as nitrogen (NO_3-N), total Kjeldahl nitrogen (TKN), total dissolved solids (TDS), and chloride (Cl). For domestic facilities with advanced treatment, additional contaminants include total suspended solids (TSS), biochemical oxygen demand (BOD_5), and fecal coliform bacteria. Contaminants of concern at industrial and mining sites include pH, metals, and organic compounds. List all that apply.

A-10. Ground Water Conditions.

The depth to ground water beneath your facility and/or discharge site must be provided. This is true even if your facility or operation is intended to have no discharge. Discharge Permits are required for "no-discharge" lagoons, storage tanks, etc. because of the potential for a discharge to occur due to factors such as improper installation, poor maintenance, equipment failure or accidents.

The best way to determine the depth to water is to measure it in an on-site or nearby monitoring well. If a monitoring well is not available, the measurement may be from a water supply well. If there is a well but it is not possible to access it for a measurement, you could refer to the well log for that well and/or others in the vicinity. Well log information is available on the website of the State Engineer's office:

http://www.ose.state.nm.us/.

Be aware that water levels have dropped in many areas of the state, so more recent well logs in those areas are more reliable.

There may be a significant discrepancy in the depth to water in different wells, even when falling water levels is not a factor. One reason for this is that a water supply well may rely on a deep aquifer rather than water in the "first" or most shallow aquifer. Discharge Permits are intended to protect all ground water, so it is important to report the most shallow depth in the vicinity of your site.

The total dissolved solids (TDS) concentration of the ground water prior to discharge must be provided. As explained for the depth to water, this is true even if your facility or operation is intended to have no discharge. The TDS value provides a general indication of the quality of the ground water that could be affected by your operation.

The best way to obtain a pre-discharge TDS concentration is to sample an on-site or nearby well before your facility begins operating. It is better to sample a shallow rather than a deep well, if possible. It may be that a neighboring facility has existing analytical data for its Discharge Permit. (If so, be sure to obtain data from a non-impacted well.)

If there are no wells in your vicinity or it is not possible to sample them, you may find general TDS concentrations in reports available from sources such as a university, the State Engineer's Office (http://www.ose.state.nm.us/) or the US Geological Survey (http://nm.water.usgs.gov/). If you are renewing or modifying your Discharge Permit, you may refer to the TDS concentration previously determined if there was a sound basis for it. Monitoring data or other information obtained since the permit was issued, however, may warrant listing a different value.

A-12. Public Notice.

The latest revision of 20.6.2.3108 NMAC, which specifies the applicant's public notice requirements, is effective as of July 16, 2006. Once NMED has determined that your application is administratively complete, **the instructions and materials necessary to complete the public notice requirements will be sent to you.**

Attachment A-1

Proposed Process Circuit



DESIGN: -	DRAWN: -	REVIEWED: -	
CHECKED: -	APPROVED: -	DATE: 12/6/2010	
FILE NAME: PoO_Fig3-05_ProposedProcessCircuit_JQG_20101201.dwg			

PREPARED FOR:

NEW MEXICO COPPER CORPORATION

COPPER FLAT PROJECT

DRAWING TITLE:

PROPOSED PROCESS CIRCUIT

DRAWING NO. **FIGURE 3-5**

REVISION NO. **A**

JOB NO. **191000-03**

H:\Copper_Flat\New Mexico Copper Corp\191000_03_Copper_Flat_Permitting\040_Drafting\20101115\PoO_Fig3-05_ProposedProcessCircuit_JQG_20101201.dwg

Attachment A-2

Stage 1 Abatement Plan

GROUND WATER DISCHARGE PERMIT APPLICATION
PART B: OPERATIONAL, MONITORING, CONTINGENCY AND CLOSURE PLANS
GENERAL FORM (VARIOUS FACILITY TYPES)

Operational Plan *[Section 20.6.2.3106.C, 3109.C NMAC]*

B-1. **Source(s) of the Discharge.** Describe what generates the wastewater, sludge or other discharges processed and/or disposed of at your facility. Identify all sources. Attach additional pages, if needed. See Supplemental Instructions.

See Sections 3.2.1 through 3.2.3 of Attachment B-1, the PoO

B-2. **Discharge Quantity.** Describe the methods/calculations used to determine the maximum discharge volume listed in Item A-6 in Part A of your application. Attach additional pages, if needed. See Supplemental Instructions.

Tailings deposition would be at the rate of approximately 17,500 tons per day (tpd). Tailings going to the impoundment are expected to be 50% solids by weight. Calculations to get gallons per day are:

(0.5 ton liquids x 2000 lb/ton)/(62.4 lb/ft^3 = 16.03 ft^3 liquids in slurry

(0.5 ton solids x 2000 lb/ton)/(62.4 lb/ft^3 x 2.7 SG) = 5.94 ft^3 solids in slurry

16.03 ft^3/ton + 5.94 ft^3/ton = 21.97 ft^3/ton total tailings slurry

(17,500 tons/day x 21.97 ft^3/ton x 7.48 gal/ft^3)

= 2,875,873 gallons per day total slurry going to tailings impoundment

B-3. **Site Map.** Attach a site map showing the components of your proposed system and relevant surrounding features, clearly labeled, such as:

- treatment units
- lagoons
- tanks
- sumps
- manure separators
- land application fields
- domestic wastewater reuse areas
- pits
- stockpiles
- leachfields
- sludge drying beds
- roads
- buildings
- supply wells
- monitoring wells
- extraction/injection wells
- arroyos
- nearby water bodies such as ponds or canals
- property boundaries
- other permitted discharges
- required setbacks
- north arrow

If map is not to scale, mark distances on the map.

■ Site map is attached. **(See maps in Attachment B-2, the Proposed Facility Layout and Well Locations)**

B-4. **Flood Protection**. Describe the methods used to prevent flooding and run-off at the facility (tank protection, berms, diversion channels, etc.)

See Section 3.2.2, Section 5.7.4.2, and Section 5.7.4.3 of Attachment B-1, the PoO.
Water erosion controls, such as berms and diversion ditches, would be installed to divert runoff away from waste rock disposal areas. Water diversion ditches would also be used to control water inflow onto waste rock disposal piles containing partially oxidized and unoxidized material.
Runoff from the waste rock disposal areas and the low-grade ore stockpile would be controlled by diverting the runoff water into a collection ditch and then recycling it into the process water system. No discharge is expected to occur. The final grading plan for the waste rock disposal areas would be designed to eliminate surface water run on, enhance runoff, reduce infiltration, reduce visual impacts, and facilitate revegetation through back-grading or crowned grading. Thirty-foot wide catch benches would be left in place to interrupt surface sheet flow.
The tailings impoundment has been designed to contain the equivalent of 75 percent of the probable maximum precipitation (PMP) during operations. A spillway capable of passing 75 percent of the PMP would be required upon closure.
The mining and concentrating process would not involve any discharge to surface water courses. Surface runoff (stormwater) from the mine and plant site area would be collected in containment (settling) ponds and recycled into the process water system. Stormwater outside the plant and mine site would not come in contact with the proposed operation due to existing diversion ditches, dams, and berms.

B-5. **Plans and Specifications.** For new facilities and for new components of existing systems, attach plans and specifications certified by a New Mexico registered professional engineer. *[Section 20.6.2.1202 NMAC]*

☐ Not applicable because no new facilities are proposed.

■ Plans and specifications are attached.

For Tailings Impoundment Plans see Appendix D of Attachment B-1, the PoO

☐ Plans and specifications were previously submitted. Submittal date(s): _____

B-6. **Description of Components.** Provide descriptive details of all components of your processing, treatment, storage and/or disposal system. Include all components listed under Item A-8 in Part A.

(Detailed designs may result in changes to this list)

Component	Description (construction material, liner type, irrigation method, capacity, dimensions, area, etc.)
Pit-01	**See Section 3.2.1 of Attachment B-1, the PoO**
Waste Rock Pile - 01	**See Section 3.2.2 of Attachment B-1, the PoO**
Waste Rock Pile - 02	**See Section 3.2.2 of Attachment B-1, the PoO**
Waste Rock Pile - 03	**See Section 3.2.2 of Attachment B-1, the PoO**
Waste Rock Pile - 04	**See Section 3.2.2 of Attachment B-1, the PoO**
Ore Stockpile-01	**See Section 3.2.2 of Attachment B-1, the PoO**
Tailings Impoundment - 01	**See Sections 3.2.3.4 and 3.2.3.5 of Attachment B-1, the PoO**
Stormwater/Settling Pond – 01	**See Section 3.2.7.1 of Attachment B-1, the PoO**
Stormwater/Settling Pond - 02	**See Section 3.2.7.1 of Attachment B-1, the PoO**
Septic Tank – 01	**See Section 3.4.10.1 and Section 5.16.5.6 of Attachment B-1, the PoO**
Septic Leachfield - 01	**See Section 3.4.10.1 of the PoO**
Septic Tank – 02	**See Section 3.4.10.1 and Section 5.16.5.6 of the PoO**
Septic Leachfield - 02	**See Section 3.4.10.1 of the PoO**

B-7. **Operational Plan.** Attach a detailed description of how you operate your processing, treatment, storage and/or disposal system.

Animal feeding operations: include stormwater management, nutrient management plans, method for mixing irrigation and wastewater.

Domestic wastewater treatment facilities: include pre-treatment, solids management, vegetation management for land application.

Facilities using reclaimed domestic wastewater above ground: include proposed water quality classification(s), effluent monitoring, setbacks, irrigation schedules, etc. that will result in protection of public health and the environment. Please refer to *NMED Ground Water Quality Bureau Guidance: Above-Ground Use of Reclaimed Domestic Wastewater* for further information. A copy of the guidance document is available on the NMED website www.nmenv.state.nm.us under "Ground Water Quality".

■ Operational plan is attached. **See Attachment B-1, the Plan of Operations (PoO), December 2010**

☐ Operational plan was previously submitted. Submittal date(s): _____

B-8. **System Maintenance**. Attach a description of the operations and maintenance procedures which ensure that your processing, treatment and disposal system functions properly; e.g., inspections, pumping schedules, equipment maintenance, etc.

■ O & M procedures are attached. **See Section 3.4 in Appendix E of Attachment B-1, the PoO**

☐ O & M procedures were previously submitted. Submittal date(s): _____

B-9. **Backflow Prevention.** If wastewater is used for land application or irrigation, describe methods used to protect wells from contamination by wastewater backflow. For new facilities or new systems at an existing facility, only air gap or reduced pressure valve assemblies are acceptable methods.

a) Clearly describe and/or sketch the location of air gaps or devices and attach specifications.

Water supply system is in the process of being designed, but will contain all necessary backflow prevention devices.

b) Describe how devices are maintained.

Water supply system is in the process of being designed.

B-10. **Water Rights.** Animal feeding operations which land apply wastewater must attach documentation of irrigation water rights for the proposed land application fields, sufficient to sustain the intended crop rotation.

Water rights are described in declarations, amended declarations, and supporting documents under New Mexico State Engineer File Nos. LRG-4652 through LRG-4652-S-17 and LRG-4654.

■ Water right documentation is attached. **(See Attachment B-3, Water Rights Documentation)**

☐ Not applicable.

B-11. **Past Ground Water Monitoring Results**. *This item applies only to existing facilities seeking renewal and/or modification of a Discharge Permit that required ground water monitoring.*

a) Attach a graph or a table showing all analytical results from ground water sampling at your facility. If preparing graphs, a separate graph should be developed for each constituent, except that nitrate and TKN may be shown on the same graph. Multiple wells may be shown on the same graph. See Supplemental Instructions for sample table and graph.
(See Section 3.4 of Attachment A-2, the Stage 1 Abatement Plan)

b) If the monitoring results indicate that ground water standards have been violated or that there is an upward trend approaching standards, attach a description of what actions you have taken or will take to address the elevated concentrations. Ground water standards are listed in Section 20.6.2.3103 NMAC. See the Supplemental Instructions for frequently referenced standards.
(See Attachment A-2, the Stage 1 Abatement Plan)

Monitoring Plan *[Section 20.6.2.3107.A NMAC]*

B-12. **Discharge Volumes.** Describe how and where the monthly discharge volume at your facility will be. For all measuring devices, provide type, location, and units of measure including multipliers (e.g., gallons, gallons x 100, acre-ft, etc.) See Supplemental Instructions. Attach additional pages, if necessary.

Water supply system is still in the process of being designed. The volume of discharge going to the tailings impoundment will be measured after it leaves the tailings thickener and before it reaches the tailings impoundment.

B-13. Discharge Quality Monitoring. Discharge Permits typically require that the discharge (treated wastewater, sludge, septage, etc.) be sampled on a regular basis. The frequency of sampling varies by type of facility, as do the contaminants of concern. Domestic and agricultural Discharge Permits typically require sampling for total Kjeldahl nitrogen (TKN), nitrate-nitrogen (NO_3-N), total dissolved solids (TDS) and chloride on a quarterly or semi-annual basis. *(continued on next page)*

If reclaimed domestic wastewater will be discharged for above ground uses, testing of the discharge for additional parameters is appropriate. Please refer to the *NMED Ground Water Quality Bureau Guidance: Above-Ground Use of Reclaimed Domestic Wastewater* for further information.

In the space below, provide a description or sketch of the sampling point(s) to be used for sampling the discharge at your facility.

Water supply system is still in the process of being designed. A monitoring program will be part of the Mine Plan. The quality of discharge going to the tailings impoundment will be measured after it leaves the tailings thickener and before it reaches the tailings impoundment.

Optional: In the space below (or as an attachment), you may propose revisions or additions to the standard discharge quality monitoring requirements. If you do, provide the rationale for your proposal.

NA

B-14. Ground Water Quality Monitoring. Discharge Permits typically require that ground water samples be collected quarterly from properly constructed monitoring wells located downgradient from discharge locations. The samples must be analyzed for contaminants of concern. For most domestic and agricultural Discharge Permits, the typical contaminants of concern are total Kjeldahl nitrogen (TKN), nitrate-nitrogen (NO_3-N), total dissolved solids (TDS) and chloride.

Optional: In the space below (or as an attachment), you may propose revisions or additions to the standard ground water monitoring requirements. If you do, provide the rationale for your proposal.

A baseline characterization study is in progress (See Attachment A-2, the Stage 1 Abatement Plan).

A groundwater monitoring program will be proposed based on the results.

For existing facilities:

Indicate number of existing monitoring wells: _____

Attach copies of monitoring well logs.

■ Well logs attached. ☐ Well logs cannot be located.

☐ Well logs previously submitted. Submittal date(s): _____

(See Appendix 4 of Attachment A-2, the Stage 1 Abatement Plan)

Attach copy of monitoring well survey (typically not applicable if fewer than 3 monitoring wells).

☐ Survey attached. ☐ No survey has been conducted.

☐ Survey previously submitted. Submittal date(s): _____

B-15. Other Monitoring. In addition to discharge volumes, discharge quality monitoring and ground water sampling, Discharge Permits typically require the following monitoring, depending on the type of facility:

- inspection and pumping of septic tanks, grease tanks, lift stations
- inspection of leachfields
- inspection of lagoons
- process testing for treatment plants
- land application data sheets (LADS)
- tracking of chemical fertilizer applications to land application areas
- soil sampling (agricultural and selected other facilities land applying wastewater)
- harvested plant material testing (agricultural facilities)

Optional: In the space below (or as an attachment), you may propose revisions or additions to the other standard monitoring requirements for your type of facility. If you do, provide the rationale for your proposal.

(See Appendix E of Attachment B-1, the PoO)

Contingency Plan *[Section 20.6.2.3107.A.10 NMAC]*

B-16. System Failure. Describe your contingency plan in the event there is a failure of your wastewater or discharge system (e.g., wastewater back-up, pump failure, pipe breaks, tank overflow, leachfield failure, saturated fields etc.)

(See Appendix E of Attachment B-1, the PoO)

B-17. Contingency Leachfield Location. *This item applies only if your disposal system includes a leachfield.* Identify a location on your site map (Item B-3) for a contingency leachfield in the event that your leachfield must be replaced. If no land is available for a contingency leachfield at an existing facility, describe how you will address a failed leachfield. New facilities must provide for a contingency leachfield location.

NA

B-18. Other Contingencies. Discharge Permits typically contain standard contingencies to address:

- exceeding wastewater quality limits
- violation of ground water or surface water standards
- spills or illegal releases of wastewater
- migration of soil nitrogen
- loading nitrogen above limit

Propose additional contingency plans, if appropriate:

NA

Closure Plan *[Section 20.6.2.3107(A)11 NMAC]*

B-18. Facility Closure and Post-Closure Monitoring. Discharge Permits contain standard requirements to address the closure of part or all of your discharge system, as follows:

- cap or plug lines to prevent the flow of wastewater to treatment or disposal system
- empty and remove or backfill tanks
- empty lagoons, perforate or remove liners, re-grade to surface topography
- appropriately dispose of solids
- regrade and cover stockpiles at mine facilities
- continue ground water monitoring for at least two years, longer as appropriate
- enact contingency plans if ground water standards are violated
- financial assurance may be required.

Propose additional closure plans in the space below or as an attachment, if appropriate:

(See Section 5 of Attachment B-1, the PoO)

Please Note: You must also complete Part C of the application.

Supplemental Instructions for Part B – General Form

B-1. Source(s) of the Discharge.

Be specific in describing all sources. Consider the following examples:

- Municipalities – identify particular industries or specialized facilities contributing wastewater.
- RV Parks – identify showers, dump stations, laundromat, etc.
- Subdivisions – identify homes, apartments, commercial developments, water softener backwash, etc.
- Landfarms or disposal facilities – specify type of materials accepted, e.g., residential septage, car wash grit trap waste, contaminated soils/water, treated municipal sludge, etc.
- Dairies – identify milking parlors, type of washdown used, sources of stormwater runoff, etc.
- Schools – identify cafeteria, gym, showers, etc.
- Truck stops – identify restaurant, showers, car wash, etc.
- Facilities receiving reclaimed wastewater – identify the treatment facility providing the reclaimed wastewater.
- Food processing and industrial facilities – describe the processes which produce the waste stream and chemicals used.
- Mines – identify processes including beneficiation, tailing, waste rock, leach facilities, pipelines, ponds, catchments, booster stations, in-situ leach facilities.

You do not need to include solid wastes, hazardous wastes or discharges being managed under other permits; however, these should be listed under Item C-7 in Part C of the application.

B-2. Discharge Quantity.

Your Discharge Permit will allow for the treatment, processing and/or discharge of up to a specified volume, generally, a maximum number of gallons per day. The flow at your facility on any given day must not exceed this "maximum discharge volume." It is determined based on the expected contributions from the sources you identified in Item B-1.

NMED will carefully review the basis of the maximum discharge volume you propose. Show all your calculations and assumptions.

Animal feeding operations must provide calculations based on the number of animals and water conservation practices in place.

Landfarms, disposal facilities, processing facilities typically identify the expected number of loads to be delivered.

For septic systems and wastewater treatment plants, the maximum discharge volume is also referred to as the "design flow." It includes a peaking or safety factor to guard against back-ups and overflows.

Municipal wastewater treatment facilities should identify the population served, growth assumptions, and expected per capita usage considering any contributing industries.

On-site domestic wastewater treatment facilities should rely on published design flows such as those provided in the NMED Liquid Waste Regulations (20.7.3 NMAC), the Uniform Plumbing Code or the USEPA On-site Wastewater Treatment Systems Manual.

For existing facilities, the maximum discharge volume may be based on a record of measured flows if no changes are anticipated. At least two years of flow data must be submitted, and the highest monthly discharge volume must be multiplied by a peaking factor of 1.5.

NMED will verify that your proposed or existing facility can handle maximum discharge volume you propose.

B-11. Past Monitoring Results.

A complete list of ground water standards can be found in Section 20.6.2.3103 NMAC. The standards for contaminants most frequently monitored under Discharge Permits are as follows:

Nitrate-nitrogen (NO_3-N).....10 mg/L
Chloride ..... 250 mg/L
Total dissolved solids (TDS) ... 1000 mg/L
Sulfate (SO_4).....600 mg/L
pH ..... between 6 and 9

There is no ground water standard for total Kjeldahl nitrogen (TKN). Because TKN converts readily to nitrate as it moves through the vadose zone, however, concentrations approaching or exceeding 10 mg/L are of concern.

Additional parameters typically apply at mining or industrial facilities.

Some ground waters in the state have TDS or chloride concentrations that naturally exceed these standards. In that case, the standard is the naturally occurring level. You must provide documentation of such elevated natural conditions, such as analytical results from a non-impacted well.

An example table and graph follow:

Date	Monitoring Well 1	
	NO3-N	TKN
Jan-04	4.2	2.2
Apr-04	3.4	1.2
Jul-04	6.5	3.2
Oct-04	10	4.8
Jan-05	3.5	5.6
Apr-05	4.2	2.1
Jul-05	5.5	1.3
Oct-05	5.5	0.8
Jan-06	4.2	3.3
Apr-06	3.2	2.2
Jul-06	6.5	2.2



B-12. Discharge Volumes.

You must provide a method for measuring the discharge volume (Section 20.6.2.3109.H.1 NMAC). At facilities with treatment or storage lagoons, it is necessary to measure both the volume entering the treatment system as well as the volume ultimately discharged.

If you land apply wastewater to more that one discharge location, you must be able to track the volume to each location.

If your facility is small and relies on gravity to carry wastewater to the treatment and disposal system, it may be acceptable to estimate the wastewater flow. This can be done by metering water usage and deducting the volume of water used for fresh-water irrigation, swimming pools, evaporative cooling, livestock watering or other uses that do not result in wastewater flowing to the treatment system.

Attachment B-1

Plan of Operations

Attachment B-2

Proposed Facility Layout



EXPLANATION

Public
Plant Facilities
Waste Rock
Tailings
Pit
Diversion
Access Road
Mine Boundary
Pond
Topsoil Stockpile
Ore Stockpile
Haul Road
Ancillary

IF THE ABOVE BAR DOES NOT SCALE 1 INCH, THE DRAWING SCALE IS ALTERED

DESIGN: -	DRAWN: -	REVIEWED: -	
CHECKED: -	APPROVED: -	DATE: 12/1/2010	
FILE NAME: PoO_Fig3-01_PropFacilities_JQG_20101123			

NEW MEXICO COPPER CORPORATION

COPPER FLAT MINE

DRAWING TITLE: **PROPOSED FACILITY LAYOUT**

DRAWING NO. **FIGURE 3-1**	SHEET 4 OF 28	REVISION NO. **A**
JOB NO. **191000-03**		

Path: H:\Copper_Flat\New Mexico Copper Corp\191000_03_Copper_Flat_Permitting\040_Drafting\20101115\PoO_Fig3-01_PropFacilities_JQG_20101123.mxd



N

0 3,000 6,000 12,000 18,000

Feet

Legend

- Monitoring Well
- Production Well
- Proposed Mine Permit Boundary

Mine Boundary:
Tom Van Bebber
Projection Information:
-New Mexico State Plane West, NAD 1927

INTERA

Figure B-2b
Well Locations,
Discharge Permit Application
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Discharge_Permit_Figures\FigB2b_Topo.mxd 3/28/2011

00337

Attachment B-3

Water Rights Documentation

OPTION and PURCHASE AGREEMENT

THIS AGREEMENT (this "Agreement") is made effective ~~August~~ September 9, 2010 (the "Effective Date") by and

BETWEEN

WILLIAM FROST and LINDA JO FROST, husband and wife (separately and collectively, "**Frost**"), and **HARRIS GRAY**, a single man ("**Gray**"). In this Agreement, Frost and Gray are separately and collectively called ("**Optionors**");

AND

NEW MEXICO COPPER CORPORATION, a New Mexico corporation ("**Optionee**").

WHEREAS:

(A) Optionors own the water rights and related property described in Schedule A (the "**Water Rights**");

(B) Optionors wish to grant Optionee the exclusive Option (as defined in Section 1.1) to acquire the Water Rights on the terms and conditions set forth in this Agreement; and

(C) Optionee wishes to be granted the exclusive Option to acquire the Water Rights on such terms and conditions.

NOW, THEREFORE, for and in consideration of the sum of [redacted] paid by Optionee to Optionors (which is consideration for this Agreement and not consideration for the grant of the Option) and for other good and valuable consideration (for this Agreement and not for the grant of the Option), the receipt and sufficiency of which consideration is hereby acknowledged by each Party, the Parties agree as follows:

ARTICLE 1
INTERPRETATION

Section 1.1 Definitions

When used in this Agreement, except as otherwise defined herein, the following bold-faced words and phrases shall have the indicated meanings:

Affiliate means any individual, partnership, joint venture, corporation, limited liability company or other form of entity or enterprise that directly or indirectly controls, is controlled by, or is under common control with, a Party. For purposes of the preceding sentence, "control" means possession, directly or indirectly, of the power to direct or cause direction of management through ownership of voting securities, contract, voting trust or otherwise.

Business Day means a day on which commercial banks are open for business in Albuquerque, New Mexico.

Data means all information and materials in the possession of or reasonably available to a Party relating to the Water Rights.

Encumbrance means any mortgage, charge, pledge, hypothecation, security interest, assignment, option, right of first refusal, right of first offer, statutory or other lien, charge, title retention agreement or arrangement, royalty, restrictive covenant or other encumbrance of any nature.

Force Majeure means any cause beyond a Party's control, including acts of God; fire; flood; explosion; strike, lockout or other labor disturbance; terrorist act; military or paramilitary act or order; law, rule, regulation, decree or order of any court or governmental authority; failure of any governmental authority to issue any permit, approval or consent reasonably required for the commercial operation of the Copper Flat Mine (the "**Mine**"); non-availability of materials or transportation; or protests, demonstrations or other activities by environmental activists or other protesters delaying or interfering with exploration, development or mining at the Mine.

Option means the exclusive option granted to Optionee pursuant to Section 3.1.

Option Period means the period beginning on the Effective Date and ending (i) when Optionee exercises the Option pursuant to Section 3.2 or (ii) upon the termination hereof pursuant to Section 3.3, Section 3.4, or otherwise.

Parties means Optionors and Optionee.

Party means Optionors or Optionee.

Section 1.2 Gender and Number

This Agreement will be read with such changes in gender and number as the context requires.

Section 1.3 Headings

The headings of the Articles and Sections hereof and of the Schedules hereto are inserted for convenience only and are not intended to affect the construction or interpretation hereof.

Section 1.4 References

Any reference herein to a numbered or lettered Article, Section or Schedule refers to the Article or Section or Schedule hereto bearing that number or letter. The words "this Agreement", "hereby," "herein," "hereof," "hereto," "hereunder," "herewith," and words of similar meaning mean this entire Agreement and the Schedules, together with any modification and amendments hereof and thereof. Any reference to laws, rules, regulations, permits, licenses, certificates, judgments, injunctions, orders, writs or decrees (separately and collectively, "Laws") shall include all amendments and modifications thereof and replacements therefor. The word "including" shall be deemed to be followed by "but not limited to."

Section 1.5 Currency

All dollar amounts expressed herein refer to the lawful currency of the United States of America.

Section 1.6 Schedules

Schedule A ("The Water Rights"), Schedule B ("Adverse Claims to Water Rights"), Schedule C ("Optionors' Deed"), Schedule D ("Optionee's Deed"), Schedule E ("Memorandum of Agreement"), and Schedule F ("Release of Memorandum of Agreement"), are attached hereto and incorporated herein by reference.

Section 1.7 Governing Law

This Agreement shall be governed by and construed according to the law of New Mexico applicable to contracts made in and relating to water rights in New Mexico.

Section 1.8 Severability

If any provision hereof is or becomes illegal, invalid or unenforceable, in whole or in part, the remaining provisions will (i) nevertheless be and remain valid and subsisting and (ii) be construed as if this Agreement did not contain the illegal, invalid or unenforceable provision.

Section 1.10 Payments to Optionors

All payments to be made hereunder by Optionee to Optionors shall be paid one-half to Frost and one-half to Gray, or as otherwise directed in a writing duly executed by Frost and Gray.

ARTICLE 2

REPRESENTATIONS AND WARRANTIES

Section 2.1 Optionee's Representations and Warranties

Optionee represents and warrants to Optionors that:

(a) it is a corporation duly incorporated and validly subsisting under the laws of New Mexico;

(b) it has full corporate power and authority to enter into this Agreement and perform its obligations hereunder;

(c) neither its execution, delivery or performance hereof nor the consummation of the transactions contemplated hereby will conflict with, result in a violation or breach of or accelerate any performance required by, any Laws or by any agreement, indenture, lease or other instrument to which it is a party or by which it is bound;

(d) the execution, delivery and performance hereof do not violate any of its organizational documents;

(e) all required authorizations have been obtained for its execution, delivery and performance hereof; and

(f) this Agreement constitutes its legal, valid and binding obligation, enforceable against it in accordance with its terms.

Section 2.2 Optionors' Representations and Warranties

Optionors jointly and severally represent and warrant to Optionee that:

(a) he or she is fully qualified and competent to enter into this Agreement and perform his or her obligations hereunder;

(b) neither his or her execution, delivery or performance hereof nor his or her consummation of the transactions contemplated hereby will conflict with, result in a violation or breach of or accelerate any performance required by, any Laws or by any agreement, indenture, lease or other instrument to which he or she is a party or by which he or she is bound;

(c) no third-party authorizations are for his or her execution, delivery and performance hereof;

(d) the Water Rights are all of the Water Rights with points of diversion and/or places of use in Sierra County owned by the Optionors;

(e) they are the sole owners of and are vested with good and merchantable fee simple title to the Water Rights, free from all Encumbrances, and have no knowledge of any action on the part of the State Engineer or otherwise to declare any part of the Water Rights forfeited or abandoned;

(f) they collectively have the exclusive right to enter into this Agreement and all necessary rights and authority to transfer the Water Rights to Optionee in accordance with the terms and conditions hereof;

(g) they have the exclusive rights to receive all amounts that might be paid by Optionee pursuant to Section 3.2;

(h) except as set forth in Schedule B, there are no actual or pending, or to their actual knowledge alleged, threatened or potential, adverse claims, challenges, suits, actions, prosecutions, investigations or proceedings affecting or relating to the Water Rights or any portion thereof that, individually or in the aggregate and directly or indirectly, could at any time adversely affect (A) Optionors' ability to perform each of their obligations hereunder, (B) the correctness of each of their representations and warranties hereunder, or (C) the validity of, title to, quantity or priority of, or authorized points of diversion and/or places of use and/or purposes of use of, the Water Rights; and

(i) this Agreement constitutes his or her legal, valid and binding obligation, enforceable against him or her in accordance with its terms.

Section 2.3 Survival of Representations and Warranties

The representations and warranties set forth in this Article 2 shall survive the Option Period and the acquisition of the Water Rights by Optionee.

ARTICLE 3
OPTION AND PURCHASE

Section 3.1 Grant of Option

For and in consideration of and upon and subject to the terms and conditions hereof and Optionee's payment of [redacted] to Optionors (as consideration for the grant by Optionors of the Option and not as an Option payment), Optionors hereby grant to Optionee the sole and exclusive right and option (the "**Option**"), to acquire the Water Rights in accordance herewith, free and clear of all Encumbrances.

Section 3.2 Exercise of Option

To exercise the Option, shall make, in cash, the non-refundable Option payments set forth in this Section 3.2 on or before the dates indicated (or such later dates as may be applicable pursuant to Article 6):

Amount	On or Before:
$200,000	the written acknowledgment by the Office of the New Mexico State Engineer of the filing by Optionor of amended declarations, with appropriate supporting documents, for the Water Rights based upon the use of approximately 1,900 acre feet of water in prior operations at the Mine.
$300,000	September 30, 2010
$1,000,000	February 14, 2011, when the final option payment is due under the Option and Purchase Agreement dated July 23, 2009 by and between Optionee and Hydro Resources Corporation, et al., unless the due date for said payment is deferred pursuant to said Option and Purchase Agreement to May 16, 2011, in which case the due date for payment pursuant hereto by Optionee to Optionors of said [redacted] shall also be deferred to on or before May 16, 2011.
$700,000	Within 60 days after the Mining and Minerals Division of the New Mexico Energy, Minerals and Natural Resources Department issues a permit for the commercial operation of the Mine or August 1, 2018, whichever occurs first.

Optionee shall provide semi-annual progress reports to Optionee regarding its progress in obtaining a permit for the commercial operation of the Mine from the Mining and Minerals Division of the New Mexico Energy, Minerals and Natural Resources Department.

In no event shall Optionee be obligated to make any Option payment provided for in this Section 3.2. However, if Optionee timely makes each Option payment provided for in this Section 3.2, (i) Optionee shall have exercised the Option and (ii) Optionors shall transfer and convey the Water Rights to Optionee pursuant to Section 4.2.

Section 3.3 Optionee's Election to Terminate

Optionee may elect at any time prior to exercising the Option to terminate the Option, this Agreement, and its rights and further obligations hereunder except those set forth in Section 3.5, by delivering a written notice of termination to Optionors.

Section 3.4 Optionors' Election to Terminate

If Optionee fails timely to make any Option payment provided for in Section 3.2, Optionors may elect to give Optionee written notice of their intent to terminate the Option and this Agreement. Unless Optionee thereafter pays Optionors the full amount of such Option payment within ten days after its receipt of such notice, Optionors may terminate the Option and this Agreement and their rights and further obligations hereunder by delivering written notice of termination to Optionee. Upon such delivery, the Option will be of no further force and effect, the Option and this Agreement will terminate, and Optionee will acquire no interest in the Water Rights and neither Party will have further rights or obligations hereunder except those set forth in Section 3.5.

Section 3.5 Rights and Obligations Upon Termination

Upon termination hereof pursuant to Section 3.3 or Section 3.4, (i) Optionors shall be entitled to retain all amounts theretofore paid to Optionors and (ii) Optionee shall return to Optionors all Data previously delivered by Optionors to Optionee. In addition, (i) Rodey, Dickason, Sloan, Akin & Robb, P.A. (the "**Rodey Firm**") shall promptly at the request of Optionors return to Optionors all documents held by it in escrow pursuant to Section 4.2 and (ii) Optionee shall promptly execute and deliver to Optionors such further documents as may necessary or desirable, in Optionors' commercially reasonable opinion, to eliminate Optionee's interest, if any, in the Water Rights and to return the Water Rights to Optionors free and clear of Encumbrances voluntarily or involuntarily created by Optionee's act or failure to act. The respective obligations set forth in this Section 3.5 shall survive termination.

ARTICLE 4
OPTION PERIOD RIGHTS AND OBLIGATIONS; DEFAULT

Section 4.1 Optionee's Rights to Test and Evaluate

During the Option Period, Optionee and its officers, employees, agents and independent contractors may test and evaluate the availability, quality and other characteristics of the water associated with the Water Rights, subject to any requirements and restrictions existing under applicable Laws. Optionee acknowledges that its option to acquire the Water Rights is based on Optionee's own review, investigation, and inspection. The acceptance by the State Engineer Office of the amended declarations does not constitute validation of the right claimed. Except as expressly stated in this Agreement, nothing herein constitutes a warranty, express or implied, of the validity of the water rights or their fitness for a particular purpose.

Section 4.2 Transfer Documents

Forthwith upon the execution hereof by both Parties, (i) Optionors shall execute a special warranty deed in the form attached hereto as Schedule C ("**Optionors' Deed**") transferring and conveying the Water Rights to Optionee, (ii) Optionee shall execute a

special warranty deed in the form attached hereto as Schedule D ("**Optionee's Deed**") retransferring and reconveying the Water Rights to Optionors, and (iii) both Parties shall execute a Memorandum of Agreement in the form attached hereto as Schedule E (the "**Memorandum**") and a Release of Memorandum of Agreement (the "**Release**") in the form attached hereto as Schedule F.

The Optionors' Deed, the Optionee's Deed, and the Release shall be deposited with and held in escrow in accordance with the terms hereof by the Rodey Firm, whose address is 315 Paseo de Peralta, Santa Fe, New Mexico 87501 (Attention: Mark K. Adams). The Memorandum shall also be delivered to the Rodey Firm, which shall promptly record it in Sierra County, New Mexico ("**Sierra County**").

If this Agreement terminates pursuant to Section 3.3 or Section 3.4, the Parties shall instruct the Rodey Firm to promptly (i) file the Release for record in Sierra County and (ii) deliver the Optionors' Deed and the Optionee's Deed to Optionors.

If Optionee exercises the Option in accordance with this Agreement, (i) title to the Water Rights shall vest in Optionee, (ii) the Rodey Firm shall promptly file the Optionors' Deed for record in Sierra County, and (iii) should there be any Encumbrance on the Water Rights which has been incurred voluntarily or involuntarily by Optionors, Optionors shall promptly remove the same at their expense.

Section 4.3 Optionors' Obligations During Option Period

Optionors shall during the Option Period:

(a) make all Data in their possession or readily available to them available to Optionee in Albuquerque, New Mexico;

(b) file amended declarations with the New Mexico Office of the State Engineer, with appropriate supporting documents, for the Water Rights based upon the use of approximately 1,900 acre feet of water in prior operations at the Mine;

(c) not grant, convey, transfer, offer, lease, make or suffer any Encumbrance, or make any other arrangement or agreement or attempt to make any other arrangement or agreement relating in any way to the Water Rights that could adversely affect the rights of Optionee hereunder to (i) exercise the Option and (ii) become absolutely vested with title to the Water Rights, free and clear of all Encumbrances (and any such grant, conveyance, transfer, offer, lease, Encumbrance, arrangement, or agreement, and any such attempted arrangement or agreement, shall be void and without effect;

(d) take all commercially reasonable steps to keep the Water Rights in good standing and in full force and effect and refrain from doing anything to jeopardize the good standing and effectiveness of the Water Rights;

(e) not cause waste of or damage to the Water Rights; and

(f) promptly notify Optionee in writing if any of Optionors' representations and warranties set forth in Section 2.2 becomes untrue or incorrect in any material respect.

Section 4.4 Optionee's Obligation During Option Period

Optionee shall during the Option Period:

(a) not cause waste of or damage to the Water Rights;

(b) take all commercially reasonable steps (i) to keep the Water Rights free and clear of Encumbrances arising from its activities and (ii) to proceed with diligence to contest and discharge any such Encumbrance; and

(c) promptly notify Optionors in writing if any of Optionee's representations and warranties set forth in Section 2.1 becomes untrue or incorrect in any material respect.

Section 4.5 Default

(a) **By Optionor.** If (i) any of Optionors' representations and warranties set forth in Section 2.2 is at any time untrue or incorrect in any material respect or (ii) Optionors fail in any material respect to perform any of their obligations hereunder (unless Optionors' failure is due to the failure of Optionee to perform any of its obligations hereunder), after ten (10) Business Days' notice from Optionee, Optionee may elect to initiate an action for specific performance and/or to recover its actual and reasonable out-of-pocket damages resulting from Optionors' default. Optionee hereby waives any right to seek or recover consequential or punitive damages and damages for lost profits. Optionors acknowledge that the Water Rights are unique and that, accordingly, it would be equitable for any court of competent jurisdiction to order the specific performance by Optionors of Optionors' obligations hereunder.

(b) **By Optionee.** If (i) any of Optionee's representations and warranties set forth in Section 2.1 is at any time untrue or incorrect in any material respect or (ii) Optionee fails in any material respect to perform any of its obligations hereunder (unless Optionee's failure is due to the failure of Optionors to perform any of their obligations hereunder), after ten (10) Business Days' notice from Optionors, Optionors may elect to initiate an

action to recover their actual and reasonable out-of-pocket damages resulting from Optionee's default. Optionors hereby waive any right to seek or recover consequential or punitive damages or damages for lost profits.

ARTICLE 5
TRANSFERS

Section 5.1 Limitations on Transfers

During the Option Period, neither Party may in any way transfer, convey, assign, delegate, mortgage, grant an option in respect of or a right to purchase or in any other manner transfer, alienate or otherwise dispose of (each a "**Transfer**") to any non-Party any or all of its rights, titles, and interests in, to or under the Water Rights or hereunder (collectively, "**Interests**") except in compliance with this Article 5.

Section 5.2 Permitted Transfers

During the Option Period, either Party may Transfer its Interests to a non-Party

(a) if all of its Interests are transferred;

(b) when the transferring Party (the "**Transferring Party**") is not in material default of any of its covenants and agreements hereunder; and

(c) after the Transfer has been approved by the non-transferring Party (the "**Non-Transferring Party**"). If within 30 days after it receives a written request for approval of the Transfer from the Transferring Party, the Non-Transferring Party has not given the Transferring Party written notice of whether it has approved or disapproved the Transfer, the Transfer shall be deemed approved.

Section 5.3 Exceptions

Nothing in this Article 5 applies to or restricts in any manner:

(a) a sale by Optionee of all or a substantial part of its interests in the Copper Flat Project;

(b) a Transfer after the Option Period, except as provided in Section 5.5;

(c) a Transfer to an Affiliate of the Transferring Party; or

(d) a merger, amalgamation or corporate reorganization involving the Transferring Party which has the effect of the surviving entity owning all the property, rights and interests and being subject to all the debts, liabilities and obligations of the predecessor entity.

Section 5.4 Conditions of Transfers

As a condition of any Transfer to a non-Party during the Option Period, the non-Party must agree in writing with the Non-Transferring Party to be bound hereby, including this Article 5.

Section 5.5 Sale of Water Rights

If Optionee (i) exercises the Option and (ii) subsequently sells all or part of the Water Rights after mining and reclamation at the Mine are completed, the first [redacted] in the aggregate of the sale proceeds ("**Proceeds**") shall be distributed to Optionee. If and after Optionee has received [redacted] in the aggregate from Proceeds, one-third of any additional Proceeds shall be distributed to Optionors and two-thirds of any additional Proceeds shall be distributed to Optionee.

ARTICLE 6
FORCE MAJEURE

Section 6.1 Effects of Force Majeure

Notwithstanding any other provision hereof, (i) a Party will not be liable for failure to perform any obligation hereunder when the failure results from an event of Force Majeure and (ii) all time limits hereunder shall be extended by a period equal to the period of delay resulting from the event of Force Majeure.

Section 6.2 Obligation to Eliminate Force Majeure

A Party claiming an event of Force Majeure shall take all commercially reasonable steps to eliminate such event and, if commercially reasonable for it to do so, shall perform its obligations hereunder to the extent practicable, but nothing herein will require a Party to settle or adjust any labor dispute or to question or test the validity of any Laws.

Section 6.3 Giving Notice of Force Majeure

A Party relying upon an event of Force Majeure shall give notice to the other Party forthwith upon the (i) occurrence of the event and (ii) elimination of the event.

ARTICLE 7
CONFIDENTIAL DATA

Section 7.1 Non-Disclosure of Data

During the Option Period and except as specifically otherwise provided in Sections 7.2 and 7.3, neither Party shall disclose any Data except if and to the extent (i) required by Laws or the rules and regulations of any stock exchange, (ii) required or

desirable to protect or enhance the good standing, validity and/or value of the Water Rights, or (iii) the other Party has consented in writing to disclosure.

Section 7.2 Information in Public Domain

The provisions of this Article 7 do not apply to Data which is or becomes part of the public domain other than through a breach hereof.

ARTICLE 8
NOTICE

Section 8.1 Method of Giving Notice

Each notice, consent, demand or other communication (each a "**Notice**") required or permitted to be given hereunder shall be in writing and (i) personally delivered to the party entitled to receive notice or (ii) transmitted by email to the email address set forth in this Section 8.1. A Notice will be deemed to have been given and received, if personally delivered, on the date of delivery and, if given by email, on the date sent, if sent during normal business hours of the recipient on a Business Day, and otherwise on the next Business Day. For the purposes of this Section 8.1, (i) Optionors' email address is harrismgray@yahoo.com and Billfrost4@aol.com, and (ii) Optionee's email address is mKadams@rodey.com.

Section 8.2 Changing Addresses

Either Party may at any time and from time to time notify the other Party in accordance with this Article 8 of a change in its email address or facsimile number to which Notices will be given to it thereafter until further notice in accordance with this Section 8.2.

ARTICLE 9
GENERAL

Section 9.1 Other Activities and Interests

This Agreement and the respective rights and obligations of the Parties are limited to the express terms and provisions hereof and to the Water Rights. Except as otherwise expressly set forth herein, each Party will have the free and unrestricted right to enter into, conduct and benefit from business ventures of any kind whatsoever, whether or not competitive with any activities undertaken pursuant hereto, without disclosing such activities to the other Party or inviting or allowing the other Party to participate.

Section 9.2 Entire Agreement

This Agreement and the Schedules (i) constitute the entire agreement between the Parties relating to the Water Rights and supersede and replace any and all other prior agreements, understandings and arrangements, whether oral or written or express or implied, between the Parties relating to the Water Rights and (ii) may not be supplemented, amended or modified except by a written instrument duly executed and delivered by both Parties.

Section 9.3 No Waiver

No consent hereunder or waiver of or with respect to any breach, default, term, condition, representation, warranty, covenant or agreement hereof or hereunder shall be (i) effective unless it is in writing and duly executed and delivered by the consenting or waiving Party or (ii) deemed or construed to be consent to or a waiver of any other breach, default, term, condition, representation, warranty, covenant or agreement.

Section 9.4 Further Assurances

Each Party will promptly execute and deliver, or cause to be executed and delivered, such documents, deeds, conveyances and other instruments which may be reasonably necessary or advisable to carry out fully the purposes hereof.

Section 9.5 Manner of Payment

All payments to be made pursuant hereto by a Party to the other Party shall be in immediately available funds for the account of the receiving Party at such bank in the United States as the receiving Party may designate from time to time by Notice to the paying Party. Such bank shall be deemed the agent of the receiving Party for the purposes of receiving, collecting and receipting for such payment.

Section 9.6 Inurnment; No Third Party Beneficiaries

This Agreement will inure to the benefit of and be binding upon the Parties and their respective successors and permitted assigns. There are no third party beneficiaries hereof.

Section 9.7 Injunctive Relief

Each of the Parties agrees that its failure to comply with the provisions of Articles 3, 4, 5, or 7 hereof would result in injury and damage to the other Party that would be impossible to measure monetarily. Therefore, in the event of any such failure, the other Party shall, in addition and without prejudice to any other right or remedy that it may have at law or in equity, be entitled to injunctive relief restraining, enjoining the violation of or specifically enforcing such covenants and the provisions of Articles 3, 4,

5, and 7, and each Party hereby waives any defence it may have at law or in equity to such relief.

Section 9.8 Time of the Essence

Time is of the essence in the performance of each obligation hereunder.

Section 9.9 Counterparts and Fax Execution

This Agreement may be executed and delivered (i) in any number of counterparts, all of which taken together shall be deemed one and the same instrument, and (ii) by facsimile and/or by email.

IN WITNESS WHEREOF, this Agreement has been executed on the respective dates set forth below but effective as of the Effective Date.

OPTIONORS

William Frost — Date: Aug. 31, 2010

William Frost

Linda Jo Frost — Date: Aug. 31, 2010

Linda Jo Frost

Harris Gray — Date: Aug 31, 2010

Harris Gray

OPTIONEE

New Mexico Copper Corporation

By: _____ Date: _____, 2010

5, and 7, and each Party hereby waives any defence it may have at law or in equity to such relief.

Section 9.8 Time of the Essence

Time is of the essence in the performance of each obligation hereunder.

Section 9.9 Counterparts and Fax Execution

This Agreement may be executed and delivered (i) in any number of counterparts, all of which taken together shall be deemed one and the same instrument, and (ii) by facsimile and/or by email.

IN WITNESS WHEREOF, this Agreement has been executed on the respective dates set forth below but effective as of the Effective Date.

OPTIONORS

_____ Date: _____, 2010
William Frost

_____ Date: _____, 2010
Linda Jo Frost

_____ Date: _____, 2010
Harris Gray

OPTIONEE

New Mexico Copper Corporation

By: _____ Date: Sept 9, 2010
President

Schedule A

The Water Rights

DESCRIPTION OF WATER RIGHTS

All of Optionors' right, title and interest in and to the following declared water rights, as described in the records of the New Mexico Office of the State Engineer ("OSE"):

OSE File No.	Township, Range, Section	Quarters
LRG-4652	T 15S, R5W, Sec. 30	SW 1/4, SE 1/4, SE 1/4
LRG-4652-S	T 15S, R5W, Sec. 31	NE 1/4, SE 1/4, NE 1/4
LRG-4652-S-2	T 15S, R5W, Sec. 30	SW 1/4, SE 1/4, SW 1/4
LRG-4652-S-3	T 15S, R5W, Sec. 31	NW 1/4, SW 1/4, NE 1/4
LRG-4652-S-11	T 16S, R6W, Sec. 10	SE 1/4, SW 1/4, NW 1/4
LRG-4652-S-12	T 16S, R6W, Sec. 9	NE 1/4, NW 1/4, NW 1/4
LRG-4652-S-13	T 15S, R6W, Sec. 31	SE 1/4, SE 1/4, SE 1/4
LRG-4652-S-14	T 15S, R5W, Sec. 30	NE 1/4, SW 1/4, SE 1/4
LRG-4652-S-15	T 15S, R6W, Sec. 25	SW 1/4, NE 1/4, SE 1/4
LRG-4652-S-16	T 15S, R6W, Sec. 28	SW 1/4, SW 1/4, SE 1/4

title to which water rights was quieted by the Seventh Judicial District Court in Sierra County, New Mexico, in *Hydro Resources Corporation v. Harris Gray and William J. Frost*, Case No. D09721 CV 2001-04. *See* attached Judgment and Quiet Title Decree to Water Rights on Mandate attached hereto as Exhibit "A-1."

STATE OF NEW MEXICO
SEVENTH JUDICIAL
DISTRICT COURT
FILED

2008 JAN 22 AM 8 46

Kathy Enchias
COURT CLERK
BY Lisa Frazier DEPUTY

SEVENTH JUDICIAL DISTRICT
STATE OF NEW MEXICO
COUNTY OF SIERRA

HYDRO RESOURCES CORPORATION, a New Mexico Corporation,

Plaintiff,

v.

NO. D-0721 CV 2001-04

HARRIS GRAY and WILLIAM J. FROST, Individuals,

Defendants.

JUDGMENT AND QUIET TITLE
DECREE TO WATER RIGHTS ON MANDATE

THIS MATTER having been remanded from the New Mexico Supreme Court in *Hydro Resources Corp. v. Gray*, 2007-NMSC-061, with instructions to quiet title in the disputed water rights in Defendants,

IT IS THEREFORE ORDERED, ADJUDGED AND DECREED that title in the water rights at issue in this case, described more particularly in the attached Ex. "A" is quieted in the name of Defendants, Harris Gray and William J. Frost, as requested in the Counterclaim of Harris Gray and William Frost filed in this action. It is further ordered that the Notice of Lis Pendens filed in this matter on January 8, 2001 be and hereby is removed.

Edmund H. Kase III

Hon. Edmund H. Kase III
District Court Judge

Exhibit "A-1"

Respectfully submitted,

LAW & RESOURCE PLANNING ASSOCIATES,
A Professional Corporation

By: _____

Charles T. DuMars
Christina J. Bruff
Tanya L. Scott
Stephen Curtice
Attorneys for Harris Gray and William Frost
Albuquerque Plaza, 201 Third Street NW, Ste. 1750
Albuquerque, NM 87102
(505) 346-0998

APPROVED AS TO FORM:

Telephonically approved 01/16/08

_____
Mr. Stuart R. Butzier, Esq.
Modrall Sperling Roehl Harris & Sisk PA
P.O. Box 2168
Albuquerque NM 87103-2168
(505) 848-1832

Telephonically approved by Stuart Butzier, 01/16/08

_____
Mr. L. Michael Messina, Esq.
Law Office of L. Michael Messina PA
20 First Plaza NW #306
Albuquerque NM 87102-3352

Telephonically approved by Stuart Butzier, 01/16/08

_____
Ms. Nancy L. Simmons, Esq.
Law Offices of Nancy Simmons
2001 Carlisle Blvd NE #E
Albuquerque NM 87110-4943

Any and all right, title and interest in and to inchoate and beneficially used water rights as such rights are specified in the New Mexico Office of the State Engineer and relating to certain real property all as described below:

SEO FILE	SUBDIVISION	SECTION	TOWNSHIP	RANGE
LRG-4652	SW/4 SE/4 SE/4	30	15S	5W
LRG-4652-S	NE/4 SE/4 NE/4	31	15S	5W
LRG-4652-S-2	SE/4 SE/4 SW/4	30	15S	5W
LRG-4652-S-3	NW/4 SW/4 NE/4	31	15S	5W
LRG-4652-S-11	SE/4 SW/4 NW/4	10	16S	6W
LRG-4652-S-12	NE/4 NW/4 NW/4	9	16S	6W
LRG-4652-S-13	SE/4 SE/4 SE/4	31	15S	6W
LRG-4652-S-14	NE/4 SE/4 SE/4	30	15S	5W
LRG-4652-S-15	SW/4 NE/4 SE/4	25	15S	6W
LRG-4652-S-16	SW/4 SW/4 SE/4	28	1S	6W

RECEIVED
2003 ... 22 PM 4 11
STATE ... E
LAS CRUCES, NEW MEXICO

EXHIBIT A

006

Schedule B

Adverse Claims to the Water Rights

None

Schedule C

Optionors' Deed

SPECIAL WARRANTY DEED

Water Rights and Related Property

William Frost and **Linda Jo Frost**, husband and wife, and **Harris Gray**, a single man, for consideration paid, grant to **New Mexico Copper Corporation**, a New Mexico corporation, whose address is 2425 San Pedro NE, Albuquerque, New Mexico 87110, with special warranty covenants, the water rights and related property more particularly described in **Schedule A** attached hereto and incorporated herein by reference, which water rights have points of diversion and places of use in Sierra County, New Mexico.

Witness their hands and seals this _____ day of August, 2010.

_____ _____

William Frost Linda Jo Frost

_____

Harris Gray

***

State of New Mexico)
)ss
County of _____)

The foregoing instrument was acknowledged before me on August ___, 2010 by William Frost and Linda Jo Frost, husband and wife.

SEAL

_____

Notary Public

My Commission Expires:_____

***

State of New Mexico)
)ss
County of _____)

The foregoing instrument was acknowledged before me on August ___, 2010 by Harris Gray, a single man.

SEAL

_____

Notary Public

My Commission Expires: _____

NM

Schedule A

DESCRIPTION OF WATER RIGHTS

All of Optionors' right, title and interest in and to the following declared water rights, as described in the records of the New Mexico Office of the State Engineer ("OSE"):

OSE File No.	Township, Range, Section	Quarters
LRG-4652	T 15S, R5W, Sec. 30	SW 1/4, SE 1/4, SE 1/4
LRG-4652-S	T 15S, R5W, Sec. 31	NE 1/4, SE 1/4, NE 1/4
LRG-4652-S-2	T 15S, R5W, Sec. 30	SW 1/4, SE 1/4, SW 1/4
LRG-4652-S-3	T 15S, R5W, Sec. 31	NW 1/4, SW 1/4, NE 1/4
LRG-4652-S-11	T 16S, R6W, Sec. 10	SE 1/4, SW 1/4, NW 1/4
LRG-4652-S-12	T 16S, R6W, Sec. 9	NE 1/4, NW 1/4, NW 1/4
LRG-4652-S-13	T 15S, R6W, Sec. 31	SE 1/4, SE 1/4, SE 1/4
LRG-4652-S-14	T 15S, R5W, Sec. 30	NE 1/4, SW 1/4, SE 1/4
LRG-4652-S-15	T 15S, R6W, Sec. 25	SW 1/4, NE 1/4, SE 1/4
LRG-4652-S-16	T 15S, R6W, Sec. 28	SW 1/4, SW 1/4, SE 1/4

title to which water rights was quieted by the Seventh Judicial District Court in Sierra County, New Mexico, in *Hydro Resources Corporation v. Harris Gray and William J. Frost*, Case No. D09721 CV 2001-04. *See* attached Judgment and Quiet Title Decree to Water Rights on Mandate attached hereto as Exhibit "A-1."

STATE OF NEW MEXICO
SEVENTH JUDICIAL
DISTRICT COURT
FILED

2008 JAN 22 AM 8 46

Kathy Enchias
COURT CLERK
BY Lisa Frazier DEPUTY

SEVENTH JUDICIAL DISTRICT
STATE OF NEW MEXICO
COUNTY OF SIERRA

HYDRO RESOURCES CORPORATION, a New Mexico Corporation,

Plaintiff,

v.

NO. D-0721 CV 2001-04

HARRIS GRAY and WILLIAM J. FROST, Individuals,

Defendants.

JUDGMENT AND QUIET TITLE
DECREE TO WATER RIGHTS ON MANDATE

THIS MATTER having been remanded from the New Mexico Supreme Court in *Hydro Resources Corp. v. Gray*, 2007-NMSC-061, with instructions to quiet title in the disputed water rights in Defendants,

IT IS THEREFORE ORDERED, ADJUDGED AND DECREED that title in the water rights at issue in this case, described more particularly in the attached Ex. "A" is quieted in the name of Defendants, Harris Gray and William J. Frost, as requested in the Counterclaim of Harris Gray and William Frost filed in this action. It is further ordered that the Notice of Lis Pendens filed in this matter on January 8, 2001 be and hereby is removed.

Edmund H. Kase III

Hon. Edmund H. Kase III
District Court Judge

Respectfully submitted,

LAW & RESOURCE PLANNING ASSOCIATES,
A Professional Corporation

By: _____

Charles T. DuMars
Christina J. Bruff
Tanya L. Scott
Stephen Curtice
Attorneys for Harris Gray and William Frost
Albuquerque Plaza, 201 Third Street NW, Ste. 1750
Albuquerque, NM 87102
(505) 346-0998

APPROVED AS TO FORM:

Telephonically approved 01/16/08

_____

Mr. Stuart R. Butzier, Esq.
Modrall Sperling Roehl Harris & Sisk PA
P.O. Box 2168
Albuquerque NM 87103-2168
(505) 848-1832

Telephonically approved by Stuart Butzier, 01/16/08

_____

Mr. L. Michael Messina, Esq.
Law Office of L. Michael Messina PA
20 First Plaza NW #306
Albuquerque NM 87102-3352

Telephonically approved by Stuart Butzier, 01/16/08

_____

Ms. Nancy L. Simmons, Esq.
Law Offices of Nancy Simmons
2001 Carlisle Blvd NE #E
Albuquerque NM 87110-4943

Any and all right, title and interest in and to inchoate and beneficially used water rights as such rights are specified in the New Mexico Office of the State Engineer and relating to certain real property all as described below:

SEO FILE	SUBDIVISION	SECTION	TOWNSHIP	RANGE
LRG-4652	SW/4 SE/4 SE/4	30	15S	5W
LRG-4652-S	NE/4 SE/4 NE/4	31	15S	5W
LRG-4652-S-2	SE/4 SE/4 SW/4	30	15S	5W
LRG-4652-S-3	NW/4 SW/4 NE/4	31	15S	5W
LRG-4652-S-11	SE/4 SW/4 NW/4	10	16S	6W
LRG-4652-S-12	NE/4 NW/4 NW/4	9	16S	6W
LRG-4652-S-13	SE/4 SE/4 SE/4	31	15S	6W
LRG-4652-S-14	NE/4 SE/4 SE/4	30	15S	5W
LRG-4652-S-15	SW/4 NE/4 SE/4	25	15S	6W
LRG-4652-S-16	SW/4 SW/4 SE/4	28	1S	6W

RECEIVED
2003 JUL 22 PM 4:11
STATE ENGINEER
LAS CRUCES, NEW MEXICO

EXHIBIT A

006

Schedule D

Optionee's Deed

SPECIAL WARRANTY DEED

Water Rights and Related Property

New Mexico Copper Corporation, a New Mexico corporation, for consideration paid, grants to **William Frost and Linda Jo Frost**, husband and wife, and **Harris Gray,** a single man, whose address is 1109 West Taylor Road, Las Cruces, NM 88005, with special warranty covenants, New Mexico, the water rights and related property more particularly described in **Schedule A** attached hereto and incorporated herein by reference, which water rights have points of diversion and places of use in Sierra County, New Mexico.

Witness its hand and seal this ___ day of August, 2010.

New Mexico Copper Corporation

By:_____
Barrett E. G. Sleeman, its President

***

State of _____)
)ss
County of _____)

The foregoing instrument was acknowledged before me on August ___, 2010 by Barrett E. G. Sleeman, as President of New Mexico Copper Corporation, a New Mexico corporation.

SEAL

_____
NOTARY PUBLIC

My Commission Expires:_____

Schedule A

DESCRIPTION OF WATER RIGHTS

All of Optionors' right, title and interest in and to the following declared water rights, as described in the records of the New Mexico Office of the State Engineer ("OSE"):

OSE File No.	Township, Range, Section	Quarters
LRG-4652	T 15S, R5W, Sec. 30	SW 1/4, SE 1/4, SE 1/4
LRG-4652-S	T 15S, R5W, Sec. 31	NE 1/4, SE 1/4, NE 1/4
LRG-4652-S-2	T 15S, R5W, Sec. 30	SW 1/4, SE 1/4, SW 1/4
LRG-4652-S-3	T 15S, R5W, Sec. 31	NW 1/4, SW 1/4, NE 1/4
LRG-4652-S-11	T 16S, R6W, Sec. 10	SE 1/4, SW 1/4, NW 1/4
LRG-4652-S-12	T 16S, R6W, Sec. 9	NE 1/4, NW 1/4, NW 1/4
LRG-4652-S-13	T 15S, R6W, Sec. 31	SE 1/4, SE 1/4, SE 1/4
LRG-4652-S-14	T 15S, R5W, Sec. 30	NE 1/4, SW 1/4, SE 1/4
LRG-4652-S-15	T 15S, R6W, Sec. 25	SW 1/4, NE 1/4, SE 1/4
LRG-4652-S-16	T 15S, R6W, Sec. 28	SW 1/4, SW 1/4, SE 1/4

title to which water rights was quieted by the Seventh Judicial District Court in Sierra County, New Mexico, in *Hydro Resources Corporation v. Harris Gray and William J. Frost*, Case No. D09721 CV 2001-04. *See* attached Judgment and Quiet Title Decree to Water Rights on Mandate attached hereto as Exhibit "A-1."

STATE OF NEW MEXICO
SEVENTH JUDICIAL
DISTRICT COURT
FILED

2008 JAN 22 AM 8 46

Kathy Enckias
COURT CLERK
BY Lisa Frazier DEPUTY

SEVENTH JUDICIAL DISTRICT
STATE OF NEW MEXICO
COUNTY OF SIERRA

HYDRO RESOURCES CORPORATION, a New Mexico Corporation,

Plaintiff,

v.

NO. D-0721 CV 2001-04

HARRIS GRAY and WILLIAM J. FROST, Individuals,

Defendants.

JUDGMENT AND QUIET TITLE
DECREE TO WATER RIGHTS ON MANDATE

THIS MATTER having been remanded from the New Mexico Supreme Court in *Hydro Resources Corp. v. Gray*, 2007-NMSC-061, with instructions to quiet title in the disputed water rights in Defendants,

IT IS THEREFORE ORDERED, ADJUDGED AND DECREED that title in the water rights at issue in this case, described more particularly in the attached Ex. "A" is quieted in the name of Defendants, Harris Gray and William J. Frost, as requested in the Counterclaim of Harris Gray and William Frost filed in this action. It is further ordered that the Notice of Lis Pendens filed in this matter on January 8, 2001 be and hereby is removed.

Edmund H. Kase III

Hon. Edmund H. Kase III
District Court Judge

Respectfully submitted,

LAW & RESOURCE PLANNING ASSOCIATES,
A Professional Corporation

By: _____

Charles T. DuMars
Christina J. Bruff
Tanya L. Scott
Stephen Curtice
Attorneys for Harris Gray and William Frost
Albuquerque Plaza, 201 Third Street NW, Ste. 1750
Albuquerque, NM 87102
(505) 346-0998

APPROVED AS TO FORM:

Telephonically approved 01/16/08

Mr. Stuart R. Butzier, Esq.
Modrall Sperling Roehl Harris & Sisk PA
P.O. Box 2168
Albuquerque NM 87103-2168
(505) 848-1832

Telephonically approved by Stuart Butzier, 01/16/08

Mr. L. Michael Messina, Esq.
Law Office of L. Michael Messina PA
20 First Plaza NW #306
Albuquerque NM 87102-3352

Telephonically approved by Stuart Butzier, 01/16/08

Ms. Nancy L. Simmons, Esq.
Law Offices of Nancy Simmons
2001 Carlisle Blvd NE #E
Albuquerque NM 87110-4943

Any and all right, title and interest in and to inchoate and beneficially used water rights as such rights are specified in the New Mexico Office of the State Engineer and relating to certain real property all as described below:

SEO FILE	SUBDIVISION	SECTION	TOWNSHIP	RANGE
LRG-4652	SW/4 SE/4 SE/4	30	15S	5W
LRG-4652-S	NE/4 SE/4 NE/4	31	15S	5W
LRG-4652-S-2	SE/4 SE/4 SW/4	30	15S	5W
LRG-4652-S-3	NW/4 SW/4 NE/4	31	15S	5W
LRG-4652-S-11	SE/4 SW/4 NW/4	10	16S	6W
LRG-4652-S-12	NE/4 NW/4 NW/4	9	16S	6W
LRG-4652-S-13	SE/4 SE/4 SE/4	31	15S	6W
LRG-4652-S-14	NE/4 SE/4 SE/4	30	15S	5W
LRG-4652-S-15	SW/4 NE/4 SE/4	25	15S	6W
LRG-4652-S-16	SW/4 SW/4 SE/4	28	1S	6W

RECEIVED
2003 JUL 22 PM 4:11
LAS CRUCES, NEW MEXICO

EXHIBIT A

006

Schedule E

Memorandum of Agreement

Memorandum of Agreement

THIS MEMORANDUM of AGREEMENT relates to the Option and Purchase Agreement (the "Agreement") effective as of August ___, 2010 by and between **New Mexico Copper Corporation**, a New Mexico corporation ("Optionee"), and **William Frost** and **Linda Jo Frost**, husband and wife, and **Harris Gray**, a single man (separately and collectively, "Optionors").

1. For and in consideration of [redacted] paid by Optionee to Optionors and other good and valuable consideration, Optionors agreed in the Agreement to grant Optionee the sole and exclusive right and option described in the Agreement (the "Option") to acquire the Water Rights with points of diversion and places of use in Sierra County, New Mexico and related property described in Schedule A to the Agreement and in Schedule A hereto.

2. Upon the exercise of the Option by Optionee pursuant to and in accordance with the Agreement, the Water Rights shall be transferred and conveyed by Optionors to Optionee, free and clear of all Encumbrances. If Optionee fails to so exercise the Option, the Water Rights shall remain the property of Optionor.

3. Optionee has an office at 315 Paseo de Peralta, Santa Fe, New Mexico 87501. Additional information about the Agreement may be obtained from Optionee at such office.

4. This Memorandum has been executed for the purpose of recording in the records of Sierra County, New Mexico and filing in the records of the New Mexico State Engineer to give notice of the Agreement. This Memorandum does not in any way modify, supplement or abridge the Agreement or any of its provisions, as the same are now or may hereafter be in force and effect.

IN WITNESS WHEREOF, Optionors and Optionee have duly executed and delivered this Memorandum of Agreement.

Optionee

New Mexico Copper Corporation

By: _____
Barrett E. G. Sleeman, it President

Optionors

_____

_____

_____

State of _____)
) ss
County of _____)

The foregoing instrument was acknowledged before me on August _____, 2010 by Barrett E. G. Sleeman, as President of New Mexico Copper Corporation, a New Mexico corporation.

_____
Notary Public

My Commission expires: _____

State of New Mexico)
) ss
County of _____)

The foregoing instrument was acknowledged before me on August ___, 2010 by William Frost and Linda Jo Frost, husband and wife.

_____
Notary Public

My Commission expires: _____

State of New Mexico)
) ss
County of _____)

The foregoing instrument was acknowledged before me on August ___, 2010 by Harris Gray, a single man.

_____
Notary Public

My Commission expires: _____

&

DESCRIPTION OF WATER RIGHTS

All of Optionors' right, title and interest in and to the following declared water rights, as described in the records of the New Mexico Office of the State Engineer ("OSE"):

OSE File No.	Township, Range, Section	Quarters
LRG-4652	T 15S, R5W, Sec. 30	SW 1/4, SE 1/4, SE 1/4
LRG-4652-S	T 15S, R5W, Sec. 31	NE 1/4, SE 1/4, NE 1/4
LRG-4652-S-2	T 15S, R5W, Sec. 30	SW 1/4, SE 1/4, SW 1/4
LRG-4652-S-3	T 15S, R5W, Sec. 31	NW 1/4, SW 1/4, NE 1/4
LRG-4652-S-11	T 16S, R6W, Sec. 10	SE 1/4, SW 1/4, NW 1/4
LRG-4652-S-12	T 16S, R6W, Sec. 9	NE 1/4, NW 1/4, NW 1/4
LRG-4652-S-13	T 15S, R6W, Sec. 31	SE 1/4, SE 1/4, SE 1/4
LRG-4652-S-14	T 15S, R5W, Sec. 30	NE 1/4, SW 1/4, SE 1/4
LRG-4652-S-15	T 15S, R6W, Sec. 25	SW 1/4, NE 1/4, SE 1/4
LRG-4652-S-16	T 15S, R6W, Sec. 28	SW 1/4, SW 1/4, SE 1/4

title to which water rights was quieted by the Seventh Judicial District Court in Sierra County, New Mexico, in *Hydro Resources Corporation v. Harris Gray and William J. Frost*, Case No. D09721 CV 2001-04. *See* attached Judgment and Quiet Title Decree to Water Rights on Mandate attached hereto as Exhibit "A-1."

STATE OF NEW MEXICO
SEVENTH JUDICIAL
DISTRICT COURT
FILED

2008 JAN 22 AM 8 46

Kathy Encinias
COURT CLERK
BY Lisa Frazier DEPUTY

SEVENTH JUDICIAL DISTRICT
STATE OF NEW MEXICO
COUNTY OF SIERRA

HYDRO RESOURCES CORPORATION, a New Mexico Corporation,

Plaintiff,

v.

NO. D-0721 CV 2001-04

HARRIS GRAY and WILLIAM J. FROST, Individuals,

Defendants.

JUDGMENT AND QUIET TITLE
DECREE TO WATER RIGHTS ON MANDATE

THIS MATTER having been remanded from the New Mexico Supreme Court in *Hydro Resources Corp. v. Gray*, 2007-NMSC-061, with instructions to quiet title in the disputed water rights in Defendants,

IT IS THEREFORE ORDERED, ADJUDGED AND DECREED that title in the water rights at issue in this case, described more particularly in the attached Ex. "A" is quieted in the name of Defendants, Harris Gray and William J. Frost, as requested in the Counterclaim of Harris Gray and William Frost filed in this action. It is further ordered that the Notice of Lis Pendens filed in this matter on January 8, 2001 be and hereby is removed.

Edmund H. Kase III

Hon. Edmund H. Kase III
District Court Judge

CERTIFIED

Respectfully submitted,

LAW & RESOURCE PLANNING ASSOCIATES,
A Professional Corporation

By: _____

Charles T. DuMars
Christina J. Bruff
Tanya L. Scott
Stephen Curtice
Attorneys for Harris Gray and William Frost
Albuquerque Plaza, 201 Third Street NW, Ste. 1750
Albuquerque, NM 87102
(505) 346-0998

APPROVED AS TO FORM:

Telephonically approved 01/16/08

Mr. Stuart R. Butzier, Esq.
Modrall Sperling Roehl Harris & Sisk PA
P.O. Box 2168
Albuquerque NM 87103-2168
(505) 848-1832

Telephonically approved by Stuart Butzier, 01/16/08

Mr. L. Michael Messina, Esq.
Law Office of L. Michael Messina PA
20 First Plaza NW #306
Albuquerque NM 87102-3352

Telephonically approved by Stuart Butzier, 01/16/08

Ms. Nancy L. Simmons, Esq.
Law Offices of Nancy Simmons
2001 Carlisle Blvd NE #E
Albuquerque NM 87110-4943

Any and all right, title and interest in and to inchoate and beneficially used water rights as such rights are specified in the New Mexico Office of the State Engineer and relating to certain real property all as described below:

SEO FILE	SUBDIVISION	SECTION	TOWNSHIP	RANGE
LRG-4652	SW/4 SE/4 SE/4	30	15S	5W
LRG-4652-S	NE/4 SE/4 NE/4	31	15S	5W
LRG-4652-S-2	SE/4 SE/4 SW/4	30	15S	5W
LRG-4652-S-3	NW/4 SW/4 NE/4	31	15S	5W
LRG-4652-S-11	SE/4 SW/4 NW/4	10	16S	6W
LRG-4652-S-12	NE/4 NW/4 NW/4	9	16S	6W
LRG-4652-S-13	SE/4 SE/4 SE/4	31	15S	6W
LRG-4652-S-14	NE/4 SE/4 SE/4	30	15S	5W
LRG-4652-S-15	SW/4 NE/4 SE/4	25	15S	6W
LRG-4652-S-16	SW/4 SW/4 SE/4	28	1S	6W

RECEIVED
2005 [illegible] 22 PM 4:1[illegible]
STATE [illegible]
LAS CRUCES, NEW MEXICO

EXHIBIT A

006

Schedule F

Release of Memorandum of Agreement

Release of Memorandum of Agreement

Effective _____, the undersigned, as Optionee and Optionors, hereby release the Memorandum of Agreement filed for record in Sierra County, New Mexico on _____, 2010 as Document No. _____ and recorded in Book __, at Page __, of the real property records of Sierra County.

IN WITNESS WHEREOF, Optionee and Optionors have duly executed this Release of Memorandum of Agreement.

Optionee	Optionors
New Mexico Copper Corporation	_____
By: _____	_____
Barrett E. G. Sleeman, its President	_____

***

State of _____)
) ss
County of _____)

The foregoing instrument was acknowledged before me on August ___, 2010 by Barrett E. G. Sleeman, as President of New Mexico Copper Corporation, a New Mexico corporation.

_____
Notary Public

My Commission expires: _____

***

State of New Mexico)
) ss
County _____)

The foregoing instrument was acknowledged before me on August ___, 2010 by William Frost and Linda Jo Frost, husband and wife.

_____
Notary Public

My Commission expires: _____

State of New Mexico)
) ss
County of _____)

The foregoing instrument was acknowledged before me on August ___, 2010 by Harris Gray, a single man.

_____
Notary Public

My Commission expires: _____

&

SECOND AMENDMENT OF OPTION and PURCHASE AGREEMENT

THIS SECOND AMENDMENT OF OPTION and PURCHASE AGREEMENT (this "**Second Amendment**") is made effective April 1, 2010 (the "**Second Amendment Effective Date**") by and

BETWEEN:

> **NEW MEXICO COPPER CORPORATION,** a New Mexico corporation, having an office at 315 Paseo de Peralta, Santa Fe, New Mexico 87501, email address: patrickharford@mercatorgold.com, and facsimile number: +44 (0) 20 7929 1015 ("**Optionee**"),

AND:

> **HYDRO RESOURCES CORPORATION,** a New Mexico corporation, and **CU FLAT, LLC,** a New Mexico limited liability company, both having an office at 4011 Mesa Verde NE, Albuquerque, New Mexico 87110, email address: glotspeich@aol.com, and facsimile number: 505-266-2900, and **GCM, INC.,** a New Mexico corporation, having an office at 2219 Vista Larga NE, Albuquerque, New Mexico 87106, email address: lmmessina99@yahoo.com, and facsimile number: 505-243-3329 (collectively, "**Optionor**").

WHEREAS:

(A) Optionor and Optionee are parties to an Option and Purchase Agreement (the "Original Agreement") effective July 23, 2009 pursuant to which Optionee may acquire certain Property;

(B) Optionor and Optionee amended the Original Agreement by a First Amendment of Option and Purchase Agreement ("First Amendment") effective January 20, 2010 (the Original Agreement, as amended by the First Amendment, is herein called the "Option and Purchase Agreement"); and

(C) Optionor and Optionee wish to further amend the Option and Purchase Agreement as expressly provided in this Second Amendment and, except as so expressly provided, for the Option and Purchase Agreement to remain in full force and effect according to its terms.

NOW, THEREFORE, THIS SECOND AMENDMENT WITNESSES that for and in consideration of the sum of [redacted] paid by Optionee to Optionor and other good and valuable consideration, the receipt and sufficiency of which is hereby acknowledged, which

consideration is for this Second Amendment and not for the grant of the Option, Optionee and Optionor agree as follows:

Section 1. Definitions. Each capitalized term used in this Second Amendment and not otherwise defined herein shall have the meaning assigned to such term in the Option and Purchase Agreement.

Section 2. Amendments. The Option and Purchase Agreement is hereby amended by adding to it the following new Section 3.6:

"Section 3.6 Hydro Water Rights.

In the event that Optionee exercises the Option and makes the final payment of [redacted] pursuant to Section 3.2, Hydro shall by special warranty deed ("the **Hydro Water Rights Deed**") convey and transfer to Optionee all rights, titles, interests and claims now or hereafter existing in, to, under, in connection with or relating to New Mexico State Engineer ("**State Engineer**") Files No. LRG-4652-S-4, LRG-4652-S-5, LRG-4652-S-6, LRG-4652-S-7, LRG-4652-S-8, LRG-4652-S-9, LRG-4652-S-10, LRG-4652-S-17, and LRG-4654 and any and all wells, drill holes, casing, tubing, pipes, pumps, pipelines, electric power lines, tanks, easements, right-of-way, and other equipment, facilities, appurtenances, fixtures, and real and personal property associated, used, or useful in connection with any of said rights, titles, interests or claims (collectively, the "**Hydro Water Rights**"). The Hydro Water Rights Deed shall (i) provide that if and when the Hydro Water Rights are no longer necessary in connection with the development, operation, reclamation or closure of the Mine, Optionee shall convey and transfer an undivided 2/3 interest in the Hydro Water Rights to Hydro and an undivided 1/3 interest in the Hydro Water Rights to GCM and (ii) promptly upon execution and delivery be filed for record in the real property records of Sierra County. Optionee, acting as a prudent operator and with due regard to the interests of itself and Optionor, shall apply water produced pursuant to the Hydro Water Rights to beneficial use at the Mine and may from time-to-time apply to the State Engineer for one or more permits to change the points of diversion of any or all of the Hydro Water Rights to one or more wells on the Real Property, the Patented Mining Claims, the Unpatented Claims, or other real property owned or controlled by Optionee. Optionee shall furnish Optionor with copies of data developed by Optionee or otherwise in its possession relating to the Hydro Water Rights. Optionor hereby consents to any such applications and permits. Optionee may not mortgage, pledge or grant a lien or security interest in the Hydro Water Rights."

Section 3. Representations and Warranties. Optionee represents and warrants to Optionor that the representations and warranties by Optionee in Section 2.1 of the Option and Purchase Agreement are true and correct on and as of the Second Amendment Effective Date and apply to this Second Amendment as well as to the Option and Purchase Agreement. Optionor represents and warrants to Optionee that the representations and warranties by Optionor in Section 2.2 of the Option and Purchase Agreement are true and

correct as of the Second Amendment Effective Date and apply to this Second Amendment as well as to the Option and Purchase Agreement.

Section 4. Effectiveness. This Second Amendment is effective as of the Second Amendment Effective Date. Except as expressly set forth in this Second Amendment, the Option and Purchase Agreement remains unchanged and in full force and effect.

Section 5. Counterparts and Fax Execution. This Second Amendment may be executed in any number of counterparts, all of which taken together shall be deemed to constitute one and the same instrument. This Second Amendment may be executed, accepted and delivered by facsimile.

IN WITNESS WHEREOF, this Second Amendment has been executed as of the respective dates set forth below and is effective as of the Second Amendment Effective Date.

New Mexico Copper Corporation

By: _____

Its: President, Patrick A. Harford
Date: April ___, 2010

Hydro Resources Corporation

By: George O Lotspeich

Its: President, George O. Lotspeich
Date: April 1, 2010

Cu Flat, LLC

By: George O Lotspeich

Its: Managing Member, George O. Lotspeich
Date: April 1, 2010

GCM, Inc.

By: L. Michael Messina

Its: President, L. Michael Messina
Date: April 1, 2010

GROUND WATER DISCHARGE PERMIT APPLICATION
PART C: SITE INFORMATION
All Facilities

C-1. **Area Map.** Attach a current area map showing roads and clearly mark the location of your facility.
See Attachment C-1, the Regional Location Map, which is also Figure 1-1 of the PoO

C-2. **Directions to Site.** Provide driving directions to the site from the nearest town or, if located in a town, from an easily identifiable location.

See Attachment C-2, the Regional Location Map, which is also Figure 1-2 of the PoO
The Site can be reached by traveling south 15 miles from Truth or Consequences on Interstate Highway 25, then 12 miles west on New Mexico Highway 152. The Project area lies two miles west-northwest from New Mexico Highway 152. Access to the Site is via Gold Dust Rd/Co. Rd. Bo27.

C-3. **Topographic Map.** Attach a copy of the appropriate US Geological Survey topographic map. You may provide just the relevant portion. USGS maps are available at many outdoor equipment stores or bookstores, from the USGS at www.usgs.gov or 1-888-ASKUSGS, and from commercial websites.

On the map clearly indicate the location of your facility. Also identify the approximate locations of all wells within 1,000 feet of your discharge locations. The Office of the State Engineer has a searchable database of supply wells on its website at www.ose.state.nm.us.

■ USGS map attached with facility location and neighboring wells marked.
See Attachment C-3, the Topographic Maps

C-4. **Flood Potential.** Attach a copy of the latest Federal Emergency Management Agency (FEMA) flood map with your facility's location clearly marked, to the best of your ability. Information about how to obtain this map, formally known as a Flood Insurance Rate Map (FIRM) is available at www.fema.gov, insurance agencies or county government offices. A site specific analysis may be substituted.

■ FEMA map or site-specific analysis attached.
See Attachment C-4, the Flood Potential Map

☐ Previously submitted and still up-to-date. Submittal date(s): _____

C-5. **Soils.** Attach either:

a) A copy of the appropriate Natural Resource Conservation Service (NRCS) soil survey map, with your site clearly identified to the best of your ability. Include the descriptive information for soils associated with the discharge locations. To obtain the map, contact your local NRCS office – there is one in every county.

b) A site-specific assessment showing the soils classifications. This is preferred over the more generalized NRCS surveys.

■ NRCS soil survey or site-specific assessment attached.
See Attachment C-5, the Soil Survey Map

☐ Previously submitted. Submittal date(s): _____

C-6. Geology. Provide information on the geology beneath the site by attaching relevant portions of geologic reports, well logs for on-site or nearby wells, or site specific assessments. A variety of geology publications and resources are available from the New Mexico Bureau of Geology and Mineral Resources at http://geoinfo.nmt.edu or 505-835-5420 (Socorro). Well logs are available from the New Mexico State Engineer's Office at http://www.ose.state.nm.us/.

■ Geologic report attached. ■ Well log(s) attached.

See Section 2.2 of Attachment A-2, the Stage 1 Abatement Plan and

Section 4.2 and Figures 4-1 through 4-4 of Attachment B-1, the PoO

☐ Geologic information previously submitted. Submittal date(s): _____

C-7. Ground Water Hydrology. Ground water hydrology refers to the occurrence, distribution, movement and chemistry of ground water. The ground water hydrology at your site will determine in large part whether your discharge will adversely affect ground water quality. You may need to present detailed information in order to "demonstrate that the Discharge Permit will not result in concentrations in excess of the standards of Section 20.6.2.3103 NMAC or the presence of any toxic pollutant." (20.2.3106.C.7 NMAC)

At a minimum, provide information below on the direction of ground water flow. Ground water may not flow in the same direction as water on the surface of the ground. A monitoring well survey is one of the best methods to determine the direction of ground water flow at a particular site. Such surveys are routinely required for many Discharge Permit locations.

If a survey is not available, check with well drillers, the city water department, staff at the Office of the State Engineer, environmental consultants or other knowledgeable persons in your area. In addition, relevant reports have been published for some areas. See the OSE website at www.ose.state.nm.us or the NMBGMR website at http://geoinfo.nmt.edu.

Direction of ground water flow: **WSW**

If ground water flow shifts seasonally, describe here: _____

Reference: **See Section 2.3 of Attachment A-2, the Stage 1 Abatement Plan and Section 4.4 and Figures 4-7 through 4-12 of Attachment B-1, the PoO**

■ On-site well survey attached. ☐ Previously submitted. Submittal date(s): _____

■ Nearby well survey attached. ☐ Previously submitted. Submittal date(s): _____

☐ Other. Specify: _____

☐ Relevant portion attached.

☐ Previously submitted. Submittal date(s): _____

Attach any additional information available about ground water hydrology at the site.

C-8. Other Permitted Discharge Locations. If applicable, list other locations of wastewater or stormwater discharges on your site that are not described in this application and indicate what permits apply to them. Examples include discharges from small septic systems (covered by Liquid Waste Permits, discharges to surface waters under a NPDES permit, a discharge covered by a separate Discharge Permit, etc. Be sure these other discharge locations are identified on the site map required in Item B-3.

Discharge Type	Permit Identification
(none)	

C-9. **Other Information.** Describe below or attach any additional information to demonstrate that your proposed discharge plan will be protective of ground water quality, public health and property.

Mineral exploration and development drill holes, monitoring, and production wells subject to state regulations would be abandoned in accordance with applicable rules and regulations (NMAC 19.27.4 et seq.). Boreholes would be sealed to prevent cross contamination between aquifers and required shallow seals would be placed to prevent contamination by surface access. Monitoring wells around the tailings impoundment would be maintained until NMCC is released from this requirement by the NMED, MMD, and BLM. These wells would then be plugged and abandoned according to applicable requirements.

Attachment C-1

Project Location Map





NORTH

DESIGN: -	DRAWN: -	REVIEWED: -	
CHECKED: -	APPROVED: -	DATE: 12/2/2010	
FILE NAME PoO_Fig1-01_Location_JQG_20101202			

NEW MEXICO COPPER CORPORATION

COPPER FLAT MINE

PROJECT LOCATION

DRAWING NO. **FIGURE 1-1**	SHEET 1 OF 28	REVISION NO. **A**
JOB NO. **191000-03**		

Path: H:\Copper_Flat\New Mexico Copper Corp\191000_03_Copper_Flat_Permitting\040_Drafting\20101115\PoO_Fig1-01_Location_JQG_20101202.mxd

Attachment C-2

Regional Location Map



Figure 1-2
Regional Location
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\1_introduction\1-1_SiteLocationMap.mxd 07/22/2010

Attachment C-3

Topographic Maps



N

0 3,000 6,000 12,000 18,000

Feet

Legend

- Monitoring Well
- Production Well
- Proposed Mine Permit Boundary

Mine Boundary:
Tom Van Bebber
Projection Information:
-New Mexico State Plane West, NAD 1927

Figure C-3a
USGS Topographic Map
Discharge Permit Application
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Discharge_Permit_Figures\FigC3a_Topo_rev2.mxd 3/28/2011



N

0 750 1,500 3,000 4,500

Feet

Legend

- Domestic Well (OSE WATERS)
- Mining Well (OSE WATERS)
- Stock Well (OSE WATERS)
- Unknown Well (OSE WATERS)
- Monitoring Well
- Proposed Mine Permit Boundary
- Road

INTERA

Mine Boundary:
Tom Van Bebber
Projection Information:
-New Mexico State Plane West, NAD 1927

Figure C-3b
USGS Topographic Map Closeup
Discharge Permit Application
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Discharge_Permit_Figures\FigC3b_CloseTopo_rev2.mxd 3/28/2011

Attachment C-4

Flood Potential Map

ZONE	EXPLANATION
A	Areas of 100-year flood; base flood elevations and flood hazard factors not determined.
A0	Areas of 100-year shallow flooding where depths are between one (1) and three (3) feet; average depths of inundation are shown, but no flood hazard factors are determined.
AH	Areas of 100-year shallow flooding where depths are between one (1) and three (3) feet; base flood elevations are shown, but no flood hazard factors are determined.
A1-A30	Areas of 100-year flood; base flood elevations and flood hazard factors determined.
A99	Areas of 100-year flood to be protected by flood protection system under construction; base flood elevations and flood hazard factors not determined.
B	Areas between limits of the 100-year flood and 500-year flood; or certain areas subject to 100-year flooding with average depths less than one (1) foot or where the contributing drainage area is less than one square mile; or areas protected by levees from the base flood. (Medium shading)
C	Areas of minimal flooding. (No shading)
D	Areas of undetermined, but possible, flood hazards.
V	Areas of 100-year coastal flood with velocity (wave action); base flood elevations and flood hazard factors not determined.
V1-V30	Areas of 100-year coastal flood with velocity (wave action); base flood elevations and flood hazard factors determined.

ZONE C

ZONE A

ZONE A

Grayback Gulch

Wicks Gulch

NM-152 ROUTE 90

R7W R6W

T15S T16S

T015S/R007W

T016S/R007W

27 26 25 30 34 35 36 31 32 3 2 1 6 5

N

0 750 1,500 3,000 4,500

Feet

Map Source: Federal Emergency Management Agency
-Flood Insurance Rate Map #350071 0675B.
Mine Boundary:
-Tom Van Bebber
Projection Information:
-New Mexico State Plane West, NAD 1927

Legend

Road

Proposed Mine Permit Boundary

Figure C-4
Flood Potential Map
Discharge Permit Application
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Discharge_Permit_Figures\FigC4_FIRM.mxd 3/7/2011

Attachment C-5

Soil Survey Map



N

0 750 1,500 3,000 4,500

Feet

Mine Boundary:
Tom Van Bebber
Projection Information:
-New Mexico State Plane West, NAD 1927

Legend

- Road
- Proposed Mine Permit Boundary
- Waste Rock
- Topsoil Stockpile
- Tailings
- Stockpile
- Pit
- Haul Road
- Diversion
- Ancillary
- Access Road

Figure C-5
Soil Survey
Discharge Permit Application
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Discharge_Permit_Figures\FigC5_Soil.mxd 2/24/2011

Stage I Abatement Plan
for the
Copper Flat Mine

March 31, 2011

Prepared for:
New Mexico Copper Corporation

Prepared by:

Submitted to:
Ground Water Quality Bureau
Mining Environmental Compliance Section
New Mexico Environment Department

00401

Table of Contents

List of Figures iii
List of Tables iv
List of Appendices iv
Acronyms and Abbreviations v
1 Introduction 1
1.1 Purpose and Objectives of the Abatement Plan 1
1.2 Abatement Plan Organization 2
2 Site Description 2
2.1 Climate 2
2.2 Geologic Conditions 3
2.3 Hydrologic Conditions 4
2.3.1 Groundwater Hydrology of the Site 4
2.3.2 Aquifer Characteristics in the Permit Area 4
2.3.3 Surface Water Hydrology of the Permit Area 6
3 Site History and Status 7
3.1 Historical Mine Activities 8
3.2 Previous Surface Water Studies 9
3.2.1 Volumetric Flow 9
3.2.2 Water Quality 10
3.3 Previous Pit Lake Studies 11
3.4 Previous Groundwater Studies 12
4 Ongoing Investigation Activities 13
4.1 Surface Water Monitoring 13
4.2 Pit Lake Characterization 14
4.3 Groundwater Monitoring 15
5 Proposed Characterization Activities 17
5.1 Characterization of Tailings Dam Impacts 17
5.1.1 Geology of the Tailings Dam Area 17
5.1.2 Groundwater Impacts in the Tailings Dam Area 19
5.2 Characterization of Potential Impacts of the Pit Lake 19
5.2.1 Pit Lake Hydraulics 19
5.2.2 Wildlife Exposure 20

5.3 Characterization of Acid Rock Drainage 20
5.3.1 Data Review and Material Type Delineation 21
5.3.2 Sample Interval Selection 21
5.3.3 Sample Collection and Field Screening 22
5.3.4 Geochemical Test Work 22
5.3.5 Kinetic Testing Program 23
5.3.6 Data Validation and Compilation 23
5.3.7 Fate and Transport Modeling 23
5.3.8 Surface Water Monitoring Program 24
6 Quality Assurance Project Plan 24
7 Site Health and Safety Plan 24
8 Reporting 25
9 Schedule 25
10 References 26

List of Figures

Figure 1-1 Site Location
Figure 2-1 Regional Surface Geology
Figure 2-2 Schematic Geologic Cross Section (A-A')
Figure 2-3 Geologic Structural Features of the Region
Figure 2-4 Schematic of Groundwater Flow System
Figure 2-5 Water Level Contours
Figure 2-6 Water Level Map of Copper Flat Pit Area
Figure 2-7 Schematic Groundwater Flow Direction in the Vicinity of the Pit Lake
Figure 2-8 Spring and Stream Locations
Figure 2-9 Conceptual Design, Tailings Seepage Control
Figure 2-10 Surface Water Monitoring Locations
Figure 3-1 Proposed Copper Flat Permit Area with Topography
Figure 3-2 Proposed Copper Flat Permit Area with Air Photography
Figure 3-3 Aerial View to the West at Copper Flat Mine, 1982
Figure 3-4 Aerial View to the East at Copper Flat Mine, 1982
Figure 3-5 Bathymetry Map of the Pit Lake
Figure 3-6 Sulfate Concentration in the Mine Pit Lake
Figure 3-7 Total Dissolved Solid Concentrations in the Mine Pit Lake
Figure 3-8 pH in the Mine Pit Lake
Figure 3-9 Spring and Regional Well Locations
Figure 4-1 Historical Groundwater Quality Sampling
Figure 4-2 Surface Water Monitoring Locations
Figure 4-3 2010 Q1 Groundwater Monitoring Locations
Figure 4-4 2010 Q2 Groundwater Monitoring Locations
Figure 4-5 2010 Q3 Groundwater Monitoring Locations
Figure 5-1 Tailings Impoundment Layout
Figure 5-2 NP-3 Sulfate and Total Dissolved Solids
Figure 5-3 NP-4 Sulfate and Total Dissolved Solids
Figure 5-4 NP-2 Sulfate and Total Dissolved Solids
Figure 5-5 Sulfate and TDS Concentration Depth Profiles
Figure 5-6 Actual and Proposed Monitoring Wells
Figure 5-7 GWQ96-22A Sulfate and Total Dissolved Solids
Figure 5-8 GWQ96-22A Metals
Figure 5-9 GWQ96-23A Sulfate and Total Dissolved Solids
Figure 5-10 GWQ96-23A Metals

List of Tables

Table 2-1	Stratigraphy of the Copper Flat Area
Table 3-1	Historical Flow and Water Quality Parameters
Table 4-1	NMWQCC Surface Water Standard Exceedances
Table 4-2	NMWQCC Pit Lake Standard Exceedances
Table 4-3	NMWQCC Groundwater Standard Exceedances
Table 5-1	Proposed Analytical Parameters with Method Reporting Limits

List of Appendices

Appendix A	New Mexico Environment Department Ground Water Quality Bureau Mining Environmental Compliance Section Letters Dated August 20, 2008 and March 18, 2009
Appendix B1	Surface Water Analytical Results
Appendix B2	Pit Lake Analytical Results
Appendix B3	Groundwater Analytical Results
Appendix C	The Natural Defenses of Copper Flat, Sierra County, New Mexico (J.S. Raugust, 2003)
Appendix D	Geologic Logs
Appendix E	Copper Flat Geochemical Characterization Program
Appendix F	Copper Flat Static and Kinetic Geochemical Testwork
Appendix G	Quality Assurance Project Plan
Appendix H	Site Health and Safety Plan

Acronyms and Abbreviations

ABA	Acid Base Accounting
ABC	Adrian Brown Consultants
Air Sciences	Air Sciences Inc.
Alta Gold	Alta Gold Company
amsl	above mean sea level
ARD	acid rock drainage
BLM	U.S. Bureau of Land Management
CFQM	Copper Flat Quartz Monzonite
cfs	cubic feet per second
CRF	chemical release function
EA	environmental assessment
EIS	environmental impact statement
EMNRD	New Mexico Energy, Minerals and Natural Resources Department
°F	degrees Fahrenheit
ft	feet
GIS	geographic information system
gpm	gallons per minute
GWQB	Ground Water Quality Bureau
HSU	hydrostratigraphic unit
lbs	pounds
Ma	million years ago
MECS	Mining Environmental Compliance Section
mg/L	milligrams per liter
MMD	Mining and Minerals Division
MSF	Middle Santa Fe Group hydrostratigraphic unit
Mst	million standard tons
MWMP	Meteoric Water Mobility Procedure
NAG	Net Acid Generation
NMAC	New Mexico Administrative Code
NMCC	New Mexico Copper Corporation
NMED	New Mexico Environment Department
oz	ounce

PFEIS	Preliminary Final Environmental Impact Statement
Quintana	Quintana Minerals Corporation
Rio Gold	Rio Gold Mining Ltd
SAP	Sampling and Analysis Plan
Site	Copper Flat Mine
TDS	total dissolved solids
Tenneco	Tenneco Minerals
USF	Upper Santa Fe Group hydrostratigraphic unit
WETLab	Western Environmental Testing Laboratory
WQCC	New Mexico Water Quality Control Commission

1 Introduction

The New Mexico Copper Corporation (NMCC) is submitting this Stage 1 Abatement Plan for the Copper Flat Mine in response to the New Mexico Environment Department (NMED) Ground Water Quality Bureau (GWQB) Mining Environmental Compliance Section (MECS) letters dated August 20, 2008, and March 18, 2009 (Appendix A). This Stage 1 Abatement Plan was prepared in accordance with the provisions of New Mexico Administrative Code (NMAC) 20.6.2.4103 Abatement Standards and Requirements and relevant regulations, and per discussions with the NMED MECS.

The Copper Flat Mine (Site) is located approximately 20 miles southwest of Truth or Consequences, New Mexico, and approximately 5 miles northeast of Hillsboro, New Mexico (Figure 1-1). The proposed mining operation is located in Sections 30 and 31, Township 15 South, Range 5 West (T15S, R5W); Sections 30 and 31, T15S, R6W; Sections 23 through 27 and 34 through 36, T15S, R7W; Section 6, T16S, R6W; and Section 2, T16S, R7W (all with reference to the New Mexico Principal Meridian) in Sierra County, New Mexico. The mineralized zone is centered at approximately latitude 32.970300, longitude −107.533527.

The Copper Flat properties comprise 3,304.75 acres in contiguous and noncontiguous lands that include patented and unpatented mining claims (lode, placer, and mill site) and fee parcels. The acreage inside the Site permit boundary is 2,190 acres. NMCC will mine copper ore by open pit extraction methods in the area. Molybdenum, gold, and silver will be recovered as byproducts.

The owners of the Copper Flat properties (Hydro Resources Corporation, a New Mexico corporation; Cu Flat, LLC, a New Mexico limited liability company; and GCM, Inc., a New Mexico Corporation) have granted NMCC an exclusive option to acquire the Copper Flat properties per a July 23, 2009 Option and Purchase Agreement, as amended. NMCC is a wholly owned subsidiary of THEMAC Resources Group, Ltd., a Canadian corporation. Because of the exclusive option, NMCC is acting on behalf of the facility owner as the responsible person, as defined in 20.6.2.7 NMAC, regarding all aspects of abatement of subsurface and surface-water pollution.

1.1 Purpose and Objectives of the Abatement Plan

As defined in 20.06.2.4106C NMAC, the purpose of the Stage 1 Abatement Plan is to "…design and conduct a site investigation that will adequately define Site conditions, and provide the data necessary to select and design an effective abatement option." To achieve this purpose, NMCC proposes to design and implement a Site investigation program that will address MECS's concerns, which are summarized as follows:

- Potential groundwater impacts from the existing unlined tailings impoundment.
- Potential groundwater impacts from the existing pit lake.
- Potential impacts to wildlife caused by exposure to the existing pit lake.
- Potential groundwater impacts caused by acid rock drainage (ARD) from existing exposed waste rock.

These concerns were identified in the NMED letters provided in Appendix A and have been discussed in subsequent meetings with NMED MECS staff. The objectives of this plan are to summarize pertinent historical information, describe pertinent ongoing investigations, and propose additional investigations, which, in combination with historical and ongoing investigations, will meet the stated Stage 1 Abatement Plan purpose to address the identified concerns.

1.2 Abatement Plan Organization

This Stage 1 Abatement Plan is divided into ten sections: 1.0 Introduction, 2.0 Site Description, 3.0 Site History and Status, 4.0 Ongoing Investigation Activities, 5.0 Proposed Characterization Activities, 6.0 Quality Assurance Project Plan, 7.0 Site Health and Safety Plan, 8.0 Reporting, 9.0 Schedule, and 10.0 References. The Figures, Tables, and Appendices are included at the end of this document.

2 Site Description

This section provides a description of the Site as identified in Figure 1-1 and includes a discussion of climate, geologic conditions, and hydrologic conditions.

2.1 Climate

The Site lies within the belt of mid-latitude westerlies where the prevailing wind direction is from the west. Winds at the Truth or Consequences, New Mexico, airport, located about 30 miles northeast of the Site, are generally from the northwest; however, the Black Range and foothills cause local variations in the winds. At Copper Flat, the wind direction is predominantly west to east, and secondarily north to south. Local wind speeds average about 10 to 15 miles per hour, although winds in excess of 50 miles per hour may occur at times. Temperature inversions are rare at Copper Flat, but are more common farther east along the Rio Grande valley, especially during the winter months. Vertical air dilution is generally good because of the area's high surface temperatures, creating strong daytime thermal mixing. Thermal mixing and moderate winds generally tend to suppress occasional nighttime inversions. The presence of higher winds and the lack of inversions contribute to a relatively clean atmosphere at the Site since any pollutants are readily mixed and dispersed (BLM, 1999).

Temperature data for the Site show a wide diurnal and seasonal variability, which is typical of dry climates. The warmest temperatures occur in June and July, and the coldest temperatures usually occur in December and January. In spring and fall, daily maximum temperatures are moderate, typically averaging 65 to 85 degrees Fahrenheit (°F). Nights are cooler, with low temperatures averaging 32° to 50°F. Winter temperatures are frequently below freezing at night, but can be above 50°F during the day. During summer, temperatures can approach 100°F during the day. Daily temperature fluctuations of 30°F are common throughout the year (BLM, 1999).

Precipitation at the Site averages about 13 inches per year (ranging from nearly 3 inches in 1956 to over 20 inches in 1986). As much as half of the annual precipitation occurs in the form of intense thunderstorms during the months of July, August, and September when moist air enters the region from the Gulf of Mexico. Summer thunderstorms can result in heavy rainfall and flash floods. Average monthly precipitation in January through June is typically 0.50 inch or less. Snowfall is possible from October through April, but most likely (greater than 1 inch) from December through February (BLM, 1996).

Evaporation exceeds precipitation in southwestern New Mexico. Pan evaporation data, the most commonly collected data, are correlated with lake evaporation (i.e., free water surface evaporation) to predict evaporation from reservoirs and lakes. Lake evaporation at the Site is estimated to be approximately 58 to 65 inches per year, and pan evaporation is estimated to be approximately 80 to 90 inches per year (SRK, 1995).

Historical baseline meteorological data including PM_{10} ambient air monitoring were completed by Air Sciences, Inc. (Air Sciences), a contractor to Alta Gold Company (Alta Gold) in the mid-90s. Reports of these data were prepared by Air Sciences, and present the meteorological protocols used to collect data, including a letter from the New Mexico Air Quality Bureau approving the protocols. They also present the baseline air conditions for six

months of on-Site data (collected from August 19 to February 20, 1995) and six months of complimentary Truth or Consequences data (collected from February 21 to August 18, 1964), which was used for air dispersion modeling.

On July 9, 2010, NMCC and its current air quality contractor, Class One, visited the New Mexico Air Quality Bureau to meet with David Heath of the air modeling group, and Norma Perez and Kathy Primm, Environmental and Permit Specialists, respectively, to describe the air monitoring protocols that Class One would use, and to discuss the location of the on-Site meteorological tower, which is the same location that was used by Alta Gold in 1994 and 1995. No objections were noted to either the protocols or the tower location (Air Sciences, 1995a and 1995b).

The meteorological tower and air quality sampling stations were installed in July 2010 and operations of instrumentation commenced on August 6, 2010. Meteorological data are collected each second. Air quality samples are collected every six days. These data will be used for addressing the requirements of the Mine Permit as well as for geochemical and hydrologic modeling to address permitting and abatement issues (Section 5.0) (INTERA, 2010).

2.2 Geologic Conditions

The Site lies within the Mexican Highlands portion of the Basin and Range Physiographic Province. It is located in the Hillsboro Mining District in the Las Animas Hills, which are part of the Animas Uplift, a horst on the western edge of the Rio Grande valley (Raugust, 2003). The Animas Uplift is separated from the Rio Grande by nearly 20 miles of Santa Fe Group alluvial sediments, referred to as the Palomas Basin of the Rio Grande valley. To the west of the Animas Uplift is the Warm Springs valley, a graben that parallels the Rio Grande valley (BLM, 1999; Raugust, 2003). Further west, the Black Mountains form the backbone of the Continental Divide, rising to about 9,000 feet (ft) above mean sea level (amsl). The surface geology of the Copper Flat region is shown in Figure 2-1, and a schematic geologic cross section is shown in Figure 2-2.

Basement rocks in the area consist of Precambrian granite and Paleozoic and Mesozoic sandstones, shales, limestones, and evaporites. Sedimentary units that crop out within the Animas Uplift include the Ordovician Montoya Limestone, the Silurian Fusselman Dolomite, and the Devonian Percha Shale. The Cretaceous-age Laramide orogeny, which was characterized by the intrusion of magma associated with the subduction of the Farallon plate beneath the North American plate, affected this region between 75 and 50 million years ago (Ma). Volcanic activity during the late Cretaceous and Tertiary periods resulted in localized flows, dikes, and intrusive bodies, some of which were associated with the development of the nearby Tertiary Emory and Good Sight-Cedar Hills cauldrons (Figure 2-3); later basaltic flows resulted from the tectonic activity associated with the formation of the Rio Grande rift. Tertiary and Quaternary alluvial sediments of the Santa Fe Group and more recent valley fill overlie the older Paleozoic and Mesozoic units in the area. The regional stratigraphy of the lower Rio Grande Valley is summarized in Table 2-1 (BLM, 1999).

The geologic structure of the region is characterized by block and rift faulting (Figure 2-3). The Tertiary cauldrons associated with the earlier block faulting formed between 35 and 45 Ma. Rift faulting and associated north-south block faulting associated with continental extension and the formation of the Rio Grande rift began approximately 25 to 30 Ma. The Las Animas Hills are bounded by faults associated with rifting (Dunn, 1982). Continental extension continues to the present, as evidenced by north-south trending grabens represented by the Rio Grande and Warm Springs valleys.

Further details of the Site geology are provided in the Copper Flat Sampling and Analysis Plan (SAP) (INTERA, 2010).

2.3 Hydrologic Conditions

Groundwater is a major source of water for domestic and agricultural use in southern New Mexico. The high evaporation rate during the long, hot summers coupled with low average annual precipitation in the area result in surface waters generally being unreliable sources of water on a year-round basis. The Rio Grande is a significant surface water resource at the Site. At the confluence with the Rio Grande, Las Animas Creek and Percha Creek are intermittent or ephemeral, but both include perennial reaches upstream of the confluence that serve as local sources of water. The river and associated shallow alluvial deposits of its inner valley also served as the ultimate discharge zone for pre-development groundwater flow from the adjacent Greenhorn Arroyo, Las Animas Creek, and Percha Creek drainage basins (Hawley et al., 2004, Wilson et al. 1981). Additional water supply comes from shallow domestic and agricultural wells. This section provides a description of the regional and local groundwater along with a proposed sampling and analysis approach to characterizing baseline conditions of groundwater resources. Baseline studies have been completed in the project area since the 1960s, and relevant information and data are referenced in subsequent sub-sections.

2.3.1 Groundwater Hydrology of the Site

Three aquifers exist in the Site area, as shown schematically on Figure 2-4. The deepest aquifer is the crystalline bedrock aquifer that receives water from the highlands to the west of Animas Peak and carries this water along bedding planes, faults, and solution cavities toward the center of the Lower Rio Grande Basin. The crystalline bedrock aquifer consists of Cretaceous andesite and monzonite breccias underlain by Paleozoic rocks in the Animas Uplift area, Tertiary volcanic rocks to the west of the pit lake area in the graben associated with the Animas uplift, and Paleozoic sedimentary rocks to the east of the pit lake area in the Palomas Basin. The Santa Fe Group aquifer system, which consists of interbedded sandstones, silts, and clays, overlies the Paleozoic bedrock units to the east of the pit lake area within the Palomas Basin. This aquifer system receives water from precipitation and from the losing reaches of streams. The uppermost aquifer at the Site is the Quaternary alluvial aquifer along Las Animas and Percha Creeks (Figure 2-4). This alluvium is up to 40-ft thick in the Las Animas Creek area and carries water that is in hydraulic equilibrium with the water flowing in Las Animas Creek (BLM, 1999). The Percha Creek alluvial aquifer is less studied than the Las Animas Creek alluvial aquifer, and as a result, less historical data about its aquifer characteristics are available. The aquifers of greatest importance in terms of water supply in the area are within the Palomas Basin to the east of the pit lake and include the intermediate Santa Fe Group aquifer system and the alluvial aquifer associated with Las Animas Creek.

Figure 2-5, adapted from the Adrian Brown Consultants (ABC) (1998), presents a piezometric contour map showing the general configuration of groundwater level elevations at the Site as interpreted at that time. Groundwater levels near the existing pit are approximately 5,450 ft amsl, and at Caballo Reservoir, the levels are about 4,200 ft amsl. Figure 2-5 indicates that groundwater flow is generally to the east toward Caballo Reservoir. Hydraulic gradients are relatively large (closely spaced contours) in the western portion of the Site, reflecting lower transmissivity in the bedrock aquifer and in the western portion of the Palomas Basin in the Santa Fe Group aquifer system. The wider spacing of contours in the eastern portion of the Site suggests that transmissivity of the Santa Fe Group aquifer increases toward Caballo reservoir. The widest spacing of contours (highest transmissivity) appears to occur in the area of the groundwater production wellfield (wells PW-1, 2, 3, and 4 on Figure 2-5). This area coincides with an interpreted graben structure, which reflects an increased thickness of the Santa Fe Group in this area.

2.3.2 Aquifer Characteristics in the Permit Area

Characteristics of the three principal aquifers in the area are summarized in this section.

2.3.2.1 Crystalline Bedrock Aquifer Characteristics

Groundwater within the mining district and the area of the present open pit occurs in andesitic volcanic rocks and quartz monzonite breccia intrusive rocks (Figure 2-4). The current pit lake was reported by SRK (1997b) to be at an elevation of 5,442 ft amsl, which is about 50 to 100 ft below the pre-mining ground elevation (5,500 to 5,540 ft amsl reported in the Preliminary Final Environmental Impact Statement [PFEIS][BLM, 1999]). Groundwater levels measured in the pit and tailings areas as of 1997 are shown on Figure 2-6. Newcomer et al. (1993) reported a pre-mining (1981) water level of 5,370 ft amsl in well GWQ-5, which was approximately 4,000 ft east-southeast from the pit and within the old plant site area. These authors also reported a water level of 5,360 ft amsl in the Hillscher West well (GWQ-6), which lies approximately 2,500 ft southeast from well GWQ-5. These limited groundwater elevation data suggest that the groundwater gradient in the andesitic volcanic rocks may be to the east or southeast from the current pit lake area as shown in larger scale on Figure 2-6. Within 500 ft of the pit lake (see Figure 2-7), however, groundwater gradients are toward the pit lake, which may act as a local evaporative sink (BLM, 1999).

In January 2010, NMCC resurveyed the pit lake and as many of the groundwater monitoring wells established for the PFEIS as could be located. The pit lake elevation was 5,444 ft amsl in January 2010, revealing that the pit lake elevation remains below the pre-mining water level elevation of 5,500 to 5,540 ft amsl. Further discussion of the pit lake hydrology and the groundwater sink are provided in Section 5.

2.3.2.2 Santa Fe Group Aquifer System

Overview

Overlying the crystalline bedrock aquifer at the Site is the Santa Fe Group aquifer system, a system that is locally represented by two hydrostratigraphic units (HSUs): (1) the Upper Santa Fe Group HSU (USF), and (2) the Middle Santa Fe Group HSU (MSF). As defined by Hawley et al. (2004), these HSUs are mappable bodies of basin and valley fill that are grouped according to genesis and position in both lithostratigraphic and chronostratigraphic sequences. Informally, these HSUs comprise the major basin-fill aquifer zones and correspond roughly to the upper (Palomas) and middle (Rincon valley) lithostratigraphic subdivisions of the Santa Fe Group used in local and regional geologic mapping (Hawley et al., 2004).

The Santa Fe Group is composed chiefly of coalescing alluvial fan deposits that are discontinuous and locally heterogeneous with inter-bedded sandstones, silts, and clays of varying percentages. The Upper Santa Fe Group Palomas Formation (Lozinsky and Hawley, 1986) represents the USF at the Site. This formation grades eastward from the Animas Uplift from coarse alluvial fan material to braided-stream and deltaic sands and silts to clays near the Rio Grande. The interfingering with clays begins approximately 3 to 5 miles west of the current position of the Rio Grande and is responsible for the flowing wells common in this part of the Site (Murray, 1959; Figure 2-4). A basalt flow dated at 4.2 million years before present caps the Palomas Formation gravels near Copper Flat (Seager et al., 1984).

The Middle Santa Fe Group Rincon Valley Formation (Seager and Hawley, 1973) is exposed near Hillsboro, New Mexico, where the reddish-brown clays and clayey silts characteristic of this basal unit are interbedded with basalts dated at 28 million years before present (Seager et al., 1984). The Rincon Valley Formation represents the MSF at the Site and generally contains water, but the yield is low due to the low hydraulic conductivity of the clays. The Rincon Valley Formation lacustrine red clays underlie the Palomas Formation and thicken southward toward Hatch, New Mexico, and the Rincon Basin (Wilson et al., 1981).

Tailings Dam Vicinity

The present tailings impoundment facility overlies the old placer workings of Grayback Arroyo and Hunkidori Gulch (Figure 2-8). A study of these placer workings by Segerstrom and Antweiler (1975) showed that the placers were found in paleo-stream terrace alluvium, approximately 25 to 30 ft thick, that is underlain by a calcium carbonate horizon and reddish-brown clay. SRK (1995) and SHB (1980) confirmed and expanded the areal extent of this reddish-brown clay layer and determined that the top of the Palomas Formation is stratigraphically below the red clay layer. According to the studies completed by SRK and SHB, the clay layer and the 25 to 30 ft of paleo-stream terrace gravels that lie above the clay have acted to prevent downward migration of water draining from the eastern half of the existing tailings. This clay layer has enabled a mound of water beneath the tailings impoundment to develop, and was determined by SRK (1995) and SHB (1980) to extend eastward beyond the tailings dam. This mounding of water, due to drainage of the tailings according to SRK (1995), became evident in some tailings dam monitor wells completed above the clay layer. The central and western sections of the existing tailings facility appear to communicate hydrologically with the USF that lies beneath the tailings area because the clay zone thins and disappears in this area, as shown in Figure 2-9. Further discussion of tailings seepage impacts and this clay layer are provided in Section 5.0.

The thickness of the Palomas Formation increases locally over a graben structure (labeled Dutch Gulch in Figure 2-2), which is reflected in higher transmissivity and relatively low hydraulic gradients in the USF. Based on a 7-day aquifer pumping test (ABC, 1996), the transmissivity of the USF in the tailings dam area is about 187 ft^2/day. East of the tailings area (see Figure 2-2) is a 10- to 30-foot thick clayey sand and gravel layer, underlain by a 25- to 100-foot-thick clay layer, which in turn is underlain by a silty sand and gravel layer (SRK, 1995). The lower silty sand and gravel layer is considered by ABC (1996) to be the USF and, based on drilling information, has a thickness of at least 200 ft. The hydraulic gradient in this area is about 30 ft per mile.

East of the graben structure, labeled as Dutch Gulch in Figure 2-2, the Palomas Formation (labeled Tsfp) thins and is interpreted to have significantly reduced transmissivity. The hydraulic gradient in this area ranges from about 130 to 330 ft/mile. The contact between the Palomas Formation and the underlying Rincon Valley Formation clay unit (labeled Tsf in Figure 2-2) is a highly irregular depositional contact. Locally, the Palomas Formation (USF) may be unsaturated, with the water table existing in the underlying Rincon Valley Formation (MSF) (BLM, 1999).

2.3.3 Surface Water Hydrology of the Permit Area

The Copper Flat area falls within the Lower Rio Grande watershed, as defined by the New Mexico Water Quality Control Commission (WQCC). This watershed includes approximately 5,000 square miles in Catron, Socorro, Sierra, and Doña Ana Counties, and is dominated by the Rio Grande and its tributaries as well as the two large reservoirs of Elephant Butte and Caballo. Numerous tributaries feed into the Rio Grande from the west, but none contribute perennial flow to the Rio Grande.

The Site is drained by ephemeral streams (arroyos) within the Greenhorn Arroyo drainage basin, a sixth-level sub-watershed defined by the Hydrologic Unit classification system (Seaber et al., 1987) that drains 29,414 acres of land on the eastern slope of the Animas Uplift to a single outlet into the Rio Grande (Figure 2-10). Flows within the Greenhorn Arroyo drainage basin are ephemeral, as they only occur in direct response to precipitation. As a result, this drainage, similar to others in the region, does not contribute any perennial surface water flow to the Rio Grande.

Numerous arroyos contribute to the trunk channel of Greenhorn Arroyo. Of these, Grayback Arroyo is the primary drainage through the Site. Grayback Arroyo originates west of the Site and drains eastward along the Site axis until it converges with the trunk channel of Greenhorn Arroyo approximately 8 miles east of the Site

boundary (Figure 2-10). In pre-mining times, Grayback Arroyo drained directly through the mine area, but was later re-routed around the southern perimeter of the mine area for flood control purposes (Raugust, 2003). Newcomer and Finch (1993) measured flow rates in Grayback Arroyo of 12.5 gallons per minute (gpm) in March 1993 at a point east of the pit and former plant site. Three seeps have been identified along Grayback Arroyo (BLM, 1999). One seep with riparian vegetation is located near a buried storm water collection pond, a second is located downstream from the first seep and supports a small cottonwood/willow stand, and the third is south of the operations area (Figure 2-10).

Two creeks drain basins directly to the north and south of the Greenhorn Arroyo drainage basin: Las Animas Creek in the north and Percha Creek to the south (Figure 2-10). Both Las Animas and Percha Creeks have ephemeral, intermittent, and perennial reaches. Streamflow in Las Animas Creek varies from perennial to intermittent from the area near sampling site MAS (Figure 2-8) to Caballo Reservoir (BLM, 1999). For example, Davie and Spiegel (1967) show flow rates ranging from about 450 to 900 gpm in the upper reach (T14S R7W, Sections 34 through 36, near sampling sites LAC-A and LAC-B in Figure 2-10) and middle reach (within T15S R5W) of the creek; according to Davie and Spiegel, these reaches are “losing reaches” of the creek. Streamflow in Percha Creek is intermittent in the Hillsboro reach and perennial in the area known as the Percha Box, a steep-walled reach of the drainage that has incised into Paleozoic bedrock (BLM, 1996) (Figure 2-8). SRK (1995) reported measurable streamflows just east of the Percha Box of roughly 200 to 250 gpm. This was the only reach of Percha Creek with measurable flows during the SRK sampling period. Though both Las Animas Creek and Percha Creek have perennial reaches, neither creek contributes perennial flow to the Lower Rio Grande Basin.

Two springs are located within the Greenhorn Arroyo drainage basin to the north and west of the Site (Figure 2-8). Other unnamed seeps occur in the pit walls surrounding the pit lake after precipitation events; these are likely the result of fractured flow through the bedrock exposed in the pit wall. Several springs in the Percha Creek basin and one in the Las Animas Creek basin have been identified for sampling, but have been studied less than those within the Greenhorn Arroyo basin. As a result, there is little information prior to 2010 on their flow rates or quality, although Newcomer and Finch (1993) did attempt to measure flow.

The open pit that was mined during the early 1980s now contains a lake. Since 1989, the pit lake has been sampled for water quality approximately 65 times at various locations and depths, including by past operators of the mine, state regulatory agencies, and academic researchers studying the mine (BLM, 1999). For the proposed operations, NMCC would consume the pit lake waters for mine operations and dust suppression. If necessary, pit water could be temporarily stored in a reservoir in the plant area (SRK, 2010a).

Mine water from milling operations would be discharged into an evaporation pond or re-used for several purposes: (1) plant processing streams, (2) the tailings facility with pump-back to the plant, and/or (3) dust control (SRK, 2010a). Both a National Pollution Discharge Elimination System permit and an NMED groundwater discharge permit are required for NMCC to discharge mine water. In preparation for both permits, NMCC will characterize the water quality of the mine discharge through scheduled gauging and sampling of discharge. In addition, NMCC will design a storm water management system to manage discharge for the proposed facilities. Mine water discharge is not expected to reach the Lower Rio Grande or any lake, spring, reservoir, riparian, or wetland areas.

3 Site History and Status

The collection of baseline data at the Copper Flat Mine began in the late 1970s with an environmental assessment (EA) prepared for Quintana Minerals Corporation (Quintana) (BLM, 1978), followed by Rio Gold Mining Ltd (Rio Gold), Gold Express, and Alta Gold. These data are relevant and provide insights for future

permitting activities. The Copper Flat Mine was first permitted by Quintana during the 1980s. In 1992, a new plan of operations was submitted and an EA was begun by Gold Express, but the operation was never restarted. Alta Gold acquired the property in the mid-1990s and reinitiated the permitting and approvals process, collecting significant baseline data and submitting applications for all major state and federal permits. Alta Gold declared bankruptcy in early 1999, but not before a draft environmental impact statement (EIS) (BLM, 1996) and PFEIS (BLM, 1999) had been prepared and the associated public comments received; a public hearing had also been held on the New Mexico Mining Act Permit and the New Mexico Groundwater Discharge Permit. However, no final permits had been issued and there had been no opportunity for appeals or litigation regarding the operation. Figures 3-1 and 3-2 illustrate the Site permit boundary with topography and the 2009 aerial photo, respectively.

3.1 Historical Mine Activities

Ore was first discovered in the Hillsboro district in April 1877, and the town of Hillsboro was established that same year. A number of mining claims were patented for the Site between 1892 and the 1940s; these now form most of the private land occupied by the Copper Flat mine.

In 1952, Newmont began exploration in the district for porphyry copper mineralization by drilling nearly 3,599 ft in six angle holes into the Copper Flat Quartz Monzonite (CFQM) (Kuellmer, 1955). Bear Creek drilled another 9,300+ ft in 1958−1959 in 20 widely spaced core holes, hoping to find an enrichment blanket of secondary copper (which was not found). Both the Newmont and Bear Creek drill and assay data are available (Dunn, 1984). Porphyry copper exploration was advanced by Inspiration again in the late 1960s. Inspiration completed 30 core drill holes by 1973, purchased the patented claims, performed metallurgical work, and completed two water wells on the property (Dunn, 1984).

In 1974, Inspiration leased the property to Quintana, which undertook a comprehensive mine development program with metallurgical work, underground drifting, bulk sampling, and drill hole composite testing (all preformed by the Colorado School of Mines Research Center). The program included detailed geologic investigations into the relationship between the breccia pipe and the quartz monzonite host rocks, as well as the relationship between host rocks and mineralization. An EA was initially prepared for state and federal agencies in 1975, but low copper prices caused the project to be shelved from late 1976 until 1979. At that time, processing methods were reviewed and semi-autogenous grinding and copper-molybdenum flotation separation became the basis for subsequent design work. Mineable reserves were estimated at 60 million standard tons (Mst) with 0.42 percent copper and 0.012 percent molybdenum, plus some gold and silver (SRK Consulting, 2010).

With Quintana as the overall project manager, the Copper Flat mine began full production in March 1982 at a rated capacity of 15,000 Mst a day, a waste-to-ore ratio of 1.8:1, and a cut-off grade of 0.25 percent copper. The combination of low copper prices and high interest rates on the financing loan resulted in the mine closing down just 3 months later, at the end of June. During its short operational period, the mine produced 1.48 Mst of ore containing 7.4 pounds (lbs) of copper, 2,301 ounces (oz) of gold, and 55,955 oz of silver (SRK Consulting, 2010). By the end of 1985, the surface facilities' equipment had been sold and the site reclaimed as required by state and federal guidelines. However, all structural foundations, power lines, water wells, and in-ground infrastructure were left in place.

Hydro Resources of Albuquerque, New Mexico, acquired the Copper Flat property, including all royalties, from Inspiration in 1989. Rio Gold and Tenneco Minerals (Tenneco) drilled six large-diameter holes in 1990. Gold Express optioned the property in 1993, and then sold it to Alta Gold in 1994 without performing any exploration or development. A PFEIS for the Alta Gold mining project was issued in March 1999, but Alta Gold went

bankrupt (due to financial problems with other assets) before any permits were issued. Hydro Resources reacquired all the properties in 2001 along with all royalties. Hydro Resources maintains an archive of information related to the mine, including over 14,000 sample pulps and skeleton core from the Quintana drilling programs (SRK Consulting, 2010).

In 2009 and early 2010, NMCC conducted a sample verification program that included pulp reject analysis and drilling as part of the requirements for a NI43-101 report on the resources at Copper Flat (SRK Consulting, 2010). The program was designed to verify different aspects of the mineralization and geology of the deposit, as well as to comply with new reporting requirements. The drill holes were plugged with bentonite and capped with cement, as required by the New Mexico Energy, Minerals and Natural Resources Department (EMNRD) Mining and Minerals Division (MMD). NMCC completed seven drill holes comprising 5,046.5 ft of core. Three of the drill holes terminated prematurely due to bad ground. The drill sites were reclaimed as per MMD requirements (SRK Consulting, 2010).

Approximately 60 percent of the proposed Site has been disturbed by previous operations. Remnants of the 1982 mining operation include an open pit and pit lake, a tailings impoundment area, waste rock disposal areas, a number of buried building foundations, and ancillary facilities including decant towers, roads, power transmission lines, and waterlines (Figures 3-3 and 3-4). These features are clearly delineated on Bureau of Land Management (BLM) geographic information system (GIS) maps and aerial photographs, and have been considered as part of the proposed plan of operations. Although some reclamation was done to the area in 1986, much of the Site remains disturbed (Figure 3-2).

3.2 Previous Surface Water Studies

Existing surface water data are summarized in this section. Surface water at the Site was most recently investigated by SRK (1995), which collected flow and water quality data from Percha Creek and Las Animas Creek (Figure 2-10). Newcomer et al. (1993) performed a hydrologic assessment of the Greenhorn Arroyo drainage basin, measuring flow and water quality along Grayback Arroyo and at a number of seeps and springs. The oldest known surface water investigation at the Site was performed by Davie and Spiegel (1967), who collected flow data for Las Animas Creek. Results of these investigations were compiled by Raugust (2003) and are also summarized in the BLM's PFEIS for Copper Flat (BLM, 1999).

3.2.1 Volumetric Flow

3.2.1.1 Streams

Flow rate data for streams at the Site are limited by the generally intermittent nature of flows. Recent measurements of flows were made by Newcomer et al. (1993) and ABC (1996). Additional historical measurements were compiled in the PFEIS (BLM, 1999). These data are summarized in Table 3-1.

Grayback Arroyo is an ephemeral stream and generally flows only during periods of snow melt or rain events. Flow rates in Grayback Arroyo at SWQ-3 (Figure 2-10) were measured by Newcomer et al. (1993) to be 12.5 gpm (0.028 cubic feet per second [cfs]) in March of 1993.

Two measurements of flow rate are recorded for Las Animas Creek. Davie and Spiegel (1967) reported flows of between 1.0 and 2.0 cfs in the creek's upper reaches, and between 1.0 and 1.5 cfs in its middle reaches (BLM, 1999). ABC made a single flow measurement of 245 gpm (0.546 cfs) at LAC-E (Figure 2-10) in 1996.

Volumetric flow in Percha Creek was measured at 13 locations by ABC (1996) from approximately ¼ mile upstream of the entry to Percha Box to approximately 5 miles downstream of the exit from Percha Box. Flow

was found to be localized, occurring within and immediately to the east of Percha Box, and ranging from 456 gpm (1.02 cfs) to 119 gpm (0.265 cfs), with many reaches dry or with standing water only.

3.2.1.2 Springs and Seeps

Spring and seep flow rates are infrequently reported in the available literature for the Site and surrounding areas. Several springs and seeps have been identified within the Greenhorn Arroyo drainage basin. Two springs, identified as BG and BG-2, are located to the north and west of the Site (Figure 2-10), and several unnamed seeps occur in the walls surrounding the pit lake. BG and BG-2 were judged by Newcomer et al. (1993) to be ephemeral. The seeps along the pit walls are observed to flow in response to precipitation events, and as mentioned above, are likely the result of fractured flow through the bedrock exposed in the pit wall. All known springs and seeps in the Greenhorn Arroyo drainage basin are upgradient of the proposed mine water discharge location. Other seeps and springs shown in Figure 2-8 have not been measured in the past and thus have no associated historical flow information.

3.2.2 Water Quality

3.2.2.1 Streams

The surface water chemistry of Grayback Arroyo was initially investigated in 1977 at three locations as part of an EA prepared by the BLM in response to an application by Quintana for an open pit copper mine at the Site (BLM, 1978). The three locations sampled in 1977 generally correspond to the sampling locations SWQ-1, SWQ-2, and SWQ-3 proposed in Figure 2-10, with one location upstream of the permit boundary, one within the Site approximately 300 yards from the mine rim, and a third located where the arroyo leaves the Site (BLM, 1978). Water samples were collected in January, March, and July of 1977.

WQCC standards for metals were not exceeded at any location in any of the 1977 sample events. Results for pH (7.6–8.1) were in the same range as samples collected later at these three locations. Total dissolved solids (TDS) results upstream of the Site (720–1000 milligrams per liter [mg/L]) were comparable to those of samples collected later, but samples taken at locations within and downstream of the Site were comparatively lower (800–1,320 mg/L) than the results for later sampling events, such as those conducted by Newcomer et al. (1993) at SWQ-1 (upgradient of the pit lake), SWQ-2 (downgradient of the pit lake but within the area of mining disturbance), and SWQ-3 (approximately 1 mile downgradient of the pit lake) (Figure 2-10). Field parameters measured by Newcomer et al. are shown in Table 3-1, and complete analytical results are presented in Appendix B1. Water quality in Grayback Arroyo upstream of the pit lake at SWQ-1 had a pH ranging from 7.4 to 8.3, sodium at 107 mg/L, bicarbonate values ranging from 400 to 500 mg/L, sulfate ranging from 275 to 300 mg/L, and TDS ranging from 780 to 965 mg/L. At SWQ-2, sodium concentration increased from the previous sampling event by BLM to 270 mg/L, sulfate increased to between 1,150 and 1,650 mg/L, TDS increased to between 2,300 and 3,300 mg/L, and pH and metal concentrations remained essentially unchanged. Water quality indicators at SWQ-3 fell within the range of values at SWQ-2.

Las Animas Creek water quality was examined by ABC (1996) and for the PFEIS (BLM, 1999). ABC obtained a single sample at LAC-E with a pH of 7.81, sulfate concentration of 18 mg/L, and TDS of 300 mg/L. The PFEIS reports that Las Animas Creek water quality is dominated by calcium or sodium bicarbonate, with pH in the range of 7.0 to 8.0, sulfate in the range of 20 to 70 mg/L, and TDS in the range of 300 to 400 mg/L. Occasionally, sodium and chloride are higher, with chloride concentrations as high as 300 to 400 mg/L, possibly due to agricultural practices along the creek (BLM, 1999). Complete analytical results for Las Animas Creek are compiled in Appendix B1.

Percha Creek water quality was examined by ABC (1996) and for the PFEIS (BLM, 1999). ABC sampled Percha Creek at the entry and exit to Percha Box and 5,000 ft downstream from the exit from Percha Box, and measured field parameters at all seven locations in which water was found (Table 3-1). For the three samples submitted for laboratory analysis, pH ranged from 7.62 to 7.82, sulfate ranged from 63 to 71 mg/L, and TDS ranged from 336 to 406 mg/L. The PFEIS (BLM, 1999) reports that surface water flowing in Percha Creek has a chemistry dominated by calcium bicarbonate, with pH in the range of 7.0 to 8.0, sulfate in the range of 20 to 70 mg/L, and TDS in the range of 300 to 400 mg/L. Complete analytical results for Percha Creek are compiled in Appendix B1.

Sampling of the Caballo Reservoir (the receiving water for these drainages) during November 1994 showed the water to be dominated by sodium bicarbonate with a bicarbonate value of 180 mg/L and a sulfate value of 110 mg/L (SRK, 1995). As summarized in the PFEIS (BLM, 1999) chloride values were less than 100 mg/L, and TDS was 440 mg/L. The water chemistry was within WQCC standards for metals, sulfate, chlorine, pH, and TDS. As a comparison, water samples from the Rio Grande at EI Paso, Texas, were sodium-sulfate-dominated with high TDS in the range of 800 to 1,000 mg/L, sulfate values of 200 to 340 mg/L, and bicarbonate values of around 100 mg/L (Wilson et al., 1981).

3.2.2.2 Springs and Seeps

Newcomer et al. (1993) sampled the BG and BG-2 springs (Figure 2-10) in April 1993, and ABC observed and sampled seeps in the pit wall in August 1997 (ABC, 1997). Field parameters and water chemistry analytical data for these locations are presented in Table 3-1 and Appendix B1, respectively. Samples from BG and BG-2 had pH ranging from 8.0 to 8.2, sodium ranging from 90 to 124 mg/L, bicarbonate ranging from 411 to 535 mg/L, sulfate ranging from 184 to 228 mg/L, and TDS ranging from 680 to 690 mg/L. The pit wall seep sample had a pH of 8.16, a sulfate content of 3,100 mg/L, and TDS of 5,020 mg/L. On the basis of these results, ABC (1997) judged BG and BG-2 to be qualitatively similar to the Grayback Arroyo sample location SWQ-1, while the pit wall location appears to have been subject to a similar process as the locations at SWQ-2 and SWQ-3.

3.3 Previous Pit Lake Studies

The 12.8-acre lake that has formed in the existing pit was estimated to be about 40 ft deep, based on a pit bottom elevation of 5,380 ft amsl and water level elevation of 5,420 ft amsl as measured in 1986 (SRK, 2010b). The water quality of the pit lake has been sampled over 65 times at various depths and locations since the initial samples were collected on April 13, 1989, by the New Mexico Environment Improvement Board (Raugust, 2003); the latest samples were collected in January 2011. Pit water has historically exceeded the WQCC standards for sulfate, chloride, TDS, manganese, and uranium (20.6.2.4103 of the NMAC) and has, at times, dropped below the acceptable pH range of 6 to 9. Figure 3-5 illustrates the current pit lake bathymetry which has been defined by collecting over 400 water-depth measurements along both north-south and east-west transects throughout the pit lake. Analytical results of samples collected from 1989 to 1998 suggest that sulfate, chloride, TDS, manganese, and pH all increased over this period. For example, sulfate increased from a range of 2,250 to 3,000 mg/L to a range of 3,500 to 4,300 mg/L over this time period (Figure 3-6). Chloride increased from an average of around 100 mg/L to around 250 mg/L, which may be attributed to lower average annual precipitation and higher annual temperatures during this period (BLM, 1999). However, the sulfate-to-chloride ratio dropped during this time period, suggesting that sulfate rose at a slower rate than chloride due to the formation of gypsum and the subsequent buffering of the sulfate concentration in pit lake water by gypsum (gypsum is observed along the margins of the pit lake during the summer months when the pit lake level drops). TDS ranged from 2,700 mg/L in 1991 (Newcomer et al., 1993) to about 6,000 mg/L in 1998 (Raugust, 2003; Figure 3-7). Manganese ranged from 1.8 to 4.3 mg/L (BLM, 1999). The measured pH values have generally increased over

time to about 8.0 (Figure 3-8). However, in 1992 and again in 2008, pH decreased to 4.4 and 4.5 (NMED GWQB, 2008), respectively, deviating from the overall trend of elevated pH values. The overall rise in the pH may be due to buffering by wall rock. No historical data are available for uranium, other than a sample collected in 2004 that showed the water exceeded the WQCC standard (NMED GWQB, 2008).

Variability in the methods, locations, and depths from which samples were collected may explain many of the differences observed in pit water quality results. However, samples collected in January 2010 confirm that concentrations of sulfate, chloride, TDS, and manganese have increased. The 2010 sampling yielded a sulfate concentration of 5,200 mg/L, a chloride concentration of 390 mg/L, a TDS concentration of 7,770 mg/L, and a manganese concentration of 41 mg/L, all of which were higher than previous measurements from the 1989 to 1998 period. In addition, concentrations of aluminum, copper, cobalt, iron, and fluoride in the 2010 sample all exceeded WQCC standards. In contrast, pH, the most widely variable parameter measured during the 1989 to 1998 period, was 6.3 in January 2010, which is within the acceptable range of 6 to 9.

Other key studies that discuss the water quality of the Site are summarized in SRK (1997b) and include hydrogeologic and hydrogeochemical studies (SRK, 1995), post-closure pit water balance model calculations (SRK, 1997b), water quality and host-rock geochemical studies (SRK, 1997b), and post-hearing submittals that followed the 1997 New Mexico Mine Permit public hearing.

3.4 Previous Groundwater Studies

A wealth of groundwater data are available for the Site because the mine was active in the past and was characterized by previous operators that either mined the Site or worked on permit applications to mine the Site. These historical data are being used in conjunction with the baseline groundwater quality data that are being collected under the procedures set forth in the SAP (INTERA, 2010) and this Stage 1 Abatement Plan to provide a regional understanding of groundwater quality conditions prior to the re-initiation of mining at Copper Flat. These data will provide the foundation for evaluation of required abatement activities. Key resources that contain data to be used for the regional groundwater analysis include: Groundwater monitoring well exceedances provided by SRK Consulting (2010); the PFEIS (BLM, 1999); the Hydrologic Assessment, Copper Flat Project Sierra County, New Mexico (Newcomer et. al, 1993); and The Natural Defenses of Copper Flat, Sierra County, New Mexico (Raugust, 2003). A brief summary of the data available in these key reports follows.

The PFEIS (BLM, 1999) provides a summary of groundwater quality data collected up to through the late 1990's. The wells identified in this study are illustrated in Figure 3-9. The PFEIS (BLM, 1999) concluded that groundwater quality at the Site was good and generally useable for domestic and agricultural purposes. This document also concluded that past mining in the Hillsboro District, the Copper Flat Mine tailings facility drainage, and the presence of an oxidized sulfide-bearing ore body have impacted groundwater within and immediately adjacent to the area of past mining, resulting in elevated TDS and sulfate that exceed WQCC standards. These impacts were found to be localized within the immediate vicinity of the mine features or associated with wells completed in the ore body.

Newcomer et al. (1993) determined that the quality of groundwater at the Site has changed little since the early 1980s and probably since the 1800s. The authors found that there have been some increases in TDS and sulfate in some wells along Grayback Arroyo below the mine site and down-gradient of the tailings dam, associated with mining and milling activities in the 1980s. Newcomer et al. (1993) determined that the only constituents exceeding the WQCC standards were barium from a spring sample, and, cadmium and fluoride from a pit lake water sample.

Raugust (2003) compiled historical groundwater data and summarized groundwater quality conditions, and based on his data compilation and analysis, concluded:

- Groundwater pH measurements both up and downgradient of the pit lake range from 7 to 8.2.
- TDS and sulfate values are less than WQCC standards in the wells evaluated for this analysis; however, samples downgradient of the mine have increased gradually over time and are approaching the standards for TDS.
- Pre-mine (1981) sampling of well GWQ-5 (now destroyed), located east and downgradient of the pit lake, indicates that water quality in the vicinity of the pit lake may have been affected naturally by the presence of the ore body prior to mining in 1982. Sulfate concentrations taken from GWQ-5 in 1981 were higher (477 mg/L to 575 mg/L) than sulfate concentrations in GWQ-96-23A immediately down-gradient of the pit (<450 mg/L) (Raugust, 2003). Concentrations of TDS revealed similar results (1,070 mg/L to 1,260 mg/L in GWQ-5 and <1,000 mg/L in GWQ-96-23A).
- The groundwater upgradient of the mine pit lake is high quality with relatively high proportions of chloride and sulfate. Groundwater downgradient of the pit lake shows relatively higher proportions of bicarbonate and calcium and relatively lower proportions of sulfates. Pre-Quintana mining (June 15, 1981) groundwater data collected from wells downgradient of the pit lake show similar anions and cation distributions to post-Quintana mining activities (1996 and 1998). This indicates that groundwater quality downgradient of the ore body reflects the natural weathering of the Copper Flat porphyry system.

4 Ongoing Investigation Activities

As discussed in Section 3.0, the Site and surrounding area have been subject to extensive surface water and groundwater quality monitoring. Groundwater has been sampled from a network of wells that remains, in whole or in part, active to the present day since 1975. To emphasize this point, Figure 4-1 illustrates all groundwater monitoring wells, some of which do not exist or could not be located in 2010 (Saladone Well, GWQ-5, and Delores Well), that have been sampled at the Site from 1975 to January 2011. As shown by the key, the amount of times these wells have been sampled is indicated by the size and color of the symbol at the well location. In contrast, surface water has been sampled from a select number of locations since 1981.

NMCC is characterizing surface water and groundwater conditions at the Site in response to baseline monitoring requirements of the EMNRD MMD. These data are an important foundation for addressing the abatement issues identified by MECS. To date, NMCC has collected three quarters of surface water data, two quarters of pit lake data, and three quarters of groundwater data. These data are summarized in the following subsections.

4.1 Surface Water Monitoring

NMCC's baseline surface water monitoring program is described in detail in the SAP (INTERA, 2010). The baseline surface water monitoring program is designed to establish pre-operational flow and water quality conditions of streams, seeps, and springs in the vicinity of the Site (the Pit Lake is addressed separately in Section 4.2, below). The existence and location of significant surface water features were verified by review of historical records and field reconnaissance. Monitoring locations, shown on Figure 4-2, were selected by NMCC to characterize background hydrologic conditions in drainage basins that could directly or indirectly be affected by mining operations.

The surface water monitoring program began in the summer of 2010. Volumetric flow and water quality of streams, seeps, and springs are monitored on a quarterly basis. All surface water features are sampled if flowing water is present. Volumetric flow in streams is calculated using the standard velocity-area approach, where velocity is measured with a Marsh-McBirney electromagnetic current meter (INTERA, 2010). Volumetric

discharge of seeps and springs is measured by a variety of timed-fill approaches. In one case, water is bailed out of an artificial spring box of known volume and the recharge time is measured. In another, the sole overflow from a spring box is diverted into a five-gallon container and the time required to fill it is measured. For seeps and springs without spring boxes, flow is diverted into a variety of containers. However, flow is not measured at surface water features where the discharge is very low or diffuse, or when it is otherwise impractical to make measurements.

In addition, automated flow and sampling systems have been installed at three locations on Grayback Arroyo (SWQ-1, SWQ-2 and SWQ-3, Figure 4-2) and on the lowermost reaches of Percha Creek (PC-E) and Las Animas Creek (LAC-E) (Figure 4-2). The auto-samplers on Grayback Arroyo are positioned to allow potential ARD from waste rock to be detected by comparing upgradient, cross-gradient, and downgradient water chemistry. (Further discussion of ARD issues is provided in Section 5.3). SWQ-1 is west and upgradient of the waste rock dumps; SWQ-2 is on the Site, collocated with the waste rock dumps; and SWQ-3 is at the eastern margin of the Site, downgradient of the waste rock dumps. These systems consist of an automated controller, a data logger, a pressure transducer, and a peristaltic sampler. The transducer is installed in the stream bed and is monitored at 30-minute intervals by the automated controller; measurements are stored in the data logger. When streamflow is detected, the controller activates the peristaltic sampler. Samples are then collected and submitted for laboratory analysis. The automated flow and sampling systems on Grayback Arroyo and Percha Creek are installed on intermittent or ephemeral reaches and are programmed to collect a sample of any discharge whatsoever in those drainages. The reach of Las Animas Creek monitored by an automated system has experienced perennial flow since the summer of 2010 and is only sampled during flood stage conditions.

A summary of exceedances to date of the appropriate WQCC standards for surface water is presented in Table 4-1, with exceedances of applicable NMED surface water standards highlighted. These data show the presence of the metals arsenic, barium, boron, calcium, iron, magnesium, manganese, molybdenum, potassium, silicon, sodium, and uranium to be at levels below WQCC standards, and aluminum, beryllium, cadmium, cobalt, copper, selenium, and zinc to be at levels that exceed WQCC standards. The anions chloride, fluoride, sulfate, and nitrate have been detected at levels below the surface water standards; neither nitrite nor ammonia has been detected. No other analytes have been detected in exceedance of surface water standards. Analytical results of all surface water samples for constituents for which WQCC standards exist are provided in Appendix B1.

NMCC is aware of MECS' concern with respect to ARD generation at the Site. These surface water quality data will assist in forming the baseline against which long-term monitoring data can be compared to ensure that ARD is not a problem at this Site when mining activity resumes. If these data indicate there is an existing problem at the Site, they will enable NMCC to develop an appropriate response action. Further discussion of ARD and ongoing work to address this issue is provided in Section 5.3.

4.2 Pit Lake Characterization

The NMCC plan for characterizing the quality of pit lake water is described in detail in Chapter 8 of the SAP (INTERA, 2010). Following the SAP, water quality samples have been collected on a quarterly basis since September 2010. During the first quarter, a bathymetric survey was completed to identify the deepest point of the pit lake where the sampling station was established for collecting all water quality samples. During each of the four sampling events, vertical profiles of temperature, pH, oxygen/reduction potential, dissolved oxygen, and conductivity are measured at intervals not greater than 12 inches. Based on the results from the vertical profile, a surface water sample has been or will be collected from up to three depths at the sampling station. These profiles are used to determine whether the lake is either thermally or chemically stratified and to support geochemical modeling of the pit lake system. If the vertical temperature profile shows that no thermocline is

present in the lake (i.e., there is less than 1°C difference between the surface and bottom temperatures of the lake), then three water-quality samples are collected from within the euphotic zone, defined as the depth of light extinction. If a thermocline is present (i.e., if there is greater than 1°C difference between the surface and bottom temperatures of the lake), a sample is taken from the top, middle, and bottom of the entire water column. In either instance, a composite sample of all three discrete samples is also collected. Table 4-2 shows exceedances of all applicable WQCC standards from samples collected from the Pit Lake. Appendix B2 contains the water quality data collected to date for the pit lake.

NMCC is aware that MECS is concerned about groundwater flowing through the pit lake area and impacting groundwater downgradient of the lake, as well as the potential for impacts to wildlife caused by contact with water in the pit lake. These pit lake water quality data, in conjunction with the activities described in Section 5.2, will enable NMCC to address this issue and, as necessary, develop the appropriate response action.

4.3 Groundwater Monitoring

The NMCC plan for baseline groundwater characterization is provided in the SAP (INTERA, 2010). The program is designed to characterize the pre-operational elevation and configuration of the potentiometric surface and the water quality of the aquifers in the permit area. To this end, water levels are measured and groundwater samples are collected from existing wells on a quarterly basis. As discussed in Section 2.3.1, three aquifers exist in the permit area: a lower crystalline bedrock aquifer; the intermediate Santa Fe Group aquifer system that comprises interbedded sandstones, silts, and clays; and an upper Quaternary alluvial aquifer. The aquifers of greatest importance for water supply in the area of the Site are within the Palomas Basin to the east of the Site and include the Santa Fe Group aquifer system and the alluvial aquifer associated with Las Animas Creek. The groundwater monitoring program incorporates sampling and water level measurements from wells screened in all of these aquifers. In response to comments received on the SAP, NMCC met with NMED on March 10, 2011 to discuss this monitoring well network, go over the rationale for the network, and obtain input from the NMED for ongoing regional surface water and groundwater studies. NMED staff stated that further comments on the groundwater monitoring network would be forthcoming after review of the Stage 1 Abatement Plan, but did not disagree with NMCC's approach.

In an effort to fully characterize hydrologic conditions, the network of monitoring wells has expanded over the course of the baseline monitoring program that commenced in January 2010. Groundwater monitoring locations for each of the first three quarterly events are shown in Figures 4-3, 4-4, and 4-5, respectively. Table 4-3 summarizes exceedances of the WQCC groundwater standards to date. Analytical results of all historical groundwater sampling for constituents to which WQCC standards are available are provided in Appendix B3.

The groundwater monitoring well network used to characterize the quality and potentiometric surface within the three principal aquifer systems in the area of the Copper Flat Mine was based on two primary selection criteria: 1) an understanding of well construction details, and 2) agency and public comments on the initial baseline characterization work conducted by Alta Gold in the 1990s in partial fulfillment of the environmental review conducted under the National Environmental Policy Act described in the draft EIS (BLM, 1996).

Alta Gold collected baseline water quality and water level data that primarily focused on the immediate vicinity of the mine permit boundary and production well field defined in the draft EIS. During public review of the draft EIS, Alta Gold's groundwater characterization program received criticism from the public and state agencies in the form of comments on the draft EIS and in DBS&A (1998) for being limited only to the localized areas of the mine and the production well field. In response to these concerns, Alta Gold's consultant, SRK, developed a revised monitoring program to expand the breadth of groundwater sampling and water level measurements to include areas beyond the immediate vicinity of the mine and production well field (SRK, 1997a).

NMCC obtained from SRK all available well construction details for project wells considered as part of the Alta Gold Project. Well construction details, including total depth of well, depth to top and bottom of well screen, well diameter, casing materials and boring logs (where available) were used to identify monitoring wells that were suitable for collecting groundwater quality samples or water level measurements. Based on this information from the 1990s from SRK (1997a) and on well construction details for the wells, NMCC proposed a quarterly sampling program to characterize the Quaternary alluvial, Santa Fe Group, and crystalline bedrock aquifer systems using existing wells. The first quarter of sampling conducted in January 2010 included gauging water levels from 19 wells and sampling water quality from 8 groundwater wells (2 within the crystalline bedrock aquifer, 1 within the Quaternary alluvial aquifer, and 5 within the Santa Fe Group aquifer system) (Figure 4-3). Due to access restrictions that prevented sampling or gauging on private lands, the baseline work was limited to existing wells located within the mine permit boundary.

To expand the breadth of the sampling program, in June through July of 2010 (Quarter 2), NMCC increased the number of water quality samples collected from 8 to 16, and expanded the number of wells proposed for gauging from 19 to 37. This larger set of wells was distributed over a larger area that extended to the north and south of the production well field and included wells on Las Animas and Percha Creeks (Figure 4-4). During this initial second-quarter visit to many of these wells, access issues prevented NMCC from collecting water levels or water quality samples from all of the proposed wells. Instead of the 37 wells proposed for gauging water levels, only 23 were accessible for measuring a water level. For example, continued access restrictions prevented sampling or gauging on some private and public lands (i.e., Saladone well, Airstrip well, MW-1, MW-2, MW-4, MW-5, MW-8, Highway well, Upper Percha well, and Lower Percha well). Restricted access at MW-6 due to the landing plate prevented NMCC from obtaining a water level. However, the owner was available to turn on the pump test that allowed for a water quality sample to be collected.

Working within the limitations of the infrastructure in place at existing monitoring wells proposed for sampling and gauging, NMCC collected 20 water quality samples and gauged 33 wells as part of the third quarter of baseline sampling (Figure 4-5). Further progress with obtaining access agreements permitted NMCC to access additional wells screened in the crystalline bedrock aquifer to the west and to the south of the mine permit boundary and to gain access to wells east of the mine permit boundary in the Santa Fe Group aquifer system and alluvial aquifer. However, during the third-quarter visits to some of these wells, access issues prevented NMCC from collecting water levels or water quality samples from all of the proposed wells:

- Overgrown vegetation on the access road to MW-5 prevented NMCC from collecting a water quality sample.
- A water level could not be collected from the Saladone well at Ladder Ranch because it had been destroyed.
- Water levels and water quality samples could not be collected from MW-4, Highway well, Upper Percha well, and Lower Percha well because equipment in the wells was plumbed directly to a stock tank and there were no well access ports to obtain a water level measurement.
- The Delores well could not be located.
- The absence of an access port large enough to accommodate a water level meter on some of the wells prevented water levels from being measured (in some cases, however, existing pumps or windmills permitted NMCC to collect a water quality sample, e.g., MW-1, MW-2, and MW-6).

The wells used to collect information as part of the fourth quarter of gauging and sampling, planned for April 2011, once again will be proposed based on obtaining permission to access and sample the wells from landowners and land management agencies, as well as well on construction details and well distribution throughout the project area. NMCC will discuss these wells with MMD and NMED to ensure the wells used to

collect water level and water quality data, given existing access constraints, are appropriate for characterizing baseline data.

NMCC is aware that MECS is concerned about groundwater impacts associated with the seepage from the unlined tailings impoundment and ARD effects. These data, in conjunction with the activities described in Section 5.0 will enable NMCC to address this issue and, as necessary, develop a response action.

5 Proposed Characterization Activities

As discussed above, the abatement issues identified by MECS are summarized as follows:

- Potential groundwater impacts from the existing unlined tailings impoundment.
- Potential groundwater impacts from the existing pit lake.
- Potential impacts to wildlife caused by exposure to the existing pit lake.
- Potential groundwater impacts caused by ARD from existing exposed waste rock.

The historical and baseline characterization data described in the preceding sections provide important information to help address MECS' concerns. The following subsections describe NMCC's approach to supplementing the historical and baseline data that will provide the basis for (1) determining if implementation of a remedial action is required, and if so, (2) selecting the appropriate abatement technology.

The SAP, which has been reviewed by MECS, contains standard operating procedures for the ongoing baseline characterization field activities as well as the activities discussed in the following subsections. The comments made by NMED on pertinent sections of the SAP will be addressed in the Stage 1 Investigation Report. NMCC attended a meeting with the agencies to discuss these comments as well as NMCC's proposed action plan for these comments on March 21, 2011. The state agencies agreed with NMCC's proposed approach to address these comments. In general, the more significant SAP comments will be addressed as part of the Baseline Characterization Report and the regional hydrologic analysis that will be performed as part of the BLM's EIS process. NMED will be an integral part of this process where water issues are concerned. The activities proposed below relate specifically to the abatement issues identified above.

5.1 Characterization of Tailings Dam Impacts

It is clear from the data described in the preceding sections, that impacts to groundwater have occurred as a result of seepage past the tailings impoundment. This subsection describes the proposed additional data to be collected to further refine NMCC's understanding of this issue.

5.1.1 Geology of the Tailings Dam Area

As described most recently in Raugust (2003), the tailings impoundment (or tailings dam) consists of an earthen embankment constructed across a minor valley. The tailings impoundment is approximately 6,600 ft long with a maximum toe-to-crest height of 60 ft. The impoundment was divided into north and south cells. During the approximate three months of operation, approximately 1.2 million tons of tailings were deposited into the north cell (Figure 5-1). The existing tailings cover an area of approximately 60 acres.

Extensive engineering and hydrogeologic studies have been completed and numerous reports prepared. Table 7 of Raugust (2003) provides a summary of the existing reports, including authors, dates, and purposes. Raugust (2003) also provides an excellent summary of these studies, and this document is provided as Appendix C.

Several conclusions which were drawn from these studies that are pertinent to the Stage 1 Abatement Investigation are summarized as follows:

- The compacted clay liner did not prevent seepage from migrating past the toe of the impoundment.
- A potential paleochannel near the center of the impoundment may be the source for seepage migration beyond the toe of the impoundment.
- There are three hydrologic zones beneath the tailings impoundment (Raugust, 2003):
  - An upper unconfined perched aquifer that contains sands and gravels located adjacent to and down-gradient of the tailings impoundment which dips and thickens to the east where the aquifer becomes confined.
  - An underlying clay layer up to 150 ft thick.
  - An underlying clayey, silty sand aquifer of the upper Santa Fe Group that is confined in the vicinity of the tailings impoundment and becomes unconfined to the west where the unit outcrops at the surface. This unit is believed to be 200 ft thick (SRK, 1998).

Newcomer (1993) attributed downgradient impacts from tailings seepage to a paleochannel, containing gravels and coarse-grained sand and a basalt flow buried about 10 ft below the original land surface in the central part of the tailings impoundment. Based on Newcomer's interpretation, the paleochannel and the basalt create a zone (oriented east-west) of high permeability which was believed to be a preferred pathway for tailings seepage to migrate to the upper alluvial aquifer.

In 1994, ABC/SRK performed a pumping test of monitoring well GWQ94-17 and the results indicated that the upper and lower aquifers described above are not hydraulically connected. Therefore, according to the investigations summarized above, the clay layer affects the hydraulic connection between the shallow alluvial aquifer and deeper zones within the Santa Fe Group and must also have an effect on the migration of tailings seepage in this area.

Review of historical geologic information reveals that of the more than 40 available geologic logs in the vicinity of the tailings impoundment area, the majority of the logs indicate the presence of the clay layer referred to in Raugust (2003) and the PFEIS (BLM, 1999) (Appendix D). Most of these borings are located just east of the tailings impoundment. The clay is typically logged as red in color. The geologic setting includes pyroclastic breccias and flows in some areas that could have been altered to material that includes a proportion of clay Dunn (1984) also notes that there are Santa Fe Group clastics east of the volcanic and intrusive center (east of the Animas Hills), some of which are interbedded with basalt. This is corroborated by the geologic logs referenced above as some of the geologic logs that include clay layers also include thin lenses of basalt within these clay zones. If the clay layer is associated with volcanic or volcano-clastic deposits, the unit may pinch out to the east.

The paleochannel and the clay layer described above have had an influence on the tailings seepage impacts to groundwater in this area. A detailed map and cross section of the stratigraphy in the vicinity of the tailings impoundment employing the numerous borehole data available will be completed. Appendix D contains the borehole logs that will be evaluated to complete this geologic analysis for the Stage I Abatement investigation in order to evaluate the potential impacts to tailings seepage migration and to evaluate the ideal location for a monitoring well. Boreholes will be geo-referenced to the extent possible with the available information. In addition, E-W and N-S cross sections in the vicinity of the tailings impoundment will be developed and references for borehole locations used for the analysis will be provided on the cross sections. These data will be incorporated into the geologic block model for the Site and used to inform the hydrologic modeling that will be completed as part of the EIS.

5.1.2 Groundwater Impacts in the Tailings Dam Area

NMCC acknowledges that additional groundwater characterization data will be needed to define the extent of the tailings seepage impacts. Before deciding on the best locations for new wells, it is important to analyze existing data. The tailings seepage impacts are best illustrated by looking at concentrations of sulfate and TDS in this area as well as groundwater concentrations over time.

Figure 5-2 is a time series plot of sulfate and TDS concentrations in well NP-3 from October 1981 to October 2010. NP-3 is a shallow alluvial monitoring well which is located immediately downgradient from the tailings impoundment, approximately mid-center of the impoundment. Clearly illustrated in this figure is the rise in concentrations in the early 1980s, likely resulting from tailings deposition that began in 1982, and the subsequent seepage impacts causing a rise in sulfate and TDS concentrations. Beginning in about 1987, concentrations in samples from NP-3 appear to level off for both TDS and sulfate and have remained relatively constant. Figure 5-3 is a time series plot of sulfate and TDS concentrations in NP-4, a shallow alluvial well immediately to the north of the tailings impoundment; and Figure 5-4 is a time series plot of sulfate and TDS concentrations for NP-2, a shallow alluvial well to the south of the tailings impoundment. Except for a slight increase above the TDS standard for NP-2 circa 1995 and a slight increase in both sulfate and TDS for NP-4, again circa 1995, these data do not indicate elevated concentrations of sulfate or TDS in these areas, and demonstrate that the sulfate and TDS plumes are bound to the north and south. Therefore, the plume needs to be bound in the downgradient direction.

Figure 5-5 shows the vertical distribution of these constituents in all wells from the tailings impoundment area. As illustrated in Figure 5-5, the WQCC standards are exceeded for TDS and sulfate at two distinct horizons in the groundwater directly downgradient from the tailings impoundment, at approximately 50 ft below ground surface and approximately 80 to 110 ft below ground surface. In order to define the downgradient and vertical extent of the tailings seepage plume, additional characterization data will be needed to the east of the tailings impoundment.

Figure 5-6 illustrates the groundwater monitoring well network at the Site and the proposed location of a new monitoring well pair to characterize the extent of the TDS and sulfate plume. A well pair is proposed in order to evaluate the extent of the plume in the shallow and deep zones described earlier. The exact location for this well pair will be informed by the geologic analysis described in the previous subsection and is subject to change. All new wells at the Site will be installed in accordance with NMED's guidance for monitoring well construction and the Office of the State Engineer's requirements for well installation.

The new monitoring well pair will be sampled in accordance with the standard operating procedures provided in the SAP and analyzed for the parameters provided in Table 5-1.

5.2 Characterization of Potential Impacts of the Pit Lake

5.2.1 Pit Lake Hydraulics

Constituent concentrations in pit lake water quality samples exceed WQCC standards. Therefore, the pit lake could be a source for further groundwater impacts if these constituents migrate away from the lake in the direction of regional groundwater flow to the east/southeast (i.e., if the pit lake is a "flow-through" system). Historical and baseline data reveal that the pit lake is a hydraulic sink (i.e., all groundwater flow is towards the pit). This is often the case for pit lakes in the arid southwest as evaporation (i.e., the amount of water leaving the system) is usually greater than precipitation (i.e., the amount of water entering the system). Figure 2-7 adapted from the PFEIS (BLM, 1999) and discussed in Section 2.3.2.1, is a schematic diagram which illustrates this concept. MECS requires further analysis and validation of this conceptual model using current data.

Ongoing baseline data collection to address this concern will enable further confirmation of this conceptual model through the following activities:

- Ongoing data collection from the onsite meteorological station, specifically precipitation and pan evaporation, will be used to complete site-specific water balance calculations.
- New survey data for water levels in monitoring wells near the pit lake and pit lake water elevation will be used to more accurately measure the potentiometric surface in relation to that of the pit lake elevation. Pit lake elevations will be measured at the same time as monitoring well water levels, and groundwater flow directions will be computed.
- Four quarters of water level data will be used to evaluate potential seasonal effects on groundwater flow in the vicinity of the pit lake.
- Evaluation of water quality samples from the pit lake, upgradient and downgradient wells will be completed to analyze potential wildlife exposure and changes to water quality parameters through time.

As described in Section 4, water quality investigations are underway to evaluate the potential for pit lake impacts to water quality. Figures 5-7 and 5-8 are time series plots for sulfate and TDS, and key metals, respectively, from GWQ96-22A, a monitoring well located upgradient of the pit lake (Figure 5-6) based on the established regional gradient. Except for manganese, all constituents of concern are below WQCC standards. Figures 5-9 and 5-10 are time series plots for sulfate and TDS, and key metals, respectively, from GWQ96-23A, a monitoring well located downgradient of the pit lake, based on the established regional gradient. Similarly, except for manganese, all constituents of concern are below WQCC standards. These data support the conceptual model that the pit lake is a hydraulic sink; however, further analysis as described above will be added to validate this important conceptual model.

5.2.2 Wildlife Exposure

Existing and additional water quality data collected from the pit lake will be compared to wildlife habitat standards for water quality. These data will help guide any mitigation or abatement measures necessary to address this concern.

5.3 Characterization of Acid Rock Drainage

NMCC has initiated a geologic sampling program to address the potential for geologic strata and waste rock to create ARD, to degrade surface or groundwater quality, or to cause a hindrance to reclamation. This sampling program is defined in INTERA (2010). This demonstration is a requirement of MMD's Mine Permit and will generate data sufficient to address MECS' concerns about ARD at the Site. Appendix E provides additional detail on the current geochemical characterization program and addresses some of the comments that were generated from MECS' review of the SAP. Appendix F provides a summary with analysis of historical geochemical data, as well as geochemical data and preliminary analysis from the current program. Also included in Appendix F is a memorandum summarizing how the three data sets from 1996, 1997, and 2010 will ultimately provide key information to address the ARD concerns of MECS as well as the requirement of the MMD Mine Permit application.

The geochemical analysis program includes an assessment of waste rock geochemistry designed to predict the potential geochemical reactivity of waste rock that has been and will be exposed during the proposed mining operation, and to provide input into a future pit lake hydrogeochemical model. This assessment includes characterization of ore-grade materials that will be processed and deposited as tailings in the tailings impoundment.

The material characterization component of the this program will address mineralogy, bulk geochemical characteristics, and the potential of the waste rock and processed ore (tailings) to generate acid or net-neutral drainage. This program will also generate data to form the basis for prediction of future water quality that would result from precipitation contacting the material, and prediction of the impacts this water may have on groundwater, surface water, and pit lake quality at the Site. The data generated from this program will provide essential input to the groundwater flow model to be developed for the Site. The geochemical analysis combined with the hydrologic modeling will form the basis for determining whether abatement measures are, or will be required, to mitigate ARD at the Site. The following subsections contain a general description of the program.

5.3.1 Data Review and Material Type Delineation

NMCC's contractor has reviewed all data available from the previous and current exploration drilling programs, including the drill hole database, drill logs, assay data, and bulk element geochemistry. From this review, the main rock types, alteration types, and oxidation states identified by SRK in the late 1990s have been updated and are identified in Appendix E. The combination of these parameters was used to define material types for the project that are the focus of the geochemical characterization program. This program is defined in more detail in the Materials Characterization Program which is Appendix C of the Plan of Operations.

5.3.2 Sample Interval Selection

Several types of geologic material are available from the exploration drill programs for sampling, including coarse rejects and half-split core from the core and rotary drilling. However, the core will be the preferred sample material. The available half-split core material was sampled for geochemical characterization as it was identified as the best material available for geochemical testing. These core intervals were targeted in the waste rock characterization portion of this sampling program.

In late 1997, SRK collected 46 samples for Acid Base Accounting (ABA) testing, 59 for Net Acid Generation (NAG) testing, 1 for short-term leach testing, and 5 for humidity cell kinetic testing. In addition, 14 samples were collected from the historic tailings impoundment for static test analysis, and approximately 130 samples from waste rock and pit walls were collected for field NAG test and paste chemistry. Figure 1 of Appendix E shows the locations of the surface samples taken in 1997.

These 1997 samples were characterized by lithology, alteration, oxidation, and absence/presence of sulfides. Samples were generated by collecting material from consecutive intervals within the same drill hole, and each sample consisted of a single material type as defined by rock type, alteration type, and oxidation state. These samples were submitted to certified laboratories in Reno, Nevada, for sample preparation and laboratory testing.

Twenty-four additional samples were taken in April 2010 to create a sample database that is vertically and horizontally representative of waste rock associated with the current project. All 24 samples were submitted for ABA, NAG, and multi-element analysis. In addition, 50 ore-grade samples were collected from drill core; 40 of these were selected and analyzed using the Meteoric Water Mobility Procedure (MWMP), and 21 samples were selected for humidity cell testing beginning in January 2011. Figure 1 of Appendix E shows the locations of these 2010 samples.

NMCC's approach to sample selection was designed to ensure that samples with end-member reactivity are sufficiently represented in the program to provide a comprehensive and representative understanding of the full range of geochemical characteristics for each of the material types. To this end, NMCC's contractor has focused on understanding the geological controls on the geochemical behavior of the different materials as the basis for sample selection.

5.3.3 Sample Collection and Field Screening

Geochemical characterization samples were collected by qualified geologists from consecutive intervals within the same drill hole. Each sample consisted of a single material type as defined by rock type, alteration type, and oxidation state.

Once the main material types were delineated and sampled, a number of field tests could be performed to assess broad geochemical behavior of the identified material types and confirm the geological classification of the materials.

Field tests were used in the 1997 geochemical characterization program to identify ideal sampling locations. Because these tests are inexpensive and quick, a significant amount of data can be collected quickly with minimal cost. By using the field screening to define a representative sample set, the "representativeness" of the sample set is more defensible and the number of samples selected for the more expensive static test suite can be minimized.

The field method is referred to as "paste pH and EC" and was used in 1996–1997 to characterize samples, particularly from the waste rock dump. Based on the material type and paste results for that material, samples were selected for laboratory analysis. The field method is summarized as follows:

- Sampling: This involved collecting < 5mm chips from a 5kg sample taken in a cubic meter area of the waste rock. The fines were then split into quarters and one quarter was retained for whole rock and mineralogy analysis, one quarter was used for paste test (which often involved cone and quartering again), and one quarter was kept for NAG testing. This method is employed because water quality in a dump is largely controlled by the fines and this is a good indication of reactivity.
- Testing: The paste test comprises mixing a 1:1 of fines with distilled water and measuring TDS and pH of the resulting solution. Where the water went blue, the sample was analyzed for copper and sulfate by a field colormetric spectrometry.
- NAG Testing: This test involved reacting hydrogen peroxide with the fines and then back titrating with NaOH to determine acid generation.

5.3.4 Geochemical Test Work

Based on the geologic logging and field screening, a representative number of larger samples was selected for standard static testing, including: multi-element analyses, ABA with sulfur speciation, MWMP, and NAG. These static tests are intended to define the potential of a material to generate acid, buffer acid, and/or leach constituents under field conditions.

Based on the results of the field work and static testing, samples of material with an uncertain acid generation potential or leaching characteristics were selected for kinetic testing. Because the static test work assumes that all minerals that have the potential to generate acid, buffer acid, or leach metals will react completely, they can only define the chemical/mineralogical potential of the rock and do not take into account reaction rates that will ultimately control whether the material will actually generate acid, buffer acid, or leach metals under field conditions.

The samples collected in Step 3 were submitted to a certified laboratory for sample preparation and the first phase of static testing at Nevada-certified laboratories as follows:

1. Whole rock analysis using four-acid digest and ICP analysis to determine total metal and metalloid chemistry for 48 elements (ALS Chemex Method ME-MS61).
2. ABA using the modified Sobek method (Memorandum No. 96-79) with sulfur speciation.

3. NAG test reporting final NAG pH and final NAG value after a two-stage hydrogen peroxide digest.
4. MWMP (ASTM D5744-96) with geochemical analysis of the leachate for applicable constituents.

This work was supervised by NMCC's contractor at McClelland Laboratories of Sparks, Nevada, with analysis by Western Environmental Testing Laboratory (WETLab) of Sparks, Nevada; ALS Chemex of Reno, Nevada; and SVL Laboratories of Kellogg, Idaho.

The first phase of geochemical testing was completed to assess the range of reactivity of each of the material types and the results were used to select samples for MWMP testing with geochemical analysis of the leachate for applicable constituents. Samples demonstrating end-member reactivity, as determined from the first phase of static laboratory testing, were selected for MWMP testing to provide a comprehensive and representative understanding of the leaching characteristics of the different material types associated with the Copper Flat deposit. Mineralogical analysis was also completed on about 20 samples to provide a better understanding of the influence geologic controls have on the geochemical behavior of the waste rock and ore.

The new MWMP and mineralogical data were completed in November 2010. The results are described in detail in Appendices E and F.

5.3.5 Kinetic Testing Program

Based on the results of the static and MWMP testing described above, any material types that exhibit uncertain or highly variable geochemical behavior will require further characterization using kinetic test methods to determine the rates and character of longer-term leaching. Twenty-one samples were selected for humidity cell testing, which was initiated in January 2011 (ASTM D-5744-96-7).

5.3.6 Data Validation and Compilation

The geochemical data are being reviewed as they are received to ensure the quality of data and consistency in analyses. NMCC's contractor will then verify the quality of all data and confirm that no anomalies are related to laboratory error prior to interpretation and reporting. At a minimum, NMCC's contractor will utilize their internal standard data validation procedures, although guidance from other sources may also be considered (e.g., U.S. Environmental Protection Agency). All geochemical data collected as part of the static testing program will be compiled into a single database for evaluation.

Preliminary results are presented in Appendix F.

5.3.7 Fate and Transport Modeling

The Copper Flat plan of operations calls for leaving waste rock from previous mining activities in place and extending the waste rock facilities to accommodate waste rock from proposed new mining activities.

Existing and new waste rock have the potential to affect land and water resources through mobilization and transport of mine rock materials, whether as solid or dissolved phases, from the facilities to the surrounding environment. Potential receptors include soils, surface water, and groundwater resources near the facilities.

Static testing and geochemical analyses of existing waste rock and potential future waste rock and pit wall materials revealed a range of results. Some samples were characterized as having acid generation potential, whereas other samples demonstrated a potential to be acid consuming or neutral using the BLM waste rock guidelines for static testing. Kinetic testing of a subset of these mine rock samples began in January 2011 and will be used to characterize potential leachate chemistry and provide the basis for generating chemical release functions (CRFs) that are mathematical descriptions of each constituent of interest's observed time-varying

leachate concentration. When weighted by the mass of each rock type to be produced, the resulting composite CRFs will serve as quantitative measures of leaching behavior to be used to simulate solute chemistry and transport through the waste rock facilities and the underlying variably saturated sediments, and thereby assess potential impacts.

The overall approach will be to complete the characterization of waste rock and its leachate, then assess the impacts resulting from the flow and chemical transformations of the leachate as it moves through the waste rock facilities and the underlying vadose zone to groundwater in the aquifers beneath the proposed facilities. Potential impacts to groundwater will be evaluated with a numerical flow and solute transport model developed from the Site-specific conceptual model. The objective of the vadose zone flow modeling will be to estimate the volumes and flux rates of water moving through the waste rock facilities and through the underlying vadose zone materials, and ultimately to estimate the water fluxes reaching groundwater. Potential impact criteria included the location and magnitude of water flux leaving the waste rock facility (seepage), the time of travel through the facility, and the total time of travel and magnitude of water flux reaching groundwater resources. The analysis will adopt a conservative approach to simulate flow through the facilities and the vadose zone sediments by weighting uncertainties that increased infiltration over those that decreased infiltration.

The vadose zone transport model will assesses potential impacts to groundwater resources by predicting the concentrations and flux rates of selected solutes from the facilities to those resources. The model focuses on geochemical transformation processes that operate within the vadose zone on solid and dissolved phases of critical solutes, including arsenic, antimony, mercury, and others. Potential impact criteria focus on solute concentrations and time-varying solute flux rates in the leachate from the facility and in the water reaching groundwater resources.

If the appropriate assumptions are met, then the current pit lake chemistry may serve as an analog of future pit water and waste rock leachate. If the pit lake water is in equilibrium with the pit wall rock under saturated conditions, the observed pit lake water quality may be a conservative estimator of leachate chemistry formed under variably saturated conditions for both waste rock and the pit wall materials.

5.3.8 Surface Water Monitoring Program

The surface water monitoring program described in Section 4.1, particularly the opportunistic water and soil sampling, is designed to evaluate baseline conditions and reveal if ARD issues caused by runoff from the waste piles are a problem under current site conditions. Four quarters of data will be combined with historical data to evaluate changes over time to surface water conditions and to determine if an ARD process is causing impacts to water quality under current site conditions.

6 Quality Assurance Project Plan

A Quality Assurance Project Plan was developed for the SAP (INTERA, 2010). It is provided as Appendix G.

7 Site Health and Safety Plan

NMCC's contractor has developed a general Site Health and Safety Plan for all characterization activities conducted pursuant to the Copper Flat Stage 1 Abatement Plan. This document is included as Appendix H.

8 Reporting

A Stage 1 Investigation Report will be developed at the conclusion of all field activities and studies described in this plan. The report will include a detailed description of all field investigations, methodology, data analyses, results, quality assurance, conclusions, and recommendations. In addition, as required by 20.6.2.4106.C(6) NMAC, quarterly progress reports summarizing key activities and preliminary findings will be initiated upon receipt of an approval to this Stage 1 Abatement Plan from the NMED.

9 Schedule

The Stage 1 Abatement Investigation Report will be delivered to NMED at the conclusion of all field activities and data analysis. The projected date for completion of this report is January 31, 2012.

10 References

Adrian Brown Consultants (ABC), 1996, Appendix F of Copper Flat project hydrology impact evaluation report.

———. 1997, Copper Flat hydrology impact evaluation post-hearing submittal exhibits, including revised appendices O, F, and L: Report 1356A.970326.

———. 1998, Hydrologic impact evaluation for the proposed action, Copper Flat project: Report 1356A.981219. Prepared for Alta Gold Co., December 19, 1998.

Air Sciences Inc., 1995a, Meteorological data report, Copper Flat project, November 1, 1994 – January 31, 1995, prepared for Alta Gold Company, Truth or Consequences, New Mexico: Lakewood, Colo., Air Sciences, Inc.

———. 1995b, Baseline meteorology report, Copper Flat project, Alta Gold: Lakewood, Colo., Air Sciences, Inc.

Bureau of Land Management (BLM), 1978, Environmental assessment record on Quintana Minerals Corporation's proposed open pit copper mine at Copper Flat, Sierra County, New Mexico: Las Cruces, N. Mex., 170 p.

———. 1996, Draft environmental impact statement, Copper Flat project: Las Cruces, N. Mex., U.S. Department of the Interior. Prepared by ENSR, Fort Collins, Colo.

———. 1999, Preliminary final environmental impact statement, Copper Flat project: Las Cruces, N. Mex., U.S. Department of the Interior, 491 p. Prepared by ENSR, Fort Collins, Colo.

Daniel B. Stephens and Associates, Inc. (DBS&A), 1998, Environmental evaluation report, Copper Flat project. Prepared for the Energy, Mining and Natural Resources Department, Mining and Minerals Division, Santa Fe, New Mexico.

Davie, W., Jr., and Spiegel, Z., 1967, Las Animas Creek hydrographic survey report, geology and water resources of Las Animas Creek and vicinity, Sierra County, New Mexico: New Mexico State Engineering Report.

Dunn, P.G., 1982, Geology of the Copper Flat porphyry copper deposit, Hillsboro, Sierra County, New Mexico in Advances in geology of the porphyry copper deposits, southwestern North America: Tucson, Ariz., University of Arizona Press, p. 313-325.

Dunn, P., 1984, Geologic studies during the development of the Copper Flat porphyry deposit: Mining Engineering, February, 1984, pg.151.

Hawley, J.W., Kennedy, J.F., Ortiz, M., and Carrasco, S., 2004, Digital Hydrogeologic Framework Model of the Rincon Valley and Adjacent areas of Dona Ana, Sierra, and Luna Counties, NM: Addendum to the Creation of a Digital Hydrogeologic Framework Model of the Mesilla Basin and Southern Jornada del Muerto Basin, New Mexico Water Resources Research Institute, New Mexico State University, Technical Report No. 332, June 2004, 12 p.

INTERA, 2010, Sampling and analysis plan for Copper Flat Mine. Prepared for New Mexico Copper Corporation. Submitted to Mining and Minerals Division, New Mexico Energy Minerals and Natural Resources Department, September, 2010.

Kuellmer, F.J., 1955, Geology of a disseminated copper deposit near Hillsboro, Sierra County, New Mexico: New Mexico Bureau of Mines and Mineral Resources Circular 34, 46 p.

Lozinsky, R.P. and J.W. Hawley. 1986. The Palomas Formation of south-central New Mexico -- a formal definition. New Mexico Geology. 8. 4, p: 73-82.

Murray, C. R., 1959, Ground-water conditions in the nonthermal artesian-water basin south of Hot Springs, Sierra County, New Mexico: New Mexico State Engineering Technical Report 10.

Newcomer, R.W., and Finch, S.T., 1993, Water quality and impacts of proposed mine and mill, Copper Flat Mine site, Sierra County, New Mexico, 30 p. Prepared for Gold Express Corporation.

Newcomer, R. W. Jr., Shomaker, J.W., and Finch, S.T., Jr., 1993, Hydrologic assessment, Copper Flat project, Sierra County, New Mexico. Prepared for Gold Express Corporation.

New Mexico Environment Department Groundwater Quality Bureau (NMED GWQB), 2008, Letter to Mr. George Lotspeich regarding Abatement plan required at Copper Flat Mine site, DP-1, August 20, 2 p.

Raugust, J.S., 2003, The natural defenses of Copper Flat Sierra County, New Mexico: New Mexico Bureau of Geology and Mineral Resources Open-File Report 475, Socorro, N. Mex., New Mexico Institute of Mining and Technology.

Seaber, P.R., Kapinos, F.P., and Knapp, G.L., 1987, Hydrologic unit maps: U.S. Geological Survey Water-Supply Paper 2294, 63 p.

Seager, W.R., Shafiqullah, M., Hawley, J.W., and Marvin, R.F., 1984, New K-Ar dates from basalts and the evolution of the southern Rio Grande rift: Geological Society of America Bulletin, v. 95, p. 87–99.

Seager, W.R. and J.W. Hawley. 1973. Geology of Rincon quadrangle, New Mexico. New Mexico Bureau of Mines and Mineral Resources Bulletin 102, 56 p.

Segerstrom, K. and Antweiler, J.C., III, 1975, Placer-gold deposits of the Las Animas District, Sierra County, New Mexico: USGS OFR 75-206.

Sergent, Hauskins, and Beckwith (SHB), 1980, Geotechnical and design development report, tailings dam and disposal area, Quintana Minerals Corporation, Copper Flat Project, Golddust, New Mexico. Technical report prepared for Quintana Minerals.

Steffen, Robertson and Kirsten, Inc. (SRK), 1995, Copper Flat Mine, hydrological studies: Reno, Nev.

———. 1997a, Copper Flat Mine project monitoring plans, monitoring plan R3F-05/13/97, Consultant's report prepared for the Alta Gold Co. by SRK, Adrian Brown Associates, and Southwest Rangeland Services, May 1997, 84 p.

———. 1997b, Copper Flat Mine compilation of pit lake studies, prepared by SRK for Alta Gold Co., October 1997, 76 p.

———. 1998, Tailings seepage modeling, Copper Flat Mine: Lakewood, Colo. August 1998.

———. 2010a, Preliminary draft Copper Flat plan of operations, New Mexico Copper Corporation: SRK Consulting, Reno, Nevada.

———. 2010b, NI-43-101 Preliminary assessment, THEMAC Resources Group Limited, Copper Flat project, Sierra County, New Mexico: Lakewood, Colo. Prepared by SRK Consulting for THEMAC Resource Group Limited, June 30, 2010.

SRK Consulting, 2010, NI-43-101 Preliminary Assessment, THEMAC Resources Group Limited, Copper Flat Project, Sierra County, New Mexico: Lakewood, Colo. Prepared by SRK Consulting for THEMAC Resource Group Limited, June 30, 2010.

Wilson, C.A., Orr, C.A., White, R.R., and Roybal, R.G., 1981, Water resources of the Rincon and Mesilla valleys and adjacent areas: New Mexico State Engineering Report No. 43.

FIGURES



Imagery Information:
-Landsat Imagery from
University of Maryland NLCD

Figure 1-1
Site Location
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\1-1_SiteLocationMap.mxd

00437



STRATIGRAPHY

TERTIARY - QUATERNARY	CRETACEOUS	PALEOZOIC AND PRECAMBRIAN
Quaternary Alluvium (Qvy+Qvo)	Late Cretaceous – Silicic Intrusives (Kli)	Paleozoic Siliciastic and Carbonate Sedimentary Rocks (pC through PM)
Tertiary Volcanics (TQb+Tv)	Cretaceous Latite – Andesite Intrusives (Kql+Kd+Kls)	
Tertiary Santa Fe Group (Tsfp+Tsf)	Andesite rocks near Copper Flat (Ka)	

LEGEND

NORMAL FAULT, BALL ON DOWNTHROWN SIDE; DASHED WHERE INFERRED, DOTTED WHERE BURIED.

CONTACT

A A' CROSS SECTION LOCATION

NORTH

0 5,825 11,650

FEET

SOURCES:
(1) HARLEY (1934)
(2) SEAGER ET AL. (1982)
(3) HEDLUND (1977)
(4) ALMINAS ET AL. (1975)

(see Figure 2-2 for cross section detail)

from BLM, 1999

Figure 2-1
Regional Surface Geology
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\2-1_general_surface_geology.mxd

A

A'



Path: S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\2-2_cross-sectionAA.mxd

LEGEND:

QUATERNARY
- Qvy, Qvo — Stream Alluvium

TERTIARY
- Tsfp — Palomas Formation
- Tsfp Clay — Palomas Formation
- Tsf — Rincon Valley Formation
- Tv — Tertiary Volcanics

CRETACEOUS
- Ka, Kis — Volcanics and Intrusives

PALEOZOIC
- Bedrock Carbonate and Clastic Rocks

SOURCES:
(1) HARLEY (1934)
(2) SEAGER ET AL. (1982)
(3) HEDLUND (1977)
(4) ALMINAS ET AL. (1975)

SCALE IN FEET
VERTICAL 1500 0'
HORIZONTAL 6000 0'

(see Figure 2-1 for cross section location)

from BLM, 1999

Figure 2-2
Schematic Geologic Cross Section (A-A')
New Mexico Copper Corporation



from BLM, 1999

Figure 2-3
Geologic Structural Features of the Region
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\2-3_regional-features.mxd



from John W. Shomaker, Inc., 1993

Figure 2-4
Schematic of Groundwater Flow System

New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\2-4_concep_hydrogeo.mxd



4300 WATER TABLE ELEVATION

from ABC, 1998B

Figure 2-5
Water Level Contours
New Mexico Copper Corporation

Path: S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\2-5_wtr-level-contours.mxd



from ABC, 1997

Figure 2-6
Water Level Map of
Copper Flat Pit Area

New Mexico Copper Corporation

Path: S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\2-6_wtr-table-map.mxd



Figure 2-7
Schematic Groundwater Flow Direction in the Vicinity of the Pit Lake

New Mexico Copper Corporation

from SRK, 1998

Path: S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\2-7_well_WQReports.mxd



N
W E
S

Watersheds:
USGS Hydrologic Unit Map
Mine Boundary:
Tom Van Bebber
Imagery Information:
-USGS 7.5-Minutes County DOQQ mosaic
Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

0 3,500 7,000 14,000 21,000
Feet

Legend

- Identified Spring
- Proposed Mine Permit Boundary

Watersheds
- Caballo
- El Paso-Las Cruces
- Sub-Watershed

Figure 2-8
Spring and Stream Locations
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\2-8_spring_locations.mxd



from SRK, 1995

Figure 2-9
Conceptual Design,
Tailings Seepage Control

New Mexico Copper Corporation

Path: S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\2-9_seepage-control.mxd



Watersheds:
USGS Hydrologic Unit Map
Mine Boundary:
Tom Van Bebber
Imagery Information:
-USGS 7.5-Minutes County DOQQ mosaic
Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

0 3,500 7,000 14,000 21,000
Feet

Legend

- Surface Water Monitoring Location
- Proposed Mine Permit Boundary

Watersheds
- Caballo
- El Paso-Las Cruces
- Sub-Watershed

Figure 2-10
Surface Water Monitoring Locations
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\2-10_SW-mineArea.mxd



Mine Boundary:
Tom Van Bebber
Imagery Information:
-USGS 7.5-Minutes Quads; Skute Stone Arroyo & Hillsboro
Projection Information:
-New Mexico State Plane West, NAD 1927

Legend

Proposed Mine Permit Boundary

Figure 3-1
Proposed Copper Flat Permit Area with Topography

New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\3-1_proposed-permit_topo.mxd

N
W E
S

0 1,000 2,000 4,000 6,000

Feet

Mine Boundary:
Tom Van Bebber
Imagery Information:
-USGS 7.5-Minutes County DOQQ
mosaic Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

Legend

Proposed Mine Permit Boundary

Figure 3-2
Proposed Copper Flat Permit Area with Air Photography

New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\3-2_proposed-permit_photo.mxd

Figure 3-3
Aerial View to the West at Copper Flat Mine, 1982

New Mexico Copper Corporation

from Hydro Resources, Inc.

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\3-3_1982photo-west.mxd

Figure 3-4
Aerial View to the East at Copper Flat Mine, 1982

New Mexico Copper Corporation

from Hydro Resources, Inc.

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\3-4_1982photo-east.mxd



0 50 100 200

Feet

Imagery Information:
-USGS 7.5-Minutes County DOQQ mosaic
Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

Legend

Depth of Pit Bottom in Feet

Figure 3-5
Bathymetry Map of the Pit Lake
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\3-5_LakeProfiles.mxd



Figure 3-6
Sulfate Concentration in the Mine Pit Lake

New Mexico Copper Corporation

from Raugust, 2003

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\3-6_SulfateTrends.mxd



from Raugust, 2003

Figure 3-7
Total Dissolved Solid Concentrations in the Mine Pit Lake

New Mexico Copper Corporation

Path: S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\3-7_TDSTrends.mxd



from Raugust, 2003

Figure 3-8
pH in the Mine Pit Lake

New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\3-8_pHTrends.mxd



LEGEND:

- MONITORING WELL
- WELL
- IRRIGATION WELL
- WINDMILL
- SPRING
- STREAM GAGING STATION OR SURFACE WATER SAMPLE SITE

NORTH

0 5,825 11,650

FEET

from SRK, Preliminary Final Environmental Impact Statement March 1999

Figure 3-9
Spring and Regional Well Locations
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\3-9_regionalGWwells.mxd



N
W E
S

Well Locations:
INTERA, SRK, or OSE
Mine Boundary:
Tom Van Bebber
Imagery Information:
-USGS 7.5-Minutes County DOQQ mosaic
Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

0 3,000 6,000 12,000 18,000
Feet

Legend

Number of Samples Collected from 1975 - 2011
- 1 - 2
- 3 - 7
- 8 - 38
- 39 - 99

Proposed Mine Permit Boundary

- BLM
- Private
- State
- Reclamation

Figure 4-1
Historical Groundwater Quality Sampling
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\4-1_GWsampleFrequency.mxd

00457



N
W E
S

Watersheds:
USGS Hydrologic Unit Map
Mine Boundary:
Tom Van Bebber
Imagery Information:
-USGS 7.5-Minutes County DOQQ mosaic
Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

0 3,500 7,000 14,000 21,000
Feet

Legend

- Surface Water Monitoring Location
- Proposed Mine Permit Boundary

Watersheds
- Caballo
- El Paso-Las Cruces
- Sub-Watershed

Figure 4-2
Surface Water Monitoring Locations
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\4-2_SWmonLocs.mxd



N
W E
S

Well Locations:
INTERA, SRK, or OSE
Mine Boundary:
Tom Van Bebber
Imagery Information:
-USGS 7.5-Minutes County DOQQ mosaic
Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

0 3,000 6,000 12,000 18,000
Feet

Legend

- Q1 Groundwater Monitoring Location
- Proposed Mine Permit Boundary

Figure 4-3
2010 Q1 Groundwater Monitoring Locations
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\4-3_GWQ1monLocs.mxd

00459



Well Locations:
INTERA, SRK, or OSE
Mine Boundary:
Tom Van Bebber
Imagery Information:
-USGS 7.5-Minutes County DOQQ mosaic
Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

0 3,000 6,000 12,000 18,000
Feet

Legend

- Q2 Groundwater Monitoring Location
- Proposed Mine Permit Boundary

Figure 4-4
2010 Q2 Groundwater Monitoring Locations
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\4-4_GWQ2monLocs.mxd



N
W E
S

Well Locations:
INTERA, SRK, or OSE
Mine Boundary:
Tom Van Bebber
Imagery Information:
-USGS 7.5-Minutes County DOQQ mosaic
Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

0 3,000 6,000 12,000 18,000
Feet

Legend

- Q3 Groundwater Monitoring Location
- Proposed Mine Permit Boundary

Figure 4-5
2010 Q3 Groundwater Monitoring Locations
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\4-5_GWQ3monLocs.mxd

00461



Point No.	ΔL	Station	Azimuth (Degrees)	State Plane Coordinates North	State Plane Coordinates East
1	0	0+00		710656	601660
	414.6		95.00		
2		4+15		710620	602073
	947.0		89.31		
3		13+62		710628	603020
	127.1		curve		
4		14+89		710712	603100
	3508.0		.016		
5		49+97		714220	603102
	934.1		curve		
6		59+31		715012	602700
	696.9		305.50		
7		66+28		715420	602135
	0				
8		0+00*		713035	601490
	1613.0				
9		16+13* 38+15**		713038	603101.3

* Divider Dike
** Starter Dam

REVISIONS:	TOPOGRAPHIC PLAN SHOWING LOCATION OF TEST BORINGS	
11-6-80	TAILINGS DAM CONSTRUCTION COPPER FLAT PARTNERSHIP QUINTANA MINERALS CORPORATION, MGR. HILLSBORO, NEW MEXICO	
DESIGNED BY: J.E.H.	SERGENT, HAUSKINS & BECKWITH CONSULTING SOIL AND FOUNDATION ENGINEERS	JOB NO.: SHB E80-1030
DRAWN BY: R.S.R.		SHEET: 1 OF 7
REVIEWED BY: R.D.B.		
DATE: 10-15-80		

from New Mexico Bureau of Geology and Mineral Resources Open-file report 475;
The Natural Defenses of Copper Flat Sierra County, New Mexico, August 2003

Figure 5-1
Tailings Impoundment Layout
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\5-1_TailingsImpoundment.mxd



Notes:

NMWQCC = New Mexico Water Quality Control Commission

Non-detect measurements are plotted at half the analyte detection limit.

NMWQCC Standards (mg/L)

Sulfate = 600.0

Total Dissolved Solids = 1000.0

Legend

- Sulfate
- Total Dissolved Solids
- Detect
- Non-detect
- Analyte standard (shown if exceedences are present)

Figure 5-2
NP-3 Sulfate and
Total Dissolved Solids
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\5-2_3_4_8_9_10_11_timeSeries.pptx



Notes:

NMWQCC = New Mexico Water Quality Control Commission

Non-detect measurements are plotted at half the analyte detection limit.

NMWQCC Standards (mg/L)

Sulfate = 600.0

Total Dissolved Solids = 1000.0

Legend

- Sulfate
- Total Dissolved Solids
- Detect
- Non-detect
- Analyte standard (shown if exceedences are present)

Figure 5-3
NP-4 Sulfate and
Total Dissolved Solids
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\5-2_3_4_8_9_10_11_timeSeries.pptx



Notes:

NMWQCC = New Mexico Water Quality Control Commission

Non-detect measurements are plotted at half the analyte detection limit.

NMWQCC Standards (mg/L)

Sulfate = 600.0

Total Dissolved Solids = 1000.0

Legend

- Sulfate
- Total Dissolved Solids
- Detect
- Non-detect
- Analyte standard (shown if exceedences are present)

Figure 5-4
NP-2 Sulfate and
Total Dissolved Solids
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\5-2_3_4_8_9_10_11_timeSeries.pptx

Wells

GWQ-10
GWQ-11
GWQ-3
GWQ-5
GWQ-6
GWQ-7
GWQ94-13
GWQ94-15
GWQ94-16
GWQ94-20
GWQ94-21B
GWQ96-22A
GWQ96-22B
GWQ96-23A
GWQ96-23B
IW-1
IW-2
IW-3
NP-1
NP-2
NP-3



Figure 5-5
Sulfate and TDS Concentration Depth Profiles
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\5-5_TDSsulfateVSdepth.mxd



N
W E
S

Well Locations:
INTERA, SRK, or OSE
Mine Boundary:
Tom Van Bebber
Imagery Information:
-USGS 7.5-Minutes County DOQQ mosaic
Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

0 3,000 6,000 12,000 18,000
Feet

Legend

- Monitoring Well in Baseline Program
- Proposed Monitoring Well Nest
- Proposed Mine Permit Boundary
- BLM
- Private
- State
- Reclamation

Figure 5-6
Actual and Proposed Monitoring Wells
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\5-6_monitoringWells.mxd

00467



Notes:

NMWQCC = New Mexico Water Quality Control Commission

Non-detect measurements are plotted at half the analyte detection limit.

NMWQCC Standards (mg/L)

Sulfate = 600.0

Total Dissolved Solids = 1000.0

Legend

- Sulfate
- Total Dissolved Solids
- Detect
- Non-detect
- Analyte standard (shown if exceedences are present)

Figure 5-7
GWQ96-22A Sulfate and Total Dissolved Solids
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\5-2_3_4_8_9_10_11_timeSeries.pptx



Notes:

NMWQCC = New Mexico Water Quality Control Commission

Non-detect measurements are plotted at half the analyte detection limit.

NMWQCC Standards (mg/L)

Arsenic = 0.1
Copper = 1.0
Manganese=0.2
Uranium=0.03

Legend

- Arsenic
- Copper
- Manganese
- Uranium
- Detect
- Non-detect
- Analyte standard (shown if exceedences are present)

Figure 5-8
GWQ96-22A Metals
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\5-2_3_4_8_9_10_11_timeSeries.pptx

00469



Notes:

NMWQCC = New Mexico Water Quality Control Commission

Non-detect measurements are plotted at half the analyte detection limit.

NMWQCC Standards (mg/L)

Sulfate = 600.0

Total Dissolved Solids = 1000.0

Legend

- Sulfate
- Total Dissolved Solids
- Detect
- Non-detect
- Analyte standard (shown if exceedences are present)

Figure 5-9
GWQ96-23A Sulfate and Total Dissolved Solids
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\5-2_3_4_8_9_10_11_timeSeries.pptx



Notes:

NMWQCC = New Mexico Water Quality Control Commission

Non-detect measurements are plotted at half the analyte detection limit.

NMWQCC Standards (mg/L)

Arsenic = 0.1
Copper = 1.0
Manganese=0.2
Uranium=0.03

Legend

- Arsenic
- Copper
- Manganese
- Uranium
- Detect
- Non-detect
- Analyte standard (shown if exceedences are present)

INTERA

Figure 5-10
GWQ96-23A Metals
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\Reports\AbatementPlan\5-2_3_4_8_9_10_11_timeSeries.pptx

00471

TABLES

Table 2-1
Stratigraphy of the Copper Flat Area

Era	Geologic Unit		Thickness (ft)
Cenozoic 0–65 million years ago (Ma)	Pleistocene and Holocene valley alluvium		10–70
	Pleistocene river, arroyo, and fan deposits		50–100
	Pliocene basalt flows, dikes, and plugs		50–200
	Upper Santa Fe Group fanglomerates (Palomas Formation)		300–100
	Santa Fe Group, Rincon Formation		1000–2000
	Tertiary volcanics		1000
Mesozoic 65–225 Ma	Quartz latite dikes Intermediate composition intrusive Late Cretaceous andesite dikes Late Cretaceous silicic intrusives	**Copper Flat volcanic and intrusive (mineralization associated with emplacement)**	>3000
	Sandstone		
	Mancos Shale (not exposed)		300–400
	Dakota Sandstone (not exposed)		100–200
Paleozoic 225–570 Ma	Manazano Group sedimentary rocks. Abo Sandstone, Yeso Formation shales, sandstones, and gypsum deposits, and San Andres Limestone. Not exposed west of Rio Grande at Site.		1000–2000
	Pennsylvanian carbonate rocks including Syrena, Oswaldo, and Magdalena Groups, minor conglomeratic sandstone and cherty massive limestone.		400–1000
	Devonian and Mississippian carbonate rocks (Kelly Limestone, Lake Valley Limestone, Caballero Formation) and Percha Shale.		200–500
	Ordovician Montoya Group and Fusselman Dolomite.		250–600
	Cambrian-Ordovician Bliss Sandstone and El Paso Group Limestone.		500–700
Precambrian 570–1,500 Ma	Precambrian massive granite		

Source: BLM, 1999, Tables 3-1 and 3-2

Table 3-1
Historical Flow and Water Quality Parameters

Location	Date	Description	Flow (cfs)	pH	Conductivity (µS/cm)	Temperature (°C)
Las Animas Creek	1967	Upper Reach	1.0 – 2.0	NM	NM	NM
Las Animas Creek	1967	Middle Reach	1.0 – 1.5	NM	NM	NM
Las Animas Creek	1996	LAC-E	0.546	8.2	400	17
Percha Box	1996	1200’ u/s of Box entry	Dry	NA	NA	NA
Percha Box	1996	700’ u/s of Box entry	0	8.1	600	32
Percha Box	1996	400’ u/s of Box entry	Dry	NA	NA	NA
Percha Box	1996	Box entry	0.265	7.7	500	23
Percha Box	1996	1500’ d/s of Box entry	0.446	8.2	500	23
Percha Box	1996	Box exit	1.02	8.4	400	25
Percha Box	1996	2400’ d/s of Box exit	0	9.3	400	32
Percha Box	1996	2500’ d/s of Box exit	Dry	NA	NA	NA
Percha Box	1996	5000’ d/s of Box exit	0.394	9.0	400	28
Percha Box	1996	5400’ d/s of Box exit	0	9.0	400	32
Percha Box	1996	5500’ d/s of Box exit	Dry	NA	NA	NA
Percha Box	1996	3 miles d/s of Box exit	Dry	NA	NA	NA
Percha Box	1996	5 miles d/s of Box exit	Dry	NA	NA	NA
Grayback Arroyo	4/1/93	SWQ-1	1 – 2	8.3	1150	NM
Grayback Arroyo	5/7/93	SWQ-1	Dry	NA	NA	NA
Grayback Arroyo	3/31/93	SWQ-2	< 1	7.7	3150	NM
Grayback Arroyo	3/31/93	SWQ-3	12.5	8.1	3330	NM
Spring/Seep	4/1/93	BG	1 – 2	8.2	1090	NM
Spring/Seep	5/7/93	BG	Dry	NA	NA	NA
Spring/Seep	4/1/93	BG-2	< 1	8.2	1030	NM
Spring/Seep	5/7/93	BG-2	< 1	NM	NM	NM
Spring/Seep	1997	PW-2	NM	8.16	NM	NM
Spring/Seep	1967	WS	0.8	NM	NM	81.5
Spring/Seep	4/2/93	WS	0.00735	8.5	1980	NM

Notes:

Box = Percha Box
u/s = upstream
d/s = downstream
NA = no water present for sampling
NM = parameter not measured or not available

Table 4-1
NMWQCC Surface Water Standard Exceedances

Sample ID	Collection Date	Aluminum	Antimony	Arsenic	Barium	Beryllium	Boron	Cadmium	Chromium	Cobalt	Copper	Cyanide	Lead	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	Selenium	Thallium	Uranium	Vanadium	Zinc
NMWQCC SW Standard (mg/L)		**5.0**	**0.006**	**0.01**	**2.0**	**0.004**	**0.75**	**0.005**	**0.1**	**0.05**	**0.2**	**0.0052**	**0.015**	**0.00077**	**1.0**	**0.7**	**10**	**0.05**	**0.002**	**0.**	**0.10**	**2.0**
Category[1]		**IRR**	**DWS**	**DWS**	**DWS**	**DWS**	**IRR**	**DWS**	**DWS**	**IRR**	**IRR**	**WH**	**DWS**	**WH**	**IRR**	**DWS**	**DWS**	**DWS**	**DWS**	**DWS**	**LW**	**IRR**
PWS-1	19-Aug-10	540.0				0.140		0.140		1.50	80.0							0.086		1.40		12.0
SWQ-2	27-Oct-81													0.0040								
	23-Dec-83																11					
	19-Jul-91																13					

Notes: [1]Category selection based on most stringent standard for analyte
DWS = Domestic Water Supply
IRR = Irrigation
LW = Livestock Watering
mg/L = milligrams per liter
NMWQCC = New Mexico Water Quality Control Commission
SW = Surface Water
WH = Wildlife Habitat
Metals analyzed using EPA Method 200.7/200.8/245.1/9012B and reported in mg/

Table 4-2
NMWQCC Pit Lake Standard Exceedances

Location	Collection Date	Aluminum	Antimony	Arsenic	Barium	Beryllium	Boron	Cadmium	Chromium	Cobalt	Copper	Cyanide	Lead	Mercury	Molybdenum	Nickel	Nitrate as N	Nitrite + Nitrate	Selenium	Thallium	Uranium	Vanadium	Zinc
NMWQCC SW Standard (mg/L)		**5**	**0.006**	**0.01**	**2**	**0.004**	**0.75**	**0.005**	**0.1**	**0.05**	**0.2**	**0.0052**	**0.015**	**0.00077**	**1**	**0.7**	**10**	**132**	**0.05**	**0.002**	**0.03**	**0.1**	**2**
Category[1]		**IRR**	**DWS**	**AqL**	**DWS**	**DWS**	**IRR**	**DWS**	**DWS**	**IRR**	**IRR**	**WH**	**DWS**	**AqL**	**IRR**	**DWS**	**DWS**	**LW**	**DWS**	**DWS**	**DWS**	**IRR/LW**	**IRR**
PL-WQ	11-Feb-91							0.035															
	29-Aug-91										0.64												
	15-Dec-92										3.208												
	12-Dec-94							0.017															
	19-Dec-94							0.017															
	21-Sep-95							0.014															
	30-Jan-10	5.5				0.017		0.056		0.35	9.0								0.026				6.5
PL-WQ-05	20-Jan-11					0.016		0.062		0.39	0.61								0.025				5.8
PL-WQ-06	20-Jan-11					0.016		0.062		0.38	0.59								0.025				5.7
PL-WQ-07	20-Jan-11					0.016		0.061		0.39	0.64		0.026						0.031				6
PL-WQ-08	20-Jan-11					0.015		0.06		0.37	0.59								0.03				5.3

Notes:

[1]Category based on the most stringent applicable standard
AqL = Aquatic Life
DWS = Domestic Water Supply
IRR = Irrigation
LW = Livestock Watering
NMWQCC = New Mexico Water Quality Control Commission
SW = Surface Water
WH = Wildlife Habitat
Metals analyzed using EPA Method 200.7/200.8/245.1/9012B and reported in mg/L

Table 4-3
NMWQCC Groundwater Standard Exceedances

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Lead	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.05	0.2	0.002	1.0	0.2	10	6-9	0.05	0.05	600	1000	0.03	10
GWQ-1	02-Feb-81												1.7													
GWQ-3	15-Jun-81													0.07												
	25-Feb-82																							1040		
	09-Aug-83																							1060		
	01-Nov-83																							1240		
	16-Mar-84																							1190		
GWQ-5	15-Jun-81																							1260		
GWQ-6	15-Jun-81															0.002										
	01-Apr-93												5.1		0.4											
GWQ-7	02-Feb-81												3.8													
	06-Apr-81										0.4															
	10-Aug-81												1.7													
	21-Feb-83														0.3											
	30-Mar-93																		138							
	25-May-94											2.1			1.1								1300.0	2420		
	21-Jul-94											16.0	1.2		0.2											
GWQ-8	04-Jun-76																		17							
	02-Feb-81												1.7						60							
GWQ-9	02-Feb-81												1.8													
GWQ-10	10-Aug-81	10.2											2.3		1.2											
	30-Oct-81				0.77																					
	13-Nov-81														0.5											
	26-May-94												1.1													
GWQ-11	10-Aug-81												1.1		0.5											
	07-Dec-81															0.006										

Table 4-3
NMWQCC Groundwater Standard Exceedances

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Lead	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.05	0.2	0.002	1.0	0.2	10	6-9	0.05	0.05	600	1000	0.03	10
GWQ94-13	15-Nov-94																						720.0	1570		
	01-Jul-96																						620.0	1520		
	02-Jul-10						290																770.0	1730		
	05-Oct-10						280																760.0	1670		
GWQ94-15	29-Jan-10																							1080		
GWQ94-16	13-Nov-94																							1140		
	01-Jul-96																							1160		
	29-Jun-10																							1190		
	30-Sep-10																							1170		
GWQ94-20	15-Nov-94														0.4											
GWQ94-21B	13-Nov-94														0.4											
GWQ96-22A	13-Jul-96											3.3														
	09-Apr-97												6.5		2.8											
	08-Aug-97											2.2			0.5											
	30-Jan-10											2.6	2.1		0.7											
	01-Jul-10											2.7			0.7											
	07-Oct-10											2.7			0.5											
GWQ96-22B	13-Jul-96											1.8			0.4											
	07-Oct-10											3.0	9.3		1.2											
GWQ96-23A	09-Apr-97														0.8											
	08-Aug-97														1.6											
	30-Jan-10											1.7			0.6											
	01-Jul-10														0.4											
	06-Oct-10														0.4											
GWQ96-23B	14-Jul-96	7.4											3.7													
	06-Oct-10											2.1	1.4		0.4											

Table 4-3
NMWQCC Groundwater Standard Exceedances

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Lead	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.05	0.2	0.002	1.0	0.2	10	6-9	0.05	0.05	600	1000	0.03	10
IW-1	04-Mar-87						575																1901.0	3802		
	19-Jul-91						633																1985.0	4235		
	29-Aug-91						642																1917.9	4120		
	26-Nov-91						615																1634.0	3979		
	15-Mar-92						611																2201.0	4026		
	25-May-92						598																2203.0	4155		
	16-Jul-92						585																1775.0	4297		
	08-Oct-92						617																1726.8	3996		
	27-Nov-92						605																1716.6	4004		
	15-Dec-92						609																1414.6	3969		
	28-Sep-93						521																1150.0	3661		
	17-Mar-94						405																1569.0	3684		
	24-May-94						470																1500.0	3500		
	23-Jun-94						474																1444.0	3555		
	22-Jul-94						431																1480.0	3450		
	22-Sep-94						436																1348.0	3466		
	29-Jan-95						663																1478.5	3395		
	29-Mar-95						419																1350.7	3465		
	27-Jun-95						446																1680.1	3599		
	21-Sep-95						459																1710.8			
	10-Jan-96						442																1595.5	3437		
	25-Sep-96						568																1493.0	3551		
	15-Jan-97						410																1694.5			
IW-2	02-Sep-82						409																2252.0	4010		
	25-May-94	22.0					340						16.0		0.8								1000.0	2400		
	22-Jul-94						380																1040.0	2390		
	31-Jan-10						600						1.3		1.6								1200.0	2770		
	29-Jun-10						580								2.2								1100.0	2700		
	30-Sep-10						500								2.2								1000.0	2280		

Table 4-3
NMWQCC Groundwater Standard Exceedances

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Lead	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.05	0.2	0.002	1.0	0.2	10	6-9	0.05	0.05	600	1000	0.03	10
IW-3	02-Sep-82																						707.3	1562		
	25-Feb-93						590																1738.9	3892		
	26-May-94	32.0						0.06		6.0			22.0	0.08	0.4									1870		
	23-Jul-94																							1300		
	03-Apr-96						433																1566.3	3364		
Ladder-Higgins	02-Aug-94											1.9														
Miranda	31-Jul-47						380																			
MW-2	07-May-75											2.3														
	20-Jul-94											3.1														
	28-Sep-10											3.3								9.27						
MW-6	01-Jan-75											3.4														
	08-Jul-10											8.1														
	27-Sep-10											8.2														
MW-8	01-Jan-75																		15							
	12-Oct-10																			9.23						

Table 4-3
NMWQCC Groundwater Standard Exceedances

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Lead	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.05	0.2	0.002	1.0	0.2	10	6-9	0.05	0.05	600	1000	0.03	10
NP-1	08-Oct-81														0.9											
	04-Nov-81														0.6											
	13-Nov-81														1.3											
	17-Nov-81														1.4											
	23-Nov-81														1.2											
	07-Dec-81														1.2											
	15-Dec-81														1.2											
	22-Dec-81														1.0											
	05-Jan-82														0.7											
	26-Jan-82														0.5											
	22-Feb-82														0.3											
	26-Apr-82												1.2													
	24-May-82														0.3											
	28-May-82														0.2											
	08-Jun-82														0.3											
	16-Mar-84															0.008										
	26-Nov-91																							1484		
	24-May-94												9.5													
	21-Jul-94														0.3											

Table 4-3
NMWQCC Groundwater Standard Exceedances

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Lead	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.05	0.2	0.002	1.0	0.2	10	6-9	0.05	0.05	600	1000	0.03	10
NP-2	08-Oct-81											**1.8**			**0.6**											
	06-Nov-81														**0.4**											
	13-Nov-81														**0.8**											
	23-Nov-81														**0.5**											
	07-Dec-81														**0.5**											
	15-Dec-81														**0.5**											
	22-Dec-81														**0.5**											
	05-Jan-82														**0.5**											
	26-Jan-82														**0.3**											
	22-Feb-82														**0.3**											
	26-Apr-82												**1.2**		**0.3**											
	18-May-82					**0.02**																				
	30-Mar-93												**1.9**											**1310**		
	28-Sep-93																							**1170**		
	24-May-94												**4.5**													
	29-Mar-95																							**1164**		

Table 4-3
NMWQCC Groundwater Standard Exceedances

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Lead	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.05	0.2	0.002	1.0	0.2	10	6-9	0.05	0.05	600	1000	0.03	10
NP-3	08-Oct-81														0.8											
	27-Oct-81											1.9			1.0											
	30-Oct-81														1.0											
	06-Nov-81														0.5											
	13-Nov-81														1.0											
	17-Nov-81														1.0											
	23-Nov-81														1.0											
	07-Dec-81														0.8											
	15-Dec-81														0.9											
	22-Dec-81														0.8											
	05-Jan-82														0.7											
	26-Jan-82														0.7											
	22-Feb-82														0.7											
	26-Apr-82														0.4											
	17-May-82						562								0.2				12				900.0	2460		
	30-May-84																							1060		
	12-Sep-84						270																	1140		
	27-Nov-84						290																	1150		
	17-May-85						310																	1470		
	13-Nov-85						288																	1520		
	23-May-86						282																624.0	1590		
	08-Oct-86						272																620.0	1710		
	03-Mar-87																						695.0			
	04-Mar-87						283																695.0	1882		
	25-May-87																						735.5			
	12-Jan-88						359								0.6								755.0	1584		
	04-Apr-88						254																	1772		
	23-Aug-88						251																835.2	1744		
	09-Feb-89						254																763.4	1583		

Table 4-3
NMWQCC Groundwater Standard Exceedances

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Lead	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.05	0.2	0.002	1.0	0.2	10	6-9	0.05	0.05	600	1000	0.03	10
NP-3	01-Jun-89																						713.6	1596		
	30-Nov-89																						742.9	1600		
	14-Nov-90																						821.6	1675		
	11-Feb-91						256															255.90	970.5	1551		
	19-Jul-91																						820.3	1663		
	29-Aug-91						254																854.1	1616		
	26-Nov-91																						745.2	1613		
	15-Mar-92																						921.3	1644		
	25-May-92																						752.9	1607		
	16-Jul-92																						802.2	1578		
	08-Oct-92																						799.1	1445		
	27-Nov-92						255																796.1	1640		
	15-Dec-92																							1558		
	25-Feb-93																						793.6	1580		
	30-Mar-93												5.0		0.3								825.0	1560		
	28-Sep-93														0.2								619.4	1544		
	17-Mar-94														0.3								746.9	1609		
	23-Jun-94																						778.6	1628		
	22-Jul-94														0.6								796.0	1620		
	22-Sep-94																						707.1	1691		
	29-Jan-95						566																651.9	1623		
	29-Mar-95																							1639		
	27-Jun-95																						717.0	1607		
	21-Sep-95																						822.0	1557		
	10-Jan-96																						724.1	1464		
	03-Apr-96																						722.6	1415		
	25-Sep-96																							1472		
	15-Jan-97																						657.4	1478		
	08-Jul-10						270																790.0	1740		

Table 4-3
NMWQCC Groundwater Standard Exceedances

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Lead	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.05	0.2	0.002	1.0	0.2	10	6-9	0.05	0.05	600	1000	0.03	10
NP-3	07-Oct-10						290																830.0	1660		
NP-4	26-Apr-82												3.8		0.6											
	17-May-82																			9.40						
	30-Jun-82																			9.50						
	21-Feb-83																			9.30						
	19-Jul-91												5.1													
	08-Oct-92																			9.01						
	15-Dec-92																			9.52						
	25-Feb-93																			9.85						
	31-Mar-93														0.8	0.009										
	26-May-94												15.0													12.00
	15-Jan-97																						1113.0	2651		
NP-5	17-Nov-81														0.3											
	26-Apr-82												3.8		6.9											
	24-May-94												1.2													
O. Williams	19-Dec-45						425																			
	13-Jun-46						418																			
PW-3	14-Aug-81											2.5														
QMC-4	27-Mar-81											2.5														
SHB-28	22-Sep-76														0.4											

Notes: GW = Groundwater
mg/L = milligrams per liter
NMWQCC = New Mexico Water Quality Control Commission
Metals analyzed using EPA Method 200.7/200.8/245.1/9012B and reported in mg/L

Table 5-1

Proposed Analytical Parameters with Method Reporting Limits

Parameter	Method	Method Reporting Limit
Alkalinity, CaCO3 (Acidity)	SM 2320B	1
CO3, CaCO3	SM 2320B	1
HCO3	SM 2320B	1
Aluminum	EPA 200.7	0.045
Antimony	EPA 200.8	0.0025
Arsenic	EPA 200.8	0.005
Barium	EPA 200.7	0.01
Beryllium	EPA 200.7	0.001
Bismuth	EPA 200.7	0.1
Boron	EPA 200.7	0.1
Cadmium	EPA 200.8	0.001
Calcium	EPA 200.7	0.5
Chloride	EPA 300.0	1
Chromium	EPA 200.7	0.005
Cobalt	EPA 200.7	0.01
Copper	EPA 200.8	0.05
Fluoride	EPA 300.0	0.1
Gallium	EPA 200.7	0.1
Iron	EPA 200.7	0.01
Lead	EPA 200.8	0.01
Lithium	EPA 200.7	0.1
Magnesium	EPA 200.7	0.5
Manganese	EPA 200.7	0.005
Mercury	EPA 200.8	0.0001
Molybdenum	EPA 200.7	0.01
Nickel	EPA 200.7	0.01
Nitrate as N	EPA 300.0	1
Nitrite as N	EPA 300.0	1
pH (s.u.)	SM 4500-H+ B	--

Parameter	Method	Method Reporting Limit
Phosphorus	EPA 200.7	0.5
Potassium	EPA 200.7	0.5
Scandium	EPA 200.7	0.1
Selenium	EPA 200.8	0.005
Silver	EPA 200.7	0.005
Sodium	EPA 200.7	0.5
Strontium	EPA 200.7	0.1
Sulfate	EPA 300.0	1
Thallium	EPA 200.8	0.001
Tin	EPA 200.7	0.1
Titanium	EPA 200.7	0.1
Total Dissolved Solids	SM 2540C	10
Uranium	EPA 200.8	0.002
Vanadium	EPA 200.7	0.01
Zinc	EPA 200.7	0.01

Appendix A

New Mexico Environment Department Ground Water Quality Bureau Mining Environmental Compliance Section Letters Dated August 20, 2008 and March 18, 2009

NEW MEXICO
ENVIRONMENT DEPARTMENT

Ground Water Quality Bureau

1190 St. Francis Drive
P.O. Box 26110, Santa Fe, NM 87502
Phone (505) 827-2918 Fax (505) 827-2965
www.nmenv.state.nm.us
William C. Olson, Bureau Chief

BILL RICHARDSON
Governor
DIANE DENISH
Lieutenant Governor

RON CURRY
Secretary
JON GOLDSTEIN
Deputy Secretary

CERTIFIED MAIL – RETURN RECEIPT REQUESTED

August 20, 2008

George Lotspeich, President
Hydro Resources Corporation
4011 Mesa Verde Ave. NE
Albuquerque, NM 87110

Re: Abatement Plan Required at Copper Flat Mine Site, DP-1

Dear Mr. Lotspeich:

Pursuant to the New Mexico Water Quality Control Commission (WQCC) Regulations Sections 20.6.2.1203.A(9), 20.6.2.4104 and 20.6.2.4106.A NMAC, the New Mexico Environment Department (NMED) hereby provides notification that you, George Lotspeich and Hydro Resources Corporation (HRC) as a "responsible person", as defined in WQCC regulation 20.6.2.7.00 NMAC, are required to submit an abatement plan for the Copper Flat Mine site, located approximately 6 miles northeast of Hillsboro, New Mexico. The May 1997 Alta Gold submittal entitled "Copper Flat Mine Project Monitoring Plans" lists historical ground water exceedences of WQCC standards through 1994. Additional ground water sampling in 1997 and 1998 confirmed that standards set forth in WQCC regulation 20.6.2.4103 NMAC have been exceeded. Sampling the water quality of the pit lake at Copper Flat in 2004 indicates the pit lake water also exceeds WQCC standards for sulfate, total dissolved solids, chloride, manganese and uranium. Additional sampling of the pit lake was conducted in June 2008. Although analytical data is not yet available from this recent sampling event the field pH was measured at approximately 4.5 which is below the acceptable range of 6 to 9. Field observations indicate high concentrations of sulfate and total dissolved solids.

Within 60 days of receipt of this letter, HRC shall submit to NMED an abatement plan proposal for a Stage 1 Abatement Plan to characterize ground and surface water contamination at the Copper Flat Mine site.

The purpose of the Stage 1 Abatement Plan is to define site conditions and provide the data necessary to select and design an effective abatement alternative. WQCC regulation

20.6.2.4106.C NMAC describes the information that may be required for a Stage 1 Abatement Plan. HRC's abatement plan proposal must include an adequate investigation for the definition of extent and magnitude of ground and surface water contamination as well as characterization of the hydrogeology of the site.

For your reference, a current copy (effective July 16, 2006) of the WQCC Regulations, 20.6.2 NMAC is enclosed.

Please contact Kurt Vollbrecht at 505-827-0195 with any questions.

Sincerely,

William C. Olson, Chief
Ground Water Quality Bureau

Enc.: WQCC Regulations 20.6.2 NMAC

cc: Mary Ann Menetrey, Program Manager, GWQB-MECS
Karen Garcia, Chief, Mine Reclamation Bureau
Russell MacRae, U.S. Fish and Wildlife Service, 2105 Osuna NE, Abq., Nm 87113

NEW MEXICO
ENVIRONMENT DEPARTMENT

Ground Water Quality Bureau

1190 St. Francis Drive, P.O. Box 5469
Santa Fe, New Mexico 87502-5469
Phone (505) 827-2900 Fax (505) 827-2965
www.nmenv.state.nm.us

BILL RICHARDSON
Governor
DIANE DENISH
Lieutenant Governor

RON CURRY
Secretary
JON GOLDSTEIN
Deputy Secretary



CERTIFIED MAIL – RETURN RECEIPT REQUESTI

March 18, 2009

George Lotspeich, President
Hydro Resources Corporation
4011 Mesa Verde Avenue, NE
Albuquerque, NM 87110

RE: Copper Flat Mine Site Information

Dear Mr. Lotspeich:

Thank you for meeting with the New Mexico Environment Department (NMED) regarding the Copper Flat Mine Site Stage 1 Abatement Plan on February 25, 2009. Your cooperation with this project is greatly appreciated.

I've reviewed and inventoried the reports available through NMED. These files are available for review at the NMED Ground Water Quality Bureau Santa Fe offices and include the following:

- Hydrology Impact Evaluation, 1996
- Baseline Data, Volume 1. Copper Flat Project, 1995
- Copper Flat Mine-Mine Permit Application, volumes 1-4, 1996
- Copper Flat Mine Project Monitoring Plans, 1996
- Appendices-volume II of II, Copper Flat Project Soil Cover Modeling Study, 1996 (I cannot locate volume I of II)
- Environmental Impact Statement, Copper Flat Project, 1995
- Response to Closure Plan Comments, Copper Flat Project, 1996
- Final Geotechnical and Design Development Report, Tailings Dam and Disposal Area, Copper Flat Project, 1981

In addition, eight water quality samples were collected from the Pit Lake and submitted for analysis by NMED on 12/09/2004 and 06/16/2008. Copies of the results are attached for your records.

The first step in initiating a Stage 1 Abatement Plan as described in WQCC Regulation 20.6.2.4106 NMAC (page 26) will be to walk the property and identify existing monitoring wells that may be used to collect water quality samples for the assessment of ground water at the site. I have March 24th scheduled to meet you in Hillsborough at 10:30 to conduct that inspection.

Following sample collection and results analysis, NMED and Hydro Resources Corporation will cooperate in the development of an appropriate Stage 1 Abatement Plan for the facility.

Please contact me at (505) 827-1046 with any questions you may have.

Regards,

Greg Huey
Ground Water Quality Bureau

Enc.: Water Quality Sample Reports

Appendix B1

Surface Water Analytical Results

APPENDIX B1
SURFACE WATER ANALYTICAL RESULTS
Stage 1 Abatement Plan Investigation Report
Copper Flat Mine Site, New Mexico

Sample ID	Collection Date	Aluminum	Antimony	Arsenic	Barium	Beryllium	Boron	Cadmium	Chromium	Cobalt	Copper	Cyanide	Lead	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	Selenium	Thallium	Uranium	Vanadium	Zinc
NMWQCC SW Standard (mg/L)		0.087	0.0056	0.0023	2.0	0.004	0.75	0.005	0.1	0.05	0.2	0.2	0.05	0.00077	1.0	0.1	10	0.005	0.0017	5.0	0.10	2.0
*Category		AqL	DWS	DWS	DWS	DWS	IRR	DWS	DWS	IRR	IRR	DWS	DWS	AqL	IRR	DWS	DWS	DWS	DWS	DWS	IRR	IRR
CSCS-B	8/25/2010	0.035	<0.001	**0.0042**	0.013	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006		<0.005		0.011	<0.01		0.0012	<0.001		<0.05	<0.01
	11/4/2010	<0.02	<0.001	**0.0045**	0.015	<0.002	0.048	<0.002	<0.006	<0.006	<0.006		<0.005		0.012	<0.01	0.36	0.0011	<0.001		<0.05	<0.01
	1/20/2011	0.038	<0.001	**0.0038**	0.013	<0.002	0.045	<0.002	<0.006	<0.006	<0.006		<0.005		0.012	<0.01	0.2	0.0015	<0.001		<0.05	<0.01
CSCS-C	8/25/2010	**0.38**	<0.001	0.0012	0.015	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006		<0.005		<0.008	<0.01		<0.001	<0.001		<0.05	<0.01
LAC-A	8/24/2010	<0.02	<0.001	0.0012	0.011	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006	<0.005	<0.005		<0.008	<0.01		<0.001	<0.001		<0.05	0.015
	11/3/2010	<0.02	<0.001	0.0011	0.016	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006		<0.005		<0.008	<0.01		<0.001	<0.001		<0.05	0.02
LAC-B	8/24/2010	<0.02	<0.001	0.0016	0.012	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006	<0.005	<0.005		<0.008	<0.01		<0.001	<0.001		<0.05	0.014
	11/3/2010	<0.02	<0.001	**0.004**	0.022	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006		<0.005		<0.008	<0.01		<0.001	<0.001		<0.05	<0.01
LAC-C	8/23/2010	<0.020	<0.0010	0.0021	0.014	<0.0020	<0.040	<0.0020	<0.0060	<0.0060	<0.0060	<0.0050	<0.0050		<0.0080	<0.010		<0.0010	<0.0010		<0.050	<0.010
	11/3/2010	<0.02	<0.001	0.0019	0.014	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006		<0.005		<0.008	<0.01		<0.001	<0.001		<0.05	<0.01
	1/18/2011	<0.02	<0.001	0.002	0.015	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006		<0.005		<0.008	<0.01		<0.001	<0.001		<0.05	0.01
LAC-D	8/24/2010	<0.02	<0.001	0.0022	0.018	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006	<0.005	<0.005		<0.008	<0.01		<0.001	<0.001		<0.05	<0.01
	11/4/2010	<0.02	<0.001	0.0022	0.019	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006		<0.005		<0.008	<0.01	<0.1	<0.001	<0.001		<0.05	<0.01
LAC-E	8/20/2010	<0.020	<0.0010	0.0020	0.018	<0.0020	<0.040	<0.0020	<0.0060	<0.0060	<0.0060	<0.0050	<0.0050		<0.0080	<0.010		<0.0010	<0.0010		<0.050	<0.010
	1/19/2011	<0.02	<0.001	0.0017	0.021	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006		<0.005		<0.008	<0.01	<0.1	<0.001	<0.001		<0.05	<0.01
NWS	8/24/2010	<0.02	<0.001	**0.0065**	0.023	<0.002	0.041	<0.002	<0.006	<0.006	<0.006	<0.005	<0.005		<0.008	<0.01		<0.001	<0.001		<0.05	0.012
	11/3/2010	<0.02	<0.001	**0.0062**	0.024	<0.002	0.043	<0.002	<0.006	<0.006	<0.006		<0.005		<0.008	<0.01		<0.001	<0.001		<0.05	<0.01
PC-A	8/24/2010	<0.02	<0.001	0.0016	0.04	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006	<0.005	<0.005		<0.008	<0.01		<0.001	<0.001		<0.05	<0.01
	11/8/2010	<0.02	<0.001	0.0012	0.035	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006		<0.005		<0.008	<0.01		<0.001	<0.001		<0.05	0.013
	11/19/2010											<0.01										
PC-B	8/26/2010	<0.02	<0.001	0.0018	0.032	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006		<0.005		<0.008	<0.01		<0.001	<0.001		<0.05	0.018
	11/8/2010	<0.02	<0.001	0.0013	0.037	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006		<0.005		<0.008	<0.01		<0.001	<0.001		<0.05	<0.01
	11/19/2010											<0.01										
PC-C	8/26/2010	<0.02	<0.001	0.0018	0.032	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006		<0.005		<0.008	<0.01		<0.001	<0.001		<0.05	0.016
	11/9/2010	0.066	<0.001	0.0022	0.032	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006		<0.005		<0.008	<0.01		<0.001	<0.001		<0.05	0.026

APPENDIX B1
SURFACE WATER ANALYTICAL RESULTS
Stage 1 Abatement Plan Investigation Report
Copper Flat Mine Site, New Mexico

Sample ID	Collection Date	Aluminum	Antimony	Arsenic	Barium	Beryllium	Boron	Cadmium	Chromium	Cobalt	Copper	Cyanide	Lead	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	Selenium	Thallium	Uranium	Vanadium	Zinc
NMWQCC SW Standard (mg/L)		0.087	0.0056	0.0023	2.0	0.004	0.75	0.005	0.1	0.05	0.2	0.2	0.05	0.00077	1.0	0.1	10	0.005	0.0017	5.0	0.10	2.0
*Category		AqL	DWS	DWS	DWS	DWS	IRR	DWS	DWS	IRR	IRR	DWS	DWS	AqL	IRR	DWS	DWS	DWS	DWS	DWS	IRR	IRR
PC-D	8/27/2010	<0.02	<0.001	0.002	0.029	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006		<0.005		<0.008	<0.01		<0.001	<0.001		<0.05	0.025
	11/9/2010	<0.02	<0.001	0.0022	0.027	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006		<0.005		<0.008	<0.01		<0.001	<0.001		<0.05	<0.01
PCS-A	8/26/2010	<0.02	<0.001	0.0019	0.0099	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006		<0.005		<0.008	<0.01		0.0011	<0.001		<0.05	0.047
PWS-1	8/19/2010	**540**	<0.0010	0.0016	<0.10	**0.14**	<2.0	**0.14**	<0.30	**1.5**	**80**	<0.0050	<0.25		<0.40	<0.50		**0.086**	<0.0010		<2.5	**12**
SWQ-1	12/28/1982							<0.005			<0.05	<0.01		<0.001	<0.05		0.9	<0.005				
	2/21/1983							<0.005			<0.05	<0.01		<0.001	<0.05		4.4	<0.005				
SWQ-2	10/27/1981	<0.01		<0.01	<0.2			<0.005	<0.01	<0.02	<0.05	<0.01	<0.02	**0.004**	<0.05		6.6	<0.005				
	2/25/1982							<0.005			<0.05	<0.01		<0.001	<0.05		4.2	<0.005				
	5/12/1982							<0.005			<0.05	<0.01		<0.001	<0.05		3	<0.005				
	2/21/1983							<0.005			<0.05	<0.01		<0.001	<0.05		0.8	<0.005				
	5/13/1983							<0.005			<0.05	<0.01		<0.001	<0.05		0.3	<0.005				
	8/9/1983							<0.005			<0.05	<0.01		<0.001	<0.05		<0.2	<0.005				
	11/1/1983							<0.005			<0.05	<0.01		<0.001	<0.05		0.3	<0.005				
	12/23/1983							<0.005			<0.05	<0.01		<0.001	<0.05		**11.2**	<0.005				
	3/16/1984							<0.005			<0.05	<0.01		<0.001	<0.05		5.3	<0.005				
	5/30/1984							<0.005			<0.05	<0.01		<0.001	<0.05		0.4	<0.005				
	9/12/1984							<0.005			<0.05	<0.01		<0.001	<0.05		0.4	<0.005				
	11/27/1984							<0.005			<0.05	<0.01		<0.001	<0.05		<0.2	<0.005				
	7/19/1991			<0.002	<0.01			<0.005	<0.02				<0.005	<0.0002			**12.74**	<0.001				
	8/25/2010	**1.5**	<0.001	<0.001	0.01	<0.002	<0.04	<0.002	<0.006	<0.006	0.085		<0.005		<0.008	<0.01		<0.001	<0.001		<0.05	<0.01
SWQ-2A	10/27/1981	<0.01		<0.01	<0.2			<0.005	<0.01	<0.02	<0.05	<0.01	<0.02	<0.001	<0.05		0.3	<0.005				
	2/25/1982							<0.005			<0.05	<0.01		<0.001	<0.05		0.2	<0.005				
SWQ-3	7/19/1991			<0.002	0.03			<0.005	<0.02				<0.005	<0.0002			1.39	<0.001				
	8/29/1991										0.015											
	11/26/1991										0.001											
	8/19/2010	<0.020	<0.0010	<0.0010	0.062	<0.0020	0.14	<0.0020	<0.0060	<0.0060	0.062	<0.0050	<0.0050		0.047	<0.010		**0.013**	<0.0010		<0.050	0.023

APPENDIX B1
SURFACE WATER ANALYTICAL RESULTS
Stage 1 Abatement Plan Investigation Report
Copper Flat Mine Site, New Mexico

Sample ID	Collection Date	Aluminum	Antimony	Arsenic	Barium	Beryllium	Boron	Cadmium	Chromium	Cobalt	Copper	Cyanide	Lead	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	Selenium	Thallium	Uranium	Vanadium	Zinc
NMWQCC SW Standard (mg/L)		0.087	0.0056	0.0023	2.0	0.004	0.75	0.005	0.1	0.05	0.2	0.2	0.05	0.00077	1.0	0.1	10	0.005	0.0017	5.0	0.10	2.0
*Category		AqL	DWS	DWS	DWS	DWS	IRR	DWS	DWS	IRR	IRR	DWS	DWS	AqL	IRR	DWS	DWS	DWS	DWS	DWS	IRR	IRR
SWQ-3	10/21/2010	<0.02	<0.001	<0.005	0.053	<0.002	0.089	<0.002	<0.006	<0.006	0.023		<0.005		0.03	<0.01		**0.016**	<0.001		<0.05	0.48
WS	8/25/2010	<0.02	<0.001	<0.001	0.01	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006		<0.005		<0.008	<0.01		<0.001	<0.001		<0.05	0.016
	11/4/2010	<0.02	<0.001	<0.001	0.0098	<0.002	0.066	<0.002	<0.006	<0.006	<0.006		<0.005		<0.008	<0.01	<0.1	<0.001	<0.001		<0.05	<0.01
	1/20/2011	<0.02	<0.001	<0.001	0.011	<0.002	0.069	<0.002	<0.006	<0.006	<0.006		<0.005		<0.008	<0.01	<0.1	<0.001	<0.001		<0.05	<0.01
WSCS-A	8/25/2010	**0.74**	<0.001	**0.0081**	0.016	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006		<0.005		0.011	<0.01		<0.001	<0.001		<0.05	<0.01
	1/20/2011	**0.18**	<0.001	**0.0031**	0.063	<0.002	0.043	<0.002	<0.006	<0.006	<0.006		<0.005		0.011	<0.01	2.7	0.0018	<0.001		<0.05	<0.01

Notes:

NMWQCC = New Mexico Water Quality Commission

Category selection based on most stringent standard for analyte

AqL = Aquatic Life

DWS = Domestic Water Supply

IRR = Irrigation

Measurement values that exceed the NMWQCC standard are in bold

Non-detects are indicated with a "<" & the detection limit

Solid grey indicates 'No Data' or 'Not Measured'

Appendix B2

Pit Lake Analytical Results

APPENDIX B2
PIT LAKE ANALYTICAL RESULTS
Stage 1 Abatement Plan Investigation Report
Copper Flat Mine Site, New Mexico

Sample ID	Collection Date	Aluminum	Antimony	Arsenic	Barium	Beryllium	Boron	Cadmium	Chromium	Cobalt	Copper	Cyanide	Lead	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	Selenium	Thallium	Uranium	Vanadium	Zinc
NMWQCC SW Standard (mg/L)		0.087	0.0056	0.0023	2.0	0.004	0.75	0.005	0.1	0.05	0.2	0.2	0.05	0.00077	1.0	0.1	10	0.005	0.0017	5.0	0.10	2.0
*Category		AqL	DWS	DWS	DWS	DWS	IRR	DWS	DWS	IRR	IRR	DWS	DWS	AqL	IRR	DWS	DWS	DWS	DWS	DWS	IRR	IRR
PL-WQ	4/3/1989	<0.1			<0.1	<0.1		<0.1	<0.1	<0.05	<0.1		<0.1		<0.1							0.4
	2/11/1991			<0.001	<0.01			**0.035**	0.06				0.006	<0.0002			0.1	<0.001				
	7/19/1991			<0.002	<0.01			<0.005	<0.02				<0.005	<0.0002			0.03	<0.001				
	8/29/1991										**0.64**											
	11/26/1991										0.084											
	12/15/1992										**3.208**											
	9/28/1993										0.001											0.01
	3/17/1994										0.089											1.01
	12/12/1994	<0.05	<0.005	<0.005	<0.1	<0.002		**0.017**	<0.025	<0.05	0.03		<0.005	<0.001	<0.05		<5	<0.005				0.095
	12/19/1994	<0.05	<0.005	<0.005	<0.1	<0.002		**0.017**	<0.025	<0.05	0.032		<0.005	<0.001	<0.05		<5	<0.005				0.092
	9/21/1995	**0.13**	<0.005	<0.005	<0.05	<0.002		**0.014**	<0.025	<0.05	<0.025		<0.005	<0.001	<0.05		<5	<0.25				0.071
	1/30/2010	**5.5**	<0.0010	**0.0062**	0.017	**0.017**	<0.20	**0.056**	<0.030	**0.35**	**9.0**		<0.025		<0.040	0.074		**0.026**	<0.0050			**6.5**
PL-WQ-05	1/20/2011	**0.48**	<0.001	<0.001	0.01	**0.016**	<0.2	**0.062**	<0.03	**0.39**	**0.61**		<0.025		<0.04	0.069	<0.1	**0.025**	<0.001		<0.25	**5.8**
PL-WQ-06	1/20/2011	**0.51**	<0.001	<0.001	0.011	**0.016**	<0.2	**0.062**	<0.03	**0.38**	**0.59**		<0.025		<0.04	0.066	<0.1	**0.025**	<0.005		<0.25	**5.7**
PL-WQ-07	1/20/2011	**0.54**	<0.005	<0.005	0.012	**0.016**	<0.2	**0.061**	<0.03	**0.39**	**0.64**		0.026		<0.04	0.068	<0.1	**0.031**	<0.005		<0.25	**6**
PL-WQ-08	1/20/2011	**0.48**	<0.005	<0.005	0.01	**0.015**	<0.2	**0.06**	<0.03	**0.37**	**0.59**		<0.025		<0.04	0.066	<0.1	**0.03**	<0.005		<0.25	**5.3**

Notes:

NMWQCC = New Mexico Water Quality Commission

Category selection based on most stringent standard for analyte

AqL = Aquatic Life

DWS = Domestic Water Supply

IRR = Irrigation

Measurement values that exceed the NMWQCC standard are in bold

Non-detects are indicated with a "<" & the detection limit

Solid grey indicates 'No Data' or 'Not Measured'

Appendix B3

Groundwater Analytical Results

APPENDIX B3
GROUNDWATER SAMPLE ANALYTICAL RESULTS
Stage 1 Abatement Plan Investigation Report
Copper Flat Mine Site, New Mexico

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	Lead	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.2	0.002	1.0	0.2	10	0.05	6-9	0.05	0.05	600	1000	0.03	0.03
15.6.31.431	6/4/1976				<0.1		14.3					0.52	0.002	0.003				1.39		7.78			137	520		
	4/9/1981	<0.1	<0.005	<0.1	0.025	<0.001	22	<0.005		0.7		0.58	<0.25	<0.05		0.005	<0.01	1.14	<0.005		<0.005		144.5			**0.14**
Brannon	7/31/1947						15					0.8						0.4					13	270		
Dawson 1	6/14/1946						18					1.3						0.8					36	219		
	6/7/1947						11					1						1.1					58	283		
Dawson 2	7/31/1947						13					1.2						1.3					52	283		
Eaton	7/31/1947						17					0.2						0.2					21	356		
Folcher	6/20/1946						6					0.4						2.4					19	147		
GWQ-1	1/20/1981						200						0.05							7.3			250	450		
	2/2/1981						20						**1.7**							7.9			156	520		
	3/27/1981		<0.01							<0.05	<0.01	0.6						5.5	<0.02							**0.16**
	6/11/1981	<0.05	<0.005	<0.1	<0.1	<0.0005		<0.025	<0.05	<0.025			<0.05	<0.03	<0.001	<0.05	<0.05		<0.005		<0.005	<0.025				<0.05
	6/15/1981	<0.25	<0.01	<1	0.076	<0.005	16	<0.05	<0.05	<0.05	<0.01	0.51	<0.05	<0.02	<0.001	<0.05	<0.05	3.75	<0.02	7.4	0.0022	<0.02	117	500		**0.12**
	2/25/1982					<0.005	22			<0.05	<0.01	0.3	0.14	0.063	<0.001	<0.05		0.2		7.9	<0.005		84	410		
	3/30/1989	<0.1		<0.1	<0.1	<0.1	20	<0.1	<0.05	<0.1			<0.1	<0.05		<0.1	<0.1		<0.1			<0.1	133	512		<0.1
	7/19/1991		0.003	0.01		<0.005	21.1	<0.02		<0.02		0.58	<0.05	<0.02	<0.0002			5.19	<0.005	7.34	<0.002	<0.02	136.4	543		
	3/31/1993	<0.01	<0.005	<0.5	0.03	<0.002	22	<0.02	<0.05	<0.01	<0.01	0.54	<0.05	<0.02	<0.001	<0.02	<0.01	4.9	<0.02	7.7	<0.005	<0.01	160	536		<0.01
	5/25/1994	0.025	<0.005	<0.1		<0.0005	22	<0.025		<0.025		0.52	<0.05	<0.03	<0.001		<0.05	4.3	<0.005	7.9	<0.005	<0.025	150	614		<0.05
	7/21/1994	<0.05	<0.005	<0.1	<0.1	<0.0005	25	<0.025	<0.05	<0.025		0.52	<0.05	<0.03	<0.001	<0.05	<0.05	4.2	<0.005	7.97	<0.005	<0.025	162	558		<0.05
GWQ-2	6/15/1981	<0.01	<0.01	<0.2	<0.1	<0.005	20	<0.01	<0.1	<0.05	<0.01	0.5	<0.1	<0.05	0.0013	<0.05	<0.05	5.6	<0.02	7.3	<0.005	<0.02	140	530		**0.16**
	6/25/1981	<0.025	<0.002	<1	0.162	<0.01	24.8	<0.05	<0.05	<0.02	<0.05	0.48	0.1	<0.02	<0.001	<0.1	<0.05	4.3	<0.05		0.0022	<0.02	111	448		**0.11**
GWQ-3	3/27/1981		<0.01							<0.05	<0.01	0.6						5.5	<0.02							**0.16**
	6/15/1981	<0.25	<0.01	<1	<0.1	<0.005	32	<0.01	<0.05	<0.05	<0.01	0.7	<0.05	0.02	<0.001	<0.1	<0.05	0.25	**0.073**	7	0.0037	<0.02	383	890		**0.32**
	2/25/1982					<0.005	56			<0.05	<0.01	0.6	<0.1	<0.05	<0.001	<0.05		0.4		7.9	<0.005		490	**1040**		
	5/12/1982					<0.005	56			<0.05	<0.01	0.7	<0.1	<0.05	<0.001	<0.05		0.2		7.9	<0.005		410	930		
	6/30/1982					<0.005	48			<0.05	<0.01	0.7	<0.1	<0.05	<0.001	<0.05		0.4		7.6	<0.005		365	860		
	12/23/1982					<0.005	64			<0.05	<0.01	0.7	<0.1	<0.05	<0.001	<0.05		0.2		8.5	<0.005		340	990		
	2/21/1983					<0.005	68			<0.05	<0.01	0.7	<0.1	<0.05	<0.001	<0.05		0.2		7.7	<0.005		428	970		

APPENDIX B3
GROUNDWATER SAMPLE ANALYTICAL RESULTS
Stage 1 Abatement Plan Investigation Report
Copper Flat Mine Site, New Mexico

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	Lead	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.2	0.002	1.0	0.2	10	0.05	6-9	0.05	0.05	600	1000	0.03	0.03
GWQ-3	5/13/1983					<0.005	82			<0.05	<0.01	0.6	<0.1	<0.05	<0.001	0.11		0.3		8	<0.005		437	980		
	8/9/1983					<0.005	78			<0.05	<0.01	0.7	0.11	<0.05	<0.001	<0.05		<0.2		7.8	<0.005		385	**1060**		
	11/1/1983					<0.005	90			<0.05	<0.01	0.7	<0.1	<0.05	<0.001	<0.05		0.3		8	<0.005		529	**1240**		
	3/16/1984					<0.005	74			<0.05	<0.01	0.3	<0.1	<0.05	<0.001	<0.05		3.4		8.2	<0.005		530	**1190**		
GWQ-4	6/15/1981	<0.01	<0.002	<0.2	0.065	<0.01	30	<0.05	<0.05	<0.05	<0.05	0.68	<0.1	<0.05	<0.001	<0.05	<0.05	0.53	<0.02	7.2	<0.005	<0.02	255	776		<0.025
	11/6/1981	<0.01	<0.01	<0.2	<0.1	<0.005	22	<0.01	<0.02	<0.05	<0.01	0.7	<0.1	<0.05	<0.001	<0.05	<0.05	2	<0.02	7.9	<0.005	<0.02	162	500		**0.28**
	4/1/1993	<0.1	<0.005	1	0.02	<0.002	27	<0.02	<0.05	<0.01	<0.01	0.73	0.2	<0.02	<0.001	<0.02	<0.01	0.1	<0.02	7.6	<0.005	<0.01	235	702		**0.38**
	5/26/1994	<0.025	<0.005	<0.1	<0.1	<0.0005	30	<0.025	<0.05	<0.025		0.63	0.13	<0.03	<0.001	<0.05	<0.05	<1	<0.005	8.08	<0.005	<0.025	220	926		**0.56**
	11/5/2010	<0.02	<0.001	0.057	<0.04	<0.002	72	<0.006	<0.006	0.0075		0.73	0.059	0.029	<0.0002	<0.008	<0.01		<0.005	7.53	0.0059	<0.005	230	798	0.0037	**0.14**
GWQ-5	6/15/1981	<0.25	<0.002	<1	0.054	<0.005	42	<0.01	<0.05	<0.02	<0.01	1.03	<0.1	<0.02	<0.001	<0.05	<0.05	0.37	<0.02	7.3	<0.005	<0.02	575	**1070**		<0.025
GWQ-6	6/15/1981	<0.01	<0.01	<1	0.135	<0.01	32.6	<0.01	<0.05	<0.02	<0.01	1.09	<0.05	0.11	**0.00235**	<0.05	<0.05	3.3	<0.05	7.3	0.0046	<0.02	40.5	400		<0.05
	2/25/1982					<0.005	102			<0.05	<0.01	1.1	<0.1	<0.05	<0.001	<0.05		0.5		8.3	<0.005		220	810		
	4/1/1993	<0.1	<0.005	0.6	0.09	<0.002	22	<0.02	<0.05	0.03	<0.01	0.84	**5.05**	**0.36**	<0.001	<0.02	<0.01	1.1	<0.02	7.7	<0.005	<0.01	10	304		0.03
GWQ-7	1/20/1981						200						0.03							7.2			350	500		
	2/2/1981						20						**3.8**							7.9			156	530		
	3/27/1981		<0.01							<0.05	<0.01	0.6						1.4	<0.02							**0.28**
	4/6/1981		0.003							<0.05	**0.36**	0.59						0.9	<0.01							**0.24**
	6/15/1981	<0.25	<0.01	<1	<0.1	<0.005	20	<0.01	<0.05	<0.02	<0.05	0.5	<0.05	<0.02	<0.001	<0.05	<0.05	1.1	<0.05	7.2	<0.005	<0.02	165	510		**0.38**
	8/7/1981						100						0.02							7.4			150	475		
	8/10/1981		<0.01				24			<0.05	<0.01	0.6	**1.7**					1.2	<0.02	7.7			162	490		**0.63**
	10/23/1981	<0.01	<0.01	<0.02	<0.1	<0.005	26	<0.01	<0.02	<0.05	<0.01	0.5	0.14	<0.05	<0.001	<0.05	<0.05	1.1	<0.02		<0.005	<0.02	160	490		**0.16**
	11/6/1981	<0.01	<0.01	<0.2	<0.1	<0.005	24	<0.01	<0.02	<0.05	<0.01	0.8	<0.1	<0.05	<0.001	<0.05	<0.05	1.2	<0.02	8.1	<0.005	<0.02	158	480		**0.19**
	2/25/1982					<0.005	26			<0.05	<0.01	0.5	0.17	<0.05	<0.001	<0.05		0.8		8	<0.005		162	510		
	12/28/1982					<0.005	20			<0.05	<0.01	0.3	0.26	0.16	<0.001	<0.05		<0.2		8.1	<0.005		40	250		
	2/21/1983					<0.005	22			<0.05	<0.01	0.4	<0.1	**0.27**	<0.001	<0.05		2.8		8.3	<0.005		47	250		
	3/16/1983													<0.05												
	5/13/1983					<0.005	20			<0.05	<0.01	0.6	<0.1	<0.05	<0.001	<0.05		1.2		8.1	<0.005		158	470		
	8/9/1983					<0.005	22			<0.05	<0.01	0.6	<0.1	<0.05	<0.001	<0.05		1		8	<0.005		130	490		
	11/1/1983					<0.005	22			<0.05	<0.01	0.6	<0.1	<0.05	<0.001	<0.05		1.8		8.1	<0.005		137	500		

APPENDIX B3

GROUNDWATER SAMPLE ANALYTICAL RESULTS

Stage 1 Abatement Plan Investigation Report

Copper Flat Mine Site, New Mexico

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	Lead	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.2	0.002	1.0	0.2	10	0.05	6-9	0.05	0.05	600	1000	0.03	0.03
GWQ-7	3/16/1984					<0.005	20			<0.05	<0.01	0.8	<0.1	<0.05	<0.001	0.08		1		8.3	<0.005		140	450		
	5/30/1984					<0.005	20			<0.05	0.02	0.6	<0.1	<0.05	<0.001	<0.05		0.9		7.7	<0.005		154	470		
	9/12/1984					<0.005	20			<0.05	<0.01	0.6	<0.1	<0.05	<0.001	<0.05		1.4		8	<0.005		128	500		
	11/27/1984					<0.005	18			<0.05	<0.01	0.6	<0.1	<0.05	<0.001	<0.05		1.4		7.7	<0.005		144	490		
	5/17/1985						20													7.9			144	500		
	11/13/1985						18													7.8			137	450		
	5/23/1986						22													7.9			142	490		
	10/8/1986						22													7.4			116	460		
	3/30/1989	<0.1		<0.1	<0.1	<0.1	15.9	<0.1	<0.05	<0.1			<0.1	<0.05		<0.1	<0.1		<0.1			<0.1	131	492		**0.1**
	3/30/1993	<0.1	<0.005	<0.5	0.04	<0.002	21	<0.02	<0.05	<0.01	<0.01	0.56	<0.05	<0.02	<0.001	<0.02	<0.01	**138**	<0.02	7.8	<0.005	<0.01	138	482		**0.1**
	5/25/1994	0.25	<0.005	<0.1		0.00058	20	<0.025		0.11		**2.1**	0.72	**1.1**	<0.001		<0.05	<1	<0.005	7.26	<0.005	<0.025	**1300**	**2420**		<0.05
	7/21/1994	<0.05	<0.005	<0.1	<0.1	<0.0005	22	<0.025	<0.05	<0.025		**16**	**1.2**	**0.21**	<0.001	<0.05	<0.05	<1	<0.005	7.72	<0.005	<0.025	<5	224		<0.05
GWQ-8	6/4/1976				<0.1		16.7					0.51	0.002	0.003				**16.8**		7.48			114	560		
	2/2/1981						20						**1.7**					**60**		7.9			156	520		
	8/19/1981	<0.25	<0.004	<1	0.076	<0.01	24	<0.05	<0.05	<0.05	<0.05	0.59	<0.1	0.047	<1	<0.1	<0.05	2.8	<0.05	7.42	0.004	<0.02	134	608		**0.69**
	2/25/1982					<0.005	38			<0.05	<0.01	1	<0.1	0.17	<0.001	<0.05		0.3		7.6	<0.005		220	380		
	3/31/1993	<0.1	<0.005	<0.5	0.03	<0.002	22	<0.01	<0.05	0.01	<0.01	0.51	<0.05	<0.02	<0.001	<0.02	<0.02	5.7	<0.02	7.7	<0.005	<0.01	283	764		**0.09**
	5/25/1994	<0.025	<0.005	<0.1	<0.1	<0.0005	41	<0.025	<0.05	<0.025		0.5	0.24	<0.03	<0.001	<0.05	<0.05	5.3	<0.005	7.97	<0.005	<0.025	290	792		<0.05
GWQ-9	6/4/1976				<0.1		19.9					0.44	0.004	0.001				4		8.6			34	350		
	1/20/1981						200						0.05							7.4			300	450		
	2/2/1981						20						**1.8**							7.9			156	510		
	3/27/1981		<0.01							<0.05	<0.01	0.6						1.4	<0.02							**0.16**
	4/6/1981		0.002							<0.05	0.15	0.56						1.2	<0.01							**0.13**
	8/7/1981						100						0.06							7.4			140	450		
	8/10/1981		<0.01				22			<0.05	<0.01	0.5	0.49					1.4	0.033	8			148	470		**0.96**
	10/8/1981	<0.25	<0.004	<1	0.044	<0.01	22.4	<0.05	<0.05	<0.05	<0.05	0.6	<0.1	<0.02	<1	<0.1	<0.05	0.96	<0.05	7.22	<0.002	<0.02	133	476		**0.35**
	2/25/1982					<0.005	26			<0.05	<0.01	0.5	<0.1	<0.05	<0.001	<0.05		0.9		8.3	<0.005		160	430		
	12/28/1982					<0.005	20			<0.05	<0.01	0.5	<0.1	<0.05	<0.001	<0.05		1		7.8	<0.005		150	480		
	2/21/1983					<0.005	20			<0.05	<0.01	0.5	<0.1	<0.05	<0.001	<0.05		1.4		8	<0.005		161	480		

APPENDIX B3
GROUNDWATER SAMPLE ANALYTICAL RESULTS
Stage 1 Abatement Plan Investigation Report
Copper Flat Mine Site, New Mexico

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	Lead	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.2	0.002	1.0	0.2	10	0.05	6-9	0.05	0.05	600	1000	0.03	0.03
GWQ-9	5/13/1983					<0.005	20			<0.05	<0.01	0.5	<0.1	<0.05	<0.001	<0.05		1.1		8.2	<0.005		158	460		
	8/9/1983					<0.005	20			<0.05	<0.01	0.5	<0.1	<0.05	<0.001	<0.05		0.9		8	<0.005		135	480		
	11/1/1983					<0.005	18			<0.05	<0.01	0.5	<0.1	<0.05	<0.001	<0.05		0.8		8.2	<0.005		132	460		
	3/16/1984					<0.005	18			<0.05	<0.01	0.7	<0.1	<0.05	<0.001	<0.05		1.7		8.1	<0.005		132	460		
	5/30/1984					<0.005	18			<0.05	<0.01	0.5	<0.1	<0.05	<0.001	<0.05		0.9		7.6	<0.005		154	450		
	9/12/1984					<0.005	20			<0.05	<0.01	0.5	<0.1	<0.05	<0.001	<0.05		1.3		8	<0.005		132	470		
	11/27/1984					<0.005	16			<0.05	<0.01	0.5	<0.1	<0.05	<0.001	<0.05		1.5		7.9	<0.005		132	470		
	5/17/1985						20													8			149	490		
	11/13/1985						20													7.8			142	450		
	5/23/1986						36													7.9			137	490		
	10/8/1986						20													7.6			125	460		
GWQ-10	4/6/1981		0.002			<0.01				<0.05	0.02	0.53			<1			4.6	<0.01							**0.12**
	8/10/1981	**10.2**	<0.004	<1	0.016	<0.01	23.5	<0.05	<0.05	<0.05	<0.05	1.14	**2.31**	**1.18**	<1	<0.1	<0.05	0.22	<0.05	7.48	<0.002	<0.02	143	528		**0.23**
	10/27/1981	<0.01	<0.01	<0.2	<0.1	<0.005	22	<0.01	<0.02	<0.05	<0.01	0.6	<0.01	<0.05	<0.001	<0.05	<0.05	1.1	<0.02	8.2	<0.005	<0.02	168	520		**0.25**
	10/30/1981	<0.25	<0.005	<1	**0.77**	<0.01	22.8	<0.05	<0.05	<0.05	<0.05	0.98	<1	<0.02	<0.001	<0.1	<0.02	0.66	<0.05	8.1	<0.002	<0.02	122	588		**0.24**
	11/6/1981	<0.01	<0.01	<0.2	<0.1	<0.005	22	<0.01	<0.02	<0.05	<0.01	0.7	<0.1	<0.05	<0.001	<0.05	<0.05	2	<0.02	7.9	<0.005	<0.02	162	500		**0.28**
	11/13/1981	0.37	<0.005	0.25	0.037	0.001	22.85	<0.005			0.001	0.62		**0.5**	<0.0005	<0.01	<0.05	1.8	<0.005	7.75	0.01	<0.001	140.9	509		**0.9**
	11/17/1981	<0.01	<0.01	<0.2	<0.1	<0.005	26	<0.01	<0.02	<0.05	<0.01	0.6	<0.1	<0.05	<0.001	<0.05	<0.05	1.8	<0.02	7.9	<0.005	<0.02	156	500		**0.28**
	11/23/1981	<0.01	<0.01	<0.2	<0.1	<0.005	26	<0.01	<0.02	<0.05	<0.01	0.6	<0.1	<0.05	<0.001	<0.05	<0.05	1.8	<0.02	7.7	<0.005	<0.02	161	650		**0.37**
	12/7/1981	<0.01	<0.01	<0.2	<0.1	<0.005	24	<0.01	<0.02	<0.05	<0.01	0.5	<0.1	<0.05	<0.001	<0.05	<0.05	1.8	<0.02	8.2	<0.005	<0.02	168	490		**0.87**
	12/15/1981	<0.01	<0.01	<0.2	<0.1	<0.005	24	<0.01	<0.02	<0.05	<0.01	0.7	<0.1	<0.05	<0.001	<0.05	<0.05	2.6	<0.02	7.9	<0.005	<0.02	181	550		**0.44**
	12/22/1981	<0.01	<0.01	<0.2	<0.1	<0.005	24	<0.01	<0.02	<0.05	<0.01	0.5	<0.1	<0.05	<0.001	<0.05	<0.05	2.5	<0.02	8.1	<0.005	<0.02	168	480		**0.35**
	1/5/1982	<0.01	<0.01	<0.2	<0.1	<0.005	22	<0.01	<0.02	<0.05	<0.01	0.6	0.13	<0.05	<0.001	<0.05	<0.05	2.9	<0.02	7.5	<0.005	<0.02	174	430		**0.31**
	1/26/1982					<0.005	24			<0.05	<0.01	0.6	<0.1	<0.05	<0.001	<0.1		2.3		7.8	<0.005		162	490		
	2/22/1982					<0.005	24			<0.05	<0.01	0.6	0.12	<0.05	<0.001	<0.05		2.1		7.6	<0.005		161	510		
	4/26/1982					<0.005	20			<0.05	<0.01	0.6	0.41	<0.05	<0.001	<0.05		2		7.4	<0.005		168	840		
	5/17/1982					<0.005	28			<0.05	<0.01	0.6	0.1	<0.05	<0.001	<0.05		2.3		7.7	<0.005		175	490		
	6/8/1982					<0.005	22			<0.05	<0.01	0.5	<0.1	<0.05	<0.001	<0.05		2.2		8	<0.005		162	500		
	6/30/1982					<0.005	20			<0.05	<0.01	0.6	0.62	<0.05	<0.001	<0.05		3.3		8	<0.005		160	510		

APPENDIX B3
GROUNDWATER SAMPLE ANALYTICAL RESULTS
Stage 1 Abatement Plan Investigation Report
Copper Flat Mine Site, New Mexico

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	Lead	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.2	0.002	1.0	0.2	10	0.05	6-9	0.05	0.05	600	1000	0.03	0.03
GWQ-10	9/2/1982					<0.001	22.3					0.54		<0.05		<0.01		2.25		7.3	<0.005		143.4	506		
	12/23/1982					<0.005	26			<0.05	<0.01	0.6	<0.1	<0.05	<0.001	<0.05		1.7		8.5	<0.005		138	500		
	2/21/1983					<0.005	24			<0.05	<0.01	0.6	<0.1	<0.05	<0.001	<0.05		2.4		7.9	<0.005		161	470		
	5/13/1983					<0.005	32			<0.05	0.02	0.6	<0.1	<0.05	<0.001	<0.05		2.4		8	<0.005		161	480		
	8/9/1983					<0.005	36			<0.05	<0.01	0.6	<0.1	<0.05	<0.001	<0.05		2.4		7.9	<0.005		142	510		
	11/1/1983					<0.005	34			<0.05	<0.01	0.6	0.17	<0.05	<0.001	<0.05		4.8		8.1	<0.005		125	500		
	3/16/1984					<0.005	42			<0.05	<0.01	0.5	0.11	<0.05	<0.001	<0.05		3.5		8.2	<0.005		128	500		
	5/30/1984					<0.005	56			<0.05	<0.01	0.5	<0.1	<0.05	<0.001	<0.05		3.3		7.5	<0.005		161	530		
	9/12/1984					<0.005	68			<0.05		0.5	<0.1	<0.05	<0.001	<0.05		4.2		7.8	<0.005		158	580		
	11/27/1984					<0.005	64			<0.05	<0.01	0.6	<0.1	<0.05	<0.001	<0.05		4.9		7.7	<0.005		163	580		
	5/17/1985						52													7.8			163	570		
	11/13/1985						42													7.7			149	500		
	5/23/1986						58													7.9			151	560		
	10/8/1986						54													7.5			137	550		
	3/4/1987	<0.1		<0.1	<0.1	<0.1	59	<0.1	<0.05	<0.1			<0.1	<0.05		<0.1	<0.1		<0.1			<0.1	150	568		<0.1
	5/25/1987																						154.2			
	1/12/1988	<0.1		<0.1	<0.1	<0.1	78.8	<0.1	<0.05	<0.1			<0.1	<0.05		<0.1	<0.1		<0.1			<0.1	173	648		<0.1
	4/4/1988						65																170.6	552		
	8/23/1988						63																179.2	692		
	2/9/1989						76.3																180.5	618		
	6/1/1989						67.9																162.7	604		
	11/30/1989						72.1																161.7	620		
	11/14/1990						92.7																178	635		
	2/11/1991		<0.001				78.1																213.5	696		
	7/19/1991		0.002	0.02		<0.005	83.3	<0.02				0.51	0.07	<0.02	<0.0002			3.88	<0.005	8.05	0.002	<0.02	166.6	645		
	8/29/1991						84.7													7.44			191.7	665		
	11/26/1991						58.2													7.46			171.2	648		
	3/15/1992						82.5													7.85			191.6	641		
	5/25/1992						83.8													7.41			169.2	621		

APPENDIX B3

GROUNDWATER SAMPLE ANALYTICAL RESULTS

Stage 1 Abatement Plan Investigation Report

Copper Flat Mine Site, New Mexico

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	Lead	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.2	0.002	1.0	0.2	10	0.05	6-9	0.05	0.05	600	1000	0.03	0.03
GWQ-10	7/16/1992						76.3													7.51			166.6	626		
	10/8/1992						83.4													7.43			161.4	659		
	11/27/1992						80.3													7.89			174.4	654		
	12/15/1992						90.9													7.48			168.7	582		
	2/25/1993						95.5													7.39			175.8	620		
	3/30/1993	<0.1	<0.005	<0.5	0.04	<0.002	94	<0.02	<0.05	<0.01	<0.01	0.52	<0.05	<0.02	<0.001	<0.02	<0.01	3.9	<0.02	7.8	<0.005	<0.01	183	642		**0.11**
	9/28/1993						96													7.7			142.6	693		
	5/26/1994	0.85	<0.005	<0.1		<0.0005	92	<0.025		0.026		0.51	**1.1**	0.059	<0.001		<0.05	3.5	<0.005	7.82	<0.005	<0.025	175	1000		**0.55**
	6/23/1994						103.6													7.97			191.6	671		
	7/23/1994	<0.05	<0.005	<0.1	<0.1	<0.0005	98	<0.025	<0.05	<0.025		0.49	<0.05	<0.03	<0.001	<0.05	<0.05	3.5	<0.005	7.97	<0.005	<0.025	184	696		<0.05
	9/22/1994						89.2													7.45			155.8	668		
	1/29/1995						87.5													7.52			65.7	672		
	3/29/1995						84.9													7.67			176	622		
	6/27/1995						84.8													7.29			168.7	677		
	9/21/1995						91.3													7.42			187.4	693		
	1/10/1996						97.7													7.29			197.5	654		
	4/3/1996						97.4													6.95			218.2	628		
	9/25/1996						86.2													7.56			190.8	679		
	1/15/1997						91													7.59			203.67	746		
GWQ-11	8/10/1981	<0.25	<0.004	<1	0.092	<0.01	37	<0.05	<0.05	<0.05	<0.05	0.9	**1.14**	**0.45**	<1	<0.1	<0.05	1.02	<0.05	7.38	0.006	<0.02	123	612		<0.05
	10/27/1981	<0.01	<0.01	<0.2	<0.1	<0.005	36	<0.01	<0.02	<0.05	<0.01	1	<0.1	<0.05	<0.001	<0.05	<0.05	0.7	<0.02	8.1	<0.005	<0.02	183	550		**0.17**
	10/30/1981	<0.25	<0.005	<1	0.55	<0.01	39.1	<0.05	<0.05	<0.05	<0.05	0.96	<0.1	<0.02	<0.001	<0.1	<0.02	0.61	<0.05	8.4	<0.011	<0.02	101	536		**0.23**
	11/6/1981	<0.01	<0.01	<0.2	<0.1	<0.005	36	<0.01	<0.02	<0.05	<0.01	1	<0.1	<0.05	<0.001	<0.05	<0.05	1.5	<0.02	8.1	<0.005	<0.02	168	520		**0.29**
	11/13/1981	<0.25	<0.005	0.2	0.041	0.001	37.64	<0.005			<0.001	0.99		<0.05	<0.0005	0.12	<0.05	1.33	<0.005	7.7	0.023	<0.001	155.6	544		**0.79**
	11/17/1981	<0.01	<0.01	<0.2	<0.1	<0.005	36	<0.01	<0.02	<0.05	<0.01	1	<0.1	<0.05	<0.001	<0.05	<0.05	1.3	<0.02	8	<0.005	<0.02	165	520		**0.64**
	11/23/1981	<0.01	<0.01	<0.2	<0.1	<0.005	36	<0.01	<0.02	<0.05	<0.01	0.9	<0.1	<0.05	<0.001	<0.05	<0.05	1.7	<0.02	7.8	<0.005	<0.02	181	570		**0.53**
	12/7/1981	<0.01	<0.01	<0.2	<0.1	<0.005	56	<0.01	<0.02	<0.05	<0.01	0.9	<0.1	<0.05	**0.0064**	<0.05	<0.05	1.6	<0.02	7.9	<0.005	<0.02	184	560		**1.6**
	12/15/1981	<0.01	<0.01	<0.2	<0.1	<0.005	38	<0.01	<0.02	<0.05	<0.01	1	<0.1	<0.05	<0.001	<0.05	<0.05	1.5	<0.02	7.9	<0.005	<0.02	191	570		**1.1**
	12/22/1981	<0.01	<0.01	<0.2	<0.1	<0.005	40	<0.01	<0.02	<0.05	<0.01	0.5	0.27	0.093	<0.001	<0.05	<0.05	1.9	<0.02	8	<0.005	<0.02	185	530		**0.42**

APPENDIX B3
GROUNDWATER SAMPLE ANALYTICAL RESULTS
Stage 1 Abatement Plan Investigation Report
Copper Flat Mine Site, New Mexico

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	Lead	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.2	0.002	1.0	0.2	10	0.05	6-9	0.05	0.05	600	1000	0.03	0.03
GWQ-11	1/5/1982	<0.01	<0.01	<0.2	<0.1	<0.005	40	<0.01	<0.02	<0.05	<0.01	1	0.14	<0.05	<0.001	<0.05	<0.05	2.5	<0.02	7.5	<0.005	<0.02	174	480		**0.44**
	1/26/1982					<0.005	40			<0.05	<0.01	1	<0.1	<0.05	<0.001	<0.1		1.7		7.9	<0.005		168	500		
	2/22/1982					<0.005	38			<0.05	<0.01	0.9	0.11	<0.05	<0.001	<0.05		1.4		7.7	<0.005		168	510		
	4/26/1982					<0.005	40			<0.05	<0.01	0.8	0.36	<0.05	<0.001	0.05		1.3		7.6	<0.005		165	510		
	5/17/1982					<0.005	44			<0.05	<0.01	0.8	0.11	<0.05	<0.001	<0.05		1.9		7.8	<0.005		185	510		
	6/8/1982					<0.005	44			<0.05	<0.01	0.8	<0.1	<0.05	<0.001	<0.05		1.7		7.9	<0.005		185	530		
	6/30/1982					<0.005	44			<0.05	<0.01	0.8	0.39	<0.05	<0.001	<0.05		2.3		7.9	<0.005		198	590		
	9/2/1982					<0.001	52.22					0.78		<0.05		<0.01		1.94		7.3	<0.005		247.6	700		
	12/23/1982					<0.005	52			<0.05	<0.01	0.8	<0.1	<0.05	<0.001	<0.05		1.6		8.5	<0.005		235	650		
	2/21/1983					<0.005	44			<0.05	<0.01	0.8	0.38	<0.05	<0.001	<0.05		1.7		8	<0.005		218	600		
	5/13/1983					<0.005	44			<0.05	0.01	0.8	<0.1	<0.05	<0.001	<0.05		1.9		8.1	<0.005		206	570		
	8/9/1983					<0.005	46			<0.05	<0.01	0.8	<0.1	<0.05	<0.001	<0.05		2		7.9	<0.005		168	580		
	11/1/1983					<0.005	46			<0.05	<0.01	0.8	<0.1	<0.05	<0.001	<0.05		4.8		8	<0.005		174	580		
	3/16/1984					<0.005	52			<0.05	<0.01	0.6	<0.1	<0.05	<0.001	<0.05		3.8		8.3	<0.005		184	540		
	5/30/1984					<0.005	58			<0.05	<0.01	0.8	<0.1	<0.05	<0.001	<0.05		1.9		7.5	<0.005		195	550		
	9/12/1984					<0.005	60			<0.05	<0.01	0.8	<0.1	<0.05	<0.001	<0.05		2.3		7.9	<0.005		181	590		
	11/27/1984					<0.005	60			<0.05	<0.01	0.8	<0.1	<0.05	<0.001	<0.05		2.3		7.7	<0.005		165	570		
	5/17/1985						64													7.8			197	640		
	11/13/1985						62													7.7			183	600		
	5/23/1986						66													7.8			210	650		
	10/8/1986						70													7.6			200	560		
	3/4/1987	<0.1		<0.1	<0.1	<0.1	69	<0.1	<0.05	<0.1			<0.1	<0.05		<0.1	<0.1		<0.1	6.7		<0.1	200	696		<0.1
	5/25/1987																						230			
	1/12/1988	<0.1		<0.1	<0.1	<0.1	77.1	<0.1	<0.05	<0.1			<0.1	<0.05		<0.1	<0.1		<0.1			<0.1	253	718		<0.1
	4/4/1988						74.6																277.7	694		
	8/23/1988						73																293.8	772		
	2/9/1989						77																258.4	730		
	6/1/1989						69.7																238.2	708		
	11/30/1989						79.8																254.3	732		

APPENDIX B3
GROUNDWATER SAMPLE ANALYTICAL RESULTS
Stage 1 Abatement Plan Investigation Report
Copper Flat Mine Site, New Mexico

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	Lead	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.2	0.002	1.0	0.2	10	0.05	6-9	0.05	0.05	600	1000	0.03	0.03
GWQ-11	11/14/1990						104.4																257.4	746		
	2/11/1991		<0.001				88.9																233.4	790		
	7/19/1991		0.004	0.1		<0.005	89.7	<0.02				0.74	<0.05	<0.02	<0.0002			3.93	<0.002	7.36	0.002	<0.02	210.2	785		
	8/29/1991						92.6													7.46			278.6	771		
	11/26/1991						89.3													7.29			240.7	770		
	3/15/1992						65.1													7.91			260.2	765		
	5/25/1992						96.2													7.45			258.1	761		
	10/8/1992						96													7.42			226.9	755		
	11/27/1992						96													7.85			248.4	763		
	12/15/1992						98.1			0.017										7.59			220	741		
	2/25/1993						104													7.64			273.3	762		
	3/30/1993	0.2	<0.005	<0.5	0.04	<0.002	104	<0.02	<0.05	<0.01	<0.01	0.52	0.33	0.03	<0.001	<0.02	<0.01	4.1	<0.02	7.7	<0.005	<0.01	271	776		0.03
	9/28/1993						105.6													7.57			207.7	800		
	5/25/1994	0.14	<0.005	<0.1		<0.0005	110	<0.025		<0.025		0.72	0.16	<0.03	<0.001		<0.05	3.8	<0.005	7.88	<0.005	<0.025	260	820		<0.05
	6/23/1994						117.2													7.42			274.6	802		
	7/22/1994	<0.05	<0.005	<0.1	<0.1	<0.0005	116	<0.025	<0.05	<0.025		0.7	<0.05	<0.03	<0.001	<0.05	<0.05	3.8	<0.005	7.7	<0.005	<0.025	272	808		<0.05
	9/22/1994						112.3													7.37			234.5	816		
	1/29/1995						199.5													7.6			158.7	861		
	3/29/1995						99.4													7.96			136.9	793		
	6/27/1995						101.7													7.67			278.8	835		
	9/21/1995						112.1													7.58			289.5	865		
	1/10/1996						120.8													7.36			287.5	777		
	4/3/1996						119.2													7.38			276.5	767		
	9/25/1996						116													7.78			229.9	835		
	1/15/1997						127													7.68			303.9	860		
GWQ-12	2/21/1983					<0.005	18			<0.05	<0.01	1	<0.1	<0.05		<0.05		2.2		7.7	<0.005		53	360		
	5/13/1983					<0.005	16			<0.05	<0.01	1	<0.1	<0.05	<0.001	<0.05		2.1		8.1	<0.005		37	330		
	8/9/1983					<0.005	22			<0.05	<0.01	0.6	<0.1	<0.05	<0.001	<0.05		1.1		7.8	<0.005		130	480		
	11/1/1983					<0.005	14			<0.05	<0.01	1.1	0.32	<0.05	<0.001	<0.05		2.8		8.2	<0.005		38	340		

APPENDIX B3
GROUNDWATER SAMPLE ANALYTICAL RESULTS
Stage 1 Abatement Plan Investigation Report
Copper Flat Mine Site, New Mexico

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	Lead	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.2	0.002	1.0	0.2	10	0.05	6-9	0.05	0.05	600	1000	0.03	0.03
GWQ-12	3/16/1984					<0.005	14			<0.05	<0.01	1.1	<0.1	<0.05	<0.001	<0.05		3.8		8.2	<0.005		44	320		
	5/30/1984					<0.005	16			<0.05	<0.01	1	<0.1	<0.05	<0.001	<0.05		2.5		8	<0.005		47	320		
	9/12/1984					<0.005	16			<0.05	<0.01	1	<0.1	<0.05	<0.001	<0.05		2.2		8	<0.005		38	330		
	11/27/1984					<0.005	14			<0.05	<0.01	1	<0.1	<0.05	<0.001	<0.05		2.3		7.8	<0.005		37	340		
	5/27/1985						14													8			36	370		
	11/13/1985						14													7.8			35	310		
	5/23/1986						16													7.8			31	330		
	10/8/1986						16													7.6			35	310		
	7/21/1994	<0.05	<0.005	<0.1	<0.1	<0.0005	16	<0.025	<0.05	<0.025		0.99	<0.05	<0.03	<0.001	<0.05	<0.05	2.1	<0.005	7.75	<0.005	<0.025	38	358		<0.05
GWQ94-13	11/15/1994	<0.05	<0.005	<0.1	<0.1	<0.0005	190	<0.025	<0.05	<0.025		0.36	0.11	<0.03	<0.001	<0.05	<0.05	4.6	<0.005	7.74	<0.005	<0.025	**720**	**1570**		<0.05
	7/1/1996	<0.025	<0.005	<0.05	<0.05	<0.0005	200	<0.025	<0.05	<0.025		0.34	<0.05	<0.03	<0.001	<0.05	<0.05	5.2	<0.005	7.76	0.0068	<0.05	**620**	**1520**		<0.05
	7/2/2010	<0.020	<0.0010	0.040	<0.040	<0.0020	**290**	<0.0060	<0.0060	<0.0060		0.35	<0.020	<0.0020	0.00026	<0.0080	<0.010		<0.0050	8	0.024	<0.0050	**770**	**1730**	0.0016	<0.010
	10/5/2010	<0.02	<0.005	0.038	<0.04	<0.002	**280**	<0.006	<0.006	<0.006		0.32	<0.02	<0.002	<0.0002	<0.008	<0.01		<0.005	7.39	0.024	<0.005	**760**	**1670**	0.0015	<0.01
GWQ94-14	1/1/1900	<0.05	<0.005	<0.1	<0.1	<0.0005	22	<0.025	<0.05	<0.025		0.52	<0.05	<0.03	<0.001	<0.05	<0.05	1.3	<0.005	7.95	<0.005	<0.025	140	560		<0.05
	6/30/1996	<0.025	<0.005	<0.05	<0.05	<0.0005	26	<0.025	<0.05	<0.025		0.48	<0.05	<0.03	<0.001	<0.05	<0.05	1.5	<0.005	8.44	<0.005	<0.05	140	520		<0.05
	1/29/2010	<0.020	0.0030	0.045	<0.040	<0.0020	50	<0.0060	<0.0060	<0.0060		0.48	<0.020	<0.0020	<0.00020	<0.0080	<0.010		<0.0050	8	0.0061	<0.0050	140	543		0.010
	6/29/2010	<0.020	0.0023	0.048	<0.040	<0.0020	49	<0.0060	<0.0060	<0.0060		0.48	<0.020	<0.0020	<0.00020	<0.0080	<0.010		<0.0050	8	0.0052	<0.0050	150	573	0.0014	<0.010
	10/5/2010	<0.02	0.0024	0.045	<0.04	<0.002	50	<0.006	<0.006	<0.006		0.53	<0.02	<0.002	<0.0002	<0.008	<0.01		<0.005	7.57	0.0053	<0.005	150	563	0.0013	<0.01
GWQ94-15	11/14/1994	<0.05	<0.005	<0.1	<0.1	<0.0005	110	<0.025	<0.05	<0.025		0.46	<0.05	<0.03	<0.001	<0.05	<0.05	2.1	<0.005	7.74	<0.005	<0.025	180	790		<0.05
	7/1/1996	<0.025	<0.005	<0.05	<0.05	<0.0005	130	<0.025	<0.05	<0.025		0.42	0.41	<0.03	<0.001	<0.05	<0.05	2.5	<0.005	7.31	<0.005	<0.05	240	780		<0.05
	1/29/2010	<0.020	0.0042	0.058	<0.040	<0.0020	170	<0.0060	<0.0060	<0.0060		0.30	<0.020	<0.0020	<0.00020	<0.0080	<0.010		<0.0050	7	0.021	<0.0050	420	**1080**		0.022
	6/29/2010	<0.020	<0.0010	0.059	<0.040	<0.0020	110	<0.0060	<0.0060	<0.0060		0.43	<0.020	0.0049	<0.00020	<0.0080	<0.010		<0.0050	8	0.0095	<0.0050	260	805	0.0017	<0.010
	10/1/2010	<0.02	<0.001	0.056	<0.04	<0.002	110	<0.006	<0.006	<0.006		0.44	<0.02	<0.002	<0.0002	<0.008	<0.01		<0.005	7.52	0.012	<0.005	260	794	0.0018	<0.01
GWQ94-16	11/13/1994	<0.05	<0.005	<0.1	<0.1	<0.0005	190	<0.025	<0.05	<0.025		0.66	<0.05	0.038	<0.001	<0.05	<0.05	3.8	<0.005	7.55	<0.005	<0.025	410	**1140**		<0.05
	7/1/1996	<0.025	<0.005	<0.05	<0.05	<0.0005	200	<0.025	<0.05	<0.025		0.57	0.22	<0.03	<0.001	<0.05	<0.05	3.7	<0.005	7.95	<0.005	<0.05	500	**1160**		<0.05
	6/29/2010	<0.020	0.0022	0.039	0.048	<0.0020	180	<0.0060	<0.0060	<0.0060		0.62	<0.020	<0.0020	<0.00020	<0.0080	<0.010		<0.0050	8	0.011	<0.0050	440	**1190**	0.0025	<0.010
	9/30/2010	<0.02	0.0024	0.038	0.053	<0.002	190	<0.006	<0.006	<0.006		0.67	<0.02	<0.002	<0.0002	<0.008	<0.01		<0.005	7.5	0.015	<0.005	440	**1170**	0.0024	<0.01
GWQ94-17	11/15/1994	<0.05	<0.005	<0.1	<0.1	<0.0005	110	<0.025	<0.05	<0.025		0.46	<0.05	<0.03	<0.001	<0.05	<0.05	2.4	<0.005	7.71	<0.005	<0.025	240	820		<0.05

APPENDIX B3
GROUNDWATER SAMPLE ANALYTICAL RESULTS
Stage 1 Abatement Plan Investigation Report
Copper Flat Mine Site, New Mexico

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	Lead	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.2	0.002	1.0	0.2	10	0.05	6-9	0.05	0.05	600	1000	0.03	0.03
GWQ94-17	6/30/1996	<0.025	<0.005	<0.05	<0.05	<0.0005	81	<0.025	<0.05	<0.025		0.46	0.062	<0.03	<0.001	<0.05	<0.05	2	<0.005	8.56	<0.005	<0.05	190	690		<0.05
	7/6/2010	<0.020	0.0022	0.047	<0.040	<0.0020	68	<0.0060	<0.0060	<0.0060		0.52	<0.020	<0.0020	<0.00020	<0.0080	<0.010		<0.0050	8	0.0062	<0.0050	180	629	0.0016	<0.010
GWQ94-20	11/15/1994	<0.05	<0.005	<0.1	0.11	<0.0005	19	<0.025	<0.05	<0.025		0.36	<0.05	**0.42**	<0.001	<0.05	<0.05	1	<0.005	7.66	<0.005	<0.025	40	370		<0.05
	6/30/1996	<0.025	<0.005	0.12	0.086	<0.0005	21	<0.025	<0.05	<0.025		0.29	<0.05	<0.03	<0.001	<0.05	<0.05	<1	<0.005	8.79	<0.005	<0.05	56	390		<0.05
GWQ94-21A	11/13/1994	<0.05	<0.005	<0.1	<0.1	<0.0005	18	<0.025	<0.05	<0.025		0.57	<0.05	0.2	<0.001	<0.05	<0.05	1	<0.005	7.25	<0.005	<0.025	130	480		<0.05
	6/30/1996	<0.025	<0.005	<0.05	<0.05	<0.0005	16	<0.025	<0.05	<0.025		0.51	<0.05	<0.03	<0.001	<0.05	<0.05	1.1	<0.005	8.22	<0.005	<0.05	120	470		<0.05
GWQ94-21B	11/13/1994	<0.05	<0.005	<0.1	<0.1	<0.0005	19	<0.025	<0.05	<0.025		0.39	<0.05	**0.37**	<0.001	<0.05	<0.05	<1	<0.005	7.57	<0.005	<0.025	130	440		<0.05
	6/30/1996	<0.025	<0.005	<0.05	<0.05	<0.0005	17	<0.025	<0.05	<0.025		0.52	<0.05	<0.03	<0.001	<0.05	<0.05	1.1	<0.005	8.6	<0.005	<0.05	120	470		<0.05
GWQ96-22A	7/13/1996	<0.025	<0.005	<0.05	<0.05	<0.0005	89	<0.025	<0.05	<0.025		**3.3**	<0.05	0.075	<0.001	<0.05	<0.05	<1	<0.005	7.5	<0.005	<0.05	250	700		<0.05
	4/9/1997						20			<0.025		0.8	**6.5**	**2.8**	<0.001					7.58	<0.005		150	770		
	8/8/1997	0.028	<0.005	0.057	0.23	<0.002	89	<0.025	<0.05	<0.05		**2.2**	0.13	**0.53**		<0.05	<0.05	<1	<0.005	7.65	<0.005	<0.025	230	700		<0.05
	1/30/2010	<0.020	0.0029	0.094	0.28	<0.0020	81	<0.0060	<0.0060	<0.0060		**2.6**	**2.1**	**0.74**	<0.00020	<0.0080	<0.010		<0.0050	8	<0.0025	<0.0050	44	557		<0.010
	7/1/2010	<0.020	0.0035	0.079	0.28	<0.0020	70	<0.0060	<0.0060	<0.0060		**2.7**	0.021	**0.65**	<0.00020	<0.0080	<0.010		<0.0050	8	0.0011	<0.0050	52	573	<0.0010	<0.010
	10/7/2010	<0.02	0.0035	0.084	0.28	<0.002	75	<0.006	<0.006	<0.006		**2.7**	0.32	**0.49**	<0.0002	<0.008	<0.01		<0.005	8	<0.001	<0.005	34	564	<0.001	<0.01
GWQ96-22B	7/13/1996	<0.025	<0.005	0.096	0.12	<0.0005	210	<0.025	<0.05	<0.025		**1.8**	<0.05	**0.41**	<0.001	<0.05	<0.05	<1	<0.005	7.75	<0.005	<0.05	79	650		<0.05
	10/7/2010	<0.02	0.0057	0.11	0.24	<0.002	110	<0.006	<0.006	<0.006		**3**	**9.3**	**1.2**	<0.0002	<0.008	<0.01		<0.005	7.52	0.0011	<0.005	<0.5	730	<0.001	<0.01
GWQ96-23A	7/14/1996	0.28	<0.005	0.064	<0.05	<0.0005	22	<0.025	<0.05	<0.025		0.84	0.26	0.05	<0.001	<0.05	<0.05	<1	<0.005	7.95	<0.005	<0.05	140	520		<0.05
	4/9/1997						16			<0.025		1.4	0.1	**0.75**	<0.001						<0.005		170	580		
	8/8/1997	0.036	<0.005	0.13	0.067	<0.002	18	<0.025	<0.05	<0.025		1.2	0.82	**1.6**		<0.05	<0.05	<1	<0.005	7.68	<0.005	<0.025	410	920		<0.05
	1/30/2010	<0.020	0.0027	0.091	0.074	<0.0020	12	<0.0060	<0.0060	<0.0060		**1.7**	0.66	**0.63**	<0.00020	<0.0080	<0.010		<0.0050	8	<0.0025	<0.0050	5.6	689		<0.010
	7/1/2010	<0.020	0.0011	0.13	0.068	<0.0020	14	<0.0060	<0.0060	<0.0060		1.5	0.048	**0.37**	<0.00020	<0.0080	<0.010		<0.0050	8	0.0014	<0.0050	140	804	0.0025	<0.010
	10/6/2010	<0.02	<0.001	0.087	0.08	<0.002	12	<0.006	<0.006	<0.006		1.6	0.31	**0.41**	<0.0002	<0.008	<0.01		<0.005	7.89	0.0013	<0.005	99	769	0.0037	<0.01
GWQ96-23B	7/14/1996	**7.4**	<0.005	0.093	0.058	<0.0005	20	<0.025	<0.05	<0.025		1.1	**3.7**	0.13	<0.001	<0.05	<0.05	<1	<0.005	8.15	<0.005	<0.05	170	550		<0.05
	10/6/2010	<0.02	<0.001	0.1	0.14	<0.002	19	<0.006	<0.006	<0.006		**2.1**	**1.4**	**0.36**	<0.0002	<0.008	<0.01		<0.005	7.85	0.0011	<0.005	<0.5	554	<0.001	<0.01
Hill	7/31/1947						10					0.6						0.7					76	320		
IW-1	3/4/1987						**575**													6.6			**1901**	**3802**		
	7/19/1991		<0.002	<0.01		<0.005	**632.6**	<0.02		<0.02		0.69	<0.05	<0.02	0.0005			9.06	<0.005	7.87	0.015	<0.02	**1985**	**4235**		
	8/29/1991						**642.4**													7.13			**1917.9**	**4120**		

APPENDIX B3

GROUNDWATER SAMPLE ANALYTICAL RESULTS

Stage 1 Abatement Plan Investigation Report

Copper Flat Mine Site, New Mexico

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	Lead	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.2	0.002	1.0	0.2	10	0.05	6-9	0.05	0.05	600	1000	0.03	0.03
IW-1	11/26/1991						**615.1**													7.53			**1634**	**3979**		
	3/15/1992						**610.7**													7.88			**2201**	**4026**		
	5/25/1992						**598.2**													7.09			**2203**	**4155**		
	7/16/1992						**584.6**													7.12			**1775**	**4297**		
	10/8/1992						**616.9**													6.96			**1726.8**	**3996**		
	11/27/1992						**604.8**													7.71			**1716.6**	**4004**		
	12/15/1992						**608.9**													7.4			**1414.6**	**3969**		
	9/28/1993						**521.1**													7.12			**1150**	**3661**		
	3/17/1994						**404.8**													7			**1569**	**3684**		
	5/24/1994	0.94	<0.005	<0.1		<0.0005	**470**	<0.025		<0.025		0.7	1	<0.03	<0.001		<0.05	5.8	<0.005	7.84	<0.005	<0.025	**1500**	**3500**		**0.053**
	6/23/1994						**473.8**													7.69			**1444**	**3555**		
	7/22/1994	<0.05	<0.005	<0.1	0.1	<0.0005	**431**	<0.025	<0.05	<0.025		0.72	<0.05	<0.03	<0.001	<0.05	<0.05	5.9	<0.005	7.51	0.018	<0.025	**1480**	**3450**		<0.05
	9/22/1994						**435.9**													7.05			**1348**	**3466**		
	1/29/1995						**663**													7.18			**1478.5**	**3395**		
	3/29/1995						**419.4**													7.49			**1350.7**	**3465**		
	6/27/1995						**446.1**													6.99			**1680.1**	**3599**		
	9/21/1995						**458.7**													6.82			**1710.8**	34.87		
	1/10/1996						**442.2**													7.23			**1595.5**	**3437**		
	9/25/1996						**568**													7.17			**1493**	**3551**		
	1/15/1997						**410**													7.44			**1694.5**	35.97		
IW-2	9/2/1982					<0.001	**409.07**					1.22		<0.05		<0.01		1.38		7.3	<0.005		**2252**	**4010**		
	5/25/1994	**22**	<0.005	0.12		<0.0005	**340**	0.046		<0.025		0.66	**16**	**0.77**	<0.001		0.097	1.5	0.0073	7.75	<0.005	<0.025	**1000**	**2400**		**0.084**
	7/22/1994	<0.05	<0.005	<0.1	0.15	<0.0005	**380**	<0.025	<0.05	<0.025		0.69	<0.05	0.036	<0.001	<0.05	<0.05	<1	<0.005	7.78	0.014	<0.025	**1040**	**2390**		<0.05
	1/31/2010	0.13	0.0092	0.024	0.075	<0.0020	**600**	<0.0060	0.0065	<0.0060		0.74	**1.3**	**1.6**	<0.00020	0.020	<0.010		<0.0050	8	0.033	<0.0050	**1200**	**2770**		<0.010
	6/29/2010	<0.020	<0.0010	0.029	0.061	<0.0020	**580**	<0.0060	<0.0060	<0.0060		0.67	0.87	**2.2**	0.00048	0.024	<0.010		<0.0050	7	0.029	<0.0050	**1100**	**2700**	0.0060	<0.010
	9/30/2010	0.044	<0.001	0.028	0.073	<0.002	**500**	<0.006	<0.006	<0.006		0.68	0.41	**2.2**	<0.0002	0.02	<0.01		<0.005	7.36	0.037	<0.005	**1000**	**2280**	0.0057	0.018
IW-3	9/2/1982					<0.001	159.12					0.42		<0.05		<0.01		4.12		7.2	<0.005		**707.3**	**1562**		
	2/25/1993						**589.5**													7.27			**1738.9**	**3892**		
	5/26/1994	**32**	<0.005	0.2		<0.0005	209	**0.059**		**6**		0.47	**22**	**0.35**	<0.001		0.19	5.7	**0.077**	7.83	<0.005	<0.025	415	**1870**		**0.15**

APPENDIX B3

GROUNDWATER SAMPLE ANALYTICAL RESULTS

Stage 1 Abatement Plan Investigation Report

Copper Flat Mine Site, New Mexico

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	Lead	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.2	0.002	1.0	0.2	10	0.05	6-9	0.05	0.05	600	1000	0.03	0.03
IW-3	7/23/1994	<0.05	<0.005	<0.1	<0.1	<0.0005	206	<0.025	<0.05	0.058		0.48	<0.05	0.13	<0.001	0.062	<0.05	5	<0.005	7.76	0.011	<0.025	437	**1300**		<0.05
	4/3/1996						**432.6**													7.04			**1566.3**	**3364**		
Ladder-Higgins	8/2/1994	<0.05	<0.005	<0.1	0.11	<0.0005	48	<0.025	<0.05	<0.025		**1.9**	<0.05	<0.03	<0.001	<0.05	<0.05	<1	<0.005	8.01	<0.005	<0.025	22	286		<0.05
McCravey-Greyback	3/31/1993	<0.1	<0.005	<0.5	<0.04	<0.002	30	<0.02	<0.05	<0.01	<0.01	0.51	0.05	<0.02	<0.001	<0.02	<0.01	3	<0.02	7.8	<0.005	<0.01	207	632		0.01
Miranda	7/31/1947						**380**					0.2						4.2					64	823		
MW-1	1/1/1975						10					0.7						6.1		8.1			73	433		
	9/28/2010	<0.02	0.0039	0.022	0.044	<0.002	14	<0.006	<0.006	<0.006		0.4	0.11	0.0054	<0.0002	<0.008	<0.01		<0.005	8.1	<0.005	<0.005	48	303	0.0016	**0.43**
MW-2	5/7/1975						8					**2.3**								7.9			40	327		
	7/20/1994	<0.05	0.019	<0.1	0.16	<0.0005	5.5	<0.025	<0.05	<0.025		**3.1**	0.069	<0.03	<0.001	<0.05	<0.05	<1	<0.005	9	<0.005	<0.025	18	254		<0.05
	9/28/2010	<0.02	0.02	<0.002	0.15	<0.002	5.8	0.032	<0.006	<0.006		**3.3**	<0.02	<0.002	<0.0002	<0.008	<0.01		<0.005	**9.27**	<0.005	<0.005	18	274	0.0022	<0.01
MW-4	6/13/1975						15					0.63								7.9			110			
	7/20/1994	<0.05	<0.005	<0.1	<0.1	<0.0005	17	<0.025	<0.05	<0.025		0.28	<0.05	<0.03	<0.001	<0.05	<0.05	<1	<0.005	8.34	<0.005	<0.025	66	256		<0.05
MW-5	9/19/1975						30					0.61						<0.5		7.7			26	260		
	7/20/1994	<0.05	<0.005	<0.1	<0.1	<0.0005	17	<0.025	<0.05	<0.025		0.18	<0.05	<0.03	<0.001	<0.05	<0.05	<1	<0.005	7.97	<0.005	<0.025	24	440		<0.05
MW-6	1/1/1975						66					**3.4**						4.3		7.6			38	260		
	8/2/1994	<0.05	0.013	<0.1	0.16	<0.0005	75	<0.025	<0.05	<0.025		1.6	0.41	<0.03	<0.001	<0.05	<0.05	<1	<0.005	8.09	<0.005	<0.025	45	436		<0.05
	7/8/2010	<0.020	0.018	0.0095	0.15	<0.0020	75	0.016	<0.0060	<0.0060		**8.1**	0.024	0.0027	<0.00020	0.013	<0.010		<0.0050	8	0.0015	<0.0050	49	456	<0.0010	<0.010
	9/27/2010	<0.02	0.02	0.0093	0.16	<0.002	73	0.016	<0.006	<0.006		**8.2**	0.021	<0.002	<0.0002	0.013	<0.01		<0.005	8.44	<0.005	<0.005	49	468	<0.001	<0.01
MW-8	1/1/1975						10					0.86						**15.4**		7.7			21	293		
	7/21/1994	<0.05	0.012	<0.1	<0.1	<0.0005	6.6	<0.025	<0.05	<0.025		1	0.14	<0.03	<0.001	<0.05	<0.05	<1	<0.005	8.88	<0.005	<0.025	18	290		<0.05
	10/12/2010	<0.02	0.013	<0.002	0.085	<0.002	6.5	<0.006	<0.006	<0.006		1.1	<0.02	0.0033	<0.0002	<0.008	<0.01		<0.005	**9.23**	0.0016	<0.005	16	287	0.0016	<0.01
MW-9	11/16/1994	<0.05	<0.005	<0.1	<0.1	<0.0005	12	<0.025	<0.05	<0.025		1.4	<0.05	<0.03	<0.001	<0.05	<0.05	<1	<0.005	8.05	<0.005	<0.025	12	230		<0.05
	7/7/2010	<0.020	0.0039	0.0023	<0.040	<0.0020	13	<0.0060	<0.0060	<0.0060		1.4	<0.020	<0.0020	<0.00020	<0.0080	<0.010		<0.0050	8	<0.0010	<0.0050	12	206	0.0012	<0.010
	10/4/2010	<0.02	0.0039	<0.002	0.051	<0.002	13	<0.006	<0.006	<0.006		1.3	<0.02	<0.002	<0.0002	<0.008	<0.01		<0.005	8.06	<0.001	<0.005	11	194	0.0012	<0.01
MW-10	11/16/1994	<0.05	<0.005	<0.1	<0.1	<0.0005	14	<0.025	<0.05	<0.025		0.43	<0.05	<0.03	<0.001	<0.05	<0.05	<1	<0.005	7.84	<0.005	<0.025	25	310		<0.05
MW-11	11/16/1994	<0.05	<0.005	<0.1	<0.1	<0.0005	15	<0.025	<0.05	<0.025		0.45	<0.05	<0.03	<0.001	<0.05	<0.05	<1	<0.005	7.79	<0.005	<0.025	21	314		<0.05

APPENDIX B3
GROUNDWATER SAMPLE ANALYTICAL RESULTS
Stage 1 Abatement Plan Investigation Report
Copper Flat Mine Site, New Mexico

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	Lead	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.2	0.002	1.0	0.2	10	0.05	6-9	0.05	0.05	600	1000	0.03	0.03
MW-11	7/7/2010	<0.020	0.0015	0.018	<0.040	<0.0020	14	<0.0060	<0.0060	<0.0060		0.49	<0.020	<0.0020	<0.00020	<0.0080	<0.010		<0.0050	7	<0.0010	<0.0050	15	289	<0.0010	<0.010
	10/4/2010	<0.02	0.0016	0.02	<0.04	<0.002	14	<0.006	<0.006	<0.006		0.49	<0.02	<0.002	<0.0002	<0.008	<0.01		<0.005	7.32	<0.001	<0.005	14	301	<0.001	<0.01
NP-1	10/8/1981	<0.25	<0.004	<1	<0.004	<0.01	24.9	<0.05	<0.05	<0.05	<0.05	0.84	0.27	**0.92**	<1	<0.1	<0.05	0.47	<0.05	7.6	0.003	<0.02	108	496		**0.4**
	11/4/1981	<0.01	<0.01	<0.2	<0.1	<0.005	28	<0.01	<0.02	<0.05	0.04	1	<0.1	**0.6**	<0.001	<0.05	<0.05	0.3	<0.02	8.1	<0.005	<0.02	148	470		**0.14**
	11/13/1981	<0.25	<0.005	0.2	0.044	0.006	24.08	<0.005			0.001	0.83		**1.34**	<0.0005	0.011	<0.05	0.09	<0.005	7.65	0.029	<0.001	130.7	470		**0.44**
	11/17/1981	<0.01	<0.005	0.24	<0.1	<0.005	24	<0.01	<0.02	0.069	<0.01	0.8	<0.1	**1.4**	<0.001	0.06	<0.05	0.2	<0.02	8	<0.005	<0.02	154	460		**3.9**
	11/23/1981	<0.01	<0.01	0.02	<0.1	<0.005	26	<0.02	<0.02	<0.05	<0.01	0.8	<0.1	**1.2**	<0.001	<0.05	<0.05	0.2	<0.02	7.7	<0.005	<0.02	146	530		**4.1**
	12/7/1981	<0.01	<0.01	<0.2	<0.1	<0.005	24	<0.01	<0.02	<0.05	<0.01	0.8	<0.1	**1.2**	<0.001	<0.05	<0.05	0.2	<0.02	7.3	<0.005	<0.02	158	490		**5.1**
	12/15/1981	<0.01	<0.01	<0.2	<0.1	<0.005	24	<0.01	<0.02	<0.05	<0.01	0.8	<0.1	**1.2**	<0.001	<0.05	<0.05	<0.2	<0.02	7.8	<0.005	<0.02	151	480		**5.3**
	12/22/1981	<0.01	<0.01	<0.2	<0.1	<0.005	22	<0.01	<0.02	<0.05	<0.01	0.8	<0.1	**1**	<0.001	<0.05	<0.05	0.3	<0.02	7.8	<0.005	<0.02	149	450		**4.1**
	1/5/1982	<0.01	<0.01	<0.2	<0.1	<0.005	22	<0.01	<0.02	<0.05	<0.01	0.8	0.14	**0.71**	0.0012	<0.05	<0.05	0.7	<0.02	7.6	<0.02	<0.02	163	400		**4.1**
	1/26/1982					<0.005	22			<0.05	<0.01	0.7	<0.1	**0.45**	<0.001	<0.1		0.5		7.9	<0.005		154	440		
	2/22/1982					<0.005	24			0.48	<0.01	0.7	0.83	**0.26**	<0.001	<0.05		0.6		7.9	<0.005		158	460		
	4/26/1982					<0.005	26			<0.05	<0.01	0.6	**1.2**	0.16	<0.001	<0.05		0.7		7.9	<0.005		154	440		
	5/24/1982												<0.1	**0.28**												
	5/28/1982												<0.1	**0.22**												
	6/8/1982					<0.005	20			<0.05	<0.01	0.6	<0.1	**0.25**	<0.001	<0.05		1.1		7.5	<0.005		162	500		
	6/30/1982					<0.005	18			<0.05	<0.01	0.6	<0.1	0.18	<0.001	<0.05		1.1		7.7	<0.005		143	500		
	10/27/1982					<0.005	20			<0.05	<0.01	0.7	0.45	0.058	<0.001	<0.05		1.3		7.7	<0.005		151	470		
	2/21/1983					<0.005	18			<0.05	<0.01	0.7	<0.1	<0.05	<0.001	<0.05		1.3		7.7	<0.005		156	490		
	5/13/1983					<0.005	24			<0.05	<0.01	0.6	<0.1	<0.05	<0.001	<0.05		1.1		7.9	<0.005		149	470		
	8/9/1983					<0.005	22			<0.05	<0.01	0.6	0.22	<0.05	<0.001	<0.05		1.1		7.8	<0.005		130	480		
	11/1/1983					<0.005	18			<0.05	<0.01	0.6	0.14	<0.05	<0.001	<0.05		2.1		7.8	<0.005		125	500		
	3/16/1984					<0.005	22			<0.05	<0.01	0.6	<0.1	<0.05	**0.0083**	<0.05		1.8		8.2	<0.005		124	480		
	4/9/1984														<0.001											
	5/30/1984					<0.005	22			<0.05	<0.01	0.6	<0.1	<0.05	<0.001	<0.05		0.7		7.5	<0.005		154	510		
	9/12/1984					<0.005	22			<0.05	<0.01	0.6	<0.1	<0.05	<0.001	<0.05		1.1		7.7	<0.005		137	480		
	11/27/1984					<0.005	16			<0.05	<0.01	0.6	<0.1	<0.05	<0.001	<0.05		1.1		7.8	<0.005		144	480		
	5/17/1985						20													7.6			144	510		

APPENDIX B3

GROUNDWATER SAMPLE ANALYTICAL RESULTS

Stage 1 Abatement Plan Investigation Report

Copper Flat Mine Site, New Mexico

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	Lead	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.2	0.002	1.0	0.2	10	0.05	6-9	0.05	0.05	600	1000	0.03	0.03
NP-1	11/13/1985						16													7.3			149	480		
	5/23/1986						18													7.6			142	500		
	10/8/1986						22													7.4			107	470		
	3/30/1989	<0.1		<0.1	<0.1	<0.1	14.9	<0.1	<0.05	<0.1			<0.1	<0.05		<0.1	<0.1		<0.1			<0.1	137	492		**2.6**
	7/19/1991		0.003	0.02		<0.005	21.6	<0.02				0.58	0.59	<0.02	<0.0002			0.99	0.007	8.04	<0.002	<0.02	133.4	530		
	8/29/1991						21.1													7.69			140.7	501		
	11/26/1991						22.7													7.12			136.8	**1484**		
	3/15/1992						22.1													7.8			146.2	510		
	5/25/1992						28.6													7.49			128.2	608		
	7/16/1992						21.7													7.5			142.2	487		
	10/8/1992						21.7													7.35			128.8	517		
	11/27/1992						21.3													7.85			142.4	498		
	12/15/1992						23.7													7.58			125	502		
	2/25/1993						22.6													7.42			138.3	510		
	3/30/1993	<0.1	<0.005	<0.5	0.03	<0.002	22	<0.02	<0.05	<0.01	<0.01	0.59	0.17	<0.02	<0.001	<0.02	<0.01	1.1	<0.02	7.7	<0.005	<0.01	145	496		**1.13**
	9/28/1993						36.2													7.48			110.1	508		
	3/17/1994						24													7.3			134.2	516		
	5/24/1994	0.83	0.005	<0.1		0.0096	22	<0.025		<0.025		0.56	**9.5**	0.1	<0.001		<0.05	1.1	0.016	7.53	<0.005	<0.025	130	510		**5.7**
	6/23/1994						40.3													7.5			142.3	453		
	7/21/1994	<0.05	<0.005	<0.1	<0.1	<0.0005	23	<0.025	<0.05	<0.025		0.65	0.052	**0.27**	<0.001	<0.05	<0.05	<1	<0.005	7.87	<0.005	<0.025	133	464		**4.9**
	9/22/1994						24.3													7.49			118.8	488		
	1/29/1995						26.2													7.94			125.4	407		
	3/29/1995						23.3													7.98			86.2	392		
	6/27/1995						24.1													8.02			113.7	385		
	9/21/1995						27.2													7.96			145	373		
	1/10/1996						26.1													7.73			109.4	277		
	4/3/1996						25.7													7.89			123.3	300		
	9/25/1996						23.6													8.22			94.4	320		
	1/15/1997						25.6													8.42			109.13	318		

APPENDIX B3

GROUNDWATER SAMPLE ANALYTICAL RESULTS

Stage 1 Abatement Plan Investigation Report

Copper Flat Mine Site, New Mexico

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	Lead	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.2	0.002	1.0	0.2	10	0.05	6-9	0.05	0.05	600	1000	0.03	0.03
NP-1	1/31/2010	<0.020	<0.0025	0.037	<0.040	<0.0020	38	<0.0060	<0.0060	<0.0060		0.55	0.10	0.0088	<0.00020	<0.0080	<0.010		<0.0050	8	0.0055	<0.0050	140	514		**0.38**
	6/28/2010	<0.020	0.0034	0.043	<0.040	<0.0020	37	<0.0060	<0.0060	<0.0060		0.61	<0.020	<0.0020	<0.00020	<0.0080	<0.010		<0.0050	8	0.0045	<0.0050	150	548	0.0019	**0.047**
	10/5/2010	0.14	0.0035	0.041	0.04	<0.002	35	<0.006	<0.006	<0.006		0.58	<0.02	<0.002	<0.0002	<0.008	<0.01		<0.005	7.63	0.0045	<0.005	140	537	0.0018	**0.055**
NP-2	10/8/1981	<0.25	0.024	<1	0.08	<0.01	45.1	<0.05	<0.05	<0.05	<0.05	**1.78**	<0.1	**0.62**	<1	<0.1	<0.05	0.23	<0.05	7.39	<0.002	<0.02	198	476		**0.31**
	11/6/1981	<0.01	<0.01	<0.2	<0.1	<0.005	35	<0.01	<0.02	<0.05	<0.01	1.4	<0.1	**0.39**	<0.001	0.21	<0.05	0.4	<0.02	7.6	<0.005	<0.02	164	450		**1.7**
	11/13/1981	<0.25	<0.005	<0.1	0.04	<0.001	30.79	<0.005			0.0026	1.14		**0.79**	<0.0005	0.04	<0.01	0.25	<0.005	7.65	0.017	<0.001	162.4	466		**3.18**
	11/23/1981	<0.01	<0.01	0.02	<0.1	<0.005	30	<0.02	<0.02	<0.05	<0.01	0.9	<0.1	**0.54**	<0.001	0.06	<0.05	0.7	<0.02	7.7	<0.005	<0.02	156	520		**3.5**
	12/7/1981	<0.01	<0.01	<0.2	<0.1	<0.005	30	<0.01	<0.02	<0.05	<0.01	0.8	<0.1	**0.54**	<0.001	0.06	<0.05	0.6	<0.02	7.5	<0.005	<0.02	160	490		**4.4**
	12/15/1981	<0.01	<0.01	<0.2	<0.1	<0.005	32	<0.01	<0.02	<0.05	<0.01	0.9	<0.1	**0.52**	<0.001	0.072	<0.05	0.5	<0.02	8	<0.005	<0.02	161	480		**2.9**
	12/22/1981	<0.01	<0.01	0.21	<0.1	<0.005	32	<0.01	<0.02	<0.05	<0.01	0.6	0.12	**0.51**	<0.001	0.053	<0.05	0.8	<0.02	8	<0.005	<0.02	161	440		**2.8**
	1/5/1982	<0.01	<0.01	<0.2	<0.1	<0.005	28	<0.01	<0.02	<0.05	<0.01	0.9	0.14	**0.49**	<0.001	0.07	<0.05	0.9	<0.02	7.6	<0.02	<0.02	158	400		**3.2**
	1/26/1982					<0.005	24			<0.05	<0.01	0.7	<0.1	**0.34**	<0.001	<0.1		1.1		8	<0.005		160	450		
	2/22/1982					<0.005	30			0.069	<0.01	0.7	0.37	**0.3**	<0.001	<0.05		0.8		8	<0.005		151	440		
	4/26/1982					<0.005	42			<0.05	<0.01	1	**1.2**	**0.29**	<0.001	<0.05		2.4		8	<0.005		149	450		
	5/18/1982					**0.015**	34			<0.05	<0.01	0.6	0.68	0.078	<0.001	<0.05		1.8		7.9	<0.005		128	460		
	5/24/1982												<0.1	<0.05												
	5/28/1982												<0.1	<0.05												
	6/8/1982					<0.005	26			<0.05	<0.01	0.5	<0.1	<0.05	<0.001	<0.05		0.9		7.8	<0.005		158	490		
	6/30/1982					<0.005	26			<0.05	<0.01	0.6	<0.1	<0.05	<0.001	<0.05		1.4		7.8	<0.005		133	490		
	9/2/1982					<0.001	26.49					0.54		<0.05		<0.01		1.66		7.4	<0.005		127	468		
	10/27/1982					<0.005	26			<0.05	<0.01	0.6	0.29	<0.05	<0.001	<0.05		1.6		7.9	<0.005		120	440		
	2/21/1983					<0.005	24			<0.05	<0.01	0.6	0.12	<0.05	<0.001	<0.05		1.6		7.8	<0.005		127	440		
	5/13/1983					<0.005	24			<0.05	<0.01	0.6	<0.1	<0.05	<0.001	<0.05		1.5		8.1	<0.005		139	460		
	8/9/1983					<0.005	36			<0.05	<0.01	0.6	<0.1	<0.05	<0.001	<0.05		1.6		7.9	<0.005		148	560		
	11/1/1983					<0.005	24			<0.05	<0.01	0.6	0.17	<0.05	<0.001	<0.05		2.3		8	<0.005		111	470		
	3/16/1984					<0.005	30			<0.05	<0.01	0.8	<0.1	<0.05	0.001	<0.05		1.6		8.2	<0.005		146	500		
	5/30/1984					<0.005	32			<0.05	<0.01	0.6	<0.1	<0.05	<0.001	<0.05		1.4		7.7	<0.005		175	520		
	9/12/1984					<0.005	22			<0.05	<0.01	0.6	<0.1	<0.05	<0.001	<0.05		1.7		7.8	<0.005		134	470		
	11/27/1984					<0.005	20			<0.05	<0.01	0.6	<0.1	<0.05	<0.001	<0.05		1.7		7.9	<0.005		125	470		

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	Lead	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.2	0.002	1.0	0.2	10	0.05	6-9	0.05	0.05	600	1000	0.03	0.03
NP-2	5/17/1985						22													7.8			120	480		
	11/13/1985						22													7.4			115	460		
	5/23/1986						28													7.6			113	480		
	10/8/1986						24													7.4			100	430		
	3/30/1989	<0.1		<0.1	<0.1	<0.1	29.2	<0.1	<0.05	<0.1			<0.1	0.06		<0.1	<0.1		<0.1			<0.1	124	376		**0.5**
	7/19/1991		<0.002	<0.01		<0.005	60.9	<0.02		<0.02		0.64	<0.05	<0.02	<0.0002			0.02	<0.005	7.55	0.018	<0.02	180.8	453		
	8/29/1991						62.8													8.11			197.6	471		
	11/26/1991						63													7.45			170	460		
	3/15/1992						67.6						<0.05							8.07			194.2	467		
	5/25/1992						66.6						<0.05							8.34			161.7	456		
	7/16/1992						65.3						<0.05							8.13			183.7	479		
	10/8/1992						78.2													8.26			178.9	494		
	11/27/1992						63.7													8.38			179.4	451		
	12/15/1992						82.5						<0.05							8.43			166.8	612		
	2/25/1993						77.8													8.62			197.2	475		
	3/30/1993	0.5	<0.005	0.6	0.1	<0.002	239	<0.02	<0.05	0.01	<0.01	1.33	**1.85**	0.07	<0.001	<0.02	<0.01	3.3	<0.02	7.7	0.005	<0.01	436	**1310**		**0.67**
	9/28/1993						207													7.92			299.9	**1170**		
	3/17/1994						118.2													7.65			300.5	971		
	5/24/1994	4.6	<0.005	<0.1		0.00097	130	<0.025		<0.025		0.97	**4.5**	0.19	<0.001		<0.05	<0.1	0.0079	8.03	<0.005	<0.025	300	878		**4.1**
	6/23/1994						124.3													7.69			267.6	848		
	7/22/1994	<0.05	<0.005	<0.1	<0.1	<0.0005	128	<0.025	<0.05	<0.025		0.94	<0.05	<0.03	<0.001	<0.05	<0.05	1.5	<0.005	7.88	<0.005	<0.025	299	878		**1.2**
	9/22/1994						123.8													7.55			252.7	963		
	1/29/1995						94.1													7.57			120.9	791		
	3/29/1995						90.7													7.69			228.7	**1164**		
	6/27/1995						95.9													7.93			247.1	778		
	9/21/1995						86.6													7.36			211.8	722		
	1/10/1996						78.6													7.1			173.1	632		
	4/3/1996						76.8													7.23			168.7	603		
	9/25/1996						57.2													7.68			118	598		

APPENDIX B3
GROUNDWATER SAMPLE ANALYTICAL RESULTS
Stage 1 Abatement Plan Investigation Report
Copper Flat Mine Site, New Mexico

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	Lead	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.2	0.002	1.0	0.2	10	0.05	6-9	0.05	0.05	600	1000	0.03	0.03
NP-2	1/15/1997						56													7.44			148.4	536		
	1/31/2010	<0.020	0.0032	0.058	<0.040	<0.0020	150	<0.0060	<0.0060	<0.0060		0.48	0.089	0.19	<0.00020	<0.0080	<0.010		<0.0050	8	0.017	<0.0050	210	746		**1.1**
	6/28/2010	<0.020	<0.0010	0.057	<0.040	<0.0020	170	<0.0060	<0.0060	<0.0060		0.44	<0.020	0.021	<0.00020	<0.0080	<0.010		<0.0050	7	0.012	<0.0050	260	846	0.0017	**0.26**
NP-3	10/8/1981	<0.25	0.005	<1	0.188	<0.01	28.6	<0.05	<0.05	<0.05	<0.05	1.58	<0.1	**0.81**	<1	<0.1	<0.05	<0.05	<0.05	6.98	0.005	<0.02	94.5	460		**1.25**
	10/27/1981	<0.01	<0.01	0.2	<0.1	<0.005	28	<0.01	<0.02	<0.05	<0.01	**1.9**	0.39	**1**	<0.001	0.16	<0.05	0.4	<0.02	8	<0.005	<0.02	148	390		**0.98**
	10/30/1981	<0.25	<0.005	<1	0.29	<0.01	31.2	<0.05	<0.05	<0.05	<0.05	1.6	<0.1	**1.03**	<0.001	<0.1	<0.02	<0.05	<0.05	7.89	<0.002	<0.02	102	428		**0.93**
	11/6/1981	<0.01	<0.01	<0.2	<0.1	<0.005	28	<0.01	<0.02	<0.05	<0.01	1.6	<0.1	**0.47**	<0.001	0.26	<0.05	0.2	<0.02	7.9	<0.005	<0.02	140	380		**1.1**
	11/13/1981	<0.25	0.009	<0.1	0.034	<0.001	26.71	<0.005				1.39		**1.01**	<0.0005	0.065	<0.05	0.16	<0.005	7.6	0.023	0.023	140.6	446		**1.59**
	11/17/1981	<0.01	<0.01	0.24	<0.1	<0.005	26	<0.01	<0.02	<0.05	<0.01	1.4	<0.1	**1**	<0.001	0.2	<0.05	<0.2	<0.02	8.1	<0.005	<0.02	144	390		**1.2**
	11/23/1981	<0.01	<0.01	0.02	<0.1	<0.005	26	<0.02	<0.02	<0.05	<0.01	1.2	<0.1	**0.96**	<0.001	0.15	<0.05	0.2	<0.02	7.8	<0.005	<0.01	144	460		**1.9**
	12/7/1981	<0.01	<0.01	<0.2	<0.1	<0.005	28	<0.01	<0.02	<0.05	<0.01	1.1	<0.1	**0.78**	<0.001	0.13	<0.05	<0.2	<0.02	7.9	<0.005	<0.02	153	450		**3.5**
	12/15/1981	<0.01	<0.01	<0.2	<0.1	<0.005	26	<0.01	<0.02	<0.05	<0.01	1.1	<0.1	**0.87**	<0.001	0.094	<0.05	0.2	<0.02	7.8	<0.005	<0.02	149	450		**2.5**
	12/22/1981	<0.01	<0.01	<0.2	<0.1	<0.005	26	<0.01	<0.02	<0.05	<0.01	0.9	<0.1	**0.76**	<0.001	0.1	<0.05	0.2	<0.02	7.9	<0.005	<0.02	149	410		**2.1**
	1/5/1982	<0.01	<0.01	<0.2	<0.1	<0.005	26	<0.01	<0.02	<0.05	<0.01	1.1	0.31	**0.72**	<0.001	0.01	<0.05	0.2	<0.02	7.7	<0.02	<0.02	154	360		**1.7**
	1/26/1982					<0.005	30			<0.05	<0.01	1	<0.1	**0.7**	<0.001	<0.1		0.2		8.1	<0.005		151	400		
	2/22/1982					<0.005	28			<0.05	<0.01	0.9	0.14	**0.66**	<0.001	<0.05		<0.2		8	<0.005		137	420		
	4/26/1982					<0.005	28			<0.05	<0.01	0.8	0.24	**0.4**	<0.001	<0.05		<0.2		7.9	<0.005		146	410		
	5/17/1982					<0.005	**562**			<0.05	<0.01	0.7	0.16	**0.23**	<0.001	<0.05		**12**		7.6	<0.005		**900**	**2460**		
	5/24/1982												<0.1	0.053												
	5/28/1982												<0.1	0.063												
	6/8/1982					<0.005	30			<0.05	<0.01	0.5	<0.1	0.1	<0.001	<0.05		1.9		7.9	<0.005		150	500		
	6/30/1982					<0.005	26			<0.05	<0.01	0.5	<0.1	0.081	<0.001	<0.05		1.8		7.9	<0.005		128	510		
	9/2/1982					<0.001	27.82					0.53		<0.05		<0.01		1.94		7.5	<0.005		123.8	498		
	10/27/1982					<0.005	26			<0.05	<0.01	0.6	<0.1	<0.05	<0.001	<0.05		1.6		8	<0.005		132	450		
	2/21/1983					<0.005	26			<0.05	<0.01	0.5	<0.1	<0.05	<0.001	<0.05		1.4		8.2	<0.005		131	410		
	5/13/1983					<0.005	64			<0.05	<0.01	0.5	<0.1	<0.05	<0.001	<0.05		2.1		8	<0.005		139	500		
	8/9/1983					<0.005	114			<0.05	<0.01	0.5	<0.1	<0.05	<0.001	<0.05		2.3		7.8	<0.005		100	630		
	11/1/1983					<0.005	162			<0.05	<0.01	0.5	0.14	<0.05	<0.001	<0.05		3.8		7.9	<0.005		163	760		
	3/16/1984					<0.005	228			<0.05	<0.01	0.6	<0.1	<0.05	0.001	<0.05		3.2		8.1	<0.005		216	870		

APPENDIX B3

GROUNDWATER SAMPLE ANALYTICAL RESULTS

Stage 1 Abatement Plan Investigation Report

Copper Flat Mine Site, New Mexico

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	Lead	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.2	0.002	1.0	0.2	10	0.05	6-9	0.05	0.05	600	1000	0.03	0.03
NP-3	5/30/1984					<0.005	248			<0.05	<0.01	0.4	<0.1	<0.05	<0.001	<0.05		2.9		7.8	<0.005		292	**1060**		
	9/12/1984					<0.005	**270**			<0.05	<0.01	0.4	<0.1	<0.05	<0.001	<0.05		3.1		7.7	<0.005		292	**1140**		
	11/27/1984					<0.005	**290**			<0.05	<0.01	0.4	<0.1	<0.05	<0.001	<0.05		3.5		7.8	<0.005		348	**1150**		
	5/17/1985						**310**													7.7			453	**1470**		
	11/13/1985						**288**													7.2			541	**1520**		
	5/23/1986						**282**													7.5			**624**	**1590**		
	10/8/1986						**272**													7.4			**620**	**1710**		
	3/3/1987																						**695**			
	3/4/1987						**283**													6.8			**695**	**1882**		
	5/25/1987																						**735.5**			
	1/12/1988	<0.1		<0.1	<0.1	<0.1	**359**	<0.1	<0.05	<0.1			<0.1	**0.57**		<0.1	<0.1		<0.1			<0.1	**755**	**1584**		**1.1**
	4/4/1988						**254**																587	**1772**		
	8/23/1988						**251.4**																**835.2**	**1744**		
	2/9/1989						**254.3**																**763.4**	**1583**		
	6/1/1989						241.1																**713.6**	**1596**		
	11/30/1989						158.9																**742.9**	**1600**		
	11/14/1990						228.7																**821.6**	**1675**		
	2/11/1991		<0.001				**255.9**															**255.9**	**970.5**	**1551**		
	7/19/1991		<0.002	<0.01		<0.005	239.2	<0.02		<0.02		0.66	0.28	0.08	0.0002			0.23	<0.005	8.29	0.011	<0.02	**820.3**	**1663**		
	8/29/1991						**254.3**													7.84			**854.1**	**1616**		
	11/26/1991						248.1													7.08			**745.2**	**1613**		
	3/15/1992						227.8													7.63			**921.3**	**1644**		
	5/25/1992						216.4													7.85			**752.9**	**1607**		
	7/16/1992						226.1													7.26			**802.2**	**1578**		
	10/8/1992						211.6													7.69			**799.1**	**1445**		
	11/27/1992						**254.7**													7.49			**796.1**	**1640**		
	12/15/1992						223.2			0.01										7.75			545.3	**1558**		
	2/25/1993						219.3													7.65			**793.6**	**1580**		
	3/30/1993	0.1	<0.005	<0.5	0.02	<0.002	205	<0.02	<0.05	0.01	<0.01	0.54	**4.99**	**0.32**	<0.001	<0.02	<0.01		<0.02	7.4	<0.005	<0.01	**825**	**1560**		**6.98**

APPENDIX B3

GROUNDWATER SAMPLE ANALYTICAL RESULTS

Stage 1 Abatement Plan Investigation Report

Copper Flat Mine Site, New Mexico

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	Lead	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.2	0.002	1.0	0.2	10	0.05	6-9	0.05	0.05	600	1000	0.03	0.03
NP-3	9/28/1993						210.3			<0.001			<0.05	**0.24**						7.88			**619.4**	**1544**		**1.04**
	3/17/1994						169.5			0.012			0.24	**0.33**						7.46			**746.9**	**1609**		**2.58**
	6/23/1994						205.7													7.77			**778.6**	**1628**		
	7/22/1994	<0.05	<0.005	<0.1	<0.1	<0.0005	194	<0.025	<0.05	<0.025		0.34	<0.05	**0.61**	<0.001	<0.05	<0.05	<1	<0.005	7.83	<0.005	<0.025	**796**	**1620**		**1.8**
	9/22/1994						195.5													7.65			**707.1**	**1691**		
	1/29/1995						**566.4**													7.45			**651.9**	**1623**		
	3/29/1995						185.5													7.48			558	**1639**		
	6/27/1995						202.7													7.38			**717**	**1607**		
	9/21/1995						208.4													7.5			**822**	**1557**		
	1/10/1996						208.5													7.32			**724.1**	**1464**		
	4/3/1996						208.3													7.29			**722.6**	**1415**		
	9/25/1996						190.5													7.72			536.5	**1472**		
	1/15/1997						207													7.51			**657.4**	**1478**		
	7/8/2010	<0.020	<0.0010	0.030	<0.040	<0.0020	**270**	<0.0060	<0.0060	<0.0060		0.36	0.049	0.031	<0.00020	<0.0080	<0.010		<0.0050	8	0.023	<0.0050	**790**	**1740**	0.0014	**0.44**
	10/7/2010	<0.02	<0.005	0.031	<0.04	<0.002	**290**	<0.006	<0.006	<0.006		0.29	0.1	0.015	<0.0002	<0.008	<0.01		<0.005	7.57	0.023	<0.005	**830**	**1660**	0.0015	**0.31**
NP-4	4/26/1982					<0.005	46			0.051	<0.01	1.5	**3.8**	**0.6**	<0.001	0.07		0.6		8.6	<0.005		132	410		
	5/17/1982					<0.005	46			<0.05	<0.01	1	0.11	<0.05	<0.001	<0.05		1.3		**9.4**	<0.005		138	310		
	5/24/1982												<0.1	<0.05												
	5/28/1982												<0.1	<0.05												
	6/8/1982					<0.005	26			<0.05	<0.01	0.5	<0.1	<0.05	<0.001	<0.05		4.5		8.4	<0.005		140	420		
	6/30/1982					<0.005	28			<0.05	<0.01	0.4	<0.1	<0.05	<0.001	<0.05		<0.2		**9.5**	<0.005		115	270		
	9/2/1982					<0.001	28.72					0.4		<0.05		<0.01		0.03		8.5	<0.005		107.1	252		
	10/27/1982					0.0061	36			<0.05	<0.01	0.4	0.34	<0.05	<0.001	<0.05		<0.2		8.9	<0.005		108	230		
	2/21/1983					<0.005	48			<0.05	<0.01	0.4	0.28	<0.05	0.001	<0.05		0.2		**9.3**	<0.005		115	250		
	5/13/1983					<0.005	76			<0.05	<0.01	0.4	<0.1	<0.05	<0.001	<0.05		<0.2		7.9	<0.005		134	340		
	8/9/1983					<0.005	94			<0.05	<0.01	0.3	<0.1	<0.05	<0.001	<0.05		<0.2		8.8	<0.005		156	430		
	11/1/1983					<0.005	114			<0.05	<0.01	0.3	<0.1	<0.05	<0.001	<0.05		0.6		8.2	<0.005		206	530		
	3/16/1984					<0.005	126			<0.05	<0.01	0.6	<0.1	<0.05	0.001	<0.05		0.2		8	<0.005		256	540		
	5/30/1984					<0.005	134			<0.05	<0.01	0.3	<0.1	<0.05	<0.001	<0.05		<0.2		8	<0.005		320	630		

APPENDIX B3

GROUNDWATER SAMPLE ANALYTICAL RESULTS

Stage 1 Abatement Plan Investigation Report

Copper Flat Mine Site, New Mexico

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	Lead	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.2	0.002	1.0	0.2	10	0.05	6-9	0.05	0.05	600	1000	0.03	0.03
NP-4	9/12/1984					<0.005	134			<0.05	<0.01	0.3	<0.1	<0.05	<0.001	<0.05		0.9		8	<0.005		339	760		
	11/27/1984					<0.005	140			<0.05	<0.01	0.3	<0.1	<0.05	<0.001	<0.05		0.2		8.5	<0.005		354	740		
	5/17/1985						146													8.2			348	770		
	11/13/1985						142													8			292	690		
	5/23/1986						136													8			300	690		
	10/8/1986						134													7.8			290	660		
	5/25/1987																						278.5			
	1/12/1988	<0.1		<0.1	<0.1	<0.1	137	<0.1	<0.05	<0.1			<0.1	0.06		<0.1	<0.1		<0.1			<0.1	256	612		**0.1**
	4/4/1988						130.4																328.8	610		
	8/23/1988						132.1																292.2	688		
	2/9/1989						130																266.8	604		
	6/1/1989						116.4																243.5	580		
	11/30/1989						96.9																237.4	572		
	11/14/1990						153.1																254.5	262		
	2/11/1991		<0.001				126.1																288.9	676		
	7/19/1991		<0.002	0.28		<0.005	112.3	<0.02				0.41	**5.14**	<0.02	<0.0002			0.07	<0.005	7.81	<0.002	<0.02	198.5	532		
	8/29/1991						110.7													8.37			232	532		
	11/26/1991						99													8.54			193.6	522		
	3/15/1992						102.9													8.85			216.5	465		
	5/25/1992						106.2													8.62			171.4	439		
	7/16/1992						94.4													7.64			176.8	458		
	10/8/1992						102.9													**9.01**			182.9	535		
	11/27/1992						97.5													8.12			201.7	495		
	12/15/1992						84.4													**9.52**			151.2	424		
	2/25/1993						76.6													**9.85**			150.8	349		
	3/31/1993	0.3	<0.005	<0.5	0.04	<0.002	45	<0.02	<0.05	0.01	<0.01	0.53	0.62	**0.84**	**0.009**	<0.02	<0.01	3.7	<0.02	7.6	<0.005	<0.01	134	504		**2.41**
	9/28/1993						56.9													8.2			108.5	437		
	5/26/1994	3.5	<0.005	<0.1		0.0034	39	<0.025		<0.025		0.46	**15**	0.16	<0.001		<0.05	4.3	0.018	8.1	<0.005	<0.025	131	666		**12**
	6/23/1994						48.5													8.13			133.5	498		

APPENDIX B3

GROUNDWATER SAMPLE ANALYTICAL RESULTS

Stage 1 Abatement Plan Investigation Report

Copper Flat Mine Site, New Mexico

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	Lead	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.2	0.002	1.0	0.2	10	0.05	6-9	0.05	0.05	600	1000	0.03	0.03
NP-4	7/23/1994	<0.05	<0.005	<0.1	<0.1	<0.0005	34	<0.025	<0.05	<0.025		0.48	<0.05	<0.03	<0.001	<0.05	<0.05	4.6	<0.005	7.9	<0.005	<0.025	120	536		**0.51**
	9/22/1994						36.9													7.73			111	547		
	1/29/1995						34.5													7.88			110.7	447		
	3/29/1995						33.8													7.86			121.7	494		
	6/27/1995						33.2													7.37			134.1	487		
	9/21/1995						35.3													7.51			132.1	509		
	1/10/1996						34.7													7.35			123.1	483		
	4/3/1996						26													7.19			123.3	475		
	9/25/1996						31.7													7.75			125.6	504		
	1/15/1997						98													7.43			**1113**	**2651**		
	1/31/2010	<0.020	<0.0025	0.036	<0.040	<0.0020	40	<0.0060	<0.0060	<0.0060		0.46	0.040	0.0098	<0.00020	<0.0080	<0.010		<0.0050	8	0.0057	<0.0050	190	626		**1.3**
	7/2/2010	<0.020	<0.0010	0.039	<0.040	<0.0020	39	<0.0060	<0.0060	<0.0060		0.46	<0.020	0.0020	<0.00020	<0.0080	<0.010		<0.0050	8	0.0043	<0.0050	190	640	0.0023	**0.82**
NP-5	11/4/1981	<0.01	<0.01	<0.2	<0.1	<0.005	50	<0.01	<0.02	<0.05	<0.01	1.3	<0.1	0.1	<0.001	<0.05	<0.05	4.1	<0.02	8	<0.005	<0.02	196	570		**0.14**
	11/13/1981	0.239	<0.005	0.218	0.07	<0.001	37.89	<0.005		<0.1	0.001	1.28		0.14	<0.0005	0.015	0.019	3.56	<0.005	7.7	0.014	<0.001	162	488		<0.05
	11/17/1981	<0.01	<0.01	<0.2	<0.1	<0.005	42	<0.01	<0.02	<0.05	<0.01	1.3	<0.1	**0.3**	<0.001	0.07	<0.05	2.7	<0.02	8	<0.005	<0.02	158	500		**0.19**
	11/23/1981	<0.01	<0.01	<0.2	<0.1	<0.005	36	<0.02	<0.02	<0.05	<0.01	1.2	<0.1	0.091	<0.001	<0.05	<0.05	4	<0.02	7.8	<0.005	<0.1	161	580		**0.21**
	12/7/1981	<0.01	<0.01	<0.2	<0.1	<0.005	34	<0.01	<0.02	<0.05	<0.01	1.2	<0.1	<0.05	<0.001	<0.05	<0.05	3.1	<0.02	7.9	<0.005	<0.02	172	510		**0.24**
	12/15/1981	<0.01	<0.01	<0.2	<0.1	<0.005	36	<0.01	<0.02	<0.05	<0.01	1.2	<0.1	0.08	<0.001	<0.05	<0.05	3.3	<0.02	7.8	<0.005	<0.02	168	500		**0.37**
	12/22/1981	<0.01	<0.01	<0.2	<0.1	<0.005	36	<0.01	<0.02	<0.05	<0.01	1.1	<0.1	<0.05	<0.001	<0.05	<0.05	3.8	<0.02	7.9	<0.005	<0.02	161	460		**0.32**
	1/5/1982	<0.01	<0.01	<0.2	<0.1	<0.005	34	<0.01	<0.02	<0.05	<0.01	1.1	0.18	<0.05	<0.001	<0.05	<0.05	4.1	<0.02	7.7	<0.02	<0.02	163	420		**0.4**
	1/26/1982					<0.005	32			<0.05	<0.01	1.1	<0.01	<0.05	<0.001	<0.1		2.9		8	<0.005		158	440		
	2/22/1982					<0.005	32			<0.05	<0.01	1	0.12	<0.05	<0.001	<0.05		2		8	<0.005		150	450		
	4/26/1982					<0.005	30			0.31	0.04	1.1	**3.8**	**6.9**	<0.001	<0.05		1.1		7.9	<0.005		154	450		
	5/17/1982					<0.005	36			<0.05	<0.01	1.1	0.14	<0.05	<0.001	<0.05		6.7		8	<0.005		165	490		
	5/24/1982												<0.1	<0.05												
	5/28/1982												<0.1	<0.05												
	6/8/1982					<0.005	30			<0.05	<0.01	0.9	0.44	<0.05	<0.001	<0.05		4.5		8.1	<0.005		150	420		
	6/30/1982					<0.005	28			<0.05	<0.01	0.9	0.36	<0.05	<0.001	<0.05		3.9		8.1	<0.005		133	460		
	9/2/1982					<0.001	33.98					0.82		<0.05		<0.01		4.2		7.6	<0.005		137.2	472		

APPENDIX B3

GROUNDWATER SAMPLE ANALYTICAL RESULTS

Stage 1 Abatement Plan Investigation Report

Copper Flat Mine Site, New Mexico

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	Lead	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.2	0.002	1.0	0.2	10	0.05	6-9	0.05	0.05	600	1000	0.03	0.03
NP-5	10/27/1982					<0.005	34			<0.05	<0.01	0.8	0.21	<0.05	<0.001	<0.05		3.7		8	<0.005		139	440		
	2/21/1983					<0.005	26			<0.05	<0.01	0.5	<0.1	<0.05	<0.001	<0.05		1.3		8.3	<0.005		139	420		
	5/13/1983					<0.005	70			<0.05	<0.01	0.4	<0.1	<0.05	<0.001	<0.05		0.2		8.9	<0.005		134	290		
	8/9/1983					<0.005	26			<0.05	<0.01	0.8	<0.1	<0.05	<0.001	<0.05		3.7		8.1	<0.005		108	460		
	11/1/1983					<0.005	30			<0.05	<0.01	0.8	0.1	<0.05	<0.001	<0.05		5.2		8.2	<0.005		111	440		
	3/16/1984					<0.005	26			<0.05	<0.01	0.4	<0.1	<0.05	<0.001	<0.05		3		8	<0.005		130	380		
	5/30/1984					<0.005	22			<0.05	<0.01	0.8	<0.1	<0.05	<0.001	<0.05		2.9		7.8	<0.005		139	400		
	9/12/1984					<0.005	28			<0.05	<0.01	0.8	<0.1	<0.05	<0.001	<0.05		3.4		8	<0.005		125	420		
	11/27/1984					<0.005	28			<0.05	<0.01	0.8	<0.1	<0.05	<0.001	<0.05		3.2		8.2	<0.005		120	420		
	5/17/1985						28													7.9			130	450		
	11/13/1985						24													7.8			134	400		
	5/23/1986						28													7.9			120	430		
	10/8/1986						28													7.8			113	420		
	3/30/1989	<0.1		<0.1	<0.1	<0.1	32	<0.1	<0.05	<0.1			<0.1	<0.05		<0.1	<0.1		<0.1			<0.1	125	458		**0.4**
	8/29/1991						38.7													7.68			152.1	499		
	11/26/1991						37.7													7			129.5	472		
	3/15/1992						46.7													7.89			140.7	456		
	5/25/1992						75.5													7.8			131.1	490		
	7/16/1992						37.8													7.63			132.4	476		
	10/8/1992						39.4													7.64			133.2	431		
	11/27/1992						117.2													8.01			133.9	475		
	12/15/1992						40.4			0.025										7.8			104	402		
	2/25/1993						41.4													7.65			140.8	487		
	3/30/1993	0.2	<0.005	<0.5	0.04	<0.002	39	<0.02	<0.05	<0.01	<0.01	0.77	0.29	0.02	<0.001	<0.02	<0.01	4	<0.02	7.8	<0.005	<0.01	146	488		**0.19**
	9/28/1993						48.1													7.79			109.2	518		
	5/24/1994	1.1	<0.005	<0.1		<0.0005	41	<0.025		<0.025		0.74	**1.2**	0.086	<0.001		<0.05	3.4	0.0077	7.84	<0.005	<0.025	130	520		**2.3**
	6/23/1994						54.1													7.66			142.3	466		
	7/23/1994	<0.05	<0.005	<0.1	<0.1	<0.0005	41	<0.025	<0.05	<0.025		0.71	<0.05	<0.03	<0.001	<0.05	<0.05	3.3	<0.005	7.89	<0.005	<0.025	131	494		<0.05
	9/22/1994						42.8													7.73			117.7	526		

APPENDIX B3
GROUNDWATER SAMPLE ANALYTICAL RESULTS
Stage 1 Abatement Plan Investigation Report
Copper Flat Mine Site, New Mexico

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	Lead	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.2	0.002	1.0	0.2	10	0.05	6-9	0.05	0.05	600	1000	0.03	0.03
NP-5	1/29/1995						43.5													7.99			101.2	490		
	3/29/1995						42.4													7.94			130.8	449		
	6/27/1995						43.4													7.64			119.4	525		
	9/21/1995						44.3													7.71			134.6	483		
	1/10/1996						41.6													8.04			136.6	406		
	4/3/1996						31.8													7.67			130	405		
	9/25/1996						42.5													8.09			129.4	504		
	1/15/1997						45.7													7.76			140.69	498		
	6/28/2010	<0.020	0.0014	0.018	<0.040	<0.0020	80	<0.0060	<0.0060	<0.0060		0.68	<0.020	<0.0020	<0.00020	<0.0080	<0.010		<0.0050	8	0.0067	<0.0050	180	623	0.0013	**0.29**
	9/30/2010	<0.02	0.0015	0.018	0.041	<0.002	83	<0.006	<0.006	<0.006		0.71	<0.02	0.005	<0.0002	<0.008	<0.01		<0.005	7.72	0.0079	<0.005	170	629	0.0013	**0.2**
O. Williams	12/19/1945						**425**					0.6						1.9					62	883		
	6/13/1946						**418**					0.4						2.2					66	847		
Pague	8/20/1946						26					1.2						1.2					80	348		
PW-1	12/23/1975						16					0.46						3.5		7.8			10	217		
	8/14/1981		<0.01				32			<0.05	<0.01	0.9	0.2					0.7	<0.02	8.1			24	250		<0.05
PW-2	1/15/1976						17					0.66						3.5		8.1			<5	257		
	11/27/1984					<0.005	20			<0.05	<0.01	0.6	<0.1	<0.05	<0.001			1.7		7.9	<0.005		125	470		
	8/2/1994	<0.05	<0.005	<0.1	<0.1	<0.0005	24	<0.025	<0.05	<0.025		0.39	0.062	0.032	<0.001	<0.05	<0.05	<1	<0.005	7.63	<0.005	<0.025	27	338		<0.05
PW-3	1/27/1976						24					0.64						2.6		8			<5	243		
	8/14/1981		<0.01				66			<0.05	0.01	**2.5**	0.31					0.8	<0.02	8.2			31	300		**0.19**
PW-4	8/2/1994	<0.05	0.0058	<0.1	<0.1	<0.0005	27	<0.025	<0.05	<0.025		0.46	<0.05	<0.03	<0.001	<0.05	<0.05	<1	<0.005	7.57	<0.005	<0.025	17	274		<0.05
QMC-4	3/27/1981		<0.01							<0.05	<0.01	**2.5**						<0.2	<0.02							<0.05
Saladone Well	12/5/1992																	0.19		7.91			23	354		
SHB-27	9/22/1976		<0.01		<0.1	<0.001	20.6	0.002	<0.001	0.002		0.77	0.007	0.039	<0.0004	0.002		0.8	<0.001	7.61	<0.01	<0.001	233	434		0.004
SHB-28	9/22/1976				<0.1	<0.001	51.2	0.002	<0.001	0.005		0.97	0.015	**0.42**	<0.0004	0.003		<0.1	<0.001	7.58	<0.01	<0.001	353	840		0.018
SHB-29	9/22/1976				0.1	0.001		0.004	0.001	0.002			0.52	0.049	<0.0004	0.003		<0.1	0.002	7.98	<0.01	<0.001		384		**0.16**

APPENDIX B3
GROUNDWATER SAMPLE ANALYTICAL RESULTS
Stage 1 Abatement Plan Investigation Report
Copper Flat Mine Site, New Mexico

Sample ID	Collection Date	Aluminum	Arsenic	Barium	Boron	Cadmium	Chloride	Chromium	Cobalt	Copper	Cyanide	Fluoride	Iron	Manganese	Mercury	Molybdenum	Nickel	Nitrate as N (NO3)	Lead	pH	Selenium	Silver	Sulfate	Total Dissolved Solids	Uranium	Zinc
NMWQCC GW Standard (mg/L)		5.0	0.1	1.0	0.75	0.01	250	0.05	0.05	1.0	0.2	1.6	1.0	0.2	0.002	1.0	0.2	10	0.05	6-9	0.05	0.05	600	1000	0.03	0.03
SHB-30	9/22/1976		0.02		<0.1	<0.001	21	0.004	<0.001	0.002		0.79	0.009	0.036	<0.0004	0.002		0.7	<0.001	7.77	<0.01	<0.001	145	486		0.004
SHB-34	9/22/1976				<0.1	0.001	<1	0.002	<0.001	0.002		0.14	0.009	0.004	<0.0004	<0.001		<0.1	0.001	7.36	<0.01	<0.001	<1	50		0.014
Shipping Pen	12/18/1992																	0.66		7.92			19.2	345		
Stone	7/31/1947						88					0.6						3.3					26	369		
Young 1	7/31/1947						238					0.6						0.8					43	568		
Young 2	7/31/1947						148					1						4.1					32	471		
LRG 04159	11/4/2010	<0.02	<0.001	0.018	<0.04	<0.002	23	<0.006	<0.006	<0.006		0.66	0.036	<0.002	<0.0002	<0.008	<0.01		<0.005	7.31	0.0049	<0.005	220	730	0.004	**0.037**

Notes:

NMWQCC = New Mexico Water Quality Commission

Measurement values that exceed the NMWQCC standard are in bold

Non-detects are indicated with a "<" & the detection limit

Solid grey indicates 'No Data' or 'Not Measured'

Appendix C

The Natural Defenses of Copper Flat, Sierra County, New Mexico (J.S. Raugust, 2003)



New Mexico Bureau of Geology and Mineral Resources
Open-file report 475

The Natural Defenses of Copper Flat
Sierra County, New Mexico

By

J. Steven Raugust

A technical report submitted in partial
fulfillment for the degree of

Master of Science

in

Mineral Engineering

Department of Mineral Engineering
New Mexico Institute of Mining and Technology, Socorro, New Mexico

00525

August 2003

ACKNOWLEDGMENTS

Acknowledgments are due to Dr. Virginia McLemore for introducing me to the project, supporting my research through the Bureau of Geology and Mineral Resources, technical advice and companionship in the field, and diligent reviews of manuscript. To Dr. William X. Chavez for preparing me to succeed in this project through prior coursework in mine waste characterization and enlightening revisions to the manuscript. Thanks to Dr. Navid Mojtabai for his constant academic and administrative assistance. I would also like to acknowledge Dr. Ali Fakhimi and Dr. Catherine Aimone-Martin for their direct contribution of passing their knowledge and expertise on to me.

Other acknowledgments are due to Mr. George Lotspeich, whom owns the Copper Flat Mine. Mr. Lotspeich allowed me access to both his property and his personal files, which contained a wealth of technical information that he shared with me. I wish to thank Woman's Auxiliary to the American Institute of Mining, Metallurgical, and Petroleum Engineers, whose generous scholarship was essential. Special thanks to Linda Ulbricht, who entered the reams of data contained in these appendices into electronic format just before she died of cancer on March 9, 2003. I'd like to thank Dr. George Austin and Mr. Chris McKee for teaching me the techniques of X-ray diffraction, Mark Mansell and Tim Summers for their tireless and enthusiastic computer support. Thanks to Kathy Glesener, Leo Gabaldon, and Tom Kaus for teaching me how to use a MacIntosh and software to generate my own computer graphics, for which I had no prior experience. Also acknowledgements to Glen Jones for converting State planar coordinates into more useful UTM coordinates for most of the groundwater wells on the property. And to Dr. Maureen Wilks and Lynne Hemenway for converting this document into a Bureau of Geology and Mineral Resources open file report.

Lastly, but not least important, to my wife, Eve Gedanic, for her patience and self sufficiency during my absences in pursuit of this academic adventure.

TABLE OF CONTENTS

ACKNOWLEDGMENTS ii

TABLE OF CONTENTS iii

LIST OF FIGURES v

LIST OF TABLES viii

LIST OF APPENDICES ix

LIST OF ACRONYMS x

ABSTRACT xii

1.0 INTRODUCTION 1
- 1.1 PURPOSE OF THE COPPER FLAT INVESTIGATION 1
- 1.2 SITE BACKGROUND 1
- 1.2.1 GOLOGICAL HISTRORY OF THE HILLSBORO MINING DISTRICT 1
- 1.2.1.1 GEOLOGY 1
- 1.2.1.2 HYDROTHERMAL ALTERATION OF IGNEOUS ROCKS 3
- 1.2.2 HISTORY OF HILLSBORO MINING DISTRICT 5
- 1.2.3 PREVIOUS INVESTIGATIONS 7

2.0 STUDY AREA INVESTIGATIONS 9
- 2.1 SURFACE FEATURES 9
- 2.2 MINE PIT INVESTIGATION 10
- 2.2.1 MINE PIT AND GRAYBACK GULCH SURFACE WATER 10
- 2.2.2 MINE PIT LAKE AND GROUNDWATER 13
- 2.3 ROCK STORAGE PILES AND PIT WALL INVESTIGATIONS 13
- 2.4 TAILINGS DAM INVESTIGATIONS 15

3.0 NATURE AND EXTENT OF POTENTIAL ENVIRONMENTAL ISSUES 21
- 3.1 MINE PIT LAKE INVESTIGATIVE RESULTS 21
- 3.1.1 MINE PIT LAKE SURFACE WATER 21
- 3.1.2 GREYBACK GULCH SURFACE WATER 23
- 3.1.3 GROUNDWATER 25
- 3.2 ROCK STORAGE PILE INVESTIGATIVE RESULTS 26
- 3.2.1 METAL CONTENT AND MINERALOGY 26
- 3.2.2 PASTE pH 27

00528

3.2.3 ACID-BASE ACCOUNTING 27
3.2.4 NET ACID GENERATION TESTING 28
3.2.5 KINETIC TESTING 28
3.2.5.1 KINETIC TEST RESULTS – pH 29
3.2.5.2 KINETIC TEST RESULTS – ELECTRICAL CONDUCTIVITY 29
3.2.5.3 KINETIC TEST RESULTS – SULFATE 29
3.2.5.4 KINETIC TEST RESULTS – COPPER AND IRON 29
3.2.5.5 KINETIC TEST RESULTS – ALKALINITY AND ACIDITY 30
3.3 RESULTS OF TAILINGS DAM INVESTIGATIONS 30
3.3.1 GEOCHEMICAL INVESTIGATIVE RESULTS 30
3.3.2 HYDROGEOLOGICAL INVESTIGATIVE RESULTS 31
3.3.3 PERMEABILITY TESTING 32
3.3.4 GROUNDWATER IMPACTS 33
3.3.5 LINER BORROW MATERIAL STUDY 34

4.0 CONCLUSIONS AND RECOMMENDATIONS 36
4.1 MINE PIT CONCLUSIONS 36
4.1.1 SURFACE WATER QUALITY, MINE PIT LAKE 36
4.1.2 SURFACE WATER QUALITY, GREYBACK GULCH AND LOCAL SEEPS 37
4.1.3 GROUNDWATER QUALITY 39
4.2 RECOMMENDATIONS FOR THE MINE PIT 40
4.2.1 MINE PIT LAKE 40
4.2.2 SURFACE WATER QUALITY 40
4.2.3 GROUNDWATER 41
4.3 ROCK STORAGE PILE CONCLUSIONS 41
4.3.1 EXTRACTABLE METALS FROM ROCK STORAGE PILE SAMPLE WD-1 41
4.3.2 PASTE pH, ACID-BASE ACCOUNTING, AND NET ACID GENERATION TESTING 42
4.3.3 KINETIC TESTS 43
4.4 RECOMMENDATIONS FOR THE ROCK STORAGE PILES 44
4.5 TAILINGS DAM CONCLUSIONS 45
4.6 RECOMMENDATIONS FOR THE TAILINGS DAM 47

5.0 SUMMARY OF CONCLUSIONS 47
5.1 WATERS 47
5.2 STORED ROCK AND PIT WALL ROCK 50
5.3 TAILINGS 51
5.4 RECOMMENDATIONS FOR FURTHER STUDY 52

6.0 REFERENCES 54

00529

FIGURE 1 Site Location Map, Copper Flat, New Mexico

FIGURE 2 Geologic Schematic of the Hillsboro Mining District, Copper Flat, New Mexico

FIGURE 3 Arizona-New Mexico-New Mexico Porphyry Copper Belt

FIGURE 4 Copper Flat Mine, 1982, View West, Copper Flat, New Mexico

FIGURE 5 Copper Flat Mine, 1982, View East, Copper Flat, New Mexico

FIGURE 6 Copper Flat Mills, 1982, Copper Flat, New Mexico

FIGURE 7 Copper Flat Mine Site, 1988, Copper Flat, New Mexico

FIGURE 8 Copper Flat Mine Layout and Property Ownership, Copper Flat, New Mexico

FIGURE 9 Well and Spring Locations, Copper Flat, New Mexico

FIGURE 10 Well and Spring Locations, Pit and Tailings Impoundment Detail, Copper Flat, New Mexico

FIGURE 11 Pit Wall, Waste Rock, and Core Sample Locations, Copper Flat, New Mexico

FIGURE 12 Pit Area Paste pH Sample Locations, Copper Flat, New Mexico

FIGURE 13 Approximate Pond Sample Locations, Copper Flat, New Mexico

FIGURE 14 Tailings Impoundment Layout and Decant Alignment Boring Locations, Copper Flat, New Mexico

FIGURE 15 Geotechnical Soil Boring and Test Pit Locations, Copper Flat, New Mexico

FIGURE 16 1976 Groundwater Sample Locations, Copper Flat, New Mexico

FIGURE 17 Copper Concentrations in the Mine Pit Lake, Copper Flat, New Mexico

FIGURE 18 pH in the Mine Pit Lake, Copper Flat, New Mexico

FIGURE 19 Total Dissolved Solids Concentrations in the Mine Pit Lake, Copper Flat, New Mexico

FIGURE 20 Sulfate Concentrations in the Mine Pit Lake, Copper Flat, New Mexico

FIGURE 21 pH from Greyback Gulch Surface Water, Copper Flat, New Mexico

FIGURE 22 TDS Concentrations from Greyback Gulch Surface Water, Copper Flat, New Mexico

FIGURE 23 Sulfate Concentrations from Greyback Gulch Surface Water, Copper Flat, New Mexico

FIGURE 24 Greyback Gulch Surface Water Stiff Diagrams, Copper Flat, New Mexico

FIGURE 25 Groundwater pH, Mine Pit Vicinity, Copper Flat, New Mexico

FIGURE 26 Groundwater TDS Concentrations, Mine Pit Vicinity, Copper Flat, New Mexico

FIGURE 27 Groundwater Sulfate Concentrations, Mine Pit Vicinity, Copper Flat, New Mexico

FIGURE 28 Paste pH Distributions by Rock Type, Copper Flat, New Mexico

FIGURE 29 Comparison of Sobek vrs Modified Sobek Methods for Estimating Acid Generation Potential vrs Acid Neutralization Potential, Copper Flat, New Mexico

FIGURE 30 Acid Generation Potential vrs Neutralization Potential, Copper Flat, New Mexico

FIGURE 31 NAG pH Frequency Distribution by Rock Type, Copper Flat, New Mexico

FIGURE 32 Kinetic Test pH vrs Time, Copper Flat, New Mexico

FIGURE 33 Kinetic Test, Electrical Conductivity vrs Time, Copper Flat, New Mexico

FIGURE 34 Kinetic Test, Sulfate vrs Time, Copper Flat, New Mexico

FIGURE 35 Kinetic Test, Copper vrs Time, Copper Flat, New Mexico

FIGURE 36 Kinetic Test, Iron vrs Time, Copper Flat, New Mexico

FIGURE 37 Kinetic Test, Alkalinity and Acidity vrs Time, Copper Flat, New Mexico

FIGURE 38 Subsurface Cross-Section Through the North and South Cells of the Tailings Impoundment, Copper Flat, New Mexico

FIGURE 39 Groundwater pH, NP-3, NP-4, Copper Flat, New Mexico

FIGURE 40 Groundwater TDS Concentrations, NP-3, NP-4, Copper Flat, New Mexico

FIGURE 41 Groundwater Sulfate Concentrations, NP-3, NP-4, Copper Flat, New Mexico

FIGURE 42 Piper Diagram, Copper Flat Surface Water and Groundwater, Copper Flat, New Mexico

FIGURE 43 Groundwater Contours Beneath the Mine Site, Copper Flat, New Mexico

FIGURE 44 Guide to Collapsibility, Compressibility, and Expansion Based on In-Situ Dry Density and Liquid Limit

TABLE 1 Summary of Hydrothermal Alteration Associated with Mineralization in the Vicinity of Copper Flat, Copper Flat, New Mexico

TABLE 2 Investigative Reports Prepared for Alta Gold, Copper Flat, New Mexico

TABLE 3 Dates and Estimated Flow Rates for the Springs Samples by Newcomer et. al., 1993, Copper Flat, New Mexico

TABLE 4 Rock Storage Pile, Pit Wall, Drill Core, and Drill Cutting Samples, 1994 SRK Acid Rock Drainage Study, Copper Flat, New Mexico

TABLE 5 Additional Sample Analysis Summary, 1994 SRK Acid Rock Drainage Study, Copper Flat, New Mexico

TABLE 6 Rock Storage Pile Characterization Sample Distribution, Copper Flat, New Mexico

TABLE 7 Historical Tailings Impoundment Reports, Copper Flat, New Mexico

TABLE 8 Whole Rock Analyses Summary Pit Lake Sediment and Wall Rock Samples Collected by McLemore et. al. on November 20, 1996, Copper Flat, New Mexico

TABLE 9 Summary of Surface Water Samples from Greyback Gulch Stations A, B, and C, Copper Flat, New Mexico

TABLE 10 Extractable Metals from Rock Storage Pile Sample WD-1, Copper Flat, New Mexico

TABLE 11 Total Extractable Metals in Tailings Sample T-10-12, Copper Flat, New Mexico

TABLE 12 Physical and Relational Characteristics, Copper Flat Tailings Impoundment Liner Material, Copper Flat, New Mexico

TABLE 13 Summary of Geotechnical Results, Copper Flat Tailings Impoundment Liner Material, Copper Flat, New Mexico

TABLE 14 Clay Mineralogy and Distribution of Samples SR-1 and SR-3, Copper Flat Tailings Impoundment Liner Material, Copper Flat, New Mexico

TABLE 15 New Mexico Water Quality Control Commission Numeric Standards

TABLE 16 Probable Expansion Estimated from Classification Test Data

APPENDIX A Comprehensive Surface Water Chemistry Data

APPENDIX B
Appendix B-1
Comprehensive Groundwater Chemistry Data
Appendix B-2
Pre 1980 SHB Groundwater Sample Results

APPENDIX C Whole Rock Chemical Analyses for PW-3, WD-1, and November 20, 1996 Pond Rock Samples

APPENDIX D
Appendix D-1
Paste pH and Conductivity Data,
Acid-Base Accounting Data, and
Net Acid Generation Data
Appendix D-2
Humidity Cell Data

APPENDIX E
Appendix E-1
SHB Permeability Data
Appendix E-2
Tailings Impoundment Liner Material Hydrometer Analysis and Gradation Plot,
Appendix E-3
Geotechnical Boring Logs and
Geotechnical Analytical Data Sheets

APPENDIX F Bulk XRD and Clay Mineralogy Distribution Data Scans and Calculations

μS/cm	microSiemens per centimeter
ABA	acid-base accounting
ABC	Adrian Brawn Consultants
Alta Gold	Alta Gold Corporation
AP	acid generating potential
Ar^{40}/AR^{39}	Argon-Argon age dating technique
BLM	U.S. Bureau of Land Management
$CaCO_3$	calcuium carbonate
CFQM	Copper Flat quartz monzonite
cm/s	centimeters per second
EA	Environmental Assessment
EIS	Environmental Impact Statement
ft	foot
ft/yr	feet per year
gpm	gallons per minute
Hydro Resources	Hydro Resources, Inc.
ICP	inductively coupled plasma
Inspiration	Inspiration Consolidated Copper
mg/L	milligram per liter
NAG	net acid generating
NMEIB	New Mexico Environmental Improvement Board
NMMMD	New Mexico Mining and Minerals Division
NP	acid neutralizing potential

QMC	Quintana Minerals Corporation
SHB	Sergent, Hauskins and Beckwith, Inc.
SRK	Steffen, Robertson, and Kirsten, Inc.
USBR	U.S. Bureau of Reclamation
WQCC	New Mexico Water Quality Control Commission
XRD	X-ray diffraction

The Natural Defenses

Of Copper Flat

Sierra County, New Mexico

Abstract

Copper Flat is located in southwestern New Mexico, approximately 23 miles southwest of Truth or Consequences and 5 miles northeast of Hillsboro. It is a porphyry copper deposit with associated gold, silver, molybdenum, and sulfide minerals. The stock contains a 75 million-year-old quartz monzonite breccia pipe forming the center of an eroded andesite strato-volcano. The breccia pipe is approximately 1,300 feet long, 600 feet wide, and 1,000 feet deep. Records indicated that the Sternberg Mine located at Copper Flat was mined as early as 1911, but it wasn't until 1982 that the mining occurred at a significant scale. Quintana Minerals Corporation mined the property for three months in 1982 producing 7.4 million pounds of copper, 2,306 ounces of gold, and 55,966 ounces of silver. Mining activities ceased because of low copper prices. The mining equipment was dismantled and sold. The Canadian Imperial Bank reclaimed the site. Subsequent efforts to permit mining operations by Gold Express of Denver, Colorado and Alta Gold of Henderson, Nevada were never completed. The property is now owned by Hydro Resources, Inc. of Albuquerque, New Mexico as a combination of fee simple properties and patented mining claims.

Since no mining activities have occurred since 1982, the site is an excellent field laboratory for studying the behavior of metals and sulfide minerals exposed with waste rock and tailings in the southwest. In addition, there is a 12.8-acre pit lake on site that is located near the center of the breccia pipe. This study focuses on the potential impact of the pit lake, the waste rock piles, and the tailing impoundment of the local surface and groundwater quality.

The pit lake has been sampled at least 65 times between 1980 and 1997. The pH of the lake is typically neutral to alkaline, with exception occurring in 1992 and 1993, where the pH dropped as low as 4.4. At least one intermittent seep from the pit wall has been sampled and the results reported a pH of 2.64, a total dissolved solid concentration (TDS) of 12,770 milligrams per liter (mg/L), and a sulfate concentration of 790 mg/L.

However, groundwater inflow into the pit lake is neutral to alkaline with pH ranging from 7.2 to 8, TDS of 920 mg/L, and sulfate less than 410 mg/L. The andesitic host rocks surrounding the ore body have a high acid buffering capacity as shown by the partial dissolution of calcite and the precipitation of gypsum and goethite. The alkalinity of the groundwater and host rocks quickly neutralizes and dilutes acidic discharges into the pit lake.

Samples collected from the waste rock piles and drill core indicated initially that the rocks produce more acid than they can neutralize. However, kinetic testing showed that leachate derived from the waste rock is predominantly alkaline and has low sulfate and metal concentrations. These results indicated that sulfide oxidation is slow and acid buffering through mineral water reactions and groundwater recharge is sufficient to maintain a non-acidic environment.

Samples collected from the tailings dam indicated a moderate potential for acid generation and high metals concentrations. However, paste pH values were all greater than 6.1 and leachate samples indicated the metals are not easily leached. A down-gradient monitoring well showed elevated concentrations of TDS and sulfate soon after tailings were slurried into the impoundment indicating a some leakage into the environment despite significant geotechnical information, which suggested leakage was not likely.

Significant data collection and analyses collected from Copper Flat over the last 35 years indicated that the production of acid mine drainage and metals mobilization is possible. However, because of the high acid neutralization capacity of the natural groundwater and host rocks, coarse, crystalline pyrite, a low volume of disseminated sulfides, and low humidity and precipitation, sulfide oxidation is slow and metal release from all lithologies is low.

1.0 Introduction

1.1 Purpose of the Copper Flat Investigation

The purpose of this investigation is to compile and assess the existing ground- and surface-water quality in the vicinity of an existing mine pit lake, waste rock piles, and mine tailings impoundment at Copper Flat, Hillsboro district, New Mexico, 25 miles southwest of Truth of Consequences and 5 miles northeast of Hillsboro (Fig. 1). Data from existing historical reports and documents have been reviewed and integrated. This report is intended to be a comprehensive source with respect to assessing the potential for environmental impacts of the mine pit lake, waste rock piles, and tailings impoundment based on existing conditions. Water quality data associated with this research have been incorporated into an electronic format that will become part of the New Mexico Mines Database.

1.2 Site Background

1.2.1 Geological History of the Hillsboro Mining District

1.2.1.1 Geology

The predominant geologic feature of the Hillsboro district is the Cretaceous Copper Flat strato-volcano (Fig. 2). This structure is eroded to a topographic low and is approximately 4 miles in diameter (Hedlund, 1985). The Hillsboro district comprises part of the Animas Hills, a low range formed by a horst at the western edge of the Rio Grande rift. The Animas hills are separated from the Black Range to the west by a graben, in which sits the town of Hillsboro. Faults that bound the Animas Hills horst are related to the to the tectonic activity of the Miocene-age Rio Grande rift (Dunn, 1982).

00539

The 4-mile diameter circular block of andesite represents the central part of the Animas Hills, of which the eastern edge of the andesite block forms the eastern edge of the horst. At this location the andesite is in fault contact with Santa Fe Group sediments deposited in the ancestral Rio Grande rift. A drill hole in the southwest corner of T15S, R6W indicates that Santa Fe Group sediments are at least 2,000 ft thick (Dunn, 1982). The remaining periphery of the volcanic terrain is marked by nearly vertical faults along which the andesite has been down-dropped against Paleozoic sedimentary rocks. The vertical displacement along these faults is not known, but drill holes collared in andesite were still in andesite at depths greater than 3,000 ft from the surface. The thickness of the andesite and the concentric fault pattern suggest a deeply eroded Cretaceous-age volcanic complex (Dunn, 1982).

The core of the volcanic complex is intruded by a quartz monzonite stock, the Copper Flat Quartz Monzonite (CFQM). The CFQM stock has a surface expression of approximately 0.4 square miles. The CFQM has been dated by the argon-argon ($^{40}Ar/^{39}Ar$) techniques to be 74.93 +/- 0.66 million years old (McLemore et al., 2000). The surrounding andesites also have been dated using argon-argon techniques to be 75.4 +/- 3.5 million years old (McLemore et al., 2000). At least 34 dikes radiate out from the quartz monzonite intrusion. The quartz latite and low silica rhyolite dikes are generally oriented N 45-55 E and N 40-50 W and represent a late stage differentiation of the CFQM stock. The dikes are as much as 38 meters (m) (125 ft) wide and 1.6 km (5,200 ft) long (Hedlund 1985). The dikes are gray to tan, typically holocrystalline and porphyrytic. Two predominant types of dikes occur: a pohyrytic latite with large orthoclase phenocrysts and an aphanitic latite. The dikes contain quartz, potassium

feldspar, plagioclase, biotite, magnetite, locally hornblende, pyrite, apatite, and rutile (McLemore et al., 2000). Polymetallic veins are associated with the latite and quartz latite dikes that radiate outwards from the CFQM. They are subparallel to the dikes.

The Copper Flat porphyry copper deposit is one of the older Laramide porhyry copper deposits in the Arizona-Sonora-New Mexico porphyry copper belt (Fig. 3) and is characterized by low-grade hypogene mineralization that is concentrated within a breccia pipe in the CFQM stock. The CFQM is a medium to coarse-grained, holocrystalline, porphyritic intrusion that consists of potassium feldspar, plagioclase, hornblende, biotite, and trace amounts of magnetite, apatite, zircon, and rutile with local concentrations of pyrite, chalcopyrite, and molybdenite (McLemore et al., 2000). Current proven and probable reserves are 50,210,000 tons of ore containing 0.45 percent copper (Hydro Resources, 2002).

1.2.1.2 Hydrothermal Alteration of Igneous Rocks

Andesite in the study area is typically altered adjacent to the CFQM, the latite/quartz latite dikes, and the polymetallic veins (Table 1). Three types of alteration mineral assemblages are recognized in the Copper Flat porphyry copper deposit: biotite-potassic, potassic, and sericitic alteration (Fowler, 1982). Biotite-potassic alteration coincides with the highest copper grades in the deposit, and is characterized by hydrothermal biotite, potassium feldspar, quartz, and pyrite occurring in veinlets and replacement of monzonite (McLemore et al., 2000). Potassic alteration is peripheral to the deposit and is characterized by large potassium feldspar phenocrysts and as rimming of plagioclase by potassium feldspar, chlorite, quartz, and pyrite (Fowler, 1982). Sericitic alteration is the outermost alteration zone of the deposit and is characterized by

replacement of biotite and feldspar by sericite. Veinlets of quartz-sericite (+/- pyrite) are common (McLemore et al., 2000) and represent significant sources of Fe and S from the Copper Flat deposit.

The latite/quartz latite dikes are extensively altered and are commonly associated with polymetallic quartz veins. Quartz, potassium feldspar, chlorite, pyrite and locally epidote characterize alteration in the dikes, which have replaced biotite, hornblende, feldspars, and the groundmass. Local sericitic alteration is common, which consists of quartz and sericite. Two stages of pyrite are common in the dikes. Early pyrite is altered and corroded and later pyrite is fresh and unaltered. Some younger pyrite may contain chalcopyrite. A third stage of pyrite has been observed that is locally present as inclusions within younger chalcopyrite and quartz veinlets (McLemore et al., 2000).

Propylitic alteration is adjacent to the mineralized veins. Epidote, chlorite, sericite, pyrite, and locally magnetite characterize this alteration. Typically, pyrite and magnetite are altered to iron oxides. Epidote and chlorite locally replace plagioclase. Epidote-pyrite and pyrite veinlets are common along fractures within the andesite. Disseminated pyrite occurs in the andesite for a distance of several meters away from the contact with the latite/quartz latite dikes and polymetallic veins. Pyrite locally replaces hornblende and olivine grains (McLemore et al., 2000).

Adjacent to, and overlapping, the propylitic alteration is the argillic alteration zone. Sericite, chlorite, quartz, and pyrite characterize this zone. Chlorite has replaced mafic minerals and the groundmass within the andesite. Disseminated pyrite is present locally in the andesite. Calcite occurs in thin veins and also replaces feldspar crystals. Sercite also replaces potassium feldspar crystals (McLemore et al., 2000).

A second, less common, propylitic alteration is present in the andesite adjacent to a few dikes. This mineral assemblage consists of a white to greenish-gray fault gouge compose of chlorite, kaolinite, sericite, calcite, quartz, and pyrite. As observed in underground workings, these zones are locally thicker where polymetallic veins pinch out or form several small veinlets of quartz and pyrite (McLemore et al., 2000).

The andesite exhibits a variable prophylitic to argillic alteration where adjacent to the CFQM. Typically, the andesite is fractured and locally contains veinlets of chalcopyrite and pyrite in association with chrysocolla, malachite, and azurite. Chlorite, sericite, and iron oxides are common in the andesite (McLemore et al., 2000).

1.2.2 History of Hillsboro Mining District

Ore was first discovered in the Hillsboro district in April 1877 along one of the veins that extend southwest of the Copper Flat stock (Jones, 1904; Dunn, 1982). Placer gold was discovered in November of that same year in Snake and Wick Gulches. The town of Hillsboro was established in 1877 and a tent city named Gold Dust was founded in 1881. Hillsboro was the county seat for Sierra County from 1884 to 1938 (Mclemore et al., 2000). Most underground mining was prior to 1893, but some efforts extended into the early 1990s (Hedlund, 1985; McLemore, 2003). Reflecting an increase in the price of gold, placer mining activity increased from 1932 to 1943 and still continues today on a small scale (Hedlund, 1985; McLemore, 2003).

At Copper Flat, the Sternberg Mine yielded 200 tons of copper ore between 1911 and 1934 from a weakly-developed oxidized zone in the Copper Flat stock (Harley, 1934; Hedlund, 1985). Newmont Mining Company explored the Copper Flat area in 1952 drilling six inclined holes totalling 3,396 feet. Hilltop Mining then operated a copper

leach plant for a short time before Bear Creek Mining, in 1958 and 1959, drilled 20 additional holes that totaled 9,346 feet. Bear Creek Mining was credited with recognizing the potential of brecciated mineralized zone of the CFQM and that a supergene-enriched zone probably did not exist. Inspiration Consolidated Copper (Inspiration) drilled an additional 28 holes totaling 23,046 feet of core between 1967 and 1973. In addition, Inspiration proceeded with deep drilling in the andesite, drilled some shallow water wells, and prepared a preliminary feasibility study and mine plan for an open pit mine. Quintana Minerals Corporation (QMC) leased the property from Inspiration in 1974 and from 1974 to 1976, drilled another 127 holes for 94,097 feet of core. QMC developed 2,241 feet of underground workings to provide bulk samples for pilot plant metallurgical studies. Data from the underground workings were used to cross check the ore reserve calculations, which were calculated from the vertical drill holes. QMC also established a water supply and mapped the immediate area of the porphyry deposit at a scale of 1:2,400, completing a feasibility study in 1976 (Dunn, 1982; Hedlund, 1985).

In 1982, the Copper Flat Partnership, Ltd. with QMC as the mine operator, developed and operated an open pit copper mine, including a 15,000-ton-per-day flotation mill and a tailings impoundment, at the Copper Flat site (Figs. 4, 5, 6). The mine operated for 3 months before it ceased operation due to unfavorable economic conditions. During three months of operation, the mine produced 7.4 million pounds of copper, 2,306 ounces of gold, and 55,966 ounces of silver (Hedlund, 1985). The plant was placed on a “care and maintenance” status until 1986 when the facilities were sold and dismantled. The mining leases were returned to Inspiration and the site was partially

reclaimed. Figure 7 presents an aerial photograph that shows the contoured property in 1988.

Gold Express Corporation of Denver, Colorado acquired the property from Inspiration in 1991 and prepared a draft environmental assessment (EA). In 1993, the Bureau of Land Management (BLM) notified Gold Express Corporation that an environmental impact statement (EIS) would be required due to concerns related to water resources issues (BLM, 1999).

In 1994, the Alta Gold Company (Alta Gold) of Henderson, Nevada acquired the Copper Flat Project from Gold Express. Alta Gold and consultant, Steffen, Robertson, and Kirsten, Inc. (SRK) of Reno, Nevada, prepared a draft EIS in 1996. Significant comments on the EIS were received and two years of additional study was required to address water resource issues. The final draft of the EIS was prepared for the BLM by ENSR of Fort Collins Colorado and completed in March 1999. However, the EIS was never finalized because Alta Gold declared bankruptcy in 1999 (BLM, 1999). Hydro Resources, Inc. (Hydro Resources) of Albuquerque, New Mexico now owns the property (Hydro Resources, 2002).

1.2.3 Previous Investigations

Some information from these early exploration activities dating to the 1950s is stored at Hydro Resources in Albuquerque, New Mexico. Hedlund (1985), briefly described the geology, mining history, porphyry copper deposit, vein deposits, and placer deposits associated with Copper Flat. Subsequently, Dunn (1992) described the field work done in support of the feasibility study prepared by QMC in 1976 including the diamond drilling results, sample preparation and assaying, ore reserve estimates,

metallurgical sampling results, water supply information, and locating non-mineralized areas suitable for the location of the processing facilities. Dunn (1992) determined that the minable reserve is 60 million tons with an average grade of 0.42 percent Cu and 0.012 percent Mo plus trace, but economically significant silver and gold. The cost of the exploration work was estimated at $2.75 million (Dunn, 1992). QMC hired a civil engineering firm, Sergent, Hauskins, and Beckwith (SHB) of Albuquerque, New Mexico to design and to supervise the construction of the tailings starter dam. SHB performed geotechnical investigations and construction oversight activities from 1976 to 1981. The BLM with the assistance of Fred A. Glover of Fort Collins, Colorado prepared an EA on QMC's proposed open pit copper mine (BLM, 1978; Glover, 1977). QMC hired W. K. Summers and Associates of Socorro, New Mexico to perform step pumping test of water well CWQ-7 (Summers, 1981). Also, QMC hired Water Development Corporation of Tucson, Arizona to conduct pumping tests of the production water wells (WDC, 1975, 1976, 1980).

Gold Express prepared an EA for re-opening the copper mine at Copper Flat. The EA is based on the previous EA prepared by the BLM and Glover. Gold Express also contracted John W. Shomaker, Inc. of Albuquerque, New Mexico to complete a hydrologic assessment of the Copper Flat Project (Newcomer et al., 1993).

Alta Gold did a significant amount of work in support of obtaining a mining permit from the New Mexico Mining and Minerals Division (NMMMD) and approval by the BLM. Table 2 presents some of the more significant reports prepared for Alta Gold by their consultants, SRK, Adrian Brown Consultants (ABC), and ENSR. In addition,

the NMMMD contracted an independent environmental evaluation report, which was prepared by Daniel B. Stephens and Associates, dated November 17, 1997.

Munroe (1999), Munroe et al. (1999, 2000) examined and reported on the geochemistry, minerology, and physical characteristics of mine waste rock piles in southwestern New Mexico. McLemore et al. (1999, 2000) examined the geology and evolution of the mineral deposits of the Hillsboro district and the geochemistry of the Copper Flat porphyry and the associated deposits. Bakkom and Salvas (1997) proposed a phased reclamation plan for the area of the former processing plant.

2.0 Study Area Investigations

2.1 Surface Features

Surface features of the Copper Flat mine area include a mine pit lake, rock storage piles, the former mine and mill areas, and a tailings impoundment area. Land disturbed by the Copper Flat mine includes 358 acres of public land managed by the BLM and 331 acres of private lands (Fig. 8). The pit lake is approximately 12.8 acres, with a depth of approximately 40 ft. The elevation of the pit bottom in 1986 was 5,380 ft. The surface water elevation in 1999 was 5,420 ft (BLM, 1999). The existing overburden waste rock piles have been identified as the north, west, south, and east (SRK, July 1998) (Fig. 8). The tailings dam is at an approximate elevation of 5220 ft, is 6,600 ft long , and has a maximum crest height of 60 ft. The tailings dam is divided into the north cell and the south cell. Approximately 1.2 million tons of tailings were deposited into the north cell during the 1982 mining activities, and cover an area of 60 acres (km^2) (SRK, May 1995).

There is an unpaved but well maintained road from New Mexico Highway 152 to the mill area and a primitive road to the pit area. A 115-kilovolt-power line exists from Highway 152 to a termination 300 feet short of the former mill facility. A 20-inch welded steel water line still exists for transporting water from the four production wells in the Caballo Basin, east of the area, to the mine site. This pipeline is buried 2 ft deep and was in good condition based on 1990 inspection (BLM, 1999). The primary drainage through the site is Greyback Wash, which has been diverted around the perimeter of the site.

2.2 Mine Pit Lake Investigations

The water chemistry of the waters of the mine pit lake is influenced by:

- surface water discharge to the pit, occurring almost exclusively during times of heavy precipitation,
- geochemistry of the pit wall rock and surrounding rock storage piles, and
- groundwater recharge.

This section presents the investigations and techniques used to collect surface water from springs and seeps and groundwater in the vicinity of the mine pit lake. Pit wall and waste rock sampling will be discussed in Section 2.3. Sample results will be presented and discussed in Section 3.0.

2.2.1 Mine Pit Lake and Grayback Gulch Surface Water

The pit lake has been sampled 65 times between 1989 and 1998 (BLM, 1999; Bakkom and Salvas, 1997). Sampling of the pit lake commenced on April 3, 1989 by the New Mexico Environmental Improvement Board (NMEIB), which collected two pit lake surface water samples. Gold Express funded the analyses of 16 pit lake samples between

February 11, 1991 and March 17, 1994. Following Gold Express, Alta Gold and/or their subcontractors, SRK and ABC, collected and analyzed 37 more samples between May 24, 1994 and October 1, 1997. Bakkom and Salvas (1997) collected 16 samples on a quarterly basis between November 15, 1996 and October 8, 1997, four samples per quarter. The samples were collected at various locations and depths. Typically, the samples were analyzed for pH, major cations and anions, and metals. Sample analytical suites varied and sometimes the samples were filtered and sometimes not. Notes on the surface sample collections accompany the associated sample results, which are tabulated in Appendix A.

There are several unnamed springs and seeps in the area west of the pit in the Animas Hills and along Grayback Gulch. As observed by Newcomer et al. (1993), these springs and seeps were flowing in March, but dry by early May and are therefore ephemeral. The springs west of the pit drain into the bowl-shaped Copper Flat area (Newcomer et al., 1993). In 1993, attempts were made to measure the discharge of these springs and seeps. Where possible, the flows were measured with a 60 degree-notch weir. In cases where the weir could not be used due to lack of flow or proper weir positioning, flow was estimated (Newcomer et al., 1993). Seeps and springs sampled by Newcomer et al (1993) are named SWQ-1, SWQ-2, SWQ-3, BG, BG-2, and Warm Spring (Figs. 9, 10), and a seep denoted as Acid Drainage. This seep appears to have been an intermittent seep slowly discharging from a rock storage pile, however, the map showing the location of this seep is not presently available. Table 3 presents the dates and estimated flow rates in gallons per minute (gpm) for the springs and seeps sampled by Newcomer et al (1993).

Surface-water samples were first collected from Grayback Gulch in 1977, prior to the mining activities of QMC (BLM, 1978). These surface water-samples appear to have been collected quarterly during 1976 and 1977, and sample locations are identified as Station A, where the creek enters the QMC property; Station B, approximately 300 feet east of the present mine pit rim; and Station C, where the creek leaves the QMC property (BLM, 1978). An accurate map showing the locations of Stations A, B, and C is not available.

Alta Gold's consultant, SRK, collected one surface water sample from Grayback Gulch, from the outfall of a culvert in a land bridge built to support the tailings slurry line from the tailings thickener. When the sample was collected on May 26, 1994, there was no visible flow in the creek and the water was stagnant (SRK, May, 1995). In August of 1997, SRK observed and sampled seeps in the pit wall at locations PW-1 and PW-2 (Fig. 11). These seeps are in the vicinity of the Sternberg Lode area. Also in August of 1997, SRK observed and sampled a seep from the toe of the West rock storage pile. These were the first recorded seeps in four years of site study by SRK (SRK, Dec., 1997, and July, 1998).

SRK and others conducted additional surface water sampling along Las Animas Creek, north of the site, and Percha Creek, south of the site. However, those data will not be discussed in this report because Grayback Wash, the principal drainage from Copper Flat, discharges to Greenhorn Arroyo approximately 10 miles east of the mine site. Greenhorn Arroyo discharge directly into the Rio Grande at Caballo Reservoir, approximately 3.5 miles beyond the confluence of Grayback Gulch and Greenhorn Arroyo (BLM, 1999).

2.2.2 Mine Pit Lake and Groundwater

Prior to 1996, only one well was available for sampling groundwater in the vicinity of the pit lake. This monitoring well, GWQ-4, is located approximately one-half mile east of the existing pit. Two other wells, EIW and WIW, are located in the existing pit; however, these wells are thought to have been drilled for in-situ leaching and are not appropriate for the characterization of natural groundwater underlying the pit area. SRK drilled two new monitoring wells, each with dual completion, in 1996. Monitoring well GWQ96-22 was drilled up-gradient of the mine pit and well GWQ96-23 was drilled down-gradient (Fig. 10). GWQ96-22A is the shallow completion and GWQ96-22B is the deep completion of the GWQ96-22 well cluster. GWQ96-23A is the shallow completion and GWQ96-23B is the deep completion of the GWQ96-23 well cluster (SRK, Dec., 1998). GWQ96-22A was sampled 16 times between July 13, 1996 and October 15, 1998. GWQ-22B was sampled twice, once on July 13, 1996 and once on February 5, 1997. GWQ-96-23A was sampled 16 times between July 14, 1996 to October 15, 1998. GWQ-23B was sampled four times from July 14, 1996 to April 1, 1997 (BLM, 1999). Sample dates and sampling notes are tabulated in Appendix B.

2.3 Rock Storage Piles and Pit Wall Investigations

Two phases of rock storage pile characterization have been completed at Copper Flat by SRK. A preliminary assessment of the waste rock was conducted in 1994 and a more detailed study was performed in 1997. Both studies were conducted to assess the existing rock pile geochemical characteristics and the potential for future acid generation.

00551

Work performed in 1994 was to support the EIS. Work done in 1997 was for the preparation of the rock pile management plan (SRK, July, 1998).

In 1994, 19 samples were collected from the existing pit wall rock, rock storage piles, and archived drill core and cuttings (Fig. 11). The samples were subjected to:

- paste pH and conductivity measurements to determine if acid rock drainage is possible,
- determination of total metals concentrations,
- acid-base accounting (ABA) to assess the balance between potentially acid generating and potentially acid neutralizing minerals,
- agitated leach extraction tests to measure the amount of immediately soluble metals,
- humidity column testing to simulate long-term oxidation of the waste rock and evaluate drainage water quality,
- geotechnical testing to estimate the physical and hydraulic properties of the compacted rock storage materials (SRK, July 1998).

All waste rock samples were subjected to static testing, including sulfur speciation and neutralization potential tests, to assess the relationship of acid generating and acid neutralizing potential in the rock piles (Table 4). Samples indicated by the static tests as having the potential to generate acid were selected for kinetic testing. Based on the static tests, five samples were selected for the 29-week long kinetic column testing. These nineteen locations were considered by SRK to be typical of the rocks to be encountered during the mining operations (SRK, May 1995).

Of these 19 samples, five were selected based on paste pH results for further study using the kinetic column testing technique. The five samples selected were

00552

- SW-1 and LGSSP-2 from the sulfide-bearing waste rock piles,
- PW-2, quartz breccia from the pit wall, in the vicinity of the Sternberg Lode,
- IDC24-222-241 and CF10 –190-199, CFQM from archived drill core (SRK, May, 1995).

Table 5 summarizes additional testing that was done on the above samples.

In August of 1997, field work was conducted to produce detailed geologic and geochemical maps of the waste rock piles and the mine pit. One hundred and twelve samples were collected from 6-ft long trenches along benches on the rock storage piles. Figure 13 shows the locations and values of the pH samples collected in the vicinity of the pit lake. Fifty-one samples were analyzed for ABA and 59 samples were analyzed for net acid generation (NAG) (SRK, July, 1998). Table 6 presents the sample numbers of samples analyzed in the rock pile characterization studies.

McLemore et al. (1996) collected 12 samples of pond sediment and sulfide material from the pit walls about the mine pit lake. These samples were run for whole rock analysis using atomic adsorption and inductively coupled plasma spectrometry (Table 8, Fig. 13).

2.4 Tailings Dam Investigations

The tailings impoundment consists of an earthen embankment constructed across a minor valley, and is approximately 6,600 ft long with a maximum toe to crest height of 60 ft (Fig. 14). The impoundment is divided into the north and south cells, into which tailings were to be deposited. During the three months of operation, approximately 1.2 million tons of tailings were deposited into the north cell of the impoundment. The existing tailings cover a surface area of 60 acres in the north cell and have a mean surface elevation of 5220 ft (SRK, May 1995).

Extensive engineering design, construction, and short- and long-term groundwater monitoring work was done on the tailings dam. Numerous reports have been prepared that describe the work conducted at the Copper Flat tailings impoundment. Table 7 summarizes the reports in terms of authors, dates, and purposes.

In 1976, SHB performed 37 soil borings along the starter dam centerline (Fig. 15), with boring depths varying from 45 to 1,100 ft below grade. Borings along the centerline were spaced approximately 300 ft apart. Standard penetration testing and open-end drive sampling were performed at 5-ft intervals in most borings. Five test borings, ranging from 40 to 75 ft in depth, were drilled in the pond area (SHB, Oct.14, 1980).

SHB excavated 46 test pits and one test trench within the pond area to investigate the nature of the near surface materials and explore for borrow sources for the starter dam construction. In 1980, several of the pits were reopened and sampled for additional laboratory testing (SHB, Oct. 14, 1980).

SHB performed three types of permeability tests:

- 15 constant head tests were performed in uncased open auger holes using the U.S. Bureau of Reclamation E-19 Method,
- five double packer tests in accordance to U.S. Bureau of Reclamation Method E-18. Permeability test were performed in both volcanic rock and the overlying soils of the Santa Fe Group, and
- three special in-place permeability tests were made by placing 10-ft long screen in boreholes 5-inches in diameter and filling the annular space with clean filter sand. Annular space above the sand was grouted for at least 25 ft to isolate the screened interval. Long term permeability tests were performed on these piezometers in accordance with the Navy Design Manual. Two of the tests were performed in screened intervals below the water table (SHB, Oct. 14, 1980).

Geotechnical testing during 1976 included moisure-density relations, grain size analysis, Atterberg Limits, permeabilty, consolidation, and direct shear tests. In addition, grain-size analysis, Atterberg Limits, and moisture-density relations were performed on a sample of tailings produced by a project pilot plant operated by the Colorado School of Mines Research Institute. Tailings slimes were tested for moisture-density relations and direct shear to investigate the range of shear strength, which might be present near the dam slope (SHB, Oct. 14, 1980). Laboratory permeability tests were performed on samples of the synthetic drain materials and conventional granular filter materials (SHB, Oct. 14, 1980; SHB, Aug 29, 1980).

During this investigation, SHB collected several samples of water and soils for chemical analyses. These samples included four water samples from wells down-gradient of the dam alignment. Figure 16 presents the locations of groundwater samples 1, 2, 3, and 4; however, the map does not identify the specific wells from which the groundwater samples were collected. SHB also collected a sample of the thickener underflow water, which is assumed to be a groundwater sample collected from below the proposed location of the thickener. These groundwater samples were analyzed for general chemistry and metals. Three soil samples were collected from boring #5 at depths of 4.5, 14.5, and 29.5 feet below grade and two more samples were collected from Pit A-1, and Pit C-2 (Fig. 16). These soil samples were analyzed for cyanide. Soil samples also were collected from test pits A-1, A-2, F-1, and F-2. Aqueous suspensions of these soils were made and the liquid was measured for soluble anions, cations, and metals. Finally, water samples collected from borings 29, 30, 31, 33, and 34 were analyzed for

general chemistry and metals. No discussions of how the monitoring wells were constructed are associated with these borings (SHB, Oct., 1980).

In October 1980, an additional geotechnical investigation with respect to the decant line alignments and decant towers was conducted. Twelve additional soil borings were performed (Fig. 14), with borings drilled from 10 to 31 ft below grade. Standard penetration and open-end drive sampling were performed at selected intervals in the borings.

In April 1981, SHB produced a report responding to concerns by the New Mexico State Engineers office regarding potential settlement of the earthen dam structure. SHB elaborated on the original settlement analysis prepared in 1976 with additional dispersivity tests on two soil samples and verification of stress and strain calculations (SHB, Apr. 13, 1981). On September 4, 1981, SHB submitted a Geohydrological Evaluation to support the groundwater discharge to QMC. This report contains the results of the geohydrological field studies and data analyses, recommendations concerning the mitigation and monitoring of water quality effects, and a discussion of contingency measures (SHB, June 29, 1981). Unfortunately, this report was not located for review and incorporation into this study. It was not in the NMEIB files during a file review nor could it be found with the other files stored with Hydro Resources, Inc.

Two reports by SHB address the compacted clay plating that was placed to limit seepage through basaltic flow channels located adjacent to the impoundment divider dike. The exposed basalts were considered to be of higher permeability than the surrounding Santa Fe Group sediments. The purpose of the 1.5-ft thick clay plating was to minimize seepage in the northeast area of the south cell and in the southeast corner of the north cell

(Fig. 14). In addition, compacted clay was placed over six exploratory borings (nos. 4, 9, 10, 11, 14, and 15) to eliminate the possibility of the borings becoming seepage conduits. Monitoring well NP-5 was installed to monitor seepage within the basalt (SHB, Oct 13, 1981, SHB, Oct. 28, 1981).

John W. Shomaker, Inc. studied the ambient water quality underlying the tailings impoundment in 1993, approximately 11 years after the impoundment was filled (Newcomer, et al, 1993). From 1991 to 1993, groundwater samples from monitoring wells NP-1, NP-2, NP-3, NP-4, NP-5, GWQ-1, GWQ6, GWQ-7, GWQ-8, GWQ-10, GWQ-11, and McGravy-Greyback were collected and analyzed for general minerals, metals, and phenols (Fig. 10). Newcomer et al. (1993) identified a potential paleo-channel associated with the basalts noted by SHB near the center of the impoundment. Results are presented in Appendix B.

In 1994, SRK performed a study of the tailings impoundment (SRK, Aug., 1994). The study involved a review and interpretation of the tailings dam design, construction, operation, and monitoring activities and additional field investigations. In May and June 1994, SRK advanced two soil borings through the tailings and underlying alluvial and volcanic deposits (Fig. 10). The borings were converted to monitoring wells denoted as SRKBH-1-94 and SRKBH-2-94. One well was screened in the Santa Fe Group alluvial sediments and one well was screened in the basalts. Falling head permeability testing was done in both of the wells.

In 1994, Adrian Brown Consultants (ABC) was contracted by SRK to perform an aquifer test on well GWQ94-17 in order to estimate the lower of two near surface aquifers that receive recharge from areas impounded by the tailings dam and to determine

if the two water bearing zones are hydraulically connected (ABC, 1996). SRK also described the conceptual subsurface hydrology in tailings seepage modeling that the performed in support of the proposed re-use of the tailings impoundment by Alta Gold (SRK, Aug., 1998).

In support of the EIS, SRK sampled numerous wells in tailings impoundment area as well as other wells associated with Copper Flat from 1994 to 1998. Notes on these sampling activities and the sample results are tabulated in Appendix B.

On April 3, 2003, the author and Dr. Virginia McLemore visited the area north of the tailings dam to collect samples clay from an exposure of the clay in an arroyo north of the tailings dam (SHB, Oct. 1976). The principal material that SHB described as using in the clay plating of the basalts exposed in the center of the impoundment appears to have been reddish brown, highly plastic, sandy clay. The author and Dr. McLemore collected three materials, denoted as SR-1, SR-2, and SR-3, in close proximity to each other at latitude of 32.97 degrees and a longitude of 107.50 degrees (R6W, T15S, Section 30) (Fig 11). Sample SR-1 is a red sandy silt; SR-2 is a white cemented material, and SR-3 is a brown sandy silt. Stratigaphically, SR-2 overlies SR-1, which overlies SR-3. These clay samples were analyzed for bulk mineralogy and clay mineralogy. Visual-manual classifications of the clay and the results of the mineralogical analyses are discussed in Section 3.0

3.0 Nature and Extent of Potential Environmental Issues

3.1 Mine Pit Lake Investigative Results

3.1.1 Mine Pit Lake Surface Water

Pit lake water analyses per sample varied from pH only to anions, cations, and metals. Only copper concentrations exceeded the New Mexico Water Quality Control Commission (WQCC) water quality standards for surface water (WQCC, 2001). The WQCC surface water standard for livestock and wildlife is 0.5 milligrams per liter (mg/L). The pit lake was sampled and analyzed for copper 31 times (Fig. 17). Three times the concentration exceeded livestock and wildlife surface water standards; August 29, 1991, December 15, 1992, and February 12, 1993. The concentrations of copper that were reported from these three sampling events are 0.64 mg/L, 3.21 mg/L, and 2.6 mg/L, respectively.

Typically, water pH has been neutral to alkaline and indicates that the pit lake has been in a neutral to alkaline state for the last ten years (Fig. 18). However, from March 1992 to October 1992, the pH of the pit lake dropped below 5, with a low of pH = 4.4 in July 1992 A steady increase in the TDS concentrations of the pit lake was observed from April 1989 to October 1997 from approximately 3500 mg/L to 5850 mg/L (Fig. 19). A gradual increase in sulfate in the pit lake waters over the same time from 2340 mg/L to 4300 mg/L (Fig. 20) was also recorded. The TDS and sulfate results show some water quality degradation; however, the WQCC does not regulate either TDS or sulfate in New Mexico surface waters. The chemistry of the pit lake does not change significantly laterally or with depth (SRK, Dec. 1997). Analytical results of pit lake sampling are tabulated in Appendix A.

Sources of water to the pit lake are groundwater inflow, direct precipitation, and surface runoff. The major sources of dissolved solids are from reactions between oxidizing pit lake waters and reduced minerals in the pit walls, surface water runoff, and evaporation of the pit lake water. The remainder of the sulfate must be derived directly from sulfide oxidation or from the dissolution of secondary minerals such as jarosite and gypsum (SRK, Dec. 1997).

Because the pit lake is a topographic low, it is a hydraulic sink. Historic seeps have been described and sampled along the mine pit wall and rock storage piles. Newcomer et al. (1993) described a seep initiating from a sulfide-bearing rock pile having a discharge rate less than 1 gpm. This seep was sampled on May 7, 1993, but the location of this seep is uncertain because the associated sample location map is apparently not available. However, SRK identified a small area of sulfate precipitation near the base of the East rock storage pile, which they suggest is the site of the seep that Newcomer reported (BLM, 1996). This seep water sample reported a pH of 1.9, a TDS concentration of 17,020 mg/L and a sulfate concentration of 10,000 mg/L (Newcomer et al., 1993); however, no water or evidence of significant flow was observed during the 1995 SRK site visit (BLM, 1996), suggesting that this seep is an ephemeral source of low-pH, sulfate-bearing solution.

Another small seep was identified by SRK during a site visit in 1997. This seep flowed into a small, acidic, ferruginous pool located below the Sternberg Lode. A pit wall sample was collected near this area and denoted as PW-1 (Fig. 11) (SRK, Dec. 1997). The pH of water sampled from this seep was reported to be 2.64; the TDS concentration was 11,430 mg/L; and the sulfate concentration was 16,850 mg/L (BLM,

1999). This seep, observed in August of 1997, was the first recorded seep in the pit wall in four years of study by SRK and is believed to be the result of unusually high precipitation in June and July 1997 (SRK, Dec. 1997). A second pit wall seep was sampled by SRK in August 1997, denoted as PW-2 (Fig. 11). The results of this sample show lower concentrations of sulfate (3,100) and TDS (5020) and a greater pH (8.16) than the PW-1 sample.

SRK collected a seep sample from the West rock storage pile also in August of 1997. This sample has a pH of 3.03, and concentrations of TDS and sulfate at 25,440 mg/L and 22,100 mg/L, respectively (SRK, July, 1998). Full results of the seep sample analytical suites are presented in Appendix A

3.1.2 Greyback Gulch Surface Water

Greyback Gulch is an ephemeral stream that is dry most of the year except for runoff from storm events. The earliest surface water sampling was in 1976 and 1977 in support of the EA prepared for QMC. These surface water samples pre-date the 1982 mining activities by QMC, but post-date less extensive historical mining activities. Surface water results are available for January, March, and July 1977. They were collected from 3 stations described as Station A, where the creek enters the QMC property; Station B, approximately 300 feet east of the estimated mine rim; and Station 3, where the creek leaves the QMC property (BLM, 1978). The water quality of these samples is good compared to post-mining samples collected from similar locations (Table 9).

Three surface water locations have been sampled frequently in Grayback Gulch. These locations are SWQ-1, upstream of the mine pit; SWQ-2, downstream of the pit in

the former plant area; and SWQ-3, north of the tailing dam (Fig. 10). The SWQ-1 location was sampled five times between 1982 and 1993, SWQ-2 35 times between 1982 and 1998, and SWQ-3 26 times between 1991 and 1998.

All pH measurements at locations SWQ-1, SWQ-2, and SWQ–3 were neutral to alkaline (Fig. 21). Figure 23 presents the TDS measured in these three locations. Samples collected from SWQ-1 were all less than 1000 mg/L. A logarithmic trend line placed through the five points of the SWQ-1 data set indicates a gradual increase in TDS over time. Samples collected from SWQ-2 ranged from 1000 mg/L in the early 1980s to as high as approximately 4500 mg/L in the late 1990s. A logarithmic trend line placed through the 35 points of the SWQ-2 data set indicates a more pronounced increase in TDS over time. The 26 points from the SWQ-3 data set ranged from 1866 mg/L to 4432 mg/L. Sample frequencies and dates for sulfate are the same as the TDS (Fig. 23). Sulfate results for SWQ-1 were all less than 325 mg/L and the trend line increases slightly over time. The scatter of the data sets from SQW-2 and SWQ-3 was similar to the TDS results. Sulfate concentrations in waters sampled from SWQ-2 ranged from 445 mg/L to 2566 mg/L. The sulfate trend line increases with time. Sulfate concentrations in waters sampled from SWQ-3 ranged from 952 mg/L to 2382 mg/L, and sulfate appears to increase with time. The pH, TDS, sulfate and other constituent results are tabulated in Appendix A.

Figure 24 presents Stiff diagrams developed by Newcomer et al. (1993) from a sampling event that occurred in March and April of 1993. The patterns indicate that the water quality is higher at the up stream location, SWQ-1, not the downstream location SWQ-2 and SWQ-3. The increases in TDS and sulfate appear to be the result of mining,

mineral processing, construction, and road building activities during the mining activities of the early 1980s (Newcomer et al., 1993). However, water pH has been consistently neutral to alkaline and the WQCC does not have numeric standards for TDS and sulfate.

3.1.3 Groundwater

A set of nested monitoring wells exists up gradient of the mine pit lake, GWQ-96-22A (shallow) and GWQ-96-22B (deep), and a set of nested wells exist down-gradient, GWQ-96-23A (shallow) and GWQ-96-23B (deep). The down-gradient wells are referred to as Well construction details and surveyed location are not available for these wells; however, they are shown on Figure 10.

Figures 25, 26, and 27 show the results of groundwater sample results for pH, TDS, and sulfate respectively. The wells were sampled several times from 1996 to 1998. The pH is neutral in the GWQ-96-22A and slightly alkaline in GWQ-96-22B (Fig. 25). TDS is below the WQCC groundwater numeric standard of 1000 mg/L (WQCC, 1995) (Fig. 26). TDS concentrations found in the samples collected from both GWQ-96-22A and B are below 700 mg/L. TDS concentrations found in groundwater sampled from GWQ-96-23A and B also are less than 1000 mg/L. However, there may be a trend showing that TDS is increased gradually over time in the shallow down-gradient well. Sulfate concentrations are below the WQCC numeric standard of 600 mg/L in both the up gradient and down-gradient wells both shallow and deep (Fig. 27). In groundwater sampled from GWQ-96-22A, sulfate concentrations do not exceed 300 mg/L. In GWQ-96-22B, the single sulfate concentration was found to be 79 mg/L. In groundwater sampled from GWQ-96-23A, sulfate concentrations do not exceed 450 mg/L. In GWQ-96-23B, the sulfate concentrations were found to be less than 240 mg/L. However, the

sulfate concentrations from the down-gradient shallow well indicate that the sulfate concentrations are gradually increasing over time.

3.2 Rock Storage Pile Investigative Results

Section 2.3 describes the pit wall and rock storage pile investigations conducted in 1994 and 1997 for potential sulfide oxidation. Tables 4, 5 and 6 present the analyses done on the samples and Figures 11, 12, and 13 present sample locations.

3.2.1 Metal Content and Mineralogy

The mineralogy of the samples was determined visually. The most common sulfide mineral was coarse crystalline pyrite. Concentrations of pyrite were estimated between less than 1 percent and 10 percent. In one location in the North waste rock pile, the pyrite concentration was estimated to be as high as 20 percent (SRK, July 1998). Sulfides observed were chalcopyrite, bornite, tetrahedrite, enargite, covellite, and molybdenite. Gangue minerals associated with the sulfide mineralization include quartz, feldspars, and biotite. Other minerals include calcite, flourite, siderite, magnitite, sericite, epidote, and chlorite (SRK, July 1998).

Whole rock chemistry analyses of the samples collected by McLemore in 1996 and PW-3 and WD-1 collected by SRK in 1994 indicate high concentrations of aluminum, manganese, copper, and iron (Appendix C). Copper, molybdenum, sulfer, silver, zinc, and cadmium are enriched relative to typical crustal abundance (SRK, July 1998).

An extractable metals analysis was run on the WD-1 sample using EPA Method 1312 leaching method (Table 10). This sample was selected for the extractable metals because it was a transition waste rock that exhibited low field pH. Therefore the leachate

constituent concentrations would be expected to be greater than the fresh unoxidized waste rock samples (SRK, July 1998).

3.2.2 Paste pH

Paste pH analysis was performed on 141 samples. The number of paste pH analyses run per rock type was:

- quartz monzonite - 94
- quartz breccia - 28
- biotite breccia – 10
- quartz vein – 8
- andesite – 1.

The pH results range between 3 and 9 for all rock types but the andesite (Fig. 28). The one paste pH result in Andesite was 9. The greater frequencies are acidic.

3.2.3 Acid Base Accounting

Acid Base Accounting tests were done in 1994 and 1997. The ABA tests indirectly estimate acid generation potential (AP) by comparing sulfide sulfur content to the acid neutralizing potential (NP) of the sample. The Sobek method was used to analyze the 1994 samples and the modified Sobek method was used to analyze the 1997 sample. The modified Sobek method is considered to be more conservative for estimating NP (SRK, July 1998). Figure 29 compares the NP versus AP. Figure 30 presents the NP versus AP by rock type for the 1997 data. The diagonal line on Figure 30 represents NP is equivalent to AP. The results of the 1997 acid base accounting indicate that most of the samples have the potential to produce more acid than they can neutralize (SRK, July 1998).

00565

3.2.4 Net Acid Generation Testing

Fifty-nine samples were run for NAG pH. The NAG test underestimates the amount of sulfide in the sample, but assumes complete oxidation of the sulfide. The results provide a realistic indication of the amount of sulfide that may react in the field. For all rock types, the majority of the samples are acidic (Fig. 30) (SRK, July 1998). The raw data for paste pH, ABA, and NAG are found in Appendix D.

3.2.5 Kinetic Testing

Kinetic testing or humidity column testing was conducted on four quartz monzonite samples and a quartz breccia sample:

- samples SW-1 and LGSSP-2 were obtained from the sulfide waste rock piles,
- sample PW-2 was obtained from the pit wall in the vicinity of the former Sternberg Lode,
- samples IDC 24-222-224 and CF10-190-199 were obtained from archived drill core (Fig. 12).

The sulfide waste samples (SW-1 and LGSSP-2) are representative of previously mined unoxidized materials that have been exposed to weathering since 1982. The samples contain fresh pyrite and chalcopyrite which coat fractures and are disseminated throughout the rock. Sample PW-2 was collected from the wall on the south side of the pit. The sample was highly oxidized, but contained residual disseminated pyrite and chalcopyrite. The core samples (IDC 24-222-241 and CF10-190-199) are representative of the unoxidized quartz monzonite that may be mined in the future. They contain fresh pyrite and chalcopyrite.

00566

3.2.5.1 Kinetic Test Results – pH

The kinetic tests were run initially for 19 weeks. A problem occurred in week 20 causing inconsistent results, which was later identified as contaminated deionized leachate water. The kinetic tests were halted for seven weeks while the problem was corrected and the tests were continued in week 27 and 28.

The results from all of the samples except PW-2 were neutral to alkaline ranging from 7 to 8.1 (Fig. 32). Sample PW-2 was slightly acidic with pH results ranging from 5.8 to 6.5 (SRK, July 1998; SRK, May 1995).

3.2.5.2 Kinetic Test Results – Electrical Conductivity

Leachate conductivity is an indicator of soluble metals and sulfate (TDS). Figure 33 indicates that electrical conductivity decreased over time. By week 20, the conductivity of all test leachates was less than 100 microSiemens per centimeter (μS/cm). This low conductivity suggest limited leaching of metals and sulfate (SRK, July 1998; SRK, May 1995).

3.2.5.3 Kinetic Test Results – Sulfate

After 15 weeks, the sulfate concentration in the leachate from all samples is less than 50 mg/L (Fig. 34). These results are well below the WQCC numeric groundwater standard of 600 mg/L.

3.2.5.4 Kinetic Test Results – Copper and Iron

Concentrations of copper and iron in the leachate were recorded during the kinetic testing (Fig. 35). Metal concentrations in both graphs drop off rapidly in all of the samples. Metal concentrations in most samples fall below the detection limits (SRK, July 1998; SRK, May 1995).

3.2.5.5 Kinetic Test Results – Alkalinity and Acidity

Concentrations of alkalinity and acidity (as milligrams of $CaCO_3$ per liter) in the leachate were recorded during the kinetic testing (Fig. 37). The concentrations of alkalinity gradually decrease over time; however, acidity concentrations are several times less than alkalinity and are stable over time. The gradual decrease of alkalinity suggests consumption during the neutralization of acid (SRK, July 1998; SRK, May 1995). The results of the kinetic tests are presented in Appendix D.

3.3 Results of Tailings Dam Investigations

The tailings system was reclaimed in 1986 in accordance with the requirements at that time. The reclamation included covering the existing tailings with topsoil. The topsoil was re-vegetated and the intermediate decant pipe intakes were sealed (SRK, May 1995).

3.3.1 Geochemical Investigative Results

During the 1976 geotechnical investigations conducted by SHB, several samples of groundwater and leachate from native soils were analyzed for chemical constituents. Four groundwater samples were collected from wells down-gradient from the tailings dam. The locations of these samples are shown on Figure 17; however, SHB did not identify the wells by name or reference. Theses samples were analyzed for general mineralogy and some metals. SHB collected soil samples from test pits A-1, A-2, F-1, and F-2 (Fig. 15). Aqueous suspensions containing the soluble components of the soils were made and analyzed for general chemistry and metals. Finally, groundwater was collected from soil borings 29, 30 31, 33, and 34 (Fig. 15) (SHB, Oct. 1980). The results are presented in Appendix B.

00568

In 1996, SRK excavated five test pits in the in the existing tailings impoundment. Eleven tailings samples were collected from the five test pits and were grouped in accordance to their appearance; yellow tailings were assumed to be derived from oxidized or transition oxidized-reduced materials. These samples are identified with "TTLS" in the sample identification. Gray sample colors are assumed to be derived from unoxidized quartz monzonite protolith, and are denoted with "UTLS" in the sample identification. Black tailings are assumed to be derived from biotite breccia, and are denoted with "BTLS".

The reactivity of the tailings samples are low, with paste pH for all of the samples varying from 6.2 to 7.8. ABA analyses indicate that five of the 11 samples had NP:AP ratios less than 1, indicating that these samples have moderate potential to generate acid. The remaining samples had an NP:AP greater than 1, indicating weak potential for generating acid (SRK, July 1998).

In 1994, SRK collected two samples from boring SRKBH-1-94 (Fig. 10). One of two samples, T-10-12, was analyzed for total metals by ICP and extractable metals by EPA Method 1312 (Table 11). The sample had high concentrations of aluminum (2,700 parts per million (ppm), copper (1,600 ppm), iron (19,000 ppm), magnesium (1,800 ppm), potassium (1,400 ppm), and zinc (418 ppm). The results of a single leach test indicate that these metals are not easily leached (SRK, May 1995).

3.3.2 Hydrogeological Investigative Results.

The subsurface hydrology beneath the tailings impoundment consists of three zones Fig. 38):

- The upper “perched” zone contains sands and gravels, which are located adjacent and down-gradient of the tailings impoundment. This unit dips and thickens to the east and groundwater in this zone is unconfined.
- Underlying the upper zone is a clay layer. This unit is up to 150 ft thick.
- The lower zone consists of clayey and silty sands of the Santa Fe Group. Groundwater in this zone is confined beneath the clay, but unconfined to the west, where the unit outcrops at the surface. This zone is assumed to be approximately 200 ft thick (SRK, Aug. 1998).

In 1994, ABC/SRK conducted a pumping test of monitoring well GWQ94-17. The results of this pumping test indicated that upper and lower water bearing zones are not hydraulically connected (ABC, Sept, 1996).

SHB (Oct 1980), Newcomer et al. (1993), and SRK (Aug. 1994) indicate a potential paleochannel buried near the surface in the vicinity of the levee bisecting the impoundment. SHB observed breciated basalts in this area and recommended that a compacted clay liner be installed in these areas (Fig. 14).

3.3.3 Permeability Testing

SHB performed 15 constant head permeability tests in uncased bore holes by the U.S. Bureau of Reclamation (USBR) E-19 Method, 5 USBR Method E-18 double packer permeability tests in volcanic rock and typical soils, and 3 long term falling head permeability tests in constructed piezometers. The results of the E-19 tests performed in the clayey sands and gravel averaged (14.6 ft per year (ft/yr) (1.4×10^{-5} centimeters per second (cm/s)). The E-18 tests in clay showed no measurable permeability and the basalts indicated average permeability values of 234 ft/yr (2.3×10^{-4} cm/s). The falling head piezometer permeability results in clayey sands and gravel were 61 ft/yr (5.9×10^{-5}

00570

cm/s) (SHB, Oct. 1980). Remolded permeability sample results of the clay used in the exposed breccia compacted liner averaged 0.7 ft/yr (7.0 x 10^{-7} cm/s) (SHB, Oct. 1980). Results from the SHB permeability testing are in Appendix E.

SRK performed one additional falling head test in the Santa Fe Group and in the basalts. These tests were done in 1994 in wells SRKBH-1-94 and SRKBH-2-94 (Fig. 10). The results of these permeability tests are 279 ft/yr (2.7 x 10^{-4} cm/s) for the basalts and 383 ft/yr (3.7 x 10^{-4} cm/s) for Santa Fe Group sediments (SHB, Aug. 1994).

3.3.4 Groundwater Impacts

The two wells down-gradient of the tailings impoundment with the longest sampling history are NP-3 and NP-4. They are indicators of the effectiveness of the seepage control engineered for the existing impoundment. Figure 39 shows pH concentrations in NP-3 from October 1981 to July 1998 and in NP-4 from April 1982 to July 1998; this figure shows that groundwater sampled from these wells has always been neutral to alkaline. Figure 40 shows concentrations in TDS in groundwater sampled from the two wells over the same time periods. The TDS concentration from NP-3 groundwater exceeded the WQCC numeric groundwater standard of 1000 mg/L in early 1984 and apparently peaked at 1,880 mg/L in early 1987 and has been gradually decreasing since. However, the latest measurement of 1,433 mg/L taken on July 13, 1998 still exceeds the standard. TDS concentrations in NP-4 have stabilized at approximately 500 mg/L. There are anomalous readings in the TDS concentrations from the samples collected on September 24, 1994 from NP-3 and January 15, 1997 from NP-4. These measurements do not fit the trend of the data and must be suspect. Figure 41 shows similar trends to the TDS for sulfate concentrations. The sulfate concentrations in

groundwater collected from NP-3 peaks at 971 mg/L in 1991 and then gradually decreases with time. The most recent measurement collected on July 28, 1998 is 718 mg/L, which is higher than the WQCC numeric standard of 600 mg/L. Sulfate concentrations in NP-4 never exceed the standard and most recently appear stable at less than 200 mg/L. NP-3 is the well that most consistently exceeds any WQCC numeric standards in the vicinity of the tailings impoundment other than GWQ-13. The three samples collected from this well are similar in TDS and sulfate concentration to NP-3, and they are adjacent to each other.

3.3.5 Liner Borrow Material Study

SHB recommended that compacted clay liners (approximately 1.5 ft thick) be placed where brecciated basalts are exposed at the surface in the center of the impoundment. Alta Gold accepted this recommendation and the lined areas are shown on Figure 14. The liner material was borrowed from the site and SHB observed that very similar materials were exposed in an arroyo north of the impoundment (SHB, Oct, 1976). On April 4, 2003, a sample of this material and two additional soils were collected. A global positioning reading was taken at the location of the sample collection (32.97613 degrees latitude and 107.50392 degrees longitude). That latitude and longitude was loaded in the ALL TOPO, a geographic software program, and the location was adjusted slightly to 32.96987 degrees latitude and 107.50239 degrees latitude (Fig. 10). A visual-manual description of the soils and the locations of the materials relative to each other were noted (Table 12).

The red sandy clay material was the predominant material borrowed and used in the compacted clay liner (Table 13). SHB conducted sieve analyses, Atterberg Limits,

Proctor maximum density and optimum moisture content, and permeability testing on similar material. Sieve analyses also were performed on the brown sandy clay/silt. The locations of these samples can found on Figures 14 and 15. SHB boring/test pit logs and test worksheets are presented as Appendix F.

From April 28 to May 4, 2003, a hydrometer analysis was conducted to determine the clay fraction of red material (sample SR-1) in accordance with the U. S. Army Laboratory Soils Testing Manual (USACE, 1965). The results show that approximately 3.4 percent of the material is sand, approximately 2.5 percent of the material is clay, and the remainder is silt. A free swell test also was performed by adding 10 milliliters of the dry fines to a graduated cylinder, submerging in water, and allowing the material to expand in the cylinder. After 24 hours, the material had expanded to 16 ml, which is a swell of 60 percent. The natural moisture content on the sample was 6.3 percent (Appendix F).

On April 11, 2003, bulk mineralogy using X-ray diffraction (XRD) was performed on samples SR-1, SR-2, and SR-3. The predominant minerals present in sample SR-1 are quartz, calcite, feldspars and undifferentiated clays. The predominant mineral in sample SR-2 is calcite. The predominant minerals in sample SR-3 are quartz, muscovite, feldspar and undifferentiated clays. Clay slides were prepared for samples SR-1 and SR-3 (Table 14). Clay was not present in sample SR-2. The clay slides for samples SR-1 and SR-2 were run after air drying, after 24 hours in a glycol chamber, and after 30 minutes of heating at approximately 375 degrees centigrade (Hall, no date). The bulk XRD test scans, the clay test scans, and the clay mineralogy distribution calculations are presented as Appendix G.

4.0 Conclusions and Recommendations

4.1 Mine Pit Conclusions

4.1.1 Surface Water Quality, Mine Pit Lake

The water quality of the pit lake does not exceed New Mexico WQCC surface water numeric standards for livestock and wildlife as of 1998 (Table 15). Historically, only copper concentrations exceeded the WQCC numeric standard of 0.5 mg/L. The most recent surface water sample to exceed this standard was collected in February 1993, with a concentration of 2.6 mg/L. No other metal, cation, or anion exceeded any of these standards except chromium, once on November 16, 1994, a pit lake sample had a concentration of 0.2 mg/L, which exceeds the domestic and irrigation use numeric standard of 0.1 mg/L.

Since 1994, pH measurements have consistently remained neutral to alkaline (Fig. 18). Copper has not exceeded the numeric standard for livestock and wildlife since 1993 (Fig. 17). Although sulfate and TDS are gradually increasing over time; there are no numeric surface water quality standards for these parameters (Figs. 19, 20). The drop in the elevation of the surface of the lake in recent years may explain the increase in TDS. From 1993 to 1997, the water level in the lake dropped approximately 10 ft, which has caused the evaporative concentration of salts in the pit lake (SRK, Dec. 1997).

Analysis of the anions and cations from pit water sample data collected on April 3, 1989, September 21, 1995, and July 21, 1998 indicate that even though the water quality is poor, the pit water does not exceed any livestock or wildlife standards. Figure 42 presents a Piper diagram showing that the pit water has consistently high contents of

calcium, chloride, and sulfate relative to surface water in Greyback Gulch and local groundwater.

The surface water chemistry found in the lake can be explained by:

- The inflow of neutral to alkaline groundwater has relatively low concentrations of TDS and sulfate.
- The composition of the host rock is acid buffering. The composition of the host rocks includes approximately 5 percent calcite, 30 percent feldspar, and one percent other carbonates. The dissolution of the calcite in the host rocks and the precipitation of gypsum and geothite around the pit lake indicates that acid buffering is occurring.
- There is a typical volume of disseminated pyrite in the rocks surrounding the pit lake, typically 1 to 5 percent. The pyrite is disseminated thoughout the groundmass of the host rock limiting access of water and air to allow oxidation. In addition the pyrite is coarse grained, which limits the surface area pyrite crystal, when it is exposed to oxidation (SRK, Dec. 1997).
- Low precipitation in the area is probably the most important reason for the relatively good quality of the pit lake surface water, with respect to pH and concentration of metals. Low precipitation limits the flushing of the oxidized products into the environment via runoff, seep, and discharges (Chavez, 2003).

The net effect is that while sulfide oxidation is occurring, the transport of the oxidation products is slow, except locally in the Copper Flat area.

4.1.2 Surface Water Quality, Greyback Gulch and Local Seeps

Surface water samples collected from locations along the ephemeral Greyback Gluch, SWQ-1, SWQ-2, and SWQ-3 indicate higher quality runoff upstream of the mine site (SWQ-1) than downstream (SWQ-2 and SWQ-3). Although pH measurements remain neutral to alkaline in samples collected from both upstream and downstream

00575

location (Fig. 21), TDS and sulfate concentrations are greater downstream and have increased over time (Figs. 22, 23). In SWQ-2, downstream of the mine pit, nitrate has exceeded domestic use WQCC numeric standard (10 mg/L) four times from 1981 to 1998, with a maximum nitrate concentration of was 14.5 mg/L. No numeric standard for livestock or wildlife has ever been exceeded in samples from these three locations.

The Piper diagram (Fig. 42) indicates that the downstream surface water in Greyback Gulch has higher proportions of calcium, chloride, and sulfate than upstream surface water for one set of data collected from SWQ-1, SWQ-2, and SWQ-3 in March/April 1993. The upstream surface water has a higher proportion of bicarbonate. This may indicate that some of the alkalinity upstream is being consumed by acid via neutralization as surface water move over and through the Copper Flat ore body.

Possible reasons for the lower surface water quality in the downstream sample locations in Greyback Gulch are:

- evaporative concentration of dissolved load of anions and cations,
- gypsum dissolution, which is regionally widespread,
- water-mineral interactions within the copper-porphyry deposit, and
- disturbance from the construction of roads and rock storage piles and stream diversion (SRK, Dec. 1997).

There have been a few intermittent seeps from the pit wall and rock storage piles. Typically, these seeps do not flow except following heavy precipitation. When they do flow, they are typically acidic and have high concentrations of anions, cations, and metals. Historically seeps have been identified on the southern wall of the mine pit (PW-1 and PW-2) and from the East and West waste rock piles (Fig. 11). Typically, surface

water from these seeps are characterized with pH concentrations of 2 to 3, except PW-2 with a pH of 8.16, high TDS concentrations of 5,000 to 25,000 mg/L, and high sulfate concentrations of 3,000 to 22,000 mg/L. Concentrations of surface water from these seeps have exceeded WQCC surface water livestock and wildlife numeric standards for aluminum, cadmium, copper, cobalt, selenium, and zinc. Domestic numeric standards have been exceeded for arsenic, beryllium, chromium, cadmium, nickel, and selenium. Irrigation numeric standards have been exceeded for boron, chromium, and cadmium.

4.1.3 Ground Water Quality

The pH measurements both up- and down-gradient range from approximately 7 to 8.2 (Fig. 25). TDS is less than the WQCC numeric groundwater standard of 1,000 mg/L (Fig. 26). However the groundwater down-gradient of the mine pit is increasing gradually over time and approaching the numeric standard. Sulfate concentrations also are lower than the WQCC numeric groundwater standard of 600 mg/L (Fig. 29); however, the sulfate concentrations in the down-gradient well are increasing with time.

An appropriate conceptual model of the Copper Flat mine pit lake is that of a local hydraulic sink. Figure 43 presents groundwater contours below the mine area (BLM, 1999, ABC, 1997). Historical sampling of well GWQ-5, further to the east (Fig. 10), indicate that water quality in the vicinity may have been affected naturally by the presence of the ore body prior to mining in 1982 (BLM, 1999). Concentrations of sulfate sampled in 1981 by SHB from GWQ-5 range from 477 mg/L to 575 mg/L, which is higher than the sulfate concentrations in well GWQ-96-23A immediately down-gradient of the pit (<450 mg/L). Concentrations of TDS also sampled in 1981 by SHB from

GWQ-5 range from 1,070 mg/L to 1,260 mg/L, which is higher than the TDS concentrations in the well GWQ-96-23A (<1,000 mg/L).

The Piper diagram (Fig. 42) indicates that the groundwater up gradient of the mine pit (well GWQ-96-22A and B) is high quality with relatively high proportions of chloride and sulfate. Groundwater down-gradient of the pit (GWQ-96-23A and B) shows relatively higher proportions of bicarbonate and calcium and relatively lower proportions of sulfates. Pre-Quintana mining (June 15, 1981) groundwater data collected from down-gradient wells GWQ-5 and GWQ-6 show similar anions and cation distributions to post Quintana mining activities (1996 and 1998). This indicates that groundwater quality down-gradient of the ore body reflects the natural weathering of the Copper Flat porphyry system.

4.2 Recommendations for the Mine Pit

4.2.1 Mine Pit Lake

The mine pit lake appears to be geochemically stable under existing conditions. Presently, the surface water appears to be fit for livestock and wildlife. Although the surface water does not exceed WQCC domestic or irrigation standards, it is not recommended for that use because of occasional geochemical variability from irregular, heavy precipitation. Such heavy precipitation and water level fluctuation does affect the chemistry of pit lake water; therefore, periodic monitoring of water quality is reasonable, especially because it is currently a source of water for livestock and wildlife.

4.2.2 Surface Water Quality

The surface water quality in Greyback Gulch does not exceed any WQCC numeric standards. However, nitrate has been exceeded in the past at location SWQ-2.

The quality of the surface water is lower downstream of the mine pit; however, the contributing factors to the water quality degradation is probably from naturally occurring processes such as evaporation and weathering exposure to the copper porphyry ore body. Certain re-contouring, re-vegetation, and soil amendments might improve the surface water quality in downstream reaches, but such actions are difficult to justify considering the current land use of cattle grazing and potential mineral development.

Low water quality seeps only occur during times of high precipitation. Although infiltration of rainwater might be arrested by significant restoration program of re-contouring, re-vegetation, and soil amendments, most of the documented seeps drain into the bowl-shaped mine pit lake.

4.2.3 Groundwater

Groundwater quality down-gradient of the mine pit deteriorated with respect to sulfate and TDS from 1996 to 1998; however, more time-based sampling data would be required to ascertain whether this is a real trend or transient phenomenon. Annual monitoring of monitoring wells GWQ-96-22A, GWQ-96-22B, GWQ-96-23A, GWQ-96-23B, GWQ-5, and GWQ-6 would be very useful in establishing groundwater quality trends over time. It appears from the existing data that the ore body is likely the most significant contributor to water quality down-gradient of the pit, and that additional data would be useful in evaluating this hypothesis.

4.3 Rock Storage Pile Conclusions

4.3.1 Extractable Metals From Rock Storage Pile Sample WD-1

The results of the extractable metals analysis from the rock pile sample WD-1 (Fig. 12) indicate low leachate concentrations. This sample was selected because it

00579

represents a transition material having a low field pH. Leachate concentrations would be expected to be greater than fresh, unoxidized waste rock (SRK, July 1998). The WD-1 leachate had a pH of 3, a high sulfate concentration of 3,050 mg/L, high acidity (as $CaCO_3$) of 1050 mg/L, and no alkalinity (as $CaCO_3$). WQCC surface water numeric standards for livestock and wildlife were exceeded for two metals, aluminum and copper. The concentration of aluminum was reported as 151 mg/L, which exceeds the numeric standard of 5 mg/L. The concentration of copper was reported as 13.6 mg/L, which exceeded the numeric standard of 0.5 mg/L. Both aluminum and copper exceed the numeric standard by approximately 30 times.

4.3.2 Paste pH, Acid Base Accounting, and Net Acid Generation Testing

One hundred and forty-one paste pH analyses were run on the primary lithologies about the mine site, which include quartz monzonite, quartz breccia, biotite breccia, quartz vein, and andesite. The frequency distribution of pH measurements indicates that all of the rock types except andesite have the potential to generate acidic drainage (Fig. 28).

The 32 rock samples analyzed for acid base accounting by the modified Sobek method indicated that only 5 of the samples could produce enough alkalinity to buffer their potential to generate acid (Fig. 31). The remaining 27 rock samples had the potential to generate more acid than they could neutralize (SRK, July 1998).

The NAG pH frequency distribution (Fig. 32) indicates that the majority of the 59 rock samples have the potential to generate acidic NAG pH values. This is the case for all four rock types involved, quartz monzonite (33 samples), quartz breccia (17), biotite breccia (6), and quartz vein (3).

4.3.3 Kinetic Tests

Kinetic testing was conducted on four quartz monzonite samples and a quartz breccia sample, selected from 19 rock samples collected in 1994 and considered to be representative of unoxidized waste rock exposed to weathering since 1982, highly oxidized pit wall rock, and unoxidized quartz monzonite from within the ore body. The sample locations are presented on Figure 11 and are identified as:

- samples SW-1 and LGSSP-2 were obtained from the sulfide waste rock piles,
- sample PW-2 was obtained from the pit wall in the vicinity of the former Sternberg Lode,
- samples IDC 24-222-224 and CF10-190-199 were obtained from archived drill core.

The results from all of the samples except PW-2 were neutral to alkaline ranging from 7 to 8.1 (Fig. 32). Sample PW-2 was slightly acidic with pH results ranging from 5.8 to 6.5. (SRK, July 1998; SRK, May 1995).

By week 20, the electrical conductivity of all test leachates was less than 100 μS/cm (Fig. 33). This low conductivity suggests limited leaching of metals and sulfate (SRK, July 1998; SRK, May 1995).

After 15 weeks, the sulfate concentration in the leachate from all of samples is less than 50 mg/L (Fig. 34). These results are well below the WQCC numeric groundwater standard of 600 mg/L (SRK, July 1998; SRK, May 1995).

Copper and iron concentrations decrease rapidly over the duration of the tests (Figs. 35, 36). Metal concentrations in most samples fall below the detection limits (SRK, July 1998; SRK, May 1995).

Alkalinity gradually decreases over time; however, acidity values are several times less than alkalinity and are stable over time (Fig. 37). The gradual decrease of alkalinity suggests consumption of anions during the neutralization of acid (SRK, July 1998; SRK, May 1995).

4.4 Recommendations for the Rock Storage Pile

According to the results of the paste pH, acid base accounting, and net acid generating tests, all rock types except the andesite have a significant to moderate potential to generate acid. However, the extractable metals analysis of rock pile sample WD-1 and kinetic test results suggest that sulfide oxidation products are slowly released at the Copper Flat mine site.

Additional evidence of low oxidation rates is the abundance of sulfide minerals on the waste rock pile surfaces despite exposure to weathering since 1982. Potential explanations for the low oxidation rates are:

- low precipitation limits the access of water to the sulfide minerals and the flushing of the oxidation products,
- coarse grained pyrite crystals with low surface area to volume ratios,
- disseminated pyrite within the groundmass limits the opportunity for sulfide oxidation, and
- neutral to alkaline groundwater recharge assists in acid neutralization.

The disturbed area of the existing Copper Flat mine site consists of several hundred acres. Although, five kinetic samples and one extractable metals analysis suggest that sulfide oxidation is low in this environment, six samples is not enough to be representative of this site. The current physical, mineralogical, and climatic conditions are favorable to

00582

minimize sulfide oxidation and acid rock drainage; however, wetter seasons and/or land use changes may demand more characterization and monitoring at the Copper Flat site.

4.5 Tailings Dam Conclusions

Under the existing drained conditions, the tailings appear to be geochemically stable. Eleven tailings samples collected in 1994 indicate that tailings pH varies from 6.2 to 7.8. Leachate concentrations of extractable metals from a single tailings sample are low, and WQCC numeric standards for groundwater were only exceeded for sulfate and manganese in the leachate. Sulfate has a WQCC domestic use standard of 600 mg/L, which was exceeded in the leachate sample with a concentration of 940 mg/L. Manganese has a WQCC domestic numeric standard of 0.2 mg/L. The leachate sample was found to have a manganese concentration of 1.5 mg/L. No other metals exceeded WQCC groundwater standards.

Figures 40 and 41 indicate that TDS and sulfate concentrations in groundwater sampled from a down-gradient well (NP-3) exceed the WQCC groundwater numeric standards for domestic use of 600 mg/L and 1,000 mg/L, respectively. The concentrations of sulfate and TDS are very gradually decreasing over time, but still remain above standards, 16 years after initial tailings discharge into the tailings impoundment. This information indicates that the tailings dam leaks contaminants into the groundwater, in-spite of the significant study that accompanied the impoundment design.

Figure 14 shows areas where a compacted clay liner was placed in an effort to control seepage below the impoundment through exposed brecciated basalt. The predominant minerals present in clay liner material, as determined by x-ray diffraction,

are quartz, calcite, feldspars and undifferentiated clays. The clays consist of 2/10 smectite, 6/10 mixed-layered smectite and illite, and 2/10 kaolinite.

The liner material appears to have a small clay fraction, approximately 2.5 percent, and a small sand fraction, approximately 3.4 percent. The remainder, 91.1 percent, is silt- sized particles. The material will compact into a low permeability layer with a conductivity of 10^{-6} to 10^{-8} cm/s. The clay is highly active, which is determined by dividing the percent clay by the plasticity index. Based on the plasticity indices (Table 13), the activity of the material is approximately 14. Clay is considered active if the activity is greater than 1.25 (Holtz and Kovacs, 1981). The high plasticity indices correlate with high free swell as shown by Table 16. These parameters combined with the fact that 80 percent of the clay fraction is composed of smectite and mixed layer illite and smectite raise concern with respect to the shrink and swell characteristics of the liner material. Smectite and illite are the most active clays with respect to expansion and contraction due to moisture content (Holtz and Kovacs, 1981). Figure 44 presents a relationship between liquid limit and maximum dry density with respect to swelling and collapse based on work done by the U.S. Bureau of Reclamation (Gibbs, 1969, Mitchell and Gardner, 1975, and Holtz and Kovacs, 1981). In this case, a maximum dry density of 105 pounds per cubic foot (1.7 Mega-gram per cubic meter) and a liquid limit of 50 (Table 13) would place the soil in the medium to high range for expansion. The moisture content of the clay material is unknown, although in 1994, the tailings were approximately 20 percent water at depths up to 12 ft below grade (SRK, Aug. 1994). Desiccation could occur if the clay layer dries out, which would compromise the compacted permeability.

4.6 Recommendations for the Tailings Dam

Both SHB, who designed the tailings impoundment, and SRK, who proposed re-using it, have recognized the potential leakage of the facility. SHB suggested and SRK proposed possible engineering modifications to the facility should leakage occur, which it has. SRK proposed a groundwater pump back system to hydraulically contain groundwater impacted by the tailings.

If the tailings dam is ever considered for reuse in the future, some engineering modification must be implemented to secure the impoundment. If not hydraulic containment, then a constructed liner should be considered. If the local red silt is to be considered for a liner material, additional geotechnical analyses should be performed to fully understand the shrinkage and swelling characteristics of the material and its suitability.

5.0 Summary of Conclusions

5.1 Waters

Analysis of the anions and cations from pit water indicate that even though the pit water does not exceed any WQCC numeric livestock or wildlife standards, the water is of marginal quality. The pit water has a consistently high concentration of calcium, chloride, and sulfate relative to surface water in Greyback Gulch and local groundwater. However, the pH is historically neutral to alkaline with some exceptions. Only copper has occasionally exceeded WQCC numeric standards for livestock and wildlife. The pit lake is a local hydraulic sink; therefore increases in TDS and sulfate concentrations could possibly be due to evaporation of the pit lake water concentrating soluble salts.

The surface water chemistry found in the lake can be explained by:

00585

- The inflow of neutral to alkaline groundwater has relatively low concentrations of TDS and sulfate.
- The composition of the host rock is acid buffering. The composition of the host rocks includes approximately 5 percent calcite, 30 percent feldspar, and one percent other carbonates. The dissolution of the calcite in the host rocks and the precipitation of gypsum and geothite around the pit lake indicates that acid buffering is occurring.
- There is a low volume of disseminated pyrite in the rocks surrounding the pit lake, typically 1 to 5 percent. The pyrite is disseminated thoughout the groundmass of the host rock limiting access of water and air to allow oxidation. In addition the pyrite is coarse grained, which limits the surface area pyrite crystal to oxidation, when it is exposed (SRK, Dec. 1997).
- Low precipitation in the area is probably the most important reason for the relatively good quality of the pit lake surface water, with respect to pH and concentration of metals. Low precipitation limits the flushing of the oxidized products into the environment via runoff, seep, and discharges (Chavez, 2003).

The net effect is that while sulfide oxidation is occurring, the transport of the oxidation products is slow, except locally in the Copper Flat environment.

Surface water samples collected from locations along the perennial Greyback Glulch indicate higher quality runoff upstream of the mine site than downstream. Although pH measurements remain neutral to alkaline in samples collected from both upstream and downstream location, TDS and sulfate concentrations are greater down stream and concentrations have increased over time. No numeric standard for livestock or wildlife has ever been exceeded in samples from these three locations.

The Piper diagram (Fig. 42) indicates that the downstream surface water in Greyback Gulch has higher proportions of calcium, chloride, and sulfate than upstream

surface water for one set of data collected from SWQ-1, SWQ-2, and SWQ-3 in March/April 1993. The upstream surface water has a higher proportion of bicarbonate. This may indicate that some of the alkalinity upstream is being consumed by acid neutralization as the water moves over and through the Copper Flat ore body.

Possible reasons for the lower surface water quality in the downstream sample locations in Greyback Gulch are:

- evaporative concentration of the dissolved load of anions and cations,
- gypsum dissolution, which is regionally widespread,
- water-mineral interactions within the copper-porphyry deposit, and
- disturbance from the construction of roads and rock storage piles and stream diversion (SRK, Dec. 1997).

There have been a few intermittent seeps from the pit wall and rock storage piles. Typically, these seeps do not flow except following heavy precipitation. When they do flow, they are typically acidic and have high concentrations of anions, cations, and metals. Historically seeps have been identified on the southern wall of the mine pit and from the East and West waste rock piles. Typically, surface water from these seeps are characterized with pH concentrations of 2 to 3, except PW-2 with a pH of 8.16, high TDS concentrations of 5,000 to 25,000 mg/L, and high sulfate concentrations of 3,000 to 22,000 mg/L. Concentrations of surface water from these seeps have exceeded WQCC surface water livestock and wildlife numeric standards for aluminum, cadmium, copper, cobalt, selenium, and zinc.

Groundwater pH measurements both up and down-gradient range from approximately 7 to 8.2. TDS is less than the WQCC numeric groundwater standard of 1,000 mg/L. However the groundwater down-gradient of the mine pit is increasing

gradually over time and approaching the numeric standard. Sulfate concentrations are also lower than the WQCC numeric groundwater standard of 600 mg/L; however, sulfate concentrations in the down-gradient well are increasing with time.

Historical sampling of well GWQ-5, further to the east, indicate that water quality in the vicinity may have been affected naturally by the presence of the ore body prior to mining in 1982. Concentrations of sulfate sampled in 1981 from GWQ-5 range from 477 mg/L to 575 mg/L, which is higher than the sulfate concentrations in well GWQ-96-23A immediately down-gradient of the pit (<450 mg/L). Concentrations of TDS also sampled in 1981 from GWQ-5 range from 1,070 mg/L to 1,260 mg/L, which is also higher than the TDS concentrations in the well GWQ-96-23A (<1,000 mg/L).

The groundwater up gradient of the mine pit (GWQ-9622A and B) is high quality with relatively high proportions of chloride and sulfate. Groundwater down-gradient of the pit (GWQ-96-23A and B) shows relatively higher proportions of bicarbonate and calcium and relatively lower proportions of sulfates. Pre-Quintana mining (June 15, 1981) groundwater data collected from down-gradient wells GWQ-5 and GWQ-6 show similar anions and cation distributions to post Quintana mining activities (1996 and 1998). This indicates that groundwater quality down-gradient of the ore body reflects the natural weathering of the Copper Flat porphyry system.

5.2 Stored Rock and Pit Wall Rock

According to the results of the paste pH, acid base accounting, and net acid generating tests, all rock types except the andesite have a significant to moderate potential to generate acid. However, the extractable metals analysis of rock pile sample

WD-1 and kinetic test results suggest that sulfide oxidation products are slowly released at the Copper Flat mine site.

Additional evidence of low oxidation rates is the abundance of sulfide minerals on the waste rock pile surfaces despite exposure to weathering since 1982. Potential explanations for the low oxidation rates are:

- low precipitation limits the access of water to the sulfide minerals and the flushing of the oxidation products,
- coarse grained pyrite crystals with low surface area to volume ratios,
- disseminated pyrite within the groundmass limits the opportunity for sulfide oxidation, and

neutral to alkaline groundwater recharge assists in acid neutralization.

5.3 Tailings

Under the existing drained conditions, the tailings appear to be geochemically stable. Eleven tailings samples collected in 1994 indicate that tailings pH varies from 6.2 to 7.8. Leachate concentrations of extractable metals from a single tailings sample are low, and WQCC numeric standards for groundwater were only exceeded for sulfate and manganese in the leachate. Sulfate has a WQCC domestic use standard of 600 mg/L, which was exceeded in the leachate sample with a concentration of 940 mg/L. Manganese has a WQCC domestic numeric standard of 0.2 mg/L. The leachate sample was found to have a manganese concentration of 1.5 mg/L. No other metals exceeded WQCC groundwater standards.

TDS and sulfate concentrations in groundwater sampled from a down-gradient well (NP-3) exceed the WQCC groundwater numeric standards for domestic use of 600 mg/L and 1,000 mg/L, respectively. The concentrations of sulfate and TDS are very

00589

gradually decreasing over time, but still remain above standards, 16 years after initial tailings discharge into the tailings impoundment. This information indicates that the tailings dam leaks contaminants into the groundwater, in-spite of the significant study that accompanied the impoundment design.

A compacted clay liner was placed in an effort to control seepage below the impoundment through exposed brecciated basalt. The predominant minerals present in clay liner material, as determined by x-ray diffraction, are quartz, calcite, feldspars and undifferentiated clays. The clays consist of 2/10 smectite, 6/10 mixed-layered smectite and illite, and 2/10 kaolinite.

The liner material appears to have a small clay fraction, approximately 2.5 percent, and a small sand fraction, approximately 3.4 percent. The remainder, 91.1 percent, is silt- sized particles. The material will compact into a low permeability layer with a conductivity of 0.01 to 1.0 ft/yr (10^{-6} to 10^{-8} cm/s). The clay is highly active and 80 percent of the clay fraction is composed of smectite and mixed layer illite and smectite, which raises concern with respect to the shrink and swell characteristics of the liner material. Desiccation could occur if the clay layer dries out, which would compromise the compacted permeability.

5.4 Recommendations for Further Study

Further study that could aid in the more complete understanding of the physical processes occurring at Copper Flat are:

- Periodic water quality monitoring of the waters of the pit lake since the lake is a source of water supply for local wildlife and livestock.

00590

- Periodic measurement of water level elevations of the pit lake and local precipitation so that a relationship can be developed between the quality of the pit lake waters and water level elevation and rainfall.
- Periodic observations to locate acidic seeps and determine their relationships with precipitation events, drainage water quality, and to evaluate corrective drainage control by various engineering and vegetation techniques.
- Periodic monitoring of surface and groundwater above and below the Copper Flat ore body to defend the hypothesis that the ore body is naturally contributing to the quality of waters below the mine pit area.
- Additional rock storage pile samples for extractable metals and more kinetic leachate testing of rock storage material, oxidized and unoxidized rock material is appropriate for a sit of this size. Results of previous leachate sample results are favorable with respect to release of oxidation products, but the frequency is inadequate.
- If used again, the tailings dam will require engineered alternatives to eliminate leakage of tailings liquids.
- If used for a tailings impoundment liner material, local materials should be analyzed for particle size distribution through the clay size fraction. The clay fraction should be analyzed by XRD for expansive clay content.

6.0 References

Adrian Brown Consultants, Inc., September 1996, "Tailings Dam Area Pumping Test" Prepared for Steffen, Robertson and Kirsten, Inc, Reno, Nevada, Adrian Brown Consultants, Inc., Denver, Colorado.

Alta Gold Corporation, 1995, "Copper Flat Project, Hillsboro, New Mexico," Alta Gold Corporation, Henderson, Nevada.

Bakkom, E. and Salvas, S., 1997, "Copper Flats Reclamation Plan, Phase I," Senior Thesis Presented to the Departments of Mineral and Environmental Engineering, New Mexico Institute of Mining and Technology, Socorro, New Mexico.

BLM, 1978, "Environmental Assessment Record on Quintana Minerals Corporations' Proposed Open Pit Copper Mine at Copper Flat, Sierra County, New Mexico," United States Bureau of Land Management, Las Cruces, New Mexico.

BLM, 1996, "Draft Environmental Assessment, Copper Flat Project," United States Department of the Interior, Bureau of Land Management, Las Cruces, New Mexico, Prepared by Steffen, Robertson, and Kirsten, Inc., Reno, Nevada.

BLM, March 1999, "Preliminary Final, Environmental Impact Statement, Copper Flat Project," United States Department of the Interior, Bureau of Land Management, Las Cruces, New Mexico, Prepared by ENSR, Fort Collins, Colorado.

Chavez, W.X., 2003, "Personal Communication on July 7, 2003", New Mexico Institute of Mining and Technology, Socorro, New Mexico.

Dunn, P.G., 1982, "Geology of the Copper Flat Porphyry Copper Deposit, Hillsboro, Sierra County, New Mexico," Advances in Geology of the Porphyry Copper Deposits, Southwestern North America, University of Arizona Press, Tucson, Arizona, p. 313-325.

Dunn, P.G. 1992, "Development Geology of the Copper Flat Porphyry Copper Deposit," Case Study, SME Mining Engineering Handbook, Society for Mining, Metallurgy, and Exploration, Inc., Littleton, Colorado.

Fowler, L.L., 1982, "Brecciation, Alteration, and Mineralization at the Copper Flat Porphyry Copper Deposit, Hillsboro, New Mexico," University of Arizona, Tucson.

Glover, F.A., 1977, "Environmental Assessment Report, Copper Flat Mnine Development," Fort Collins, Colorado.

Hedlund, 1985, "Economic Geology of Some Selected Mines in the Hillsboro and San Lorenzo Quadrangles, Grant and Sierra Counties, New Mexico, Open File Report, 85-0456," United States Department of the Interior, Geological Survey, Denver, Colorado.

Holtz, R. D., W. D. Kovacs, “An Introduction to Geotechnical Engineering,” Prentice Hall, Englewood Cliffs, New Jersey.

Hydro Resources, Inc., 2002, “Copper Flat,” unpublished report by Hydro Resources, Inc., Albuquerque, New Mexico.

Jones, F.A., 1904, “New Mexico Mines and Minerals,” Santa Fe, New Mexico Printing Company.

McLemore, V.T., et al., 1996, “Personal Field Notes from November 20, 1996 trip to Copper Flat, Sierra County, New Mexico” Bureau of Geology and Mineral Resources, Socorro, New Mexico.

McLemore, V.T., E.A. Munroe, M.T. Heizler, C. McKee, 1999, “Geochemistry of the Copper Flat Porphyry and Associated Deposits in the Hillsboro Mining District, Siera County, New Mexico, USA,” Journal of Geochemical Exploration (Reprint), Nepean, Ontario, Canada.

McLemore, V.T., Munroe, E.A., Heizler, M.T., McKee, C., 2000, “Geology and Evolution of the Mineral Deposits in the Hillsboro District, Sierra County, New Mexico.

McLemore, V.T., 2003, “Personal Communication,” New Mexico Bureau of Geology and Mineral Resources, Socorro, New Mexico.

Munroe, E.A., 1999, “Geology and Geochemistry of Waste Rock Piles in the Hillsboro Mining District, Sierra County, New Mexico,” MS Thesis, Department of Earth and Environmental Sciences, New Mexico Institute of Mining and Technology, Socorro, New Mexico.

Munroe, E.A. V.T. McLemore, 1999, “Waste Rock Pile Characterization, Heterogeneity, and Geochemical Anomalies in the Hillsboro, Mining District, Sierra County, New Mexico,” Journal of Geochemical Exploration (Reprint), Nepean, Ontario, Canada.

Munroe, E.A., V.T. McLemore, N.W. Dunbar, “Mine Waste Rock Pile Geochemistry and Mineralogy in Southwestern New Mexico, USA,” Proceedings from the Fifth International Conference on Acid Rock Drainage, Volume II, Society for Mining, Metallurgy, and Exploration, Inc., Littleton, Colorado.

Newcomer, R.W., 1993, “Hydrologic Assessment, Copper Flat Project, Sierra County, New Mexico,” John W. Shomaker, Inc., Albuquerque, New Mexico.

Sergent, Hauskins and Beckwith, Inc., August 29, 1980, “Letter to Milton W. Hood of Quintana Minerals Corporation Regarding Copper Flat Tailings Dam,” Sergent, Hauskins and Beckwith, Inc., Albuquerque, New Mexico.

Sergent, Hauskins and Beckwith, Inc., October 14, 1980, “Final Geotechnical and Design Development Report,” Sergent, Hauskins and Beckwith, Inc., Albuquerque, New Mexico.

Sergent, Hauskins and Beckwith, Inc., October 17, 1980, “Letter to Milton W. Hood of Quintana Minerals Corporation Regarding Copper Flat Tailings Dam and Disposal Area,” Sergent, Hauskins and Beckwith, Inc., Albuquerque, New Mexico.

Sergent, Hauskins and Beckwith, Inc., December 17, 1980, “Letter to Milton W. Hood of Quintana Minerals Corporation Regarding Copper Flat Decant System, Tailings Dam and Disposal Area,” Sergent, Hauskins and Beckwith, Inc., Albuquerque, New Mexico.

Sergent, Hauskins and Beckwith, Inc., April 13, 1981, “Letter to the New Mexico State Engineers Office Regarding Copper Flat Tailings Dam and Disposal Area,” Sergent, Hauskins and Beckwith, Inc., Albuquerque, New Mexico.

Sergent, Hauskins and Beckwith, Inc., June 29, 1981, “Letter to Milton W. Hood of Quintana Minerals Corporation Regarding Geohydrological Evaluation for Submission of Discharge Plan,” Sergent, Hauskins and Beckwith, Inc., Albuquerque, New Mexico.

Sergent, Hauskins and Beckwith, Inc., October 13, 1981, “Letter to the Maxine S. Goad, New Mexico State Environmental Improvement Board Regarding Geohydrological Evaluation for Submission of Discharge Plan,” Sergent, Hauskins and Beckwith, Inc., Albuquerque, New Mexico.

Sergent, Hauskins and Beckwith, Inc., October 28, 1981, “Letter to the Maxine S. Goad, New Mexico State Environmental Improvement Board Regarding Geohydrological Evaluation for Submission of Discharge Plan,” Sergent, Hauskins and Beckwith, Inc., Albuquerque, New Mexico.

Steffen, Robertson and Kirsten, Inc., August 1994, “Copper Flat Tailings Study, Technical Memorandum,” Steffen, Robertson and Kirsten, Inc, Reno, Nevada.

Steffen, Robertson and Kirsten, Inc., December 1994, “Characterization of Post-Closure Pit Water Quality, Copper Flat Project, Hillsboro, New Mexico” Steffen, Robertson and Kirsten, Inc, Lakewood, Colorado.

Steffen, Robertson and Kirsten, Inc., May 1995, “Copper Flat Mine, Hydrological Studies” Steffen, Robertson and Kirsten, Inc, Reno, Nevada.

Steffen, Robertson and Kirsten, Inc., February 1996, “Copper Flat Mine Permit Application” Steffen, Robertson and Kirsten, Inc, Reno, Nevada.

Steffen, Robertson and Kirsten, Inc., December 1997, “Copper Flat Mine, Compilation of Pit Lake Studies” Steffen, Robertson and Kirsten, Inc, Reno, Nevada.

Steffen, Robertson and Kirsten, Inc., June 1998, “Background Groundwater Concentrations, Technical Memorandum” Steffen, Robertson and Kirsten, Inc, Lakewood, Colorado.

Steffen, Robertson and Kirsten, Inc., July 1998, “Copper Flat Mine, Waste Rock Management Plan” Steffen, Robertson and Kirsten, Inc, Reno, Nevada.

Steffen, Robertson and Kirsten, Inc., August 1998, “Tailings Seepage Modeling, Copper Flat Mine” Steffen, Robertson and Kirsten, Inc, Lakewood, Colorado.

Summers, W.K., G.E. Schwab, 1981, “Step Pumping Test of Water Well CWQ-7, Copper Flat, New Mexico,” W.K. Summers and Associates, Inc., Socorro, New Mexico.

Water Development Corporation, 1975, “Correspondence to W.E. Seagart of Quintana Minerals Corporation,” Water Development Corporation, Tucson, Arizona.

Water Development Corporation, 1976, “Basic-Data Report, Quintana Minerals Corporation, Copper Flat Project Production Wells, Hillsboro, New Mexico,” Water Development Corporation, Tucson, Arizona.

Water Development Corporation, 1976, “Basic-Data Report, Quintana Minerals Corporation, Copper Flat Project Production Well #4, Hillsboro, New Mexico,” Water Development Corporation, Tucson, Arizona.

U.S. Army, 1965, “Laboratory Soils Testing Manual, EM 1110-2—1906,” Department of the Army, Office of the Chief Engineer.

TABLES 1-16

Table 1
Summary of Hydrothermal Alteration Associated with Mineralization in the Vicinity of Copper Flat
Copper Flat, New Mexico
(From Fowler, 1982; McLemore et al., 2000)

Host Rock/Type of Mineral Deposit	Alteration Mineral Assembly	Alteration Type
Quartz monzonite/porphyry copper deposit	Bitotite, potassium feldspar, quartz, pyrite,	Biotite-potassic
Quartz monzonite/porphyry copper deposit	Potassium feldspar, chlorite, quartz, pyrite	Potassic
Quartz monzonite/porphyry copper deposit	Sericite, quartz, pyrite	Sericitic
Andesites adjacent to latite dikes and polymetallic veins	Epidote, chlorite, sericite, pyrite, magnetite	Propylitic (1)
Andesites adjacent to latite dikes and polymetallic veins	Sericite, calcite, chlorite, quartz, pyrite.	Argillic
Andesites adjacent to latite dikes and polymetallic veins	Chlorite, kaolinite, sericite, quartz, pyrite	Propylitic (2)
Latite dikes associated with polymetallic veins	Quartz, potassium feldspar, pyrite, epidote, and chlorite	Propylitic (1)
Latite dikes associated with polymetallic veins	Quartz, sericite, chlorite, pyrite	Sericitic

Table 2
Investigative Reports Prepared for Alta Gold Corporation
Copper Flat, New Mexico

Copper Flat Tailings Study, Technical Memorandum	SRK	August 30, 1994
Characterization of Post-Closure Pit Water Quality, Copper Flat Project	SRK	December 22, 1994
Copper Flat Mine, Hydrological Studies	SRK	May 12, 1995
Copper Flat Mine Permit Application	SRK	February 20, 1996
Draft Environmental Impact Statement	BLM/SRK	February 1996
Tailings Dam Area Pumping Test	SRK/ABC	September 9, 1996
Copper Flat Mine, Compilation of Pit Lake Studies	SRK	December 1997
Background Groundwater Concentrations, Technical Memorandum	SRK	June 30, 1998
Copper Flat Mine, Waste Rock Management Plan	SRK	July 9, 1998
Tailings Seepage Modeling, Copper Flat Mine	SRK	August 7, 1998
Preliminary Final, Environmental Impact Statement, Copper Flat Project	BLM/ENSR	March 1999

Table 3
Dates and Estimated Flow Rates
For the Springs and Seeps Sampled by Newcomer et al., 1993
Copper Flat, New Mexico

Spring/Seep	Date	Flow (gpm)
SWQ-1	4/1/93	1 to 2
SWQ-1	5/7/93	Dry
SWQ-2	3/31/93	<1
SWQ-3	3/31/93	12.5
BG	4/1/93	1 to 2
BG	5/7/93	Dry
BG-2	4/1/93	<1
BG-2	5/7/93	<1
Acid Drainage	4/1/93	<1
Acid Drainage	5/7/93	<1
Acid Drainage	5/18/93	<1
Warm Spring	4/2/93	3.3

Table 4
Rock Storage Pile, Pit Wall, Drill Core, and Drill Cutting Samples
Copper Flat, New Mexico
(From SRK, May 1995)

Sample Identification	Sample Description
WD-1	West dump area, CFQM waste rock
PW-3	Pit wall, northwest of pit lake
SW-1	Sulfide waste pile, CFQM waste rock
PW-2	Pit wall, oxidized cap rock
PW-4	Pit wall, northeast of pit lake
SWP-1	Sulfide waste pile, CFQM rock
LGSSP-1	Sulfide waste pile, CFQM rock
LGSSP-2	Sulfide waste pile, CFQM rock
WD-2	West dump area, CFQM waste rock
IDC-24-222-241	CFQM from IDC-24 drill hole, 222-241 ft.
CF10-177.8-190	Andesite from CF10 drill hole, 177.8-190 ft.
CF10-177.8-190	CFQM from drill hole CF10, 190-199 ft.
CF10-214-220	CFQM from drill hole CF10, 214-220 ft.
H75-53-42	CFQM reverse circulation cuttings
H75-64-44	CFQM reverse circulation cuttings
H75-51-34	CFQM reverse circulation cuttings
H75-48-58	CFQM reverse circulation cuttings
H75-48-44	CFQM reverse circulation cuttings
PW-1	Pit wall, SW of pit, transition zone, CFQM

Table 5
Additional Sample Analysis Summary
Copper Flat, New Mexico
(From SRK, May 1995)

Sample Identification	**Analysis**
LGSSP-2	Gradation (ASTM D-422)
LGSSP-2	Atterberg Limits (ASTM D-4318)
LGSSP-2	Modified Procter compaction (ASTM (D-4318)
LGSSP-2	Hydraulic Conductivity in a fixed wall permeameter ant near maximum dry density
PW-3	Whole rock analysis (EPA 3051/ICP)
WD-1	Whole rock analysis (EPA 3051/ICP)
WD-1	Leachable metals (EPA 1312)

Table 6
Rock Storage Pile Characterization Sample Distribution
Copper Flat, New Mexico

Analysis	1994 EIS	1997 WMG	Total	Analytical Laboratory
Paste pH /Conductivity	19	0	19	SRK, Lakewood, Colorado
Paste pH /Conductivity	0	141	141	SRK, Field Parameters
Total Metals (ICP)	2	0	2	ACZ Laboratory, Steamboat Springs, Colorado
Acid-base accounting	19	0	19	ACZ Laboratory, Steamboat Springs, Colorado
Acid-base accounting	0	32	32	Sierra Environmental Monitoring Laboratory, Reno, Nevada
Net acid generating	0	59	59	School of Engineering, University College of Wales, Cardiff, UK
EPA 1312	1	0	1	ACZ Laboratory, Steamboat Springs, Colorado
Kinetic testing	5	0	5	Cominco Engineering Services Laboratory, Vancouver, BC, Canada
Physical testing	1	0	1	?

Table 7
Historical Tailings Impoundment Reports
Copper Flat, New Mexico

Report	Date	Authors	Purpose
Draft Geotechnical Investigation Report, Tailings Dam and Pond	10/14/1976	Sergent, Hauskins and Beckwith (SHB)	Geotechnical Investigation
Permeability Report on Materials Proposed for Impoundment Drains and Filters	8/29/1980	SHB	Geotechnical Investigation
Fianl Geotechnical and Design Development Report	10/14/1980	SHB	Geotechnical Investigation
Report on Filter Fabric Suitability	10/17/1980	SHB	Geotechnical Investigation
Decant System Design Recommendations	12/17/1980	SHB	Geotechnical Investigation
Comment Resolution to the New Mexico State Engineers Regarding Stress and Strain of the Dam Structure	4/13/1981	SHB	Geotechnical Investigation
Permeability, Placement, and Compaction of Clay Liner in South Cell	10/13/81	SHB	Geotechnical Investigation
Permeability, Placement, and Compaction of Clay Liner in South Cell and Monitoring Well Details for NP-5	10/28/81	SHB	Geotechnical Investigation
Hydrologic Assessment	5/1993	John W. Shomaker, Inc.	Hydrologic Assessment
Tailings Study	8/30/1994	SRK	Geological Investigation
Tailings Dam Area Pumping Test	9/9/1996	ABC/SRK	Aquifer Analysis
Tailings Seepage Modeling	8/7/1998	SRK	Hydrogeologic Conceptual Model and Seepage Modeling of Proposed Impoundment Re-use

Table 8
Whole Rock Analyses Summary
Pit Lake Sediment and Wall Rock Samples
Collected on November 20, 1996
Copper Flat, New Mexico
(From McLemore et al., 1996)

Sample ID	Sample Description	Analyses
POND03	brown precipitate	Metals by AA and ICP; Strontium by XRF
POND04	lake sediment, south pit	Metals by AA and ICP; Strontium by XRF
POND05	lake sediment, east pit	Metals by AA and ICP; Strontium by XRF
POND06	lake sediment, north pit	Metals by AA and ICP; Strontium by XRF
POND07	lake sediment, west pit	Metals by AA and ICP; Strontium by XRF
POND08	grab of pit wall, chalcocite veins	Metals by AA and ICP; Strontium by XRF
POND09	grab of pit wall, pyrite veins and disseminated	Metals by AA and ICP; Strontium by XRF
POND10	grab of pit wall, pyrite with molybdenite	Metals by AA and ICP; Strontium by XRF
POND11	select 1-2 inch chalcocite-quartz vein	Metals by AA and ICP; Strontium by XRF
POND12	grab of blue-brown precipitate from pit wall	Metals by AA and ICP; Strontium by XRF

Table 9
Summary of Surface Water Samples From
Greyback Gulch Stations A, B, C, 1977
(From BLM 1978)

Para-Meter[1]		Jan 1977			Jan 1977			Mar 1977		July 1977
Station	A	B	C	A	B	C	A	B	C	A
pH	7.7	7.6	7.8	7.8	7.7	7.8	7.9	8.0	8.1	NA[2]
EC[3]	899	1159	7226	899	1178	1212	916.3	916.3	1260	NA
TDS	720	800	840	800	800	880	1000	1080	1320	NA
Alk	317.2	280.6	262.3	305.0	292.8	268.4	240.2	220.2	220.2	NA
Hard	1660.3	2394.8	2554.4	1596.4	2203.0	2477.7	434.53	567.63	667.15	NA
N	5.48	6.8	4.9	5.6	7.5	3.68	3.8	3.3	3.6	NA
P	0.4	0.49	0.47	0.43	0.5	0.47	0.46	0.41	0.38	NA
F	0.4	0.5	0.4	0.4	0.5	0.4	0.2	0.5	0.3	NA
Cu	0.04	0.4	0.03	0.03	0.05	0.05	-0.005	-0.005	-0.005	-0.005
Ag	0.01	0.01	0.01	0.01	0.01	0.01	-0.01	-0.01	-0.01	-0.005
Mo	0.01	0.03	0.03	0.01	0.03	0.02	0.01	0.08	0.08	0.05
Zn	0.05	0.04	0.04	0.04	0.04	0.04	-0.01	0.02	0.02	0.01
Fe	0.23	0.19	0.23	0.3	0.29	0.37	0.10	0.15	0.10	0.14
Mn	0.01	0.01	0.01	0.01	0.01	0.01	-0.01	-0.01	-0.01	0.07
K	3.0	2.9	3.8	2.6	2.7	3.5	3.0	2.5	3.1	1.8
Ca	NA	NA	NA	NA	NA	NA	NA	NA	NA	168.5
Mg	NA	NA	NA	NA	NA	NA	NA	NA	NA	29.0

Notes

1. All parameters except EC are reported in milligrams per liter,
   EC – Electrical Conductivity
   TDS – Total Dissolved Solids
   Alk – Alkalinity (as $CaCO_3$)
   Hard – Hardness (as $CaCO_3$)
   N – Nitrate
   P – Phosphorous
   F – Flouride
   Cu – Copper
   Ag – Silver
   Mo – Molybdenum
   Zn – Zinc
   Fe – Iron
   Mn – Manganese
   K – Potassium
   Ca – Calcium
   Mg – Magnesium.

2. Electrical Conductivity reported in micro ohms per centimeter.
3. NA – Not Analyzed

Table 10
Extractable Metals from Rock Storage Pile Sample WD-1
(From SRK, July 1998)

Parameter	Results (mg/L)
pH	3
Conductivity	5.6 (mmhos/cm)
Sulfate	3050
Acidity (as $CaCO_3$)	1050
Alkalinity (as $CaCO_3$)	0
Aluminum	151
Antimony	N/A
Arsenic	<0.1
Barium	0.09
Boron	0.1
Cadmium	0.019
Calcium	314
Chloride	6
Chromium	0.03
Cobalt	0.29
Copper	13.6
Flouride	1.2
Iron	102
Lead	<0.021
Magnesium	23
Manganese	3.35
Mercury	<0.0002
Molybdenum	<0.01
Nickel	0.11
Potassium	4
Selenium	<0.1
Silver	<0.01
Sodium	13
Vanadium	<0.01
Zinc	0.87

Table 11
Total and Extractable Metals in Tailings Sample T-10-12
(From SRK, July, 1998)

Parameter	Total Metals in Solid (ppm)	Extractable Metals (mg/L)
Aluminum	2,700	<0.05
Antimony	<0.5	N/A
Arsenic	1.3	<0.1
Barium	52	0.10
Boron	<2	0.07
Cadmium	1.8	<0.005
Calcium	8,500	300
Chloride	N/A	6
Chromium	5	<0.01
Cobalt	13	<0.02
Copper	1600	0.03
Flouride	N/A	1.4
Iron	19,000	<0.02
Lead	15	<0.021
Magnesium	1,800	22
Manganese	251	1.5
Mercury	<0.02	<0.0002
Molybdenum	34	0.19
Nickel	3	<0.02
Potassium	1400	44
Selenium	<0.03	<0.1
Silver	<1	<0.01
Sodium	200	44
Sulfate	N/A	940
Vanadium	7	<0.01
Zinc	418	0.42

Table 12
Physical and Relational Characteristics
Copper Flat Tailings Impoundment Liner Material

Sample ID	Lithology (Visual) (ASTM, 1993)	Physical Relationship
SR-1	Sandy Clay/Silt; red; medium plastic; sand fraction fine grained, poorly graded; weakly cemented	Overlies SR-3 and underlies SR-2
SR-2	Clay/Silt; buff; non plastic; < 10 % fine sand, cemented	Overlies SR-1
SR-3	Sandy Clay/Silt; brown, highly plastic, sand fraction fine grained, poorly graded; weakly cemented	Underlies SR-1

Table 13
Summary of Geotechnical Results
Copper Flat Tailings Impoundment Liner Material
(From SHB, Oct. 1980)

Material/ Similar to Sample ID	Location	Percent Passing #200 Sieve	Liquid Limit	Plastic Index	USCS Symbol	Max. Density (lb/ft^3)	Optimum Moisture (%)	Compacted Permeability (cm/s)
Red/ SR-1	Sta. 32 Sta. 13	57	61	38	CH	103.5	19.5	NA
Red/ SR-1	Sta. 0 Sta. 10	63	61	28	MH	98.2	20.9	NA
Red/ SR-1	Clay Borrow	65	46	28	CL	105.3	19.3	NA
Red/ SR-1	Pit A 2.5-6 ft	61	45	25	CL	118.2	11.4	1.8×10^{-6}
Red/ SR-1	Pit E 2-5 ft	76	38	14	CL	104.8	15.6	2.9×10^{-7}
Red/ SR-1	Pit F 2-5	99	58	34	CH	104.7	15.3	2.1×10^{-8}
Brown/ SR-3	Boring #1, 15 ft	74	49	20	ML	NA	NA	NA
Brown/ SR-3	Boring #18, 34.5 ft	68	40	20	CL	NA	NA	NA

Table 14
Clay Mineralogy and Distribution
Of Samples SR-1 and SR-3
Copper Flat Tailings Impoundment Liner Material

Sample ID	Illite (parts in 10)	Smectite (parts in 10)	Mixed Layer (I/S) (parts in 10)	Kaolinite (Parts in 10)
SR-1 (Red)	0	2	6	2
SR-3 (Brown)	2	0	6	2

Table 15
New Mexico Water Quality Control Commission Numeric Standards
(From NMWQCC, 1995, 2001)

	Discharge to Groundwater (mg/L)[1]/ Surface Water (mg/L)[2]					
Parameter	**Human Health**	**Domestic Use**	**Irrigation Use**	**Domestic Use**	**Irrigation Use**	**Livestock/ Wildlife**
Aluminum			5.0		5.0	5.0
Antimony	0.006			0.006		
Arsenic	0.1			0.05	0.10	0.2
Barium	1.0			2.0		
Beryllium				0.004		
Boron			0.75		0.75	5.0
Cadmium	0.01			0.005	0.01	0.05
Chloride		250				
Chromium	0.05			0.1	0.1	1.0
Cobalt			0.05		0.05	1.0
Copper		1.0			0.2	0.5
Cyanide	0.2			0.2		
Fluoride	1.6					
Iron		1.0				
Lead	0.05			0.05	5.0	0.1
Manganese		0.2				
Mercury	0.002			0.002		0.01
Molyb-denum			1.0		1.0	
Nitrate (as N)	10.0			10.0		
Nickel			0.2	0.1		
‘pH		6-9				
Radium	30			5		30
Selenium	0.05			0.05	0.13(0.25)[3]	0.05
Silver	0.05					
Sulfate		600				
Thallium				0.002		
TDS		1000				
Uranite	5.0			5.0		
Vanadium					0.1	0.1
Zinc		10			2.0	25

[1] New Mexico Water Quality Control Commission, Title 20, Chapter 6, Part 2, Ground and Surface Water Protection, December, 1995, Standards for groundwater of 10,000 mg/L or less.
[2] New Mexico Water Quality Control Commission, Title 20, Chapter 6, Part 1, Water Quality Standards for Interstate Streams in New Mexico, December, 2001.
[3] In presence of >500 mg/L sulfate.

Table 16
Probable Expansion Estimated
From Classification Test Data
(from Holtz and Kovacs, 1981, after Holtz, 1959 and USBR, 1974)

Degree of Expansion	Probable Expansion as a % of the Total Volume Change (Dry to Saturated Condition)†	Colloidal Content (% −1 μm)	Plasticity Index, PI	Shrinkage Limit, SL
Very high	> 30	> 28	> 35	< 11
High	20–30	20–31	25–41	7–12
Medium	10–20	13–23	15–28	10–16
Low	< 10	< 15	< 18	> 15

FIGURES



Figure 1
Site Location Map
Copper Flat, New Mexico
(from BLM, 1978)



Figure 2
Geologic Schematic of the
Hillsboro Mining District, New Mexico
(from McLemore et al., 2000; Dunn, 1982; Hedlund, 1985)



Figure 3
Arizona-Sonora-New Mexico Porphyry Copper Belt
(from McLemore et al., 2000)

00616

Figure 4
Copper Flat Mine, 1982, View West
Copper Flat, New Mexico
(Courtesy of Hydro Resources, Inc.)

Figure 5
Copper Flat Mine, 1982, View East
Copper Flat, New Mexico
(Courtesy of Hydro Resources, Inc.)



Figure 6
Copper Flat Mills, 1982
Copper Flat, New Mexico
(from Alta Gold Corporation, 1995)

Figure 7
Copper Flat Mine Site, 1988
Copper Flat, New Mexico
(from Alta Gold Corporation, 1995)

COPPER FLAT PROJECT

FIGURE 2-5
PROPOSED DEVELOPMENT
REDUCED STRIPPING RATIO ALTERNATIVE

DIVERSION DITCH
HAUL ROAD
NORTH WASTE ROCK DISPOSAL AREA
WEST WASTE ROCK DISPOSAL AREA
ANIMAS PEAK
FRESH WATER STORAGE
EAST WASTE ROCK DISPOSAL AREA
PIT LAKE
W.L. 5442.3
(10/11/94)
PIT
TAILINGS THICKENER
HAUL ROAD
TS
SOUTH WASTE ROCK DISPOSAL AREA
PLANT AREA
PROCESS WATER RESERVOIR
ABOVE GROUND WATER LINE
GREYBACK WASH
ACCESS ROAD
TONY HOUSE
115 KV LINE
TAILINGS SLURRY PIPELINE
NORTH DECANT TOWER
TAILINGS IMPOUNDMENT
HILLSCHER HOUSE
COUNTY ROAD
SOUTH DECANT TOWER
RECLAIM RESERVOIR
CORRAL
WAREHOUSE
T15S, R6W
T15S, R7W
T15S
T16S
R7W
R6W
E 591000
E 594000
E 597000
E 600000
E 603000
N 720000
N 717000
N 714000
N 711000

LEGEND:

- EXISTING DISTURBANCE AREA
- DIVERSION
- HAUL ROAD
- PUBLIC LAND
- PRIVATE LAND
- TS — TOPSOIL STOCKPILE
- PROPOSED PROJECT DISTURBANCE BOUNDARY (REDUCED STRIPPING RATIO ALTERNATIVE)

NORTH
1000 500 0 1000
SCALE IN FEET

Figure 8
Copper Flat Mine Layout and Property Ownership
Copper Flat, New Mexico
(from BLM, 1999, after SRK)



Figure 9
Well and Spring Locations
Copper Flat, New Mexico
(from BLM, 1999, after SRK)



Figure 10
Well and Spring Locations, Pit and Tailings Impoundment Detail
Copper Flat, New Mexico
(from BLM, 1999, after SRK)



Figure 11
Pit Wall, Waste Rock, and Drill Core Locations
Copper Flat, New Mexico
(from BLM, 1999, after SRK)



KEY

8.31 ● Aquatic pH

6.8 ○ Paste pH

—5600— Contours (ft)

SOURCE: SRK (1995, 1997)

NORTH

0 1Km

Scale

COPPER FLAT PROJECT

FIGURE A2-31
PASTE AND MEASURED AQUATIC pH MAP OF WASTE ROCK, PIT LAKE AND SURFACE WATERS

Figure 12
Pit Area Paste pH Sample Locations
Copper Flat, New Mexico
(from BLM 1999, after SRK)



Figure 13
Approximate Pond Rock Sample Locations
Copper Flat, New Mexico
(Approximate Scale: 1": 500')

^
North

00626



Point No.	ΔL	Station	Azimuth (Degrees)	State Plane Coordinates North	East
1	0	0+00		710656	601660
	414.6		95.00		
2		4+15		710620	602073
	947.0		89.31		
3		13+62		710628	603020
	127.1		curve		
4		14+89		710712	603100
	3508.0		.016		
5		49+97		714220	603102
	934.1		curve		
6		59+31		715012	602700
	696.9		305.50		
7		66+28		715420	602135
	0				
8		0+00*		713035	601490
	1613.0				
9		16+13* 38+15**		713038	603101.3

* Divider Dike
** Starter Dam

REVISIONS:	TOPOGRAPHIC PLAN SHOWING LOCATION OF TEST BORINGS	
11-6-80	TAILINGS DAM CONSTRUCTION COPPER FLAT PARTNERSHIP QUINTANA MINERALS CORPORATION, MGR. HILLSBORO, NEW MEXICO	
DESIGNED BY: J.E.H.	SERGENT, HAUSKINS & BECKWITH CONSULTING SOIL AND FOUNDATION ENGINEERS	JOB NO.: SHB E80-1030
DRAWN BY: R.S.R.		SHEET: 1 OF 7
REVIEWED BY: R.D.B.		
DATE: 10-15-80		

Figure 14
Tailings Impoundment Layout and Decant Alignment Boring Locations
Copper Flat, New Mexico
(from SHB, 1980)



Figure 15
Geotechnical Soil Boring and Test Pit Locations
Copper Flat, New Mexico
(from SHB, 1980)



Figure 16
1976 Groundwater and Soil Sample Locations
Copper Flat, New Mexico
(from SHB, 1980)



Figure 17
Copper Concentrations in the Mine Pit Lake
Copper Flat, New Mexico



Figure 18
pH in the Mine Pit Lake
Copper Flat, New Mexico



Figure 19
Total Dissolved Solid Concentrations in the Mine Pit Lake
Copper Flat, New Mexico



Figure 20
Sulfate Concentration in the Mine Pit Lake
Copper Flat, New Mexico



Figure 21
pH from Greyback Gulch Surface Water
Copper Flat, New Mexico



Figure 22
TDS Concentrations from Greyback Gulch Surface Water
Copper Flat, New Mexico



Figure 23
Sulfate Concentrations from Greyback Gulch Surface Water
Copper Flat, New Mexico

Sample	Date	NaK	Ca	Mg	Fe	CO3	SO4	HCO3	Cl
		Chemical Constituents in Equivalents per Million							
SWQ-1	1/ 4/1993	4.70	5.44	2.96	0.00	0.00	5.75	5.90	0.76
SWQ-2	31/ 3/1993	12.19	21.76	6.83	0.00	0.00	30.40	4.92	3.47
SWQ-3	31/ 3/1993	11.84	22.21	8.97	0.00	0.00	32.90	5.08	3.81



Figure 24
Greyback Gulch Surface Water Stiff Diagrams
Copper Flat, New Mexico
(from Newcomer et al., 1993)



Figure 25
Groundwater pH, Mine Pit Vicinity
Copper Flat, New Mexico



Figure 26
Groundwater TDS Concentrations, Mine Pit Vicinity
Copper Flat, New Mexico



Figure 27
Groundwater Sulfate Concentrations, Mine Pit Vicinity
Copper Flat, New Mexico



Figure 28
Paste pH Distributions by Rock Type
Copper Flat, New Mexico
(from SRK, July 1998)



Figure 29
Comparison of Sobek vrs Modified Sobek Methods for
Estimating Acid Generation Potential vrs Neutralization Potential
Copper Flat, New Mexico
(from SRK, July 1998)



Figure 30
Acid Generation Potential vrs Neutralization Potential
Pit Wall and Waste Rock Samples
Copper Flat, New Mexico
(from SRK, July 1998)



Figure 31
NAG pH Frequency Distribution by Rock Type
Copper Flat, New Mexico
(from SRK, July 1998)



Figure 32
Kinetic Test, pH vrs Time
Copper Flat, New Mexico
(from SRK, July 1998)



Figure 33
Kinetic Test, Electrical Conductivity vrs Time
Copper Flat, New Mexico
(from SRK, July 1998)



Figure 34
Kinetic Test, Sulfate vrs Time
Copper Flat, New Mexico
(from SRK, July 1998)



Figure 35
Kinetic Test, Copper vrs Time
Copper Flat, New Mexico
(from SRK, July 1998)



Figure 36
Kinetic Test, Iron vrs Time
Copper Flat, New Mexico
(from SRK, July 1998)





Figure 37
Kinetic Test, Alkalinity vrs Time
Copper Flat, New Mexico
(from SRK, July 1998)



IDEALIZED GEOLOGICAL SECTION A–A' (NORTH CELL)



IDEALIZED GEOLOGICAL SECTION B–B' (SOUTH CELL)

400 200 0 400
HORIZONTAL SCALE IN FEET

100 50 0 100
VERTICAL SCALE IN FEET

STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

PROJECT NO.	DATE	REVISION
68608	01/95	A

FIGURE 7–1

IDEALIZED GEOLOGIC CROSS SECTIONS,
NORTH AND SOUTH CELLS
Copper Flat Project

Figure 38
Subsurface Cross-Section Through the North and South Cells of the Tailings Impoundment
Copper Flat, New Mexico
(from SRK, May 1995)



Figure 39
Groundwater pH, NP-3, NP-4
Copper Flat, New Mexico



Figure 40
Groundwater TDS Concentrations, NP-3, NP-4
Copper Flat, New Mexico



Figure 41
Groundwater Sulfate Concentrations, NP-3, NP-4
Copper Flat, New Mexico



Figure 42
Piper Diagram, Copper Flat Surface Water and Groundwater
Copper Flat, New Mexico
(data from BLM, 1999, after SRK)



Figure 43
Groundwater Contours Beneath the Mine Site
Copper Flat, New Mexico
(from BLM, 1999; after ABC, 1997)



Figure 44
Guide to Collapsibility, Compressibility, and Expansion
Based on Insitu Dry Density and Liquid Limit
(from Holtz and Kovacs, after Mitchell and Gardner, 1975 and Gibbs, 1969)

APPENDIX A Comprehensive Surface Water Chemistry Data

APPENDIX B

Appendix B-1
Comprehensive Groundwater Chemistry Data

Appendix B-2
Pre 1980 SHB Groundwater Sample Results

APPENDIX C Whole Rock Chemical Analyses for PW-3, WD-1, and November 20, 1996 Pond Rock Samples

APPENDIX D

Appendix D-1
Paste pH and Conductivity Data,
Acid-Base Accounting Data, and
Net Acid Generation Data

Appendix D-2
Humidity Cell Data

APPENDIX E

Appendix E-1
SHB Permeability Data

Appendix E-2
Tailings Impoundment Liner Material Hydrometer Analysis and Gradation Plot,

Appendix E-3
Geotechnical Boring Logs and
Geotechnical Analytical Data Sheets

APPENDIX F Bulk XRD and Clay Mineralogy Distribution Data Scans and Calculations

Appendix A

Comprehensive Surface Water Chemistry Data

Well Name	Date	Sampler	Notes	Lat	Long
BG-2Spring	4/1/1993	Shomaker			
BG-2 Spring	7/1/1998		15.7.26.1.1.3	32.97897	107.53876
BG-2 Spring	8/1/1998		15.7.26.1.1.3	32.97897	107.53876
BG-2 Spring	9/1/1998		15.7.26.1.1.3	32.97897	107.53876
BG Spring	4/1/1993	Shomaker			
BG Spring	7/1/1998		15.7.28.4.4.3	32.96977	107.55911
BG Spring	8/1/1998		15.7.28.4.4.3	32.96977	107.55911
BG Spring	9/1/1998		15.7.28.4.4.3	32.96977	107.55911
Casa Moya Wier	6/1/1998		15.5.27.4.4.	32.9704	107.54251
Casa Moya Wier	7/1/1998		15.5.27.4.4.	32.9704	107.54251
Casa Moya Wier	8/1/1998		15.5.27.4.4.	32.9704	107.54251
Casa Moya Wier	9/1/1998		15.5.27.4.4.	32.9704	107.54251
Danfelser Spring	1/1/1998				
Danfelser Spring	2/1/1998				
Danfelser Spring	3/1/1998				
Danfelser Spring	4/15/1998	Goff			
Danfelser Spring	5/1/1998				
Danfelser Spring	6/1/1998				
Danfelser Spring	7/22/1998	Brownfield			
Danfelser Spring	8/1/1998				
Danfelser Spring	9/1/1998				
Due South of Pit	8/1/1997				
Erwin Wier	5/1/1998		15.7.30.2.4.2.	32.97627	107.59198
Erwin Wier	6/1/1998		15.7.30.2.4.2.	32.97627	107.59198
Erwin Wier	7/1/1998		15.7.30.2.4.2.	32.97627	107.59198
Erwin Wier	8/1/1998		15.7.30.2.4.2.	32.97627	107.59198
Erwin Wier	9/1/1998		15.7.30.2.4.2.	32.97627	107.59198
Greyback Station A	1/77	BLM	where Greyback enters QMC property		
Greyback Station A	1/77	BLM	where Greyback enters QMC property		
Greyback Station B	1/77	BLM	In greyback, 300 yards east of mine rim		
Greyback Station B	1/77	BLM	In greyback, 300 yards east of mine rim		
Greyback Station C	1/77	BLM	where Greyback leaves QMC property		
Greyback Station C	1/77	BLM	where Greyback leaves QMC property		
Greyback Station A	3/77	BLM	where Greyback enters QMC property		
Greyback Station B	3/77	BLM	In greyback, 300 yards east of mine rim		
Greyback Station C	3/77	BLM	where Greyback leaves QMC property		

Well Name	Date	Sampler	Notes	Lat	Long
Greyback Station B	7/77	BLM	In greyback, 300 yards east of mine rim		
Greyback	5/17/1982	QMC			
Greyback	2/11/1991	FTS/GE	W/mine site Greyback SHB 5		
Greyback	2/11/1991	FTS/GE	West of pit, ds Greyback SHB 2		
Greyback	2/11/1991	FTS/GE	E of GWQ-4, SHB 1	32.96599	107.54639
Greyback Outfall	8/1/1995				
Greyback Outfall	9/21/1995				
Greyback Wash	3/1/1997				
Humphries Wier	6/1/1998		15.6.24.31.1		
Humphries Wier	7/1/1998		15.6.24.31.1		
Humphries Wier	8/1/1998		15.6.24.31.1		
Humphries Wier	9/1/1998		15.6.24.31.1		
Las Animas Creek	10/1/1997		exact date not known		
Las Animas Creek	4/15/1998	Goff	LA Ck. At road crossing at Irwins		
Las Animas Creek	10/22/1998	Goff			
Las Animas/Seco Creek	7/31/1974		15.5.22.122		
Las Animas/Seco Creek	7/12/1974		15.5.27.333		
Las Animas/Seco Creek	5/7/1974		15.5.27.413		
Las Animas/Seco Creek	7/11/1974		15.5.27.442		
Las Animas/Seco Creek	7/11/1974		15.5.27.443		
Las Animas/Seco Creek	5/7/1974		15.5.29.424		
Las Animas/Seco Creek	7/9/1974		15.5.30.213		
Las Animas/Seco Creek	1/1/2001		LAC-1		
Las Animas/Seco Creek	11/16/1994		MW-9		
Las Animas/Seco Creek	11/16/1994		MW-10		
Las Animas/Seco Creek	11/16/1994		MW-11		
Left Side of Haul Road	8/1/1997		exact date not known		
Pit Lake	4/3/1989	EID	Dipped		
Pit Lake	4/3/1989	EID	Dipped, near the drive down to lake		
Pit Lake	11/14/1990	GE			
Pit Lake	2/11/1991	FTS/GE	5' down, SHB 4		
Pit Lake	2/11/1991	FTS/GE	25' down, SHB 3		
Pit Lake	7/19/1991	MT/GE			
Pit Lake	8/29/1991	BI/GE			
Pit Lake	11/26/1991	MH/GE			
Pit Lake	3/15/1992	BI/GE			

Well Name	Date	Sampler	Notes	Lat	Long
Pit Lake	3/15/1992	BI/GE			
Pit Lake	5/25/1992	BI/GE			
Pit Lake	7/16/1992	BI/GE			
Pit Lake	10/8/1992	BI/GE			
Pit Lake	11/27/1992	MH/GE			
Pit Lake	12/15/1992	BI/GE			
Pit Lake	2/12/1993	Shomaker			
Pit Lake	2/25/1993	BI/GE			
Pit Lake	9/28/1993	BI/GE			
Pit Lake	3/17/1994	BI/GE			
Pit Lake	5/24/1994	SRK	NLP8M-North Edge of Pit Lake, Sample at 8 meters, N elev		
Pit Lake	5/24/1994	SRK	SLP3M-South Edge of Pit lake, Sample at 3 meters , N elev		
Pit Lake	5/24/1994	SRK	SPL5M-South Edge of Pit Lake, Sample at 5 meters, N elev		
Pit Lake	5/24/1994	SRK	NLP3M-North Edge of Pit Lake, Sampled at 3 meters, N ele		
Pit Lake	9/22/1994	BI/GE	Sample loss - no sulfate analysis		
Pit Lake	11/16/1994	SRK	Samle at 3 meters		
Pit Lake	11/16/1994	SRK	Sample at 7 meters		
Pit Lake	12/12/1994	ABC	N elevated due to TDS		
Pit Lake	12/19/1994	ABC	N elevated due to TDS		
Pit Lake	1/29/1995	BI/GE			
Pit Lake	3/29/1995	BI/GE			
Pit Lake	6/27/1995	BI/GE			
Pit Lake	8/1/1995	UKN			
Pit Lake	8/1/1995		Duplicate		
Pit Lake	9/21/1995				
Pit Lake	9/21/1995	BI/GE			
Pit Lake	1/10/1996	BI/GE			
Pit Lake	4/3/1996	BI/GE			
Pit Lake	6/1/1996		exact date not known		
Pit Lake	9/25/1996	BI/GE			
Pit Lake	11/15/1996	Bakkom/Salvas	North Shore		
Pit Lake	11/15/1996	Bakkom/Salvas	South Shore		
Pit Lake	11/15/1996	Bakkom/Salvas	East Shore		
Pit Lake	11/15/1996	Bakkom/Salvas	West Shore		
Pit Lake	1/15/1997	BI/GE			
Pit Lake	1/18/1997	Bakkom/Salvas	North Shore		

Well Name	Date	Sampler	Notes	Lat	Long
Pit Lake	1/18/1997	Bakkom/Salvas	South Shore		
Pit Lake	1/18/1997	Bakkom/Salvas	East Shore		
Pit Lake	1/18/1997	Bakkom/Salvas	West Shore		
Pit Lake	7/1/1997		exact date not known		
Pit Lake	7/16/1997	Bakkom/Salvas	North Shore		
Pit Lake	7/16/1997	Bakkom/Salvas	South Shore		
Pit Lake	7/16/1997	Bakkom/Salvas	East Shore		
Pit Lake	7/16/1997	Bakkom/Salvas	West Shore		
Pit Lake	8/1/1997	SRK	exact date not known		
Pit Lake	10/1/1997		Duplicate		
Pit Lake	10/8/1997	Bakkom/Salvas	North Shore		
Pit Lake	10/8/1997	Bakkom/Salvas	South Shore		
Pit Lake	10/8/1997	Bakkom/Salvas	East Shore		
Pit Lake	10/8/1997	Bakkom/Salvas	West Shore		
Pit Lake	1/15/1998	BI			
Pit Lake	1/24/1998	Goff			
Pit Lake	2/1/1998				
Pit Lake	3/1/1998				
Pit Lake	4/9/1998	BI			
Pit Lake	5/1/1998				
Pit Lake	6/1/1998				
Pit Lake	7/13/1998	BI			
Pit Lake	7/21/1998	Brownfield			
Pit Lake	8/1/1998				
Pit Lake	9/1/1998				
Pit Lake	10/15/1998	Goff			
Pit Lake	10/1/1997		exact date not known		
PP	8/9/1997	SRK	Stagnant Water near Petroglyph		
PW-1	8/8/1997	SRK	Seep in NW corner of pit		
PW-1	8/9/1997	SRK	Seep in NW corner of pit		
PW-2	8/9/1997	SRK	Seep in SW corner of pit		
Seep	5/17/1982	QMC			
Seep	9/2/1982	EID			
Seep	12/23/1982	QMC			
Seep	2/21/1983	QMC			
Acid Rock Drianage	5/7/1993	Shomaker			

Bold exceeds livestock/wildlife standard
underline exceeds domestic standard
itlaic exceeds irrigation standard

Well Name	Date	North	East	Flow Rate	Filtered?	pH	Sp. Cond.	TDS	SO4	Bicarbonate
BG-2Spring	4/1/1993					8.2	1090	690	184	535
BG-2 Spring	7/1/1998	262745	3651627	0						
BG-2 Spring	8/1/1998	262745	3651627	0						
BG-2 Spring	9/1/1998	262745	3651627	0						
BG Spring	4/1/1993					8	1030	680	228	411
BG Spring	7/1/1998	260819	3650652	0						
BG Spring	8/1/1998	260819	3650652	0						
BG Spring	9/1/1998	260819	3650652	0						
Casa Moya Wier	6/1/1998	262372	3650684	0						
Casa Moya Wier	7/1/1998	262372	3650684	0						
Casa Moya Wier	8/1/1998	262372	3650684	0						
Casa Moya Wier	9/1/1998	262372	3650684	0						
Danfelser Spring	1/1/1998			26						
Danfelser Spring	2/1/1998			25.25						
Danfelser Spring	3/1/1998			21.25						
Danfelser Spring	4/15/1998			22.7	TRUE	7.66	405	241	33	
Danfelser Spring	5/1/1998			18						
Danfelser Spring	6/1/1998			13.6						
Danfelser Spring	7/22/1998			1.2	TRUE			257	32	
Danfelser Spring	8/1/1998			7.25						
Danfelser Spring	9/1/1998			10.8						
Due South of Pit	8/1/1997				TRUE	8.03		5710		
Erwin Wier	5/1/1998	257763	3651448	193						
Erwin Wier	6/1/1998	257763	3651448	38						
Erwin Wier	7/1/1998	257763	3651448	0						
Erwin Wier	8/1/1998	257763	3651448	367						
Erwin Wier	9/1/1998	257763	3651448	0						
Greyback Station A	1/77					7.7		720		
Greyback Station A	1/77					7.8		800		
Greyback Station B	1/77					7.6		800		
Greyback Station B	1/77					7.7		800		
Greyback Station C	1/77					7.8		840		
Greyback Station C	1/77					7.8		880		
Greyback Station A	3/77					7.9		1000		
Greyback Station B	3/77					8		1080		
Greyback Station C	3/77					8.1		1320		

Well Name	Date	North	East	Flow Rate	Filtered?	pH	Sp. Cond.	TDS	SO4	Bicarbonate
Greyback Station B	7/77									
Greyback	5/17/1982				TRUE	8.3		670	300	
Greyback	2/11/1991					7.83	1504	966	391.8	370
Greyback	2/11/1991					7.51	3380	2178	1510.6	314.8
Greyback	2/11/1991	261998	3650205			7.9	3190	2112	1248.2	338
Greyback Outfall	8/1/1995				TRUE	7.61		3450	1730	620
Greyback Outfall	9/21/1995				TRUE	7.61	3860	3450	1730	620
Greyback Wash	3/1/1997				TRUE	8.08		3200	1930	349
Humphries Wier	6/1/1998			0						
Humphries Wier	7/1/1998			0						
Humphries Wier	8/1/1998			0						
Humphries Wier	9/1/1998			0						
Las Animas Creek	10/1/1997				TRUE	8.31		238	16.6	
Las Animas Creek	4/15/1998				TRUE	8.09	260	190	12	127
Las Animas Creek	10/22/1998				TRUE	8.31	527	238	16.6	
Las Animas/Seco Creek	7/31/1974					8			49	
Las Animas/Seco Creek	7/12/1974					8			16	
Las Animas/Seco Creek	5/7/1974					8			61	
Las Animas/Seco Creek	7/11/1974					8			48	
Las Animas/Seco Creek	7/11/1974					8			25	
Las Animas/Seco Creek	5/7/1974					8.2			13	
Las Animas/Seco Creek	7/9/1974					7.9			29	
Las Animas/Seco Creek	1/1/2001					7.81		300	18	
Las Animas/Seco Creek	11/16/1994					8.11		190	12	
Las Animas/Seco Creek	11/16/1994					7.84		310	25	
Las Animas/Seco Creek	11/16/1994					7.79		314	21	
Left Side of Haul Road	8/1/1997				TRUE	7.91		217		
Pit Lake	4/3/1989				TRUE					
Pit Lake	4/3/1989				TRUE			3546	2240	96.4
Pit Lake	11/14/1990							4064	2770	
Pit Lake	2/11/1991					7.14	3980	2711	2437	54.9
Pit Lake	2/11/1991					7.2	3980	2704	2464	45.1
Pit Lake	7/19/1991					7.76	6340	4520	2920	87.9
Pit Lake	8/29/1991					7.61		4384	2674.2	
Pit Lake	11/26/1991					7.61		4175	2540	
Pit Lake	3/15/1992				TRUE	4.88		3819	2857	

Well Name	Date	North	East	Flow Rate	Filtered?	pH	Sp. Cond.	TDS	SO4	Bicarbonate
Pit Lake	3/15/1992				TRUE	4.88		3819	2857	
Pit Lake	5/25/1992				TRUE	4.82		3846	2665	
Pit Lake	7/16/1992				TRUE	4.36		4229	2397	
Pit Lake	10/8/1992				TRUE	4.85		4258	2706	
Pit Lake	11/27/1992					6.26		3900	2499.5	
Pit Lake	12/15/1992				TRUE	6.04		4151	2902	
Pit Lake	2/12/1993					5.6	3893	3776	2390	7
Pit Lake	2/25/1993				TRUE	6.29		3951	2748	
Pit Lake	9/28/1993				TRUE	6.71		4468	1566	
Pit Lake	3/17/1994				TRUE	7.46		3179	2670	
Pit Lake	5/24/1994				TRUE	7.68	4030	4340	71	550
Pit Lake	5/24/1994				TRUE	7.89	4310	4010	2800	73
Pit Lake	5/24/1994				TRUE	7.85	4320	3900	2700	68
Pit Lake	5/24/1994				TRUE	7.8	4170	4510	2700	72
Pit Lake	9/22/1994				TRUE	8.04		5124		
Pit Lake	11/16/1994					7.52	4690	4380	104	550
Pit Lake	11/16/1994					7.71	4720	4600	2910	102
Pit Lake	12/12/1994				TRUE	7.71	4720	4600	2910	102
Pit Lake	12/19/1994				TRUE	7.52	4690	4380	2970	104
Pit Lake	1/29/1995				TRUE	7.69		4675	2906	
Pit Lake	3/29/1995				TRUE	7.53		4891	2609.5	
Pit Lake	6/27/1995				TRUE			5604	2923.8	
Pit Lake	8/1/1995				TRUE	7.8		5846	4312	
Pit Lake	8/1/1995				TRUE	7.76		5651	2861	
Pit Lake	9/21/1995				TRUE	8.31	5230	5230	3170	122
Pit Lake	9/21/1995				TRUE	8.11		5642	3603.4	
Pit Lake	1/10/1996				TRUE	7.9		5398	3452.1	
Pit Lake	4/3/1996				TRUE	7.95		5378	3304.4	
Pit Lake	6/1/1996				TRUE	8.51		6095	2969	
Pit Lake	9/25/1996				TRUE	8.26		6041	3290	
Pit Lake	11/15/1996					8.15				
Pit Lake	11/15/1996					8.07				
Pit Lake	11/15/1996					8.06				
Pit Lake	11/15/1996					8.09				
Pit Lake	1/15/1997				TRUE	8.05		5772	3509	
Pit Lake	1/18/1997					8.01				

Well Name	Date	North	East	Flow Rate	Filtered?	pH	Sp. Cond.	TDS	SO4	Bicarbonate
Pit Lake	1/18/1997					8.05				
Pit Lake	1/18/1997					8.22				
Pit Lake	1/18/1997					8.04				
Pit Lake	7/1/1997				TRUE	7.45		5905	3017	
Pit Lake	7/16/1997					8.07				
Pit Lake	7/16/1997					8.12				
Pit Lake	7/16/1997					8.09				
Pit Lake	7/16/1997					8.01				
Pit Lake	8/1/1997					8.16	5530	5020	3100	172
Pit Lake	10/1/1997				TRUE	7.67		5651	2861	
Pit Lake	10/8/1997					7.96				
Pit Lake	10/8/1997					8.02				
Pit Lake	10/8/1997					7.87				
Pit Lake	10/8/1997					7.85				
Pit Lake	1/15/1998				TRUE	7.84	6920	5376	2981	
Pit Lake	1/24/1998			5437.48	TRUE	7.93	5720	5334	3946	201.9
Pit Lake	2/1/1998			5437.18						
Pit Lake	3/1/1998			5437.13						
Pit Lake	4/9/1998			5436.67	TRUE		5700	5422	3430	
Pit Lake	5/1/1998			5436.15						
Pit Lake	6/1/1998			5436.8						
Pit Lake	7/13/1998			5435.06	TRUE		7040	5956	3909	
Pit Lake	7/21/1998				TRUE			5952	3808	181
Pit Lake	8/1/1998			5434.72						
Pit Lake	9/1/1998			5435.09						
Pit Lake	10/15/1998				TRUE	7.8	7500	5846	4312	
Pit Lake	10/1/1997				TRUE	7.8		5846	4312	
PP	8/9/1997				TRUE	8.89	237	230	5.1	126
PW-1	8/8/1997				TRUE	2.64				
PW-1	8/9/1997				TRUE					
PW-2	8/9/1997				TRUE	8.16	5530	5020	3100	172
Seep	5/17/1982				TRUE	7.8		790	430	
Seep	9/2/1982				TRUE	7.5	1290	1010	525	219
Seep	12/23/1982				TRUE	8.3		1110	530	
Seep	2/21/1983					8.1		1130	517	
Acid Rock Drianage	5/7/1993					1.9		17020	10000	-1

Well Name	Date	Calcium(Ca)	Cl	Flouride(F)	Nitrate (NO_3)	Sodium(Na)	Potassium(K)	Aluminum(Al)
BG-2Spring	4/1/1993	49	15	0.82	0	124	1.1	-0.1
BG-2 Spring	7/1/1998							
BG-2 Spring	8/1/1998							
BG-2 Spring	9/1/1998							
BG Spring	4/1/1993	45	13	0.86	0	90	0.8	-0.1
BG Spring	7/1/1998							
BG Spring	8/1/1998							
BG Spring	9/1/1998							
Casa Moya Wier	6/1/1998							
Casa Moya Wier	7/1/1998							
Casa Moya Wier	8/1/1998							
Casa Moya Wier	9/1/1998							
Danfelser Spring	1/1/1998							
Danfelser Spring	2/1/1998							
Danfelser Spring	3/1/1998							
Danfelser Spring	4/15/1998	42.2	4.4	0.71	0.78	33.9	1.3	
Danfelser Spring	5/1/1998							
Danfelser Spring	6/1/1998							
Danfelser Spring	7/22/1998	40.7	4.8	0.7	0.83	32.5	2.5	
Danfelser Spring	8/1/1998							
Danfelser Spring	9/1/1998							
Due South of Pit	8/1/1997		232.8	10.3				
Erwin Wier	5/1/1998							
Erwin Wier	6/1/1998							
Erwin Wier	7/1/1998							
Erwin Wier	8/1/1998							
Erwin Wier	9/1/1998							
Greyback Station A	1/77			0.4	5.48		3	
Greyback Station A	1/77			0.4	5.6		2.6	
Greyback Station B	1/77			0.5	6.8		2.9	
Greyback Station B	1/77			0.5	7.5		2.7	
Greyback Station C	1/77			0.4	4.9		3.8	
Greyback Station C	1/77			0.4	3.68		3.5	
Greyback Station A	3/77			0.2	3.8		3	
Greyback Station B	3/77			0.5	3.3		2.5	
Greyback Station C	3/77			0.3	3.6		3.1	

Well Name	Date	Calcium(Ca)	Cl	Flouride(F)	Nitrate (NO_3)	Sodium(Na)	Potassium(K)	Aluminum(Al)
Greyback Station B	7/77	168.5					8.9	
Greyback	5/17/1982		46	1.2	0.3			
Greyback	2/11/1991	147.8	59.3	0.69	1.7	128.0	2.0	
Greyback	2/11/1991	443	160.9	0.56	22.0	226.5	5.5	
Greyback	2/11/1991	363.5	129.1	0.89	15.78	230.2	5.9	
Greyback Outfall	8/1/1995	490	94	1.4	6.2	360	2.1	0.033
Greyback Outfall	9/21/1995	490	94	1.4	6.2	360	2.1	0.033
Greyback Wash	3/1/1997		180	0.93	-5			
Humphries Wier	6/1/1998							
Humphries Wier	7/1/1998							
Humphries Wier	8/1/1998							
Humphries Wier	9/1/1998							
Las Animas Creek	10/1/1997		14.9		0.1			
Las Animas Creek	4/15/1998	35.9	9.3	0.46	-0.05	15.6	0.8	
Las Animas Creek	10/22/1998		14.9		0.1			
Las Animas/Seco Creek	7/31/1974	89	330	0.9	0.7	170	9.6	
Las Animas/Seco Creek	7/12/1974	22	26	0.6	0.6	46	4.9	
Las Animas/Seco Creek	5/7/1974		110	420	0.5	180	11.0	
Las Animas/Seco Creek	7/11/1974	85	380	0.7	0.6	200	9.1	
Las Animas/Seco Creek	7/11/1974	38	120	0.7	0.4	80	6.5	
Las Animas/Seco Creek	5/7/1974	43	16	0.4	0.1	46	3.1	
Las Animas/Seco Creek	7/9/1974	75	15	0.5	0.1	32	2.4	
Las Animas/Seco Creek	1/1/2001	72	15	0.46	-1.0	21	1.9	-0.05
Las Animas/Seco Creek	11/16/1994	12	12	1.4	-1.0	54	2.3	-0.05
Las Animas/Seco Creek	11/16/1994	59	14	0.43	-1.0	29	1.9	-0.05
Las Animas/Seco Creek	11/16/1994	63	15	0.45	-1.0	23	1.5	-0.05
Left Side of Haul Road	8/1/1997		4.1	0.96				
Pit Lake	4/3/1989	570						-0.1
Pit Lake	4/3/1989	640	47.3			165	11	
Pit Lake	11/14/1990		102.2					
Pit Lake	2/11/1991	600	79.8	4.58	0.10	223.6	16.4	
Pit Lake	2/11/1991	611.2	82.5	4.77	0.10	223.5	16.4	
Pit Lake	7/19/1991	684.1	88.6	6.25	0.03	248.0	20.3	
Pit Lake	8/29/1991		88.9					
Pit Lake	11/26/1991		86.6					
Pit Lake	3/15/1992		85.3					

Well Name	Date	Calcium(Ca)	Cl	Flouride(F)	Nitrate (NO_3)	Sodium(Na)	Potassium(K)	Aluminum(Al)
Pit Lake	3/15/1992		85.3					
Pit Lake	5/25/1992		89.7					
Pit Lake	7/16/1992		76.1					
Pit Lake	10/8/1992		90.1					
Pit Lake	11/27/1992		730.5					
Pit Lake	12/15/1992		88.5					
Pit Lake	2/12/1993	583	96	6.21		222	10	2
Pit Lake	2/25/1993		92.1					
Pit Lake	9/28/1993		111.2					
Pit Lake	3/17/1994		101.4					
Pit Lake	5/24/1994	100	7		-5	270	15	0.20
Pit Lake	5/24/1994	560	110	7.3	-5	270	15	0.18
Pit Lake	5/24/1994	540	110	7.2	-5	270	15	0.18
Pit Lake	5/24/1994	650	110	7.3	-5	290	16	0.19
Pit Lake	9/22/1994		140.9					
Pit Lake	11/16/1994	130	8.1		-5	320	18	-0.05
Pit Lake	11/16/1994	580	140		-5	350	17	-0.05
Pit Lake	12/12/1994	580	140	8.1	-5	350	17	-0.05
Pit Lake	12/19/1994	550	130	8.1	-5	320	18	-0.05
Pit Lake	1/29/1995		217.6					
Pit Lake	3/29/1995		108.6					
Pit Lake	6/27/1995		161.4					
Pit Lake	8/1/1995		237		-0.05			0.13
Pit Lake	8/1/1995		219					
Pit Lake	9/21/1995	620	150	10	-5	430	21	0.13
Pit Lake	9/21/1995		172.3					
Pit Lake	1/10/1996		182.8					
Pit Lake	4/3/1996		188.9					
Pit Lake	6/1/1996		210.6					
Pit Lake	9/25/1996		199.6					
Pit Lake	11/15/1996							
Pit Lake	11/15/1996							
Pit Lake	11/15/1996							
Pit Lake	11/15/1996							
Pit Lake	1/15/1997		216					
Pit Lake	1/18/1997							

Well Name	Date	Calcium(Ca)	Cl	Flouride(F)	Nitrate (NO_3)	Sodium(Na)	Potassium(K)	Aluminum(Al)
Pit Lake	1/18/1997							
Pit Lake	1/18/1997							
Pit Lake	1/18/1997							
Pit Lake	7/1/1997		228					
Pit Lake	7/16/1997							
Pit Lake	7/16/1997							
Pit Lake	7/16/1997							
Pit Lake	7/16/1997							
Pit Lake	8/1/1997	440	190	11	-3	410	20	0.14
Pit Lake	10/1/1997		219					
Pit Lake	10/8/1997							
Pit Lake	10/8/1997							
Pit Lake	10/8/1997							
Pit Lake	10/8/1997							
Pit Lake	1/15/1998		216	11.8	-0.05			
Pit Lake	1/24/1998	615.6	224	10.8		524.3	33.6	
Pit Lake	2/1/1998							
Pit Lake	3/1/1998							
Pit Lake	4/9/1998		222	12.4	-0.05			
Pit Lake	5/1/1998							
Pit Lake	6/1/1998							
Pit Lake	7/13/1998		245	12.85	-0.05			
Pit Lake	7/21/1998	638.3	244	13.6	-0.05	516.8	20.6	
Pit Lake	8/1/1998							
Pit Lake	9/1/1998							
Pit Lake	10/15/1998		237		-0.05			
Pit Lake	10/1/1997		237		-0.05			
PP	8/9/1997	30	1.8	0.37	-1	15	4.7	0.037
PW-1	8/8/1997				-1	10	-1	**410**
PW-1	8/9/1997							**640**
PW-2	8/9/1997	440	190	11	-3	410	20	0.14
Seep	5/17/1982		54	2.1	1.4			
Seep	9/2/1982	160.8	59.96	2.75	0.24	120		
Seep	12/23/1982		54	1.6	1.5			
Seep	2/21/1983		54	1.7	0.9			
Acid Rock Drianage	5/7/1993	446	35	11.1	0.9	93	3.1	**3720**

Well Name	Date	Arsenic(As)	Silver(Ag)	Boron(B)	Berrylium(Be)	Barium(Ba)	Cadmium(Cd)	Chromium(Cr)
BG-2Spring	4/1/1993	-0.005	-0.01	0.03		0.6	-0.002	-0.02
BG-2 Spring	7/1/1998							
BG-2 Spring	8/1/1998							
BG-2 Spring	9/1/1998							
BG Spring	4/1/1993	-0.005	-0.01	0.02		1.2	-0.002	-0.02
BG Spring	7/1/1998							
BG Spring	8/1/1998							
BG Spring	9/1/1998							
Casa Moya Wier	6/1/1998							
Casa Moya Wier	7/1/1998							
Casa Moya Wier	8/1/1998							
Casa Moya Wier	9/1/1998							
Danfelser Spring	1/1/1998							
Danfelser Spring	2/1/1998							
Danfelser Spring	3/1/1998							
Danfelser Spring	4/15/1998							
Danfelser Spring	5/1/1998							
Danfelser Spring	6/1/1998							
Danfelser Spring	7/22/1998							
Danfelser Spring	8/1/1998							
Danfelser Spring	9/1/1998							
Due South of Pit	8/1/1997							
Erwin Wier	5/1/1998							
Erwin Wier	6/1/1998							
Erwin Wier	7/1/1998							
Erwin Wier	8/1/1998							
Erwin Wier	9/1/1998							
Greyback Station A	1/77		0.01					
Greyback Station A	1/77		0.01					
Greyback Station B	1/77		0.01					
Greyback Station B	1/77		0.01					
Greyback Station C	1/77		0.01					
Greyback Station C	1/77		0.01					
Greyback Station A	3/77		0.01					
Greyback Station B	3/77		-0.01					
Greyback Station C	3/77		-0.01					

Well Name	Date	Arsenic(As)	Silver(Ag)	Boron(B)	Berrylium(Be)	Barium(Ba)	Cadmium(Cd)	Chromium(Cr)
Greyback Station B	7/77		-0.005					
Greyback	5/17/1982						-0.005	
Greyback	2/11/1991		0.04			0.04	*0.043*	*0.1*
Greyback	2/11/1991		-0.02			0.03	*0.015*	-0.02
Greyback	2/11/1991		-0.02			0.03	*0.015*	-0.02
Greyback Outfall	8/1/1995		-0.025			-0.05	-0.0025	-0.025
Greyback Outfall	9/21/1995		-0.025	-0.1	-0.002	-0.05	-0.0025	-0.025
Greyback Wash	3/1/1997							-0.025
Humphries Wier	6/1/1998							
Humphries Wier	7/1/1998							
Humphries Wier	8/1/1998							
Humphries Wier	9/1/1998							
Las Animas Creek	10/1/1997							-0.005
Las Animas Creek	4/15/1998							-0.005
Las Animas Creek	10/22/1998							-0.005
Las Animas/Seco Creek	7/31/1974							
Las Animas/Seco Creek	7/12/1974							
Las Animas/Seco Creek	5/7/1974			0.12				
Las Animas/Seco Creek	7/11/1974							
Las Animas/Seco Creek	7/11/1974							
Las Animas/Seco Creek	5/7/1974							
Las Animas/Seco Creek	7/9/1974							
Las Animas/Seco Creek	1/1/2001		-0.03	-0.10		-0.1	-0.001	-0.03
Las Animas/Seco Creek	11/16/1994		-0.03	-0.10		-0.1	-0.005	-0.03
Las Animas/Seco Creek	11/16/1994		-0.03	-0.10		-0.1	-0.005	-0.03
Las Animas/Seco Creek	11/16/1994		-0.03	-0.10		-0.1	-0.005	-0.03
Left Side of Haul Road	8/1/1997							
Pit Lake	4/3/1989		-0.1	-0.1	-0.1	-0.1	-0.1	-0.1
Pit Lake	4/3/1989							
Pit Lake	11/14/1990							
Pit Lake	2/11/1991		0.03			-0.01	0.035	0.06
Pit Lake	2/11/1991		-0.02			-0.01	0.015	-0.02
Pit Lake	7/19/1991		-0.02			-0.01	-0.005	-0.02
Pit Lake	8/29/1991							
Pit Lake	11/26/1991							
Pit Lake	3/15/1992							

Well Name	Date	Arsenic(As)	Silver(Ag)	Boron(B)	Berrylium(Be)	Barium(Ba)	Cadmium(Cd)	Chromium(Cr)
Pit Lake	3/15/1992							
Pit Lake	5/25/1992							
Pit Lake	7/16/1992							
Pit Lake	10/8/1992							
Pit Lake	11/27/1992							
Pit Lake	12/15/1992							
Pit Lake	2/12/1993		-0.1	-0.1		-0.1	-0.1	-0.1
Pit Lake	2/25/1993							
Pit Lake	9/28/1993							
Pit Lake	3/17/1994							
Pit Lake	5/24/1994		-0.025	-0.1		-0.01	0.021	-0.025
Pit Lake	5/24/1994		-0.025	-0.1		-0.01	0.021	-0.025
Pit Lake	5/24/1994		-0.025	-0.1		-0.01	0.021	-0.025
Pit Lake	5/24/1994		-0.025	-0.1		-0.01	0.017	-0.025
Pit Lake	9/22/1994							
Pit Lake	11/16/1994		-0.025	-0.1	-0.002	-0.01	0.017	*0.2*
Pit Lake	11/16/1994		-0.025	-0.1	-0.002	-0.01	0.017	-0.025
Pit Lake	12/12/1994		-0.025	-0.1	-0.002	-0.01	0.017	-0.025
Pit Lake	12/19/1994		-0.025	-0.1	-0.002	-0.01	0.017	-0.025
Pit Lake	1/29/1995							
Pit Lake	3/29/1995							
Pit Lake	6/27/1995							
Pit Lake	8/1/1995		-0.05	-0.05		-0.05	0.0014	
Pit Lake	8/1/1995							
Pit Lake	9/21/1995		-0.025	-0.1	-0.002	-0.05	0.014	-0.025
Pit Lake	9/21/1995							
Pit Lake	1/10/1996							
Pit Lake	4/3/1996							
Pit Lake	6/1/1996							
Pit Lake	9/25/1996							
Pit Lake	11/15/1996						-0.01	
Pit Lake	11/15/1996						-0.01	
Pit Lake	11/15/1996						-0.01	
Pit Lake	11/15/1996						-0.01	
Pit Lake	1/15/1997							
Pit Lake	1/18/1997						-0.01	

Well Name	Date	Arsenic(As)	Silver(Ag)	Boron(B)	Berrylium(Be)	Barium(Ba)	Cadmium(Cd)	Chromium(Cr)
Pit Lake	1/18/1997						-0.01	
Pit Lake	1/18/1997						-0.01	
Pit Lake	1/18/1997						-0.01	
Pit Lake	7/1/1997							
Pit Lake	7/16/1997							
Pit Lake	7/16/1997							
Pit Lake	7/16/1997							
Pit Lake	7/16/1997							
Pit Lake	8/1/1997		-0.025	0.12	-0.002	-0.005	-0.002	-0.015
Pit Lake	10/1/1997							
Pit Lake	10/8/1997							
Pit Lake	10/8/1997							
Pit Lake	10/8/1997							
Pit Lake	10/8/1997							
Pit Lake	1/15/1998							
Pit Lake	1/24/1998							
Pit Lake	2/1/1998							
Pit Lake	3/1/1998							
Pit Lake	4/9/1998							
Pit Lake	5/1/1998							
Pit Lake	6/1/1998							
Pit Lake	7/13/1998							
Pit Lake	7/21/1998							
Pit Lake	8/1/1998							
Pit Lake	9/1/1998							
Pit Lake	10/15/1998							
Pit Lake	10/1/1997							
PP	8/9/1997		-0.025	0.064	-0.002	-0.05	-0.002	-0.025
PW-1	8/8/1997		-0.025	*1*	0.22	-0.05	**0.18**	*0.11*
PW-1	8/9/1997		-0.025	*1.6*	0.48	-0.05	**0.19**	*0.15*
PW-2	8/9/1997		-0.025	0.12	-0.002	-0.05	-0.002	-0.025
Seep	5/17/1982						-0.005	
Seep	9/2/1982							
Seep	12/23/1982						-0.005	
Seep	2/21/1983						-0.005	
Acid Rock Drianage	5/7/1993							

Well Name	Date	Copper(Cu)	Cobalt(Co)	Lead(Pb)	Iron(Fe)	Magnesium(Mg)	Molybdenum(Mo)	Manganese(Mn)
BG-2Spring	4/1/1993	-0.01	-0.05	-0.02	-0.05	56	-0.02	0.1
BG-2 Spring	7/1/1998							
BG-2 Spring	8/1/1998							
BG-2 Spring	9/1/1998							
BG Spring	4/1/1993	-0.01	-0.05	-0.02	-0.05	66	-0.02	0.2
BG Spring	7/1/1998							
BG Spring	8/1/1998							
BG Spring	9/1/1998							
Casa Moya Wier	6/1/1998							
Casa Moya Wier	7/1/1998							
Casa Moya Wier	8/1/1998							
Casa Moya Wier	9/1/1998							
Danfelser Spring	1/1/1998							
Danfelser Spring	2/1/1998							
Danfelser Spring	3/1/1998							
Danfelser Spring	4/15/1998	-0.005			-0.05	3.9	-0.5	-0.02
Danfelser Spring	5/1/1998							
Danfelser Spring	6/1/1998							
Danfelser Spring	7/22/1998	-0.005			-0.05	3.6	-0.05	-0.02
Danfelser Spring	8/1/1998							
Danfelser Spring	9/1/1998							
Due South of Pit	8/1/1997							
Erwin Wier	5/1/1998							
Erwin Wier	6/1/1998							
Erwin Wier	7/1/1998							
Erwin Wier	8/1/1998							
Erwin Wier	9/1/1998							
Greyback Station A	1/77	*0.04*			0.23		0.01	0.01
Greyback Station A	1/77	*0.03*			0.3		0.01	0.01
Greyback Station B	1/77	*0.04*			0.19		0.03	0.01
Greyback Station B	1/77	*0.05*			0.29		0.03	0.01
Greyback Station C	1/77	*0.03*			0.23		0.03	0.01
Greyback Station C	1/77	*0.05*			0.37		0.02	0.01
Greyback Station A	3/77	-0.005			0.1		0.01	-0.01
Greyback Station B	3/77	-0.005			0.15		0.08	-0.01
Greyback Station C	3/77	-0.005			0.1		0.08	-0.01

Well Name	Date	Copper(Cu)	Cobalt(Co)	Lead(Pb)	Iron(Fe)	Magnesium(Mg)	Molybdenum(Mo)	Manganese(Mn)
Greyback Station B	7/77	-0.005			0.14	29	0.05	0.07
Greyback	5/17/1982	-0.05			-0.01		0.08	-0.05
Greyback	2/11/1991			0.008	0.36	41.9		0.18
Greyback	2/11/1991			0.009	0.1	103		0.04
Greyback	2/11/1991			0.006	-0.05	98.1		-0.02
Greyback Outfall	8/1/1995	-0.025	-0.05	-0.005	0.057		-0.05	0.17
Greyback Outfall	9/21/1995	-0.025	-0.05	-0.005	0.057	140	-0.05	0.17
Greyback Wash	3/1/1997	-0.025			-0.05			-0.025
Humphries Wier	6/1/1998							
Humphries Wier	7/1/1998							
Humphries Wier	8/1/1998							
Humphries Wier	9/1/1998							
Las Animas Creek	10/1/1997				-0.05			
Las Animas Creek	4/15/1998				0.08	5.1	-0.05	-0.02
Las Animas Creek	10/22/1998				-0.05			
Las Animas/Seco Creek	7/31/1974					12		
Las Animas/Seco Creek	7/12/1974					3		
Las Animas/Seco Creek	5/7/1974				0	13		
Las Animas/Seco Creek	7/11/1974					8		
Las Animas/Seco Creek	7/11/1974				0.05	5		
Las Animas/Seco Creek	5/7/1974				0	6		
Las Animas/Seco Creek	7/9/1974				0.01	11		0.01
Las Animas/Seco Creek	1/1/2001	-0.03	-0.05	-0.01	-0.05	9	-0.05	-0.03
Las Animas/Seco Creek	11/16/1994	-0.03	-0.05	-0.01	-0.05	1	-0.05	-0.03
Las Animas/Seco Creek	11/16/1994	-0.03	-0.05	-0.01	-0.05	9	-0.05	-0.03
Las Animas/Seco Creek	11/16/1994	-0.03	-0.05	-0.01	-0.05	10	-0.05	-0.03
Left Side of Haul Road	8/1/1997							
Pit Lake	4/3/1989	-0.1	-0.05	-0.1	-0.1	130	-0.1	1.1
Pit Lake	4/3/1989					129		
Pit Lake	11/14/1990							
Pit Lake	2/11/1991			0.006	0.16	155.6		1.82
Pit Lake	2/11/1991			0.006	0.18	157.3		1.84
Pit Lake	7/19/1991			-0.005	0.27	209.1		2.03
Pit Lake	8/29/1991	**0.64**						
Pit Lake	11/26/1991	0.084						
Pit Lake	3/15/1992							

Well Name	Date	Copper(Cu)	Cobalt(Co)	Lead(Pb)	Iron(Fe)	Magnesium(Mg)	Molybdenum(Mo)	Manganese(Mn)
Pit Lake	3/15/1992							
Pit Lake	5/25/1992							
Pit Lake	7/16/1992							
Pit Lake	10/8/1992							
Pit Lake	11/27/1992							
Pit Lake	12/15/1992	**3.208**						
Pit Lake	2/12/1993	**2.6**	*0.1*	-0.1	0.1	181	-0.1	4.9
Pit Lake	2/25/1993							
Pit Lake	9/28/1993	0.001						
Pit Lake	3/17/1994	0.089						
Pit Lake	5/24/1994	0.051	-0.05	-0.005	0.19	200	-0.05	3.3
Pit Lake	5/24/1994	0.06	-0.05	-0.005	0.25	210	-0.05	3.9
Pit Lake	5/24/1994	0.06	-0.05	-0.005	0.22	200	-0.05	3.7
Pit Lake	5/24/1994	0.041	-0.05	-0.005	0.26	230	-0.05	0.46
Pit Lake	9/22/1994							
Pit Lake	11/16/1994	0.032	-0.025	-0.005	-0.05	250	-0.05	3.4
Pit Lake	11/16/1994	*0.3*	-0.025	-0.05	-0.05	250	-0.05	3.6
Pit Lake	12/12/1994	0.03	-0.05	0.005	-0.05	250	-0.05	3.6
Pit Lake	12/19/1994	0.032	-0.05	0.005	-0.05	250	-0.05	3.4
Pit Lake	1/29/1995							
Pit Lake	3/29/1995							
Pit Lake	6/27/1995							
Pit Lake	8/1/1995	0.064	-0.05	-0.005	0.23		-0.05	
Pit Lake	8/1/1995							
Pit Lake	9/21/1995	-0.025	-0.05	-0.005	-0.05	300	-0.05	3
Pit Lake	9/21/1995							
Pit Lake	1/10/1996							
Pit Lake	4/3/1996							
Pit Lake	6/1/1996							
Pit Lake	9/25/1996							
Pit Lake	11/15/1996	-0.1		-0.05				
Pit Lake	11/15/1996	-0.1		-0.05				
Pit Lake	11/15/1996	-0.1		-0.05				
Pit Lake	11/15/1996	-0.1		-0.05				
Pit Lake	1/15/1997							
Pit Lake	1/18/1997	-0.1		-0.05				

Well Name	Date	Copper(Cu)	Cobalt(Co)	Lead(Pb)	Iron(Fe)	Magnesium(Mg)	Molybdenum(Mo)	Manganese(Mn)
Pit Lake	1/18/1997	-0.1		-0.05				
Pit Lake	1/18/1997	-0.1		-0.05				
Pit Lake	1/18/1997	-0.1		-0.05				
Pit Lake	7/1/1997							
Pit Lake	7/16/1997							
Pit Lake	7/16/1997							
Pit Lake	7/16/1997							
Pit Lake	7/16/1997							
Pit Lake	8/1/1997	0.05	-0.05	-0.005	-0.5	290	0.058	0.83
Pit Lake	10/1/1997							
Pit Lake	10/8/1997							
Pit Lake	10/8/1997							
Pit Lake	10/8/1997							
Pit Lake	10/8/1997							
Pit Lake	1/15/1998	-0.005			-0.05	331.9	0.05	
Pit Lake	1/24/1998	-0.005				364.8	-0.05	1.76
Pit Lake	2/1/1998							
Pit Lake	3/1/1998							
Pit Lake	4/9/1998	0.055			-0.05		1.5	0.15
Pit Lake	5/1/1998							
Pit Lake	6/1/1998							
Pit Lake	7/13/1998	-0.05			-0.5		-0.5	1.3
Pit Lake	7/21/1998	-0.05			-0.5	386.5	-0.5	0.72
Pit Lake	8/1/1998							
Pit Lake	9/1/1998							
Pit Lake	10/15/1998	0.064			0.23			
Pit Lake	10/1/1997	0.064			0.23			
PP	8/9/1997	-0.025	-0.05	-0.005	-0.05	7.4	-0.05	-0.025
PW-1	8/8/1997	**97**	**1.5**	-0.005	1400	170	0.075	25
PW-1	8/9/1997	**110**	**2.1**	-0.005	1700	200	0.087	30
PW-2	8/9/1997	0.05	-0.05	-0.005	-0.05	290	0.058	0.83
Seep	5/17/1982	-0.05			0.1		1.1	0.15
Seep	9/2/1982					28.2		
Seep	12/23/1982	-0.05			-0.01		1.1	-0.05
Seep	2/21/1983	-0.05			-0.01		1.1	-0.05
Acid Rock Drianage	5/7/1993	**684**			375	236		142

Mercury(Hg)	Well Name	Date	Nickel(Ni)	Antimony(Sb)	Selenium(Se)	Zinc(Zn)
-0.001	BG-2Spring	4/1/1993	-0.01		-0.005	-0.01
	BG-2 Spring	7/1/1998				
	BG-2 Spring	8/1/1998				
	BG-2 Spring	9/1/1998				
-0.001	BG Spring	4/1/1993	-0.01		-0.005	-0.01
	BG Spring	7/1/1998				
	BG Spring	8/1/1998				
	BG Spring	9/1/1998				
	Casa Moya Wier	6/1/1998				
	Casa Moya Wier	7/1/1998				
	Casa Moya Wier	8/1/1998				
	Casa Moya Wier	9/1/1998				
	Danfelser Spring	1/1/1998				
	Danfelser Spring	2/1/1998				
	Danfelser Spring	3/1/1998				
-0.002	Danfelser Spring	4/15/1998				
	Danfelser Spring	5/1/1998				
	Danfelser Spring	6/1/1998				
-0.002	Danfelser Spring	7/22/1998				
	Danfelser Spring	8/1/1998				
	Danfelser Spring	9/1/1998				
	Due South of Pit	8/1/1997				
	Erwin Wier	5/1/1998				
	Erwin Wier	6/1/1998				
	Erwin Wier	7/1/1998				
	Erwin Wier	8/1/1998				
	Erwin Wier	9/1/1998				
	Greyback Station A	1/77				0.05
	Greyback Station A	1/77				0.04
	Greyback Station B	1/77				0.04
	Greyback Station B	1/77				0.04
	Greyback Station C	1/77				0.04
	Greyback Station C	1/77				0.04
	Greyback Station A	3/77				-0.01
	Greyback Station B	3/77				0.02
	Greyback Station C	3/77				0.02

Mercury(Hg)	Well Name	Date	Nickel(Ni)	Antimony(Sb)	Selenium(Se)	Zinc(Zn)
	Greyback Station B	7/77				0.01
-0.001	Greyback	5/17/1982			-0.005	
-0.0002	Greyback	2/11/1991			-0.001	
0.0007	Greyback	2/11/1991			-0.001	
0.0002	Greyback	2/11/1991			-0.001	
-0.001	Greyback Outfall	8/1/1995	-0.05		-0.025	-0.05
-0.001	Greyback Outfall	9/21/1995	-0.05	-0.005	-0.25	-0.05
	Greyback Wash	3/1/1997				-0.05
	Humphries Wier	6/1/1998				
	Humphries Wier	7/1/1998				
	Humphries Wier	8/1/1998				
	Humphries Wier	9/1/1998				
	Las Animas Creek	10/1/1997				
0.002	Las Animas Creek	4/15/1998			-0.05	
	Las Animas Creek	10/22/1998				
	Las Animas/Seco Creek	7/31/1974				
	Las Animas/Seco Creek	7/12/1974				
	Las Animas/Seco Creek	5/7/1974				
	Las Animas/Seco Creek	7/11/1974				
	Las Animas/Seco Creek	7/11/1974				
	Las Animas/Seco Creek	5/7/1974				
	Las Animas/Seco Creek	7/9/1974				
-0.001	Las Animas/Seco Creek	1/1/2001	-0.05			-0.05
-0.001	Las Animas/Seco Creek	11/16/1994	-0.05		-0.005	-0.05
-0.001	Las Animas/Seco Creek	11/16/1994	-0.05		-0.005	-0.05
-0.001	Las Animas/Seco Creek	11/16/1994	-0.05		-0.005	-0.05
	Left Side of Haul Road	8/1/1997				
	Pit Lake	4/3/1989	-0.1			0.4
	Pit Lake	4/3/1989				
	Pit Lake	11/14/1990				
0.0004	Pit Lake	2/11/1991			-0.001	
-0.0002	Pit Lake	2/11/1991			-0.001	
-0.0002	Pit Lake	7/19/1991			-0.001	
	Pit Lake	8/29/1991				
	Pit Lake	11/26/1991				
	Pit Lake	3/15/1992				

Mercury(Hg)	Well Name	Date	Nickel(Ni)	Antimony(Sb)	Selenium(Se)	Zinc(Zn)
	Pit Lake	3/15/1992				
	Pit Lake	5/25/1992				
	Pit Lake	7/16/1992				
	Pit Lake	10/8/1992				
	Pit Lake	11/27/1992				
	Pit Lake	12/15/1992				
-0.0005	Pit Lake	2/12/1993	-0.1		-0.005	1.8
	Pit Lake	2/25/1993				
	Pit Lake	9/28/1993				0.01
	Pit Lake	3/17/1994				1.01
-0.001	Pit Lake	5/24/1994	-0.05	-0.005	-0.005	0.6
-0.001	Pit Lake	5/24/1994	-0.05	-0.005	-0.005	0.56
-0.001	Pit Lake	5/24/1994	-0.05	-0.005	-0.005	0.57
-0.001	Pit Lake	5/24/1994	-0.05	-0.005	-0.005	0.54
	Pit Lake	9/22/1994				
-0.001	Pit Lake	11/16/1994	0.05	-0.005	-0.005	0.092
-0.001	Pit Lake	11/16/1994	-0.05	-0.005	-0.005	0.095
-0.001	Pit Lake	12/12/1994	-0.05	-0.005	-0.005	0.095
-0.001	Pit Lake	12/19/1994	-0.05	-0.005	-0.005	0.092
	Pit Lake	1/29/1995				
	Pit Lake	3/29/1995				
	Pit Lake	6/27/1995				
-0.001	Pit Lake	8/1/1995	-0.05		-0.025	
	Pit Lake	8/1/1995				
-0.001	Pit Lake	9/21/1995	-0.05	-0.005	-0.25	0.071
	Pit Lake	9/21/1995				
	Pit Lake	1/10/1996				
	Pit Lake	4/3/1996				
	Pit Lake	6/1/1996				
	Pit Lake	9/25/1996				
-0.001	Pit Lake	11/15/1996				0.28
-0.001	Pit Lake	11/15/1996				0.17
-0.001	Pit Lake	11/15/1996				0.2
-0.001	Pit Lake	11/15/1996				0.29
	Pit Lake	1/15/1997				
-0.001	Pit Lake	1/18/1997				0.23

Mercury(Hg)	Well Name	Date	Nickel(Ni)	Antimony(Sb)	Selenium(Se)	Zinc(Zn)
-0.001	Pit Lake	1/18/1997				0.23
-0.001	Pit Lake	1/18/1997				0.23
-0.001	Pit Lake	1/18/1997				0.19
	Pit Lake	7/1/1997				
	Pit Lake	7/16/1997				
	Pit Lake	7/16/1997				
	Pit Lake	7/16/1997				
	Pit Lake	7/16/1997				
	Pit Lake	8/1/1997	-0.05	-0.005	-0.005	0.11
	Pit Lake	10/1/1997				
	Pit Lake	10/8/1997				
	Pit Lake	10/8/1997				
	Pit Lake	10/8/1997				
	Pit Lake	10/8/1997				
-0.002	Pit Lake	1/15/1998			-0.05	
	Pit Lake	1/24/1998			-0.05	
	Pit Lake	2/1/1998				
	Pit Lake	3/1/1998				
-0.002	Pit Lake	4/9/1998			-0.05	
	Pit Lake	5/1/1998				
	Pit Lake	6/1/1998				
-0.002	Pit Lake	7/13/1998			-0.05	
-0.002	Pit Lake	7/21/1998			-0.05	
	Pit Lake	8/1/1998				
	Pit Lake	9/1/1998				
	Pit Lake	10/15/1998				
	Pit Lake	10/1/1997				
	PP	8/9/1997	-0.05		-0.005	-0.05
	PW-1	8/8/1997	0.37		**0.043**	16
	PW-1	8/9/1997	0.36		-0.05	19
	PW-2	8/9/1997	-0.05		-0.005	0.11
-0.001	Seep	5/17/1982			-0.005	
	Seep	9/2/1982				
-0.001	Seep	12/23/1982			-0.005	
-0.001	Seep	2/21/1983			-0.005	
	Acid Rock Drianage	5/7/1993				**51**

Well Name	Flow Rate	Date	Sampler	Notes	Lat	Long
Seep		5/13/1983	QMC			
Seep		11/1/1983	QMC			
Seep		3/16/1984	QMC			
Seep		8/9/1993	QMC			
Spring		11/14/1990	GE	Greyback, rock house below cu flat		
Spring		11/14/1990	GE	Wet weather spring		
Spring		2/12/1991	GE	Wet weather spring, SHB #7		
SWQ1		12/28/1982	QMC		32.96645	107.54562
SWQ1		2/21/1983	QMC		32.96645	107.54562
SWQ1		7/16/1992	BI/GE	Mislabeled as GQW1	32.96645	107.54562
SWQ1		11/27/1992	GE	Greyback wash 1/2 mi. w of pit	32.96645	107.54562
SWQ1		2/25/1993	BI/GE	Greyback wash 1/2 mi. w of pit	32.96645	107.54562
SWQ1		4/1/1993	Shomaker		32.96645	107.54562
SWQ2		10/27/1981		BG Arroyo	32.96404	107.52329
SWQ2		2/25/1982	QMC		32.96404	107.52329
SWQ2		5/12/1982	QMC		32.96404	107.52329
SWQ2		2/21/1983	QMC		32.96404	107.52329
SWQ2		5/13/1983	QMC		32.96404	107.52329
SWQ2		8/9/1983	QMC		32.96404	107.52329
SWQ2		11/1/1983	QMC		32.96404	107.52329
SWQ2		12/23/1983	QMC		32.96404	107.52329
SWQ2		3/16/1984	QMC		32.96404	107.52329
SWQ2		5/30/1984	QMC		32.96404	107.52329
SWQ2		9/12/1984	CFP		32.96404	107.52329
SWQ2		11/27/1984	CFP		32.96404	107.52329
SWQ2		5/17/1985	CFP		32.96404	107.52329
SWQ2		11/13/1985	CFP		32.96404	107.52329
SWQ2		6/5/1986	CFP	No flow	32.96404	107.52329
SWQ2		10/13/1986	CFP		32.96404	107.52329
SWQ2		7/19/1991	GE	Greyback wash s of plant	32.96404	107.52329
SWQ2		7/16/1992	BI/GE	Mislabeled as GQW2, greyback wash of plant	32.96404	107.52329
SWQ2		10/8/1992	BI/GE		32.96404	107.52329
SWQ2		12/15/1992	BI/GE	Greyback wash s of plant	32.96404	107.52329
SWQ2		2/25/1993	BI/GE	Greyback wash s of plant	32.96404	107.52329
SWQ2		3/31/1993	Shomaker		32.96404	107.52329
SWQ2		6/23/1994	BI/AG	S on grayback of mill site	32.96404	107.52329

Well Name	Flow Rate	Date	Sampler	Notes	Lat	Long
SWQ2		1/29/1995	BI/AG	Mislabeled as gwq2, grayback s of mill	32.96404	107.52329
SWQ2		3/29/1995	BI/AG	Mislabeled as qwq1, south of mill site	32.96404	107.52329
SWQ2		6/27/1995	BI/AG	Mislabeled as qwq1, south of mill site	32.96404	107.52329
SWQ2		9/21/1995	BI/AG	Mislabeled as qwq1, south of mill site	32.96404	107.52329
SWQ2		1/10/1996	BI/AG	Mislabeled as qwq1, south of mill site	32.96404	107.52329
SWQ2		4/3/1996	BI/AG	Mislabeled as qwq1, south of mill site	32.96404	107.52329
SWQ2		9/25/1996	BI/AG	Mislabeled as qwq2 rock house of grayback	32.96404	107.52329
SWQ2		1/15/1997	BI/AG	Mislabeled as qwq1, south of mill site	32.96404	107.52329
SWQ2		7/1/1997	BI	exact date not known	32.96404	107.52329
SWQ2		8/10/1997	SRK		32.96404	107.52329
SWQ2		10/1/1997	BI	exact date not known	32.96404	107.52329
SWQ2		1/15/1998	BI	Labled GWQ-1 South [of] Mill Site	32.96404	107.52329
SWQ2		4/9/1998	BI	Labled GWQ-1 South [of] Mill Site	32.96404	107.52329
SWQ2A		10/27/1981	QMC	BG Arroyo		
SWQ2A		2/25/1982	QMC			
SWQ3		7/19/1991	GE	Greyback wash E of Rock house	32.96654	107.51597
SWQ3		8/29/1991	BI/GE	Greyback wash Opp. Rock House	32.96654	107.51597
SWQ3		11/26/1991	MH/GE	Greyback wash Opp. Rock House	32.96654	107.51597
SWQ3		3/15/1992	BI/GE		32.96654	107.51597
SWQ3		3/15/1992	BI/GE	Greyback wash Opp. Rock House	32.96654	107.51597
SWQ3		2/25/1992	BI/GE		32.96654	107.51597
SWQ3		7/16/1992	BI/GE	Greyback wash E of plant	32.96654	107.51597
SWQ3		10/8/1992	BI/GE		32.96654	107.51597
SWQ3		11/27/1992	MH/GE	Greyback wash Opp. Rock House	32.96654	107.51597
SWQ3		12/15/1992	BI/GE	Greyback wash e of plant	32.96654	107.51597
SWQ3		2/25/1993	BI/GE	Greyback wash E of plant	32.96654	107.51597
SWQ-3		3/31/1993	Shomaker		32.96654	107.51597
SWQ3		9/28/1993	BI/GE		32.96654	107.51597
SWQ3		6/23/1994	BI/AG	Mislabeled as GWQ3, grayback at rock house	32.96654	107.51597
SWQ3		1/29/1995	BI/AG	Mislabeled as gwq1, grayback at rock house	32.96654	107.51597
SWQ3		3/29/1995	BI/AG	Mislabeled as gwq2, rock house on greyback	32.96654	107.51597
SWQ3		6/27/1995	BI/AG	Mislabeled as gwq2, at rock house on greyback	32.96654	107.51597
SWQ3		9/21/1995	BI/AG	Mislabeled as gwq2 rock house of greyback	32.96654	107.51597
SWQ3		1/10/1996	BI/AG	Mislabeled as gwq2 rock house of greyback	32.96654	107.51597
SWQ3		4/3/1996	BI/AG	Mislabeled as gwq2 rock house of greyback	32.96654	107.51597
SWQ3		9/25/1996	BI/AG	Mislabeled as gwq2 rock house of greyback	32.96654	107.51597

Well Name	Flow Rate	Date	Sampler	Notes	Lat	Long
SWQ3		1/15/1997	BI/AG	Mislabeled as gwq2 rock house of greyback	32.96654	107.51597
SWQ3		7/1/1997	BI	exact date not known		
SWQ3		8/10/1997	SRK			
SWQ3		10/1/1997	BI	exact date not known		
SWQ3		1/15/1998	BI	Labeled GWQ-2 Greyback Rock House		
SWQ3		4/9/1998	BI	Labeled GWQ-2 Greyback Rock House		
US Greyback		2/11/1991	FTS/GE	SHB6		
Warm Springs South	18	4/1/1998		16.7.5.2.2.3	32.94974	107.57747
Warm Springs South	5	7/21/1998	Brownfield	16.7.5.2.2.3	32.94974	107.57747
W.Waste	0.01	8/10/1997	SRK	Seep at E. toe of W. waste rock dump		
Caballo Reservoir		11/16/1994		CF-Caballo		
Rio Grande @ El Paso		1/1/1958				
Rio Grande @ El Paso		1/1/1964				
Rio Grande @ El Paso		1/1/1975				
Rio Grande @ El Paso		12/30/1975				
Warm Springs Canyon		4/2/1993				

Well Name	Date	North	East	Filtered?	pH	Sp. Cond.	TDS	SO4	Bicarbonate
Seep	5/13/1983				8.2		1120	600	
Seep	11/1/1983				8		1160	529	
Seep	3/16/1984				8.3		1300	620	
Seep	8/9/1993				8.0		1210	505	
Spring	11/14/1990						2618	1559.1	
Spring	11/14/1990						541	200.8	
Spring	2/12/1991					1095	679	245.0	
SWQ1	12/28/1982	262071	3650254		8.0		250	68	
SWQ1	2/21/1983	262071	3650254		8.0		470	161	
SWQ1	7/16/1992	262071	3650254	TRUE	7.37		965	298.3	
SWQ1	11/27/1992	262071	3650254		8.31		545	180.8	
SWQ1	2/25/1993	262071	3650254	TRUE	8.34		844	323.1	
SWQ1	4/1/1993	262071	3650254		8.30	1150	782	276	430
SWQ2	10/27/1981	264152	3649937	TRUE	8.7		1060	460	
SWQ2	2/25/1982	264152	3649937	TRUE	8.1		1360	658	
SWQ2	5/12/1982	264152	3649937	TRUE	7.9		1380	700	
SWQ2	2/21/1983	264152	3649937		8.4		990	445	
SWQ2	5/13/1983	264152	3649937		8.4		1120	517	
SWQ2	8/9/1983	264152	3649937		8.0		1620	675	
SWQ2	11/1/1983	264152	3649937		8.2		1170	553	
SWQ2	12/23/1983	264152	3649937	TRUE	8.0		1180	550	
SWQ2	3/16/1984	264152	3649937		8.3		1140	515	
SWQ2	5/30/1984	264152	3649937		8.1		1420	720	
SWQ2	9/12/1984	264152	3649937		8.1		1190	577	
SWQ2	11/27/1984	264152	3649937		8.2		1360	675	
SWQ2	5/17/1985	264152	3649937		8.0		1640	770	
SWQ2	11/13/1985	264152	3649937		7.9		1590	770	
SWQ2	6/5/1986	264152	3649937						
SWQ2	10/13/1986	264152	3649937		7.9		1840	830	
SWQ2	7/19/1991	264152	3649937		7.57	4310	3019	1585.5	
SWQ2	7/16/1992	264152	3649937	TRUE	7.57		2305	1154.9	
SWQ2	10/8/1992	264152	3649937	TRUE	7.53		2685	1470.5	
SWQ2	12/15/1992	264152	3649937	TRUE	7.61		3108	1613.0	
SWQ2	2/25/1993	264152	3649937	TRUE	7.58		2713	1459.3	
SWQ2	3/31/1993	264152	3649937		7.7	3150	2720	1460	376
SWQ2	6/23/1994	264152	3649937	TRUE	8.87		3958	2369	

Well Name	Date	North	East	Filtered?	pH	Sp. Cond.	TDS	SO4	Bicarbonate
SWQ2	1/29/1995	264152	3649937	TRUE	7.64		2653	1286.2	
SWQ2	3/29/1995	264152	3649937	TRUE	7.83		2866	1388.2	
SWQ2	6/27/1995	264152	3649937	TRUE	7.74		3235	1877.0	
SWQ2	9/21/1995	264152	3649937	TRUE	7.58		500	271.2	
SWQ2	1/10/1996	264152	3649937	TRUE	7.37		3991	2336.9	
SWQ2	4/3/1996	264152	3649937	TRUE	8.06		4464	2566.3	
SWQ2	9/25/1996	264152	3649937	TRUE	7.66		3997	1987	
SWQ2	1/15/1997	264152	3649937	TRUE	7.43		3436	1356	
SWQ2	7/1/1997	264152	3649937	TRUE	7.34		3507	2033	
SWQ2	8/10/1997	264152	3649937	TRUE	7.89	3267	2890	1410	
SWQ2	10/1/1997	264152	3649937	TRUE	7.75		2015	960	
SWQ2	1/15/1998	264152	3649937	TRUE	7.67	3380	2643	1500	
SWQ2	4/9/1998	264152	3649937	TRUE		3360	2365	2029	
SWQ2A	10/27/1981			TRUE	8.2		830	360	
SWQ2A	2/25/1982			TRUE	8.4		800	320	
SWQ3	7/19/1991	264842	3650197		7.52	3120	2191	1108.2	
SWQ3	8/29/1991	264842	3650197	TRUE	7.82		3596	1884.2	
SWQ3	11/26/1991	264842	3650197		7.71		2857	1419	
SWQ3	3/15/1992	264842	3650197	TRUE	8.08		2393	1247.6	
SWQ3	3/15/1992	264842	3650197	TRUE	8.08		2393	1247.6	
SWQ3	2/25/1992	264842	3650197	TRUE	8.07		2380	1185.2	
SWQ3	7/16/1992	264842	3650197	TRUE	7.66		3364	1654.0	
SWQ3	10/8/1992	264842	3650197	TRUE	7.49		3611	1667.4	
SWQ3	11/27/1992	264842	3650197		8.35		1866	952.2	
SWQ3	12/15/1992	264842	3650197	TRUE	8.15		3436	1549.4	
SWQ3	2/25/1993	264842	3650197	TRUE	8.01		2974	1573.7	
SWQ-3	3/31/1993	264842	3650197		8.1	3330	2950	1580	409
SWQ3	9/28/1993	264842	3650197	TRUE	8.13		4432	1254	
SWQ3	6/23/1994	264842	3650197	TRUE	8.37		2934	1712	
SWQ3	1/29/1995	264842	3650197	TRUE	7.93		3185	1671.7	
SWQ3	3/29/1995	264842	3650197	TRUE	8.23		3216	1709.7	
SWQ3	6/27/1995	264842	3650197	TRUE	7.51		3393	1792.4	
SWQ3	9/21/1995	264842	3650197	TRUE	8.73		3741	2382.0	
SWQ3	1/10/1996	264842	3650197	TRUE	7.78		3666	1936.6	
SWQ3	4/3/1996	264842	3650197	TRUE	7.38		3635	2236.3	
SWQ3	9/25/1996	264842	3650197	TRUE	7.64		2568	1153	

Well Name	Date	North	East	Filtered?	pH	Sp. Cond.	TDS	SO4	Bicarbonate
SWQ3	1/15/1997	264842	3650197	TRUE	8.13		3436		1356
SWQ3	7/1/1997			TRUE	7.79		3854		2185
SWQ3	8/10/1997			TRUE	7.92	3590	3310		1670
SWQ3	10/1/1997			TRUE	7.91		2964		1489
SWQ3	1/15/1998			TRUE	7.7	3800	3115		1738
SWQ3	4/9/1998			TRUE		3570	3361		2050
US Greyback	2/11/1991				7.78	1418	908		348.6
Warm Springs South	4/1/1998	259047	3648474						
Warm Springs South	7/21/1998	259047	3648474	TRUE			543		96
W.Waste	8/10/1997			TRUE	3.03	12280	25440		22100
Caballo Reservoir	11/16/1994				7.97		440		110
Rio Grande @ El Paso	1/1/1958						721		260
Rio Grande @ El Paso	1/1/1964						1058		340
Rio Grande @ El Paso	1/1/1975						846		275
Rio Grande @ El Paso	12/30/1975						809		129
Warm Springs Canyon	4/2/1993				8.5		1370		351

Well Name	Date	Calcium(Ca)	Cl	Flouride(F)	Nitrate (NO_3)	Sodium(Na)	Potassium(K)	Aluminum(Al)
Seep	5/13/1983		52	1.9	0.9			
Seep	11/1/1983		56	1.5	1.1			
Seep	3/16/1984		52	1.7	5.6			
Seep	8/9/1993		52	1.5	1.2			
Spring	11/14/1990		141.2					
Spring	11/14/1990		26.1					
Spring	2/12/1991		43.3	0.3	0.08	78.6	1.6	
SWQ1	12/28/1982		10	0.3	0.9			
SWQ1	2/21/1983		20	0.3	4.4			
SWQ1	7/16/1992		47.2					
SWQ1	11/27/1992		16.7					
SWQ1	2/25/1993		28.9					
SWQ1	4/1/1993	109	27	0.53	0	107	1.8	-0.1
SWQ2	10/27/1981		46	0.8	6.6			-0.01
SWQ2	2/25/1982		80	0.7	4.2			
SWQ2	5/12/1982		108	0.7	3			
SWQ2	2/21/1983		68	0.7	0.8			
SWQ2	5/13/1983		84	0.8	0.3			
SWQ2	8/9/1983		142	0.7	-0.2			
SWQ2	11/1/1983		72	0.8	0.3			
SWQ2	12/23/1983		82	0.5	11.2			
SWQ2	3/16/1984		68	0.8	5.3			
SWQ2	5/30/1984		94	0.8	0.4			
SWQ2	9/12/1984		80	0.9	0.4			
SWQ2	11/27/1984		88	0.8	-0.2			
SWQ2	5/17/1985		102					
SWQ2	11/13/1985		94					
SWQ2	6/5/1986							
SWQ2	10/13/1986		136					
SWQ2	7/19/1991		216.7	0.57	12.74	264.3	10.9	
SWQ2	7/16/1992		93.4					
SWQ2	10/8/1992		130.7					
SWQ2	12/15/1992		192.5					
SWQ2	2/25/1993		135.9					
SWQ2	3/31/1993	436	123	0.63	14.5	279	2.1	-0.1
SWQ2	6/23/1994		197.3					

Well Name	Date	Calcium(Ca)	Cl	Flouride(F)	Nitrate (NO_3)	Sodium(Na)	Potassium(K)	Aluminum(Al)
SWQ2	1/29/1995		89.2					
SWQ2	3/29/1995		83.9					
SWQ2	6/27/1995		127.3					
SWQ2	9/21/1995		31.1					
SWQ2	1/10/1996		167.2					
SWQ2	4/3/1996		222.6					
SWQ2	9/25/1996		143.7					
SWQ2	1/15/1997		148					
SWQ2	7/1/1997		168					
SWQ2	8/10/1997		97	0.86	2.1	290	9.6	0.12
SWQ2	10/1/1997		64.1					
SWQ2	1/15/1998		67.2	0.87	11.3			
SWQ2	4/9/1998		88	0.95	6			
SWQ2A	10/27/1981		46	0.6	0.3			-0.01
SWQ2A	2/25/1982		50	0.7	-0.2			
SWQ3	7/19/1991		143.9	0.73	1.39	189.5	7.4	
SWQ3	8/29/1991		231.3					
SWQ3	11/26/1991		141.1					
SWQ3	3/15/1992		99.2					
SWQ3	3/15/1992		99.2					
SWQ3	2/25/1992		102.9					
SWQ3	7/16/1992		128.7					
SWQ3	10/8/1992		174.4					
SWQ3	11/27/1992		160.5					
SWQ3	12/15/1992		221.6					
SWQ3	2/25/1993		150.7					
SWQ-3	3/31/1993	445	135	0.97	6.9	271	2.2	-0.1
SWQ3	9/28/1993		226.9					
SWQ3	6/23/1994		157.4					
SWQ3	1/29/1995		237.6					
SWQ3	3/29/1995		100.6					
SWQ3	6/27/1995		200.3					
SWQ3	9/21/1995		178.5					
SWQ3	1/10/1996		112.0					
SWQ3	4/3/1996		157.0					
SWQ3	9/25/1996		96.7					

Well Name	Date	Calcium(Ca)	Cl	Flouride(F)	Nitrate (NO_3)	Sodium(Na)	Potassium(K)	Aluminum(Al)
SWQ3	1/15/1997		148					
SWQ3	7/1/1997		176					
SWQ3	8/10/1997		130	0.85	-1	300	9	0.032
SWQ3	10/1/1997		118					
SWQ3	1/15/1998		114	0.99	1.6			
SWQ3	4/9/1998		116	1.07	0.12			
US Greyback	2/11/1991		49.9	0.37	0.07	118.5	1.2	
Warm Springs South	4/1/1998							
Warm Springs South	7/21/1998		17	16.15	-0.05	148.3	9.3	
W.Waste	8/10/1997		16	0.31	4.7	20	-1	**2100**
Caballo Reservoir	11/16/1994		71	0.57		79	5.8	-0.05
Rio Grande @ El Paso	1/1/1958		87			116		
Rio Grande @ El Paso	1/1/1964		199			224		
Rio Grande @ El Paso	1/1/1975		124			159		
Rio Grande @ El Paso	12/30/1975					151		
Warm Springs Canyon	4/2/1993		52	22.2	0	457	22	-0.01

Well Name	Date	Arsenic(As)	Silver(Ag)	Boron(B)	Berrylium(Be)	Barium(Ba)	Cadmium(Cd)	Chromium(Cr)
Seep	5/13/1983						-0.005	
Seep	11/1/1983						-0.005	
Seep	3/16/1984						-0.005	
Seep	8/9/1993						-0.005	
Spring	11/14/1990					0.1	*0.027*	
Spring	11/14/1990							
Spring	2/12/1991	-0.001	-0.001			0.1	*0.027*	0.05
SWQ1	12/28/1982						-0.005	
SWQ1	2/21/1983						-0.005	
SWQ1	7/16/1992							
SWQ1	11/27/1992							
SWQ1	2/25/1993							
SWQ1	4/1/1993	-0.005	-0.01	0.02		-0.05	-0.002	-0.02
SWQ2	10/27/1981	-0.01	-0.02	-0.01		-0.02	-0.005	-0.01
SWQ2	2/25/1982						-0.005	
SWQ2	5/12/1982						-0.005	
SWQ2	2/21/1983						-0.005	
SWQ2	5/13/1983						-0.005	
SWQ2	8/9/1983						-0.005	
SWQ2	11/1/1983						-0.005	
SWQ2	12/23/1983						-0.005	
SWQ2	3/16/1984						-0.005	
SWQ2	5/30/1984						-0.005	
SWQ2	9/12/1984						-0.005	
SWQ2	11/27/1984						-0.005	
SWQ2	5/17/1985							
SWQ2	11/13/1985							
SWQ2	6/5/1986							
SWQ2	10/13/1986							
SWQ2	7/19/1991	-0.002	-0.02			-0.01	-0.005	-0.02
SWQ2	7/16/1992							
SWQ2	10/8/1992							
SWQ2	12/15/1992							
SWQ2	2/25/1993							
SWQ2	3/31/1993	-0.005	-0.01	0.08		-0.5	-0.002	-0.02
SWQ2	6/23/1994							

Well Name	Date	Arsenic(As)	Silver(Ag)	Boron(B)	Berrylium(Be)	Barium(Ba)	Cadmium(Cd)	Chromium(Cr)
SWQ2	1/29/1995							
SWQ2	3/29/1995							
SWQ2	6/27/1995							
SWQ2	9/21/1995							
SWQ2	1/10/1996							
SWQ2	4/3/1996							
SWQ2	9/25/1996							
SWQ2	1/15/1997							
SWQ2	7/1/1997							
SWQ2	8/10/1997	-0.005	-0.025	0.11	-0.002	0.12	-0.002	-0.025
SWQ2	10/1/1997							
SWQ2	1/15/1998							
SWQ2	4/9/1998							
SWQ2A	10/27/1981	-0.01	-0.02	-0.01		-0.02	-0.005	-0.01
SWQ2A	2/25/1982						-0.005	
SWQ3	7/19/1991	-0.002	-0.02			0.03	-0.005	-0.02
SWQ3	8/29/1991							
SWQ3	11/26/1991							
SWQ3	3/15/1992							
SWQ3	3/15/1992							
SWQ3	2/25/1992							
SWQ3	7/16/1992							
SWQ3	10/8/1992							
SWQ3	11/27/1992							
SWQ3	12/15/1992							
SWQ3	2/25/1993							
SWQ-3	3/31/1993	-0.005	-0.01	0.06		-0.05	-0.002	-0.02
SWQ3	9/28/1993							
SWQ3	6/23/1994							
SWQ3	1/29/1995							
SWQ3	3/29/1995							
SWQ3	6/27/1995							
SWQ3	9/21/1995							
SWQ3	1/10/1996							
SWQ3	4/3/1996							
SWQ3	9/25/1996							

Well Name	Date	Arsenic(As)	Silver(Ag)	Boron(B)	Berrylium(Be)	Barium(Ba)	Cadmium(Cd)	Chromium(Cr)
SWQ3	1/15/1997							
SWQ3	7/1/1997							
SWQ3	8/10/1997	-0.005	-0.025	0.11	-0.002	0.1	-0.002	-0.025
SWQ3	10/1/1997							
SWQ3	1/15/1998							
SWQ3	4/9/1998							
US Greyback	2/11/1991	-0.001	0.08			0.06	**0.38**	0.07
Warm Springs South	4/1/1998							
Warm Springs South	7/21/1998							
W.Waste	8/10/1997	*0.14*	-0.025	0.21	0.49	-0.05	**0.82**	0.068
Caballo Reservoir	11/16/1994	-0.005	-0.03	0.14		-0.1	-0.005	-0.03
Rio Grande @ El Paso	1/1/1958							
Rio Grande @ El Paso	1/1/1964							
Rio Grande @ El Paso	1/1/1975							
Rio Grande @ El Paso	12/30/1975							
Warm Springs Canyon	4/2/1993	-0.005	-0.01	0.15		-0.5	-0.002	-0.02

Well Name	Date	Copper(Cu)	Cobalt(Co)	Lead(Pb)	Iron(Fe)	Magnesium(Mg)	Molybdenum(Mo)	Manganese(Mn)	Mercury(Hg)
Seep	5/13/1983	0.089			-0.01		1.8	-0.05	-0.001
Seep	11/1/1983	-0.05			-0.01		1.1	-0.05	-0.001
Seep	3/16/1984	-0.05			-0.01		0.88	-0.05	-0.001
Seep	8/9/1993	-0.05			-0.01		0.87	-0.05	0.001
Spring	11/14/1990								
Spring	11/14/1990								
Spring	2/12/1991			-0.005	0.24	24.7		0.07	-0.0002
SWQ1	12/28/1982	-0.05			-0.01		-0.05	-0.05	-0.001
SWQ1	2/21/1983	-0.05			-0.01		-0.05	-0.05	-0.001
SWQ1	7/16/1992								
SWQ1	11/27/1992								
SWQ1	2/25/1993								
SWQ1	4/1/1993	-0.01	-0.05	-0.02	-0.05	36	-0.02	-0.02	-0.001
SWQ2	10/27/1981	-0.05	-0.02	-0.02	-0.05		-0.05	-0.05	0.004
SWQ2	2/25/1982	-0.05			0.13		-0.05	-0.05	-0.001
SWQ2	5/12/1982	-0.05			-0.01		-0.05	-0.05	-0.001
SWQ2	2/21/1983	-0.05			-0.01		-0.05	-0.05	-0.001
SWQ2	5/13/1983	-0.05			-0.01		-0.05	-0.05	-0.001
SWQ2	8/9/1983	-0.05			-0.01		-0.05	-0.05	-0.001
SWQ2	11/1/1983	-0.05			-0.01		-0.05	-0.05	-0.001
SWQ2	12/23/1983	-0.05			-0.01		-0.05	-0.05	-0.001
SWQ2	3/16/1984	-0.05			-0.01		-0.05	-0.05	-0.001
SWQ2	5/30/1984	-0.05			-0.01		-0.05	-0.05	-0.001
SWQ2	9/12/1984	-0.05			-0.01		-0.05	-0.05	-0.001
SWQ2	11/27/1984	-0.05			-0.01		-0.05	-0.05	-0.001
SWQ2	5/17/1985								
SWQ2	11/13/1985								
SWQ2	6/5/1986								
SWQ2	10/13/1986								
SWQ2	7/19/1991			-0.005	-0.05	129.1		-0.02	-0.0002
SWQ2	7/16/1992								
SWQ2	10/8/1992								
SWQ2	12/15/1992								
SWQ2	2/25/1993								
SWQ2	3/31/1993	0.01	-0.05	-0.02	-0.05	83	-0.02	0.03	-0.001
SWQ2	6/23/1994								

Well Name	Date	Copper(Cu)	Cobalt(Co)	Lead(Pb)	Iron(Fe)	Magnesium(Mg)	Molybdenum(Mo)	Manganese(Mn)	Mercury(Hg)
SWQ2	1/29/1995								
SWQ2	3/29/1995								
SWQ2	6/27/1995								
SWQ2	9/21/1995								
SWQ2	1/10/1996								
SWQ2	4/3/1996								
SWQ2	9/25/1996								
SWQ2	1/15/1997								
SWQ2	7/1/1997								
SWQ2	8/10/1997	0.098	-0.05	-0.005	0.068	110	-0.05	1.6	
SWQ2	10/1/1997								
SWQ2	1/15/1998	-0.005			0.15	93.4	-0.05		-0.002
SWQ2	4/9/1998	0.02			-0.2		-0.05	0.03	-0.002
SWQ2A	10/27/1981	-0.05	-0.02	-0.02	-0.05		-0.05	-0.05	-0.001
SWQ2A	2/25/1982	-0.05			0.1		-0.05	-0.05	-0.001
SWQ3	7/19/1991			-0.005	0.14	84.6		-0.02	-0.0002
SWQ3	8/29/1991	0.015							
SWQ3	11/26/1991	0.001							
SWQ3	3/15/1992								
SWQ3	3/15/1992								
SWQ3	2/25/1992								
SWQ3	7/16/1992								
SWQ3	10/8/1992								
SWQ3	11/27/1992								
SWQ3	12/15/1992								
SWQ3	2/25/1993								
SWQ-3	3/31/1993	0.01	-0.05	-0.02	-0.05	109	-0.02	-0.02	-0.001
SWQ3	9/28/1993								
SWQ3	6/23/1994								
SWQ3	1/29/1995								
SWQ3	3/29/1995								
SWQ3	6/27/1995								
SWQ3	9/21/1995								
SWQ3	1/10/1996								
SWQ3	4/3/1996								
SWQ3	9/25/1996								

Well Name	Date	Copper(Cu)	Cobalt(Co)	Lead(Pb)	Iron(Fe)	Magnesium(Mg)	Molybdenum(Mo)	Manganese(Mn)	Mercury(Hg)
SWQ3	1/15/1997								
SWQ3	7/1/1997								
SWQ3	8/10/1997	0.047	-0.05	-0.005	-0.05	140	-0.05	0.17	
SWQ3	10/1/1997								
SWQ3	1/15/1998	-0.005			-0.05	120.9	-0.05		-0.002
SWQ3	4/9/1998	0.011			-0.05		-0.05	0.02	-0.002
US Greyback	2/11/1991			-0.005	-0.05	42.1		0.07	-0.0002
Warm Springs South	4/1/1998								
Warm Springs South	7/21/1998	-0.005			-0.05	7.8	-0.05	0.03	0.0023
W.Waste	8/10/1997	**1800**	**9.9**	-0.005	310	580	0.28	170	
Caballo Reservoir	11/16/1994	-0.03	-0.05	-0.01	-0.05	14	-0.05	-0.03	-0.001
Rio Grande @ El Paso	1/1/1958								
Rio Grande @ El Paso	1/1/1964								
Rio Grande @ El Paso	1/1/1975								
Rio Grande @ El Paso	12/30/1975								
Warm Springs Canyon	4/2/1993	-0.01	-0.05	-0.02	0.09	3	-0.02	-0.02	-0.001

Well Name	Date	Nickel(Ni)	Antimony(Sb)	Selenium(Se)	Zinc(Zn)
Seep	5/13/1983			-0.005	
Seep	11/1/1983			-0.005	
Seep	3/16/1984			-0.005	
Seep	8/9/1993			-0.005	
Spring	11/14/1990				
Spring	11/14/1990				
Spring	2/12/1991			**0.05**	
SWQ1	12/28/1982			-0.005	
SWQ1	2/21/1983			-0.005	
SWQ1	7/16/1992				
SWQ1	11/27/1992				
SWQ1	2/25/1993				
SWQ1	4/1/1993	-0.01		-0.005	-0.01
SWQ2	10/27/1981	-0.05		-0.005	
SWQ2	2/25/1982			-0.005	
SWQ2	5/12/1982			-0.005	
SWQ2	2/21/1983			-0.005	
SWQ2	5/13/1983			-0.005	
SWQ2	8/9/1983			-0.005	
SWQ2	11/1/1983			-0.005	
SWQ2	12/23/1983			-0.005	
SWQ2	3/16/1984			-0.005	
SWQ2	5/30/1984			-0.005	
SWQ2	9/12/1984			-0.005	
SWQ2	11/27/1984			-0.005	
SWQ2	5/17/1985				
SWQ2	11/13/1985				
SWQ2	6/5/1986				
SWQ2	10/13/1986				
SWQ2	7/19/1991			-0.001	
SWQ2	7/16/1992				
SWQ2	10/8/1992				
SWQ2	12/15/1992				
SWQ2	2/25/1993				
SWQ2	3/31/1993	-0.01		0.008	0.01
SWQ2	6/23/1994				

Well Name	Date	Nickel(Ni)	Antimony(Sb)	Selenium(Se)	Zinc(Zn)
SWQ2	1/29/1995				
SWQ2	3/29/1995				
SWQ2	6/27/1995				
SWQ2	9/21/1995				
SWQ2	1/10/1996				
SWQ2	4/3/1996				
SWQ2	9/25/1996				
SWQ2	1/15/1997				
SWQ2	7/1/1997				
SWQ2	8/10/1997	-0.05		-0.005	-0.05
SWQ2	10/1/1997				
SWQ2	1/15/1998			-0.05	
SWQ2	4/9/1998			-0.05	
SWQ2A	10/27/1981	-0.05		-0.005	
SWQ2A	2/25/1982			-0.005	
SWQ3	7/19/1991			-0.001	
SWQ3	8/29/1991				
SWQ3	11/26/1991				
SWQ3	3/15/1992				
SWQ3	3/15/1992				
SWQ3	2/25/1992				
SWQ3	7/16/1992				
SWQ3	10/8/1992				
SWQ3	11/27/1992				
SWQ3	12/15/1992				
SWQ3	2/25/1993				
SWQ-3	3/31/1993	-0.01		-0.005	-0.01
SWQ3	9/28/1993				
SWQ3	6/23/1994				
SWQ3	1/29/1995				
SWQ3	3/29/1995				
SWQ3	6/27/1995				
SWQ3	9/21/1995				
SWQ3	1/10/1996				
SWQ3	4/3/1996				
SWQ3	9/25/1996				

Well Name	Date	Nickel(Ni)	Antimony(Sb)	Selenium(Se)	Zinc(Zn)
SWQ3	1/15/1997				
SWQ3	7/1/1997				
SWQ3	8/10/1997	-0.05		-0.005	-0.05
SWQ3	10/1/1997				
SWQ3	1/15/1998			-0.05	
SWQ3	4/9/1998			-0.05	
US Greyback	2/11/1991			-0.001	
Warm Springs South	4/1/1998				
Warm Springs South	7/21/1998			-0.05	
W.Waste	8/10/1997	1.3		**0.11**	**38**
Caballo Reservoir	11/16/1994	-0.05		-0.005	-0.05
Rio Grande @ El Paso	1/1/1958				
Rio Grande @ El Paso	1/1/1964				
Rio Grande @ El Paso	1/1/1975				
Rio Grande @ El Paso	12/30/1975				
Warm Springs Canyon	4/2/1993	-0.01		-0.005	-0.01

Appendix B

B-1 Comprehensive Groundwater Chemistry Data
B-2 Pre 1980 SHB Groundwater Sample Results

Appendix B-1

Comprehensive Groundwater Chemistry Data

Well Name	Water Depth	USGS Quad	Well Depth	Sample ID	Date	Sampler	Notes
EPA DWS							
NM GWQ-1						Domestic Use	
NM SWQ-1						Domestic Use	
NM GWQ-2						Livestock	
NM SWQ-2						Livestock	
15.6.30.432	190		-1	15.6.30.432-1	6/6/1981	SHB	
15.6.31.343	98.11	Skute Stone Arroyo	-1	15.6.31.343-1	6/6/1981	SHB	
15.6.31.431		Skute Stone Arroyo	-1	15.6.31.431-1	6/4/1976	SHB	
15.6.31.431		Skute Stone Arroyo	-2	15.6.31.431-2	4/9/1981	SHB	
15.6.31.431	76.39	Skute Stone Arroyo	-3	15.6.31.431-3	6/9/1981	SHB	
15.7.26.324	28.4	Hillsboro	-1	15.7.26.324-1	6/11/1981	SHB	
15.7.26.344	56.5	Hillsboro	-1	15.7.26.344-1	1/11/1981	SHB	
15.7.26.431	34.5	Hillsboro	-1	15.7.26.431-1	6/1/1981	SHB	
Adams	4.15		-1	Adams-1	1/1/1998		
Adams	4		-2	Adams-2	2/1/1998		
Adams	3.4		-3	Adams-3	3/1/1998		
Adams	3.25		-4	Adams-4	4/15/1998	Goff	15.5.28.3.1
Adams	3.1		-5	Adams-5	5/1/1998		
Adams	3.4		-6	Adams-6	6/1/1998		
Adams	3.25		-7	Adams-7	7/22/1998	Brownfield	15.5.28.3.1
Adams	2.75		-8	Adams-8	8/1/1998		
Adams	2.75		-9	Adams-9	9/1/1998		
Branno			-1	Branno-1	7/31/1947		
Bussman	12.65		-1	Bussman-1	1/1/1998		
Bussman	12.5		-2	Bussman-2	2/1/1998		
Bussman	12.3		-3	Bussman-3	3/1/1998		
Bussman	12.26		-4	Bussman-4	4/15/1998	Goff	
Bussman	12.73		-5	Bussman-5	5/1/1998		
Bussman	12.86		-6	Bussman-6	6/1/1998		
Bussman	13.35		-7	Bussman-7	7/22/1998	Brownfield	
Bussman	12.45		-8	Bussman-8	8/1/1998		
Bussman	13.16		-9	Bussman-9	9/1/1998		
Casa-Moya	2.9		-1	Casa-Moya-1	1/1/1998		
Casa-Moya	13.1		-2	Casa-Moya-2	2/1/1998		
Casa-Moya	13.3		-3	Casa-Moya-3	3/1/1998		
Casa-Moya	1		-4	Casa-Moya-4	5/1/1998		

Well Name	Water Depth	USGS Quad	Well Depth	Sample ID	Date	Sampler	Notes
Casa-Moya	2.75		-5	Casa-Moya-5	6/1/1998		
Casa-Moya	2.2		-6	Casa-Moya-6	7/22/1998	Brownfield	
Casa-Moya	2.25		-7	Casa-Moya-7	8/1/1998		
Casa-Moya	2.6		-8	Casa-Moya-8	9/1/1998		
Dawson 1			-1	Dawson 1-1	6/14/1946		
Dawson 1			-2	Dawson 1-2	6/7/1947		
Dawson 2			-1	Dawson 2-1	7/31/1947		
Delores	31.58	Hillsboro	-1	Delores-1	7/1/1998		15.7.25.1.2.1
Delores	30.64	Hillsboro	-2	Delores-2	8/1/1998		15.7.25.1.2.1
Delores	30.85	Hillsboro	-3	Delores-3	9/1/1998		15.7.25.1.2.1
Eaton			-1	Eaton-1	7/31/1947		
ElW	39.855		-1	ElW-1	2/5/1997	SRK	
El Oro	64.2		-1	El Oro-1	6/11/1981	SHB	
Folcher			-1	Folcher-1	6/20/1946		
Guest House	5.94	Hillsboro	-1	Guest House-1	6/9/1981	SHB	
GWQ-1		Skute Stone Arroyo	-1	GWQ-1-1	5/1/1975		exact data unknown
GWQ-1		Skute Stone Arroyo	-2	GWQ-1-2	1/20/1981	SHB	QMC-3, Cl,Na icon
GWQ-1		Skute Stone Arroyo	-3	GWQ-1-3	2/2/1981	SHB	QMC-3, in SHB (198
GWQ-1		Skute Stone Arroyo	-4	GWQ-1-4	3/27/1981	SHB	QMC-3 in SHB (198
GWQ-1	70.6	Skute Stone Arroyo	-5	GWQ-1-5	6/11/1981	SHB	
GWQ-1		Skute Stone Arroyo	-6	GWQ-1-6	6/15/1981	SHB	
GWQ-1		Skute Stone Arroyo	-7	GWQ-1-7	6/15/1981	SHB	
GWQ-1		Skute Stone Arroyo	-8	GWQ-1-8	2/25/1982	QMC	
GWQ-1		Skute Stone Arroyo	-9	GWQ-1-9	3/30/1989	EID	
GWQ-1	0	Skute Stone Arroyo	-10	GWQ-1-10	7/19/1991	GE	lab pH
GWQ-1		Skute Stone Arroyo	-11	GWQ-1-11	3/31/1993	JWS	
GWQ-1	0	Skute Stone Arroyo	-12	GWQ-1-12	5/25/1994	SRK	Artesian
GWQ-1	0	Skute Stone Arroyo	-13	GWQ-1-13	7/21/1994	SRK	Artesian
GWQ-1		Skute Stone Arroyo	-14	GWQ-1-14	9/1/1995		
GWQ-1	-0.38	Skute Stone Arroyo	-15	GWQ-1-15	1/24/1998	GOFF	Artesian
GWQ-1	-0.4	Skute Stone Arroyo	-16	GWQ-1-16	2/1/1998		
GWQ-1	-0.43	Skute Stone Arroyo	-17	GWQ-1-17	3/1/1998		
GWQ-1	-0.71	Skute Stone Arroyo	-18	GWQ-1-18	4/14/1998	Goff	Artesian
GWQ-1	-0.38	Skute Stone Arroyo	-19	GWQ-1-19	5/1/1998		
GWQ-1	-0.38	Skute Stone Arroyo	-20	GWQ-1-20	6/1/1998		
GWQ-1	-0.23	Skute Stone Arroyo	-21	GWQ-1-21	7/21/1998	Brownfield	

Well Name	Water Depth	USGS Quad	Well Depth	Sample ID	Date	Sampler	Notes
GWQ-1	-0.1	Skute Stone Arroyo	-22	GWQ-1-22	8/1/1998		
GWQ-1	-0.04	Skute Stone Arroyo	-23	GWQ-1-23	9/1/1998		
GWQ-10		Skute Stone Arroyo	-1	GWQ-10-1	4/6/1981	QMC	
GWQ-10	90.62	Skute Stone Arroyo	-2	GWQ-10-2	8/10/1981	QMC	
GWQ-10		Skute Stone Arroyo	-3	GWQ-10-3	10/27/1981	QMC	
GWQ-10		Skute Stone Arroyo	-4	GWQ-10-4	10/30/1981	QMC	
GWQ-10		Skute Stone Arroyo	-5	GWQ-10-5	11/6/1981	QMC	
GWQ-10	84.81	Skute Stone Arroyo	-6	GWQ-10-6	11/12/1981	QMC	
GWQ-10	84.09	Skute Stone Arroyo	-7	GWQ-10-7	11/13/1981	EID	
GWQ-10	83.25	Skute Stone Arroyo	-8	GWQ-10-8	11/17/1981	QMC	
GWQ-10	82.69	Skute Stone Arroyo	-9	GWQ-10-9	11/23/1981	QMC	
GWQ-10	80.04	Skute Stone Arroyo	-10	GWQ-10-10	12/7/1981	QMC	
GWQ-10	81.46	Skute Stone Arroyo	-11	GWQ-10-11	12/15/1981	QMC	
GWQ-10	80.04	Skute Stone Arroyo	-12	GWQ-10-12	12/22/1981	QMC	
GWQ-10		Skute Stone Arroyo	-13	GWQ-10-13	1/5/1982	QMC	
GWQ-10	78.46	Skute Stone Arroyo	-14	GWQ-10-14	1/18/1982	QMC	
GWQ-10	78.4	Skute Stone Arroyo	-15	GWQ-10-15	1/26/1982	QMC	
GWQ-10	77.92	Skute Stone Arroyo	-16	GWQ-10-16	2/16/1982	QMC	
GWQ-10	77.9	Skute Stone Arroyo	-17	GWQ-10-17	2/22/1982	QMC	
GWQ-10	75.5	Skute Stone Arroyo	-18	GWQ-10-18	3/12/1982	QMC	
GWQ-10	70.17	Skute Stone Arroyo	-19	GWQ-10-19	4/16/1982	QMC	
GWQ-10	70.2	Skute Stone Arroyo	-20	GWQ-10-20	4/26/1982	QMC	
GWQ-10	20.58	Skute Stone Arroyo	-21	GWQ-10-21	5/17/1982	QMC	
GWQ-10	6.2	Skute Stone Arroyo	-22	GWQ-10-22	6/8/1982	QMC	
GWQ-10	6.17	Skute Stone Arroyo	-23	GWQ-10-23	6/14/1982	QMC	
GWQ-10	4.5	Skute Stone Arroyo	-24	GWQ-10-24	6/30/1982	QMC	
GWQ-10	4.5	Skute Stone Arroyo	-25	GWQ-10-25	7/26/1982	QMC	
GWQ-10	6.6	Skute Stone Arroyo	-26	GWQ-10-26	7/18/1982	QMC	
GWQ-10	7.7	Skute Stone Arroyo	-27	GWQ-10-27	9/2/1982	EID	
GWQ-10	8.6	Skute Stone Arroyo	-28	GWQ-10-28	9/14/1982	QMC	
GWQ-10	11.8	Skute Stone Arroyo	-29	GWQ-10-29	10/18/1982	QMC	
GWQ-10	14.7	Skute Stone Arroyo	-30	GWQ-10-30	11/11/1982	QMC	
GWQ-10	18.5	Skute Stone Arroyo	-31	GWQ-10-31	12/23/1982	QMC	
GWQ-10	18.5	Skute Stone Arroyo	-32	GWQ-10-32	12/28/1982	QMC	
GWQ-10	21.2	Skute Stone Arroyo	-33	GWQ-10-33	2/21/1983	QMC	
GWQ-10	25.1	Skute Stone Arroyo	-34	GWQ-10-34	5/6/1983	QMC	

Well Name	Water Depth	USGS Quad	Well Depth	Sample ID	Date	Sampler	Notes
GWQ-10	25.1	Skute Stone Arroyo	-35	GWQ-10-35	5/13/1983	QMC	
GWQ-10	26.2	Skute Stone Arroyo	-36	GWQ-10-36	6/2/1983	QMC	
GWQ-10	28	Skute Stone Arroyo	-37	GWQ-10-37	7/5/1983	QMC	
GWQ-10	30.2	Skute Stone Arroyo	-38	GWQ-10-38	8/9/1983	QMC	
GWQ-10	30.2	Skute Stone Arroyo	-39	GWQ-10-39	8/25/83	QMC	
GWQ-10	32.6	Skute Stone Arroyo	-40	GWQ-10-40	10/20/1983	QMC	
GWQ-10	32.6	Skute Stone Arroyo	-41	GWQ-10-41	11/1/1983	QMC	
GWQ-10	33.9	Skute Stone Arroyo	-42	GWQ-10-42	12/7/1983	QMC	
GWQ-10	34.7	Skute Stone Arroyo	-43	GWQ-10-43	1/28/1984	QMC	
GWQ-10	35	Skute Stone Arroyo	-44	GWQ-10-44	2/13/1984	QMC	
GWQ-10	33.1	Skute Stone Arroyo	-45	GWQ-10-45	3/1/1984	QMC	
GWQ-10	33.1	Skute Stone Arroyo	-46	GWQ-10-46	3/16/1984	CFP	
GWQ-10	33.2	Skute Stone Arroyo	-47	GWQ-10-47	4/18/1984	CFP	
GWQ-10	32.4	Skute Stone Arroyo	-48	GWQ-10-48	5/22/1984	CFP	
GWQ-10	32.4	Skute Stone Arroyo	-49	GWQ-10-49	5/30/1984	CFP	
GWQ-10	32.3	Skute Stone Arroyo	-50	GWQ-10-50	6/26/1984	CFP	
GWQ-10	32.2	Skute Stone Arroyo	-51	GWQ-10-51	7/25/1984	CFP	
GWQ-10	32	Skute Stone Arroyo	-52	GWQ-10-52	8/27/1984	CFP	
GWQ-10	31.5	Skute Stone Arroyo	-53	GWQ-10-53	9/12/1984	CFP	
GWQ-10	31.8	Skute Stone Arroyo	-54	GWQ-10-54	9/21/1984	CFP	
GWQ-10	32.1	Skute Stone Arroyo	-55	GWQ-10-55	11/19/1984	CFP	
GWQ-10	32.1	Skute Stone Arroyo	-56	GWQ-10-56	11/27/1984	CFP	
GWQ-10	31.7	Skute Stone Arroyo	-57	GWQ-10-57	12/17/1984	CFP	
GWQ-10	31.5	Skute Stone Arroyo	-58	GWQ-10-58	5/17/1985	CFP	

Well Name	Date	Latitude	Longitude	UTM Easting	UTM Northing	UTM Zone	Elevation	Filtered?	Chloride
EPA DWS								FALSE	
NM GWQ-1								FALSE	
NM SWQ-1								FALSE	
NM GWQ-2								FALSE	
NM SWQ-2								FALSE	
15.6.30.432	6/6/1981							TRUE	
15.6.31.343	6/6/1981							TRUE	
15.6.31.431	6/4/1976						5171	TRUE	14.3
15.6.31.431	4/9/1981						5171	TRUE	22
15.6.31.431	6/9/1981						5171	FALSE	
15.7.26.324	6/11/1981						5531	TRUE	
15.7.26.344	1/11/1981						5480	TRUE	
15.7.26.431	6/1/1981						5335	TRUE	
Adams	1/1/1998								
Adams	2/1/1998								
Adams	3/1/1998								
Adams	4/15/1998							TRUE	24.5
Adams	5/1/1998								
Adams	6/1/1998								
Adams	7/22/1998							TRUE	24.4
Adams	8/1/1998								
Adams	9/1/1998								
Branno	7/31/1947							FALSE	15
Bussman	1/1/1998								
Bussman	2/1/1998								
Bussman	3/1/1998								
Bussman	4/15/1998							TRUE	15.3
Bussman	5/1/1998								
Bussman	6/1/1998								
Bussman	7/22/1998							TRUE	14.3
Bussman	8/1/1998								
Bussman	9/1/1998								
Casa-Moya	1/1/1998								
Casa-Moya	2/1/1998								
Casa-Moya	3/1/1998								
Casa-Moya	5/1/1998								

Well Name	Date	Latitude	Longitude	UTM Easting	UTM Northing	UTM Zone	Elevation	Filtered?	Chloride
Casa-Moya	6/1/1998								
Casa-Moya	7/22/1998							TRUE	81.6
Casa-Moya	8/1/1998								
Casa-Moya	9/1/1998								
Dawson 1	6/14/1946							FALSE	18
Dawson 1	6/7/1947							FALSE	11
Dawson 2	7/31/1947							FALSE	13
Delores	7/1/1998								
Delores	8/1/1998								
Delores	9/1/1998								
Eaton	7/31/1947							FALSE	17
ElW	2/5/1997							TRUE	
El Oro	6/11/1981							TRUE	
Folcher	6/20/1946							FALSE	6
Guest House	6/9/1981	32.96821	107.50922	265478	3650367	13	5283	TRUE	
GWQ-1	5/1/1975	32.96712	107.49556	266753	3650216	13	5183		20
GWQ-1	1/20/1981	32.96712	107.49556	266753	3650216	13	5183	TRUE	200
GWQ-1	2/2/1981	32.96712	107.49556	266753	3650216	13	5183	TRUE	20
GWQ-1	3/27/1981	32.96712	107.49556	266753	3650216	13	5183	TRUE	
GWQ-1	6/11/1981	32.96712	107.49556	266753	3650216	13	5183	TRUE	
GWQ-1	6/15/1981	32.96712	107.49556	266753	3650216	13	5183	TRUE	16
GWQ-1	6/15/1981	32.96712	107.49556	266753	3650216	13	5183	TRUE	22
GWQ-1	2/25/1982	32.96712	107.49556	266753	3650216	13	5183	TRUE	22
GWQ-1	3/30/1989	32.96712	107.49556	266753	3650216	13	5183	TRUE	20
GWQ-1	7/19/1991	32.96712	107.49556	266753	3650216	13	5183	TRUE	21.1
GWQ-1	3/31/1993	32.96712	107.49556	266753	3650216	13	5183	TRUE	22
GWQ-1	5/25/1994	32.96712	107.49556	266753	3650216	13	5183	FALSE	22
GWQ-1	7/21/1994	32.96712	107.49556	266753	3650216	13	5183	TRUE	25
GWQ-1	9/1/1995	32.96712	107.49556	266753	3650216	13	5183		31.1
GWQ-1	1/24/1998	32.96712	107.49556	266753	3650216	13	5183	TRUE	24.5
GWQ-1	2/1/1998	32.96712	107.49556	266753	3650216	13	5183		
GWQ-1	3/1/1998	32.96712	107.49556	266753	3650216	13	5183		
GWQ-1	4/14/1998	32.96712	107.49556	266753	3650216	13	5183	TRUE	24.9
GWQ-1	5/1/1998	32.96712	107.49556	266753	3650216	13	5183		
GWQ-1	6/1/1998	32.96712	107.49556	266753	3650216	13	5183		
GWQ-1	7/21/1998	32.96712	107.49556	266753	3650216	13	5183	TRUE	25.7

Well Name	Date	Latitude	Longitude	UTM Easting	UTM Northing	UTM Zone	Elevation	Filtered?	Chloride
GWQ-1	8/1/1998	32.96712	107.49556	266753	3650216	13	5183		
GWQ-1	9/1/1998	32.96712	107.49556	266753	3650216	13	5183		
GWQ-10	4/6/1981	32.96325	107.49677	266630	3649790	13	5200	FALSE	
GWQ-10	8/10/1981	32.96325	107.49677	266630	3649790	13	5200	TRUE	23.5
GWQ-10	10/27/1981	32.96325	107.49677	266630	3649790	13	5200	TRUE	22
GWQ-10	10/30/1981	32.96325	107.49677	266630	3649790	13	5200	FALSE	22.8
GWQ-10	11/6/1981	32.96325	107.49677	266630	3649790	13	5200	TRUE	22
GWQ-10	11/12/1981	32.96325	107.49677	266630	3649790	13	5200	FALSE	
GWQ-10	11/13/1981	32.96325	107.49677	266630	3649790	13	5200	TRUE	22.85
GWQ-10	11/17/1981	32.96325	107.49677	266630	3649790	13	5200	TRUE	26
GWQ-10	11/23/1981	32.96325	107.49677	266630	3649790	13	5200	TRUE	26
GWQ-10	12/7/1981	32.96325	107.49677	266630	3649790	13	5200	TRUE	24
GWQ-10	12/15/1981	32.96325	107.49677	266630	3649790	13	5200	TRUE	24
GWQ-10	12/22/1981	32.96325	107.49677	266630	3649790	13	5200	TRUE	24
GWQ-10	1/5/1982	32.96325	107.49677	266630	3649790	13	5200	TRUE	22
GWQ-10	1/18/1982	32.96325	107.49677	266630	3649790	13	5200	TRUE	
GWQ-10	1/26/1982	32.96325	107.49677	266630	3649790	13	5200	TRUE	24
GWQ-10	2/16/1982	32.96325	107.49677	266630	3649790	13	5200	FALSE	
GWQ-10	2/22/1982	32.96325	107.49677	266630	3649790	13	5200	TRUE	24
GWQ-10	3/12/1982	32.96325	107.49677	266630	3649790	13	5200	FALSE	
GWQ-10	4/16/1982	32.96325	107.49677	266630	3649790	13	5200	FALSE	
GWQ-10	4/26/1982	32.96325	107.49677	266630	3649790	13	5200	TRUE	20
GWQ-10	5/17/1982	32.96325	107.49677	266630	3649790	13	5200	TRUE	28
GWQ-10	6/8/1982	32.96325	107.49677	266630	3649790	13	5200	TRUE	22
GWQ-10	6/14/1982	32.96325	107.49677	266630	3649790	13	5200	FALSE	
GWQ-10	6/30/1982	32.96325	107.49677	266630	3649790	13	5200	TRUE	20
GWQ-10	7/26/1982	32.96325	107.49677	266630	3649790	13	5200	FALSE	
GWQ-10	7/18/1982	32.96325	107.49677	266630	3649790	13	5200	FALSE	
GWQ-10	9/2/1982	32.96325	107.49677	266630	3649790	13	5200	TRUE	22.3
GWQ-10	9/14/1982	32.96325	107.49677	266630	3649790	13	5200	FALSE	
GWQ-10	10/18/1982	32.96325	107.49677	266630	3649790	13	5200	FALSE	
GWQ-10	11/11/1982	32.96325	107.49677	266630	3649790	13	5200	FALSE	
GWQ-10	12/23/1982	32.96325	107.49677	266630	3649790	13	5200	TRUE	26
GWQ-10	12/28/1982	32.96325	107.49677	266630	3649790	13	5200	FALSE	
GWQ-10	2/21/1983	32.96325	107.49677	266630	3649790	13	5200	TRUE	24
GWQ-10	5/6/1983	32.96325	107.49677	266630	3649790	13	5200	FALSE	

Well Name	Date	Latitude	Longitude	UTM Easting	UTM Northing	UTM Zone	Elevation	Filtered?	Chloride
GWQ-10	5/13/1983	32.96325	107.49677	266630	3649790	13	5200	TRUE	32
GWQ-10	6/2/1983	32.96325	107.49677	266630	3649790	13	5200	FALSE	
GWQ-10	7/5/1983	32.96325	107.49677	266630	3649790	13	5200	FALSE	
GWQ-10	8/9/1983	32.96325	107.49677	266630	3649790	13	5200	TRUE	36
GWQ-10	8/25/83	32.96325	107.49677	266630	3649790	13	5200	FALSE	
GWQ-10	10/20/1983	32.96325	107.49677	266630	3649790	13	5200	FALSE	
GWQ-10	11/1/1983	32.96325	107.49677	266630	3649790	13	5200	TRUE	34
GWQ-10	12/7/1983	32.96325	107.49677	266630	3649790	13	5200	FALSE	
GWQ-10	1/28/1984	32.96325	107.49677	266630	3649790	13	5200	FALSE	
GWQ-10	2/13/1984	32.96325	107.49677	266630	3649790	13	5200	FALSE	
GWQ-10	3/1/1984	32.96325	107.49677	266630	3649790	13	5200	FALSE	
GWQ-10	3/16/1984	32.96325	107.49677	266630	3649790	13	5200	TRUE	42
GWQ-10	4/18/1984	32.96325	107.49677	266630	3649790	13	5200	FALSE	
GWQ-10	5/22/1984	32.96325	107.49677	266630	3649790	13	5200	FALSE	
GWQ-10	5/30/1984	32.96325	107.49677	266630	3649790	13	5200	TRUE	56
GWQ-10	6/26/1984	32.96325	107.49677	266630	3649790	13	5200	FALSE	
GWQ-10	7/25/1984	32.96325	107.49677	266630	3649790	13	5200	FALSE	
GWQ-10	8/27/1984	32.96325	107.49677	266630	3649790	13	5200	FALSE	
GWQ-10	9/12/1984	32.96325	107.49677	266630	3649790	13	5200	TRUE	68
GWQ-10	9/21/1984	32.96325	107.49677	266630	3649790	13	5200	FALSE	
GWQ-10	11/19/1984	32.96325	107.49677	266630	3649790	13	5200	FALSE	
GWQ-10	11/27/1984	32.96325	107.49677	266630	3649790	13	5200	TRUE	64
GWQ-10	12/17/1984	32.96325	107.49677	266630	3649790	13	5200	FALSE	
GWQ-10	5/17/1985	32.96325	107.49677	266630	3649790	13	5200	FALSE	52

Sulfate	Well Name	Date	pH	TDS	Alkalinity	Bicarb	Spec. Cond.	Flouride	Nitrate	Aluminum	Antimony
500	EPA DWS								-1	-0.025	-0.005
600	NM GWQ-1		6-9						-1	-0.025	-0.005
600	NM SWQ-1								-1	-0.025	-0.005
600	NM GWQ-2								-1	-0.025	-0.005
	NM SWQ-2								-1	-0.025	-0.005
	15.6.30.432	6/6/1981									
	15.6.31.343	6/6/1981									
137	15.6.31.431	6/4/1976	7.78	520		228	720	0.52	1.39		
144.5	15.6.31.431	4/9/1981				285.7		0.58	1.14	-0.1	
	15.6.31.431	6/9/1981									
	15.7.26.324	6/11/1981									
	15.7.26.344	1/11/1981									
	15.7.26.431	6/1/1981									
	Adams	1/1/1998									
	Adams	2/1/1998									
	Adams	3/1/1998									
16	Adams	4/15/1998	7.87	212			413	0.53	0.5		
	Adams	5/1/1998									
	Adams	6/1/1998									
16	Adams	7/22/1998		194				0.47	0.47		
	Adams	8/1/1998									
	Adams	9/1/1998									
13	Branno	7/31/1947		270		232	404	0.8	0.4		
	Bussman	1/1/1998									
	Bussman	2/1/1998									
	Bussman	3/1/1998									
18	Bussman	4/15/1998	7.45	238			428	0.5	-0.05		
	Bussman	5/1/1998									
	Bussman	6/1/1998									
13	Bussman	7/22/1998		234				0.46	-0.05		
	Bussman	8/1/1998									
	Bussman	9/1/1998									
	Casa-Moya	1/1/1998									
	Casa-Moya	2/1/1998									
	Casa-Moya	3/1/1998									
	Casa-Moya	5/1/1998									

Sulfate	Well Name	Date	pH	TDS	Alkalinity	Bicarb	Spec. Cond.	Flouride	Nitrate	Aluminum	Antimony
	Casa-Moya	6/1/1998									
29.3	Casa-Moya	7/22/1998		722				0.68	0.61		
	Casa-Moya	8/1/1998									
	Casa-Moya	9/1/1998									
36	Dawson 1	6/14/1946		219		169	369	1.3	0.8		
58	Dawson 1	6/7/1947		283		180	385	1	1.1		
52	Dawson 2	7/31/1947		283		158	360	1.2	1.3		
	Delores	7/1/1998									
	Delores	8/1/1998									
	Delores	9/1/1998									
21	Eaton	7/31/1947		356		329	546	0.2	0.2		
	ElW	2/5/1997									
	El Oro	6/11/1981									
19	Folcher	6/20/1946		147		126	216	0.4	2.4		
	Guest House	6/9/1981									
130	GWQ-1	5/1/1975				273		0.5	2.8		
250	GWQ-1	1/20/1981	7.3	450		280.6					
156	GWQ-1	2/2/1981	7.9	520		276					
	GWQ-1	3/27/1981						0.6	5.5		
	GWQ-1	6/11/1981								-0.05	-0.005
148	GWQ-1	6/15/1981	7.4	500	220	251	700	0.5	5.1	-0.01	
117	GWQ-1	6/15/1981		500				0.51	3.75	-0.25	
84	GWQ-1	2/25/1982	7.9	410				0.3	0.2		
133	GWQ-1	3/30/1989		512		280				-0.1	
136.4	GWQ-1	7/19/1991	7.34	543	215	262.4	799	0.58	5.19		
160	GWQ-1	3/31/1993	7.7	536		297	822	0.54	4.9	-0.01	
150	GWQ-1	5/25/1994	7.9	614		270	760	0.52	4.3	0.025	-0.005
162	GWQ-1	7/21/1994	7.97	558		278	861	0.52	4.2	-0.05	0.0052
271.2	GWQ-1	9/1/1995	7.58	500							
148	GWQ-1	1/24/1998	7.7	508			901	0.52			
	GWQ-1	2/1/1998									
	GWQ-1	3/1/1998									
155	GWQ-1	4/14/1998	7.68	521			879	0.55	3.8		
	GWQ-1	5/1/1998									
	GWQ-1	6/1/1998									
132	GWQ-1	7/21/1998		460				0.55	1.19		

Sulfate	Well Name	Date	pH	TDS	Alkalinity	Bicarb	Spec. Cond.	Flouride	Nitrate	Aluminum	Antimony
	GWQ-1	8/1/1998									
	GWQ-1	9/1/1998									
	GWQ-10	4/6/1981						0.53	4.6		
143	GWQ-10	8/10/1981	7.48	528	179	219		1.14	0.22	10.2	
168	GWQ-10	10/27/1981	8.2	520				0.6	1.1	-0.01	
122	GWQ-10	10/30/1981	8.1	588				0.98	0.66	-0.25	
162	GWQ-10	11/6/1981	7.9	500				0.7	2	-0.01	
	GWQ-10	11/12/1981									
140.9	GWQ-10	11/13/1981	7.75	509		275.6	700	0.62	1.8	0.37	
156	GWQ-10	11/17/1981	7.9	500				0.6	1.8	-0.01	
161	GWQ-10	11/23/1981	7.7	650				0.6	1.8	-0.01	
168	GWQ-10	12/7/1981	8.2	490				0.5	1.8	-0.01	
181	GWQ-10	12/15/1981	7.9	550				0.7	2.6	-0.01	
168	GWQ-10	12/22/1981	8.1	480				0.5	2.5	-0.01	
174	GWQ-10	1/5/1982	7.5	430				0.6	2.9	-0.01	
	GWQ-10	1/18/1982									
162	GWQ-10	1/26/1982	7.8	490				0.6	2.3		
	GWQ-10	2/16/1982									
161	GWQ-10	2/22/1982	7.6	510				0.6	2.1		
	GWQ-10	3/12/1982									
	GWQ-10	4/16/1982									
168	GWQ-10	4/26/1982	7.4	840				0.6	2		
175	GWQ-10	5/17/1982	7.7	490				0.6	2.3		
162	GWQ-10	6/8/1982	8	500				0.5	2.2		
	GWQ-10	6/14/1982									
160	GWQ-10	6/30/1982	8	510				0.6	3.3		
	GWQ-10	7/26/1982									
	GWQ-10	7/18/1982									
143.4	GWQ-10	9/2/1982	7.3	506		278	690	0.54	2.25		
	GWQ-10	9/14/1982									
	GWQ-10	10/18/1982									
	GWQ-10	11/11/1982									
138	GWQ-10	12/23/1982	8.5	500				0.6	1.7		
	GWQ-10	12/28/1982									
161	GWQ-10	2/21/1983	7.9	470				0.6	2.4		
	GWQ-10	5/6/1983									

Sulfate	Well Name	Date	pH	TDS	Alkalinity	Bicarb	Spec. Cond.	Flouride	Nitrate	Aluminum	Antimony
161	GWQ-10	5/13/1983	8	480				0.6	2.4		
	GWQ-10	6/2/1983									
	GWQ-10	7/5/1983									
142	GWQ-10	8/9/1983	7.9	510				0.6	2.4		
	GWQ-10	8/25/83									
	GWQ-10	10/20/1983									
125	GWQ-10	11/1/1983	8.1	500				0.6	4.8		
	GWQ-10	12/7/1983									
	GWQ-10	1/28/1984									
	GWQ-10	2/13/1984									
	GWQ-10	3/1/1984									
128	GWQ-10	3/16/1984	8.2	500				0.5	3.5		
	GWQ-10	4/18/1984									
	GWQ-10	5/22/1984									
161	GWQ-10	5/30/1984	7.5	530				0.5	3.3		
	GWQ-10	6/26/1984									
	GWQ-10	7/25/1984									
	GWQ-10	8/27/1984									
158	GWQ-10	9/12/1984	7.8	580				0.5	4.2		
	GWQ-10	9/21/1984									
	GWQ-10	11/19/1984									
163	GWQ-10	11/27/1984	7.7	580				0.6	4.9		
	GWQ-10	12/17/1984									
163	GWQ-10	5/17/1985	7.8	570							

Arsenic	Well Name	Date	Boron	Barium	Berrylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron
-0.005	EPA DWS			-0.1		-0.0005		-0.025		-0.025	-0.05
-0.005	NM GWQ-1			-0.1		-0.0005		-0.025		-0.025	-0.05
-0.005	NM SWQ-1			-0.1		-0.0005		-0.025		-0.025	-0.05
-0.005	NM GWQ-2			-0.1		-0.0005		-0.025		-0.025	-0.05
-0.005	NM SWQ-2			-0.1		-0.0005		-0.025		-0.025	-0.05
	15.6.30.432	6/6/1981									
	15.6.31.343	6/6/1981									
	15.6.31.431	6/4/1976	-0.1				117				
-0.005	15.6.31.431	4/9/1981	0.025	-0.1		-0.001		-0.005			0.002
	15.6.31.431	6/9/1981								0.7	-0.25
	15.7.26.324	6/11/1981									
	15.7.26.344	1/11/1981									
	15.7.26.431	6/1/1981									
	Adams	1/1/1998									
	Adams	2/1/1998									
	Adams	3/1/1998									
	Adams	4/15/1998					34.2			-0.005	-0.05
	Adams	5/1/1998									
	Adams	6/1/1998									
	Adams	7/22/1998					32.7			-0.005	-0.05
	Adams	8/1/1998									
	Adams	9/1/1998									
	Branno	7/31/1947					28				
	Bussman	1/1/1998									
	Bussman	2/1/1998									
	Bussman	3/1/1998									
	Bussman	4/15/1998					57			0.013	4.09
	Bussman	5/1/1998									
	Bussman	6/1/1998									
	Bussman	7/22/1998					55.5			-0.005	1.33
	Bussman	8/1/1998									
	Bussman	9/1/1998									
	Casa-Moya	1/1/1998									
	Casa-Moya	2/1/1998									
	Casa-Moya	3/1/1998									
	Casa-Moya	5/1/1998									

Arsenic	Well Name	Date	Boron	Barium	Berrylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron
	Casa-Moya	6/1/1998									
	Casa-Moya	7/22/1998					84.1			-0.005	-0.05
	Casa-Moya	8/1/1998									
	Casa-Moya	9/1/1998									
	Dawson 1	6/14/1946					21				
	Dawson 1	6/7/1947					22				
	Dawson 2	7/31/1947					24				
	Delores	7/1/1998									
	Delores	8/1/1998									
	Delores	9/1/1998									
	Eaton	7/31/1947					71				
	ElW	2/5/1997									
	El Oro	6/11/1981									
	Folcher	6/20/1946					18				
	Guest House	6/9/1981									
	GWQ-1	5/1/1975					81				
	GWQ-1	1/20/1981					84				0.05
	GWQ-1	2/2/1981					74				1.7
-0.01	GWQ-1	3/27/1981								-0.05	
-0.005	GWQ-1	6/11/1981	-0.1	-0.1	-0.002	-0.0005		-0.025	-0.05	-0.025	-0.05
-0.01	GWQ-1	6/15/1981	-0.1	-0.2		-0.005	82	-0.01	-0.05	-0.05	-0.1
-0.002	GWQ-1	6/15/1981	0.076	-1		-0.01	81	-0.05	-0.05	-0.02	-0.05
	GWQ-1	2/25/1982				-0.005				-0.05	0.14
	GWQ-1	3/30/1989	-0.1	-0.1	-0.1	-0.1	84	-0.1	-0.05	-0.1	-0.1
0.003	GWQ-1	7/19/1991		0.01		-0.005	88	-0.02		-0.02	-0.05
-0.005	GWQ-1	3/31/1993	0.03	-0.5		-0.002	82	-0.02	-0.05	-0.01	-0.05
-0.005	GWQ-1	5/25/1994		-0.1		-0.0005	80	-0.025		-0.025	-0.05
-0.005	GWQ-1	7/21/1994	-0.1	-0.1	-0.002	-0.0005	95	-0.025	-0.05	-0.025	-0.05
	GWQ-1	9/1/1995									
	GWQ-1	1/24/1998					76.5			-0.005	
	GWQ-1	2/1/1998									
	GWQ-1	3/1/1998									
	GWQ-1	4/14/1998					90.4			-0.005	0.13
	GWQ-1	5/1/1998									
	GWQ-1	6/1/1998									
	GWQ-1	7/21/1998					71.2			-0.005	0.11

Arsenic	Well Name	Date	Boron	Barium	Berrylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron
	GWQ-1	8/1/1998									
	GWQ-1	9/1/1998									
0.002	GWQ-10	4/6/1981				-0.01				-0.05	
-0.004	GWQ-10	8/10/1981	0.016	-1		-0.01	74	-0.05	-0.05	-0.05	2.31
-0.01	GWQ-10	10/27/1981	-0.1	-0.2		-0.005	68	-0.01	-0.02	-0.05	-0.01
-0.005	GWQ-10	10/30/1981	0.77	-1		-0.01		-0.05	-0.05	-0.05	-1
-0.01	GWQ-10	11/6/1981	-0.1	-0.2		-0.005	72	-0.01	-0.02	-0.05	-0.1
	GWQ-10	11/12/1981									
-0.005	GWQ-10	11/13/1981	0.037	0.25		0.001	84.2	-0.005			
-0.01	GWQ-10	11/17/1981	-0.1	-0.2		-0.005	70	-0.01	-0.02	-0.05	-0.1
-0.01	GWQ-10	11/23/1981	-0.1	-0.2		-0.005	70	-0.01	-0.02	-0.05	-0.1
-0.01	GWQ-10	12/7/1981	-0.1	-0.2		-0.005	67	-0.01	-0.02	-0.05	-0.1
-0.01	GWQ-10	12/15/1981	-0.1	-0.2		-0.005	89	-0.01	-0.02	-0.05	-0.1
-0.01	GWQ-10	12/22/1981	-0.1	-0.2		-0.005	85	-0.01	-0.02	-0.05	-0.1
-0.01	GWQ-10	1/5/1982	-0.1	-0.2		-0.005	80	-0.01	-0.02	-0.05	0.13
	GWQ-10	1/18/1982									
	GWQ-10	1/26/1982				-0.005				-0.05	-0.1
	GWQ-10	2/16/1982									
	GWQ-10	2/22/1982				-0.005				-0.05	0.12
	GWQ-10	3/12/1982									
	GWQ-10	4/16/1982									
	GWQ-10	4/26/1982				-0.005				-0.05	0.41
	GWQ-10	5/17/1982				-0.005				-0.05	0.1
	GWQ-10	6/8/1982				-0.005				-0.05	-0.1
	GWQ-10	6/14/1982									
	GWQ-10	6/30/1982				-0.005				-0.05	0.62
	GWQ-10	7/26/1982									
	GWQ-10	7/18/1982									
	GWQ-10	9/2/1982				-0.001	82.6				
	GWQ-10	9/14/1982									
	GWQ-10	10/18/1982									
	GWQ-10	11/11/1982									
	GWQ-10	12/23/1982				-0.005				-0.05	-0.1
	GWQ-10	12/28/1982									
	GWQ-10	2/21/1983				-0.005				-0.05	-0.1
	GWQ-10	5/6/1983									

Arsenic	Well Name	Date	Boron	Barium	Berrylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron
	GWQ-10	5/13/1983				-0.005				-0.05	-0.1
	GWQ-10	6/2/1983									
	GWQ-10	7/5/1983									
	GWQ-10	8/9/1983				-0.005				-0.05	-0.01
	GWQ-10	8/25/83									
	GWQ-10	10/20/1983									
	GWQ-10	11/1/1983				-0.005				-0.05	0.17
	GWQ-10	12/7/1983									
	GWQ-10	1/28/1984									
	GWQ-10	2/13/1984									
	GWQ-10	3/1/1984									
	GWQ-10	3/16/1984				-0.005				-0.05	0.11
	GWQ-10	4/18/1984									
	GWQ-10	5/22/1984									
	GWQ-10	5/30/1984				-0.005				-0.05	-0.1
	GWQ-10	6/26/1984									
	GWQ-10	7/25/1984									
	GWQ-10	8/27/1984									
	GWQ-10	9/12/1984				-0.005				-0.05	-0.1
	GWQ-10	9/21/1984									
	GWQ-10	11/19/1984									
	GWQ-10	11/27/1984				-0.005				-0.05	-0.1
	GWQ-10	12/17/1984									
	GWQ-10	5/17/1985									

Lead	Well Name	Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium
-0.005	EPA DWS			-0.03	-0.001		-0.05		-0.005	-0.025	
-0.005	NM GWQ-1			-0.03	-0.001		-0.05		-0.005	-0.025	
-0.005	NM SWQ-1			-0.03	-0.001		-0.05		-0.005	-0.025	
-0.005	NM GWQ-2			-0.03	-0.001		-0.05		-0.005	-0.025	
-0.005	NM SWQ-2			-0.03	-0.001		-0.05		-0.005	-0.025	
	15.6.30.432	6/6/1981									
	15.6.31.343	6/6/1981									
	15.6.31.431	6/4/1976						1.78			50.4
	15.6.31.431	4/9/1981	25.6	0.003		0.005	-0.01		-0.005		
-0.005	15.6.31.431	6/9/1981		-0.05							
	15.7.26.324	6/11/1981									
	15.7.26.344	1/11/1981									
	15.7.26.431	6/1/1981									
	Adams	1/1/1998									
	Adams	2/1/1998									
	Adams	3/1/1998									
	Adams	4/15/1998	4.7	-0.02	-0.0002	-0.05		4.3	-0.05		38.9
	Adams	5/1/1998									
	Adams	6/1/1998									
	Adams	7/22/1998	4.2	-0.02	-0.0002	-0.05		3.6	-0.05		33.7
	Adams	8/1/1998									
	Adams	9/1/1998									
	Branno	7/31/1947	3.6								
	Bussman	1/1/1998									
	Bussman	2/1/1998									
	Bussman	3/1/1998									
	Bussman	4/15/1998	7.1	-0.02	-0.0002	-0.05		0.9	-0.05		19.9
	Bussman	5/1/1998									
	Bussman	6/1/1998									
	Bussman	7/22/1998	6.7	0.09	0.0002	-0.05		0.5	-0.05		18.3
	Bussman	8/1/1998									
	Bussman	9/1/1998									
	Casa-Moya	1/1/1998									
	Casa-Moya	2/1/1998									
	Casa-Moya	3/1/1998									
	Casa-Moya	5/1/1998									

Lead	Well Name	Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium
	Casa-Moya	6/1/1998									
	Casa-Moya	7/22/1998	8.5	-0.02	0.0004	-0.05		84	-0.05		122.5
	Casa-Moya	8/1/1998									
	Casa-Moya	9/1/1998									
	Dawson 1	6/14/1946	4.4								
	Dawson 1	6/7/1947	2.5								
	Dawson 2	7/31/1947	1.6								
	Delores	7/1/1998									
	Delores	8/1/1998									
	Delores	9/1/1998									
	Eaton	7/31/1947	12								
	ElW	2/5/1997									
	El Oro	6/11/1981									
	Folcher	6/20/1946	3.9								
	Guest House	6/9/1981									
	GWQ-1	5/1/1975	14	0.17				2.1			57
	GWQ-1	1/20/1981	14.6								632
	GWQ-1	2/2/1981	20								60
-0.02	GWQ-1	3/27/1981									
-0.005	GWQ-1	6/11/1981		-0.03	-0.001	-0.05	-0.05		-0.005	-0.025	
-0.02	GWQ-1	6/15/1981	19	-0.05	-0.001	-0.05	-0.05	2	-0.005	-0.02	57
-0.05	GWQ-1	6/15/1981	12	-0.02	-0.001	-0.1	-0.05	3.06	-0.0022	-0.02	49.1
	GWQ-1	2/25/1982		-0.063	-0.001	-0.05			-0.005		
-0.1	GWQ-1	3/30/1989	16	-0.05		-0.1	-0.1	3		-0.1	61
-0.005	GWQ-1	7/19/1991	18	-0.02	-0.0002			2.7	-0.002	-0.2	39.6
-0.02	GWQ-1	3/31/1993	21	-0.02	-0.001	-0.02	-0.01	2.1	-0.005	-0.01	67
-0.005	GWQ-1	5/25/1994	18	-0.03	-0.001		-0.05	2.7	-0.005	-0.025	55
-0.005	GWQ-1	7/21/1994	19	-0.03	-0.001	-0.05	-0.05	2.7	-0.005	-0.025	66
	GWQ-1	9/1/1995									
	GWQ-1	1/24/1998	17.8	-0.02							61.5
	GWQ-1	2/1/1998									
	GWQ-1	3/1/1998									
	GWQ-1	4/14/1998	17.9	-0.02	-0.0002	-0.05		1.7	-0.05		62
	GWQ-1	5/1/1998									
	GWQ-1	6/1/1998									
	GWQ-1	7/21/1998	15.1	0.02	0.0004	-0.05		2.7	-0.05		57.5

Lead	Well Name	Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium
	GWQ-1	8/1/1998									
	GWQ-1	9/1/1998									
-0.01	GWQ-10	4/6/1981			-1			8.25			
-0.05	GWQ-10	8/10/1981	11.3	1.18	-1	-0.1	-0.05	8.32	-0.002	-0.02	58.7
-0.02	GWQ-10	10/27/1981		-0.05	-0.001	-0.05	-0.05		-0.005	-0.02	
-0.05	GWQ-10	10/30/1981		-0.02	-0.001	-0.1	-0.02		-0.002	-0.02	
-0.02	GWQ-10	11/6/1981		-0.05	-0.001	-0.05	-0.05		-0.005	-0.02	
	GWQ-10	11/12/1981									
-0.005	GWQ-10	11/13/1981	17.5	0.5	-0.0005	-0.01	-0.05	2.34	0.01	-0.001	39.1
-0.02	GWQ-10	11/17/1981		-0.05	-0.001	-0.05	-0.05		-0.005	-0.02	
-0.02	GWQ-10	11/23/1981		-0.05	-0.001	-0.05	-0.05		-0.005	-0.02	
-0.02	GWQ-10	12/7/1981		-0.05	-0.001	-0.05	-0.05		-0.005	-0.02	
-0.02	GWQ-10	12/15/1981		-0.05	-0.001	-0.05	-0.05		-0.005	-0.02	
-0.02	GWQ-10	12/22/1981		-0.05	-0.001	-0.05	-0.05		-0.005	-0.02	
-0.02	GWQ-10	1/5/1982		-0.05	-0.001	-0.05	-0.05		-0.005	-0.02	
	GWQ-10	1/18/1982									
	GWQ-10	1/26/1982		-0.05	-0.001	-0.1			-0.005		
	GWQ-10	2/16/1982									
	GWQ-10	2/22/1982		-0.05	-0.001	-0.05			-0.005		
	GWQ-10	3/12/1982									
	GWQ-10	4/16/1982									
	GWQ-10	4/26/1982		-0.05	-0.001	-0.05			-0.005		
	GWQ-10	5/17/1982		-0.05	-0.001	-0.05			-0.005		
	GWQ-10	6/8/1982		-0.05	-0.001	-0.05			-0.005		
	GWQ-10	6/14/1982									
	GWQ-10	6/30/1982		-0.05	-0.001	-0.05			-0.005		
	GWQ-10	7/26/1982									
	GWQ-10	7/18/1982									
	GWQ-10	9/2/1982	17	-0.05		-0.01		2.73	-0.005		57.5
	GWQ-10	9/14/1982									
	GWQ-10	10/18/1982									
	GWQ-10	11/11/1982									
	GWQ-10	12/23/1982		-0.05	-0.001	-0.05			-0.005		
	GWQ-10	12/28/1982									
	GWQ-10	2/21/1983		-0.05	-0.001	-0.05			-0.005		
	GWQ-10	5/6/1983									

Lead	Well Name	Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium
	GWQ-10	5/13/1983		-0.05	-0.001	-0.05			-0.005		
	GWQ-10	6/2/1983									
	GWQ-10	7/5/1983									
	GWQ-10	8/9/1983		-0.05	-0.001	-0.05			-0.005		
	GWQ-10	8/25/83									
	GWQ-10	10/20/1983									
	GWQ-10	11/1/1983		-0.05	-0.001	-0.05			-0.005		
	GWQ-10	12/7/1983									
	GWQ-10	1/28/1984									
	GWQ-10	2/13/1984									
	GWQ-10	3/1/1984									
	GWQ-10	3/16/1984		-0.05	-0.001	-0.05			-0.005		
	GWQ-10	4/18/1984									
	GWQ-10	5/22/1984									
	GWQ-10	5/30/1984		-0.05	-0.001	-0.05			-0.005		
	GWQ-10	6/26/1984									
	GWQ-10	7/25/1984									
	GWQ-10	8/27/1984									
	GWQ-10	9/12/1984		-0.05	-0.001	-0.05			-0.005		
	GWQ-10	9/21/1984									
	GWQ-10	11/19/1984									
	GWQ-10	11/27/1984		-0.05	-0.001	-0.05			-0.005		
	GWQ-10	12/17/1984									
	GWQ-10	5/17/1985									

Thallium	Well Name	Date	Zinc	Temp (C)	Tin	Vanadium
	EPA DWS		-0.05			
	NM GWQ-1		-0.05			
	NM SWQ-1		-0.05			
	NM GWQ-2		-0.05			
	NM SWQ-2		-0.05			
	15.6.30.432	6/6/1981				
	15.6.31.343	6/6/1981				
	15.6.31.431	6/4/1976				
	15.6.31.431	4/9/1981	0.14			
	15.6.31.431	6/9/1981				
	15.7.26.324	6/11/1981				
	15.7.26.344	1/11/1981				
	15.7.26.431	6/1/1981				
	Adams	1/1/1998				
	Adams	2/1/1998				
	Adams	3/1/1998				
	Adams	4/15/1998				
	Adams	5/1/1998				
	Adams	6/1/1998				
	Adams	7/22/1998				
	Adams	8/1/1998				
	Adams	9/1/1998				
	Branno	7/31/1947				
	Bussman	1/1/1998				
	Bussman	2/1/1998				
	Bussman	3/1/1998				
	Bussman	4/15/1998				
	Bussman	5/1/1998				
	Bussman	6/1/1998				
	Bussman	7/22/1998				
	Bussman	8/1/1998				
	Bussman	9/1/1998				
	Casa-Moya	1/1/1998				
	Casa-Moya	2/1/1998				
	Casa-Moya	3/1/1998				
	Casa-Moya	5/1/1998				

Thallium	Well Name	Date	Zinc	Temp (C)	Tin	Vanadium
	Casa-Moya	6/1/1998				
	Casa-Moya	7/22/1998				
	Casa-Moya	8/1/1998				
	Casa-Moya	9/1/1998				
	Dawson 1	6/14/1946		23.7999992		
	Dawson 1	6/7/1947				
	Dawson 2	7/31/1947				
	Delores	7/1/1998				
	Delores	8/1/1998				
	Delores	9/1/1998				
	Eaton	7/31/1947				
	ElW	2/5/1997				
	El Oro	6/11/1981				
	Folcher	6/20/1946				
	Guest House	6/9/1981				
	GWQ-1	5/1/1975				
	GWQ-1	1/20/1981				
	GWQ-1	2/2/1981				
	GWQ-1	3/27/1981	0.16			
-0.005	GWQ-1	6/11/1981	-0.05			
	GWQ-1	6/15/1981	0.12	22		
-0.005	GWQ-1	6/15/1981	0.078			
	GWQ-1	2/25/1982				
	GWQ-1	3/30/1989	-0.1		-0.1	-0.1
	GWQ-1	7/19/1991				
	GWQ-1	3/31/1993	-0.01			
	GWQ-1	5/25/1994	-0.05			
-0.005	GWQ-1	7/21/1994	-0.05			
	GWQ-1	9/1/1995				
	GWQ-1	1/24/1998				
	GWQ-1	2/1/1998				
	GWQ-1	3/1/1998				
	GWQ-1	4/14/1998				
	GWQ-1	5/1/1998				
	GWQ-1	6/1/1998				
	GWQ-1	7/21/1998				

Thallium	Well Name	Date	Zinc	Temp (C)	Tin	Vanadium
	GWQ-1	8/1/1998				
	GWQ-1	9/1/1998				
	GWQ-10	4/6/1981	0.12			
	GWQ-10	8/10/1981	0.23			
	GWQ-10	10/27/1981	0.25			
	GWQ-10	10/30/1981	0.24			
	GWQ-10	11/6/1981	0.28			
	GWQ-10	11/12/1981				
-0.005	GWQ-10	11/13/1981	0.9	19.5		
	GWQ-10	11/17/1981	0.28			
	GWQ-10	11/23/1981	0.37			
	GWQ-10	12/7/1981	0.87			
	GWQ-10	12/15/1981	0.44			
	GWQ-10	12/22/1981	0.35			
	GWQ-10	1/5/1982	0.31			
	GWQ-10	1/18/1982				
	GWQ-10	1/26/1982				
	GWQ-10	2/16/1982				
	GWQ-10	2/22/1982				
	GWQ-10	3/12/1982				
	GWQ-10	4/16/1982				
	GWQ-10	4/26/1982				
	GWQ-10	5/17/1982				
	GWQ-10	6/8/1982				
	GWQ-10	6/14/1982				
	GWQ-10	6/30/1982				
	GWQ-10	7/26/1982				
	GWQ-10	7/18/1982				
	GWQ-10	9/2/1982				
	GWQ-10	9/14/1982				
	GWQ-10	10/18/1982				
	GWQ-10	11/11/1982				
	GWQ-10	12/23/1982				
	GWQ-10	12/28/1982				
	GWQ-10	2/21/1983				
	GWQ-10	5/6/1983				

Thallium	Well Name	Date	Zinc	Temp (C)	Tin	Vanadium
	GWQ-10	5/13/1983				
	GWQ-10	6/2/1983				
	GWQ-10	7/5/1983				
	GWQ-10	8/9/1983				
	GWQ-10	8/25/83				
	GWQ-10	10/20/1983				
	GWQ-10	11/1/1983				
	GWQ-10	12/7/1983				
	GWQ-10	1/28/1984				
	GWQ-10	2/13/1984				
	GWQ-10	3/1/1984				
	GWQ-10	3/16/1984				
	GWQ-10	4/18/1984				
	GWQ-10	5/22/1984				
	GWQ-10	5/30/1984				
	GWQ-10	6/26/1984				
	GWQ-10	7/25/1984				
	GWQ-10	8/27/1984				
	GWQ-10	9/12/1984				
	GWQ-10	9/21/1984				
	GWQ-10	11/19/1984				
	GWQ-10	11/27/1984				
	GWQ-10	12/17/1984				
	GWQ-10	5/17/1985				

Well Name	Water Depth	USGS Quad	Well Depth	Sample ID	Date	Sampler	Notes
GWQ-10	23.4	Skute Stone Arroyo	-59	GWQ-10-59	11/13/1985	CFP	
GWQ-10	21.2	Skute Stone Arroyo	-60	GWQ-10-60	5/23/1986	CFP	
GWQ-10	20.7	Skute Stone Arroyo	-61	GWQ-10-61	10/8/1986	CFP	
GWQ-10	16	Skute Stone Arroyo	-62	GWQ-10-62	3/4/1987	EID	
GWQ-10		Skute Stone Arroyo	-63	GWQ-10-63	5/25/1987		
GWQ-10	15.5	Skute Stone Arroyo	-64	GWQ-10-64	1/12/1988	EID	
GWQ-10		Skute Stone Arroyo	-65	GWQ-10-65	4/4/1988	Irwin	lab pH
GWQ-10	20.75	Skute Stone Arroyo	-66	GWQ-10-66	8/23/1988	Irwin	lab pH
GWQ-10	17.58	Skute Stone Arroyo	-67	GWQ-10-67	2/9/1989	Irwin	lab pH
GWQ-10	17.2	Skute Stone Arroyo	-68	GWQ-10-68	6/1/1989	Irwin	lab pH
GWQ-10	17.5	Skute Stone Arroyo	-69	GWQ-10-69	11/30/1989	Irwin	lab pH
GWQ-10	17.5	Skute Stone Arroyo	-70	GWQ-10-70	11/14/1990	GE	
GWQ-10	21.2	Skute Stone Arroyo	-71	GWQ-10-71	2/11/1991	SHB	
GWQ-10	15.31	Skute Stone Arroyo	-72	GWQ-10-72	7/19/1991	GE	lab pH
GWQ-10	16.58	Skute Stone Arroyo	-73	GWQ-10-73	8/29/1991	Irwin	lab pH
GWQ-10	14.6	Skute Stone Arroyo	-74	GWQ-10-74	11/26/1991	Hood	lab pH
GWQ-10	15	Skute Stone Arroyo	-75	GWQ-10-75	3/15/1992	Irwin	lab pH
GWQ-10		Skute Stone Arroyo	-76	GWQ-10-76	5/25/1992	Irwin	lab pH
GWQ-10		Skute Stone Arroyo	-77	GWQ-10-77	7/16/1992	Irwin	lab pH
GWQ-10	14.5	Skute Stone Arroyo	-78	GWQ-10-78	10/8/1992	Irwin	lab pH
GWQ-10	15.58	Skute Stone Arroyo	-79	GWQ-10-79	11/27/1992	Hood	lab pH
GWQ-10		Skute Stone Arroyo	-80	GWQ-10-80	12/15/1992	Irwin	lab pH
GWQ-10	15.42	Skute Stone Arroyo	-81	GWQ-10-81	2/25/1993	Irwin	lab pH
GWQ-10		Skute Stone Arroyo	-82	GWQ-10-82	3/30/1993	JWS	
GWQ-10		Skute Stone Arroyo	-83	GWQ-10-83	9/28/1993	Irwin	lab pH
GWQ-10	16.7	Skute Stone Arroyo	-84	GWQ-10-84	5/26/1994	SRK	
GWQ-10		Skute Stone Arroyo	-85	GWQ-10-85	6/23/1994	Irwin	lab pH
GWQ-10		Skute Stone Arroyo	-86	GWQ-10-86	7/23/1994	SRK	
GWQ-10		Skute Stone Arroyo	-87	GWQ-10-87	9/22/1994	Irwin	lab pH
GWQ-10		Skute Stone Arroyo	-88	GWQ-10-88	1/29/1995	Irwin	lab pH
GWQ-10		Skute Stone Arroyo	-89	GWQ-10-89	3/29/1995	Irwin	lab pH
GWQ-10		Skute Stone Arroyo	-90	GWQ-10-90	3/29/1995	Irwin	lab pH
GWQ-10	19.58	Skute Stone Arroyo	-91	GWQ-10-91	6/27/1995	Irwin	lab pH
GWQ-10		Skute Stone Arroyo	-92	GWQ-10-92	9/21/1995	Irwin	lab pH
GWQ-10		Skute Stone Arroyo	-93	GWQ-10-93	1/10/1996	Irwin	lab pH
GWQ-10		Skute Stone Arroyo	-94	GWQ-10-94	4/3/1996	Irwin	lab pH

Well Name	Water Depth	USGS Quad	Well Depth	Sample ID	Date	Sampler	Notes
GWQ-10		Skute Stone Arroyo	-95	GWQ-10-95	6/1/1996		
GWQ-10		Skute Stone Arroyo	-96	GWQ-10-96	9/25/1996	Irwin	lab pH
GWQ-10		Skute Stone Arroyo	-97	GWQ-10-97	1/15/1997	Irwin	lab pH
GWQ-10		Skute Stone Arroyo	-98	GWQ-10-98	4/1/1997		
GWQ-10		Skute Stone Arroyo	-99	GWQ-10-99	7/1/1997		
GWQ-10		Skute Stone Arroyo	-100	GWQ-10-100	8/1/1997		
GWQ-10		Skute Stone Arroyo	-101	GWQ-10-101	10/1/1997		
GWQ-10		Skute Stone Arroyo	-102	GWQ-10-102	10/1/1997		
GWQ-10	22.1	Skute Stone Arroyo	-103	GWQ-10-103	1/15/1998	Irwin	
GWQ-10	22.25	Skute Stone Arroyo	-104	GWQ-10-104	4/9/1998	Irwin	
GWQ-10	22.42	Skute Stone Arroyo	-105	GWQ-10-105	7/13/1998	Irwin	
GWQ-10		Skute Stone Arroyo	-106	GWQ-10-106	10/15/1998	Goff	
GWQ-11	34.83	Skute Stone Arroyo	-1	GWQ-11-1	8/10/1981	QMC	
GWQ-11		Skute Stone Arroyo	-2	GWQ-11-2	10/27/1981	QMC	
GWQ-11		Skute Stone Arroyo	-3	GWQ-11-3	10/30/1981		
GWQ-11	34.85	Skute Stone Arroyo	-4	GWQ-11-4	11/6/1981	QMC	
GWQ-11	34.82	Skute Stone Arroyo	-5	GWQ-11-5	11/13/1981	EID	
GWQ-11	34.17	Skute Stone Arroyo	-6	GWQ-11-6	11/17/1981	QMC	
GWQ-11	36.02	Skute Stone Arroyo	-7	GWQ-11-7	11/23/1981	QMC	
GWQ-11	34.75	Skute Stone Arroyo	-8	GWQ-11-8	12/7/1981	QMC	
GWQ-11	35.02	Skute Stone Arroyo	-9	GWQ-11-9	12/15/1981	QMC	
GWQ-11	35.02	Skute Stone Arroyo	-10	GWQ-11-10	12/22/1981	QMC	
GWQ-11	34.74	Skute Stone Arroyo	-11	GWQ-11-11	1/5/1982	QMC	
GWQ-11	36.67	Skute Stone Arroyo	-12	GWQ-11-12	1/18/1982	QMC	
GWQ-11	36.66	Skute Stone Arroyo	-13	GWQ-11-13	1/26/1982	QMC	
GWQ-11	34.92	Skute Stone Arroyo	-14	GWQ-11-14	2/16/1982	QMC	
GWQ-11	34.91	Skute Stone Arroyo	-15	GWQ-11-15	2/22/1982	QMC	
GWQ-11	35.17	Skute Stone Arroyo	-16	GWQ-11-16	3/12/1982	QMC	
GWQ-11	28.67	Skute Stone Arroyo	-17	GWQ-11-17	4/16/1982	QMC	
GWQ-11	28.16	Skute Stone Arroyo	-18	GWQ-11-18	4/26/1982	QMC	
GWQ-11	23.8	Skute Stone Arroyo	-19	GWQ-11-19	5/17/1982	QMC	
GWQ-11	19.7	Skute Stone Arroyo	-20	GWQ-11-20	6/8/1982	QMC	
GWQ-11	19.67	Skute Stone Arroyo	-21	GWQ-11-21	6/14/1982	QMC	
GWQ-11	15.1	Skute Stone Arroyo	-22	GWQ-11-22	6/30/1982	QMC	
GWQ-11	15.08	Skute Stone Arroyo	-23	GWQ-11-23	7/26/1982	QMC	
GWQ-11	13.2	Skute Stone Arroyo	-24	GWQ-11-24	8/18/1982	QMC	

Well Name	Water Depth	USGS Quad	Well Depth	Sample ID	Date	Sampler	Notes
GWQ-11	12.3	Skute Stone Arroyo	-25	GWQ-11-25	9/2/1982	EID	
GWQ-11	11.8	Skute Stone Arroyo	-26	GWQ-11-26	9/14/1982	QMC	
GWQ-11	11.1	Skute Stone Arroyo	-27	GWQ-11-27	10/18/1982	QMC	
GWQ-11	11.2	Skute Stone Arroyo	-28	GWQ-11-28	11/11/1982	QMC	
GWQ-11	11.2	Skute Stone Arroyo	-29	GWQ-11-29	12/23/1982	QMC	
GWQ-11	11.2	Skute Stone Arroyo	-30	GWQ-11-30	12/28/1982	QMC	
GWQ-11	11.4	Skute Stone Arroyo	-31	GWQ-11-31	2/21/1983	QMC	
GWQ-11	12.5	Skute Stone Arroyo	-32	GWQ-11-32	5/6/1983	QMC	
GWQ-11	12.5	Skute Stone Arroyo	-33	GWQ-11-33	5/13/1983	QMC	
GWQ-11	12.9	Skute Stone Arroyo	-34	GWQ-11-34	6/2/1983	QMC	
GWQ-11	13.6	Skute Stone Arroyo	-35	GWQ-11-35	7/5/1983	QMC	
GWQ-11	14.1	Skute Stone Arroyo	-36	GWQ-11-36	8/9/1983	QMC	
GWQ-11	14.1	Skute Stone Arroyo	-37	GWQ-11-37	8/25/1983	QMC	
GWQ-11	14.6	Skute Stone Arroyo	-38	GWQ-11-38	10/20/1983	QMC	
GWQ-11	14.6	Skute Stone Arroyo	-39	GWQ-11-39	11/1/1983	QMC	
GWQ-11	14.3	Skute Stone Arroyo	-40	GWQ-11-40	12/7/1984	QMC	
GWQ-11	14.8	Skute Stone Arroyo	-41	GWQ-11-41	1/28/1984	QMC	
GWQ-11	14.9	Skute Stone Arroyo	-42	GWQ-11-42	2/13/1984	QMC	
GWQ-11	14.9	Skute Stone Arroyo	-43	GWQ-11-43	3/1/1984	CFP	
GWQ-11	14.9	Skute Stone Arroyo	-44	GWQ-11-44	3/16/1984	CFP	
GWQ-11	15.2	Skute Stone Arroyo	-45	GWQ-11-45	4/18/1984	CFP	
GWQ-11	15.5	Skute Stone Arroyo	-46	GWQ-11-46	5/22/1984	CFP	
GWQ-11	15.5	Skute Stone Arroyo	-47	GWQ-11-47	5/30/1984	CFP	
GWQ-11	15.8	Skute Stone Arroyo	-48	GWQ-11-48	6/26/1984	CFP	
GWQ-11	15.9	Skute Stone Arroyo	-49	GWQ-11-49	7/25/1984	CFP	
GWQ-11	16	Skute Stone Arroyo	-50	GWQ-11-50	8/27/1984	CFP	
GWQ-11	16	Skute Stone Arroyo	-51	GWQ-11-51	9/12/1984	CFP	
GWQ-11	16	Skute Stone Arroyo	-52	GWQ-11-52	9/21/1984	CFP	
GWQ-11	16.3	Skute Stone Arroyo	-53	GWQ-11-53	11/19/1984	CFP	
GWQ-11	16.3	Skute Stone Arroyo	-54	GWQ-11-54	11/27/1984	CFP	
GWQ-11	16.4	Skute Stone Arroyo	-55	GWQ-11-55	12/17/1984	CFP	
GWQ-11	16.4	Skute Stone Arroyo	-56	GWQ-11-56	5/17/1985	CFP	
GWQ-11	16.2	Skute Stone Arroyo	-57	GWQ-11-57	11/13/1985	CFP	
GWQ-11	16.1	Skute Stone Arroyo	-58	GWQ-11-58	5/23/1986	CFP	
GWQ-11	16.1	Skute Stone Arroyo	-59	GWQ-11-59	10/8/1986	CFP	
GWQ-11	14.54	Skute Stone Arroyo	-60	GWQ-11-60	3/4/1987	EID	

Well Name	Water Depth	USGS Quad	Well Depth	Sample ID	Date	Sampler	Notes
GWQ-11		Skute Stone Arroyo	-61	GWQ-11-61	5/25/1987		
GWQ-11	15	Skute Stone Arroyo	-62	GWQ-11-62	1/12/1988	EID	
GWQ-11		Skute Stone Arroyo	-63	GWQ-11-63	4/4/1988	Irwin	
GWQ-11	18.2	Skute Stone Arroyo	-64	GWQ-11-64	8/23/1988	Irwin	
GWQ-11	15.66	Skute Stone Arroyo	-65	GWQ-11-65	2/9/1989	Irwin	
GWQ-11	16.25	Skute Stone Arroyo	-66	GWQ-11-66	6/1/1989	Irwin	
GWQ-11	16.25	Skute Stone Arroyo	-67	GWQ-11-67	11/30/1989	Irwin	
GWQ-11	15.75	Skute Stone Arroyo	-68	GWQ-11-68	11/14/1990	GE	
GWQ-11		Skute Stone Arroyo	-69	GWQ-11-69	2/11/1991	SHB	
GWQ-11	17.9	Skute Stone Arroyo	-70	GWQ-11-70	7/19/1991	GE	
GWQ-11	17.42	Skute Stone Arroyo	-71	GWQ-11-71	8/29/1991	Irwin	lab pH
GWQ-11	16	Skute Stone Arroyo	-72	GWQ-11-72	11/26/1991	Hood	lab pH
GWQ-11	16	Skute Stone Arroyo	-73	GWQ-11-73	3/15/1992	Irwin	lab pH
GWQ-11		Skute Stone Arroyo	-74	GWQ-11-74	5/25/1992	Irwin	lab pH
GWQ-11	15.75	Skute Stone Arroyo	-75	GWQ-11-75	10/8/1992	Irwin	lab pH
GWQ-11	15.25	Skute Stone Arroyo	-76	GWQ-11-76	11/27/1992	Hood	lab pH
GWQ-11		Skute Stone Arroyo	-77	GWQ-11-77	12/15/1992	Irwin	lab pH
GWQ-11	16.17	Skute Stone Arroyo	-78	GWQ-11-78	2/25/1993	Irwin	lab pH
GWQ-11		Skute Stone Arroyo	-79	GWQ-11-79	3/30/1993	JWS	
GWQ-11		Skute Stone Arroyo	-80	GWQ-11-80	9/28/1993	Irwin	lab pH
GWQ-11	15.95	Skute Stone Arroyo	-81	GWQ-11-81	5/25/1994	SRK	
GWQ-11		Skute Stone Arroyo	-82	GWQ-11-82	6/23/1994	Irwin	lab pH
GWQ-11		Skute Stone Arroyo	-83	GWQ-11-83	7/22/1994	SRK	
GWQ-11		Skute Stone Arroyo	-84	GWQ-11-84	9/22/1994	Irwin	lab pH

Well Name	Date	Latitude	Longitude	UTM Easting	UTM Northing	UTM Zone	Elevation	Filtered?	Chloride	Sulfate
GWQ-10	11/13/1985	32.96325	107.49677	266630	3649790	13	5200	FALSE	42	149
GWQ-10	5/23/1986	32.96325	107.49677	266630	3649790	13	5200	FALSE	58	151
GWQ-10	10/8/1986	32.96325	107.49677	266630	3649790	13	5200	FALSE	54	137
GWQ-10	3/4/1987	32.96325	107.49677	266630	3649790	13	5200	TRUE	59	150
GWQ-10	5/25/1987	32.96325	107.49677	266630	3649790	13	5200	FALSE		154.2
GWQ-10	1/12/1988	32.96325	107.49677	266630	3649790	13	5200	TRUE	78.8	173
GWQ-10	4/4/1988	32.96325	107.49677	266630	3649790	13	5200	FALSE	65	170.6
GWQ-10	8/23/1988	32.96325	107.49677	266630	3649790	13	5200	FALSE	63	179.2
GWQ-10	2/9/1989	32.96325	107.49677	266630	3649790	13	5200	FALSE	76.3	180.5
GWQ-10	6/1/1989	32.96325	107.49677	266630	3649790	13	5200	FALSE	67.9	162.7
GWQ-10	11/30/1989	32.96325	107.49677	266630	3649790	13	5200	FALSE	72.1	161.7
GWQ-10	11/14/1990	32.96325	107.49677	266630	3649790	13	5200	FALSE	92.7	178
GWQ-10	2/11/1991	32.96325	107.49677	266630	3649790	13	5200	FALSE	78.1	213.5
GWQ-10	7/19/1991	32.96325	107.49677	266630	3649790	13	5200	TRUE	83.3	166.6
GWQ-10	8/29/1991	32.96325	107.49677	266630	3649790	13	5200	FALSE	84.7	191.7
GWQ-10	11/26/1991	32.96325	107.49677	266630	3649790	13	5200	FALSE	58.2	171.2
GWQ-10	3/15/1992	32.96325	107.49677	266630	3649790	13	5200	FALSE	82.5	191.6
GWQ-10	5/25/1992	32.96325	107.49677	266630	3649790	13	5200	FALSE	83.8	169.2
GWQ-10	7/16/1992	32.96325	107.49677	266630	3649790	13	5200	FALSE	76.3	166.6
GWQ-10	10/8/1992	32.96325	107.49677	266630	3649790	13	5200	FALSE	83.4	161.4
GWQ-10	11/27/1992	32.96325	107.49677	266630	3649790	13	5200	FALSE	80.3	174.4
GWQ-10	12/15/1992	32.96325	107.49677	266630	3649790	13	5200	FALSE	90.9	168.7
GWQ-10	2/25/1993	32.96325	107.49677	266630	3649790	13	5200	FALSE	95.5	175.8
GWQ-10	3/30/1993	32.96325	107.49677	266630	3649790	13	5200	FALSE	94	183
GWQ-10	9/28/1993	32.96325	107.49677	266630	3649790	13	5200	FALSE	96	142.6
GWQ-10	5/26/1994	32.96325	107.49677	266630	3649790	13	5200	FALSE	92	175
GWQ-10	6/23/1994	32.96325	107.49677	266630	3649790	13	5200	FALSE	103.6	191.6
GWQ-10	7/23/1994	32.96325	107.49677	266630	3649790	13	5200	TRUE	98	184
GWQ-10	9/22/1994	32.96325	107.49677	266630	3649790	13	5200	FALSE	89.2	155.8
GWQ-10	1/29/1995	32.96325	107.49677	266630	3649790	13	5200	FALSE	87.5	65.7
GWQ-10	3/29/1995	32.96325	107.49677	266630	3649790	13	5200	FALSE	84.9	176
GWQ-10	3/29/1995	32.96325	107.49677	266630	3649790	13	5200	FALSE	84.9	176
GWQ-10	6/27/1995	32.96325	107.49677	266630	3649790	13	5200	FALSE	84.8	168.7
GWQ-10	9/21/1995	32.96325	107.49677	266630	3649790	13	5200	FALSE	91.3	187.4
GWQ-10	1/10/1996	32.96325	107.49677	266630	3649790	13	5200	FALSE	97.7	197.5
GWQ-10	4/3/1996	32.96325	107.49677	266630	3649790	13	5200	FALSE	97.4	218.2

Well Name	Date	Latitude	Longitude	UTM Easting	UTM Northing	UTM Zone	Elevation	Filtered?	Chloride	Sulfate
GWQ-10	6/1/1996	32.96325	107.49677	266630	3649790	13	5200		94.2	190
GWQ-10	9/25/1996	32.96325	107.49677	266630	3649790	13	5200	TRUE	86.2	190.8
GWQ-10	1/15/1997	32.96325	107.49677	266630	3649790	13	5200	TRUE	91	203.67
GWQ-10	4/1/1997	32.96325	107.49677	266630	3649790	13	5200	TRUE	94.9	205
GWQ-10	7/1/1997	32.96325	107.49677	266630	3649790	13	5200	TRUE	91	197
GWQ-10	8/1/1997	32.96325	107.49677	266630	3649790	13	5200	TRUE	94.5	
GWQ-10	10/1/1997	32.96325	107.49677	266630	3649790	13	5200	TRUE	95	193
GWQ-10	10/1/1997	32.96325	107.49677	266630	3649790	13	5200	TRUE	17.9	19
GWQ-10	1/15/1998	32.96325	107.49677	266630	3649790	13	5200	TRUE	86	201
GWQ-10	4/9/1998	32.96325	107.49677	266630	3649790	13	5200	TRUE	92.2	206
GWQ-10	7/13/1998	32.96325	107.49677	266630	3649790	13	5200	TRUE	85	209
GWQ-10	10/15/1998	32.96325	107.49677	266630	3649790	13	5200	TRUE	17.9	19
GWQ-11	8/10/1981	32.96027	107.49667	266632	3649459	13	5183	TRUE	37	123
GWQ-11	10/27/1981	32.96027	107.49667	266632	3649459	13	5183	TRUE	36	183
GWQ-11	10/30/1981	32.96027	107.49667	266632	3649459	13	5183	FALSE	39.1	101
GWQ-11	11/6/1981	32.96027	107.49667	266632	3649459	13	5183	TRUE	36	168
GWQ-11	11/13/1981	32.96027	107.49667	266632	3649459	13	5183	TRUE	37.64	155.6
GWQ-11	11/17/1981	32.96027	107.49667	266632	3649459	13	5183	TRUE	36	165
GWQ-11	11/23/1981	32.96027	107.49667	266632	3649459	13	5183	TRUE	36	181
GWQ-11	12/7/1981	32.96027	107.49667	266632	3649459	13	5183	TRUE	56	184
GWQ-11	12/15/1981	32.96027	107.49667	266632	3649459	13	5183	TRUE	38	191
GWQ-11	12/22/1981	32.96027	107.49667	266632	3649459	13	5183	TRUE	40	185
GWQ-11	1/5/1982	32.96027	107.49667	266632	3649459	13	5183	TRUE	40	174
GWQ-11	1/18/1982	32.96027	107.49667	266632	3649459	13	5183	FALSE		
GWQ-11	1/26/1982	32.96027	107.49667	266632	3649459	13	5183	TRUE	40	168
GWQ-11	2/16/1982	32.96027	107.49667	266632	3649459	13	5183	FALSE		
GWQ-11	2/22/1982	32.96027	107.49667	266632	3649459	13	5183	TRUE	38	168
GWQ-11	3/12/1982	32.96027	107.49667	266632	3649459	13	5183	FALSE		
GWQ-11	4/16/1982	32.96027	107.49667	266632	3649459	13	5183	FALSE		
GWQ-11	4/26/1982	32.96027	107.49667	266632	3649459	13	5183	TRUE	40	165
GWQ-11	5/17/1982	32.96027	107.49667	266632	3649459	13	5183	TRUE	44	185
GWQ-11	6/8/1982	32.96027	107.49667	266632	3649459	13	5183	TRUE	44	185
GWQ-11	6/14/1982	32.96027	107.49667	266632	3649459	13	5183	FALSE		
GWQ-11	6/30/1982	32.96027	107.49667	266632	3649459	13	5183	TRUE	44	198
GWQ-11	7/26/1982	32.96027	107.49667	266632	3649459	13	5183	FALSE		
GWQ-11	8/18/1982	32.96027	107.49667	266632	3649459	13	5183	FALSE		

Well Name	Date	Latitude	Longitude	UTM Easting	UTM Northing	UTM Zone	Elevation	Filtered?	Chloride	Sulfate
GWQ-11	9/2/1982	32.96027	107.49667	266632	3649459	13	5183	TRUE	52.22	247.6
GWQ-11	9/14/1982	32.96027	107.49667	266632	3649459	13	5183	FALSE		
GWQ-11	10/18/1982	32.96027	107.49667	266632	3649459	13	5183	FALSE		
GWQ-11	11/11/1982	32.96027	107.49667	266632	3649459	13	5183	FALSE		
GWQ-11	12/23/1982	32.96027	107.49667	266632	3649459	13	5183	TRUE	52	235
GWQ-11	12/28/1982	32.96027	107.49667	266632	3649459	13	5183	FALSE		
GWQ-11	2/21/1983	32.96027	107.49667	266632	3649459	13	5183	TRUE	44	218
GWQ-11	5/6/1983	32.96027	107.49667	266632	3649459	13	5183	FALSE		
GWQ-11	5/13/1983	32.96027	107.49667	266632	3649459	13	5183	TRUE	44	206
GWQ-11	6/2/1983	32.96027	107.49667	266632	3649459	13	5183	FALSE		
GWQ-11	7/5/1983	32.96027	107.49667	266632	3649459	13	5183	FALSE		
GWQ-11	8/9/1983	32.96027	107.49667	266632	3649459	13	5183	TRUE	46	168
GWQ-11	8/25/1983	32.96027	107.49667	266632	3649459	13	5183	FALSE		
GWQ-11	10/20/1983	32.96027	107.49667	266632	3649459	13	5183	FALSE		
GWQ-11	11/1/1983	32.96027	107.49667	266632	3649459	13	5183	TRUE	46	174
GWQ-11	12/7/1984	32.96027	107.49667	266632	3649459	13	5183	FALSE		
GWQ-11	1/28/1984	32.96027	107.49667	266632	3649459	13	5183	FALSE		
GWQ-11	2/13/1984	32.96027	107.49667	266632	3649459	13	5183	FALSE		
GWQ-11	3/1/1984	32.96027	107.49667	266632	3649459	13	5183	FALSE		
GWQ-11	3/16/1984	32.96027	107.49667	266632	3649459	13	5183	TRUE	52	184
GWQ-11	4/18/1984	32.96027	107.49667	266632	3649459	13	5183	FALSE		
GWQ-11	5/22/1984	32.96027	107.49667	266632	3649459	13	5183	FALSE		
GWQ-11	5/30/1984	32.96027	107.49667	266632	3649459	13	5183	TRUE	58	195
GWQ-11	6/26/1984	32.96027	107.49667	266632	3649459	13	5183	FALSE		
GWQ-11	7/25/1984	32.96027	107.49667	266632	3649459	13	5183	FALSE		
GWQ-11	8/27/1984	32.96027	107.49667	266632	3649459	13	5183	FALSE		
GWQ-11	9/12/1984	32.96027	107.49667	266632	3649459	13	5183	TRUE	60	181
GWQ-11	9/21/1984	32.96027	107.49667	266632	3649459	13	5183	FALSE		
GWQ-11	11/19/1984	32.96027	107.49667	266632	3649459	13	5183	FALSE		
GWQ-11	11/27/1984	32.96027	107.49667	266632	3649459	13	5183	TRUE	60	165
GWQ-11	12/17/1984	32.96027	107.49667	266632	3649459	13	5183	FALSE		
GWQ-11	5/17/1985	32.96027	107.49667	266632	3649459	13	5183	FALSE	64	197
GWQ-11	11/13/1985	32.96027	107.49667	266632	3649459	13	5183	FALSE	62	183
GWQ-11	5/23/1986	32.96027	107.49667	266632	3649459	13	5183	FALSE	66	210
GWQ-11	10/8/1986	32.96027	107.49667	266632	3649459	13	5183	FALSE	70	200
GWQ-11	3/4/1987	32.96027	107.49667	266632	3649459	13	5183	TRUE	69	200

Well Name	Date	Latitude	Longitude	UTM Easting	UTM Northing	UTM Zone	Elevation	Filtered?	Chloride	Sulfate
GWQ-11	5/25/1987	32.96027	107.49667	266632	3649459	13	5183	FALSE		230
GWQ-11	1/12/1988	32.96027	107.49667	266632	3649459	13	5183	TRUE	77.1	253
GWQ-11	4/4/1988	32.96027	107.49667	266632	3649459	13	5183	FALSE	74.6	277.7
GWQ-11	8/23/1988	32.96027	107.49667	266632	3649459	13	5183	FALSE	73	293.8
GWQ-11	2/9/1989	32.96027	107.49667	266632	3649459	13	5183	FALSE	77	258.4
GWQ-11	6/1/1989	32.96027	107.49667	266632	3649459	13	5183	FALSE	69.7	238.2
GWQ-11	11/30/1989	32.96027	107.49667	266632	3649459	13	5183	FALSE	79.8	254.3
GWQ-11	11/14/1990	32.96027	107.49667	266632	3649459	13	5183	FALSE	104.4	257.4
GWQ-11	2/11/1991	32.96027	107.49667	266632	3649459	13	5183	FALSE	88.9	233.4
GWQ-11	7/19/1991	32.96027	107.49667	266632	3649459	13	5183	TRUE	89.7	210.2
GWQ-11	8/29/1991	32.96027	107.49667	266632	3649459	13	5183	FALSE	92.6	278.6
GWQ-11	11/26/1991	32.96027	107.49667	266632	3649459	13	5183	FALSE	89.3	240.7
GWQ-11	3/15/1992	32.96027	107.49667	266632	3649459	13	5183	FALSE	65.1	260.2
GWQ-11	5/25/1992	32.96027	107.49667	266632	3649459	13	5183	FALSE	96.2	258.1
GWQ-11	10/8/1992	32.96027	107.49667	266632	3649459	13	5183	FALSE	96	226.9
GWQ-11	11/27/1992	32.96027	107.49667	266632	3649459	13	5183	FALSE	96	248.4
GWQ-11	12/15/1992	32.96027	107.49667	266632	3649459	13	5183	FALSE	98.1	220
GWQ-11	2/25/1993	32.96027	107.49667	266632	3649459	13	5183	FALSE	104	273.3
GWQ-11	3/30/1993	32.96027	107.49667	266632	3649459	13	5183	FALSE	104	271
GWQ-11	9/28/1993	32.96027	107.49667	266632	3649459	13	5183	FALSE	105.6	207.7
GWQ-11	5/25/1994	32.96027	107.49667	266632	3649459	13	5183	FALSE	110	260
GWQ-11	6/23/1994	32.96027	107.49667	266632	3649459	13	5183	FALSE	117.2	274.6
GWQ-11	7/22/1994	32.96027	107.49667	266632	3649459	13	5183	TRUE	116	272
GWQ-11	9/22/1994	32.96027	107.49667	266632	3649459	13	5183	FALSE	112.3	234.5

Well Name	Date	pH	TDS	Alkalinity	Bicarb	Spec. Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
GWQ-10	11/13/1985	7.7	500								
GWQ-10	5/23/1986	7.9	560								
GWQ-10	10/8/1986	7.5	550								
GWQ-10	3/4/1987		568		256	740			-0.1	0.9	
GWQ-10	5/25/1987										
GWQ-10	1/12/1988		648		243				-0.1		
GWQ-10	4/4/1988		552								
GWQ-10	8/23/1988		692								
GWQ-10	2/9/1989		618								
GWQ-10	6/1/1989		604								
GWQ-10	11/30/1989		620								
GWQ-10	11/14/1990		635								
GWQ-10	2/11/1991		696								-0.001
GWQ-10	7/19/1991	8.05	645	198	241.6	975	0.51	3.88			0.002
GWQ-10	8/29/1991	7.44	665								
GWQ-10	11/26/1991	7.46	648								
GWQ-10	3/15/1992	7.85	641								
GWQ-10	5/25/1992	7.41	621								
GWQ-10	7/16/1992	7.51	626								
GWQ-10	10/8/1992	7.43	659								
GWQ-10	11/27/1992	7.89	654								
GWQ-10	12/15/1992	7.48	582								
GWQ-10	2/25/1993	7.39	620								
GWQ-10	3/30/1993	7.8	642		254	1020	0.52	3.9	-0.1		-0.005
GWQ-10	9/28/1993	7.7	693								
GWQ-10	5/26/1994	7.82	1000		232	1050	0.51	3.5	0.85	-0.005	-0.005
GWQ-10	6/23/1994	7.97	671								
GWQ-10	7/23/1994	7.97	696		238	1050	0.49	3.5	-0.05	-0.005	-0.005
GWQ-10	9/22/1994	7.45	668								
GWQ-10	1/29/1995	7.52	672								
GWQ-10	3/29/1995	7.67	62								
GWQ-10	3/29/1995	7.67	622								
GWQ-10	6/27/1995	7.29	677								
GWQ-10	9/21/1995	7.42	693								
GWQ-10	1/10/1996	7.29	654								
GWQ-10	4/3/1996	6.95	628								

Well Name	Date	pH	TDS	Alkalinity	Bicarb	Spec. Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
GWQ-10	6/1/1996	7.29	637								
GWQ-10	9/25/1996	7.56	679								
GWQ-10	1/15/1997	7.59	746								
GWQ-10	4/1/1997		659				0.4				
GWQ-10	7/1/1997	7.34	689								
GWQ-10	8/1/1997	7.23	683				0.6				
GWQ-10	10/1/1997	7.52	662								
GWQ-10	10/1/1997	7.57	304					-0.05			
GWQ-10	1/15/1998	7.45	637			1090	0.56	3.3			
GWQ-10	4/9/1998		674			1200	0.56	3.8			
GWQ-10	7/13/1998		661			973	0.58	3.5			
GWQ-10	10/15/1998	7.57	304			551		-0.05			
GWQ-11	8/10/1981	7.38	612		237		0.9	1.02	-0.25		-0.004
GWQ-11	10/27/1981	8.1	550				1	0.7	-0.01		-0.01
GWQ-11	10/30/1981	8.4	536				0.96	0.61	-0.25		-0.005
GWQ-11	11/6/1981	8.1	520				1	1.5	-0.01		-0.01
GWQ-11	11/13/1981	7.7	544		241.1	700	0.99	1.33	-0.25		-0.005
GWQ-11	11/17/1981	8	520				1	1.3	-0.01		-0.01
GWQ-11	11/23/1981	7.8	570				0.9	1.7	-0.01		-0.01
GWQ-11	12/7/1981	7.9	560				0.9	1.6	-0.01		-0.01
GWQ-11	12/15/1981	7.9	570				1	1.5	-0.01		-0.01
GWQ-11	12/22/1981	8	530				0.5	1.9	-0.01		-0.01
GWQ-11	1/5/1982	7.5	480				1	2.5	-0.01		-0.01
GWQ-11	1/18/1982										
GWQ-11	1/26/1982	7.9	500				1	1.7			
GWQ-11	2/16/1982										
GWQ-11	2/22/1982	7.7	510				0.9	1.4			
GWQ-11	3/12/1982										
GWQ-11	4/16/1982										
GWQ-11	4/26/1982	7.6	510				0.8	1.3			
GWQ-11	5/17/1982	7.8	510				0.8	1.9			
GWQ-11	6/8/1982	7.9	530				0.8	1.7			
GWQ-11	6/14/1982										
GWQ-11	6/30/1982	7.9	590								
GWQ-11	7/26/1982										
GWQ-11	8/18/1982										

Well Name	Date	pH	TDS	Alkalinity	Bicarb	Spec. Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
GWQ-11	9/2/1982	7.3	700		226	940	0.78	1.94			
GWQ-11	9/14/1982										
GWQ-11	10/18/1982										
GWQ-11	11/11/1982										
GWQ-11	12/23/1982	8.5	650				0.8	1.6			
GWQ-11	12/28/1982										
GWQ-11	2/21/1983	8	600				0.8	1.7			
GWQ-11	5/6/1983										
GWQ-11	5/13/1983	8.1	570				0.8	1.9			
GWQ-11	6/2/1983										
GWQ-11	7/5/1983										
GWQ-11	8/9/1983	7.9	580				0.8	2			
GWQ-11	8/25/1983										
GWQ-11	10/20/1983										
GWQ-11	11/1/1983	8	580				0.8	4.8			
GWQ-11	12/7/1984										
GWQ-11	1/28/1984										
GWQ-11	2/13/1984										
GWQ-11	3/1/1984										
GWQ-11	3/16/1984	8.3	540				0.6	3.8			
GWQ-11	4/18/1984										
GWQ-11	5/22/1984										
GWQ-11	5/30/1984	7.5	550				0.8	1.9			
GWQ-11	6/26/1984										
GWQ-11	7/25/1984										
GWQ-11	8/27/1984										
GWQ-11	9/12/1984	7.9	590				0.8	2.3			
GWQ-11	9/21/1984										
GWQ-11	11/19/1984										
GWQ-11	11/27/1984	7.7	570				0.8	2.3			
GWQ-11	12/17/1984										
GWQ-11	5/17/1985	7.8	640								
GWQ-11	11/13/1985	7.7	600								
GWQ-11	5/23/1986	7.8	650								
GWQ-11	10/8/1986	7.6	560								
GWQ-11	3/4/1987	6.7	696		220	820			-0.1	1.1	

Well Name	Date	pH	TDS	Alkalinity	Bicarb	Spec. Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
GWQ-11	5/25/1987										
GWQ-11	1/12/1988		718		214				-0.1		
GWQ-11	4/4/1988		694								
GWQ-11	8/23/1988		772								
GWQ-11	2/9/1989		730								
GWQ-11	6/1/1989		708								
GWQ-11	11/30/1989		732								
GWQ-11	11/14/1990		746								
GWQ-11	2/11/1991		790								-0.001
GWQ-11	7/19/1991	7.36	785	181	220.9	1100	0.74	3.93			0.004
GWQ-11	8/29/1991	7.46	771								
GWQ-11	11/26/1991	7.29	770								
GWQ-11	3/15/1992	7.91	765								
GWQ-11	5/25/1992	7.45	761								
GWQ-11	10/8/1992	7.42	755								
GWQ-11	11/27/1992	7.85	763								
GWQ-11	12/15/1992	7.59	741								
GWQ-11	2/25/1993	7.64	762								
GWQ-11	3/30/1993	7.7	776		227	1170	0.52	4.1	0.2		-0.005
GWQ-11	9/28/1993	7.57	800								
GWQ-11	5/25/1994	7.88	820		199	1130	0.72	3.8	0.14	-0.005	-0.005
GWQ-11	6/23/1994	7.42	802								
GWQ-11	7/22/1994	7.7	808		207	1210	0.7	3.8	-0.054	0.0055	-0.005
GWQ-11	9/22/1994	7.37	816								

Well Name	Date	Boron	Barium	Berrylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
GWQ-10	11/13/1985										
GWQ-10	5/23/1986										
GWQ-10	10/8/1986										
GWQ-10	3/4/1987	-0.1	-0.1	-0.1	-0.1	90	-0.1	-0.05	-0.1	-0.1	-0.1
GWQ-10	5/25/1987	-0.1	-0.1	-0.1	-0.1						
GWQ-10	1/12/1988	-0.1	-0.1	-0.1	-0.1	116	-0.1	-0.05	-0.1	-0.1	-0.1
GWQ-10	4/4/1988										
GWQ-10	8/23/1988										
GWQ-10	2/9/1989										
GWQ-10	6/1/1989										
GWQ-10	11/30/1989										
GWQ-10	11/14/1990										
GWQ-10	2/11/1991										
GWQ-10	7/19/1991		0.02		-0.005	106.3	-0.02			0.07	-0.005
GWQ-10	8/29/1991										
GWQ-10	11/26/1991										
GWQ-10	3/15/1992										
GWQ-10	5/25/1992										
GWQ-10	7/16/1992										
GWQ-10	10/8/1992										
GWQ-10	11/27/1992										
GWQ-10	12/15/1992										
GWQ-10	2/25/1993										
GWQ-10	3/30/1993	0.04	-0.5		-0.002	104	-0.02	-0.05	-0.01	-0.05	-0.02
GWQ-10	9/28/1993										
GWQ-10	5/26/1994		-0.1		-0.0005	100	-0.025		0.026	1.1	-0.005
GWQ-10	6/23/1994										
GWQ-10	7/23/1994	-0.1	-0.1	-0.002	-0.0005	110	-0.025	-0.05	-0.025	-0.05	-0.005
GWQ-10	9/22/1994										
GWQ-10	1/29/1995										
GWQ-10	3/29/1995										
GWQ-10	3/29/1995										
GWQ-10	6/27/1995										
GWQ-10	9/21/1995										
GWQ-10	1/10/1996										
GWQ-10	4/3/1996										

Well Name	Date	Boron	Barium	Berrylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
GWQ-10	6/1/1996										
GWQ-10	9/25/1996										
GWQ-10	1/15/1997										
GWQ-10	4/1/1997								-0.005	0.15	
GWQ-10	7/1/1997										
GWQ-10	8/1/1997										
GWQ-10	10/1/1997										
GWQ-10	10/1/1997								-0.005	-0.05	
GWQ-10	1/15/1998								-0.005	0.05	
GWQ-10	4/9/1998								-0.005	-0.05	
GWQ-10	7/13/1998								-0.005	0.09	
GWQ-10	10/15/1998								-0.005	-0.05	
GWQ-11	8/10/1981	0.092	-1		-0.01	68.3	-0.05	-0.05	-0.05	1.14	-0.05
GWQ-11	10/27/1981	-0.01	-0.2		-0.005	72	-0.01	-0.02	-0.05	-0.1	-0.02
GWQ-11	10/30/1981	0.55	-1		-0.01		-0.05	-0.05	-0.05	-0.1	-0.05
GWQ-11	11/6/1981	-0.1	-0.2		-0.005	67	-0.01	-0.02	-0.05	-0.1	-0.02
GWQ-11	11/13/1981	0.041	-0.2		0.001	82.6	-0.05				-0.005
GWQ-11	11/17/1981	-0.1	-0.2		-0.005	71	-0.01	-0.02	-0.05	-0.1	-0.02
GWQ-11	11/23/1981	-0.1	-0.2		-0.005	67	-0.01	-0.02	-0.05	-0.1	-0.02
GWQ-11	12/7/1981	-0.1	-0.2		-0.005	57	-0.01	-0.02	-0.05	-0.1	-0.02
GWQ-11	12/15/1981	-0.1	-0.2		-0.005	85	-0.01	-0.02	-0.05	-0.1	-0.02
GWQ-11	12/22/1981	-0.1	-0.2		-0.005	82	-0.01	-0.02	-0.05	0.27	-0.02
GWQ-11	1/5/1982	-0.1	-0.2		-0.005	79	-0.01	-0.02	-0.05	0.14	-0.02
GWQ-11	1/18/1982										
GWQ-11	1/26/1982				-0.005				-0.05	-0.1	
GWQ-11	2/16/1982								-0.05		
GWQ-11	2/22/1982				-0.005				-0.05	0.11	
GWQ-11	3/12/1982										
GWQ-11	4/16/1982										
GWQ-11	4/26/1982				-0.005				-0.05	0.36	
GWQ-11	5/17/1982				-0.005				-0.05	0.11	
GWQ-11	6/8/1982				-0.005				-0.05	-0.1	
GWQ-11	6/14/1982										
GWQ-11	6/30/1982								-0.05	0.39	
GWQ-11	7/26/1982										
GWQ-11	8/18/1982										

Well Name	Date	Boron	Barium	Berrylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
GWQ-11	9/2/1982				-0.001	111.2					
GWQ-11	9/14/1982										
GWQ-11	10/18/1982										
GWQ-11	11/11/1982										
GWQ-11	12/23/1982					-0.005			-0.05	-0.1	
GWQ-11	12/28/1982										
GWQ-11	2/21/1983				-0.005				-0.05	0.38	
GWQ-11	5/6/1983										
GWQ-11	5/13/1983				-0.005				-0.05	-0.1	
GWQ-11	6/2/1983										
GWQ-11	7/5/1983										
GWQ-11	8/9/1983				-0.005				-0.05	-0.1	
GWQ-11	8/25/1983										
GWQ-11	10/20/1983										
GWQ-11	11/1/1983				-0.005				-0.05	-0.1	
GWQ-11	12/7/1984										
GWQ-11	1/28/1984										
GWQ-11	2/13/1984										
GWQ-11	3/1/1984										
GWQ-11	3/16/1984				-0.005				-0.05	-0.1	
GWQ-11	4/18/1984										
GWQ-11	5/22/1984										
GWQ-11	5/30/1984				-0.005				-0.05	-0.1	
GWQ-11	6/26/1984										
GWQ-11	7/25/1984										
GWQ-11	8/27/1984										
GWQ-11	9/12/1984				-0.005				-0.05	-0.1	
GWQ-11	9/21/1984										
GWQ-11	11/19/1984										
GWQ-11	11/27/1984				-0.005				-0.05	-0.1	
GWQ-11	12/17/1984										
GWQ-11	5/17/1985										
GWQ-11	11/13/1985										
GWQ-11	5/23/1986										
GWQ-11	10/8/1986										
GWQ-11	3/4/1987	-0.1	-0.1	-0.1	-0.1	108	-0.1	-0.05	-0.1	-0.1	-0.1

Well Name	Date	Boron	Barium	Berrylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
GWQ-11	5/25/1987										
GWQ-11	1/12/1988	-0.1	-0.1	-0.1	-0.1	128	-0.1	-0.05	-0.1	-0.1	-0.1
GWQ-11	4/4/1988										
GWQ-11	8/23/1988										
GWQ-11	2/9/1989										
GWQ-11	6/1/1989										
GWQ-11	11/30/1989										
GWQ-11	11/14/1990										
GWQ-11	2/11/1991										
GWQ-11	7/19/1991		0.1		-0.005	122.5	-0.02			-0.05	-0.002
GWQ-11	8/29/1991										
GWQ-11	11/26/1991										
GWQ-11	3/15/1992										
GWQ-11	5/25/1992										
GWQ-11	10/8/1992										
GWQ-11	11/27/1992										
GWQ-11	12/15/1992								0.017		
GWQ-11	2/25/1993										
GWQ-11	3/30/1993	0.04	-0.5		-0.002	126	-0.02	-0.05	-0.01	0.33	-0.02
GWQ-11	9/28/1993										
GWQ-11	5/25/1994		-0.1		-0.0005	120	-0.025		-0.025	0.16	-0.005
GWQ-11	6/23/1994										
GWQ-11	7/22/1994	-0.1	-0.1	-0.002	-0.0005	140	-0.025	-0.05	-0.25	-0.05	-0.005
GWQ-11	9/22/1994										

Well Name	Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium	Thallium
GWQ-10	11/13/1985										
GWQ-10	5/23/1986										
GWQ-10	10/8/1986										
GWQ-10	3/4/1987	20.7	-0.05		-0.1	-0.1	2.34		-0.1	73.6	
GWQ-10	5/25/1987										
GWQ-10	1/12/1988	24	-0.05		-0.1	-0.01	3		-0.1	64	
GWQ-10	4/4/1988										
GWQ-10	8/23/1988										
GWQ-10	2/9/1989										
GWQ-10	6/1/1989										
GWQ-10	11/30/1989										
GWQ-10	11/14/1990										
GWQ-10	2/11/1991										
GWQ-10	7/19/1991	24.1	-0.02	-0.0002			3.9	0.002	-0.02	46.9	
GWQ-10	8/29/1991										
GWQ-10	11/26/1991										
GWQ-10	3/15/1992										
GWQ-10	5/25/1992										
GWQ-10	7/16/1992										
GWQ-10	10/8/1992										
GWQ-10	11/27/1992										
GWQ-10	12/15/1992										
GWQ-10	2/25/1993										
GWQ-10	3/30/1993	27	-0.02	-0.001	-0.02	-0.01	2.3	-0.005	-0.01	71	
GWQ-10	9/28/1993										
GWQ-10	5/26/1994	25	0.059	-0.001		-0.05	3.1	-0.005	-0.025	56	
GWQ-10	6/23/1994										
GWQ-10	7/23/1994	26	-0.03	-0.001	-0.05	-0.05	2.8	-0.005	-0.025	66	-0.005
GWQ-10	9/22/1994										
GWQ-10	1/29/1995										
GWQ-10	3/29/1995										
GWQ-10	3/29/1995										
GWQ-10	6/27/1995										
GWQ-10	9/21/1995										
GWQ-10	1/10/1996										
GWQ-10	4/3/1996										

Well Name	Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium	Thallium
GWQ-10	6/1/1996										
GWQ-10	9/25/1996										
GWQ-10	1/15/1997										
GWQ-10	4/1/1997		-0.02								
GWQ-10	7/1/1997										
GWQ-10	8/1/1997										
GWQ-10	10/1/1997										
GWQ-10	10/1/1997										
GWQ-10	1/15/1998	25.3		-0.0002	-0.05			-0.05			
GWQ-10	4/9/1998		-0.02	-0.0002	-0.05			-0.05			
GWQ-10	7/13/1998		0.06	-0.0002	-0.05			-0.05			
GWQ-10	10/15/1998										
GWQ-11	8/10/1981	13.5	0.45	0.1	-0.1	-0.05	7.88	0.006	-0.02	48.1	
GWQ-11	10/27/1981		-0.05	-0.001	-0.05	-0.05		-0.005	-0.02		
GWQ-11	10/30/1981		-0.02	-0.001	-0.1	-0.02		-0.011	-0.02		
GWQ-11	11/6/1981		-0.05	-0.001	-0.05	-0.05		-0.005	-0.02		
GWQ-11	11/13/1981	17.2	-0.05	-0.0005	0.12	-0.05	3.9	0.023	-0.001	43.7	
GWQ-11	11/17/1981		-0.05	-0.001	-0.05	-0.05		-0.005	-0.02		
GWQ-11	11/23/1981		-0.05	-0.001	-0.05	-0.05		-0.005	-0.02		
GWQ-11	12/7/1981		-0.05	0.0064	-0.05	-0.05		-0.005	-0.02		
GWQ-11	12/15/1981		-0.05	-0.001	-0.05	-0.05		-0.005	-0.02		
GWQ-11	12/22/1981		0.093	-0.001	-0.05	-0.05		-0.005	-0.02		
GWQ-11	1/5/1982		-0.05	-0.001	-0.05	-0.05		-0.005	-0.02		
GWQ-11	1/18/1982										
GWQ-11	1/26/1982		-0.05	-0.001	-0.1			-0.005			
GWQ-11	2/16/1982										
GWQ-11	2/22/1982		-0.05	-0.001	-0.05			-0.005			
GWQ-11	3/12/1982										
GWQ-11	4/16/1982										
GWQ-11	4/26/1982		-0.05	-0.001	0.05			-0.005			
GWQ-11	5/17/1982		-0.05	-0.001	-0.05			-0.005			
GWQ-11	6/8/1982		-0.05	-0.001	-0.05			-0.005			
GWQ-11	6/14/1982										
GWQ-11	6/30/1982		-0.05	-0.001	-0.05			-0.005			
GWQ-11	7/26/1982										
GWQ-11	8/18/1982										

Well Name	Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium	Thallium
GWQ-11	9/2/1982	27.6	-0.05		-0.01		3.51	-0.005		57.5	
GWQ-11	9/14/1982										
GWQ-11	10/18/1982										
GWQ-11	11/11/1982										
GWQ-11	12/23/1982		-0.05	-0.001	-0.05			-0.005			
GWQ-11	12/28/1982										
GWQ-11	2/21/1983		-0.05	-0.001	-0.05			-0.005			
GWQ-11	5/6/1983										
GWQ-11	5/13/1983		-0.05	-0.001	-0.05			-0.005			
GWQ-11	6/2/1983										
GWQ-11	7/5/1983										
GWQ-11	8/9/1983		-0.05	-0.001	-0.05			-0.005			
GWQ-11	8/25/1983										
GWQ-11	10/20/1983										
GWQ-11	11/1/1983		-0.05	-0.001	-0.05			-0.005			
GWQ-11	12/7/1984										
GWQ-11	1/28/1984										
GWQ-11	2/13/1984										
GWQ-11	3/1/1984										
GWQ-11	3/16/1984		-0.05	-0.001	-0.05			-0.005			
GWQ-11	4/18/1984										
GWQ-11	5/22/1984										
GWQ-11	5/30/1984		-0.05	-0.001	-0.05			-0.005			
GWQ-11	6/26/1984										
GWQ-11	7/25/1984										
GWQ-11	8/27/1984										
GWQ-11	9/12/1984		-0.05	-0.001	-0.05						
GWQ-11	9/21/1984										
GWQ-11	11/19/1984										
GWQ-11	11/27/1984		-0.05	-0.001	-0.05			-0.005			
GWQ-11	12/17/1984										
GWQ-11	5/17/1985										
GWQ-11	11/13/1985										
GWQ-11	5/23/1986										
GWQ-11	10/8/1986										
GWQ-11	3/4/1987	26.1	-0.05		-0.1	-0.1	3.51		-0.1	62.1	

Well Name	Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium	Thallium
GWQ-11	5/25/1987										
GWQ-11	1/12/1988	31	-0.005		-0.1	-0.1	4		-0.1	63	
GWQ-11	4/4/1988										
GWQ-11	8/23/1988										
GWQ-11	2/9/1989										
GWQ-11	6/1/1989										
GWQ-11	11/30/1989										
GWQ-11	11/14/1990										
GWQ-11	2/11/1991										
GWQ-11	7/19/1991	33.6	-0.02	-0.0002			3.9	0.002	-0.02	40.1	
GWQ-11	8/29/1991										
GWQ-11	11/26/1991										
GWQ-11	3/15/1992										
GWQ-11	5/25/1992										
GWQ-11	10/8/1992										
GWQ-11	11/27/1992										
GWQ-11	12/15/1992										
GWQ-11	2/25/1993										
GWQ-11	3/30/1993	34	0.03	-0.001	-0.02	-0.01	2.9	-0.005	-0.01	68	
GWQ-11	9/28/1993										
GWQ-11	5/25/1994	34	-0.03	-0.001		-0.05	3.5	-0.005	-0.025	55	
GWQ-11	6/23/1994										
GWQ-11	7/22/1994	37	-0.03	-0.001	-0.05	-0.05	3.4	-0.005	-0.025	66	-0.005
GWQ-11	9/22/1994										

Well Name	Date	Zinc	Temp (C)	Tin	Vanadium
GWQ-10	11/13/1985				
GWQ-10	5/23/1986				
GWQ-10	10/8/1986				
GWQ-10	3/4/1987	-0.1	21.5	-0.1	-0.1
GWQ-10	5/25/1987				
GWQ-10	1/12/1988	-0.1		0.2	-0.1
GWQ-10	4/4/1988				
GWQ-10	8/23/1988				
GWQ-10	2/9/1989				
GWQ-10	6/1/1989				
GWQ-10	11/30/1989				
GWQ-10	11/14/1990				
GWQ-10	2/11/1991				
GWQ-10	7/19/1991				
GWQ-10	8/29/1991				
GWQ-10	11/26/1991				
GWQ-10	3/15/1992				
GWQ-10	5/25/1992				
GWQ-10	7/16/1992				
GWQ-10	10/8/1992				
GWQ-10	11/27/1992				
GWQ-10	12/15/1992				
GWQ-10	2/25/1993				
GWQ-10	3/30/1993	0.11			
GWQ-10	9/28/1993				
GWQ-10	5/26/1994	0.55			
GWQ-10	6/23/1994				
GWQ-10	7/23/1994	-0.05			
GWQ-10	9/22/1994				
GWQ-10	1/29/1995				
GWQ-10	3/29/1995				
GWQ-10	3/29/1995				
GWQ-10	6/27/1995				
GWQ-10	9/21/1995				
GWQ-10	1/10/1996				
GWQ-10	4/3/1996				

Well Name	Date	Zinc	Temp (C)	Tin	Vanadium
GWQ-10	6/1/1996				
GWQ-10	9/25/1996				
GWQ-10	1/15/1997				
GWQ-10	4/1/1997				
GWQ-10	7/1/1997				
GWQ-10	8/1/1997				
GWQ-10	10/1/1997				
GWQ-10	10/1/1997				
GWQ-10	1/15/1998				
GWQ-10	4/9/1998				
GWQ-10	7/13/1998				
GWQ-10	10/15/1998				
GWQ-11	8/10/1981	-0.05			
GWQ-11	10/27/1981	0.17			
GWQ-11	10/30/1981	0.23			
GWQ-11	11/6/1981	0.29			
GWQ-11	11/13/1981	0.79	21		
GWQ-11	11/17/1981	0.64			
GWQ-11	11/23/1981	0.53			
GWQ-11	12/7/1981	1.6			
GWQ-11	12/15/1981	1.1			
GWQ-11	12/22/1981	0.42			
GWQ-11	1/5/1982	0.44			
GWQ-11	1/18/1982				
GWQ-11	1/26/1982				
GWQ-11	2/16/1982				
GWQ-11	2/22/1982				
GWQ-11	3/12/1982				
GWQ-11	4/16/1982				
GWQ-11	4/26/1982				
GWQ-11	5/17/1982				
GWQ-11	6/8/1982				
GWQ-11	6/14/1982				
GWQ-11	6/30/1982				
GWQ-11	7/26/1982				
GWQ-11	8/18/1982				

Well Name	Date	Zinc	Temp (C)	Tin	Vanadium
GWQ-11	9/2/1982		23		
GWQ-11	9/14/1982				
GWQ-11	10/18/1982				
GWQ-11	11/11/1982				
GWQ-11	12/23/1982				
GWQ-11	12/28/1982				
GWQ-11	2/21/1983				
GWQ-11	5/6/1983				
GWQ-11	5/13/1983				
GWQ-11	6/2/1983				
GWQ-11	7/5/1983				
GWQ-11	8/9/1983				
GWQ-11	8/25/1983				
GWQ-11	10/20/1983				
GWQ-11	11/1/1983				
GWQ-11	12/7/1984				
GWQ-11	1/28/1984				
GWQ-11	2/13/1984				
GWQ-11	3/1/1984				
GWQ-11	3/16/1984				
GWQ-11	4/18/1984				
GWQ-11	5/22/1984				
GWQ-11	5/30/1984				
GWQ-11	6/26/1984				
GWQ-11	7/25/1984				
GWQ-11	8/27/1984				
GWQ-11	9/12/1984				
GWQ-11	9/21/1984				
GWQ-11	11/19/1984				
GWQ-11	11/27/1984				
GWQ-11	12/17/1984				
GWQ-11	5/17/1985				
GWQ-11	11/13/1985				
GWQ-11	5/23/1986				
GWQ-11	10/8/1986				
GWQ-11	3/4/1987	-0.1	15	-0.1	-0.1

Well Name	Date	Zinc	Temp (C)	Tin	Vanadium
GWQ-11	5/25/1987				
GWQ-11	1/12/1988	-0.1		0.2	-0.1
GWQ-11	4/4/1988				
GWQ-11	8/23/1988				
GWQ-11	2/9/1989				
GWQ-11	6/1/1989				
GWQ-11	11/30/1989				
GWQ-11	11/14/1990				
GWQ-11	2/11/1991				
GWQ-11	7/19/1991				
GWQ-11	8/29/1991				
GWQ-11	11/26/1991				
GWQ-11	3/15/1992				
GWQ-11	5/25/1992				
GWQ-11	10/8/1992				
GWQ-11	11/27/1992				
GWQ-11	12/15/1992				
GWQ-11	2/25/1993				
GWQ-11	3/30/1993	0.03			
GWQ-11	9/28/1993				
GWQ-11	5/25/1994	-0.05			
GWQ-11	6/23/1994				
GWQ-11	7/22/1994	-0.05			
GWQ-11	9/22/1994				

Well Name	Water Depth	USGS Quad	Well Depth	Sample ID	Date	Sampler	Notes
GWQ-11		Skute Stone Arroyo	-85	GWQ-11-85	01/29/95	Irwin	lab pH
GWQ-11		Skute Stone Arroyo	-86	GWQ-11-86	03/29/95	Irwin	lab pH
GWQ-11	17.42	Skute Stone Arroyo	-87	GWQ-11-87	06/27/95	Irwin	lab pH
GWQ-11		Skute Stone Arroyo	-88	GWQ-11-88	09/21/95	Irwin	lab pH
GWQ-11		Skute Stone Arroyo	-89	GWQ-11-89	01/10/96	Irwin	lab pH
GWQ-11		Skute Stone Arroyo	-90	GWQ-11-90	04/03/96	Irwin	lab pH
GWQ-11		Skute Stone Arroyo	-91	GWQ-11-91	06/01/96		
GWQ-11		Skute Stone Arroyo	-92	GWQ-11-92	09/25/96	Irwin	lab pH
GWQ-11		Skute Stone Arroyo	-93	GWQ-11-93	01/15/97	Irwin	lab pH
GWQ-11		Skute Stone Arroyo	-94	GWQ-11-94	04/01/97		
GWQ-11		Skute Stone Arroyo	-95	GWQ-11-95	04/01/97		
GWQ-11		Skute Stone Arroyo	-96	GWQ-11-96	07/01/97		
GWQ-11		Skute Stone Arroyo	-97	GWQ-11-97	08/01/97		
GWQ-11		Skute Stone Arroyo	-98	GWQ-11-98	10/01/97		
GWQ-11	18.5	Skute Stone Arroyo	-99	GWQ-11-99	01/15/98	Irwin	
GWQ-11	18.5	Skute Stone Arroyo	-100	GWQ-11-100	04/09/98	Irwin	
GWQ-11	18.75	Skute Stone Arroyo	-101	GWQ-11-101	07/13/98	Irwin	
GWQ-12	100.33	Skute Stone Arroyo	-1	GWQ-12-1	05/17/82	QMC	
GWQ-12	100.33	Skute Stone Arroyo	-2	GWQ-12-2	06/14/82	QMC	
GWQ-12	100.25	Skute Stone Arroyo	-3	GWQ-12-3	07/26/82	QMC	
GWQ-12	100.5	Skute Stone Arroyo	-4	GWQ-12-4	08/18/82	QMC	
GWQ-12	100.5	Skute Stone Arroyo	-5	GWQ-12-5	09/14/82	QMC	
GWQ-12	100.6	Skute Stone Arroyo	-6	GWQ-12-6	10/18/82	QMC	
GWQ-12	100.6	Skute Stone Arroyo	-7	GWQ-12-7	11/11/82	QMC	
GWQ-12	100.9	Skute Stone Arroyo	-8	GWQ-12-8	12/28/82	QMC	
GWQ-12		Skute Stone Arroyo	-9	GWQ-12-9	02/21/83	QMC	
GWQ-12	101.2	Skute Stone Arroyo	-10	GWQ-12-10	05/06/83	QMC	
GWQ-12		Skute Stone Arroyo	-11	GWQ-12-11	05/13/83	QMC	
GWQ-12	101.4	Skute Stone Arroyo	-12	GWQ-12-12	06/02/83	QMC	
GWQ-12	101.5	Skute Stone Arroyo	-13	GWQ-12-13	07/05/83	QMC	
GWQ-12		Skute Stone Arroyo	-14	GWQ-12-14	08/09/83	QMC	
GWQ-12	101.6	Skute Stone Arroyo	-15	GWQ-12-15	08/25/83	QMC	
GWQ-12	101.7	Skute Stone Arroyo	-16	GWQ-12-16	10/20/83	QMC	
GWQ-12		Skute Stone Arroyo	-17	GWQ-12-17	11/01/83	QMC	
GWQ-12	101.7	Skute Stone Arroyo	-18	GWQ-12-18	12/07/83	QMC	
GWQ-12	101.7	Skute Stone Arroyo	-19	GWQ-12-19	01/28/84	QMC	

Well Name	Water Depth	USGS Quad	Well Depth	Sample ID	Date	Sampler	Notes
GWQ-12	101.9	Skute Stone Arroyo	-20	GWQ-12-20	02/13/84	QMC	
GWQ-12	101.7	Skute Stone Arroyo	-21	GWQ-12-21	03/01/84	QMC	
GWQ-12		Skute Stone Arroyo	-22	GWQ-12-22	03/16/84	CFP	
GWQ-12	101.7	Skute Stone Arroyo	-23	GWQ-12-23	04/18/84	CFP	
GWQ-12	101.8	Skute Stone Arroyo	-24	GWQ-12-24	05/22/84	CFP	
GWQ-12		Skute Stone Arroyo	-25	GWQ-12-25	05/30/84	CFP	
GWQ-12	101.9	Skute Stone Arroyo	-26	GWQ-12-26	06/26/84	CFP	
GWQ-12	101.9	Skute Stone Arroyo	-27	GWQ-12-27	07/25/84	CFP	
GWQ-12	101.8	Skute Stone Arroyo	-28	GWQ-12-28	08/27/84	CFP	
GWQ-12		Skute Stone Arroyo	-29	GWQ-12-29	09/12/84	CFP	
GWQ-12	101.7	Skute Stone Arroyo	-30	GWQ-12-30	09/21/84	CFP	
GWQ-12	101.7	Skute Stone Arroyo	-31	GWQ-12-31	11/19/84	CFP	
GWQ-12		Skute Stone Arroyo	-32	GWQ-12-32	11/27/84	CFP	
GWQ-12	101.6	Skute Stone Arroyo	-33	GWQ-12-33	12/17/84	CFP	
GWQ-12	101.7	Skute Stone Arroyo	-34	GWQ-12-34	05/27/85	CFP	
GWQ-12	100.8	Skute Stone Arroyo	-35	GWQ-12-35	11/13/85	CFP	
GWQ-12	99.3	Skute Stone Arroyo	-36	GWQ-12-36	05/23/86	CFP	
GWQ-12	99	Skute Stone Arroyo	-37	GWQ-12-37	10/08/86	CFP	
GWQ-12		Skute Stone Arroyo	-38	GWQ-12-38	07/21/94	SRK	
GWQ-12		Skute Stone Arroyo	-39	GWQ-12-39	04/01/97		
GWQ-2		Skute Stone Arroyo	-1	GWQ-2-1	06/15/81	SHB	
GWQ-2		Skute Stone Arroyo	-2	GWQ-2-2	06/25/81	SHB	
GWQ-3		Hillsboro	-1	GWQ-3-1	03/27/81		
GWQ-3	8.6	Hillsboro	-2	GWQ-3-2	06/06/81	SHB	
GWQ-3		Hillsboro	-3	GWQ-3-3	06/15/81	SHB	
GWQ-3		Hillsboro	-4	GWQ-3-4	06/15/81	SHB	
GWQ-3		Hillsboro	-5	GWQ-3-5	02/25/82	QMC	
GWQ-3		Hillsboro	-6	GWQ-3-6	05/12/82	QMC	
GWQ-3		Hillsboro	-7	GWQ-3-7	06/30/82	QMC	
GWQ-3		Hillsboro	-8	GWQ-3-8	12/23/82	QMC	
GWQ-3	10.25	Hillsboro	-9	GWQ-3-9	02/21/83	QMC	
GWQ-3		Hillsboro	-10	GWQ-3-10	05/13/83	QMC	
GWQ-3		Hillsboro	-11	GWQ-3-11	08/09/83	QMC	
GWQ-3		Hillsboro	-12	GWQ-3-12	11/01/83	QMC	
GWQ-3		Hillsboro	-13	GWQ-3-13	03/16/84	QMC	
GWQ-3	35	Hillsboro	-14	GWQ-3-14	06/10/81	SHB	

Well Name	Water Depth	USGS Quad	Well Depth	Sample ID	Date	Sampler	Notes
GWQ-4		Hillsboro		-1 GWQ-4-1	06/15/81	SHB	Windmill
GWQ-4		Hillsboro		-2 GWQ-4-2	06/15/81	SHB	Windmill
GWQ-4	86.39	Hillsboro		-3 GWQ-4-3	11/06/81		
GWQ-4		Hillsboro		-4 GWQ-4-4	04/01/93	JWS	Windmill
GWQ-4		Hillsboro		-5 GWQ-4-5	05/26/94	SRK	Windmill
GWQ-4	10.45	Hillsboro		-6 GWQ-4-6	06/10/81	SHB	
GWQ-5		Hillsboro		-1 GWQ-5-1	06/15/81	SHB	
GWQ-5		Hillsboro		-2 GWQ-5-2	06/15/81	SHB	
GWQ-5	25.45	Hillsboro		-3 GWQ-5-3	06/09/81	SHB	
GWQ-6		Hillsboro		-4 GWQ-6-4	06/15/81	SHB	
GWQ-6		Hillsboro		-5 GWQ-6-5	06/15/81	SHB	
GWQ-6		Hillsboro		-6 GWQ-6-6	02/25/82	QMC	
GWQ-6		Hillsboro		-7 GWQ-6-7	04/01/93	JWS	
GWQ-6	23.26	Hillsboro		-8 GWQ-6-8		SHB	
GWQ-6		Hillsboro		-9 GWQ-6-9	01/20/81	SHB	QMC-1,CI,N
GWQ-7				-1 GWQ-7-1	02/02/81		
GWQ-7				-2 GWQ-7-2	02/02/81	SHB	QMC-1,SHE
GWQ-7				-3 GWQ-7-3	03/27/81		
GWQ-7				-4 GWQ-7-4	03/27/81	SHB	QMC-1 in SI
GWQ-7				-5 GWQ-7-5	04/06/81		
GWQ-7	77			-6 GWQ-7-6	06/09/81	SHB	
GWQ-7				-7 GWQ-7-7	06/15/81	SHB	
GWQ-7				-8 GWQ-7-8	06/15/81	SHB	
GWQ-7				-9 GWQ-7-9	08/07/81		
GWQ-7				-10 GWQ-7-10	08/10/81		
GWQ-7				-11 GWQ-7-11	10/23/81	QMC	
GWQ-7				-12 GWQ-7-12	10/23/81	QMC	
GWQ-7				-13 GWQ-7-13	11/06/81	QMC	
GWQ-7				-14 GWQ-7-14	02/25/82	QMC	
GWQ-7				-15 GWQ-7-15	12/28/82	QMC	
GWQ-7				-16 GWQ-7-16	02/21/83	QMC	
GWQ-7				-17 GWQ-7-17	03/16/83	QMC	
GWQ-7				-18 GWQ-7-18	05/13/83	QMC	
GWQ-7				-19 GWQ-7-19	08/09/83	QMC	
GWQ-7				-20 GWQ-7-20	11/01/83	QMC	
GWQ-7				-21 GWQ-7-21	03/16/84	CFP	

Well Name	Water Depth	USGS Quad	Well Depth	Sample ID	Date	Sampler	Notes
GWQ-7			-22	GWQ-7-22	05/30/84	CFP	
GWQ-7			-23	GWQ-7-23	09/12/84	CFP	
GWQ-7			-24	GWQ-7-24	11/27/84	CFP	
GWQ-7			-25	GWQ-7-25	05/17/85	CFP	
GWQ-7			-26	GWQ-7-26	11/13/85	CFP	
GWQ-7			-27	GWQ-7-27	05/23/86	CFP	
GWQ-7			-28	GWQ-7-28	10/08/86	CFP	
GWQ-7			-29	GWQ-7-29	03/30/89	EID	
GWQ-7			-30	GWQ-7-30	03/30/93	JWS	Electric Pu
GWQ-7	33.9		-31	GWQ-7-31	05/25/94	SRK	
GWQ-7			-32	GWQ-7-32	07/21/94	SRK	Electric Pu
GWQ-8		Skute Stone Arroyo	-1	GWQ-8-1	06/04/76	SHB	
GWQ-8		Skute Stone Arroyo	-2	GWQ-8-2	02/02/81		Windmill
GWQ-8	83.55	Skute Stone Arroyo	-3	GWQ-8-3	06/09/81	SHB	
GWQ-8		Skute Stone Arroyo	-4	GWQ-8-4	08/19/81	QMC	Windmill
GWQ-8		Skute Stone Arroyo	-5	GWQ-8-5	10/01/81		
GWQ-8		Skute Stone Arroyo	-6	GWQ-8-6	02/25/82	QMC	Windmill
GWQ-8		Skute Stone Arroyo	-7	GWQ-8-7	03/01/93		
GWQ-8		Skute Stone Arroyo	-8	GWQ-8-8	03/31/93	JWS	Windmill
GWQ-8		Skute Stone Arroyo	-9	GWQ-8-9	03/31/93	JWS	
GWQ-8		Skute Stone Arroyo	-10	GWQ-8-10	05/25/94	SRK	Windmill
GWQ-8		Skute Stone Arroyo	-11	GWQ-8-11	04/01/97	Goff	
GWQ-8		Skute Stone Arroyo	-12	GWQ-8-12	04/14/98	Goff	
GWQ-8		Skute Stone Arroyo	-13	GWQ-8-13	07/21/98	Brownfield	lab pH

Well Name	Date	Latitude	Longitude	UTM Easting	UTM Northing	UTM Zone	Elevation	Filtered?	Chloride	Sulfate
GWQ-11	01/29/95	32.96027	107.49667	266632	3649459	13	5183	FALSE	199.5	158.7
GWQ-11	03/29/95	32.96027	107.49667	266632	3649459	13	5183	FALSE	99.4	136.9
GWQ-11	06/27/95	32.96027	107.49667	266632	3649459	13	5183	FALSE	101.7	278.8
GWQ-11	09/21/95	32.96027	107.49667	266632	3649459	13	5183	FALSE	112.1	289.5
GWQ-11	01/10/96	32.96027	107.49667	266632	3649459	13	5183	FALSE	120.8	287.5
GWQ-11	04/03/96	32.96027	107.49667	266632	3649459	13	5183	FALSE	119.2	276.5
GWQ-11	06/01/96	32.96027	107.49667	266632	3649459	13	5183		122.3	281.4
GWQ-11	09/25/96	32.96027	107.49667	266632	3649459	13	5183	TRUE	116	229.9
GWQ-11	01/15/97	32.96027	107.49667	266632	3649459	13	5183	TRUE	127	303.9
GWQ-11	04/01/97	32.96027	107.49667	266632	3649459	13	5183	TRUE	120	690
GWQ-11	04/01/97	32.96027	107.49667	266632	3649459	13	5183	TRUE	128.1	305
GWQ-11	07/01/97	32.96027	107.49667	266632	3649459	13	5183	TRUE	129	269
GWQ-11	08/01/97	32.96027	107.49667	266632	3649459	13	5183	TRUE	4.1	
GWQ-11	10/01/97	32.96027	107.49667	266632	3649459	13	5183	TRUE	123	284
GWQ-11	01/15/98	32.96027	107.49667	266632	3649459	13	5183	TRUE	130	276
GWQ-11	04/09/98	32.96027	107.49667	266632	3649459	13	5183	TRUE	127.2	294
GWQ-11	07/13/98	32.96027	107.49667	266632	3649459	13	5183	TRUE	127.5	300
GWQ-12	05/17/82	32.95278	107.47190	268928	3648574	13	5223	FALSE		
GWQ-12	06/14/82	32.95278	107.47190	268928	3648574	13	5223	FALSE		
GWQ-12	07/26/82	32.95278	107.47190	268928	3648574	13	5223	FALSE		
GWQ-12	08/18/82	32.95278	107.47190	268928	3648574	13	5223	FALSE		
GWQ-12	09/14/82	32.95278	107.47190	268928	3648574	13	5223	FALSE		
GWQ-12	10/18/82	32.95278	107.47190	268928	3648574	13	5223	FALSE		
GWQ-12	11/11/82	32.95278	107.47190	268928	3648574	13	5223	FALSE		
GWQ-12	12/28/82	32.95278	107.47190	268928	3648574	13	5223	FALSE		
GWQ-12	02/21/83	32.95278	107.47190	268928	3648574	13	5223	TRUE	18	53
GWQ-12	05/06/83	32.95278	107.47190	268928	3648574	13	5223	FALSE		
GWQ-12	05/13/83	32.95278	107.47190	268928	3648574	13	5223	TRUE	16	37
GWQ-12	06/02/83	32.95278	107.47190	268928	3648574	13	5223	FALSE		
GWQ-12	07/05/83	32.95278	107.47190	268928	3648574	13	5223	FALSE		
GWQ-12	08/09/83	32.95278	107.47190	268928	3648574	13	5223	TRUE	22	130
GWQ-12	08/25/83	32.95278	107.47190	268928	3648574	13	5223	FALSE		
GWQ-12	10/20/83	32.95278	107.47190	268928	3648574	13	5223	FALSE		
GWQ-12	11/01/83	32.95278	107.47190	268928	3648574	13	5223	TRUE	14	38
GWQ-12	12/07/83	32.95278	107.47190	268928	3648574	13	5223	FALSE		
GWQ-12	01/28/84	32.95278	107.47190	268928	3648574	13	5223	FALSE		

Well Name	Date	Latitude	Longitude	UTM Easting	UTM Northing	UTM Zone	Elevation	Filtered?	Chloride	Sulfate
GWQ-12	02/13/84	32.95278	107.47190	268928	3648574	13	5223	FALSE		
GWQ-12	03/01/84	32.95278	107.47190	268928	3648574	13	5223	FALSE		
GWQ-12	03/16/84	32.95278	107.47190	268928	3648574	13	5223	TRUE	14	44
GWQ-12	04/18/84	32.95278	107.47190	268928	3648574	13	5223	FALSE		
GWQ-12	05/22/84	32.95278	107.47190	268928	3648574	13	5223	FALSE		
GWQ-12	05/30/84	32.95278	107.47190	268928	3648574	13	5223	TRUE	16	47
GWQ-12	06/26/84	32.95278	107.47190	268928	3648574	13	5223	FALSE		
GWQ-12	07/25/84	32.95278	107.47190	268928	3648574	13	5223	FALSE		
GWQ-12	08/27/84	32.95278	107.47190	268928	3648574	13	5223	FALSE		
GWQ-12	09/12/84	32.95278	107.47190	268928	3648574	13	5223	TRUE	16	38
GWQ-12	09/21/84	32.95278	107.47190	268928	3648574	13	5223	FALSE		
GWQ-12	11/19/84	32.95278	107.47190	268928	3648574	13	5223	FALSE		
GWQ-12	11/27/84	32.95278	107.47190	268928	3648574	13	5223	TRUE	14	37
GWQ-12	12/17/84	32.95278	107.47190	268928	3648574	13	5223	FALSE		
GWQ-12	05/27/85	32.95278	107.47190	268928	3648574	13	5223	FALSE	14	36
GWQ-12	11/13/85	32.95278	107.47190	268928	3648574	13	5223	FALSE	14	35
GWQ-12	05/23/86	32.95278	107.47190	268928	3648574	13	5223	FALSE	16	31
GWQ-12	10/08/86	32.95278	107.47190	268928	3648574	13	5223	FALSE	16	35
GWQ-12	07/21/94	32.95278	107.47190	268928	3648574	13	5223	TRUE	16	38
GWQ-12	04/01/97	32.95278	107.47190	268928	3648574	13	5223	TRUE	36	43
GWQ-2	06/15/81	32.97342	107.49899	266450	3650923	13	5216	TRUE	20	140
GWQ-2	06/25/81	32.97342	107.49899	266450	3650923	13	5216	TRUE	24.8	111
GWQ-3	03/27/81	32.97084	107.50472	265907	3650649	13	5250	FALSE		
GWQ-3	06/06/81	32.97084	107.50472	265907	3650649	13	5250	TRUE		
GWQ-3	06/15/81	32.97084	107.50472	265907	3650649	13	5250	TRUE	32	383
GWQ-3	06/15/81	32.97084	107.50472	265907	3650649	13	5250	TRUE	40.1	335
GWQ-3	02/25/82	32.97084	107.50472	265907	3650649	13	5250	TRUE	56	490
GWQ-3	05/12/82	32.97084	107.50472	265907	3650649	13	5250	TRUE	56	410
GWQ-3	06/30/82	32.97084	107.50472	265907	3650649	13	5250	TRUE	48	365
GWQ-3	12/23/82	32.97084	107.50472	265907	3650649	13	5250	TRUE	64	340
GWQ-3	02/21/83	32.97084	107.50472	265907	3650649	13	5250	TRUE	68	428
GWQ-3	05/13/83	32.97084	107.50472	265907	3650649	13	5250	TRUE	82	437
GWQ-3	08/09/83	32.97084	107.50472	265907	3650649	13	5250	TRUE	78	385
GWQ-3	11/01/83	32.97084	107.50472	265907	3650649	13	5250	TRUE	90	529
GWQ-3	03/16/84	32.97084	107.50472	265907	3650649	13	5250	TRUE	74	530
GWQ-3	06/10/81	32.97084	107.50472	265907	3650649	13	5250	TRUE		

Well Name	Date	Latitude	Longitude	UTM Easting	UTM Northing	UTM Zone	Elevation	Filtered?	Chloride	Sulfate
GWQ-4	06/15/81	32.96641	107.54305	262311	3650244	13	5539	FALSE	30	270
GWQ-4	06/15/81	32.96641	107.54305	262311	3650244	13	5539	TRUE	35.1	255
GWQ-4	11/06/81	32.96641	107.54305	262311	3650244	13	5539	FALSE	22	162
GWQ-4	04/01/93	32.96641	107.54305	262311	3650244	13	5539	FALSE	27	235
GWQ-4	05/26/94	32.96641	107.54305	262311	3650244	13	5539	FALSE	30	220
GWQ-4	06/10/81	32.96641	107.54305	262311	3650244	13	5539	TRUE		
GWQ-5	06/15/81							TRUE	42	575
GWQ-5	06/15/81							TRUE	45	477
GWQ-5	06/09/81							TRUE		
GWQ-6	06/15/81							TRUE	32.6	40.5
GWQ-6	06/15/81							TRUE	28	37
GWQ-6	02/25/82							TRUE	102	220
GWQ-6	04/01/93							FALSE	22	10
GWQ-6								TRUE		
GWQ-6	01/20/81							TRUE	200	350
GWQ-7	02/02/81	32.95646	107.49585	266698	3649035	13	5172	FALSE	20	156
GWQ-7	02/02/81	32.95646	107.49585	266698	3649035	13	5172	TRUE	20	156
GWQ-7	03/27/81	32.95646	107.49585	266698	3649035	13	5172	FALSE		
GWQ-7	03/27/81	32.95646	107.49585	266698	3649035	13	5172	TRUE		
GWQ-7	04/06/81	32.95646	107.49585	266698	3649035	13	5172	FALSE		
GWQ-7	06/09/81	32.95646	107.49585	266698	3649035	13	5172	TRUE		
GWQ-7	06/15/81	32.95646	107.49585	266698	3649035	13	5172	TRUE	20	165
GWQ-7	06/15/81	32.95646	107.49585	266698	3649035	13	5172	TRUE	24.5	110
GWQ-7	08/07/81	32.95646	107.49585	266698	3649035	13	5172	FALSE	100	150
GWQ-7	08/10/81	32.95646	107.49585	266698	3649035	13	5172	FALSE	24	162
GWQ-7	10/23/81	32.95646	107.49585	266698	3649035	13	5172	TRUE	26	160
GWQ-7	10/23/81	32.95646	107.49585	266698	3649035	13	5172	TRUE	26	162
GWQ-7	11/06/81	32.95646	107.49585	266698	3649035	13	5172	TRUE	24	158
GWQ-7	02/25/82	32.95646	107.49585	266698	3649035	13	5172	TRUE	26	162
GWQ-7	12/28/82	32.95646	107.49585	266698	3649035	13	5172	TRUE	20	40
GWQ-7	02/21/83	32.95646	107.49585	266698	3649035	13	5172	TRUE	22	47
GWQ-7	03/16/83	32.95646	107.49585	266698	3649035	13	5172	TRUE		
GWQ-7	05/13/83	32.95646	107.49585	266698	3649035	13	5172	TRUE	20	158
GWQ-7	08/09/83	32.95646	107.49585	266698	3649035	13	5172	TRUE	22	130
GWQ-7	11/01/83	32.95646	107.49585	266698	3649035	13	5172	TRUE	22	137
GWQ-7	03/16/84	32.95646	107.49585	266698	3649035	13	5172	TRUE	20	140

Well Name	Date	Latitude	Longitude	UTM Easting	UTM Northing	UTM Zone	Elevation	Filtered?	Chloride	Sulfate
GWQ-7	05/30/84	32.95646	107.49585	266698	3649035	13	5172	TRUE	20	154
GWQ-7	09/12/84	32.95646	107.49585	266698	3649035	13	5172	TRUE	20	128
GWQ-7	11/27/84	32.95646	107.49585	266698	3649035	13	5172	TRUE	18	144
GWQ-7	05/17/85	32.95646	107.49585	266698	3649035	13	5172	TRUE	20	144
GWQ-7	11/13/85	32.95646	107.49585	266698	3649035	13	5172	FALSE	18	137
GWQ-7	05/23/86	32.95646	107.49585	266698	3649035	13	5172	FALSE	22	142
GWQ-7	10/08/86	32.95646	107.49585	266698	3649035	13	5172	FALSE	22	116
GWQ-7	03/30/89	32.95646	107.49585	266698	3649035	13	5172	TRUE	15.9	131
GWQ-7	03/30/93	32.95646	107.49585	266698	3649035	13	5172	FALSE	21	138
GWQ-7	05/25/94	32.95646	107.49585	266698	3649035	13	5172	FALSE	20	1300
GWQ-7	07/21/94	32.95646	107.49585	266698	3649035	13	5172	TRUE	22	5
GWQ-8	06/04/76	32.96722	107.49801	266524	3650233	13	5203	TRUE	16.7	114
GWQ-8	02/02/81	32.96722	107.49801	266524	3650233	13	5203	FALSE	20	156
GWQ-8	06/09/81	32.96722	107.49801	266524	3650233	13	5203	TRUE		
GWQ-8	08/19/81	32.96722	107.49801	266524	3650233	13	5203	TRUE	24	134
GWQ-8	10/01/81	32.96722	107.49801	266524	3650233	13	5203		24	134
GWQ-8	02/25/82	32.96722	107.49801	266524	3650233	13	5203	TRUE	38	220
GWQ-8	03/01/93	32.96722	107.49801	266524	3650233	13	5203		38	283
GWQ-8	03/31/93	32.96722	107.49801	266524	3650233	13	5203	FALSE	38	283
GWQ-8	03/31/93	32.96722	107.49801	266524	3650233	13	5203	TRUE	22	260
GWQ-8	05/25/94	32.96722	107.49801	266524	3650233	13	5203	FALSE	41	290
GWQ-8	04/01/97	32.96722	107.49801	266524	3650233	13	5203	TRUE	46.3	318
GWQ-8	04/14/98	32.96722	107.49801	266524	3650233	13	5203	TRUE	55.3	376
GWQ-8	07/21/98	32.96722	107.49801	266524	3650233	13	5203	TRUE	55.2	362

Well Name	Date	pH	TDS	Alkalinity	Bicarb	Spec. Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
GWQ-11	01/29/95	7.6	861								
GWQ-11	03/29/95	7.96	793								
GWQ-11	06/27/95	7.67	835								
GWQ-11	09/21/95	7.58	865								
GWQ-11	01/10/96	7.36	777								
GWQ-11	04/03/96	7.38	767								
GWQ-11	06/01/96	7.49	848								
GWQ-11	09/25/96	7.78	835								
GWQ-11	01/15/97	7.68	860								
GWQ-11	04/01/97		810				0.65				
GWQ-11	04/01/97		797				0.9				
GWQ-11	07/01/97	7.53	838								
GWQ-11	08/01/97	7.91	217				0.96				
GWQ-11	10/01/97	7.41	820								
GWQ-11	01/15/98	7.54	812			1310	0.84	3.73			
GWQ-11	04/09/98		817			1230	0.79	4			
GWQ-11	07/13/98		796			971	0.85	3.8			
GWQ-12	05/17/82										
GWQ-12	06/14/82										
GWQ-12	07/26/82										
GWQ-12	08/18/82										
GWQ-12	09/14/82										
GWQ-12	10/18/82										
GWQ-12	11/11/82										
GWQ-12	12/28/82										
GWQ-12	02/21/83	7.7	360				1	2.2			
GWQ-12	05/06/83										
GWQ-12	05/13/83	8.1	330				1	2.1			
GWQ-12	06/02/83										
GWQ-12	07/05/83										
GWQ-12	08/09/83	7.8	480				0.6	1.1			
GWQ-12	08/25/83										
GWQ-12	10/20/83										
GWQ-12	11/01/83	8.2	340				1.1	2.8			
GWQ-12	12/07/83										
GWQ-12	01/28/84										

Well Name	Date	pH	TDS	Alkalinity	Bicarb	Spec. Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
GWQ-12	02/13/84										
GWQ-12	03/01/84										
GWQ-12	03/16/84	8.2	320				1.1	3.8			
GWQ-12	04/18/84										
GWQ-12	05/22/84										
GWQ-12	05/30/84	8	320				1	2.5			
GWQ-12	06/26/84										
GWQ-12	07/25/84										
GWQ-12	08/27/84										
GWQ-12	09/12/84	8	330				1	2.2			
GWQ-12	09/21/84										
GWQ-12	11/19/84										
GWQ-12	11/27/84	7.8	340				1	2.3			
GWQ-12	12/17/84										
GWQ-12	05/27/85	8	370								
GWQ-12	11/13/85	7.8	310								
GWQ-12	05/23/86	7.8	330								
GWQ-12	10/08/86	7.6	310								
GWQ-12	07/21/94	7.75	358		262	537	0.99	2.1	-0.05	0.0064	-0.005
GWQ-12	04/01/97		353				1.3				
GWQ-2	06/15/81	7.3	530		242	700	0.5	5.6	-0.01		-0.01
GWQ-2	06/25/81		448		261		0.48	4.3	-0.025		-0.002
GWQ-3	03/27/81						0.6	5.5			-0.01
GWQ-3	06/06/81										
GWQ-3	06/15/81	7	890	275	327	1100	0.7	0.1	-0.01		-0.01
GWQ-3	06/15/81		868		354		0.72	0.25	-0.25		0.004
GWQ-3	02/25/82	7.9	1040				0.6	0.4			
GWQ-3	05/12/82	7.9	930				0.7	0.2			
GWQ-3	06/30/82	7.6	860				0.7	0.4			
GWQ-3	12/23/82	8.5	990				0.7	0.2			
GWQ-3	02/21/83	7.7	970				0.7	0.2			
GWQ-3	05/13/83	8	980				0.6	0.3			
GWQ-3	08/09/83	7.8	1060				0.7	-0.2			
GWQ-3	11/01/83	8	1240				0.7	0.3			
GWQ-3	03/16/84	8.2	1190				0.3	3.4			
GWQ-3	06/10/81										

Well Name	Date	pH	TDS	Alkalinity	Bicarb	Spec. Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
GWQ-4	06/15/81	7.2	770		376	1000	0.6	1.1	-0.01		-0.01
GWQ-4	06/15/81		776		370		0.68	0.53	-0.25		-0.002
GWQ-4	11/06/81	7.9	500				0.7	2	-0.01		-0.01
GWQ-4	04/01/93	7.6	702		404	1060	0.73	0.1	-0.1		-0.005
GWQ-4	05/26/94	8.08	926		316	1010	0.63	-1	-0.025	-0.005	-0.005
GWQ-4	06/10/81										
GWQ-5	06/15/81	7.3	1260	330	398	1500	1	0.6	-0.01		-0.01
GWQ-5	06/15/81		1070		431		1.03	0.37	-0.25		-0.002
GWQ-5	06/09/81										
GWQ-6	06/15/81		400		309		1.09	3.3	-0.25		-0.002
GWQ-6	06/15/81	7.3	420	245	317	600	1.2	3.8	-0.01		-0.01
GWQ-6	02/25/82	8.3	810				1.1	0.5			
GWQ-6	04/01/93	7.7	304		322	597	0.84	1.1	-0.1		-0.005
GWQ-6											
GWQ-6	01/20/81	7.2	500		341.6						
GWQ-7	02/02/81	7.9	530		278						
GWQ-7	02/02/81	7.9	530		278						
GWQ-7	03/27/81						0.6	1.4			-0.01
GWQ-7	03/27/81						0.6	1.4			-0.01
GWQ-7	04/06/81						0.59	0.9			0.003
GWQ-7	06/09/81										
GWQ-7	06/15/81	7.2	510	210	266	700	0.5	1.1	-0.01		-0.01
GWQ-7	06/15/81		496		285		0.53	0.54	-0.25		-0.002
GWQ-7	08/07/81	7.4	475		268.4						
GWQ-7	08/10/81	7.7	490		229		0.6	1.2			-0.01
GWQ-7	10/23/81		490				0.5	1.1	-0.01		-0.01
GWQ-7	10/23/81		500				0.5	1.3	-0.01		-0.01
GWQ-7	11/06/81	8.1	480				0.8	1.2	-0.01		-0.01
GWQ-7	02/25/82	8	510				0.5	0.8			
GWQ-7	12/28/82	8.1	250				0.3	-0.2			
GWQ-7	02/21/83	8.3	250				0.4	2.8			
GWQ-7	03/16/83										
GWQ-7	05/13/83	8.1	470				0.6	1.2			
GWQ-7	08/09/83	8	490				0.6	1			
GWQ-7	11/01/83	8.1	500				0.6	1.8			
GWQ-7	03/16/84	8.3	450				0.8	1			

Well Name	Date	pH	TDS	Alkalinity	Bicarb	Spec. Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
GWQ-7	05/30/84	7.7	470				0.6	0.9			
GWQ-7	09/12/84	8	500				0.6	1.4			
GWQ-7	11/27/84	7.7	490				0.6	1.4			
GWQ-7	05/17/85	7.9	500								
GWQ-7	11/13/85	7.8	450								
GWQ-7	05/23/86	7.9	490								
GWQ-7	10/08/86	7.4	460								
GWQ-7	03/30/89		492		278				-0.1		
GWQ-7	03/30/93	7.8	482		298	752	0.56	138	-0.1		-0.005
GWQ-7	05/25/94	7.26	2420		480	2630	2.1	-1	0.25	-0.005	-0.005
GWQ-7	07/21/94	7.72	224		349	660	16	-1	-0.05	-0.005	-0.005
GWQ-8	06/04/76	7.48	560		241	780	0.51	16.8			
GWQ-8	02/02/81	7.9	520		276			60			
GWQ-8	06/09/81										
GWQ-8	08/19/81	7.42	608		283		0.59	2.8	-0.25		-0.004
GWQ-8	10/01/81	7.4	608		283		0.59	2.8			
GWQ-8	02/25/82	7.6	380				1	0.3			
GWQ-8	03/01/93	7.6	764		298		0.53	5.7			
GWQ-8	03/31/93	7.6	764		298	1110	0.51	6.3	-0.1		-0.005
GWQ-8	03/31/93	7.7	290		262		0.53	5.7	-0.05		-0.005
GWQ-8	05/25/94	7.97	792		272	1060	0.5	5.3	-0.025	-0.005	-0.005
GWQ-8	04/01/97		854				0.4				
GWQ-8	04/14/98	7.36	871			1290	0.6	4.2			
GWQ-8	07/21/98		887				0.6	4.7			

Well Name	Date	Boron	Barium	Berrylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
GWQ-11	01/29/95										
GWQ-11	03/29/95										
GWQ-11	06/27/95										
GWQ-11	09/21/95										
GWQ-11	01/10/96										
GWQ-11	04/03/96										
GWQ-11	06/01/96										
GWQ-11	09/25/96										
GWQ-11	01/15/97										
GWQ-11	04/01/97								-0.025	-0.05	
GWQ-11	04/01/97								-0.005	-0.05	
GWQ-11	07/01/97										
GWQ-11	08/01/97										
GWQ-11	10/01/97										
GWQ-11	01/15/98								-0.005	-0.05	
GWQ-11	04/09/98								-0.005	-0.05	
GWQ-11	07/13/98								-0.005	0.13	
GWQ-12	05/17/82										
GWQ-12	06/14/82										
GWQ-12	07/26/82										
GWQ-12	08/18/82										
GWQ-12	09/14/82										
GWQ-12	10/18/82										
GWQ-12	11/11/82										
GWQ-12	12/28/82										
GWQ-12	02/21/83				-0.005				-0.05	-0.1	
GWQ-12	05/06/83										
GWQ-12	05/13/83				-0.005				-0.05	-0.1	
GWQ-12	06/02/83										
GWQ-12	07/05/83										
GWQ-12	08/09/83				-0.005				-0.05	-0.1	
GWQ-12	08/25/83										
GWQ-12	10/20/83										
GWQ-12	11/01/83				-0.005				-0.05	0.32	
GWQ-12	12/07/83										
GWQ-12	01/28/84										

Well Name	Date	Boron	Barium	Berrylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
GWQ-12	02/13/84										
GWQ-12	03/01/84										
GWQ-12	03/16/84				-0.005				-0.05	-0.1	
GWQ-12	04/18/84										
GWQ-12	05/22/84										
GWQ-12	05/30/84				-0.005				-0.05	-0.1	
GWQ-12	06/26/84										
GWQ-12	07/25/84										
GWQ-12	08/27/84										
GWQ-12	09/12/84				-0.005				-0.05	-0.1	
GWQ-12	09/21/84										
GWQ-12	11/19/84										
GWQ-12	11/27/84				-0.005				-0.05	-0.1	
GWQ-12	12/17/84										
GWQ-12	05/27/85										
GWQ-12	11/13/85										
GWQ-12	05/23/86										
GWQ-12	10/08/86										
GWQ-12	07/21/94	-0.1	-0.1	-0.002	-0.0005	59	-0.025	-0.05	-0.025	-0.05	-0.005
GWQ-12	04/01/97								-0.005	2.2	
GWQ-2	06/15/81	-0.1	-0.2		-0.005	102	-0.01	-0.1	-0.05	-0.1	-0.02
GWQ-2	06/25/81	0.162	-1		-0.01	98	-0.05	-0.05	-0.02	0.1	-0.05
GWQ-3	03/27/81								-0.05		-0.02
GWQ-3	06/06/81										
GWQ-3	06/15/81	-0.1	-0.2		-0.005	146	-0.01	-0.05	-0.05	-0.1	0.073
GWQ-3	06/15/81	0.108	-1		-0.01	138	-0.05	-0.05	-0.02	-0.05	-0.05
GWQ-3	02/25/82				-0.005				-0.05	-0.1	
GWQ-3	05/12/82				-0.005				-0.05	-0.1	
GWQ-3	06/30/82				-0.005				-0.05	-0.1	
GWQ-3	12/23/82				-0.005				-0.05	-0.1	
GWQ-3	02/21/83				-0.005				-0.05	-0.1	
GWQ-3	05/13/83				-0.005				-0.05	-0.1	
GWQ-3	08/09/83				-0.005				-0.05	0.11	
GWQ-3	11/01/83				-0.005				-0.05	-0.1	
GWQ-3	03/16/84				-0.005				-0.05	-0.1	
GWQ-3	06/10/81										

Well Name	Date	Boron	Barium	Berrylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
GWQ-4	06/15/81	-0.1	-0.2		-0.005	137	-0.01	-0.05	-0.05	-0.1	-0.02
GWQ-4	06/15/81	0.065	-1		-0.01	132	-0.05	-0.05	-0.02	-0.05	-0.05
GWQ-4	11/06/81	-0.1	-0.2		-0.005	72	-0.01	-0.02	-0.05	-0.1	-0.02
GWQ-4	04/01/93	0.02	1		-0.002	125	-0.02	-0.05	-0.01	0.2	-0.02
GWQ-4	05/26/94	-0.1	-0.1		-0.0005	93	-0.025	-0.05	-0.025	0.13	-0.005
GWQ-4	06/10/81										
GWQ-5	06/15/81	-0.1	-0.2		-0.005	200	-0.01	-0.05	-0.05	-0.1	-0.02
GWQ-5	06/15/81	0.054	-1		-0.01	175	-0.05	-0.05	0.02	0.07	-0.05
GWQ-5	06/09/81										
GWQ-6	06/15/81	0.135	-1		-0.01	68	-0.05	-0.05	-0.02	-0.05	-0.05
GWQ-6	06/15/81	-0.1	-0.2		-0.005	73	-0.01	-0.05	-0.05	-0.1	-0.02
GWQ-6	02/25/82				-0.005				-0.05	-0.1	
GWQ-6	04/01/93	0.09	0.6		-0.002	49	-0.02	-0.05	0.03	5.05	-0.02
GWQ-6											
GWQ-6	01/20/81					96				0.03	
GWQ-7	02/02/81					74				3.8	
GWQ-7	02/02/81					74				3.8	
GWQ-7	03/27/81								-0.05		-0.02
GWQ-7	03/27/81								-0.05		-0.02
GWQ-7	04/06/81								-0.05		-0.01
GWQ-7	06/09/81										
GWQ-7	06/15/81	-0.1	-0.2		-0.005	86	-0.01	-0.05	-0.05	-0.1	-0.02
GWQ-7	06/15/81	0.065	-1		-0.01	88	-0.05	-0.05	-0.02	-0.05	-0.05
GWQ-7	08/07/81					80				0.02	
GWQ-7	08/10/81					68			-0.05	1.7	-0.02
GWQ-7	10/23/81	-0.1	-0.02		-0.005	71	-0.01	-0.02	-0.05	0.14	-0.02
GWQ-7	10/23/81	-0.1	-0.2		-0.005	70	-0.01	-0.02	-0.05	-0.1	-0.02
GWQ-7	11/06/81	-0.1	-0.2		-0.005	71	-0.01	-0.02	-0.05	-0.1	-0.02
GWQ-7	02/25/82				-0.005				-0.05	0.17	
GWQ-7	12/28/82				-0.005				-0.05	0.26	
GWQ-7	02/21/83				-0.005				-0.05	-0.1	
GWQ-7	03/16/83										
GWQ-7	05/13/83				-0.005				-0.05	-0.1	
GWQ-7	08/09/83				-0.005				-0.05	-0.1	
GWQ-7	11/01/83				-0.005				-0.05	-0.1	
GWQ-7	03/16/84				-0.005				-0.05	-0.1	

Well Name	Date	Boron	Barium	Berrylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
GWQ-7	05/30/84				-0.005				-0.05	-0.1	
GWQ-7	09/12/84				-0.005				-0.05	-0.1	
GWQ-7	11/27/84				-0.005				-0.05	-0.1	
GWQ-7	05/17/85										
GWQ-7	11/13/85										
GWQ-7	05/23/86										
GWQ-7	10/08/86										
GWQ-7	03/30/89	-0.1	-0.1	-0.1	-0.1	80	-0.1	-0.05	-0.1	-0.1	-0.1
GWQ-7	03/30/93	0.04	-0.5		-0.002	68	-0.02	-0.05	-0.01	-0.05	-0.02
GWQ-7	05/25/94		-0.1		0.00058	490	-0.025		0.11	0.72	-0.005
GWQ-7	07/21/94	-0.1	-0.1	-0.002	-0.0005	14	-0.025	-0.05	-0.025	1.2	-0.005
GWQ-8	06/04/76	-0.1				122				0.002	
GWQ-8	02/02/81					74				1.7	
GWQ-8	06/09/81										
GWQ-8	08/19/81	0.076	-1		-0.01	72.9	-0.05	-0.05	-0.05	-0.1	-0.05
GWQ-8	10/01/81					73					
GWQ-8	02/25/82				-0.005				-0.05	-0.1	
GWQ-8	03/01/93					132					
GWQ-8	03/31/93	0.03	-0.05		-0.002	132	-0.02	-0.05	0.01	-0.05	-0.02
GWQ-8	03/31/93	-0.1	0.042		-0.0005	149	-0.01	-0.01	-0.01	0.038	-0.002
GWQ-8	05/25/94	-0.1	-0.1		-0.0005	120	-0.025	-0.05	-0.025	0.24	-0.005
GWQ-8	04/01/97								-0.005	0.2	
GWQ-8	04/14/98					168.5			-0.005	-0.05	
GWQ-8	07/21/98					162			-0.005	0.23	

Well Name	Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium	Thallium
GWQ-11	01/29/95										
GWQ-11	03/29/95										
GWQ-11	06/27/95										
GWQ-11	09/21/95										
GWQ-11	01/10/96										
GWQ-11	04/03/96										
GWQ-11	06/01/96										
GWQ-11	09/25/96										
GWQ-11	01/15/97										
GWQ-11	04/01/97		-0.025								
GWQ-11	04/01/97		-0.02								
GWQ-11	07/01/97										
GWQ-11	08/01/97										
GWQ-11	10/01/97										
GWQ-11	01/15/98	37.3		0.0004	-0.05			-0.05			
GWQ-11	04/09/98		-0.02	-0.0002	-0.05			-0.05			
GWQ-11	07/13/98		0.05	0.0004	-0.05			-0.05			
GWQ-12	05/17/82										
GWQ-12	06/14/82										
GWQ-12	07/26/82										
GWQ-12	08/18/82										
GWQ-12	09/14/82										
GWQ-12	10/18/82										
GWQ-12	11/11/82										
GWQ-12	12/28/82										
GWQ-12	02/21/83		-0.05		-0.05			-0.005			
GWQ-12	05/06/83										
GWQ-12	05/13/83		-0.05	-0.001	-0.05			-0.005			
GWQ-12	06/02/83										
GWQ-12	07/05/83										
GWQ-12	08/09/83		-0.05	-0.001	-0.05			-0.005			
GWQ-12	08/25/83										
GWQ-12	10/20/83										
GWQ-12	11/01/83		-0.05	-0.001	-0.05			-0.005			
GWQ-12	12/07/83										
GWQ-12	01/28/84										

Well Name	Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium	Thallium
GWQ-12	02/13/84										
GWQ-12	03/01/84										
GWQ-12	03/16/84		-0.05	-0.001	-0.05			-0.005			
GWQ-12	04/18/84										
GWQ-12	05/22/84										
GWQ-12	05/30/84		-0.05	-0.001	-0.05			-0.005			
GWQ-12	06/26/84										
GWQ-12	07/25/84										
GWQ-12	08/27/84										
GWQ-12	09/12/84		-0.05	-0.001	-0.05			-0.005			
GWQ-12	09/21/84										
GWQ-12	11/19/84										
GWQ-12	11/27/84		-0.05	-0.001	-0.05			-0.005			
GWQ-12	12/17/84										
GWQ-12	05/27/85										
GWQ-12	11/13/85										
GWQ-12	05/23/86										
GWQ-12	10/08/86										
GWQ-12	07/21/94	19	-0.03	-0.001	-0.05	-0.05	3.2	-0.005	-0.025	29	-0.005
GWQ-12	04/01/97		0.14	-0.002							
GWQ-2	06/15/81	16	-0.05	0.0013	-0.05	-0.05	2.3	-0.005	-0.02	42	
GWQ-2	06/25/81	11.4	-0.02	-0.001	-0.1	-0.05	2.96	0.0022	-0.02	41.2	
GWQ-3	03/27/81										
GWQ-3	06/06/81										
GWQ-3	06/15/81	33	-0.05	-0.001	-0.05	-0.05	1.7	-0.005	-0.02	95	
GWQ-3	06/15/81	25.8	0.02	-0.001	-0.1	-0.05	2.66	0.0037	-0.02	86	
GWQ-3	02/25/82		-0.05	-0.001	-0.05			-0.005			
GWQ-3	05/12/82		-0.05	-0.001	-0.05			-0.005			
GWQ-3	06/30/82		-0.05	-0.001	-0.05			-0.005			
GWQ-3	12/23/82		-0.05	-0.001	-0.05			-0.005			
GWQ-3	02/21/83		-0.05	-0.001	-0.05			-0.005			
GWQ-3	05/13/83		-0.05	-0.001	0.11			-0.005			
GWQ-3	08/09/83		-0.05	-0.001	-0.05			-0.005			
GWQ-3	11/01/83		-0.05	-0.001	-0.05			-0.005			
GWQ-3	03/16/84		-0.05	-0.001	-0.05			-0.005			
GWQ-3	06/10/81										

Well Name	Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium	Thallium
GWQ-4	06/15/81	27	-0.05	-0.001	-0.05	-0.05	1.2	-0.005	-0.02	91	
GWQ-4	06/15/81	18.6	-0.02	-0.001	-0.1	-0.05	2.03	0.0025	-0.02	73.8	
GWQ-4	11/06/81		-0.05	-0.001	-0.05	-0.05		-0.005	-0.02		
GWQ-4	04/01/93	23	-0.02	-0.001	-0.02	-0.01	1	-0.005	-0.01	86	
GWQ-4	05/26/94	22	-0.03	-0.001	-0.05	-0.05	1.8	-0.005	-0.025	74	
GWQ-4	06/10/81										
GWQ-5	06/15/81	49	-0.05	-0.001	-0.05	-0.05	1.1	-0.005	-0.02	173	
GWQ-5	06/15/81	35.8	-0.02	-0.001	-0.1	-0.05	2.26	0.0062	-0.02	126	
GWQ-5	06/09/81										
GWQ-6	06/15/81	11.1	0.076	0.00235	-0.1	-0.05	2.4	0.0046	-0.02	57	
GWQ-6	06/15/81	16	0.11	-0.001	-0.05	-0.05	1.6	-0.005	-0.02	61	
GWQ-6	02/25/82		-0.05	-0.001	-0.05			-0.005			
GWQ-6	04/01/93	14	0.36	-0.001	-0.02	-0.01	3.1	-0.005	-0.01	53	
GWQ-6											
GWQ-6	01/20/81	14.6								781	
GWQ-7	02/02/81	27								51	
GWQ-7	02/02/81	27								51	
GWQ-7	03/27/81										
GWQ-7	03/27/81										
GWQ-7	04/06/81										
GWQ-7	06/09/81										
GWQ-7	06/15/81	24	-0.05	-0.001	-0.05	-0.05	1.6	-0.005	-0.02	61	
GWQ-7	06/15/81	15.7	-0.02	-0.001	-0.1	-0.05	2.33	-0.0005	-0.02	47.9	
GWQ-7	08/07/81	19.4								138.9	
GWQ-7	08/10/81	21								48	
GWQ-7	10/23/81		-0.05	-0.001	-0.05	-0.05		-0.005	-0.02		
GWQ-7	10/23/81		-0.05	-0.001	-0.05	-0.05		-0.005	-0.02		
GWQ-7	11/06/81		-0.05	-0.001	-0.05	-0.05		-0.005	-0.02		
GWQ-7	02/25/82		-0.05	-0.001	-0.05			-0.005			
GWQ-7	12/28/82		0.16	-0.001	-0.05			-0.005			
GWQ-7	02/21/83		0.27	-0.001	-0.05			-0.005			
GWQ-7	03/16/83		-0.05								
GWQ-7	05/13/83		-0.05	-0.001	-0.05			-0.005			
GWQ-7	08/09/83		-0.05	-0.001	-0.05			-0.005			
GWQ-7	11/01/83		-0.05	-0.001	-0.05			-0.005			
GWQ-7	03/16/84		-0.05	-0.001	0.08			-0.005			

Well Name	Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium	Thallium
GWQ-7	05/30/84		-0.05	-0.001	-0.05			-0.005			
GWQ-7	09/12/84		-0.05	-0.001	-0.05			-0.005			
GWQ-7	11/27/84		-0.05	-0.001	-0.05			-0.005			
GWQ-7	05/17/85										
GWQ-7	11/13/85										
GWQ-7	05/23/86										
GWQ-7	10/08/86										
GWQ-7	03/30/89	22	-0.05		-0.1	-0.1	2		-0.1	47	
GWQ-7	03/30/93	31	-0.02	-0.001	-0.02	-0.01	1.6	-0.005	-0.01	52	
GWQ-7	05/25/94	51	1.1	-0.001		-0.05	14	-0.005	-0.025	80	
GWQ-7	07/21/94	8.2	0.21	-0.001	-0.05	-0.05	13	-0.005	-0.025	47	-0.005
GWQ-8	06/04/76	15.5	0.003				1.72			76.1	
GWQ-8	02/02/81	20									
GWQ-8	06/09/81										
GWQ-8	08/19/81	12.1	0.047	-1	-0.1	-0.05	4.2	0.004	-0.02	84.1	
GWQ-8	10/01/81	12					4.2			84	
GWQ-8	02/25/82		0.17	-0.001	-0.05			-0.005			
GWQ-8	03/01/93	18					3.5			94	
GWQ-8	03/31/93	18	-0.02	-0.001	-0.02	-0.01	1.8	-0.005	-0.01	94	
GWQ-8	03/31/93	21	-0.01	-0.0002	-0.02	-0.02	3.5	-0.005	-0.01	94	
GWQ-8	05/25/94	20	-0.03	-0.001	-0.05	-0.05	2.4	-0.005	-0.025	76	
GWQ-8	04/01/97		-0.02	-0.002				0.056			
GWQ-8	04/14/98	25.2	-0.02	-0.0002	-0.05		1.7	-0.05		91.2	
GWQ-8	07/21/98	23.9	-0.02	0.0003	-0.05		2.3	-0.05		85.3	

Well Name	Date	Zinc	Temp (C)	Tin	Vanadium
GWQ-11	01/29/95				
GWQ-11	03/29/95				
GWQ-11	06/27/95				
GWQ-11	09/21/95				
GWQ-11	01/10/96				
GWQ-11	04/03/96				
GWQ-11	06/01/96				
GWQ-11	09/25/96				
GWQ-11	01/15/97				
GWQ-11	04/01/97				
GWQ-11	04/01/97				
GWQ-11	07/01/97				
GWQ-11	08/01/97				
GWQ-11	10/01/97				
GWQ-11	01/15/98				
GWQ-11	04/09/98				
GWQ-11	07/13/98				
GWQ-12	05/17/82				
GWQ-12	06/14/82				
GWQ-12	07/26/82				
GWQ-12	08/18/82				
GWQ-12	09/14/82				
GWQ-12	10/18/82				
GWQ-12	11/11/82				
GWQ-12	12/28/82				
GWQ-12	02/21/83				
GWQ-12	05/06/83				
GWQ-12	05/13/83				
GWQ-12	06/02/83				
GWQ-12	07/05/83				
GWQ-12	08/09/83				
GWQ-12	08/25/83				
GWQ-12	10/20/83				
GWQ-12	11/01/83				
GWQ-12	12/07/83				
GWQ-12	01/28/84				

Well Name	Date	Zinc	Temp (C)	Tin	Vanadium
GWQ-12	02/13/84				
GWQ-12	03/01/84				
GWQ-12	03/16/84				
GWQ-12	04/18/84				
GWQ-12	05/22/84				
GWQ-12	05/30/84				
GWQ-12	06/26/84				
GWQ-12	07/25/84				
GWQ-12	08/27/84				
GWQ-12	09/12/84				
GWQ-12	09/21/84				
GWQ-12	11/19/84				
GWQ-12	11/27/84				
GWQ-12	12/17/84				
GWQ-12	05/27/85				
GWQ-12	11/13/85				
GWQ-12	05/23/86				
GWQ-12	10/08/86				
GWQ-12	07/21/94	-0.05			
GWQ-12	04/01/97				
GWQ-2	06/15/81	0.16	21		
GWQ-2	06/25/81	0.11			
GWQ-3	03/27/81	0.016			
GWQ-3	06/06/81				
GWQ-3	06/15/81	0.32	19		
GWQ-3	06/15/81	0.061			
GWQ-3	02/25/82				
GWQ-3	05/12/82				
GWQ-3	06/30/82				
GWQ-3	12/23/82				
GWQ-3	02/21/83				
GWQ-3	05/13/83				
GWQ-3	08/09/83				
GWQ-3	11/01/83				
GWQ-3	03/16/84				
GWQ-3	06/10/81				

Well Name	Date	Zinc	Temp (C)	Tin	Vanadium
GWQ-4	06/15/81	0.056	20		
GWQ-4	06/15/81	-0.025			
GWQ-4	11/06/81	0.28			
GWQ-4	04/01/93	0.38			
GWQ-4	05/26/94	0.56			
GWQ-4	06/10/81				
GWQ-5	06/15/81	0.064	20		
GWQ-5	06/15/81	-0.025			
GWQ-5	06/09/81				
GWQ-6	06/15/81	-0.025			
GWQ-6	06/15/81	-0.05	20.5		
GWQ-6	02/25/82				
GWQ-6	04/01/93	0.03			
GWQ-6					
GWQ-6	01/20/81				
GWQ-7	02/02/81				
GWQ-7	02/02/81				
GWQ-7	03/27/81	0.28			
GWQ-7	03/27/81	0.28			
GWQ-7	04/06/81	0.24			
GWQ-7	06/09/81				
GWQ-7	06/15/81	0.38	22		
GWQ-7	06/15/81	0.278			
GWQ-7	08/07/81				
GWQ-7	08/10/81	0.63			
GWQ-7	10/23/81	0.41			
GWQ-7	10/23/81	0.16			
GWQ-7	11/06/81	0.19			
GWQ-7	02/25/82				
GWQ-7	12/28/82				
GWQ-7	02/21/83				
GWQ-7	03/16/83				
GWQ-7	05/13/83				
GWQ-7	08/09/83				
GWQ-7	11/01/83				
GWQ-7	03/16/84				

Well Name	Date	Zinc	Temp (C)	Tin	Vanadium
GWQ-7	05/30/84				
GWQ-7	09/12/84				
GWQ-7	11/27/84				
GWQ-7	05/17/85				
GWQ-7	11/13/85				
GWQ-7	05/23/86				
GWQ-7	10/08/86				
GWQ-7	03/30/89	0.1		0.2	-0.1
GWQ-7	03/30/93	0.1			
GWQ-7	05/25/94	-0.05			
GWQ-7	07/21/94	-0.05			
GWQ-8	06/04/76				
GWQ-8	02/02/81				
GWQ-8	06/09/81				
GWQ-8	08/19/81	0.69			
GWQ-8	10/01/81				
GWQ-8	02/25/82				
GWQ-8	03/01/93				
GWQ-8	03/31/93	0.09			
GWQ-8	03/31/93	0.075			
GWQ-8	05/25/94	-0.05			
GWQ-8	04/01/97				
GWQ-8	04/14/98				
GWQ-8	07/21/98				

Well Name	Water Depth	USGS Quad	Well Depth		Sample ID	Sample Date	Sampler	Notes
GWQ-9				-1	GWQ-9-1	6/4/1976	SHB	
GWQ-9				-2	GWQ-9-2	1/20/1981	SHB	QMC-2,CI,Na incon
GWQ-9				-3	GWQ-9-3	2/2/1981		
GWQ-9				-4	GWQ-9-4	2/2/1981	SHB	Qmc-2 in SHB (198
GWQ-9				-5	GWQ-9-5	3/27/1981		
GWQ-9				-6	GWQ-9-6	3/27/1981	SHB	Qmc-2 in SHB (198
GWQ-9				-7	GWQ-9-7	4/6/1981		
GWQ-9	197			-8	GWQ-9-8	6/10/1981	SHB	
GWQ-9				-9	GWQ-9-9	8/7/1981		
GWQ-9				-10	GWQ-9-10	8/10/1981		
GWQ-9				-11	GWQ-9-11	10/8/1981	QMC	
GWQ-9				-12	GWQ-9-12	2/25/1982	QMC	
GWQ-9				-13	GWQ-9-13	12/28/1982	QMC	
GWQ-9				-14	GWQ-9-14	2/21/1983	QMC	
GWQ-9				-15	GWQ-9-15	5/13/1983	QMC	
GWQ-9				-16	GWQ-9-16	8/9/1983	QMC	
GWQ-9				-17	GWQ-9-17	11/1/1983	QMC	
GWQ-9				-18	GWQ-9-18	3/16/1984	CFP	
GWQ-9				-19	GWQ-9-19	5/30/1984	CFP	
GWQ-9				-20	GWQ-9-20	9/12/1984	CFP	labeled "GWQ-9a"
GWQ-9				-21	GWQ-9-21	11/27/1984	CFP	
GWQ-9				-22	GWQ-9-22	5/17/1985	CFP	
GWQ-9	20.9			-23	GWQ-9-23	6/27/1985	QMC	
GWQ-9	20			-24	GWQ-9-24	11/13/1985	CFP	
GWQ-9	17.2			-25	GWQ-9-25	5/23/1985	CFP	
GWQ-9	17.4			-26	GWQ-9-26	10/8/1986	CFP	
GWQ-9				-27	GWQ-9-27	8/1/1997		
GWQ-94-13				-1	GWQ-94-13-1	11/15/1994	SRK	
GWQ-94-13				-2	GWQ-94-13-2	7/1/1996	ABC	
GWQ-94-13				-3	GWQ-94-13-3	8/1/1997		
GWQ-94-14				-1	GWQ-94-14-1	11/14/1994	SRK	
GWQ-94-14				-2	GWQ-94-14-2	6/30/1996	ABC	
GWQ-94-14				-3	GWQ-94-14-3	8/1/1997		
GWQ-94-15				-1	GWQ-94-15-1	11/14/1994	SRK	
GWQ-94-15				-2	GWQ-94-15-2	7/1/1996	ABC	
GWQ-94-15				-3	GWQ-94-15-3	8/1/1997		

Well Name	Water Depth	USGS Quad	Well Depth		Sample ID	Sample Date	Sampler	Notes
GWQ-94-15				-4	GWQ-94-15-4	10/1/1997		
GWQ-94-15	0.54			-5	GWQ-94-15-5	1/24/1998	Goff	
GWQ-94-15	0.49			-6	GWQ-94-15-6	2/1/1998		
GWQ-94-15	0.43			-7	GWQ-94-15-7	3/1/1998		
GWQ-94-15	0.6			-8	GWQ-94-15-8	4/14/1998	Goff	
GWQ-94-15	0.61			-9	GWQ-94-15-9	5/1/1998		
GWQ-94-15	0.83			-10	GWQ-94-15-1	6/1/1998		
GWQ-94-15	1.03			-11	GWQ-94-15-1	7/21/1998	Brownfield	
GWQ-94-15	1.03			-12	GWQ-94-15-1	8/1/1998		
GWQ-94-15	1.1			-13	GWQ-94-15-1	9/1/1998		
GWQ-94-15		Skute Stone Arroyo		-14	GWQ-94-15-1	10/15/1998	Goff	
GWQ-94-16		Skute Stone Arroyo		-1	GWQ-94-16-1	11/13/1994	SRK	
GWQ-94-16		Skute Stone Arroyo		-2	GWQ-94-16-2	7/1/1996	ABC	
GWQ-94-17		Skute Stone Arroyo		-1	GWQ-94-17-1	11/15/1994	SRK	
GWQ-94-17		Skute Stone Arroyo		-2	GWQ-94-17-2	6/30/1996	ABC	
GWQ-94-17		Skute Stone Arroyo		-3	GWQ-94-17-3	5/1/1997		
GWQ-94-17	6.11	Skute Stone Arroyo		-4	GWQ-94-17-4	1/24/1998	Goff	
GWQ-94-17	6.1	Skute Stone Arroyo		-5	GWQ-94-17-5	2/1/1998		
GWQ-94-17	6.8	Skute Stone Arroyo		-6	GWQ-94-17-6	3/1/1998		
GWQ-94-17	6.13	Skute Stone Arroyo		-7	GWQ-94-17-7	4/14/1998	Goff	
GWQ-94-17	6.22	Skute Stone Arroyo		-8	GWQ-94-17-8	5/1/1998		
GWQ-94-17	6.34	Skute Stone Arroyo		-9	GWQ-94-17-9	5/1/1998		
GWQ-94-17	6.55	Skute Stone Arroyo		-10	GWQ-94-17-1	7/21/1998	Brownfield	
GWQ-94-17	6.55	Skute Stone Arroyo		-11	GWQ-94-17-1	8/1/1998		
GWQ-94-17	6.59	Skute Stone Arroyo		-12	GWQ-94-17-1	9/1/1998		
GWQ-94-20		Skute Stone Arroyo		-1	GWQ-94-20-1	11/15/1994	SRK	
GWQ-94-20		Skute Stone Arroyo		-2	GWQ-94-20-2	6/30/1996	ABC	
GWQ-94-20		Skute Stone Arroyo		-3	GWQ-94-20-3	8/1/1997		
GWQ-94-21A		Skute Stone Arroyo		-1	GWQ-94-21A-	11/13/1994	SRK	
GWQ-94-21A		Skute Stone Arroyo		-2	GWQ-94-21A-	6/30/1996	ABC	
GWQ-94-21A	2.41	Skute Stone Arroyo		-3	GWQ-94-21A-	1/24/1998	Goff	
GWQ-94-21A	2.1	Skute Stone Arroyo		-4	GWQ-94-21A-	2/1/1998		
GWQ-94-21A	2.01	Skute Stone Arroyo		-5	GWQ-94-21A-	3/1/1998		
GWQ-94-21A	2.11	Skute Stone Arroyo		-6	GWQ-94-21A-	4/14/1998	Goff	
GWQ-94-21A	2.53	Skute Stone Arroyo		-7	GWQ-94-21A-	5/1/1998		
GWQ-94-21A	2.64	Skute Stone Arroyo		-8	GWQ-94-21A-	6/1/1998		

Well Name	Water Depth	USGS Quad	Well Depth		Sample ID	Sample Date	Sampler	Notes
GWQ-94-21A	3.44	Skute Stone Arroyo		-9	GWQ-94-21A-	7/21/1998	Brownfield	
GWQ-94-21A	2.8	Skute Stone Arroyo		-10	GWQ-94-21A-	8/1/1998		
GWQ-94-21A	2.86	Skute Stone Arroyo		-11	GWQ-94-21A-	9/1/1998		
GWQ-94-21B		Skute Stone Arroyo		-1	GWQ-94-21B-	11/13/1994	SRK	
GWQ-94-21B		Skute Stone Arroyo		-2	GWQ-94-21B-	6/30/1996	ABC	
GWQ-96-22A				-1	GWQ-96-22A-	7/13/1996	ABC	
GWQ-96-22A	44.93			-2	GWQ-96-22A-	2/5/1997	SRK	
GWQ-96-22A				-3	GWQ-96-22A-	4/1/1997		
GWQ-96-22A				-4	GWQ-96-22A-	8/1/1997		
GWQ-96-22A				-5	GWQ-96-22A-	8/8/1997	SRK	
GWQ-96-22A				-6	GWQ-96-22A-	10/1/1997		
GWQ-96-22A	45.92			-7	GWQ-96-22A-	1/24/1998	Goff	
GWQ-96-22A	46.09			-8	GWQ-96-22A-	2/1/1998		
GWQ-96-22A	46.74			-9	GWQ-96-22A-	3/1/1998		
GWQ-96-22A	47.27			-10	GWQ-96-22A-	4/14/1998	Goff	
GWQ-96-22A	47.89			-11	GWQ-96-22A-	5/1/1998		
GWQ-96-22A	48.24			-12	GWQ-96-22A-	6/1/1998		
GWQ-96-22A	46			-13	GWQ-96-22A-	7/21/1998	Brownfield	
GWQ-96-22A	45.1			-14	GWQ-96-22A-	8/1/1998		
GWQ-96-22A	46.5			-15	GWQ-96-22A-	9/1/1998		
GWQ-96-22A				-16	GWQ-96-22A-	10/15/1998	Goff	
GWQ-96-22B				-1	GWQ-96-22B-	7/13/1996	ABC	
GWQ-96-22B	45.22			-2	GWQ-96-22B-	2/5/1997	SRK	
GWQ-96-23A				-1	GWQ-96-23A-	7/14/1996	ABC	
GWQ-96-23A	35.18			-2	GWQ-96-23A-	2/5/1997	SRK	
GWQ-96-23A				-3	GWQ-96-23A-	4/1/1997		
GWQ-96-23A				-4	GWQ-96-23A-	4/1/1997		
GWQ-96-23A				-5	GWQ-96-23A-	8/1/1997		
GWQ-96-23A				-6	GWQ-96-23A-	8/8/1997	SRK	
GWQ-96-23A	35.89			-7	GWQ-96-23A-	1/24/1998	Goff	Dup sample had v. h
GWQ-96-23A	35.82			-8	GWQ-96-23A-	2/1/1998		
GWQ-96-23A	35.6			-9	GWQ-96-23A-	3/1/1998		
GWQ-96-23A	35.71			-10	GWQ-96-23A-	4/14/1998	Goff	
GWQ-96-23A	34.91			-11	GWQ-96-23A-	5/1/1998		
GWQ-96-23A	34.97			-12	GWQ-96-23A-	6/1/1998		
GWQ-96-23A	36.68			-13	GWQ-96-23A-	7/21/1998	Brownfield	

Well Name	Water Depth	USGS Quad	Well Depth		Sample ID	Sample Date	Sampler	Notes
GWQ-96-23A	36.32			-14	GWQ-96-23A-	8/1/1998		
GWQ-96-23A	36.35			-15	GWQ-96-23A-	9/1/1998		
GWQ-96-23A				-16	GWQ-96-23A-	10/15/1998	Goff	
GWQ-96-23B				-1	GWQ-96-23B-	7/14/1996	ABC	
GWQ-96-23B	36.745			-2	GWQ-96-23B-	2/5/1997	SRK	
GWQ-96-23B				-3	GWQ-96-23B-	4/1/1997		
GWQ-96-23B				-4	GWQ-96-23B-	4/1/1997		
Hansen	12.6			-1	Hansen-1	1/1/1998		
Hansen	12.5			-2	Hansen-2	2/1/1998		
Hansen	12.2			-3	Hansen-3	3/1/1998		
Hansen	11.3			-4	Hansen-4	4/1/1998		
Hansen	11			-5	Hansen-5	5/1/1998		
Hansen	11.25			-6	Hansen-6	6/1/1998		
Hansen	11.25			-7	Hansen-7	7/22/1998	Brownfield	
Hansen	12			-8	Hansen-8	8/1/1998		
Hansen	11			-9	Hansen-9	9/1/1998		
Highway		Skute Stone Arroyo		-1	Highway-1	5/27/1994	SRK	
Highway		Skute Stone Arroyo		-2	Highway-2	4/14/1998	Goff	Labeled "Birdy Wind"
Hill				-1	Hill-1	7/13/1947		
Humphries-Deep				-1	Humphries-De	10/1/1997		
Humphries-Deep	36.75			-2	Humphries-De	1/23/1998	Goff	
Humphries-Deep	36.5			-3	Humphries-De	2/1/1998		
Humphries-Deep	36.05			-4	Humphries-De	3/1/1998		
Humphries-Deep	36.29			-5	Humphries-De	4/15/1998	Goff	

Well Name	Sample Date	Latitude	Longitude	UTM Easting	UTM Northing	UTM Zone	Elevation	Filtered?	Chloride	Sulfate
GWQ-9	6/4/1976	32.96438	107.49539	266762	3649912	13	5195	TRUE	19.9	34
GWQ-9	1/20/1981	32.96438	107.49539	266762	3649912	13	5195	TRUE	200	300
GWQ-9	2/2/1981	32.96438	107.49539	266762	3649912	13	5195	FALSE	20	156
GWQ-9	2/2/1981	32.96438	107.49539	266762	3649912	13	5195	TRUE	20	156
GWQ-9	3/27/1981	32.96438	107.49539	266762	3649912	13	5195	FALSE		
GWQ-9	3/27/1981	32.96438	107.49539	266762	3649912	13	5195	TRUE		
GWQ-9	4/6/1981	32.96438	107.49539	266762	3649912	13	5195	FALSE		
GWQ-9	6/10/1981	32.96438	107.49539	266762	3649912	13	5195	TRUE		
GWQ-9	8/7/1981	32.96438	107.49539	266762	3649912	13	5195	FALSE	100	140
GWQ-9	8/10/1981	32.96438	107.49539	266762	3649912	13	5195	FALSE	22	148
GWQ-9	10/8/1981	32.96438	107.49539	266762	3649912	13	5195	TRUE	22.4	133
GWQ-9	2/25/1982	32.96438	107.49539	266762	3649912	13	5195	TRUE	26	160
GWQ-9	12/28/1982	32.96438	107.49539	266762	3649912	13	5195	TRUE	20	150
GWQ-9	2/21/1983	32.96438	107.49539	266762	3649912	13	5195	TRUE	20	161
GWQ-9	5/13/1983	32.96438	107.49539	266762	3649912	13	5195	TRUE	20	158
GWQ-9	8/9/1983	32.96438	107.49539	266762	3649912	13	5195	TRUE	20	135
GWQ-9	11/1/1983	32.96438	107.49539	266762	3649912	13	5195	TRUE	18	132
GWQ-9	3/16/1984	32.96438	107.49539	266762	3649912	13	5195	TRUE	18	132
GWQ-9	5/30/1984	32.96438	107.49539	266762	3649912	13	5195	TRUE	18	154
GWQ-9	9/12/1984	32.96438	107.49539	266762	3649912	13	5195	TRUE	20	132
GWQ-9	11/27/1984	32.96438	107.49539	266762	3649912	13	5195	TRUE	16	132
GWQ-9	5/17/1985	32.96438	107.49539	266762	3649912	13	5195	TRUE	20	149
GWQ-9	6/27/1985	32.96438	107.49539	266762	3649912	13	5195	FALSE		
GWQ-9	11/13/1985	32.96438	107.49539	266762	3649912	13	5195	FALSE	20	142
GWQ-9	5/23/1985	32.96438	107.49539	266762	3649912	13	5195	FALSE	36	137
GWQ-9	10/8/1986	32.96438	107.49539	266762	3649912	13	5195	FALSE	20	125
GWQ-9	8/1/1997	32.96438	107.49539	266762	3649912	13	5195	TRUE	55.1	
GWQ-94-13	11/15/1994	32.96113	107.49664	266637	3649555	13	5186	TRUE	190	720
GWQ-94-13	7/1/1996	32.96113	107.49664	266637	3649555	13	5186	TRUE	200	620
GWQ-94-13	8/1/1997	32.96113	107.49664	266637	3649555	13	5186	TRUE	196.1	
GWQ-94-14	11/14/1994	32.96082	107.49482	266806	3649515	13	5178	TRUE	22	140
GWQ-94-14	6/30/1996	32.96082	107.49482	266806	3649515	13	5178	TRUE	26	140
GWQ-94-14	8/1/1997	32.96082	107.49482	266806	3649515	13	5178	TRUE	32	
GWQ-94-15	11/14/1994	32.95942	107.49490	266794	3649361	13	5168	TRUE	110	180
GWQ-94-15	7/1/1996	32.95942	107.49490	266794	3649361	13	5168	TRUE	130	240
GWQ-94-15	8/1/1997	32.95942	107.49490	266794	3649361	13	5168	TRUE	51.7	

Well Name	Sample Date	Latitude	Longitude	UTM Easting	UTM Northing	UTM Zone	Elevation	Filtered?	Chloride	Sulfate
GWQ-94-15	10/1/1997	32.95942	107.49490	266794	3649361	13	5168	TRUE	53	150.5
GWQ-94-15	1/24/1998	32.95942	107.49490	266794	3649361	13	5168	TRUE	55.2	148
GWQ-94-15	2/1/1998	32.95942	107.49490	266794	3649361	13	5168			
GWQ-94-15	3/1/1998	32.95942	107.49490	266794	3649361	13	5168			
GWQ-94-15	4/14/1998	32.95942	107.49490	266794	3649361	13	5168	TRUE	73.6	158
GWQ-94-15	5/1/1998	32.95942	107.49490	266794	3649361	13	5168			
GWQ-94-15	6/1/1998	32.95942	107.49490	266794	3649361	13	5168			
GWQ-94-15	7/21/1998	32.95942	107.49490	266794	3649361	13	5168	TRUE	57.3	154
GWQ-94-15	8/1/1998	32.95942	107.49490	266794	3649361	13	5168			
GWQ-94-15	9/1/1998	32.95942	107.49490	266794	3649361	13	5168			
GWQ-94-15	10/15/1998	32.95942	107.49490	266794	3649361	13	5168	TRUE	53	150.5
GWQ-94-16	11/13/1994	32.96016	107.49671	266627	3649447	13	5183	TRUE	190	410
GWQ-94-16	7/1/1996	32.96016	107.49671	266627	3649447	13	5183	TRUE	200	500
GWQ-94-17	11/15/1994	32.96115	107.49601	266696	3649555	13	5183	TRUE	110	240
GWQ-94-17	6/30/1996	32.96115	107.49601	266696	3649555	13	5183	TRUE	81	190
GWQ-94-17	5/1/1997	32.96115	107.49601	266696	3649555	13	5183	TRUE	61.2	
GWQ-94-17	1/24/1998	32.96115	107.49601	266696	3649555	13	5183	TRUE	46.5	141
GWQ-94-17	2/1/1998	32.96115	107.49601	266696	3649555	13	5183			
GWQ-94-17	3/1/1998	32.96115	107.49601	266696	3649555	13	5183			
GWQ-94-17	4/14/1998	32.96115	107.49601	266696	3649555	13	5183	TRUE	47.5	136
GWQ-94-17	5/1/1998	32.96115	107.49601	266696	3649555	13	5183			
GWQ-94-17	5/1/1998	32.96115	107.49601	266696	3649555	13	5183			
GWQ-94-17	7/21/1998	32.96115	107.49601	266696	3649555	13	5183	TRUE	48.1	140
GWQ-94-17	8/1/1998	32.96115	107.49601	266696	3649555	13	5183			
GWQ-94-17	9/1/1998	32.96115	107.49601	266696	3649555	13	5183			
GWQ-94-20	11/15/1994	32.96148	107.49676	266626	3649593	13	5189	TRUE	19	40
GWQ-94-20	6/30/1996	32.96148	107.49676	266626	3649593	13	5189	TRUE	21	56
GWQ-94-20	8/1/1997	32.96148	107.49676	266626	3649593	13	5189	TRUE	22	
GWQ-94-21A	11/13/1994	32.96099	107.49399	266884	3649533	13	5177	TRUE	18	130
GWQ-94-21A	6/30/1996	32.96099	107.49399	266884	3649533	13	5177	TRUE	16	120
GWQ-94-21A	1/24/1998	32.96099	107.49399	266884	3649533	13	5177	TRUE	19.1	130
GWQ-94-21A	2/1/1998	32.96099	107.49399	266884	3649533	13	5177			
GWQ-94-21A	3/1/1998	32.96099	107.49399	266884	3649533	13	5177			
GWQ-94-21A	4/14/1998	32.96099	107.49399	266884	3649533	13	5177	TRUE	19.6	142
GWQ-94-21A	5/1/1998	32.96099	107.49399	266884	3649533	13	5177			
GWQ-94-21A	6/1/1998	32.96099	107.49399	266884	3649533	13	5177			

Well Name	Sample Date	Latitude	Longitude	UTM Easting	UTM Northing	UTM Zone	Elevation	Filtered?	Chloride	Sulfate
GWQ-94-21A	7/21/1998	32.96099	107.49399	266884	3649533	13	5177	TRUE	19.9	119
GWQ-94-21A	8/1/1998	32.96099	107.49399	266884	3649533	13	5177			
GWQ-94-21A	9/1/1998	32.96099	107.49399	266884	3649533	13	5177			
GWQ-94-21B	11/13/1994	32.96099	107.49399	266884	3649533	13	5177	TRUE	19	130
GWQ-94-21B	6/30/1996	32.96099	107.49399	266884	3649533	13	5177	TRUE	17	120
GWQ-96-22A	7/13/1996							TRUE	89	250
GWQ-96-22A	2/5/1997							TRUE		
GWQ-96-22A	4/1/1997							TRUE	96.5	267
GWQ-96-22A	8/1/1997							TRUE	93.2	
GWQ-96-22A	8/8/1997							TRUE	89	230
GWQ-96-22A	10/1/1997							TRUE	80	260
GWQ-96-22A	1/24/1998							TRUE	80.4	254
GWQ-96-22A	2/1/1998									
GWQ-96-22A	3/1/1998									
GWQ-96-22A	4/14/1998							TRUE	83.8	254
GWQ-96-22A	5/1/1998									
GWQ-96-22A	6/1/1998									
GWQ-96-22A	7/21/1998							TRUE	81.4	303.4
GWQ-96-22A	8/1/1998									
GWQ-96-22A	9/1/1998									
GWQ-96-22A	10/15/1998							TRUE	80	260
GWQ-96-22B	7/13/1996							TRUE	210	79
GWQ-96-22B	2/5/1997							TRUE		
GWQ-96-23A	7/14/1996							TRUE	22	140
GWQ-96-23A	2/5/1997							TRUE		
GWQ-96-23A	4/1/1997							TRUE	20	150
GWQ-96-23A	4/1/1997							TRUE	25	174
GWQ-96-23A	8/1/1997							TRUE	18.2	
GWQ-96-23A	8/8/1997							TRUE	18	410
GWQ-96-23A	1/24/1998							TRUE	19.6	85
GWQ-96-23A	2/1/1998									
GWQ-96-23A	3/1/1998									
GWQ-96-23A	4/14/1998							TRUE	18.9	323
GWQ-96-23A	5/1/1998									
GWQ-96-23A	6/1/1998									
GWQ-96-23A	7/21/1998							TRUE	18.6	330

Well Name	Sample Date	Latitude	Longitude	UTM Easting	UTM Northing	UTM Zone	Elevation	Filtered?	Chloride	Sulfate
GWQ-96-23A	8/1/1998									
GWQ-96-23A	9/1/1998									
GWQ-96-23A	10/15/1998							TRUE	18.3	450.7
GWQ-96-23B	7/14/1996							TRUE	20	170
GWQ-96-23B	2/5/1997							TRUE		
GWQ-96-23B	4/1/1997							TRUE	16	170
GWQ-96-23B	4/1/1997							TRUE	22.1	238
Hansen	1/1/1998									
Hansen	2/1/1998									
Hansen	3/1/1998									
Hansen	4/1/1998									
Hansen	5/1/1998									
Hansen	6/1/1998									
Hansen	7/22/1998							TRUE	26.5	21
Hansen	8/1/1998									
Hansen	9/1/1998									
Highway	5/27/1994							FALSE	23	42
Highway	4/14/1998							TRUE	22.6	50
Hill	7/13/1947							FALSE	10	76
Humphries-De	10/1/1997							TRUE	19.4	19
Humphries-De	1/23/1998							TRUE	18.6	18
Humphries-De	2/1/1998									
Humphries-De	3/1/1998									
Humphries-De	4/15/1998							TRUE	18.1	19

Well Name	Sample Date	pH	TDS	Alkalinity	Bicarb	Spec.Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
GWQ-9	6/4/1976	8.6	350		188	480	0.44	4			
GWQ-9	1/20/1981	7.4	450		305						
GWQ-9	2/2/1981	7.9	510		273						
GWQ-9	2/2/1981	7.9	510		273						
GWQ-9	3/27/1981						0.6	1.4			-0.01
GWQ-9	3/27/1981						0.6	1.4			-0.01
GWQ-9	4/6/1981						0.56	1.2			0.002
GWQ-9	6/10/1981										
GWQ-9	8/7/1981	7.4	450		268.4						
GWQ-9	8/10/1981	8	470		268		0.5	1.4			-0.01
GWQ-9	10/8/1981	7.22	476		302		0.6	0.96	-0.25		-0.004
GWQ-9	2/25/1982	8.3	430				0.5	0.9			
GWQ-9	12/28/1982	7.8	480				0.5	1			
GWQ-9	2/21/1983	8	480				0.5	1.4			
GWQ-9	5/13/1983	8.2	460				0.5	1.1			
GWQ-9	8/9/1983	8	480				0.5	0.9			
GWQ-9	11/1/1983	8.2	460				0.5	0.8			
GWQ-9	3/16/1984	8.1	460				0.7	1.7			
GWQ-9	5/30/1984	7.6	450				0.5	0.9			
GWQ-9	9/12/1984	8	470				0.5	1.3			
GWQ-9	11/27/1984	7.9	470				0.5	1.5			
GWQ-9	5/17/1985	8	490								
GWQ-9	6/27/1985										
GWQ-9	11/13/1985	7.8	450								
GWQ-9	5/23/1985	7.9	490								
GWQ-9	10/8/1986	7.6	460								
GWQ-9	8/1/1997	7.3	867				0.58				
GWQ-94-13	11/15/1994	7.74	1570		159	2026	0.36	4.6	-0.05	-0.005	-0.005
GWQ-94-13	7/1/1996	7.76	1520	128	156	2000	0.34	5.2	-0.025	-0.002	-0.005
GWQ-94-13	8/1/1997	7.2	1330				0.55				
GWQ-94-14	11/14/1994	7.95	560		279	745	0.52	1.3	-0.05	-0.005	-0.005
GWQ-94-14	6/30/1996	8.44	520	222	261	641	0.48	1.5	-0.025	-0.002	-0.005
GWQ-94-14	8/1/1997	7.32	475				0.55				
GWQ-94-15	11/14/1994	7.74	790		265	1058	0.46	2.1	-0.05	-0.005	-0.005
GWQ-94-15	7/1/1996	7.31	780	186	227	1190	0.42	2.5	-0.025	-0.002	-0.005
GWQ-94-15	8/1/1997	8.08	441				0.55				

Well Name	Sample Date	pH	TDS	Alkalinity	Bicarb	Spec.Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
GWQ-94-15	10/1/1997	7.56	530					1.45			
GWQ-94-15	1/24/1998	7.61	567		257.4	900	0.57				
GWQ-94-15	2/1/1998										
GWQ-94-15	3/1/1998										
GWQ-94-15	4/14/1998	7.5	563			872	0.58	1.6			
GWQ-94-15	5/1/1998										
GWQ-94-15	6/1/1998										
GWQ-94-15	7/21/1998		505				0.58	1.7			
GWQ-94-15	8/1/1998										
GWQ-94-15	9/1/1998										
GWQ-94-15	10/15/1998	7.56	530			915		1.45			
GWQ-94-16	11/13/1994	7.55	1140		199	1600	0.66	3.8	-0.05	-0.005	-0.005
GWQ-94-16	7/1/1996	7.95	1160	158	193	1620	0.57	3.7	-0.025	-0.002	-0.005
GWQ-94-17	11/15/1994	7.71	820		232	1147	0.46	2.4	-0.05	-0.005	-0.005
GWQ-94-17	6/30/1996	8.56	690	198	227	925	0.46	2	-0.025	-0.002	-0.005
GWQ-94-17	5/1/1997	7.18	558				0.57				
GWQ-94-17	1/24/1998	7.64	519		262.3	837	0.6				
GWQ-94-17	2/1/1998										
GWQ-94-17	3/1/1998										
GWQ-94-17	4/14/1998	7.51	502			855	0.6	1.4			
GWQ-94-17	5/1/1998										
GWQ-94-17	5/1/1998										
GWQ-94-17	7/21/1998		553				0.67	1.59			
GWQ-94-17	8/1/1998										
GWQ-94-17	9/1/1998										
GWQ-94-20	11/15/1994	7.66	370		296	588	0.36	1	-0.05	-0.005	-0.005
GWQ-94-20	6/30/1996	8.79	390	256	273	597	0.29	-1	-0.025	-0.002	-0.005
GWQ-94-20	8/1/1997	7.31	361				0.37				
GWQ-94-21A	11/13/1994	7.25	480		267	672	0.57	1	-0.05	-0.005	-0.005
GWQ-94-21A	6/30/1996	8.22	470	220	268	649	0.51	1.1	-0.025	-0.002	-0.005
GWQ-94-21A	1/24/1998	7.72	472		258	791	0.61				
GWQ-94-21A	2/1/1998										
GWQ-94-21A	3/1/1998										
GWQ-94-21A	4/14/1998	7.96	474			760	0.71	1.16			
GWQ-94-21A	5/1/1998										
GWQ-94-21A	6/1/1998										

Well Name	Sample Date	pH	TDS	Alkalinity	Bicarb	Spec.Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
GWQ-94-21A	7/21/1998		464				0.7	1.34			
GWQ-94-21A	8/1/1998										
GWQ-94-21A	9/1/1998										
GWQ-94-21B	11/13/1994	7.57	440		255	669	0.39	-1	-0.05	-0.005	-0.005
GWQ-94-21B	6/30/1996	8.6	470	226	256	648	0.52	1.1	-0.025	-0.002	-0.005
GWQ-96-22A	7/13/1996	7.5	700	102	124	1040	3.3	-1	-0.025	-0.003	-0.005
GWQ-96-22A	2/5/1997										
GWQ-96-22A	4/1/1997		707				1.7				
GWQ-96-22A	8/1/1997	7.32	687				2.5				
GWQ-96-22A	8/8/1997	7.65	700	145	177	1140	2.2	-1	0.028		-0.005
GWQ-96-22A	10/1/1997	7.69	689				0.8	-0.05			
GWQ-96-22A	1/24/1998	7.59	665		154.3	1190	2.53				
GWQ-96-22A	2/1/1998										
GWQ-96-22A	3/1/1998										
GWQ-96-22A	4/14/1998	7.65	655		148	1130	3	0.1			
GWQ-96-22A	5/1/1998										
GWQ-96-22A	6/1/1998										
GWQ-96-22A	7/21/1998		669				2.86	0.07			
GWQ-96-22A	8/1/1998										
GWQ-96-22A	9/1/1998										
GWQ-96-22A	10/15/1998	7.69	689			1120		-0.05			
GWQ-96-22B	7/13/1996	7.75	650	116	141	1070	1.8	-1	-0.025	-0.003	-0.005
GWQ-96-22B	2/5/1997										
GWQ-96-23A	7/14/1996	7.95	520	230	280	760	0.84	-1	0.28	-0.003	-0.005
GWQ-96-23A	2/5/1997										
GWQ-96-23A	4/1/1997		770								
GWQ-96-23A	4/1/1997		737				0.5				
GWQ-96-23A	8/1/1997	7.03	939				1.3				
GWQ-96-23A	8/8/1997	7.68	920	269	328	1130	1.2	-1	0.036		-0.005
GWQ-96-23A	1/24/1998	7.8	519		503.25	933	1.76				
GWQ-96-23A	2/1/1998										
GWQ-96-23A	3/1/1998										
GWQ-96-23A	4/14/1998	7.57	918			1390	1.54	-0.05			
GWQ-96-23A	5/1/1998										
GWQ-96-23A	6/1/1998										
GWQ-96-23A	7/21/1998		916				1.69	-0.05			

Well Name	Sample Date	pH	TDS	Alkalinity	Bicarb	Spec.Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
GWQ-96-23A	8/1/1998										
GWQ-96-23A	9/1/1998										
GWQ-96-23A	10/15/1998	7.67	986			1320		-0.05			
GWQ-96-23B	7/14/1996	8.15	550	200	234	780	1.1	-1	7.4	-0.003	-0.005
GWQ-96-23B	2/5/1997										
GWQ-96-23B	4/1/1997		580				1.4				
GWQ-96-23B	4/1/1997		375				0.8				
Hansen	1/1/1998										
Hansen	2/1/1998										
Hansen	3/1/1998										
Hansen	4/1/1998										
Hansen	5/1/1998										
Hansen	6/1/1998										
Hansen	7/22/1998		232				0.59	0.7			
Hansen	8/1/1998										
Hansen	9/1/1998										
Highway	5/27/1994	8.19	342		227	513	0.89	2.4	-0.05	0.0076	-0.005
Highway	4/14/1998	8.38	304			545	1.1	2.2			
Hill	7/13/1947		320		190	426	0.6	0.7			
Humphries-Deep	10/1/1997	8.05	259					-0.05			
Humphries-Deep	1/23/1998	7.33	267		253.8	539	0.2				
Humphries-Deep	2/1/1998										
Humphries-Deep	3/1/1998										
Humphries-Deep	4/15/1998	7.6	290			501	0.22	0.15			

Well Name	Sample Date	Boron	Barium	Berylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
GWQ-9	6/4/1976	-0.1				69.2				0.004	
GWQ-9	1/20/1981					92				0.05	
GWQ-9	2/2/1981					73				1.8	
GWQ-9	2/2/1981					73				1.8	
GWQ-9	3/27/1981								-0.05		-0.02
GWQ-9	3/27/1981								-0.05		-0.02
GWQ-9	4/6/1981								-0.05		-0.01
GWQ-9	6/10/1981										
GWQ-9	8/7/1981					80				0.06	
GWQ-9	8/10/1981					76			-0.05	0.49	0.033
GWQ-9	10/8/1981	0.044	-1		-0.01	51.8	-0.05	-0.05	-0.05	-0.1	-0.05
GWQ-9	2/25/1982				-0.005				-0.05	-0.1	
GWQ-9	12/28/1982				-0.005				-0.05	-0.1	
GWQ-9	2/21/1983				-0.005				-0.05	-0.1	
GWQ-9	5/13/1983				-0.005				-0.05	-0.1	
GWQ-9	8/9/1983				-0.005				-0.05	-0.1	
GWQ-9	11/1/1983				-0.005				-0.05	-0.1	
GWQ-9	3/16/1984				-0.005				-0.05	-0.1	
GWQ-9	5/30/1984				-0.005				-0.05	-0.1	
GWQ-9	9/12/1984				-0.005				-0.05	-0.1	
GWQ-9	11/27/1984				-0.005				-0.05	-0.1	
GWQ-9	5/17/1985										
GWQ-9	6/27/1985										
GWQ-9	11/13/1985										
GWQ-9	5/23/1985										
GWQ-9	10/8/1986										
GWQ-9	8/1/1997										
GWQ-94-13	11/15/1994	-0.1	-0.1	-0.002	-0.0005	270	-0.025	-0.05	-0.025	0.11	-0.005
GWQ-94-13	7/1/1996	-0.05	-0.05	-0.002	-0.0005	290	-0.025	-0.05	-0.025	-0.05	-0.005
GWQ-94-13	8/1/1997										
GWQ-94-14	11/14/1994	-0.1	-0.1	-0.002	-0.0005	81	-0.025	-0.05	-0.025	-0.05	-0.005
GWQ-94-14	6/30/1996	-0.05	-0.05	-0.002	-0.0005	87	-0.025	-0.05	-0.025	-0.05	-0.005
GWQ-94-14	8/1/1997										
GWQ-94-15	11/14/1994	-0.1	-0.1	-0.002	-0.0005	110	-0.025	-0.05	-0.025	-0.05	-0.005
GWQ-94-15	7/1/1996	-0.05	-0.05	-0.002	-0.0005	140	-0.025	-0.05	-0.025	0.41	-0.005
GWQ-94-15	8/1/1997										

Well Name	Sample Date	Boron	Barium	Berylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
GWQ-94-15	10/1/1997								-0.005	-0.05	
GWQ-94-15	1/24/1998					84			-0.005		
GWQ-94-15	2/1/1998										
GWQ-94-15	3/1/1998										
GWQ-94-15	4/14/1998					99.9			-0.005	-0.05	
GWQ-94-15	5/1/1998										
GWQ-94-15	6/1/1998										
GWQ-94-15	7/21/1998					66.9			-0.005	-0.05	
GWQ-94-15	8/1/1998										
GWQ-94-15	9/1/1998										
GWQ-94-15	10/15/1998								-0.005	-0.05	
GWQ-94-16	11/13/1994	-0.1	-0.1	-0.002	-0.0005	190	-0.025	-0.05	-0.025	-0.05	-0.005
GWQ-94-16	7/1/1996	-0.05	-0.05	-0.002	-0.0005	200	-0.025	-0.05	-0.025	0.22	-0.005
GWQ-94-17	11/15/1994	-0.1	-0.1	-0.002	-0.0005	120	-0.025	-0.05	-0.025	-0.05	-0.005
GWQ-94-17	6/30/1996	-0.05	-0.05	-0.002	-0.0005	120	-0.025	-0.05	-0.025	0.062	-0.005
GWQ-94-17	5/1/1997										
GWQ-94-17	1/24/1998					84.9			-0.005		
GWQ-94-17	2/1/1998										
GWQ-94-17	3/1/1998										
GWQ-94-17	4/14/1998					97.6			-0.005	-0.05	
GWQ-94-17	5/1/1998										
GWQ-94-17	5/1/1998										
GWQ-94-17	7/21/1998					91.2			-0.005	0.23	
GWQ-94-17	8/1/1998										
GWQ-94-17	9/1/1998										
GWQ-94-20	11/15/1994	0.11	-0.1	-0.002	-0.0005	48	-0.025	-0.05	-0.025	-0.05	-0.005
GWQ-94-20	6/30/1996	0.086	0.12	-0.002	-0.0005	58	-0.025	-0.05	-0.025	-0.05	-0.005
GWQ-94-20	8/1/1997										
GWQ-94-21A	11/13/1994	-0.1	-0.1	-0.002	-0.0005	82	-0.025	-0.05	-0.025	-0.05	-0.005
GWQ-94-21A	6/30/1996	-0.05	-0.05	-0.002	-0.0005	86	-0.025	-0.05	-0.025	-0.05	-0.005
GWQ-94-21A	1/24/1998					73.3			-0.005		
GWQ-94-21A	2/1/1998										
GWQ-94-21A	3/1/1998										
GWQ-94-21A	4/14/1998					88.4			-0.005	-0.05	
GWQ-94-21A	5/1/1998										
GWQ-94-21A	6/1/1998										

Well Name	Sample Date	Boron	Barium	Berylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
GWQ-94-21A	7/21/1998					83.9			0.017	-0.05	
GWQ-94-21A	8/1/1998										
GWQ-94-21A	9/1/1998										
GWQ-94-21B	11/13/1994	-0.1	-0.1	-0.002	-0.0005	71	-0.025	-0.05	-0.025	-0.05	-0.005
GWQ-94-21B	6/30/1996	-0.05	-0.05	-0.002	-0.0005	87	-0.025	-0.05	-0.025	-0.05	-0.005
GWQ-96-22A	7/13/1996	-0.05	-0.05	-0.002	-0.0005	71	-0.025	-0.05	-0.025	-0.05	-0.005
GWQ-96-22A	2/5/1997										
GWQ-96-22A	4/1/1997								-0.005	1.2	
GWQ-96-22A	8/1/1997										
GWQ-96-22A	8/8/1997	0.23	0.057	-0.002	-0.002	73	-0.025	-0.05	-0.025	0.13	-0.005
GWQ-96-22A	10/1/1997								-0.005	0.61	
GWQ-96-22A	1/24/1998					60			-0.005		
GWQ-96-22A	2/1/1998										
GWQ-96-22A	3/1/1998										
GWQ-96-22A	4/14/1998					67.3			0.007	0.07	
GWQ-96-22A	5/1/1998										
GWQ-96-22A	6/1/1998										
GWQ-96-22A	7/21/1998					69.3			-0.005	-0.05	
GWQ-96-22A	8/1/1998										
GWQ-96-22A	9/1/1998										
GWQ-96-22A	10/15/1998								-0.005	0.61	
GWQ-96-22B	7/13/1996	0.12	0.096	-0.002	-0.0005	66	-0.025	-0.05	-0.025	-0.05	-0.005
GWQ-96-22B	2/5/1997										
GWQ-96-23A	7/14/1996	-0.05	0.064	-0.002	-0.0005	59	-0.025	-0.05	-0.025	0.26	-0.005
GWQ-96-23A	2/5/1997										
GWQ-96-23A	4/1/1997										
GWQ-96-23A	4/1/1997								-0.005		
GWQ-96-23A	8/1/1997										
GWQ-96-23A	8/8/1997	0.0687	0.13	-0.002	-0.002	130	0.025	-0.05	-0.025	0.82	-0.005
GWQ-96-23A	1/24/1998					80.3			-0.005		
GWQ-96-23A	2/1/1998										
GWQ-96-23A	3/1/1998										
GWQ-96-23A	4/14/1998					169.4			0.019	0.41	
GWQ-96-23A	5/1/1998										
GWQ-96-23A	6/1/1998										
GWQ-96-23A	7/21/1998					168.1			-0.005	2.59	

Well Name	Sample Date	Boron	Barium	Berylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
GWQ-96-23A	8/1/1998										
GWQ-96-23A	9/1/1998										
GWQ-96-23A	10/15/1998								-0.005	0.65	
GWQ-96-23B	7/14/1996	0.058	0.093	-0.002	-0.0005	67	-0.025	-0.05	-0.025	3.7	-0.005
GWQ-96-23B	2/5/1997										
GWQ-96-23B	4/1/1997								-0.025	0.1	
GWQ-96-23B	4/1/1997								-0.005	0.25	
Hansen	1/1/1998										
Hansen	2/1/1998										
Hansen	3/1/1998										
Hansen	4/1/1998										
Hansen	5/1/1998										
Hansen	6/1/1998										
Hansen	7/22/1998					19.7			-0.005	-0.05	
Hansen	8/1/1998										
Hansen	9/1/1998										
Highway	5/27/1994	-0.01	-0.1	-0.002	-0.0005	63	-0.025	-0.05	-0.025	-0.05	-0.005
Highway	4/14/1998					63.6			0.014	0.22	
Hill	7/13/1947					37					
Humphries-Deep	10/1/1997								-0.005	0.17	
Humphries-Deep	1/23/1998					61.3			-0.005		
Humphries-Deep	2/1/1998										
Humphries-Deep	3/1/1998										
Humphries-Deep	4/15/1998					66.2			-0.005	-0.05	

Well Name	Sample Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium
GWQ-9	6/4/1976	15.2	0.001				1.56			30
GWQ-9	1/20/1981	9.7								703
GWQ-9	2/2/1981	24								49
GWQ-9	2/2/1981	24								49
GWQ-9	3/27/1981									
GWQ-9	3/27/1981									
GWQ-9	4/6/1981									
GWQ-9	6/10/1981									
GWQ-9	8/7/1981	19.4								128.9
GWQ-9	8/10/1981	20								47
GWQ-9	10/8/1981	17.1	-0.02	-1	-0.1	-0.05	3.3	-0.002	-0.02	71
GWQ-9	2/25/1982		-0.05	-0.001	-0.05			-0.005		
GWQ-9	12/28/1982		-0.05	-0.001	-0.05			-0.005		
GWQ-9	2/21/1983		-0.05	-0.001	-0.05			-0.005		
GWQ-9	5/13/1983		-0.05	-0.001	-0.05			-0.005		
GWQ-9	8/9/1983		-0.05	-0.001	-0.05			-0.005		
GWQ-9	11/1/1983		-0.05	-0.001	-0.05			-0.005		
GWQ-9	3/16/1984		-0.05	-0.001	-0.05			-0.005		
GWQ-9	5/30/1984		-0.05	-0.001	-0.05			-0.005		
GWQ-9	9/12/1984		-0.05	-0.001	-0.05			-0.005		
GWQ-9	11/27/1984		-0.05	-0.001	-0.05			-0.005		
GWQ-9	5/17/1985									
GWQ-9	6/27/1985									
GWQ-9	11/13/1985									
GWQ-9	5/23/1985									
GWQ-9	10/8/1986									
GWQ-9	8/1/1997									
GWQ-94-13	11/15/1994	56	-0.03	-0.001	-0.05	-0.05	3.9	-0.005	-0.025	110
GWQ-94-13	7/1/1996	62	-0.03	-0.001	-0.05	-0.05	3.6	0.0068	-0.05	120
GWQ-94-13	8/1/1997									
GWQ-94-14	11/14/1994	23	-0.03	-0.001	-0.05	-0.05	1.9	-0.005	-0.025	46
GWQ-94-14	6/30/1996	23	-0.03	-0.001	-0.05	-0.05	1.9	-0.005	-0.05	51
GWQ-94-14	8/1/1997									
GWQ-94-15	11/14/1994	29	-0.03	-0.001	-0.05	-0.05	2.5	-0.005	-0.025	68
GWQ-94-15	7/1/1996	38	-0.03	-0.001	-0.05	-0.05	2.4	-0.005	-0.05	77
GWQ-94-15	8/1/1997									

Well Name	Sample Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium
GWQ-94-15	10/1/1997									
GWQ-94-15	1/24/1998	25.4	-0.02				5.5			54.2
GWQ-94-15	2/1/1998									
GWQ-94-15	3/1/1998									
GWQ-94-15	4/14/1998	25.9	-0.02	-0.0002	-0.05		1.3	-0.05		52.8
GWQ-94-15	5/1/1998									
GWQ-94-15	6/1/1998									
GWQ-94-15	7/21/1998	24	-0.02	0.0003	-0.05		2	-0.05		49.5
GWQ-94-15	8/1/1998									
GWQ-94-15	9/1/1998									
GWQ-94-15	10/15/1998									
GWQ-94-16	11/13/1994	51	0.038	-0.001	-0.05	-0.05	3.7	-0.005	-0.025	78
GWQ-94-16	7/1/1996	54	-0.03	-0.001	-0.05	-0.05	3.4	-0.005	-0.05	80
GWQ-94-17	11/15/1994	33	-0.03	-0.001	-0.05	-0.05	2.4	-0.005	-0.025	62
GWQ-94-17	6/30/1996	28	-0.03	-0.001	-0.05	-0.05	2	-0.005	-0.05	61
GWQ-94-17	5/1/1997									
GWQ-94-17	1/24/1998	23.3	-0.02				5.2			45.7
GWQ-94-17	2/1/1998									
GWQ-94-17	3/1/1998									
GWQ-94-17	4/14/1998	23.5	-0.02	-0.0002	-0.05		1.2	-0.05		44.7
GWQ-94-17	5/1/1998									
GWQ-94-17	5/1/1998									
GWQ-94-17	7/21/1998	22.3	-0.02	0.0004	-0.05		2.1	-0.05		41.8
GWQ-94-17	8/1/1998									
GWQ-94-17	9/1/1998									
GWQ-94-20	11/15/1994	9.8	0.42	-0.001	-0.05	-0.05	3.2	-0.005	-0.025	67
GWQ-94-20	6/30/1996	10	-0.03	-0.001	-0.05	-0.05	3.1	-0.005	-0.05	75
GWQ-94-20	8/1/1997									
GWQ-94-21A	11/13/1994	23	0.2	-0.001	-0.05	-0.05	2.1	-0.005	-0.025	39
GWQ-94-21A	6/30/1996	22	-0.03	-0.001	-0.05	-0.05	1.5	-0.005	-0.05	37
GWQ-94-21A	1/24/1998	22.1	-0.02				4.3			35.3
GWQ-94-21A	2/1/1998									
GWQ-94-21A	3/1/1998									
GWQ-94-21A	4/14/1998	23.2	-0.02	-0.0002	-0.05		1.4	-0.05		35.7
GWQ-94-21A	5/1/1998									
GWQ-94-21A	6/1/1998									

Well Name	Sample Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium
GWQ-94-21A	7/21/1998	22	-0.02	0.0002	-0.05		2	-0.05		
GWQ-94-21A	8/1/1998									
GWQ-94-21A	9/1/1998									
GWQ-94-21B	11/13/1994	18	0.37	-0.001	-0.05	-0.05	2.6	-0.005	-0.025	56
GWQ-94-21B	6/30/1996	22	-0.03	-0.001	-0.05	-0.05	1.7	-0.005	-0.05	40
GWQ-96-22A	7/13/1996	6.7	0.075	-0.001	-0.05	-0.05	2.5	-0.005	-0.05	150
GWQ-96-22A	2/5/1997									
GWQ-96-22A	4/1/1997		0.44	-0.002				-0.001		
GWQ-96-22A	8/1/1997									
GWQ-96-22A	8/8/1997	8.2	0.53		-0.05	-0.05	6.2	-0.005	-0.025	170
GWQ-96-22A	10/1/1997									
GWQ-96-22A	1/24/1998	5.5	0.163				7.6			146.3
GWQ-96-22A	2/1/1998									
GWQ-96-22A	3/1/1998									
GWQ-96-22A	4/14/1998	4.8	0.12	-0.0002	-0.05		3.6	-0.05		
GWQ-96-22A	5/1/1998									
GWQ-96-22A	6/1/1998									
GWQ-96-22A	7/21/1998	5.7	0.04	-0.0002	-0.05		3.7	-0.05		143.9
GWQ-96-22A	8/1/1998									
GWQ-96-22A	9/1/1998									
GWQ-96-22A	10/15/1998									
GWQ-96-22B	7/13/1996	10	0.41	-0.001	-0.05	-0.05	10	-0.005	-0.05	130
GWQ-96-22B	2/5/1997									
GWQ-96-23A	7/14/1996	18	0.05	-0.001	-0.05	-0.05	4.2	-0.005	-0.05	98
GWQ-96-23A	2/5/1997									
GWQ-96-23A	4/1/1997									
GWQ-96-23A	4/1/1997		2.56	-0.002				0.043		
GWQ-96-23A	8/1/1997									
GWQ-96-23A	8/8/1997	36	1.6		-0.05	-0.05	2.5	-0.005	-0.025	72
GWQ-96-23A	1/24/1998	22.4	0.36				5.6			83.6
GWQ-96-23A	2/1/1998									
GWQ-96-23A	3/1/1998									
GWQ-96-23A	4/14/1998	43.4	1.4	-0.0002	-0.05		2.5	-0.05		86.6
GWQ-96-23A	5/1/1998									
GWQ-96-23A	6/1/1998									
GWQ-96-23A	7/21/1998	41.8	1.67	-0.0002	-0.05		3.2	-0.05		80

Well Name	Sample Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium
GWQ-96-23A	8/1/1998									
GWQ-96-23A	9/1/1998									
GWQ-96-23A	10/15/1998									
GWQ-96-23B	7/14/1996	20	0.13	-0.001	-0.05	-0.05	4	-0.005	-0.05	79
GWQ-96-23B	2/5/1997									
GWQ-96-23B	4/1/1997		0.75							
GWQ-96-23B	4/1/1997		0.72	0.002				0.027		
Hansen	1/1/1998									
Hansen	2/1/1998									
Hansen	3/1/1998									
Hansen	4/1/1998									
Hansen	5/1/1998									
Hansen	6/1/1998									
Hansen	7/22/1998	2.1	-0.02	-0.0002	-0.05		3.9	-0.05		46
Hansen	8/1/1998									
Hansen	9/1/1998									
Highway	5/27/1994	14	-0.03	-0.001	-0.05	-0.05	3	-0.005	-0.025	28
Highway	4/14/1998	13.9	-0.02	-0.0002	-0.05		0.9	-0.05		27.2
Hill	7/13/1947	1.9								
Humphries-Deep	10/1/1997									
Humphries-Deep	1/23/1998	11	-0.02				4.8			22
Humphries-Deep	2/1/1998									
Humphries-Deep	3/1/1998									
Humphries-Deep	4/15/1998	11	-0.02	-0.0002	-0.05		1.8	-0.05		21.8

Thallium	Well Name	Sample Dat	Zinc	Temp (C)	Tin	Vanadium
	GWQ-9	6/4/1976				
	GWQ-9	1/20/1981				
	GWQ-9	2/2/1981				
	GWQ-9	2/2/1981				
	GWQ-9	3/27/1981	0.16			
	GWQ-9	3/27/1981	0.16			
	GWQ-9	4/6/1981	0.13			
	GWQ-9	6/10/1981				
	GWQ-9	8/7/1981				
	GWQ-9	8/10/1981	0.96			
	GWQ-9	10/8/1981	0.35			
	GWQ-9	2/25/1982				
	GWQ-9	12/28/1982				
	GWQ-9	2/21/1983				
	GWQ-9	5/13/1983				
	GWQ-9	8/9/1983				
	GWQ-9	11/1/1983				
	GWQ-9	3/16/1984				
	GWQ-9	5/30/1984				
	GWQ-9	9/12/1984				
	GWQ-9	11/27/1984				
	GWQ-9	5/17/1985				
	GWQ-9	6/27/1985				
	GWQ-9	11/13/1985				
	GWQ-9	5/23/1985				
	GWQ-9	10/8/1986				
	GWQ-9	8/1/1997				
-0.005	GWQ-94-13	11/15/1994	-0.05			
-0.001	GWQ-94-13	7/1/1996	-0.05			
	GWQ-94-13	8/1/1997				
-0.005	GWQ-94-14	11/14/1994	-0.05			
-0.001	GWQ-94-14	6/30/1996	-0.05			
	GWQ-94-14	8/1/1997				
-0.005	GWQ-94-15	11/14/1994	-0.05			
-0.001	GWQ-94-15	7/1/1996	-0.05			
	GWQ-94-15	8/1/1997				

Thallium	Well Name	Sample Dat	Zinc	Temp (C)	Tin	Vanadium
	GWQ-94-15	10/1/1997				
	GWQ-94-15	1/24/1998				
	GWQ-94-15	2/1/1998				
	GWQ-94-15	3/1/1998				
	GWQ-94-15	4/14/1998				
	GWQ-94-15	5/1/1998				
	GWQ-94-15	6/1/1998				
	GWQ-94-15	7/21/1998				
	GWQ-94-15	8/1/1998				
	GWQ-94-15	9/1/1998				
	GWQ-94-15	10/15/1998				
-0.005	GWQ-94-16	11/13/1994	-0.05			
-0.001	GWQ-94-16	7/1/1996	-0.05			
-0.005	GWQ-94-17	11/15/1994	-0.05			
-0.001	GWQ-94-17	6/30/1996	-0.05			
	GWQ-94-17	5/1/1997				
	GWQ-94-17	1/24/1998				
	GWQ-94-17	2/1/1998				
	GWQ-94-17	3/1/1998				
	GWQ-94-17	4/14/1998				
	GWQ-94-17	5/1/1998				
	GWQ-94-17	5/1/1998				
	GWQ-94-17	7/21/1998				
	GWQ-94-17	8/1/1998				
	GWQ-94-17	9/1/1998				
-0.005	GWQ-94-20	11/15/1994	-0.05			
-0.001	GWQ-94-20	6/30/1996	-0.05			
	GWQ-94-20	8/1/1997				
-0.005	GWQ-94-21A	11/13/1994	-0.05			
-0.001	GWQ-94-21A	6/30/1996	-0.05			
	GWQ-94-21A	1/24/1998				
	GWQ-94-21A	2/1/1998				
	GWQ-94-21A	3/1/1998				
	GWQ-94-21A	4/14/1998				
	GWQ-94-21A	5/1/1998				
	GWQ-94-21A	6/1/1998				

Thallium	Well Name	Sample Dat	Zinc	Temp (C)	Tin	Vanadium
33.2	GWQ-94-21A	7/21/1998				
	GWQ-94-21A	8/1/1998				
	GWQ-94-21A	9/1/1998				
-0.005	GWQ-94-21B	11/13/1994	-0.05			
-0.001	GWQ-94-21B	6/30/1996	-0.05			
-0.001	GWQ-96-22A	7/13/1996	-0.05			
	GWQ-96-22A	2/5/1997				
	GWQ-96-22A	4/1/1997				
	GWQ-96-22A	8/1/1997				
-0.001	GWQ-96-22A	8/8/1997	-0.05			
	GWQ-96-22A	10/1/1997				
	GWQ-96-22A	1/24/1998				
	GWQ-96-22A	2/1/1998				
	GWQ-96-22A	3/1/1998				
	GWQ-96-22A	4/14/1998				
	GWQ-96-22A	5/1/1998				
	GWQ-96-22A	6/1/1998				
	GWQ-96-22A	7/21/1998				
	GWQ-96-22A	8/1/1998				
	GWQ-96-22A	9/1/1998				
	GWQ-96-22A	10/15/1998				
-0.001	GWQ-96-22B	7/13/1996	-0.05			
	GWQ-96-22B	2/5/1997				
-0.001	GWQ-96-23A	7/14/1996	-0.05			
	GWQ-96-23A	2/5/1997				
	GWQ-96-23A	4/1/1997				
	GWQ-96-23A	4/1/1997				
	GWQ-96-23A	8/1/1997				
-0.001	GWQ-96-23A	8/8/1997	-0.05			
	GWQ-96-23A	1/24/1998				
	GWQ-96-23A	2/1/1998				
	GWQ-96-23A	3/1/1998				
	GWQ-96-23A	4/14/1998				
	GWQ-96-23A	5/1/1998				
	GWQ-96-23A	6/1/1998				
	GWQ-96-23A	7/21/1998				

Thallium	Well Name	Sample Dat	Zinc	Temp (C)	Tin	Vanadium
	GWQ-96-23A	8/1/1998				
	GWQ-96-23A	9/1/1998				
	GWQ-96-23A	10/15/1998				
-0.001	GWQ-96-23B	7/14/1996	-0.05			
	GWQ-96-23B	2/5/1997				
	GWQ-96-23B	4/1/1997				
	GWQ-96-23B	4/1/1997				
	Hansen	1/1/1998				
	Hansen	2/1/1998				
	Hansen	3/1/1998				
	Hansen	4/1/1998				
	Hansen	5/1/1998				
	Hansen	6/1/1998				
	Hansen	7/22/1998				
	Hansen	8/1/1998				
	Hansen	9/1/1998				
-0.005	Highway	5/27/1994	-0.05			
	Highway	4/14/1998				
	Hill	7/13/1947				
	Humphries-Deep	10/1/1997				
	Humphries-Deep	1/23/1998				
	Humphries-Deep	2/1/1998				
	Humphries-Deep	3/1/1998				
	Humphries-Deep	4/15/1998				

Well Name	Water Depth	USGS Quad	Well Depth		Sample ID	Date	Sampler	Notes
Humphries.Deep				-6	Humphries.Deep-6	5/1/1998		
Humphries-Deep				-7	Humphries-Deep-7	6/1/1998		
Humphries-Deep				-8	Humphries-Deep-8	7/22/1998	Brownfield	
Humphries-Deep				-9	Humphries-Deep-9	8/1/1998		
Humphries-Deep				-10	Humphries-Deep-10	9/1/1998		
Humphries-Deep				-11	Humphries-Deep-11	10/15/1998	Goff	
Humphries-Shallow				-1	Humphries-Shallow-1	1/23/1998	Goff	
Humphries-Shallow				-2	Humphries-Shallow-2	2/1/1998		
Humphries-Shallow				-3	Humphries-Shallow-3	3/1/1998		
Humphries-Shallow				-4	Humphries-Shallow-4	4/15/1998	Goff	
Humphries-Shallow				-5	Humphries-Shallow-5	5/1/1998		
Humphries-Shallow				-6	Humphries-Shallow-6	6/1/1998		
Humphries-Shallow				-7	Humphries-Shallow-7	7/22/1998	Brownfield	
Humphries-Shallow				-8	Humphries-Shallow-8	8/1/1998		
Humphries-Shallow				-9	Humphries-Shallow-9	9/1/1998		
IW-1		Skute Stone Arroyo		-1	IW-1-1	3/4/1987	EID	
IW-1		Skute Stone Arroyo		-2	IW-1-2	7/19/1997	GE	lab pH
IW-1		Skute Stone Arroyo		-3	IW-1-3	8/29/1991	Irwin	lab pH
IW-1		Skute Stone Arroyo		-4	IW-1-4	11/26/1991	Hood	lab pH
IW-1		Skute Stone Arroyo		-5	IW-1-5	3/15/1992	Irwin	lab pH
IW-1		Skute Stone Arroyo		-6	IW-1-6	5/25/1992	Irwin	lab pH
IW-1		Skute Stone Arroyo		-7	IW-1-7	7/16/1992	Irwin	lab pH
IW-1		Skute Stone Arroyo		-8	IW-1-8	10/18/1992	Irwin	lab pH
IW-1		Skute Stone Arroyo		-9	IW-1-9	11/27/1992	Hood	lab pH
IW-1		Skute Stone Arroyo		-10	IW-1-10	12/15/1992	Irwin	lab pH
IW-1		Skute Stone Arroyo		-11	IW-1-11	9/28/1993	Irwin	lab pH
IW-1		Skute Stone Arroyo		-12	IW-1-12	3/17/1994	Irwin	lab pH
IW-1		Skute Stone Arroyo		-13	IW-1-13	5/24/1994	SRK	Mislabeled NP-3A
IW-1		Skute Stone Arroyo		-14	IW-1-14	6/23/1994	Irwin	lab pH
IW-1		Skute Stone Arroyo		-15	IW-1-15	7/22/1994	SRK	
IW-1		Skute Stone Arroyo		-16	IW-1-16	9/22/1994	Irwin	lab pH
IW-1		Skute Stone Arroyo		-17	IW-1-17	1/29/1995	Irwin	lab pH
IW-1		Skute Stone Arroyo		-18	IW-1-18	3/29/1995	Irwin	lab pH
IW-1		Skute Stone Arroyo		-19	IW-1-19	6/27/1995	Irwin	lab pH
IW-1		Skute Stone Arroyo		-20	IW-1-20	9/21/1995	Irwin	lab pH
IW-1		Skute Stone Arroyo		-21	IW-1-21	1/10/1996	Irwin	lab pH

Well Name	Water Depth	USGS Quad	Well Depth	Sample ID	Date	Sampler	Notes
IW-1		Skute Stone Arroyo	-22	IW-1-22	4/1/1996		
IW-1		Skute Stone Arroyo	-23	IW-1-23	6/1/1996		
IW-1		Skute Stone Arroyo	-24	IW-1-24	9/25/1996	Irwin	lab pH
IW-1		Skute Stone Arroyo	-25	IW-1-25	1/15/1997	Irwin	lab pH
IW-1		Skute Stone Arroyo	-26	IW-1-26	7/1/1997		
IW-1		Skute Stone Arroyo	-27	IW-1-27	10/1/1997		
IW-1		Skute Stone Arroyo	-28	IW-1-28	1/15/1998	Irwin	
IW-1		Skute Stone Arroyo	-29	IW-1-29	4/9/1998	Irwin	
IW-1		Skute Stone Arroyo	-30	IW-1-30	7/13/1998	Irwin	
IW-2		Skute Stone Arroyo	-1	IW-2-1	9/2/1982	EID	
IW-2		Skute Stone Arroyo	-2	IW-2-2	5/25/1994	SRK	Mislabeled NP-3B
IW-2		Skute Stone Arroyo	-3	IW-2-3	7/22/1994	SRK	
IW-3		Skute Stone Arroyo	-1	IW-3-1	9/2/1982	EID	
IW-3		Skute Stone Arroyo	-2	IW-3-2	2/25/1993	Irwin	lab pH
IW-3		Skute Stone Arroyo	-3	IW-3-3	5/26/1994	SRK	Significant sediment
IW-3		Skute Stone Arroyo	-4	IW-3-4	7/23/1994	SRK	
IW-3		Skute Stone Arroyo	-5	IW-3-5	4/3/1996	Irwin	lab pH
Ladder-Higgins			-1	Ladder-Higgins-1	8/2/1994	SRK	
McGarvey-Greyback		Skute Stone Arroyo	-1	McGarvey-Greyback-1	3/31/1993	JWS	
McGarvey-Greyback		Skute Stone Arroyo	-2	McGarvey-Greyback-2	10/1/1997		
McGarvey-Greyback		Skute Stone Arroyo	-3	McGarvey-Greyback-3	1/24/1998	Goff	
McGarvey-Greyback		Skute Stone Arroyo	-4	McGarvey-Greyback-4	2/1/1998		
McGarvey-Greyback		Skute Stone Arroyo	-5	McGarvey-Greyback-5	3/1/1998		
McGarvey-Greyback		Skute Stone Arroyo	-6	McGarvey-Greyback-6	4/15/1998	Goff	
McGarvey-Greyback		Skute Stone Arroyo	-7	McGarvey-Greyback-7	5/1/1998		
McGarvey-Greyback		Skute Stone Arroyo	-8	McGarvey-Greyback-8	6/1/1998		
McGarvey-Greyback		Skute Stone Arroyo	-9	McGarvey-Greyback-9	7/21/1998	Brownfield	
McGarvey-Greyback		Skute Stone Arroyo	-10	McGarvey-Greyback-1	8/1/1998		
McGarvey-Greyback		Skute Stone Arroyo	-11	McGarvey-Greyback-1	9/1/1998		
McGarvey-Greyback		Skute Stone Arroyo	-12	McGarvey-Greyback-1	10/15/1998	Goff	
Miranda			-1	Miranda-1	7/31/1947		
MW-1		Skute Stone Arroyo	-1	MW-1-1	1/1/1975		
MW-10			-1	MW-10-1	11/16/1994	SRK	
MW-10	67.08		-2	MW-10-2	1/23/1998	Goff	
MW-10	66.91		-3	MW-10-3	2/1/1998		
MW-10	66.82		-4	MW-10-4	3/1/1998		

Well Name	Water Depth	USGS Quad	Well Depth	Sample ID	Date	Sampler	Notes
MW-10	66.94		-5	MW-10-5	4/15/1998	Goff	
MW-10	66.19		-6	MW-10-6	5/1/1998		
MW-10	66.54		-7	MW-10-7	6/1/1998		
MW-10	66.98		-8	MW-10-8	7/22/1998	Brownfield	
MW-10	67.02		-9	MW-10-9	8/1/1998		
MW-10	66.92		-10	MW-10-10	9/1/1998		
MW-11			-1	MW-11-1	11/16/1994	SRK	
MW-11			-2	MW-11-2	4/1/1997		
MW-11			-3	MW-11-3	4/1/1997		
MW-11			-4	MW-11-4	8/1/1997		
MW-11			-5	MW-11-5	10/1/1997		
MW-11	5.9		-6	MW-11-6	1/24/1998	Goff	
MW-11	5.61		-7	MW-11-7	2/1/1998		
MW-11	5.52		-8	MW-11-8	3/1/1998		
MW-11	5.43		-9	MW-11-9	4/15/1998	Goff	
MW-11	6.32		-10	MW-11-10	5/1/1998		
MW-11	6.76		-11	MW-11-11	6/1/1998		
MW-11	7.61		-12	MW-11-12	7/22/1998	Brownfield	
MW-11	6.21		-13	MW-11-13	8/1/1998		
MW-11	6.84		-14	MW-11-14	9/1/1998	Goff	
MW-11			-15	MW-11-15	10/15/1998		
MW-2		Skute Stone Arroyo	-1	MW-2-1	5/7/1975		
MW-2		Skute Stone Arroyo	-2	MW-2-2	7/20/1994	SRK	
MW-3			-1	MW-3-1	10/15/1998	Goff	
MW-4		Skute Stone Arroyo	-1	MW-4-1	6/13/1975		
MW-4	122.87	Skute Stone Arroyo	-2	MW-4-2	6/9/1981	SHB	
MW-4		Skute Stone Arroyo	-3	MW-4-3	7/20/1994	SRK	
MW-4		Skute Stone Arroyo	-4	MW-4-4	4/1/1997		
MW-4		Skute Stone Arroyo	-5	MW-4-5	4/1/1997		
MW-4		Skute Stone Arroyo	-6	MW-4-6	8/1/1997		
MW-4	79.92	Skute Stone Arroyo	-7	MW-4-7	1/24/1998	Goff	
MW-4	80	Skute Stone Arroyo	-8	MW-4-8	2/1/1998		
MW-4	80.1	Skute Stone Arroyo	-9	MW-4-9	3/1/1998		
MW-4	80.43	Skute Stone Arroyo	-10	MW-4-10	4/14/1998	Goff	
MW-4	80.5	Skute Stone Arroyo	-11	MW-4-11	5/1/1998		
MW-4	80.68	Skute Stone Arroyo	-12	MW-4-12	6/1/1998		

Well Name	Water Depth	USGS Quad	Well Depth	Sample ID	Date	Sampler	Notes
MW-4	80.86	Skute Stone Arroyo	-13	MW-4-13	7/21/1998	Brownfield	
MW-4	81.19	Skute Stone Arroyo	-14	MW-4-14	8/1/1998		
MW-4	81.21	Skute Stone Arroyo	-15	MW-4-15	9/1/1998		
MW-5		Skute Stone Arroyo	-1	MW-5-1	9/19/1975		
MW-5		Skute Stone Arroyo	-2	MW-5-2	7/20/1994	SRK	
MW-5	325.04	Skute Stone Arroyo	-3	MW-5-3	1/1/1998		
MW-5	324.74	Skute Stone Arroyo	-4	MW-5-4	2/1/1998		
MW-5	324.11	Skute Stone Arroyo	-5	MW-5-5	3/1/1998		
MW-5	324.27	Skute Stone Arroyo	-6	MW-5-6	4/1/1998		
MW-5	325.08	Skute Stone Arroyo	-7	MW-5-7	5/1/1998		
MW-5	325.2	Skute Stone Arroyo	-8	MW-5-8	6/1/1998		
MW-5	327.88	Skute Stone Arroyo	-9	MW-5-9	7/1/1998		
MW-5	325.42	Skute Stone Arroyo	-10	MW-5-10	8/1/1998		
MW-5	327.87	Skute Stone Arroyo	-11	MW-5-11	9/1/1998		
MW-6		Skute Stone Arroyo	-1	MW-6-1	1/1/1975		
MW-6		Skute Stone Arroyo	-2	MW-6-2	8/2/1994	SRK	
MW-6		Skute Stone Arroyo	-3	MW-6-3	4/1/1997		
MW-6		Skute Stone Arroyo	-4	MW-6-4	8/1/1997		
MW-6		Skute Stone Arroyo	-5	MW-6-5	4/14/1998	Goff	
MW-6		Skute Stone Arroyo	-6	MW-6-6	7/21/1998	Brownfield	
MW-8		Skute Stone Arroyo	-1	MW-8-1	1/1/1975		
MW-8		Skute Stone Arroyo	-2	MW-8-2	7/21/1994	SRK	
MW-8	353.87	Skute Stone Arroyo	-3	MW-8-3	1/1/1998		
MW-8	353.77	Skute Stone Arroyo	-4	MW-8-4	2/1/1998		

Well Name	Date	Latitude	Longitude	UTM Easting	UTM Northing	UTM Zone	Elevation	Filtered?	Chloride	Sulfate
Humphries.Deep	5/1/1998									
Humphries-Deep	6/1/1998									
Humphries-Deep	7/22/1998							TRUE	18.2	19
Humphries-Deep	8/1/1998									
Humphries-Deep	9/1/1998									
Humphries-Deep	10/15/1998							TRUE	19.4	19
Humphries-Shallow	1/23/1998							TRUE	18	18
Humphries-Shallow	2/1/1998									
Humphries-Shallow	3/1/1998									
Humphries-Shallow	4/15/1998							TRUE	12.4	17
Humphries-Shallow	5/1/1998									
Humphries-Shallow	6/1/1998									
Humphries-Shallow	7/22/1998							TRUE	13.8	19
Humphries-Shallow	8/1/1998									
Humphries-Shallow	9/1/1998									
IW-1	3/4/1987	32.96120	107.49678	266624	3649563	13	5186	TRUE	575	1901
IW-1	7/19/1997	32.96120	107.49678	266624	3649563	13	5186	TRUE	632.6	1985
IW-1	8/29/1991	32.96120	107.49678	266624	3649563	13	5186	FALSE	642.4	1917.9
IW-1	11/26/1991	32.96120	107.49678	266624	3649563	13	5186	FALSE	615.1	1634
IW-1	3/15/1992	32.96120	107.49678	266624	3649563	13	5186	FALSE	598.2	2203
IW-1	5/25/1992	32.96120	107.49678	266624	3649563	13	5186	FALSE	598.2	2203
IW-1	7/16/1992	32.96120	107.49678	266624	3649563	13	5186	FALSE	584.6	1775
IW-1	10/18/1992	32.96120	107.49678	266624	3649563	13	5186	FALSE	616.9	1726.8
IW-1	11/27/1992	32.96120	107.49678	266624	3649563	13	5186	FALSE	604.8	1716.6
IW-1	12/15/1992	32.96120	107.49678	266624	3649563	13	5186	FALSE	608.9	1414.6
IW-1	9/28/1993	32.96120	107.49678	266624	3649563	13	5186	FALSE	521.1	1150
IW-1	3/17/1994	32.96120	107.49678	266624	3649563	13	5186	FALSE	404.8	1569
IW-1	5/24/1994	32.96120	107.49678	266624	3649563	13	5186	FALSE	470	1500
IW-1	6/23/1994	32.96120	107.49678	266624	3649563	13	5186	FALSE	473.8	1444
IW-1	7/22/1994	32.96120	107.49678	266624	3649563	13	5186	TRUE	431	1480
IW-1	9/22/1994	32.96120	107.49678	266624	3649563	13	5186	FALSE	195.5	707.1
IW-1	1/29/1995	32.96120	107.49678	266624	3649563	13	5186	FALSE	663	1478.5
IW-1	3/29/1995	32.96120	107.49678	266624	3649563	13	5186	FALSE	419.4	1350.7
IW-1	6/27/1995	32.96120	107.49678	266624	3649563	13	5186	FALSE	446.1	1680.1
IW-1	9/21/1995	32.96120	107.49678	266624	3649563	13	5186	FALSE	458.7	1710.8
IW-1	1/10/1996	32.96120	107.49678	266624	3649563	13	5186	FALSE	442.2	1595.5

Well Name	Date	Latitude	Longitude	UTM Easting	UTM Northing	UTM Zone	Elevation	Filtered?	Chloride	Sulfate
IW-1	4/1/1996	32.96120	107.49678	266624	3649563	13	5186		432.6	1566
IW-1	6/1/1996	32.96120	107.49678	266624	3649563	13	5186		426.8	1369.6
IW-1	9/25/1996	32.96120	107.49678	266624	3649563	13	5186	TRUE	568	1493
IW-1	1/15/1997	32.96120	107.49678	266624	3649563	13	5186	TRUE	410	1694.5
IW-1	7/1/1997	32.96120	107.49678	266624	3649563	13	5186	TRUE	375	2185
IW-1	10/1/1997	32.96120	107.49678	266624	3649563	13	5186	TRUE	400	1709
IW-1	1/15/1998	32.96120	107.49678	266624	3649563	13	5186	TRUE	385	1791
IW-1	4/9/1998	32.96120	107.49678	266624	3649563	13	5186	TRUE	373	1865
IW-1	7/13/1998	32.96120	107.49678	266624	3649563	13	5186	TRUE	383	1954
IW-2	9/2/1982	32.96214	107.49682	266622	3649667	13	5195	TRUE	409.07	2252
IW-2	5/25/1994	32.96214	107.49682	266622	3649667	13	5195	FALSE	340	1000
IW-2	7/22/1994	32.96214	107.49682	266622	3649667	13	5195	TRUE	380	1040
IW-3	9/2/1982	32.96313	107.49684	266623	3649776	13	5200	TRUE	159.12	707.3
IW-3	2/25/1993	32.96313	107.49684	266623	3649776	13	5200	FALSE	589.5	1738.9
IW-3	5/26/1994	32.96313	107.49684	266623	3649776	13	5200	FALSE	209	415
IW-3	7/23/1994	32.96313	107.49684	266623	3649776	13	5200	TRUE	206	437
IW-3	4/3/1996	32.96313	107.49684	266623	3649776	13	5200	FALSE	432.6	1566.3
Ladder-Higgins	8/2/1994							TRUE	48	22
McGarvey-Greyback	3/31/1993	32.96882	107.49714	266610	3650408	13	5195	TRUE	30	207
McGarvey-Greyback	10/1/1997	32.96882	107.49714	266610	3650408	13	5195	TRUE	47.2	14.3
McGarvey-Greyback	1/24/1998	32.96882	107.49714	266610	3650408	13	5195	TRUE	51.9	3
McGarvey-Greyback	2/1/1998	32.96882	107.49714	266610	3650408	13	5195			
McGarvey-Greyback	3/1/1998	32.96882	107.49714	266610	3650408	13	5195			
McGarvey-Greyback	4/15/1998	32.96882	107.49714	266610	3650408	13	5195	TRUE	50.5	2
McGarvey-Greyback	5/1/1998	32.96882	107.49714	266610	3650408	13	5195			
McGarvey-Greyback	6/1/1998	32.96882	107.49714	266610	3650408	13	5195			
McGarvey-Greyback	7/21/1998	32.96882	107.49714	266610	3650408	13	5195	TRUE	51	3
McGarvey-Greyback	8/1/1998	32.96882	107.49714	266610	3650408	13	5195			
McGarvey-Greyback	9/1/1998	32.96882	107.49714	266610	3650408	13	5195			
McGarvey-Greyback	10/15/1998	32.96882	107.49714	266610	3650408	13	5195	TRUE	47.2	14.3
Miranda	7/31/1947							FALSE	380	64
MW-1	1/1/1975	32.93787	107.46704	269344	3646910	13	4995	FALSE	10	73
MW-10	11/16/1994	32.97845	107.38743	276891	3651238	13	4443	TRUE	14	25
MW-10	1/23/1998	32.97845	107.38743	276891	3651238	13	4443	TRUE	18	19
MW-10	2/1/1998	32.97845	107.38743	276891	3651238	13	4443			
MW-10	3/1/1998	32.97845	107.38743	276891	3651238	13	4443			

Well Name	Date	Latitude	Longitude	UTM Easting	UTM Northing	UTM Zone	Elevation	Filtered?	Chloride	Sulfate
MW-10	4/15/1998	32.97845	107.38743	276891	3651238	13	4443	TRUE	18.1	19
MW-10	5/1/1998	32.97845	107.38743	276891	3651238	13	4443			
MW-10	6/1/1998	32.97845	107.38743	276891	3651238	13	4443			
MW-10	7/22/1998	32.97845	107.38743	276891	3651238	13	4443	TRUE	14.83	12
MW-10	8/1/1998	32.97845	107.38743	276891	3651238	13	4443			
MW-10	9/1/1998	32.97845	107.38743	276891	3651238	13	4443			
MW-11	11/16/1994	32.97832	107.38747	276886	3651224	13	4443	TRUE	15	21
MW-11	4/1/1997	32.97832	107.38747	276886	3651224	13	4443	TRUE	18	16
MW-11	4/1/1997	32.97832	107.38747	276886	3651224	13	4443	TRUE	20.2	24
MW-11	8/1/1997	32.97832	107.38747	276886	3651224	13	4443	TRUE	19.9	
MW-11	10/1/1997	32.97832	107.38747	276886	3651224	13	4443	TRUE	17.8	21.6
MW-11	1/24/1998	32.97832	107.38747	276886	3651224	13	4443	TRUE	18.5	19
MW-11	2/1/1998	32.97832	107.38747	276886	3651224	13	4443			
MW-11	3/1/1998	32.97832	107.38747	276886	3651224	13	4443			
MW-11	4/15/1998	32.97832	107.38747	276886	3651224	13	4443	TRUE	17.9	19
MW-11	5/1/1998	32.97832	107.38747	276886	3651224	13	4443			
MW-11	6/1/1998	32.97832	107.38747	276886	3651224	13	4443			
MW-11	7/22/1998	32.97832	107.38747	276886	3651224	13	4443	TRUE	14.5	17
MW-11	8/1/1998	32.97832	107.38747	276886	3651224	13	4443			
MW-11	9/1/1998	32.97832	107.38747	276886	3651224	13	4443			
MW-11	10/15/1998	32.97832	107.38747	276886	3651224	13	4443	TRUE	17.8	21.6
MW-2	5/7/1975	32.92415	107.46436	269558	3645382	13	4980	FALSE	8	40
MW-2	7/20/1994	32.92415	107.46436	269558	3645382	13	4980	TRUE	5.5	18
MW-3	10/15/1998	32.92415	107.46436	269558	3645382	13	4980	TRUE	17	50.2
MW-4	6/13/1975	32.95405	107.48797	267429	3648750	13	5135	FALSE	15	110
MW-4	6/9/1981	32.95405	107.48797	267429	3648750	13	5135	TRUE		
MW-4	7/20/1994	32.95405	107.48797	267429	3648750	13	5135	TRUE	17	66
MW-4	4/1/1997	32.95405	107.48797	267429	3648750	13	5135	TRUE	20	62
MW-4	4/1/1997	32.95405	107.48797	267429	3648750	13	5135	TRUE	17	47
MW-4	8/1/1997	32.95405	107.48797	267429	3648750	13	5135	TRUE	20	
MW-4	1/24/1998	32.95405	107.48797	267429	3648750	13	5135	TRUE	20.1	48
MW-4	2/1/1998	32.95405	107.48797	267429	3648750	13	5135			
MW-4	3/1/1998	32.95405	107.48797	267429	3648750	13	5135			
MW-4	4/14/1998	32.95405	107.48797	267429	3648750	13	5135	TRUE	20.3	48
MW-4	5/1/1998	32.95405	107.48797	267429	3648750	13	5135			
MW-4	6/1/1998	32.95405	107.48797	267429	3648750	13	5135			

Well Name	Date	Latitude	Longitude	UTM Easting	UTM Northing	UTM Zone	Elevation	Filtered?	Chloride	Sulfate
MW-4	7/21/1998	32.95405	107.48797	267429	3648750	13	5135	TRUE	20.3	46
MW-4	8/1/1998	32.95405	107.48797	267429	3648750	13	5135			
MW-4	9/1/1998	32.95405	107.48797	267429	3648750	13	5135			
MW-5	9/19/1975	32.97023	107.38902	276722	3650330	13	4700	FALSE	30	26
MW-5	7/20/1994	32.97023	107.38902	276722	3650330	13	4700	TRUE	17	24
MW-5	1/1/1998	32.97023	107.38902	276722	3650330	13	4700			
MW-5	2/1/1998	32.97023	107.38902	276722	3650330	13	4700			
MW-5	3/1/1998	32.97023	107.38902	276722	3650330	13	4700			
MW-5	4/1/1998	32.97023	107.38902	276722	3650330	13	4700			
MW-5	5/1/1998	32.97023	107.38902	276722	3650330	13	4700			
MW-5	6/1/1998	32.97023	107.38902	276722	3650330	13	4700			
MW-5	7/1/1998	32.97023	107.38902	276722	3650330	13	4700			
MW-5	8/1/1998	32.97023	107.38902	276722	3650330	13	4700			
MW-5	9/1/1998	32.97023	107.38902	276722	3650330	13	4700			
MW-6	1/1/1975	32.97312	107.40611	275132	3650687	13	4756	FALSE	66	38
MW-6	8/2/1994	32.97312	107.40611	275132	3650687	13	4756	TRUE	75	45
MW-6	4/1/1997	32.97312	107.40611	275132	3650687	13	4756	TRUE	71.4	62
MW-6	8/1/1997	32.97312	107.40611	275132	3650687	13	4756	TRUE	75.7	
MW-6	4/14/1998	32.97312	107.40611	275132	3650687	13	4756	TRUE	75.6	47
MW-6	7/21/1998	32.97312	107.40611	275132	3650687	13	4756	TRUE	78	49
MW-8	1/1/1975	32.96885	107.46111	269979	3650332	13	5012	FALSE	10	21
MW-8	7/21/1994	32.96885	107.46111	269979	3650332	13	5012	TRUE	6.6	18
MW-8	1/1/1998	32.96885	107.46111	269979	3650332	13	5012			
MW-8	2/1/1998	32.96885	107.46111	269979	3650332	13	5012			

Well Name	Date	pH	TDS	Alkalinity	Bicarb	Spec. Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
Humphries.Deep	5/1/1998										
Humphries-Deep	6/1/1998										
Humphries-Deep	7/22/1998		278				0.2	0.12			
Humphries-Deep	8/1/1998										
Humphries-Deep	9/1/1998										
Humphries-Deep	10/15/1998	8.05	259			544	0	-0.05			
Humphries-Shallow	1/23/1998	7.11	269		238.5	493	0.48				
Humphries-Shallow	2/1/1998										
Humphries-Shallow	3/1/1998										
Humphries-Shallow	4/15/1998	7.54	231			395	0.55	-0.05			
Humphries-Shallow	5/1/1998										
Humphries-Shallow	6/1/1998										
Humphries-Shallow	7/22/1998		262				0.56	-0.05			
Humphries-Shallow	8/1/1998										
Humphries-Shallow	9/1/1998										
IW-1	3/4/1987	6.6	3802		193	3950					
IW-1	7/19/1997	7.87	4235	182	222.1	6460	0.69	9.06			-0.002
IW-1	8/29/1991	7.13	4120								
IW-1	11/26/1991	7.53	3979								
IW-1	3/15/1992	7.09	4155								
IW-1	5/25/1992	7.09	4155								
IW-1	7/16/1992	7.12	4297								
IW-1	10/18/1992	6.96	3996								
IW-1	11/27/1992	7.71	4004								
IW-1	12/15/1992	7.4	3969								
IW-1	9/28/1993	7.12	3661								
IW-1	3/17/1994	7	3684								
IW-1	5/24/1994	7.84	3500		248	3920	0.7	5.8	0.94	-0.005	-0.005
IW-1	6/23/1994	7.69	3555								
IW-1	7/22/1994	7.51	3450		256	4100	0.72	5.9	-0.05	-0.005	-0.005
IW-1	9/22/1994	7.65	1691								
IW-1	1/29/1995	7.18	3395								
IW-1	3/29/1995	7.49	3465								
IW-1	6/27/1995	6.99	3599								
IW-1	9/21/1995	6.82	34.87								
IW-1	1/10/1996	7.32	3437								

Well Name	Date	pH	TDS	Alkalinity	Bicarb	Spec. Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
IW-1	4/1/1996	7.04	3364								
IW-1	6/1/1996	7.17	3570								
IW-1	9/25/1996	7.17	3551								
IW-1	1/15/1997	7.44	35.97								
IW-1	7/1/1997	6.92	3604								
IW-1	10/1/1997	6.95	3576								
IW-1	1/15/1998	7.38	3529			5000	0.72	5.1			
IW-1	4/9/1998		3554			3760	0.74	5.1			
IW-1	7/13/1998		3558			3800	0.77	4.1			
IW-2	9/2/1982	7.3	4010		185	4250	1.22	1.38			
IW-2	5/25/1994	7.75	2400		534	2890	0.66	1.5	22	-0.005	-0.005
IW-2	7/22/1994	7.78	2390		300	3400	0.69	-0.1	-0.05	-0.005	-0.005
IW-3	9/2/1982	7.2	1562		179	1700	0.42	4.12			
IW-3	2/25/1993	7.27	3892								
IW-3	5/26/1994	7.83	1870		341	1790	0.47	5.7	32	-0.005	-0.005
IW-3	7/23/1994	7.76	1300		255	1860	0.48	5	-0.05	0.0055	-0.005
IW-3	4/3/1996	7.04	3364								
Ladder-Higgins	8/2/1994	8.01	286		137	450	1.9	-0.1	-0.05	-0.0082	-0.005
McGarvey-Greyback	3/31/1993	7.8	632		302	927	0.51	3	-0.1		-0.005
McGarvey-Greyback	10/1/1997	7.98	156					0.08			
McGarvey-Greyback	1/24/1998	9.22	166		101.3	385	1.23				
McGarvey-Greyback	2/1/1998										
McGarvey-Greyback	3/1/1998										
McGarvey-Greyback	4/15/1998	9.22	144			414	1.29	-0.05			
McGarvey-Greyback	5/1/1998										
McGarvey-Greyback	6/1/1998										
McGarvey-Greyback	7/21/1998		158				1.19	-0.05			
McGarvey-Greyback	8/1/1998										
McGarvey-Greyback	9/1/1998										
McGarvey-Greyback	10/15/1998	7.89	156			434		0.08			
Miranda	7/31/1947		823		117	1490	0.2	4.2			
MW-1	1/1/1975	8.1	433		215	480	0.7	6.1			
MW-10	11/16/1994	7.84	310		262	473	0.43	-1	-0.05	-0.005	-0.005
MW-10	1/23/1998	7.08	294		248.3	540	0.51				
MW-10	2/1/1998										
MW-10	3/1/1998										

Well Name	Date	pH	TDS	Alkalinity	Bicarb	Spec. Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
MW-10	4/15/1998	7.26	287			482	0.53	-0.05			
MW-10	5/1/1998										
MW-10	6/1/1998										
MW-10	7/22/1998		235				0.5	-0.05			
MW-10	8/1/1998										
MW-10	9/1/1998										
MW-11	11/16/1994	7.79	314		263	480	0.45	-1	-0.05	-0.005	-0.005
MW-11	4/1/1997		290				0.41				
MW-11	4/1/1997		275				0.6				
MW-11	8/1/1997	7.03	305				0.51				
MW-11	10/1/1997	7.94	286					-0.05			
MW-11	1/24/1998	6.94	288		245.8	520	0.56				
MW-11	2/1/1998										
MW-11	3/1/1998										
MW-11	4/15/1998	7.21	281			482	0.54	-0.05			
MW-11	5/1/1998										
MW-11	6/1/1998										
MW-11	7/22/1998		240				0.49	-0.05			
MW-11	8/1/1998										
MW-11	9/1/1998										
MW-11	10/15/1998	7.94	286			529		-0.05			
MW-2	5/7/1975	7.9	327		209	400	2.3				
MW-2	7/20/1994	9	254		149	347	3.1	-0.1	-0.05	-0.005	0.019
MW-3	10/15/1998	8.73	212			487		-0.05			
MW-4	6/13/1975	7.9			226	620	0.63				
MW-4	6/9/1981										
MW-4	7/20/1994	8.34	256		139	408	0.28	-1	-0.05	-0.005	-0.005
MW-4	4/1/1997		171				0.5				
MW-4	4/1/1997		200				0.29				
MW-4	8/1/1997	8.78	202				0.38				
MW-4	1/24/1998	8.76	208		141.5	431	0.37				
MW-4	2/1/1998										
MW-4	3/1/1998										
MW-4	4/14/1998	8.83	213			442	0.39	-0.05			
MW-4	5/1/1998										
MW-4	6/1/1998										

Well Name	Date	pH	TDS	Alkalinity	Bicarb	Spec. Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
MW-4	7/21/1998		220				0.43	-0.05			
MW-4	8/1/1998										
MW-4	9/1/1998										
MW-5	9/19/1975	7.7	260		157	390	0.61	-0.5			
MW-5	7/20/1994	7.97	440		274	507	0.18	-1	-0.05	-0.005	-0.005
MW-5	1/1/1998										
MW-5	2/1/1998										
MW-5	3/1/1998										
MW-5	4/1/1998										
MW-5	5/1/1998										
MW-5	6/1/1998										
MW-5	7/1/1998										
MW-5	8/1/1998										
MW-5	9/1/1998										
MW-6	1/1/1975	7.6	260		146	520	3.4	4.3			
MW-6	8/2/1994	8.09	436		154	626	1.6	-1	-0.05	0.01	0.013
MW-6	4/1/1997		417				6.9				
MW-6	8/1/1997	8.27	416				8				
MW-6	4/14/1998	8.4	431			667	9.2	0.97			
MW-6	7/21/1998		423				8.4	0.97			
MW-8	1/1/1975	7.7	293		222	440	0.86	15.4			
MW-8	7/21/1994	8.88	290		196	438	1	-1	-0.05	-0.005	0.012
MW-8	1/1/1998										
MW-8	2/1/1998										

Well Name	Date	Boron	Barium	Berrylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
Humphries.Deep	5/1/1998										
Humphries-Deep	6/1/1998										
Humphries-Deep	7/22/1998					64.1			-0.005	-0.05	
Humphries-Deep	8/1/1998										
Humphries-Deep	9/1/1998										
Humphries-Deep	10/15/1998								-0.005	0.17	
Humphries-Shallow	1/23/1998					59.9			-0.005		
Humphries-Shallow	2/1/1998										
Humphries-Shallow	3/1/1998										
Humphries-Shallow	4/15/1998					52.1			-0.005	-0.05	
Humphries-Shallow	5/1/1998										
Humphries-Shallow	6/1/1998										
Humphries-Shallow	7/22/1998					58.3			-0.005	-0.05	
Humphries-Shallow	8/1/1998										
Humphries-Shallow	9/1/1998										
IW-1	3/4/1987					564					
IW-1	7/19/1997		-0.01		-0.005	635.5	-0.02		-0.02	-0.05	-0.005
IW-1	8/29/1991										
IW-1	11/26/1991										
IW-1	3/15/1992										
IW-1	5/25/1992										
IW-1	7/16/1992										
IW-1	10/18/1992										
IW-1	11/27/1992										
IW-1	12/15/1992										
IW-1	9/28/1993										
IW-1	3/17/1994										
IW-1	5/24/1994		-0.1		-0.0005	550	-0.025		-0.025	1	-0.005
IW-1	6/23/1994										
IW-1	7/22/1994	0.1	-0.1	-0.002	-0.0005	570	-0.025	-0.05	-0.025	-0.05	-0.005
IW-1	9/22/1994										
IW-1	1/29/1995										
IW-1	3/29/1995										
IW-1	6/27/1995										
IW-1	9/21/1995										
IW-1	1/10/1996										

Well Name	Date	Boron	Barium	Berrylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
IW-1	4/1/1996										
IW-1	6/1/1996										
IW-1	9/25/1996										
IW-1	1/15/1997										
IW-1	7/1/1997										
IW-1	10/1/1997										
IW-1	1/15/1998								-0.005	-0.05	
IW-1	4/9/1998								-0.005	-0.2	
IW-1	7/13/1998								-0.005	-0.05	
IW-2	9/2/1982				-0.001	320					
IW-2	5/25/1994		0.12		-0.0005	430	0.046		-0.025	16	0.0073
IW-2	7/22/1994	0.15	-0.1	-0.002	-0.0005	390	-0.025	-0.05	-0.025	-0.05	-0.005
IW-3	9/2/1982			0	-0.001	233.6					
IW-3	2/25/1993										
IW-3	5/26/1994		0.2		-0.0005	240	0.059		6	22	0.077
IW-3	7/23/1994	-0.1	-0.1	-0.002	-0.0005	200	-0.025	-0.05	0.058	-0.05	-0.005
IW-3	4/3/1996	0	0	0							
Ladder-Higgins	8/2/1994	0.11	-0.1	-0.002	-0.0005	51	-0.025	-0.05	-0.025	-0.05	-0.005
McGarvey-Greyback	3/31/1993	-0.04	-0.5	0	-0.0002	97	-0.02	-0.05	-0.01	0.05	-0.02
McGarvey-Greyback	10/1/1997	-0.005	0.43						-0.005	0.43	
McGarvey-Greyback	1/24/1998					4.5			-0.005		
McGarvey-Greyback	2/1/1998										
McGarvey-Greyback	3/1/1998										
McGarvey-Greyback	4/15/1998					2.8			-0.005	0.24	
McGarvey-Greyback	5/1/1998										
McGarvey-Greyback	6/1/1998										
McGarvey-Greyback	7/21/1998					5			-0.005	0.35	
McGarvey-Greyback	8/1/1998										
McGarvey-Greyback	9/1/1998										
McGarvey-Greyback	10/15/1998								-0.005	0.43	
Miranda	7/31/1947					126					
MW-1	1/1/1975					28					
MW-10	11/16/1994	-0.1	-0.1	-0.002	-0.0005	59	-0.025	-0.05	-0.025	-0.05	-0.005
MW-10	1/23/1998					54.3			-0.005		
MW-10	2/1/1998										
MW-10	3/1/1998										

Well Name	Date	Boron	Barium	Berrylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
MW-10	4/15/1998					67.4			-0.005	-0.05	
MW-10	5/1/1998										
MW-10	6/1/1998										
MW-10	7/22/1998					57.7			-0.005	-0.05	
MW-10	8/1/1998										
MW-10	9/1/1998										
MW-11	11/16/1994	-0.1	-0.1	-0.002	-0.0005	63	-0.025	-0.05	-0.025	-0.05	-0.005
MW-11	4/1/1997								-0.025	-0.05	
MW-11	4/1/1997								-0.005	-0.05	
MW-11	8/1/1997										
MW-11	10/1/1997								0.09	-0.05	
MW-11	1/24/1998					64.1			-0.005		
MW-11	2/1/1998										
MW-11	3/1/1998										
MW-11	4/15/1998					65.8			-0.005	-0.05	
MW-11	5/1/1998										
MW-11	6/1/1998										
MW-11	7/22/1998					56			-0.005	-0.05	
MW-11	8/1/1998										
MW-11	9/1/1998										
MW-11	10/15/1998								0.09	-0.05	
MW-2	5/7/1975					9					
MW-2	7/20/1994	0.16	-0.1	-0.002	-0.0005	2.5	-0.025	-0.05	-0.025	0.069	-0.005
MW-3	10/15/1998								-0.005	1.68	
MW-4	6/13/1975					46					
MW-4	6/9/1981										
MW-4	7/20/1994	-0.1	-0.1	-0.002	-0.0005	15	-0.025	-0.05	-0.025	-0.05	-0.005
MW-4	4/1/1997								-0.005	9.9	
MW-4	4/1/1997								-0.025	-0.05	
MW-4	8/1/1997										
MW-4	1/24/1998					11.7			-0.005		
MW-4	2/1/1998										
MW-4	3/1/1998										
MW-4	4/14/1998					11.5			-0.005	0.88	
MW-4	5/1/1998										
MW-4	6/1/1998										

Well Name	Date	Boron	Barium	Berrylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
MW-4	7/21/1998					11.6			-0.005	3.43	
MW-4	8/1/1998										
MW-4	9/1/1998										
MW-5	9/19/1975					26					
MW-5	7/20/1994	-0.1	-0.1	-0.002	-0.0005	71	-0.025	-0.05	-0.025	-0.05	-0.005
MW-5	1/1/1998										
MW-5	2/1/1998										
MW-5	3/1/1998										
MW-5	4/1/1998										
MW-5	5/1/1998										
MW-5	6/1/1998										
MW-5	7/1/1998										
MW-5	8/1/1998										
MW-5	9/1/1998										
MW-6	1/1/1975					19					
MW-6	8/2/1994	0.16	-0.1	-0.002	-0.0005	14	-0.025	-0.025	-0.025	0.41	-0.005
MW-6	4/1/1997								-0.005	0.45	
MW-6	8/1/1997										
MW-6	4/14/1998					13.5			-0.005	0.24	
MW-6	7/21/1998					14.3			-0.005	0.36	
MW-8	1/1/1975					34					
MW-8	7/21/1994	-0.1	-0.1	-0.002	-0.0005	4.8	-0.025	-0.05	-0.025	0.14	-0.005
MW-8	1/1/1998										
MW-8	2/1/1998										

Well Name	Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium	Thallium
Humphries.Deep	5/1/1998										
Humphries-Deep	6/1/1998										
Humphries-Deep	7/22/1998	10.2	-0.02	-0.0002	-0.05		1.5	-0.05		19.3	
Humphries-Deep	8/1/1998										
Humphries-Deep	9/1/1998										
Humphries-Deep	10/15/1998										
Humphries-Shallow	1/23/1998	8.5	-0.02				3.7			22.4	
Humphries-Shallow	2/1/1998										
Humphries-Shallow	3/1/1998										
Humphries-Shallow	4/15/1998	6.7	-0.02	-0.0002	-0.05		1.1	-0.05		19.5	
Humphries-Shallow	5/1/1998										
Humphries-Shallow	6/1/1998										
Humphries-Shallow	7/22/1998	7.1	-0.02	0.0005	-0.05		1	-0.05		19.6	
Humphries-Shallow	8/1/1998										
Humphries-Shallow	9/1/1998										
IW-1	3/4/1987						3.12			273.7	
IW-1	7/19/1997	181.6	-0.02	0.0005			7	0.015	-0.02	375	
IW-1	8/29/1991										
IW-1	11/26/1991										
IW-1	3/15/1992										
IW-1	5/25/1992										
IW-1	7/16/1992										
IW-1	10/18/1992										
IW-1	11/27/1992										
IW-1	12/15/1992										
IW-1	9/28/1993										
IW-1	3/17/1994										
IW-1	5/24/1994	170	-0.03	-0.001		-0.05	2.9	-0.005	-0.025	250	
IW-1	6/23/1994										
IW-1	7/22/1994	200	-0.03	-0.001	-0.05	-0.05	2.5	0.018	-0.025	280	0.0063
IW-1	9/22/1994										
IW-1	1/29/1995										
IW-1	3/29/1995										
IW-1	6/27/1995										
IW-1	9/21/1995										
IW-1	1/10/1996										

Well Name	Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium	Thallium
IW-1	4/1/1996										
IW-1	6/1/1996										
IW-1	9/25/1996										
IW-1	1/15/1997										
IW-1	7/1/1997										
IW-1	10/1/1997										
IW-1	1/15/1998	160.9		0.0004	-0.05						
IW-1	4/9/1998		-0.02	0.0003	-0.05			-0.05			
IW-1	7/13/1998		0.2	0.0008	-0.05			-0.05			
IW-2	9/2/1982	173.7	-0.05		-0.01		234	-0.005		720	
IW-2	5/25/1994	94	0.77	-0.001		0.097	3.2	-0.005	-0.025	290	
IW-2	7/22/1994	110	0.036	-0.001	-0.05	-0.05	1.3	0.014	-0.025	360	0.0073
IW-3	9/2/1982	42.1	-0.05		-0.01		3.51	-0.005		168	
IW-3	2/25/1993										
IW-3	5/26/1994	51	0.35	-0.001		0.19	4	-0.005	-0.025	69	
IW-3	7/23/1994	66	0.13	-0.001	0.062	-0.05	3.5	0.011	-0.025	89	-0.005
IW-3	4/3/1996										
Ladder-Higgins	8/2/1994	9	-0.03	-0.001	-0.05	-0.05	3	-0.005	-0.025	24	-0.005
McGarvey-Greyback	3/31/1993	24	-0.02	-0.001	-0.02	-0.01	2	-0.005	-0.01	78	
McGarvey-Greyback	10/1/1997										
McGarvey-Greyback	1/24/1998	1.6	-0.02				6			64.9	
McGarvey-Greyback	2/1/1998										
McGarvey-Greyback	3/1/1998										
McGarvey-Greyback	4/15/1998	0.7	-0.02	-0.0002	-0.05		2.3	-0.05		64.3	
McGarvey-Greyback	5/1/1998										
McGarvey-Greyback	6/1/1998										
McGarvey-Greyback	7/21/1998	1.1	-0.02	-0.0002	-0.05		4.4	-0.05		58	
McGarvey-Greyback	8/1/1998										
McGarvey-Greyback	9/1/1998										
McGarvey-Greyback	10/15/1998										
Miranda	7/31/1947	17									
MW-1	1/1/1975	1					10.6			85	
MW-10	11/16/1994	9.4	-0.03	-0.001	-0.05	-0.05	1.9	-0.005	-0.025	29	-0.005
MW-10	1/23/1998	11.1	-0.02				8.6			23.9	
MW-10	2/1/1998										
MW-10	3/1/1998										

Well Name	Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium	Thallium
MW-10	4/15/1998	8.3	-0.02	0.0002	-0.05		1.1	-0.05		22	
MW-10	5/1/1998										
MW-10	6/1/1998										
MW-10	7/22/1998	6.7	-0.02	-0.0002	-0.05		0.9	-0.05		18.3	
MW-10	8/1/1998										
MW-10	9/1/1998										
MW-11	11/16/1994	9.7	-0.03	-0.001	-0.05	-0.05	1.5	-0.005	-0.025	23	-0.005
MW-11	4/1/1997		-0.025								
MW-11	4/1/1997		-0.02	-0.002				-0.001			
MW-11	8/1/1997										
MW-11	10/1/1997										
MW-11	1/24/1998	9.2	-0.02				3.3			23.2	
MW-11	2/1/1998										
MW-11	3/1/1998										
MW-11	4/15/1998	8.1	-0.02	-0.0002	-0.05		0.9	-0.05		2.1	
MW-11	5/1/1998										
MW-11	6/1/1998										
MW-11	7/22/1998	6.6	-0.02	0.0006	-0.05		0.5	-0.05		18.1	
MW-11	8/1/1998										
MW-11	9/1/1998										
MW-11	10/15/1998										
MW-2	5/7/1975	0					5.3			89	
MW-2	7/20/1994	0.16	-0.03	-0.001	-0.05	-0.05	-1	-0.005	-0.025	79	-0.005
MW-3	10/15/1998										
MW-4	6/13/1975	10					4.4			73	
MW-4	6/9/1981										
MW-4	7/20/1994	13	-0.03	-0.001	-0.05	-0.05	3.4	-0.005	-0.025	56	-0.005
MW-4	4/1/1997		-0.02	-0.002				0.019			
MW-4	4/1/1997		-0.025								
MW-4	8/1/1997										
MW-4	1/24/1998	10.9	0.06				5.9			56.2	
MW-4	2/1/1998										
MW-4	3/1/1998										
MW-4	4/14/1998	10.5	-0.02	0.0003	-0.05		2.2	-0.05		54.8	
MW-4	5/1/1998										
MW-4	6/1/1998										

Well Name	Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium	Thallium
MW-4	7/21/1998	9.5	-0.02	-0.0002	-0.05		2.7	-0.05		51.3	
MW-4	8/1/1998										
MW-4	9/1/1998										
MW-5	9/19/1975	3					4.1			54	
MW-5	7/20/1994	11	-0.03	-0.001	-0.05	-0.05	3.6	-0.005	-0.025	33	-0.005
MW-5	1/1/1998										
MW-5	2/1/1998										
MW-5	3/1/1998										
MW-5	4/1/1998										
MW-5	5/1/1998										
MW-5	6/1/1998										
MW-5	7/1/1998										
MW-5	8/1/1998										
MW-5	9/1/1998										
MW-6	1/1/1975	1					7.3			90	
MW-6	8/2/1994	0.95	-0.03	-0.001	-0.05	-0.05	6.2	-0.005	-0.025	120	-0.005
MW-6	4/1/1997		-0.02								
MW-6	8/1/1997										
MW-6	4/14/1998	0.6	-0.02	0.0003	-0.05		5.4	-0.05		116.6	
MW-6	7/21/1998	0.5	-0.02	0.0008	-0.05		5.8	-0.05		105.9	
MW-8	1/1/1975	10					6.2			45	
MW-8	7/21/1994	1	-0.03	-0.001	-0.05	-0.05	3.4	-0.005	-0.025	89	-0.005
MW-8	1/1/1998										
MW-8	2/1/1998										

Well Name	Date	Zinc	Temp (C)	Tin	Vanadium
Humphries.Deep	5/1/1998				
Humphries-Deep	6/1/1998				
Humphries-Deep	7/22/1998				
Humphries-Deep	8/1/1998				
Humphries-Deep	9/1/1998				
Humphries-Deep	10/15/1998				
Humphries-Shallow	1/23/1998				
Humphries-Shallow	2/1/1998				
Humphries-Shallow	3/1/1998				
Humphries-Shallow	4/15/1998				
Humphries-Shallow	5/1/1998				
Humphries-Shallow	6/1/1998				
Humphries-Shallow	7/22/1998				
Humphries-Shallow	8/1/1998				
Humphries-Shallow	9/1/1998				
IW-1	3/4/1987		22.5		
IW-1	7/19/1997				
IW-1	8/29/1991				
IW-1	11/26/1991				
IW-1	3/15/1992				
IW-1	5/25/1992				
IW-1	7/16/1992				
IW-1	10/18/1992				
IW-1	11/27/1992				
IW-1	12/15/1992				
IW-1	9/28/1993				
IW-1	3/17/1994				
IW-1	5/24/1994	0.053			
IW-1	6/23/1994				
IW-1	7/22/1994	-0.05			
IW-1	9/22/1994				
IW-1	1/29/1995				
IW-1	3/29/1995				
IW-1	6/27/1995				
IW-1	9/21/1995				
IW-1	1/10/1996				

Well Name	Date	Zinc	Temp (C)	Tin	Vanadium
IW-1	4/1/1996				
IW-1	6/1/1996				
IW-1	9/25/1996				
IW-1	1/15/1997				
IW-1	7/1/1997				
IW-1	10/1/1997				
IW-1	1/15/1998				
IW-1	4/9/1998				
IW-1	7/13/1998				
IW-2	9/2/1982				
IW-2	5/25/1994	0.084			
IW-2	7/22/1994	-0.05			
IW-3	9/2/1982				
IW-3	2/25/1993				
IW-3	5/26/1994	0.15			
IW-3	7/23/1994	-0.05			
IW-3	4/3/1996				
Ladder-Higgins	8/2/1994	-0.05			
McGarvey-Greyback	3/31/1993	0.01			
McGarvey-Greyback	10/1/1997				
McGarvey-Greyback	1/24/1998				
McGarvey-Greyback	2/1/1998				
McGarvey-Greyback	3/1/1998				
McGarvey-Greyback	4/15/1998				
McGarvey-Greyback	5/1/1998				
McGarvey-Greyback	6/1/1998				
McGarvey-Greyback	7/21/1998				
McGarvey-Greyback	8/1/1998				
McGarvey-Greyback	9/1/1998				
McGarvey-Greyback	10/15/1998				
Miranda	7/31/1947				
MW-1	1/1/1975				
MW-10	11/16/1994	-0.05			
MW-10	1/23/1998				
MW-10	2/1/1998				
MW-10	3/1/1998				

Well Name	Date	Zinc	Temp (C)	Tin	Vanadium
MW-10	4/15/1998				
MW-10	5/1/1998				
MW-10	6/1/1998				
MW-10	7/22/1998				
MW-10	8/1/1998				
MW-10	9/1/1998				
MW-11	11/16/1994	-0.05			
MW-11	4/1/1997				
MW-11	4/1/1997				
MW-11	8/1/1997				
MW-11	10/1/1997				
MW-11	1/24/1998				
MW-11	2/1/1998				
MW-11	3/1/1998				
MW-11	4/15/1998				
MW-11	5/1/1998				
MW-11	6/1/1998				
MW-11	7/22/1998				
MW-11	8/1/1998				
MW-11	9/1/1998				
MW-11	10/15/1998				
MW-2	5/7/1975				
MW-2	7/20/1994	-0.05			
MW-3	10/15/1998				
MW-4	6/13/1975				
MW-4	6/9/1981				
MW-4	7/20/1994	-0.05			
MW-4	4/1/1997				
MW-4	4/1/1997				
MW-4	8/1/1997				
MW-4	1/24/1998				
MW-4	2/1/1998				
MW-4	3/1/1998				
MW-4	4/14/1998				
MW-4	5/1/1998				
MW-4	6/1/1998				

Well Name	Date	Zinc	Temp (C)	Tin	Vanadium
MW-4	7/21/1998				
MW-4	8/1/1998				
MW-4	9/1/1998				
MW-5	9/19/1975				
MW-5	7/20/1994	-0.05			
MW-5	1/1/1998				
MW-5	2/1/1998				
MW-5	3/1/1998				
MW-5	4/1/1998				
MW-5	5/1/1998				
MW-5	6/1/1998				
MW-5	7/1/1998				
MW-5	8/1/1998				
MW-5	9/1/1998				
MW-6	1/1/1975				
MW-6	8/2/1994	-0.05			
MW-6	4/1/1997				
MW-6	8/1/1997				
MW-6	4/14/1998				
MW-6	7/21/1998				
MW-8	1/1/1975				
MW-8	7/21/1994	-0.05			
MW-8	1/1/1998				
MW-8	2/1/1998				

Well Name	Water Depth	USGS Quad	Well Depth			Sample Date	Sampler	Notes
MW-8	353.7	Skute Stone Arroyo		-5	MW-8-5	3/1/1998		
MW-8	353.7	Skute Stone Arroyo		-6	MW-8-6	4/1/1998		
MW-8	352.19	Skute Stone Arroyo		-7	MW-8-7	5/1/1998		
MW-8	353.43	Skute Stone Arroyo		-8	MW-8-8	6/1/1998		
MW-8	355.06	Skute Stone Arroyo		-9	MW-8-9	7/1/1998		
MW-8	354.55	Skute Stone Arroyo		-10	MW-8-10	8/1/1998		
MW-8	356.11	Skute Stone Arroyo		-11	MW-8-11	9/1/1998		
MW-9				-1	MW-9-1	11/16/1994	SRK	Animas Ck.
MW-9				-2	MW-9-2	8/1/1997		
MW-9	67.74			-3	MW-9-3	1/23/1998	Goff	
MW-9	67.72			-4	MW-9-4	2/1/1998		
MW-9	67.71			-5	MW-9-5	3/1/1998		
MW-9	67.75			-6	MW-9-6	4/15/1998	Goff	
MW-9	67.94			-7	MW-9-7	5/1/1998		
MW-9	68.7			-8	MW-9-8	6/1/1998		
MW-9	68375			-9	MW-9-9	7/22/1998	Brownfield	
MW-9	68.72			-10	MW-9-10	8/1/1998		
MW-9	68.65			-11	MW-9-11	9/1/1998		
MW-9				-12	MW-9-12	10/15/1998	Goff	
NP-1	83.7	Skute Stone Arroyo		-1	NP-1-1	10/8/1981	QMC	
NP-1	85.6	Skute Stone Arroyo		-2	NP-1-2	11/4/1981	QMC	
NP-1	85.67	Skute Stone Arroyo		-3	NP-1-3	11/13/1981	EID	
NP-1	84.5	Skute Stone Arroyo		-4	NP-1-4	11/17/1981	QMC	
NP-1	84.1	Skute Stone Arroyo		-5	NP-1-5	11/23/1981	QMC	
NP-1	88.2	Skute Stone Arroyo		-6	NP-1-6	12/7/1981	QMC	
NP-1	84	Skute Stone Arroyo		-7	NP-1-7	12/15/1981	QMC	
NP-1	84	Skute Stone Arroyo		-8	NP-1-8	12/22/1981	QMC	
NP-1	85.5	Skute Stone Arroyo		-9	NP-1-9	1/5/1982	QMC	
NP-1	84.42	Skute Stone Arroyo		-10	NP-1-10	1/18/1982	QMC	
NP-1	84.4	Skute Stone Arroyo		-11	NP-1-11	1/26/1982	QMC	
NP-1	85.17	Skute Stone Arroyo		-12	NP-1-12	2/16/1982	QMC	
NP-1	85.2	Skute Stone Arroyo		-13	NP-1-13	2/22/1982	QMC	
NP-1	84.83	Skute Stone Arroyo		-14	NP-1-14	3/12/1982	QMC	
NP-1	84.5	Skute Stone Arroyo		-15	NP-1-15	4/16/1982	QMC	
NP-1	84.5	Skute Stone Arroyo		-16	NP-1-16	4/26/1982	QMC	
NP-1	84.08	Skute Stone Arroyo		-17	NP-1-17	5/17/1982	QMC	

Well Name	Water Depth	USGS Quad	Well Depth			Sample Date	Sampler	Notes
NP-1		Skute Stone Arroyo		-18	NP-1-18	5/24/1982	QMC	
NP-1		Skute Stone Arroyo		-19	NP-1-19	5/28/1982	QMC	
NP-1	83.3	Skute Stone Arroyo		-20	NP-1-20	6/8/1982	QMC	
NP-1	83.33	Skute Stone Arroyo		-21	NP-1-21	6/14/1982	QMC	
NP-1	82.1	Skute Stone Arroyo		-22	NP-1-22	6/30/1982	QMC	
NP-1	82.08	Skute Stone Arroyo		-23	NP-1-23	7/26/1982	QMC	
NP-1	81.5	Skute Stone Arroyo		-24	NP-1-24	8/18/1982	QMC	
NP-1	80.6	Skute Stone Arroyo		-25	NP-1-25	9/14/1982	QMC	
NP-1	79.1	Skute Stone Arroyo		-26	NP-1-26	10/18/1982	QMC	
NP-1	79.1	Skute Stone Arroyo		-27	NP-1-27	10/27/1982	QMC	
NP-1	78	Skute Stone Arroyo		-28	NP-1-28	11/11/1982	QMC	
NP-1	76.1	Skute Stone Arroyo		-29	NP-1-29	12/28/1982	QMC	
NP-1	74.4	Skute Stone Arroyo		-30	NP-1-30	2/21/1983	QMC	
NP-1	72.1	Skute Stone Arroyo		-31	NP-1-31	5/6/1983	QMC	
NP-1	72.1	Skute Stone Arroyo		-32	NP-1-32	5/13/1983	QMC	
NP-1	71.5	Skute Stone Arroyo		-33	NP-1-33	6/2/1983	QMC	
NP-1	71.2	Skute Stone Arroyo		-34	NP-1-34	7/5/1983	QMC	
NP-1	70.7	Skute Stone Arroyo		-35	NP-1-35	8/9/1983	QMC	
NP-1	70.7	Skute Stone Arroyo		-36	NP-1-36	8/25/1983	QMC	
NP-1	69.6	Skute Stone Arroyo		-37	NP-1-37	10/20/1983	QMC	
NP-1	69.6	Skute Stone Arroyo		-38	NP-1-38	11/1/1983	QMC	
NP-1	68.3	Skute Stone Arroyo		-39	NP-1-39	12/7/1983	QMC	
NP-1	67.3	Skute Stone Arroyo		-40	NP-1-40	1/28/1984	QMC	
NP-1	67.1	Skute Stone Arroyo		-41	NP-1-41	2/13/1984	QMC	
NP-1	66.6	Skute Stone Arroyo		-42	NP-1-42	3/1/1984	QMC	
NP-1	66.6	Skute Stone Arroyo		-43	NP-1-43	3/16/1984	CFP	
NP-1		Skute Stone Arroyo		-44	NP-1-44	4/9/1984	CFP	
NP-1	66.1	Skute Stone Arroyo		-45	NP-1-45	4/18/1984	CFP	
NP-1	65.7	Skute Stone Arroyo		-46	NP-1-46	5/22/1984	CFP	
NP-1	65.7	Skute Stone Arroyo		-47	NP-1-47	5/30/1984	CFP	
NP-1	65.6	Skute Stone Arroyo		-48	NP-1-48	6/26/1984	CFP	
NP-1	65.4	Skute Stone Arroyo		-49	NP-1-49	7/25/1984	CFP	
NP-1	65.2	Skute Stone Arroyo		-50	NP-1-50	8/27/1984	CFP	
NP-1	64.4	Skute Stone Arroyo		-51	NP-1-51	9/12/1984	CFP	
NP-1	64.4	Skute Stone Arroyo		-52	NP-1-52	9/21/1984	CFP	
NP-1	64.1	Skute Stone Arroyo		-53	NP-1-53	11/19/1984	CFP	

Well Name	Water Depth	USGS Quad	Well Depth			Sample Date	Sampler	Notes
NP-1	64.1	Skute Stone Arroyo		-54	NP-1-54	11/27/1984	CFP	
NP-1	63.6	Skute Stone Arroyo		-55	NP-1-55	12/17/1984	CFP	
NP-1	62.3	Skute Stone Arroyo		-56	NP-1-56	5/17/1985	CFP	
NP-1	54.9	Skute Stone Arroyo		-57	NP-1-57	11/13/1985	CFP	
NP-1	52.9	Skute Stone Arroyo		-58	NP-1-58	5/23/1986	CFP	
NP-1	52.9	Skute Stone Arroyo		-59	NP-1-59	10/8/1986	CFP	
NP-1		Skute Stone Arroyo		-60	NP-1-60	3/30/1989	EID	
NP-1	29	Skute Stone Arroyo		-61	NP-1-61	7/19/1991	GE	lab pH
NP-1	29.17	Skute Stone Arroyo		-62	NP-1-62	8/29/1991	Irwin	lab pH
NP-1	28	Skute Stone Arroyo		-63	NP-1-63	11/26/1991	Hood	lab pH
NP-1	16.17	Skute Stone Arroyo		-64	NP-1-64	3/15/1992	Irwin	lab pH
NP-1		Skute Stone Arroyo		-65	NP-1-65	5/25/1992	Irwin	lab pH
NP-1		Skute Stone Arroyo		-66	NP-1-66	7/16/1992	Irwin	lab pH
NP-1	26.17	Skute Stone Arroyo		-67	NP-1-67	10/8/1992	Irwin	lab pH
NP-1	25.25	Skute Stone Arroyo		-68	NP-1-68	11/27/1992	Hood	lab pH
NP-1		Skute Stone Arroyo		-69	NP-1-69	12/15/1992	Irwin	lab pH
NP-1	26.17	Skute Stone Arroyo		-70	NP-1-70	2/25/1993	Irwin	lab pH
NP-1		Skute Stone Arroyo		-71	NP-1-71	3/30/1993	JWS	
NP-1		Skute Stone Arroyo		-72	NP-1-72	9/28/1993	Irwin	lab pH
NP-1	27	Skute Stone Arroyo		-73	NP-1-73	3/17/1994	Irwin	lab pH
NP-1	26.45	Skute Stone Arroyo		-74	NP-1-74	5/24/1994	SRK	
NP-1		Skute Stone Arroyo		-75	NP-1-75	6/23/1994	Irwin	lab pH
NP-1		Skute Stone Arroyo		-76	NP-1-76	7/21/1994	SRK	
NP-1		Skute Stone Arroyo		-77	NP-1-77	9/22/1994	Irwin	lab pH
NP-1		Skute Stone Arroyo		-78	NP-1-78	1/29/1995	Irwin	lab pH
NP-1		Skute Stone Arroyo		-79	NP-1-79	3/29/1995	Irwin	lab pH
NP-1	28.33	Skute Stone Arroyo		-80	NP-1-80	6/27/1995	Irwin	lab pH
NP-1		Skute Stone Arroyo		-81	NP-1-81	9/21/1995	Irwin	lab pH
NP-1		Skute Stone Arroyo		-82	NP-1-82	1/10/1996	Irwin	lab pH
NP-1		Skute Stone Arroyo		-83	NP-1-83	4/3/1996	Irwin	lab pH
NP-1		Skute Stone Arroyo		-84	NP-1-84	6/1/1996		
NP-1		Skute Stone Arroyo		-85	NP-1-85	9/25/1996	Irwin	lab pH
NP-1		Skute Stone Arroyo		-86	NP-1-86	1/15/1997	Irwin	lab pH
NP-1		Skute Stone Arroyo		-87	NP-1-87	4/1/1997		
NP-1		Skute Stone Arroyo		-88	NP-1-88	7/1/1997		
NP-1		Skute Stone Arroyo		-89	NP-1-89	10/1/1997		

Well Name	Water Depth	USGS Quad	Well Depth			Sample Date	Sampler	Notes
NP-1	30.42	Skute Stone Arroyo		-90	NP-1-90	1/15/1998	Irwin	
NP-1	30.33	Skute Stone Arroyo		-91	NP-1-91	4/9/1998	Irwin	
NP-1	30.92	Skute Stone Arroyo		-92	NP-1-92	7/13/1998	Irwin	
NP-2	87.29	Skute Stone Arroyo		-1	NP-2-1	10/8/1981	QMC	
NP-2	87	Skute Stone Arroyo		-2	NP-2-2	11/6/1981	QMC	
NP-2	87.5	Skute Stone Arroyo		-3	NP-2-3	11/13/1981	EID	
NP-2	90.1	Skute Stone Arroyo		-4	NP-2-4	11/23/1981	QMC	
NP-2	87.83	Skute Stone Arroyo		-5	NP-2-5	12/7/1981	QMC	
NP-2	87.39	Skute Stone Arroyo		-6	NP-2-6	12/15/1981	QMC	
NP-2	87.12	Skute Stone Arroyo		-7	NP-2-7	12/22/1981	QMC	
NP-2	87.125	Skute Stone Arroyo		-8	NP-2-8	1/5/1982	QMC	
NP-2	86.67	Skute Stone Arroyo		-9	NP-2-9	1/18/1982	QMC	
NP-2	86.66	Skute Stone Arroyo		-10	NP-2-10	1/25/1982	QMC	
NP-2	86.5	Skute Stone Arroyo		-11	NP-2-11	2/16/1982	QMC	
NP-2	86.45	Skute Stone Arroyo		-12	NP-2-12	2/22/1982	QMC	
NP-2	86	Skute Stone Arroyo		-13	NP-2-13	3/12/1982	QMC	
NP-2	85.75	Skute Stone Arroyo		-14	NP-2-14	4/16/1982	QMC	
NP-2	85.45	Skute Stone Arroyo		-15	NP-2-15	4/26/1982	QMC	
NP-2	84	Skute Stone Arroyo		-16	NP-2-16	5/15/1982	QMC	
NP-2		Skute Stone Arroyo		-17	NP-2-17	5/24/1982	QMC	
NP-2		Skute Stone Arroyo		-18	NP-2-18	5/28/1982	QMC	
NP-2	81.91	Skute Stone Arroyo		-19	NP-2-19	6/8/1982	QMC	
NP-2	80.5	Skute Stone Arroyo		-20	NP-2-20	6/14/1982	QMC	
NP-2	77.8	Skute Stone Arroyo		-21	NP-2-21	6/30/1982		

Well Name	Sample Date	Latitude	Longitude	UTM Easting	UTM Northing	UTM Zone	Elevation	Filtered?	Chloride	Sulfate
MW-8	3/1/1998	32.96885	107.46111	269979	3650332	13	5012			
MW-8	4/1/1998	32.96885	107.46111	269979	3650332	13	5012			
MW-8	5/1/1998	32.96885	107.46111	269979	3650332	13	5012			
MW-8	6/1/1998	32.96885	107.46111	269979	3650332	13	5012			
MW-8	7/1/1998	32.96885	107.46111	269979	3650332	13	5012			
MW-8	8/1/1998	32.96885	107.46111	269979	3650332	13	5012			
MW-8	9/1/1998	32.96885	107.46111	269979	3650332	13	5012			
MW-9	11/16/1994	32.97841	107.38760	276875	3651234	13	4444	TRUE	12	12
MW-9	8/1/1997	32.97841	107.38760	276875	3651234	13	4444	TRUE	13.7	
MW-9	1/23/1998	32.97841	107.38760	276875	3651234	13	4444	TRUE	13.7	14
MW-9	2/1/1998	32.97841	107.38760	276875	3651234	13	4444			
MW-9	3/1/1998	32.97841	107.38760	276875	3651234	13	4444			
MW-9	4/15/1998	32.97841	107.38760	276875	3651234	13	4444	TRUE	13.1	13
MW-9	5/1/1998	32.97841	107.38760	276875	3651234	13	4444			
MW-9	6/1/1998	32.97841	107.38760	276875	3651234	13	4444			
MW-9	7/22/1998	32.97841	107.38760	276875	3651234	13	4444	TRUE	13.9	13
MW-9	8/1/1998	32.97841	107.38760	276875	3651234	13	4444			
MW-9	9/1/1998	32.97841	107.38760	276875	3651234	13	4444			
MW-9	10/15/1998	32.97841	107.38760	276875	3651234	13	4444	TRUE	10.2	14.5
NP-1	10/8/1981	32.95503	107.49676	266610	3648878	13	5176	TRUE	24.9	108
NP-1	11/4/1981	32.95503	107.49676	266610	3648878	13	5176	TRUE	28	148
NP-1	11/13/1981	32.95503	107.49676	266610	3648878	13	5176	TRUE	24.08	130.7
NP-1	11/17/1981	32.95503	107.49676	266610	3648878	13	5176	TRUE	24	154
NP-1	11/23/1981	32.95503	107.49676	266610	3648878	13	5176	TRUE	26	146
NP-1	12/7/1981	32.95503	107.49676	266610	3648878	13	5176	TRUE	24	158
NP-1	12/15/1981	32.95503	107.49676	266610	3648878	13	5176	TRUE	24	151
NP-1	12/22/1981	32.95503	107.49676	266610	3648878	13	5176	TRUE	22	149
NP-1	1/5/1982	32.95503	107.49676	266610	3648878	13	5176	TRUE	22	163
NP-1	1/18/1982	32.95503	107.49676	266610	3648878	13	5176	FALSE		
NP-1	1/26/1982	32.95503	107.49676	266610	3648878	13	5176	TRUE	22	154
NP-1	2/16/1982	32.95503	107.49676	266610	3648878	13	5176	FALSE		
NP-1	2/22/1982	32.95503	107.49676	266610	3648878	13	5176	TRUE	24	158
NP-1	3/12/1982	32.95503	107.49676	266610	3648878	13	5176	FALSE		
NP-1	4/16/1982	32.95503	107.49676	266610	3648878	13	5176	FALSE		
NP-1	4/26/1982	32.95503	107.49676	266610	3648878	13	5176	TRUE	26	154
NP-1	5/17/1982	32.95503	107.49676	266610	3648878	13	5176	FALSE		

Well Name	Sample Date	Latitude	Longitude	UTM Easting	UTM Northing	UTM Zone	Elevation	Filtered?	Chloride	Sulfate
NP-1	5/24/1982	32.95503	107.49676	266610	3648878	13	5176	TRUE		
NP-1	5/28/1982	32.95503	107.49676	266610	3648878	13	5176	TRUE		
NP-1	6/8/1982	32.95503	107.49676	266610	3648878	13	5176	TRUE	20	162
NP-1	6/14/1982	32.95503	107.49676	266610	3648878	13	5176	TRUE		
NP-1	6/30/1982	32.95503	107.49676	266610	3648878	13	5176	TRUE	18	143
NP-1	7/26/1982	32.95503	107.49676	266610	3648878	13	5176	FALSE		
NP-1	8/18/1982	32.95503	107.49676	266610	3648878	13	5176	FALSE		
NP-1	9/14/1982	32.95503	107.49676	266610	3648878	13	5176	FALSE		
NP-1	10/18/1982	32.95503	107.49676	266610	3648878	13	5176	FALSE		
NP-1	10/27/1982	32.95503	107.49676	266610	3648878	13	5176	TRUE	20	151
NP-1	11/11/1982	32.95503	107.49676	266610	3648878	13	5176	FALSE		
NP-1	12/28/1982	32.95503	107.49676	266610	3648878	13	5176	FALSE		
NP-1	2/21/1983	32.95503	107.49676	266610	3648878	13	5176	TRUE	18	156
NP-1	5/6/1983	32.95503	107.49676	266610	3648878	13	5176	FALSE		
NP-1	5/13/1983	32.95503	107.49676	266610	3648878	13	5176	TRUE	24	149
NP-1	6/2/1983	32.95503	107.49676	266610	3648878	13	5176	FALSE		
NP-1	7/5/1983	32.95503	107.49676	266610	3648878	13	5176	FALSE		
NP-1	8/9/1983	32.95503	107.49676	266610	3648878	13	5176	TRUE	22	130
NP-1	8/25/1983	32.95503	107.49676	266610	3648878	13	5176	FALSE		
NP-1	10/20/1983	32.95503	107.49676	266610	3648878	13	5176	FALSE		
NP-1	11/1/1983	32.95503	107.49676	266610	3648878	13	5176	TRUE	18	125
NP-1	12/7/1983	32.95503	107.49676	266610	3648878	13	5176	FALSE		
NP-1	1/28/1984	32.95503	107.49676	266610	3648878	13	5176	FALSE		
NP-1	2/13/1984	32.95503	107.49676	266610	3648878	13	5176	FALSE		
NP-1	3/1/1984	32.95503	107.49676	266610	3648878	13	5176	FALSE		
NP-1	3/16/1984	32.95503	107.49676	266610	3648878	13	5176	TRUE	22	124
NP-1	4/9/1984	32.95503	107.49676	266610	3648878	13	5176	FALSE		
NP-1	4/18/1984	32.95503	107.49676	266610	3648878	13	5176	FALSE		
NP-1	5/22/1984	32.95503	107.49676	266610	3648878	13	5176	FALSE		
NP-1	5/30/1984	32.95503	107.49676	266610	3648878	13	5176	TRUE	22	154
NP-1	6/26/1984	32.95503	107.49676	266610	3648878	13	5176	FALSE		
NP-1	7/25/1984	32.95503	107.49676	266610	3648878	13	5176	FALSE		
NP-1	8/27/1984	32.95503	107.49676	266610	3648878	13	5176	FALSE		
NP-1	9/12/1984	32.95503	107.49676	266610	3648878	13	5176	FALSE	22	137
NP-1	9/21/1984	32.95503	107.49676	266610	3648878	13	5176	FALSE		
NP-1	11/19/1984	32.95503	107.49676	266610	3648878	13	5176	FALSE		

Well Name	Sample Date	Latitude	Longitude	UTM Easting	UTM Northing	UTM Zone	Elevation	Filtered?	Chloride	Sulfate
NP-1	11/27/1984	32.95503	107.49676	266610	3648878	13	5176	FALSE	16	144
NP-1	12/17/1984	32.95503	107.49676	266610	3648878	13	5176	FALSE		
NP-1	5/17/1985	32.95503	107.49676	266610	3648878	13	5176	FALSE	20	144
NP-1	11/13/1985	32.95503	107.49676	266610	3648878	13	5176	FALSE	16	149
NP-1	5/23/1986	32.95503	107.49676	266610	3648878	13	5176	FALSE	18	142
NP-1	10/8/1986	32.95503	107.49676	266610	3648878	13	5176	FALSE	22	107
NP-1	3/30/1989	32.95503	107.49676	266610	3648878	13	5176	TRUE	14.9	137
NP-1	7/19/1991	32.95503	107.49676	266610	3648878	13	5176	TRUE	21.6	133.4
NP-1	8/29/1991	32.95503	107.49676	266610	3648878	13	5176	FALSE	21.1	140.7
NP-1	11/26/1991	32.95503	107.49676	266610	3648878	13	5176	FALSE	22.7	136.8
NP-1	3/15/1992	32.95503	107.49676	266610	3648878	13	5176	FALSE	22.1	146.2
NP-1	5/25/1992	32.95503	107.49676	266610	3648878	13	5176	FALSE	28.6	128.2
NP-1	7/16/1992	32.95503	107.49676	266610	3648878	13	5176	FALSE	21.7	142.2
NP-1	10/8/1992	32.95503	107.49676	266610	3648878	13	5176	FALSE	21.7	128.8
NP-1	11/27/1992	32.95503	107.49676	266610	3648878	13	5176	FALSE	21.3	142.4
NP-1	12/15/1992	32.95503	107.49676	266610	3648878	13	5176	FALSE	23.7	125
NP-1	2/25/1993	32.95503	107.49676	266610	3648878	13	5176	FALSE	22.6	138.3
NP-1	3/30/1993	32.95503	107.49676	266610	3648878	13	5176	FALSE	22	145
NP-1	9/28/1993	32.95503	107.49676	266610	3648878	13	5176	FALSE	36.2	110.1
NP-1	3/17/1994	32.95503	107.49676	266610	3648878	13	5176	FALSE	24	134.2
NP-1	5/24/1994	32.95503	107.49676	266610	3648878	13	5176	FALSE	22	130
NP-1	6/23/1994	32.95503	107.49676	266610	3648878	13	5176	FALSE	40.3	142.3
NP-1	7/21/1994	32.95503	107.49676	266610	3648878	13	5176	TRUE	23	133
NP-1	9/22/1994	32.95503	107.49676	266610	3648878	13	5176	FALSE	24.3	118.8
NP-1	1/29/1995	32.95503	107.49676	266610	3648878	13	5176	FALSE	26.2	125.4
NP-1	3/29/1995	32.95503	107.49676	266610	3648878	13	5176	FALSE	23.3	86.2
NP-1	6/27/1995	32.95503	107.49676	266610	3648878	13	5176	FALSE	24.1	113.7
NP-1	9/21/1995	32.95503	107.49676	266610	3648878	13	5176	FALSE	27.2	145
NP-1	1/10/1996	32.95503	107.49676	266610	3648878	13	5176	FALSE	26.1	109.4
NP-1	4/3/1996	32.95503	107.49676	266610	3648878	13	5176	FALSE	25.7	123.3
NP-1	6/1/1996	32.95503	107.49676	266610	3648878	13	5176		26.6	126.3
NP-1	9/25/1996	32.95503	107.49676	266610	3648878	13	5176	TRUE	23.6	94.4
NP-1	1/15/1997	32.95503	107.49676	266610	3648878	13	5176	TRUE	25.6	109.13
NP-1	4/1/1997	32.95503	107.49676	266610	3648878	13	5176	TRUE	26	114
NP-1	7/1/1997	32.95503	107.49676	266610	3648878	13	5176	TRUE	25.9	112
NP-1	10/1/1997	32.95503	107.49676	266610	3648878	13	5176	TRUE	26.2	119

Well Name	Sample Date	Latitude	Longitude	UTM Easting	UTM Northing	UTM Zone	Elevation	Filtered?	Chloride	Sulfate
NP-1	1/15/1998	32.95503	107.49676	266610	3648878	13	5176	TRUE	25.2	111
NP-1	4/9/1998	32.95503	107.49676	266610	3648878	13	5176	TRUE	26.8	120
NP-1	7/13/1998	32.95503	107.49676	266610	3648878	13	5176	TRUE	25	110
NP-2	10/8/1981	32.95807	107.49674	266619	3649215	13	5179	TRUE	45.1	198
NP-2	11/6/1981	32.95807	107.49674	266619	3649215	13	5179	TRUE	35	164
NP-2	11/13/1981	32.95807	107.49674	266619	3649215	13	5179	TRUE	30.79	162.4
NP-2	11/23/1981	32.95807	107.49674	266619	3649215	13	5179	TRUE	30	156
NP-2	12/7/1981	32.95807	107.49674	266619	3649215	13	5179	TRUE	30	160
NP-2	12/15/1981	32.95807	107.49674	266619	3649215	13	5179	TRUE	32	161
NP-2	12/22/1981	32.95807	107.49674	266619	3649215	13	5179	TRUE	32	161
NP-2	1/5/1982	32.95807	107.49674	266619	3649215	13	5179	TRUE	28	158
NP-2	1/18/1982	32.95807	107.49674	266619	3649215	13	5179	FALSE		
NP-2	1/25/1982	32.95807	107.49674	266619	3649215	13	5179	TRUE	24	160
NP-2	2/16/1982	32.95807	107.49674	266619	3649215	13	5179	FALSE		
NP-2	2/22/1982	32.95807	107.49674	266619	3649215	13	5179	TRUE	30	151
NP-2	3/12/1982	32.95807	107.49674	266619	3649215	13	5179	FALSE		
NP-2	4/16/1982	32.95807	107.49674	266619	3649215	13	5179	FALSE		
NP-2	4/26/1982	32.95807	107.49674	266619	3649215	13	5179	TRUE	42	149
NP-2	5/15/1982	32.95807	107.49674	266619	3649215	13	5179	TRUE	34	128
NP-2	5/24/1982	32.95807	107.49674	266619	3649215	13	5179	TRUE		
NP-2	5/28/1982	32.95807	107.49674	266619	3649215	13	5179	TRUE		
NP-2	6/8/1982	32.95807	107.49674	266619	3649215	13	5179	TRUE	26	158
NP-2	6/14/1982	32.95807	107.49674	266619	3649215	13	5179	FALSE		
NP-2	6/30/1982	32.95807	107.49674	266619	3649215	13	5179	TRUE	26	133

Well Name	Sample Date	pH	TDS	Alkalinity	Bicarb	Spec.Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
MW-8	3/1/1998										
MW-8	4/1/1998										
MW-8	5/1/1998										
MW-8	6/1/1998										
MW-8	7/1/1998										
MW-8	8/1/1998										
MW-8	9/1/1998										
MW-9	11/16/1994	8.05	230		149	293	1.4	-1	-0.05	-0.005	-0.005
MW-9	8/1/1997	8.13	174				1.33				
MW-9	1/23/1998	7.96	189		146.4	350	1.43				
MW-9	2/1/1998										
MW-9	3/1/1998										
MW-9	4/15/1998	8.07	189			336	1.53	0.91			
MW-9	5/1/1998										
MW-9	6/1/1998										
MW-9	7/22/1998		172				1.96	0.95			
MW-9	8/1/1998										
MW-9	9/1/1998										
MW-9	10/15/1998	7.79	175			382		0.83			
NP-1	10/8/1981	7.6	496		266		0.84	0.47	-0.25		-0.004
NP-1	11/4/1981	8.1	470				1	0.3	-0.01		-0.01
NP-1	11/13/1981	7.65	470		274.4	625	0.83	0.09	-0.25		-0.005
NP-1	11/17/1981	8	460				0.8	0.2	-0.01		-0.005
NP-1	11/23/1981	7.7	530				0.8	0.2	-0.01		-0.01
NP-1	12/7/1981	7.3	490				0.8	0.2	-0.01		-0.01
NP-1	12/15/1981	7.8	480				0.8	-0.2	-0.01		-0.01
NP-1	12/22/1981	7.8	450				0.8	0.3	-0.01		-0.01
NP-1	1/5/1982	7.6	400				0.8	0.7	-0.01		-0.01
NP-1	1/18/1982										
NP-1	1/26/1982	7.9	440				0.7	0.5			
NP-1	2/16/1982										
NP-1	2/22/1982	7.9	460				0.7	0.6			
NP-1	3/12/1982										
NP-1	4/16/1982										
NP-1	4/26/1982	7.9	440				0.6	0.7			
NP-1	5/17/1982										

Well Name	Sample Date	pH	TDS	Alkalinity	Bicarb	Spec.Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
NP-1	5/24/1982										
NP-1	5/28/1982										
NP-1	6/8/1982	7.5	500				0.6	1.1			
NP-1	6/14/1982										
NP-1	6/30/1982	7.7	500				0.6	1.1			
NP-1	7/26/1982										
NP-1	8/18/1982										
NP-1	9/14/1982										
NP-1	10/18/1982										
NP-1	10/27/1982	7.7	470				0.7	1.3			
NP-1	11/11/1982										
NP-1	12/28/1982										
NP-1	2/21/1983	7.7	490				0.7	1.3			
NP-1	5/6/1983										
NP-1	5/13/1983	7.9	470				0.6	1.1			
NP-1	6/2/1983										
NP-1	7/5/1983										
NP-1	8/9/1983	7.8	480				0.6	1.1			
NP-1	8/25/1983										
NP-1	10/20/1983										
NP-1	11/1/1983	7.8	500				0.6	2.1			
NP-1	12/7/1983										
NP-1	1/28/1984										
NP-1	2/13/1984										
NP-1	3/1/1984										
NP-1	3/16/1984	8.2	480				0.6	1.8			
NP-1	4/9/1984										
NP-1	4/18/1984										
NP-1	5/22/1984										
NP-1	5/30/1984	7.5	510				0.6	0.7			
NP-1	6/26/1984										
NP-1	7/25/1984										
NP-1	8/27/1984										
NP-1	9/12/1984	7.7	480				0.6	1.1			
NP-1	9/21/1984										
NP-1	11/19/1984										

Well Name	Sample Date	pH	TDS	Alkalinity	Bicarb	Spec.Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
NP-1	11/27/1984	7.8	480				0.6	1.1			
NP-1	12/17/1984										
NP-1	5/17/1985	7.6	510								
NP-1	11/13/1985	7.3	480								
NP-1	5/23/1986	7.6	500								
NP-1	10/8/1986	7.4	470								
NP-1	3/30/1989		492		279				0.1		
NP-1	7/19/1991	8.04	530	210	256.3	761	0.58	0.99			0.003
NP-1	8/29/1991	7.69	501								
NP-1	11/26/1991	7.12	1484								
NP-1	3/15/1992	7.8	510								
NP-1	5/25/1992	7.49	608								
NP-1	7/16/1992	7.5	487								
NP-1	10/8/1992	7.35	517								
NP-1	11/27/1992	7.85	498								
NP-1	12/15/1992	7.58	502								
NP-1	2/25/1993	7.42	510								
NP-1	3/30/1993	7.7	496		306	767	0.59	1.1	-0.1		-0.005
NP-1	9/28/1993	7.48	508								
NP-1	3/17/1994	7.3	516								
NP-1	5/24/1994	7.53	510		263	680	0.56	1.1	0.83	-0.005	0.005
NP-1	6/23/1994	7.5	453								
NP-1	7/21/1994	7.87	464		249	698	0.65	-1	-0.05	-0.005	-0.005
NP-1	9/22/1994	7.49	488								
NP-1	1/29/1995	7.94	407								
NP-1	3/29/1995	7.98	392								
NP-1	6/27/1995	8.02	385								
NP-1	9/21/1995	7.96	373								
NP-1	1/10/1996	7.73	277								
NP-1	4/3/1996	7.89	300								
NP-1	6/1/1996	7.73	312								
NP-1	9/25/1996	8.22	320								
NP-1	1/15/1997	8.42	318								
NP-1	4/1/1997		280				0.8				
NP-1	7/1/1997	8.06	288								
NP-1	10/1/1997	8.31	296								

Well Name	Sample Date	pH	TDS	Alkalinity	Bicarb	Spec.Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
NP-1	1/15/1998	7.87	276			582	0.63	-0.05			
NP-1	4/9/1998		319			564	0.58	0.11			
NP-1	7/13/1998		301			531	0.61	-0.05			
NP-2	10/8/1981	7.39	476		159		1.75	0.23	-0.25		0.024
NP-2	11/6/1981	7.6	450				1.4	0.4	-0.01		-0.1
NP-2	11/13/1981	7.65	466		221.3	675	1.14	0.25	-0.25		-0.005
NP-2	11/23/1981	7.7	520				0.9	0.7	-0.01		-0.01
NP-2	12/7/1981	7.5	490				0.8	0.6	-0.01		-0.01
NP-2	12/15/1981	8	480				0.09	0.5	-0.01		-0.01
NP-2	12/22/1981	8	440				0.6	0.8	-0.01		-0.01
NP-2	1/5/1982	7.6	400				0.9	0.9	-0.01		-0.01
NP-2	1/18/1982										
NP-2	1/25/1982	8	450				0.7	1.1			
NP-2	2/16/1982										
NP-2	2/22/1982	8	440				0.7	0.8			
NP-2	3/12/1982										
NP-2	4/16/1982										
NP-2	4/26/1982	8	450				1	2.4			
NP-2	5/15/1982	7.9	480				0.6	1.8			
NP-2	5/24/1982										
NP-2	5/28/1982										
NP-2	6/8/1982	7.8	490				0.5	0.9			
NP-2	6/14/1982										
NP-2	6/30/1982	7.8	490				0.6	1.4			

Well Name	Sample Date	Boron	Barium	Berylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
MW-8	3/1/1998										
MW-8	4/1/1998										
MW-8	5/1/1998										
MW-8	6/1/1998										
MW-8	7/1/1998										
MW-8	8/1/1998										
MW-8	9/1/1998										
MW-9	11/16/1994	-0.1	-0.1	-0.002	-0.0005	12	-0.025	-0.05	-0.025	-0.05	-0.005
MW-9	8/1/1997										
MW-9	1/23/1998					12.1			-0.005		
MW-9	2/1/1998										
MW-9	3/1/1998										
MW-9	4/15/1998					13.5			-0.005		
MW-9	5/1/1998										
MW-9	6/1/1998										
MW-9	7/22/1998					13			-0.005	-0.05	
MW-9	8/1/1998										
MW-9	9/1/1998										
MW-9	10/15/1998								-0.005	0.07	
NP-1	10/8/1981	-0.004	-1		-0.01	55.7	-0.05	-0.05	-0.05	0.27	-0.05
NP-1	11/4/1981	-0.1	-0.2		-0.005	54	-0.01	-0.02	-0.05	-0.1	-0.02
NP-1	11/13/1981	0.044	0.2		0.006	71.6	-0.005				-0.005
NP-1	11/17/1981	-0.1	0.24		-0.005	59	-0.01	-0.02	0.069	-0.1	-0.02
NP-1	11/23/1981	-0.1	0.02		-0.005	58	-0.02	-0.02	-0.05	-0.1	-0.02
NP-1	12/7/1981	-0.1	-0.2		-0.005	58	-0.01	-0.02	-0.05	-0.1	-0.02
NP-1	12/15/1981	-0.1	-0.2		-0.005	68	-0.01	-0.02	-0.05	-0.1	-0.02
NP-1	12/22/1981	-0.1	-0.2		-0.005	66	-0.01	-0.02	-0.05	-0.1	-0.02
NP-1	1/5/1982	-0.1	-0.2		-0.005	67	-0.01	-0.02	-0.05	0.14	-0.02
NP-1	1/18/1982										
NP-1	1/26/1982				-0.005				-0.05	-0.1	
NP-1	2/16/1982										
NP-1	2/22/1982				-0.005				0.48	0.83	
NP-1	3/12/1982										
NP-1	4/16/1982										
NP-1	4/26/1982				-0.005				-0.05	1.2	
NP-1	5/17/1982										

Well Name	Sample Date	Boron	Barium	Berylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
NP-1	5/24/1982									-0.1	
NP-1	5/28/1982									-0.1	
NP-1	6/8/1982				-0.005				-0.05	-0.1	
NP-1	6/14/1982										
NP-1	6/30/1982				-0.005				-0.05	-0.1	
NP-1	7/26/1982										
NP-1	8/18/1982										
NP-1	9/14/1982										
NP-1	10/18/1982										
NP-1	10/27/1982				-0.005				-0.05	0.45	
NP-1	11/11/1982										
NP-1	12/28/1982										
NP-1	2/21/1983				-0.005				-0.05	-0.1	
NP-1	5/6/1983										
NP-1	5/13/1983				-0.005				-0.05	-0.1	
NP-1	6/2/1983										
NP-1	7/5/1983										
NP-1	8/9/1983				-0.005				-0.05	0.22	
NP-1	8/25/1983										
NP-1	10/20/1983										
NP-1	11/1/1983				-0.005				-0.05	0.14	
NP-1	12/7/1983										
NP-1	1/28/1984										
NP-1	2/13/1984										
NP-1	3/1/1984										
NP-1	3/16/1984				-0.005				-0.05	-0.1	
NP-1	4/9/1984										
NP-1	4/18/1984										
NP-1	5/22/1984										
NP-1	5/30/1984				-0.005				-0.05	-0.1	
NP-1	6/26/1984										
NP-1	7/25/1984										
NP-1	8/27/1984										
NP-1	9/12/1984				-0.005				-0.05	-0.1	
NP-1	9/21/1984										
NP-1	11/19/1984										

Well Name	Sample Date	Boron	Barium	Berylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
NP-1	11/27/1984				-0.005				-0.05	-0.1	
NP-1	12/17/1984										
NP-1	5/17/1985										
NP-1	11/13/1985										
NP-1	5/23/1986										
NP-1	10/8/1986										
NP-1	3/30/1989	-0.1	-0.1	-0.01	-0.1	88	-0.1	-0.05	-0.1	-0.1	-0.1
NP-1	7/19/1991			0.02	-0.005	81.1	-0.02			-0.59	0.007
NP-1	8/29/1991										
NP-1	11/26/1991										
NP-1	3/15/1992										
NP-1	5/25/1992										
NP-1	7/16/1992										
NP-1	10/8/1992										
NP-1	11/27/1992										
NP-1	12/15/1992										
NP-1	2/25/1993										
NP-1	3/30/1993	0.03	-0.5		-0.002	79	-0.02	-0.05	-0.01	0.17	-0.02
NP-1	9/28/1993										
NP-1	3/17/1994										
NP-1	5/24/1994		-0.1		0.0096	79	-0.025		-0.025	9.5	0.016
NP-1	6/23/1994										
NP-1	7/21/1994	-0.1	-0.1	-0.002	-0.0005	71	-0.025	-0.05	-0.025	0.052	-0.005
NP-1	9/22/1994			-0.002							
NP-1	1/29/1995										
NP-1	3/29/1995										
NP-1	6/27/1995										
NP-1	9/21/1995										
NP-1	1/10/1996										
NP-1	4/3/1996										
NP-1	6/1/1996										
NP-1	9/25/1996										
NP-1	1/15/1997										
NP-1	4/1/1997								-0.005	1.2	
NP-1	7/1/1997										
NP-1	10/1/1997										

Well Name	Sample Date	Boron	Barium	Berylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
NP-1	1/15/1998								-0.005	1.3	
NP-1	4/9/1998								0.01	2.11	
NP-1	7/13/1998								-0.005	0.32	
NP-2	10/8/1981	0.08	-1		-0.01	46	-0.05	-0.05	-0.05	-0.1	-0.05
NP-2	11/6/1981	-0.1	-0.2		-0.005	53	-0.01	-0.02	-0.05	-0.1	-0.02
NP-2	11/13/1981	0.04	-0.1		-0.001	65.1	-0.005				-0.005
NP-2	11/23/1981	-0.1	0.02		-0.005	57	-0.02	-0.02	-0.05	-0.1	-0.02
NP-2	12/7/1981	-0.1	-0.2		-0.005	53	-0.01	-0.02	-0.05	-0.1	-0.02
NP-2	12/15/1981	-0.1	-0.2		-0.005	62	-0.01	-0.02	-0.05	-0.1	-0.02
NP-2	12/22/1981	-0.1	0.21		-0.005	73	-0.01	-0.02	-0.05	0.12	-0.02
NP-2	1/5/1982	-0.1	-0.2		-0.005	65	-0.01	-0.02	-0.05	0.14	-0.02
NP-2	1/18/1982										
NP-2	1/25/1982				-0.005				-0.05	-0.1	
NP-2	2/16/1982										
NP-2	2/22/1982				-0.005				0.069	0.37	
NP-2	3/12/1982										
NP-2	4/16/1982										
NP-2	4/26/1982				-0.005				-0.05	1.2	
NP-2	5/15/1982				0.015				-0.05	0.68	
NP-2	5/24/1982									-0.1	
NP-2	5/28/1982									-0.1	
NP-2	6/8/1982				-0.005				-0.05	-0.1	
NP-2	6/14/1982										
NP-2	6/30/1982				-0.005				-0.05	-0.1	

Well Name	Sample Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium	Thallium
MW-8	3/1/1998										
MW-8	4/1/1998										
MW-8	5/1/1998										
MW-8	6/1/1998										
MW-8	7/1/1998										
MW-8	8/1/1998										
MW-8	9/1/1998										
MW-9	11/16/1994	1	-0.03	-0.001	-0.05	-0.05	2.3	-0.005	-0.025	52	-0.005
MW-9	8/1/1997										
MW-9	1/23/1998	1.6	-0.02				4.6			50.1	
MW-9	2/1/1998										
MW-9	3/1/1998										
MW-9	4/15/1998	0.8	-0.02	-0.0002	-0.05		1.5	-0.05		51.2	
MW-9	5/1/1998										
MW-9	6/1/1998										
MW-9	7/22/1998	0.6	-0.02	0.0004	-0.05		1.6	-0.05		45.8	
MW-9	8/1/1998										
MW-9	9/1/1998										
MW-9	10/15/1998										
NP-1	10/8/1981	13.7	0.92	-1	-0.1	-0.05	8.25	0.003	-0.02	61.7	
NP-1	11/4/1981		0.6	-0.001	-0.05	-0.05		-0.005	-0.02		
NP-1	11/13/1981	19.28	1.34	-0.0005	0.011	-0.05	5.85	0.029	-0.001	39.1	
NP-1	11/17/1981		1.4	-0.001	0.06	-0.05		-0.005	-0.02		
NP-1	11/23/1981		1.2	-0.001	-0.05	-0.05		-0.005	-0.02		
NP-1	12/7/1981		1.2	-0.001	-0.05	-0.05		-0.005	-0.02		
NP-1	12/15/1981		1.2	-0.001	-0.05	-0.05		-0.005	-0.02		
NP-1	12/22/1981		1	-0.001	-0.05	-0.05		-0.005	-0.02		
NP-1	1/5/1982		0.71	0.0012	-0.05	-0.05		-0.02	-0.02		
NP-1	1/18/1982										
NP-1	1/26/1982		0.45	-0.001	-0.1			-0.005			
NP-1	2/16/1982										
NP-1	2/22/1982		0.26	-0.001	-0.05			-0.005			
NP-1	3/12/1982										
NP-1	4/16/1982										
NP-1	4/26/1982		0.16	-0.001	-0.05			-0.005			
NP-1	5/17/1982										

Well Name	Sample Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium	Thallium
NP-1	5/24/1982		0.28								
NP-1	5/28/1982		0.022								
NP-1	6/8/1982		0.025	-0.001	-0.05			-0.005			
NP-1	6/14/1982										
NP-1	6/30/1982		0.18	-0.001	-0.05			-0.005			
NP-1	7/26/1982										
NP-1	8/18/1982							-0.005			
NP-1	9/14/1982										
NP-1	10/18/1982										
NP-1	10/27/1982		0.058	-0.001	-0.05			-0.005			
NP-1	11/11/1982										
NP-1	12/28/1982										
NP-1	2/21/1983		-0.05	-0.001	-0.05			-0.005			
NP-1	5/6/1983										
NP-1	5/13/1983		-0.05	-0.001	-0.05			-0.005			
NP-1	6/2/1983										
NP-1	7/5/1983										
NP-1	8/9/1983		-0.05	-0.001	-0.05			-0.005			
NP-1	8/25/1983										
NP-1	10/20/1983										
NP-1	11/1/1983		-0.05	-0.001	-0.05			-0.005			
NP-1	12/7/1983										
NP-1	1/28/1984										
NP-1	2/13/1984										
NP-1	3/1/1984										
NP-1	3/16/1984		-0.05	0.0083	-0.05			-0.005			
NP-1	4/9/1984			-0.001							
NP-1	4/18/1984										
NP-1	5/22/1984										
NP-1	5/30/1984		-0.05	-0.001	-0.05			-0.005			
NP-1	6/26/1984										
NP-1	7/25/1984										
NP-1	8/27/1984										
NP-1	9/12/1984		-0.05	-0.001	-0.05			-0.005			
NP-1	9/21/1984										
NP-1	11/19/1984										

Well Name	Sample Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium	Thallium
NP-1	11/27/1984		-0.05	-0.001	-0.05			-0.005			
NP-1	12/17/1984										
NP-1	5/17/1985										
NP-1	11/13/1985										
NP-1	5/23/1986										
NP-1	10/8/1986										
NP-1	3/30/1989	23	-0.05		-0.1	-0.1	3		-0.1	46	
NP-1	7/19/1991	23.9	-0.02	-0.0002			2	-0.002	-0.02	31.2	
NP-1	8/29/1991										
NP-1	11/26/1991										
NP-1	3/15/1992										
NP-1	5/25/1992										
NP-1	7/16/1992										
NP-1	10/8/1992										
NP-1	11/27/1992										
NP-1	12/15/1992										
NP-1	2/25/1993										
NP-1	3/30/1993	27	-0.02	-0.001	-0.02	-0.01	1.8	-0.005	-0.01	52	
NP-1	9/28/1993										
NP-1	3/17/1994										
NP-1	5/24/1994	23	0.1	-0.001		-0.05	2.5	-0.005	-0.025	48	
NP-1	6/23/1994										
NP-1	7/21/1994	23	0.27	-0.001	-0.05	-0.05	2.2	-0.005	-0.025	47	-0.005
NP-1	9/22/1994										
NP-1	1/29/1995										
NP-1	3/29/1995										
NP-1	6/27/1995										
NP-1	9/21/1995										
NP-1	1/10/1996										
NP-1	4/3/1996										
NP-1	6/1/1996										
NP-1	9/25/1996										
NP-1	1/15/1997										
NP-1	4/1/1997		-0.02	-0.002				0.0026			
NP-1	7/1/1997										
NP-1	10/1/1997										

Well Name	Sample Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium	Thallium
NP-1	1/15/1998	19.7		-0.0002	-0.05			-0.05			
NP-1	4/9/1998		0.02	-0.0002	-0.05			-0.05			
NP-1	7/13/1998		0.05	0.0007	-0.05			-0.05			
NP-2	10/8/1981	14.6	0.62	-1	-0.1	-0.05	9.57	-0.002	-0.02	93.5	
NP-2	11/6/1981		0.39	-0.001	0.21	-0.05		-0.005	-0.02		
NP-2	11/13/1981	18.67	0.79	-0.0005	0.04	-0.01	3.9	0.017	-0.001	59.8	
NP-2	11/23/1981		0.54	-0.001	0.06	-0.05		-0.005	-0.02		
NP-2	12/7/1981		0.54	-0.001	0.06	-0.05		-0.005	-0.02		
NP-2	12/15/1981		0.52	-0.001	0.072	-0.05		-0.005	-0.02		
NP-2	12/22/1981		0.51	-0.001	0.053	-0.05		-0.005	-0.02		
NP-2	1/5/1982		0.49	-0.001	0.07	-0.05		-0.02	-0.02		
NP-2	1/18/1982										
NP-2	1/25/1982		0.34	-0.001	-0.1			-0.005			
NP-2	2/16/1982										
NP-2	2/22/1982		0.3	-0.001	-0.05			-0.005			
NP-2	3/12/1982										
NP-2	4/16/1982										
NP-2	4/26/1982		0.29	-0.001	-0.05			-0.005			
NP-2	5/15/1982		0.078	-0.001	-0.05			-0.005			
NP-2	5/24/1982		-0.05								
NP-2	5/28/1982		-0.05								
NP-2	6/8/1982		-0.05	-0.001	-0.05			-0.005			
NP-2	6/14/1982										
NP-2	6/30/1982		-0.05	-0.001	-0.05			-0.005			

Well Name	Sample Date	Zinc	Temp (C)	Tin	Vanadium
MW-8	3/1/1998				
MW-8	4/1/1998				
MW-8	5/1/1998				
MW-8	6/1/1998				
MW-8	7/1/1998				
MW-8	8/1/1998				
MW-8	9/1/1998				
MW-9	11/16/1994	-0.05			
MW-9	8/1/1997				
MW-9	1/23/1998				
MW-9	2/1/1998				
MW-9	3/1/1998				
MW-9	4/15/1998				
MW-9	5/1/1998				
MW-9	6/1/1998				
MW-9	7/22/1998				
MW-9	8/1/1998				
MW-9	9/1/1998				
MW-9	10/15/1998				
NP-1	10/8/1981	0.4			
NP-1	11/4/1981	0.14			
NP-1	11/13/1981	0.44	20		
NP-1	11/17/1981	3.9			
NP-1	11/23/1981	4.1			
NP-1	12/7/1981	5.1			
NP-1	12/15/1981	5.3			
NP-1	12/22/1981	4.1			
NP-1	1/5/1982	4.1			
NP-1	1/18/1982				
NP-1	1/26/1982				
NP-1	2/16/1982				
NP-1	2/22/1982				
NP-1	3/12/1982				
NP-1	4/16/1982				
NP-1	4/26/1982				
NP-1	5/17/1982				

Well Name	Sample Date	Zinc	Temp (C)	Tin	Vanadium
NP-1	5/24/1982				
NP-1	5/28/1982				
NP-1	6/8/1982				
NP-1	6/14/1982				
NP-1	6/30/1982				
NP-1	7/26/1982				
NP-1	8/18/1982				
NP-1	9/14/1982				
NP-1	10/18/1982				
NP-1	10/27/1982				
NP-1	11/11/1982				
NP-1	12/28/1982				
NP-1	2/21/1983				
NP-1	5/6/1983				
NP-1	5/13/1983				
NP-1	6/2/1983				
NP-1	7/5/1983				
NP-1	8/9/1983				
NP-1	8/25/1983				
NP-1	10/20/1983				
NP-1	11/1/1983				
NP-1	12/7/1983				
NP-1	1/28/1984				
NP-1	2/13/1984				
NP-1	3/1/1984				
NP-1	3/16/1984				
NP-1	4/9/1984				
NP-1	4/18/1984				
NP-1	5/22/1984				
NP-1	5/30/1984				
NP-1	6/26/1984				
NP-1	7/25/1984				
NP-1	8/27/1984				
NP-1	9/12/1984				
NP-1	9/21/1984				
NP-1	11/19/1984				

Well Name	Sample Date	Zinc	Temp (C)	Tin	Vanadium
NP-1	11/27/1984				
NP-1	12/17/1984				
NP-1	5/17/1985				
NP-1	11/13/1985				
NP-1	5/23/1986				
NP-1	10/8/1986				
NP-1	3/30/1989	2.6		0.2	-0.1
NP-1	7/19/1991				
NP-1	8/29/1991				
NP-1	11/26/1991				
NP-1	3/15/1992				
NP-1	5/25/1992				
NP-1	7/16/1992				
NP-1	10/8/1992				
NP-1	11/27/1992				
NP-1	12/15/1992				
NP-1	2/25/1993				
NP-1	3/30/1993	1.13			
NP-1	9/28/1993				
NP-1	3/17/1994				
NP-1	5/24/1994	5.7			
NP-1	6/23/1994				
NP-1	7/21/1994	4.9			
NP-1	9/22/1994				
NP-1	1/29/1995				
NP-1	3/29/1995				
NP-1	6/27/1995				
NP-1	9/21/1995				
NP-1	1/10/1996				
NP-1	4/3/1996				
NP-1	6/1/1996				
NP-1	9/25/1996				
NP-1	1/15/1997				
NP-1	4/1/1997				
NP-1	7/1/1997				
NP-1	10/1/1997				

Well Name	Sample Date	Zinc	Temp (C)	Tin	Vanadium
NP-1	1/15/1998				
NP-1	4/9/1998				
NP-1	7/13/1998				
NP-2	10/8/1981	0.31			
NP-2	11/6/1981	1.7			
NP-2	11/13/1981	3.18	21		
NP-2	11/23/1981	3.5			
NP-2	12/7/1981	4.4			
NP-2	12/15/1981	2.9			
NP-2	12/22/1981	2.8			
NP-2	1/5/1982	3.2			
NP-2	1/18/1982				
NP-2	1/25/1982				
NP-2	2/16/1982				
NP-2	2/22/1982				
NP-2	3/12/1982				
NP-2	4/16/1982				
NP-2	4/26/1982				
NP-2	5/15/1982				
NP-2	5/24/1982				
NP-2	5/28/1982				
NP-2	6/8/1982				
NP-2	6/14/1982				
NP-2	6/30/1982				

Well Name	Water Depth	USGS Quad	Well Depth	Sample ID	Sample Date	Sampler	Notes
NP-2	77.83	Skute Stone Arroyo	-22	NP-2-22	7/26/1982	QMC	
NP-2	76.6	Skute Stone Arroyo	-23	NP-2-23	8/18/1982	QMC	
NP-2	75.6	Skute Stone Arroyo	-24	NP-2-24	9/2/1982	EID	
NP-2	75.1	Skute Stone Arroyo	-25	NP-2-25	9/14/1982	QMC	
NP-2	72.9	Skute Stone Arroyo	-26	NP-2-26	10/18/1982	QMC	
NP-2	72.9	Skute Stone Arroyo	-27	NP-2-27	10/27/1982	QMC	
NP-2	71.6	Skute Stone Arroyo	-28	NP-2-28	11/11/1982	QMC	
NP-2	69.7	Skute Stone Arroyo	-29	NP-2-29	12/28/1982	QMC	
NP-2	67.8	Skute Stone Arroyo	-30	NP-2-30	2/21/1983	QMC	
NP-2	67	Skute Stone Arroyo	-31	NP-2-31	5/6/1983	QMC	
NP-2	67	Skute Stone Arroyo	-32	NP-2-32	5/13/1983	QMC	
NP-2	66.8	Skute Stone Arroyo	-33	NP-2-33	6/2/1983	QMC	
NP-2	66.8	Skute Stone Arroyo	-34	NP-2-34	7/5/1983	QMC	
NP-2	66.9	Skute Stone Arroyo	-35	NP-2-35	8/9/1983	QMC	
NP-2	66.9	Skute Stone Arroyo	-36	NP-2-36	8/25/1983	QMC	
NP-2	66.2	Skute Stone Arroyo	-37	NP-2-37	10/20/1983	QMC	
NP-2	66.2	Skute Stone Arroyo	-38	NP-2-38	11/1/1983	QMC	
NP-2	65	Skute Stone Arroyo	-39	NP-2-39	12/7/1983	QMC	
NP-2	64.4	Skute Stone Arroyo	-40	NP-2-40	1/28/1984	QMC	
NP-2	64.2	Skute Stone Arroyo	-41	NP-2-41	2/13/1984	QMC	
NP-2	63.8	Skute Stone Arroyo	-42	NP-2-42	3/84	QMC	
NP-2	63.8	Skute Stone Arroyo	-43	NP-2-43	3/16/1984	CFP	
NP-2	63.8	Skute Stone Arroyo	-44	NP-2-44	4/18/1984	CFP	
NP-2	63.7	Skute Stone Arroyo	-45	NP-2-45	5/22/1984	CFP	
NP-2	63.7	Skute Stone Arroyo	-46	NP-2-46	5/30/1984	CFP	
NP-2	63.4	Skute Stone Arroyo	-47	NP-2-47	6/26/1984	CFP	
NP-2	63.4	Skute Stone Arroyo	-48	NP-2-48	7/25/1984	CFP	
NP-2	63.3	Skute Stone Arroyo	-49	NP-2-49	8/27/1984	CFP	
NP-2	62.5	Skute Stone Arroyo	-50	NP-2-50	9/12/1984	CFP	
NP-2	62.5	Skute Stone Arroyo	-51	NP-2-51	9/21/1984	CFP	
NP-2	62.6	Skute Stone Arroyo	-52	NP-2-52	11/19/1984	CFP	
NP-2	62.6	Skute Stone Arroyo	-53	NP-2-53	12/27/1984	CFP	
NP-2	61.9	Skute Stone Arroyo	-54	NP-2-54	12/17/1984	CFP	
NP-2	61.4	Skute Stone Arroyo	-55	NP-2-55	5/17/1985	CFP	
NP-2	53.1	Skute Stone Arroyo	-56	NP-2-56	11/13/1985	CFP	
NP-2	51	Skute Stone Arroyo	-57	NP-2-57	5/23/1986	CFP	

Well Name	Water Depth	USGS Quad	Well Depth	Sample ID	Sample Date	Sampler	Notes
NP-2	51.6	Skute Stone Arroyo	-58	NP-2-58	10/8/1986	CFP	
NP-2		Skute Stone Arroyo	-59	NP-2-59	3/30/1989	EID	
NP-2	3.9	Skute Stone Arroyo	-60	NP-2-60	7/19/1991	GE	Lab NP-3- mixed w/
NP-2	30	Skute Stone Arroyo	-61	NP-2-61	8/29/1991	Irwin	lab pH
NP-2		Skute Stone Arroyo	-62	NP-2-62	10/26/1991	Hood	lab pH
NP-2	28.33	Skute Stone Arroyo	-63	NP-2-63	3/15/1992	Irwin	lab pH
NP-2		Skute Stone Arroyo	-64	NP-2-64	5/25/1992	Irwin	lab pH
NP-2		Skute Stone Arroyo	-65	NP-2-65	7/16/1992	Irwin	lab pH
NP-2	27.33	Skute Stone Arroyo	-66	NP-2-66	10/8/1992	Irwin	lab pH
NP-2	25.58	Skute Stone Arroyo	-67	NP-2-67	11/27/1992	Hood	lab pH
NP-2		Skute Stone Arroyo	-68	NP-2-68	12/15/1992	Irwin	lab pH
NP-2	27.5	Skute Stone Arroyo	-69	NP-2-69	2/25/1993	Irwin	lab pH
NP-2		Skute Stone Arroyo	-70	NP-2-70	3/30/1993	JWS	
NP-2		Skute Stone Arroyo	-71	NP-2-71	9/28/1993	Irwin	lab pH
NP-2	18.67	Skute Stone Arroyo	-72	NP-2-72	3/17/1994	Irwin	lab pH
NP-2	26.7	Skute Stone Arroyo	-73	NP-2-73	5/24/1994	SRK	
NP-2		Skute Stone Arroyo	-74	NP-2-74	6/23/1994	Irwin	lab pH
NP-2		Skute Stone Arroyo	-75	NP-2-75	7/22/1994	SRK	
NP-2		Skute Stone Arroyo	-76	NP-2-76	9/22/1994	Irwin	lab pH
NP-2		Skute Stone Arroyo	-77	NP-2-77	1/29/1995	Irwin	lab pH
NP-2		Skute Stone Arroyo	-78	NP-2-78	3/29/1995	Irwin	lab pH
NP-2	30.25	Skute Stone Arroyo	-79	NP-2-79	6/27/1995	Irwin	lab pH
NP-2		Skute Stone Arroyo	-80	NP-2-80	9/21/1995	Irwin	lab pH
NP-2		Skute Stone Arroyo	-81	NP-2-81	1/10/1996	Irwin	lab pH
NP-2		Skute Stone Arroyo	-82	NP-2-82	4/3/1996	Irwin	lab pH
NP-2		Skute Stone Arroyo	-83	NP-2-83	6/1/1996		
NP-2		Skute Stone Arroyo	-84	NP-2-84	9/25/1996	Irwin	lab pH
NP-2		Skute Stone Arroyo	-85	NP-2-85	1/15/1997	Irwin	lab pH
NP-2		Skute Stone Arroyo	-86	NP-2-86	7/1/1997		
NP-2		Skute Stone Arroyo	-87	NP-2-87	10/1/1997		
NP-2	33.25	Skute Stone Arroyo	-88	NP-2-88	1/15/1998	Irwin	
NP-2	32.75	Skute Stone Arroyo	-89	NP-2-89	4/9/1998	Irwin	
NP-2	33	Skute Stone Arroyo	-90	NP-2-90	7/13/1998	Irwin	

Well Name	Sample Date	Latitude	Longitude	UTM Easting	UTM Northing	UTM Zone	Elevation	Filtered?	Chloride	Sulfate
NP-2	7/26/1982	32.95807	107.49674	266619	3649215	13	5179	FALSE		
NP-2	8/18/1982	32.95807	107.49674	266619	3649215	13	5179	FALSE		
NP-2	9/2/1982	32.95807	107.49674	266619	3649215	13	5179	TRUE	26.49	127
NP-2	9/14/1982	32.95807	107.49674	266619	3649215	13	5179	FALSE		
NP-2	10/18/1982	32.95807	107.49674	266619	3649215	13	5179	FALSE		
NP-2	10/27/1982	32.95807	107.49674	266619	3649215	13	5179	TRUE	26	120
NP-2	11/11/1982	32.95807	107.49674	266619	3649215	13	5179	FALSE		
NP-2	12/28/1982	32.95807	107.49674	266619	3649215	13	5179	FALSE		
NP-2	2/21/1983	32.95807	107.49674	266619	3649215	13	5179	TRUE	24	127
NP-2	5/6/1983	32.95807	107.49674	266619	3649215	13	5179	FALSE		
NP-2	5/13/1983	32.95807	107.49674	266619	3649215	13	5179	TRUE	24	139
NP-2	6/2/1983	32.95807	107.49674	266619	3649215	13	5179	FALSE		
NP-2	7/5/1983	32.95807	107.49674	266619	3649215	13	5179	FALSE		
NP-2	8/9/1983	32.95807	107.49674	266619	3649215	13	5179	TRUE	36	148
NP-2	8/25/1983	32.95807	107.49674	266619	3649215	13	5179	FALSE		
NP-2	10/20/1983	32.95807	107.49674	266619	3649215	13	5179	FALSE		
NP-2	11/1/1983	32.95807	107.49674	266619	3649215	13	5179	TRUE	24	111
NP-2	12/7/1983	32.95807	107.49674	266619	3649215	13	5179	FALSE		
NP-2	1/28/1984	32.95807	107.49674	266619	3649215	13	5179	FALSE		
NP-2	2/13/1984	32.95807	107.49674	266619	3649215	13	5179	FALSE		
NP-2	3/84	32.95807	107.49674	266619	3649215	13	5179	FALSE		
NP-2	3/16/1984	32.95807	107.49674	266619	3649215	13	5179	TRUE	30	146
NP-2	4/18/1984	32.95807	107.49674	266619	3649215	13	5179	FALSE		
NP-2	5/22/1984	32.95807	107.49674	266619	3649215	13	5179	FALSE		
NP-2	5/30/1984	32.95807	107.49674	266619	3649215	13	5179	TRUE	32	175
NP-2	6/26/1984	32.95807	107.49674	266619	3649215	13	5179	FALSE		
NP-2	7/25/1984	32.95807	107.49674	266619	3649215	13	5179	FALSE		
NP-2	8/27/1984	32.95807	107.49674	266619	3649215	13	5179	FALSE		
NP-2	9/12/1984	32.95807	107.49674	266619	3649215	13	5179	TRUE	22	134
NP-2	9/21/1984	32.95807	107.49674	266619	3649215	13	5179	FALSE		
NP-2	11/19/1984	32.95807	107.49674	266619	3649215	13	5179	FALSE		
NP-2	12/27/1984	32.95807	107.49674	266619	3649215	13	5179	TRUE	20	125
NP-2	12/17/1984	32.95807	107.49674	266619	3649215	13	5179	FALSE		
NP-2	5/17/1985	32.95807	107.49674	266619	3649215	13	5179	FALSE	22	120
NP-2	11/13/1985	32.95807	107.49674	266619	3649215	13	5179	FALSE	22	115
NP-2	5/23/1986	32.95807	107.49674	266619	3649215	13	5179	FALSE	28	113

Well Name	Sample Date	Latitude	Longitude	UTM Easting	UTM Northing	UTM Zone	Elevation	Filtered?	Chloride	Sulfate
NP-2	10/8/1986	32.95807	107.49674	266619	3649215	13	5179	FALSE	24	100
NP-2	3/30/1989	32.95807	107.49674	266619	3649215	13	5179	TRUE	29.2	124
NP-2	7/19/1991	32.95807	107.49674	266619	3649215	13	5179	TRUE	60.9	180.8
NP-2	8/29/1991	32.95807	107.49674	266619	3649215	13	5179	FALSE	62.8	197.6
NP-2	10/26/1991	32.95807	107.49674	266619	3649215	13	5179	FALSE	63	170
NP-2	3/15/1992	32.95807	107.49674	266619	3649215	13	5179	FALSE	67.6	194.2
NP-2	5/25/1992	32.95807	107.49674	266619	3649215	13	5179	FALSE	66.6	161.7
NP-2	7/16/1992	32.95807	107.49674	266619	3649215	13	5179	FALSE	65.3	183.7
NP-2	10/8/1992	32.95807	107.49674	266619	3649215	13	5179	FALSE	78.2	178.9
NP-2	11/27/1992	32.95807	107.49674	266619	3649215	13	5179	FALSE	63.7	179.4
NP-2	12/15/1992	32.95807	107.49674	266619	3649215	13	5179	FALSE	82.5	166.8
NP-2	2/25/1993	32.95807	107.49674	266619	3649215	13	5179	FALSE	77.8	197.2
NP-2	3/30/1993	32.95807	107.49674	266619	3649215	13	5179	FALSE	239	436
NP-2	9/28/1993	32.95807	107.49674	266619	3649215	13	5179	FALSE	207	299.9
NP-2	3/17/1994	32.95807	107.49674	266619	3649215	13	5179	FALSE	118.2	300.5
NP-2	5/24/1994	32.95807	107.49674	266619	3649215	13	5179	FALSE	130	300
NP-2	6/23/1994	32.95807	107.49674	266619	3649215	13	5179	FALSE	124.3	267.5
NP-2	7/22/1994	32.95807	107.49674	266619	3649215	13	5179	TRUE	128	299
NP-2	9/22/1994	32.95807	107.49674	266619	3649215	13	5179	FALSE	123.8	252.7
NP-2	1/29/1995	32.95807	107.49674	266619	3649215	13	5179	FALSE	94.1	120.9
NP-2	3/29/1995	32.95807	107.49674	266619	3649215	13	5179	FALSE	90.7	228.7
NP-2	6/27/1995	32.95807	107.49674	266619	3649215	13	5179	FALSE	95.9	247.1
NP-2	9/21/1995	32.95807	107.49674	266619	3649215	13	5179	FALSE	86.6	211.8
NP-2	1/10/1996	32.95807	107.49674	266619	3649215	13	5179	FALSE	78.6	173.1
NP-2	4/3/1996	32.95807	107.49674	266619	3649215	13	5179	FALSE	76.8	168.7
NP-2	6/1/1996	32.95807	107.49674	266619	3649215	13	5179		74.4	181
NP-2	9/25/1996	32.95807	107.49674	266619	3649215	13	5179	TRUE	57.2	118
NP-2	1/15/1997	32.95807	107.49674	266619	3649215	13	5179	TRUE	56	148.4
NP-2	7/1/1997	32.95807	107.49674	266619	3649215	13	5179	TRUE	55.8	121
NP-2	10/1/1997	32.95807	107.49674	266619	3649215	13	5179	TRUE	55	127
NP-2	1/15/1998	32.95807	107.49674	266619	3649215	13	5179	TRUE	59	121
NP-2	4/9/1998	32.95807	107.49674	266619	3649215	13	5179	TRUE	61.8	122
NP-2	7/13/1998	32.95807	107.49674	266619	3649215	13	5179	TRUE	64.6	120

Well Name	Sample Date	pH	TDS	Alkalinity	Bicarb	Spec.Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
NP-2	7/26/1982										
NP-2	8/18/1982										
NP-2	9/2/1982	7.4	468		316	650	0.54	1.66			
NP-2	9/14/1982										
NP-2	10/18/1982										
NP-2	10/27/1982	7.9	440				0.6	1.6			
NP-2	11/11/1982										
NP-2	12/28/1982										
NP-2	2/21/1983	7.8	440				0.6	1.6			
NP-2	5/6/1983										
NP-2	5/13/1983	8.1	460				0.6	1.5			
NP-2	6/2/1983										
NP-2	7/5/1983										
NP-2	8/9/1983	7.9	560				0.6	1.6			
NP-2	8/25/1983										
NP-2	10/20/1983										
NP-2	11/1/1983	8	470				0.6	2.3			
NP-2	12/7/1983										
NP-2	1/28/1984										
NP-2	2/13/1984										
NP-2	3/84										
NP-2	3/16/1984	8.2	500				0.8	1.6			
NP-2	4/18/1984										
NP-2	5/22/1984										
NP-2	5/30/1984	7.7	520				0.6	1.4			
NP-2	6/26/1984										
NP-2	7/25/1984										
NP-2	8/27/1984										
NP-2	9/12/1984	7.8	470				0.6	1.7			
NP-2	9/21/1984										
NP-2	11/19/1984										
NP-2	12/27/1984	7.9	470				0.6	1.7			
NP-2	12/17/1984										
NP-2	5/17/1985	7.8	480								
NP-2	11/13/1985	7.4	460								
NP-2	5/23/1986	7.6	480								

Well Name	Sample Date	pH	TDS	Alkalinity	Bicarb	Spec.Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
NP-2	10/8/1986	7.4	430								
NP-2	3/30/1989		376		183				-0.1		
NP-2	7/19/1991	7.55	453	46	56.1	726	0.64	0.02			-0.002
NP-2	8/29/1991	8.11	471								
NP-2	10/26/1991	7.45	460								
NP-2	3/15/1992	8.07	467								
NP-2	5/25/1992	8.34	456								
NP-2	7/16/1992	8.13	479								
NP-2	10/8/1992	8.26	494								
NP-2	11/27/1992	8.38	451								
NP-2	12/15/1992	8.43	612								
NP-2	2/25/1993	8.62	475								
NP-2	3/30/1993	7.7	1310		289	1910	1.33	3.3	0.5		-0.005
NP-2	9/28/1993	7.92	1170								
NP-2	3/17/1994	7.65	971								
NP-2	5/24/1994	8.03	878		261	1250	0.97	-0.1	4.6	-0.005	-0.005
NP-2	6/23/1994	7.69	848								
NP-2	7/22/1994	7.88	878		270	1360	0.94	1.5	-0.05	0.0059	-0.005
NP-2	9/22/1994	7.55	963								
NP-2	1/29/1995	7.57	791								
NP-2	3/29/1995	7.69	1164								
NP-2	6/27/1995	7.93	778								
NP-2	9/21/1995	7.36	772								
NP-2	1/10/1996	7.1	632								
NP-2	4/3/1996	7.23	603								
NP-2	6/1/1996	6.91	642								
NP-2	9/25/1996	7.68	598								
NP-2	1/15/1997	7.44	536								
NP-2	7/1/1997	7.41	496								
NP-2	10/1/1997	7.49	489								
NP-2	1/15/1998	7.54	486			853	0.61	1.8			
NP-2	4/9/1998		536			802	0.56	1.9			
NP-2	7/13/1998		500			795	0.62	1.5			

Well Name	Sample Date	Boron	Barium	Berylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
NP-2	7/26/1982										
NP-2	8/18/1982										
NP-2	9/2/1982				-0.001	73.8					
NP-2	9/14/1982										
NP-2	10/18/1982										
NP-2	10/27/1982				-0.005				-0.05	0.29	
NP-2	11/11/1982										
NP-2	12/28/1982										
NP-2	2/21/1983				-0.005				-0.05	0.12	
NP-2	5/6/1983										
NP-2	5/13/1983				-0.005				-0.05	-0.1	
NP-2	6/2/1983										
NP-2	7/5/1983										
NP-2	8/9/1983				-0.005				-0.05	-0.1	
NP-2	8/25/1983										
NP-2	10/20/1983										
NP-2	11/1/1983				-0.005				-0.05	0.17	
NP-2	12/7/1983										
NP-2	1/28/1984										
NP-2	2/13/1984										
NP-2	3/84										
NP-2	3/16/1984				-0.005				-0.05	-0.1	
NP-2	4/18/1984										
NP-2	5/22/1984										
NP-2	5/30/1984				-0.005				-0.05	-0.1	
NP-2	6/26/1984										
NP-2	7/25/1984										
NP-2	8/27/1984										
NP-2	9/12/1984				-0.005				-0.05	-0.1	
NP-2	9/21/1984										
NP-2	11/19/1984										
NP-2	12/27/1984				-0.005				-0.05	-0.1	
NP-2	12/17/1984										
NP-2	5/17/1985										
NP-2	11/13/1985										
NP-2	5/23/1986										

Well Name	Sample Date	Boron	Barium	Berylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
NP-2	10/8/1986										
NP-2	3/30/1989	-0.1	-0.1	-0.1	-0.1	52	-0.1	-0.05	-0.1	-0.1	-0.1
NP-2	7/19/1991		-0.01		-0.005	34.2	-0.02		-0.02	-0.05	-0.005
NP-2	8/29/1991										
NP-2	10/26/1991										
NP-2	3/15/1992									-0.05	
NP-2	5/25/1992									-0.05	
NP-2	7/16/1992									-0.05	
NP-2	10/8/1992										
NP-2	11/27/1992										
NP-2	12/15/1992									-0.05	
NP-2	2/25/1993										
NP-2	3/30/1993	0.1	0.6		-0.002	163	-0.02	-0.05	0.01	1.85	-0.02
NP-2	9/28/1993										
NP-2	3/17/1994										
NP-2	5/24/1994		-0.1		0.00097	120	-0.025		-0.025	4.5	0.0079
NP-2	6/23/1994										
NP-2	7/22/1994	-0.1	-0.1	-0.002	-0.0005	120	-0.025	-0.05	-0.025	-0.05	-0.005
NP-2	9/22/1994										
NP-2	1/29/1995										
NP-2	3/29/1995										
NP-2	6/27/1995										
NP-2	9/21/1995										
NP-2	1/10/1996										
NP-2	4/3/1996										
NP-2	6/1/1996										
NP-2	9/25/1996										
NP-2	1/15/1997										
NP-2	7/1/1997										
NP-2	10/1/1997										
NP-2	1/15/1998								-0.005	0.25	
NP-2	4/9/1998								0.005	0.24	
NP-2	7/13/1998								-0.005	0.11	

Well Name	Sample Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium	Thallium
NP-2	7/26/1982										
NP-2	8/18/1982										
NP-2	9/2/1982	17.9	-0.05		-0.01		1.95	-0.005		57.5	
NP-2	9/14/1982										
NP-2	10/18/1982										
NP-2	10/27/1982		-0.05	-0.001	-0.05			-0.005			
NP-2	11/11/1982										
NP-2	12/28/1982										
NP-2	2/21/1983		-0.05	-0.001	-0.05			-0.005			
NP-2	5/6/1983										
NP-2	5/13/1983		-0.05	-0.001	-0.05			-0.005			
NP-2	6/2/1983										
NP-2	7/5/1983										
NP-2	8/9/1983		-0.05	-0.001	-0.05			-0.005			
NP-2	8/25/1983										
NP-2	10/20/1983										
NP-2	11/1/1983		-0.05	-0.001	-0.05			-0.005			
NP-2	12/7/1983										
NP-2	1/28/1984										
NP-2	2/13/1984										
NP-2	3/84										
NP-2	3/16/1984		-0.05	-0.001	-0.05			-0.005			
NP-2	4/18/1984										
NP-2	5/22/1984										
NP-2	5/30/1984		-0.05	-0.001	-0.05			-0.005			
NP-2	6/26/1984										
NP-2	7/25/1984										
NP-2	8/27/1984										
NP-2	9/12/1984		-0.05	-0.001	-0.05			-0.005			
NP-2	9/21/1984										
NP-2	11/19/1984										
NP-2	12/27/1984		-0.05	-0.001	-0.05			-0.005			
NP-2	12/17/1984										
NP-2	5/17/1985										
NP-2	11/13/1985										
NP-2	5/23/1986										

Well Name	Sample Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium	Thallium
NP-2	10/8/1986										
NP-2	3/30/1989	18	0.06		-0.1	-0.1	3		-0.1	65	
NP-2	7/19/1991	24	-0.02	-0.0002			0.8	0.018	-0.02	47.8	
NP-2	8/29/1991										
NP-2	10/26/1991										
NP-2	3/15/1992										
NP-2	5/25/1992										
NP-2	7/16/1992										
NP-2	10/8/1992										
NP-2	11/27/1992										
NP-2	12/15/1992										
NP-2	2/25/1993										
NP-2	3/30/1993	61	0.07	-0.001	-0.02	-0.01	0.9	0.005	-0.01	163	
NP-2	9/28/1993										
NP-2	3/17/1994										
NP-2	5/24/1994	47	0.19	-0.001		-0.05	2.3	-0.005	-0.025	100	
NP-2	6/23/1994										
NP-2	7/22/1994	43	-0.03	-0.001	-0.05	-0.05	1.3	-0.005	-0.025	120	-0.005
NP-2	9/22/1994										
NP-2	1/29/1995										
NP-2	3/29/1995										
NP-2	6/27/1995										
NP-2	9/21/1995										
NP-2	1/10/1996										
NP-2	4/3/1996										
NP-2	6/1/1996										
NP-2	9/25/1996										
NP-2	1/15/1997										
NP-2	7/1/1997										
NP-2	10/1/1997										
NP-2	1/15/1998	20.4		-0.0002	-0.05			-0.05			
NP-2	4/9/1998		-0.02	-0.0002	-0.05			-0.05			
NP-2	7/13/1998		0.05	0.0005	-0.05			-0.05			

Well Name	Sample Date	Zinc	Temp (C)	Tin	Vanadium
NP-2	7/26/1982				
NP-2	8/18/1982				
NP-2	9/2/1982		22		
NP-2	9/14/1982				
NP-2	10/18/1982				
NP-2	10/27/1982				
NP-2	11/11/1982				
NP-2	12/28/1982				
NP-2	2/21/1983				
NP-2	5/6/1983				
NP-2	5/13/1983				
NP-2	6/2/1983				
NP-2	7/5/1983				
NP-2	8/9/1983				
NP-2	8/25/1983				
NP-2	10/20/1983				
NP-2	11/1/1983				
NP-2	12/7/1983				
NP-2	1/28/1984				
NP-2	2/13/1984				
NP-2	3/84				
NP-2	3/16/1984				
NP-2	4/18/1984				
NP-2	5/22/1984				
NP-2	5/30/1984				
NP-2	6/26/1984				
NP-2	7/25/1984				
NP-2	8/27/1984				
NP-2	9/12/1984				
NP-2	9/21/1984				
NP-2	11/19/1984				
NP-2	12/27/1984				
NP-2	12/17/1984				
NP-2	5/17/1985				
NP-2	11/13/1985				
NP-2	5/23/1986				

Well Name	Sample Date	Zinc	Temp (C)	Tin	Vanadium
NP-2	10/8/1986				
NP-2	3/30/1989	0.5		-0.1	-0.1
NP-2	7/19/1991				
NP-2	8/29/1991				
NP-2	10/26/1991				
NP-2	3/15/1992				
NP-2	5/25/1992				
NP-2	7/16/1992				
NP-2	10/8/1992				
NP-2	11/27/1992				
NP-2	12/15/1992				
NP-2	2/25/1993				
NP-2	3/30/1993	0.67			
NP-2	9/28/1993				
NP-2	3/17/1994				
NP-2	5/24/1994	4.1			
NP-2	6/23/1994				
NP-2	7/22/1994	1.2			
NP-2	9/22/1994				
NP-2	1/29/1995				
NP-2	3/29/1995				
NP-2	6/27/1995				
NP-2	9/21/1995				
NP-2	1/10/1996				
NP-2	4/3/1996				
NP-2	6/1/1996				
NP-2	9/25/1996				
NP-2	1/15/1997				
NP-2	7/1/1997				
NP-2	10/1/1997				
NP-2	1/15/1998				
NP-2	4/9/1998				
NP-2	7/13/1998				

Well Name	Water Depth	USGS Quad	Well Depth	sample ID	Date	Sampler	Notes
NP-3	73.45	Skute Stone Arroyo	-1	NP-3-1	10/8/1981	QMC	
NP-3		Skute Stone Arroyo	-2	NP-3-2	10/27/1981	QMC	
NP-3		Skute Stone Arroyo	-3	NP-3-3	10/30/1981		
NP-3	71.58	Skute Stone Arroyo	-4	NP-3-4	11/6/1981	QMC	
NP-3	71.58	Skute Stone Arroyo	-5	NP-3-5	11/12/1981	QMC	
NP-3	71.4	Skute Stone Arroyo	-6	NP-3-6	11/13/1981	EID	
NP-3	69	Skute Stone Arroyo	-7	NP-3-7	11/17/1981	QMC	
NP-3	69.85	Skute Stone Arroyo	-8	NP-3-8	11/23/1981	QMC	
NP-3	70.1	Skute Stone Arroyo	-9	NP-3-9	12/7/1981	QMC	
NP-3	68.67	Skute Stone Arroyo	-10	NP-3-10	12/15/1981	QMC	
NP-3	77.67	Skute Stone Arroyo	-11	NP-3-11	12/22/1981	QMC	
NP-3		Skute Stone Arroyo	-12	NP-3-12	1/5/1982	QMC	
NP-3	66.17	Skute Stone Arroyo	-13	NP-3-13	1/18/1982	QMC	
NP-3	66.16	Skute Stone Arroyo	-14	NP-3-14	1/26/1982	QMC	
NP-3	64.67	Skute Stone Arroyo	-15	NP-3-15	2/16/1982	QMC	
NP-3	64.62	Skute Stone Arroyo	-16	NP-3-16	2/22/1982	QMC	
NP-3	63.42	Skute Stone Arroyo	-17	NP-3-17	3/12/1982	QMC	
NP-3	57.67	Skute Stone Arroyo	-18	NP-3-18	4/16/1982	QMC	
NP-3	57.5	Skute Stone Arroyo	-19	NP-3-19	4/26/1982	QMC	
NP-3	5.75	Skute Stone Arroyo	-20	NP-3-20	5/17/1982	QMC	
NP-3		Skute Stone Arroyo	-21	NP-3-21	5/24/1982	QMC	
NP-3		Skute Stone Arroyo	-22	NP-3-22	5/28/1982	QMC	
NP-3	0	Skute Stone Arroyo	-23	NP-3-23	6/8/1982	QMC	
NP-3	0	Skute Stone Arroyo	-24	NP-3-24	6/14/1982	QMC	
NP-3	0	Skute Stone Arroyo	-25	NP-3-25	6/30/1982	QMC	
NP-3	0	Skute Stone Arroyo	-26	NP-3-26	7/26/1982	QMC	
NP-3	0	Skute Stone Arroyo	-27	NP-3-27	8/18/1982	QMC	
NP-3	0	Skute Stone Arroyo	-28	NP-3-28	9/2/1982	EID	
NP-3	0	Skute Stone Arroyo	-29	NP-3-29	9/14/1982	QMC	
NP-3	0.8	Skute Stone Arroyo	-30	NP-3-30	10/18/1982	QMC	
NP-3	0.8	Skute Stone Arroyo	-31	NP-3-31	10/27/1982	QMC	
NP-3	2.7	Skute Stone Arroyo	-32	NP-3-32	11/11/1982	QMC	
NP-3	6.6	Skute Stone Arroyo	-33	NP-3-33	12/28/1982	QMC	
NP-3	9.2	Skute Stone Arroyo	-34	NP-3-34	2/21/1983	QMC	
NP-3	14.4	Skute Stone Arroyo	-35	NP-3-35	5/6/1983	QMC	
NP-3	14.4	Skute Stone Arroyo	-36	NP-3-36	5/13/1983	QMC	

Well Name	Water Depth	USGS Quad	Well Depth		sample ID	Date	Sampler	Notes
NP-3	15.7	Skute Stone Arroyo		-37	NP-3-37	6/2/1983	QMC	
NP-3	17	Skute Stone Arroyo		-38	NP-3-38	7/5/1983	QMC	
NP-3	19.1	Skute Stone Arroyo		-39	NP-3-39	8/9/1983	QMC	
NP-3	19.1	Skute Stone Arroyo		-40	NP-3-40	8/25/1983	QMC	
NP-3	21.5	Skute Stone Arroyo		-41	NP-3-41	10/20/1983	QMC	
NP-3	21.5	Skute Stone Arroyo		-42	NP-3-42	11/1/1983	QMC	
NP-3	22.7	Skute Stone Arroyo		-43	NP-3-43	12/7/1983	QMC	
NP-3	22.5	Skute Stone Arroyo		-44	NP-3-44	1/28/1984	QMC	
NP-3	22.5	Skute Stone Arroyo		-45	NP-3-45	2/13/1984	QMC	
NP-3	22.4	Skute Stone Arroyo		-46	NP-3-46	3/1/1984	QMC	
NP-3	22.4	Skute Stone Arroyo		-47	NP-3-47	3/16/1984	CFP	
NP-3	22.4	Skute Stone Arroyo		-48	NP-3-48	4/18/1984	CFP	
NP-3	22.4	Skute Stone Arroyo		-49	NP-3-49	5/22/1984	CFP	
NP-3	22.4	Skute Stone Arroyo		-50	NP-3-50	5/30/1984	CFP	
NP-3	22.8	Skute Stone Arroyo		-51	NP-3-51	6/26/1984	CFP	
NP-3	22.9	Skute Stone Arroyo		-52	NP-3-52	7/25/1984	CFP	
NP-3	22.9	Skute Stone Arroyo		-53	NP-3-53	8/27/1984	CFP	
NP-3	22.4	Skute Stone Arroyo		-54	NP-3-54	9/12/1984	CFP	
NP-3	22.4	Skute Stone Arroyo		-55	NP-3-55	9/21/1984	CFP	
NP-3	22.6	Skute Stone Arroyo		-56	NP-3-56	11/19/1984	CFP	
NP-3	22.6	Skute Stone Arroyo		-57	NP-3-57	11/27/1984	CFP	
NP-3	22.5	Skute Stone Arroyo		-58	NP-3-58	12/17/1984	CFP	
NP-3	22.4	Skute Stone Arroyo		-59	NP-3-59	5/17/1985	CFP	
NP-3	12.5	Skute Stone Arroyo		-60	NP-3-60	11/13/1985	CFP	
NP-3	11.1	Skute Stone Arroyo		-61	NP-3-61	5/23/1986	CFP	
NP-3	10.9	Skute Stone Arroyo		-62	NP-3-62	10/8/1986	CFP	
NP-3	5.12	Skute Stone Arroyo		-63	NP-3-63	3/3/1987		
NP-3	5.12	Skute Stone Arroyo		-64	NP-3-64	3/4/1987	EID	
NP-3		Skute Stone Arroyo		-65	NP-3-65	5/25/1987		
NP-3	6.5	Skute Stone Arroyo		-66	NP-3-66	1/12/1988	EID	
NP-3		Skute Stone Arroyo		-67	NP-3-67	4/4/1988	Irwin	lab pH
NP-3	7.58	Skute Stone Arroyo		-68	NP-3-68	8/23/1988	Irwin	lab pH
NP-3	6.5	Skute Stone Arroyo		-69	NP-3-69	2/9/1989	Irwin	lab pH
NP-3	6.8	Skute Stone Arroyo		-70	NP-3-70	6/1/1989	Irwin	lab pH
NP-3	5.66	Skute Stone Arroyo		-71	NP-3-71	11/30/1989	Irwin	lab pH
NP-3	4.9	Skute Stone Arroyo		-72	NP-3-72	11/14/1990	GE	

Well Name	Water Depth	USGS Quad	Well Depth	sample ID	Date	Sampler	Notes
NP-3	10.9	Skute Stone Arroyo	-73	NP-3-73	2/11/1991	SHB	
NP-3	30.3	Skute Stone Arroyo	-74	NP-3-74	7/19/1991	GE	Lab NP-2-mixed w/
NP-3	3.92	Skute Stone Arroyo	-75	NP-3-75	8/29/1991	Irwin	lab pH
NP-3	3.67	Skute Stone Arroyo	-76	NP-3-76	11/26/1991	Hood	lab pH
NP-3	3.42	Skute Stone Arroyo	-77	NP-3-77	3/15/1992	Irwin	lab pH
NP-3		Skute Stone Arroyo	-78	NP-3-78	5/25/1992	Irwin	lab pH
NP-3		Skute Stone Arroyo	-79	NP-3-79	7/16/1992	Irwin	lab pH
NP-3	2.42	Skute Stone Arroyo	-80	NP-3-80	10/8/1992	Irwin	lab pH
NP-3	3.58	Skute Stone Arroyo	-81	NP-3-81	11/27/1992	Hood	lab pH
NP-3		Skute Stone Arroyo	-82	NP-3-82	12/15/1992	Irwin	lab pH
NP-3	3.58	Skute Stone Arroyo	-83	NP-3-83	2/25/1993	Irwin	lab pH
NP-3		Skute Stone Arroyo	-84	NP-3-84	3/30/1993	JWS	
NP-3		Skute Stone Arroyo	-85	NP-3-85	9/28/1993	Irwin	lab pH
NP-3	3.56	Skute Stone Arroyo	-86	NP-3-86	3/17/1994	Irwin	lab pH
NP-3		Skute Stone Arroyo	-87	NP-3-87	6/23/1994	Irwin	lab pH
NP-3		Skute Stone Arroyo	-88	NP-3-88	7/22/1994	SRK	25 ft of sediment l
NP-3		Skute Stone Arroyo	-89	NP-3-89	9/22/1994	Irwin	lab pH
NP-3		Skute Stone Arroyo	-90	NP-3-90	1/29/1995	Irwin	lab pH
NP-3		Skute Stone Arroyo	-91	NP-3-91	3/29/1995	Irwin	lab pH
NP-3	7.58	Skute Stone Arroyo	-92	NP-3-92	6/27/1995	Irwin	lab pH
NP-3		Skute Stone Arroyo	-93	NP-3-93	9/21/1995	Irwin	lab pH
NP-3		Skute Stone Arroyo	-94	NP-3-94	1/10/1996	Irwin	lab pH
NP-3		Skute Stone Arroyo	-95	NP-3-95	4/3/1996	Irwin	lab pH
NP-3		Skute Stone Arroyo	-96	NP-3-96	6/1/1996		
NP-3		Skute Stone Arroyo	-97	NP-3-97	9/25/1996	Irwin	lab pH
NP-3		Skute Stone Arroyo	-98	NP-3-98	1/15/1997	Irwin	lab pH
NP-3		Skute Stone Arroyo	-99	NP-3-99	7/1/1997		
NP-3		Skute Stone Arroyo	-100	NP-3-100	10/1/1997		
NP-3	10.5	Skute Stone Arroyo	-101	NP-3-101	1/15/1998	Irwin	
NP-3	10.35	Skute Stone Arroyo	-102	NP-3-102	4/9/1998	Irwin	
NP-3	10.5	Skute Stone Arroyo	-103	NP-3-103	7/13/1998	Irwin	
NP-4	82.25	Skute Stone Arroyo	-1	NP-4-1	4/16/1982	QMC	
NP-4	82.2	Skute Stone Arroyo	-2	NP-4-2	4/26/1982	QMC	
NP-4	68.5	Skute Stone Arroyo	-3	NP-4-3	5/17/1982	QMC	
NP-4		Skute Stone Arroyo	-4	NP-4-4	5/24/1982	QMC	
NP-4		Skute Stone Arroyo	-5	NP-4-5	5/28/1982	QMC	

Well Name	Water Depth	USGS Quad	Well Depth	sample ID	Date	Sampler	Notes
NP-4	42.5	Skute Stone Arroyo	-6	NP-4-6	6/8/1982	QMC	
NP-4	42.5	Skute Stone Arroyo	-7	NP-4-7	6/14/1982	QMC	
NP-4		Skute Stone Arroyo	-8	NP-4-8	6/30/1982	QMC	
NP-4	31.62	Skute Stone Arroyo	-9	NP-4-9	7/26/1982	QMC	
NP-4	31.3	Skute Stone Arroyo	-10	NP-4-10	8/18/1982	QMC	
NP-4	31.2	Skute Stone Arroyo	-11	NP-4-11	9/2/1982	EID	
NP-4	31.1	Skute Stone Arroyo	-12	NP-4-12	9/14/1982	QMC	
NP-4	31.6	Skute Stone Arroyo	-13	NP-4-13	10/18/1982	QMC	
NP-4	31.6	Skute Stone Arroyo	-14	NP-4-14	10/27/1982	QMC	
NP-4	33.1	Skute Stone Arroyo	-15	NP-4-15	11/11/1982	QMC	
NP-4	35.1	Skute Stone Arroyo	-16	NP-4-16	12/28/1982	QMC	
NP-4	38.9	Skute Stone Arroyo	-17	NP-4-17	2/21/1983	QMC	
NP-4	39.7	Skute Stone Arroyo	-18	NP-4-18	5/6/1983	QMC	
NP-4	39.7	Skute Stone Arroyo	-19	NP-4-19	5/13/1983	QMC	
NP-4	40.6	Skute Stone Arroyo	-20	NP-4-20	6/2/1983	QMC	
NP-4	41.8	Skute Stone Arroyo	-21	NP-4-21	7/5/1983	QMC	
NP-4	43.7	Skute Stone Arroyo	-22	NP-4-22	8/9/1983	QMC	
NP-4	43.7	Skute Stone Arroyo	-23	NP-4-23	8/25/1983	QMC	
NP-4	45.2	Skute Stone Arroyo	-24	NP-4-24	10/20/1983	QMC	
NP-4	45.2	Skute Stone Arroyo	-25	NP-4-25	11/1/1983	QMC	
NP-4	48.4	Skute Stone Arroyo	-26	NP-4-26	12/7/1983	QMC	
NP-4	47.1	Skute Stone Arroyo	-27	NP-4-27	1/28/1984	QMC	
NP-4	46.8	Skute Stone Arroyo	-28	NP-4-28	2/13/1984	QMC	
NP-4	46.6	Skute Stone Arroyo	-29	NP-4-29	3/1/1984	QMC	
NP-4	46.6	Skute Stone Arroyo	-30	NP-4-30	3/16/1984	CFP	
NP-4	46.7	Skute Stone Arroyo	-31	NP-4-31	4/18/1984	CFP	
NP-4	44.9	Skute Stone Arroyo	-32	NP-4-32	5/22/1984	CFP	
NP-4	44.9	Skute Stone Arroyo	-33	NP-4-33	5/30/1984	CFP	
NP-4	44.6	Skute Stone Arroyo	-34	NP-4-34	6/26/1984	CFP	
NP-4	44.3	Skute Stone Arroyo	-35	NP-4-35	7/25/1984	CFP	
NP-4	44.1	Skute Stone Arroyo	-36	NP-4-36	8/27/1984	CFP	
NP-4	43.8	Skute Stone Arroyo	-37	NP-4-37	9/12/1984	CFP	
NP-4	43.8	Skute Stone Arroyo	-38	NP-4-38	9/21/1984	CFP	
NP-4	43.1	Skute Stone Arroyo	-39	NP-4-39	11/19/1984	CFP	
NP-4	42.1	Skute Stone Arroyo	-40	NP-4-40	11/27/1984	CFP	
NP-4	42.9	Skute Stone Arroyo	-41	NP-4-41	12/17/1984	CFP	

Well Name	Water Depth	USGS Quad	Well Depth		sample ID	Date	Sampler	Notes
NP-4	42.7	Skute Stone Arroyo		-42	NP-4-42	5/17/1985	CFP	
NP-4	37.3	Skute Stone Arroyo		-43	NP-4-43	11/13/1985	CFP	
NP-4	34.4	Skute Stone Arroyo		-44	NP-4-44	5/23/1986	CFP	
NP-4	34.5	Skute Stone Arroyo		-45	NP-4-45	10/8/1986	CFP	
NP-4		Skute Stone Arroyo		-46	NP-4-46	5/25/1987		
NP-4	29.8	Skute Stone Arroyo		-47	NP-4-47	1/12/1988	EID	
NP-4		Skute Stone Arroyo		-48	NP-4-48	4/4/1988	Irwin	lab pH
NP-4	29.33	Skute Stone Arroyo		-49	NP-4-49	8/23/1988	Irwin	lab pH
NP-4	29.25	Skute Stone Arroyo		-50	NP-4-50	2/9/1989	Irwin	lab pH
NP-4	27.3	Skute Stone Arroyo		-51	NP-4-51	6/1/1989	Irwin	lab pH
NP-4	29.2	Skute Stone Arroyo		-52	NP-4-52	11/30/1989	Irwin	lab pH
NP-4	29.75	Skute Stone Arroyo		-53	NP-4-53	11/14/1990		
NP-4		Skute Stone Arroyo		-54	NP-4-54	2/11/1991		
NP-4		Skute Stone Arroyo		-55	NP-4-55	7/19/1991	GE	lab pH
NP-4	27.5	Skute Stone Arroyo		-56	NP-4-56	8/29/1991	Irwin	lab pH
NP-4	27	Skute Stone Arroyo		-57	NP-4-57	11/26/1991	Hood	lab pH
NP-4	26.42	Skute Stone Arroyo		-58	NP-4-58	3/15/1992	Irwin	lab pH
NP-4		Skute Stone Arroyo		-59	NP-4-59	5/25/1992	Irwin	lab pH
NP-4		Skute Stone Arroyo		-60	NP-4-60	7/16/1992	Irwin	lab pH
NP-4	26	Skute Stone Arroyo		-61	NP-4-61	10/8/1992	Irwin	lab pH
NP-4	26.92	Skute Stone Arroyo		-62	NP-4-62	11/27/1992	Hood	lab pH
NP-4		Skute Stone Arroyo		-63	NP-4-63	12/15/1992	Irwin	lab pH
NP-4	27.08	Skute Stone Arroyo		-64	NP-4-64	2/25/1993	Irwin	lab pH
NP-4		Skute Stone Arroyo		-65	NP-4-65	3/31/1993	JWS	
NP-4		Skute Stone Arroyo		-66	NP-4-66	9/28/1993	Irwin	lab pH
NP-4	27.85	Skute Stone Arroyo		-67	NP-4-67	5/26/1994	SRK	
NP-4		Skute Stone Arroyo		-68	NP-4-68	6/23/1994	Irwin	lab pH
NP-4		Skute Stone Arroyo		-69	NP-4-69	7/23/1994	SRK	
NP-4		Skute Stone Arroyo		-70	NP-4-70	9/22/1994	Irwin	lab pH
NP-4		Skute Stone Arroyo		-71	NP-4-71	1/29/1995	Irwin	lab pH
NP-4		Skute Stone Arroyo		-72	NP-4-72	3/29/1995	Irwin	lab pH
NP-4	30.75	Skute Stone Arroyo		-73	NP-4-73	6/27/1995	Irwin	lab pH
NP-4		Skute Stone Arroyo		-74	NP-4-74	9/21/1995	Irwin	lab pH
NP-4		Skute Stone Arroyo		-75	NP-4-75	1/10/1996	Irwin	lab pH
NP-4		Skute Stone Arroyo		-76	NP-4-76	4/3/1996	Irwin	lab pH
NP-4		Skute Stone Arroyo		-77	NP-4-77	6/1/1996		

Well Name	Water Depth	USGS Quad	Well Depth		sample ID	Date	Sampler	Notes
NP-4		Skute Stone Arroyo		-78	NP-4-78	9/25/1996	Irwin	lab pH
NP-4		Skute Stone Arroyo		-79	NP-4-79	1/15/1997	Irwin	lab pH
NP-4		Skute Stone Arroyo		-80	NP-4-80	7/1/1997		
NP-4		Skute Stone Arroyo		-81	NP-4-81	10/1/1997		
NP-4	33.3	Skute Stone Arroyo		-82	NP-4-82	1/15/1998	Irwin	
NP-4		Skute Stone Arroyo		-83	NP-4-83	1/24/1998	Goff	
NP-4	33.75	Skute Stone Arroyo		-84	NP-4-84	4/9/1998	Irwin	
NP-4	33.75	Skute Stone Arroyo		-85	NP-4-85	7/13/1998	Irwin	
NP-4		Skute Stone Arroyo		-86	NP-4-86	7/21/1998	Brownfield	
NP-5	37.56	Skute Stone Arroyo		-1	NP-5-1	11/4/1981	QMC	
NP-5	34.83	Skute Stone Arroyo		-2	NP-5-2	11/11/1981	QMC	
NP-5	37.49	Skute Stone Arroyo		-3	NP-5-3	11/13/1981	EID	
NP-5	34.83	Skute Stone Arroyo		-4	NP-5-4	11/17/1981	QMC	
NP-5	33	Skute Stone Arroyo		-5	NP-5-5	11/23/1981	QMC	
NP-5	37.56	Skute Stone Arroyo		-6	NP-5-6	12/7/1981	QMC	

Well Name	Date	Latitude	Longitude	UTM_easting	UTM_northing	UTM_zone	Elevation	Filtered?	Chloride	Sulfate
NP-3	10/8/1981	32.96126	107.49678	266624	3649569	13	5200	TRUE	28.6	94.5
NP-3	10/27/1981	32.96126	107.49678	266624	3649569	13	5200	TRUE	28	148
NP-3	10/30/1981	32.96126	107.49678	266624	3649569	13	5200	FALSE	31.2	102
NP-3	11/6/1981	32.96126	107.49678	266624	3649569	13	5200	TRUE	28	140
NP-3	11/12/1981	32.96126	107.49678	266624	3649569	13	5200	FALSE		
NP-3	11/13/1981	32.96126	107.49678	266624	3649569	13	5200	TRUE	26.71	140.6
NP-3	11/17/1981	32.96126	107.49678	266624	3649569	13	5200	TRUE	26	144
NP-3	11/23/1981	32.96126	107.49678	266624	3649569	13	5200	TRUE	26	144
NP-3	12/7/1981	32.96126	107.49678	266624	3649569	13	5200	TRUE	28	153
NP-3	12/15/1981	32.96126	107.49678	266624	3649569	13	5200	TRUE	26	149
NP-3	12/22/1981	32.96126	107.49678	266624	3649569	13	5200	TRUE	26	149
NP-3	1/5/1982	32.96126	107.49678	266624	3649569	13	5200	TRUE	26	154
NP-3	1/18/1982	32.96126	107.49678	266624	3649569	13	5200	FALSE		
NP-3	1/26/1982	32.96126	107.49678	266624	3649569	13	5200	TRUE	30	151
NP-3	2/16/1982	32.96126	107.49678	266624	3649569	13	5200	FALSE		
NP-3	2/22/1982	32.96126	107.49678	266624	3649569	13	5200	TRUE	28	137
NP-3	3/12/1982	32.96126	107.49678	266624	3649569	13	5200	FALSE		
NP-3	4/16/1982	32.96126	107.49678	266624	3649569	13	5200	FALSE		
NP-3	4/26/1982	32.96126	107.49678	266624	3649569	13	5200	TRUE	28	146
NP-3	5/17/1982	32.96126	107.49678	266624	3649569	13	5200	TRUE	562	900
NP-3	5/24/1982	32.96126	107.49678	266624	3649569	13	5200	TRUE		
NP-3	5/28/1982	32.96126	107.49678	266624	3649569	13	5200	TRUE		
NP-3	6/8/1982	32.96126	107.49678	266624	3649569	13	5200	TRUE	30	150
NP-3	6/14/1982	32.96126	107.49678	266624	3649569	13	5200	FALSE		
NP-3	6/30/1982	32.96126	107.49678	266624	3649569	13	5200	TRUE	26	128
NP-3	7/26/1982	32.96126	107.49678	266624	3649569	13	5200	FALSE		
NP-3	8/18/1982	32.96126	107.49678	266624	3649569	13	5200	FALSE		
NP-3	9/2/1982	32.96126	107.49678	266624	3649569	13	5200	TRUE	27.82	123.8
NP-3	9/14/1982	32.96126	107.49678	266624	3649569	13	5200	FALSE		
NP-3	10/18/1982	32.96126	107.49678	266624	3649569	13	5200	FALSE		
NP-3	10/27/1982	32.96126	107.49678	266624	3649569	13	5200	TRUE	26	132
NP-3	11/11/1982	32.96126	107.49678	266624	3649569	13	5200	FALSE		
NP-3	12/28/1982	32.96126	107.49678	266624	3649569	13	5200	FALSE		
NP-3	2/21/1983	32.96126	107.49678	266624	3649569	13	5200	TRUE	26	131
NP-3	5/6/1983	32.96126	107.49678	266624	3649569	13	5200	FALSE		
NP-3	5/13/1983	32.96126	107.49678	266624	3649569	13	5200	TRUE	64	139

Well Name	Date	Latitude	Longitude	UTM_easting	UTM_northing	UTM_zone	Elevation	Filtered?	Chloride	Sulfate
NP-3	6/2/1983	32.96126	107.49678	266624	3649569	13	5200	FALSE		
NP-3	7/5/1983	32.96126	107.49678	266624	3649569	13	5200	FALSE		
NP-3	8/9/1983	32.96126	107.49678	266624	3649569	13	5200	TRUE	114	100
NP-3	8/25/1983	32.96126	107.49678	266624	3649569	13	5200	FALSE		
NP-3	10/20/1983	32.96126	107.49678	266624	3649569	13	5200	FALSE		
NP-3	11/1/1983	32.96126	107.49678	266624	3649569	13	5200	TRUE	162	163
NP-3	12/7/1983	32.96126	107.49678	266624	3649569	13	5200	FALSE		
NP-3	1/28/1984	32.96126	107.49678	266624	3649569	13	5200	FALSE		
NP-3	2/13/1984	32.96126	107.49678	266624	3649569	13	5200	FALSE		
NP-3	3/1/1984	32.96126	107.49678	266624	3649569	13	5200	FALSE		
NP-3	3/16/1984	32.96126	107.49678	266624	3649569	13	5200	TRUE	228	216
NP-3	4/18/1984	32.96126	107.49678	266624	3649569	13	5200	FALSE		
NP-3	5/22/1984	32.96126	107.49678	266624	3649569	13	5200	FALSE		
NP-3	5/30/1984	32.96126	107.49678	266624	3649569	13	5200	TRUE	248	292
NP-3	6/26/1984	32.96126	107.49678	266624	3649569	13	5200	FALSE		
NP-3	7/25/1984	32.96126	107.49678	266624	3649569	13	5200	FALSE		
NP-3	8/27/1984	32.96126	107.49678	266624	3649569	13	5200	FALSE		
NP-3	9/12/1984	32.96126	107.49678	266624	3649569	13	5200	TRUE	270	292
NP-3	9/21/1984	32.96126	107.49678	266624	3649569	13	5200	FALSE		
NP-3	11/19/1984	32.96126	107.49678	266624	3649569	13	5200	FALSE		
NP-3	11/27/1984	32.96126	107.49678	266624	3649569	13	5200	TRUE	290	348
NP-3	12/17/1984	32.96126	107.49678	266624	3649569	13	5200	FALSE		
NP-3	5/17/1985	32.96126	107.49678	266624	3649569	13	5200	FALSE	310	453
NP-3	11/13/1985	32.96126	107.49678	266624	3649569	13	5200	FALSE	288	541
NP-3	5/23/1986	32.96126	107.49678	266624	3649569	13	5200	FALSE	282	624
NP-3	10/8/1986	32.96126	107.49678	266624	3649569	13	5200	FALSE	272	620
NP-3	3/3/1987	32.96126	107.49678	266624	3649569	13	5200	FALSE		695
NP-3	3/4/1987	32.96126	107.49678	266624	3649569	13	5200	TRUE	283	695
NP-3	5/25/1987	32.96126	107.49678	266624	3649569	13	5200	FALSE		735.5
NP-3	1/12/1988	32.96126	107.49678	266624	3649569	13	5200	TRUE	359	755
NP-3	4/4/1988	32.96126	107.49678	266624	3649569	13	5200	FALSE	254	587
NP-3	8/23/1988	32.96126	107.49678	266624	3649569	13	5200	FALSE	251.4	835.2
NP-3	2/9/1989	32.96126	107.49678	266624	3649569	13	5200	FALSE	254.3	763.4
NP-3	6/1/1989	32.96126	107.49678	266624	3649569	13	5200	FALSE	241.1	713.6
NP-3	11/30/1989	32.96126	107.49678	266624	3649569	13	5200	FALSE	158.9	742.9
NP-3	11/14/1990	32.96126	107.49678	266624	3649569	13	5200	FALSE	228.7	821.6

Well Name	Date	Latitude	Longitude	UTM_easting	UTM_northing	UTM_zone	Elevation	Filtered?	Chloride	Sulfate
NP-3	2/11/1991	32.96126	107.49678	266624	3649569	13	5200	FALSE	255.9	970.5
NP-3	7/19/1991	32.96126	107.49678	266624	3649569	13	5200	TRUE	239.2	820.3
NP-3	8/29/1991	32.96126	107.49678	266624	3649569	13	5200	FALSE	254.3	854.1
NP-3	11/26/1991	32.96126	107.49678	266624	3649569	13	5200	FALSE	248.1	745.2
NP-3	3/15/1992	32.96126	107.49678	266624	3649569	13	5200	FALSE	227.8	921.3
NP-3	5/25/1992	32.96126	107.49678	266624	3649569	13	5200	FALSE	216.4	752.9
NP-3	7/16/1992	32.96126	107.49678	266624	3649569	13	5200	FALSE	226.1	802.2
NP-3	10/8/1992	32.96126	107.49678	266624	3649569	13	5200	FALSE	211.6	799.1
NP-3	11/27/1992	32.96126	107.49678	266624	3649569	13	5200	FALSE	254.7	796.1
NP-3	12/15/1992	32.96126	107.49678	266624	3649569	13	5200	FALSE	223.2	545.3
NP-3	2/25/1993	32.96126	107.49678	266624	3649569	13	5200	FALSE	219.3	793.6
NP-3	3/30/1993	32.96126	107.49678	266624	3649569	13	5200	FALSE	205	825
NP-3	9/28/1993	32.96126	107.49678	266624	3649569	13	5200	FALSE	210.3	619.4
NP-3	3/17/1994	32.96126	107.49678	266624	3649569	13	5200	FALSE	169.5	746.9
NP-3	6/23/1994	32.96126	107.49678	266624	3649569	13	5200	FALSE	205.7	778.6
NP-3	7/22/1994	32.96126	107.49678	266624	3649569	13	5200	TRUE	194	796
NP-3	9/22/1994	32.96126	107.49678	266624	3649569	13	5200	FALSE	435.9	1348
NP-3	1/29/1995	32.96126	107.49678	266624	3649569	13	5200	FALSE	566.4	651.9
NP-3	3/29/1995	32.96126	107.49678	266624	3649569	13	5200	FALSE	185.5	558
NP-3	6/27/1995	32.96126	107.49678	266624	3649569	13	5200	FALSE	202.7	717
NP-3	9/21/1995	32.96126	107.49678	266624	3649569	13	5200	FALSE	208.4	822
NP-3	1/10/1996	32.96126	107.49678	266624	3649569	13	5200	FALSE	208.5	724.1
NP-3	4/3/1996	32.96126	107.49678	266624	3649569	13	5200	FALSE	208.3	722.6
NP-3	6/1/1996	32.96126	107.49678	266624	3649569	13	5200		210.6	556.5
NP-3	9/25/1996	32.96126	107.49678	266624	3649569	13	5200	TRUE	190.5	536.5
NP-3	1/15/1997	32.96126	107.49678	266624	3649569	13	5200	TRUE	207	657.4
NP-3	7/1/1997	32.96126	107.49678	266624	3649569	13	5200	TRUE	211	711
NP-3	10/1/1997	32.96126	107.49678	266624	3649569	13	5200	TRUE	226	719
NP-3	1/15/1998	32.96126	107.49678	266624	3649569	13	5200	TRUE	217	627
NP-3	4/9/1998	32.96126	107.49678	266624	3649569	13	5200	TRUE	219	683
NP-3	7/13/1998	32.96126	107.49678	266624	3649569	13	5200	TRUE	220	715
NP-4	4/16/1982	32.96513	107.49789	266530	3650000	13	5187	FALSE		
NP-4	4/26/1982	32.96513	107.49789	266530	3650000	13	5187	TRUE	46	132
NP-4	5/17/1982	32.96513	107.49789	266530	3650000	13	5187	FALSE	46	138
NP-4	5/24/1982	32.96513	107.49789	266530	3650000	13	5187	TRUE		
NP-4	5/28/1982	32.96513	107.49789	266530	3650000	13	5187	TRUE		

Well Name	Date	Latitude	Longitude	UTM_easting	UTM_northing	UTM_zone	Elevation	Filtered?	Chloride	Sulfate
NP-4	6/8/1982	32.96513	107.49789	266530	3650000	13	5187	TRUE	26	140
NP-4	6/14/1982	32.96513	107.49789	266530	3650000	13	5187	FALSE		
NP-4	6/30/1982	32.96513	107.49789	266530	3650000	13	5187	TRUE	28	115
NP-4	7/26/1982	32.96513	107.49789	266530	3650000	13	5187	FALSE		
NP-4	8/18/1982	32.96513	107.49789	266530	3650000	13	5187	FALSE		
NP-4	9/2/1982	32.96513	107.49789	266530	3650000	13	5187	TRUE	28.72	107.1
NP-4	9/14/1982	32.96513	107.49789	266530	3650000	13	5187	FALSE		
NP-4	10/18/1982	32.96513	107.49789	266530	3650000	13	5187	FALSE		
NP-4	10/27/1982	32.96513	107.49789	266530	3650000	13	5187	TRUE	36	108
NP-4	11/11/1982	32.96513	107.49789	266530	3650000	13	5187	FALSE		
NP-4	12/28/1982	32.96513	107.49789	266530	3650000	13	5187	FALSE		
NP-4	2/21/1983	32.96513	107.49789	266530	3650000	13	5187	TRUE	48	115
NP-4	5/6/1983	32.96513	107.49789	266530	3650000	13	5187	FALSE		
NP-4	5/13/1983	32.96513	107.49789	266530	3650000	13	5187	TRUE	76	134
NP-4	6/2/1983	32.96513	107.49789	266530	3650000	13	5187	FALSE		
NP-4	7/5/1983	32.96513	107.49789	266530	3650000	13	5187	FALSE		
NP-4	8/9/1983	32.96513	107.49789	266530	3650000	13	5187	TRUE	94	156
NP-4	8/25/1983	32.96513	107.49789	266530	3650000	13	5187	FALSE		
NP-4	10/20/1983	32.96513	107.49789	266530	3650000	13	5187	FALSE		
NP-4	11/1/1983	32.96513	107.49789	266530	3650000	13	5187	TRUE	114	206
NP-4	12/7/1983	32.96513	107.49789	266530	3650000	13	5187	FALSE		
NP-4	1/28/1984	32.96513	107.49789	266530	3650000	13	5187	FALSE		
NP-4	2/13/1984	32.96513	107.49789	266530	3650000	13	5187	FALSE		
NP-4	3/1/1984	32.96513	107.49789	266530	3650000	13	5187	FALSE		
NP-4	3/16/1984	32.96513	107.49789	266530	3650000	13	5187	TRUE	126	256
NP-4	4/18/1984	32.96513	107.49789	266530	3650000	13	5187	FALSE		
NP-4	5/22/1984	32.96513	107.49789	266530	3650000	13	5187	FALSE		
NP-4	5/30/1984	32.96513	107.49789	266530	3650000	13	5187	TRUE	134	320
NP-4	6/26/1984	32.96513	107.49789	266530	3650000	13	5187	FALSE		
NP-4	7/25/1984	32.96513	107.49789	266530	3650000	13	5187	FALSE		
NP-4	8/27/1984	32.96513	107.49789	266530	3650000	13	5187	FALSE		
NP-4	9/12/1984	32.96513	107.49789	266530	3650000	13	5187	TRUE	134	339
NP-4	9/21/1984	32.96513	107.49789	266530	3650000	13	5187	FALSE		
NP-4	11/19/1984	32.96513	107.49789	266530	3650000	13	5187	FALSE		
NP-4	11/27/1984	32.96513	107.49789	266530	3650000	13	5187	TRUE	140	354
NP-4	12/17/1984	32.96513	107.49789	266530	3650000	13	5187	FALSE		

Well Name	Date	Latitude	Longitude	UTM_easting	UTM_northing	UTM_zone	Elevation	Filtered?	Chloride	Sulfate
NP-4	5/17/1985	32.96513	107.49789	266530	3650000	13	5187	FALSE	146	348
NP-4	11/13/1985	32.96513	107.49789	266530	3650000	13	5187	FALSE	142	292
NP-4	5/23/1986	32.96513	107.49789	266530	3650000	13	5187	FALSE	136	300
NP-4	10/8/1986	32.96513	107.49789	266530	3650000	13	5187	FALSE	134	290
NP-4	5/25/1987	32.96513	107.49789	266530	3650000	13	5187	FALSE		278.5
NP-4	1/12/1988	32.96513	107.49789	266530	3650000	13	5187	TRUE	137	256
NP-4	4/4/1988	32.96513	107.49789	266530	3650000	13	5187	FALSE	130.4	328.8
NP-4	8/23/1988	32.96513	107.49789	266530	3650000	13	5187	FALSE	132.1	292.2
NP-4	2/9/1989	32.96513	107.49789	266530	3650000	13	5187	FALSE	130	266.8
NP-4	6/1/1989	32.96513	107.49789	266530	3650000	13	5187	FALSE	116.4	243.5
NP-4	11/30/1989	32.96513	107.49789	266530	3650000	13	5187	FALSE	96.9	237.4
NP-4	11/14/1990	32.96513	107.49789	266530	3650000	13	5187	FALSE	153.1	254.5
NP-4	2/11/1991	32.96513	107.49789	266530	3650000	13	5187	FALSE	126.1	288.9
NP-4	7/19/1991	32.96513	107.49789	266530	3650000	13	5187	TRUE	112.3	198.5
NP-4	8/29/1991	32.96513	107.49789	266530	3650000	13	5187	FALSE	110.7	232
NP-4	11/26/1991	32.96513	107.49789	266530	3650000	13	5187	FALSE	99	193.6
NP-4	3/15/1992	32.96513	107.49789	266530	3650000	13	5187	FALSE	102.9	216.5
NP-4	5/25/1992	32.96513	107.49789	266530	3650000	13	5187	FALSE	106.2	171.4
NP-4	7/16/1992	32.96513	107.49789	266530	3650000	13	5187	FALSE	94.4	176.8
NP-4	10/8/1992	32.96513	107.49789	266530	3650000	13	5187	FALSE	102.9	182.9
NP-4	11/27/1992	32.96513	107.49789	266530	3650000	13	5187	FALSE	97.5	201.7
NP-4	12/15/1992	32.96513	107.49789	266530	3650000	13	5187	FALSE	84.4	151.2
NP-4	2/25/1993	32.96513	107.49789	266530	3650000	13	5187	FALSE	76.6	150.8
NP-4	3/31/1993	32.96513	107.49789	266530	3650000	13	5187	FALSE	45	134
NP-4	9/28/1993	32.96513	107.49789	266530	3650000	13	5187	FALSE	56.9	108.5
NP-4	5/26/1994	32.96513	107.49789	266530	3650000	13	5187	FALSE	39	131
NP-4	6/23/1994	32.96513	107.49789	266530	3650000	13	5187	FALSE	48.5	133.5
NP-4	7/23/1994	32.96513	107.49789	266530	3650000	13	5187	TRUE	34	120
NP-4	9/22/1994	32.96513	107.49789	266530	3650000	13	5187	FALSE	36.9	111
NP-4	1/29/1995	32.96513	107.49789	266530	3650000	13	5187	FALSE	34.5	110.7
NP-4	3/29/1995	32.96513	107.49789	266530	3650000	13	5187	FALSE	33.8	121.7
NP-4	6/27/1995	32.96513	107.49789	266530	3650000	13	5187	FALSE	33.2	134.1
NP-4	9/21/1995	32.96513	107.49789	266530	3650000	13	5187	FALSE	35.3	132.1
NP-4	1/10/1996	32.96513	107.49789	266530	3650000	13	5187	FALSE	34.7	123.1
NP-4	4/3/1996	32.96513	107.49789	266530	3650000	13	5187	FALSE	26	123.3
NP-4	6/1/1996	32.96513	107.49789	266530	3650000	13	5187		34.4	123

Well Name	Date	Latitude	Longitude	UTM_easting	UTM_northing	UTM_zone	Elevation	Filtered?	Chloride	Sulfate
NP-4	9/25/1996	32.96513	107.49789	266530	3650000	13	5187	TRUE	31.7	125.6
NP-4	1/15/1997	32.96513	107.49789	266530	3650000	13	5187	TRUE	98	1113
NP-4	7/1/1997	32.96513	107.49789	266530	3650000	13	5187	TRUE	33.2	119
NP-4	10/1/1997	32.96513	107.49789	266530	3650000	13	5187	TRUE	34.3	123
NP-4	1/15/1998	32.96513	107.49789	266530	3650000	13	5187	TRUE	33.4	137
NP-4	1/24/1998	32.96513	107.49789	266530	3650000	13	5187	TRUE	35.8	130
NP-4	4/9/1998	32.96513	107.49789	266530	3650000	13	5187	TRUE	34.2	120
NP-4	7/13/1998	32.96513	107.49789	266530	3650000	13	5187	TRUE	32.9	131
NP-4	7/21/1998	32.96513	107.49789	266530	3650000	13	5187	TRUE	33.2	128
NP-5	11/4/1981	32.95888	107.49677	266618	3649305	13	5186	TRUE	50	196
NP-5	11/11/1981	32.95888	107.49677	266618	3649305	13	5186	FALSE		
NP-5	11/13/1981	32.95888	107.49677	266618	3649305	13	5186	TRUE	37.89	162
NP-5	11/17/1981	32.95888	107.49677	266618	3649305	13	5186	TRUE	42	158
NP-5	11/23/1981	32.95888	107.49677	266618	3649305	13	5186	TRUE	36	161
NP-5	12/7/1981	32.95888	107.49677	266618	3649305	13	5186	TRUE	34	172

Well Name	Date	pH	TDS	Alkalinity	Bicarb	Spec. Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
NP-3	10/8/1981	6.98	460		211		1.58	-0.5	-0.25		0.005
NP-3	10/27/1981	8	390				1.9	0.4	-0.01		-0.01
NP-3	10/30/1981	7.89	428				1.6	-0.5	-0.25		-0.005
NP-3	11/6/1981	7.9	380				1.6	0.2	-0.01		-0.01
NP-3	11/12/1981										
NP-3	11/13/1981	7.6	446		190.3	600	1.39	0.16	-0.25		0.009
NP-3	11/17/1981	8.1	390				1.4	-0.2	-0.01		-0.01
NP-3	11/23/1981	7.8	460				1.2	0.2	-0.01		-0.01
NP-3	12/7/1981	7.9	450				1.1	-0.2	-0.01		-0.01
NP-3	12/15/1981	7.8	450				1.1	0.2	-0.01		-0.01
NP-3	12/22/1981	7.9	410				0.9	0.2	-0.01		-0.01
NP-3	1/5/1982	7.7	360				1.1	0.2	-0.01		-0.01
NP-3	1/18/1982										
NP-3	1/26/1982	8.1	400				1	0.2			
NP-3	2/16/1982										
NP-3	2/22/1982	8	420				0.9	-0.2			
NP-3	3/12/1982										
NP-3	4/16/1982										
NP-3	4/26/1982	7.9	410				0.8	-0.2			
NP-3	5/17/1982	7.6	2460				0.7	12			
NP-3	5/24/1982										
NP-3	5/28/1982										
NP-3	6/8/1982	7.9	500				0.5	1.9			
NP-3	6/14/1982										
NP-3	6/30/1982	7.9	510				0.5	1.8			
NP-3	7/26/1982										
NP-3	8/18/1982										
NP-3	9/2/1982	7.5	498		308	750	0.53	1.94			
NP-3	9/14/1982										
NP-3	10/18/1982										
NP-3	10/27/1982	8	450				0.6	1.6			
NP-3	11/11/1982										
NP-3	12/28/1982										
NP-3	2/21/1983	8.2	410				0.5	1.4			
NP-3	5/6/1983										
NP-3	5/13/1983	8	500				0.5	2.1			

Well Name	Date	pH	TDS	Alkalinity	Bicarb	Spec. Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
NP-3	6/2/1983										
NP-3	7/5/1983										
NP-3	8/9/1983	7.8	630				0.5	2.3			
NP-3	8/25/1983										
NP-3	10/20/1983										
NP-3	11/1/1983	7.9	760				0.5	3.8			
NP-3	12/7/1983										
NP-3	1/28/1984										
NP-3	2/13/1984										
NP-3	3/1/1984										
NP-3	3/16/1984	8.1	870				0.6	3.2			
NP-3	4/18/1984										
NP-3	5/22/1984										
NP-3	5/30/1984	7.8	1060				0.4	2.9			
NP-3	6/26/1984										
NP-3	7/25/1984										
NP-3	8/27/1984										
NP-3	9/12/1984	7.7	1140				0.4	3.1			
NP-3	9/21/1984										
NP-3	11/19/1984										
NP-3	11/27/1984	7.8	1150				0.4	3.5			
NP-3	12/17/1984										
NP-3	5/17/1985	7.7	1470								
NP-3	11/13/1985	7.2	1520								
NP-3	5/23/1986	7.5	1590								
NP-3	10/8/1986	7.4	1710								
NP-3	3/3/1987										
NP-3	3/4/1987	6.8	1882		188						
NP-3	5/25/1987										
NP-3	1/12/1988		1584		30				-0.1		
NP-3	4/4/1988		1772								
NP-3	8/23/1988		1744								
NP-3	2/9/1989		1583								
NP-3	6/1/1989		1596								
NP-3	11/30/1989		1600								
NP-3	11/14/1990		1675								

Well Name	Date	pH	TDS	Alkalinity	Bicarb	Spec. Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
NP-3	2/11/1991		1551								-0.001
NP-3	7/19/1991	8.29	1663	167	191.6	2520	0.66	0.23			-0.002
NP-3	8/29/1991	7.84	1616								
NP-3	11/26/1991	7.08	1613								
NP-3	3/15/1992	7.63	1644								
NP-3	5/25/1992	7.85	1607								
NP-3	7/16/1992	7.26	1578								
NP-3	10/8/1992	7.69	1445								
NP-3	11/27/1992	7.49	1640								
NP-3	12/15/1992	7.75	1558								
NP-3	2/25/1993	7.65	1580								
NP-3	3/30/1993	7.4	1560		29	2070	0.54		0.1		-0.005
NP-3	9/28/1993	7.88	1544								
NP-3	3/17/1994	7.46	1609								
NP-3	6/23/1994	7.77	1628								
NP-3	7/22/1994	7.83	1620		118	2160	0.34	-1	-0.05	-0.005	-0.005
NP-3	9/22/1994	7.05	3466								
NP-3	1/29/1995	7.45	1623								
NP-3	3/29/1995	7.48	1639								
NP-3	6/27/1995	7.38	1607								
NP-3	9/21/1995	7.5	1557								
NP-3	1/10/1996	7.32	1464								
NP-3	4/3/1996	7.29	1415								
NP-3	6/1/1996	7.64	1422								
NP-3	9/25/1996	7.72	1472								
NP-3	1/15/1997	7.51	1478								
NP-3	7/1/1997	7.28	1486								
NP-3	10/1/1997	7.79	1440								
NP-3	1/15/1998	7.39	1406			1980	0.29	-0.05			
NP-3	4/9/1998		1448			1810	0.028	-0.05			
NP-3	7/13/1998		1433			1830	0.031	0.06			
NP-4	4/16/1982										
NP-4	4/26/1982	8.6	410				1.5	0.6			
NP-4	5/17/1982	9.4	310				1	1.3			
NP-4	5/24/1982										
NP-4	5/28/1982										

Well Name	Date	pH	TDS	Alkalinity	Bicarb	Spec. Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
NP-4	6/8/1982	8.4	420				0.5	4.5			
NP-4	6/14/1982										
NP-4	6/30/1982	9.5	270				0.4	-0.2			
NP-4	7/26/1982										
NP-4	8/18/1982										
NP-4	9/2/1982	8.5	252		63.1	410	0.4	0.03			
NP-4	9/14/1982										
NP-4	10/18/1982										
NP-4	10/27/1982	8.9	230				0.4	-0.2			
NP-4	11/11/1982										
NP-4	12/28/1982										
NP-4	2/21/1983	9.3	250				0.4	0.2			
NP-4	5/6/1983										
NP-4	5/13/1983	7.9	340				0.4	-0.2			
NP-4	6/2/1983										
NP-4	7/5/1983										
NP-4	8/9/1983	8.8	430				0.3	-0.2			
NP-4	8/25/1983										
NP-4	10/20/1983										
NP-4	11/1/1983	8.2	530				0.3	0.6			
NP-4	12/7/1983										
NP-4	1/28/1984										
NP-4	2/13/1984										
NP-4	3/1/1984										
NP-4	3/16/1984	8	540				0.6	0.2			
NP-4	4/18/1984										
NP-4	5/22/1984										
NP-4	5/30/1984	8	630				0.3	-0.2			
NP-4	6/26/1984										
NP-4	7/25/1984										
NP-4	8/27/1984										
NP-4	9/12/1984	8	760				0.3	0.9			
NP-4	9/21/1984										
NP-4	11/19/1984										
NP-4	11/27/1984	8.5	740				0.3	0.2			
NP-4	12/17/1984										

Well Name	Date	pH	TDS	Alkalinity	Bicarb	Spec. Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
NP-4	5/17/1985	8.2	770								
NP-4	11/13/1985	8	690								
NP-4	5/23/1986	8	690								
NP-4	10/8/1986	7.8	690								
NP-4	5/25/1987										
NP-4	1/12/1988		612		24.4				-0.1		
NP-4	4/4/1988		610								
NP-4	8/23/1988		688								
NP-4	2/9/1989		604								
NP-4	6/1/1989		580								
NP-4	11/30/1989		572								
NP-4	11/14/1990		262								
NP-4	2/11/1991		676								-0.001
NP-4	7/19/1991	7.81	532	45	54.9	802	0.41	0.07			-0.002
NP-4	8/29/1991	8.37	532								
NP-4	11/26/1991	8.54	522								
NP-4	3/15/1992	8.85	565								
NP-4	5/25/1992	8.62	439								
NP-4	7/16/1992	7.64	458								
NP-4	10/8/1992	9.01	535								
NP-4	11/27/1992	8.12	495								
NP-4	12/15/1992	9.52	424								
NP-4	2/25/1993	9.85	349								
NP-4	3/31/1993	7.6	504		275	813	0.53	3.7	0.3		-0.005
NP-4	9/28/1993	8.2	437								
NP-4	5/26/1994	8.1	666		320	800	0.46	4.3	3.5	-0.005	-0.005
NP-4	6/23/1994	8.13	498								
NP-4	7/23/1994	7.9	536		279	828	0.48	4.6	-0.05	0.01	-0.005
NP-4	9/22/1994	7.73	547								
NP-4	1/29/1995	7.88	447								
NP-4	3/29/1995	7.86	494								
NP-4	6/27/1995	7.37	487								
NP-4	9/21/1995	7.51	509								
NP-4	1/10/1996	7.35	483								
NP-4	4/3/1996	7.19	475								
NP-4	6/1/1996	7.36	478								

Well Name	Date	pH	TDS	Alkalinity	Bicarb	Spec. Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
NP-4	9/25/1996	7.75	504								
NP-4	1/15/1997	7.43	2651								
NP-4	7/1/1997	7.53	500								
NP-4	10/1/1997	7.66	503								
NP-4	1/15/1998	7.73	489			847	0.56	5.97			
NP-4	1/24/1998	7.56	527		287.9	864	0.058				
NP-4	4/9/1998		534			850	0.54	6.3			
NP-4	7/13/1998		503			784	0.58	6			
NP-4	7/21/1998		543				0.61	6.2			
NP-5	11/4/1981	8	570				1.3	4.1	-0.01		-0.01
NP-5	11/11/1981										
NP-5	11/13/1981	7.7	488		186.7	650	1.28	3.56	0.239		-0.005
NP-5	11/17/1981	8	500				1.3	2.7	-0.01		-0.01
NP-5	11/23/1981	7.8	580				1.2	4	-0.01		-0.01
NP-5	12/7/1981	7.9	510				1.2	3.1	-0.01		-0.01

Well Name	Date	Boron	Barium	Berrylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
NP-3	10/8/1981	0.188	-1		-0.01	40.9	-0.05	-0.05	-0.05	-0.1	-0.05
NP-3	10/27/1981	-0.01	0.2		-0.005	41	-0.01	-0.02	-0.05	0.39	-0.02
NP-3	10/30/1981	0.29	-1		-0.01		-0.05	-0.05	-0.05	-0.1	-0.05
NP-3	11/6/1981	-0.01	-0.2		-0.005	39	-0.01	-0.02	-0.05	-0.1	-0.02
NP-3	11/12/1981										
NP-3	11/13/1981	0.034	-0.1		-0.001	55.2	-0.005				-0.005
NP-3	11/17/1981	-0.1	0.24		-0.005	44	-0.01	-0.02	-0.05	-0.1	-0.02
NP-3	11/23/1981	-0.1	0.02		-0.005	47	-0.02	-0.02	-0.05	-0.1	-0.02
NP-3	12/7/1981	-0.1	-0.2		-0.005	47	-0.01	-0.02	-0.05	-0.1	-0.02
NP-3	12/15/1981	-0.1	-0.2		-0.005	56	-0.01	-0.02	-0.05	-0.1	-0.02
NP-3	12/22/1981	-0.1	-0.2		-0.005	73	-0.01	-0.02	-0.05	-0.1	-0.02
NP-3	1/5/1982	-0.1	-0.2		-0.005	56	-0.01	-0.02	-0.05	0.31	-0.02
NP-3	1/18/1982										
NP-3	1/26/1982				-0.005				-0.05	-0.1	
NP-3	2/16/1982										
NP-3	2/22/1982				-0.005				-0.05	0.14	
NP-3	3/12/1982										
NP-3	4/16/1982										
NP-3	4/26/1982				-0.005				-0.05	0.24	
NP-3	5/17/1982				-0.005				-0.05	0.016	
NP-3	5/24/1982									-0.1	
NP-3	5/28/1982									-0.1	
NP-3	6/8/1982				-0.005				-0.05	-0.1	
NP-3	6/14/1982										
NP-3	6/30/1982				-0.005				-0.05	-0.1	
NP-3	7/26/1982										
NP-3	8/18/1982										
NP-3	9/2/1982				-0.001	77.4					
NP-3	9/14/1982										
NP-3	10/18/1982										
NP-3	10/27/1982				-0.005				-0.05	-0.1	
NP-3	11/11/1982										
NP-3	12/28/1982										
NP-3	2/21/1983				-0.005				-0.05	-0.1	
NP-3	5/6/1983										
NP-3	5/13/1983				-0.005				-0.05	-0.1	

Well Name	Date	Boron	Barium	Berrylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
NP-3	6/2/1983										
NP-3	7/5/1983										
NP-3	8/9/1983				-0.005				-0.05	-0.1	
NP-3	8/25/1983										
NP-3	10/20/1983										
NP-3	11/1/1983				-0.005				-0.05	0.14	
NP-3	12/7/1983										
NP-3	1/28/1984										
NP-3	2/13/1984										
NP-3	3/1/1984										
NP-3	3/16/1984				-0.005				-0.05	-0.1	
NP-3	4/18/1984										
NP-3	5/22/1984										
NP-3	5/30/1984				-0.005				-0.05	-0.1	
NP-3	6/26/1984										
NP-3	7/25/1984										
NP-3	8/27/1984										
NP-3	9/12/1984				-0.005				-0.05	-0.1	
NP-3	9/21/1984										
NP-3	11/19/1984										
NP-3	11/27/1984				-0.005				-0.05	-0.1	
NP-3	12/17/1984										
NP-3	5/17/1985										
NP-3	11/13/1985										
NP-3	5/23/1986										
NP-3	10/8/1986										
NP-3	3/3/1987										
NP-3	3/4/1987					320					
NP-3	5/25/1987										
NP-3	1/12/1988	-0.1	-0.1	-0.1	-0.1	268	-0.1	-0.05	-0.1	-0.1	-0.1
NP-3	4/4/1988										
NP-3	8/23/1988										
NP-3	2/9/1989										
NP-3	6/1/1989										
NP-3	11/30/1989										
NP-3	11/14/1990										

Well Name	Date	Boron	Barium	Berrylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
NP-3	2/11/1991										
NP-3	7/19/1991		-0.01		-0.005	287	-0.02		-0.02	0.28	-0.005
NP-3	8/29/1991										
NP-3	11/26/1991										
NP-3	3/15/1992										
NP-3	5/25/1992										
NP-3	7/16/1992										
NP-3	10/8/1992										
NP-3	11/27/1992										
NP-3	12/15/1992								0.01		
NP-3	2/25/1993										
NP-3	3/30/1993	0.02	-0.5		-0.002	296	-0.02	-0.05	0.01	4.99	-0.02
NP-3	9/28/1993								-0.001	-0.05	
NP-3	3/17/1994								0.012	0.24	
NP-3	6/23/1994										
NP-3	7/22/1994	-0.1	-0.1	-0.002	-0.0005	320	-0.025	-0.05	-0.025	-0.05	-0.005
NP-3	9/22/1994										
NP-3	1/29/1995										
NP-3	3/29/1995										
NP-3	6/27/1995										
NP-3	9/21/1995										
NP-3	1/10/1996										
NP-3	4/3/1996										
NP-3	6/1/1996										
NP-3	9/25/1996										
NP-3	1/15/1997										
NP-3	7/1/1997										
NP-3	10/1/1997										
NP-3	1/15/1998								-0.005	0.2	
NP-3	4/9/1998								-0.005	-0.2	
NP-3	7/13/1998								-0.005	-0.05	
NP-4	4/16/1982										
NP-4	4/26/1982				-0.005				0.051	3.8	
NP-4	5/17/1982				-0.005				-0.05	0.11	
NP-4	5/24/1982									-0.1	
NP-4	5/28/1982									-0.1	

Well Name	Date	Boron	Barium	Berrylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
NP-4	6/8/1982				-0.005				-0.05	-0.1	
NP-4	6/14/1982										
NP-4	6/30/1982				-0.005				-0.05	-0.1	
NP-4	7/26/1982										
NP-4	8/18/1982										
NP-4	9/2/1982				-0.001	7.2					
NP-4	9/14/1982										
NP-4	10/18/1982										
NP-4	10/27/1982				0.0061				-0.05	0.34	
NP-4	11/11/1982										
NP-4	12/28/1982										
NP-4	2/21/1983				-0.005				-0.05	0.28	
NP-4	5/6/1983										
NP-4	5/13/1983				-0.005				-0.05	-0.1	
NP-4	6/2/1983										
NP-4	7/5/1983										
NP-4	8/9/1983				-0.005				-0.05	-0.1	
NP-4	8/25/1983										
NP-4	10/20/1983										
NP-4	11/1/1983				-0.005				-0.05	-0.1	
NP-4	12/7/1983										
NP-4	1/28/1984										
NP-4	2/13/1984										
NP-4	3/1/1984										
NP-4	3/16/1984				-0.005				-0.05	-0.1	
NP-4	4/18/1984										
NP-4	5/22/1984										
NP-4	5/30/1984				-0.005				-0.05	-0.1	
NP-4	6/26/1984										
NP-4	7/25/1984										
NP-4	8/27/1984										
NP-4	9/12/1984				-0.005				-0.05	-0.1	
NP-4	9/21/1984										
NP-4	11/19/1984										
NP-4	11/27/1984				-0.005				-0.05	-0.1	
NP-4	12/17/1984										

Well Name	Date	Boron	Barium	Berrylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
NP-4	5/17/1985										
NP-4	11/13/1985										
NP-4	5/23/1986										
NP-4	10/8/1986										
NP-4	5/25/1987										
NP-4	1/12/1988	-0.1	-0.1	-0.1	-0.1	76	-0.1	-0.05	-0.1	-0.1	-0.1
NP-4	4/4/1988										
NP-4	8/23/1988										
NP-4	2/9/1989										
NP-4	6/1/1989										
NP-4	11/30/1989										
NP-4	11/14/1990										
NP-4	2/11/1991										
NP-4	7/19/1991		0.28		-0.005	63.4	-0.02			5.14	-0.005
NP-4	8/29/1991										
NP-4	11/26/1991										
NP-4	3/15/1992										
NP-4	5/25/1992										
NP-4	7/16/1992										
NP-4	10/8/1992										
NP-4	11/27/1992										
NP-4	12/15/1992										
NP-4	2/25/1993										
NP-4	3/31/1993	0.04	-0.5		-0.002	76	-0.02	-0.05	0.01	0.62	-0.02
NP-4	9/28/1993										
NP-4	5/26/1994		-0.1		0.0034	73	-0.025		-0.025	15	0.018
NP-4	6/23/1994										
NP-4	7/23/1994	-0.1	-0.1	-0.002	-0.0005	88	-0.025	-0.05	-0.025	-0.05	-0.005
NP-4	9/22/1994										
NP-4	1/29/1995										
NP-4	3/29/1995										
NP-4	6/27/1995										
NP-4	9/21/1995										
NP-4	1/10/1996										
NP-4	4/3/1996										
NP-4	6/1/1996										

Well Name	Date	Boron	Barium	Berrylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
NP-4	9/25/1996										
NP-4	1/15/1997										
NP-4	7/1/1997										
NP-4	10/1/1997										
NP-4	1/15/1998								-0.005	1	
NP-4	1/24/1998					77			-0.005		
NP-4	4/9/1998								0.009	-0.2	
NP-4	7/13/1998								-0.005	0.76	
NP-4	7/21/1998					87			-0.005	0.42	
NP-5	11/4/1981	-0.01	-0.2		-0.005	86	-0.01	-0.02	-0.05	-0.1	-0.02
NP-5	11/11/1981										
NP-5	11/13/1981	0.07	0.218		-0.001	88.6	-0.005		-0.1		-0.005
NP-5	11/17/1981	-0.1	-0.2		-0.005	72	-0.01	-0.02	-0.05	-0.1	-0.02
NP-5	11/23/1981	-0.1	-0.2		-0.005	73	-0.02	-0.02	-0.05	-0.1	-0.02
NP-5	12/7/1981	-0.1	-0.2		-0.005	66	-0.01	-0.02	-0.05	-0.1	-0.02

Well Name	Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium	Thallium
NP-3	10/8/1981	9.55	0.81	-1	-0.1	-0.05	9.71	0.005	-0.02	79	
NP-3	10/27/1981		1	-0.001	0.16	-0.05		-0.005	-0.02		
NP-3	10/30/1981		1.03	-0.001	-0.1	-0.02		-0.002	-0.02		
NP-3	11/6/1981		0.47	-0.001	0.26	-0.05		-0.005	-0.02		
NP-3	11/12/1981										
NP-3	11/13/1981	13.05	1.01	-0.0005	0.65	-0.05	5.85	0.023	0.023	43.7	
NP-3	11/17/1981		1	-0.001	0.2	-0.05		-0.005	-0.02		
NP-3	11/23/1981		0.96	-0.001	0.15	-0.05		-0.005	-0.01		
NP-3	12/7/1981		0.78	-0.001	0.13	-0.05		-0.005	-0.02		
NP-3	12/15/1981		0.87	-0.001	0.094	-0.05		-0.005	-0.02		
NP-3	12/22/1981		0.76	-0.001	0.1	-0.05		-0.005	-0.02		
NP-3	1/5/1982		0.72	-0.001	0.01	-0.05		-0.02	-0.02		
NP-3	1/18/1982										
NP-3	1/26/1982		0.7	-0.001	-0.1			-0.005			
NP-3	2/16/1982										
NP-3	2/22/1982		0.66	-0.001	-0.05			-0.005			
NP-3	3/12/1982										
NP-3	4/16/1982										
NP-3	4/26/1982		0.4	-0.001	-0.05			-0.005			
NP-3	5/17/1982		0.23	-0.001	-0.05			-0.005			
NP-3	5/24/1982		0.053								
NP-3	5/28/1982		0.063								
NP-3	6/8/1982		0.1	-0.001	-0.05			-0.005			
NP-3	6/14/1982										
NP-3	6/30/1982		0.081	-0.001	-0.05			-0.005			
NP-3	7/26/1982										
NP-3	8/18/1982										
NP-3	9/2/1982	15.1	-0.05		-0.01		3.9	-0.005		64.4	
NP-3	9/14/1982										
NP-3	10/18/1982										
NP-3	10/27/1982		-0.05	-0.001	-0.05			-0.005			
NP-3	11/11/1982										
NP-3	12/28/1982										
NP-3	2/21/1983		-0.05	-0.001	-0.05			-0.005			
NP-3	5/6/1983										
NP-3	5/13/1983		-0.05	-0.001	-0.05			-0.005			

Well Name	Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium	Thallium
NP-3	6/2/1983										
NP-3	7/5/1983										
NP-3	8/9/1983		-0.05	-0.001	-0.05			-0.005			
NP-3	8/25/1983										
NP-3	10/20/1983										
NP-3	11/1/1983		-0.05	-0.001	-0.05			-0.005			
NP-3	12/7/1983										
NP-3	1/28/1984										
NP-3	2/13/1984										
NP-3	3/1/1984										
NP-3	3/16/1984		-0.05	-0.001	-0.05			-0.005			
NP-3	4/18/1984										
NP-3	5/22/1984										
NP-3	5/30/1984		-0.05	-0.001	-0.05			-0.005			
NP-3	6/26/1984										
NP-3	7/25/1984										
NP-3	8/27/1984										
NP-3	9/12/1984		-0.05	-0.001	-0.05			-0.005			
NP-3	9/21/1984										
NP-3	11/19/1984										
NP-3	11/27/1984		-0.05	-0.001	-0.05			-0.005			
NP-3	12/17/1984										
NP-3	5/17/1985										
NP-3	11/13/1985										
NP-3	5/23/1986										
NP-3	10/8/1986										
NP-3	3/3/1987										
NP-3	3/4/1987	67.1					4.29			117.3	
NP-3	5/25/1987										
NP-3	1/12/1988	57	0.57		-0.1	-0.1	38		-0.1	142	
NP-3	4/4/1988										
NP-3	8/23/1988										
NP-3	2/9/1989										
NP-3	6/1/1989										
NP-3	11/30/1989										
NP-3	11/14/1990										

Well Name	Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium	Thallium
NP-3	2/11/1991								255.9		
NP-3	7/19/1991	53.4	0.08	0.0002			7	0.011	-0.02	189.7	
NP-3	8/29/1991										
NP-3	11/26/1991										
NP-3	3/15/1992										
NP-3	5/25/1992										
NP-3	7/16/1992										
NP-3	10/8/1992										
NP-3	11/27/1992										
NP-3	12/15/1992										
NP-3	2/25/1993										
NP-3	3/30/1993	35	0.32	-0.001	-0.02	-0.01	4.1	-0.005	-0.01	129	
NP-3	9/28/1993		0.24								
NP-3	3/17/1994		0.33								
NP-3	6/23/1994										
NP-3	7/22/1994	73	0.61	-0.001	-0.05	-0.05	4.5	-0.005	-0.025	120	-0.005
NP-3	9/22/1994										
NP-3	1/29/1995										
NP-3	3/29/1995										
NP-3	6/27/1995										
NP-3	9/21/1995										
NP-3	1/10/1996										
NP-3	4/3/1996										
NP-3	6/1/1996										
NP-3	9/25/1996										
NP-3	1/15/1997										
NP-3	7/1/1997										
NP-3	10/1/1997										
NP-3	1/15/1998	54.8		-0.0002	-0.05			-0.05			
NP-3	4/9/1998		0.15	-0.0002	-0.05			-0.05			
NP-3	7/13/1998		0.33	-0.0002	-0.05			-0.05			
NP-4	4/16/1982										
NP-4	4/26/1982		0.6	-0.001	0.07			-0.005			
NP-4	5/17/1982		-0.05	-0.001	-0.05			-0.005			
NP-4	5/24/1982		-0.05								
NP-4	5/28/1982		-0.05								

Well Name	Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium	Thallium
NP-4	6/8/1982		-0.05	-0.001	-0.05			-0.005			
NP-4	6/14/1982										
NP-4	6/30/1982		-0.05	-0.001	-0.05			-0.005			
NP-4	7/26/1982										
NP-4	8/18/1982										
NP-4	9/2/1982	3.5	-0.05		-0.01		3.9	-0.005		71.3	
NP-4	9/14/1982										
NP-4	10/18/1982										
NP-4	10/27/1982		-0.05	-0.001	-0.05			-0.005			
NP-4	11/11/1982										
NP-4	12/28/1982										
NP-4	2/21/1983		-0.05	-0.001	-0.05			-0.005			
NP-4	5/6/1983										
NP-4	5/13/1983		-0.05	-0.001	-0.05			-0.005			
NP-4	6/2/1983										
NP-4	7/5/1983										
NP-4	8/9/1983		-0.05	-0.001	-0.05			-0.005			
NP-4	8/25/1983										
NP-4	10/20/1983										
NP-4	11/1/1983		-0.05	-0.001	-0.05			-0.005			
NP-4	12/7/1983										
NP-4	1/28/1984										
NP-4	2/13/1984										
NP-4	3/1/1984										
NP-4	3/16/1984		-0.05	0.001	-0.05			-0.005			
NP-4	4/18/1984										
NP-4	5/22/1984										
NP-4	5/30/1984		-0.05	-0.001	-0.05			-0.005			
NP-4	6/26/1984										
NP-4	7/25/1984										
NP-4	8/27/1984										
NP-4	9/12/1984		-0.05	-0.001	-0.05			-0.005			
NP-4	9/21/1984										
NP-4	11/19/1984										
NP-4	11/27/1984		-0.05	-0.001	-0.05			-0.005			
NP-4	12/17/1984										

Well Name	Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium	Thallium
NP-4	5/17/1985										
NP-4	11/13/1985										
NP-4	5/23/1986										
NP-4	10/8/1986										
NP-4	5/25/1987										
NP-4	1/12/1988	21	0.06		-0.1	-0.1	5		-0.1	86	
NP-4	4/4/1988										
NP-4	8/23/1988										
NP-4	2/9/1989										
NP-4	6/1/1989										
NP-4	11/30/1989										
NP-4	11/14/1990										
NP-4	2/11/1991										
NP-4	7/19/1991	20.8	-0.02	-0.0002			3.1	-0.002	-0.02	66.7	
NP-4	8/29/1991										
NP-4	11/26/1991										
NP-4	3/15/1992										
NP-4	5/25/1992										
NP-4	7/16/1992										
NP-4	10/8/1992										
NP-4	11/27/1992										
NP-4	12/15/1992										
NP-4	2/25/1993										
NP-4	3/31/1993	17	0.84	0.009	-0.02	-0.01	2.2	-0.005	-0.01	79	
NP-4	9/28/1993										
NP-4	5/26/1994	15	0.16	-0.001		-0.05	3	-0.005	-0.025	62	
NP-4	6/23/1994										
NP-4	7/23/1994	16	-0.03	-0.001	-0.05	-0.05	2.5	-0.005	-0.025	72	-0.005
NP-4	9/22/1994										
NP-4	1/29/1995										
NP-4	3/29/1995										
NP-4	6/27/1995										
NP-4	9/21/1995										
NP-4	1/10/1996										
NP-4	4/3/1996										
NP-4	6/1/1996										

Well Name	Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium	Thallium
NP-4	9/25/1996										
NP-4	1/15/1997										
NP-4	7/1/1997										
NP-4	10/1/1997										
NP-4	1/15/1998	13.8		-0.0002	-0.05			-0.05			
NP-4	1/24/1998	14.8	-0.02				5.3			70.1	
NP-4	4/9/1998		0.03	-0.0002	-0.05			-0.05			
NP-4	7/13/1998		0.08	-0.0002	-0.05			-0.05			
NP-4	7/21/1998	13.8	-0.02	0.0004	-0.05		2.2	-0.05		64.6	
NP-5	11/4/1981		0.1	-0.001	-0.05	-0.05		-0.005	-0.02		
NP-5	11/11/1981										
NP-5	11/13/1981	14.4	0.14	-0.0005	0.015	0.019	5.07	0.014	-0.001	43.7	
NP-5	11/17/1981		0.3	-0.001	0.07	-0.05		-0.005	-0.02		
NP-5	11/23/1981		0.091	-0.001	-0.05	-0.05		-0.005	-0.1		
NP-5	12/7/1981		-0.05	-0.001	-0.05	-0.05		-0.005	-0.02		

Well Name	Date	Zinc	Temp (C)	Tin	Vanadium
NP-3	10/8/1981	1.25			
NP-3	10/27/1981	0.98			
NP-3	10/30/1981	0.93			
NP-3	11/6/1981	1.1			
NP-3	11/12/1981				
NP-3	11/13/1981	1.59	20.5		
NP-3	11/17/1981	1.2			
NP-3	11/23/1981	1.9			
NP-3	12/7/1981	3.5			
NP-3	12/15/1981	2.5			
NP-3	12/22/1981	2.1			
NP-3	1/5/1982	1.7			
NP-3	1/18/1982				
NP-3	1/26/1982				
NP-3	2/16/1982				
NP-3	2/22/1982				
NP-3	3/12/1982				
NP-3	4/16/1982				
NP-3	4/26/1982				
NP-3	5/17/1982				
NP-3	5/24/1982				
NP-3	5/28/1982				
NP-3	6/8/1982				
NP-3	6/14/1982				
NP-3	6/30/1982				
NP-3	7/26/1982				
NP-3	8/18/1982				
NP-3	9/2/1982		26		
NP-3	9/14/1982				
NP-3	10/18/1982				
NP-3	10/27/1982				
NP-3	11/11/1982				
NP-3	12/28/1982				
NP-3	2/21/1983				
NP-3	5/6/1983				
NP-3	5/13/1983				

Well Name	Date	Zinc	Temp (C)	Tin	Vanadium
NP-3	6/2/1983				
NP-3	7/5/1983				
NP-3	8/9/1983				
NP-3	8/25/1983				
NP-3	10/20/1983				
NP-3	11/1/1983				
NP-3	12/7/1983				
NP-3	1/28/1984				
NP-3	2/13/1984				
NP-3	3/1/1984				
NP-3	3/16/1984				
NP-3	4/18/1984				
NP-3	5/22/1984				
NP-3	5/30/1984				
NP-3	6/26/1984				
NP-3	7/25/1984				
NP-3	8/27/1984				
NP-3	9/12/1984				
NP-3	9/21/1984				
NP-3	11/19/1984				
NP-3	11/27/1984				
NP-3	12/17/1984				
NP-3	5/17/1985				
NP-3	11/13/1985				
NP-3	5/23/1986				
NP-3	10/8/1986				
NP-3	3/3/1987				
NP-3	3/4/1987		17.5		
NP-3	5/25/1987				
NP-3	1/12/1988	1.1		0.2	-0.1
NP-3	4/4/1988				
NP-3	8/23/1988				
NP-3	2/9/1989				
NP-3	6/1/1989				
NP-3	11/30/1989				
NP-3	11/14/1990				

Well Name	Date	Zinc	Temp (C)	Tin	Vanadium
NP-3	2/11/1991				
NP-3	7/19/1991				
NP-3	8/29/1991				
NP-3	11/26/1991				
NP-3	3/15/1992				
NP-3	5/25/1992				
NP-3	7/16/1992				
NP-3	10/8/1992				
NP-3	11/27/1992				
NP-3	12/15/1992				
NP-3	2/25/1993				
NP-3	3/30/1993	6.98			
NP-3	9/28/1993	1.04			
NP-3	3/17/1994	2.58			
NP-3	6/23/1994				
NP-3	7/22/1994	1.8			
NP-3	9/22/1994				
NP-3	1/29/1995				
NP-3	3/29/1995				
NP-3	6/27/1995				
NP-3	9/21/1995				
NP-3	1/10/1996				
NP-3	4/3/1996				
NP-3	6/1/1996				
NP-3	9/25/1996				
NP-3	1/15/1997				
NP-3	7/1/1997				
NP-3	10/1/1997				
NP-3	1/15/1998				
NP-3	4/9/1998				
NP-3	7/13/1998				
NP-4	4/16/1982				
NP-4	4/26/1982				
NP-4	5/17/1982				
NP-4	5/24/1982				
NP-4	5/28/1982				

Well Name	Date	Zinc	Temp (C)	Tin	Vanadium
NP-4	6/8/1982				
NP-4	6/14/1982				
NP-4	6/30/1982				
NP-4	7/26/1982				
NP-4	8/18/1982				
NP-4	9/2/1982				
NP-4	9/14/1982				
NP-4	10/18/1982				
NP-4	10/27/1982				
NP-4	11/11/1982				
NP-4	12/28/1982				
NP-4	2/21/1983				
NP-4	5/6/1983				
NP-4	5/13/1983				
NP-4	6/2/1983				
NP-4	7/5/1983				
NP-4	8/9/1983				
NP-4	8/25/1983				
NP-4	10/20/1983				
NP-4	11/1/1983				
NP-4	12/7/1983				
NP-4	1/28/1984				
NP-4	2/13/1984				
NP-4	3/1/1984				
NP-4	3/16/1984				
NP-4	4/18/1984				
NP-4	5/22/1984				
NP-4	5/30/1984				
NP-4	6/26/1984				
NP-4	7/25/1984				
NP-4	8/27/1984				
NP-4	9/12/1984				
NP-4	9/21/1984				
NP-4	11/19/1984				
NP-4	11/27/1984				
NP-4	12/17/1984				

Well Name	Date	Zinc	Temp (C)	Tin	Vanadium
NP-4	5/17/1985				
NP-4	11/13/1985				
NP-4	5/23/1986				
NP-4	10/8/1986				
NP-4	5/25/1987				
NP-4	1/12/1988	0.1		0.5	-0.1
NP-4	4/4/1988				
NP-4	8/23/1988				
NP-4	2/9/1989				
NP-4	6/1/1989				
NP-4	11/30/1989				
NP-4	11/14/1990				
NP-4	2/11/1991				
NP-4	7/19/1991				
NP-4	8/29/1991				
NP-4	11/26/1991				
NP-4	3/15/1992				
NP-4	5/25/1992				
NP-4	7/16/1992				
NP-4	10/8/1992				
NP-4	11/27/1992				
NP-4	12/15/1992				
NP-4	2/25/1993				
NP-4	3/31/1993	241			
NP-4	9/28/1993				
NP-4	5/26/1994	12			
NP-4	6/23/1994				
NP-4	7/23/1994	0.51			
NP-4	9/22/1994				
NP-4	1/29/1995				
NP-4	3/29/1995				
NP-4	6/27/1995				
NP-4	9/21/1995				
NP-4	1/10/1996				
NP-4	4/3/1996				
NP-4	6/1/1996				

Well Name	Date	Zinc	Temp (C)	Tin	Vanadium
NP-4	9/25/1996				
NP-4	1/15/1997				
NP-4	7/1/1997				
NP-4	10/1/1997				
NP-4	1/15/1998				
NP-4	1/24/1998				
NP-4	4/9/1998				
NP-4	7/13/1998				
NP-4	7/21/1998				
NP-5	11/4/1981	0.14			
NP-5	11/11/1981				
NP-5	11/13/1981	-0.05	20		
NP-5	11/17/1981	0.19			
NP-5	11/23/1981	0.21			
NP-5	12/7/1981	0.24			

Well Name	Water Depth	USGS Quad	Well Depth		Sample ID	Date	Sampler	Notes
NP-5	37.95	Skute Stone Arroyo		-7	NP-5-7	12/15/1981	QMC	
NP-5	37.58	Skute Stone Arroyo		-8	NP-5-8	12/22/1981	QMC	
NP-5	37.66	Skute Stone Arroyo		-9	NP-5-9	1/5/1982	QMC	
NP-5	37.58	Skute Stone Arroyo		-10	NP-5-10	1/18/1982	QMC	
NP-5	37.58	Skute Stone Arroyo		-11	NP-5-11	1/26/1982	QMC	
NP-5	37.75	Skute Stone Arroyo		-12	NP-5-12	2/16/1982	QMC	
NP-5	37.7	Skute Stone Arroyo		-13	NP-5-13	2/22/1982	QMC	
NP-5	37.83	Skute Stone Arroyo		-14	NP-5-14	3/1/1982	QMC	
NP-5	34.08	Skute Stone Arroyo		-15	NP-5-15	4/16/1982	QMC	
NP-5	33.58	Skute Stone Arroyo		-16	NP-5-16	4/26/1982	QMC	
NP-5	27.16	Skute Stone Arroyo		-17	NP-5-17	5/17/1982	QMC	
NP-5	28.5	Skute Stone Arroyo		-18	NP-5-18	5/17/1982	QMC	
NP-5		Skute Stone Arroyo		-19	NP-5-19	5/24/1982	QMC	
NP-5		Skute Stone Arroyo		-20	NP-5-20	5/28/1982	QMC	
NP-5	23.7	Skute Stone Arroyo		-21	NP-5-21	6/8/1982	QMC	
NP-5	23.67	Skute Stone Arroyo		-22	NP-5-22	6/14/1982	QMC	
NP-5	18	Skute Stone Arroyo		-23	NP-5-23	6/30/1982	QMC	
NP-5	18	Skute Stone Arroyo		-24	NP-5-24	7/26/1982	QMC	
NP-5	15.9	Skute Stone Arroyo		-25	NP-5-25	8/18/1982	QMC	
NP-5	14.9	Skute Stone Arroyo		-26	NP-5-26	9/2/1982	EID	
NP-5	14.4	Skute Stone Arroyo		-27	NP-5-27	9/14/1982	QMC	
NP-5	13.6	Skute Stone Arroyo		-28	NP-5-28	10/18/1982	QMC	
NP-5	13.6	Skute Stone Arroyo		-29	NP-5-29	10/27/1982	QMC	
NP-5	13.4	Skute Stone Arroyo		-30	NP-5-30	11/11/1982	QMC	
NP-5	13.6	Skute Stone Arroyo		-31	NP-5-31	12/28/1982	QMC	
NP-5	13.9	Skute Stone Arroyo		-32	NP-5-32	2/21/1983	QMC	
NP-5	14.8	Skute Stone Arroyo		-33	NP-5-33	5/6/1983	QMC	
NP-5	14.8	Skute Stone Arroyo		-34	NP-5-34	5/13/1983	QMC	
NP-5	15.3	Skute Stone Arroyo		-35	NP-5-35	6/2/1983	QMC	
NP-5	15.9	Skute Stone Arroyo		-36	NP-5-36	7/5/1983	QMC	
NP-5	16.6	Skute Stone Arroyo		-37	NP-5-37	8/9/1983	QMC	
NP-5	16.6	Skute Stone Arroyo		-38	NP-5-38	8/25/1983	QMC	
NP-5	17	Skute Stone Arroyo		-39	NP-5-39	10/20/1983	QMC	
NP-5	17	Skute Stone Arroyo		-40	NP-5-40	11/1/1983	QMC	
NP-5	16.8	Skute Stone Arroyo		-41	NP-5-41	12/7/1983	QMC	
NP-5	17.3	Skute Stone Arroyo		-42	NP-5-42	1/28/1984	QMC	

Well Name	Water Depth	USGS Quad	Well Depth		Sample ID	Date	Sampler	Notes
NP-5	17.4	Skute Stone Arroyo		-43	NP-5-43	2/13/1984	QMC	
NP-5	17.5	Skute Stone Arroyo		-44	NP-5-44	3/1/1984	QMC	
NP-5	17.5	Skute Stone Arroyo		-45	NP-5-45	3/16/1984	CFP	
NP-5	17.8	Skute Stone Arroyo		-46	NP-5-46	4/18/1984	CFP	
NP-5	18.1	Skute Stone Arroyo		-47	NP-5-47	5/22/1984	CFP	
NP-5	18.1	Skute Stone Arroyo		-48	NP-5-48	5/30/1984	CFP	
NP-5	18.2	Skute Stone Arroyo		-49	NP-5-49	6/26/1984	CFP	
NP-5	18.3	Skute Stone Arroyo		-50	NP-5-50	7/25/1984	CFP	
NP-5	18.5	Skute Stone Arroyo		-51	NP-5-51	8/27/1984	CFP	
NP-5	18.6	Skute Stone Arroyo		-52	NP-5-52	9/12/1984	CFP	
NP-5	18.6	Skute Stone Arroyo		-53	NP-5-53	9/21/1984	CFP	
NP-5	19	Skute Stone Arroyo		-54	NP-5-54	11/19/1984	CFP	
NP-5	19	Skute Stone Arroyo		-55	NP-5-55	11/27/1984	CFP	
NP-5	19	Skute Stone Arroyo		-56	NP-5-56	12/17/1984	CFP	
NP-5	18.9	Skute Stone Arroyo		-57	NP-5-57	5/17/1985	CFP	
NP-5	18.9	Skute Stone Arroyo		-58	NP-5-58	11/13/1985	CFP	
NP-5	18	Skute Stone Arroyo		-59	NP-5-59	5/23/1986	CFP	
NP-5	18.3	Skute Stone Arroyo		-60	NP-5-60	10/8/1986	CFP	
NP-5		Skute Stone Arroyo		-61	NP-5-61	3/30/1989	EID	
NP-5	17.17	Skute Stone Arroyo		-62	NP-5-62	8/29/1991	Irwin	lab pH
NP-5	18.75	Skute Stone Arroyo		-63	NP-5-63	11/26/1991	Hood	lab pH
NP-5	18.33	Skute Stone Arroyo		-64	NP-5-64	3/15/1992	Irwin	lab pH
NP-5		Skute Stone Arroyo		-65	NP-5-65	5/25/1992	Irwin	lab pH
NP-5		Skute Stone Arroyo		-66	NP-5-66	7/16/1992	Irwin	lab pH
NP-5	18.58	Skute Stone Arroyo		-67	NP-5-67	10/8/1992	Irwin	lab pH
NP-5	18.5	Skute Stone Arroyo		-68	NP-5-68	11/27/1992	Hood	lab pH
NP-5		Skute Stone Arroyo		-69	NP-5-69	12/15/1992	Irwin	lab pH
NP-5	18.58	Skute Stone Arroyo		-70	NP-5-70	2/25/1993	Irwin	lab pH
NP-5		Skute Stone Arroyo		-71	NP-5-71	3/30/1993	JWS	
NP-5		Skute Stone Arroyo		-72	NP-5-72	9/28/1993	Irwin	lab pH
NP-5	18.74	Skute Stone Arroyo		-73	NP-5-73	5/24/1994	SRK	
NP-5		Skute Stone Arroyo		-74	NP-5-74	6/23/1994	Irwin	lab pH
NP-5		Skute Stone Arroyo		-75	NP-5-75	7/23/1994	SRK	
NP-5		Skute Stone Arroyo		-76	NP-5-76	9/22/1994	Irwin	lab pH
NP-5		Skute Stone Arroyo		-77	NP-5-77	1/29/1995	Irwin	lab pH
NP-5		Skute Stone Arroyo		-78	NP-5-78	3/29/1995	Irwin	lab pH

Well Name	Water Depth	USGS Quad	Well Depth	Sample ID	Date	Sampler	Notes
NP-5	20.08	Skute Stone Arroyo	-79	NP-5-79	6/27/1995	Irwin	lab pH
NP-5		Skute Stone Arroyo	-80	NP-5-80	9/21/1995	Irwin	lab pH
NP-5		Skute Stone Arroyo	-81	NP-5-81	1/10/1996	Irwin	lab pH
NP-5		Skute Stone Arroyo	-82	NP-5-82	4/3/1996	Irwin	lab pH
NP-5		Skute Stone Arroyo	-83	NP-5-83	6/1/1996		
NP-5		Skute Stone Arroyo	-84	NP-5-84	9/25/1996	Irwin	lab pH
NP-5		Skute Stone Arroyo	-85	NP-5-85	1/15/1997	Irwin	lab pH
NP-5		Skute Stone Arroyo	-86	NP-5-86	4/1/1997		
NP-5		Skute Stone Arroyo	-87	NP-5-87	7/1/1997		
NP-5		Skute Stone Arroyo	-88	NP-5-88	10/1/1997		
NP-5	21.58	Skute Stone Arroyo	-89	NP-5-89	1/15/1998	Irwin	
NP-5	21.25	Skute Stone Arroyo	-90	NP-5-90	4/9/1998	Irwin	
NP-5	21.5	Skute Stone Arroyo	-91	NP-5-91	7/13/1998	Irwin	
O. Williams			-1	O. Williams-1	12/19/1945		
O. Williams			-2	O. Williams-2	6/13/1946		
Pague		Hillsboro	-1	Pague-1	8/20/1946		
Paxton		Hillsboro	-1	Paxton-1	4/14/1998	Goff	
Paxton		Hillsboro	-2	Paxton-2	7/21/1998	Brownfield	
PW-1		Skute Stone Arroyo	-1	PW-1-1	12/23/1975		Production Well
PW-1		Skute Stone Arroyo	-2	PW-1-2	8/14/1981	SHB	Production Well
PW-1	325.02	Skute Stone Arroyo	-3	PW-1-3	8/2/1994	SRK	
PW-2		Skute Stone Arroyo	-1	PW-2-1	1/15/1976	SHB	Production Well
PW-2		Skute Stone Arroyo	-2	PW-2-2	11/27/1984	SHB	Production Well
PW-2	302.92	Skute Stone Arroyo	-3	PW-2-3	8/2/1994	SRK	Production Well
PW-3		Skute Stone Arroyo	-1	PW-3-1	1/27/1976	SHB	Production Well
PW-3		Skute Stone Arroyo	-2	PW-3-2	8/14/1981	SHB	Production Well
PW-3	347.1	Skute Stone Arroyo	-3	PW-3-3	8/2/1994	SRK	
PW-4	285.42	Skute Stone Arroyo	-1	PW-4-1	8/2/1994	SRK	Production Well
QMC-4			-1	QMC-4-1	3/27/1981	SHB	Unknown-SHB (19
Saladone Well		Saladone Tank	-1	Saladone Well-1	12/5/1992	Adkins	
SHB-27	38		-1	SHB-27-1	9/22/1976	SHB	geotech boring, water
SHB-28	29		-1	SHB-28-1	9/22/1976	SHB	geotech boring, water
SHB-29	67		-1	SHB-29-1	9/22/1976	SHB	geotech boring, water
SHB-30	73		-1	SHB-30 -1	9/22/1976	SHB	geotech boring, water
SHB-34	72		-1	SHB-34-1	9/22/1976	SHB	HCO3, cond, SO4, CI
Shipping Pen		Saladone Tank	-1	Shipping Pen-1	12/18/1992	Adkins	

Well Name	Water Depth	USGS Quad	Well Depth	Sample ID	Date	Sampler	Notes
Stone				-1 Stone-1	7/31/1947		
Young 1				-1 Young 1-1	7/31/1947		
Young 2				-1 Young 2-1	7/31/1947		

Well Name	Date	Latitude	Longitude	UTM_easting	UTM_northing	UTM_zone	Elevation	Filtered?	Chloride	Sulfate
NP-5	12/15/1981	32.95888	107.49677	266618	3649305	13	5186	TRUE	36	168
NP-5	12/22/1981	32.95888	107.49677	266618	3649305	13	5186	TRUE	36	161
NP-5	1/5/1982	32.95888	107.49677	266618	3649305	13	5186	TRUE	34	163
NP-5	1/18/1982	32.95888	107.49677	266618	3649305	13	5186	FALSE		
NP-5	1/26/1982	32.95888	107.49677	266618	3649305	13	5186	TRUE	32	158
NP-5	2/16/1982	32.95888	107.49677	266618	3649305	13	5186	FALSE		
NP-5	2/22/1982	32.95888	107.49677	266618	3649305	13	5186	TRUE	32	150
NP-5	3/1/1982	32.95888	107.49677	266618	3649305	13	5186	FALSE		
NP-5	4/16/1982	32.95888	107.49677	266618	3649305	13	5186	FALSE		
NP-5	4/26/1982	32.95888	107.49677	266618	3649305	13	5186	TRUE	30	154
NP-5	5/17/1982	32.95888	107.49677	266618	3649305	13	5186	TRUE	36	165
NP-5	5/17/1982	32.95888	107.49677	266618	3649305	13	5186	FALSE		
NP-5	5/24/1982	32.95888	107.49677	266618	3649305	13	5186	TRUE		
NP-5	5/28/1982	32.95888	107.49677	266618	3649305	13	5186	TRUE		
NP-5	6/8/1982	32.95888	107.49677	266618	3649305	13	5186	TRUE	30	150
NP-5	6/14/1982	32.95888	107.49677	266618	3649305	13	5186	FALSE		
NP-5	6/30/1982	32.95888	107.49677	266618	3649305	13	5186	TRUE	28	133
NP-5	7/26/1982	32.95888	107.49677	266618	3649305	13	5186	FALSE		
NP-5	8/18/1982	32.95888	107.49677	266618	3649305	13	5186	FALSE		
NP-5	9/2/1982	32.95888	107.49677	266618	3649305	13	5186	TRUE	33.98	137.2
NP-5	9/14/1982	32.95888	107.49677	266618	3649305	13	5186	FALSE		
NP-5	10/18/1982	32.95888	107.49677	266618	3649305	13	5186	FALSE		
NP-5	10/27/1982	32.95888	107.49677	266618	3649305	13	5186	TRUE	34	139
NP-5	11/11/1982	32.95888	107.49677	266618	3649305	13	5186	FALSE		
NP-5	12/28/1982	32.95888	107.49677	266618	3649305	13	5186	FALSE		
NP-5	2/21/1983	32.95888	107.49677	266618	3649305	13	5186	TRUE	26	139
NP-5	5/6/1983	32.95888	107.49677	266618	3649305	13	5186	FALSE		
NP-5	5/13/1983	32.95888	107.49677	266618	3649305	13	5186	TRUE	70	134
NP-5	6/2/1983	32.95888	107.49677	266618	3649305	13	5186	FALSE		
NP-5	7/5/1983	32.95888	107.49677	266618	3649305	13	5186	FALSE		
NP-5	8/9/1983	32.95888	107.49677	266618	3649305	13	5186	TRUE	26	108
NP-5	8/25/1983	32.95888	107.49677	266618	3649305	13	5186	FALSE		
NP-5	10/20/1983	32.95888	107.49677	266618	3649305	13	5186	FALSE		
NP-5	11/1/1983	32.95888	107.49677	266618	3649305	13	5186	TRUE	30	111
NP-5	12/7/1983	32.95888	107.49677	266618	3649305	13	5186	FALSE		
NP-5	1/28/1984	32.95888	107.49677	266618	3649305	13	5186	FALSE		

Well Name	Date	Latitude	Longitude	UTM_easting	UTM_northing	UTM_zone	Elevation	Filtered?	Chloride	Sulfate
NP-5	2/13/1984	32.95888	107.49677	266618	3649305	13	5186	FALSE		
NP-5	3/1/1984	32.95888	107.49677	266618	3649305	13	5186	FALSE		
NP-5	3/16/1984	32.95888	107.49677	266618	3649305	13	5186	TRUE	26	130
NP-5	4/18/1984	32.95888	107.49677	266618	3649305	13	5186	FALSE		
NP-5	5/22/1984	32.95888	107.49677	266618	3649305	13	5186	FALSE		
NP-5	5/30/1984	32.95888	107.49677	266618	3649305	13	5186	TRUE	22	139
NP-5	6/26/1984	32.95888	107.49677	266618	3649305	13	5186	FALSE		
NP-5	7/25/1984	32.95888	107.49677	266618	3649305	13	5186	FALSE		
NP-5	8/27/1984	32.95888	107.49677	266618	3649305	13	5186	FALSE		
NP-5	9/12/1984	32.95888	107.49677	266618	3649305	13	5186	TRUE	28	125
NP-5	9/21/1984	32.95888	107.49677	266618	3649305	13	5186	FALSE		
NP-5	11/19/1984	32.95888	107.49677	266618	3649305	13	5186	FALSE		
NP-5	11/27/1984	32.95888	107.49677	266618	3649305	13	5186	TRUE	28	120
NP-5	12/17/1984	32.95888	107.49677	266618	3649305	13	5186	FALSE		
NP-5	5/17/1985	32.95888	107.49677	266618	3649305	13	5186	FALSE	28	130
NP-5	11/13/1985	32.95888	107.49677	266618	3649305	13	5186	FALSE	24	134
NP-5	5/23/1986	32.95888	107.49677	266618	3649305	13	5186	FALSE	28	120
NP-5	10/8/1986	32.95888	107.49677	266618	3649305	13	5186	FALSE	28	113
NP-5	3/30/1989	32.95888	107.49677	266618	3649305	13	5186	TRUE	32	125
NP-5	8/29/1991	32.95888	107.49677	266618	3649305	13	5186	FALSE	38.7	152.1
NP-5	11/26/1991	32.95888	107.49677	266618	3649305	13	5186	FALSE	37.7	129.5
NP-5	3/15/1992	32.95888	107.49677	266618	3649305	13	5186	FALSE	46.7	140.7
NP-5	5/25/1992	32.95888	107.49677	266618	3649305	13	5186	FALSE	75.5	131.1
NP-5	7/16/1992	32.95888	107.49677	266618	3649305	13	5186	FALSE	37.8	132.4
NP-5	10/8/1992	32.95888	107.49677	266618	3649305	13	5186	FALSE	39.4	133.2
NP-5	11/27/1992	32.95888	107.49677	266618	3649305	13	5186	FALSE	117.2	133.9
NP-5	12/15/1992	32.95888	107.49677	266618	3649305	13	5186	FALSE	40.4	104
NP-5	2/25/1993	32.95888	107.49677	266618	3649305	13	5186	FALSE	41.4	140.8
NP-5	3/30/1993	32.95888	107.49677	266618	3649305	13	5186	FALSE	39	146
NP-5	9/28/1993	32.95888	107.49677	266618	3649305	13	5186	FALSE	48.1	109.2
NP-5	5/24/1994	32.95888	107.49677	266618	3649305	13	5186	FALSE	41	130
NP-5	6/23/1994	32.95888	107.49677	266618	3649305	13	5186	FALSE	54.1	142.3
NP-5	7/23/1994	32.95888	107.49677	266618	3649305	13	5186	TRUE	41	131
NP-5	9/22/1994	32.95888	107.49677	266618	3649305	13	5186	FALSE	42.8	117.7
NP-5	1/29/1995	32.95888	107.49677	266618	3649305	13	5186	FALSE	43.5	101.2
NP-5	3/29/1995	32.95888	107.49677	266618	3649305	13	5186	FALSE	42.4	130.8

Well Name	Date	Latitude	Longitude	UTM_easting	UTM_northing	UTM_zone	Elevation	Filtered?	Chloride	Sulfate
NP-5	6/27/1995	32.95888	107.49677	266618	3649305	13	5186	FALSE	43.4	119.4
NP-5	9/21/1995	32.95888	107.49677	266618	3649305	13	5186	FALSE	44.3	134.6
NP-5	1/10/1996	32.95888	107.49677	266618	3649305	13	5186	FALSE	41.6	136.6
NP-5	4/3/1996	32.95888	107.49677	266618	3649305	13	5186	FALSE	31.8	130
NP-5	6/1/1996	32.95888	107.49677	266618	3649305	13	5186		47.3	118.1
NP-5	9/25/1996	32.95888	107.49677	266618	3649305	13	5186	TRUE	42.5	129.4
NP-5	1/15/1997	32.95888	107.49677	266618	3649305	13	5186	TRUE	45.7	140.69
NP-5	4/1/1997	32.95888	107.49677	266618	3649305	13	5186	TRUE	47	151
NP-5	7/1/1997	32.95888	107.49677	266618	3649305	13	5186	TRUE	44.8	134
NP-5	10/1/1997	32.95888	107.49677	266618	3649305	13	5186	TRUE	45.3	132
NP-5	1/15/1998	32.95888	107.49677	266618	3649305	13	5186	TRUE	47.9	147
NP-5	4/9/1998	32.95888	107.49677	266618	3649305	13	5186	TRUE	47.8	135
NP-5	7/13/1998	32.95888	107.49677	266618	3649305	13	5186	TRUE	45.2	141
O. Williams	12/19/1945							FALSE	425	62
O. Williams	6/13/1946							FALSE	418	66
Pague	8/20/1946							FALSE	26	80
Paxton	4/14/1998	32.94392	107.53059	263416	3647722	13	5500	TRUE	25.5	163
Paxton	7/21/1998	32.94392	107.53059	263416	3647722	13	5500	TRUE	49.7	265
PW-1	12/23/1975	32.96935	107.38766	276846	3650229	13	4693	FALSE	16	10
PW-1	8/14/1981	32.96935	107.38766	276846	3650229	13	4693	FALSE	32	24
PW-1	8/2/1994	32.96935	107.38766	276846	3650229	13	4693	FALSE		
PW-2	1/15/1976	32.96311	107.38526	277055	3649533	13	4670	FALSE	17	-5
PW-2	11/27/1984	32.96311	107.38526	277055	3649533	13	4670	FALSE	20	125
PW-2	8/2/1994	32.96311	107.38526	277055	3649533	13	4670	TRUE	24	27
PW-3	1/27/1976	32.96851	107.39606	276059	3650155	13	4717	FALSE	24	-5
PW-3	8/14/1981	32.96851	107.39606	276059	3650155	13	4717	FALSE	66	31
PW-3	8/2/1994	32.96851	107.39606	276059	3650155	13	4717	FALSE		
PW-4	8/2/1994	32.96856	107.40469	275252	3650178	13	4645	TRUE	27	17
QMC-4	3/27/1981							TRUE		
Saladone Well	12/5/1992							FALSE		23
SHB-27	9/22/1976							TRUE	20.6	233
SHB-28	9/22/1976							TRUE	51.2	353
SHB-29	9/22/1976							TRUE		
SHB-30	9/22/1976							TRUE	21	145
SHB-34	9/22/1976							TRUE	-1	-1
Shipping Pen	12/18/1992							FALSE		19.2

Well Name	Date	Latitude	Longitude	UTM_easting	UTM_northing	UTM_zone	Elevation	Filtered?	Chloride	Sulfate
Stone	7/31/1947							FALSE	88	26
Young 1	7/31/1947							FALSE	238	43
Young 2	7/31/1947							FALSE	148	32

Well Name	Date	pH	TDS	Alkalinity	Bicarb	Spec. Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
NP-5	12/15/1981	7.8	500				1.2	3.3	-0.01		-0.01
NP-5	12/22/1981	7.9	460				1.1	3.8	-0.01		-0.01
NP-5	1/5/1982	7.7	420				1.1	4.1	-0.01		-0.01
NP-5	1/18/1982										
NP-5	1/26/1982	8	440				1.1	2.9			
NP-5	2/16/1982										
NP-5	2/22/1982	8	450				1	2			
NP-5	3/1/1982										
NP-5	4/16/1982										
NP-5	4/26/1982	7.9	450				1.1	1.1			
NP-5	5/17/1982	8	490				1.1	6.7			
NP-5	5/17/1982										
NP-5	5/24/1982										
NP-5	5/28/1982										
NP-5	6/8/1982	8.1	420				0.9	4.5			
NP-5	6/14/1982										
NP-5	6/30/1982	8.1	460				0.9	3.9			
NP-5	7/26/1982										
NP-5	8/18/1982										
NP-5	9/2/1982	7.6	472		206	650	0.82	4.2			
NP-5	9/14/1982										
NP-5	10/18/1982										
NP-5	10/27/1982	8	440				0.8	3.7			
NP-5	11/11/1982										
NP-5	12/28/1982										
NP-5	2/21/1983	8.3	420				0.5	1.3			
NP-5	5/6/1983										
NP-5	5/13/1983	8.9	290				0.4	0.2			
NP-5	6/2/1983										
NP-5	7/5/1983										
NP-5	8/9/1983	8.1	460				0.8	3.7			
NP-5	8/25/1983										
NP-5	10/20/1983										
NP-5	11/1/1983	8.2	440				0.8	5.2			
NP-5	12/7/1983										
NP-5	1/28/1984										

Well Name	Date	pH	TDS	Alkalinity	Bicarb	Spec. Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
NP-5	2/13/1984										
NP-5	3/1/1984										
NP-5	3/16/1984	8	380				0.4	3			
NP-5	4/18/1984										
NP-5	5/22/1984										
NP-5	5/30/1984	7.8	400				0.8	2.9			
NP-5	6/26/1984										
NP-5	7/25/1984										
NP-5	8/27/1984										
NP-5	9/12/1984	8	420				0.8	3.4			
NP-5	9/21/1984										
NP-5	11/19/1984										
NP-5	11/27/1984	8.2	420				0.8	3.2			
NP-5	12/17/1984										
NP-5	5/17/1985	7.9	450								
NP-5	11/13/1985	7.8	400								
NP-5	5/23/1986	7.9	430								
NP-5	10/8/1986	7.8	420								
NP-5	3/30/1989		458		211				-0.1		
NP-5	8/29/1991	7.68	499								
NP-5	11/26/1991	7	472								
NP-5	3/15/1992	7.89	456								
NP-5	5/25/1992	7.8	490								
NP-5	7/16/1992	7.63	476								
NP-5	10/8/1992	7.64	431								
NP-5	11/27/1992	8.01	475								
NP-5	12/15/1992	7.8	402								
NP-5	2/25/1993	7.65	487								
NP-5	3/30/1993	7.8	488		221	746	0.77	4	0.2		-0.005
NP-5	9/28/1993	7.79	518								
NP-5	5/24/1994	7.84	520		211	680	0.74	3.4	1.1	-0.005	-0.005
NP-5	6/23/1994	7.66	466								
NP-5	7/23/1994	7.89	494		206	749	0.71	3.3	-0.05	-0.005	-0.005
NP-5	9/22/1994	7.73	526								
NP-5	1/29/1995	7.99	490								
NP-5	3/29/1995	7.94	449								

Well Name	Date	pH	TDS	Alkalinity	Bicarb	Spec. Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
NP-5	6/27/1995	7.64	525								
NP-5	9/21/1995	7.71	483								
NP-5	1/10/1996	8.04	406								
NP-5	4/3/1996	7.67	405								
NP-5	6/1/1996	7.52	457								
NP-5	9/25/1996	8.09	504								
NP-5	1/15/1997	7.76	498								
NP-5	4/1/1997		526				0.7				
NP-5	7/1/1997	7.58	478								
NP-5	10/1/1997	7.79	473								
NP-5	1/15/1998	7.41	489			824	0.86	3.73			
NP-5	4/9/1998		493			770	0.8	3.7			
NP-5	7/13/1998		503			605	0.86	3.5			
O. Williams	12/19/1945		883		96	1609	0.6	1.9			
O. Williams	6/13/1946		847		98	1620	0.4	2.2			
Pague	8/20/1946		348		242	409	1.2	1.2			
Paxton	4/14/1998	7.77	773			936	0.83	1.9			
Paxton	7/21/1998		741				1.04	0.09			
PW-1	12/23/1975	7.8	217		145	340	0.46	3.5			
PW-1	8/14/1981	8.1	250		171		0.9	0.7			-0.01
PW-1	8/2/1994										
PW-2	1/15/1976	8.1	257		153	310	0.66	3.5			
PW-2	11/27/1984	7.9	470				0.6	1.7			
PW-2	8/2/1994	7.63	338		273	506	0.39	-1	-0.05	0.011	-0.005
PW-3	1/27/1976	8	243		158	330	0.64	2.6			
PW-3	8/14/1981	8.2	300		139		2.5	0.8			-0.01
PW-3	8/2/1994										
PW-4	8/2/1994	7.57	274		190	398	0.46	-1	-0.05	0.0062	0.0058
QMC-4	3/27/1981						2.5	-0.2			-0.01
Saladone Well	12/5/1992	7.91	354	174.8	213.2	429		0.19			
SHB-27	9/22/1976	7.61	434		205	720	0.77	0.8			-0.01
SHB-28	9/22/1976	7.58	840		264	1260	0.97	-0.1			
SHB-29	9/22/1976	7.98	384			640		-0.1			
SHB-30	9/22/1976	7.77	486		211	720	0.79	0.7			0.02
SHB-34	9/22/1976	7.36	50		12	41	0.14	-0.1			
Shipping Pen	12/18/1992	7.92	345	160	195	484		0.66			

Well Name	Date	pH	TDS	Alkalinity	Bicarb	Spec. Cond.	Flouride	Nitrate	Aluminum	Antimony	Arsenic
Stone	7/31/1947		369		188	607	0.6	3.3			
Young 1	7/31/1947		568		122	1030	0.6	0.8			
Young 2	7/31/1947		471		177	800	1	4.1			

Well Name	Date	Boron	Barium	Berrylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
NP-5	12/15/1981	-0.1	-0.2		-0.005	90	-0.01	-0.02	-0.05	-0.1	-0.02
NP-5	12/22/1981	-0.1	-0.2		-0.005	101	-0.01	-0.02	-0.05	-0.1	-0.02
NP-5	1/5/1982	-0.1	-0.2		-0.005	87	-0.01	-0.02	-0.05	0.18	-0.02
NP-5	1/18/1982										
NP-5	1/26/1982				-0.005				-0.05	-0.01	
NP-5	2/16/1982										
NP-5	2/22/1982				-0.005				-0.05	0.12	
NP-5	3/1/1982										
NP-5	4/16/1982										
NP-5	4/26/1982				-0.005				0.31	3.8	
NP-5	5/17/1982				-0.005				-0.05	0.14	
NP-5	5/17/1982										
NP-5	5/24/1982									-0.1	
NP-5	5/28/1982									-0.1	
NP-5	6/8/1982				-0.005				-0.05	0.44	
NP-5	6/14/1982										
NP-5	6/30/1982				-0.005				-0.05	0.36	
NP-5	7/26/1982										
NP-5	8/18/1982										
NP-5	9/2/1982				-0.001	72.6					
NP-5	9/14/1982										
NP-5	10/18/1982										
NP-5	10/27/1982				-0.005				-0.05	0.21	
NP-5	11/11/1982										
NP-5	12/28/1982										
NP-5	2/21/1983				-0.005				-0.05	-0.1	
NP-5	5/6/1983										
NP-5	5/13/1983				-0.005				-0.05	-0.1	
NP-5	6/2/1983										
NP-5	7/5/1983										
NP-5	8/9/1983				-0.005				-0.05	-0.1	
NP-5	8/25/1983										
NP-5	10/20/1983										
NP-5	11/1/1983				-0.005				-0.05	-0.1	
NP-5	12/7/1983										
NP-5	1/28/1984										

Well Name	Date	Boron	Barium	Berrylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
NP-5	2/13/1984										
NP-5	3/1/1984										
NP-5	3/16/1984				-0.005				-0.05	-0.1	
NP-5	4/18/1984										
NP-5	5/22/1984										
NP-5	5/30/1984				-0.005				-0.05	-0.1	
NP-5	6/26/1984										
NP-5	7/25/1984										
NP-5	8/27/1984										
NP-5	9/12/1984				-0.005				-0.05	-0.1	
NP-5	9/21/1984										
NP-5	11/19/1984										
NP-5	11/27/1984				-0.005				-0.05	-0.1	
NP-5	12/17/1984										
NP-5	5/17/1985										
NP-5	11/13/1985										
NP-5	5/23/1986										
NP-5	10/8/1986										
NP-5	3/30/1989	-0.1	-0.1	-0.1	-0.1	82	-0.1	-0.05	-0.1	-0.1	-0.1
NP-5	8/29/1991										
NP-5	11/26/1991										
NP-5	3/15/1992										
NP-5	5/25/1992										
NP-5	7/16/1992										
NP-5	10/8/1992										
NP-5	11/27/1992										
NP-5	12/15/1992								0.025		
NP-5	2/25/1993										
NP-5	3/30/1993	0.04	-0.5		-0.002	76	-0.02	-0.05	-0.01	0.29	-0.02
NP-5	9/28/1993										
NP-5	5/24/1994		-0.1		-0.0005	86	-0.025		-0.025	1.2	0.0077
NP-5	6/23/1994										
NP-5	7/23/1994	-0.1	-0.1	-0.002	-0.0005	79	-0.025	-0.05	-0.025	-0.05	-0.005
NP-5	9/22/1994										
NP-5	1/29/1995										
NP-5	3/29/1995										

Well Name	Date	Boron	Barium	Berrylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
NP-5	6/27/1995										
NP-5	9/21/1995										
NP-5	1/10/1996										
NP-5	4/3/1996										
NP-5	6/1/1996										
NP-5	9/25/1996										
NP-5	1/15/1997										
NP-5	4/1/1997								-0.005	0.25	
NP-5	7/1/1997										
NP-5	10/1/1997										
NP-5	1/15/1998								-0.005	0.15	
NP-5	4/9/1998								-0.005	-0.05	
NP-5	7/13/1998								-0.005	0.02	
O. Williams	12/19/1945					105					
O. Williams	6/13/1946					108					
Pague	8/20/1946					63					
Paxton	4/14/1998					140.5			0.038	0.85	
Paxton	7/21/1998					69			-0.005	0.17	
PW-1	12/23/1975					22					
PW-1	8/14/1981					28			-0.05	0.2	-0.02
PW-1	8/2/1994										
PW-2	1/15/1976					21					
PW-2	11/27/1984				-0.005				-0.05	-0.1	
PW-2	8/2/1994	-0.1	-0.1	-0.002	-0.0005	60	-0.025	-0.05	-0.025	0.062	-0.005
PW-3	1/27/1976					23					
PW-3	8/14/1981					16			-0.05	0.31	-0.02
PW-3	8/2/1994										
PW-4	8/2/1994	-0.1	-0.1	-0.002	-0.0005	21	-0.025	-0.05	-0.025	-0.05	-0.005
QMC-4	3/27/1981								-0.05		-0.02
Saladone Well	12/5/1992					54.8					
SHB-27	9/22/1976	-0.1			-0.001	5.86	0.002	-0.001	0.002	0.007	-0.001
SHB-28	9/22/1976	-0.1			-0.001	163	0.002	-0.001	0.005	0.015	-0.001
SHB-29	9/22/1976	-0.1			0.001	65.1	0.004	-0.001	0.002	0.52	0.002
SHB-30	9/22/1976	-0.1			-0.001	84.8	0.004	-0.001	0.002	0.009	-0.001
SHB-34	9/22/1976	-0.1			0.001	3.67	0.002	-0.001	0.002	0.009	-0.001
Shipping Pen	12/18/1992					54					

Well Name	Date	Boron	Barium	Berrylium	Cadmium	Calcium	Chromium	Cobalt	Copper	Iron	Lead
Stone	7/31/1947					39					
Young 1	7/31/1947					66					
Young 2	7/31/1947					44					

Well Name	Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium
NP-5	12/15/1981		0.08	-0.001	-0.05	-0.05		-0.005	-0.02	
NP-5	12/22/1981		-0.05	-0.001	-0.05	-0.05		-0.005	-0.02	
NP-5	1/5/1982		-0.05	-0.001	-0.05	-0.05		-0.02	-0.02	
NP-5	1/18/1982									
NP-5	1/26/1982		-0.05	-0.001	-0.1			-0.005		
NP-5	2/16/1982									
NP-5	2/22/1982		-0.05	-0.001	-0.05	-0.05		-0.005		
NP-5	3/1/1982									
NP-5	4/16/1982									
NP-5	4/26/1982		6.9	-0.001	-0.05			-0.005		
NP-5	5/17/1982		-0.05	-0.001	-0.05			-0.005		
NP-5	5/17/1982									
NP-5	5/24/1982		-0.05							
NP-5	5/28/1982		-0.05							
NP-5	6/8/1982		-0.05	-0.001	-0.05			-0.005		
NP-5	6/14/1982									
NP-5	6/30/1982		-0.05	-0.001	-0.05			-0.005		
NP-5	7/26/1982									
NP-5	8/18/1982									
NP-5	9/2/1982	21.8	-0.05		-0.01		3.9	-0.005		46
NP-5	9/14/1982									
NP-5	10/18/1982									
NP-5	10/27/1982		-0.05	-0.001	-0.05			-0.005		
NP-5	11/11/1982									
NP-5	12/28/1982									
NP-5	2/21/1983		-0.05	-0.001	-0.05			-0.005		
NP-5	5/6/1983									
NP-5	5/13/1983		-0.05	-0.001	-0.05			-0.005		
NP-5	6/2/1983									
NP-5	7/5/1983									
NP-5	8/9/1983		-0.05	-0.001	-0.05			-0.005		
NP-5	8/25/1983									
NP-5	10/20/1983									
NP-5	11/1/1983		-0.05	-0.001	-0.05			-0.005		
NP-5	12/7/1983									
NP-5	1/28/1984									

Well Name	Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium
NP-5	2/13/1984									
NP-5	3/1/1984									
NP-5	3/16/1984		-0.05	-0.001	-0.05			-0.005		
NP-5	4/18/1984									
NP-5	5/22/1984									
NP-5	5/30/1984		-0.05	-0.001	-0.05			-0.005		
NP-5	6/26/1984									
NP-5	7/25/1984									
NP-5	8/27/1984									
NP-5	9/12/1984		-0.05	-0.001	-0.05			-0.005		
NP-5	9/21/1984									
NP-5	11/19/1984									
NP-5	11/27/1984		-0.05	-0.001	-0.05			-0.005		
NP-5	12/17/1984									
NP-5	5/17/1985									
NP-5	11/13/1985									
NP-5	5/23/1986									
NP-5	10/8/1986									
NP-5	3/30/1989	22	-0.05		-0.1	-0.1	3		-0.1	39
NP-5	8/29/1991									
NP-5	11/26/1991									
NP-5	3/15/1992									
NP-5	5/25/1992									
NP-5	7/16/1992									
NP-5	10/8/1992									
NP-5	11/27/1992									
NP-5	12/15/1992									
NP-5	2/25/1993									
NP-5	3/30/1993	26	0.02	-0.001	-0.02	-0.01	2.5	-0.005	-0.01	43
NP-5	9/28/1993									
NP-5	5/24/1994	26	0.086	-0.001		-0.05	3.4	-0.005	-0.025	40
NP-5	6/23/1994									
NP-5	7/23/1994	24	-0.03	-0.001	-0.05	-0.05	3.1	-0.005	-0.025	45
NP-5	9/22/1994									
NP-5	1/29/1995									
NP-5	3/29/1995									

Well Name	Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium
NP-5	6/27/1995									
NP-5	9/21/1995									
NP-5	1/10/1996									
NP-5	4/3/1996									
NP-5	6/1/1996									
NP-5	9/25/1996									
NP-5	1/15/1997									
NP-5	4/1/1997		-0.02	-0.002				0.0076		
NP-5	7/1/1997									
NP-5	10/1/1997									
NP-5	1/15/1998	24.2		-0.0002	-0.05			-0.05		
NP-5	4/9/1998		-0.02	-0.0002	-0.05			-0.05		
NP-5	7/13/1998		0.05	-0.0002	-0.05			-0.05		
O. Williams	12/19/1945	14								
O. Williams	6/13/1946	15								
Pague	8/20/1946	21								
Paxton	4/14/1998	17.4	-0.02	0.0003	-0.05		0.7	-0.05		66.9
Paxton	7/21/1998	23.5	-0.02	-0.0002	-0.05		4.09	-0.05		110.6
PW-1	12/23/1975	3					4.5			38
PW-1	8/14/1981	4								53
PW-1	8/2/1994									
PW-2	1/15/1976	3					4.3			39
PW-2	11/27/1984		-0.05	-0.001				-0.005		
PW-2	8/2/1994	8.4	0.032	-0.001	-0.05	-0.05	3.4	-0.005	-0.025	46
PW-3	1/27/1976	3					5.1			44
PW-3	8/14/1981	1								87
PW-3	8/2/1994									
PW-4	8/2/1994	1.7	-0.03	-0.001	-0.05	-0.05	3.5	-0.005	-0.025	73
QMC-4	3/27/1981									
Saladone Well	12/5/1992	23					2.16			22.4
SHB-27	9/22/1976	21.4	0.039	-0.0004	0.002		5.86	-0.01	-0.001	51.1
SHB-28	9/22/1976	32	0.42	-0.0004	0.003		11.5	-0.01	-0.001	81.7
SHB-29	9/22/1976	14.5	0.049	-0.0004	0.003		5.02	-0.01	-0.001	60.3
SHB-30	9/22/1976	21.3	0.036	-0.0004	0.002		4.88	-0.01	-0.001	50.6
SHB-34	9/22/1976	0.52	0.004	-0.0004	-0.001		0.63	-0.01	-0.001	2.55
Shipping Pen	12/18/1992	11.4					2.51			29.6

Well Name	Date	Magnesium	Manganese	Mercury	Molybdenum	Nickel	Potassium	Selenium	Silver	Sodium
Stone	7/31/1947	5.7								
Young 1	7/31/1947	7.9								
Young 2	7/31/1947	6.7								

Thallium	Well Name	Date	Zinc	Temp (C)	Tin	Vanadium
	NP-5	12/15/1981	0.37			
	NP-5	12/22/1981	0.32			
	NP-5	1/5/1982	0.4			
	NP-5	1/18/1982				
	NP-5	1/26/1982				
	NP-5	2/16/1982				
	NP-5	2/22/1982				
	NP-5	3/1/1982				
	NP-5	4/16/1982				
	NP-5	4/26/1982				
	NP-5	5/17/1982				
	NP-5	5/17/1982				
	NP-5	5/24/1982				
	NP-5	5/28/1982				
	NP-5	6/8/1982				
	NP-5	6/14/1982				
	NP-5	6/30/1982				
	NP-5	7/26/1982				
	NP-5	8/18/1982				
	NP-5	9/2/1982				
	NP-5	9/14/1982				
	NP-5	10/18/1982				
	NP-5	10/27/1982				
	NP-5	11/11/1982				
	NP-5	12/28/1982				
	NP-5	2/21/1983				
	NP-5	5/6/1983				
	NP-5	5/13/1983				
	NP-5	6/2/1983				
	NP-5	7/5/1983				
	NP-5	8/9/1983				
	NP-5	8/25/1983				
	NP-5	10/20/1983				
	NP-5	11/1/1983				
	NP-5	12/7/1983				
	NP-5	1/28/1984				

Thallium	Well Name	Date	Zinc	Temp (C)	Tin	Vanadium
	NP-5	2/13/1984				
	NP-5	3/1/1984				
	NP-5	3/16/1984				
	NP-5	4/18/1984				
	NP-5	5/22/1984				
	NP-5	5/30/1984				
	NP-5	6/26/1984				
	NP-5	7/25/1984				
	NP-5	8/27/1984				
	NP-5	9/12/1984				
	NP-5	9/21/1984				
	NP-5	11/19/1984				
	NP-5	11/27/1984				
	NP-5	12/17/1984				
	NP-5	5/17/1985				
	NP-5	11/13/1985				
	NP-5	5/23/1986				
	NP-5	10/8/1986				
	NP-5	3/30/1989	0.4		0.1	-0.1
	NP-5	8/29/1991				
	NP-5	11/26/1991				
	NP-5	3/15/1992				
	NP-5	5/25/1992				
	NP-5	7/16/1992				
	NP-5	10/8/1992				
	NP-5	11/27/1992				
	NP-5	12/15/1992				
	NP-5	2/25/1993				
	NP-5	3/30/1993	0.19			
	NP-5	9/28/1993				
	NP-5	5/24/1994	2.3			
	NP-5	6/23/1994				
-0.005	NP-5	7/23/1994	-0.05			
	NP-5	9/22/1994				
	NP-5	1/29/1995				
	NP-5	3/29/1995				

Thallium	Well Name	Date	Zinc	Temp (C)	Tin
	NP-5	6/27/1995			
	NP-5	9/21/1995			
	NP-5	1/10/1996			
	NP-5	4/3/1996			
	NP-5	6/1/1996			
	NP-5	9/25/1996			
	NP-5	1/15/1997			
	NP-5	4/1/1997			
	NP-5	7/1/1997			
	NP-5	10/1/1997			
	NP-5	1/15/1998			
	NP-5	4/9/1998			
	NP-5	7/13/1998			
	O. Williams	12/19/1945		22.2000008	
	O. Williams	6/13/1946			
	Pague	8/20/1946			
	Paxton	4/14/1998			
	Paxton	7/21/1998			
	PW-1	12/23/1975			
	PW-1	8/14/1981	-0.05		
	PW-1	8/2/1994			
	PW-2	1/15/1976			
	PW-2	11/27/1984			
-0.005	PW-2	8/2/1994	-0.05		
	PW-3	1/27/1976			
	PW-3	8/14/1981	0.19		
	PW-3	8/2/1994			
-0.005	PW-4	8/2/1994	-0.05		
	QMC-4	3/27/1981	-0.05		
	Saladone Well	12/5/1992			
	SHB-27	9/22/1976	0.004		
	SHB-28	9/22/1976	0.018		
	SHB-29	9/22/1976	0.16		
	SHB-30	9/22/1976	0.004		
	SHB-34	9/22/1976	0.014		
	Shipping Pen	12/18/1992			

Thallium	Well Name	Date	Zinc	Temp (C)	Tin	Vanadium
	Stone	7/31/1947				
	Young 1	7/31/1947				
	Young 2	7/31/1947				

Appendix B-2

Pre 1980 SHB Groundwater Sample Results

CUSTOMER Sergent, Hauskins & Beckwith
ATTENTION Mr. Booth
ADDRESS 2821 Girard N.E.
CITY Albuquerque, NM 87107
INVOICE NO. 606081

REPORT OF ANALYSIS

SAMPLES RECEIVED 6-4-76

CUSTOMER ORDER NUMBER

TYPE OF ANALYSIS Water Analysis

Analysis	Sample #1	Sample #2	Sample #4
Calcium	117	122	692
Magnesium	25.6	15.5	15.2
Sodium	50.4	76.1	30.0
Potassium	1.78	1.72	1.56
Bicarbonate	228	241	188
Sulfate	137	114	34
Chloride	14.3	16.7	19.9
Fluoride	0.52	0.51	0.44
Boron	< 0.1	< 0.1	< 0.1
Nitrate	1.39	16.8	4.0
Silica	40.9	36.3	41.9
Iron	0.002	0.002	0.004
Manganese	0.003	0.003	0.001
Total Dissolved Solids	520	560	350
Specific Conductance umhos	720	780	480
pH Units	7.78	7.48	8.60
Hardness	301	269	211

APPROVED BY

James J. Mueller, President

6-16-76 PAGE 1 OF 1 PAGE

CEP
Controls for Environmental Pollution, Inc.
1925 Rosina • P. O. Box 5351 • Santa Fe, New Mexico 87501 • Telephone 505/982-8841

CUSTOMER Sergent, Hauskins & Beckwith
ATTENTION Mr. Booth
ADDRESS 2821 Girard N.E.
CITY Albuquerque, NM 87107
INVOICE NO. 606081

REPORT OF ANALYSIS

SAMPLES RECEIVED 6-4-76 | CUSTOMER ORDER NUMBER

TYPE OF ANALYSIS Water Analysis

Analysis	Sample #3	Underflow	Underflow Percolate
Calcium	64.1	80.1	34.5
Magnesium	22.4	4.6	22.1
Sodium	47.2	69.7	106
Potassium	1.75	55.4	2.10
Bicarbonate	137	43.7	120
Sulfate	544	299	258
Chloride	18.9	36.1	41.8
Fluoride	0.77	2.94	1.97
Boron	< 0.1	< 0.1	0.3
Nitrate	1.1	17.7	< 0.1
Silica	42.4	4.2	24.4
Iron	0.017	0.75	0.007
Manganese	0.001	0.095	0.22
Total Dissolved Solids	409	654	672
Specific Conductance umhos	570	960	900
pH	8.16	8.35	7.61
Hardness	215	217	274
Arsenic	0.02	0.02	0.08
Cadmium	< 0.001	< 0.001	< 0.001
Chromium	0.002	0.003	0.002
Cobalt	< 0.001	< 0.001	< 0.001
Copper	< 0.001	0.004	0.002
Cyanide	< 0.01	0.30	9.03

APPROVED BY

James J. Mueller, President
6-16-76 PAGE 1 OF 2 PAGE

Controls for Environmental Pollution, Inc.
1925 Rosina • P. O. Box 5351 • Santa Fe, New Mexico 87501 • Telephone 505/982-4811

CUSTOMER Sergent, Hauskins & Beckwith
ATTENTION Mr. Booth
ADDRESS 2821 Girard N.E.
CITY Albuquerque, NM 87107
INVOICE NO. 606081

REPORT OF ANALYSIS

SAMPLES RECEIVED 6-4-76

CUSTOMER ORDER NUMBER

TYPE OF ANALYSIS Water Analysis

Analysis	Sample #3	Underflow	Underflow Percolate
Lead	0.023	0.002	0.015
Mercury	< 0.0004	< 0.0004	0.0013
Molybdenum	0.001	0.020	0.073
Selenium	< 0.01	< 0.01	0.04
Silver	< 0.001	< 0.001	< 0.001
Zinc	< 0.01	0.01	0.54

APPROVED BY

James J. Mueller, President
6-16-76 PAGE 2 OF 2 PAGE

Controls for Environmental Pollution, Inc.
1925 Rosina • P. O. Box 5351 • Santa Fe, New Mexico 87501 • Telephone 505/

CUSTOMER: Sergent, Hauskins & Beckwith
ATTENTION: Mr. Booth
ADDRESS: 2821 Girard NE
CITY: Albuquerque, NM 87107
INVOICE NO. 606112

REPORT OF ANALYSIS

SAMPLES RECEIVED	6/18/76	CUSTOMER ORDER NUMBER	
TYPE OF ANALYSIS	Water and Soils Analysis - Cyanide		RUSH

Sample Identification	mg/l
Underflow Percolate Pit C 5½ - 9'	0.57
Job No. E76 - 1023 Boring 5 Depth 4½' Blows 25-25-33	ug/gm 0.15
Job N. E76-1023 Boring 5 Depth 14½' Blows 14-15-16	0.98
Job No. E76-1023 Boring 5 Depth 29½' Blows 15-22-29	1.06
Job No. E76-1023 Pit A-1 2' - 15½'	0.32
Job No. E76-1023 Pit C#2 5½ - 9'	0.15

APPROVED BY

James J. Mueller, President
6/22/76

Controls for Environmental Pollution, Inc.
1925 Rosina • P. O. Box 5351 • Santa Fe, New Mexico 87501 • Telephone 505/982-0925

CUSTOMER Sargent, Hauskins & Beckwith
ATTENTION Mr. Booth
ADDRESS 2501 Candelaria Road N.E.
CITY Albuquerque, NM 87107
INVOICE NO. 609066

REPORT OF ANALYSIS

SAMPLES RECEIVED 9/9/76

CUSTOMER ORDER NUMBER

TYPE OF ANALYSIS Soil Analysis -

Analysis	A-1 BH 2½ - 6' mg/l	A-2 BH 2½ - 6' mg/l
Calcium	11.6	8.89
Magnesium	1.8	1.6
Sodium	8.9	9.6
Potassium	1.3	1.2
Bicarbonate (as $CaCO_3$)	40.3	40.8
Sulfate	7	6
Chloride	1.06	< 0.05
Fluoride	0.64	1.08
Boron	0.3	0.1
Nitrate (as N)	3.11	1.14
Silica	6.8	6.8
Iron	0.27	0.33
Manganese	0.01	0.02
Total Dissolved Solids	127	142
Specific Conductance (umhos)	131	109
pH (Units)	8.18	8.20
Hardness (as $CaCO_3$)	51.4	42.5
Arsenic	< 0.01	< 0.01
Cadmium	< 0.001	< 0.001
Chromium	< 0.001	< 0.001
Cobalt	< 0.001	< 0.001
Copper	0.003	0.003
Cyanide	< 0.1	< 0.1
Lead	< 0.001	< 0.001
Mercury	< 0.0004	< 0.0004
Molybdenum	< 0.001	< 0.001
Selenium	< 0.01	< 0.01
Silver	< 0.001	< 0.001
Zinc	0.004	0.004

APPROVED BY
James J. Mueller, President
9/14/76

PAGE 1 OF 1 PAGE

Controls for Environmental Pollution, Inc.
1925 Rosina • P. O. Box 5351 •

CUSTOMER Sargent Hauskins & Beckwith
ATTENTION Mr. Booth
ADDRESS 2501 Candelari Road NE
CITY Albuquerque, NM 87107
INVOICE NO. 610073

REPORT OF ANALYSIS

SAMPLES RECEIVED 9/1/76	CUSTOMER ORDER NUMBER

TYPE OF ANALYSIS .. Soil Analysis -

Analysis	BH F-1 mg/l	BH F-2 mg/l
Calcium	21.4	23.0
Magnesium	1.19	1.57
Sodium	23.7	28.5
Potassium	1.26	1.11
Bicarbonate (as $CaCO_3$)	42.8	42.2
Sulfate	19.4	2.3
Chloride	5.0	10.5
Fluoride	0.66	0.74
Boron	0.2	0.2
Nitrogen Nitrate	5.7	3.7
Silica	48.9	42.7
Iron	0.048	0.063
Manganese	0.002	0.002
Total Dissolved Solids	204	208
Specific Conductance umhos	230	268
pH	7.88	7.80
Hardness (as$CaCO_3$)	56.7	75.7
Arsenic	0.01	< 0.01
Cadmium	0.005	0.005
Chromium	0.004	0.003
Cobalt	< 0.001	< 0.001
Copper	0.008	0.006
Cyanide	< 0.1	< 0.1
Lead	< 0.001	< 0.001
Mercury	< 0.0004	< 0.0004
Molybdenum	0.001	< 0.001
Selenium	< 0.01	< 0.01
Silver	0.009	0.002
Zinc	0.018	0.014

APPROVED BY
James J. Mueller, President
10/14/76

PAGE 1 OF 1 PAGE

Controls for Environmental Pollution, Inc.
1925 Rosina • P. O. Box 5351 • Santa Fe, New Mexico 87501 • Telephone 505/982-9841

CONSULTANTS ON
WATER QUALITY

BACTERIA AND
CHEMICAL ANALYSES

Environmental Biochemists

4115 SILVER AVE., S. E.
ALBUQUERQUE, NEW MEXICO 87108
Telephone (505) 266-9106 – Night 296-6164

E.B. No. 76911
Revised

Sept. 21, 1976

Sergent Hauskins & Beckwith
2821 Gerard N.E.
Albuquerque, N.M.

Att:Gary Allen

In our recent telephone conversation you asked that our previous report be revised to reflect milligrams per liter of the soluble components from soil samples that we analyzed for you. Aqueous suspensions of the soils were made as previously described and were 10;1 ml/g.

	Milligrams per liter	
	BH A-1	BH A-2
Moisture, %	4.22	4.35
pH	6.9	6.5
Hardness	26	26
Cyanide	<0.01	<0.01
Calcium	7.5	7.5
Magnesium	1.8	1.7
Sodium	7.3	9.2
Potassium	1.8	3.4
Iron	0.4	0.5
Manganese	<0.05	<0.05
Arsenic	<0.02	<0.02
Cadmium	<0.05	<0.05
Chromium	<0.05	<0.05
Cobalt	<0.025	<0.025
Copper	<0.01	<0.01
Lead	<0.025	<0.025
Mercury	<0.001	<0.001
Molybdemum	<0.05	<0.05
Selenium	<0.02	<0.02
Silver	<0.01	<0.01
Zinc	<0.025	<0.025
Bicarbonate	41	37.3
Sulfate	<0.05	<0.05
Chloride	7.0	6.0
Fluoride	1.28	1.75
Boron	<0.05	0.2
Nitrate	14.3	11.4
Silica	2.4	2.5
Tot. Diss. Solids	24	68
Conductance, umhos	110	135

Raymond C. Pfleger, Ph.D.

CONSULTANTS ON
WATER QUALITY

BACTERIA AND
CHEMICAL ANALYSES

Environmental Biochemists

4115 SILVER AVE., S. E.
ALBUQUERQUE, NEW MEXICO 87108
Telephone (505) 266-9106 – Night 296-6164

E.B. No. 76925A

Sept. 25, 1976

Sergent-Hauskins & Beckwith
2821 Gerard N.E.
Albuquerque, N.M.

Att: Gary Allen

On Sept. 2, 1976, two soil samples were delivered to our laboratory for analysis. A 10:1 aqueous:soil suspension was made and the components analyzed in the aqueous phase after filtration through a 0.45 um membrane. The soil was screened through a 2mm sieve.

Sample	F 1		F 2
	ppm		ppm
Moisture, %	2.0		2.2
pH	7.56		6.67
Cyanide	0.02		0.03
Bicarbonate	4.91		4.33
Sulfate	31.2		29.2
Chloride	7.5		15.5
Fluoride	0.96		0.98
Nitrate	9.7		5.5
Calcium	11.4		15.0
Magnesium	1.1		0.75
Sodium	8.1		9.1
Potassium	3.2		2.4
Iron	0.3		0.3
Manganese	<0.05		<0.05
Arsenic	<0.02		<0.02
Cadmium	<0.004		<0.004
Chromium	<0.05		<0.05
Cobalt	<0.025		<0.025
Lead	<0.025		<0.025
Molybdemum	<0.05		<0.05
Selenium	<0.02		<0.02
Silver	<0.01		<0.01
Zinc	<0.025		<0.025
Mercury	<0.001		<0.001
Copper	0.02		0.02
Boron	<0.1		<0.1
Conductance	115	(umhos/cm)	125
Silica	11.75		11.0
Hardness	33		40
Total Dissolved Solids	106		96

ppm = parts per million in aqueous phase = milligrams per liter.

Thank you.

Raymond C. Pfleger, Ph.D.

CUSTOMER Sargent, Hauskins & Beckwith
ATTENTION Mr. Booth
ADDRESS 2501 Candelaria Road, N.E.
CITY Albuquerque, NM 87107
INVOICE NO. 610090

REPORT OF ANALYSIS

SAMPLES RECEIVED 9-22-76	CUSTOMER ORDER NUMBER

TYPE OF ANALYSIS: Water Analysis

Analysis	E76-1100 #29 mg/l	E76-1100 #34 mg/l
Calcium	65.1	3.67
Magnesium	14.5	0.52
Sodium	60.3	2.55
Potassium	5.02	0.63
Bicarbonate (as $CaCO_3$)	QNS	12
Sulfate	QNS	<1
Chloride	QNS	<1.0
Fluoride	QNS	0.14
Boron	0.1	<0.1
Nitrate	<0.1	<0.1
Silica	54.0	51.2
Iron	0.052	0.009
Manganese	0.049	0.004
Total Dissolved Solids	384	50
Specific Conductance (umhos)	640	41
pH Units	7.98	7.36
Hardness (as $CaCO_3$)	QNS	517
Arsenic	QNS	QNS
Cadmium	0.001	0.001
Chromium	0.004	0.002
Cobalt	0.001	<0.001
Copper	0.002	0.002

APPROVED BY James J. Mueller /EDH

James J. Mueller, President
10-20-76 PAGE 1 OF 2 PAGE

cep
Controls for Environmental Pollution, Inc.
1925 Rosina • P. O. Box 5351 • Santa Fe, New Mexico 87502

CUSTOMER Sargent, Hauskins & Beckwith
ATTENTION Mr. Booth
ADDRESS 2501 Candelaria Road, N.E.
CITY Albuquerque, NM 87107
INVOICE NO. 610090

REPORT OF ANALYSIS

SAMPLES RECEIVED 9-22-76	CUSTOMER ORDER NUMBER

TYPE OF ANALYSIS Water Analysis

Analysis	E76-1100 #29 mg/l	E76-1100 #34 mg/l
Cyanide	QNS	QNS
Lead	0.002	0.001
Mercury	< 0.0004	< 0.0004
Molybdenum	0.003	< 0.001
Selenium	< 0.01	< 0.01
Silver	< 0.001	< 0.001
Zinc	0.016	0.014

QNS = Quantity of Water not Sufficient for Analysis.

APPROVED BY James J. Mueller, PE

James J. Mueller, President
10-20-76 PAGE 2 OF 2 PAGE

cep
Controls for Environmental Pollution, Inc.
1925 Rosina • P. O. Box 5351 • Santa Fe, New Mexico

CUSTOMER Sargent, Hauskins & Beckwith
ATTENTION Mr. Booth
ADDRESS 2501 Candelaria Road, N.E.
CITY Albuquerque, NM 87107
INVOICE NO. 610090

REPORT OF ANALYSIS

SAMPLES RECEIVED 9-22-76

CUSTOMER ORDER NUMBER

TYPE OF ANALYSIS Water Analysis

Analysis	E76-1100 #30 mg/l	E76-1100 #31 mg/l	E76-1100 #33 mg/l
Calcium	84.8	87.5	163
Magnesium	21.3	21.4	32.0
Sodium	50.6	51.1	81.7
Potassium	4.88	5.86	11.5
Bicarbonate (as $CaCO_3$)	211	205	264
Sulfate	145	233	353
Chloride	21.0	20.6	51.2
Fluoride	0.79	0.77	0.97
Boron	< 0.1	< 0.1	< 0.1
Nitrate	0.7	0.8	< 0.1
Silica	50.7	58.3	53.8
Iron	0.009	0.007	0.015
Manganese	0.036	0.039	0.42
Total Dissolved Solids	486	434	840
Specific Conductance (umhos)	720	720	1260
pH	7.77	7.61	7.58
Hardness (as $CaCO_3$)	318	279	530
Arsenic	0.02	< 0.01	QNS
Cadmium	< 0.001	< 0.001	< 0.001
Chromium	0.004	0.002	0.002
Cobalt	< 0.001	< 0.001	< 0.001
Copper	0.002	0.002	0.005

APPROVED BY James J. Mueller, EDM
James J. Mueller, President
10-20-76 PAGE 1 OF 2 PAGE

cep
Controls for Environmental Pollution, Inc.
1925 Rosina • P. O. Box 5351 • Santa Fe, New Mexico 87502

CUSTOMER Sargent, Hauskins & Beckwith
ATTENTION Mr. Booth
ADDRESS 2501 Candelaria Road, N.E.
CITY Albuquerque, NM 87107
INVOICE NO. 610090

REPORT OF ANALYSIS

SAMPLES RECEIVED	9-22-76	CUSTOMER ORDER NUMBER	
TYPE OF ANALYSIS	Water Analysis		

Analysis	E76-1100 #30 mg/l	E76-1100 #31 mg/l	E76-1100 #33 mg/l
Cyanide	< 0.01	< 0.01	QNS
Lead	< 0.001	< 0.001	< 0.001
Mercury	< 0.0004	< 0.0004	< 0.0004
Molybdenum	0.002	0.002	0.003
Selenium	< 0.01	< 0.01	< 0.01
Silver	< 0.001	< 0.001	< 0.001
Zinc	0.004	0.004	0.018

QNS = Quantity of Water not Sufficient for Analysis.

APPROVED BY James J. Mueller, President
10-20-76

cep
Controls for Environmental Pollution, Inc.
1925 Rosina • P.O. Box 5351 • Santa Fe, New Mexico

CUSTOMER Sergent, Hauskins & Beckwith
ATTENTION Mr. Booth
ADDRESS 2821 Girard NE
CITY Albuquerque, NM 87107
INVOICE NO. 606081

REPORT OF ANALYSIS

SAMPLES RECEIVED	6/4/76	CUSTOMER ORDER NUMBER	
TYPE OF ANALYSIS	Water Analysis - Corrected Report		

Analysis	Sample #1	Sample #2	Sample #4
Calcium	117	122	69.2
Magnesium	25.6	15.5	15.2
Sodium	50.4	76.1	30.0
Potassium	1.78	1.72	1.56
Bicarbonate	228	241	188
Sulfate	137	114	34
Chloride	14.3	16.7	19.9
Fluoride	0.52	0.51	0.44
Boron	< 0.1	< 0.1	< 0.1
Nitrate	1.39	16.8	4.0
Silica	40.9	36.3	41.9
Iron	0.002	0.002	0.004
Manganese	0.003	0.003	0.001
Total Dissolved Solids	520	560	350
Specific Conductance umhos	720	780	480
pH Units	7.78	7.48	8.60
Hardness	301	269	211

APPROVED BY
James J. Mueller, President
6/16/76

Controls for Environmental Pollution, Inc.
1925 Rosina • P. O. Box 5351 • Santa Fe, New Mexico

Figure 4

LOCATION OF WATER WELLS



0 2,000 4,000 6,000

Scale in Feet

Tailings Dam and Pond
Copper Flat Project
Hillsboro, New Mexico
SHB Job No. E80-1030

SERGENT, HAUSKINS & BECKWITH

Appendix C

Whole Rock Chemical Analyses for PW-3, WD-1, and November 20, 1996 Pond Rock Samples

Client : Steffen Robertson and Kirsten
Address : 3232 S. Vance St., Ste. 210
Lakewood, CO 80227
Attn. : Gene Muller
Project : 68605, Copper Flat

Sample Matrix: Waste Rock
Sample ID: 68605, PW-3
Sample Date Time: Unknown

Lab No. : 94-RT/00595
Date Received: 06/10/94

Parameters			
Moisture %	0.3	%	
Phosphorus, total	0.04	%	
Aluminum, total	2950.	mg/kg	4
Antimony, total	-0.10	mg/kg	4
Arsenic, total	1.9	mg/kg	4
Barium, total	24.	mg/kg	4
Boron, total	-2.	mg/kg	4
Cadmium, total	-0.5	mg/kg	4
Calcium, total	700.	mg/kg	4
Chromium, total	-1.	mg/kg	4
Cobalt, total	9.	mg/kg	4
Copper, total	226.	mg/kg	4
Iron, total	40800.	mg/kg	4
Lead, total	4.	mg/kg	4
Magnesium, total	800.	mg/kg	4
Manganese, total	39.	mg/kg	4
Mercury, total	-0.02	mg/kg	4
Molybdenum, total	57.	mg/kg	4
Nickel, total	3.	mg/kg	4
Potassium, total	1300.	mg/kg	4
Selenium, total	9.0	mg/kg	4
Silver, total	-1.	mg/kg	4
Sodium, total	200.	mg/kg	4
Vanadium, total	5.	mg/kg	4
Zinc, total	14.	mg/kg	4

1 EPA SW846, Method 3051 Digestion.

Remarks:
Note: Negative sign "-" denotes that the value is less than "<"

Scott Habermehl, Project Manager/SH.

Frank E. Polniak, Inorganic Laboratory Supervisor/FP

Client : Steffen Robertson and Kirsten
Address : 3232 S. Vance St., Ste. 210
Lakewood, CO 80227
Attn. : Gene Muller
Project : 68605, Copper Flat

Sample Matrix: Waste Rock
Sample ID: 68605, PW-3
Sample Date Time: Unknown

Lab No. : 94-SI/00595
Date Received: 06/10/94

Parameters		
Acid-Base Potent.(CaCO3)	-69.	Tons/1000T
Conductivity, sat. paste	5.94	mmhos/cm 1
pH, saturated paste	2.6	units 1
Neutralization Potential	-0.1	% as CaCO3
Sulfur, total	2.20	%
Sulfur, sulfate	-0.01	%
Sulfur, pyritic	0.84	%

1 Saturated Paste Extraction
Remarks: Negative (-) sign on ABP denotes a negative value
Note: Negative sign "-" denotes that the value is less than "<"

Scott Habermehl, Project Manager

Frank E. Polniak, Inorganic Laboratory Supervisor SH.

ACZ LABORATORIES INC | DATA MANAGEMENT SYSTEM
07/25/94 | ANALYTICAL REPORT | 12:36
Page 1

lient : Steffen Robertson and Kirsten
ddress : 3232 S. Vance St., Ste. 210
Lakewood, CO 80227
ttn. : Gene Muller
roject : 68605, Copper Flat

JUL 28 1994

ample Matrix: Waste Rock
ample ID: 68605, WD 1
ample Date Time: Unknown

Lab No. : 94-RT-00594
Date Received: 06/10/94

Parameters			
Moisture %	0.2	%	
Phosphorus, total	0.01	%	
Aluminum, total	1890.	mg/kg	4
Antimony, total	-0.10	mg/kg	4
Arsenic, total	0.4	mg/kg	4
Barium, total	10.	mg/kg	4
Boron, total	-2.	mg/kg	4
Cadmium, total	-0.5	mg/kg	4
Calcium, total	700.	mg/kg	4
Chromium, total	-1.	mg/kg	4
Cobalt, total	11.	mg/kg	4
Copper, total	186.	mg/kg	4
Iron, total	41600.	mg/kg	4
Lead, total	2.	mg/kg	4
Magnesium, total	200.	mg/kg	4
Manganese, total	8.	mg/kg	4
Mercury, total	-0.02	mg/kg	4
Molybdenum, total	7.	mg/kg	4
Nickel, total	-2.	mg/kg	4
Potassium, total	1200.	mg/kg	4
Selenium, total	3.9	mg/kg	4
Silver, total	-1.	mg/kg	4
Sodium, total	200.	mg/kg	4
Vanadium, total	1.	mg/kg	4
Zinc, total	7.	mg/kg	4

4 EPA SW846, Method 3051 Digestion.

Remarks:
Note: Negative sign "-" denotes that the value is less than "<"

Scott Habermehl, Project Manager

Frank E. Polniak, Inorganic Laboratory Supervisor

00939

Client : Steffen Robertson and Kirsten
Address : 3232 S. Vance St., Ste. 210
Lakewood, CO 80227
Attn. : Gene Muller
Project : 68605, Copper Flat

Sample Matrix: Waste Rock
Sample ID: 68605, PW-1
Sample Date Time: Unknown

Lab No. : 94-SI/00612
Date Received: 06/10/94

Parameters		
Acid-Base Potent.(CaCO3)	-81.	Tons/1000T
Neutralization Potential	3.2	% as CaCO3
Sulfur, total	3.61	%
Sulfur, sulfate	0.14	%
Sulfur, pyritic	2.00	%

Remarks: Negative (-) sign on ABP denotes a negative Value
Note: Negative sign "-" denotes that the value is less than "<"

Scott Habermehl, Project Manager

Frank E. Polniak, Inorganic Laboratory Supervisor /S.H.

Appendix D

D-1
Paste pH and Conductivity Data
Acid-Base Accounting Data
Net Acid Generation Data

D-2
Humidity Cell Data

Appendix D-1

Paste pH and Conductivity Data
Acid-Base Accounting Data
Net Acid Generation Data

1997 Surface Sample Analyses

Sample	Type	Lithology	Visible sulfide %	EC	Paste pH	NAG kg/T H_2SO_4	NAG pH	Sulfate %	Sulfide %	Sulfur Total %	SO_4/S %	AGP m/g $CaCO_3$	NP m/g $CaCO_3$	NNP	NP:AP
WRC 5480 019	HS	QM	2	3020	2.66										
WRC 5480 020	HS	QM	2	878	3.96										
WRC 5480 021	HS	QM	2	1009	4.38										
WRC 5480 022	HS	QM	2	1850	2.97										
WRC 5480 023	HS	QM	2	1880	2.64										
WRC 5480 024	HS	QM	1.5	1190	2.71										
WRC 5480 025	LS	QM	1	637	8.6										
WRC 5480 026	LS	QM	1	129	9.65										
WRC 5480 027	HS	QM	2	1580	2.12										
WRC 5480 028	HS	QM	2	964	4.89										
WRC 5480 029	HS	QM	2	580	3.59										
WRC 5480 030	HS	QM	2	258	5.85										
WRC 5580 005	T	QV(Sternberg)pw2	2	19000	3.79										
WRD 4480 010	LS	QM	1	50	6.06										
WRD 5560 020	LS	QM	1	64	6.72										
WRD 5560 027	HS	QM	2	3990	2.56										
WRD 5560 028	HS	QM	2	730	2.95										
WRD 5560 029	HS	QM	2	1552	2.53										
WRD 5560 030	HS	QM	2	321	4.64										
WRD 5560 031	HS	QM	2	282	4.4										
WRD 5560 032	HS	QM	2	620	2.99										
WRD 5560 034	HS	QM	2	201	3.95										
WRD 5560 035	HS	QM	2	833	4.35										
WRD 5560 036	HS	QM	2	171	3.79										
WRD 5560 037	HS	QM	2	164	7.8										
WRD 5560 038	HS	QM	5	54	6.59	18.33	7.92	0.3	1.2	1.5	20.00	47	30.2	-16.8	0.64
WRD 5560 039	HS	QB	6	1848	2.81	72.13	3.92	0.1	2.1	2.2	4.55	70	0.1	-69.9	0.00
WRD 5560 040	HS	QB	3	456	3.97	36.46	2.98								
WRD 5560 041	HS	QB	4	2190	3.31	50.57	4.18	0.3	1.4	1.7	17.65	53	7.6	-45.4	0.14
WRD 5580 001	LS	QM	1	133	4	21.56	2.27	0.3	0.8	1.1	27.27	33	17.8	-15.2	0.54
WRD 5580 002	HS	QM	3	1422	2.77	34.01	6.00								
WRD 5580 004	O	QB			4.82			0.33	0.1	0.34	97.06	11	0.1	-10.9	0.01
WRD 5580 005	LS	QM	2	93	6.72	29.40	5.01								
WRD 5580 006	T	QM	0.5	212	3.2	30.77	5.06								
WRD 5580 007	HS	QB	2	345	3.02	31.07	4.87								
WRD 5580 008	HS	QB	2	230	5.55	29.01	5.15								
WRD 5580 009	HS	QM	2	325	3.14	28.62	5.01								
WRD 5580 011	HS	QM	2	8	5.6	28.03	5.29								
WRD 5580 012	HS	QM	2	305	5.4	29.11	5.1								
WRD 5580 013	HS	BB	7	2860	2.45	47.14	2.09								
WRD 5580 014	HS	BB	4	21	5	31.85	5.27	0.2	1.96	2.16	9.26	73.8	43.7	-30.1	0.59
WRD 5580 015	HS	QB	4	156	4.45	31.16	3.05								
WRD 5580 016	HS	QM	2	45.6	5.72	22.74	4.06								
WRD 5580 017	HS	QM	2	41	5.54	30.48	5.04								

00943

1997 Surface Sample Analyses

Sample	Type	Lithology	Visible sulfide %	EC	Paste pH	NAG kg/T H_2SO_4	NAG pH	Sulfate %	Sulfide %	Sulfur Total %	SO_4/S %	AGP m/g $CaCO_3$	NP m/g $CaCO_3$	NNP	NP:AP
NRD 5650 017	LS	QM	1	41.4	6.09	23.72	4.11	0.13	0.22	0.35	37.14	11	0.1	-10.9	0.01
NRD 5650 018	HS	QM	2	89	4.82										
NRD 5650 019	HS	QM	2	3620	2.79	46.35	4.40	0.1	1.3	1.4	7.14	45	0.1	-44.9	0.00
SRD 5470 006	HS	QM	2	63	5.94										
SRD 5470 010	LS	QM	1	196	7.05	8.72	2.51								
SRD 5470 011	HS	QV	5	2200	2.54	43.51	3.10	0.21	1.3	1.5	14.00	47	6.7	-40.3	0.14
SRD 5470 012	HS	QB	6	182	7.63			0.46	1.4	1.9	24.21	59	38.9	-20.1	0.66
SRD 5470 013	HS	QM	3	821	4.4										
SRD 5470 014	HS	QB	4	62.9	5.26	5.88	2.29								
SRD 5470 015	HS	QM	3	118.5	5.55										
SRD 5470 016	HS	QM	4	89.6	7.06										
SRD 5470 016	HS	QV	5	6570	2.66										
SRD 5470 017	HS	QB	4	27	5.02	21.56	2.27								
SRD 5470 018	HS	QB	5	1703	3.08										
SRD 5470 019	HS	QV	5	229	4.55										
SRD 5470 020	HS	QM	3	162	7.83	12.74	2.47	0.31	1.1	1.4	22.14	44	36.4	-7.6	0.83
SRD 5470 021	HS	QB	4	321	4.32										
SRD 5470 022	HS	QM	2	386	6.03										
SRD 5470 023	HS	QM	4	27	5.51										
SRD 5470 024	HS	QM	5	3970	2.52										
SRD 5470 025	HS	QM	3	172.2	5.21										
SRD 5470 027	HS	QM	2	3520	2.72	15.78	2.52								
SRD 5490 007	O	QM		42	8.76	19.70	3.32								
SRD 5500 001	HS	QM	2	831	5.31	8.23	4.10	0.37	0.7	1.1	33.64	33	34.2	1.2	1.04
SRD 5500 002	HS	BB	4	33	7.38	22.05	4.63								
SRD 5500 003	O	BB		58.7	4.75										
SRD 5500 004	HS	QB	4	231	5.5										
SRD 5500 005	HS	QV	5	292	6.05	19.01	3.96								
WRC 5440 30	HS	QM	2	227	4.1	15.88									
WRC 5440 31A	LS	QM	0.5		7.91			0.23	0.32	0.55	41.82	33	34.2	1.2	1.04
WRC 5440 31B	T	QM	0.5		8.35			0.21	0.11	0.32	65.63	10	10.1	0.1	1.01
WRC 5440 32	O	QM		347	6.55			0.19	0.05	0.24	79.17	7.5	9.6	2.1	1.28
WRC 5480 006	HS	QB	5	3680	3.7	31.46									
WRC 5480 007	HS	QB	5	1643	3.18	33.52									
WRC 5480 007	HS	QV	5	550	3.41	32.73									
WRC 5480 008	HS	QM	2	785	3.67	15.09									
WRC 5480 009	HS	BB	3	764	3.73	32.54									
WRC 5480 010	HS	BB	4	1338	3.76	28.71									
WRC 5480 012	LS	QB	1	589	4.01	33.81									
WRC 5480 013	LS	QM	1	297	6.95	15.19									
WRC 5480 014	T	QB	0.5	801	4.12	20.19		1.25	0.89	2.08	60.10	65	47.6	-17.4	0.73
WRC 5480 015	HS	QM	2	826	3.42										
WRC 5480 016	LS	QM	1	470	6.26										
WRC 5480 018	HS	QM	2	4840	3.02										

00944

1997 Surface Sample Analyses

Sample	Type	Lithology	Visible sulfide %	EC	Paste pH	NAG kg/T H_2SO_4	NAG pH	Sulfate %	Sulfide %	Sulfur Total %	SO_4/S %	AGP m/g $CaCO_3$	NP m/g $CaCO_3$	NNP	NP:AP
ERD 5500 001	T	QM	1	3140	3.63	29.60	5.11	0.71	0.74	1.45	48.97	45.3	18.9	-26.4	0.42
ERD 5500 002	HS	QB	4	19	7.94	15.48	2.48	0.44	2.46	2.9	15.17	53.1	62.5	9.4	1.18
ERD 5500 004	LS	QM	1	430	5.31										
ERD 5500 005	LS	QM	1	595	3.31										
ERD 5500 006	LS	QM	1.5	891	5.72										
ERD 5500 009	HS	BB	10	4000	2.71	80.75	6.30	0.6	2.3	2.9	20.69	91	9.1	-81.9	0.10
ERD 5500 010	LS	QM	1.5	471	4.55	19.99	3.92								
ERD 5500 012	HS	QM	2	1928	2.71										
ERD 5500 014	HS	QM	2	4370	2.73										
ERD 5510 002	LS	QM	1.5	257	4.71										
ERD 5560 001	O	AN			9.14			0.01	0.005	0.01	100.00	0.3	23.2	22.9	77.33
ERD 5560 002	HS	QM	8	467	6.76			0.3	2.6	2.9	10.34	90	23.7	-66.3	0.26
ERD 5560 006	HS	QB	2	1305	3.38										
ERD 5560 008	HS	QV	5	330	4.08			0.47	1.7	2.2	21.36	68	2	-66	0.03
ERD 5560 010	LS	QM	1.5	708	4.55	23.62	3.87								
ERD 5560 011	HS	QB	3	1565	4.54	22.05	4.07								
ERD 5600 001	LS	QM	1	450	4.44			0.1	0.43	0.53	18.87	17	0.1	-16.9	0.01
ERD 5600 003	HS	QB	3	4230	2.9	33.81	3.19	0.96	1.3	2.2	43.64	69	0.1	-68.9	0.00
ERD 5600 005	T	QB	0.5	2700	3.23	27.05	4.34								
ERD 5600 007	T	QM	0.5	174	6.88	14.31	2.68								
ERD 5600 009	T	QM	0.5	657	4.73										
ERD 5600 011	T	QM	0.5	847	5.43										
ERD 5600 012	T	QM	0.5	254	6.82										
ERD 5600 013	HS	QM	2	321	5.17										
ERD 5600 014	HS	BB	2	2080	3.55										
ERD 5600 070	HS	BB	4	227	4.92	11.27	2.45								
NRD 5620 001	HS	BB	4	41	5.05	10.68	3.41								
NRD 5620 001	HS	QB	5	1193	2.91	19.80	2.45								
NRD 5620 002	HS	QB	6	1717	2.68	77.62	2.98	0.3	2.6	2.9	10.34	90	23.7	-66.3	0.26
NRD 5620 003	HS	QM	4	1111	3.56	57.33	4.12	0.2	1.6	1.8	11.11	55	0.1	-54.9	0.00
NRD 5620 004	O	QM			4.75			0.17	0.1	0.18	94.44	5.6	0.1	-5.5	0.02
NRD 5620 005	T	QV	1	2170	2.81	9.60	4.81								
NRD 5620 006	HS	QM	2	260	3.68										
NRD 5620 007	HS	QM	2	1009	2.98										
NRD 5620 008	HS	QM	3	235	4.13	42.63	5.90	0.15	1.1	1.3	11.54	40	0.8	-39.2	0.02
NRD 5620 009	HS	QM	2	663	3.28										
NRD 5620 010	HS	QM	2	128	3.86										
NRD 5620 011	HS	QM	2	1219	2.68	39.69	3.51	0.28	0.92	1.2	23.33	36	0.1	-35.9	0.00
NRD 5620 012	HS	QB	4	997	2.75	58.80	4.08	0.2	1.6	1.8	11.11	57	0.1	-56.9	0.00
NRD 5620 013	HS	QM	2	2240	2.62										
NRD 5620 014	HS	QB	20	4860	2.5	223.44	3.65	0.9	6.2	7.1	12.68	220	0.1	-219.9	0.00
NRD 5620 015	HS	QB	2	1075	3.71										
NRD 5620 016	HS	QM	2	3390	2.51										

00945

1997 Surface Sample Analyses

Sample	Type	Lithology	Visible sulfide %	EC	Paste pH	NAG kg/T H_2SO_4	NAG pH	Sulfate %	Sulfide %	Sulfur Total %	SO_4/S %	AGP m/g $CaCO_3$	NP m/g $CaCO_3$	NNP	NP:AP
WRD 5580 018	HS	QM	2	112	6.4	32.93	5.55								
WRD 5580 019	HS	QM	2	42	6.14	19.60	3.91								
WRD 5580 021	HS	QM	2	65	5.87	19.89	3.98								
WRD 5580 022	HS	QM	2	170	5.61	39.79	3.00								
WRD 5580 023	HS	QM	2	103	7.67	21.17	4.63								
WRD 5580 024	HS	QM	1.5	183	5.39	21.56	4.07								
WRD 5580 025	HS	QM	1.5	42	5.74	15.78	2.52								
WRD 5580 026	HS	QM	2	84	6.1	34.79	6.42								
WRD 5580 033	HS	QM	1.5	237	3.82	38.71	7.74								
WRD 5580 042	HS	QB	5	1080	2.35	76.93	2.10	0.15	2.2	2.4	6.25	74	0.1	-73.9	0.00

KEY

Lithology QM= Quartz Monzonite QB= Quartz Breccia BB= Biotite Breccia QV = Quartz Vein AN = Andesite

Visible sulfide (%) = Observed pyrite/sulfide content in hand specimen

Type HS=High Sulfide (>2% visible sulfide) LS= Low Sulfide (<2% visible sulfide) T=Transitional (trace sulfide & acidic paste pH) O=Oxide (no observed sulfide)

NAG (eqkg H2SO4/T)= $\frac{49 \times \text{Volume of NaOH titrated} \times \text{molality of NaOH (0.1M)}}{\text{weight of sample (5g)}}$

00946

APPENDIX A.2

PASTE pH AND CONDUCTIVITY DATA

ACID BASE ACCOUNTING DATA

and

NET ACID GENERATION DATA

Copper Flat Project
Static Test on Wall Rock and Drill Core from the Pit Area
1994 Sampling

Sample	Paste PH	Total	Sulfide	Sulfate	NP	AP	NNP	NP/AP
PW-1 SW pitwall transition	6.1	3.61	3.47	0.14	32	108.44	-76.44	0.3
PW-2 Oxidized pitwall	--	0.37	0.365	0.005	11	11.41	-0.41	0.96
PW-3 NW pitwall	2.6	2.2	2.195	0.005	0.1	68.59	-68.49	--
PW-4 NE pitwall	3.9	1.89	1.885	0.005	16	58.91	-42.91	0.27
IDC24-222-241, QM – core	--	1.74	1.735	0.005	31	54.22	-23.22	0.57
CF10-177-190, andesite – core	--	2.86	2.8	0.06	52	87.5	-35.5	0.59
CF10-190-199 QM—core	--	3.59	3.52	0.07	44	110	-66	0.4
CF10-214-220, QM – core	--	3.92	3.915	0.005	65	122.34	-57.34	0.53
H75-53-42, QM - reverse circ.	8.2	1.77	1.765	0.005	36	55.16	-19.16	0.65
H75-64-44, QM - reverse circ.	7.2	1.69	1.685	0.005	39	52.66	-13.66	0.74
H75-51-34, QM - reverse circ.	8.6	2.02	2.015	0.005	49	62.97	-13.97	0.78
H75-48-58, QM - reverse circ.	7.2	1.18	1.175	0.005	16	36.72	-20.72	0.44
H75-48-44, QM - reverse circ.	7.4	1.06	1.055	0.005	9	32.97	-23.97	0.27

SOURCE: *Copper Flat Mine - Compliation of Pit Lake Studies (SRK 1997)*

Appendix D-2

Humidity Cell Data

APPENDIX A.3

HUMIDITY COLUMN TEST DATA

Parameter	Cycle 1	Cycle 2	Cycle 3	Cycle 4	Cycle 5	Cycle 6	Cycle 7	Cycle 8	Cycle 9	Cycle 10	Cycle 11	Cycle 12	Cycle 13	Cycle 14	Cycle 15
Ag ug/l	1.	4.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Al mg/l	0.03	0.05	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
As ug/l	30.	30.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
B ug/l	50.	50.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
Ba ug/l	75.	60.	30.	15.	35.	45.	35.	40.	40.	45.	40.	45.	35.	35.	15.
Be ug/l	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Bi ug/l	6.	26.	2.	2.	2.	2.	2.	2.	2.	2.	2.	6.	2.	2.	2.
Ca mg/l	30.48	23.76	18.11	12.95	18.44	15.01	13.24	13.16	13.42	15.01	13.19	15.92	13.85	11.87	5.47
Cd ug/l	1.	2.	1.	1.	3.	1.	1.	3.	1.	1.	1.	1.	1.	1.	1.
Co ug/l	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
Cr ug/l	5.	20.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
Cu ug/l	14.	16.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.
Fe mg/l	0.04	0.06	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
K mg/l	1.56	1.47	0.65	0.13	0.47	0.61	0.12	0.79	0.9	0.22	0.68	0.94	0.34	0.75	0.18
Li ug/l	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
Mg mg/l	1.26	1.04	0.59	0.36	0.58	0.42	0.39	0.39	0.37	0.34	0.52	0.65	0.48	0.48	0.18
Mn mg/l	0.07	0.03	0.02	0.02	0.035	0.03	0.025	0.025	0.025	0.02	0.015	0.02	0.015	0.01	0.005
Mo ug/l	6.	4.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	4.
Na mg/l	5.24	4.63	2.19	1.26	2.38	1.79	1.65	1.82	1.27	1.57	2.34	2.98	2.05	2.12	0.52
Ni ug/l	10.	15.	10.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	10.
P ug/l	40.	110.	10.	10.	10.	10.	30.	10.	10.	10.	10.	10.	10.	30.	10.
Pb ug/l	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	8.	10.	2.	2.
Sb ug/l	10.	34.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	4.	2.
Se ug/l	85.	150.	5.	5.	5.	5.	50.	25.	15.	15.	30.	40.	5.	30.	15.
Si mg/l	0.87	0.6	0.53	0.3	0.6	0.39	0.51	0.52	0.5	0.53	0.56	0.73	0.48	0.57	0.28
Sn ug/l	100.	174.	2.	2.	2.	2.	2.	2.	6.	22.	46.	2.	2.	80.	2.
Sr ug/l	124.	104.	50.	28.	44.	32.	32.	34.	34.	32.	34.	46.	36.	34.	18.
Tl ug/l	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.
V ug/l	2.	5.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Zn ug/l	28.	25.	12.	3.	9.	20.	11.	16.	1.	1.	2.	6.	8.	5.	9.
pH	7.73	7.8	7.55	7.4	7.85	7.64	7.52	7.53	7.54	7.59	7.61	7.63	7.72	7.51	7.16
Redox (mV)	300.	289.	307.	321.	295.	311.	318.	321.	341.	287.	272.	264.	265.	265.	296.
Conductivity (uS/cm)	132.	104.	70.	45.	69.	53.	45.	42.	41.	46.	50.	63.	49.	44.	19.
Alkalinity (mg $CaCO_3$/l)	43.	31.	24.	17.	26.	18.	16.	17.	17.	20.	19.	26.	19.	16.	10.
Acidity (pH 4.5)	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
Acidity (pH 8.3)	1.	2.	2.	2.	1.	1.	2.	1.	1.	2.	1.	2.9	2.	2.	3.
Cum Acidity (pH 8.3)	0.1	0.1	0.2	0.3	0.3	0.4	0.5	0.5	0.6	0.7	0.7	0.9	1.	1.1	1.2
Sulphate (mg/l)	9.	9.	5.	6.	8.	6.	5.	4.	4.	4.	5.	4.	3.	4.	2.
Cum Sulphate (mg/kg)	0.5	0.8	1.	1.2	1.6	1.9	2.2	2.4	2.6	2.8	3.	3.2	3.4	3.6	3.7
Water added (L)	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2
pH of water added	5.45	6.26	5.98	5.59	6.15	6.03	5.83	5.98	6.15	6.05	5.96	6.04	6.06	6.56	6.23
Leachate collected (L)	0.214	0.144	0.184	0.148	0.188	0.218	0.169	0.23	0.188	0.231	0.189	0.191	0.212	0.21	0.194
Cumulative Iron	0.04	0.1	0.11	0.12	0.13	0.14	0.15	0.16	0.17	0.18	0.19	0.2	0.21	0.22	0.23
Cumulative Copper	14.	30.	32.	34.	36.	38.	40.	42.	44.	46.	48.	50.	52.	54.	56.

00951

Parameter	Cycle 16	Cycle 17	Cycle 18	Cycle 19	Cycle 20	Cycle 21	Cycle 22	Cycle 23	Cycle 24	Cycle 25	Cycle 26	Cycle 27	Cycle 28	Cycle 29
Ag ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Al mg/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
As ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
B ug/l	<0.10	<0.10	<0.10	<0.10	<0.10								<0.10	<0.10
Ba ug/l	0.014	0.022	0.018	0.046	0.033								0.061	0.057
Be ug/l	<0.005	<0.005	<0.005	<0.005	<0.005								<0.005	<0.005
Bi ug/l	<0.10	<0.1	<0.1	<0.1	<0.1								<0.1	<0.1
Ca mg/l	1.5	2.75	2.2	4.49	2.7								6.21	8.
Cd ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.010	<0.010
Co ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Cr ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Cu ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.010	<0.010
Fe mg/l	<0.030	<0.030	<0.030	<0.030	<0.030								<0.030	<0.030
K mg/l	<2.0	<2.0	<2.0	<2.0	<2.0								<2.0	<2.0
Li ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Mg mg/l	0.091	0.12	0.12	0.323	0.16								0.453	0.621
Mn mg/l	0.008	0.005	0.005	0.007	<0.005								0.016	0.012
Mo ug/l	<0.030	<0.030	<0.030	<0.030	<0.030								<0.030	<0.030
Na mg/l	<2.0	<2.0	<2.0	<2.0	<2.0								<2.0	<2.0
Ni ug/l	<0.020	<0.020	<0.020	<0.020	<0.020								<0.020	<0.020
P ug/l	<0.30	<0.30	<0.30	<0.30	<0.30								<0.30	<0.30
Pb ug/l	<0.050	<0.050	<0.050	<0.050	<0.050								<0.050	<0.050
Sb ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
Se ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
Si mg/l	0.143	0.207	0.171	0.377	0.231								0.432	0.596
Sn ug/l	<0.30	<0.30	<0.30	<0.30	<0.30								<0.30	<0.30
Sr ug/l	0.011	0.016	0.015	0.03	0.022								0.04	0.053
Ti ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.010	<0.010
V ug/l	<0.030	<0.030	<0.030	<0.030	<0.030								<0.030	<0.030
Zn ug/l	0.01	0.006	0.009	0.012	0.015								0.022	0.024
pH	7.08	7.29	7.23	7.4	6.64								7.59	7.69
Redox (mV)	304.	284.	295.	288.	281.								291.	293.
Conductivity (uS/cm)	10.	16.	15.	32.	19.								45.	58.
Alkalinity (mg $CaCO_3$/l)	6.	10.	7.	12.	8.								16.	20.
Acidity (pH 4.5)	0.	0.	0.	0.	0.								0.	0.
Acidity (pH 8.3)	5.	5.	6.	3.	6.								5.9	6.9
Cum Acidity (pH 8.3)	1.4	1.6	1.9	2.1	2.4								2.6	3.
Sulphate (mg/l)	2.	2.	2.	4.	3.								4.	4.
Cum Sulphate (mg/kg)	3.8	3.9	3.9	4.1	4.3								4.5	4.7
Water added (L)	0.2	0.2	0.2	0.2	0.2								0.2	0.2
pH of water added	5.92	5.57	5.66	6.09	5.23								5.93	5.7
Leachate collected (L)	0.151	0.175	0.198	0.181	0.205								0.185	0.216
Cumulative Iron	0.23	0.23	0.23	0.23	0.23								0.23	0.23
Cumulative Copper	56.	56.	56.	56.	56.								56.	56.

Laboratory Equipment Failure
Weeks 21-27
No Samples Collected

00952

LGSSP-2 - Kinetic Test Data

Parameter	Cycle 1	Cycle 2	Cycle 3	Cycle 4	Cycle 5	Cycle 6	Cycle 7	Cycle 8	Cycle 9	Cycle 10	Cycle 11	Cycle 12	Cycle 13	Cycle 14	Cycle 15
Ag ug/l	7.	6.	1.	1.	1.	1.	1.	1.	1.	1.	2.	1.	1.	1.	1.
Al mg/l	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
As ug/l	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
B ug/l	60.	70.	40.	30.	10.	10.	30.	10.	10.	10.	10.	10.	10.	10.	10.
Ba ug/l	200.	105.	60.	55.	60.	40.	70.	75.	50.	90.	80.	60.	60.	75.	45.
Be ug/l	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Bi ug/l	6.	26.	2.	2.	2.	2.	2.	2.	2.	2.	8.	2.	2.	2.	2.
Ca mg/l	155.59	115.41	85.41	76.19	55.92	41.91	51.46	44.1	38.78	54.5	52.94	37.69	45.46	51.56	32.69
Cd ug/l	18.	13.	5.	1.	5.	1.	3.	5.	1.	1.	6.	1.	7.	1.	1.
Co ug/l	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
Cr ug/l	20.	25.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
Cu ug/l	82.	54.	28.	26.	16.	18.	34.	16.	14.	12.	10.	6.	10.	10.	6.
Fe mg/l	0.41	0.28	0.04	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.08	0.01	0.01	0.01	0.01
K mg/l	7.07	7.1	7.65	7.2	4.99	4.56	5.84	4.95	4.58	4.64	5.79	4.85	5.52	6.79	4.62
Li ug/l	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
Mg mg/l	16.36	11.17	8.56	7.12	4.48	2.92	4.14	3.22	2.68	4.25	4.34	2.58	3.58	4.32	2.2
Mn mg/l	0.04	0.035	0.02	0.01	0.03	0.015	0.01	0.015	0.005	0.01	0.015	0.01	0.005	0.005	0.005
Mo ug/l	242.	306.	288.	282.	176.	122.	140.	96.	74.	126.	126.	60.	90.	98.	66.
Na mg/l	7.5	7.94	7.2	6.55	3.88	2.91	3.15	2.04	1.79	2.48	2.69	1.54	2.31	2.5	1.63
Ni ug/l	5.	15.	10.	5.	5.	5.	5.	5.	5.	5.	10.	5.	5.	5.	5.
P ug/l	230.	270.	300.	340.	220.	200.	240.	190.	120.	200.	220.	180.	200.	270.	150.
Pb ug/l	32.	20.	2.	2.	2.	2.	2.	2.	2.	2.	2.	6.	12.	2.	2.
Sb ug/l	18.	22.	2.	2.	2.	2.	2.	2.	2.	2.	10.	2.	2.	2.	2.
Se ug/l	530.	405.	285.	245.	125.	30.	210.	145.	160.	225.	170.	110.	125.	115.	70.
Si mg/l	5.53	6.71	7.61	8.57	6.18	7.08	7.17	5.79	6.24	5.6	5.38	4.81	5.66	5.39	5.
Sn ug/l	574.	508.	2.	2.	2.	2.	26.	92.	60.	64.	90.	44.	44.	52.	2.
Sr ug/l	1,018.	680.	492.	418.	270.	178.	252.	204.	168.	262.	234.	142.	216.	224.	126.
Tl ug/l	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.
V ug/l	11.	10.	5.	4.	2.	1.	4.	1.	1.	1.	6.	3.	2.	2.	2.
Zn ug/l	28.	14.	12.	13.	6.	17.	13.	14.	1.	1.	1.	1.	9.	1.	3.
pH	8.07	8.1	8.09	8.16	8.11	8.13	8.13	8.05	8.21	8.03	8.04	8.01	8.07	7.96	8.02
Redox (mV)	325.	306.	318.	330.	310.	322.	335.	337.	344.	294.	281.	271.	268.	269.	296.
Conductivity (uS/cm)	979.	690.	533.	448.	308.	196.	261.	204.	170.	264.	279.	170.	226.	267.	151.
Alkalinity (mg $CaCO_3$/l)	53.	54.	58.	64.	54.	53.	58.	49.	54.	50.	51.	41.	54.	48.	49.
Acidity (pH 4.5)	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
Acidity (pH 8.3)	1.	1.	1.	1.	1.	1.	1.	1.	0.5	1.	1.	1.	1.	1.	1.
Cum Acidity (pH 8.3)	0.	0.1	0.1	0.1	0.1	0.2	0.2	0.2	0.3	0.3	0.3	0.4	0.4	0.5	0.5
Sulphate (mg/l)	432.	243.	155.	141.	82.	29.	64.	49.	21.	69.	69.	30.	48.	72.	16.
Cum Sulphate (mg/kg)	10.4	17.5	22.6	25.9	28.7	29.6	32.	33.6	34.2	36.8	39.5	40.5	42.3	45.7	46.2
Water added (L)	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2
pH of water added	5.45	6.26	5.98	5.59	6.15	6.03	5.83	5.98	6.15	6.05	5.96	6.04	6.06	6.56	6.23
Leachate collected (L)	0.102	0.122	0.139	0.101	0.144	0.119	0.162	0.138	0.112	0.158	0.165	0.153	0.158	0.198	0.127
Cumulative Iron	0.41	0.69	0.73	0.74	0.75	0.76	0.77	0.78	0.79	0.8	0.88	0.89	0.9	0.91	0.92
Cumulative Copper	82.	136.	164.	190.	206.	224.	258.	274.	288.	300.	310.	316.	326.	336.	342.

00953

Parameter	Cycle 16	Cycle 17	Cycle 18	Cycle 19	Cycle 20	Cycle 21	Cycle 22	Cycle 23	Cycle 24	Cycle 25	Cycle 26	Cycle 27	Cycle 28	Cycle 29
Ag ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Al mg/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
As ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.10	<0.10
B ug/l	<0.10	<0.10	<0.10	<0.10	<0.10								0.101	0.084
Ba ug/l	0.058	0.048	0.037	0.038	0.044								<0.005	<0.005
Be ug/l	<0.005	<0.005	<0.005	<0.005	<0.005								<0.10	<0.10
Bi ug/l	<0.10	<0.10	<0.10	<0.10	<0.10								66.2	65.3
Ca mg/l	27.3	22.4	16.4	17.	14.6								<0.010	<0.010
Cd ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.015	<0.015
Co ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Cr ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								0.014	0.018
Cu ug/l	0.019	0.016	0.011	0.011	<0.010								<0.030	<0.030
Fe mg/l	<0.030	<0.030	<0.030	<0.030	<0.030								4.4	4.2
K mg/l	4.	3.4	2.2	2.8	<2.0								<0.015	<0.015
Li ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								6.2	6.19
Mg mg/l	2.7	2.11	1.49	1.55	1.29								<0.005	<0.005
Mn mg/l	<0.005	<0.005	<0.005	<0.005	<0.005								0.065	0.093
Mo ug/l	0.066	0.041	<0.030	0.03	<0.030								<2.0	<2.0
Na mg/l	<2.0	<2.0	<2.0	<2.0	<2.0								<0.020	<0.020
Ni ug/l	<0.020	<0.020	<0.020	<0.020	<0.020								<0.30	<0.30
P ug/l	<0.30	<0.30	<0.30	<0.30	<0.30								<0.050	<0.050
Pb ug/l	<0.050	<0.050	<0.050	<0.050	<0.050								<0.20	<0.20
Sb ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
Se ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								4.12	5.03
Si mg/l	5.55	4.58	3.18	3.22	2.26								<0.30	<0.30
Sn ug/l	<0.30	<0.30	<0.30	<0.30	<0.30								0.409	0.393
Sr ug/l	0.179	0.14	0.104	0.108	0.093								<0.010	<0.010
Ti ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.030	<0.030
V ug/l	<0.030	<0.030	<0.030	<0.030	<0.030								0.008	0.005
Zn ug/l	0.005	0.009	<0.005	<0.005	<0.005								7.9	7.96
pH	8.12	8.09	8.01	7.92	7.22								313.	296.
Redox (mV)	288.	298.	294.	290.	280.								402.	384.
Conductivity (uS/cm)	177.	138.	104.	109.	93.								36.	49.
Alkalinity (mg $CaCO_3$/l)	57.	48.	34.	38.	30.								0.	0.
Acidity (pH 4.5)	0.	0.	0.	0.	0.								3.	2.
Acidity (pH 8.3)	1.	1.	2.	2.	3.								1.	1.
Cum Acidity (pH 8.3)	0.5	0.5	0.6	0.7	0.8								139.	124.
Sulphate (mg/l)	20.	10.	11.	11.	8.								54.4	59.3
Cum Sulphate (mg/kg)	46.8	47.1	47.5	47.9	48.3								0.2	0.2
Water added (L)	0.2	0.2	0.2	0.2	0.2								5.93	5.7
pH of water added	5.92	5.57	5.66	6.09	5.23								0.183	0.67
Leachate collected (L)	0.127	0.131	0.16	0.158	0.203								0.92	0.92
Cumulative Iron	0.92	0.92	0.92	0.92	0.92								342.	342.
Cumulative Copper	342.	342.	342.	342.	342.									

Laboratory Equipment Failure
Weeks 21-27
No Samples Collected

00954

C10-190-199-2 - Kinetic Test Data

Parameter	Cycle 1	Cycle 2	Cycle 3	Cycle 4	Cycle 5	Cycle 6	Cycle 7	Cycle 8	Cycle 9	Cycle 10	Cycle 11	Cycle 12	Cycle 13	Cycle 14	Cycle 15
Ag ug/l	5.	5.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Al mg/l	0.01	0.04	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
As ug/l	10.	30.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
B ug/l	50.	30.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
Ba ug/l	50.	30.	45.	35.	15.	25.	15.	15.	15.	25.	20.	35.	35.	15.	30.
Be ug/l	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Bi ug/l	6.	16.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	8.
Ca mg/l	48.27	40.54	43.47	34.16	32.33	30.47	23.86	25.61	19.7	22.26	20.91	23.92	22.28	18.03	22.24
Cd ug/l	3.	8.	2.	1.	1.	3.	3.	3.	1.	1.	1.	1.	4.	4.	3.
Co ug/l	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
Cr ug/l	10.	15.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
Cu ug/l	52.	34.	24.	20.	14.	10.	8.	8.	6.	4.	2.	2.	4.	4.	2.
Fe mg/l	0.05	0.11	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
K mg/l	3.95	3.56	4.39	2.98	2.07	1.51	2.13	2.16	1.36	0.77	1.5	1.78	1.35	1.31	2.1
Li ug/l	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
Mg mg/l	4.25	3.86	4.68	3.49	3.06	2.59	2.22	2.35	1.47	1.79	1.83	2.5	2.3	2.04	2.4
Mn mg/l	0.11	0.065	0.05	0.035	0.045	0.04	0.035	0.035	0.025	0.025	0.025	0.025	0.025	0.02	0.03
Mo ug/l	10.	12.	6.	4.	6.	2.	2.	2.	2.	2.	2.	4.	2.	4.	4.
Na mg/l	3.83	4.18	4.35	3.16	2.22	2.01	1.98	1.78	1.24	1.01	1.09	1.82	1.61	1.66	1.87
Ni ug/l	5.	10.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
P ug/l	60.	100.	10.	30.	10.	10.	10.	30.	10.	10.	10.	10.	10.	10.	20.
Pb ug/l	6.	22.	2.	2.	2.	2.	2.	2.	2.	2.	2.	6.	2.	2.	4.
Sb ug/l	14.	22.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.
Se ug/l	205.	200.	80.	75.	40.	5.	50.	95.	95.	75.	15.	70.	10.	35.	60.
Si mg/l	0.85	0.7	1.02	0.82	0.71	0.78	0.9	0.81	0.57	0.53	0.5	0.66	0.3	0.41	0.74
Sn ug/l	66.	316.	2.	2.	148.	2.	18.	66.	24.	50.	2.	2.	8.	58.	2.
Sr ug/l	372.	320.	324.	244.	194.	184.	136.	150.	100.	110.	94.	132.	120.	80.	140.
Ti ug/l	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.
V ug/l	5.	6.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	2.
Zn ug/l	31.	29.	21.	16.	13.	13.	14.	8.	1.	1.	10.	30.	19.	17.	36.
pH	8.07	7.91	7.9	7.37	7.75	7.8	7.66	7.4	7.78	7.57	7.55	7.45	7.03	7.04	7.45
Redox (mV)	306.	297.	315.	327.	303.	320.	326.	329.	346.	292.	279.	276.	277.	281.	304.
Conductivity (uS/cm)	259.	225.	253.	181.	165.	142.	112.	114.	77.	89.	90.	114.	103.	86.	107.
Alkalinity (mg $CaCO_3$/l)	43.	30.	32.	22.	19.	25.	20.	21.	19.	17.	15.	15.	11.	10.	16.
Acidity (pH 4.5)	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
Acidity (pH 8.3)	1.	1.	1.	2.	1.	1.	2.	2.	0.5	2.	1.	2.	2.	2.	2.
Cum Acidity (pH 8.3)	0.	0.1	0.1	0.2	0.2	0.3	0.3	0.4	0.4	0.5	0.6	0.7	0.8	0.9	0.9
Sulphate (mg/l)	65.	58.	70.	57.	51.	33.	25.	26.	12.	17.	20.	30.	27.	20.	22.
Cum Sulphate (mg/kg)	3.2	5.5	7.8	9.5	12.	13.4	14.2	15.4	15.9	16.7	17.6	19.	20.3	21.2	22.1
Water added (L)	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2
pH of water added	5.45	6.26	5.98	5.59	6.15	6.03	5.83	5.98	6.15	6.05	5.96	6.04	6.06	6.56	6.23
Leachate collected (L)	0.228	0.175	0.149	0.139	0.224	0.19	0.158	0.198	0.195	0.219	0.215	0.208	0.219	0.206	0.194
Cumulative Iron	0.05	0.16	0.17	0.18	0.19	0.2	0.21	0.22	0.23	0.24	0.25	0.26	0.27	0.28	0.29
Cumulative Copper	52.	86.	110.	130.	144.	154.	162.	170.	176.	180.	182.	184.	188.	192.	194.

00955

Parameter	Cycle 16	Cycle 17	Cycle 18	Cycle 19	Cycle 20	Cycle 21	Cycle 22	Cycle 23	Cycle 24	Cycle 25	Cycle 26	Cycle 27	Cycle 28	Cycle 29
Ag ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Al mg/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
As ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
B ug/l	<0.10	<0.10	<0.10	<0.10	<0.10								<0.10	<0.10
Ba ug/l	0.026	0.022	0.013	0.011	0.023								0.096	0.066
Be ug/l	<0.005	<0.005	<0.005	<0.005	<0.005								<0.005	<0.005
Bi ug/l	<0.10	<0.10	<0.10	<0.10	<0.10								<0.10	<0.10
Ca mg/l	11.8	10.8	4.76	3.15	14.3								45.3	50.7
Cd ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.010	<0.010
Co ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Cr ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Cu ug/l	0.017	0.015	0.012	0.015	0.016								0.036	0.034
Fe mg/l	<0.030	<0.030	<0.030	<0.030	<0.030								<0.030	<0.030
K mg/l	<2.0	<2.0	<2.0	<2.0	<2.0								<2.0	<2.0
Li ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Mg mg/l	2.05	1.75	0.749	0.456	1.48								6.05	7.52
Mn mg/l	0.032	0.029	0.013	0.012	0.035								0.083	0.089
Mo ug/l	<0.030	<0.030	<0.030	<0.030	<0.030								<0.030	<0.030
Na mg/l	<2.0	<2.0	<2.0	<2.0	<2.0								<2.0	<2.0
Ni ug/l	<0.020	<0.020	<0.020	<0.020	<0.020								<0.020	<0.020
P ug/l	<0.30	<0.30	<0.30	<0.30	<0.30								<0.30	<0.30
Pb ug/l	<0.050	<0.050	<0.050	<0.050	<0.050								<0.050	<0.050
Sb ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
Se ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
Si mg/l	0.541	0.547	0.275	0.169	0.346								0.614	0.679
Sn ug/l	<0.30	<0.30	<0.30	<0.30	<0.30								<0.30	<0.30
Sr ug/l	0.131	0.108	0.047	0.03	0.112								0.393	0.427
Ti ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.010	<0.010
V ug/l	<0.030	<0.030	<0.030	<0.030	<0.030								<0.030	<0.030
Zn ug/l	0.02	0.02	0.016	0.015	0.041								0.078	0.058
pH	7.52	7.64	7.27	6.87	6.66								7.49	7.41
Redox (mV)	309.	290.	301.	297.	290.								320.	307.
Conductivity (uS/cm)	95.	80.	37.	26.	104.								309.	335.
Alkalinity (mg $CaCO_3$/l)	15.	15.	8.	5.	8.								14.	15.
Acidity (pH 4.5)	0.	0.	0.	0.	0.								0.	0.
Acidity (pH 8.3)	3.	6.	2.	4.	4.								6.9	8.9
Cum Acidity (pH 8.3)	1.1	1.3	1.4	1.6	1.8								2.1	2.5
Sulphate (mg/l)	19.	14.	7.	6.	28.								118.	124.
Cum Sulphate (mg/kg)	22.9	23.5	23.8	24.1	25.3								30.2	35.5
Water added (L)	0.2	0.2	0.2	0.2	0.2								0.2	0.2
pH of water added	5.92	5.57	5.66	6.09	5.23								5.93	5.7
Leachate collected (L)	0.177	0.205	0.194	0.219	0.197								0.188	0.198
Cumulative Iron	0.29	0.29	0.29	0.29	0.29								0.29	0.29
Cumulative Copper	194.	194.	194.	194.	194.								194.	194.

Laboratory Equipment Failure
Weeks 21-27
No Samples Collected

Sample SW-1 - Kinetic Test Data

Parameter	Cycle 1	Cycle 2	Cycle 3	Cycle 4	Cycle 5	Cycle 6	Cycle 7	Cycle 8	Cycle 9	Cycle 10	Cycle 11	Cycle 12	Cycle 13	Cycle 14	Cycle 15
Ag ug/l	2.	4.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Al mg/l	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
As ug/l	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
B ug/l	20.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
Ba ug/l	50.	30.	20.	20.	10.	10.	20.	25.	25.	15.	20.	25.	15.	20.	15.
Be ug/l	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Bi ug/l	6.	6.	2.	2.	2.	2.	2.	2.	2.	2.	8.	2.	2.	2.	2.
Ca mg/l	53.15	45.51	34.83	36.28	31.01	23.67	23.36	24.87	30.06	23.22	23.31	30.56	20.57	22.22	17.45
Cd ug/l	2.	2.	1.	1.	1.	1.	7.	1.	1.	1.	4.	5.	1.	1.	5.
Co ug/l	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
Cr ug/l	15.	15.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
Cu ug/l	26.	16.	10.	12.	6.	2.	2.	2.	6.	2.	2.	2.	2.	2.	2.
Fe mg/l	0.08	0.08	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
K mg/l	2.98	2.71	2.19	2.94	2.35	1.69	1.41	1.07	2.17	0.15	1.7	2.14	1.98	1.47	1.28
Li ug/l	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
Mg mg/l	4.46	3.72	2.5	2.78	2.19	1.24	1.38	1.49	2.02	1.32	1.42	2.38	1.26	1.37	1.02
Mn mg/l	0.04	0.015	0.01	0.015	0.01	0.005	0.005	0.005	0.015	0.005	0.005	0.005	0.005	0.005	0.005
Mo ug/l	102.	84.	50.	62.	44.	26.	22.	32.	32.	14.	32.	32.	10.	26.	20.
Na mg/l	1.57	1.17	0.82	1.01	0.79	0.28	0.47	0.43	0.66	0.36	0.43	0.7	0.41	0.52	0.34
Ni ug/l	10.	10.	5.	10.	5.	5.	5.	5.	5.	5.	5.	15.	5.	5.	5.
P ug/l	120.	140.	40.	150.	100.	90.	180.	140.	130.	100.	140.	180.	50.	140.	80.
Pb ug/l	4.	8.	2.	2.	2.	2.	2.	2.	2.	2.	6.	2.	4.	2.	12.
Sb ug/l	14.	20.	2.	2.	2.	2.	2.	2.	2.	2.	6.	2.	2.	60.	2.
Se ug/l	210.	155.	65.	110.	25.	5.	80.	45.	80.	40.	70.	85.	20.	2.06	35.
Si mg/l	3.69	3.95	3.56	4.88	4.05	1.99	2.6	1.99	3.74	2.51	2.31	2.82	1.93	2.	1.98
Sn ug/l	300.	376.	2.	2.	2.	2.	80.	2.	44.	12.	2.	8.	50.	60.	2.
Sr ug/l	194.	166.	104.	110.	82.	56.	62.	68.	88.	56.	60.	78.	48.	2.	38.
Ti ug/l	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.
V ug/l	5.	6.	1.	1.	1.	1.	1.	1.	1.	1.	2.	1.	1.	1.	1.
Zn ug/l	27.	9.	7.	7.	4.	8.	4.	9.	1.	1.	7.	3.	11.	1.	4.
pH	7.65	7.73	7.87	7.91	8.04	7.65	7.69	7.66	8.	7.78	7.85	7.75	7.62	7.74	7.54
Redox (mV)	287.	265.	280.	305.	296.	302.	320.	317.	309.	260.	251.	241.	233.	233.	278.
Conductivity (uS/cm)	266.	231.	187.	174.	144.	95.	92.	105.	125.	84.	94.	138.	78.	84.	65.
Alkalinity (mg $CaCO_3$/l)	34.	29.	27.	37.	35.	21.	23.	18.	34.	26.	26.	26.	20.	22.	14.
Acidity (pH 4.5)	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
Acidity (pH 8.3)	0.5	2.	1.	2.	1.	0.5	2.	1.	1.	1.	1.	2.	2.	2.	4.
Cum Acidity (pH 8.3)	0.	0.1	0.2	0.2	0.2	0.2	0.3	0.3	0.4	0.4	0.5	0.6	0.6	0.7	0.9
Sulphate (mg/l)	77.	60.	32.	30.	24.	12.	11.	20.	14.	8.	11.	25.	8.	9.	6.
Cum Sulphate (mg/kg)	3.9	6.7	8.2	8.2	8.2	8.8	9.3	10.3	10.7	11.1	11.6	12.9	13.2	13.6	13.9
Water added (L)	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2
pH of water added	5.45	6.26	5.98	5.59	6.15	6.03	5.83	5.98	6.15	6.05	5.96	6.04	6.06	6.56	6.23
Leachate collected (L)	0.166	0.207	0.157	0.128	0.181	0.166	0.188	0.194	0.162	0.209	0.198	0.206	0.179	0.186	0.206
Cumulative Iron	0.08	0.16	0.17	0.18	0.19	0.2	0.21	0.22	0.23	0.24	0.25	0.26	0.27	0.28	0.29
Cumulative Copper	26.	42.	52.	64.	70.	72.	74.	76.	82.	84.	86.	88.	90.	92.	94.

00957

Sample SW-1 - Kinetic Test Data

Parameter	Cycle 16	Cycle 17	Cycle 18	Cycle 19	Cycle 20	Cycle 21	Cycle 22	Cycle 23	Cycle 24	Cycle 25	Cycle 26	Cycle 27	Cycle 28	Cycle 29
Ag ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Al mg/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
As ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
B ug/l	<0.10	<0.10	<0.10	<0.10	<0.10								<0.10	<0.10
Ba ug/l	0.018	0.014	<0.010	0.012	0.013								0.021	0.021
Be ug/l	<0.005	<0.005	<0.005	<0.005	<0.005								<0.005	<0.005
Bi ug/l	<0.10	<0.10	<0.10	<0.10	<0.10								<0.10	<0.10
Ca mg/l	10.9	8.36	6.44	7.72	4.2								7.65	7.26
Cd ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.010	<0.010
Co ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Cr ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Cu ug/l	0.011	<0.010	<0.010	0.01	<0.010								0.011	0.012
Fe mg/l	<0.030	<0.031	<0.032	<0.033	<0.034								<0.035	<0.036
K mg/l	<2.0	<2.1	<2.2	<2.3	<2.4								<2.5	<2.6
Li ug/l	<0.015	<0.016	<0.017	<0.018	<0.019								<0.020	<0.021
Mg mg/l	1.14	0.766	0.636	0.782	0.414								0.851	0.775
Mn mg/l	<0.005	<0.005	0.005	0.008	0.007								0.022	0.013
Mo ug/l	<0.030	<0.031	<0.032	<0.033	<0.034								<0.035	<0.036
Na mg/l	<2.0	<2.1	<2.2	<2.3	<2.4								<2.5	<2.6
Ni ug/l	<0.020	<0.020	<0.020	<0.020	<0.020								<0.020	<0.020
P ug/l	<0.30	<0.30	<0.30	<0.30	<0.30								<0.30	<0.30
Pb ug/l	<0.050	<0.050	<0.050	<0.050	<0.050								<0.050	<0.050
Sb ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
Se ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
Si mg/l	1.99	1.33	1.25	1.38	0.705								0.581	0.928
Sn ug/l	<0.30	<0.31	<0.32	<0.33	<0.34								<0.35	<0.36
Sr ug/l	0.055	0.044	0.034	0.039	0.026								0.037	0.035
Ti ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.010	<0.010
V ug/l	<0.030	<0.030	<0.030	<0.030	<0.030								<0.030	<0.030
Zn ug/l	0.008	0.005	0.007	0.008	0.011								0.026	0.014
pH	7.79	7.64	7.55	7.44	6.54								7.2	7.32
Redox (mV)	261.	280.	283.	274.	260.								298.	277.
Conductivity (uS/cm)	73.	53.	40.	51.	27.								55.	49.
Alkalinity (mg $CaCO_3$/l)	13.	13.	16.	15.	9.								4.	4.
Acidity (pH 4.5)	0.													
Acidity (pH 8.3)	3.	3.	5.	5.	5.								10.9	11.9
Cum Acidity (pH 8.3)	1.	1.2	1.4	1.6	1.9								2.3	3.
Sulphate (mg/l)	5.	4.	4.	6.	4.								11.	6.
Cum Sulphate (mg/kg)	14.1	14.3	14.5	14.7	14.9								15.4	15.7
Water added (L)	0.2	0.2	0.2	0.2	0.2								0.2	0.2
pH of water added	5.92	5.57	5.66	6.09	5.23								5.93	5.7
Leachate collected (L)	0.171	0.178	0.188	0.177	0.211								0.175	0.22
Cumulative Iron	0.29	0.29	0.29	0.29	0.29								0.29	0.29
Cumulative Copper	94.	94.	94.	94.	94.								94.	94.

Laboratory Equipment Failure
Weeks 21-27
No Samples Collected

00958

Sample PW-2 - Kinetic Test Data

Parameter	Cycle 1	Cycle 2	Cycle 3	Cycle 4	Cycle 5	Cycle 6	Cycle 7	Cycle 8	Cycle 9	Cycle 10	Cycle 11	Cycle 12	Cycle 13	Cycle 14	Cycle 15
Ag ug/l	36.	3.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Al mg/l	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
As ug/l	30.	20.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
B ug/l	10.	20.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
Ba ug/l	110.	75.	25.	45.	15.	60.	25.	25.	25.	30.	35.	60.	30.	35.	35.
Be ug/l	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Bi ug/l	26.	42.	2.	2.	2.	2.	2.	2.	2.	2.	8.	8.	2.	2.	16.
Ca mg/l	30.55	33.63	9.45	11.3	3.49	12.99	4.86	4.17	3.87	4.01	5.17	5.19	4.91	4.48	7.33
Cd ug/l	26.	25.	12.	1.	1.	8.	7.	7.	1.	1.	4.	1.	4.	1.	1.
Co ug/l	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
Cr ug/l	5.	10.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
Cu ug/l	302.2	280.	67.4	63.4	23.6	83.8	31.4	28.	42.4	43.6	62.6	81.8	59.8	69.	102.2
Fe mg/l	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
K mg/l	5.11	5.88	1.53	2.22	0.3	2.22	0.58	0.62	0.01	0.4	1.42	1.26	1.61	1.46	1.51
Li ug/l	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
Mg mg/l	1.6	2.03	0.44	0.52	0.11	0.58	0.18	0.15	0.13	0.13	0.27	0.26	0.19	0.22	0.37
Mn mg/l	0.1	0.145	0.045	0.055	0.02	0.07	0.03	0.02	0.025	0.03	0.035	0.04	0.035	0.035	0.065
Mo ug/l	24.	14.	8.	10.	2.	6.	2.	2.	2.	2.	6.	4.	2.	4.	6.
Na mg/l	1.29	1.64	0.38	0.55	0.06	0.56	0.18	0.16	0.12	0.13	0.23	0.2	0.2	0.39	0.33
Ni ug/l	5.	10.	5.	5.	5.	5.	5.	5.	5.	5.	5.	10.	5.	5.	5.
P ug/l	70.	80.	10.	10.	30.	30.	20.	30.	10.	10.	40.	10.	10.	10.	70.
Pb ug/l	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	28.	8.	2.	2.	2.
Sb ug/l	2.	16.	2.	2.	2.	2.	2.	2.	2.	2.	8.	2.	2.	2.	2.
Se ug/l	120.	125.	5.	5.	5.	5.	5.	5.	25.	10.	45.	5.	5.	10.	5.
Si mg/l	7.32	9.68	2.54	4.08	1.	4.73	1.54	1.42	1.4	1.46	1.76	1.79	1.28	1.41	1.71
Sn ug/l	2.	328.	88.	2.	2.	2.	2.	2.	58.	50.	2.	2.	34.	12.	2.
Sr ug/l	98.	114.	18.	20.	2.	30.	8.	10.	8.	6.	14.	12.	8.	10.	14.
Tl ug/l	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.
V ug/l	1.	3.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Zn ug/l	473.	492.	114.	126.	43.	176.	58.	51.	3.	1.	66.	96.	68.	64.	145.
pH	6.52	5.87	5.99	5.9	6.42	6.1	6.03	6.26	6.43	6.31	6.14	6.1	6.14	6.13	5.95
Redox (mV)	367.	332.	306.	321.	281.	335.	310.	316.	362.	297.	315.	307.	312.	315.	352.
Conductivity (uS/cm)	169.	193.	51.	57.	19.	63.	23.	17.	20.	21.	28.	29.	25.	27.	39.
Alkalinity (mg $CaCO_3$/l)	7.	3.	2.	3.	3.	2.	3.	2.	3.	3.	2.	2.	2.	2.	3.
Acidity (pH 4.5)	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
Acidity (pH 8.3)	8.	9.	4.	4.	3.	3.	2.	2.	2.	2.9	2.9	2.9	3.	3.	4.
Cum Acidity (pH 8.3)	0.4	0.9	1.	1.2	1.3	1.5	1.6	1.7	1.7	1.9	2.1	2.2	2.4	2.5	2.7
Sulphate (mg/l)	59.	66.	13.	15.	7.	15.	6.	5.	5.	5.	7.	7.	4.	6.	10.
Cum Sulphate (mg/kg)	2.6	6.3	6.9	7.4	7.7	8.4	8.7	9.	9.2	9.5	9.9	10.3	10.4	10.7	11.3
Water added (L)	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2
pH of water added	5.45	6.26	5.98	5.59	6.15	6.03	5.83	5.98	6.15	6.05	5.96	6.04	6.06	6.56	6.23
Leachate collected (L)	0.166	0.207	0.157	0.128	0.181	0.168	0.188	0.194	0.162	0.209	0.198	0.206	0.179	0.186	0.206
Cumulative Iron	0.01	0.02	0.03	0.04	0.05	0.06	0.07	0.08	0.09	0.1	0.11	0.12	0.13	0.14	0.15
Cumulative Copper	302.2	582.2	649.6	713.	736.6	820.4	851.8	879.8	922.2	965.8	1,028.4	1,110.2	1,170.	1,239.	1,341.2

00959

Sample PW-2 - Kinetic Test Data

Parameter	Cycle 16	Cycle 17	Cycle 18	Cycle 19	Cycle 20	Cycle 21	Cycle 22	Cycle 23	Cycle 24	Cycle 25	Cycle 26	Cycle 27	Cycle 28	Cycle 29
Ag ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Al mg/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
As ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.10	<0.10
B ug/l	<0.10	<0.10	<0.10	<0.10	<0.10								0.025	0.035
Ba ug/l	0.014	0.015	0.011	0.012	0.015								<0.005	<0.005
Be ug/l	<0.005	<0.005	<0.005	<0.005	<0.005								<0.10	<0.10
Bi ug/l	<0.10	<0.10	<0.10	<0.10	<0.10								1.02	2.02
Ca mg/l	1.06	1.09	0.51	0.548	0.761								<0.010	<0.010
Cd ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.015	<0.015
Co ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Cr ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								22.	32.
Cu ug/l	28.1	24.4	16.5	16.4	17.								<0.030	<0.030
Fe mg/l	<0.030	<0.030	<0.030	<0.030	<0.030								<2.0	<2.0
K mg/l	<2.0	<2.0	<2.0	<2.0	<2.0								<0.015	<0.015
Li ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								0.086	0.188
Mg mg/l	0.097	0.101	0.054	<0.050	0.093								0.03	0.044
Mn mg/l	0.02	0.021	0.013	0.017	0.019								<0.030	<0.030
Mo ug/l	<0.030	<0.030	<0.030	<0.030	<0.030								<2.0	<2.0
Na mg/l	<2.0	<2.0	<2.0	<2.0	<2.0								<0.020	<0.020
Ni ug/l	<0.020	<0.020	<0.020	<0.020	<0.020								<0.30	<0.30
P ug/l	<0.30	<0.30	<0.30	<0.30	<0.30								<0.050	<0.050
Pb ug/l	<0.050	<0.050	<0.050	<0.050	<0.050								<0.20	<0.20
Sb ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
Se ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								0.364	0.686
Si mg/l	0.685	0.991	0.377	0.458	0.567								<0.30	<0.30
Sn ug/l	<0.30	<0.30	<0.30	<0.30	<0.30								0.007	0.013
Sr ug/l	0.008	0.009	0.006	<0.001	0.011								<0.010	<0.010
Tl ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.030	<0.030
V ug/l	<0.030	<0.030	<0.030	<0.030	<0.030								0.058	0.077
Zn ug/l	0.038	0.04	0.023	0.027	0.04								6.31	6.03
pH	6.23	6.4	6.17	6.19	5.35								340.	332.
Redox (mV)	327.	326.	316.	306.	294.								11.	19.
Conductivity (uS/cm)	32.	12.	6.	6.	8.								2.	2.
Alkalinity (mg $CaCO_3$/l)	3.	3.	3.	2.	1.								0.	0.
Acidity (pH 4.5)	0.	0.	0.	0.	0.								11.9	11.9
Acidity (pH 8.3)	2.	2.	3.	4.	6.								4.3	5.
Cum Acidity (pH 8.3)	2.9	3.	3.1	3.3	3.7								3.	4.
Sulphate (mg/l)	3.	3.	3.	4.	4.								12.4	12.6
Cum Sulphate (mg/kg)	11.5	11.6	11.8	12.	12.2								0.2	0.2
Water added (L)	0.2	0.2	0.2	0.2	0.2								5.93	5.7
pH of water added	5.92	5.57	5.66	6.09	5.23								0.175	0.22
Leachate collected (L)	0.171	0.178	0.188	0.177	0.211								0.15	0.15
Cumulative Iron	0.15	0.15	0.15	0.15	0.15								1,465.6	1,497.6
Cumulative Copper	1,389.3	1,393.7	1,410.2	1,426.6	1,443.6									

Laboratory Equipment Failure
Weeks 21-27
No Samples Collected

09600

Appendix E

Appendix E-1
SHB Permeability Data

Appendix E-2
Tailings Impoundment Liner Material Hydrometer
Analysis and Gradation Plot

Appendix E-3
Geotechnical Boring Logs andGeotechnical Analytical Data Sheets

Appendix E-1

SHB Permeability Data

Tailings Dam & Pond
Quintana Minerals Corporation
Copper Flat Project
Hillsboro, New Mexico
SHB Job No. E76-1100

TABLE 1A - RESULTS OF IN-PLACE PERMEABILITY TESTS

Well Permeameter Tests,
U. S. Bureau of Reclamation Designation E-19

Boring No.	Soil Description	Interval Tested	Permeability (ft/yr)
17A	clayey sand	5'-15'	12.0
20A	clayey sand	10'-25'	3.0
22A	sandy clay	1'-9'	7.5
24A	silty clay	15'-25'	18.0
26A	silty clay, basalt	5'-15'	11.0
27A	silty sand, gravel	15'-30'	2.2
28A	clayey sand & gravel, basalt	5'-12½'	46.0
29A	sandy clay, silty sand, clayey sand & gravel	5'-13'	18.0
101A	clayey sand & gravel	1'-12'	32.0
106A	clayey sand & gravel	1'-15'	2.0
111A	sand, gravel, cobbles with clay	2'-15'	2.3
114A	sand, gravel & cobbles	5'-12½'	17.0
119A	sand & gravel with clay	5'-15'	6.6
122A	basalt	5'-11'	38.0
134A	sand, gravel, cobbles with clay	5'-15'	7.0

Tailings Dam & Pond
Quintana Minerals Corporation
Copper Flat Project
Hillsboro, New Mexico
SHB Job No. E76-1100

TABLE 1A - FIELD PERMEABILITY TESTS IN BORINGS

U. S. Bureau of Reclamation Designation E-18

Boring No.	Soil Description	Interval Tested	Equivalent Head	Permeability (ft/yr)
18	silty clay	10'-20'	38.0'	0
21	silty clay	15'-25'	43.0'	0
		15'-25'	55.0'	0
		15'-25'	66.0'	0
24	silty clay	15'-25'	43.0'	72.0*
		15'-25'	55.0'	114.0*
		15'-25'	66.0'	135.0*
26	basalt	10'-20'	61.0'	46.0
	brecciated basalt	22½'-32½'	50.0'	169.0
		22½'-32½'	62.0'	192.0
		22½'-32½'	74.0'	372.0
28	basalt	41'-51'	69.0'	410.0
	basalt	45'-55'	73.0'	212.0

*Packer leakage noted

TABLE 1A - LONG-TERM FALLING HEAD TESTS

(Piezometer Method)

Navy Design Manual - NAVFAL DM-7

Boring No.	Soil Description	Interval Tested	Permeability (ft/yr)
17	clayey sand	20'-30'	61.0**
27B	clayey sand & gravel	31'-41'	6.0
29B	clayey sand	70'-80'	5.0

**Calculated by modified U. S. Bureau of Reclamation Designation E-18

Appendix E-2

Tailings Impoundment Liner Material Hydrometer Analysis and Gradation Plot

HYDROMETER ANALYSIS DATA SHEET

Name RAUCUST/GERDANIC Group No. 1 Date 5/3/03
Project COPPER FLAT Specimen
Visual Description RED SILTY CLAY Hydrometer No. B
Dispersing Agent: 0.4 N Calgon - 15 ml Calibration line
Soil Specific Gravity Weight of dry soil 50.2 g

Corrections to readings: **Dispersing Agent:** - 1.0
Meniscus: - 1.0 (read top of meniscus)

Elapsed Time (min)	Temp. EC	Hydrometer Reading R'	Temperature Correction m	Corrected Reading R	Reading Height From Neck H_R	Particle Diameter (mm)	Percent Finer Partial PPF %	Percent Finer Total TPF %
0.5	20°C	40 43 43	0	42	10.44	0.058	83.4	80.6
1.0	20°C	42 42 41	0	41.67	10.50	0.044	82.8	80.0
2.0	20°C	38 38 38	0	38	11.16	0.031	75.5	72.9
4.0	20°C	35	0	35	11.70	0.022	69.5	67.1
8.0 8½	20°C	32	0	32	12.24	0.016	63.5	61.3
15.0 15.35	20°C	29	0	29	12.78	0.013	57.6	55.6
30.15	20°C	27	0	27	13.14	0.009	53.6	51.8
60.0	19.5	22	-0.1	21.9	14.06	0.0065	43.2	42.2
120.0	19	6	-0.2	5.8	16.96	0.0052	11.0	10.6
240.0	19	2	-0.2	1.8	17.68	0.0037	3.0	2.9
543.0	16.5	2	-0.3	1.7	17.69	0.0024	2.6	2.5
1217	16.5	1	-0.3	0.7	17.87	0.0016	0.6	0.6

Weight of dry soil used in hydrometer test W_s 50.2 g
Weight of dry soil used for sieving and hydrometer tests (combined analysis) W _____ g
Total weight of dry soil retained on the no. 200 sieve (combined anlaysis) W_r _____ g

NOTE: PPF is used when only the hydrometer test is performed on the sample
TPF is computed only for combined analysis

Partial Percent Finer $PPF = R(100) / W_s$ **Total Percent Finer** $TPF = PPF(W - W_r) / W$

Remarks:

Checked by _____ Date _____

NOMOGRAPH FOR HYDROMETER DATA REDUCTION

HYROMETER CALIBRATION EQUATIONS



TEMPERATURE CURRECTION FACTORS, m FOR HYDROMETER DATA REDUCTION

Degrees C	Degrees F	Correction m	Degrees C	Degrees F	Correction	Degrees C	Degrees F	Correction m
14	57.2	-0.9	21	69.8	0.2	28	82.4	1.8
14.5	58.1	-0.8	21.5	70.7	0.3	29	84.2	2.1
15	59	-0.8	22	71.6	0.4	29.5	85.1	2.2
15.5	59.9	-0.7	22.5	72.5	0.5	30	86	2.3
16	60.8	-0.6	23	73.4	0.6	30.5	86.9	2.5
16.5	61.7	-0.6	23.5	74.3	0.7	31	87.8	2.6
17	62.6	-0.5	24	75.2	0.8	31.5	88.7	2.8
17.5	63.5	-0.4	24.5	76.1	0.9	32	89.6	2.9
18	64.4	-0.4	25	77	1	32.5	90.5	3
18.5	65.3	-0.3	25.5	77.9	1.1	33	91.4	3.2
19	66.2	-0.2	26	78.8	1.3	33.5	92.3	3.3
19.5	67.1	-0.1	26.5	79.7	1.4	34	93.2	3.5
20	68	0	27	80.6	1.5			
20.5	68.9	0.1	27.5	81.5	1.6			

SIEVE ANALYSIS DATA SHEET

Name Tailings Impoundment Liner Material **Date** 5/5/03

Project Copper Flat **Specimen No.** SR-1

Visual Description Red clayey silt

Total Sample Mass (g) 94.30 **Group No.** NA

Sieve Opening (in)	Sieve Opening (mm)	U.S. Standard Seive No.	Weight Retained	Percent Retained Partial	Percent Retained Cumulative	Percent Finer by weight
0.187	4.76	4	0	0.00	0.00	100.00
0.0029	0.074	200	3.2	3.39	3.39	96.61
0.058						80.60
0.044						80.00
0.031						72.90
0.022						67.10
0.016						61.30
0.013						55.60
0.009						51.80
0.0065						42.20
0.0052						10.60
0.0037						2.90
0.0024						2.50
0.0016						0.60
Pan			91.1			
Total mass (g)			94.3			

Partial percent retained= weight retained on a sieve/total weigl

Cumulative percent retained=cumulative partial percent retain

Percent finer by weight=100-cumulative percent retained

D_{60} NA C_u NA

D_{30} NA C_c NA

D_{10} NA

Checked By _____ **Date** _____



COBBLES	GRAVEL		SAND			SILT OR CLAY
	COARSE	FINE	COARSE	MEDIUM	FINE	

SAMPLE	DEPTH	W %	LL	PL	PI	VISUAL DISCRIPTION	USCS	NEW MEXICO TECH
						Red clayey silt		PROJECT: Copper Flat Liner Material LOCATION: NM Tech BORING NO.: DATE: 5/5/03 TECHNICIAN: Raugust

00970

Percent Sand and Fines
And Swell Test

Total soil (Dry) = 94.3 g

>#200 = 3.2 g

< #200 = 91.1 g

percent retained #200 = 3.2/94.3 X 100 = 3.4 percent

Percent passing #200 = 91.1/94.3 x 100 = 96.6 percent.

Swell Test

original dry material = 10 ml

after 24 hours submerged by water = 16 ml

Percent difference = (16-10)/10 x 100 = 60 percent.

Appendix E-3

Geotechnical Boring Logs andGeotechnical Analytical Data Sheets

UNIFIED SOIL CLASSIFICATION SYSTEM

Major divisions			Group symbols	Typical names	Laboratory classification criteria
Coarse-grained soils (More than half of material is *larger* than No. 200 sieve size)	Gravels (More than half of coarse fraction larger than No. 4 sieve size)	Clean gravels (Little or no fines)	GW	Well-graded gravels, gravel-sand mixtures, little or no fines	$C_u = \frac{D_{60}}{D_{10}}$ greater than 4; $C_c = \frac{(D_{30})^2}{D_{10} \times D_{60}}$ between 1 and
			GP	Poorly graded gravels, gravel-sand mixtures, little or no fines	Not meeting all gradation requirements for GW
		Gravels with fines (Appreciable amount of fines)	GM d / u	Silty gravels, gravel-sand-silt mixtures	Atterberg limits below "A" line or P.I. less than 4
			GC	Clayey gravels, gravel-sand-clay mixtures	Atterberg limits above "A" line with P.I. greater than 7
	Sands (More than half of coarse fraction is smaller than No. 4 sieve size)	Clean sands (Little or no fines)	SW	Well-graded sands, gravelly sands, little or no fines	$C_u = \frac{D_{60}}{D_{10}}$ greater than 6; $C_c = \frac{(D_{30})^2}{D_{10} \times D_{60}}$ between 1 and 3
			SP	Poorly graded sands, gravelly sands, little or no fines	Not meeting all gradation requirements for SW
		Sands with fines (Appreciable amount of fines)	SM d / u	Silty sands, sand-silt mixtures	Atterberg limits below "A" line or P.I. less than 4
			SC	Clayey sands, sand-clay mixtures	Atterberg limits above "A" line with P.I. greater than 7
Fine-grained soils (More than half of material is *smaller* than No. 200 sieve)	Silts and clays (Liquid limit less than 50)		ML	Inorganic silts and very fine sands, rock flour, silty or clayey fine sands or clayey silts with slight plasticity	
			CL	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, lean clays	
			OL	Organic silts and organic silty clays of low plasticity	
	Silts and clays (Liquid limit greater than 50)		MH	Inorganic silts, micaceous or diatomaceous fine sandy or silty soils, elastic silts	
			CH	Inorganic clays of high plasticity, fat clays	
			OH	Organic clays of medium to high plasticity, organic silts	
Highly organic soils			Pt	Peat and other highly organic soils	

Determine percentages of sand and gravel from grain-size curve.
Depending on percentage of fines (fraction smaller than No. 200 sieve size), coarse-grained soils are classified as follows:

Less than 5 per cent	GW, GP, SW, SP
More than 12 per cent	GM, GC, SM, SC
5 to 12 per cent	*Borderline* cases requiring dual symbols

Above "A" line with P.I. between 4 and 7 are *borderline* cases requiring use of dual symbols

Limits plotting in hatched zone with P.I. between 4 and 7 are *borderline* cases requiring use of dual symbols.

Plasticity Chart



SOIL TESTING SERVICES, INC.
NORTHBROOK ILLINOIS 60062

PROJECT Tailings Dam Investigation
Copper Flat Project

JOB NO. E76-1023 DATE 4-2-76

LOG OF TEST PIT NO. A

RIG TYPE Ford
BORING TYPE Backhoe test pit
SURFACE ELEV.
DATUM

Depth in F.	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								SM		SILTY SAND, predominantly fine, low plasticity, brown
5				A				CL		SILTY CLAY, medium to high plasticity, reddish brown
10				A				GC		CLAYEY SAND & GRAVEL, predominantly medium, interbedded with caliche, medium plasticity, reddish brown mottled with white
15										Stopped backhoe at 14'6"

GROUND WATER

DEPTH	HOUR	DATE
	None	

SAMPLE TYPE
A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.

SERGENT, HAUSKINS & BECKWI
CONSULTING SOIL AND FOUNDATION ENGINEE

00974

SUMMARY OF MOISTURE DENSITY RELATIONSHIP TESTS

PROJECT Tailings Dam Investigation
Copper Flat Project — JOB NO. E76-1023

CLIENT _____ — LAB NO. 1023-1



CURVE	SOURCE	OPTIMUM MOISTURE CONTENT % DRY WT.	MAXIMUM DRY DENSITY LBS./CU. FT.	TEST DESIGNATION	TEST METHOD	LAB NO.
	Pit A @ 2½'-6'	11.4	118.2	ASTM D1557	D	1023-1

MOISTURE-DENSITY RELATIONSHIP TEST METHOD DATA

AASHTO T 99-74 and ASTM D 698-70 (Standard Proctor)

METHOD	MATERIAL	MOLD		NO. OF LAYERS	BLOWS PER LAYER	HAMMER WEIGHT	HEIGHT OF FALL	COMPACTIVE EFFORT FT. LBS/CU. FT.
		DIAMETER	HEIGHT					
A	-#4	4''	4.58''	3	25	5.5 LBS.	12''	12,375
B	-#4	6''	4.58''	3	56	5.5 LBS.	12''	12,317
C	-3/4	4''	4.58''	3	25	5.5 LBS.	12''	12,375
D	-3/4	6''	4.58''	3	56	5.5 LBS.	12''	12,317

AASHTO T 180-74 and ASTM D 1557-70 (Modified Proctor)

METHOD	MATERIAL	MOLD		NO. OF LAYERS	BLOWS PER LAYER	HAMMER WEIGHT	HEIGHT OF FALL	COMPACTIVE EFFORT FT. LBS/CU. FT.
		DIAMETER	HEIGHT					
A	-#4	4''	4.58''	5	25	10.0 LBS.	18''	56,250
B	-#4	6''	4.58''	5	56	10.0 LBS.	18''	55,986
C	-3/4	4''	4.58''	5	25	10.0 LBS.	18''	56,250
D	-3/4	6''	4.58''	5	56	10.0 LBS.	18''	55,986

SERGENT, HAUSKINS & BECKWITH
CONSULTING SOIL AND FOUNDATION ENGINEERS
MATERIALS TESTING ENGINEERS

ENGINEERING ANALYSIS • PHYSICAL TESTING • QUALITY CONTROL • FIELD EXPLORATION

REPORT OF LABORATORY TESTS

DATE _____

PROJECT Tailings Dam Investigation
Copper Flat Project — JOB NO. E76-1023

LOCATION Hillsboro, New Mexico — LAB NO. 1023-1

SAMPLE Test Pit A @ 2½'-6'

REMOLDED PERMEABILITY

INITIAL DATA

Maximum Dry Density	118.2	PCF
Optimum Moisture	11.4	%
Initial Dry Density	112.0	PCF
Initial Moisture Content	11.4	%
Degree of Maximum Density	94.8	%
Specific Gravity	2.675	
Volume of Specimen	1016	cc
Head	319.2	inches

AFTER TEST DATA

Moisture Content	26.1	%
Dry Density	108.2	PCF
Percent Saturation	100.0+	%
Coefficient of Permeability	1.77×10^{-6}	cm/sec
	1.83	ft/yr

Note: Thickener underflow from the breccia bulk flotation pilot plant studies used in test.

PROJECT Tailings Dam Investigation
Copper Flat Project

JOB NO. E76-1023 DATE 4-2-76

LOG OF TEST PIT NO. E

RIG TYPE Ford
BORING TYPE Backhoe test pit
SURFACE ELEV.
DATUM

Depth, feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								CH		CLAY, high plasticity, reddish brown
			X	A				CL		SANDY CLAY, low to medium plasticity, reddish brown
5										Stopped backhoe at 5'
10										

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWI

CONSULTING SOIL AND FOUNDATION ENGINEE
PHOENIX • TUCSON • ALBUQUERQUE • EL PA

00977

SUMMARY OF MOISTURE DENSITY RELATIONSHIP TESTS

PROJECT Tailings Dam Investigation
Copper Flat Project — JOB NO. E76-1023

CLIENT _____ LAB NO. 1023-6



CURVE	SOURCE	OPTIMUM MOISTURE CONTENT % DRY WT.	MAXIMUM DRY DENSITY LBS./CU. FT.	TEST DESIGNATION	TEST METHOD	LAB NO.
	Pit E @ 2'-5'	15.6	104.8	ASTM D1557	D	1023-6

MOISTURE-DENSITY RELATIONSHIP TEST METHOD DATA

AASHTO T 99-74 and ASTM D 698-70 (Standard Proctor)

METHOD	MATERIAL	MOLD		NO. OF LAYERS	BLOWS PER LAYER	HAMMER WEIGHT	HEIGHT OF FALL	COMPACTIVE EFFORT FT. LBS/CU. FT.
		DIAMETER	HEIGHT					
A	-#4	4''	4.58''	3	25	5.5 LBS.	12''	12,375
B	-#4	6''	4.58''	3	56	5.5 LBS.	12''	12,317
C	-3/4	4''	4.58''	3	25	5.5 LBS.	12''	12,375
D	-3/4	6''	4.58''	3	56	5.5 LBS.	12''	12,317

AASHTO T 180-74 and ASTM D 1557-70 (Modified Proctor)

METHOD	MATERIAL	MOLD		NO. OF LAYERS	BLOWS PER LAYER	HAMMER WEIGHT	HEIGHT OF FALL	COMPACTIVE EFFORT FT. LBS/CU. FT.
		DIAMETER	HEIGHT					
A	-#4	4''	4.58''	5	25	10.0 LBS.	18''	56,250
B	-#4	6''	4.58''	5	56	10.0 LBS.	18''	55,986
C	-3/4	4''	4.58''	5	25	10.0 LBS.	18''	56,250
D	-3/4	6''	4.58''	5	56	10.0 LBS.	18''	55,986

SERGENT, HAUSKINS & BECKWITH
CONSULTING SOIL AND FOUNDATION ENGINEERS
MATERIALS TESTING ENGINEERS

ENGINEERING ANALYSIS • PHYSICAL TESTING • QUALITY CONTROL • FIELD EXPLORATION

REPORT OF LABORATORY TESTS

DATE: _____

PROJECT: Tailings Dam Investigation
Copper Flat Project — JOB NO. E76-1023

LOCATION: Hillsboro, New Mexico — LAB NO. 1023-1

SAMPLE: Test Pit E @ 2'-5'

REMOLDED PERMEABILITY

INITIAL DATA

Maximum Dry Density	104.8	PCF
Optimum Moisture	15.6	%
Initial Dry Density	99.6	PCF
Initial Moisture Content	15.6	%
Degree of Maximum Density	95.0	%
Specific Gravity	2.675	
Volume of Specimen	2085	cc
Head	316.1	inches

AFTER TEST DATA

Moisture Content	28.9	%
Dry Density	96.9	PCF
Percent Saturation	100.0+	%
Coefficient of Permeability	2.86×10^{-7}	cm/sec
	0.29	ft/yr
Time Duration of Testing	198	hours

Note: Thickener underflow from the breccia bulk flotation pilot plant studies used in test.

Tailings Dam Investigation
PROJECT Copper Flat Project

LOG OF TEST PIT NO. F

JOB NO. E76-1023 DATE 4-2-76

RIG TYPE Ford
BORING TYPE Backhoe test pit
SURFACE ELEV.
DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								ML		SILT, very fine, low plasticity, light brown
5			A					CH		alternating layers of CLAY & SILT, high plasticity, dark reddish brown
10								GM		SILTY SAND & GRAVEL, predominantly fine, occasional basaltic boulders, subangular, nonplastic, brown
15										Stopped backhoe at 10'

GROUND WATER

DEPTH	HOUR	DATE

SAMPLE TYPE
A – Auger cuttings. B – Block sample

SERGENT, HAUSKINS & BECKWI
CONSULTING SOIL AND FOUNDATION ENGINEE

00980

SUMMARY OF MOISTURE DENSITY RELATIONSHIP TESTS

PROJECT Tailings Dam Investigation
Copper Flat Project — JOB NO. E76-1023

CLIENT _____ LAB NO. 1023-7



CURVE	SOURCE	OPTIMUM MOISTURE CONTENT % DRY WT.	MAXIMUM DRY DENSITY LBS./CU. FT.	TEST DESIGNATION	TEST METHOD	LAB NO.
	Pit F @ 2'-5'	15.3	104.7	ASTM D1557	D	1023-7

MOISTURE-DENSITY RELATIONSHIP TEST METHOD DATA

AASHTO T 99-74 and ASTM D 698-70 (Standard Proctor)

METHOD	MATERIAL	MOLD		NO. OF LAYERS	BLOWS PER LAYER	HAMMER WEIGHT	HEIGHT OF FALL	COMPACTIVE EFFORT FT. LBS/CU. FT.
		DIAMETER	HEIGHT					
A	-#4	4''	4.58''	3	25	5.5 LBS.	12''	12,375
B	-#4	6''	4.58''	3	56	5.5 LBS.	12''	12,317
C	-3/4	4''	4.58''	3	25	5.5 LBS.	12''	12,375
D	-3/4	6''	4.58''	3	56	5.5 LBS.	12''	12,317

AASHTO T 180-74 and ASTM D 1557-70 (Modified Proctor)

METHOD	MATERIAL	MOLD		NO. OF LAYERS	BLOWS PER LAYER	HAMMER WEIGHT	HEIGHT OF FALL	COMPACTIVE EFFORT FT. LBS/CU. FT.
		DIAMETER	HEIGHT					
A	-#4	4''	4.58''	5	25	10.0 LBS.	18''	56,250
B	-#4	6''	4.58''	5	56	10.0 LBS.	18''	55,986
C	-3/4	4''	4.58''	5	25	10.0 LBS.	18''	56,250
D	-3/4	6''	4.58''	5	56	10.0 LBS.	18''	55,986

REPORT OF LABORATORY TESTS

DATE _____

PROJECT Tailings Dam Investigation
Copper Flat Project — JOB NO. E76-1023

LOCATION Hillsboro, New Mexico — LAB NO. 1023-2

SAMPLE Test Pit F @ 2'-5'

REMOLDED PERMEABILITY

INITIAL DATA

Maximum Dry Density	104.7	PCF
Optimum Moisture	15.3	%
Initial Dry Density	99.5	PCF
Initial Moisture Content	15.3	%
Degree of Maximum Density	95.0	%
Specific Gravity	2.675	
Volume of Specimen	2085	cc
Head	881.8	inches

AFTER TEST DATA

Moisture Content	32.1	%
Dry Density	98.02	PCF
Percent Saturation	100.0+	%
Coefficient of Permeability	2.11×10^{-8}	cm/sec
	0.022	ft/yr
Time Duration of Testing	198	hours

Note: Thickener underflow from the breccia bulk flotation pilot plant studies used in test.

PROJECT Tailings Dam Investigation

JOB NO. E76-1023 DATE 3-24-76

LOG OF TEST BORING NO. 1

RIG TYPE CME-55

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in ft	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0			☒	S	30		16	CH	firm	CLAY, high plasticity, reddish brown
5			☒	S	73		16	CL	hard	SILTY CLAY, medium plasticity, reddish brown
10			☒	U	67		13			
15			☒	S	92		17		hard	CLAYEY SILT, medium plasticity, brown
20			⊠	S	50/5"		11	ML		
25			▬	S	50/3"		9			
30			⊠	S	50/4"		11			Stopped auger at 29'6" Sampler refused at 29'10"
35										

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.

SERGENT, HAUSKINS & BECKWIT

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

00983

TABULATION OF TEST RESULTS

Job No. E76-1023

Project Tailings Dam Investigation, Copper Flat Project

Hillsboro, New Mexico

Material

Source

HOLE NO.	LOCATION	DEPTH	UNIFIED CLASS.	LL	PI	SIEVE ANALYSIS — ACCUM. % PASSING												LAB. NO.
						200	100	40	16	10	4	¼	⅜	¾	1	1½	2	
1	See Site Plan	5'	CL	42	18	72	89	100										23-8
1	See Site Plan	15'	ML	49	20	74	89	98		100								23-9
2	See Site Plan	1'	GC	55	28	23	30	38		51	61		74	84	100			23-10
2	See Site Plan	20'	SC	33	13	34	47	61		76	84		92	100				23-11
2	See Site Plan	35'	SC	32	13	36	51	67		84	94		100					23-12
4	See Site Plan	1'	CL	41	22	72	78	86		98	100							23-13
5	See Site Plan	1'	SC	32	16	46	53	63		78	86		93	100				23-14
5	See Site Plan	10'	ML	39	14	93	96	98		99	100							23-15
5	See Site Plan	20'	CH	79	47	82	92	98		100								23-16
5	See Site Plan	35'	ML	40	14	74	89	99		100								23-17
5	See Site Plan	60'	CH	55	29	96	99	100										23-18
6	See Site Plan	1'	CL	41	19	83	93	99		100								23-19
6	See Site Plan	5'	CL	35	16	56	64	75		90	96		98	100				23-20
7	See Site Plan	42'	CH	54	27	91	96	99		100								23-21
9	See Site Plan	1'	SC	33	13	44	52	62		78	88		96	100				23-23

000984

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-1-76

LOG OF TEST BORING NO. 18

RIG TYPE CME-75

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Ft	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0										GRAVEL littered surface
			X	S	20		17		firm to hard	SILTY CLAY, some sand, medium to high plasticity, reddish-brown
5			X	S	33		18			note: occasional seam of clayey silt, medium plasticity, reddish-tan
10			X	S	38			CH		
15			X	S	50/5½"		22			
20			X	S	50/5½"		16			
25			X	S	85		23	ML	hard	CLAYEY SILT, some fine sand, medium plasticity, light brown
30			X	S	50/4"		20	ML	hard	SANDY SILT, considerable lime, low plasticity, light tan
35				S	50/4"				hard	SILTY CLAY, some fine sand, medium plasticity, light brown
								CL		
40				S	50/5½"		13		hard	SANDY SILT, low plasticity, light brown
										CLAYEY SAND & GRAVEL, occasional cobble, decomposed, low plasticity, brown
45				S	50/2"		11	ML		
								SC		Stopped auger at 49'6" Sampler refused at 49'8"
50				S	50/2"		19			

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

Job No. E76-1100 Date

Client:

Project Copper Flat Tailings Dam & Pond
Hillsboro, New Mexico

Material

Source

HOLE NO.	LOCATION	DEPTH	UNIFIED CLASS.	LL	PI	SIEVE ANALYSIS – ACCUM. % PASSING											moist.	LAB. NO.
						200	100	40	16	10	4	¼	⅜	¾	1	1½		
17	See Site Plan	½'	SC	35	18	43	50	64	78	84	92	94	97	100			5.2	1100-6
17	See Site Plan	9½'	SC	39	19	35	42	51	61	66	78	81	86	100			5.3	1100-8
17	See Site Plan	24½'	SC	39	20	20	24	32	45	53	66	70	78	100			4.5	1100-11
18	See Site Plan	9½'	CH	60	34	87	94	99	99	99	100						13.4	1100-20
18	See Site Plan	34½'	CL	40	20	68	82	91	95	96	98	99	100				8.2	1100-25
19	See Site Plan	14½-16'	SC	39	16	28	41	56		74	84		91	100				1100-3-1
19	See Site Plan	34½'-36'	SM-SC	35	10	21	35	84		99	100							1100-3-2
19	See Site Plan	49½-51'	MH	66	29	70	87	99		100								1100-3-3
20	See Site Plan	9½'	SC	36	14	23	30	41	52	59	74	80	88	97	100		4.3	1100-31
20	See Site Plan	39½'	CH	67	41	93	95	98	99	100							20.3	1100-37
20	See Site Plan	64½'	CH	57	31	79	95	99	100								21.3	1100-42
21	See Site Plan	29½'	CH-MH	51	23	67	83	98	99	100							14.5	1100-51
21	See Site Plan	54½'	CH-MH	60	30	92	98	99	100								16.9	1100-56
21	See Site Plan	74½'	CH	56	30	95	99	99	100								16.7	1100-60
21	See Site Plan	104½'	GC	40	20	22	25	32	42	48	61	64	72	100			9.5	1100-66

98600

SERGENT, HAUS S & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • ALBUQUERQUE • EL PASO

TABULATION OF TEST RESULTS

Job No. E76-1023

Project Tailings Dam Investigation, Copper Flat Project

Hillsboro, New Mexico

Material

Source Backhoe Test Pits

HOLE NO.	LOCATION	DEPTH	UNIFIED CLASS.	LL	PI	SIEVE ANALYSIS – ACCUM. % PASSING												LAB. NO.
						200	100	40	16	10	4	¼	⅜	¾	1	2	3	
A	See Site Plan	2'-6½'	CL	45	25	61	67	76		91	97		99		100			23-1
A	See Site Plan	7'-9'	GC	45	24	17	20	26		39	48		57	69	72	76	100	23-2
B	See Site Plan	2'-5'	SC	34	16	47	54	86		98	99		100					23-3
C	See Site Plan	1'-5'	CL	43	22	67	77	90		98	99		100					23-4
C	See Site Plan	5½'-9'	SC	31	10	26	30	39		61	75		85		86	100		23-5
E	See Site Plan	2'-5'	CL	38	14	76	90	99		100								23-6
F	See Site Plan	2'-5'	CH	58	34	99	100											23-7

00987

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS

PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

Appendix F

Bulk XRD and Clay Mineralogy Distribution Data Scans and Calculations

Clay Mineralogy Calcualtions

General Calculation

T = total counts
S1g = smectite/mixed (glycolated)
I1g = Illite (glycolated)
K1 = Kaolinite (glycolated)
I1h = Illite (heated)

T = I1h + K1

Illite = I1g/T x 10

Smectite = (S1g/4)/T x 10

Mixed Layer (I/S) = (I1h - I1g - (S1g/4))/T x 10

Kaolinite = K1/T x10

Results are in parts in 10.

Calculations

Sample ID	I1h	K1	I1g	S1g	T	Illite	Smectite	Mixed layer (I/S)	Kaolinite	Total
SR-1, Calc1	327	103	0	267	430	0.0	1.6	6.1	2.4	10
SR-1, Calc2	318	100	0	245	418	0.0	1.5	6.1	2.4	10
SR-1, Calc3	363	100	0	253	463	0.0	1.4	6.5	2.2	10
SR3	156	35	42	0	191	2.2	0.0	6.0	1.8	10

68600


[SR1-A1.MDI] SR1-A1
190
KI
103
Intensity(Counts)
2-Theta(°)
0
50
100
150
200
250
300
5
10
15
20
25
30

06600


[SR1-A2.MDI] SR1-A2
Intensity(Counts)
2-Theta(°)
0
100
200
300
400
500
2
3
4
5
6
7
8
9
10
11
12
13
14
15
516
267
116
0
92


[SR1-A31.MDI] SR1-A31
[SR1-A32.MDI] SR1-A32
Intensity(Counts)
2-Theta(°)
0
250
500
750
1000
1250
2
3
4
5
6
7
8
9
10
11
12
13
14
15
I1h
327
129

00992


[SR1-A1.MDI] SR1-A1
Intensity(Counts)
2-Theta(°)
183
KI
100
0
50
100
150
200
250
300
350
400
5
10
15
20
25
30
35
40

00993


[SR1-A2.MDI] SR1-A2
Intensity(Counts)
2-Theta(°)
0
100
200
300
400
500
2
3
4
5
6
7
8
9
10
11
12
13
14
15
51σ
245
Iσ
0
64


[SR1-A31.MDI] SR1-A31
[SR1-A32.MDI] SR1-A32
Intensity(Counts)
2-Theta(°)
0
250
500
750
1000
1250
2
3
4
5
6
7
8
9
10
11
12
13
14
15
I 1h
318
108

00995


[SR1-A1.MDI] SR1-A1
Intensity(Counts)
2-Theta(°)
178
K1
100
0
50
100
150
200
250
300
350
400
5
10
15
20
25
30
35

96600


[SR1-A2.MDI] SR1-A2
Intensity(Counts)
2-Theta(°)
0
100
200
300
400
500
2
3
4
5
6
7
8
9
10
11
12
13
14
15
51g
253
I1g
0
68

00997


[SR1-A31.MDI] SR1-A31
[SR1-A32.MDI] SR1-A32
Intensity(Counts)
2-Theta(°)
I 1h
363
116

86600


[SR3-A31.MDI] SR3-A31
[SR3-A32.MDI] SR3-A32
Intensity(Counts)
2-Theta(°)
I1h
156
67

66600


[SR3-A1.MDI] SR3-A1
Intensity(Counts)
2-Theta(°)
0
50
100
150
200
250
300
5
10
15
20
25
30
35
K1
35

01000



01001


[SR.MDI] sr-1
1500
1000
500
0
Intensity(Counts)
10
20
30
40
50
60
2-Theta(°)

01002

[SR.MDI] sr-1										Peak ID Report
SCAN: 2.0/69.98/0.03/0.5(sec), Cu, I(max)=1465, 04/11/03 11:42										
PEAK: 17-pts/Parabolic Filter, Threshold=1.0, Cutoff=0.5%, BG=2/1.0, Peak-Top=Centroid Fit										
NOTE: Intensity = Counts, 2T(0)=0.0(°), Wavelength to Compute d-Spacing = 1.54056Å (Cu/K-alpha1)										
#	2-Theta	d(Å)	Height%	Quartz, syn	Calcite, syn					
1	5.649	15.6313	5.1							
2	6.002	14.7133	4.9							
3	12.313	7.1824	1.3							
4	19.704	4.5019	8.2							
5	20.779	4.2712	11.3	-0.010 (22.0%)						
6	23.485	3.7850	1.8							
7	26.551	3.3544	48.3	0.020 (100.0%)						
8	27.837	3.2023	7.0							
9	29.333	3.0423	100.0		0.072 (100.0%)					
10	33.089	2.7050	1.9							
11	34.754	2.5792	3.8							
12	35.916	2.4983	6.1		0.050 (14.0%)					
13	36.460	2.4623	2.5	0.001 (8.0%)						
14	39.354	2.2876	9.4	0.020 (8.0%)	0.046 (18.0%)					
15	40.208	2.2410	1.9	-0.005 (4.0%)						
16	42.357	2.1321	3.6	0.027 (6.0%)						
17	43.091	2.0975	5.0		0.053 (18.0%)					
18	45.757	1.9813	1.9	-0.030 (4.0%)						
19	47.062	1.9293	2.1		0.060 (5.0%)					
20	47.443	1.9147	7.9		0.045 (17.0%)					
21	48.443	1.8775	6.6		0.069 (17.0%)					
22	50.041	1.8212	5.5	0.018 (14.0%)						
23	54.801	1.6738	1.8	-0.013 (4.0%)						
24	56.541	1.6263	1.5		0.012 (4.0%)					
25	57.337	1.6056	6.0	-0.181 (1.0%)	0.063 (8.0%)					
26	59.864	1.5437	4.2	0.003 (9.0%)						
27	60.609	1.5265	2.1		0.068 (5.0%)					
28	61.475	1.5071	2.7		-0.131 (3.0%)					
29	63.971	1.4542	1.0	-0.052 (1.0%)						
30	67.692	1.3830	2.3	-0.024 (6.0%)						

01003

[SR.MDI] sr-1										Peak ID Report
SCAN: 2.0/69.98/0.03/0.5(sec), Cu, I(max)=1465, 04/11/03 11:42										
PEAK: 17-pts/Parabolic Filter, Threshold=1.0, Cutoff=0.5%, BG=2/1.0, Peak-Top=Centroid Fit										
NOTE: Intensity = Counts, 2T(0)=0.0(°), Wavelength to Compute d-Spacing = 1.54056Å (Cu/K-alpha1)										
#	2-Theta	d(Å)	Height%	Quartz, syn	Calcite, syn					
31	68.090	1.3759	2.9	-0.042 (7.0%)						
32	69.134	1.3576	1.3		0.095 (1.0%)					
?	Unmatched Line			55.247 (2.0%)	23.022 (12.0%)					
?	Unmatched Line			68.241 (8.0%)	31.418 (3.0%)					
?	Unmatched Line				58.073 (2.0%)					
?	Unmatched Line				60.986 (4.0%)					
?	Unmatched Line				63.058 (2.0%)					
?	Unmatched Line				64.677 (5.0%)					
?	Unmatched Line				65.597 (3.0%)					
PDF#33-1161 - Quartz, syn <2T(0) = -0.08, d/d(0) = 1.0>										
PDF#05-0586 - Calcite, syn <2T(0) = 0.0, d/d(0) = 1.0>										


[SR2.MDI] sr-2
Intensity(Counts)
1500
1000
500
0
10
20
30
40
50
60
2-Theta(°)

01005

[SR2.MDI] sr-2										Peak ID Report
SCAN: 2.0/69.98/0.03/0.5(sec), Cu, I(max)=1557, 04/11/03 12:11										
PEAK: 17-pts/Parabolic Filter, Threshold=1.0, Cutoff=0.5%, BG=2/1.0, Peak-Top=Centroid Fit										
NOTE: Intensity = Counts, 2T(0)=0.0(°), Wavelength to Compute d-Spacing = 1.54056Å (Cu/K-alpha1)										
#	2-Theta	d(Å)	Height%	Calcite, syn						
1	22.951	3.8717	21.5	0.011 (12.0%)						
2	26.869	3.3155	2.1							
3	29.313	3.0443	100.0	0.032 (100.0%)						
4	31.376	2.8487	1.1	-0.018 (3.0%)						
5	35.893	2.4998	39.8	0.012 (14.0%)						
6	39.353	2.2877	61.5	-0.012 (18.0%)						
7	43.098	2.0972	27.1	-0.013 (18.0%)						
8	47.099	1.9279	19.0	-0.037 (5.0%)						
9	47.427	1.9153	10.3	0.001 (17.0%)						
10	48.451	1.8772	22.1	0.001 (17.0%)						
11	56.518	1.6269	13.1	-0.025 (4.0%)						
12	57.354	1.6052	39.6	-0.014 (8.0%)						
13	60.625	1.5262	10.2	-0.009 (5.0%)						
14	60.898	1.5200	3.5							
15	61.304	1.5109	1.9	-0.020 (3.0%)						
16	62.973	1.4748	2.8	0.025 (2.0%)						
17	64.616	1.4412	16.6	0.000 (5.0%)						
18	65.596	1.4220	2.7	-0.058 (3.0%)						
19	69.174	1.3570	1.2	-0.004 (1.0%)						
?	Unmatched Line			58.013 (2.0%)						
?	Unmatched Line			60.926 (4.0%)						
PDF#05-0586 - Calcite, syn <2T(0) = -0.06, d/d(0) = 1.0>										

01006


[SR-3.MDI] sr-3
1250
1000
750
500
250
0
Intensity(Counts)
10
20
30
40
50
60
2-Theta(°)

01007

[SR-3.MDI] sr-3										Peak ID Report
SCAN: 2.0/69.98/0.03/0.5(sec), Cu, I(max)=873, 04/11/03 12:50										
PEAK: 17-pts/Parabolic Filter, Threshold=1.0, Cutoff=0.5%, BG=2/1.0, Peak-Top=Centroid Fit										
NOTE: Intensity = Counts, 2T(0)=0.0(°), Wavelength to Compute d-Spacing = 1.54056Å (Cu/K-alpha1)										
#	2-Theta	d(Å)	Height%	Quartz, syn	Muscovite-1M, ...					
1	8.799	10.0416	4.6		0.009 (100.0%)					
2	13.827	6.3991	3.1							
3	19.682	4.5067	7.6		0.134 (90.0%)					
4	20.840	4.2589	26.8	-0.011 (22.0%)						
5	21.993	4.0383	10.6							
6	23.520	3.7794	7.7							
7	24.207	3.6737	3.9		0.152 (60.0%)					
8	26.617	3.3462	100.0	0.014 (100.0%)	-0.051 (100.0%)					
9	27.505	3.2401	11.4							
10	27.856	3.2002	22.0							
11	29.350	3.0406	8.2		-0.227 (50.0%)					
12	29.780	2.9976	5.8							
13	30.742	2.9060	6.7		-0.188 (6.0%)					
14	34.432	2.6025	4.6							
15	34.907	2.5682	7.3		0.104 (90.0%)					
16	35.609	2.5191	6.6							
17	35.979	2.4941	4.4							
18	36.507	2.4592	7.7	0.014 (8.0%)	0.202 (12.0%)					
19	37.131	2.4193	3.7		0.289 (4.0%)					
20	39.421	2.2839	8.1	0.014 (8.0%)						
21	42.424	2.1289	12.7	0.020 (6.0%)						
22	45.783	1.9802	5.7	0.005 (4.0%)						
23	50.104	1.8191	13.8	0.016 (14.0%)						
24	50.656	1.8006	2.2	-0.066 (1.0%)						
25	54.827	1.6730	3.3	0.021 (4.0%)						
26	55.208	1.6624	3.1	0.099 (2.0%)	-0.141 (18.0%)					
27	59.928	1.5422	8.9	-0.001 (9.0%)						
28	61.819	1.4995	3.0		0.084 (35.0%)					
29	63.912	1.4554	3.0	0.067 (1.0%)						
30	67.687	1.3831	5.2	0.041 (6.0%)						

01008

[SR-3.MDI] sr-3									Peak ID Report
SCAN: 2.0/69.98/0.03/0.5(sec), Cu, I(max)=873, 04/11/03 12:50									
PEAK: 17-pts/Parabolic Filter, Threshold=1.0, Cutoff=0.5%, BG=2/1.0, Peak-Top=Centroid Fit									
NOTE: Intensity = Counts, 2T(0)=0.0(°), Wavelength to Compute d-Spacing = 1.54056Å (Cu/K-alpha1)									
#	2-Theta	d(Å)	Height%	Quartz, syn	Muscovite-1M, ...				
31	68.113	1.3755	14.2	-0.004 (7.0%)					
?	Unmatched Line			40.263 (4.0%)	17.642 (35.0%)				
?	Unmatched Line			68.301 (8.0%)	20.459 (25.0%)				
?	Unmatched Line				21.664 (16.0%)				
?	Unmatched Line				33.352 (16.0%)				
?	Unmatched Line				34.774 (50.0%)				
?	Unmatched Line				35.224 (20.0%)				
?	Unmatched Line				37.827 (12.0%)				
?	Unmatched Line				40.174 (8.0%)				
?	Unmatched Line				40.684 (8.0%)				
?	Unmatched Line				41.226 (4.0%)				
?	Unmatched Line				41.926 (20.0%)				
?	Unmatched Line				42.904 (6.0%)				
?	Unmatched Line				45.056 (30.0%)				
?	Unmatched Line				46.418 (8.0%)				
?	Unmatched Line				47.894 (4.0%)				
?	Unmatched Line				55.609 (12.0%)				
?	Unmatched Line				56.274 (12.0%)				
?	Unmatched Line				61.224 (4.0%)				
PDF#33-1161 - Quartz, syn <2T(0) = -0.02, d/d(0) = 1.0>									
PDF#07-0025 - Muscovite-1M, syn <2T(0) = 0.06, d/d(0) = 1.0>									

01009

Appendix D
Geologic Logs

Steffen Robertson and Kirsten
Engineering and Environmental Consultants

LOG OF MONITORING WELL MW-9





MATERIALS DESCRIPTION

0-10', Soil/gravel, dark brown, w/abundant, silt, sand, cobbles/pebbles, wet @ 8'

7.75', ENCOUNTERED GROUNDWATER

10'-30', Alluvial gravels, varying amounts of silt/clay, sand & silt, abundant pebbles/cobbles very poorly sorted, Oxidized, wet

30'-40', Gravel, brown-slightly red brown, within clayey matrix very poorly sorted, min.-mod. sand, Oxidized, wet

40'-48', Gravel, as above with less clay/silt matrix.

48'-52', Gravel, brown-red brown within clay/silt matrix, min.-mod. sand very poorly sorted, wet.

52'-53.5', Gravel, as at 40'-48', relatively clean

53.5'-65', Gravel, brown-red brown, moderate-abundant clay/silt matrix, minor sand, very poorly sorted; wet

65'-75', clay, dark red-brown, w/min.-mod. sand & pebbles, no cobbles, moist-wet, very smooth drilling

PROJECT Copper Flat - Hillsboro, N.M.	DRILLING COMPANY Beylik Drilling
LOCATION N713191.10, E603249.22 N.M. S.P.C.	DATE DRILLED 09/20/94 - 09/26/94
JOB NUMBER 68607 (ref: 68607M9)	SURFACE ELEVATION 4440.14
GEOLOGIST C.W.	TOTAL DEPTH OF HOLE 252.50 Feet
DRILL RIG Air Rotary	WATER LEVEL Static, from TOC on 11/7/94: 71.05 Feet

Steffen Robertson and Kirsten
Engineering and Environmental Consultants

LOG OF MONITORING WELL MW-9



PROJECT Copper Flat - Hillsboro, N.M.
LOCATION N713191.10, E603249.22 N.M. S.P.C.
JOB NUMBER 68607 (ref: 68607M9)
GEOLOGIST C.W.
DRILL RIG Air Rotary

DRILLING COMPANY Beylik Drilling
DATE DRILLED 09/20/94 - 09/26/94
SURFACE ELEVATION 4440.14
TOTAL DEPTH OF HOLE 252.50 Feet
WATER LEVEL Static, from TOC on 11/7/94: 71.05 Feet

Steffen Robertson and Kirsten
Engineering and Environmental Consultants

LOG OF MONITORING WELL MW-9



PROJECT Copper Flat - Hillsboro, N.M.
LOCATION N713191.10, E603249.22 N.M. S.P.C.
JOB NUMBER 68607 (ref: 68607M9)
GEOLOGIST C.W.
DRILL RIG Air Rotary

DRILLING COMPANY Beylik Drilling
DATE DRILLED 09/20/94 - 09/26/94
SURFACE ELEVATION 4440.14
TOTAL DEPTH OF HOLE 252.50 Feet
WATER LEVEL Static, from TOC on 11/7/94: 71.05 Feet

Steffen Robertson and Kirsten
Engineering and Environmental Consultants

LOG OF MONITORING WELL MW-9



PROJECT Copper Flat - Hillsboro, N.M.
LOCATION N713191.10, E603249.22 N.M. S.P.C.
JOB NUMBER 68607 (ref: 68607M9)
GEOLOGIST C.W.
DRILL RIG Air Rotary

DRILLING COMPANY Beylik Drilling
DATE DRILLED 09/20/94 - 09/26/94
SURFACE ELEVATION 4440.14
TOTAL DEPTH OF HOLE 252.50 Feet
WATER LEVEL Static, from TOC on 11/7/94: 71.05 Feet

Steffen Robertson and Kirsten
Engineering and Environmental Consultants

LOG OF MONITORING WELL MW-11



PROJECT Copper Flat - Hillsboro, N.M.	DRILLING COMPANY Beylik Drilling
LOCATION N713751.31, E603378.24 N.M. S.P.C.	DATE DRILLED 10/11/94
JOB NUMBER 68607 (ref: 68607M11)	SURFACE ELEVATION 4439.48
GEOLOGIST CW	TOTAL DEPTH OF HOLE 65 Feet
DRILL RIG Air Rotary	WATER LEVEL Static, from TOC on 11/7/94: 10.65 Feet

STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLAT PROJECT NO.: 68607	BORING NUMBER: SRK BH-2-94	COORDINATES OR LOCATION:
LOGGED BY: HKP CHECKED BY:	SURFACE ELEVATION: PENDING	GWL DEPTH: 18' (ENCOUNTERED) GWL DEPTH: N/A (STATIC)
DRILLING METHOD: CME-75 HOLLOW STEM AUGER	HOLE DIAMETER: 8"	FLUID USED: NONE
		DATE STARTED: 5/26/94 DATE COMPLETED: 5/26/94

CASING TYPE AND SIZE: 2" dia. Sched. 40 pvc — FROM ±3' A.G.S. TO 28.5' B.G.S.
SCREEN TYPE AND SIZE: 2" dia. Sched. 40 pvc, 0.010" slots — FROM 28.5' TO 33.5'

DEPTH ( )	SAMPLE TYPE AND NUMBER	SAMPLE DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	PROFILE	DESCRIPTION
0						SW/GW, cobble cover material
						Tailings, SP-SM, medium moist to moist, tan to light brown
10						
						Very moist to saturated
20						Moist to very moist
						Sand and gravel, clayey, some cobbles, medium graded, medium moist to moist
30						Total depth 33.5'
40						
50						
60						



WELL CONSTRUCTION SUMMARY

NOTES

Stand pipe piezometer 2" schedule 40 pvc flush thread

Well head protected with steel pipe w/locking cap

STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLAT PROJECT NO.: 68607	BORING NUMBER: GWQ 94-13	COORDINATES OR LOCATION: 713,543.43 N 603,270.64 E
LOGGED BY: CW CHECKED BY:	SURFACE ELEVATION: 5177.01'	GWL DEPTH: 80.0 (ENCOUNTERED) DEPTH: 7.58 (STATIC)
DRILLING METHOD: ROTARY	HOLE DIAMETER: 12 1/4" & 9 7/8"	FLUID USED: AIR/MUD
		DATE STARTED: 9/14/94 COMPLETED: 9/19/94

CASING TYPE AND SIZE: 4 1/2" dia. Sched. 80 pvc — FROM 2.04 A.G.S. TO 73.95 B.G.S.
SCREEN TYPE AND SIZE: 4 1/2" dia. Sched. 80 pvc, 0.02" slots — FROM 73.95 TO 104.5

DEPTH ( )	SAMPLE TYPE AND NUMBER	SAMPLE DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	PROFILE	DESCRIPTION
0						Soil, medium brown, abundant basaltic pebbles/cobbles, abundant silt/sand, oxidized, dry
10						
20						Clay, red to reddish brown, minimum to moderate silt, slightly moist, very uniform, oxidized
30						Clay, red to reddish brown, moderate to abundant basaltic fragments, slightly moist, transitional sand, oxidized
40						Clay, red to reddish brown, minimum to moderate silt, very uniform, no sand, pebbles or cobbles, slightly moist, oxidized
50						
60						Clay, red to reddish brown, minimum to moderate basaltic fragments, minimum to moderate silt, moist, oxidized



NOTES

Development time = 8.8 hours
Average flow = 18.75 gpm
Dates: 9/30/94 and 10/1/94

Static water = 8.02 from toc (11/07/94)

Well head protection - 8" dia. steel pipe w/locking well cap, approx. 3.5' above surface.

STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLAT PROJECT NO.: 68607	BORING NUMBER: GWQ 94-13	COORDINATES OR LOCATION: 713,543.64 N 603,270.64 E
LOGGED BY: CW CHECKED BY:	SURFACE ELEVATION: 5177.01'	GWL DEPTH: 80.0 (ENCOUNTERED) DEPTH: 7.58 (STATIC)
DRILLING METHOD: ROTARY	HOLE DIAMETER: 12 1/4" & 9 7/8"	FLUID USED: AIR/MUD
		DATE STARTED: 9/14/94 COMPLETED: 9/19/94

CASING TYPE AND SIZE: 4 1/2" dia. Sched. 80 pvc — FROM 2.04 A.G.S. TO 73.95 B.G.S.
SCREEN TYPE AND SIZE: 4 1/2" dia. Sched. 80 pvc, 0.02" slots — FROM 73.95 TO 104.5

DEPTH ( )	SAMPLE TYPE AND NUMBER	SAMPLE DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	PROFILE	DESCRIPTION	WELL CONSTRUCTION SUMMARY
60						Clay, red to reddish brown, minimum to moderate silt, very uniform, slightly moist, oxidized	0
70						Gravel, medium grayish brown, trace to minimum silt/clay, round to very angular grains, minimum to moderate sand	12-1/4" dia. Volclay grout Top of sand: 69.5' Top of screen: 73.55'
80							Centralizer 9-7/8" dia. 4-1/2" dia. sch. 80 scr
90							
100						96' to 110' – same as above, but slightly more coarse matrix	Centralizer 104.50'
110							Slough Hole to 112'
120							

NOTES

Conductor casing remains in hole to 63' (12-1/4") below 63', 9-7/8" dia. hole

01018

STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLATS PROJECT NO.: 68607	BORING NUMBER: GWQ 94-14 (SITE #11)	COORDINATES OR LOCATION: 713,428.61 N 603,827.45 E
LOGGED BY: PTA CHECKED BY:	SURFACE ELEVATION: 5169.05'	GWL DEPTH: 140'. (ENCOUNTERED) DEPTH: 1.585' (STATIC)
DRILLING METHOD: AUGER TO 94' ROTARY 94' +	HOLE DIAMETER: 6"	FLUID USED: MUD @ 94'
		DATE STARTED: 9/27/94 COMPLETED:

CASING TYPE AND SIZE: 4" dia. Sched. 40 pvc — FROM 2.36 A.G.S. TO 127.5 B.G.S.
SCREEN TYPE AND SIZE: 4" dia. Sched. 40 pvc, 0.02" slots — FROM 127.5' TO 157.5'

DEPTH ( )	SAMPLE TYPE AND NUMBER	SAMPLE DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	PROFILE	DESCRIPTION
0	Auger cuttings	0–5'				Light brown silty fine to medium sand and fine gravel, very poorly sorted with gravel ranging up to 3" in size, contains clay lenses and some small pieces of basalt
5	Auger cuttings	5–10'				
10	Auger cuttings	10–15'				Same as above – moist, thin basalt flows, gravel sizes smaller
15	Auger cuttings	15–20'				Between 15' and 20' – a thin (~~8" thick) dike
20	Auger cuttings	20–25'				Same as above – lighter in color, almost white
25	Auger cuttings	25–30'				Red clay containing minor silt and sand
30						



WELL CONSTRUCTION SUMMARY

NOTES

Used 8 bags of volclay
Development time = 6.62 hours
Average flow = 12 gpm
Date: 10/2/94

Static water = 1,585 from TOC (11/7/94)

Well head protection – 8" dia. steel pipe w/locking well cap, approx. 3.5' above surface.

01019

STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLATS PROJECT NO.: 68607	BORING NUMBER: GWQ 94-14 (SITE #11)	COORDINATES OR LOCATION: 713,428.61 N 603,827.45 E
LOGGED BY: PTA CHECKED BY:	SURFACE ELEVATION: 5169.05'	GWL DEPTH: 140' (ENCOUNTERED) DEPTH: 1.585' (STATIC)
DRILLING METHOD: AUGER TO 94' ROTARY 94' +	HOLE DIAMETER: 6"	FLUID USED: MUD
DATE STARTED: 9/27/94 COMPLETED:		

CASING TYPE AND SIZE: 4" dia. Sched. 40 pvc — FROM 2.36 A.G.S. TO 127.5 B.G.S.
SCREEN TYPE AND SIZE: 4" dia. Sched. 40 pvc, 0.02" slots — FROM 127.5' TO 157.5'

DEPTH ( )	SAMPLE TYPE AND NUMBER	SAMPLE DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	PROFILE	DESCRIPTION
30	Auger cuttings	30–35'				Red clay containing little silt and coarse sand
35	Auger cuttings	35–40'				
40	Auger cuttings	40–45'				
45	Auger cuttings	45–50'				Red clay as above, appears to be drier and siltier
50	Auger cuttings	50–55'				
55	Auger cuttings	55–60'				
60						



WELL CONSTRUCTION SUMMARY

NOTES

STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLATS PROJECT NO.: 68607	BORING NUMBER: GWQ 94-14 (SITE #11)	COORDINATES OR LOCATION:	713,428.61 N 603,827.45 E
LOGGED BY: PTA CHECKED BY:	SURFACE ELEVATION: 5169.05'	GWL	DEPTH: 140' (ENCOUNTERED) DEPTH: 1.585' (STATIC)
DRILLING METHOD: AUGER TO 94' ROTARY 94' +	HOLE DIAMETER: 6"	FLUID USED: MUD	DATE STARTED: 9/27/94 COMPLETED:
CASING TYPE AND SIZE: 4" dia. Sched. 40 pvc SCREEN TYPE AND SIZE: 4" dia. Sched. 40 pvc, 0.02" slots		FROM 2.36 A.G.S. TO 127.5 B.G.S. FROM 127.5' TO 157.5'	

DEPTH ( )	SAMPLE TYPE AND NUMBER	SAMPLE DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	PROFILE	DESCRIPTION	WELL CONSTRUCTION SUMMARY
60	Auger cuttings	60-65'				Red clay with some silt and rare coarse sand as above	0
65	Auger cuttings	65-70'					
70	Auger cuttings	70-75'				Red clay as above, appears to have less silty material and more moisture	Volclay
75	Auger cuttings	75-80'					
80	Auger cuttings	80-85'					
85	Auger cuttings	85-90'					
90							

NOTES

STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLATS PROJECT NO.: 68607	BORING NUMBER: GWQ 94-14 (SITE #11)	COORDINATES OR LOCATION: 713,428.61 N 603,827.45 E
LOGGED BY: PTA CHECKED BY:	SURFACE ELEVATION: 5169.05'	GWL DEPTH: 140' (ENCOUNTERED) DEPTH: 1.585' (STATIC)
DRILLING METHOD: AUGER TO 94' ROTARY 94' +	HOLE DIAMETER: 6"	FLUID USED: MUD
DATE STARTED: 9/27/94 COMPLETED:		

CASING TYPE AND SIZE: 4" dia. Sched. 40 pvc
SCREEN TYPE AND SIZE: 4" dia. Sched. 40 pvc, 0.02" slots

FROM 2.36 A.G.S. TO 127.5 B.G.S.
FROM 127.5' TO 157.5'

DEPTH ( )	SAMPLE TYPE AND NUMBER	SAMPLE DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	PROFILE	DESCRIPTION
90						Red clay (continued)
95	Rotary cuttings w/mud	95-100' sample not washed				Basalt, changed to rotary w/mud Red Clay
100	Rotary cuttings w/mud	100-105'				
105	Rotary cuttings w/mud	105-110'				
110	Rotary cuttings w/mud	110-115'				
115	Rotary cuttings w/mud	115-120'				
120						

WELL CONSTRUCTION SUMMARY



NOTES

6' sample from 94' - 100' not washed. From 100' on samples are washed.

Bentonite was placed by mixing with water and pumping down the hole in a slurry. 50 pounds of bentonite was used.

STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLATS PROJECT NO.: 68607	BORING NUMBER: GWQ 94-14 (SITE #11)	COORDINATES OR LOCATION: 713,428.61 N 603,827.45 E
LOGGED BY: PTA CHECKED BY:	SURFACE ELEVATION: 5169.05'	GWL DEPTH: 140' (ENCOUNTERED) DEPTH: 1.585' (STATIC)
DRILLING METHOD: AUGER TO 94' ROTARY 94' +	HOLE DIAMETER: 6"	FLUID USED: MUD
DATE STARTED: 9/27/94 COMPLETED:		

CASING TYPE AND SIZE: 4" dia. Sched. 40 pvc — FROM 2.36 A.G.S. TO 127.5 B.G.S.
SCREEN TYPE AND SIZE: 4" dia. Sched. 40 pvc, 0.02" slots — FROM 127.5' TO 157.5'

DEPTH ( )	SAMPLE TYPE AND NUMBER	SAMPLE DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	PROFILE	DESCRIPTION
120	Rotary cuttings w/mud	120–125'				
125	Rotary cuttings w/mud	125–128'				Gravel, driller calls this "rock" so must be cemented
	Rotary cuttings w/mud	128–130'				Interbedded clay and cemented gravel
130	Rotary cuttings w/mud	130–135'				Red clay (note: this is from information from driller, cuttings are gravel and clay)
135	Rotary cuttings w/mud	135–140'				Gravel and clay, interbedded clay layers are ~2' thick
140	Rotary cuttings w/mud	140–145'				Gravel, driller thinks he hit water
145	Rotary cuttings w/mud	145–150'				
150						



WELL CONSTRUCTION SUMMARY

NOTES

Sand is CSSI silica sand – environmental media
4 bags of sand were used

STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLATS PROJECT NO.: 68607	BORING NUMBER: GWQ 94-14 (SITE #11)	COORDINATES OR LOCATION: 713,428.61 N 603,827.45 E
LOGGED BY: PTA CHECKED BY:	SURFACE ELEVATION: 5169.05'	GWL DEPTH: 140' (ENCOUNTERED) DEPTH: 1.585' (STATIC)
DRILLING METHOD: AUGER TO 94' ROTARY 94' +	HOLE DIAMETER: 6"	FLUID USED: MUD
		DATE STARTED: 9/27/94 COMPLETED:

CASING TYPE AND SIZE: 4" dia. Sched. 40 pvc — FROM 2.36' A.G.S. TO 127.5' B.G.S.
SCREEN TYPE AND SIZE: 4" dia. Sched. 40 pvc, 0.02" slots — FROM 127.5' TO 157.5'

DEPTH ( )	SAMPLE TYPE AND NUMBER	SAMPLE DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	PROFILE	DESCRIPTION	WELL CONSTRUCTION SUMMARY
150	Rotary cuttings w/mud	95-100'				Gravel (continued)	0
155	Rotary cuttings w/mud	95-100'				Plugged bit Total depth = 158'	Screen 0.020 slots 157.5'
160							
165							
170							
175							
180							

NOTES

Screen is 4" dia. sch. 40 pvc

Steffen Robertson and Kirsten
Engineering and Environmental Consultants

LOG OF MONITORING WELL GWQ94-15

WELL DIAGRAM



DEPTH (ft)	SAMPLES	SYMBOLS	MATERIALS DESCRIPTION
0			0-15', Light brown silty-sandy gravel. Very poorly sorted. Sand size is medium and finer. Gravel is poorly sorted with most size pebble or smaller (mostly < 10mm but some large pebbles. Note: 6.5'-7.5'± and 12.5'-13.5'± Basalt layers
15			15'-24', Clayey, silty sand and gravel - similar to above with clay layers. Sand and gravel is light brown; clay is red.
25			24'-30', Red silty clay with fragments of basalt in cuttings. Dry.
30			30'-35', Red, silty, sandy clay.
35			35'-89', Red, silty clay. Dry.
60			Moist at 60'.

PROJECT Copper Flat - Hillsboro, N.M.
LOCATION N712922.14, E603803.73 N.M. S.P.C.
JOB NUMBER 68607 (ref: 68607Q15)
GEOLOGIST P.T.A.
DRILL RIG Auger to 89', Rotary 89'+

DRILLING COMPANY Beylik Drilling
DATE DRILLED 10/01/94 - 10/04/94
SURFACE ELEVATION 5159.35
TOTAL DEPTH OF HOLE 148.0 Feet
WATER LEVEL Static, from TOC on 11/7/94: 0.83 Feet

Steffen Robertson and Kirsten
Engineering and Environmental Consultants

LOG OF MONITORING WELL GWQ94-15



PROJECT Copper Flat - Hillsboro, N.M.
LOCATION N712922.14, E603803.73 N.M. S.P.C.
JOB NUMBER 68607 (ref: 68607015)
GEOLOGIST P.T.A.
DRILL RIG Auger to 89', Rotary 89'+

DRILLING COMPANY Beylik Drilling
DATE DRILLED 10/01/94 - 10/04/94
SURFACE ELEVATION 5159.35
TOTAL DEPTH OF HOLE 148.0 Feet
WATER LEVEL Static, from TOC on 11/7/94: 0.63 Feet

Steffen Robertson and Kirsten
Engineering and Environmental Consultants

LOG OF MONITORING WELL GWQ94-16

WELL DIAGRAM



NOTE: Well developed 10/6/94, for 3 hrs. at 15 gpm

DEPTH (ft)	SAMPLES	SYMBOLS	MATERIALS DESCRIPTION
			0-6', Gravel w/minor sand and grey clay, increasing pebble size from 1/8"-1/4" to 1/4"-3/4"
5			6'-7', Pea size gravel
			7'-7.5', Sandy gravel
			7.5'-8', Red, clayey, sandy gravel
10			8'-9', clayey gravel (red)
			9'-10', Coarser gravel w/red clay @ 9' (GM)
			10'-12', Thin (<4") layer of white clay fragments in red clay matrix
15			12'-17', Red clay minor gravel
			17'-18', Gravel w/red clay matrix
			18'-23', Red clay w/minor gravel, soft w/ some moisture (CH)
20			
			23'-24', Increasing gravel in red clay. (1/4-3/4")
25			24'-26', Red clay w/pea size gravel
			26'-27.5', Larger gravel +1"
			27.5'-28.5', Red clay w/minor gravel
30			28.5'-29', 6" grey green clay increasing in moisture - clay dark
			29'-32', Red sticky clay w/minor gravel, slightly moist.
			32'-33', Increase in moisture, consistency of potters clay
35			33'-37', Red clay, v. moist.
			37'-45', basalt
40			
45			Total depth = 45'
50			

PROJECT Copper Flat - Hillsboro, N.M.
LOCATION N713191.10, E603249.22 N.M. S.P.C.
JOB NUMBER 68607 (ref: 68607Q16)
GEOLOGIST J.V. Parshley
DRILL RIG Auger

DRILLING COMPANY Beylik Drilling
DATE DRILLED 10/04/94
SURFACE ELEVATION 5173.71
TOTAL DEPTH OF HOLE 45 Feet
WATER LEVEL Static, from TOC on 11/7/94: 18.23 Feet

STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLAT PROJECT NO.: 68607	BORING NUMBER: GWQ 94-17	COORDINATES OR LOCATION: 713,549.66 N 603,465.41 E
LOGGED BY: JVP CHECKED BY:	SURFACE ELEVATION: 5175.23'	GWL DEPTH: 50' & 121' (ENCOUNTERED) DEPTH: 5.32' (STATIC)
DRILLING METHOD: AUGER/ROTARY	HOLE DIAMETER: 12"	FLUID USED: MUD @ 18'
		DATE STARTED: 10/5/94 COMPLETED: 10/09/94

CASING TYPE AND SIZE: 4" dia. Sched. 40 pvc — FROM 1.74' A.G.S. TO 120' B.G.S.
SCREEN TYPE AND SIZE: 4" dia. Sched. 40 pvc, 0.02" slots — FROM 120' TO 150'

DEPTH ( )	SAMPLE TYPE AND NUMBER	SAMPLE DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	PROFILE	DESCRIPTION
0						Gravel with silt and some clay, gray angular fragments, 1/2" and fragments
5						Change in color, red increasing clay, gravel fragments rounded 1/4" to 3/4"
10						White gravel with clay fragments 1/4" to 1/2"
						Red fine grained clayey gravel
						Red clay/silt with minor fine gravel
15						Basalt
						Switch to rotary, water only
20						
25						Sandy red clay, sticky thick clay with minor sand
30						

WELL CONSTRUCTION SUMMARY



NOTES

Development time = 2.15 hours
Average flow = 15 gpm
Date: 10/21/94

Static water = 5.32 from TOC (11/7/94)

Well head protection - 8" dia. steel pipe w/locking well cap, approx. 3.5' above surface.

STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLAT PROJECT NO.: 68607	BORING NUMBER: GWQ 94-17	COORDINATES OR LOCATION: 713,549.41 N 603,465.61 E
LOGGED BY: JVP CHECKED BY:	SURFACE ELEVATION: 5175.23'	GWL DEPTH: 50' & 121' (ENCOUNTERED) DEPTH: 5.32' (STATIC)
DRILLING METHOD: AUGER/ROTARY	HOLE DIAMETER: 12"	FLUID USED: MUD @ 18'
		DATE STARTED: 10/5/94 COMPLETED: 10/09/94
CASING TYPE AND SIZE: 4" dia. Sched. 40 pvc SCREEN TYPE AND SIZE: 4" dia. Sched. 40 pvc, 0.02" slots		FROM 1.74' A.G.S. TO 120' B.G.S. FROM 120' TO 150'

DEPTH ( )	SAMPLE TYPE AND NUMBER	SAMPLE DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	PROFILE	DESCRIPTION	WELL CONSTRUCTION SUMMARY
30						Red clay with minor sand (coarse)	0
35						Some fragments of fine gravel 1/2" to 3/4"	
40						Red clay with coarse sand (minor), occasional gravel fragments +1/2", sample seems wetter, but may just be sampling procedure	Volclay
45						Some coarse sand (@ 47' - 49'?)	
50						Clayey gravel, red clay matrix and clasts of volc, etc. including basalt May have hit water at lithology change, quit drilling, temporarily sit pvc screen, bailed well dry and let sit for 2 hours, water level recovered to 47'	
55							
60						Stop drilling 10/6/94, wait overnight to see if water	

NOTES

STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLAT PROJECT NO.: 68607	BORING NUMBER: GWQ 94-17	COORDINATES OR LOCATION: 713,549.44 N 603,465.41 E
LOGGED BY: JVP CHECKED BY:	SURFACE ELEVATION: 5175.23'	GWL DEPTH: 50' & 121' (ENCOUNTERED) DEPTH: 5.32' (STATIC)
DRILLING METHOD: AUGER/ROTARY	HOLE DIAMETER: 12"	FLUID USED: MUD @ 18'
		DATE STARTED: 10/5/94 COMPLETED: 10/09/94
CASING TYPE AND SIZE: 4" dia. Sched. 40 pvc SCREEN TYPE AND SIZE: 4" dia. Sched. 40 pvc, 0.02" slots	FROM 1.74' A.G.S. TO 120' B.G.S. FROM 120' TO 150'	

DEPTH ( )	SAMPLE TYPE AND NUMBER	SAMPLE DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	PROFILE	DESCRIPTION	WELL CONSTRUCTION SUMMARY
60						Sandy clay with occasional gravel, red sticky clay abundant, occasional white clay fragments	0
65							
70						Sand very minor, clay in small fragments even in wet hole	Volclay
75						White clay fragments (sand-size) increasing to 1 - 2%	
80							
85						Clay coming up as small fragments (coarse sand size) still some white clay fragments, minor sand	
90							

NOTES

STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLAT PROJECT NO.: 68607	BORING NUMBER: GWQ 94-17	COORDINATES OR LOCATION: 713,549.41 N 603,465.61 E
LOGGED BY: JVP CHECKED BY:	SURFACE ELEVATION: 5175.23'	GWL DEPTH: 50' & 121' (ENCOUNTERED) DEPTH: 5.32' (STATIC)
DRILLING METHOD: AUGER/ROTARY	HOLE DIAMETER: 12"	FLUID USED: MUD @ 18'
		DATE STARTED: 10/5/94 COMPLETED: 10/09/94
CASING TYPE AND SIZE: 4" dia. Sched. 40 pvc SCREEN TYPE AND SIZE: 4" dia. Sched. 40 pvc, 0.02" slots	FROM 1.74' A.G.S. TO 120' B.G.S. FROM 120' TO 150'	

DEPTH ( )	SAMPLE TYPE AND NUMBER	SAMPLE DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	PROFILE	DESCRIPTION	WELL CONSTRUCTION SUMMARY
90						Red clay with very minor sand, clay breaking into coarse sand size fragments, same white clay fragments	0
95							
100							Volclay grout
105						Increase in sand or sand interbeds, white clay fragments common (sand sized)	
110						Increasing sand to clayey sand	
115						Less sandy-clayey sand (red)	Bentonite seal Top of sand pack
120							

NOTES

12 bags of sand (50 pound bags)
50 pounds of bentonite

STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLAT PROJECT NO.: 68607	BORING NUMBER: GWQ 94-17	COORDINATES OR LOCATION: 713,549.44 N 603,465.41 E
LOGGED BY: JVP CHECKED BY:	SURFACE ELEVATION: 5175.23'	GWL DEPTH: 50' & 121' (ENCOUNTERED) DEPTH: 5.32' (STATIC)
DRILLING METHOD: AUGER/ROTARY	HOLE DIAMETER: 12"	FLUID USED: MUD @ 18'
		DATE STARTED: 10/5/94 COMPLETED: 10/09/94

CASING TYPE AND SIZE: 4" dia. Sched. 40 pvc FROM 1.74' A.G.S. TO 120' B.G.S.
SCREEN TYPE AND SIZE: 4" dia. Sched. 40 pvc, 0.02" slots FROM 120' TO 150'

DEPTH ( )	SAMPLE TYPE AND NUMBER	SAMPLE DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	PROFILE	DESCRIPTION	WELL CONSTRUCTION SUMMARY
120						Clayey sand, red clay occasional, white clay fragments, possible water at 121'?	0
125							
130						Stopped 10/7/94, spent 10/8/94 trying to complete hole. Had to add bentonite, start drilling again 10/9/94 Gravel, very minimal clay, pea gravel, definitely hit water, mostly dark and green fragments propylitized volcanic fragments 1/2" to +1", gravel size increasing	4" dia. pvc sch. 40 #20 screen
135							
140							
145							
150							Bottom of screen

NOTES

STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLAT PROJECT NO.: 68607	BORING NUMBER: GWQ 94-17	COORDINATES OR LOCATION: 713,549.44 N 603,465.41 E
LOGGED BY: JVP CHECKED BY:	SURFACE ELEVATION: 5175.23'	GWL DEPTH: 50' & 121' (ENCOUNTERED) DEPTH: 5.32' (STATIC)
DRILLING METHOD: AUGER/ROTARY	HOLE DIAMETER: 12"	FLUID USED: MUD @ 18'
DATE STARTED: 10/5/94 COMPLETED: 10/09/94		
CASING TYPE AND SIZE: 4" dia. Sched. 40 pvc SCREEN TYPE AND SIZE: 4" dia. Sched. 40 pvc, 0.02" slots	FROM 1.74' A.G.S. TO 120' B.G.S. FROM 120' TO 150'	

DEPTH ( )	SAMPLE TYPE AND NUMBER	SAMPLE DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	PROFILE	DESCRIPTION	WELL CONSTRUCTION SUMMARY
150						Gravel, few rounded fragments, fairly large pebbles, very minor red clay in matrix	0
155							Sand backfill
						Total depth 158'	
160							
165							
170							
175							
180							

NOTES

Steffen Robertson and Kirsten
Engineering and Environmental Consultants

LOG OF MONITORING WELL GWQ94-19

WELL DIAGRAM





PROJECT	Copper Flat - Hillsboro, N.M.	DRILLING COMPANY	Beylik Drilling
LOCATION	N713751.31, E603378.24 N.M. S.P.C.	DATE DRILLED	10/11/94
JOB NUMBER	68607 (ref: 68607Q19)	SURFACE ELEVATION	5180.29
GEOLOGIST	CW	TOTAL DEPTH OF HOLE	54 Feet
DRILL RIG	Auger	WATER LEVEL	DRY

Steffen Robertson and Kirsten
Engineering and Environmental Consultants

LOG OF MONITORING WELL GWQ94-18

WELL DIAGRAM





MATERIALS DESCRIPTION

0 - 12', Interbedded clayey gravels & silts

12'-17', Clayey silt

17'-60', Red clay

Red clay (CH)

Total depth = 60 Feet

PROJECT Copper Flat - Hillsboro, N.M.	DRILLING COMPANY Beylik Drilling
LOCATION N713356.22, E603381.90 N.M. S.P.C.	DATE DRILLED 10/94
JOB NUMBER 68607 (ref: 68607Q18)	SURFACE ELEVATION 5171.94
GEOLOGIST J.V. Parshley	TOTAL DEPTH OF HOLE 60.0 Feet
DRILL RIG Auger	WATER LEVEL DRY

STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLATS PROJECT NO.: 68607	BORING NUMBER: GWQ 94-20	COORDINATES OR LOCATION: 713,671.45 N 603,230.91 E
LOGGED BY: CW CHECKED BY:	SURFACE ELEVATION: 5180.12	GWL DEPTH: 55.0 (ENCOUNTERED) DEPTH: 10.53' (STATIC)
DRILLING METHOD: ROTARY	HOLE DIAMETER: 8 3/8"	FLUID USED: AIR
		DATE STARTED: 10/10/94 COMPLETED: 10/24/94

CASING TYPE AND SIZE: 4-1/2" dia. Sched. 80 pvc — FROM 1.85' A.G.S. TO 288' B.G.S.
SCREEN TYPE AND SIZE: 4-1/2" dia. Sched. 80 pvc, 0.02" slots — FROM 288' TO 338'

DEPTH ( )	SAMPLE TYPE AND NUMBER	SAMPLE DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	PROFILE	DESCRIPTION
0						Soil, medium to dark brown, abundant pebbles and cobbles, abundant sand/silt, weathered material
						Gravel/fill, light to medium brown, abundant pebbles and cobbles, minimum to moderate sand, trace to minimum silt, weathered, oxidized, dry, very choppy drilling
10						Rhyolite, buff to light brown, very hard, smooth drilling, minor phenocrysts on fresh surfaces
20						Clay, reddish brown, trace pebbles and cobbles, medium to abundant silt, very smooth drilling, slightly moist, oxidized, (1st water @ 55'), trace sand
30						
40						
50						
60						

WELL CONSTRUCTION SUMMARY



NOTES

Development time = 1.65 hours
Date: 10/26/94 Time = 0.65 hrs Avg. flow = 15 gpm
Date: 10/31/94 Time = 0.50 hrs Avg. flow = 10 gpm
Date: 11/03/94 Time = 0.50 hrs Avg. flow = 11 gpm

Static water = 24.32' from TOC (11/07/94)

Well head protection - 8" dia. steel pipe w/locking well cap, approx. 3.5' above surface.

STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLATS PROJECT NO.: 68607	BORING NUMBER: GWQ 94-20	COORDINATES OR LOCATION: 713,671.45 N 603,230.91 E
LOGGED BY: CW CHECKED BY:	SURFACE ELEVATION: 5180.12	GWL DEPTH: 55.0 (ENCOUNTERED) DEPTH: 10.53 (STATIC)
DRILLING METHOD: ROTARY	HOLE DIAMETER: 8 3/8"	FLUID USED: AIR
		DATE STARTED: 10/10/94 COMPLETED: 10/24/94

CASING TYPE AND SIZE: 4-1/2" dia. Sched. 80 pvc — FROM 1.85' A.G.S. TO 288' B.G.S.
SCREEN TYPE AND SIZE: 4-1/2" dia. Sched. 80 pvc, 0.02" slots — FROM 288' TO 338'

DEPTH ( )	SAMPLE TYPE AND NUMBER	SAMPLE DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	PROFILE	DESCRIPTION	WELL CONSTRUCTION SUMMARY
60						Clay, reddish brown, trace pebbles and cobbles, moderate to abundant silt, very smooth drilling, trace sand, oxidized	0
70							
						Gravel, medium brown, moderate to abundant clay/silt matrix in zones, very poorly sorted, wet	
80							Volclay grout
90							
100							
110						Clayey zone 115' to 122'	
120							

NOTES

STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLATS PROJECT NO.: 68607	BORING NUMBER: GWQ 94-20	COORDINATES OR LOCATION: 713,428.61 N 603,827.45 E
LOGGED BY: CW CHECKED BY:	SURFACE ELEVATION: 5180.12	GWL DEPTH: 55.0 (ENCOUNTERED) DEPTH: 10.53 (STATIC)
DRILLING METHOD: ROTARY	HOLE DIAMETER: 8 3/8"	FLUID USED: AIR
		DATE STARTED: 10/10/94 COMPLETED: 10/24/94

CASING TYPE AND SIZE: 4-1/2" dia. Sched. 80 pvc — FROM 1.85' A.G.S. TO 127.5' B.G.S.
SCREEN TYPE AND SIZE: 4-1/2" dia. Sched. 80 pvc, 0.02" slots — FROM 288' TO 338'

DEPTH ( )	SAMPLE TYPE AND NUMBER	SAMPLE DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	PROFILE	DESCRIPTION	WELL CONSTRUCTION SUMMARY
120						Gravel, medium brown, moderate to abundant clay/silt matrix in zones, very poorly sorted, wet.	0
130						Clayey zone 127' to 130'	
140							Volclay grout
150						Clayey zone 145' to 147'	
160						Clayey zone 152' to 155'	
170							
180							

NOTES

STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLATS PROJECT NO.: 68607	BORING NUMBER: GWQ 94-20	COORDINATES OR LOCATION: 713,428.61 N 603,827.45 E
LOGGED BY: CW CHECKED BY:	SURFACE ELEVATION: 5180.12	GWL DEPTH: 55.0 (ENCOUNTERED) DEPTH: 10.53 (STATIC)
DRILLING METHOD: ROTARY	HOLE DIAMETER: 8 3/8"	FLUID USED: AIR
		DATE STARTED: 10/10/94 COMPLETED: 10/24/94

CASING TYPE AND SIZE: 4-1/2" dia. Sched. 80 pvc — FROM 1.85' A.G.S. TO 127.5' B.G.S.
SCREEN TYPE AND SIZE: 4-1/2" dia. Sched. 80 pvc, 0.02" slots — FROM 288' TO 338'

DEPTH ( )	SAMPLE TYPE AND NUMBER	SAMPLE DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	PROFILE	DESCRIPTION	WELL CONSTRUCTION SUMMARY
180						Gravel, medium brown, moderate to abundant, clay/silt matrix in zones, very poorly sorted, wet.	0
190							
						Clayey zone 197' to 201'	
200							Volclay grout
210							
220							
230							
240							

NOTES

STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLATS PROJECT NO.: 68607	BORING NUMBER: GWQ 94-20	COORDINATES OR LOCATION: 713,428.61 N 603,827.45 E
LOGGED BY: CW CHECKED BY:	SURFACE ELEVATION: 5180.12	GWL DEPTH: 55.0 (ENCOUNTERED) DEPTH: 10.53 (STATIC)
DRILLING METHOD: ROTARY	HOLE DIAMETER: 8 3/8"	FLUID USED: AIR
		DATE STARTED: 10/10/94 COMPLETED: 10/24/94
CASING TYPE AND SIZE: 4-1/2" dia. Sched. 80 pvc SCREEN TYPE AND SIZE: 4-1/2" dia. Sched. 80 pvc, 0.02" slots		FROM 1.85' A.G.S. TO 127.5' B.G.S. FROM 288' TO 338'

DEPTH ( )	SAMPLE TYPE AND NUMBER	SAMPLE DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	PROFILE	DESCRIPTION
240						Gravel, medium brown, moderate to abundant clay/silt matrix, very poorly sorted, abundant pebbles and cobbles, minimum to moderate sand, wet
250						
260						
270						Clay, medium brown with minimum to moderate sand, minimum to moderate pebbles and cobbles, smooth drilling, little to no water production
280						
290						Gravel, medium brown, abundant pebbles and cobbles, minimum to moderate sand, moderate to abundant clay/silt matrix, wet
300						



NOTES

STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLATS PROJECT NO.: 68607	BORING NUMBER: GWQ 94-20	COORDINATES OR LOCATION: 713,428.61 N 603,827.45 E
LOGGED BY: CW CHECKED BY:	SURFACE ELEVATION: 5180.12	GWL DEPTH: 55.0 (ENCOUNTERED) DEPTH: 10.53 (STATIC)
DRILLING METHOD: ROTARY	HOLE DIAMETER: 8 3/8"	FLUID USED: AIR
		DATE STARTED: 10/10/94 COMPLETED: 10/24/94

CASING TYPE AND SIZE: 4-1/2" dia. Sched. 80 pvc — FROM 1.85' A.G.S. TO 127.5' B.G.S.
SCREEN TYPE AND SIZE: 4-1/2" dia. Sched. 80 pvc, 0.02" slots — FROM 288' TO 338'

DEPTH ( )	SAMPLE TYPE AND NUMBER	SAMPLE DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	PROFILE	DESCRIPTION	WELL CONSTRUCTION SUMMARY
300						Gravel, medium brown, abundant pebbles and cobbles, minimum to moderate sand, moderate to abundant clay/silt matrix, wet	0
310							Centralizer 4-1/2" dia. pvc sch. 80 20 slot screen (50' total)
320						Clay lense, medium brown with minimum to moderate pebbles and cobbles, little to no water production Gravel, medium brown, abundant pebbles and cobbles, minimum to moderate sand, moderate to abundant clay/silt matrix, wet	Centralizer
330							Centralizer
340						Total depth 340'	Bottom cap
350							
360							

NOTES

STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLAT PROJECT NO.: 68607	BORING NUMBER: GWQ 94-21A GWQ 94-21B	COORDINATES OR LOCATION: 713,492.54 N 604,084.48 E
LOGGED BY: CW CHECKED BY:	SURFACE ELEVATION: 5168.8	GWL DEPTH: 210 (ENCOUNTERED) DEPTH: SEE BELOW (STATIC)
DRILLING METHOD: ROTARY	HOLE DIAMETER: 9 5/8"	FLUID USED: AIR
DATE STARTED: 10/25/94 COMPLETED: 11/05/94		
CASING TYPE AND SIZE: 2" dia. Sched. 40 PVC SCREEN TYPE AND SIZE: 2" dia. Sched. 40 PVC 0.02" slot	FROM 2.5'/2' A.G.S. TO 213'/285' B.G.S. FROM 213'/285' TO 263'/315'	

DEPTH ( )	SAMPLE TYPE AND NUMBER	SAMPLE DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	PROFILE	DESCRIPTION
0						Soil/gravel, light brown to yellow brown, abundant pebbles and cobbles, abundant silt/clay, trace mineral sand, oxidized, dry
10						As above, but light to medium brown color
20						Basalt, medium dark gray to gray brown with both fresh and weathered fragments, dry
30						Rhyolite, buff to light brown, very hard/smooth drilling, fresh/unoxidized, dry
40						
50						Gravel, red brown with abundant clay/silt material, wet, no water on drilling, trace to minimum sand, oxidized
60						Clay, reddish brown, moderate to abundant silt, trace sand, trace pebbles, oxidized, moist but not wet



NOTES

Dual completion
Development time 21A = 8.5 hours
Development time 21B = 33 hours
Average flow 21A = 25 gpm Date: 11/7/94
Average flow 21B = 2 gpm Date: 11/7/94

Static water 21A = 4.58' from TOC (11/07/94)
Static water 21B = 3.95' from TOC (11/07/94)

Well head protection – 8" dia. steel pipe w/locking well cap approx. 3.5' above surface.

STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLAT PROJECT NO.: 68607	BORING NUMBER: GWQ 94-21A GWQ 94-21B	COORDINATES OR LOCATION: 713,492.54 N 604,084.48 E
LOGGED BY: CW CHECKED BY:	SURFACE ELEVATION: 5168.8	GWL DEPTH: 210 (ENCOUNTERED) DEPTH: (STATIC)
DRILLING METHOD: ROTARY	HOLE DIAMETER: 9 5/8"	FLUID USED: AIR
DATE STARTED: 10/25/94 COMPLETED: 11/05/94		
CASING TYPE AND SIZE: 2" dia. Sched. 40 PVC SCREEN TYPE AND SIZE: 2" dia. Sched. 40 PVC 0.02" slot	FROM 2.5'/2' A.G.S. TO 213'/285' B.G.S. FROM 213'/285' TO 263'/315'	

DEPTH ( )	SAMPLE TYPE AND NUMBER	SAMPLE DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	PROFILE	DESCRIPTION	WELL CONSTRUCTION SUMMARY
60						Clay, reddish brown, moderate to abundant silt, trace sand, trace pebbles, oxidized, moist but not wet	0
70							
80							Volclay grout
90							2" dia. pvc sch. 40
100						Large chips, silty, moist, at 100'	
110							
120							

NOTES

Start of clay (reddish brown) shown as 47' on geophysical log

STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLAT PROJECT NO.: 68607	BORING NUMBER: GWQ 94-21A GWQ 94-21B	COORDINATES OR LOCATION: 713,492.54 N 604,084.48 E
LOGGED BY: CW CHECKED BY:	SURFACE ELEVATION: 5168.8	GWL DEPTH: 210 (ENCOUNTERED) DEPTH: (STATIC)
DRILLING METHOD: ROTARY	HOLE DIAMETER: 9 5/8"	FLUID USED: AIR
DATE STARTED: 10/25/94 COMPLETED: 11/05/94		

CASING TYPE AND SIZE: 2" dia. Sched. 40 PVC
FROM 2.5'/2' A.G.S. TO 213'/285' B.G.S.
SCREEN TYPE AND SIZE: 2" dia. Sched. 40 PVC 0.02" slot
FROM 213'/285' TO 263'/315'

DEPTH ( )	SAMPLE TYPE AND NUMBER	SAMPLE DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	PROFILE	DESCRIPTION	WELL CONSTRUCTION SUMMARY
120						Clay, reddish brown, moderate to abundant silt, trace sand, trace pebbles, oxidized, moist but not wet	0
130							
140							Volclay grout
150							2" dia. pvc sch. 40
160						Gravel, medium brown with moderate to abundant sand, moderate to abundant clay/silt matrix	
170						Gravel, medium brown, abundant clay/silt matrix	
180							

NOTES

Red clay/gravel interface at 149' on geophysical log

STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLAT PROJECT NO.: 68607	BORING NUMBER: GWQ 94-21A GWQ 94-21B	COORDINATES OR LOCATION: 713,492.54 N 604,084.48 E
LOGGED BY: CW CHECKED BY:	SURFACE ELEVATION: 5168.8	GWL DEPTH: 210 (ENCOUNTERED) DEPTH: (STATIC)
DRILLING METHOD: ROTARY	HOLE DIAMETER: 9 5/8"	FLUID USED: AIR
DATE STARTED: 10/25/94 COMPLETED: 11/05/94		
CASING TYPE AND SIZE: 2" dia. Sched. 40 PVC SCREEN TYPE AND SIZE: 2" dia. Sched. 40 PVC 0.02" slot	FROM 2.5'/2' A.G.S. TO 213'/285' B.G.S. FROM 213'/285' TO 263'/315'	

DEPTH ( )	SAMPLE TYPE AND NUMBER	SAMPLE DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	PROFILE	DESCRIPTION	WELL CONSTRUCTION SUMMARY
180						Gravel, medium brown with abundant sand, moderate clay/silt matrix.	0
190						Gravel, medium brown to grey brown, moderate sand, abundant clay/silt matrix	2" dia. Sched. 40 pvc
200							Volclay grout
210						Gravel, gray to gray brown, minimum to moderate clay/silt, abundant pebbles and cobbles, minimum to moderate sand (medium to coarse) (makes 20 to 30 gpm on drilling)	Bentonite seal 16-40 sand Top of screen 21A
220							10-20 sand
230							
240							

NOTES

Well construction summary enlarged.

STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLAT PROJECT NO.: 68607	BORING NUMBER: GWQ 94-21A GWQ 94-21B	COORDINATES OR LOCATION: 713,492.54 N 604,084.48 E
LOGGED BY: CW CHECKED BY:	SURFACE ELEVATION: 5168.8	GWL DEPTH: 210 (ENCOUNTERED) DEPTH: SEE BELOW (STATIC)
DRILLING METHOD: ROTARY	HOLE DIAMETER: 9 5/8"	FLUID USED: AIR
		DATE STARTED: 10/25/94 COMPLETED: 11/05/94
CASING TYPE AND SIZE: 2" dia. Sched. 40 PVC SCREEN TYPE AND SIZE: 2" dia. Sched. 40 PVC 0.02" slot		FROM 2.5'/2' A.G.S. TO 213'/285' B.G.S. FROM 213'/285' TO 263'/315'

DEPTH ( )	SAMPLE TYPE AND NUMBER	SAMPLE DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	PROFILE	DESCRIPTION	WELL CONSTRUCTION SUMMARY
240						Very coarse sand to gravel in a heavy clay/silt matrix, brown, abundant pebbles, oxidized and subangular gravel	0
250						Water produced from purging only - volume decreases with depth	10-20 sand 2" dia. pvc sch. 40 0.020" screen
260							2" dia. pvc sch. 40 blank Bottom of screen 21A
270							16-40 sand
280							Bentonite seal 16-40 sand
290							Top of screen 21B 10-20 sand
300							2" dia. pvc sch. 40 0.020" screen

NOTES

From 240' down, the clay/silt matrix appears to grow progressively less permeable.

Well contruction summary enlarged.

STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLAT PROJECT NO.: 68607	BORING NUMBER: GWQ 94-21A GWQ 94-21B	COORDINATES OR LOCATION: 713,492.54 N 604,084.48 E
LOGGED BY: CW CHECKED BY:	SURFACE ELEVATION: 5168.8	GWL DEPTH: 210 (ENCOUNTERED) DEPTH: (STATIC)
DRILLING METHOD: ROTARY	HOLE DIAMETER: 9 5/8"	FLUID USED: AIR
		DATE STARTED: 10/25/94 COMPLETED: 11/05/94
CASING TYPE AND SIZE: 2" dia. Sched. 40 PVC SCREEN TYPE AND SIZE: 2" dia. Sched. 40 PVC 0.02" slot	FROM 2.5'/2' A.G.S. TO 213'/285' B.G.S. FROM 213'/285' TO 263'/315'	

DEPTH ( )	SAMPLE TYPE AND NUMBER	SAMPLE DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	PROFILE	DESCRIPTION	WELL CONSTRUCTION SUMMARY
300						Very coarse sand to gravel in a clay/silt matrix, brown, abundant pebbles, subangular and oxidized	0
310						As above, but with larger water produced when purged As above but water beginning to thicken	2" dia. pvc sch. 40 0.020" screen Bottom of screen 21B
320						T.D. = 320.	10-20 sand
330							
340							
350							
360							

NOTES

Well construction summary enlarged.

Steffen Robertson and Kirsten
Engineering and Environmental Consultants

LOG OF MONITORING WELL MW-10



PROJECT Copper Flat - Hillsboro, N.M.	DRILLING COMPANY Beylik Drilling
LOCATION N719968.25, E636740.99 N.M. S.P.C.	DATE DRILLED 10/94
JOB NUMBER 68607 (ref: 68607M10)	SURFACE ELEVATION 4439.27
GEOLOGIST CW	TOTAL DEPTH OF HOLE 128.0 Feet
DRILL RIG Air Rotary	WATER LEVEL Static, from TOC on 11/7/94: 70.625 Feet

Steffen Robertson and Kirsten
Engineering and Environmental Consultants

LOG OF MONITORING WELL MW-10



PROJECT Copper Flat - Hillsboro, N.M.
LOCATION N719968.25, E636740.99 N.M. S.P.C.
JOB NUMBER 68607 (ref: 68607M10)
GEOLOGIST CW
DRILL RIG Air Rotary

DRILLING COMPANY Beylik Drilling
DATE DRILLED 10/94
SURFACE ELEVATION 4439.27
TOTAL DEPTH OF HOLE 128.0 Feet
WATER LEVEL Static, from TOC on 11/7/94: 79.626 Feet

Steffen Robertson and Kirsten
Engineering and Environmental Consultants

LOG OF MONITORING WELL MW-10



PROJECT	Copper Flat - Hillsboro, N.M.	DRILLING COMPANY	Beylik Drilling
LOCATION	N719968.25, E636740.99 N.M. S.P.C.	DATE DRILLED	10/94
JOB NUMBER	68607 (ref: 68607M10)	SURFACE ELEVATION	4439.27
GEOLOGIST	CW	TOTAL DEPTH OF HOLE	128.0 Feet
DRILL RIG	Air Rotary	WATER LEVEL	Static, from TOC on 11/7/94: 70.625 Feet

STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

LOG OF MONITORING WELL

PAGE 1 OF 1

PROJECT NAME: COPPER FLAT PROJECT NO.: 68607	BORING NUMBER: SRK BH-1-94	COORDINATES OR LOCATION:
LOGGED BY: HKP CHECKED BY:	SURFACE ELEVATION: PENDING	GWL DEPTH: 18' (ENCOUNTERED) DEPTH: N/A (STATIC)
DRILLING METHOD: CME-75 AUGER AND CORE	HOLE DIAMETER: 8"	FLUID USED: NONE
		DATE STARTED: 5/26/94 COMPLETED: 5/27/94

CASING TYPE AND SIZE: 2" dia. Sched. 40 pvc — FROM ±3' A.G.S. TO 36' B.G.S.
SCREEN TYPE AND SIZE: 2" dia. Sched. 40 pvc, 0.010" slots — FROM 36' TO 46'

DEPTH ( )	SAMPLE TYPE AND NUMBER	SAMPLE DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	DESCRIPTION
0					SW/GW, cobble (cover material)
	SS	5'-9'			Tailings, SP-SM, medium moist to moist, tan to light brown
10	SS	10'-12'			
	SS	15'-17'			Very moist to saturated
20	SS	20'-22'			Moist to very moist
	SS	25'-26'			Sand and gravel, clayey, some cobbles, clayey, medium graded, medium moist to moist
30	SS	30'-31.5'	11/6 6/6 8/6		
	SS	35'-36.5'	50/5.5		Basalt, basalt was drillable with hollow stem augers Refused at 47'
40	A	40'-45'			
	Core	48'±-53'±			Cored 48' to 53'
50					Total depth 53'
60					

WELL CONSTRUCTION SUMMARY



NOTES

Stand pipe piezometer 2" schedule 40 pvc flush thread

Well head protected with steel pipe w/locking cap

01051

Prepared by:

ADRIAN BROWN CONSULTANTS, INC.
Specialists in Environmental Protection, Remediation, and Groundwater Control
155 S. Madison Street - Suite 230 - Denver, Colorado 80209-3013

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLAT PROJECT NO.: 1356A		BORING NUMBER: GWQ96-22	COORDINATES N 717440 (APPROX.) OR LOCATION: E 589,920 (APPROX.)	
LOGGED BY: SW CHECKED BY:	SURFACE ELEVATION: 5590.0' AMSL	GWL DEPTH: ~ DEPTH: ~	(ENCOUNTERED) (STATIC)	A CASING: 2" SCH. 40 FROM: 2.30' A.G.S. TO 174' B.G.S. SCREEN: 2", 20 SLOT SCH. 40 FROM: 174' TO 244' B.G.S.
DRILLING METHOD: AIR ROTARY	HOLE DIAMETER: 8 3/4"	FLUID USED: WATER	DATE STARTED: 6/24/96 COMPLETED: 6/30/96	B CASING: 2" SCH. 40 FROM: 2.07' A.G.S. TO 340' B.G.S. SCREEN: 2", 20 SLOT SCH. 40 FROM: 340' B.G.S. TO 380' B.G.S.

SAMPLER TYPE AND NUMBER	SAMPLER DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	WATER	GRAPHIC LOG	DESCRIPTION	WELL COMPLETION DIAGRAM
				APPEARED DRY DURING DRILLING		ANDESITE; GRAYISH GREEN, FINE GRAINED, <5% OX., COMPETENT, PLAG. WEATHERED 5% MAFICS (PHENOCRYSTS AND MATRIX)	GWQ96-22A STICK-UP 2.30'; GWQ96-22B STICK-UP 2.07'; BENTONITE GROUT
						ANDESITE; DRK. GRAYISH GREEN, FINE GRAINED, <2% ox.	
						ANDESITE; DRK. GRAYISH GREEN, WITH RED CLAY	
						ANDESITE (BASALTIC?); OXIDATION, RINDS., OVERALL < 3% OX.	
						ANDESITE; VERY FINE GRAINED, LOCAL PLAG. PHENOCRYSTS UP TO 2 MM	
						ANDESITE W/MINOR CALCITE VEINLETS AND BLEBS., <1% SULFIDES, FINE GRAINED, .5-3MM PLAG., <3% OX.	
						ANDESITE; FINE GRAINED, <1% OX., 0.5-1.5MM SUBHEDRAL PLAG. AND RARE 3MM ANHEDRAL PLAG., DARK GREEN	
						ANDESITE; DRK GRAY, FINE GRAINED, 1MM CALCITE COATINGS ON FRX., <2% OX.	
						ANDESITE; DRK GRAY W/MINOR CALCITE FRX. FILLING UP TO 2MM WIDE, <1% OX.	
						ANDESITE; DRK GRAY, CALCITE FILLING, <2% OX.	
						ANDESITE; WITH CALCITE FILLINGS, OXIDATION ALONG FRACTURES NEAR COMPLETE	
						ANDESITE; PYRITE VEINLETS, <1% SULFIDES	

0 5 10 15 20 25 30 35 40 45 50 55 60

E:\1356A\1996\GWQ96-22.DWG 08/07/96

Prepared by:

ADRIAN BROWN CONSULTANTS, INC.
Specialists in Environmental Protection, Remediation, and Groundwater Control
155 S. Madison Street - Suite 230 - Denver, Colorado 80209-3013

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLAT
PROJECT NO.: 1356A

BORING NUMBER: GWQ96-22

COORDINATES N 717440 (APPROX.)
OR LOCATION: E 589,920 (APPROX.)

	SAMPLER TYPE AND NUMBER	SAMPLER DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	WATER	GRAPHIC LOG	DESCRIPTION	WELL COMPLETION DIAGRAM	
60					APPEARED DRY DURING DRILLING		ANDESITE; TRACE CALCITE AND CHALCOPYRITE (OR PYRITE)	BENTONITE GROUT	60
65							ANDESITE W/CHALCOPYRITE; SLOW DRILLING, SILICIFIED (?)		65
70							ANDESITE; POSSIBLY SILICIFIED W/DISSEMINATED CHALCOPYRITE <1%		70
75							ANDESITE AND THIN LATITE DIKE LATITE NOT ABUNDAN T, BUT CONTAINS 2-3MM EUHEDRAL-SUBHEDRAL PLAG., OXIDATION CONTATCT, EPIDOTE AND PROPYLITIC ALTERATION ALONG FRX.		75
80							ANDESITE AND THIN LATITE DIKE		80
85							ANDESITE W/INCREASING PYRITE/CHALCOPYRITE		85
90							ANDESITE; TRACE PYRITE, MINOR CALCITE, FRESH, 0% OX.		90
95							ANDESITE AS ABOVE		95
100							ANDESITE; FRESH, 0% OX., GREEN CHLORITE AND CALCITE ALONG FRACTURES, AND TRACE VEINED PYRITE		100
105							ANDESITE AS ABOVE; <1% OX.		105
110							ANDESITE; LT. GREEN TO DRK. GREENISH GRAY, PYRITE VEINLETS UP TO 1MM WIDE, 1% OX.		110
115							ANDESITE AS ABOVE;; 0% OX.		115
120									120

NOTES:

E:\1356A\1996\GWQ96-22.DWG; 08/07/96

Prepared by:

ADRIAN BROWN CONSULTANTS, INC.
Specialists in Environmental Protection, Remediation, and Groundwater Control
155 S. Madison Street - Suite 230 - Denver, Colorado 80209-3013

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLAT
PROJECT NO.: 1356A

BORING NUMBER: GWQ96-22

COORDINATES N 717440 (APPROX.)
OR LOCATION: E 589,920(APPROX.)

	SAMPLER TYPE AND NUMBER	SAMPLER DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	WATER	GRAPHIC LOG	DESCRIPTION	WELL COMPLETION DIAGRAM
120					APPEARED DRY DURING DRILLING		ANDESITE AS ABOVE; 0% OX.	
125							ANDESITE AS ABOVE (DRK. GREENISH BLACK, SUBHEDERAL-ANHEDERAL 0.5-2MM PLAG., FINE-MED. GRAINED, CALCITE AND PYRITE VEINLETS)	
130							ANDESITE W/PYRITE VEINLETS, 0% OX.	
135							ANDESITE AS ABOVE	
140							ANDESITE AS ABOVE	
145							ANDESITE AS ABOVE	
150							ANDESITE AS ABOVE	
155							ANDESITE AS ABOVE	
160							ANDESITE AS ABOVE	159.0' BENTONITE PELLETS
165							ANDESITE; W/TRACE LATITE (SMALL DIKE?) LATITE HAS WEATHERED CONTACT, 2-3MM PLAG., LT. GRAY GROUND MASS., CHLORIDE/ALTERATION ALONG FRX.	165.0' 30-60 TRANSITION SAND
170							ANDESITE; GRAYISH BLACK, W/SULFIDE AND CALCITE VEINLETS	171.0' 10-20 CSSI SAND
175							ANDESITE AS ABOVE; 0% OX.	174.0' 20 SLOT 2" SCH. 40 PVC SCREEN
180								

NOTES:

E:\1356A\1996\GWQ96-22.DWG; 08/07/96

Prepared by:

ADRIAN BROWN CONSULTANTS, INC.
Specialists in Environmental Protection, Remediation, and Groundwater Control
155 S. Madison Street – Suite 230 – Denver, Colorado 80209-3013

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLAT
PROJECT NO.: 1356A

BORING NUMBER: GWQ96-22

COORDINATES N 717440 (APPROX.)
OR LOCATION: E 589,920 (APPROX.)

	SAMPLER TYPE AND NUMBER	SAMPLER DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	WATER	GRAPHIC LOG	DESCRIPTION	WELL COMPLETION DIAGRAM	
180					APPEARED DRY DURING DRILLING		ANDESITE; W/VUGGY CALCITE AND PROPYLITIC (CHLORIDE ALTERATION) 3-5% AS ABOVE; 0% OX.	10-20 CSSI SAND	180
185							ANDESITE AND LATITE DIKE		185
190							ANDESITE; VERY FINE GRAINED, GRAYISH BLACK, MODERATE-ABUNDANT CALCITE VEINLETS AND DENDRITIC PYRITE		190
195							ANDESITE; DIKE(?) 1-2.5MM ANHEDRAL PLAG., PYRITE, CALCITE VEINLETS		195
200							ANDESITE AS ABOVE		200
205							ANDESITE AS ABOVE		205
210							ANDESITE AS ABOVE		210
215							ANDESITE AS ABOVE		215
220							ANDESITE AS ABOVE		220
225							ANDESITE AS ABOVE		225
230							ANDESITE; AS ABOVE, <1% OX. ALONG FRX.		230
235							ANDESITE		235
240									240

NOTES:

E:\1356A\1996\GWQ96-22.DWG; 08/07/96

Prepared by:

ADRIAN BROWN CONSULTANTS, INC.
Specialists in Environmental Protection, Remediation, and Stormwater Control
1155 S. Madison Street - Suite 230 - Denver, Colorado 80209-3013

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLAT
PROJECT NO.: 1356A

BORING NUMBER: GWQ96-22

COORDINATES N 717440 (APPROX.)
OR LOCATION: E 589,920 (APPROX.)

SAMPLER TYPE AND NUMBER	SAMPLER DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	WATER	GRAPHIC LOG	DESCRIPTION	WELL COMPLETION DIAGRAM
				APPEARED DRY DURING DRILLING		ANDESITE	10-20 CSSI SAND 244.5'
						ANDESITE AS ABOVE W/CALCITE VEINLETS	245.0' 30-60 TRANSITION SAND 249.0'
						ANDESITE; VERY FINE GRAINED, GRAY TO BLACK, CALCITE AND QUARTZ VEINLETS, PYRITE	BENTONITE PELLETS 254.0'
						ANDESITE; VERY FINE GRAINED, GRAY TO BLACK, CALCITE, QUARTZ AND PYRITE VEINLETS >7MM WIDE	
						ANDESITE; GRAY TO BLACK, W/FINELY DISSEMINATED PYRITE	
						ANDESITE; AS ABOVE W/PYRITE AND CALCITE VEINLETS	
						ANDESITE AS ABOVE	
						ANDESITE; AS ABOVE W/TRACE CRYSTALLINE PYRITE ON CALCITE	BENTONITE GROUT
						ANDESITE AS ABOVE	
						ANDESITE	
						ANDESITE	
						ANDESITE	

240 245 250 255 260 265 270 275 280 285 290 295 300

NOTES:

E:\1356A\1996\DWG\96-22.DWG; 08/07/96

Prepared by:

ADRIAN BROWN CONSULTANTS, INC.
Specialists in Environmental Protection, Remediation, and Groundwater Control
155 S. Madison Street - Suite 230 - Denver, Colorado 80209-3013

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLAT
PROJECT NO.: 1356A

BORING NUMBER: GWQ96-22
COORDINATES N 717440 (APPROX.)
OR LOCATION: E 589,920 (APPROX.)

	SAMPLER TYPE AND NUMBER	SAMPLER DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	WATER	GRAPHIC LOG	DESCRIPTION	WELL COMPLETION DIAGRAM
300					APPEARED DRY DURING DRILLING		ANDESITE	BENTONITE GROUT
305							ANDESITE	
310							ANDESITE	
315							ANDESITE	
320							ANDESITE	
325							ANDESITE	324.5' BENTONITE PELLETS
330							ANDESITE	330.0' 30-60 TRANSITION SAND
335							ANDESITE	335.0' 10-20 CSSI SAND
340							ANDESITE (70%) AND 30% (RHYOLITE) FELSIC ROCK; LIGHT PINKISH GRAY, FINE-MEDIUM GRAINED, ALTERED AND PYRITIZED	20 SLOT 2" SCH. 40 PVC SCREEN
345							ANDESITE AS ABOVE	
350							ANDESITE AS ABOVE	
355							50% RHYOLITE (FELSIC) 50% MAFIC ANDESITE, ABUNDANT PYRITE; SOFT DRILLING	
360								

NOTES:

Prepared by:

ADRIAN BROWN CONSULTANTS, INC.
Specialists in Environmental Protection, Remediation, and Groundwater Control
155 S. Madison Street – Suite 230 – Denver, Colorado 80209-3013

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLAT
PROJECT NO.: 1356A

BORING NUMBER: GWQ96-22

COORDINATES N 717440 (APPROX.)
OR LOCATION: E 589,920 (APPROX.)

SAMPLER TYPE AND NUMBER	SAMPLER DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	WATER	GRAPHIC LOG	DESCRIPTION	WELL COMPLETION DIAGRAM
				APPEARED DRY DURING DRILLING		RHYOLITE W/QUARTZ VEINS >8MM, RHYOLITE IS LIGHT REDDISH BROWN, VERY FINE GRAINED, <5% QUARTZ, ABUNDANT PYRITE	10-20 CSSI SAND 20 SLOT 2" SCH. 40 PVC SCREEN
						60% RHYOLITE AND 38% ANDESITE W/QUARTZ AND CALCITE VEINLETS; ABUNDANT PYRITIZATION AND PROPYLITIC ALTERATION, PYRITE STOCKWORK	
						40% RHYOLITE AND 60% ANDESITE; MINOR FREE QUARTZ (VEINED?), ABUNDANT PYRITE	370.0'
						90% ANDESITE <10% RYHOLITE; ANDESITE IS ALTERED, ABUNDANT PYRITE	10-20 CSSI SAND 20 SLOT 2" SCH. 40 PVC SCREEN
						ANDESITE; FINE GRAINED, GRAYISH BLACK, MODERATELY ABUNDANT PYRITE, ALTERED LOCALLY	380.0' 380.6'
							383.0' 30-60 TRANSITION SAND
						ANDESITE AS ABOVE; DECREASING ALTERATION	386.0'
						ANDESITE AS ABOVE	BENTONITE PELLETS
						ANDESITE AS ABOVE	396.0'
						ANDESITE AS ABOVE W/MINOR CALCITE VEINLETS AND PROPYLLITIC ALTERATION	
						ANDESITE; VERY FINE GRAINED, DECREASING ALTERATION	10-20 CSSI SAND
						ANDESITE AS ABOVE	
						ANDESITE; VERY FINE GRAINED, VERY FINELY DISSEMINATED PYRITE AND CHALCOPYRITE	
						TOTAL DEPTH – 420'	CENTRALIZER

360 365 370 375 380 385 390 395 400 405 410 415 420

NOTES:

E:\1356A\1996\GWQ96-22.DWG; 08/07/96

Prepared by:

ADRIAN BROWN CONSULTANTS, INC.
Specialists in Environmental Protection, Remediation, and Groundwater Control
155 S. Madison Street – Suite 230 – Denver, Colorado 80209-3013

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLAT PROJECT NO.: 1356A	BORING NUMBER: GWQ96-23	COORDINATES N 716,835 (APPROX.) OR LOCATION: E 593,370 (APPROX.)	
LOGGED BY: SW CHECKED BY:	SURFACE ELEVATION: 5483'	GWL DEPTH: ~ (ENCOUNTERED) DEPTH: ~ (STATIC)	CASING: A 2" SCH. 40 FROM: 2.05' A.G.S. TO 50' B.G.S. SCREEN: A 2", 20 SLOT SCH. 40 FROM: 50' B.G.S. TO 100' B.G.S.
DRILLING METHOD: AIR ROTARY	HOLE DIAMETER: 8 3/4"	FLUID USED: FOAM DATE STARTED: 7/1/96 COMPLETED: 7/12/96	CASING: B 2" SCH. 40 FROM: 1.92' A.G.S. TO 150' B.G.S. SCREEN: B 2", 20 SLOT SCH. 40 FROM: 150' B.G.S. TO 250' B.G.S.

SAMPLER TYPE AND NUMBER	SAMPLER DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	WATER	GRAPHIC LOG	DESCRIPTION
				APPEARED DRY DURING DRILLING		RHYOLITE; WEATHERED, LIGHT TAN TO GRAY, 60% OX.
						RHYOLITE/ANDESITE; LIGHT GRAY TO TAN; 60% OX., CALCITE COATINGS
						RHYOLITE; MUSCOVITE AND HORNBLENDE, <1MM IN SIZE, 55% OX.
						RHYOLITE; LIGHT TAN, MEDIUM-FINE GRAINED
						AS ABOVE; 30% OX.
						AS ABOVE; 30% OX.
						ANDESITE; GRAY, MEDIUM GRAINED, ALTERED (CHLORITE), ANHEDERAL, "GHOST" PLAG. <15% OX.
						ANDESITE; LIGHT TO DARK GRAY, PYRITE CHALCOPYRITE VEINLETS, PROPYLITIC ALTERATION (CHLORITE), <5% OX.
						ANDESITE AS ABOVE; TRACE PYRITE VEINLETS, <5% OX.
						ANDESITE AS ABOVE
						ANDESITE W/PYRITE VEINLETS; MINOR CHLORITE ALTERATION, CALCITE ON FRX., <2% OX.
						ANDESITE AS ABOVE; W/INCREASING PYRITE

WELL COMPLETION DIAGRAM

GWQ96-23A STICK-UP 2.05'
GWQ96-23B STICK-UP 1.92'

CONCRETE 0 – 5.0'
BENTONITE GROUT 5.0' – 39.0'
BENTONITE PELLETS 39.0' – 43.0'
30-60 TRANSITION SAND 43.0' – 47.0'
10-20 CSSI SAND 47.0' – 50.0'
20 SLOT 2" SCH. 40 PVC SCREEN 50.0' – 100.0'

E:\1356A\1996\GWQ96-23.DWG: 08/05/96

Prepared by:

ADRIAN BROWN CONSULTANTS, INC.
Specialists in Environmental Protection, Remediation, and Groundwater Control
133 S. Madison Street - Suite 230 - Denver, Colorado 80209-3013

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLAT
PROJECT NO.: 1356A
BORING NUMBER: GWQ96-23
COORDINATES OR LOCATION:

SAMPLER TYPE AND NUMBER	SAMPLER DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	WATER	GRAPHIC LOG	DESCRIPTION	WELL COMPLETION DIAGRAM
				APPEARED DRY DURING DRILLING		ANDESITE AS ABOVE; 0% OX.	10-20 CSSI SAND
						ANDESITE AS ABOVE; CALCITE FRX. FILLINGS UP TO 5MM	
						ANDESITE AS ABOVE	
						ANDESITE AS ABOVE	
						ANDESITE; FINE GRAINED, 0% OX.	20 SLOT 2" SCH. 40 PVC SCREEN
						ANDESITE; MODERATELY TO ABUNDANT PYRITE AND CHLORITE	
						ANDESITE AS ABOVE; <1% OX.	CENTRALIZER 89.5' TO 90.5'
						ANDESITE; <3% OX.	10-20 CSSI SAND
						RHYOLITE/MONZONITE	100.0' 100.6'
						70% RHYOLITE/MONZONITE, 30% ANDESITE; 15% OX.;	103.0' BENTONITE PELLETS
						90% RHYOLITE/MONZONITE; LIGHT TAN, MEDIUM TO FINE GRAINED, ABUNDANT PYRITE	112.0'
						QUARTZ MONZONITE; MEDIUM GRAINED, EUHEDERAL FELDSPARS, ABUNDANT PYRITE, 10% MAFICS, 0% OX.	BENTONITE GROUT

60 65 70 75 80 85 90 95 100 105 110 115 120

NOTES:

E:\1356A\1356\GWQ96-23.DWG; 08/05/96

Prepared by:

ADRIAN BROWN CONSULTANTS, INC.
Specialists in Environmental Protection, Remediation, and Groundwater Control
155 S. Madison Street - Suite 230 - Denver, Colorado 80209-3013

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLAT
PROJECT NO.: 1356A

BORING NUMBER: GWQ96-23
COORDINATES N 716,835 (APPROX.)
OR LOCATION: E 593,370 (APPROX.)

	SAMPLER TYPE AND NUMBER	SAMPLER DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	WATER	GRAPHIC LOG	DESCRIPTION	WELL COMPLETION DIAGRAM
120					APPEARED DRY DURING DRILLING		QUARTZ MONZONITE AS ABOVE	BENTONITE GROUT
125							QUARTZ MONZONITE AS ABOVE	
130							QUARTZ MONZONITE AS ABOVE	
135							QUARTZ MONZONITE	135.0
140							QUARTZ MONZONITE; <1% OX.	BENTONITE PELLETS
145							QUARTZ MONZONITE AS ABOVE	145.0
150							QUARTZ MONZONITE AS ABOVE	30-60 TRANSITION SAND 148.0
155							QUARTZ MONZONITE	10-20 CSSI SAND 20 SLOT 2" SCHD. 40 PVC SCREEN
160							QUARTZ MONZONITE AS ABOVE	
165							QUARTZ MONZONITE AS ABOVE	
170							QUARTZ MONZONITE AS ABOVE	
175							QUARTZ MONZONITE; MEDIUM TO COARSE GRAINED, BEIGE/TAN TO WHITE, 15% MAFICS, ABUNDANT PYRITE AND CALCITE VEINLETS, <1% OX.	
180								

NOTES:

E:\1356A\1996\GWQ96-23.DWG: 08/05/96

Prepared by:

ADRIAN BROWN CONSULTANTS, INC.
Specialists in Environmental Protection, Remediation, and Groundwater Control
155 S. Madison Street - Suite 230 - Denver, Colorado 80209-3013

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLAT
PROJECT NO.: 1356A

BORING NUMBER: GWQ96-23
COORDINATES N 716,835 (APPROX.)
OR LOCATION: E 593,370 (APPROX.)

	SAMPLER TYPE AND NUMBER	SAMPLER DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	WATER	GRAPHIC LOG	DESCRIPTION	WELL COMPLETION DIAGRAM
180					APPEARED DRY DURING DRILLING		AS ABOVE	10-20 CSSI SAND 20 SLOT 2" SCHD. 40 PVC SCREEN CENTRALIZER 229.5' TO 230.5' CENTRALIZER 239.5' TO 240.5'
185							QUARTZ MONZONITE	
190							QUARTZ MONZONITE	
195							QUARTZ MONZONITE	
200							QUARTZ MONZONITE; 0% OX.	
205							ANDESITE; 0% OX.	
210							60% GRANITE/MONZONITE, 40% ANDESITE; 0% OX.	
215							80% ANDESITE, 20% GRANITE/MONZONITE; MINOR PYRITE FRX. ALONG ANDESITE	
220							70% GRANITE/MONZONITE, 30% ANDESITE; CHLORITE ALTERATION ALONG FRX., 0% OX.	
225							ANDESITE; ABUNDANT PYRITE VEINLETS, VERY FINE GRAINED, CHLORITC/ PROPYLLITIC ALTERATION, QUARTZ VEIN UP TO 4MM WIDE	
230							70% ANDESITE; TRACE PYRITE STOCKWORK, <20% GRANITE, QUARTZ VEINLETS AND EXTENSIVE CHLORITE ALTERATION ON FRX., 10% RHYOLITE	
235							60% RHYOLITE, 35% ANDESITE, <5% GRANITE/MONZONITE; SILICA STOCKWORK IN RHYOLITE	
240								

NOTES:

E:\1356A\1096\GWQ96-23.DWG: 08/05/96

Prepared by:

ADRIAN BROWN CONSULTANTS, INC.
Specialists in Environmental Protection, Remediation, and Groundwater Control
155 S. Madison Street – Suite 230 – Denver, Colorado 80209-3013

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLAT
PROJECT NO.: 1356A

BORING NUMBER: GW096-23
COORDINATES N 716,835 (APPROX.)
OR LOCATION: E 593,370 (APPROX.)

SAMPLER TYPE AND NUMBER	SAMPLER DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	WATER	GRAPHIC LOG	DESCRIPTION
				APPEARED DRY DURING DRILLING		80% GRANITE/MONZONITE, <155% ANDESITE; MINOR RHYOLITE, EXTENSIVE PRYITIZATION
						AS ABOVE WITH INCREASING CHLORITE ALTERATION
						RHYOLITE
						RHYOLITE/QUARTZ MONZONITE; ABUNDANT PYRITE AND CHLORITE ALTERATION
						RHYOLITE OR LEUCO ANDESITE; CALCITE AND PYRITE FRX. FILLINGS, FINE GRAINED, TAN TO REDDISH TAN, GHOST PLAG.
						ANDESITE; TAN TO DARK GRAY, VERY FINE GRAINED, MINOR CALCITE VEIN LETS AND PYRITE
						ANDESITE; DARK GREENISH GRAY, EXTENSIVE PYRITE VEINLETS, RED SPHALERITE (?) ON FRX.
						ANDESITE AS ABOVE
						90% ANDESITE, 10% GRANITE/MONZONITE
						80% ANDESITE; DARK GREENISH GRAY, FINE GRAINED PYRITIC; 10% GRANITE OR QUARTZ MONZONITE (2 FELDSPARS, PALE GREEN MIN., 10% MAFICS
						85% ANDESITE; DARK GREENISH GRAY W/EXTENSIVE ALTERATION AND RED SPHALERITE (?) FRX. COATINGS; 10% GRANITE
						AS ABOVE

WELL COMPLETION DIAGRAM



240 245 250 255 260 265 270 275 280 285 290 295 300

NOTES:

E:\1356A\1996\GW096-23.DWG: 08/05/96

Prepared by:

ADRIAN BROWN CONSULTANTS, INC.
Specialists in Environmental Protection, Remediation, and Groundwater Control
155 S. Madison Street – Suite 230 – Denver, Colorado 80209-3013

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLAT
PROJECT NO.: 1356A

BORING NUMBER: GW096-23

COORDINATES N 716,835 (APPROX.)
OR LOCATION: E 593,370 (APPROX.)

SAMPLER TYPE AND NUMBER	SAMPLER DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	WATER	GRAPHIC LOG	DESCRIPTION	WELL COMPLETION DIAGRAM
						75% ANDESITE, 25% GRANITE/MONZONITE	BENTONITE GROUT
						75% ANDESITE, 25% GRANITE/MONZONITE; SPHALERITE (?) AND COPPER COATINGS FRX.	
						85% PINK GRANITE/MONZONITE; <15% ANDESITE; DARK GREENISH GRAY	
						85% ANDESITE <10% GRANITE/MONZONITE	
						AS ABOVE	
						GRANITE/MONZONITE; TAN TO PINK, MEDIUM TO COARSE GRAINED, FINELY DISSEMINATED PYRITE, 10–15% MAFICS	
						GRANITE/MONZONITE; TAN TO PINK, MODERATELY COARSE GRAINED, GRANITE WITH EXTENSIVE PYRITIZATION AND GREEN ALTERATION, 3% ANDESITE; DARK GRAY, FINE GRAINED	
						GRANITE/MONZONITE, <5% ANDESITE	
						GRANITE/MONZONITE	
						GRANITE AS ABOVE; MEDIUM COARSE GRAINED, ALTERED AND PYRITIZED	
						AS ABOVE	
						AS ABOVE	

300 305 310 315 320 325 330 335 340 345 350 355 360

NOTES:

E:\1356A\1096GW23.DWG: 08/05/96

Prepared by:

— ADRIAN BROWN CONSULTANTS, INC. —
Specialists in Environmental Protection, Remediation, and Groundwater Control
155 S. Madison Street - Suite 230 - Denver, Colorado 80209-3013

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLAT
PROJECT NO.: 1356A

BORING NUMBER: GWQ96-23

COORDINATES N 716,835 (APPROX.)
OR LOCATION: E 593,370 (APPROX.)

SAMPLER TYPE AND NUMBER	SAMPLER DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	WATER	GRAPHIC LOG	DESCRIPTION	WELL COMPLETION DIAGRAM
						95% GRANITE/MONZONITE; 5% ANDESITE; DARK BLACK	BENTONITE GROUT
						40% WHITE GRANITE/MONZONITE; 45% PINK GRANITE/MONZONITE; 5% DARK ANDESITE; ABUNDANT PYRITE	
						70% PINK GRANITE/MONZONITE; 30% WHITE GRANITE/MONZONITE	
						AS ABOVE	
						60% PINK GRANITE/MONZONITE; MODERATELY COARSE GRAINED; 40% WHITE GRANITE/MONZONITE; PYRITE, 0% OX.	
						GRANITE/MONZONITE AS ABOVE; 0% OX.	
						95% GRANITE/MONZONITE; 5% ANDESITE; <5% OX.	
						AS ABOVE	
						70% GRANITE/MONZONITE; 20% ANDESITE; 10% RHYOLITE (?); 0% OX.	
						80% GRANITE/MONZONITE, 20% ANDESITE (DACITE?) DIKE; 2% OX.	
						GRANITE W/MINOR RHYOLITE OR ANDESITE DIKE; OXIDATION ALONG CONTACT, TRACE TO MINOR PYRITE	
						GRANITE; TRACE PYRITE, CALCITE (GYPSUM?) ALONG FRX. UP TO 3MM WIDE	

360 365 370 375 380 385 390 395 400 405 410 415 420

NOTES:

E:\1356A\1996\GWQ96-23.DWG: 08/05/96

Prepared by:

ADRIAN BROWN CONSULTANTS, INC.
Specialists in Environmental Protection, Remediation, and Groundwater Control
155 S. Madison Street – Suite 230 – Denver, Colorado 80209-3013

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLAT
PROJECT NO.: 1356A

BORING NUMBER: GWQ96-23

COORDINATES N 716,835 (APPROX.)
OR LOCATION: E 593,370 (APPROX.)

	SAMPLER TYPE AND NUMBER	SAMPLER DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	WATER	GRAPHIC LOG	DESCRIPTION	WELL COMPLETION DIAGRAM	
420							GRANITE/MONZONITE; <2% OX. MINOR RHYOLITE DIKE		420
425							GRANITE/MONZONITE; PYRITE VEINLETS ABUNDANT ON FRX. >1MM		425
430							GRANITE/MONZONITE; VEINED PYRITE 1-2MM, ORTHOCLASE MEGACRYSTS (PINK MICROCLINE)		430
435							GRANITE/MONZONITE; PYRITE VEINLETS ABUNDANT		435
440							GRANITE/MONZONITE; VERY COARSE GRAINED		440
445							80% GRANITE/MONZONITE; <20% ANDESITE DIKE; <1% OX., OXIDE ZONE >10 MM DEEP ALONG FRX.	BENTONITE GROUT	445
350							GRANITE/MONZONITE; W/ABUNDANT PYRITE		350
455							AS ABOVE		455
460							GRANITE/MONZONITE; COARSE GRAINED, EUHEDRAL FELDSPAR, 10-15% MAFICS, 0% OX.		460
465							AS ABOVE		465
470							AS ABOVE		470
415							GRANITE/MONZONITE AS ABOVE; ABUNDANT PYRITE AND TRACE FILLED FRX.		415
480									480

NOTES:

E:\1356A\[illegible]3.DWG: 08/05/96

Prepared by:

ADRIAN BROWN CONSULTANTS, INC.
Specialists in Environmental Protection, Remediation, and Groundwater Control
155 S. Madison Street - Suite 230 - Denver, Colorado 80209-3013

LOG OF MONITORING WELL

PROJECT NAME: COPPER FLAT	BORING NUMBER: GWQ96-23	COORDINATES N 716,835 (APPROX.)
PROJECT NO.: 1356A		OR LOCATION: E 593,370 (APPROX.)

	SAMPLER TYPE AND NUMBER	SAMPLER DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	WATER	GRAPHIC LOG	DESCRIPTION	WELL COMPLETION DIAGRAM
480							AS ABOVE	
485							AS ABOVE	
490							GRANITE/MONZONITE AS ABOVE	BENTONITE GROUT
495							QUARTZ/MONZONITE; ABUNDANT PYRITE AND CHLORITE	
500							TOAL DEPTH 500'	500.0'

NOTES:

E:\1356A\1996\GWQ96-23.DWG; 08/05/96

TEST DRILLING EQUIPMENT & PROCEDURES

Drilling Equipment Truck-mounted CME-55 drill rigs powered with 6 cylinder Ford industrial engines are used in advancing test borings. The 6 cylinder engines are capable of delivering about 6,500 foot/pounds torque to the drill spindle. The spindle is advanced with twin hydraulic rams capable of exerting 12,000 pounds downward force. Drilling through soil or softer rock is performed with 6-1/2 inch O.D., 3-1/4 I.D. hollow stem auger or 4-1/2 inch continuous flight auger. Carbide insert teeth are normally used on the auger bits so they can often penetrate rock or very strongly cemented soils which require blasting or very heavy equipment for excavation. Where refusal is experienced in auger drilling, the holes are sometimes advanced with tricone gear bits and NX rods using water or air as a drilling fluid.

Sampling Procedures Dynamically driven tube samples are usually obtained at selected intervals in the borings by the ASTM D1586 procedures. In most cases, 2" O.D., 1-3/8" I.D. samplers are used to obtain the standard penetration resistance. "Undisturbed" samples of firmer soils are often obtained with 3" O.D. samplers lined with 2.42" I.D. brass rings. The driving energy is generally recorded as the number of blows of a 140 pound 30 inch free fall drop hammer required to advance the samplers in 6 inch increments. However, in stratified soils, driving resistance is sometimes recorded in 2 or 3 inch increments so that soil changes and the presence of scattered gravel or cemented layers can be readily detected and the realistic penetration values obtained for consideration in design. These values are expressed in blows per foot on the logs. "Undisturbed" sampling of softer soils is sometimes performed with thin walled Shelby tubes (ASTM D1587). Where samples of rock are required, they are obtained by NX diamond core drilling (ASTM D2113). Tube samples are labeled and placed in watertight containers to maintain field moisture contents for testing. When necessary for testing, larger bulk samples are taken from auger cuttings.

Continuous Penetration Tests Continuous penetration tests are performed by driving a 2" O.D. blunt nosed penetrometer adjacent to or in the bottom of borings. The penetrometer is attached to 1-5/8" O.D. drill rods to provide clearance to minimize side friction so that penetration values are as nearly as possible a measure of end resistance. Penetration values are recorded as the number of blows of a 140 pound 30 inch free fall drop hammer required to advance the penetrometer in one foot increments or less.

Boring Records Drilling operations are directed by our field engineer or geologist who examines soil recovery and prepares boring logs. Soils are visually classified in accordance with the Unified Soil Classification System (ASTM D2487) with appropriate group symbols being shown on the logs.

UNIFIED SOIL CLASSIFICATION SYSTEM

Soils are visually classified by the Unified Soil Classification system on the boring logs presented in this report. Grain-size analysis and Atterberg Limits Tests are often performed on selected samples to aid in classification. The classification system is briefly outlined on this chart. For a more detailed description of the system, see "The Unified Soil Classification System" Corp of Engineers, US Army Technical Memorandum No. 3-357 (Revised April 1960) or ASTM Designation: D2487-66T.

MAJOR DIVISIONS			GRAPHIC SYMBOL	GROUP SYMBOL	TYPICAL NAMES
COARSE-GRAINED SOILS (Less than 50% passes No. 200 sieve)	GRAVELS (50% or less of coarse fraction passes No. 4 sieve)	CLEAN GRAVELS (Less than 5% passes No. 200 sieve)		GW	Well graded gravels, gravel-sand mixtures, or sand-gravel-cobble mixtures.
				GP	Poorly graded gravels, gravel-sand mixtures, or sand-gravel-cobble mixtures.
		GRAVELS WITH FINES (More than 12% passes No. 200 sieve) — Limits plot below "A" line & hatched zone on plasticity chart		GM	Silty gravels, gravel-sand-silt mixtures.
		GRAVELS WITH FINES (More than 12% passes No. 200 sieve) — Limits plot above "A" line & hatched zone on plasticity chart		GC	Clayey gravels, gravel-sand-clay mixtures.
	SANDS (More than 50% of coarse fraction passes No. 4 sieve)	CLEAN SANDS (Less than 5% passes No. 200 seive)		SW	Well graded sands, gravelly sands.
				SP	Poorly graded sands, gravelly sands.
		SANDS WITH FINES (More than 12% passes No. 200 sieve) — Limits plot below "A" line & hatched zone on plasticity chart		SM	Silty sands, sand-silt mixtures.
		SANDS WITH FINES (More than 12% passes No. 200 sieve) — Limits plot above "A" line & hatched zone on plasticity chart		SC	Clayey sands, sand-clay mixtures.
FINE-GRAINED SOILS (50% or more passes No. 200 sieve)	SILTS (Limits plot below "A" line & hatched zone on plasticity chart)	SILTS OF LOW PLASTICITY (Liquid Limit Less Than 50)		ML	Inorganic silts, clayey silts with slight plasticity.
		SILTS OF HIGH PLASTICITY (Liquid Limit More Than 50)		MH	Inorganic silts, micaceous or diatomaceous silty soils, elastic silts.
	CLAYS (Limits plot above "A" line & hatched zone on plasticity chart)	CLAYS OF LOW PLASTICITY (Liquid Limit Less Than 50)		CL	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, lean clays.
		CLAYS OF HIGH PLASTICITY (Liquid Limit More Than 50)		CH	Inorganic clays of high plasticity, fat clays, sandy clays of high plasticity.

NOTE: Coarse grained soils with between 5% & 12% passing the No. 200 sieve and fine grained soils with limits plotting in the hatched zone on the plasticity chart to have double symbol.

PLASTICITY CHART



DEFINITIONS OF SOIL FRACTIONS

SOIL COMPONENT	PARTICLE SIZE RANGE
Cobbles	Above 3 in.
Gravel	3 in. to No. 4 sieve
Coarse gravel	3 in. to ¾ in.
Fine gravel	¾ in. to No. 4 sieve
Sand	No. 4 to No. 200
Coarse	No. 4 to No. 10
Medium	No. 10 to No. 40
Fine	No. 40 to No. 200
Fines (silt or clay)	Below No. 200 sieve

TERMINOLOGY USED TO DESCRIBE THE RELATIVE DENSITY, CONSISTENCY, OR FIRMNESS, OF SOILS

The terminology used on the boring logs to describe the relative density, consistency, or firmness of soils relative to the standard penetration resistance is presented below. The standard penetration resistance (N) in blows per foot is obtained by ASTM D1586 procedure using 2" O.D., 1-3/8" I.D. samplers.

1. Relative Density. Terms for description of relative density of cohesionless, uncemented sands and sand-gravel mixtures.

N	Relative Density
0-4	Very loose
5-10	Loose
11-30	Medium dense
31-50	Dense
50+	Very dense

2. Relative Consistency. Terms for the description of clays which are saturated or near saturation.

N	Relative Consistency	Remarks
0-2	Very soft	Easily penetrated several inches with fist
3-4	Soft	Easily penetrated several inches with thumb
5-8	Medium stiff	Can be penetrated several inches with thumb with moderate effort
9-15	Stiff	Readily indented with thumb, but penetrated only with great effort
16-30	Very stiff	Readily indented with thumbnail
30+	Hard	Indented only with difficulty by thumbnail

3. Relative Firmness. Terms for the description of partially saturated and/or cemented soils which commonly occur in the Southwest including clays, cemented granular materials, silts and silty and clayey granular soils:

N	Relative Density
0-4	Very soft
5-8	Soft
9-15	Moderately firm
16-30	Firm
31-50	Very firm
50+	Hard

TERMINOLOGY FOR THE DESCRIPTION OF ROCK

General Property	Descriptive Term	Visual or Physical Properties
WEATHERING	VERY WEATHERED	Abundant fractures coated with oxides, carbonates, sulfates, mud, etc., thorough discoloration, rock disintegration, mineral decomposition
	MODERATELY WEATHERED	Some fracture coating, moderate or localized discoloration, little to no effect on cementation, slight mineral decomposition
	SLIGHTLY WEATHERED	A few stained fractures, slight discoloration, little to no effect on cementation, no mineral decomposition
	FRESH	Unaffected by weathering agents, no appreciable change with depth
FRACTURING	INTENSELY FRACTURED	Less than 1" spacing
	VERY FRACTURED	1" to 6" spacing
	MODERATELY FRACTURED	6" to 12" spacing
	SLIGHTLY FRACTURED	12" to 36" spacing
	SOLID	36" spacing or greater
STRATIFICATION	THINLY LAMINATED	less than 1/10"
	LAMINATED	1/10" to 1/2"
	VERY THINLY BEDDED	1/2" to 2"
	THINLY BEDDED	2" to 2 feet
	THICKLY BEDDED	more than 2 feet
HARDNESS	SOFT	Can be dug by hand and crushed by fingers
	MODERATELY HARD	Friable, can be gouged deeply with knife and will crumble readily under light hammer blows
	HARD	Knife scratch leaves dust trace, will withstand a few hammer blows before breaking
	VERY HARD	Scratched with knife with difficulty, difficult to break with hammer blows

PROJECT Tailings Dam Investigation

JOB NO. E76-1023 DATE 3-24-76

LOG OF TEST BORING NO. 1

RIG TYPE CME-55

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0				S	30		16	CH	firm	CLAY, high plasticity, reddish brown
5				S	73		16	CL	hard	SILTY CLAY, medium plasticity, reddish brown
10				U	67		13			
15				S	92		17		hard	CLAYEY SILT, medium plasticity, brown
20				S	50/5"		11	ML		
25				S	50/3"		9			
30				S	50/4"		11			
35										Stopped auger at 29'6" Sampler refused at 29'10"

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Tailings Dam Investigation

JOB NO. E76-1023 DATE 3-24-76

LOG OF TEST BORING NO. 2

RIG TYPE CME-55

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0			☒	S	20		10	GC	firm	SANDY CLAY, some gravel, medium to high plasticity, dark brown
5			☒	S	65		6	SM	hard	SANDY SILT, very fine, some gravel, some clay, low plasticity, brown
10			▬	S	50/5"		3	GC	hard	CLAYEY SAND & GRAVEL, coarse, low plasticity, brown
15			▬	S	50/2" (no recovery)					
20			☒	S	90		12		hard	CLAYEY SAND, medium plasticity, brown
25			▬	S	50/4"		7			
30			☒	S	50/2"		12	SC		
35			☒	S	107		13			
40			☒	S	103		12			
										Stopped auger at 39'6" Sampler refused at 40'4"
45										

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Tailings Dam Investigation

JOB NO. E76-1023 DATE 3-25-76

LOG OF TEST BORING NO. 3

RIG TYPE CME-55

BORING TYPE 6½" Hollow Stem Auger & 4½" Flight Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								ML	soft	CLAYEY SILT, very fine, some sand, medium plasticity, brown
				S	22		6			
5				S	75		5	SM	hard	SILTY SAND, predominantly fine, some clay, occasional gravel & cobble, low plasticity, brown
10				S	50/2"		3			
				S	50/2"		3		hard	SILTY SAND & GRAVEL, predominantly coarse, some cobbles, nonplastic, grayish brown
15								GM		
				S	50/1" (no recovery)					
20										
				S	50/0" (no recovery)					
25										Stopped auger at 24'6" Sampler refused at 24'6"
30										

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Tailings Dam Investigation

JOB NO. E76-1023 DATE 3-30-76

LOG OF TEST BORING NO. 4

RIG TYPE CME-55

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0				S	23		12	CL	firm	SILTY CLAY, moderately cemented, medium to high plasticity, brown
5				S	35		11		hard	SILTY GRAVEL, subangular, nonplastic, gray
10				S	90		6	GM		
15				S	50/2"		5			
20				S	50/3"		3			Stopped auger at 19'6" Sampler refused at 19'9"
25										

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Tailings Dam Investigation

JOB NO. E76-1023 DATE 3-29-76

LOG OF TEST BORING NO. 5

RIG TYPE CME-55

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0	☒	S	26		7	CL	firm to hard	SILTY CLAY, some coarse sand, trace of gravel, lightly cemented, medium plasticity, light brown
5	☒	S	58		12			
						ML	hard	CLAYEY SILT, highly cemented, medium plasticity, tan
10	☒	S	72		12			
						CH		SANDY CLAY, high plasticity, tan & red
15	☒	S	31		15		very firm to hard	CLAY, high plasticity, red & gray
20	☒	U	80		18	CH		
25	☒	U	100/10"		23			
30	☒	S	51		17		hard	CLAYEY SILT, medium plasticity, red
35	☒	S	51		25			
40	☒	S	73		19	ML		
45	☒	S	77 (no recovery)					
50								

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Tailings Dam Investigation

LOG OF TEST BORING NO. 5

JOB NO. E76-1023 DATE 3-30-76

RIG TYPE CME-55

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
50				S	95		17			
55				S	82		21		hard	CLAY, medium to high plasticity, red
60				S	66		24	CH		
65				S	75		18			
70				S	50/5"		14		hard	SANDY CLAY, with very weathered gravel, medium plasticity, red
75				S	50/4"		10	CH		
80										Stopped auger at 74'6" Sampler refused at 74'10"

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Tailings Dam Investigation

JOB NO. E76-1023 DATE 3-25-76

LOG OF TEST BORING NO. 6

RIG TYPE CME-55

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0				S	14		13		moderately firm to firm	SILTY CLAY, medium plasticity, brown
5				S	29		10	CL		
10				S	105		11		hard	SILTY SAND, predominantly fine, some gravel, nonplastic, brown
15				S	85		10	SM		
20				S	62		13			probably CONGLOMERATE composed of andesite, gravel or cobbles
25				S	50/3" (no recovery)					
30				S	50/3" (no recovery)					
35				S	50/1" (no recovery)					Auger refused at 34'6" Sampler refused at 34'7"
40										

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Tailings Dam Investigation

JOB NO. E76-1023 DATE 3-26-76

LOG OF TEST BORING NO. 7

RIG TYPE CME-55

BORING TYPE 4½" Flight Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0										SILTY SAND & GRAVEL, predominantly fine, occasional cobbles, angular, nonplastic, light brown
5			☒	A			2			
10								GM		
15			☒	A			2			
20										
			☒	A			7	SM		SILTY SAND, predominantly fine, nonplastic, tan
25										
			☒	A			5	CH		SANDY CLAY, medium to high plasticity, tan
30										
			☒	A			13			CLAY, high plasticity, red
35										
40								CH		
			☒	A			21			
45										
			☒	U	100/7"110		20			Stopped auger at 48'6" Sampler refused at 49'1"
50										

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Tailings Dam Investigation

JOB NO. E76-1023 DATE 3-26-76

LOG OF TEST BORING NO. 8

RIG TYPE CME-55

BORING TYPE 4½" Flight Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0										SILTY SAND & GRAVEL, predominantly, angular, nonplastic, light brown
5			☒	A			2	GM		
10			☒	A						
15										
20										Auger refused at 16'6"

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Tailings Dam Investigation

JOB NO. E76-1023 DATE 3-31-76

LOG OF TEST BORING NO. 9

RIG TYPE CME-55

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0				S	10		8		moderately firm to hard	CLAYEY SAND, predominantly fine, moderately cemented, low plasticity, light brown
5				S	53		4	SC		
10				S	50/5"		4		hard	SILTY SAND & GRAVEL, predominantly fine, low plasticity, light brown
15				S	98		3	GM		
20				S	70		7	GM	hard	SILTY SAND & GRAVEL, predominantly fine, some conglomerate rock, low plasticity, light brown
25										Stopped auger at 19'6" Sampler refused at 20'5"

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Tailings Dam Investigation

JOB NO. E76-1023 DATE 3-30-76

LOG OF TEST BORING NO. 10

RIG TYPE CME-55

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0			☒	S	16		10	ML	firm	CLAYEY SILT, medium plasticity, tan
5			☒	S	44		17	CH	very firm	SANDY CLAY, medium to high plasticity, tan
10			☒	S	73		10	ML	hard	CLAYEY SILT, some gravel, nonplastic, brown
15				S	50/0"(no recovery)					
				S	50/0"(no recovery)			GM	hard	SILTY SAND & GRAVEL, predominantly fine, nonplastic, brown
20										Auger refused at 17' Sampler refused at 17'

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Tailings Dam Investigation

JOB NO. E76-1023 DATE 3-31-76

LOG OF TEST BORING NO. 11

RIG TYPE CME-55

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0			☒	S	8		8		soft to very firm	CLAYEY SAND, moderately cemented, medium plasticity, brown
5			☒	S	32		9	SC		
10			☒	S	90		7		hard	SILTY SAND, predominantly medium, occasional gravel, highly cemented, nonplastic, brown
15			▬	S	50/3"		5	SM		
20			☒	S	50/5"		7			Stopped auger at 19'6" Sampler refused at 19'11"
25										

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Tailings Dam Investigation

JOB NO. E76-1023 DATE 3-31-76

LOG OF TEST BORING NO. 12

RIG TYPE CME-55

BORING TYPE 6½" Hollow Stem Auger & 4½" Flight Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0			☒	S	15		13	CL	moderately firm	SANDY CLAY, medium to high plasticity, dark reddish brown
5			☒	S	58		2	GM	hard	SILTY SAND & GRAVEL, predominantly fine, nonplastic, brown
10			☒	S	83		4	GM-GP	hard	SILTY SAND & GRAVEL, poorly graded, lightly cemented layers, sub-rounded, nonplastic, light brown
15			☒	S	93		6		hard	SILTY SAND, predominantly fine, some gravel, low plasticity, light brown
20			▬	S	50/4"		17	GM		
25			▬	S	50/3"		5			
30								GM	6½" Hollow Stem Auger refused at 25'6"	
35										
40										
45										
50										4½" Flight Auger refused at 46'

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Tailings Dam Investigation

JOB NO. E76-1023 DATE 3-25-76

LOG OF TEST BORING NO. 13

RIG TYPE CME-55

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0			☒	S	25		8	SM	firm to hard	SILTY SAND, predominantly coarse, some clay & gravel, low plasticity, grayish brown
5			☒	S	98		4			
10			—	S	50/0" (no recovery)			GM	hard	SILTY SAND & GRAVEL, predominantly fine, subangular, nonplastic, light brown
15										Auger refused at 10'6" Sampler refused at 10'6"

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Tailings Dam Investigation

JOB NO. E76-1023 DATE 3-31-76

LOG OF TEST BORING NO. 14

RIG TYPE CME-55

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0			☒	S	17		3		firm to hard	SILTY SAND & GRAVEL, predominantly fine, occasional cobbles, subangular, nonplastic, brown
5			⊠	S	50/5"		5	GM		
10			—	S	50/0"(no recovery)					
15			—	S	50/0"(no recovery)					Auger refused at 15'6" Sampler refused at 15'6"
20										

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Tailings Dam Investigation

JOB NO. E76-1023 DATE 3-31-76

LOG OF TEST BORING NO. 15

RIG TYPE CME-55

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0			☒	S	15		3	SM	moderately firm	SILTY SAND, predominantly fine, moderately cemented, medium plasticity, dark brown
5			☒	S	78		5		hard	SILTY SAND & GRAVEL, subrounded, nonplastic, brown
10			▬	S	50/3" (no recovery)			GM		
15			▬	S	50/3"		4			
			▬	S	50/1" (no recovery)					
20										Stopped auger at 19'6" Sampler refused at 19'7"
25										

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-6-76

LOG OF TEST BORING NO. 16

RIG TYPE CME-75

BORING TYPE 6½" Hollow Stem Auger, NX

SURFACE ELEV. Diamond Core & Tricone

DATUM Gear Bit

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0				S	49		5		dry very hard	SILTY SAND, GRAVEL & COBBLES, some clays, poorly graded, moderately to highly cemented, low plasticity, light tan to white
5				S	55		4	GM		
									HSA refusal at 8' Begin Tricone Gear Bit	
10				GB			26		dry very hard	CLAYEY SAND, GRAVEL & COBBLES, poorly graded, moderately to highly lime cemented, medium plasticity, light tan to white
15				GB				GM		
20				S	50/1"		20		dry very hard	SILTY SAND, GRAVEL & COBBLES, poorly graded, moderately cemented, low plasticity to non-plastic, light tan
				A			3			
25				S	50/½"		11			
				A			4			
							3			
30				S	50/1"		7			
35				S	50/1"		4	GM		
				A			4			
40				S	50/1"		3			
				A			2			
45				S	50/2"		4			
50				S	50/1"				Stopped auger at 49'6" Sampler refused at 49'7"	

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

01088

PROJECT Copper Flat Tailings Dam & Pond

LOG OF TEST BORING NO. 17

JOB NO. E76-1100 DATE 8-30-76

RIG TYPE CME-55

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0		S	29				dry hard	CLAYEY SAND, considerable gravel, trace of cobbles, moderately cemented, medium plasticity, light gray
5		S	48		7			
10		S	50/5"					
15		S	50/1"		5			
20		S	50/3"		9			note: becomes highly cemented below 21'
25		S	50/2"			SC		
30		S	50/¾"		5			
35		S	105		5			
40		S	50/½"(no recovery)					
45		S	50/0"(no recovery)					
50		S	100/3"		7			

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" i.D. tube sample.
T – 3" O.D. thin-walled Shelby tube

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

LOG OF TEST BORING NO. 17

JOB NO. E76-1100 DATE 8-20-76

RIG TYPE CME-55

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
50										
55				S	50/3"		10	SC		note: occasional seam of silty clay, medium to high plasticity, light brown
60				S	50/2½"		11			
65				S	100/1"		9			
70										Auger refused at 65'

GROUND WATER

DEPTH	HOUR	DATE

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-22-76

LOG OF TEST BORING NO. 17B

RIG TYPE CME-75

BORING TYPE 4½" Flight Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								CL-CH		SANDY CLAY, some gravel, medium plasticity, light brown
5										SILTY SAND & GRAVEL, slightly lime cemented, nonplastic, gray note: occasional cobble
10										
15								SM & GM		
20										
25										
30										Stopped auger at 30'

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-1-76

LOG OF TEST BORING NO. 18

RIG TYPE CME-75

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								GRAVEL littered surface
		S	20		17		firm to hard	SILTY CLAY, some sand, medium to high plasticity, reddish-brown
5		S	33		18			note: occasional seam of clayey silt, medium plasticity, reddish-tan
10		S	38			CH		
15		S	50/5½"		22			
20		S	50/5½"		16			
25		S	85		23	ML	hard	CLAYEY SILT, some fine sand, medium plasticity, light brown
30		S	50/4"		20	ML	hard	SANDY SILT, considerable lime, low plasticity, light tan
35		S	50/4"			CL	hard	SILTY CLAY, some fine sand, medium plasticity, light brown
40		S	50/5½"		13		hard	SANDY SILT, low plasticity, light brown
45		S	50/2"		11	ML		CLAYEY SAND & GRAVEL, occasional cobble, decomposed, low plasticity, brown
50		S	50/2"		19	SC		Stopped auger at 49'6" Sampler refused at 49'8"

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-4-76

LOG OF TEST BORING NO. 19

RIG TYPE CME-75

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0			S		28				dry firm to hard	SILTY SAND & GRAVEL, cobbles to 6", skip graded, moderately to strongly lime cemented, low plasticity, light tan note: no cobbles below 10'
5			S		50/4"			GM		
10			S		50/1½"		5			
15			S		50/5"				slightly moist hard	SILTY SAND, some gravel, trace of stratified silty clay, sand, predominantly fine to medium, slightly to moderately cemented, low plasticity, light reddish-tan
20			S		50/4"		8	SM		
25			S		50/5"		10			
30			S		50/4½"		10		slightly moist hard	SILTY SAND, trace of gravel & silty clay, stratified, sand, fairly well graded, slightly cemented, nonplastic to low plasticity, light reddish-brown note: considerable silty clay lenses at 37'
35			S		50/3"			SM		
40			S		50/4½"		11			
45			S		92		20	CH	moist hard	SILTY CLAY, some fine sands, medium to high plasticity, bright reddish-brown
50										

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-4-76

LOG OF TEST BORING NO. 19

RIG TYPE CME-75

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
50			☒	S	68			CH		
55			☒	S	50/4½"		19			
60										Stopped auger at 54'6" Sampler refused at 55'4½"

GROUND WATER

DEPTH	HOUR	DATE

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-29-76

LOG OF TEST BORING NO. 20

RIG TYPE CME-55

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0			S	16			14	CH	slightly moist, stiff to hard	SILTY CLAY, considerable sand, some cobbles, medium to high plasticity, bright reddish-brown
5			S	75			18		dry, hard	CLAYEY SAND, considerable gravel, some stratified cobbles, well graded, slightly lime cemented, nonplastic, light gray; note: some clays decomposed from weathering granitic gravels, light reddish-brown
10			S	62						
15			S	50/4"			9	SC		
20			S	50/5½"			8			
25			S	50/2"			11			
30			S	50/5"			14	SM & CL	slightly moist, hard	SILTY SAND, with laminations of silty clay, sand, predominantly medium to fine, clays, medium to high plasticity, light reddish-brown
35			S	67			32	CH	slightly moist, hard	SILTY CLAY, some sand, medium to high plasticity, bright reddish-brown, interbedded with sand, predominantly medium to fine, nonplastic, light gray
40			S	46						
45			U	50/3½"			24	CH	moist, hard	SILTY CLAY, some sand, medium to high plasticity, bright reddish-brown
50										

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-29-76

LOG OF TEST BORING NO. 20

RIG TYPE CME-55

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
50			X	S	100					
55			☒	S	50/5½"		21			
60			☒	S	50/5½"		20			
								CH		
65			☒	S	79					note: occasional seam of sandy silt, low plasticity, brown
70			☒	S	84		26			
75			☒	S	85		21			
80										Stopped auger at 74'6" Sampler refused at 75'11½"

GROUND WATER

DEPTH	HOUR	DATE

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-24-76

LOG OF TEST BORING NO. 21

RIG TYPE CME-75

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0			☒	S	15		8	CH	firm	SANDY CLAY, high plasticity, reddish-brown
5			☒	S	35		11	SC	very firm	CLAYEY SAND, predominantly fine, some lime cementation, low to medium plasticity, tan
10			☒	S	49		21	CL	very firm to hard	SILTY CLAY, medium to high plasticity, red note: plasticity highly variable between 7½'-18'
15			☒	S	56		19			
20			☒	S	75		19	CH	hard	SILTY CLAY, high plasticity, red
25			☒	S	98		15			
30			☒	S	96				hard	SILTY CLAY, marbled with clayey silt, little fine sand, medium plasticity, red
35			☒	S	60		20			
40			☒	S	73		17	CH & ML		
45			☒	S	56		30			
50										

GROUND WATER

DEPTH	HOUR	DATE

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-24-76

LOG OF TEST BORING NO. 21

RIG TYPE CME-75

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
50				S	62		31			
55				S	107			CH & ML		
60				S	115		24			
65				S	50/5"		25			
70				S	50/4"		21		hard	SILTY CLAY, medium to high plasticity, reddish-brown
75				S	167			CH		
80				S	119		17			
85				S	88		23			
								CH	hard	SANDY CLAY, medium to high plasticity, reddish-brown
90				S	50/2½"		13	CL	hard	SANDY CLAY, some fine gravel, low plasticity, reddish-tan
95				S	50/5"		10	GC	hard	CLAYEY SAND & GRAVEL, poorly graded to 1", low to medium plasticity, tan
100				S	50/3½"		15			note: gravel highly decomposed

GROUND WATER

DEPTH	HOUR	DATE

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH
CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

LOG OF TEST BORING NO. 21

JOB NO. E76-1100 DATE 8-25-76

RIG TYPE CME-75

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
100										
105			☒	S	50/3"			GC		
				S	50/½" (no recovery)					
110										Stopped auger at 109'6" Sampler refused at 109'6½"
115										

GROUND WATER

DEPTH	HOUR	DATE
105'	9:30 a.m.	8-25

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-24-76

LOG OF TEST BORING NO. 22

RIG TYPE CME-55

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0			☒	S	28		11		firm to hard	SANDY CLAY, trace of weathered gravel, sand, skip graded, medium plasticity, light reddish-brown
5			☒	S	77		7	CL		note: moderately white cementation begins at 10'
10			☒	S	37		16			
15			☒	S	30		23		firm to hard	SILTY CLAY, some fine sands, medium to high plasticity, bright reddish-brown
20			☒	S	48		21	CH		
25			☒	S	68		22			
30			☒	S	50/5½"		16	SC	hard	CLAYEY SAND, sand, predominantly fine, low plasticity, light reddish-brown
35			☒	S	104					note: possibly small stratifications interbedded with silty clay
40			☒	S	71		22	CL	hard	SILTY CLAY, some fine sand, medium plasticity, bright reddish-brown
45			☒	S	62		25			note: some 2" thick lenses of clayey sand interbedded with silty clay
50										

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-24-76

LOG OF TEST BORING NO. 22

RIG TYPE CME-55

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
50				S	58		20			note: increased amount of sandy clay lenses between 53'-57', 5" thick
55				S	70		21	CL		
60				S	63		20			
65				S	50/5"		20	CL-CH	slightly moist hard	SILTY CLAY equally interbedded with sandy clay, sand, predominantly fine, medium to high plasticity, bright reddish-brown
70				S	69		21	CH	slightly moist hard	SILTY CLAY, trace of sand, predominantly fine, medium to high plasticity, bright reddish-brown
				S	50/1"		16	GC	hard	CLAYEY SAND & GRAVEL, trace of cobbles, skip graded, highly weathered, clay, medium plasticity, greenish-gray
75										
80										Stopped auger at 74'6" Sampler refused at 74'7"

GROUND WATER

DEPTH	HOUR	DATE

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH
CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE

LOG OF TEST BORING NO. 23

RIG TYPE

BORING TYPE

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
									Boring 23 was not drilled. Boring 5 from preliminary investigation (Ref. 1) at planned location of Boring 23.	

GROUND WATER

DEPTH	HOUR	DATE

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-29 & 30-76

LOG OF TEST BORING NO. 24

RIG TYPE CME-75

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0			☒	S	30		7	SC	firm	CLAYEY SAND, predominantly fine, some gravel, low plasticity, brown
5			☒	S	31		10	CL	hard	SILTY CLAY, some sand, moderately lime cemented, medium plasticity, white
10			☒	S	97		9			
15			☒	U	50			CH	very firm	SILTY CLAY, high plasticity, reddish-brown to green
20			☒	U	82					
25			☒	S	86		19	CL	hard	SILTY CLAY, medium plasticity, reddish-brown
30			☒	S	50/6"		16	SC	hard	CLAYEY SAND, predominantly fine, very low plasticity, light brown
35			☒	S	50/5½"		10	CL	hard	SILTY CLAY, medium to high plasticity, reddish-brown
40			☒	S	88			CH	hard	SILTY CLAY, high plasticity, reddish-brown
45			☒	S	50/5½"		17	ML	hard	CLAYEY SILT, little fine sand, low to medium plasticity, light brown
50			▽	S	50/3"		15			

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-100 DATE 8-29 & 30-76

LOG OF TEST BORING NO. 24

RIG TYPE CME-75

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
50								ML		
									hard	SILTY CLAY, high plasticity, reddish-brown
55				S	77		21			
								CH		
60				S	54		24			
65				S	50/5"		7			
								GC	hard	CLAYEY SAND & GRAVEL, highly decomposed, low plasticity, brown to light brown
70										Stopped auger at 66'

GROUND WATER

DEPTH	HOUR	DATE

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-13-76

LOG OF TEST BORING NO. 24B

RIG TYPE CME-55

BORING TYPE 4½" Flight Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								GC		CLAYEY SAND & GRAVEL, some silt, moderately lime cemented, low plasticity, white
5										
10										
15								CL		SANDY CLAY, medium plasticity, reddish-brown
20										
25										Stopped auger at 25'

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond
JOB NO. E76-1100 DATE 8-24 & 25-76

LOG OF TEST BORING NO. 25

RIG TYPE CME-55
BORING TYPE 6½" Hollow Stem Auger
SURFACE ELEV.
DATUM

Depth in Feet	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0		S	15	6		dry very firm	SILTY SAND & GRAVEL, sand, medium to fine, subangular gravel, slightly cemented, stratified, low plasticity, light gray
		A		8			
5		S	37	14	GM		
10		S	50/5"	8	ML	slightly moist hard	CLAYEY SILT, some stratified gravel, slightly to moderately cemented, low plasticity, white
15		S	36	21	CL-CH	slightly moist very firm	SANDY CLAY interbedded with silty clay, sand, predominantly fine, trace of gravel, weathered, clays, medium plasticity, mottled bright yellow & gray
20		S	43	20	CL		
25		S	32			slightly moist very firm	SANDY CLAY, sands, predominantly fine, medium to high plasticity, bright reddish-brown
30		S	44	25		slightly moist very firm to hard	SILTY CLAY, some interbedded silty sands, medium to high plasticity, reddish-brown
35		S	43	21	CH		
40		S	82	25			
45		S	134	19			
50		S	50/3½"	12			

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE
A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH
CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond
JOB NO. E76-1100 DATE 8-24 & 25-76

LOG OF TEST BORING NO. 25

RIG TYPE CME-55
BORING TYPE 6½" Hollow Stem Auger
SURFACE ELEV.
DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
50								ML	slightly moist very dense	SILTY SAND, some laminated silty clay, sand, predominantly fine, low plasticity, light gray
55				S	65		20		moist to very moist hard	SILTY CLAY, medium to high plasticity, bright reddish-brown interbedded with silty sand, sand, predominantly fine, low plasticity, light grayish-brown
60				S	67		23	CH		
65				S	50/3½"		12		moist very dense	CLAYEY SAND & GRAVEL, trace of stratified cobbles, skip graded, gravel, highly weathered, clay, medium plasticity, grayish-green to brown
70				S	50/4"		8	GC		
75				S	78 (no recovery)					
80										Stopped auger at 74'6" Stopped sampler at 76'

GROUND WATER

DEPTH	HOUR	DATE

SAMPLE TYPE
A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH
CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-26-76

LOG OF TEST BORING NO. 26

RIG TYPE CME-55

BORING TYPE 6½" Hollow Stem Auger & NX Diamond Core

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0				S	110		16	CH	slightly moist hard	SILTY CLAY, some sand & gravel, medium to high plasticity, purple to reddish-brown
5				S	50/4"		4			
				A					HSA refusal at 8' Begin NX coring	
10				NX	90% Core Recovery 100% Water Return					BASALT, slightly weathered, moderately fractured, thickly bedded, hard to very hard, light gray note: some calcite in fractures, fracturing & weathering increases with depth, upper 8' mottled
				NX	100% Core Recovery 100% Water Return					
15				NX	100% Core Recovery 90% Water Return					
20				NX	95% Core Recovery 90% Water Return					
25				NX	70% Core Recovery 90% Water Return					BASALT, brecciated, containing some foreign diorite & granitic fragments, very weathered, soft, purple note: becomes calcite cemented at 28'
				NX	~~75% Core Recovery~~ 85% Water Return					
30				NX	80% Core Recovery					
				NX	70% Core Recovery 40% Water Return					CONGLOMERATE, very weathered, highly fractured, calcite cementation, soft, gray
35				NX	0% Core Recovery 50% Water Return					
				S	53				Stopped NX coring at 36'6"	
40										Stopped coring at 36'6" Stopped auger at 38'

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-29-76

LOG OF TEST BORING NO. 27

RIG TYPE CME-55

BORING TYPE 6½" Hollow Stem Auger & NX

SURFACE ELEV. Diamond Core

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0				S	7		11	ML	soft	SANDY SILT, some clay, little fine gravel, low plasticity, tan
5				S	26			CH	firm	SILTY CLAY, medium to high plasticity, brown
10				S	50/2"		10	CL	hard	SANDY CLAY, considerable gravels, some cobbles, moderately lime cemented, medium plasticity, reddish-brown
15				S	50/2"		9		hard	SILTY SAND & GRAVEL, composed of volcanic fragments, moderately cemented, nonplastic, light tan to reddish-brown
20				S	50/2"		12			
25				S	50/5½"			GM		
30				S	50/3"		13			
35				S	50/2"		11			
40				S	50/5"		20		slightly moist to wet hard	SILTY SAND & GRAVEL, some clays, trace of cobbles, skip graded, subangular, tan to reddish-brown
45				S	47		23	GM		
50										

GROUND WATER

DEPTH	HOUR	DATE
38'	11:30 a.m.	8-29

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond
JOB NO. E76-1100 DATE 8-29-76

LOG OF TEST BORING NO. 27

RIG TYPE CME-55
BORING TYPE 6½" Hollow Stem Auger & NX
SURFACE ELEV. Diamond Core
DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
50				S	187		19			
								GM		
55				S	50/3"(no recovery)				HSA refusal at 56'6"	note: large cobbles at 55'+
				NX	100% Core Recovery 100% Water Return				Begin NX coring	
60										Auger refused at 56'6" Stopped coring at 57'6"

GROUND WATER

DEPTH	HOUR	DATE

SAMPLE TYPE
A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH
CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-23-76

LOG OF TEST BORING NO. 27B

RIG TYPE CME-75

BORING TYPE 4½" Flight Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								CL-CH		SANDY CLAY, medium plasticity, brown
5										
10								SC & GC		CLAYEY SAND & GRAVEL, some cobbles, low plasticity, brown
15								SM & GM		SILTY SAND & GRAVEL, some cobbles, nonplastic, light brown
20								GM-GC		SILTY SAND & GRAVEL, some cobbles, trace of clay, nonplastic to low plasticity, brown
25								SC & GC		CLAYEY SAND & GRAVEL, some lime cementation, low plasticity, brown
30										
35								SC & GC		CLAYEY SAND & GRAVEL, medium plasticity, dark brown
40								GM-GC		SILTY SAND & GRAVEL, some cobbles, trace of clay, nonplastic, brown
45										Stopped auger at 41'

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond
JOB NO. E76-1100 DATE 8-26-76

LOG OF TEST BORING NO. 28

RIG TYPE CME-55
BORING TYPE 6½" Hollow Stem Auger & NX
SURFACE ELEV. Diamond Core
DATUM

Depth in Feet	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								FILL
		S	15		5	SM	dry	SILTY SAND, well graded, nonplastic, light grayish-brown
5		S	59		4	GC	dry hard	CLAYEY SAND & GRAVEL, some cobbles, skip graded, slightly cemented with high calcium content, light gray to white
10		S	50/1"		7			note: samples contain considerable amounts of porous basalt fragments
		A			6			
15		S	50/1" (no recovery)					
		S	50/0"				moist to very moist	BASALT, moderately to highly weathered, moderately fractured, ribboned with calcite, black to greenish-black
20								note: alternating zones which are brecciated & calcified; highly decomposed & porous forming silty sand & gravel, skip graded, nonplastic, gray to black
25		S	50/3"		10			
30		S	50/½"		12			
		A						
35		S	50/0"					
40		S	50/0"					BASALT, slightly to moderately weathered, very fractured, thickly bedded, hard, light gray
							HSA refusal at 42'6" Begin NX coring	note: fractures & voids contain crystalline calcite; becomes highly competent, moderately fractured, very hard at 47'6"
45		NX	100% Core Recovery 100% Water Return					
		NX	100% Core Recovery 100% Water Return					
50								

GROUND WATER

DEPTH	HOUR	DATE
29'	9:00 a.m.	10-26

SAMPLE TYPE
A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH
CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-26-76

LOG OF TEST BORING NO. 28

RIG TYPE CME-55

BORING TYPE 6½" Hollow Stem Auger & NX

SURFACE ELEV. Diamond Core

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
50				NX						100% Core Recovery 100% Water Return
55										100% Core Recovery 90% Water Return
				NX						25% Core Recovery 50% Water Return
60										CONGLOMERATE, very weathered, moderately fractured, thinly bedded, alternately hard & soft, light gray note: calcite cementation, fragments sub-angular; becomes clayey & highly decomposed, competent at 65'6"-67'
				NX						100% Core Recovery 50% Water Return
65										
70										Stopped coring at 68'

GROUND WATER

DEPTH	HOUR	DATE

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-25-76

LOG OF TEST BORING NO. 29

RIG TYPE CME-75

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0		S	26	11	CL	firm	SANDY CLAY, some silt, medium plasticity, brown
5		S	50		SC-SM	hard	SILTY SAND, considerable clay, some gravel, moderately to strongly cemented, low plasticity, light tan
10		S	50/4"	3			
15		S	54	8	GC	very hard to hard	CLAYEY SAND, GRAVEL & COBBLES, poorly graded to 8", subrounded, low plasticity, light brown
20		S	63			hard to very firm	SILTY CLAY, medium to high plasticity, reddish-brown note: occasional seam of silty clay
25		S	58	20			
30		S	105	13	CH		
35		S	88	14			
40		S	83				
45		S	43	15			
50					CL	very firm	SANDY CLAY, low to medium plasticity, brown

GROUND WATER

DEPTH	HOUR	DATE

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-25-76

LOG OF TEST BORING NO. 29

RIG TYPE CME-55

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
50				S	65		16	CL		
55				S	69		15	CH	hard	SILTY CLAY, high plasticity, reddish-brown note: occasional seam of clayey sand
60				S	59		22			
65				S	50/5½"		9			
70				S	50/5"		12	SC	hard	CLAYEY SAND, considerable gravel (decomposed), low to medium plasticity, reddish-brown to gray
75				S	50/4"		10			
										Stopped auger at 74'6" Sampler refused at 74'10"

GROUND WATER

DEPTH	HOUR	DATE
67'+	5:45 p.m.	8-25

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-23-76

LOG OF TEST BORING NO. 29B

RIG TYPE CME-75

BORING TYPE 4½" Flight Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								CL-CH		SANDY CLAY, some silt, medium plasticity, brown
5								SC & GC		SANDY CLAY & GRAVEL, some lime cementation, medium plasticity, light brown
10										
15								SC & GC		CLAYEY SAND & GRAVEL, some cobbles, lime cemented, low plasticity, light brown
20								GC-GM		SANDY CLAY, some silt, medium plasticity, reddish-brown
25										
30										SANDY CLAY, high plasticity, reddish-brown note: occasional layers of clay
35								CH		
40										
45										
50										

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-23-76

LOG OF TEST BORING NO. 29B

RIG TYPE CME-75

BORING TYPE 4½" Flight Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
50										
55								CH		
60										
65										CLAYEY SAND, some gravel
70								SC		
75										
80										Stopped auger at 79'

GROUND WATER

DEPTH	HOUR	DATE

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-28 & 29-76

LOG OF TEST BORING NO. 30

RIG TYPE CME-75

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0			☒	S	50/5½"		3	CH	hard	SANDY CLAY, some gravel, medium to high plasticity, reddish-brown
5			⊠	S	50/5"		4		hard	CLAYEY SAND, GRAVEL & COBBLES, poorly graded to 10", moderately to strongly lime cemented, subangular to subrounded, low to medium plasticity, light tan
10			—	S	50/0" (no recovery)			GC		
15			—	S	50/0" (no recovery)					
20										
25			⊠	S	50/5½"		20	CH	hard	SILTY CLAY, considerable lime, medium to high plasticity, reddish-brown
30			☒	S	57			CH	hard	SILTY CLAY, some lime, high plasticity, reddish-brown
35			☒	S	78		20	ML	hard	CLAYEY SILT, medium plasticity, reddish-brown
40			☒	S	75		19	CH	hard	SILTY CLAY, high plasticity, reddish-brown
45			☒	S	72			CH	hard	SILTY CLAY, medium to high plasticity, reddish-brown note: occasional seam of sandy clay, medium plasticity, brown
50										

GROUND WATER

DEPTH	HOUR	DATE

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond
JOB NO. E76-1100 DATE 8-28 & 29-76

LOG OF TEST BORING NO. 30

RIG TYPE CME-75
BORING TYPE 6½" Hollow Stem Auger
SURFACE ELEV.
DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
50				S	53		17	CH		
55				S	167		14	SC	hard	CLAYEY SAND, predominantly fine, low plasticity, brown
60				S	50/6"		19			
65				S	65			CH	hard	SILTY CLAY, high plasticity, reddish-brown
70				S	50/5½"		10	GC	hard	CLAYEY SAND & GRAVEL, poorly graded to 1", highly decomposed, low to medium plasticity, greenish-tan
75				S	50/5"		12			Stopped auger at 74'6" Sampler refused at 74'11"

GROUND WATER

DEPTH	HOUR	DATE
73'	5:00 p.m.	8-29

SAMPLE TYPE
A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH
CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-25 & 26-76

LOG OF TEST BORING NO. 31

RIG TYPE CME-55

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0				S	44		9	GC	dry dense	CLAYEY SAND & GRAVEL, trace of cobbles, skip graded, low to medium plasticity, reddish-brown
5				S	104				dry hard	CLAYEY SAND, considerable gravel, trace of cobbles, well graded, medium plasticity, light gray
10				S	50/5"			SC		
15				S	50/3"		7			
20				S	50/3"		6		dry hard	SANDY CLAY, considerable silt, some stratified gravel, moderately cemented with high calcium content, low plasticity, white
				A				CL-ML		
25				S	50/2½"		6			
30				S	40		20		slightly moist firm	SILTY CLAY, interbedded clayey sands, sand, predominantly fine, medium to high plasticity, reddish-brown
35				S	97					
40				S	50/5"		16	CH		note: clayey sand becoming sandy clays
45				S	125		19			
50										

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond
JOB NO. E76-1100 DATE 8-25 & 26-76

LOG OF TEST BORING NO. 31

RIG TYPE CME-55
BORING TYPE 6½" Hollow Stem Auger
SURFACE ELEV.
DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
50				S	102		19			note: interbedded clayey sands
55				S	72		18	CH		
60				S	50/3"		9	GC	moist hard	CLAYEY SAND, some gravel, sand, predominantly medium to fine, clays, medium plasticity, light gray to greenish-gray
65				S	50/3½"		22	CH & SC	moist hard	SILTY CLAY, interbedded clayey sands, sand, predominantly fine, medium to high plasticity, bright reddish-brown
70				S	56		25			
75				S	50/4"		12	GC	slightly moist hard	CLAYEY SAND & GRAVEL, skip graded, highly weathered, medium to high plasticity, reddish-brown to grayish-green
80										Stopped auger at 74'6" Sampler refused at 75'4"

GROUND WATER

DEPTH	HOUR	DATE

SAMPLE TYPE
A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH
CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond
JOB NO. E76-1100 DATE 8-26-76

LOG OF TEST BORING NO. 32

RIG TYPE CME-75
BORING TYPE 6½" Hollow Stem Auger
SURFACE ELEV.
DATUM

Depth in Feet	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0		S	24		11	CH	firm	SILTY CLAY, medium to high plasticity, reddish-brown
						CL		
5		S	50/5"		3		firm	SANDY CLAY, medium plasticity, reddish-brown
						SC-SM	hard	CLAYEY SAND, considerable silt, gravel & cobbles, poorly graded to 8", strongly lime cemented, subangular, low plasticity, light tan
10		S	71					
15		S	76		3			note: occasional layer of clayey sand, considerable gravel
						GC		
20		S	50/4"		4		hard	CLAYEY SAND & GRAVEL, poorly graded to 6", subrounded, low plasticity, brown
25		S	125				hard	SILTY CLAY, high plasticity, reddish-brown
						CH		note: occasional seam of lime
30		S	50/5½"		13			
35		S	44		30		very firm	SILTY CLAY, medium to high plasticity, reddish-brown
40		S	38		45	CL-CH		
45		S	50					
50								

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE
A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH
CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond
JOB NO. E76-1100 DATE 8-26-76

LOG OF TEST BORING NO. 32

RIG TYPE CME-75
BORING TYPE 6½" Hollow Stem Auger
SURFACE ELEV.
DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
50				S	70		21			
55				S	39		29			note: occasional seam of clayey sand
60				S	50/5½"			CL-CH		
65				S	50/5"		23			
70				S	96		22			note: small amount of fine gravel at 75'
75				S	50/5"		16			Stopped auger at 74'6" Sampler refused at 74'11"

GROUND WATER

DEPTH	HOUR	DATE

SAMPLE TYPE
A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH
CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-27-76

LOG OF TEST BORING NO. 33

RIG TYPE CME-75

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0		S	50		7	CH	hard	SANDY CLAY, some gravel, medium to high plasticity, reddish-brown
5		S	50/5½"		3	GC	hard	CLAYEY SAND, GRAVEL & COBBLES, poorly graded to 10", moderately to strongly lime cemented, subangular to subrounded, low to medium plasticity, reddish-tan
10		S	50/0" (no recovery)					
15		S	68		3	GM	dense	SILTY SAND & GRAVEL, poorly graded to 2", little clay, very low plasticity to nonplastic, brown
20		S	50/2"		2	GC	hard	CLAYEY SAND, GRAVEL & COBBLES, poorly graded to 6", subangular, low to medium plasticity, reddish-brown
25		S	50/5½"		18	CH	hard	SILTY CLAY, considerable lime, medium to high plasticity, light tan to white
30		S	50/2"		10			
35		S	70				hard	SILTY CLAY, considerable lime, high plasticity, reddish-brown note: occasional seam of clayey silt, medium plasticity
40		S	103		21	CH		
45		S	105		19			
50								

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond
JOB NO. E76-1100 DATE 8-27-76

LOG OF TEST BORING NO. 33

RIG TYPE CME-75
BORING TYPE 6½" Hollow Stem Auger
SURFACE ELEV.
DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
50			☒	S	87		17	CH		
55			☒	S	182		16		hard	CLAYEY SILT, low to medium plasticity, reddish-brown note: occasional seam of clayey sand, predominantly fine, low plasticity, light tan
60			▬	S	50/3"		10	ML		
65			☒	S	70		18			
70			☒	S	82			CH	hard	SILTY CLAY, high plasticity, reddish-brown
75			☒	S	84		16	CL	hard	SANDY CLAY, some fine gravel, medium plasticity, reddish-brown
80										Stopped auger at 74'6" Sampler refused at 75'11½"

GROUND WATER

DEPTH	HOUR	DATE

SAMPLE TYPE
A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH
CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond
JOB NO. E76-1100 DATE 8-26 & 27-76

LOG OF TEST BORING NO. 34

RIG TYPE CME-75
BORING TYPE 6½" Hollow Stem Auger
SURFACE ELEV.
DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0			☒	S	80		7	CH	firm	SANDY CLAY, small amount of gravel, medium to high plasticity, reddish-brown
5			☒	S	99		3	GC	hard	CLAYEY SAND & GRAVEL, well graded to 2", occasional cobble, subrounded, low plasticity, light brown
10			═	S	50/3½"		4	GC	hard	CLAYEY SAND, GRAVEL & COBBLES, poorly graded to 8" moderately to strongly lime cemented, subangular to subrounded, low plasticity, light brown
15			☒	S	50/6"			CL	hard	SANDY CLAY, considerable lime, medium plasticity, brown to white
20			☒	S	123		8	CH	hard	SILTY CLAY, some sand, considerable lime, little fine gravel, high plasticity, light tan to white
25			═	S	50/2" (no recovery)					
30			☒	S	50/5½"		12			
35			☒	S	60			CH	hard	SILTY CLAY, high plasticity, reddish-brown
40			☒	S	84		18			
45			☒	S	59		24	ML	hard	CLAYEY SILT, low to medium plasticity, reddish-brown note: occasional seam of silty sand
50										

GROUND WATER

DEPTH	HOUR	DATE

SAMPLE TYPE
A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH
CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond
JOB NO. E76-1100 DATE 8-26 & 27-76

LOG OF TEST BORING NO. 34

RIG TYPE CME-75
BORING TYPE 6½" Hollow Stem Auger
SURFACE ELEV.
DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
50				S	80		19	ML		
55				S	87		17	CL	hard	SANDY CLAY, some silt, low to medium plasticity, tan
60				S	50			CH	hard	SILTY CLAY, high plasticity, reddish-brown note: occasional seam of sandy clay, medium plasticity, reddish-tan
65				S	50		25			
70				S	50/5½"		11	GC	hard	CLAYEY SAND & GRAVEL, highly decomposed, low plasticity, brown
75				S	50/4"		12			
80										Stopped auger at 74'6" Sampler refused at 75'4"

GROUND WATER

DEPTH	HOUR	DATE
72'	12:30 p.m.	8-27

SAMPLE TYPE
A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH
CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-7 & 8-76

LOG OF TEST BORING NO. 35

RIG TYPE CME-75

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0			⊠	S	58		5	SC	slightly moist hard	CLAYEY SAND, GRAVEL & COBBLES, poorly graded, medium plasticity, reddish-brown
5				S	50/3"		4		dry hard	SILTY SAND, GRAVEL, COBBLES & BOULDERS, boulders to +18", poorly graded, moderately cemented, nonplastic to low plasticity, light tan to white note: heavy lime content at 14'-16', sample white
				A			3	GM		
10			⊠	S	50/1"		4			
				A						
15				S	50/3"		2			
				A			6		dry hard	CLAYEY SAND, considerable gravel, moderately lime cemented, sand, skip graded, low to medium plasticity, light tan to gray
20			⊠	S	135		8	SC		
25			⊠	S	50/5"		7	GC	dry hard	CLAYEY SAND & GRAVEL, skip graded, moderately cemented, low to medium plasticity, light reddish-tan
30			⊠	S	50/4"				dry hard	SILTY SAND, considerable gravel, poorly graded, moderately cemented, low plasticity, light tan note: shows alteration due to possible ground water, greenish gray to reddish-brown at 40', heavy lime cementation at 35', moist at 40'
35				S	50/1"		3			
								GM		
40			⊠	S	50/5"		10			
45				S	50/1"		6			
50			⊠	S	50/5½"		7			

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-7 & 8-76

LOG OF TEST BORING NO. 35

RIG TYPE CME-75

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
50									slightly moist hard	CLAYEY SAND & GRAVEL, alternating content of silt & clay, skip graded, moderately lime cemented, low to medium plasticity, light greenish-gray to reddish-brown
55			☒	S	91					
60			⊠	S	50/4½"		7	GC		note: trace of cobbles at 55'-60'
65			⊠	S	50/5"		7			
			⊠	S	50/1½"		12			
70										Stopped auger at 69'6" Sampler refused at 69'7½"

GROUND WATER

DEPTH	HOUR	DATE

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH
CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

LOG OF TEST BORING NO. 36

JOB NO. E76-1100 DATE 9-10-76

RIG TYPE CME-75
BORING TYPE 6½" Hollow Stem Auger & NX Diamond Core
SURFACE ELEV.
DATUM

Depth in Feet	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0		S	88			dry hard	SILTY SAND, GRAVEL & COBBLES, trace of boulders, skip graded, moderately lime cemented below 5', sugangular to angular, nonplastic to low plasticity, light brown at 0-5', light tan to gray at 5'+
5		S	50/4"	3			
10		S	50/3½"	4	GM		
15		S	118	7			
20		S	50/5½"	4			
25		S	50/4"	9	GC	dry hard	CLAYEY SAND & GRAVEL, fairly well graded, moderately lime cemented, subangular, low plasticity, light gray note: highly cemented at 32' with cobbles
30		S	50/2"	9			
35		S	50/1" 50/½" (no recovery)		GC	hard to moderately hard	CLAYEY SAND, GRAVEL & COBBLES, probable skip graded, highly cemented, subangular, low to medium plasticity, light gray
40		S	50/0"				
45		S	50/0"				
						HSA refusal at 47'6" Begin NX coring	
50		NX	25% Core Recovery 100% Water Return				

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE
A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH
CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-10-76

LOG OF TEST BORING NO. 36

RIG TYPE CME-75

BORING TYPE 6½" Hollow Stem Auger & NX

SURFACE ELEV. Diamond Core

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
50										
				NX	20% Core Recovery 100% Water Return				Stopped NX coring at 53' Advance HSA	
55				S	50/1"					
				S	50/2"		6			
60										Auger refused at 59'6" Sampler refused at 59'8"

GROUND WATER

DEPTH	HOUR	DATE

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO E76-1100 DATE 9-13 & 15-76

LOG OF TEST BORING NO. 37

RIG TYPE CME-75

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0				S	15		9	SC	slightly moist	CLAYEY SAND, some gravel, sand, skip graded, medium plasticity, reddish-brown
5				S	54				dry	SILTY SAND & GRAVEL, some cobbles, fairly well graded, moderately lime cemented, nonplastic, light gray
10				S	75		5	GM		note: considerable clay at 9'6"
15				S	50/1½"		4			
				A			5			
20				S	50/⅓"				hard	CLAYEY SAND & GRAVEL, strongly cemented, subrounded to angular, medium plasticity, gray
25				S	50/4"		5			
30				S	50/4"		5			
35				S	50/2"		6	GC		
40				S	50/2½"					
45				S	50/3"		11			
50										

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-13 & 15-76

LOG OF TEST BORING NO. 37

RIG TYPE CME-75

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
50			⊠	S	50/5"		9			
55			⊠	S	132					
60			—	S	50/1"		10			
								GC		
65			═	S	50/2"		7			
70			—	S	50/1"		4			
75			⊠	S	50/5"		11			
80										Stopped auger at 75' Sampler refused at 75'5"

GROUND WATER

DEPTH	HOUR	DATE

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-12 & 13-76

LOG OF TEST BORING NO. 38

RIG TYPE CME-75

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
50										
55				S	50/½" (no recovery)			GC		
60				S	50/1"		10			
65				S	50/1"					Auger refused at 64'6" Sampler refused at 64'7"

GROUND WATER

DEPTH	HOUR	DATE

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-12 & 13-76

LOG OF TEST BORING NO. 38

RIG TYPE CME-75

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0									dry hard	SILTY SAND & GRAVEL, considerable cobbles, skip graded, moderately lime cemented below 3", nonplastic to low plasticity, angular to subangular, light brown at 0-3', light gray at 3'+
			S	25			6			
5			S	101			9	GM		
10			S	50/5"			6			
			A						slightly moist hard	CLAYEY SAND, GRAVEL & COBBLES, skip graded, moderately to highly lime cemented, angular, low plasticity, light gray note: considerable amount of gravel, particle decomposition taking place below 35' forming reddish-brown clay
15			S	50/1½"(no recovery)						
			A							
20			S	50/4"			5			
25			S	50/2"						
30			S	50/2½"			6	GC		
35			S	50/1"			3			
40			S	50/3"			9			
45			S	50/1"			8			
50			S	50/1"						

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Tailings Dam Investigation
Copper Flat Project

JOB NO. E76-1023 DATE 4-2-76

LOG OF TEST PIT NO. A

RIG TYPE Ford
BORING TYPE Backhoe test pit
SURFACE ELEV.
DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								SM		SILTY SAND, predominantly fine, low plasticity, brown
5			A					CL		SILTY CLAY, medium to high plasticity, reddish brown
10			A					GC		CLAYEY SAND & GRAVEL, predominantly medium, interbedded with caliche, medium plasticity, reddish brown mottled with white
15										Stopped backhoe at 14'6"
20										

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH
CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

01136 A-70

Tailings Dam Investigation

PROJECT Copper Flat Project

JOB NO. E76-1023 DATE 4-2-76

LOG OF TEST PIT NO. B

RIG TYPE Ford

BORING TYPE Backhoe test pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								ML		CLAYEY SILT, some sand, low plasticity, dark brown
			A					SC		CLAYEY SAND, fine, medium plasticity, pink
5										
										Stopped backhoe at 6'
10										

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

Tailings Dam Investigation

PROJECT Copper Flat Project

JOB NO. E76-1023 DATE 4-2-76

LOG OF TEST PIT NO. C

RIG TYPE Ford

BORING TYPE Backhoe test pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0			A					CL		SILTY CLAY, medium plasticity, brown
5			A					SC		CLAYEY SAND, predominantly medium to coarse, interbedded with caliche, some gravel & cobbles, subangular, medium plasticity, brown to white
10										Stopped backhoe at 10'
15										

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

01138A-72

PROJECT Tailings Dam Investigation
Copper Flat Project

JOB NO. E76-1023 DATE 4-2-76

LOG OF TEST PIT NO. D

RIG TYPE Ford
BORING TYPE Backhoe test pit
SURFACE ELEV.
DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								GM		SILTY SAND & GRAVEL, predominantly medium, subangular, nonplastic to low plasticity, brown
5										
10								GM		SILTY SAND & GRAVEL, interbedded with caliche, large cobbles & boulders, nonplastic, light brown
15										Stopped backhoe at 12'

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH
CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

Tailings Dam Investigation

PROJECT Copper Flat Project

JOB NO. E76-1023 DATE 4-2-76

LOG OF TEST PIT NO. E

RIG TYPE Ford

BORING TYPE Backhoe test pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								CH		CLAY, high plasticity, reddish brown
			A					CL		SANDY CLAY, low to medium plasticity, reddish brown
5										Stopped backhoe at 5'
10										

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Tailings Dam Investigation
Copper Flat Project

JOB NO. E76-1023 DATE 4-2-76

LOG OF TEST PIT NO. F

RIG TYPE Ford
BORING TYPE Backhoe test pit
SURFACE ELEV.
DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								ML		SILT, very fine, low plasticity, light brown
5			A					CH		alternating layers of CLAY & SILT, high plasticity, dark reddish brown
								GM		SILTY SAND & GRAVEL, predominantly fine, occasional basaltic boulders, subangular, nonplastic, brown
10										
15										Stopped backhoe at 10'

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH
CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-2-76

LOG OF TEST PIT NO. A-1

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								CL	dry	SANDY CLAY, medium plasticity, brown
5			G					CL	dry	SILTY CLAY, some clayey sand lenses, medium plasticity, reddish-brown
10										Stopped backhoe at 6'6"

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-2-76

LOG OF TEST PIT NO. A-2

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								CL	dry	SANDY CLAY, trace of gravel, medium plasticity, brown
5			G					CL	dry	SILTY CLAY, some clayey sand lenses, medium plasticity, reddish-brown
10										Stopped backhoe at 6'6"

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-26-76

LOG OF TEST PIT NO. F-1

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								GC-GM	dry	CLAYEY SAND & GRAVEL, trace of cobbles & sand, predominantly medium to fine, low plasticity, light brown
				G				CL	dry	SILTY CLAY, interbedded with sandy clay, some cobbles, highly laminated, slightly cemented, medium to high plasticity, light tan
5									dry	BASALT BRECCIA, moderately to highly weathered, unfractured, highly stratified, moderately hard, purple & white
10										Backhoe refused at 7'

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

01144 A-78

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-26-76

LOG OF TEST PIT NO. F-2

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								SM	dry	SILTY SAND, some stratified gravel, sand, predominantly fine, nonplastic, light tan
				G				SC-CL	dry	CLAYEY SAND interbedded with silty sand, sand, predominantly fine, weakly cemented, medium plasticity, light brown
5								CL-CH	slightly moist	SILTY CLAY, medium to high plasticity, light brown
								SC	dry	CLAYEY SAND, some gravel, well graded, moderately cemented, stratified, medium plasticity, gray
10										Stopped backhoe at 10'

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

LOG OF TEST PIT NO. 101

JOB NO. E76-1100 DATE 8-31-76

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0									dry	CLAYEY SAND & GRAVEL, some cobbles, well graded, medium plasticity, light brown
			G					SC		
5										
										Stopped backhoe at 6'8"
10										

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-31-76

LOG OF TEST PIT NO. 102

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								SC	dry	CLAYEY SAND & GRAVEL, well graded, medium plasticity, brown
									dry	SILTY SAND & GRAVEL, some cobbles, moderately lime cemented, non-plastic to low plasticity, light brown
5			G					SM		
										Stopped backhoe at 7'9"
10										

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

LOG OF TEST PIT NO. 103

JOB NO. E76-1100 DATE 8-31-76

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								CL	dry	SANDY CLAY, trace of gravel, medium plasticity, brown
								SC	dry	CLAYEY SAND & GRAVEL, strongly lime cemented, light brown
5			G					GP	dry	SAND & GRAVEL, some cobbles, trace of silt, predominantly coarse, moderately caliche cemented, non-plastic, brown
								CL		SANDY CLAY, medium plasticity, brown
10										Stopped backhoe at 9'6"

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

01148 A-82

PROJECT Copper Flat Tailings Dam & Pond

LOG OF TEST PIT NO. 104

JOB NO. E76-1100 DATE 8-28-76

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								SM-SC	dry	SILTY SAND, some gravel, little clay, low plasticity, brown
								CH	slightly damp to damp	SILTY CLAY, some sand, medium to high plasticity, reddish-brown to reddish-tan
5								CL	slightly damp to damp	SANDY CLAY, considerable gravel, occasional cobble, some layers of lime cementation, medium plasticity, light tan to reddish-brown
10										Stopped backhoe at 10'6"
15										

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-1-76

LOG OF TEST PIT NO. 105

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								SC	dry	CLAYEY SAND & GRAVEL, some cobbles, well graded, low to medium plasticity, brown
5			G					GM-GP	dry	SILTY SAND & GRAVEL, trace of cobbles, poorly graded, weakly to moderately lime cemented, low plasticity, light brown
10										Stopped backhoe at 9'

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

LOG OF TEST PIT NO. 106

JOB NO. E76-1100 DATE 9-2-76

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								SC	dry	CLAYEY SAND & GRAVEL, some cobbles, well graded, low plasticity, brown
5			G					SC-SM	dry	CLAYEY SAND & GRAVEL, some cobbles, well graded, moderately lime cemented, low plasticity, light brown & white
10										Stopped backhoe at 8'5"

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-2-76

LOG OF TEST PIT NO. 107

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								SC	dry	CLAYEY SAND & GRAVEL, some cobbles & boulders, well graded, low plasticity, brown
5			G					SC	dry	CLAYEY SAND & GRAVEL, some cobbles, well graded, moderately lime cemented, medium plasticity, brown & white
10										Stopped backhoe at 9'

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-31-76

LOG OF TEST PIT NO. 108

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								SC	dry	CLAYEY SAND, some gravel & cobbles, well graded, medium plasticity, brown
									dry	SAND & GRAVEL, some cobbles & clay, occasional small boulder, well graded, low plasticity, light brown
5				G				SC-SW		
10										Stopped backhoe at 9'

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-31-76

LOG OF TEST PIT NO. 109

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0									dry	SAND & GRAVEL, some cobbles, occasional boulder, well graded, medium plasticity, light brown
5				G				SW-SC		
10										Stopped backhoe at 10'3"
15										

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-28-76

LOG OF TEST PIT NO. 110

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0			G					GP	dry	SAND & GRAVEL, little silt, poorly graded to 1", nonplastic, tan
5	G		G					SC	slightly damp	CLAYEY SAND, some gravel, well graded, low to medium plasticity, brown
10			G					CH	damp	SILTY CLAY, moderately lime cemented, high plasticity, light purple
										Stopped backhoe at 10'0"

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-19-76

LOG OF TEST BORING NO. 110

RIG TYPE CME-75

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								
		S	4		27	CL	moist very soft	SANDY CLAY, trace of gravel, medium plasticity, brown
5		S	15		20	CL	moist moderately firm	SILTY CLAY, trace of sand, medium plasticity, brown
10		S	17					
						CL	slightly damp firm	SILTY CLAY, trace of sand, medium plasticity, light reddish-brown
15		S	24		23	ML	slightly damp firm	CLAYEY SILT, low plasticity, reddish-brown
20		S	47		13	SM	slightly damp very firm	SILTY SAND, some gravel, predominantly fine, nonplastic, grayish-brown
25		S	97		11	CL	slightly damp hard	SILTY CLAY, some sand & gravel, medium plasticity, reddish-brown
30		S	63				moist hard	CLAYEY SAND & GRAVEL, angular to subangular, medium plasticity, grayish-brown
35		S	93		7	GC		
40		S	121		9			
45		S	91		11			
50								

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-19-76

LOG OF TEST BORING NO. 110

RIG TYPE CME-55

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
50			☒	S	50/3"					
55			—	S	50/1"		10			
60			═	S	50/2"		7			
								GC		
65			☒	S	50/6"		7			
70			☒	S	50/3"		7			
75			═	S	50/3"		14			
80										Stopped auger at 75' Sampler refused at 75'3"

GROUND WATER

DEPTH	HOUR	DATE

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-1-76

LOG OF TEST PIT NO. 111

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								SC	dry	CLAYEY SAND & GRAVEL, some cobbles, well graded, medium plasticity, brown
5				G				GC-GP	dry	SAND & GRAVEL, some cobbles & clay, occasional boulder, poorly graded, moderately lime cemented, low plasticity, light brown
10										Stopped backhoe at 9'

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-1-76

LOG OF TEST PIT NO. 112

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								SC	dry	CLAYEY SAND & GRAVEL, some cobbles, well graded, low plasticity, brown
5				G				SC-SM	dry	SAND & GRAVEL, some cobbles & clay, well graded, moderately lime cemented, low plasticity, light brown
10										Stopped backhoe at 9'6"

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

01159 A-93

PROJECT Copper Flat Tailings Dam & Pond

LOG OF TEST PIT NO. 113

JOB NO. E76-1100 DATE 8-30-76

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0									dry	SAND & GRAVEL, some clay, occasional cobble, well graded, moderately lime cemented, medium plasticity, light tan
5				G				GC-GW		
10										Stopped backhoe at 10'6"

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

01160

A-94

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-17-76

LOG OF TEST BORING NO. 113

RIG TYPE CME-75

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0		S	35		9		dry dense to very dense	CLAYEY SAND, GRAVEL & COBBLES, fine to coarse, moderately to strongly cemented, subangular to subrounded, medium plasticity, tan to grayish-brown
5		S	53		1			
10		S	50/5½"					
15		S	50/½"		6			
20		S	50/5"		7			
25		S	50/5"		9	GC		
30		S	50/3"		9			
35		S	50/5"					
40		S	50/4"		8			
45		S	50/5½"		11			
50		S	50/2"					

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-17-76

LOG OF TEST BORING NO. 113

RIG TYPE CME-75

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
50										
55				S	50/3"		6			
60				S	50/6"		13			
								GC		
65				S	50/5"		10			
70				S	50/2"		10			
75				S	50/5"					

Stopped auger at 74'6"
Sampler refused at 74'11"

GROUND WATER

DEPTH	HOUR	DATE

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-30-76

LOG OF TEST PIT NO. 114

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0									dry	SAND, GRAVEL & COBBLES, poorly graded to 8", some clay, moderately lime cemented, low plasticity, light tan
5				G				GC-GP		
10										Stopped backhoe at 10'6"
15										

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

01163 A-97

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-30-76

LOG OF TEST PIT NO. 115

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0									dry	SILTY SAND, GRAVEL & COBBLES, well graded to 4", occasional cobble to 10"+, poorly graded, moderately to strongly lime cemented, low plasticity, light tan
5			G					GM		
10										Backhoe refused at 7'

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

01164 A-98

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-28-76

LOG OF TEST PIT NO. 116

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								CL	dry	SANDY CLAY, some gravel, medium plasticity, brown
				G				CL		
				G				GM	dry	SANDY CLAY, considerable gravel, moderately lime cemented, considerable lime nodules, medium plasticity, white to light tan
5				G				CH	slightly damp	SILTY SAND & GRAVEL, occasional cobble, little clay, poorly graded to 2"+, very low plasticity to nonplastic, reddish-tan
									slightly damp to damp	SILTY CLAY, high plasticity, reddish-brown note: occasional lense of lime cementation and occasional seam of sandy clay
10										Stopped backhoe at 10'

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-1-76

LOG OF TEST PIT NO. 117

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								SC	dry	CLAYEY SAND & GRAVEL, some cobbles, well graded, medium plasticity, brown
5			G					SC-SW	dry	SAND & GRAVEL, some clay, trace of cobbles, well graded, moderately lime cemented, low plasticity, light brown
10										Stopped backhoe at 9'6"

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

01166 A-100

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-30-76

LOG OF TEST PIT NO. 118

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								CL	dry	SILTY CLAY, some sand, little gravel, medium plasticity, brown
5				G				GC-GP	dry	SAND & GRAVEL, some clay, occasional cobble, poorly graded, moderately to strongly lime cemented, medium plasticity, light tan
10										Stopped backhoe at 9'6"

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

01167 A-101

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-30-76

LOG OF TEST PIT NO. 119

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0				G				CH	dry	SANDY CLAY, some gravel, medium to high plasticity, reddish-brown
									dry	SAND & GRAVEL, some clay, occasional cobble, well graded, moderately to strongly lime cemented, medium plasticity, light tan
5				G				SC-SW		
10										Stopped backhoe at 9'6"

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

01168 A-102

PROJECT Copper Flat Tailings Dam & Pond

LOG OF TEST PIT NO. 120

JOB NO. E76-1100 DATE 8-30-76

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								CL	dry	SANDY CLAY, considerable gravel, medium plasticity, brown
									dry	CLAYEY SAND, little gravel, few cobbles to 8"+, poorly graded, moderately to strongly lime cemented, medium plasticity, light tan
5				G				SC		
10										Stopped backhoe at 10'

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

LOG OF TEST PIT NO. 121

JOB NO. E76-1100 DATE 8-30-76

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								ML	dry	SANDY SILT, some gravel, very low plasticity, brown
									dry	CLAYEY SAND, GRAVEL & COBBLES, poorly graded to 8"+, considerably lime cemented, medium plasticity, light tan
5			G					GC		
10										Backhoe refused at 8'3"

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

01170 A-104

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-30-76

LOG OF TEST PIT NO. 122

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0			G					ML	dry	SANDY SILT, some gravel, very low plasticity to nonplastic, brown
5										BASALT, highly fractured, moderately weathered, thinly bedded, lime in fractures, black
10										Backhoe refused at 5'6"

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

LOG OF TEST PIT NO. 123

JOB NO. E76-1100 DATE 9-1-76

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0				G				SC	dry	CLAYEY SAND & GRAVEL, some cobbles, well graded, medium plasticity, dark brown
5										Backhoe refused at 1'6"

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

LOG OF TEST PIT NO. 124

JOB NO. E76-1100 DATE 9-1-76

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0									dry	SILTY CLAY, medium plasticity, brown
5			G					CL		
10								SC	dry	CLAYEY SAND & GRAVEL, some cobbles, well graded, moderately lime cemented, low plasticity, light brown
15										Stopped backhoe at 10'6"

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-19-76

LOG OF TEST BORING NO. 124

RIG TYPE CME-75

BORING TYPE 6½" Hollow Stem Auger & NX

SURFACE ELEV. Diamond Core

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0				S	9			SM		SILTY SAND, trace of clay, predominantly fine, low plasticity, light brown
5				S	45			CL		SANDY CLAY, medium plasticity, brown
10				S	54					CLAYEY SAND & GRAVEL, considerable lime & calcareous deposits, some cobbles, medium to high plasticity, brown
15				S	50/5"					
20				S	50/4"			SC-GC		
25				S	50/5½"					
30				S	50/5"					
35				S	50/4½"				HSA refusal at 36' Begin NX coring	
				NX				GC		CLAYEY SAND, GRAVEL & COBBLES, small boulders
40										Stopped coring at 40'

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-31-76

LOG OF TEST PIT NO. 125

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0									dry	SANDY CLAY, medium plasticity, brown
5				G				CL		
									dry	CLAYEY SAND & GRAVEL, well graded, moderately lime cemented, medium plasticity, brown
								SC		
10										Stopped backhoe at 10'5"

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

LOG OF TEST PIT NO. 126

JOB NO. E76-1100 DATE 8-31-76

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0									dry	CLAYEY SAND, trace of gravel, predominantly fine to medium, low to medium plasticity, brown
				G				SC		
5										
								CL	dry	SANDY CLAY, medium plasticity, brown
								SC	dry	CLAYEY SAND & GRAVEL, well graded, low plasticity, light brown
10										Stopped backhoe at 9'6"

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

LOG OF TEST PIT NO. 127

JOB NO. E76-1100 DATE 8-31-76

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								CL	dry	SANDY CLAY, medium plasticity, brown
5			G					SC-SP	dry	SAND & GRAVEL, some clay, poorly graded, low plasticity, light brown
10										Stopped backhoe at 10'

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

LOG OF TEST PIT NO. 128

JOB NO. E76-1100 DATE 8-29-76

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								SM	dry	SILTY SAND, trace of clay, predominantly medium to fine, non-plastic to very low plasticity, light brown
								CL	dry	SANDY CLAY, some gravel, medium plasticity, light reddish-brown
5								SM-SC	dry	SILTY SAND, GRAVEL & COBBLES, considerable calcite, some clay, poorly graded, weakly cemented, low plasticity, light gray to white
10										Backhoe refused at 9'

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

LOG OF TEST PIT NO. 129

JOB NO. E76-1100 DATE 8-29-76

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								ML-CL	dry	SANDY SILT, some clay, low plasticity, light brown
									dry	SAND & GRAVEL, some clay & cobbles, poorly graded, strongly lime cemented, low plasticity, white
5								GC-GP		
10										Stopped backhoe at 10'

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-2-76

LOG OF TEST PIT NO. 130

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								SC	dry	CLAYEY SAND, trace of gravel & cobbles, medium plasticity, brown
5				G				SC	dry	CLAYEY SAND, some gravel, well graded, medium plasticity, reddish-brown
10										Stopped backhoe at 9'10"

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

01180 A 114

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-2-76

LOG OF TEST PIT NO. 131

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0			G					SC	dry	CLAYEY SAND & GRAVEL, trace of cobbles, well graded, medium plasticity, brown
										CONGLOMERATE, moderately weathered, tan
5										Backhoe refused at 3'6"

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-2-76

LOG OF TEST PIT NO. 132

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								SC	dry	CLAYEY SAND & GRAVEL, some cobbles, well graded, low plasticity, brown
5			G					GM-GW	dry	SAND & COBBLES, some silt, trace of clay, moderately lime cemented, very low plasticity, light brown to brown
10										Stopped backhoe at 9'

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-2-76

LOG OF TEST PIT NO. 133

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								SC		CLAYEY SAND & GRAVEL, some cobbles, well graded, low plasticity, brown
5			G					SC-SW		SAND & GRAVEL, some cobbles & clay, well graded, moderately lime cemented, low plasticity, light brown to brown
										Stopped backhoe at 7'6"

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-30-76

LOG OF TEST PIT NO. 134

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								CL	dry	SILTY CLAY, some sand, medium plasticity, light tan
			G					SC	dry	CLAYEY SAND, trace of gravel, predominantly fine to medium, low plasticity, reddish-tan
5			G					GC-GW		SAND, GRAVEL & COBBLES, some clay, well graded to 6", considerably lime cemented, low to medium plasticity, light tan
10										Stopped backhoe at 10'6"
15										

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

01184 A-118

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-29-76

LOG OF TEST PIT NO. 135

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0									dry	SAND, GRAVEL & COBBLES, some clay, well graded, angular to subangular gravel & cobbles, moderately cemented with pockets of calcite, low to medium plasticity, light gray
5				G				GW		
10										Stopped backhoe at 10'

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-29-76

LOG OF TEST PIT NO. 136

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0				G				SC	dry	CLAYEY SAND, some gravel, few cobbles, medium plasticity, reddish-brown
5			G					GP	dry	SAND, GRAVEL & COBBLES, little clay, poorly graded to 4"+, strongly lime cemented, medium plasticity, white
10										Stopped backhoe at 10'

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-29-76

LOG OF TEST PIT NO. 137

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0				G				CH	dry	SILTY CLAY, some sand, medium to high plasticity, reddish-brown
5				G				GC-GW	dry	SAND, GRAVEL & COBBLES, some clay, poorly graded, medium plasticity, white
10										Stopped backhoe at 10'6"
15										

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-19 & 20-76

LOG OF TEST BORING NO. 137

RIG TYPE CME-75

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0			S	22				CL-CH	slightly moist, firm	CLAY, medium to high plasticity, brown
5			S	30						
10			S	74				CL	dry, hard	SILTY CLAY, trace of sand, caliche cemented, medium plasticity, tan to white
15			S	70					hard	CLAYEY SAND & GRAVEL, fine to medium, angular to subrounded, medium plasticity, grayish-brown
20			S	50/2"				GC		
25			S	50/6"						
30			S	50/5¾"						CLAYEY SAND & GRAVEL, few cobbles, medium plasticity, reddish-brown note: occasional layer of clayey sand, nonplastic; also layers of calcareous cementation
35			S	50/3"						
40			S	50/3½"				GC		
45			S	50/4"						
50										

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

PROJECT Copper Flat Tailings Dam & Pond

LOG OF TEST BORING NO. 137

JOB NO. E76-1100 DATE 9-19 & 20-76

RIG TYPE CME-75

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
50				S	50/½" (no recovery)					
55				S	50/3¾"					
60				S	50/4½"			GC		
65				S	50/5"					
70										Auger refused at 68'

GROUND WATER

DEPTH	HOUR	DATE

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

LOG OF TEST PIT NO. 138

JOB NO. E76-1100 DATE 8-30-76

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0				G				SC	dry	CLAYEY SAND, some gravel, well graded, predominantly fine to medium, low plasticity, reddish-tan
5				G				GC	dry	SAND, GRAVEL & COBBLES, some clay, well graded to 6", moderately lime cemented, medium plasticity, light tan
10										Stopped backhoe at 9'8"

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

01190

A-124

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-31-76

LOG OF TEST PIT NO. 139

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								CL	dry	SANDY CLAY, some gravel, medium plasticity, brown
									dry	SAND, GRAVEL & COBBLES, some clay, well graded to 5"+, moderately to strongly lime cemented, medium plasticity, light tan
5				G				SC-SW		
10										Stopped backhoe at 9'9"

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX • TUCSON • ALBUQUERQUE • EL PASO

01191 A-125

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 9-21-76

LOG OF TEST BORING NO. 139

RIG TYPE CME-75

BORING TYPE 6½" Hollow Stem Auger

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0			S		18			SC & GC		CLAYEY SAND & GRAVEL, some cobbles, medium plasticity, light brown
5			S		93			SC & GC		CLAYEY SAND & GRAVEL, some cobbles, moderately lime cemented, low plasticity, tan
10			S		50/5"					CLAYEY SAND & GRAVEL, some cobbles, low to medium plasticity, light brown
15			S		50/2"			GC		
20			S		50/1¼" (no recovery)					
25			S		50/4"					CLAYEY SAND & GRAVEL, medium to high plasticity, reddish-brown
30			S		50/3"					
35			S		50/5"			GC		
40			S		50/4½"					
45			S		50/2½"					
50			S		50/0"					Auger refused at 49' Sampler refused at 49'

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

01192 A-125

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-29-76

LOG OF TEST PIT NO. 140

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0									dry	SAND, GRAVEL & COBBLES, some clay, poorly graded, stratified, weakly cemented, medium plasticity, light gray
5				G				SC-SW		
10										Stopped backhoe at 10'

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thinwalled Shelby tube

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

LOG OF TEST PIT NO. 141

JOB NO. E76-1100 DATE 8-29-76

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0			G					SC-SM	dry	CLAYEY SAND, considerable subangular gravel, poorly graded, stratified, moderately cemented at 2-7½', highly cemented at 7½-9', very gravelly at 5-7', low plasticity, light reddish-brown at 0-2', grayish-white at 2-9'
5			G							
10										Backhoe refused at 9'

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-29-76

LOG OF TEST PIT NO. 142

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0				G				SC	slightly moist	CLAYEY SAND & GRAVEL, poorly graded, stratified, moderately cemented at 2-3', medium to high plasticity, reddish-brown becoming light grayish-white
5				G				GC	dry	CLAYEY SAND, GRAVEL & COBBLES, poorly graded, highly stratified, moderately to strongly cemented, medium plasticity, light tan to white
10										Backhoe refused at 9'6"

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-30-76

LOG OF TEST PIT NO. 143

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0				G				GM-GW		SAND, GRAVEL & COBBLES, some silt, poorly graded to 5"+, moderately to strongly lime cemented, low plasticity, light tan
5										
10										Stopped backhoe at 9'

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-30-76

LOG OF TEST PIT NO. 144

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0								SC	dry	CLAYEY SAND, some gravel, low plasticity, light brown
			G					SM-SW	dry	SAND, GRAVEL & COBBLES, some silt, well graded, moderately to strongly lime cemented, nonplastic to low plasticity, light tan
5										
10										Backhoe refused at 4'6"

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-29-76

LOG OF TEST PIT NO. 145

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0									dry	SAND, GRAVEL & COBBLES, some clay, poorly graded, stratified, weakly cemented, medium plasticity, light gray
5			G					SM-SW		
10										Stopped backhoe at 10'

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

PROJECT Copper Flat Tailings Dam & Pond

JOB NO. E76-1100 DATE 8-2 -76

LOG OF TEST PIT NO. 146

RIG TYPE Ford 6500 Backhoe

BORING TYPE Test Pit

SURFACE ELEV.

DATUM

Depth in Feet	Continuous Penetration Resistance	Graphical Log	Sample	Sample Type	Blows per foot 140 lb. 30" free fall drop hammer	Dry Density Lbs. per cu. ft.	Moisture Content Percent of Dry Wt.	Unified Soil Classification	REMARKS	VISUAL CLASSIFICATION
0				G				SC	slightly moist to dry	CLAYEY SAND, considerable gravel & cobbles, considerable gravel below 5', well graded, subangular, stratified, medium plasticity, light reddish-brown
5				G						
				G				GC	dry	CLAYEY SAND, GRAVEL & COBBLES, poorly graded, stratified, moderately cemented, low plasticity, light gray to white
10										Stopped backhoe at 10'

GROUND WATER

DEPTH	HOUR	DATE
	none	

SAMPLE TYPE

A – Auger cuttings. B – Block sample
S – 2" O.D. 1.38" I.D. tube sample.
U – 3" O.D. 2.42" I.D. tube sample.
T – 3" O.D. thin-walled Shelby tube.

SERGENT, HAUSKINS & BECKWITH

CONSULTING SOIL AND FOUNDATION ENGINEERS
PHOENIX · TUCSON · ALBUQUERQUE · EL PASO

Appendix E

Copper Flat Geochemical Characterization Program

SRK Consulting
Engineers and Scientists

SRK Consulting (U.S.), Inc.
5250 Neil Road, Suite 300
Reno, Nevada
USA 89502

reno@srk.com
www.srk.com

Tel: 775.828.6800
Fax: 775.828.6820

Memorandum

To:	Steve Raugust, NMCC	**Date:**	February 7, 2011
	Cynthia Ardito, INTERA Incorporated	**From:**	Amy Prestia, Rob Bowell, Ruth Warrender
Subject:	Copper Flat Geochemical Characterization Program	**Project #:**	191000.03

This memorandum has been prepared by SRK Consulting (SRK) to provide New Mexico Copper Corporation (NMCC) with a description of the objectives, approach and test methods applied during the Copper Flat geochemical characterization study. This information is needed to address comments from NMED and MMD on the SAP that are relevant to the Abatement Plan. A summary of the preliminary results of the characterization program is also provided below. The preliminary results are described in greater detail in a separate memo submitted to NMCC in December 2010.

The primary purpose of the geochemical characterization program is to provide an understanding of the geochemical characteristics of materials specific to the Copper Flat deposit and define the potential for waste rock, pit walls and tailings material to generate acid or leach deleterious constituents. In order to accomplish the objectives of the study, samples representative of waste rock, pit walls and tailings material were collected and characterized following guidelines set forth in the *Bureau of Land Management Instruction Memorandum NV-2010-014, Nevada Bureau of Land Management Rock Characterization Resources and Water Analysis Guidance for Mining Activities (BLM, January 8, 2010).*

The following activities were completed as part of the geochemical characterization program:

- Review of site geology and identification of the primary material types for the project;
- Collection of drill core samples representative of waste rock;
- Collection of surface samples from existing waste rock dump, pit wall and tailings impoundment surfaces; and
- Static and kinetic laboratory testing of representative samples.

The two main considerations of this baseline geochemical characterization are:

- Acid generation due to oxidation of sulfide minerals, which can potentially lead to development of Acid Rock Drainage (ARD); and
- Potential for leaching of metals (e.g., copper) and salts (e.g., sulfate).

The processes of acid generation and metal leaching can operate independently, although the development of acidic conditions enhances the solubility of many metals.

At the time this memorandum was prepared, the geochemical testing program was not complete. Consequently, the conclusions concerning acid generation potential presented herein are preliminary and are based upon the results of the static testwork only. These conclusions may change pending the final characterization results upon completion of the kinetic humidity cell program. Upon completion of the data collection and evaluation, the final waste rock characterization results will be submitted in a comprehensive report.

1 Copper Flat Material Types

Waste rock is typically classified and tested according to material type and the number of samples selected for geochemical testing is based on the relative percentage of each material type predicted to be mined from the geologic block model. At this time a block model is not available for the Copper Flat project. Therefore, material types for the Copper Flat project were delineated from a review of data available from the recent exploration drilling program including the drillhole database, drill logs, assay data and bulk element geochemistry (limited to copper, molybdenum, gold silver).

The term 'rock type' refers to the basic lithological description of the rock, 'alteration type' refers to the type of mineral assemblage that has been formed as a result of hydrothermal alteration and 'oxidation state' refers to the degree of oxidation of the rock. The term 'material type' denotes a unique combination of rock type, alteration type and oxidation state.

The main rock types for the Copper Flat project include:

1. Alluvium/Overburden
2. Andesite
3. Quartz Monzonite Breccia
4. Quartz Monzonite
5. Dolerite

Alteration type is determined by visual identification of characteristic secondary mineralogy. The four alteration types for the Copper Flat deposit include:

1. Leach Cap
2. Propylitic
3. Argillic
4. Silicification

Oxidation can be determined from color and a visual estimate of sulfide mineral content and oxidation state can be broken into three categories including:

1. Oxide: material has been mostly oxidized and there are no remaining sulfide minerals.
2. Mixed: material has been partially oxidized and some sulfide minerals are still remaining.
3. Non-Oxide: sulfide minerals are not oxidized and there is no evidence of oxidation.

For the purposes of the material characterization and testing, SRK have identified a total of fourteen material types for the Copper Flat project as summarized in Table 1 below. Sample intervals in the exploration database were not coded with information on oxidation of the material. Therefore, the material type delineations are based on rock type and alteration only and do not account for oxidation state.

Table 1: Copper Flat Material Types

Material Type	Rock Type	Alteration
1	Andesite	Propylitic
2	Breccia	Argillic
3		Biotite
4		Leach cap
5		Potassic
6		Propylitic
7		Quartz
8	Dolerite	Propylitic
9	Quartz Monzonite	Argillic
10		Biotite
11		Leach cap
12		Potassic
13		Propylitic
14		Quartz sericite

2 Geochemistry Sample Selection

During the April 2010 site visit, two types of samples were collected including:

1. Drill hole samples collected at depth from recent exploration core holes.
2. Bulk surface grab samples from pit wall exposures, existing waste rock dumps and the tailings impoundment.

A description of the sample collection approach and methodology for each of the sample sources for the current investigation is provided in the following sections. The location of the recent exploration drill holes are shown in Figure 1 along with the recent geochemistry samples collected from the surface of the waste rock dumps, pit walls and tailings impoundment . Figure 1 also shows locations of samples collected in the late 1990s from pit walls and waste rock dumps in support of developing a Waste Rock Management Plan.

2.1 Drill Core Sample Selection

For this investigation, a total of fifty sample intervals were selected from six diamond core holes drilled within the footprint of the Copper Flat pit in 2009 and 2010. The sample intervals were selected to represent the range of waste rock material types that will be encountered in the Copper Flat pit and samples were classified according to rock type and alteration. Typically, drill hole intervals are reviewed in the context of the final pit boundaries in order to identify ore and waste zones within the proposed pit boundaries and ensure that the proposed sample suite is spatially representative (both vertically and horizontally) of waste rock. However, because a block model and pit outline is not available at this time for the Copper Flat project, sample intervals were selected based on the frequency of occurrence of each material within the drill holes, drill hole distribution and known geology of the deposit. For each sample interval, the coarse reject material was collected and sent to the laboratory for sample preparation and testing as described below.

2.2 Bulk Surface Samples

To augment the drill core sample set, twenty four samples were collected from the surface of the existing waste rock dumps and pit wall exposures for geochemical testing. Existing waste rock dumps and pit walls provide an opportunity to compare fresh rock samples to weathered rock samples of the same material types that have been exposed to oxygen and water for over 20 years. Samples of the main material types were collected based on the geology observed on the waste rock dumps and pit areas. In addition, four samples of tailings material were collected from the surface of the North tailings impoundment. These samples were submitted to McClelland Laboratories for testing as described below.

3 Geochemical Test Methods

The static and kinetic testing methods selected for this project were designed to address mineralogy, bulk geochemical characteristics, and the potential of the waste rock and pit walls to generate acid or release metals. “Static testing” is a general term describing those analytical methods applied to characterize acid generation and metal leaching characteristics of material at the time of testing and does not account for temporal changes that may occur in the material as chemical weathering proceeds. Static tests provide a balance of acid generating and acid consuming reactions at an end point and also may be used to determine the potential magnitude of leaching metals from a given material.

Static testing is distinguished from “kinetic tests”, which evaluate the rate of sulfide oxidation and metal release over time. Static testing provides a conservative approximation of acid generation and trace metal release potential, which is used to determine where more comprehensive kinetic testing is warranted. Based on the results of the static test work, materials that exhibit uncertain or highly variable geochemical behavior may require further characterization using kinetic test methods to determine the rates and character of longer-term leaching.

The static test methods identified for this project were selected to address total acid generating or neutralizing potential of the samples and concentration of constituents in leachates derived from the material. Static testing methodologies include the following:

- Multi-element analysis using four-acid digest and ICP analysis to determine total metal and metalloid content;

- Examination of material by optical microscopy and X-Ray diffraction (XRD) to assess mineralogy and to identify sulfide and carbonate minerals present within the material types;
- Acid Base Accounting (ABA) using the modified Sobek method (Memorandum No. 96-79) with sulfur speciation by hydrochloric acid and nitric acid extraction;
- Net Acid Generating (NAG) test that reports the final NAG pH and final NAG value after a two-stage hydrogen peroxide digest; and
- Nevada Meteoric Water Mobility Procedure (MWMP - ASTM E2242-02) and Profile II analysis of leachate.

These test methods and the criteria commonly used in the evaluation of the resulting data set are described in the following sections. Samples were submitted to McClelland Laboratories (MLI) in Sparks, Nevada for sample preparation and MWMP extraction. The MWMP extracts were then sent to WetLabs, a Nevada Certified laboratory, in Sparks, Nevada for chemical analysis. Splits of each sample were submitted to SVL Laboratories in Kellogg, Idaho for ABA and NAG testing and ALS Chemex in Reno, Nevada for multi-element analysis (respectively).

Upon completion of the static test work, a small sub-set of samples representing the most significant waste rock types were selected from the static test database for kinetic testing. The kinetic testing method selected for this project is the standard humidity cell test procedure (ASTM D-5744-96).

A sample matrix summarizing the number of samples collected for the main material types (as defined by rock type and alteration) is provided in Table 3. Typically, the number of samples selected for testing based on the relative percentage of each material type predicted to be mined according to the current resource and geologic block models. However, because a bock model and relative percentage of the different material types are not available at this time, the number of samples selected is based on our experience with this type of deposit as well as the occurrence of each material type on the waste rock dump surfaces and in the drill hole database.

Table 3: Copper Flat Sample Frequency

Lithology	Alteration	ABA/NAG/Multi-Element			MWMP			HCT		
		Drillcore	Grab	Total	Drillcore	Grab	Total	Drillcore	Grab	Total
Dolerite	Propylitic		2	2		2	2			0
Andesite	Propylitic		4	4		2	2		2	2
Quartz Monzonite	Argillic	6	2	8	3	2	5	2		2
	Biotite	3	1	4	1	1	2	1		1
	Leach Cap	5	4	9	2	2	4	1	1	2
	Potassic	6		6	3		3	2		2
	Propylitic	3		3	1		1	1		1
	Quartz Sericite	5	4	9	2	2	4	1	1	2
Quartz Monzonite Breccia	Argillic	5	1	6	2	1	3	1	1	2
	Biotite	6		6	2		2	2		2
	Leach Cap	2	1	3	1	1	2		1	1
	Potassic	2	1	3	2	1	3	1		1
	Propylitic	4		4	3		3	2		2
	Quartz	3		3	2		2	1		1
Tailings	-		4	4		2	2			0
Total		50	24	74	24	16	40	15	6	21

4 Preliminary Findings

Below are the preliminary conclusions that can be drawn from the geochemical data available to date. These conclusions are preliminary based on the results of the static testwork program and may change depending upon the HCT results, once available.

- Multi-element results show that all material types are characterized by elevated concentrations of silver, cadmium, copper, molybdenum, rhenium, sulfur, selenium, tellurium and tungsten. The elevation of these elements can be explained by the common association of these elements with porphyry copper deposits (Rose, Hawkes and Webb, 1979). The greatest levels of enrichment were observed in the Breccia-Leach Cap material.
- The BLM considers waste rock to be non-acid generating without kinetic testing if there is 300 percent excess neutralizing capacity (i.e., NP:AP> 3) and the NNP is greater than 20 eq. kg CaCO3/ton. Based on the results of the ABA testwork, the majority of the Copper Flat samples demonstrate an uncertain potential for acid generation with NP:AP values less than 3 and NNP values less than 20 eq. kg CaCO3/ton. However samples tend towards net acid generating rather than net neutralizing, with an average AP of 27.2 kg $CaCO_3$/ton and an average NP of 24 kg $CaCO_3$/ton. The exception to this is the propylitically altered material that generally exhibited non-acid forming (NAF) characteristics based on NPR values greater than 3.
- The results of the static testwork demonstrated that samples with sulfide sulfur content greater than 1% are most likely to be acid forming (AF) based on NNP values less than -20 eq. kg $CaCO_3$/ton (Figure 2). However, comparison of ABA and static NAG testwork results suggests that sulfide sulfur content is not the sole control on the acid generating potential of the Copper Flat materials.



Figure 2: Scatter plot of sulfide sulfur vs. NNP

- The results of the static NAG testing demonstrate that only the Breccia-Leach Cap and Quartz Monzonite-Quartz Sericite material types show high capacity PAF characteristics. Most other materials are unlikely to be problematic in terms of long-term acid generation based on the results of the NAG testwork.
- In general, metal mobility and metal leaching from the Copper Flat materials was found to be low, with constituents generally being released at concentrations below analytical detection limits in the MWMP leachates under circum-neutral to moderately alkaline pH (pH 6.9 – 8.8 s.u.) conditions.
- Samples that showed the highest levels of metal and acidity release were observed in grab samples collected from the waste rock dumps and pit walls (rather than core samples). Furthermore, the majority of the metal load from the grab samples was found to be made up of copper, suggesting that the elevated metal release was related to the flushing of soluble copper salts from the surface of the materials rather than the oxidation of sulfide minerals. This hypothesis is further supported by the poor correlation between metal release and the sulfide sulfur content of the materials.
- Historic tailings material collected from the North tailings dam has a residual sulfide (pyritic) sulfur content of approximately 0.75 percent by weight. However, the material was also found to have available buffering capacity, and NAG testwork confirms that this material is unlikely to be acid forming in the long-term. MWMP leach test results indicate that some copper leaching may occur from the tailings material at neutral pH.

5 Additional Work

Humidity cell testing has been initiated on 21 samples of representative waste rock and is currently in Week 1 of a multi-week kinetic testwork program (40+ weeks). The results of the humidity cell testing will be used to define and quantify rates of metal release from the material types and will be used as source terms for geochemical prediction modeling. This will utilize site-specific knowledge about hydrology, climate, hydrogeology, topography and engineering in order to allow prediction of future water quality in the pit lake and waste rock dump run-off.

A geologic block model is required to determine the relative percentages of each material type and determine if the number of samples selected for each material type is adequate for the characterization program. In addition, the sample intervals need to be reviewed in context of the anticipated pit boundary in order to determine if the current dataset is spatially representative of the deposit, or determine if additional sample collection is required. Future exploration drilling presents an opportunity to collect additional samples for geochemical testing from core holes to provide adequate spatial coverage of the deposit as the resource is expanded.

N

EXPLANATION

2010 Surface Samples · 2010 Drillcore Samples · 1997 Surface Samples

Feet

0 500 1,000

1 inch = 500 feet

IF THE ABOVE BAR DOES NOT SCALE 1 INCH, THE DRAWING SCALE IS ALTERED

SRK Consulting
Engineers and Scientists

DESIGN: JP	DRAWN: JQG	REVIEWED: -	
CHECKED: -	APPROVED: -	DATE: 2/4/2011	
FILE NAME: GIS_Database_Samples_AP_JQG_20110202			

COPPER FLAT

NEW MEXICO COPPER CORP

COPPER FLAT SAMPLES

DRAWING NO. FIGURE 1	SHEET 1 OF 1	REVISION NO. A
SRK JOB NO. 191000-03		

Path: H:\Copper_Flat\New Mexico Copper Corp\191000_03_Copper_Flat_Permitting\040_Drafting\20100901_GIS_Database\GIS_Database_Samples_AP_JQG_20110202.mxd

Appendix F

Copper Flat Static and Kinetic Geochemical Testwork

Alta Gold Co.

Copper Flat Mine

Geochemical Review of Waste Rock, Pit Lake Water Quality and Tailings

PREPARED BY:

SRK
Steffen Robertson and Kirsten
Consulting Engineers and Scientists

1755 E. Plumb Lane, Suite 241
Reno, Nevada 89502
(702) 786-3225
(702) 786-4435 (Fax)

November 1996
SRK Project No. 68609

TABLE OF CONTENTS

1 INTRODUCTION 1
2 PROJECT DESCRIPTION AND LOCAL GEOLOGY 1
3 SULFIDE OXIDATION, ACID GENERATION AND CONSUMPTION 4
3.1. Primary source of acidity 4
3.2. Secondary source of acidity 7
3.3. Acid Consumption or Neutralization 7
3.4. Adsorption and Coprecipitation 10
4 GROUND WATER CHEMISTRY 13
5 WASTE ROCK GEOCHEMISTRY 17
5.1. Bulk geochemistry of waste rock 17
5.2. Static test results 17
5.3. Kinetic test results 20
5.4. Water Quality and Environmental Implications 20
6 TAILINGS GEOCHEMISTRY 28
6.1. Static test results 28
6.2. Kinetic test results 29
6.3. Water quality and Environmental implications 29
7 PIT LAKE CHEMISTRY 30
7.1. Surface Water Chemistry 30
7.2. Geochemical Model of Pit Lake Chemistry 31
7.2.1. Model Description 31
7.2.1.1. Calibration Procedure 32
7.2.1.2. Calibration Results 40
7.2.2. Water-Quality Predictions 42
7.3. Future Trends 48
8 RECOMMENDATIONS 49
9 CONCLUSIONS 49
10 REFERENCES 50

TABLES

Table 3.1: A comparison of the Resistivities of Various Minerals (data from Thornber 1992) 4

Table 3.2: Oxidation Reactions of Iron Sulfide and Sulfate Minerals Generating Acidity (after Kleinnman and Pacelli, 1991; Thornber, 1992) 6

Table 3.3: Acid Volatile Salts 9

Table 3.4: Principal pH-buffering phases for ARD observed in this study 10

Table 3.5: pH_{pzc} for Common Minerals Associated with Mine Ochres (Parfait, 1978) 11

Table 4.1: Summary of Ground Water Chemistry of Copper Flat Area 13

Table 4.2: Saturation Indices for selected minerals in ground water wells 14

Table 5.1: Static test results for Waste Rock 19

Table 7.1: Pit Lake Water Quality (all values in mg/l except where stated otherwise) 31

Table 7.2: 6-Year Water Budget 34

Table 7.3: Solution Chemistry 35

Table 7.4: Simulated Solution Chemistry after 12 Years Scenario 2 - Unbuffered 36

Table 7.5: Simulated Solution Chemistry after 12 Years Scenario 2 - Buffered by $Fe(OH)_3$ 37

Table 7.6: Simulated Solution Chemistry after 12 Years Scenario 2 - Buffered by Calcite 38

Table 7.7: Simulated Solution Chemistry after 12 Scenario 3 - Unbuffered 39

Table 7.8: Average Pit Water Solution Chemistry Sample NLP 3m 41

Table 7.9: Local Pit Water Solution Chemistry - Pit Shore Average 41

Table 7.10: Revised Solution Chemistry for Type 1 Inflow Ground Water 44

Table 7.11: Simulated Solution Chemistry after 120 Years Post Closure, Scenario 1 - Greyback Wash Diversion In Place 45

Table 7.12: Simulated Solution Chemistry after 120 Years Post Closure, Scenario 2 - Greyback Wash Diversion Removed 46

FIGURES

Figure 2.1 Site location of the Copper Flat Project 1
Figure 2.2 Deposit geology of the Copper Flat Project 2
Figure 3.1 Eh-pH Diagram for the Fe-S-C-O-H at 298°K 8
Figure 4.1 Piper diagram of ground and surface waters from the Copper Flat area 15
Figure 4.2 Younger diagram of ground and surface waters from the Copper Flat area 16
Figure 5.1 Paste pH Map of the Pit Lake and Wall Wock 18
Figure 5.2 Humidity Column Design 20
Figure 5.3 Kinetic Test Results - pH vs. Time 21
Figure 5.4 Kinetic Test Results - Redox Potential vs. Time 21
Figure 5.5 Kinetic Test Results - Acidity vs. Time 22
Figure 5.6 Kinetic Test Results - Alkalinity vs. Time 22
Figure 5.7 Kinetic Test Results - Sulfate vs. Time 23
Figure 5.8 Kinetic Test Results - Copper vs. Time 23
Figure 5.9 Kinetic Test Results - Iron vs. Time 24
Figure 5.10 Kinetic Test Results - Conductivity vs. Time 24
Figure 5.11 Kinetic Test Results - Cumulative Acidity vs. Time 25
Figure 5.12 Kinetic Test Results - Cumulative Sulfate vs. Time 25
Figure 5.13 Kinetic Test Results - Cumulative Iron vs. Time 26
Figure 5.14 Kinetic Test Results - Cumulative Copper vs. Time 26
Figure 7.1 Copper Flat Pit Water Chemistry Estimation (25% ARD, Greyback Diverted) 47

1 INTRODUCTION

A review of the pit lake chemistry and geochemical test work and observation data of the waste rock piles and tailings impoundment at the Copper Flat project, New Mexico, is presented herein. The review is based upon previous laboratory data collected by SRK (US), Inc., a geochemical model devised by SRK (US), Inc. and field data collected during a site visit in November 1996.

Mitigation options for water quality are also discussed and recommendations made for future areas of focus and long term monitoring.

2 PROJECT DESCRIPTION AND LOCAL GEOLOGY

The Copper Flat redevelopment project is located approximately 23 miles southwest of Truth or Consequences and 5 miles northeast of Hillsboro, Sierra County, New Mexico (Figure 2.1). Alta Gold proposes to rebuild the mine site, as it existed in 1986 when owned by Quintana Minerals. Mining in the area began in 1877 with primarily alluvial gold operations with the main period of copper extraction from 1911 to 1931 (Harley, 1934).



Figure 2.1 Project Location

During the 1950's and mid-1980's, attempts were made along the Sternberg lode to extract copper by *in-situ* acid leaching. The current plans propose to produce a sulfide concentrate by flotation with the operational life expectancy of approximately 10-12 years.

The Copper Flat deposit is located within a Cretaceous age caldera which intruded into the Paleozoic marine sediments and Precambrian basement rocks exposed in the upthrust Black Range and Animas Hills west of the project boundary (Figure 2.2). To the east the Rio Grande Rift forms a prominent geographical feature. The rift created a graben which has subsequently been infilled by a 700 m thick layered gravel alluvium of the Santa Fe Group.

The oldest sedimentary unit exposed in the immediate area is the Ordovician age Montoya Limestone Group which outcrops in the southeast of the concession area. Overlying the group is the Fusselman Dolomite, a massive 70 m thick dolomite-limestone unit of Silurian age. Unconformably resting on the dolomite sequence is the Percha shale unit which comprises 50-90 m thick unit of argillceous sedimentary rocks.

Magmatic activity in the Copper Flat area began with andesitic volcanic activity, and included the placement of quartz monzonite pluton stocks and latite dykes, and culminated in the hydrothermal activity which formed the copper deposit.



COPPER FLAT PROJECT

FIGURE 2.2
DEPOSIT GEOLOGY

DATE: OCT/19/1995 12-476\401\GEO-DEP2

The andesite is a fine grained porphyritic rock with phenocrysts of plagioclase (andesine) and Ca-Mg-Fe amphibole in a groundmass of plagioclase and orthoclase. The andesite is massive with occasional agglomerates and is coarse grained in the vicinity of the Copper Flat pit. Magnetite and apatite have been observed as common accessories in the andesite.

The mineralization at Copper Flat is similar to copper porphyry style deposits with the exceptions that zonation is relatively poor and no appreciable supergene enrichment zone is observed. Both features are common in copper porphyrys elsewhere in the world. Sulfide content in the disseminated mineralized lodes in the monzonite stock varies up to 5%, with the majority being pyrite. Radiating from the stock are mineralized veins with the highest Cu grades developed in brecciated monzonite. The leached oxide cap is relatively thin (5-15 m) and sulfides are relatively unaltered in the deposit. The major sulfides are pyrite and chalcopyrite with accessory molybdenite and bornite. Trace amounts of enargite, acanthite, tetrahedrite, sphalerite and galena also occur. Gangue mineralogy includes quartz, feldspar, muscovite, biotite, apatite, calcite and fluorite. The deposit also contains appreciable gold, presumably held as a trace element in primary sulfides.

Whilst being similar to classic Copper Porphyry (Dunn, 1992; Einaudi, 1982; Titley, 1982) the deposit at Copper Flat has no appreciable supergene enrichment and is poorly zoned, but has a well developed skarn halo. The lack of supergene enrichment suggests that sulfides in the deposit are not very reactive or that environmental conditions existing at the site since formation do not significantly effect sulfide stability. The low humidity in the area has probably slowed down any potential water-rock interactions, but it is the highly crystalline nature of the sulfides which is the dominant control over sulfide stability in the deposit. By contrast, in many copper porphyrys, such as Mamut in Malaysia or Butte in Montana, sulfide grain size is smaller, total sulfide concentrations are higher, and sulfide connection is better than at Copper Flat, so electrical conductivity is maintained through sulfide material over a greater distance, increasing the distance between cathode and anode causing more intense weathering (see Section 3).

The type of zoned alteration halo and degree to which they are developed in porphyry deposits is a reflection of host rock. Here, Ca-rich andesite and basalt are dominant as opposed to more silica-rich host rocks (such as dacite) observed at other porphyry locations. The skarn reflects the wide availability of Ca and Mg in the tertiary extrusives and the high volatile CO_2 content of the original deposit. This is beneficial as the skarn contains a high proportion of acid consuming minerals which assist in maintaining an alkaline pH.

3 SULFIDE OXIDATION, ACID GENERATION AND CONSUMPTION

3.1. Primary source of acidity

The mechanisms of sulfide oxidation involve the transfer of electrons. Because most sulfide minerals are electrical conductors in the semiconductor to metallic range (Table 3.1), they can be considered as electrochemical "corrosion" cells similar to galvanic corrosion of metal alloys (Bailey & Peters, 1976; Thornber, 1975, 1983, 1992; Sato, 1992). Sulfides may be thought of as "geo-batteries" with the emphasis on "self-corrosion" by sulfide ores.

Table 3.1: A comparison of the Resistivities of Various Minerals (data from Thornber 1992)

Mineral/Rock	Log_{10} resistivity in ohm/m	Conducting nature
Metals	-8 to -6	metallic
Graphite, C	-7.5 to -5	metallic
Arsenopyrite FeAsS	-6 to -3	semi-conductor
Chalcocite Cu_2S	-4.2 to -3.9	semi-conductor
Chalcopyrite $CuFeS_2$	-4.1 to -0.3	semi-conductor
Covellite CuS	-6.8 to -4.1	semi-conductor
Galena PbS	-5.8 to -0.2	semi-conductor
Hematite Fe_2O_3	>10	insulator
Manganite MnOOH	-0.9 to -0.1	semi-conductor
Pyrite FeS_2	-5.6 to 0.5	semi-conductor
Pyrolusite MnO_2	-3.1 to 1.2	semi-conductor
Sphalerite ZnS	-2.7 to 4.2	insulator
Realgar As_2S_3	-5 to -3.2	semi-conductor
Orpiment As_4S_4	-3 to 0.2	semi-conductor/insulator
Stibnite Sb_2S_3	-2 to 2.1	insulator
Sulfide-massive	-6.6 to -1.7	semi-conductor
Sulfide-massive, weathered	-3.1 to 0.4	semi-conductor/insulator
Sulfide-matrix supported	-4.4 to 0.8	semi-conductor/insulator
Sulfide-disseminated	-0.9 to 2.9	insulator

These electrochemical reactions are a combination of a reduction reaction at a cathode and an oxidation reaction at the anode. The cathodic reduction of dissolved oxygen can be generalized as:

$$O_2 + 2H_2O + 4e^- \rightarrow 4OH^- \quad (1)$$

combined with sulfide oxidation:

$$MS + 4H_2O \rightarrow M^{2+} + SO_4^{2-} + 8H^+ - 8e^- \quad (2)$$

where M is a divalent metal

to give the total reaction:

$$MS + 2O_2 \rightarrow M^{2+} + SO_4^{2-} \quad (3)$$

Galvanic "corrosion" has been confirmed in numerous experimental studies (Bailey & Peters, 1976; Thornber, 1975; 1983; Lowson, 1982; McKibben & Barnes, 1986)

Additionally hydrogen ions are released in the process of metal hydrolysis:

$$M^{2+} + H_2O \rightarrow M(OH)^+ + H^+ \quad (4)$$

and

$$M(OH)^+ + H_2O \rightarrow M(OH)_2 + H^+ \quad (5)$$

When iron is the cation, then production of acidic solutions is most pronounced (Table 3.2). However, it should be noted that not all sulfides generate acidity on oxidation(Thornber, 1992). Indeed sulfides of the type M_2S such as Arsenopyrite and Chalcocite actually consume H+ on oxidation:

$$2Cu_2S + 6H_2O + 5O_2 = 4Cu^{2+} + 2SO_4^{2-} + 2H^+ + 8OH^-$$

Dissolution or oxidation of pyrite initially produces Fe^{2+}, which is immediately oxidized to Fe^{3+} which is either precipitated as an oxyhydroxide or reduced by pyrite generating more Fe^{2+} and increased acidity. The rate at which these reactions occur are first order (McKibben & Barnes, 1986) and fairly rapid. For example at pH 1, $3m^2$ of pyrite per litre of solution will reduce 50% of the initial ferric concentration in approximately 50 minutes.

Oxidation of ferrous iron by oxygen has been shown to be a function of pH and can be defined by the reaction rate:

$$-d[Fe^{2+}] = k' [Fe^{2+}] [O_2]$$

where $k=10^{-7}$ $atm^{-1}min^{-1}$ at 298 K.

The rate of sulfide oxidation can be controlled by the rate at which oxygen is supplied and reduced at the cathode-solution interface. The separation of the cathodic oxygen-consuming, alkali-producing reaction from the anodic, oxidizing, dissolution, acid-producing reaction will have a major control on the mineralogy of the resulting assemblage. The greater the distance between cathode and anode, the more extensive the conducting area and consequently the greater the potential for sulfide oxidation. Anodic reactions can occur deep within cracks, fissures and along grain boundaries where solutions can penetrate without the necessity for substantial dissolved oxygen (Lowson, 1982; Thornber, 1975; 1992).

The cathodic oxygen reduction reaction will be favoured on the more resistant sulfide grains, such as pyrite, chalcocite and covellite or on various gangue minerals. These resistant sulfide grains will become isolated with continued oxidation and form separate cells which will oxidize more slowly. Where the cathodic reaction dominates, water pH increases and released metals will react to form metal salts. A general sequence for pyrite oxidation, as an example of sulfide oxidation, is given in Table 3.2

Table 3.2: Oxidation Reactions of Iron Sulfide and Sulfate Minerals Generating Acidity (after Kleinnman and Pacelli, 1991; Thornber, 1992)

Reaction 1	
	a) $FeS_2 + 3½O_2 + H_2O = Fe^{2+} + 2SO_4^{2-} + 2H^+$
	b) $2FeS_2 + 7O_2 + 2H_2O = 2Fe(SO_4) + 2H_2(SO_4)$
Reaction 2	
	a) $Fe^{2+} + 2½ H_2O + ¼O_2 = Fe(OH)_3 + 2H^+$
	b) $2Fe(SO_4) + H_2(SO_4) + ½O_2 = Fe_2(SO_4)_3 + H_2O$
Reaction 3	
	$Fe^{2+} + ½O_2 + H^+ = Fe^{3+} + ½H_2O$
Reaction 4	
	$FeS_2 + 14Fe^{3+} + 8H_2O = 15Fe^{2+} + 2SO_4^{2-} + 16H^+$
Stage 1	
	Reaction 1: proceeds abiotically and by bacterial oxidation (reaction b more common with bacterial oxidation)
	Reaction 2: proceeds abiotically, slows as pH falls (reaction b more common with bacterial oxidation)
	pH approximately 4.5 or higher, high sulphate, low Fe, low pH
Stage 2	
	Reaction 1: proceeds abiotically and by bacterial oxidation (reaction b more common with bacterial oxidation)
	Reaction 2: proceeds at rate determined primarily by activity of bacteria such as *T.ferrooxidans*
	pH approximately 2.5-4.5, high sulphate, Fe and low pH. Low Fe^{3+}/Fe^{2+} ratio
Stage 3	
	Reaction 3: proceeds at rate determined by activity of *T.ferrooxidans*
	Reaction 4: proceeds at rate determined by rate of reaction 3
	pH generally below 2.5, high sulphate, total Fe and low pH. High Fe^{3+}/Fe^{2+} ratio

Consequently, massive sulfide ores are generally good conductors; however, those which contain major amounts of sphalerite and/or significant pyrite are much poorer as both minerals have moderate resistivities (Thornber, 1992). With increased acidity most metals such as Fe, Cu or Al will become more soluble.

Where sulfides are more dispersed, such as in the Copper Flat ores, the distance between oxidizing sulfides is greater and conduction is reduced so the extent of oxidation is not as great. Each sulfide grain weathers as an isolated cell and the only influence that one sulfide grain can have on another is via aqueous solution. Access by dissolved oxygen will determine leaching, and sulfide composition will influence pH, water chemistry, reaction rate, and secondary mineralogy. Generally, leaching is greatest near the surface.

3.2. Secondary source of acidity

During weathering, sulfides produce a range of sulfates, hydroxides and oxides which are stable in oxidizing acidic pH, for example the formation of jarosite (Figure 3.1).

A good example is the formation of römerite from the oxidation of pyrite:

$$3FeS_2 + 11O_2 + 16H_2O = Fe^{2+}Fe^{3+}{}_2(SO_4)_4.14H_2O + 2SO_4^{2-} + 4H^+$$

For each mole of FeS_2 oxidized, only a third of the available sulfate and "one-eighth" of the available hydrogen is released. The rest is stored as unhydrolized, partly oxidized iron mineral. These sulfate minerals are termed **Acid Volatile Sulfates**. The most common of these salts are given in Table 3.3. Not all release hydrogen and sulfate on dissolution, but all release sulfate anions.

These minerals are highly soluble, therefore, they represent an instantaneous source of acidic sulfate-rich water upon dissolution and hydrolysis, for example the dissolution of römerite:

$$Fe^{2+}Fe^{3+}{}_2(SO_4)_4 \cdot 14H_2O = 2FeO.OH + Fe^{2+} + 4SO_4^{2-} + 6H^+ + 9H_2O$$

Subsequent oxidation of ferrous iron and hydrolysis of ferric iron at pH > 2 provides an additional source of acidity (Table 3.2). Hence, iron-sulfate hydrate minerals are important as both sinks and sources of acidity, sulfate, and possibly metal ions on precipitation and rapid release on exposure to moisture (Cravotta, 1994).

Optical microscopy of field samples suggests that precipitates collected in November 1996 consist of chalcanthite, coqumibite, gypsum, aragonite, jarosite, alunite andbrochanthite. Langite and melanterite are present as pit wall precipitates close to the current pit lake level. Azurite, malachite, pseudomalachite, beaverite, legrandite, atacamite and turquoise are also present in the south wall of the pit and on the higher benches to the east. Within an andesite intrusive in the east wall vesicles associated with the contact margin of the dyke with the monzonite are infilled with azurite, malachite, scorodite, libethenite, atacamite, schlumbergite and cuprite along with zeolites, calcite and quartz. The results of X-Ray diffraction analysis are forthcoming to confirm the mineralogy.

3.3. Acid Consumption or Neutralization

Acid-neutralization reactions results from mineral buffering of H^+ in drainage. This buffering is frequently accompanied by the precipitation of metal-hydroxides, hydroxy-sulfates and oxyhydroxide minerals. These reactions can reduce the rate of acid generation by forming an inhibitory surface coating to the reactive sulfides. The major buffering minerals for ARD are shown in Table 3.4

The major mineral phase which consumes acidity is calcite by the reaction:

$$CaCO_3 + H_2SO_4 + H_2O = CaSO_4.\ 2H_2O + CO_2$$

Carbonate minerals possess varying degrees of acid neutralization. In the case of siderite and to a lesser extent ankerite, the reason for the limited neutralizing capacity is that ferrous iron in these minerals is an additional source of acidity due to the strong hydrolysis of ferrous iron in solution .

C:\RB\857RB11.CDR



Eh-pH DIAGRAM FOR Fe- C -S - H O - O SYSTEM
(Fe,S $=10^{-6}$M and $P_{CO} = 10^{-2}$)

DATE: 02/12/96	PROJ. No. U857	COPPER FLATS	
SRK	**Eh-pH DIAGRAM FOR THE Fe-S-C-O-H AT 298 K**		Figure 3.1

Table 3.3: Acid Volatile Salts

Selected soluble sulfates		Selected less soluble sulfates	
	Iron minerals		
copiapite	$Fe^{2+}Fe_4^{3+}(SO_4)_6(OH)_2.20H_2O$	amerantite	$Fe^{3+}(SO_4)OH.3H_2O$
coquimbite	$Fe_2^{3+}(SO_4)_3.9H_2O$	fibroferrite	$Fe^{3+}(SO_4)OH.5H_2O$
ferricopiapite	$Fe_{2/3}^{2+}Fe_4^{3+}(SO_4)_6(OH)_2.20H_2O$		
melanterite	$Fe^{2+}SO_4.7H_2O$	schwertmannite	$Fe_8O_8(SO_4)(OH)_6$
ferrohexahydrite	$Fe^{2+}SO_4.5H_2O$		
paracoquimbite	$Fe_2^{3+}(SO_4)_3.9H_2O$		
rhomboclase	$HFe(SO_4)_2.4H_2O$		
rozenite	$Fe^{2+}SO_4.4H_2O$		
siderotil	$Fe^{2+}SO_4.6H_2O$		
szomolnokite	$Fe^{2+}SO_4.H_2O$		
	Other transition metals		
Alunogen	$Al_2(SO_4)_3.17H_2O$	Anglesite	$PbSO_4$
Bianchite	$ZnSO_4.6H_2O$	Antlerite	$Cu_3(SO_4)(OH)_4$
Chalcanthite	$CuSO_4.5H_2O$	Basalumite	$Al(SO_4)(OH)_{10}.H_2O$
Goslarite	$ZnSO_4.7H_2O$	Brochantite	$Cu_4(SO_4)(OH)_6$
Gunningite	$ZnSO_4.H_2O$	Jurbanite	$Al(SO_4)(OH).5H_2O$
Retgesite .$2H_2O$	$NiSO_4.6H_2O$	Langite	$Cu_4(SO_4)(OH)_6$

Alunite-Jarosite Group

Very common group of Acid Mine Drainage & Gossan minerals. Can incorporate many trace metals and oxyanions.

$A^{2+}Fe_4^{3+}(SO_4)_6(OH)_2.20H_2O$ *or* $B_{2/3}^{3+}Fe_4^{3+}(SO_4)_6(OH)_2.20H_2O$

A= Ca, Cu, Fe, Mn, Mg, Zn, Co, Ni

B= Al, Fe, Cr.

Sulfate group can be partially replaced by selenite, phosphate, arsenate oxyanions.

Some examples:

argentojarosite	(K,Ag) $Fe_3^{3+}(SO_4)_2(OH)_6$
alunite	K $Al_3^{3+}(SO_4)_2(OH)_6$
jarosite	K $Fe_3^{3+}(SO_4)_2(OH)_6$
plumbojarosite	(Pb,K) $Fe_3^{3+}(SO_4)_2(OH)_6$
osarizawaite-beaverite	$(Pb,Cu)_2(Al,Fe^{3+})_2$ $(SO_4)_2(OH)_6$

[1] Or equivalent amorphous phase

[2] Acid consuming potential is given as being the weight of the mineral required to have the same neutralizing capacity as 100 g of calcite.

Table 3.4: Principal pH-buffering phases for ARD observed in this study

Mineral	Formula	Acid Consumption Potential[2]
Carbonates		
Calcite	$CaCO_3$	100
Dolomite	$CaMg(CO_3)_2$	92
Siderite	$FeCO_3$	120
Ankerite	$Ca(Fe,Mg)(CO_3)_2$	108
Hydroxides		
Gibbsite[1]	$Al(OH)_3$	26
Goethite	FeO□OH	89
Ferrihydrite[1]	$Fe(OH)_3$	96
Manganite	MnOOH	88
Aluminosilicates		
Chlorite	$(Mg,Al,Fe)_6(Si,Al)_4O_{10}(OH)_8$	124
Muscovite	$KAl_2(Si_3Al)O_{10}(OH,F)_2$	154
Alkali Feldspars	$(K,Na)AlSi_3O_8$	169
Plagioclase Feldspars	$NaAlSi_3O_8$-$CaAl_2Si_2O_8$	137
Pyroxene group		120-155
Amphibole group		110-150
Clay mineral groups		105->200

The order of carbonate neutralizing capacity is dolomite>calcite>ankerite> siderite. This order of reactivity is partly controlled by equilibrium mass-action constraints and partly by kinetic limitations. In the case of calcite, dissolution is rapid (Garrels & Christ, 1965; Appelo & Postma, 1993). Generally, the rate of dissolution is sufficient to maintain water pH in the range 7.5-7.8. Dolomite dissolution is slower, and in the case of ankerite and siderite disequilibrium is common.

If all available calcite is removed then pH will decrease to a dolomite buffer range of pH 6.9-7.9. When dolomite is depleted pH will fall to the siderite buffer regime of pH 4.8-6.3. In the carbonate buffer zones the precipitation of metal hydroxides is promoted with dissolved Fe derived from sulfides, Mn and Al from wallrock oxides and silicates. As acid generation continues and carbonate minerals are depleted, pH will fall until the hydroxide buffer zones are reached, for $Al(OH)_3$ this is the pH range 4-4.3 and for $Fe(OH)_3$ the pH range 2-4.

Under very low pH conditions, the dissolution of aluminosilicates can be an important acid neutralization mechanism. Dissolution is slow and also involve the additional contribution of dissolved secondary minerals as well.

3.4. Adsorption and Coprecipitation

This is the process of element binding at the mineral solution interface and like solubility is pH dependent. For example, the adsorption of arsenic species by goethite. Many oxide surfaces change from positive at low pH (thus attracting anions) to negative at high pH (attracting cations). This occurs through adsorption at the surface of hydroxyl groups with increasing pH. The pH at

which the change occurs is termed the *point of zero charge* or pH_{pzc} (Table 3.5). This is a measure of a surface's ability to sorb ions from solution (Parfait, 1978; Bowell, 1994). Mine drainage chemistry and particularly, the level of As and heavy metals has been shown to be influenced by adsorption onto precipitated iron oxyhydroxides or "ochres" (Bowell et al., 1996).

Table 3.5: pH_{pzc} for Common Minerals Associated with Mine Ochres (Parfait, 1978)

Mineral	pH_{pzc}
Quartz	1.8-3.5
Kaolinite/Illite	3.3-6
Smectite	2.5-6
Hematite	6.5-8.6
Goethite	6.5-7.3
Ferrihydrite	6.9
Jarosite	6.7-8

The presence of other adsorbents, such as humic substances, will also affect adsorption potential by competing for available sites on the mineral surface or for dissolved species. Precipitation of insoluble salts can lead to reduced solubility due to co-precipitation. For example, anhydrite when Ca is added to a sulfate-rich solution, especially at high pH. Co-precipitation is influenced by solubility and adsorption properties indicating a similar bonding mechanism. An important control on the diversity of the precipitated mineral assemblage is pH For example, in the oxidation of sulfides at low pH, only Fe oxides and oxyhydroxides are formed while at higher pH other salts such as covellite, smithsonite and malachite are also precipitated.

Only a small proportion of the base metals present in low pH waters will be retained, sorbed onto the Fe hydroxide; however, elements such as As, Sb, W and Mo will be retained, adsorbed as oxyanions. During sulfide oxidation there is a tendency for Fe and base metals to diffuse towards the surface of the gangue minerals and precipitate by hydrolysis reactions, lowering pH and continuing the leaching process. These reactions occur some distance from the leaching surface to form Fe oxyhydroxide crusts. Precipitated Fe oxyhydroxides can adsorb substantial concentrations of liberated metals from the mine waters depending on solution pH. Many oxide surfaces including those of goethite, are positively charged at low pH and become negatively charged at higher pH due to the increased binding of hydroxyl groups. Consequently, at low pH, oxyanions such arsenate will be adsorbed while with a pH increase metal ions will be adsorbed when the mineral surface charge is negative. The point at which this change occurs, i.e. the point at which the surface has a net zero charge can be used as a measure of the adsorption potential at another pH. The presence of smectite ($Na_3(Al,Mg)_2Si_4O_{10}(OH)_2 \square nH_2O$) and kaolinite ($2[Al_2Si_2O_5(OH)_4]$) in the flocculated material could explain the higher retention of base metals, even in very acidic waters, than has been recorded in ochres from other mine sites. Both of these clay minerals can have a pH_{zpc} (zero point charge) as low as 2.2 and up to 5. Consequently, they could provide negatively charged Helmholtz layers at their surfaces, leading to favourable conditions for sorption of positively charged base

metals at pHs as low as 2.2. The surface properties of the different minerals will also be affected by other influences such as the presence of organic acids which can reduce metal adsorption by competitive adsorption and by complexation (Tipping and Cooke, 1990; Bowell, 1994).

Although pH is a major control, the structure of the precipitated ochres may also influence element adsorption as it is also variable with Eh-pH changes. Mineral precipitates formed in highly acidic waters tend to be more crystalline and as a result have a lower surface area, and consequently a lower adsorptive capacity. Conversely, mineral precipitates from lower acidity waters are poorly crystalline and as such will have a larger surface area and greater capacity to retain ions at mineral surfaces.

Fe^{2+} and SO_4^{2-} are most likely released through bacterially catalysed decomposition of iron sulfides. A variety of intermediate phases, such as melanterite, can be formed depending on conditions being stabilized during humid or arid conditions. For example, where evaporation occurs ferric sulfates have been shown to precipitate; and these intermediate phases, if accumulated over time, may form their own source of iron, sulfate and acidity if remobilised[16]. On oxidation and hydrolysis, or ferrolysis, ferric minerals are formed. If conditions involve low-pH, high dissolved sulfate and sustained bacterial activity jarosite, ferricopiapite, schwertmannite or coquimite may be formed. With jarosite precipitation controlled by the level of Na, K, and possibly sulfate as well as pH. Mildly acidic solutions may form ferrihydrite or lepidocrocite while higher alkalinity levels will influence the precipitation of goethite. The ubiquitous presence of goethite in mine ochres would suggest that most phases are only transient with respect to goethite. The mineral speciation of the produced ochres is important in influencing the retention of metals from drainage. The presence of clay minerals in the ochres may accelerate the oxidation of ferrous iron and production of ochres by polymerization of ferric oxyhydroxides.

The mineral speciation of precipitated ochres will influence the surface chemistry of the ochres, and the ability of the ochre to accumulate available metals or oxyanions. Surface reactions may also influence mineralogy with some transient phases stabilized by complexing outside the predicted environment from the above model. For example, the transformation of ferrihydrite may be temporarily delayed by stabilization through adsorption of SiO_4 or organic compounds. The pH of drainage waters will influence the prevailing surface chemistry of the ochres depending on the pH_{pzc} of constituent minerals in the ochres.

The presence of clays like montmorillonite would greatly increase the potential for adsorption of cations at acidic pHs due to the low pH_{pzc} (Table 3.4). However, mineralogy is not the only consideration. The immobilization of metals released from associated sulfides through gangue neutralization, and their availability and speciation will influence the extent to which they are attracted to the surface of the ochres. Below pH_{pzc}, mineral surfaces will be slightly positively charged and, therefore, attract oxyanion species; above this point, they will become more negative in character and, therefore, more likely to attract cations.

4 GROUND WATER CHEMISTRY

Ground water chemistry from the Copper Flat project area is shown in Table 4.1 for water around the pit and from the ground water monitor wells shown in Figure 2.1.

The data indicate that all ground water in the vicinity of the project area is alkaline (pH> 7) with alkalinity greater than 100 mg/l. The data plot on a Piper diagram as Mg-Ca-HCO3 waters (Figure 4.1) and on a Younger diagram (Younger, 1995) as sulfate-rich to sulfate-poor alkaline waters (Figure 4.2). The dominant Ca-Mg-bicarbonate signature of ground water is most likely a reflection of rock-water interactions with the regional host rocks - andesite, dolomite and limestone. (Hem, 1985; Postma & Appelo, 1993). The elevated F levels of 0.5-3 mg/l is characteristic of ground water leaching of calc-alkaline magmatic rocks (Bowell et al., 1996).

Table 4.1: Summary of Ground Water Chemistry of Copper Flat Area

Parameter	Range (in mg/l except where stated otherwise)
pH	7.25-8.11
Conductivity, µm/cm	293-2026
Bicarbonate	149-279
Nitrate	<1-5
Sulfate	12-720
Fluoride	0.36-1.4
Chloride	12-190
Total Dissolved Solid	190-1570
Calcium	48-270
Copper	<0.025-0.03
Iron	<0.05-3.7
Magnesium	1-56
Manganese	<0.03-4
Molybdenum	<0.05
Potassium	1-10
Sodium	28-460

Despite the presence of mineralized lithologies around the pit, no evidence of metal leaching or of acid generation is reflected in ground water chemistry, up or down gradient of the pit lake (Table 4.1). This observation would support the hydrogeological model proposed for the site which indicates the pit acts as a sump below the water table with no leakage into the ground water. The sulfate levels observed in ground waters is probably a combination of two factors:

- Some oxidation of sulfide to sulfate
- Conservative behaviour of sulfate where gypsum is undersaturated.

For the ground water chemistry reported in Table 4.1, the saturation indices of calcite, gypsum and anhydrite has been calculated (Table 4.2).

The minerals most likely to form can be predicted from their Saturation Indices. Saturation Indices can be used to predict mineral phases likely to precipitate with respect to water chemistry (SI>0). Indices which are low negative values are likely to precipitate if one or more of the constituents is increased slightly. Values which are large negative SIs (<-3) are unlikely to form and if present are most probably dissolving. From the above information it can be observed that the alkaline, Ca-rich nature of ground water is reflected in the prediction that calcite is very likely to precipitate, and if sulfate is only slightly elevated, anhydrite and gypsum will precipitate. Chalcanthite, however, is unlikely to be stable and would not be expected to form in the aquifer. This suggests that high levels of sulfate in ground water are unlikely to occur long term as active precipitation will take place. It is also unlikely that secondary acid volatile sulfates will form in the aquifer as they will be unstable with respect to gypsum and anhydrite and dissolved constituents.

Table 4.2: Saturation Indices for selected minerals in ground water wells

Mineral	Saturation Indices			
	GWQ96-22	GWQ96-23	GWQ94-13	MW-11
Anhydrite	-1.252	-1.416	-0.495	-2.234
Calcite	0.299	0.771	0.619	0.536
Chalcanthite	-8.937	-9.515	-8.298	-12.337
Gypsum	-1.041	-1.206	-0.284	-2.303

D:\SR\U857\Fig4-1.cdr



c - GWQ9622A
d - GWQ9622B
e - GWQ9623A
f - GWQ9623B
g - GWQ94-16
h - GWQ94-21-11/94,7/96
l - GWQ94-15
j - GWQ94-17
k - GWQ94-20
l - GWQ94-13
m - GWQ94-14
n - MW9
o - MW10
p - MW11
q - PW1

DATE: 12/3/96	PROJ. No. U857	COPPER FLAT	
SRK	**PIPER DIAGRAM OF GROUNDWATER FROM THE COPPER FLAT AREA**		Figure 4.1

01227

D:\SR\U857\Fig4-2.cdr



DATE: 4/12/96	PROJ. No. U857	COPPER FLAT	
SRK		YOUNGER DIAGRAM FOR COPPER FLAT GROUNDWATER	Figure 4.2

01228

5 WASTE ROCK GEOCHEMISTRY

An assessment of the potential of waste rock to produce Acid Rock Drainage (ARD) has been made in the Hydrogeological investigations at Copper Flat by SRK (SRK, 1995 *Copper Flat Mine: Hydrogeological Studies*). Information on sampling and analytical protocol is given in that report and is not repeated herein.

5.1. Bulk geochemistry of waste rock

From whole rock analysis of waste rock samples (Appendix A), the primary constituents are Al, Ca, Fe, Mg and K. Trace metals of significance (> 10 ppm) are Ba, Cu, Co, Mn, Mo and Zn). Several million tons of waste rock are currently piled around the pit and along the southeast slope of Animas Peak. Although small seeps have been reported from these rock piles, none were observed during the present study. SRK has previously classified the waste rock in the area as oxidized, transitional and unoxidized (SRK, 1995). The difference is the proportion of pyrite observed in the material. The rock piles have been classed on the proportion of each type of material present with the west pile being primarily transitional waste, the north rock pile being a combination of unoxidized and oxidized waste and the south and eastern rock piles comprising essentially unoxidized sulfidic waste.

5.2. Static test results

Paste pH tests involving the mixing of approximately equal portions of solid sample and deionized water to produce a saturated paste are shown for material from the pit walls and waste rock dumps in Figure 5.1. Similar to the results reported in the 1995 study, low pH areas are observed in the West and North Waste Rock Dumps indicating release of stored acidity from ongoing oxidation and/or consumption of alkalinity from previous oxidation events. In the East dump material paste pH results suggest that insignificant oxidation has or is taking place with relatively neutral pH values recorded (Table 5.1). The acidic pH's from the West dump (pH 2.5) were observed in partially oxidized material which forms a cap to the sulfide mineralization. The values suggest that these materials are still undergoing oxidation.

Using a modified leach test, the total acid generating and consuming potential of material from the different waste rock piles has been assessed (Table 5.1). The results show that much of the material tested is acid generating in the waste rock piles and has the **potential** to produce an acidic metal-sulfate seep. An exception in the East Dump area is acid consuming and is primarily comprised of sulfidic quartz monzonite. This is reflected in the historical data on these dumps. With the exception of the small seep observed at the East Waste Rock Disposal Area, no other acidic seeps have been reported on any of the disposal areas, despite being exposed to water and oxygen for over 12 years.

D:\SR\U857\Fig5-1C.cdr



DATE: 3/12/96	PROJ. No. U857	COPPER FLAT	
SRK	**PASTE AND MEASURED AQUATIC pH MAPS OF WASTE ROCK, PIT LAKEN AND SURFACE WATERS**		Figure 5.1

01230

Table 5-1: Summary of Static Test Results

Sample ID	Sample Description	Paste pH	Total Sulfur (%)	Pyritic Sulfur (%)	Sulfate Sulfur (%)	Neutralizing Potential (t/kt)	Sulfide Sulfur (%)	Undefined Sulfur (%)	Pyrite			Sulfide		
									AP (t/kt)	NNP (t/kt)	NP/AP (t/kt)	AP (t/kt)	NNP (t/kt)	NP/AP (t/kt)
Tailings														
T-10-12	Tailings from borehole SRKBH-1-94	7.8	1.26	0.68	0.03	24	1.23	0.55	21.25	2.75	1.13	38.44	-14.44	0.62
T-5-7	Tailings from borehole SRKBH-1-94	7.5	1.10	0.53	0.18	31	0.92	0.39	16.56	14.44	1.87	28.75	2.25	1.08
	Average		**1.18**	**0.61**	**0.11**	**28**	**1.08**	**0.47**	**18.91**	**8.59**	**1.50**	**33.59**	**-6.10**	**0.85**
Waste Rock														
WD-1	West Dump Area, QM Waste Rock	2.7	4.34	2.12	0.005	0.1	4.34	2.22	66.25	-66.15	0.00	135.47	-135.37	0.00
PW-3	Pit Wall, Northwest of Pit Lake	2.6	2.20	0.84	0.005	0.1	2.20	1.36	26.25	-26.15	0.00	68.59	-68.49	0.00
SW-1	***Sulfide Waste Pile, QM Waste Rock***		***1.36***	***0.47***	***0.005***	***36***	***1.36***	***0.89***	***24.69***	***21.31***	***2.45***	***42.34***	***-6.34***	***0.85***
PW-2	***Pit Wall, Oxidized Cap Rock***		***0.37***	***0.04***	***0.005***	***11***	***0.37***	***0.33***	***1.25***	***9.75***	***8.80***	***11.41***	***-0.41***	***0.96***
PW-4	Pit Wall, Northeast of Pit Lake	3.9	1.89	0.78	0.005	16	1.89	1.11	24.38	-8.38	0.66	58.91	-42.91	0.27
SWP-1	Sulfide Waste Pile, QM Rock	6.8	3.08	1.46	0.005	40	3.08	1.62	45.63	-5.62	0.88	96.09	-56.09	0.42
LGSSP-1	Sulfide Waste Pile, QM Rock	6.6	1.52	0.61	0.005	47	1.52	0.91	19.06	27.94	2.47	47.34	-0.34	0.99
LGSSP-2	***Sulfide Waste Pile, QM Rock***	***6.9***	***0.61***	***0.20***	***0.005***	***39***	***0.61***	***0.41***	***6.25***	***32.75***	***6.24***	***18.91***	***20.09***	***2.06***
WD-2	West Dump Area, QM Waste Rock		1.98	0.87	0.005	60	1.98	1.11	27.19	32.81	2.21	61.72	-1.72	0.97
IDC-24-222-241	***QM From IDC Drillhole 24, 222-241 Feet***		***1.74***	***0.75***	***0.005***	***31***	***1.74***	***0.99***	***23.44***	***7.56***	***1.32***	***54.22***	***-23.22***	***0.57***
CF10-177.8-190	Andesite From Drillhole CF10, 177.8-190		2.86	1.77	0.06	52	2.80	1.03	55.31	-3.31	0.94	87.50	-35.50	0.59
CF10-190-199	***QM From Drillhole CF10, 190-199***		***3.59***	***1.09***	***0.07***	***44***	***3.52***	***2.43***	***34.06***	***9.94***	***1.29***	***110.00***	***-66.00***	***0.40***
CF10-214-220	QM From Drillhole CF10, 214-220		3.92	2.05	0.005	65	3.92	1.87	64.06	0.94	1.01	122.34	-57.34	0.53
H75-53-42	QM, Reverse Circulation Cuttings	8.2	1.77	0.88	0.005	36	1.77	0.89	27.50	8.50	1.31	55.16	-19.16	0.65
H75-64-44	QM, Reverse Circulation Cuttings	7.2	1.69	0.69	0.005	39	1.69	1.00	21.56	17.44	1.81	52.66	-13.66	0.74
H75-51-34	QM, Reverse Circulation Cuttings	8.6	2.02	0.72	0.005	49	2.02	1.30	22.50	26.50	2.18	62.97	-13.97	0.78
H75-48-58	QM, Reverse Circulation Cuttings	7.2	1.18	0.38	0.005	16	1.18	0.80	11.88	4.13	1.35	36.72	-20.72	0.44
H75-48-44	QM, Reverse Circulation Cuttings	7.4	1.06	0.15	0.005	9	1.06	0.91	4.69	4.31	1.92	32.97	-23.97	0.27
PW-1	Pit Wall, SW of Pit, Transition Zone, QM	6.1	3.61	2.0[illegible]	0.14	32	3.47	1.47	62.50	-30.50	0.51	108.44	-76.44	0.30
	Average		**2.15**	**0.94**	**0.02**	**33**	**2.13**	**1.19**	**29.39**	**3.36**	**1.97**	**66.51**	**-33.77**	**0.62**

Notes: Sulfate sulfur non-detect reported as 1/2 of the detection limit
Neutralization potential non-detect reported as 1/10 of the detection limit
Sulfide Sulfur = Total Sulfur - Sulfate Sulfur
Samples in *italics* selected for kinetic testing

AP pyrite) = Pyritic Sulfur x 31.25
AP (sulfide) = (Total Sulfur - Sulfate Sulfur) x 31.25

5.3. Kinetic test results

Kinetic testing on a representative suite of samples in a humidity cell (Figure 5.2) using 29-7 day cycles with 3 days humidified air, 3 days dry air.



Figure 5.2 Humidity Column Design

The results of these tests are presented in the 1995 hydrogeological report and only those of significance will be discussed herein. In both samples collected from the waste rock disposal areas, pH was above 7 except at week 20 when a sharp decrease occurred, believed to be in response to contamination of the distilled water used in the experiments. When tests resumed in week 27 pH levels were again above 7. Oxidizing conditions were indicated to have occurred throughout the experiments, based on the positive Eh readings.

The initially high conductivity in sample LGSSP-2 gradually dropped, possibly due to dissolution of sulfate salts (a similar pattern in leached sulfate, and initially Fe and acidity, are also observed suggesting initially dissolution of Fe-sulfates followed by dissolution of Na-, Mg- or Ca-salts). Alkalinity shows a gradual decrease with time, suggesting any contained alkalinity is used up, possibly to buffer acid generation. However acid generation from the samples is slow and is always an order of magnitude lower than alkalinity trends.

Initially acid generation shows a rapid increase (up to 8 mg/l total acidity), possibly due to dissolution of some Fe-sulfates.

The data indicate that if these materials are left exposed indefinitely, then the neutralizing potential will be consumed before the acid potential.

5.4. Water Quality and Environmental Implications

In the waste rock material it would be predicted that acidic seeps should be observed based on the static tests and the abundance of pyrite in the material. However, this is not reflected in water chemistry from this area or in the kinetic test work.

Acid generation is taking place in the waste rock material at slow rates and, if left unmanaged, it may ultimately produce acidic seepage. However, the rate of acid



Figure 5.3 Kinetic Test Results - pH vs. Time



Figure 5.4 Kinetic Test Results - Redox Potential vs. Time



Figure 5.5 Kinetic Test Results - Acidity vs. Time



Figure 5.6 Kinetic Test Results - Alkalinity vs. Time



Figure 5.7 Kinetic Test Results - Sulfate vs. Time



Figure 5.8 Kinetic Test Results - Copper vs. Time



Figure 5.9 Kinetic Test Results - Iron vs. Time



Figure 5.10 Kinetic Test Results - Conductivity vs. Time



Figure 5.11 Kinetic Test Results - Cumulative Acidity vs. Time



Figure 5.12 Kinetic Test Results - Cumulative Sulfate vs. Time



Figure 5.13 Kinetic Test Results - Cumulative Iron vs. Time



Figure 5.14 Kinetic Test Results - Cumulative Copper vs. Time

generation is much slower than the rate of acid consumption and consequently any acid generated is neutralized. The reasons for this are a combination of the:

- high crystallinity and coarse grain size of the pyrite
- isolated disseminated nature of the sulfide grains in the silicate-carbonate groundmass
- high evaporation over precipitation in the project area
- high levels of available phosphate fixing some of liberated iron as insoluble phosphate minerals.

However, there is only a finite volume of acidity and alkalinity in the material, and total acidity does exceed total alkalinity. The proposed closure activities for the water rock (regrading, covering and revegetating) will limit infiltration of water and diffusion of oxygen thereby slowing the rates of reaction and reducing the rate of seepage to insignificant levels.

To prevent acidic seepage in the long term, the waste rock will have to be covered by soil and vegetation to reduce oxygen diffusion. In addition, some of the highly sulfidic waste rock would make a useful substrate if Sulfur Reducing Bacteria (SRB) are introduced to the pit lake to encourage precipitation of sulfides. The storage under water would additionally reduce oxygen diffusion reducing or even preventing further sulfide oxidation or acid generation from this material. Any available oxygen would be utilized on sulfide surfaces assisting in the formation of an anoxic environment for the SRBs. The use of some sulfide in the manner would primarily be to assist in encouraging sulfide precipitation from the SRB process and in providing a bacterial substrate.

6 TAILINGS GEOCHEMISTRY

During 1982, approximately 1.2 million tons of tailings were deposited in existing tailings impoundments by Quintana Minerals. The material consisted of equal proportions of water and sand sized crushed rock and minerals. The facility is unlined and has largely drained. Samples from monitor wells located down gradient of the tailings indicate a noticeable increase in TDS and sulfate has occurred over time (see section 6.3).

To date, the evaluation of tailings behaviour has focused on the current condition of the tailings because it was not considered feasible, in the short term, to duplicate the field weathering and oxidizing conditions the tailings have been exposed to since deposition in the early 1980's. Testing and evaluations previously completed to assess tailings behavior included static (ABA) testing, paste pH tests, synthetic leaching tests and review of local monitoring well water quality data. These data are reported in the *Copper Flat Project, Hydrologic Studies* (SRK, 1995).

6.1. Static test results

Material has been taken from two boreholes into the 1982 tailings material and subjected to modified EPA 1312 static acid-base accounting tests. The average pyritic sulfur content for this material is 0.61 wt% (Table 5.2). From acid-base accounting the tailings material would be predicted to have a strong to moderate potential for net acid generation. Additional geochemical testing has been conducted on tailings samples obtained from five test pits in the existing tailings disposal area in July, 1996. Results of all static testing of tailings samples to date are summarized in table 5.2.

In general, two tailings materials were recovered from the test pits in July. These include gray, and yellow-brown tailings. The gray tailings (UTLS samples) are inferred to be derived from fresh quartz monzonite similar to that which will be mined in the future. The yellow-brown tailings (TTLS samples) are assumed to be derived from the oxidized and transition zone materials that formed the cap zone over the unoxidized quartz monzonite, and were mined concurrently with unoxidized rock during earlier operations. A bleached tailings sample (P5-BTLS) was also collected. The source of this material is unknown, however, it was likely derived from an alteration zone of limited extent.

Paste pH values in the July 1996 samples range from 6.2 to 7.8 with the majority of samples exhibiting a paste pH above 7.0. Paste conductivity is also low ranging from 298 to 686 µS/cm. In field tests performed in November 1996, paste pH ranged from 6 to 6.7 and paste pH from 502 to 691 µS/cm. The paste test data indicate low concentrations of stored acidity or oxidation products, and non-acidic to weakly acidic generating behaviour in the old tailings material.

The July tailings samples exhibit net neutralization values that range from 15.69 to -7.81 T/KT based on sulfide sulfur (total minus sulfate) content. The average acid neutralization to acid generating potential ratio (NP/AP) values are 1.21:1 and 0.94:1 for the unoxidized and transition tailings, respectively, based on sulfide sulfur content. The average reduction in the NP/AP ratio of the transition tailings is assumed to be a result of weathering and oxidation of the parent rock,

and the depletion of neutralizing potential during weathering over geologic time. A sample of bleached tailings obtained from an isolated exposure in one of the test pits exhibited an NP/AP ratio of 1.72:1.

Values for NNP and NP/AP calculated on the basis of pyritic sulfur content are also shown on the attached table. Based on pyritic sulfur content, NP/AP ratios range from 1.07:1 to 3.73:1, with most samples exhibiting ratios near 1.5:1.

Four tailings samples (three UTLS samples and 1 TTLS sample) were subjected to modified EPA method 1312 synthetic leaching tests to assess leachable metal concentrations. Tests were modified to include a 2:1 liquid to solids ratio to enhance detection of leachable metals. Deionized water was used as the leaching agent to simulate leaching under field conditions (Appendix A).

Test results indicate the primary leachable constituents are calcium, magnesium, potassium and sodium. Metals detected in the leach test extracts in trace concentrations (less that 0.5 mg/l) include aluminum, barium, copper, iron, manganese, molybdenum and zinc. These metals occur at concentrations that are not anticipated to be of concern, considering the aggressive nature of the 1312 leach test procedure.

In general, leachable metal concentrations are low in the tailings samples collected to date, and together with the paste pH and conductivity data, do not indicate that the tailings are currently acid generating.

Based on the results of the testing presented above, the existing tailings do not appear to be acid generating at present. NNP values in the range of -20 to +20 T/KT are generally considered indicative of materials with undefined potential for acid generation.

6.2. *Kinetic test results*

Kinetic testing of these materials is typically required to evaluate field behaviour. Disposal under field conditions is in essence, a large scale and extended duration kinetic test. On the basis of the extended period of weathering which the tailings have been exposed to, and the results of the static tests presented in Table 5.1, the tailings appear to have a low potential for acid generation, or are very slowly reactive.

Due to the fine grained nature of the tailings the acid generating potential may be enhanced in comparison to the waste rock. Testing completed to date indicates that the behaviour of the waste rock and tailings are very similar following an extended period of exposure to identical potential oxidizing conditions. Future tailings are expected to exhibit similar characteristics, as the ore will be derived from the same source, and it will be subjected to processing by similar methods.

Alta will conduct ongoing field scale kinetic testing of future tailings as well as waste rock piles in order to provide greater confidence in the existing geochemical models constructed from the present information.

6.3. *Water quality and Environmental implications*

Subsurface seepage recorded from the tailings monitor wells continues to show high levels of sulfate (~1200-1500 mg/l). This reflects the continued dispersion of water by subsurface seepage from the deposited tailings.

During the time of operations by Quintana the decant liquid from the tailings impoundment had a pH of 7.8, a TDS of 2230 mg/l, sulfate of 1440 mg/l and fluoride of 1.46 mg/l. The water appears to be a Ca-sulfate water, and paste pH of the material suggests it is non-acid generating or has a slow rate of acid generation.

The proposal to cover the tailings to prevent water penetration will lead to pore waters supersaturated with Ca and sulfate which will precipitate out gypsum within the tailings further reducing porosity. Any Ca and sulfate leachate will be collected in the leachate channels and used as part of the reclaimed water in the process plant.

7 PIT LAKE CHEMISTRY

7.1. Surface Water Chemistry

Surface water quality has already been discussed in detail previously in the 1995 Hydrogeological report and will not be discussed again here except for the Pit lake and Greyback wash.

Water quality in the Greyback wash is good. Upstream of the mining area TDS is in the range 780-965 mg/l, sulfate 275-300 mg/l, bicarbonate, 400-500 mg/l and pH is in the range 7.4-8.3.

Downstream of the mining area surface water quality has been modified with TDS increased to the range 2300-3000 mg/l and sulfate to 1150-1650 mg/l but pH remained unchanged and metal levels were all very low. The increases in TDS and sulfate are most likely due to evapo-concentration of surface water, but may also be affected by runoff from the plant area and by rock-water interactions within the Greyback channel.

In 1991 the pit lake had a pH of 7.2, in 1992 a sample taken along the margin of the lake during a period of high precipitation indicated this had fallen to 4.4-4.9 and the rose in 1993 to pH 5.6 (Newcomer et al., 1993). Current pH levels in the pit lake are at pH 7.7-8.3 and appear to have attained an equilibrium (Table 7.1). Total dissolved solids in the lake has increased from 1991 levels of 2700 mg/l, to 4200 mg/l in 1993, peaked in 1995 at around 5000 mg/l and currently have fallen to around 3500 mg/l. This is a reflection of the increased Ca (580 mg/l in 1991 to 620 mg/l in 1995) and sulfate (2800 mg/l in 1991 and 3170 mg/l in 1995) levels in the pit. The recent drop in TDS may be in response to a drop in water level, thus increasing salinity in residual water and consequently precipitation of gypsum. This is supported by recent field observations of the abundance of gypsum precipitated around the pit walls and at the edge of the pit lake.

At the present time, the pit water exceeds the current New Mexico human health drinking water standards for pH, sulfate, TDS, fluoride, manganese, zinc, copper and cadmium, but meets surface water standards for livestock and wildlife watering, the current use.

Table 7.1: Pit Lake Water Quality (all values in mg/l except where stated otherwise)

Parameter	Pit lake, 1994	Pit Lake, 1996	Greyback, 1996
pH	7.52	8.31	7.61
Conductivity, µm/cm	4690	5230	3860
Bicarbonate	104	122	620
Nitrate	5	<5	6.2
Sulfate	2970	3170	1730
Fluoride	8.1	10	1.4
Chloride	130	150	94
TDS	4380	5230	3450
Sodium	320	430	360
Magnesium	250	300	140
Aluminium	<0.05	0.13	0.033
Potassium	18	21	2.1
Calcium	550	620	490
Manganese	3.4	3	0.17
Iron	<0.05	<0.05	0.057
Copper	0.032	<0.025	<0.025
Molybdenum	<0.05	<0.05	<0.05
Cadmium	0.017	0.014	<0.0025

7.2. *Geochemical Model of Pit Lake Chemistry*

There are two parts to the modelling approach used in analyzing pit water quality at the Copper Flat site. The first part of the model requires calibration to reproduce the current conditions in the existing pit. Physiochemical parameters derived from the first part of the modelling effort are used in the second part of the modelling procedure. The purpose of the second part was to predict future pit water chemistry after mine closure.

7.2.1. Model Description

After cessation of historical mining activity, the existing mine pit received inflows from ground water and surface runoff. Most of the surface runoff in the catchment area probably discharges to the mine pit within a short period of time after a major rainfall event, allowing only minimal time in contact with sulfide bearing material. A fraction of the runoff, however, infiltrates rocks in the vicinity of the pit and flows into the pit as seepage. These oxygenated waters react with sulfides to form Acid Rock Drainage (ARD). All dissolved species contributed by ground water, unreacted surface runoff and ARD contact water are then concentrated by evaporation. As the pit water becomes saturated with respect to minerals or amorphous solid phases, some dissolved constituents are removed

from solution by precipitation. The concentrations of these constituents are thus limited by the solubility of certain minerals.

Based on the model described above, the chemical evolution of the existing pit water can be simulated by mixing three types of water, concentrating the mixture by evaporating pure water and equilibrating the resultant solution with an assemblage of gases and solid phases. The model calibration process involved adjusting evaporation rate and volumes of component waters until the simulated water chemistry from the model approximates to the analytical measurements for pit water chemistry. Specifically, there are four parameters that were determined during model calibration. These parameters are:

- Groundwater inflow rate
- Surface water inflow rate
- Contact water (ARD) inflow rate
- Net evaporation rate

To determine values for these parameters, there must be four constraints to the geochemical model. These constraints can be physical or chemical. The following criteria were used in the calibration of the Copper Flat pit water model:

- At the end of 6 years, the volume of water accumulated by the model must approximate the volume determined from pit geometry and the 1994 water level in the pit.
- At steady state, the net evaporation rate must equal the sum of the inflow rates. Steady state must be reached in six years.
- At the end of 12 years, the solution chemistry simulated by the model must be similar to the average chemistry of the pit water, particularly with respect to pH, calcium, and sulfate.
- The pit rocks are assumed to offer no buffering capacity to the solution (i.e. no mineral phase can precipitate unless it is precipitated first).

7.2.1.1.Calibration Procedure

A modified version of PHREEQE was used to simulate chemical changes over time in a sequential batch mode. Each batch represented an increment of time and consisted of five operations:

- Addition of groundwater
- Addition of surface water
- Addition of contact water
- Evaporation of pure water
- Solution equilibration

The first step of the procedure was to compute solution volumes using constraints 1 and 2.

$$G_s + G_i + 2S_t - 2E = V / t \qquad \text{Constraint 1}$$

and

$$S_t + G_s = E \qquad \text{Constraint 2}$$

Where: E = net evaporation rate (ft^3/yr)
G_i = initial groundwater inflow rate (ft^3/yr)
G_s = steady-state groundwater inflow rate (ft^3/yr)
S_t = total surface inflow rate (ft^3/yr)
V = volume of pit water (ft^3)
t = time to fill pit half way (yr)
= 3.0 yr

Three mixing models were considered:

1. Low evaporation (Table 7.2)
2. Moderate evaporation (Table 7.2)
3. High evaporation (Table 7.2)

The second step of the procedure was to define chemical compositions for three types of water that comprise the components of inflow to the chemical model:

1) Groundwater inflow (Table 7.3)
2) Uncontaminated surface inflow (Table 7.3)
3) Contact water (Table 7.3)

The third step of the procedure was to use PHREEQE to model the chemical evolution of pit water for each mixing model developed in the first step. Because Mixing Model 1 produced a net groundwater outflow from the pit, it was eliminated from further consideration, and geochemical modeling was restricted to Mixing Models 2 and 3. Mixing Model 1 is unlikely to produce any significant evaporative effects and is inconsistent with hydrologic data, which indicate that groundwater flows into the pit. During this step of the analytical procedure, four chemical calibration models were developed and evaluated:

TABLE 7.2: 6-Year Water Budget

Year	Ground Water	Surface	Net Evaporation	Volume Change	Total Volume
		Low Evaporation			
1	2,097,539.840	2,446,329.600	2,414,269.440	2,129,600	2,129,600
2	1,710,339.840	2,446,329.600	2,414,269.440	1,742,400	3,872,000
3	1,323,139.840	2,446,329.600	2,414,269.440	1,355,200	5,227,200
4	935,939.840	2,446,329.600	2,414,269.440	968,000	6,195,200
5	548,739.840	2,446,329.600	2,414,269.440	580,800	6,776,000
6	161,539.840	2,446,329.600	2,414,269.440	193,600	6,969,600
ss	-64,120.320	4,892,659.200	4,828,538.880	0	6,969,600
	Precipitation Rate = 13 in/yr Evaporation Rate = 65 in/yr Runoff Coefficient = 0.500				
		Moderate Evaporation			
1	3,244,736	1,812,096	2,927,232	2,129,600	2,129,600
2	2,857,536	1,812,096	2,927,232	1,742,400	3,872,000
3	2,470,336	1,812,096	2,927,232	1,355,200	5,227,200
4	2,083,136	1,812,096	2,927,232	968,000	6,195,200
5	1,695,936	1,812,096	2,927,232	580,800	6,776,000
6	1,308,736	1,812,096	2,927,232	193,600	6,969,600
ss	2,230,272	3,624,192	5,854,464	0	6,969,600
	Precipitation Rate = 12 in/yr Evaporation Rate = 75 in/yr Runoff Coefficient = 0.400				
		High Evaporation			
1	4,621,232	1,132,560	3,624,192	2,129,600	2,129,600
2	4,234,032	1,132,560	3,624,192	1,742400	3,872,000
3	3,846,832	1,132,560	3,624,192	1,355,200	5,227,200
4	3,459,632	1,132,560	3,624,192	968,000	6,195,200
5	3,072,432	1,132,560	3,624,192	580,800	6,776,000
6	2,685,232	1,132,560	3,624,192	193,600	6,969,600
ss	4,983,264	2,265,120	7,248,384	0	6,969,600
	Precipitation Rate = 10 in/yr Evaporation Rate = 88 in/yr Runoff Coefficient = 0.300				
NOTE: Steady state is indicated by the symbol "ss". A steady-state condition is reached at the end of the sixth year.					

TABLE 7.3: Solution Chemistry

Parameter	Units	Concentration
Type 1 - Inflow Ground Water		
Calcium (Ca)	mg/l	92.065
Magnesium (Mg)	mg/l	25.018
Sodium (Na)	mg/l	74.052
Potassium (K)	mg/l	2.001
Iron (Fe)	mg/l	< 0.001
Bicarbonate (HCO_3)	mg/l	260.183
Sulfate (SO_4)	mg/l	220.155
Chloride (Cl)	mg/l	30.021
pH	-log	7.200
pE	-log	5.071
pO_2	-log	34.036
NOTE: This water is supersaturated with respect to CO_2 gas; undersaturated with respect to magnesite and gypsum; and in equilibrium with calcite and $Fe(OH)_3a$.		
Type 2 Inflow - Uncontaminated Surface Water		
Calcium (Ca)	mg/l	50.019
Magnesium (Mg)	mg/l	8.003
Sodium (Na)	mg/l	40.015
Potassium (K)	mg/l	2.001
Iron (Fe)	mg/l	< 0.001
Bicarbonate (HCO_3)	mg/l	200.075
Sulfate (SO_4)	mg/l	66.025
Chloride (Cl)	mg/l	10.004
pH	-log	7.200
pE	-log	13.167
pO_2	-log	1.652
NOTE: This water is supersaturated with respect to CO2 gas; undersaturated with respect to calcite, magnesite and gypsum; and in equilibrium with $Fe(OH)_3a$.		
Type 3 Inflow - Acid Rock Drainage (Contact Water)		
Calcium (Ca)	mg/l	360.203
Magnesium (Mg)	mg/l	25.014
Sodium (Na)	mg/l	10.006
Potassium (K)	mg/l	4.002
Iron (Fe)	mg/l	100.056
Bicarbonate (HCO_3)	mg/l	0.000
Sulfate (SO_4)	mg/l	3,051.718
Chloride (Cl)	mg/l	14.008
pH	-log	1.700
pE	-log	18.661
pO_2	-log	1.677
NOTE: This water is supersaturated with respect to CO_2 gas; undersaturated with respect to magnesite and calcite; and in equilibrium with gypsum and Na-Jarosite.		

TABLE 7.4: Simulated Solution Chemistry after 12 Years Scenario 2 - Unbuffered

Parameter	Units	Concentration
Calcium (Ca)	mg/l	547.073
Magnesium (Mg)	mg/l	110.620
Sodium (Na)	mg/l	321.715
Potassium (K)	mg/l	13.564
Iron (Fe)	mg/l	61.261
Bicarbonate (HCO_3)	mg/l	20.432
Sulfate (SO_4)	mg/l	2,844.870
Chloride (Cl)	mg/l	122.600
pH	-log	2.342
pE	-log	9.938
pO_2	-log	34.000
pCO_2	-log	2.000
ARD added (Percent)		22.196
Na-Jarosite precipitated (kg):		4,685.616
Gypsum precipitated (kg):		81,455.882
NOTE: Equilibrium was imposed for CO_2 and O_2. Equilibrium was imposed for gypsum and Na-Jarosite after saturation was exceeded.		

TABLE 7.5: Simulated Solution Chemistry after 12 Years Scenario 2 - Buffered by $Fe(OH)_3$

Parameter	Units	Concentration
Calcium (Ca)	mg/l	581.273
Magnesium (Mg)	mg/l	124.558
Sodium (Na)	mg/l	< 0.001
Potassium (K)	mg/l	0.006
Iron (Fe)	mg/l	362.441
Bicarbonate (HCO_3)	mg/l	20.680
Sulfate (SO_4)	mg/l	2,345.046
Chloride (Cl)	mg/l	125.120
pH	-log	4.183
pE	-log	8.097
pO_2	-log	34.000
pCO_2	-log	2.000
ARD added (Percent)		50.000
$Fe(OH)_{3a}$ dissolved (kg):		915,878.864
Na-Jarosite precipitated (kg):		1,229,041.843
K-Jarosite precipitated (kg):		38,577.514
Gypsum precipitated (kg):		278,699.113
NOTE: Equilibrium was imposed for CO_2, O_2 and $Fe(OH)_3$. Equilibrium was imposed for gypsum, Na-Jarosite and K-Jarosite after saturation was exceeded.		

TABLE 7.6: Simulated Solution Chemistry after 12 Years Scenario 2 - Buffered by Calcite

Parameter	Units	Concentration
Calcium (Ca)	mg/l	360.203
Magnesium (Mg)	mg/l	25.014
Sodium (Na)	mg/	10.006
Potassium (K)	mg/l	4.002
Iron (Fe)	mg/l	100.056
Bicarbonate (HCO3)	mg/l	152.701
Sulfate (SO4)	mg/l	3051.718
Chloride (Cl)	mg/l	14.008
pH	-log	7.035
pE	-log	5.245
pO_2	-log	34.000
pCO_2	-log	2.000
ARD added (Percent)		50.000
$Fe(OH)_{3a}$ precipitated (kg):		59,170.365
Calcite dissolved (kg):		543,688.794
Gypsum precipitated (kg):		1,221,524.884
NOTE: Equilibrium was imposed for CO_2, O_2, calcite and $Fe(OH)_3$. Equilibrium was imposed for gypsum after saturation was exceeded.		

TABLE 7.7: Simulated Solution Chemistry after 12 Scenario 3 - Unbuffered

Parameter	Units	Concentration
Calcium (Ca)	mg/l	647.399
Magnesium (Mg)	mg/l	155.271
Sodium (Na)	mg/l	456.848
Potassium (K)	mg/	15.350
Iron (Fe)	mg/l	0.003
Bicarbonate (HCO_3)	mg/l	153.380
Sulfate (SO_4)	mg/l	2,789.615
Chloride (Cl)	mg/l	180.042
pH	-log	7.028
pE	-log	5.252
pO_2	-log	34.000
pCO_2	-log	2.000
ARD added	Percent	22.074
Fe(OH)3 precipitated (kg):		16,325.674
Calcite precipitated (kg):		34,964.369
NOTE: Equilibrium was imposed for CO_2, O_2, calcite and $Fe(OH)_3$. In the 12th year, the solution was in equilibrium with gypsum.		

- Chemical Model 1: Unbuffered Mixing Model 2 (Table 7.4)
- Chemical Model 2: Mixing Model 2 Buffered by Fe(OH)3 (Table 7.5)
- Chemical Model 3: Mixing Model 2 Buffered by Calcite (Table 7.6)
- Chemical Model 4: Unbuffered Mixing Model 3 (Table 7.7)

The output of each chemical model was compared to water-quality analyses to determine the validity of the model with respect to the third calibration criterion. The water quality analysis most representative of average pit water is summarized in Table 7.8. Table 7.9 presents data that represent localized conditions that occur along the pit shore where pit water contains a high concentration of acid rock drainage from seepage after a precipitation event.

7.2.1.2.Calibration Results

Results of model calibration indicate that acid rock drainage constitutes an important source of sulfate to the existing pit water, but a high evaporation rate is necessary to concentrate the sulfate to observed levels without lowering solution pH. Specific results for each calibration model are discussed below:

- **Chemical Model 1 (rejected):**

The output for this model run is the result of several iterations. In the iterative process, the percent ARD was adjusted until the model simulated a sulfate concentration within the analytical range of 2700 to 2900 mg/l. Model results indicate that an ARD inflow of 22 percent would produce about 2800 mg/l of sulfate, which is within the analytical range for average pit conditions. However, the simulated pH for the unbuffered model is very much lower than any analyzed pH. For this reason, this run does not satisfy calibration criteria.

- **Chemical Model 2 (rejected):**

The second calibration model assumes the presence of amorphous ferric hydroxide in the system. Because this assumption contradicts the fourth calibration criterion, the second model cannot represent the pit as a whole. However, it may provide some insight into some localized conditions that have been observed along the pit shore. The output for this model was generated with a single run using an ARD inflow volume of 50 percent. This produced a sulfate concentration of only 2300 mg/l. Additional ARD would affect this value very little because the precipitation of gypsum and jarosite limit sulfate concentration. The simulated values of pH, calcium, bicarbonate and sulfate are all consistent with analytical values for pit shore samples. In addition, all precipitates simulated by this model have been observed locally within the pit.

- **Chemical Model 3 (rejected):**

The third calibration model assumes the presence of calcite within the system. This assumption is not realistic for the Copper Flat pit because the rocks at Copper Flat contain virtually no carbonate minerals. Nevertheless, this model is the only Scenario 2 model capable of generating sulfate concentrations above

TABLE 7.8: Average Pit Water Solution Chemistry Sample NLP 3m

Parameter	Units	Concentration
Calcium (Ca)	mg/l	650
Magnesium (Mg)	mg/l	230
Sodium (Na)	mg/l	290
Potassium (K)	mg/l	16
Iron (Fe)	mg/l	0.26
Bicarbonate (HCO_3)	mg/l	72
Sulfate (SO_4)	mg/l	2,700
Chloride (Cl)	mg/l	110
pH	-log	7.8

TABLE 7.9: Local Pit Water Solution Chemistry - Pit Shore Average

Parameter	Units	Concentration
Calcium (Ca)	mg/l	597
Magnesium (Mg)	mg/l	169
Sodium (Na)	mg/l	223
Potassium (K)	mg/l	13
Iron (Fe)	mg/l	0.2
Bicarbonate (HCO3)	mg/l	35
Sulfate (SO4)	mg/l	2,400
Chloride (Cl)	mg/l	76
pH	-log	4.4
NOTE: Average concentrations were weighted to reflect the lowest pH solution. This solution represents the greatest contribution of acid rock drainage.		

2500 mg/l at near neutral pH. This model was eliminated from further consideration because it did not satisfy the fourth calibration criterion. In addition, the calcium concentration simulated by the model is considerably lower than analytical values representing average pit water chemistry.

- **Chemical Model 4 (accepted):**

The fourth calibration model represents an evaporative system. The surface-inflow and evaporation rates for this model are consistent with climatological data from the Caballo Reservoir. The chemical model did not require the presence of any solid phases in the system and was able to generate sulfate, calcium and pH levels that were very close to analytical values. All calibration criteria were satisfied. This model required 22 percent ARD to establish observed sulfate concentrations.

7.2.2. Water-Quality Predictions

The geochemical model used to predict post-closure water quality in the proposed pit incorporated data from several sources. The assumptions and data employed by the predictive geochemical model are summarized below:

- The initial rate of groundwater inflow to the proposed pit is approximately 115 gpm based on the numerical groundwater flow model;
- The rate of groundwater inflow at a pit-water level of 5440 ft msl (pre-1982 water table) is 0.06 gpm;
- The surface area and volume of the pit lake are computed from pit-water level using pit-geometry functions determined from the design of the proposed pit under the reduced stripping alternative;
- The net evaporation rate (evaporation rate minus precipitation rate) is 5.92 ft/yr based on model calibration and Caballo Reservoir data;
- The surface runoff coefficient is 0.30 based on model calibration and independent surface-runoff calculations using the SCS Method;
- The precipitation rate is 0.83 ft/yr based on model calibration and Caballo Reservoir data;
- The surface-runoff catchment area for the proposed pit is 152 acres based on surface topography;
- The inflow rate from Greyback Wash is 77.4 gpm based on a hydrologic analysis of Greyback Gulch;
- All inflow from Greyback Wash was assumed to enter the pit without contacting acid-generating material;
- ARD (i.e. contact water) was assumed to comprise 25 percent of local surface runoff, and
- Waste rock piles were assumed to be uncovered.

The inflow rate of acid rock drainage for the existing pit was estimated to be approximately 22 percent of the surface runoff rate based on geochemical model calibration. In the proposed mine closure scenario, it is unlikely that the ARD

content of surface water will exceed 25 percent. This assumption considers the following factors:

- Although surface inflow to the proposed pit may potentially contact more wall rock, the wall rock remaining after mine closure will likely have a much lower ARD potential than the wall rock in the existing pit;
- Observations made during site inspections indicate that most of the ARD in the existing pit is probably generated when surface runoff contacts highly reactive "transition" waste rock. The proposed mine closure plan minimizes the amount of this material exposed to runoff; and
- The proposed mine site will be reclaimed in a manner that will minimize surface water contact with sulfide-bearing material. The model assumes that the amount runoff contacting potentially acid-generating waste rock following closure will be similar to current conditions. Covering of the waste during mine closure should preclude surface water runoff from contacting waste rock in the disposal areas.
- 1996 field paste pH sampling of representative materials currently exposed in the pit walls indicate that approximately 25% of the material will generate low pH solutions when contacted by water (Figure 5.1).

Subsequent to model calibration, water-quality analyses were received for new monitor wells, which were drilled in proximity to the existing pit. For predictive simulations of pit water quality, the chemical composition of the Type 1 inflow was revised to be consistent with the water quality analysis for Well GWQ 96-22a (Table 7.10). This analysis was considered to be more representative of ground water in the vicinity of the mine pit.

Results of predictive simulations (Tables 7.11 and 7.12) indicate that the water quality in the proposed pit should be better than existing pit-water quality for about 120 years after mine closure. This improvement in water quality can be attributed to the proposed pit's relatively low ratio of surface area to volume. The best water quality can be obtained by diverting runoff from Greyback Wash into the proposed pit. The resulting dilution will tend to further offset the effects of evaporation. Figure 7.1 illustrates the time-dependent changes in sulfate concentration and pH for the post-closure scenario involving the diversion of Greyback Wash.

The results of the predictive geochemical model indicate a trend towards increasing sulfate concentration with time, and in the absence of inflow from Greyback Wash, a trend towards decreasing pH. These trends are considered to be realistic for the physical and geochemical environment analyzed. Although the long term trends and general behavior of pit lake geochemistry can be reasonably modeled, the estimate of precise values of simulated future concentrations may vary according to field conditions.

TABLE 7.10: Revised Solution Chemistry for Type 1 Inflow Ground Water

Parameter	Units	Concentration
Calcium (Ca)	mg/l	71.049
Magnesium (Mg)	mg/l	6.705
Sodium (Na)	mg/l	130.089
Potassium (K)	mg/l	2.502
Iron (Fe)	mg/l	< 0.001
Bicarbonate (HCO_3)	mg/l	135.092
Sulfate (SO_4)	mg/l	250.171
Chloride (Cl)	mg/l	89.061
pH	-log	7.500
pE	-log	5.071
pO_2	-log	32.836

TABLE 7.11: Simulated Solution Chemistry after 120 Years Post Closure, Scenario 1 - Greyback Wash Diversion In Place

Parameter	Units	Concentration
Calcium (Ca)	mg/l	554.030
Magnesium (Mg)	mg/l	54.359
Sodium (Na)	mg/l	750.399
Potassium (K)	mg/l	17.260
Iron (Fe)	mg/l	1.303
Bicarbonate (HCO_3)	mg/l	20.487
Sulfate (SO_4)	mg/l	2,469.052
Chloride (Cl)	mg/l	500.622
pH	-log	3.885
pE	-log	8.395
pO_2	-log	34.000
pCO_2	-log	2.000
Na-Jarosite precipitated (kg):		336,526
Gypsum precipitated (kg):		264,744
NOTE: Equilibrium was imposed for CO_2, O_2, Na-jarosite, and gypsum.		

TABLE 7.12: Simulated Solution Chemistry after 120 Years Post Closure, Scenario 2 - Greyback Wash Diversion Removed

Parameter	Units	Concentration
Calcium (Ca)	mg/l	235.965
Magnesium (Mg)	mg/l	37.374
Sodium (Na)	mg/l	342.032
Potassium (K)	mg/l	10.494
Iron (Fe)	mg/l	0.002
Bicarbonate (HCO_3)	mg/l	192.112
Sulfate (SO_4)	mg/l	1,051.469
Chloride (Cl)	mg/l	187.301
pH	-log	7.177
pE	-log	5.104
pO_2	-log	34.000
pCO_2	-log	2.000
$Fe(OH)_{3a}$ precipitated (kg):		211,335
Calcite precipitated (kg):		1,540,726
NOTE: Equilibrium was imposed for CO_2, O_2, calcite and $Fe(OH)_3$.		

D:\SR\U857\Fig7-1.cdr



DATE: 4/12/96	PROJ. No. U857	COPPER FLAT	
SRK	Copper Flat Pit Water Chemistry Estimation 25% Acid Rock Drainage Case (Greyback diverted)		Figure 7.1

01259

These variations may include ARD content, runoff coefficient, precipitation and evaporation. To assure conservative predictions, parameters were selected to favor low runoff, high evaporation and high ARD generation. These conditions over-predict solute concentrations.

7.3. Future Trends

In planning the future operating and closure activities to minimize geochemical impact of the operation on the environment, it should be noted that:

- As mining progresses the most acid producing material, the ore, will be removed and processed.
- It has been agreed already by Alta that the waste rock disposal areas will be covered by 12 inches of soil and revegetated to limit infiltration by water, reduce oxygen diffusion and reduce seepage from the pile to insignificant levels. Based on the geochemical work, this cover will be acceptable to reduce acid generation and leakage from the waste rock piles.

Based on the review of the historical data and the above geochemical model it is recommended that the Greyback Wash be diverted into the pit following cessation of mining. This dilution will occur only during high rainfall which is when acidic seepage would be greatest. The dilution will also assist in the lowering of sulfate levels in the pond.

The relatively high sulfate levels could be reduced by encouraging communities of Sulfate Reducing Bacteria in the pit. Desulfovibrio desulfuricans readily reduce sulfate to sulfide and can participate in secondary sulfide production (Kleinnman and Pacelli, 1991).

The mechanisms resulting in dissolved metal immobilization are two stages:

$$CH_2O + SO_4^{2-} = HS^- + HCO_3^-$$

where CH_2O is the labile organic material. Bisulfide is produced which reacts with dissolved metals (Me=divalent metal cation) by a mechanism such as:

$$Me^{2+} + HS^- = MeS_s + H^+$$

Organic carbon is replenished by annual growth of aquatic plants and degradation products. Cattails (*Typha laxifolia*) are currently established along the northern part of the pit). In the first few years while the community is immature it will be necessary to add a nutrient supplement such as sewage waste or the mulch produced by brewing or cider production. The local apple farms should be a good source of this material.

As a bi-product, bicarbonate is produced assisting in neutralizing any acid seepage. This mechanism has been used extensively in wetlands and treatment of heaps, waste rock piles and tailings effluent to remove pollutants (Klienmann and Pacilli, 1991; Bowell et al., 1996).

8 RECOMMENDATIONS

From the studies conducted at the site, an understanding of the geochemistry of the Copper Flat environment can be gained. During the operations at Copper Flat it will be useful to further validate the geochemical model discussed above through the use of field-sized kinetic test work.

From the hydrogeological studies undertaken by Adrian Brown it is known that the pit acts as a water sump with no outlet into ground water. Consequently, on closure the pit will refill. In order to prevent a long term build up of sulfate in the pit lake, the feasibility of in-situ sulfate reduction and/or continuous gypsum precipitation as possible reclamation options after closure should be investigated.

9 CONCLUSIONS

The mineralization at Copper Flat contains acid generating sulfide and sulfate minerals and acid consuming minerals such as carbonates, silicates and hydroxides.

From the static tests it can be observed that pyritic material in the waste rock, pit walls and tailings material have the potential to generate substantial acidity. However, some host rocks will consume significant levels of acidity.

Regional ground water is good quality and is well buffered with high alkalinity reflecting the dominance of dolomite and limestone country rocks.

Kinetic testing of acid generation reflects the high crystallinity of pyrite, the low humidity and high buffering potential of the Copper Flat environment. Test work demonstrates that acid generation is extremely slow and is more than compensated by rock buffering and ground water input.

The diversion of the Greyback Wash will assure in the long term, that pit water quality will remain good with well buffered water of reasonable quality. The dilution will reduce all constituents, except sulfate to below New Mexico human health and domestic use levels. The potential benefit of Sulfate Reducing Bacteria to water quality strongly supports the need for further investigation during operations.

The controlled precipitation of gypsum from pumped water from the tailings will assist management of the floatation circuit and provide an additional useful geological cover on closure. Field testing of this material should be undertaken during operations.

R.J.Bowell PhD
Sr. Geochemist

T. Braun PE
Sr. Hydrogeologist

G.Mudder PE
Project Engineer

K.Peterson MSc PE
Sr. Hydrologist

10 REFERENCES

1. Achmed, S.M. Electrochemical and surface chemical methods for the prevention of atmospheric oxidation of sulphide tailings and acid generation. In: *Proceedings Second Int. Conf. Abatement Acidic Drainage,* **2,** 1991,305-319. MEND Secretariat, Ottawa, Ontario.
2. Allison, J.D., Brown, D.S. and Novo-Gradac, K.J. MINTEQA2/PRODEF2: A geochemical assessment model for environmental systems. V. 3.2 User's manual. U.S. Environmental Protection Agency, 1991, *EPA/600/3-91-021,* Athens, Georgia.
3. Bailey, K.K. and Peters, E, Decomposition of pyrite in acids by pressure leaching and anodization. *Can. Metall. Q.,* **15,** 1976, 333-344.
4. Bigham, J.M. Mineralogy of ochre deposits. In: *Environmental Geochemistry of Sulfide Mine Waste,* (eds: J.L.Jambor and D.W. Blowes). 1994 103-131. MAC.
5. . Bigham, J.M., Schwertmann, U. And Carlson, L. Mineralogy of precipitates formed by the biogeochemical oxidation of Fe(II) in mine drainage. In. *Biomineralization Processes of Iron and Manganese: Modernand Ancient Environments* (H.C.W. Skinner & R.W. Fitzpatrick, eds.) Catena Verlag, Germany, 1992, 219-232.
6. Blowes, D.W., Ptacek, C.J., and Jambor, J.L. Remediation of low quality drainage in tailings impoundments. In: *Environmental Geochemistry of Sulfide Mine Waste,* (eds: J.L.Jambor and D.W. Blowes). 1994. 365-379. MAC.
7. Bowell, R.J. Arsenic sorption by Iron oxyhydroxides and oxides. *Applied Geochemistry,* **9,** 1994, 279-286.
8. Bowell, R.J. and Bruce, I. Geochemistry of ochre and mine waters, Levant mine, Cornwall. *Applied Geochemistry,* **10,** 1995, 237-250.
9. Cravotta, C.A. III Secondary iron-sulfate minerals as sources of sulfate and acidity. In: Environmental Geochemistry of Sulfide Oxidation (eds: C.N. Alpers and D.W. Blowes). *Am.Chem. Soc. Sym. Series,* **550.** 1994. 345-364.
10. . Deng, Y. and Stumm, W. Reactivity of aquatic iron (III) oxyhydroxides- implications for redox cycling of iron in natural waters. *App. Geochem,* **9,** 1994, 23-36.
11. Duniker J.C. Suspended matter in estuaries: adsorption and desorption processes. *In: Chemistry of Estuaries* (ed: E.Olausson), 1980, 121-152. John Wiley and Sons.
12. Fuge, R., Laidlaw, I.M.S., Perkins, W.T. and Rogers, K.P. The influence of acidic mine and spoil drainage on water quality in mid-Wales, *Environ Geochem. Health,* **13,** 1991, 70-75
13. Gould, W.D., Bechard, G. And Lortie, L. The nature and role of microorganisms in mine drainage. In: *Environmental Geochemistry of Sulfide Mine Waste,* (eds: J.L.Jambor and D.W. Blowes). 1994, 185-199, MAC.
14. Huang, X. and Evangelou, V.P. Supression of pyrite oxidation rate by phosphate addition. In: Environmental Geochemistry of Sulfide Oxidation (eds: C.N. Alpers and D.W. Blowes). *Am.Chem. Soc. Sym. Series,* **550.** 1994. 562-573.
15. Kalin, M., Cairns, J. and McCready, R.G.L. Ecological engineering for acid drainage treatment of coal wastes. *Resources Conserv., Recycling,* **5,** 1991, 265-275.
16. Kleinmann, R.L.P. and Pacelli, R.R. Biogeochemistry of acid mine drainage. *Mining.*

Eng., **33**, 1991, 300-6.

17. Lowson, R.I. Aqueous oxidation of pyrite by molecular oxygen. *Chem. Rev.*,**82**, 1982, 461-497.

18. McKibben, M.A. and Barnes, H.L. Oxidation of pyrite in low temperature acidic solutions: Rate laws and surface textures. *Geochim. Cosmochim. Acta.*, **50**, 1986, 1509-1520.

19. Nicholson, R.V., Gillham, R.W., Cherry, J.A. and Reardon, E.J. Reduction of acid generation in mine tailings through the use of moisture-retaining cover layers as oxygen barriers. *Can. Geotech. J.*,**26**, 1989, 1-8

20. Nordstrom, D.K. Aqueous pyrite oxidation and the consequent formation of secondary minerals. *In: Acid Sulphate Weathering*, 1982a, Soil Sci. Soc. Am.

21. Parfitt, R.L.Chemical properties of variable charge soils. In: *Soils with variable charge* (ed: B.K.G.Theng). Sp. Pub. N.Z. Soil Sci. Soc., 1980, 167-194.

22. Sato, M. Persistency-field En-pH diagrams for sulphides and their application to supergene oxidation and enrichment of sulphide ore bodies. *Geochim. Cosmochim. Acta*, **56**, 1992, 3133-3156.

23. Scott, K.M. Solid solution in, and classification of, gossan-derived members of the alunite-jarosite family, Queensland, Australia.*Am. Min.*, **72**, 1987, 178-187.

24. Sigg, L. and Stumm, W. The interaction between weak acids and hydrous iron oxides. *J. Colloid. Sci.*, **2**, 1980, 101-117.

25. Sivenas, P and Beals, F W. Natural geobatteries associated with sulphide ore deposits. *J Geochem. Explor.*, **17**, 1982, 123-143.

26. Thornber, M.R. Supergene alteration of sulphides, I: A chemical model based on massive nickel sulphide deposits at Kambalda, Western Australia. *Chem. Geol.*, **15**, 1975, 1-14.

27. Thornber, M.R. Mineralogical and electrochemical stability of the nickel-iron sulphides pentlandite and violarite. *J. Appl. Electrochem.*, **13**, 1983 253-267.

28. Thornber, M.R., Chemical processes during weathering. In: *Handbook of Exploration Geochemistry, vol 4: Regolith Exploration Geochemistry in Tropical Terrains* (eds: C R M Butt and H Zeigers), 1992, 65-99. Elsevier.

29. Tipping E. and Cooke, D. The effect of adsorbed humic substances on the surface charge of goethite. *Geochim. Cosmochim. Acta.*, **46**, 1982, 75-80.

30. Velbel, M.A. Constancy of silicate-mineral weathering-rate ratios between natural and experimental weathering implications for hydrologic control of differences in absolute rates: *Chem Geol.*, 105, 1992, 89-99.

31. Younger, P.L. Hydrogeochemistry of minewaters flowing from abandoned coal workings in County Durham. Q. J. Eng. Geo., 28, S101-S113.

Appendix A - Waste Rock Tests

lient : Steffen Robertson and Kirsten
ddress : 3232 S. Vance St., Ste. 210
Lakewood, CO 80227
ttn. : Gene Muller
roject : 68605, Copper Flat

JUL 28 1994

ample Matrix: Waste Rock
ample ID: 68605, WD-1
ample Date Time: Unknown

Lab No. : 94-RT-00594
Date Received: 06/10/94

Parameters			
Moisture %	0.2	%	
Phosphorus, total	0.01	%	
Aluminum, total	1890.	mg/kg	4
Antimony, total	-0.10	mg/kg	4
Arsenic, total	0.4	mg/kg	4
Barium, total	10.	mg/kg	4
Boron, total	-2.	mg/kg	4
Cadmium, total	-0.5	mg/kg	4
Calcium, total	700.	mg/kg	4
Chromium, total	-1.	mg/kg	4
Cobalt, total	11.	mg/kg	4
Copper, total	186.	mg/kg	4
Iron, total	41600.	mg/kg	4
Lead, total	2.	mg/kg	4
Magnesium, total	200.	mg/kg	4
Manganese, total	8.	mg/kg	4
Mercury, total	-0.02	mg/kg	4
Molybdenum, total	7.	mg/kg	4
Nickel, total	-2.	mg/kg	4
Potassium, total	1200.	mg/kg	4
Selenium, total	3.9	mg/kg	4
Silver, total	-1.	mg/kg	4
Sodium, total	200.	mg/kg	4
Vanadium, total	1.	mg/kg	4
Zinc, total	7.	mg/kg	4

4 EPA SW846, Method 3051 Digestion.

Remarks:
Note: Negative sign "-" denotes that the value is less than "<"

Scott Habermehl, Project Manager

Frank E. Polniak, Inorganic Laboratory Supervisor

Client : Steffen Robertson and Kirsten
Address : 3232 S. Vance St., Ste. 210
Lakewood, CO 80227
Attn. : Gene Muller
Project : 68605, Copper Flat

Sample Matrix: Waste Rock
Sample ID: 68605, PW-3
Sample Date Time: Unknown

Lab No. : 94-RT/00595
Date Received: 06/10/94

Parameters			
Moisture %	0.3	%	
Phosphorus, total	0.04	%	
Aluminum, total	2950.	mg/kg	4
Antimony, total	-0.10	mg/kg	4
Arsenic, total	1.9	mg/kg	4
Barium, total	24.	mg/kg	4
Boron, total	-2.	mg/kg	4
Cadmium, total	-0.5	mg/kg	4
Calcium, total	700.	mg/kg	4
Chromium, total	-1.	mg/kg	4
Cobalt, total	9.	mg/kg	4
Copper, total	226.	mg/kg	4
Iron, total	40800.	mg/kg	4
Lead, total	4.	mg/kg	4
Magnesium, total	800.	mg/kg	4
Manganese, total	39.	mg/kg	4
Mercury, total	-0.02	mg/kg	4
Molybdenum, total	57.	mg/kg	4
Nickel, total	3.	mg/kg	4
Potassium, total	1300.	mg/kg	4
Selenium, total	9.0	mg/kg	4
Silver, total	-1.	mg/kg	4
Sodium, total	200.	mg/kg	4
Vanadium, total	5.	mg/kg	4
Zinc, total	14.	mg/kg	4

4 EPA SW846, Method 3051 Digestion.
Remarks:
Note: Negative sign "-" denotes that the value is less than "<"

Scott Habermehl, Project Manager/SH.

Frank E. Polniak, Inorganic Laboratory Supervisor/FP

ACZ Laboratories, Inc.
30400 Downhill Drive
Steamboat Springs, CO 80487
(800) 334-5493

Lab Sample ID: *L10307-12*
Client Sample ID: *P5-TTLS*
Client Project ID: *68610*
ACZ Report ID: *RG29617*

Steffen Robertson And Kirsten
7175 W. Jefferson Ave. Suite 3000
Lakewood, CO 80235
Tony Melon

Date Sampled: *7/8/96 00:00*
Date Received: *7/12/96*
Date Reported: *8/14/96*

Sample Matrix: *Soil*

Metals Analysis

Parameter	EPA Method	Result	Qual	Units	MDL	PQL	Date	Analyst
Aluminum (1312-DI)	M6010 ICP	0.04	B	mg/L	0.03	0.2	8/12/96	rs
Antimony (1312-DI)	M200.7 ICP		U	mg/L	0.02	0.1	8/12/96	rs
Arsenic (1312-DI)	M7060 GFAA		U	mg/L	0.001	0.006	7/18/96	sh
Barium (1312-DI)	M200.7 ICP	0.026		mg/L	0.003	0.01	8/12/96	rs
Boron (1312-DI)	M6010 ICP		U	mg/L	0.01	0.06	8/12/96	rs
Cadmium (1312-DI)	M200.7 ICP		U	mg/L	0.003	0.02	8/12/96	rs
Calcium (1312-DI)	M200.7 ICP	177.0		mg/L	0.2	1	8/12/96	rs
Chromium (1312-DI)	M200.7 ICP		U	mg/L	0.01	0.06	8/12/96	rs
Cobalt (1312-DI)	M200.7 ICP		U	mg/L	0.01	0.06	8/12/96	rs
Copper (1312-DI)	M200.7 ICP	0.01	B	mg/L	0.01	0.06	8/12/96	rs
Iron (1312-DI)	M200.7 ICP	0.01	B	mg/L	0.01	0.06	8/12/96	rs
Lead (1312-DI)	M200.7 ICP		U	mg/L	0.02	0.1	8/12/96	rs
Magnesium (1312-DI)	M200.7 ICP	12.4		mg/L	0.2	1	8/12/96	rs
Manganese (1312-DI)	M6010 ICP	0.157		mg/L	0.006	0.03	8/12/96	rs
Molybdenum (1312-DI)	M200.7 ICP	0.14		mg/L	0.01	0.06	8/12/96	rs
Nickel (1312-DI)	M200.7 ICP		U	mg/L	0.01	0.06	8/12/96	rs
Potassium (1312-DI)	M200.7 ICP	10.9		mg/L	0.3	1	8/12/96	rs
Selenium, (1312-DI)	M7742 Modified, AA-Hydride	0.004	B	mg/L	0.001	0.005	7/22/96	rd
Silver (1312-DI)	M200.7 ICP		U	mg/L	0.006	0.03	8/12/96	rs
Sodium (1312-DI)	M200.7 ICP	1.6		mg/L	0.3	1	8/12/96	rs
Vanadium (1312-DI)	M6010 ICP		U	mg/L	0.006	0.03	8/12/96	rs
Zinc (1312-DI)	M200.7 ICP	0.01	B	mg/L	0.01	0.06	8/12/96	rs

Soil Analysis

Parameter	EPA Method	Result	Qual	Units	MDL	PQL	Date	Analyst
Acid Generation Potential	Calc. M600/2-78-054	37		tons/KT	1	5	7/29/96	as
Acid Neutralization Potential	Calc. M600/2-78-054	26		tons/KT	1	5	7/29/96	as
Acid-Base Potential (calc)	M600/2-78-054 1.	-11		tons/KT	1	5	7/29/96	as
Neutralization Potential as CaCO3	M600/2-78-054 3.2.3	2.6		%	0.1	0.5	7/29/96	jm
Sulfur Forms	M600/2-78-054 3.2.4							
Sulfur Organic		0.29		%	0.01	0.1	7/27/96	jb
Sulfur Pyritic		0.53		%	0.01	0.1	7/27/96	jb
Sulfur Sulfate		0.37		%	0.01	0.1	7/27/96	jb
Sulfur Total		1.19		%	0.01	0.1	7/27/96	jb

Inorganic Qualifiers (based on EPA CLP 3/90)

U = Analyte was analyzed for but not detected at the indicated MDL
B = Analyte concentration detected at a value between MDL and PQL
PQL = Practical Quantitation Limit

Ralph V. Poulsen

Vice President of Operations: Ralph Poulsen

ACZ Laboratories, Inc.
30400 Downhill Drive
Steamboat Springs, CO 80487
(800) 334-5493

Lab Sample ID: *L10307-11*
Client Sample ID: *P4-UTLS*
Client Project ID: *68610*
ACZ Report ID: *RG29616*

Steffen Robertson And Kirsten
7175 W. Jefferson Ave. Suite 3000
Lakewood, CO 80235
Tony Melon

Date Sampled: *7/8/96 00:00*
Date Received: *7/12/96*
Date Reported: *8/14/96*

Sample Matrix: *Soil*

Metals Analysis

Parameter	EPA Method	Result	Qual	Units	MDL	PQL	Date	Analyst
Aluminum (1312-DI)	M6010 ICP	0.05	B	mg/L	0.03	0.2	8/12/96	rs
Antimony (1312-DI)	M200.7 ICP		U	mg/L	0.02	0.1	8/12/96	rs
Arsenic (1312-DI)	M7060 GFAA		U	mg/L	0.001	0.006	7/18/96	sh
Barium (1312-DI)	M200.7 ICP	0.019		mg/L	0.003	0.01	8/12/96	rs
Boron (1312-DI)	M6010 ICP		U	mg/L	0.01	0.06	8/12/96	rs
Cadmium (1312-DI)	M200.7 ICP		U	mg/L	0.003	0.02	8/12/96	rs
Calcium (1312-DI)	M200.7 ICP	60.4		mg/L	0.2	1	8/12/96	rs
Chromium (1312-DI)	M200.7 ICP		U	mg/L	0.01	0.06	8/12/96	rs
Cobalt (1312-DI)	M200.7 ICP		U	mg/L	0.01	0.06	8/12/96	rs
Copper (1312-DI)	M200.7 ICP		U	mg/L	0.01	0.06	8/12/96	rs
Iron (1312-DI)	M200.7 ICP	0.01	B	mg/L	0.01	0.06	8/12/96	rs
Lead (1312-DI)	M200.7 ICP		U	mg/L	0.02	0.1	8/12/96	rs
Magnesium (1312-DI)	M200.7 ICP	6.4		mg/L	0.2	1	8/12/96	rs
Manganese (1312-DI)	M6010 ICP	0.013	B	mg/L	0.006	0.03	8/12/96	rs
Molybdenum (1312-DI)	M200.7 ICP	0.10		mg/L	0.01	0.06	8/12/96	rs
Nickel (1312-DI)	M200.7 ICP		U	mg/L	0.01	0.06	8/12/96	rs
Potassium (1312-DI)	M200.7 ICP	6.8		mg/L	0.3	1	8/12/96	rs
Selenium, (1312-DI)	M7742 Modified, AA-Hydride	0.003	B	mg/L	0.001	0.005	7/22/96	rd
Silver (1312-DI)	M200.7 ICP		U	mg/L	0.006	0.03	8/12/96	rs
Sodium (1312-DI)	M200.7 ICP	3.2		mg/L	0.3	1	8/12/96	rs
Vanadium (1312-DI)	M6010 ICP		U	mg/L	0.006	0.03	8/12/96	rs
Zinc (1312-DI)	M200.7 ICP		U	mg/L	0.01	0.06	8/12/96	rs

Soil Analysis

Parameter	EPA Method	Result	Qual	Units	MDL	PQL	Date	Analyst
Acid Generation Potential	Calc. M600/2-78-054	42		tons/KT	1	5	7/29/96	as
Acid Neutralization Potential	Calc. M600/2-78-054	25		tons/KT	1	5	7/29/96	as
Acid-Base Potential (calc)	M600/2-78-054 1.	-17		tons/KT	1	5	7/29/96	as
Neutralization Potential as CaCO3	M600/2-78-054 3.2.3	2.5		%	0.1	0.5	7/29/96	jm
Sulfur Forms	M600/2-78-054 3.2.4							
Sulfur Organic		0.41		%	0.01	0.1	7/27/96	jb
Sulfur Pyritic		0.46		%	0.01	0.1	7/27/96	jb
Sulfur Sulfate		0.47		%	0.01	0.1	7/27/96	jb
Sulfur Total		1.34		%	0.01	0.1	7/27/96	jb

Inorganic Qualifiers (based on EPA CLP 3/90)

U = Analyte was analyzed for but not detected at the indicated MDL
B = Analyte concentration detected at a value between MDL and PQL
PQL = Practical Quantitation Limit

Ralph V. Poulsen

Vice President of Operations: Ralph Poulsen

01268

ACZ Laboratories, Inc.
30400 Downhill Drive
Steamboat Springs, CO 80487
(800) 334-5493

Lab Sample ID: *L10307-10*
Client Sample ID: *P3-UTLS*
Client Project ID: *68610*
ACZ Report ID: *RG29615*

Steffen Robertson And Kirsten
7175 W. Jefferson Ave. Suite 3000
Lakewood, CO 80235
Tony Melon

Date Sampled: *7/8/96 00:00*
Date Received: *7/12/96*
Date Reported: *8/14/96*

Sample Matrix: *Soil*

Metals Analysis

Parameter	EPA Method	Result	Qual	Units	MDL	PQL	Date	Analyst
Aluminum (1312-DI)	M6010 ICP	0.12	B	mg/L	0.03	0.2	8/12/96	rs
Antimony (1312-DI)	M200.7 ICP		U	mg/L	0.02	0.1	8/12/96	rs
Arsenic (1312-DI)	M7060 GFAA		U	mg/L	0.001	0.006	7/18/96	sh
Barium (1312-DI)	M200.7 ICP	0.023		mg/L	0.003	0.01	8/12/96	rs
Boron (1312-DI)	M6010 ICP		U	mg/L	0.01	0.06	8/12/96	rs
Cadmium (1312-DI)	M200.7 ICP		U	mg/L	0.003	0.02	8/12/96	rs
Calcium (1312-DI)	M200.7 ICP	14.9		mg/L	0.2	1	8/12/96	rs
Chromium (1312-DI)	M200.7 ICP		U	mg/L	0.01	0.06	8/12/96	rs
Cobalt (1312-DI)	M200.7 ICP		U	mg/L	0.01	0.06	8/12/96	rs
Copper (1312-DI)	M200.7 ICP		U	mg/L	0.01	0.06	8/12/96	rs
Iron (1312-DI)	M200.7 ICP	0.02	B	mg/L	0.01	0.06	8/12/96	rs
Lead (1312-DI)	M200.7 ICP		U	mg/L	0.02	0.1	8/12/96	rs
Magnesium (1312-DI)	M200.7 ICP	0.8	B	mg/L	0.2	1	8/12/96	rs
Manganese (1312-DI)	M6010 ICP	0.010	B	mg/L	0.006	0.03	8/12/96	rs
Molybdenum (1312-DI)	M200.7 ICP	0.06		mg/L	0.01	0.06	8/12/96	rs
Nickel (1312-DI)	M200.7 ICP		U	mg/L	0.01	0.06	8/12/96	rs
Potassium (1312-DI)	M200.7 ICP	8.2		mg/L	0.3	1	8/12/96	rs
Selenium (1312-DI)	M7742 Modified, AA-Hydride	0.003	B	mg/L	0.001	0.005	7/22/96	rd
Silver (1312-DI)	M200.7 ICP		U	mg/L	0.006	0.03	8/12/96	rs
Sodium (1312-DI)	M200.7 ICP	6.0		mg/L	0.3	1	8/12/96	rs
Vanadium (1312-DI)	M6010 ICP		U	mg/L	0.006	0.03	8/12/96	rs
Zinc (1312-DI)	M200.7 ICP	0.01	B	mg/L	0.01	0.06	8/12/96	rs

Soil Analysis

Parameter	EPA Method	Result	Qual	Units	MDL	PQL	Date	Analyst
Acid Generation Potential	Calc. M600/2-78-054	44		tons/KT	1	5	7/29/96	as
Acid Neutralization Potential	Calc. M600/2-78-054	23		tons/KT	1	5	7/29/96	as
Acid-Base Potential (calc)	M600/2-78-054 1.	-21		tons/KT	1	5	7/29/96	as
Neutralization Potential as CaCO3	M600/2-78-054 3.2.3	2.3		%	0.1	0.5	7/29/96	jm
Sulfur Forms	M600/2-78-054 3.2.4							
Sulfur Organic		0.45		%	0.01	0.1	7/27/96	jb
Sulfur Pyritic		0.69		%	0.01	0.1	7/27/96	jb
Sulfur Sulfate		0.26		%	0.01	0.1	7/27/96	jb
Sulfur Total		1.40		%	0.01	0.1	7/27/96	jb

Inorganic Qualifiers (based on EPA CLP 3/90)

U = Analyte was analyzed for but not detected at the indicated MDL
B = Analyte concentration detected at a value between MDL and PQL
PQL = Practical Quantitation Limit

Ralph V. Poulsen

Vice President of Operations: Ralph Poulsen

ACZ Laboratories, Inc.
30400 Downhill Drive
Steamboat Springs, CO 80487
(800) 334-5493

Lab Sample ID: *L10307-09*
Client Sample ID: *P2-UTLS*
Client Project ID: *68610*
ACZ Report ID: *RG29614*

Steffen Robertson And Kirsten
7175 W. Jefferson Ave. Suite 3000
Lakewood, CO 80235
Tony Melon

Date Sampled: *7/8/96 00:00*
Date Received: *7/12/96*
Date Reported: *8/14/96*

Sample Matrix: *Soil*

Metals Analysis

Parameter	EPA Method	Result	Qual	Units	MDL	PQL	Date	Analyst
Aluminum (1312-DI)	M6010 ICP	0.05	B	mg/L	0.03	0.2	8/12/96	rs
Antimony (1312-DI)	M200.7 ICP		U	mg/L	0.02	0.1	8/12/96	rs
Arsenic (1312-DI)	M7060 GFAA		U	mg/L	0.001	0.006	7/18/96	sh
Barium (1312-DI)	M200.7 ICP	0.024		mg/L	0.003	0.01	8/12/96	rs
Boron (1312-DI)	M6010 ICP	0.01	B	mg/L	0.01	0.06	8/12/96	rs
Cadmium (1312-DI)	M200.7 ICP		U	mg/L	0.003	0.02	8/12/96	rs
Calcium (1312-DI)	M200.7 ICP	216.0		mg/L	0.2	1	8/12/96	rs
Chromium (1312-DI)	M200.7 ICP	0.01	B	mg/L	0.01	0.06	8/12/96	rs
Cobalt (1312-DI)	M200.7 ICP		U	mg/L	0.01	0.06	8/12/96	rs
Copper (1312-DI)	M200.7 ICP	0.01	B	mg/L	0.01	0.06	8/12/96	rs
Iron (1312-DI)	M200.7 ICP	0.01	B	mg/L	0.01	0.06	8/12/96	rs
Lead (1312-DI)	M200.7 ICP		U	mg/L	0.02	0.1	8/12/96	rs
Magnesium (1312-DI)	M200.7 ICP	10.4		mg/L	0.2	1	8/12/96	rs
Manganese (1312-DI)	M6010 ICP	0.084		mg/L	0.006	0.03	8/12/96	rs
Molybdenum (1312-DI)	M200.7 ICP	0.09		mg/L	0.01	0.06	8/12/96	rs
ickel (1312-DI)	M200.7 ICP		U	mg/L	0.01	0.06	8/12/96	rs
Potassium (1312-DI)	M200.7 ICP	13.1		mg/L	0.3	1	8/12/96	rs
Selenium (1312-DI)	M7742 Modified, AA-Hydride	0.003	B	mg/L	0.001	0.005	7/22/96	rd
Silver (1312-DI)	M200.7 ICP		U	mg/L	0.006	0.03	8/12/96	rs
Sodium (1312-DI)	M200.7 ICP	7.9		mg/L	0.3	1	8/12/96	rs
Vanadium (1312-DI)	M6010 ICP		U	mg/L	0.006	0.03	8/12/96	rs
Zinc (1312-DI)	M200.7 ICP	0.01	B	mg/L	0.01	0.06	8/12/96	rs

Soil Analysis

Parameter	EPA Method	Result	Qual	Units	MDL	PQL	Date	Analyst
Acid Generation Potential	Calc. M600/2-78-054	34		tons/KT	1	5	7/29/96	as
Acid Neutralization Potential	Calc. M600/2-78-054	27		tons/KT	1	5	7/29/96	as
Acid-Base Potential (calc)	M600/2-78-054 1.	-7		tons/KT	1	5	7/29/96	as
Neutralization Potential as CaCO3	M600/2-78-054 3.2.3	2.7		%	0.1	0.5	7/29/96	jm
Sulfur Forms	M600/2-78-054 3.2.4							
Sulfur Organic		0.21		%	0.01	0.1	7/27/96	jb
Sulfur Pyritic		0.43		%	0.01	0.1	7/27/96	jb
Sulfur Sulfate		0.46		%	0.01	0.1	7/27/96	jb
Sulfur Total		1.10		%	0.01	0.1	7/27/96	jb

Inorganic Qualifiers (based on EPA CLP 3/90)

= Analyte was analyzed for but not detected at the indicated MDL

B = Analyte concentration detected at a value between MDL and PQL

PQL = Practical Quantitation Limit

Ralph V. Poulsen

Vice President of Operations: Ralph Poulsen

SRK Consulting (UK) Ltd
5th Floor Churchill House
17 Churchill Way
Cardiff
United Kingdom
CF10 2HH
e-mail: cardiff@srk.co.uk
URL: www.srk.co.uk
Tel: + 44 (0)29 20 34 81 50
Fax: + 44 (0)29 20 34 81 99

TECHNICAL MEMORANDUM

TO: Steve Raugust, New Mexico Copper Corporation

COPY TO: Ann Carpenter, Remote Energy Solutions

FROM: Rob Bowell, Ruth Warrender, Amy Prestia **DATE:** 06 December 2010

SUBJECT: **Copper Flat Static Testwork Summary and Kinetic Test Recommendations**

1. INTRODUCTION

SRK Consulting has undertaken a geochemical characterization study to assess the Acid Rock Drainage and Metal Leaching (ARDML) potential of the Copper Flat deposit, New Mexico. This memorandum details the results of the initial characterization of the collected materials and includes recommendations for additional kinetic testwork.

A total of 74 representative grab and core samples were collected by SRK during a site visit in April 2010. A sample matrix summarising the main material types (as defined by rock and alteration type) is provided in Table 1. The collected samples were subject to a number of static geochemical tests in order to characterize the nature of materials on site and to determine their potential for ARDML generation. This included Multi Element Analysis, Acid Base Accounting (ABA), Net Acid Generation (NAG) testing and an assessment of the potential short-term metal mobility (MWMP testing). A summary of the methods used and the results of this testwork are provided below. In addition, the complete geochemical database detailing the results of the ARDML assessment has been included as an attachment to this memorandum.

Table 1: Details of samples collected for the ARDML assessment

Lithology	Alteration	ABA/NAG/Multi-Element			MWMP		
		Drillcore	Grab	Total	Drillcore	Grab	Total
Dolerite	Propylitic		2	**2**		2	**2**
Andesite	Propylitic		4	**4**		2	**2**
Quartz Monzonite	Argillic	6	2	**8**	3	2	**5**
	Biotite	3	1	**4**	1	1	**2**
	Leach Cap	5	4	**9**	2	2	**4**
	Potassic	6		**6**	3		**3**
	Propylitic	3		**3**	1		**1**
	Quartz Sericite	5	4	**9**	2	2	**4**
Quartz Monzonite Breccia	Argillic	5	1	**6**	2	1	**3**
	Biotite	6		**6**	2		**2**
	Leach Cap	2	1	**3**	1	1	**2**
	Potassic	2	1	**3**	2	1	**3**
	Propylitic	4		**4**	3		**3**
	Quartz	3		**3**	2		**2**
Tailings	-		4	**4**		2	**2**
Total		**50**	**24**	**74**	**24**	**16**	**40**

2. MULTI-ELEMENT ANALYSIS

Multi-element analysis was carried out to allow comprehensive geochemical characterisation of the 74 samples. The analysis was carried out by ALS Chemex, Reno, Nevada and involved a strong multi-acid digestion followed by Inductively Coupled Plasma Mass Spectrometry (ICP-MS) analysis. This included determination of major elements (e.g. aluminium, calcium, magnesium, sodium, potassium, iron, sulfur) and trace elements (e.g. zinc, copper, cadmium, lead).

The data were analyzed using the Geochemical Abundance Index (GAI) (INAP, 2002), which compares the concentration of an element in a given sample to its average crustal abundance. GAI values are particularly useful in determining the relative enrichment of elements based on lithology and may be used to identify elements enriched above average crustal concentrations ('ECA elements'). GAI values were calculated as follows:

$$GAI = \log_2 [C/(1.5*S)]$$

Where C is the concentration of an element as determined from the WRA and S is the average crustal abundance of the element of interest (Mason, 1966). Materials are then assigned a GAI value between zero and six based on the degree of enrichment (Table 2). According to the INAP (2002) protocol, a GAI value greater than three indicates significant enrichment.

Table 2: Interpretation of GAI values for WRA data

GAI Value	Interpretation
0	<3 times average crustal concentration
1	3 to 6 times average crustal concentration
2	6 to 12 times average crustal concentration
3	12 to 24 times average crustal concentration
4	24 to 48 times average crustal concentration
5	48 to 96 times average crustal concentration
6	>96 times average crustal concentration

The results of the multi-element analysis are provided in full in the attached database and are summarized in Table 3. The results show that all material types are characterized by elevated concentrations of silver, cadmium, copper, molybdenum, rhenium, sulfur, selenium, tellurium and tungsten, with GAI values between 1 and 6 representing up to 96 times enrichment of average crustal concentrations. Copper concentrations were elevated up to 1 wt% in the samples and sulfur concentrations reached 3.34 wt%, with particular enrichment occurring in the Argillic Breccia and the Breccia-Leach Cap materials. These elevated concentrations are associated with the sulfide mineralization, whilst the elevated concentrations of molybdenum, silver, rhenium, arsenic and zinc in the materials can be explained by the common association of these elements with porphyry copper deposits (Rose, Hawkes and Webb, 1979). The leachability of ECA elements from the material types will be examined from metal mobility (MWMP) tests, which will account for site-specific factors affecting mineral solubility.

Table 3: Summary of Multi Element Analysis Results

	#	Multi Element Anlysis - average concentrations per lithology/alteration type (mg/kg)																			
		Ag	As	Bi	Ca	Cd	Cs	Cu	Mo	Pb	Rb	Re	S	Sb	Se	Te	Th	Tl	U	W	Zn
Average crustal abundance (mg/kg)		*0.07*	*1.8*	*0.2*	*36,300*	*0.2*	*3*	*55*	*1.5*	*13*	*90*	*0.001*	*260*	*0.2*	*0.05*	*0.01*	*7.2*	*0.5*	*1.8*	*1.5*	*70*
Andesite - Propylitic	4	0.3	0.9	0.6	39,650	0.6	6.4	217	5.4	8.7	138	0.005	925	0.4	2.0	0.2	6.4	1.3	2.1	2.2	60
Breccia - Argillic	6	3.8	10.9	1.8	10,400	1.0	7.4	3,882	197	127.6	225	0.287	17,267	0.6	4.3	0.8	22.3	1.7	5.8	9.5	134
Breccia - Biotite	6	2.3	6.5	1.3	10,700	1.0	10.2	2,701	38	39.2	222	0.061	16,950	0.4	3.3	0.6	26.3	1.7	8.4	7.1	133
Breccia - Leach Cap	3	4.3	18.7	1.6	4,533	2.9	12.2	4,000	88	90.8	211	0.145	23,333	2.7	4.0	0.8	29.2	2.1	6.7	6.5	316
Breccia - Potassic	3	1.9	28.3	0.8	15,333	0.9	7.4	2,549	162	25.5	216	0.241	16,567	0.8	4.3	0.2	20.1	2.0	6.7	9.8	108
Breccia - Propylitic	4	5.2	3.6	9.2	12,725	2.5	16.3	4,796	308	46.9	245	0.269	17,250	0.4	5.0	1.3	38.0	1.9	4.3	8.6	337
Breccia - Quartz	3	4.0	24.7	1.3	11,967	1.0	7.7	4,580	114	69.9	245	0.096	14,000	0.8	4.0	0.4	26.4	1.7	10.1	8.7	127
Dolerite - Propylitic	2	0.2	0.4	0.0	58,550	2.3	6.5	1,664	4.4	6.1	62	0.028	1,350	0.2	2.5	0.1	4.7	0.3	4.9	1.0	213
Quartz Monzonite - Argillic	8	2.4	1.6	1.1	13,563	1.1	9.8	2,480	54	72.4	242	0.050	9,213	0.4	3.1	0.3	21.2	1.8	5.0	11.9	146
Quartz Monzonite - Biotite	4	1.0	1.1	0.5	4,900	0.8	7.8	1,734	109	43.7	270	0.133	6,225	0.2	2.0	0.1	31.8	1.9	8.6	8.4	119
Quartz Monzonite - Leach Cap	9	3.0	1.9	2.1	11,811	1.6	8.7	3,784	47	63.8	264	0.055	9,267	0.5	3.6	0.7	23.6	1.8	6.2	12.2	181
Quartz Monzonite - Potassic	6	1.3	1.3	1.0	14,467	0.6	8.5	1,788	52	38.1	227	0.065	8,700	0.3	2.5	0.2	21.7	1.4	5.7	9.2	96
Quartz Monzonite - Propylitic	3	0.7	1.4	0.5	21,100	1.3	13.0	856	20	29.5	216	0.017	5,167	0.3	1.0	0.1	11.5	1.2	3.6	5.6	186
Quartz Monzonite - Quartz Sericite	9	1.1	1.2	0.8	11,278	0.2	6.9	1,407	143	31.6	250	0.072	14,311	0.3	3.0	0.2	17.6	1.6	5.1	9.1	47
Tailings-North Dam	2	1.3	5.1	1.6	16,400	0.4	8.9	1,175	44	28.9	286	0.062	13,100	0.4	3.5	0.4	25.4	2.1	7.5	9.7	69
Tailings - South Dam	2	0.1	6.0	0.3	168,500	0.1	5.7	53	1	12.3	73	0.002	400	0.4	1.5	0.1	6.5	0.6	4.1	1.6	53
Average (all lithologies)	74	2.2	5.6	1.6	18,980	1.1	8.9	2,489	92	51.4	226	0.099	11,458	0.5	3.2	0.4	21.6	1.6	5.9	8.6	140

# = number of samples representing material type
GAI = 0 represents < 3 times average crustal concentrations
GAI = 1 represents 3 to 6 times average crustal concentrations
GAI = 2 represents 6 to 12 times average crustal concentrations
GAI = 3 represents 12 to 24 times average crustal concentrations
GAI = 4 represents 24 to 48 times average crustal concentrations
GAI = 5 represents 48 to 96 times average crustal concentrations
GAI = 6 represents greater than 86 times average crustal concentrations

3. ACID BASE ACCOUNTING

Acid Base Accounting (ABA) testwork was carried out by SVL laboratories using a modified Sobek method. The testwork was carried out in order to evaluate the acid generating (AP) based on speciated sulfur analysis and neutralizing potential (NP) of the samples was determined by using the modified Sobek protocol that includes a digestion to expel any CO_2 followed by a back titration with NaOH to a pH of 8.3 s.u.

The balance between the acid generating mineral phases and acid neutralizing mineral phases is referred to as the net neutralization potential (NNP), which is equal to the difference between NP and AP. The NNP allows classification of the samples as potentially acid consuming or acid producing. A positive value of NNP indicates the sample neutralizes more acid than is produced during oxidation. A negative NNP value indicates there are more acid producing constituents than acid neutralizing constituents. Material that would be considered to have a high potential for acid neutralization produce a net neutralizing potential of greater than 20 eq. kg $CaCO_3$/ton. Acid Base Accounting data is also described using the neutralization potential ratio, which is calculated by dividing the NP by the AP (i.e., NP:AP).

Acid Base Accounting results are typically compared to criteria provided by the BLM (2004) in order to determine the potential for the waste rock material to generate acid. The Nevada BLM Water Resource Data and Analysis Guide for Mining Activities (BLM 2004) establishes the following guidelines for the evaluation of ABA test results:

- NP:AP values greater than 3 and NNP values greater than 20 eq. kg CaCO3/ton are not acid generating and do not require further testing; and
- NP:AP values less than 3 and/or NNP values less than 20 eq. kg CaCO3/ton have uncertain potential and require further evaluation using kinetic test methods.

The criteria used for the assessment of acid generation for Copper Flat materials are outlined in Table 4.

Table 4: Interpretation of Copper Flat ABA data

	NNP (kg $CaCO_3$ eq/t)	NPR
Potentially Acid Forming (PAF)	NNP < -20	NPR < 1
Non Acid Forming (NAF)	NNP > +20	NPR > 3
Area of Uncertainty	NNP between -20 and +20	NPR between 1 and 3

The ABA testwork results for the Copper Flat samples are provided in full in the attached database and are summarized in Table 5. The samples were found to have an average acid generating potential of 27.7 kg $CaCO_3$ eq/t and an average neutralizing potential of 24 kg $CaCO_3$ eq/t, indicating a slight surplus of acidity in the samples. This is supported by Figure 1, which shows the samples generally tend towards net acid generating rather than net neutralising. A scatter plot comparing the acid generating and neutralizing potential of the samples as a function of material type is given in Figure 2. This demonstrates that the samples are variable in terms of their acid generating potential. Fifty-four percent of samples exhibited potentially acid forming (PAF) characteristics based on NPR values less than 1 (Figure 2). This included all samples of Biotite Breccia, Breccia-Leach Cap, Argillic Breccia, Quartz Breccia, Quartz Monzonite–Leach Cap and Quartz Monzonite–Biotite materials. In contrast, the propylitically altered materials (Andesite – Propylitic, Breccia – Propylitic, Dolerite – Propylitic and Quartz Monzonite – Propylitic) generally exhibited non-acid forming (NAF) characteristics based on NPR values greater than 3.

Figure 3 shows that the net neutralizing capacity of the Copper Flat samples is largely dependent on the sulfide sulfur content of the materials. Samples with a high sulfide sulfur content (up to 2.52 wt%) are generally characterized by a lower net neutralizing potential.

Table 5: Summary of Acid Base Accounting results

Lithology	Alteration	#	Sulfide sulfur (wt%)	AP ($CaCO_3$ eq/t)		NP ($CaCO_3$ eq/t)		NNP ($CaCO_3$ eq/t)		NPR	
				Mean	S.D.	Mean	S.D.	Mean	S.D.	Mean	S.D.
Andesite	Propylitic	4	0.08	2.50	4.40	23.8	1.58	21.5	6.04	61.9	39.7
Breccia	Argillic	6	1.39	43.4	19.3	23.7	12.3	-19.7	12.7	0.54	0.22
Breccia	Biotite	6	1.35	42.3	19.2	24.6	7.11	-17.7	26.2	0.76	0.50
Breccia	Leach cap	3	1.84	57.4	21.8	14.7	4.66	-42.7	26.0	0.31	0.25
Breccia	Potassic	3	1.17	36.6	9.89	35.0	13.4	-1.57	23.2	1.09	0.76
Breccia	Propylitic	4	1.46	45.6	23.7	34.8	5.80	-10.8	27.1	1.01	0.65
Breccia	Quartz	3	1.00	31.3	4.15	28.6	1.55	-2.73	3.88	0.92	0.10
Dolerite	Propylitic	2	0.02	0.60	0.42	44.4	49.1	43.9	49.8	137	179
Quartz monzonite	Argillic	8	0.66	20.6	13.9	19.9	10.21	-0.74	16.6	1.41	1.09
Quartz monzonite	Biotite	4	0.43	13.3	3.54	5.88	1.79	-7.40	2.93	0.45	0.13
Quartz monzonite	Leach cap	9	0.63	19.8	10.9	19.8	22.4	-0.01	21.8	3.93	8.95
Quartz monzonite	Potassic	6	0.62	19.5	7.30	26.4	13.9	6.97	18.6	1.77	1.52
Quartz monzonite	Propylitic	3	0.45	14.1	1.25	41.5	3.77	27.4	3.16	2.96	0.22
Quartz monzonite	Quartz sericite	9	1.07	33.3	22.0	21.0	19.1	-12.4	37.5	1.07	1.06
All lithologies		**74**	**0.86**	**27.7**	**19.8**	**24.0**	**62.9**	**6.92**	**70.4**	**43.3**	**217**

Number of samples representing material type
Potentially acid forming (PAF)
Potentially acid forming (lower capacity)
Non Acid Forming (NAF)



Figure 1: Neutralization Potential Ratio (NPR) vs. Net Neutralizing Potential (NNP)



Figure 2: Scatter Plot of Acid Generating Potential vs. Neutralizing Potential



Figure 3: Scatter Plot of Sulfide Sulfur vs. Net Neutralizing Potential (NNP)

4. STATIC NAG TESTING

Static Net Acid Generation (NAG) testwork was carried out in order to determine the maximum potential for acid generation from the Copper Flat samples. The static NAG test differs from the ABA test in that it provides a direct empirical estimate of the overall sample reactivity, including any acid generated by semi-soluble sulfate minerals (i.e., jarosite) as well as other potentially acid-generating sulfate and sulfide minerals. As such, the NAG test often provides a better estimate of field acid generation than the more widely-used ABA method, which defines acid potential based solely on sulfide content.

NAG testing was carried out by SVL laboratories in accordance with the method described by Miller et al. (1997). The method essentially involved intensive oxidation of the sample using hydrogen peroxide (H_2O_2), which accelerates the dissolution of sulfide minerals and has the net result that acid production and neutralisation can be measured directly.

The leachate was then titrated with sodium hydroxide in two stages (to pH 4.5 and to pH 7) to determine the NAG value, which was calculated as follows:

$$NAG = (V_{Init} / X) (49 * V_{NaOH} * M) / W$$

Where:
NAG = net acid generation (kg H2SO4/tonne);
V_{Init} = volume of initial hydrogen peroxide solution (mL);
X = volume used to determine NAG by titration (mL);
V_{NaOH} = volume of NaOH used in titration (mL);
M = concentration of NaOH used in titration (moles/litre); and
W = weight of sample reacted (g).

In general a NAG pH less than 4.5 and a NAG value greater than 5 kg H_2SO_4 per tonne are indicative of a potentially acid forming material.

The static NAG data for the Copper Flat samples are provided in full in the attached database and are summarized in Table 6. A scatter plot comparing NAG pH with net acid generation (in kg H_2SO_4 equivalents per ton) according to material type is given in Figure 4. Most material types were found to be characterized by a NAG pH greater than 4.5 and a NAG value of zero, indicating that they are unlikely to be problematic in terms of long-term acid generation. However, several material types were characterized by lower NAG pH values (2.26 – 3.76 s.u.) and indicated the potential to generate up to 44 kg H_2SO_4 per ton. In particular the Breccia-Leach Cap and the Quartz Monzonite-Quartz Sericite materials can be classified as higher capacity PAF materials based on static NAG values generally greater than 20 kg H_2SO_4 eq/t. In addition, two samples of Biotite Breccia material and two samples of Argillic Breccia material exhibited higher capacity PAF characteristics based on a NAG pH between 2.98 and 3.77 s.u. and static NAG values up to 20.5 kg H_2SO_4 eq/t. The Quartz Monzonite-Biotite material exhibited lower capacity PAF characteristics based on NAG values between 5 and 10 kg H_2SO_4 eq/t.

Comparison of ABA and static NAG testwork results suggests that sulfide sulfur content is not the sole control on the acid generating potential of the Copper Flat materials; the net neutralizing potential (NNP) of the materials was also found to influence the long-term potential for acid generation (see Figure 5 and Figure 6). Samples with a high sulfide sulfur content and high NNP were generally found to be non-acid forming based on NAG testwork results, whereas samples with a low NNP were generally found to show a greater potential for acid formation (Figure 5).

Table 6: Summary of Static NAG results

Lithology	Alteration	#	NAG pH		NAG value (kg H_2SO_4 eq/t)	
			Mean	S.D.	Mean	S.D.
Andesite	Propylitic	4	6.50	2.23	1.23	2.45
Breccia	Argillic	6	6.60	2.52	4.74	7.62
Breccia	Biotite	6	6.61	2.71	6.29	9.79
Breccia	Leach cap	3	2.98	0.20	19.5	9.27
Breccia	Potassic	3	7.50	2.14	0	0
Breccia	Propylitic	4	7.53	2.22	0	0
Breccia	Quartz	3	8.62	0.59	0	0
Dolerite	Propylitic	2	8.69	1.94	0	0
Quartz monzonite	Argillic	8	7.70	2.57	1.13	3.19
Quartz monzonite	Biotite	4	4.88	2.38	4.07	2.73
Quartz monzonite	Leach cap	9	6.69	2.01	0.75	2.25
Quartz monzonite	Potassic	6	8.01	2.17	0	0
Quartz monzonite	Propylitic	3	8.37	0.20	0	0
Quartz monzonite	Quartz sericite	9	5.84	3.19	14.2	19.3
Tailings - North Dam	-	2	8.78	0.33	0	0
Tailings - South Dam	-	2	10.32	0.87	0	0
All lithologies		**74**	**6.96**	**2.50**	**3.91**	**9.33**

#	Number of samples representing material type
	Potentially Acid Forming (PAF)
	Potentially Acid Forming Lower Capacity



Figure 4: Scatter Plot of NAG pH vs. Net Acid Generation Potential



Figure 5: Scatter Plot of Net Acid Generation Potential vs. Net Neutralizing Potential



Figure 6: Scatter Plot of Sulfide Sulfur vs. Net Acid Generation Potential

5. SHORT-TERM METAL LEACHING (MWMP)

Meteoric Water Mobility Procedure (MWMP) testing was carried out by ALS Chemex, Reno, Nevada to give an indication of short-term metal mobility from the Copper Flat materials. In particular the release of ECA elements (elements identified as being present at concentrations above average crustal abundance) was studied. The MWMP test was developed to simulate the leaching of weather mine waste materials with meteoric water during precipitation events. The results of the MWMP test can be used to identify the presence of leachable metals and readily soluble salts stored in the material as well as provide an indication of their availability for dissolution and transport in response to a precipitation event. A total of 40 representative samples were selected for MWMP testing (Table 1) based on the results of ABA and NAG testwork.

The results of the MWMP testing are provided in full in the attached database and the main findings are summarized below. In general, metal mobility and metal leaching from the Copper Flat materials was found to be low, with ECA elements generally being released at concentrations below analytical detection limits in the MWMP leachates. Furthermore, the leachates were generally characterized by circum-neutral to moderately alkaline pH (pH 6.9 – 8.8 s.u.).

Scatter plots of Ficklin metal release as a function of leachate pH and sulfide sulfur content are given in Figure 7 and Figure 8, respectively. The Ficklin plot in Figure 7 demonstrates that most leachates can be classified as 'near-neutral, low metal' solutions based on an MWMP pH between 6.9 and 8.8 s.u. However, 20% of leachates can be classified as acid with moderate to high metal concentrations based on a leachate pH between 3.02 and 5.5 and total Ficklin metal concentrations up to 292 mg/L (cadmium + cobalt + copper + nickel + lead + zinc). Further analysis of the static data demonstrated that the samples which showed higher levels of metal and acidity release were grab samples collected from the waste rock dumps (rather than core material). Furthermore, the majority of the metal load from the grab samples was found to be made up of copper (Figure 9), thus suggesting that the elevated metal release was related to the flushing of soluble copper salts from the surface of the waste rock materials rather than the oxidation of sulfide minerals. This hypothesis is further supported by the poor correlation between Ficklin metal release and the sulfide sulfur content of the materials (Figure 8).



Figure 7: Scatter Plot of MWMP pH vs. Ficklin Metal Release



Figure 8: Scatter Plot of Sulfide Sulfur vs. MWMP Ficklin Metal Release



Figure 9: Histogram of Percentage Contribution of Parameters to Total Ficklin Metal Release in MWMP test (Grab Samples)

6. REMAINING TESTWORK

The objective of the static testing was to allow rapid assessment of the acid generating and metal leaching characteristics of the main lithological units that will be exposed on site at Copper Flat. However, these static tests do not consider the temporal variations that may occur in leachate chemistry as a result of long-term changes in oxidation, dissolution and desorption reaction rates. Because chemical weathering kinetics is known to strongly affect solute release over time, the results of these static tests ideally need to be confirmed using kinetic methods. Kinetic tests (e.g. laboratory humidity cell tests) evaluate temporal changes in leachate chemistry, through the sequential leaching of the rock weathered in a regular cycle of exposure to dry and wet air in a controlled laboratory environment. These cycles simulate and accelerate the chemical weathering rates observed under field conditions, using test conditions that are specifically designed to target oxidation of sulfide minerals. The goal of kinetic testing is to provide reaction rate data to support prediction of the leachate chemistry that would likely develop during meteoric rinsing of waste rock storage area facilities. Kinetic test data can also be used to predict concentrations of constituents that would be released from pit wall rock in response to meteoric rinsing and to develop a prediction of future pit lake water quality.

A sub-set of samples from the Copper Flat static test database have been selected for kinetic testing. The samples selected for HCT testing are summarized in Table 7 below along with the prediction of acid and metal release from the static test data (i.e., ABA, NAG and MWMP tests). These samples represent the range of predicted geochemistry for the waste rock and pit wall rock types for Copper Flat.

As discussed above, the BLM only considers waste rock to be non-acid generating without kinetic testing if there is 300 percent excess neutralizing capacity (i.e., NP:AP> 3) and the NNP is greater than 20 eq. kg $CaCO_3$/ton. According to the BLM guidance (2004) samples that do not meet these criteria require kinetic testing to define the acid generating potential. The majority of the Copper Flat samples demonstrate an uncertain potential for acid generation with NP:AP values less than 3 and NNP values less than 20 eq. kg $CaCO_3$/ton.

Kinetic testing proposed for this project is the standard humidity cell test procedure designed to simulate water-rock interactions (ASTM D-5744-96). This test runs for a minimum of 20 weeks and follows a seven-day cycle until steady state conditions are achieved. During the seven-day cycle, water is trickled over the rock for two days. Air that is humidified slightly above room temperature is introduced at the bottom of the column for two days of each cycle followed by two days of dry air. On the seventh day, the sample is rinsed with distilled water and the extracted solution is collected for analysis. Key parameters including; pH, alkalinity, acidity, electrical conductivity, iron and sulfate are measured on a weekly basis. Metals are typically

measured on a weekly basis for the first 4 weeks of testing. After this, the frequency of metals analysis can be reduced to every fourth week.

Table 7: Samples selected for kinetic testing

Lithology	Alteration	Sample ID	Type	Pyritic Sulfur	NNP	NPR	NAG pH	Total NAG	MWMP pH	Metals Release
Andesite	Propylitic	SRK 0864	Grab	0.01	24.4	81.3	8.29	0	7.18	Low
		SRK 0866	Grab	0.29	12.5	2.37	3.23	4.9	6.92	Low
Breccia	Argillic	604811	Core	1.15	-3.9	0.89	8.42	0	8.24	Low
		SRK 0854	Grab	0.88	-21.5	0.22	3.77	10.98	4.54	High
	Biotite	604767	Core	2.13	-49.9	0.25	3.21	17.26	7.8	Low
		605033	Core	0.9	1.1	1.04	8.3	0	8.37	Low
	Leach Cap	SRK 0872	Grab	1.05	-13.0	0.60	3.14	8.82	3.05	Moderate
	Propylitic	604862	Core	1.16	3.5	1.10	8.28	0	8.11	Low
		604867	Core	2.34	-46.2	0.37	4.24	0	8.06	Low
	Quartz	604787	Core	0.97	-0.2	0.99	8	0	8.28	Low
	Potassic	604854	Core	1.4	-20.6	0.53	5.08	0	8.16	Low
Quartz Monzonite	Argillic	604562	Core	1.53	-31.6	0.34	7.75	0	8.28	Low
		604606	Core	0.67	2.7	1.13	9.6	0	8.31	Low
	Biotite	604673	Core	0.41	-5.9	0.54	3.66	5.29	8.33	Low
	Leach Cap	604569	Core	1.05	-14.8	0.55	8.33	0	8.25	Low
		SRK 0867	Grab	0.77	-17.7	0.27	4.35	0	4.84	Moderate
	Potassic	604669	Core	0.63	-16.5	0.16	4.08	0	8.39	Low
		604653	Core	0.77	2.3	1.10	8.38	0	--	--
	Propylitic	605153	Core	0.49	26.7	2.75	8.56	0	8.15	Low
	Quartz Sericite	SRK 0858	Grab	0.62	-15.3	0.21	3.15	9.22	3.99	Moderate
		604656	Core	0.59	33.4	2.82	8.2	0	8.27	Low

HCTs are run until steady state effluent chemistry is observed. At which time the tests will be terminated. Steady state is reached once constituent concentrations remain constant for more than four consecutive weeks following evidence of sulfide leaching in previous leaching cycles. After the leaching reactions have been adequately characterized in the HCT, the cell will be rested for two weeks and rinsed again to determine if significant salt accumulation has occurred during the resting period. SRK will also conduct pre-leach and post-leach, ABA, multi-element analysis, and mineralogy on all samples selected for kinetic tests. This further defines the mineralogical processes that occur as the materials are exposed to oxygen and water.

7. LABORATORY COSTS AND SCHEDULE

A total of 21 samples have been selected from the Copper Flat database for kinetic testing. These samples have already been prepared and are being stored at McClelland Laboratories awaiting further instruction. The estimated laboratory costs for the HCTs are summarized in Table 8 below.

Table 8: Estimated kinetic test laboratory costs

Kinetic Test Cost Estimate	Lab	# of samples	Cost Per Sample	Total Cost
Pre-Leach Mineralogy	SRK UK	21	$150	$3,150
Humidity Cell Test Set-up	McClelland	21	$130	$2,730
Humidity Cell Test [1]	McClelland	21	$2,200	$46,200
Profile II for HCT Extracts [1]	WetLAB	21	$3,200	$67,200
Termination Testing (4-Acid Digest, ABA, Min)	SVL	21	$285	$5,985
Reporting	McClelland	21	$750	$15,750
			Total	$141,015

[1] Assumes the HCT will be run for 20 weeks and that samples will be collected for Weeks 0, 1, 2, 3, 4, 8, 12, 16, 20 and final rinse for Profile II testing (10 Profile II tests per sample @ $320/test).

The HCTs will be run until the data indicate that the reactions have stabilized. This can take a minimum of 20 weeks but can take longer depending upon the results. For the purposes of this cost estimate we are assuming that the data we need should be available in 20 weeks. Once the cells have reached a steady-state, the cells will be rested for two weeks and rinsed again to determine if significant salt accumulation has occurred during the resting period. Following the final rinse, a split of the post-leach sample material will be collected for mineralogy, ABA and multi-element analysis. The cost estimate also assumes mineralogy testing will be conducted on the pre-leach samples.

While the kinetic tests are being performed, SRK will continue with the data compilation from the static tests and the analysis of those data. After the final data are available, it will take about six to eight weeks to finalize the analysis of the characterization results and complete the draft report.

8. REFERENCES

INAP (International Network for Acid Production) (2002). Prediction and kinetic control of AMD: Australian Mineral Industries Research Association (AMIRA), Project P387A, May 2002, 42pp.

Mason, B (1966). Principles of Geochemistry. Third Edition. John Wiley, 329pp.

Miller, S., Robertson, A., and Donohue, T. (1997). Advances in Acid Drainage Prediction Using The Net Acid Generation (NAG) Test. In: Proceedings of the Fourth International Conference on Acid Rock Drainage, Vancouver, B.C., Canada, 1997, vol II, pp. 535-547.

Rose, A., Hawkes, H.E. and Webb, J.S. (1979). Geochemistry in Mineral Exploration. Second Edition. Academic Press, 657pp

SRK Consulting (U.S.), Inc.
5250 Neil Road, Suite 300
Reno, Nevada
USA 89502

reno@srk.com
www.srk.com

Tel: 775.828.6800
Fax: 775.828.6820

Technical Memorandum

To:	Cynthia Ardito, Intera Inc.	Date:	March 30, 2011
Cc:	Steve Raugust, New Mexico Copper Corporation	From:	Ruth Warrender, Amy Prestia, Rob Bowell,
Subject:	Copper Flat Geochemical Characterization Program: Incorporation of 1997 Static Test Data	Project #:	191000.03

This memorandum has been prepared by SRK Consulting (SRK) to provide Intera Inc. with a comparison of geochemical data from two separate static testwork programs carried out by SRK in both 1997 and 2010. The memorandum also discusses incorporation of the historic (1997) data into the current (2010/2011) geochemical characterization and modeling work.

1 Pre-1996 Testwork Program

As part of the initial planning and baseline studies on behalf of Alta Gold, SRK (US) Inc collected a small suite of samples from drill core, tailings and waste rock for acid base accounting, short term leachate and kinetic testing. The kinetic testing program was only run for 28 weeks. None of the current investigators were involved in this work but Rob Bowell produced a report on the work due to changes in staff in SRK (US) prior to reporting of the study. The review of this testwork was reported in the *Geochemical Review of Waste Rock, Pit Lake Water Quality and Tailings* (SRK, 1996). The testwork results were also utilized to develop predictive geochemical models to assess potential pit lake water quality.

2 1997 Testwork Program

A geochemical sampling and testwork program was carried out by SRK as part of the 1997 Copper Flat Waste Rock Management Plan. The purpose of the program was to produce detailed geological and geochemical maps of the waste rock dumps and pits.. A total of 141 surface grab samples were collected from as part of the 1997 characterization program and these samples were analyzed for field net acid generation (NAG) and paste chemistry. Forty six of these samples were then subject to laboratory Acid Base Accounting (ABA) testwork and 59 samples were submitted for NAG testwork. This work was reported in the *Copper Flat Waste Rock Management Plan* (SRK, 1998). It is important to note that further work was planned but Alta Gold went bankrupt prior to confirming work plan for further kinetic testing and leachate assessment.

3 2010 Testwork Program

Additional samples were collected by SRK representatives during a site visit in April 2010. The purpose of the 2010 sampling and testwork program was to update the previous geochemical characterization and modeling work carried out in 1997. This is based on subsequent revisions to standards outlining the characterization of mine waste, which have become significantly more involved since the previous assessment was carried out. A number of statutory regulations have also been reviewed and modified since this initial assessment, including the modification of BLM and 43 CFR 3809 regulations in addition to changes to the standards applied to both EIS and New Mexico State permit applications.

During the site visit, two types of samples were collected:

1. A total of 50 drill hole samples were collected at depth from recent exploration core holes drilled within the footprint of the Copper Flat pit in 2009 and 2010. The sample intervals were selected to represent the range of waste rock material types that will be encountered in the pit during mining operations.
2. A total of 24 bulk surface grab samples from pit wall exposures, existing waste rock dumps and the tailings impoundment. Sampling these existing waste rock dumps and pit walls provide an opportunity to compare fresh rock samples to weathered rock samples of the same material types that have been exposed to oxygen and water for over 20 years. Coverage of this data set is more comprehensive than the previous studies.

It was anticipated that the samples collected as part of the 2010 characterization program would augment the existing (1997) geochemical dataset and update the geochemical characterization and modeling work to meet current standards.

4 Comparison of 1997 and 2010 Static Test Data

In order to ensure that the geochemical datasets collected in both 1997 and 2010 are comparable, SRK has undertaken a comparison of the testwork results obtained from ABA and NAG tests. This comparison has assessed the two datasets as a whole and has not considered variations within individual material types. This is because the material type designations used in both the 1997 and the 2010 assessments were different, and thus this would not be an appropriate comparison. For example the 1997 geochemical characterization program delineates samples according to oxidation (e.g. sulfide, transitional, oxide), whilst the 2010 program classifies materials according to alteration (e.g. propylitic, argillic, silicic). Nonetheless, the lithology types sampled during both the 1997 and 2010 geochemical characterization programs are comparable (Table 1).

Table 1: Summary of 1997 and 2010 Sampling

1997 sampling		2010 sampling	
Material type	**Number of samples**	**Material type**	**Number of samples**
Quartz Monzonite	94	Quartz Monzonite	39
Quartz Breccia	28	Quartz Monzonite Breccia	25
Andesite	1	Andesite	4
Biotite Breccia	10	Dolerite	2
Quartz Vein	8		

Comparison of the 1997 and 2010 data sets is illustrated on scatter plots and box and whisker plots preseted in Figure 1 to Figure 7**.**

The scatter plot comparing the sulfide sulfur content and net neutralizing potential (NNP) of the 1997 and 2010 samples provided in Figure 1 demonstrates that the two sample sets are broadly comparable, with a similar range in values. However, the 2010 data set generally has more samples that fall within the zone of uncertainty or that are non-acid forming. Conversely, the 1997 data set contains more samples that show potentially acid forming (PAF) characteristics. The box and whisker plot provided in Figure 2 shows the range and median values of NNP for each data set. This demonstrates that the two data sets are comparable in terms of the range of NNP values, but the samples collected in 1997 generally show a trend towards more acid generating characteristics. A reason for this may have been bias in collecting higher sulfide or weathered material on the dumps, whereas a more representative sample set was collected in 2010.

The tendency of the 1997 samples towards acid generating characteristics is also illustrated in the scatter plot of paste pH vs. sulfide sulfur content presented in Figure 3. This shows that the paste pH values for the samples collected in 1997are generally lower in comparison to the 2010 data. This is likely to reflect the nature of the samples themselves, with the 1997 samples being entirely grab samples collected from surface waste rock dumps and the 2010 samples being a mixture of both surface grab samples and also drill core material from depth. The significance of this difference in sample type is that surface grab samples are likely to be characterised by the presence of soluble (and potentially acidic) salts on the material surface, whereas the drill core samples are likely to be largely unweathered. Consideration of the grab samples only (Figure 4) shows a slightly better correlation between the two datasets, but paste pH values are still generally higher than observed in the 1997 dataset.

Comparison of 1997 and 2010 NAG testwork results (Figure 5) shows a fairly significant difference between the two datasets. This is largely due to a difference in testwork methodology, with the 1997 analysis including the determination of NAG values for samples with a NAG pH greater than 4. This is different to the 2010 methodology employed, whereby the NAG value was only determined for samples showing a NAG pH less than 4 s.u. Comparison of the two datasets for only samples with a NAG pH less than 4 shows that the samples are broadly similar in terms of their net acid generating potential (Figure 6 and Figure 7).



Figure 1: Scatter Plot of Sulfide Sulfur vs. Net Neutralizing Potential (NNP)



Figure 2: Box and Whisker Plot of Net Neutralizing Potential (NNP)



Figure 3: Scatter Plot of Paste pH vs. Sulfide Sulfur Content



Figure 4: Scatter Plot of Paste pH vs. Sulfide Sulfur Content (grab samples only)



Figure 5: Scatter Plot of NAG pH vs. Net Acid Generation (NAG) value



Figure 6: Scatter Plot of NAG pH vs. Net Acid Generation (NAG) value for Samples with NAG pH <4



Figure 7: Box and Whisker Plot of NAG value for Samples with NAG pH <4

5 Summary

In general, consideration of both the 1997 and 2010 geochemical databases shows that they are comparable in terms of their geochemical characterization and acid generating potential. However, the samples collected in 1997 show a trend towards having a generally greater acid generating potential, whilst the 2010 dataset contains more samples that show uncertain or non acid forming characteristics. Any significant differences observed between the two datasets are either a function of testwork methodology utilized (in the case of the NAG results) or as a result of the nature of the samples themselves (i.e. grab samples vs. core). Another possible reason for the difference is a bias in the 1997 sample collection (i.e., preferential selection of highest sulfide/weathered materials).

Based on this comparison, the 1997 samples are analogous to waste rock materials that have been exposed to oxygen and water for over 20 years and have developed soluble acidic salts as a result of weathering. Therefore, it is important to incorporate this data into the current investigation in order to capture the range of waste rock behavior associated with the Copper Flat deposit. However, in order to properly utilize these data, the two datasets need to be reconciled with respect to the material type designations. This exercise is currently ongoing.

Appendix G

Quality Assurance Project Plan

New Mexico Copper Corporation

Quality Assurance Project Plan

Copper Flat Mine Site

March 31, 2011

Prepared for:
New Mexico Copper Corporation

Submitted to:
Mining and Minerals Division
New Mexico Energy, Minerals and Natural Resources Department

Prepared by:

INTERA

01299

TABLE OF CONTENTS

Abbreviations and Acronyms ii
1 Project Description and Management 1
1.1 Project Definition and Background 1
1.2 Quality Objectives and Criteria 1
1.2.1 Measurement Quality Objectives for Analytical Laboratory Data 1
1.3 Project Organization 3
1.4 Special Training and Certification 3
1.4.1 Health and Safety Training 3
1.5 Documents and Records 4
1.5.1 Field Documentation 4
2 Data Generation and Acquisition 4
2.1 Sampling Design 5
2.2 Field Activities 5
2.3 Sample Handling and Custody 5
2.4 Laboratory QA/QC 6
2.5 Equipment Testing, Inspection, Maintenance, and Calibration 7
3 Inspection and Acceptance of Supplies and Consumables 7
4 Data Management 7
5 Assessment, Response Actions, and Reports to Management 7
6 Data Evaluation and Usability 8
6.1 Laboratory Data Verification 8
6.2 Laboratory Data Evaluation and Usability 8
7 Reconciliation with User Requirements 8
8 References 9

LIST OF FIGURES

Figure 1 INTERA Organizational Flow Chart

LIST OF TABLES

Table 1 Key Personnel and Responsibilities

Abbreviations and Acronyms

CFR	Code of Federal Regulations
COC	chain of custody
CPR	cardiopulmonary resuscitation
DQA	data quality assessment
EPA	United States Environmental Protection Agency
ER	equipment rinsate
FTL	field team leader
GWQB	Ground Water Quality Bureau
ID number	identification number
INTERA	INTERA Incorporated
LCS	laboratory control sample
MDL	method detection limit
MECS	Mining Environmental Compliance Section
MQO	measurement quality objectives
MS	matrix spike
NMAC	New Mexico Administrative Code
NMCC	New Mexico Copper Corporation
NMED	New Mexico Environment Department
NMWQCC	New Mexico Water Quality Control Commission
OSHA	Occupational Safety and Health Administration
PARCC	precision, accuracy, representativeness, completeness, and comparability
PM	Project Manager
PPE	personal protective equipment
PRRL	project-required reporting limits
QA	quality assurance
QAPP	quality assurance project plan
QC	quality control
RPD	relative percent difference
SAP	sampling and analysis plan
Site	Copper Flat Mine Permit Area
SQL	sample quantitation limits

1 Project Description and Management

This document establishes the quality standards for products and services that have been established within the industry and through government regulations. New Mexico Copper Corporation (NMCC) and its contractors shall meet or exceed these quality standards throughout the duration of this project.

NMCC is currently initiating permitting activities for the re-opening of the Copper Flat Mine located approximately six miles northeast of Hillsboro, New Mexico, in Sierra County (Site). NMCC and its contractors will perform site investigation activities described in the Stage 1 Abatement Plan.

The project organizational flow chart for NMCC's geosciences and engineering contractor, INTERA Incorporated (INTERA) of Albuquerque, New Mexico, identifies key personnel and their functions (Figure 1). The INTERA Program Manager, Cynthia Ardito, is responsible for project direction and quality assurance (QA) for this project. The Project Manager (PM), Peter Castiglia, is responsible for organizing and implementing field activities, project oversight, data management, and report preparation. Mr. Castiglia is also responsible for ensuring that the Quality Assurance Project Plan (QAPP) and the Stage 1 Abatement Plan are appropriately developed and adhered to.

1.1 Project Definition and Background

NMCC has developed a Stage 1 Abatement Plan for the Copper Flat Mine in response to the New Mexico Environment Department (NMED) Ground Water Quality Bureau (GWQB) Mining Environmental Compliance Section (MECS) letters dated August 20, 2008, and March 18, 2009 (Appendix A of the Stage 1 Abatement Plan). This Stage 1 Abatement Plan was prepared in accordance with the provisions of New Mexico Administrative Code (NMAC) 20.6.2.4103 Abatement Standards and Requirements and relevant regulations, and per discussions with the NMED MECS. This QAPP is designed for the site characterization activities described in the Stage 1 Abatement Plan and in accordance with the field procedures developed for the Copper Flat Sampling and Analysis Plan (SAP) (INTERA, 2010).

1.2 Quality Objectives and Criteria

The following sections present the measurement quality objectives (MQO) identified for this project.

1.2.1 Measurement Quality Objectives for Analytical Laboratory Data

All analytical results for water samples will be evaluated in accordance with precision, accuracy, representativeness, completeness, and comparability (PARCC) parameters to document the quality of the data and promote data that are of sufficient quality to meet the project objectives. With regard to these PARCC parameters, precision and accuracy method blanks will be prepared at the frequency prescribed in the individual analytical method, or at a rate of 5 percent of the total samples if a frequency is not prescribed in the method. The subsections below describe each of the PARCC parameters and how they will be assessed for this task.

1.2.1.1 Precision

Precision is the degree of mutual agreement between individual measurements of the same property under similar conditions. Usually, combined field and laboratory precision is evaluated by collecting and analyzing field duplicates and then calculating the variance between the samples, typically as a relative percent difference (RPD).

$$RPD = \frac{|A - B|}{(A + B)} \times 100\%$$

where:

A	=	First duplicate concentration
B	=	Second duplicate concentration

Field sampling precision is evaluated by analyzing field duplicates. One duplicate groundwater sample will be collected during the initial groundwater sampling event to establish laboratory analytical precision at the onset of the investigation. The duplicate groundwater sample will be collected by completely filling two separate vials by alternating between the primary sample set and the replicate sample set in the order shown below:

- Fill vial #1 - primary sample set
- Fill vial #1 - replicate sample set
- Fill vial #2 - primary sample set
- Fill vial #2 - replicate sample set

Laboratory analytical precision is evaluated by analyzing matrix (laboratory) duplicates. Results for each laboratory duplicate pair will be used to determine the RPD in order to evaluate precision.

1.2.1.2 Accuracy

A program of sample spiking will be conducted to evaluate laboratory accuracy. This program will include analysis of matrix spike (MS), laboratory control samples (LCS) or blank spikes, and method blanks. The results for the spiked samples will be used to calculate the percent recovery for use in evaluating accuracy.

$$\text{Percent Recovery} = \frac{S - C}{T} \times 100\%$$

where:

S	=	Measured spike sample concentration
C	=	Sample concentration
T	=	True or actual concentration of the spike

Results that fall outside the accuracy goals will be further evaluated on the basis of the results of other quality control (QC) samples.

1.2.1.3 Representativeness

Representativeness expresses the degree to which sample data accurately and precisely represent: (1) the characteristics of a population, (2) variations in a parameter at a sampling point, or (3) an environmental condition that they are intended to represent.

Representativeness of data will also be promoted through the consistent application of established field and laboratory procedures. Equipment rinsate (ER) blanks and laboratory blanks will be evaluated for the presence of contaminants to aid in evaluating the representativeness of sample results. Data determined to be non-representative by comparison with existing data will be used only if accompanied by appropriate qualifiers.

1.2.1.4 Completeness

Completeness is a measure of the percentage of project-specific data that are valid. Valid data will be obtained when samples are collected and analyzed in accordance with QC procedures as outlined in this QAPP and when none of the QC criteria that affect data usability are exceeded. When all data evaluation is completed, the percent completeness value will be calculated by dividing the number of useable sample results by the total number of sample results planned for this investigation.

As discussed further in Section 8.0, completeness will also be evaluated as part of the data quality assessment process (EPA, 2000a). This evaluation will help assess whether any limitations are associated with the decisions to be made based on the data collected.

1.2.1.5 Comparability

Comparability expresses the confidence with which one data set can be compared with another. Comparability of data will be achieved by consistently following standard field and laboratory procedures and by using standard measurement units in reporting analytical data.

1.2.1.6 Detection and Quantitation Limits

The method detection limit (MDL) is the minimum concentration of an analyte that can be reliably distinguished from background noise for a specific analytical method. The quantitation limit represents the lowest concentration of an analyte that can be accurately reproduced in a sample matrix. Project-required reporting limits (PRRL) are contractually specified minimum quantitation limits for specific analytical methods and sample matrices, such as soil or water, and are typically several times the MDL to allow for matrix effects. PRRLs, which are established in the project scope of work for subcontract laboratories, are set to establish minimum criteria for laboratory performance. Actual laboratory quantitation limits may be substantially lower.

For this project, analytical methods have been selected so that the PRRL for each target analyte is below the applicable regulatory screening criteria, the New Mexico Water Quality Control Commission (NMWQCC) Standards for groundwater. Also, sample concentrations will be reported as estimated values if concentrations are less than PRRLs but greater than MDLs. The MDL for each analyte will be listed as the detection limit in the laboratory's electronic data deliverable.

1.3 Project Organization

Table 1 presents the roles and responsibilities for key personnel who will be involved in the Stage 1 Abatement investigations at the Site. In some cases, more than one responsibility has been assigned to one person.

1.4 Special Training and Certification

This section outlines the training and certifications required to complete the activities described in this QAPP. The following sections describe the requirements for personnel working on-site.

1.4.1 Health and Safety Training

INTERA Personnel who collect water and sediment samples from the Site are required to meet the Occupational Safety and Health Administration (OSHA) training requirements defined in Title 29 of the Code of Federal Regulations (CFR) Part 1910.120(e). These requirements include (1) 40 hours of formal off-site instruction, (2) a minimum of three days of actual on-site field experience under the supervision of a trained and experienced field supervisor, and (3) 8 hours of annual refresher training. Field personnel who directly supervise employees

engaged in work at the site shall also receive at least 8 additional hours of specialized supervisor training. The supervisor training covers health and safety program requirements, training requirements, personal protective equipment (PPE) requirements, the spill containment program, and health-hazard monitoring procedures and techniques. Every member of the field team will maintain current certification in the American Red Cross "Multimedia First Aid," and "Cardiopulmonary Resuscitation (CPR) Modular," or equivalent.

Copies of health and safety training records, including course completion certificates for the initial and refresher health and safety training, specialized supervisor training, and first aid and CPR training, are maintained in corporate files.

1.5 Documents and Records

Documentation is critical for evaluating the success of any environmental data collection activity. The following sections discuss the requirements for documenting field activities and for preparing laboratory data packages. This section also describes reports that will be generated as a result of this project.

1.5.1 Field Documentation

Field personnel will use permanently bound field logbooks with sequentially numbered pages to record and document field activities. The logbooks will list a contract name and number, the project number, the site name, the names of subcontractors, the client, and the PM. At a minimum, the following will be recorded in the field logbook:

- Names and affiliations of all on-site personnel or visitors
- Weather conditions during the field activity
- Summary of daily activities and significant events
- Notes of conversations with coordinating officials
- References to other field logbooks or forms that contain specific information
- Discussions of problems encountered and their resolutions
- Discussions of deviations from the Stage 1 Abatement Plan, the SAP or other governing documents
- Descriptions of all photographs taken

The field team may also use the field forms during certain sampling or data collection activities to document field activities. The same level of detail will be required for all field forms used during this investigation. Copies of the completed field forms will be stored in the project file.

2 Data Generation and Acquisition

This section describes the requirements for the following:

- Sampling Design (Section 2.1)
- Field Activities (Section 2.2)
- Sample Handling and Custody (Section 2.3)
- Laboratory Quality Assurance/Quality Control (QA/QC) (Section 2.4)
- Equipment Testing, Inspection, Maintenance, and Calibration (Section 2.5)

2.1 Sampling Design

Samples or data will be collected as outlined in the Stage 1 Abatement Plan. The field activities for the Stage 1 Abatement Investigation include: collection of quarterly or one-time field sampling or data collection events that were designed by NMCC and its contractors. Field activities will be implemented to optimize the time spent in the field by adhering to established scientific methods and procedures, leading coordinated field schedules, and sharing data with contractors to minimize duplication of data.

Data collected from these field activities will be used in the mine permitting process. This baseline data will also be useful in the design of mine facilities and as a reference during site reclamation activities.

2.2 Field Activities

Field activities have been broken into two separate activities. These activities, which are outlined in the Stage 1 Abatement Plan and the SAP, will be used to evaluate the need for remedial action and to establish the baseline conditions at the Site:

- Surface water sampling – To characterize the volumetric flow and water quality of seeps, springs, streams, and the pit lake and to evaluate the existing ARD potential at the Site.
- Groundwater sampling – To obtain necessary data to evaluate quantity and quality of all aquifers at the Site that could be impacted by mining activities, address data gaps identified during evaluation of the Draft EIS (BLM, 1996), meet the requirements set forth in the regulations in NMAC Title 19, Chapter 10, Part 6, to meet the guidelines set forth in MMD's draft Guidance Document for Part 6 New Mining Operations Permitting under the New Mexico Mining Act, and to meet the NMED's Stage 1 Abatement requirements identified in 20.6.2.4103 NMAC.

2.3 Sample Handling and Custody

The following section describes sample handling procedures, including sample identification and labeling, documentation, chain of custody (COC), and shipping. This section applies to water, sediment, and geologic samples that are submitted to an analytical laboratory. Other sample handling and custody procedures for vegetation and other resources are described, where appropriate, in the Stage 1 Abatement Plan and the SAP.

Each sample collected at the Site will be identified using a unique sample identification (ID) number. The description of the sample type and the point name will be recorded on the COC form, as well as in the field notes. Note that field duplicates and ERs will be given a unique sample ID. The association between primary, duplicate, and ER samples will be noted on the COC form.

A sample label will be affixed to each sample container. The label will be completed with the following information written in indelible ink: project name and location, sample ID number, date and time of collection, preservative used (if applicable), collector's initials, and analysis requested. After labeling, each sample will be refrigerated or placed in a cooler containing ice.

Documentation of sample collection will be completed in permanent black or blue ink in the field logbook. All entries will be legible. The field team leader (FTL) and sampling personnel are responsible for proper documentation of all Site activities.

Standard sample custody procedures will be used to maintain and document sample integrity during collection, transportation, storage, and analysis. COC procedures provide an accurate written record that traces the

possession of individual samples from the time of collection in the field to the time of acceptance at the laboratory.

The COC form will be placed in a waterproof plastic bag and taped to the inside of the shipping container used to transport the samples. The laboratory sample custodian will receive all incoming samples, sign the accompanying COC forms, and retain copies of the forms as permanent record. The laboratory sample custodian will record all pertinent information concerning the samples, including the persons delivering the samples, the date and time received, sample condition at the time of receipt (sealed, unsealed, or broken container; temperature; or other relevant remarks).

All samples will be either hand delivered or shipped to an accredited laboratory. Samples may need to be shipped to the laboratory in order to have them analyzed before the expiration of a particular sample's holding time.

2.4 Laboratory QA/QC

This section applies to water, sediment, and geologic samples submitted to accredited analytical laboratories. To ensure quality of laboratory analysis, the analytical laboratory will be required to analyze QA/QC samples as specified by the analytical methods. The laboratory will analyze method blanks, MSs, and LCSs.

Method blanks will be prepared at the frequency prescribed in the individual analytical method or at a rate of 5 percent of the total samples if a frequency is not prescribed in the method.

MSs will be analyzed at a frequency of 5 percent for soil and aqueous samples. The percent recoveries will be calculated for each of the spiked analytes and used to evaluate analytical accuracy. The RPD between spiked samples will be calculated to evaluate precision.

LCSs, or blank spikes, will be analyzed at the frequency prescribed in the analytical method or at a rate of 5 percent of the total samples if a frequency is not prescribed in the method. If percent recovery results for the LCS or blank spike are outside of the established goals, laboratory-specific protocols will be followed to gauge the usability of the data.

Sample quantitation limits (SQL), also referred to as practical quantitation limits, are PRRLs adjusted for the characteristics of individual samples. The PRRLs are chemical-specific levels that a laboratory should be able to routinely detect and quantitate in a given sample matrix. The PRRL is defined in the analytical method or in laboratory method documentation, and incorporates precision (reproducibility) assumptions for the analysis. The SQL takes into account changes in the preparation and analytical methodology that may alter the ability to detect an analyte, including changes such as use of a smaller sample aliquot or dilution of the sample extract. Physical characteristics such as sample matrix and percent moisture that may alter the ability to detect the analyte are also considered. The laboratory will calculate and report SQLs for all environmental samples.

The laboratory activities are overseen by a comprehensive quality assurance program to assure that laboratory practices and results adhere to its policies. The laboratory will provide a standard QA/QC report with all reports. This includes surrogate recoveries, spike recoveries, and method blanks.

The laboratory participates in the Wibby Environmental, third party, proficiency testing program. Wibby is accredited by A2LA and NIST/NVLAP. Results of all proficiency results are sent, by Wibby, to both the laboratory and to their accrediting authorities. The laboratory will also perform proficiency testing on a semiannual basis for all accredited tests. Water proficiencies in the water supply and water pollution studies will be performed in addition to soil proficiencies in hazardous waste pollution studies.

Proficiency results are reviewed by the laboratory manager and all personnel involved in reporting the data. Results that are marked as "check for error" and "unacceptable" are thoroughly reviewed and corrective actions are written for "unacceptable" data.

2.5 Equipment Testing, Inspection, Maintenance, and Calibration

All equipment used during the investigation will be properly tested, inspected, maintained, and calibrated. Samples collected during this investigation will be analyzed using both field and laboratory equipment. Calibration of the field equipment shall be recorded in the field logbook after each calibration event. The calibration procedure for each piece of field equipment used will be outlined in the final report.

The laboratory's QA plan and written operating procedures describing specific testing, inspection, maintenance, and calibration procedures for equipment will be followed. If required, maintenance procedures and schedules will be performed and documented.

3 Inspection and Acceptance of Supplies and Consumables

PMs have primary responsibility for identifying the types and quantities of supplies and consumables needed to complete projects and are responsible for identifying acceptance criteria for these items.

Supplies and consumables can be received either at the contractor's office or at a work site. When supplies are received at an office, the PM or FTL will sort them according to vendor, check packing slips against purchase orders, and inspect the condition of all supplies before they are accepted for use on a project. If an item does not meet the acceptance criteria, deficiencies will be noted on the packing slip and purchase order and the item will then be returned to the vendor for replacement or repair.

Procedures for receiving supplies and consumables in the field are similar. When supplies are received, the PM or FTL will inspect all items against the acceptance criteria. Any deficiencies or problems will be noted in the field logbook and deficient items will be returned for immediate replacement.

Analytical laboratories are required to provide certified clean containers for all analyses. These containers must meet U.S. Environmental Protection Agency (EPA) standards as described in *Specifications and Guidance for Obtaining Contaminant-Free Sampling Containers* (EPA, 1992).

4 Data Management

All field and analytical data collected during this investigation will be provided to NMED in the Stage 1 Investigation Report. Field data will be recorded in the logbook and/or field forms and will be included in the appendices. Analytical data will be summarized, tabulated, analyzed, and provided in the body of the final report. The original laboratory data will be provided in an appendix of the final report. Some data may be presented graphically.

5 Assessment, Response Actions, and Reports to Management

NMCC and NMED will oversee collection of environmental data using the appropriate assessment and audit activities. Any problems encountered during an assessment of field investigation or laboratory activities will require appropriate corrective action to ensure that the problems are resolved. The corrective actions will be discussed with NMED and will be implemented after approval from NMED is received. NMCC will perform routine audits of their subcontractor's performance. In addition, the subcontractor's project managers will

ensure that the work done under their assigned tasks complies with the QAPP and will report non compliance, problems, or other issues to NMCC in a timely manner agreed upon between NMCC and its subcontractors.

Effective management of environmental data collection requires: 1) timely assessment and review of all activities, and 2) open communication, interaction, and feedback among all project participants. NMCC and its contractors will use verbal communication with NMED oversight personnel, electronic communication, and monthly status reports to address any project-specific quality issues and to facilitate timely communication of these issues. NMCC and its contractors will develop a communications protocol to communicate with the NMED and solicit the NMED for concurrence with these communication procedures.

6 Data Evaluation and Usability

This section describes the procedures that are planned to review and evaluate field and laboratory data. This section also discusses procedures for verifying that the data are sufficient to meet MQOs for the project.

Review and evaluation of the data generated during field and laboratory activities are essential to obtaining defensible data of acceptable quality. Project team personnel will review field data to identify inconsistencies or anomalous values. Any inconsistencies discovered will be resolved as soon as possible by seeking clarification from field personnel responsible for data collection. All field personnel will be responsible for following the sampling and documentation procedures described in the Stage 1 Abatement Plan and the SAP so that defensible and justifiable data are obtained.

Data values that are significantly different from the population are called “outliers.” A systematic effort will be made to identify any outliers or errors before field personnel report the data. Outliers can result from improper sampling or measurement methodology, data transcription errors, calculation errors, or natural causes. Outliers that result from errors found during data verification will be identified and corrected; outliers that cannot be attributed to errors in sampling, measurement, transcription, or calculation will be clearly identified in project reports.

6.1 Laboratory Data Verification

Laboratory personnel will verify analytical data at the time of analysis and reporting and through subsequent reviews of the raw data for any nonconformances to the requirements of the analytical method. Laboratory personnel will make a systematic effort to identify any outliers or errors before they report the data. Outliers that result from errors found during data verification will be identified and corrected; outliers that cannot be attributed to errors in analysis, transcription, or calculation will be clearly identified in the case narrative section of the analytical data package.

6.2 Laboratory Data Evaluation and Usability

All laboratory data will be evaluated. The data evaluation strategy will not be a full data validation process, but will determine if the analytical results are within the QC limits set for the project. As part of this evaluation, the data usability will be assessed.

7 Reconciliation with User Requirements

After environmental data have been reviewed and evaluated in accordance with the procedures described in Section 7.0, the data must be further evaluated to assess whether MQOs have been met.

To the extent possible, EPA's data quality assessment (DQA) process will be followed to verify that the type, quality, and quantity of data collected are appropriate for their intended use. DQA methods and procedures are outlined in EPA's *Guidance for Data Quality Assessment, Practical Methods for Data Analysis* (EPA, 2000a). The DQA process includes five steps: (1) review the sampling objectives and sampling design, (2) conduct a preliminary data review, (3) select a statistical test, (4) verify the assumptions of the statistical test, and (5) draw conclusions from the data. In the case of water, sediment, and geologic samples, no statistical analysis is planned at this time.

When the five-step DQA process is not completely followed because the sampling objectives are qualitative, data quality and data usability will be systematically assessed. This assessment will include:

- A review of the sampling design and sampling methods to verify that these were implemented as planned and are adequate to support project objectives.
- A review of project-specific data quality indicators for PARCC and project reporting limits to evaluate whether acceptance criteria have been met.
- A review of project-specific sampling objectives to assess whether they have been achieved by the data collected.
- An evaluation of any limitations associated with the decisions to be made based on the data collected (for example, if data completeness is only 90 percent compared to a project-specific completeness objective of 95 percent, the data may still be usable to support a decision, but at a lower level of confidence).

The final report for the project will discuss any potential impacts of these reviews on data usability and will clearly define any limitations associated with the data.

8 References

Bureau of Land Management (BLM), 1996, Draft environmental impact statement (DEIS), Copper Flat Project: Las Cruces, N. Mex., U.S. Department of the Interior. Prepared by ENSR, Fort Collins, Colo.

Environmental Protection Agency (EPA), 1992, Specifications and guidance for obtaining contaminant-free sampling containers: Washington, DC, Office of Solid Waste and Emergency Response, EPA/A540/R-93/051. December.

———.2000a, Guidance for data quality assessment, practical methods for data analysis, EPA QA/G-9, QA00 Update: Washington, DC, Office of Environmental Information, EPA/600/R-96/084. July.

INTERA, 2010, Sampling and analysis plan for Copper Flat Mine. Prepared for New Mexico Copper Corporation. Submitted to Mining and Minerals Division, New Mexico Energy Minerals and Natural Resources Department. September.

Figure



Figure 1. Project Organization

Table

Table 1
INTERA Key Personnel and Responsibilities

Name	Organization	Role	Responsibilities	Contact Information
Ms. Cindy Ardito	INTERA	Program Quality Assurance (QA) Officer	Participates in development of technical approach. Reviews technical deliverables. Provides technical oversight during data collection	INTERA Inc. 6000 Uptown Blvd. NE, Suite 220 Albuquerque, NM 87110 (505) 246-1600, (505) 246-2600 FAX ext. 1206 cardito@intera.com
Mr. Peter Castiglia	INTERA	Project Manager/ Technical Lead	Responsible for overall project execution and for coordination with regulatory agencies and contractors. Actively participates in Data Quality Objective process. Provides management and technical oversight during data collection.	INTERA Inc. 6000 Uptown Blvd. NE, Suite 220 Albuquerque, NM 87110 (505) 246-1600, (505) 246-2600 FAX ext. 1217 pcastiglia@intera.com
Mr. Lee Dalton	INTERA	Field Team Leader (FTL) – Groundwater	Responsible for directing day-to-day field activities conducted by INTERA and subcontractor personnel. Verifies that field sampling and measurement procedures follow the Stage 1 Abatement Plan and the Sampling and Analysis Plan Provides project manager with regular reports on status of field activities.	INTERA Inc. 6000 Uptown Blvd. NE, Suite 220 Albuquerque, NM 87110 (505) 246-1600, (505) 246-2600 FAX ext. 1213 ldalton@intera.com
Mr. Justin Jayne	INTERA	Field Team Leader (FTL) – Surface Water	Responsible for directing day-to-day field activities conducted by INTERA and subcontractor personnel. Verifies that field sampling and measurement procedures follow the Stage 1 Abatement and the Sampling and Analysis Plan Provides project manager with regular reports on status of field activities.	INTERA Inc. 6000 Uptown Blvd. NE, Suite 220 Albuquerque, NM 87110 (505) 246-1600, (505) 246-2600 FAX ext. 1220 jjayne@intera.com
Ms. Angela Persico	INTERA	On-Site Safety Officer	Responsible for implementing health and safety plan for determining appropriate site control measures and personal protection levels. Conducts safety briefings for INTERA and subcontractor personnel and site visitors. Can suspend operations that threaten health and safety.	INTERA Inc. 6000 Uptown Blvd. NE, Suite 220 Albuquerque, NM 87110 (505) 246-1600, (505) 246-2600 FAX ext. 1207 apersico@intera.com
Ms. Angela Persico Mr. Spencer Whitman Mr. Konrad Clark Ms. Annelia Tinklenberg	INTERA	Field Sampler(s)	Responsible for collecting representative samples and conducting necessary field activities specified in Stage 1 Abatement Plan. Works under supervision of field team leader. Ensures proper sampling and handling procedures.	INTERA Inc. 6000 Uptown Blvd. NE, Suite 220 Albuquerque, NM 87110 (505) 246-1600, (505) 246-2600 FAX

Name	Organization	Role	Responsibilities	Contact Information
Mr. Bob Powell	Class One Technical Services, Inc.	Project Manager	Responsible for overall project execution and for coordination with regulatory agencies and contractors. Actively participates in Data Quality Objective process. Provides management and technical oversight during data collection by Class One Technical Services.	Class One Technical Services, Inc. 3500 Comanche Rd. NE Suite G Albuquerque, NM 87107 (505) 830-9680
Mr. Jens Deichmann	Parametrix	Project Manager – Ecological and Cultural Resources	Responsible for coordination with regulatory agencies and contractors. Actively participates in Data Quality Objective process. Provides management and technical oversight during data collection by Parametrix.	Parametrix Incorporated 8801 Jefferson NE; Bldg. 2 Albuquerque, NM 87113 (505) 998-5552 jdeichmann@parametrix.com
Mr. Chris Parrish	Parametrix	FTL - Cultural Resources	Responsible for directing day-to-day field activities conducted for cultural resources by Parametrix and subcontractor personnel. Verifies that field sampling and measurement procedures follow the Sampling and Analysis Plan. Provides project manager with regular reports on status of field activities.	Parametrix Incorporated 8801 Jefferson NE; Bldg. 2 Albuquerque, NM 87113 (505) 821-4700
Mr. Jim Nellessen	Parametrix	FTL – Natural Resources	Responsible for directing day-to-day field activities conducted for natural resources by Parametrix and subcontractor personnel. Verifies that field sampling and measurement procedures follow the Sampling and Analysis Plan. Provides project manager with regular reports on status of field activities.	Parametrix Incorporated 8801 Jefferson NE; Bldg. 2 Albuquerque, NM 87113 (505) 821-4700
Mr. Chad McKenna	Parametrix	Technical Lead – Geographic Information Systems (GIS)	Responsible for directing day-to-day activities conducted for GIS by Parametrix and subcontractor personnel. Verifies that GIS data collection procedures follow the Sampling and Analysis Plan. Provides project manager with regular reports on status of GIS data.	Parametrix Incorporated 8801 Jefferson NE; Bldg. 2 Albuquerque, NM 87113 (505) 821-4700
Mr. Mark Willow	SRK Consulting	Project Manager – Geologic Sampling	Responsible for coordination with regulatory agencies and contractors. Actively participates in Data Quality Objective process. Provides management and technical oversight during data collection by SRK.	SRK Consulting 250 Neil Road, Suite 300 Reno, Nevada 89502 (775) 828-6800 mwillow@srk.com
Dr. Robert Bowell	SRK Consulting	Technical Lead – Geologic Sampling	Responsible for directing day-to-day activities conducted for geologic by SRK and subcontractor personnel. Verifies that geologic data collection procedures follow the Sampling and Analysis Plan. Provides project manager with regular reports on status of geologic data collection and results.	SRK Consulting (UK) Ltd. 5th Floor, Churchill House 17 Churchill Way Cardiff, CF10 2HH, UK +44 (0) 29 2034 8150 egrbowel@srk.co.uk

Appendix H

Site Health and Safety Plan

HEALTH AND SAFETY PLAN

Copper Flat Groundwater and Surface-Water Sampling, Sierra County, New Mexico

Prepared for:

New Mexico Copper Corporation
315 Paseo de Peralta
Santa Fe, New Mexico 87501-2034

Prepared by:

INTERA Incorporated
6000 Uptown Blvd., Suite 220
Albuquerque, New Mexico 87110

March 31, 2011

Table of Contents

List of Figures ii
List of Tables ii
List of Forms ii
List of Appendices ii
Acronyms and Abbreviations iii
1.0 Introduction 1
2.0 Copper Flat Location and Site Description 2
3.0 Roles and Responsibilities 2
4.0 Scope of Work and Project Objectives 3
4.1 Physical Hazards 4
4.2 Biological Hazards 5
4.2.1 Snakes 6
4.3 Drowning 6
4.4 Chemical Hazards 7
4.5 Personal Protective Equipment 8
5.0 General Health and Safety Requirements 9
5.1 Safety Equipment 9
5.1.1 Head Protection 9
5.1.2 Eye Protection 10
5.1.3 Skin Protection 10
5.1.4 Footwear 10
5.1.5 Personal Flotation Devices 10
5.1.6 Respiratory Protection 11
5.2 Work Zones 11
5.3 Medical Examination/OSHA Training 12
5.4 Site Manager Notification 12
5.5 Project Safety Meetings/Compliance Agreement 12
5.6 Prohibitions 13
5.7 Site Visitors 13
6.0 Air Quality Monitoring 14
7.0 Laboratory Considerations 14
8.0 Confined Space Entry 14
9.0 Hazard Communication (HazCom) Program 14
9.1 Roles of Personnel 14
9.2 Labeling 15
9.3 Information and Training 15
9.4 Hazardous Chemical List 15
9.5 Storage and Labeling 16
9.6 Posting Requirements 16

10.0 Emergencies/Accidents 16
10.1 On-Site Personnel and Visitors 16
10.2 Surrounding Community 17

List of Figures

Figure 1 Site Map

List of Tables

Table 1 Site Health and Safety Equipment Inventory Checklist
Table 2 Emergency and Non-Emergency Phone Numbers

List of Forms

Form 1 Health and Safety Compliance Agreement Form
Form 2 Tailgate Safety Meeting Form
Form 3 Site Personnel Acknowledgement Form
Form 4 Site Visitors Log
Form 5 Incident Investigation Form

List of Appendices

Appendix A Exposure Prevention Plan

Acronyms and Abbreviations

ASTM	American Society for Testing Materials
EPA	U.S. Environmental Protection Agency
HASP	Health and Safety Plan
HazCom	Hazard Communication Plan
HSO	Health and Safety Officer
INTERA	INTERA, Incorporated
mg/kg	milligrams per kilogram
mg/l	milligrams per liter
MSDS	Material Safety Data Sheet
MVNP	Mountain View Nitrate Plume
NIOSH	National Institute for Occupational and Safety and Health
NMED	New Mexico Environment Department
NMWQCC	New Mexico Water Quality Control Commission
OSHA	Occupational Safety and Health Administration
PM	Project Manager
PPE	personal protective equipment
ppm	parts per million
PVC	polyvinyl chloride
RFP	request for proposal
SOW	scope of work
SSO	Site Safety Officer
TDS	total dissolved solids

1.0 Introduction

INTERA Incorporated's (INTERA) Site-Specific Health and Safety Plan (HASP) is a dynamic document and subject to change during the performance of the INTERA scope of work (SOW) designed for the Copper Flat surface water and groundwater sampling program located in Sierra County, New Mexico (Figure 1). This HASP applies to all INTERA and INTERA sub-contracted personnel generally involved with groundwater monitoring activities for the groundwater sampling event.

Program Manager: Cindy Ardito – INTERA (505) 246-1600 ext. 1206

Project Manager: Peter Castiglia – INTERA (505) 246-1600 ext. 1217

Site Safety Officer:

Type of Sampling	INTERA Site Safety Officer	Office Phone	Cellular Phone
Groundwater	Lee Dalton	(505) 246-1600 x. 1213	505-730-7372
Surface Water	Justin Jayne	(505) 246-1600 x. 1220	903-736-2997
Pit Lake	Peter Castiglia	(505) 246-1600 x. 1217	505-280-2889

Field Team Leader:

Sampling	INTERA Field Team Leader	Office Phone	Cellular Phone
Groundwater	Lee Dalton	(505) 246-1600 x. 1213	505-730-7372
Surface Water	Justin Jayne	(505) 246-1600 x. 1220	903-736-2997
Pit Lake	Peter Castiglia	(505) 246-1600 x. 1217	505-280-2889

INTERA On-Site Personnel:

Sampling	INTERA On-Site Personnel	Office Phone	Cellular Phone
Groundwater	Lee Dalton	(505) 246-1600 x. 1213	505-730-7372
Surface Water	Justin Jayne	(505) 246-1600 x. 1220	903-736-2997
Pit Lake	Peter Castiglia	(505) 246-1600 x. 1217	505-280-2889

Corporate Health and Safety Officer: Barbara Rigney – INTERA (512) 425-2097

INTERA Albuquerque Health and Safety Officer: Angela Persico – INTERA (505) 246-1600, ext. 1207

Copper Flat Project Manager: Mr. Steve Raugust (505) 967-9542

HASP Prepared By: Lee Dalton in accordance with applicable provisions of the Occupational Safety and Health Administration (OSHA) 1910.120, updated by Angela Persico

HASP Reviewed By: Peter Castiglia, INTERA

Project Name: Copper Flat Mine Permitting

INTERA Project No.: NMC-001-(See Specific Task)

2.0 Copper Flat Location and Site Description

Copper Flat is located in southwestern New Mexico, approximately 23 miles southwest of Truth or Consequences and 5 miles northeast of Hillsboro. It is a porphyry copper deposit with associated gold, silver, molybdenum, and sulfide minerals. The stock contains a 75 million-year-old quartz monzonite breccia pipe forming the center of an eroded andesite strato-volcano. The breccia pipe is approximately 1,300 feet long, 600 feet wide, and 1,000 feet deep. Records indicated that the Sternberg Mine located at Copper Flat was mined as early as 1911, but it wasn't until 1982 that the mining occurred at a significant scale. Quintana Minerals Corporation mined the property for three months in 1982 producing 7.4 million pounds of copper, 2,306 ounces of gold, and 55,966 ounces of silver. Mining activities ceased because of low copper prices. The mining equipment was dismantled and sold. The Canadian Imperial Bank reclaimed the site. Subsequent efforts to permit mining operations by Gold Express of Denver, Colorado and Alta Gold of Henderson, Nevada were never completed. The property is now owned by Hydro Resources, Inc. of Albuquerque, New Mexico as a combination of fee simple properties and patented mining claims.

The purpose of this investigation is to compile and assess the existing groundwater and surface-water quality in the vicinity of an existing mine pit lake, waste rock piles, and mine tailings impoundment at Copper Flat, Hillsboro district, New Mexico, 25 miles southwest of Truth of Consequences and 5 miles northeast of Hillsboro (Fig. 1).

3.0 Roles and Responsibilities

The responsibilities of the INTERA Project Management team are outlined below:

- Program Manager – Responsible for overall execution of the project and project budget.

- Project Manager – Responsible for any changes in the SOW and oversees all general operations of the project on a day to day basis.
- Field Leader – Serves as the Project Manger in case of the Project Manager's absence.
- Albuquerque Health and Safety Officer (HSO) – Responsible for health and safety of all personnel during the progress of the project, the HSO can stop work regardless of budget or other constraints if an unsafe situation is present on-Site.
- Site Safety Officer (SSO) – Responsible for site health and safety and work operations and monitoring of ambient air in the exclusion zone. The SSO is responsible to report all safety and health concerns to the Project Manager and the HSO.

4.0 Scope of Work and Project Objectives

Water sampling is designed to meet the requirements of the Stage 1 Abatement Plan groundwater and surface water characterization as well as the baseline monitoring requirements of the Mine Permit Application. Work covered under this HASP includes:

- Groundwater quality sampling and water level measurement
- Surface water flow and water quality sampling
- Pit Lake sediment and water quality sampling

The general environmental health and safety hazards at the Site include: heavy equipment/machinery; motorized vehicles; slip, trips, and falls; drilling equipment; electrical equipment; biological hazards (insects, snakes, rodents, infectious diseases), drowning in swift or high water.

- Physical hazards associated with transportation to and from the Site;
- Physical hazards associated with accessing remote areas of the Site;
- Physical hazards associated with working in hot, sunny, conditions;
- Physical hazards associated with rapidly changing weather;
- Physical hazards associated with equipment used by INTERA including submersible pump, take up reel, and hand tools;
- Physical hazards associated with cold weather and warm weather working conditions;
- Physical hazards associated with heavy lifting;
- Physical hazards associated with exposure to electrical charges;

- Physical hazards associated with contact with and working around above or below ground utilities;
- Physical hazards associated with working around heavy equipment;
- Physical hazards associated with noise exposure;
- Physical hazards associated with working in waterways and lakes;
- Biological hazards including stinging insects, snakes, feral domestic animals, and contact with wildlife;
- Biological hazards related to Hanta virus from contact with rodents or rodent excrement;
- Chemical hazards associated with inhalation of organic vapors and/or inorganic contaminants during soil gas sampling activities;
- Chemical hazards associated with skin and eye contact with organic and/or inorganic contaminants;
- Chemical hazards associated with skin and eye contact with sample preservatives;
- Chemical hazards associated with ingestion of organic and/or inorganic contaminants; and
- All on-Site personnel and Site visitors shall be made aware of and protected against the potential hazards listed above.

4.1 Physical Hazards

Driving to and from the Site can be the most dangerous part of any field project. When driving, adhere to all traffic laws, including utilizing a hands-free-device when talking on the cell phone while driving. Drive defensively, taking special care when driving on dirt roads.

Physical hazards due to weather conditions are likely. The average temperatures in the summer months can be above 90F. The signs of dehydration can be muscle and joint pains and fatigue, headaches, and constipation. Constantly drinking water while traveling and performing field tasks will help combat dehydration. Pack a cooler full of cold water, fluid replacing drinks such as Gatorade or coconut water, and snacks. **To combat dehydration drink AT LEAST half of your body weight in ounces of water each day.** When performing field work where you may lose water through sweat, additional water should be consumed.

Weather patterns change rapidly in New Mexico. It is common for a sunny warm day to rapidly become 55F and hailing. Be prepared for anything. **STOP WORK IMMEDIATELY at first sign of a thunderstorm.** The vehicle is a safe place to wait out a thunderstorm.

There is a potential on-Site of physical injury resulting from contact with sampling equipment and tools. Field personnel shall be aware of these hazards and take steps to avoid them. Use of steel-toed boots, reflective vests, and safety glasses shall be required when on the Site. Hard hats shall be worn during drilling activities when heavy equipment is being operated, when there are overhead hazards or activities, and at the discretion of the SSO. Hearing protection shall be used during the operation of heavy equipment or at the discretion of the SSO. Personnel shall be cognizant of the fact that when protective equipment such as respirators, gloves, and protective clothing are worn, visibility, hearing, and manual dexterity are impaired.

In addition to the physical hazards listed above, the protective equipment required for some activities (i.e., respirator use) places a physical strain on the wearer. Heat exhaustion and/or stroke are possible, especially during warm weather. The Exposure Prevention Plan specified in Appendix A shall be implemented to deal with this serious health hazard. The plan outlines heat stress identification, treatment, prevention, and monitoring. Fluids shall be provided on-Site to maintain the body fluid levels of field personnel.

The use of electronic equipment and rechargeable meters present exposure to potential electrical shock. Electrical shock may be avoided by maintaining safe work practices around electrical equipment and connections.

Selected subcontractors shall perform their tasks in accordance with the established safety regulations of the OSHA and all other Federal, State, County, and City regulations. Subcontractors shall follow INTERA's HASP unless their own written health and safety plan has been approved by the INTERA SSO or HSO prior to the initiation of work activities.

4.2 Biological Hazards

During the appropriate season, numerous types of pest organisms may be present at the Site. Bees, spiders, wasps, rodents, reptiles, and feral/domestic animals may be present at the Site. Field personnel are encouraged to avoid exposing hands or other body parts to cool dark areas where these pests are known to dwell. Additionally, exposure to the Hanta virus from contact with rodents and rodent excrement should be avoided at all times. Areas where visible evidence of rodent activity exists are to be strictly avoided. Agitating dried rodent urine or droppings greatly increase the potential for exposure to the Hanta virus. Field personnel are not to approach and are to avoid contact with feral/domestic animals. Authorities should be contacted if an unrestrained animal is exhibiting aggressive behavior toward Site personnel.

4.2.1 Snakes

There are a total of 46 different snakes within New Mexico. Only 8 of which are poisonous, seven species of rattlesnake and one species of coral snake. There are two types of venom toxins: Hemotoxins and Neurotoxins.

Hemotoxins- anticoagulants, can cause hemorrhaging within, degenerates organs, tissue damage. Nausea, disorientation, & headache may be delayed.

Neurotoxins- can lead to respiratory failure, paralysis, cramps, twitching, vomiting, and convulsions.

If bitten by a snake, the severity of the bite will depend on the age of the patient, location of the bite, and potency of the venom. Either way, the patient will most likely swell significantly at the bite site. Venom often is spread throughout the body by the lymphatic system (not the circulatory system). Most healthy individuals will not have severe outcomes; mainly all responses can be psychological. It is important to keep the pt clam. The following steps are recommended steps to treat a poisonous snake bite:

- Stress to the patient the importance of staying calm.
- ABC's first.
- Remove all jewelry and clothing from the bite site due to swelling.
- No ice.
- Apply a light-restricting, 1-2 inches wide, band 3 inches above site. There should be a pulse, and the band should be reapplied periodically.
- Stop profuse bleeding.
- Flush with sterile saline.
- Keep bite site below the heart.
- If splint is required, do so loosely.

Patient must be transported in a timely matter to the nearest hospital where anti-venom is available **(Sierra Vista Hospital stocks anti-venom. See Figure 1 for location map.** Confirmed by phone call to Sierra Vista Hospital Emergency Room on 10/27/10 by P. Castiglia**)**.

4.3 Drowning

Personnel and site visitors may be exposed to drowning hazards in waterways and water bodies. No INTERA personnel should conduct work in a waterway or water body without at least one

partner. Staff working in waterways within the mine permit boundary are required to check-in at the project office at the start of each day and sign-out at the end of each day, notifying the project office personnel what time you intend to return, especially if the anticipated return time is past normal business hours. **Prior to conducting any sampling, listen to the weather report and never conduct work if severe weather is predicted or if a storm occurs on site.** Follow these general precautions while conducting the work:

- Park the vehicle in a safe location clear above the ordinary high water mark or well away from the flood-stage of the stream or water way
- Never wade into swift or high water. Do not monitor the waterway if the stream is at flood stage.
- Be very careful when walking in the stream itself. Rocky-bottom streams can be very slippery and can contain deep pools; muddy-bottom streams might also prove treacherous in areas where mud, silt, or sand has accumulated in sink holes. If you must cross a stream, use a wading rod or walking stick to steady yourself and to probe for deep water or much. Your partner(s) should wait on dry land ready to assist you if you fall. Do not attempt to cross streams that are swift and above the knee in depth.
- Wear waders and wading boots, or rubber boots, and rubber gloves in streams suspected of having significant pollution problems.
- Wear a U.S. Coast Guard approved Type III personal flotation device (PFD) if working in streams above the knee.
- **If at any time you feel uncomfortable about the condition of the stream or your surroundings, stop monitoring and leave the site at once. Your safety is more important than the data!**

4.4 Chemical Hazards

Personnel and Site visitors may be exposed to chemical hazards through four routes of exposure: inhalation, ingestion, skin contact, and eye contact.

There may be potential chemical hazards at this Site, acids used to preserve sample containers, and other fluids used to calibrate field equipment. Exposure to concentrations of potential contaminants could occur during field activities at this Site.

Ingestion of chemical hazards shall be controlled on this Site by prohibiting eating, smoking, and drinking in the Exclusion Zone (refer to Section 6.2 for definitions of work zones) and by requiring all field personnel to decontaminate themselves upon leaving the Exclusion Zone.

Skin and eye contact with chemical hazards can cause serious burns, rashes, or irritations. Id skin or eye contact is made with any chemical hazards, especially the acids used as preservatives in sample containers, flush the area with as much fresh water as possible. Eye wash kits are located in the first aid kit. All field personnel shall report any skin or eye contact symptoms to the SSO so a physician can treat personnel and steps can be taken to eliminate similar exposures.

The best assurance of protection against hazardous chemicals is avoidance. Whenever possible, Site personnel shall avoid contact with contaminated (or potentially contaminated) surfaces and walk around suspect liquids and discolored soils or substances. Workers shall not kneel or place equipment on potentially-contaminated ground and shall stay away from known waste whenever possible.

If contact is unavoidable in order to perform a required task, potential hazards are minimized by using appropriate personal protective equipment (PPE) to protect against exposure to toxic materials.

4.5 Personal Protective Equipment

PPE to protect the body against contact with known or anticipated chemical hazards has been divided into four categories by the EPA (i.e., Levels A, B, C, and D) according to the degree of protection afforded. At this Site, the levels of protection selected for activities specified in Section 4.0 are:

- Level D
- Modified Level D
- Level C

Requirements for the levels of protection and their appropriate use are provided below.

PPE Level	Includes	Appropriate for Use
Level D	Coveralls or appropriate work clothes, steel-toed boots, safety glasses or chemical splash goggles, and hard hat (as necessary)	For Site workers performing groundwater investigations.
Modified Level D	Coveralls or appropriate work clothes including Tyvek, Nitrile gloves, rubber boots, safety glasses, and hard hat (as necessary)	Workers who come in direct contact with contaminated soil and/or groundwater shall use Modified Level D PPE. Workers collecting water or sediment samples from the Pit Lake. Modified Level D PPE shall be used if there is a danger of chemical hazard from skin contact but no respiratory hazard (as determined by air monitoring).

PPE Level	Includes	Appropriate for Use
Level C	Tyvek suit, MSHA/NIOSH approved full-face air-purifying respirator with organic vapor/particulate cartridges, Nitrile outer gloves, steel-toe boots, safety glasses, and hard hat (as necessary)	For Site workers required to enter areas were harmful concentrations of petroleum hydrocarbons are detected. Respirators are required when air monitoring indicates a total organic vapor concentration in excess of 100 ppm (see Section 7.0 for discussion of air monitoring).

It is anticipated that all tasks shall be conducted using Level D or Modified Level D PPE.

5.0 General Health and Safety Requirements

Safety equipment and PPE are discussed in this section so that personal protection equipment and its importance can be better understood. The SSO has the authority to make PPE exceptions for Site personnel if he/she deems it in the best interest of the field personnel's well being. Such a PPE exception (i.e., modification to the HASP) shall be based on Site-specific information such as air monitoring data, visual observations, and weather data/observations. One example of such a modification to the HASP would be to decrease the use of respirators, hard hats, or poorly-breathable clothing if heat stress is a primary concern during Site activities and the use of the PPE was intended for a low-risk precaution. Under no circumstances shall the SSO make a PPE exception/modification if personnel shall be without the protection needed to be safe or to properly protect their health. If it appears that proposed PPE is inadequate, Site work shall be suspended until new PPE or planning allows personnel to work safely.

5.1 Safety Equipment

In addition to the personal protective equipment listed below, the following general safety equipment shall be available: cellular or satellite phone (or unimpeded access to a land line phone), OSHA-approved first-aid kit, fire extinguishers, eye wash, insect repellent/treatment, rinse water, and decontamination water. **Table 1 provides a checklist for the health and safety equipment.**

5.1.1 Head Protection

Hard hats shall be worn whenever overhead hazards are present, during operation of heavy equipment, or if otherwise required.

5.1.2 Eye Protection

All personnel working on-Site shall wear safety glasses. Additionally, when personnel are performing activities where the potential exists for increased exposure due to splash, dust, or vapor, etc., safety goggles, face shields, or full-face masks shall be worn.

5.1.3 Skin Protection

Snakes have been observed in surface water drainages at or near the sampling locations in the past. Therefore, all personnel conducting work shall wear snake guards while outside the field vehicle. Snake guards are worn over the shin and are puncture-proof gaiters designed to protect you from snake bites when working in snake country.

When coming in contact with water samples or any sample containers, Site personnel will wear disposable nitrile gloves. When sampling surface water, waders will be worn, in addition to the nitrile gloves. When sampling the pit lake, Site personnel shall be required to wear disposable, chemically resistant clothing such as waterproof Tyvek suits. This PPE shall be disposed of at the decontamination station after each use or when they become worn or punctured. If the disposable protective suits appear to be deteriorating under chemical action, the Site Activities Manager and SSO shall be notified. The seams between the sleeves and gloves and the pant legs and boots shall be taped to prevent exposure in these areas.

Site personnel should also have with them a change of warm, dry cloths to prevent from hypothermia if clothing worn while sampling becomes wet or water-logged. The spare clothing and a warm blanket should be kept on dry land and should be easily accessible should it be needed in response to falling into cold water. **See Appendix A for more information on cold weather hazards, including how to identify and treat hypothermia.**

5.1.4 Footwear

Personnel engaged in field activities at the Site shall wear supportive work boots at all times. Exceptions to this are when working in the streams. Wading boots or supportive sandles (Chacos, Tevas, or Keens) may be worn over the waders. If required by the Site-specific HASP or the SSO, footwear may also need to be chemical resistant.

5.1.5 Personal Flotation Devices

All INTERA personnel are required to wear a U.S. Coast Guard Type III personal flotation device (PFD) if conducting work in a waterway with flowing water above their waste line or working from a boat. The PFD should fit comfortably and snug and should be rated appropriately for the minimum adult buoyancy for the weight of the staff member. All zippers, ties, and straps should be fastened. If you don't wear a PFD, you are risking your life.

Follow these steps to check your PFD:

- Check your PFD often for rips, tears, and holes, and to see that seams, fabric straps, and hardware are okay. There should be no signs of waterlogging, mildew odor, or shrinkage of the buoyant materials.
- Don't forget to test each PFD at the start of each season. Ones that are not in good shape should be cut up and thrown away.

5.1.6 Respiratory Protection

No respiratory protection is anticipated for this project.

5.2 Work Zones

To minimize the movement of contaminants from the Site to uncontaminated areas, three work zone areas are established as needed at Sites where investigation and/or remediation activities are performed. The work zone areas may be revised as contaminant data is collected at the Site. The three work zones include the following:

- Zone 1: Exclusion Zone
- Zone 2: Contamination Reduction Zone
- Zone 3: Clean Zone

Exclusion Zone – The Exclusion Zone is the zone where contamination does or could occur. For example, the area that immediately surrounds a wellhead. All persons entering this zone shall wear the level of protection set forth in Section 5.0, *Site Hazards.* These level-of-protection guidelines are based on the different types of field activities.

Contamination Reduction Zone – Between the Exclusion Zone and the Clean Zone is the personal Contamination Reduction Zone, which provides a transition zone between the contaminated and clean areas of the Site. This zone shall be located directly outside the Exclusion Zone. All personnel shall decontaminate in the Contamination Reduction Zone when leaving the Exclusion Zone. The following steps, some of which are not applicable to Level D PPE, shall be taken for personnel decontamination:

- Deposit equipment that needs to be decontaminated on plastic drop cloths;
- Wash boots and outer gloves with long-handled brushes in a plastic wash tub containing detergent water;

- Rinse boots and outer gloves with long-handled brushes in a plastic wash tub containing clear water or use a sprayer to rinse off boots and gloves if one is available;
- Remove tape and place in drum for disposal;
- Remove disposable outer gloves and place in drum for proper disposal;
- Remove suit and, if disposable, place in drum for disposal;
- Remove respirator and place in plastic for subsequent decontamination;
- Remove inner gloves and place in drum for disposal; and
- Wash hands and face.

Contaminated liquids and clothing from the decontamination area shall be contained in drums and stored at the drum storage area at the Site. Cleaning equipment and supplies shall be provided and used to decontaminate reusable equipment.

Clean Zone – The Clean Zone shall be an uncontaminated area from which operations shall be directed. It is essential that contamination from the Site be kept out of this area.

5.3 Medical Examination/OSHA Training

Before commencing any of the field activities defined in Section 4.0, all INTERA personnel shall have proof of their current participation in the INTERA monitoring program. Subcontractors involved in hazardous field activities shall provide medical examinations for their employees as part of a medical monitoring program. Records of proof of medical examination shall be provided to INTERA by subcontractors and maintained in the project files as needed.

All personnel on-Site shall be 40-hour OSHA HAZWOPER trained. A copy of employees' certificates is kept in a file in the Albuquerque office.

5.4 Site Manager Notification

All field personnel shall inform the Site Manager or his/her designated representative before entering the Site. If any previously unidentified potential hazards are discovered during any fieldwork, personnel shall notify the Site Manager and SSO for further instructions.

5.5 Project Safety Meetings/Compliance Agreement

A safety meeting shall be conducted by the SSO at the start of each field effort, and thereafter, at the beginning of each day, as appropriate, due to changing field conditions or the start of new tasks. Safety concerns associated with that day's activities shall be discussed. An attendance record (refer to the Forms Section for health and safety forms) shall be kept for all safety meetings.

During the first safety meeting or prior to commencement of fieldwork, all personnel shall be provided with a copy of this HASP or easy access to a copy of this HASP. Personnel shall be given the opportunity to review the plan and ask any questions. All personnel working on-Site shall sign a Compliance Agreement stating that they have read and understood the HASP requirements. Signed Compliance Agreement Forms shall be collected by the SSO and placed in the project file. Individuals refusing to sign the form will not be allowed to work on the Site.

Project safety information shall be recorded in a field logbook and/or field forms. As appropriate, safety information shall include the following:

- Names of all INTERA, subcontractor, and visitor personnel;
- Dates and times for entry and exit of all personnel at the Site;
- Lists of all accidents, injuries, illnesses, and incidences of safety infractions;
- Other information related to safety matters.

All accidents, illnesses, and/or other incidents shall be reported immediately to the Project Manager (PM), the SSO, and/or the Project Health and Safety Officer. An Accident/Investigation Form has been provided in the Forms Section.

5.6 Prohibitions

The following activities are prohibited at the Site:

- Smoking, eating, drinking, chewing gum or tobacco, and storing food or food containers in the Exclusion or Contamination Reduction Zones;
- Approach or entry into areas or spaces where toxic or explosive concentrations of gases or dust may exist without proper equipment available to enable safe entry; and
- Unauthorized entry into confined spaces.

Field personnel shall practice good personal hygiene to avoid ingesting contaminants or spreading contaminated materials.

5.7 Site Visitors

Visits involving entry to the Site by persons not directly involved in tasks identified in this HASP or the Work Plan are discouraged. Site Visitors may include employees of the facility or other contractors that are not familiar with the activities being performed, and have not been trained to identify/mitigate potential risks. Persons designated Site Visitors shall be briefed by the INTERA SSO as to on-Site procedures, conditions, and hazards and shall be required to sign

the project safety log before entering the Site. Site Visitors shall be accompanied by authorized INTERA personnel at all times while on-Site and shall be expected to follow all directives from the SSO. Site Visitors shall provide their own PPE required for the area that they are visiting and shall be expected to follow all applicable procedures and protocols.

6.0 Air Quality Monitoring

Because air quality is not expected to be impacted during the groundwater and surface water sampling events there is currently no plan to conduct air quality monitoring at the Site during these event.

7.0 Laboratory Considerations

The laboratory directors or contacts shall be informed of any contaminant levels in the samples that would require special handling procedures to prevent risks to the health and safety of laboratory personnel.

8.0 Confined Space Entry

A confined space is a space that by design has limited openings for entry and exit, unfavorable natural ventilation that could contain or produce dangerous air contaminants, and is not intended for employee occupancy without the proper training and procedures. If any confined spaces are encountered, they are not to be entered under any circumstances and shall be reported to the SSO.

9.0 Hazard Communication (HazCom) Program

The Hazard Communication (HazCom) Program is an important component of this HASP. The HazCom Program designates the project personnel responsible for the implementation and maintenance of hazardous chemical labeling, and employee training and information requirements. The HazCom Program also includes the hazardous chemical list for the Site, and describes the labeling and information requirements associated with the hazardous chemicals likely to be used on-Site.

9.1 Roles of Personnel

The SSO shall be the administrator of the Site's HazCom program in coordinating labeling, training, Material Safety Data Sheet (MSDS) information, hazardous chemical listings, subcontractor and client HazCom communications and information exchange, and any necessary trade secret requests. The SSO shall also maintain the Site's written HazCom Program and

monitor the implementation and effectiveness of this program. Upon request, The SSO shall also provide the name and phone number of the Company HazCom Program Administrator whose HazCom role, along with management, is defined by the Company HazCom Program (issued to all INTERA employees). Subcontractors are responsible for complying with all applicable INTERA policies on hazardous chemicals and for providing all HazCom information to the SSO for hazardous chemicals brought to the Site; the SSO shall then incorporate the subcontractor HazCom information into the Site's overall HazCom program. All INTERA Site personnel, other than the SSO, are responsible for the following:

- Knowing the Site location of the MSDSs and the HazCom written program;
- Identifying the Site HazCom program administrator;
- Competency in reading a MSDS and a label and knowing how to use the applicable sections for safe job performance;
- Understanding potential hazards associated with chemicals in your work area;
- Sending all received MSDSs to the SSO; and
- Notifying the SSO of products received with no labels or damaged labels or if you are uncertain of whether a MSDS is needed.

9.2 Labeling

The SSO shall be responsible for ensuring that all hazardous chemical containers on-Site are appropriately tagged, marked, or labeled to identify the material and provide the proper hazard warnings. The SSO shall also be responsible for ensuring that the labels are maintained as required. In addition, it is the responsibility of the SSO to check newly-purchased materials for labels prior to use.

9.3 Information and Training

The SSO shall also be responsible for informing and training all on-Site project personnel of the requirements of this plan, and the location and availability of the written HazCom Program including the list of hazardous chemicals and their MSDSs. The SSO shall be responsible for updating the Hazardous Chemicals List and the associated MSDS information.

9.4 Hazardous Chemical List

The chemicals of concern at the Site include acids used for preserving sample containers. In addition to the chemicals of concern, the investigation will involve the use of materials such as equipment calibration fluids (e.g. acids and bases), etc.

9.5 Storage and Labeling

All chemicals produced on-Site shall be properly labeled and disposed of. All chemicals purchased and shipped to the Site shall be stored in their original containers, and the manufacturer's labels shall not be removed. All chemicals that are transferred from a labeled container to another container shall be properly labeled. The label shall identify the material with the proper name that links that chemical to the hazardous chemical list and to the proper MSDS. The label shall also contain a brief hazard warning as to the hazardous effects of the chemical. Labels shall be legible and prominently displayed. The SSO shall review, maintain, and update label information at the beginning of each phase of the project fieldwork and prior to recommencing any fieldwork after a shutdown lasting more than 5 working days.

9.6 Posting Requirements

If a field office is established at the Site due to the duration of a project, a poster shall be displayed which explains the protections and obligations of employees under the OSHA. States with approved plans require that a state poster be displayed as well. The posters shall be displayed in a prominent place at all times. Besides the posters, employers shall post the annual summary of occupational injuries and illnesses each year during the month of February. Notices shall be posted informing employees of OSHA citations for violations, imminent danger rulings, or potential or actual exposures to toxic substances or harmful physical agents. The regulatory reference for these requirements is the Occupational Safety and Health Act of 1970 (P.L. 91-596; U.S. Code, Title 29, Part 651 et seq.).

10.0 Emergencies/Accidents

10.1 On-Site Personnel and Visitors

Illnesses, injuries, and accidents occurring on-Site shall be attended to immediately in the following manner:

- Check the accident scene to determine if you or anyone else is in danger;
- Call the emergency phone number (911) if the emergency or accident appears serious. Emergency numbers are listed in Table 2;
- Begin care for the injured or exposed person(s) by removing them from immediate danger if a neck or back injury is not suspected;
- Render minor first aid as necessary; decontaminate affected personnel as necessary;
- Evacuate other personnel on-Site to a safe place until the SSO determines that it is safe for work to resume;

- Report the accident to the Site Manager, the Project Health and Safety Officer, and the SSO immediately;
- Complete and Incident Investigation Report for all near misses and all injuries requiring medical attention;
- Collaborate with the Project Health and Safety Officer, the SSO, and the PM to develop procedures to prevent a recurrence.

If an emergency Site evacuation becomes necessary for any reason, the SSO shall alert all personnel to leave the Site. The off Site assembly point shall be designated by the SSO at the onset of field activities. Personnel shall not return to the Site until an all-clear notification has been received from the SSO.

10.2 Surrounding Community

In the highly unlikely event that a Site emergency has the potential to affect the community surrounding the Site, the SSO shall be responsible for notifying the police and the fire departments using the telephone numbers listed in Table 2. The SSO shall provide whatever technical assistance is needed by these agencies.

Figures



Figure 1 Map to Hospital

Copper Flat Mine
Hillsboro, NM

	1. Start out going NORTHEAST.	Map go 1.1 mi
	2. Turn SLIGHT RIGHT.	Map go 0.6 mi
	3. Turn SLIGHT RIGHT.	Map go 0.8 mi
	4. Turn SLIGHT RIGHT.	Map go 0.7 mi
	5. Turn LEFT onto NM-152.	Map go 12.3 mi
	6. Merge onto I-25 N via the ramp on the LEFT.	Map go 15.2 mi
	7. Take the I-25-BL exit, EXIT 79, toward TRUTH OR CONSEQUENCES.	Map go 0.2 mi
	8. Merge onto I-25 BL S / N DATE ST toward TRUTH OR CONSEQUENCES.	Map go 1.5 mi
	9. Turn LEFT onto E 9TH AVE.	Map go 0.5 mi

END 10. 800 E 9TH AVE. Map go 0.0 mi

Sierra Vista Hospital - (575) 894-2111
800 E 9th Ave, Truth Or Cnsqncs, NM 87901
Total Travel Estimate : **32.69 miles - about 41 minutes**

Tables

Table 1
Site Health and Safety Equipment Inventory Checklist

Emergency Response
☐ OSHA-Approved Industrial First Aid Kit
☐ Fire Extinguisher (1 Per Field Vehicle)
☐ Eye Wash
Personnel Protection
☐ Insect Repellent
☐ Safety Glasses
☐ Nitrile Gloves (Outer)
☐ Latex Disposable Gloves (Inner)
☐ Chemical-Resistant Coveralls (Tyvek™)/Polycoated Tyvek™ (Syranax™)
☐ Igloo™ Water Cooler/Cups
☐ Gatorade™
☐ Respirators (half-face and/or full face)
☐ Duct Tape
☐ Steel-Toed Boots
☐ Hard Hat
Personnel Decontamination
☐ 4-mil Plastic Drop Cloths
☐ Plastic Washtubs
☐ Sprayer
☐ Brushes
☐ Trash Bags
☐ Detergent
☐ Potable Or Distilled Water

Table 2
Emergency and Non-Emergency Phone Numbers

Contact	Affiliation	Phone #	Cell #	Address
Sierra Vista Hospital*	Hospital	(575) 894-2111 **Emergency: 911**		Sierra Vista Hospital 800 E 9th Ave Truth Or Cnsqncs, NM 87901
Cindy Ardito	INTERA Program Manager	(505) 246-1600 ext. 1206	(505) 379-7330	
Peter Castiglia	INTERA Project Manager	(505) 246-1600 ext. 1217	(505) 280-0680	
Lee Dalton	INTERA Deputy Project Manager/SSO/Field Team Leader	(505) 246-1600 ext. 1213	(505) 730-7372	
Angela Persico	INTERA Albuquerque Health and Safety Officer	(505) 246-1600, ext. 1207	(505) 228-8201	

***Hospital Route (Map included as Figure 1)**

Forms

FORM 1

HEALTH AND SAFETY PLAN COMPLIANCE AGREEMENT FORM

I have read the Health and Safety Plan and agree to comply with the guidelines and requirements for the safety of personnel.

_____

Name

_____

Company

_____

Signature

_____

Date

FORM 2

TAILGATE SAFETY MEETING ATTENDANCE FORM

Page __1___ of ___1___

DATE:_____ PROJECT NO.:_NMC-001-_____

PROJECT TITLE:__Copper Flat Mine Sampling_____

PROJECT TASK:_____

SAFETY TOPICS PRESENTED

Protective Clothing/Equipment _____

Emergency Procedures _____

Chemical Hazards _____

Physical Hazards _____

Mobile Phone _____

ATTENDEES

NAME (PRINTED)

_____	_____
_____	_____
_____	_____
_____	_____
_____	_____
_____	_____
_____	_____
_____	_____

Meeting Conducted by:

__Lee Dalton_____ _____

Name Printed

FORM 3

SITE PERSONNEL ACKNOWLEDGMENT FORM

By signing the following I acknowledge that I have read, understood, and agree to comply with the provided Site-specific Health and Safety Plan.

Printed Name/Affiliation	Signature	Date

FORM 4

SITE VISITOR'S LOG

Date	Time In/Out	Name	Organization	Purpose of Visit

FORM 5

INCIDENT INVESTIGATION FORM

Name of Employee involved in Incident or Injury
Date/Time of Incident/Injury
Location of Incident/Injury
Description of Incident/Injury and Severity
Task being Performed at time of Incident/Injury
Was Medical Treatment Necessary? (Yes or No)
If Yes, Medical Treatment was Administered at the Following Medical Facility
Location of Medical Facility
Name of Doctor Providing Treatment

Description of Medical Treatment
Expected Length of Medical Time-off for Accident
Suspected or Known Cause of Accident
Methods to be implemented or utilized to prevent future Incidents or Injuries

APPENDIX A

Exposure Prevention Plan

APPENDIX A
Exposure Prevention Plan

1.0 Heat Related Hazards

The increase in ambient air temperature and decreased body ventilation caused by protective outerwear creates an increase in the potential for injury, specifically, heat casualties. Site personnel shall be instructed in the identification of a heat stress victim, the first-aid treatment procedures for the victim, and the prevention of heat stress casualties.

1.1 Identification and Treatment

Heat Exhaustion

Symptoms: Usually begins with muscular weakness, dizziness, nausea, and a staggering gait. Vomiting is frequent. The bowels may move involuntarily. The victim is very pale, his skin is clammy, and he may perspire profusely. The pulse is weak and fast, and breathing is shallow. He may faint unless he lies down. This may pass, but sometimes it remains and death could occur.

First Aid: Immediately remove the victim to Zone 2, Contamination Reduction Zone, in a shady or cool area with good air circulation. Remove all protective outerwear. Call the facility emergency number. Treat the victim for shock (make him lie down, raise his feet 6-12 inches and keep him warm, but loosen all clothing). If the victim is conscious, it may be helpful to give him sips of a salt-water solution (one teaspoon of salt to one glass of water). Transport victim to a medical facility as soon as possible.

Heat Stroke

Symptoms: This is the most serious of heat casualties due to the fact that the body overheats excessively. Body temperatures often are between 107 °F and 110 °F. First, there is often pain in the head, dizziness, nausea, and the skin is dry, red, and hot. Unconsciousness follows quickly and death is imminent if exposure continues. The attack shall usually occur suddenly.

First Aid: Immediately evacuate the victim to a cool and shady area in the Contamination Reduction Zone. Lay the victim on his/her back with the head and shoulders slightly elevated. It is imperative that the body temperature be lowered immediately. This can be done by applying cold wet towels or ice bags to the head. Sponge off the bare skin with cool water or rubbing alcohol, if available, or even place victim in a tub of cool water. The main objective is to cool the victim without chilling. Give no stimulants. Transport the victim to a medical facility as soon as possible.

1.2 Prevention of Heat Stress

One of the major causes of heat casualties is the depletion of body fluids. Personnel shall replace water and salt loss from sweating. Salts can be replaced by either a 0.1 percent salt solution, more heavily salted foods, or commercial mixes such as Gatorade. The commercial mixes are advised for personnel on low sodium diets.

A work schedule shall be established so that the majority of the work shall be performed during the hours of the day when ambient air temperature levels are not at their highest.

A work/rest guideline shall be implemented for personnel required wearing Level C protection. The maximum wearing time guidelines are as follows:

Ambient Temperatures	Maximum Wearing Time
Above 90 °F	½ hour
80 – 90 °F	1 hour
70 – 80 °F	2 hours
60 – 70 °F	3 hours
50 – 60 °F	4 hours
40 – 50 °F	5 hours
30 – 40 °F	6 hours
Below 30 °F	8 hours

A sufficient period shall be allowed for personnel to "cool down." This may require shifts of workers during operations.

1.3 Heat Stress Monitoring

For monitoring the body's recuperative ability under excess heat, one or more of the following techniques shall be used as a screening mechanism.

Heart rate (HR) shall be measured by monitoring the radial pulse for 30 seconds as early as possible in the resting period. The HR at the beginning of the rest period should not exceed 110 beats per minute. If the HR is higher, the next work period shall be shortened by 10 minutes (or 33 percent), while the length of the rest period stays the same. If the pulse rate is 100 beats per minute at the beginning of the next rest period, the following work cycle shall be shortened by 33 percent.

Body temperature shall be measured orally with a clinical thermometer as early as possible in the resting period. Oral temperature (OT) at the beginning of the rest period should not exceed 99° F. If it does, the next work period shall be shortened by 10 minutes (or 33 percent), while the length of the rest period stays the same. However, if the OT exceeds 99.7 °F at the beginning of the next

period, the following work cycle shall be further shortened by 33 percent. OT shall be measured again at the end of the rest period to make sure it has dropped below 99 °F.

Monitoring of personnel wearing protective clothing shall commence when the ambient temperature is 70 °F or above. Frequency of monitoring shall increase as the ambient temperature increases or if slow recovery rates are indicated. When temperatures exceed 80 °F, workers shall be monitored for heat stress after every work period.

Ideally, body fluids shall be maintained at a constant level during the workday. This requires replacement of salt lost in sweat as well.

Good hygienic standards shall be maintained by frequent changes of clothing and daily showering. Clothing shall be permitted to dry during rest periods. Persons who notice skin problems shall immediately consult medical personnel.

2.0 Cold Weather Related Hazards

Cold stress can occur when Site personnel are subject to low air temperatures, wind, rain, or wet clothing. When working in these conditions, workers should don wind- and/or water-proof clothing before getting wet or cold, wear wool or polypropylene next to their bodies, and wear layers that can be removed or added as needed. Cold stress is manifest as either hypothermia or frostbite.

Hypothermia

Hypothermia is a cold-induced decrease in the core body temperature, which can decrease attentiveness and manual dexterity. Hypothermia produces shivering, numbness, drowsiness, muscular weakness, and if severe enough, death**. To treat:** Take the victim indoors if possible. Provide rapid but gentle re-warming. Remove wet or cold garments and provide warm, dry clothing or covering. Dry the person thoroughly. If the victim is conscious, give a hot drink. Wrap the victim together with warm water bottles, persons in blankets, or a sleeping bag, if necessary. Call for medical assistance immediately.

Frostbite

Frostbite results from the constriction of blood vessels in the extremities and decreases the supply of warm blood to these areas. The drop in blood supply may result in the formation of ice crystals in the tissues causing tissue damage. The symptoms of frostbite are white or grayish skin, blisters, or numbness. **To treat:** Bring the victim indoors and re-warm the areas quickly in water of 102 °F to 105° F. Give the victim a warm drink, but not caffeinated beverages or alcohol. Do not allow the victim to smoke because it tends to constrict the blood vessels in the

skin. Keep the frozen parts in warm water or covered with warm cloths for 30 minutes and then elevate the injured area and protect it from injury. Do not allow the blisters to be broken. Use sterile, soft, dry material to cover the injured areas. Keep the victim warm and get immediate medical care.

THEMAC RESOURCES
New Mexico Copper Corporation

December 29, 2010

New Mexico Copper Corporation
2425 San Pedro Dr, NE, Suite 100
Albuquerque, New Mexico 87110
(505) 382-5770

Mr. Michael Smith
Geologist
US Department of the Interior
Bureau of Land Management
Las Cruces District Office
1800 Marquess Street
Las Cruces, New Mexico 88005

Re: Submittal of the Plan of Operations for the Copper Flat Mine, Sierra County, New Mexico per 43 CFR 3809 Requirements.

Dear Mr. Smith:

New Mexico Copper Corporation (NMCC) is pleased to submit the Copper Flat Mine Plan of Operations (PoO). NMCC is proposing the re-establishment of a polymetallic mine and processing facility located near Hillsboro, New Mexico. The proposed mine would consist of an open pit mine, flotation mill, tailings impoundment, waste rock disposal areas, a low-grade ore stockpile, and ancillary facilities. NMCC is submitting this PoO per the 43 CFR 3809 requirements.

NMCC looks forward to working with the BLM to bring this facility back into production in accordance to all applicable federal and state regulations. Please contact me at 505.382.5770 or steve.raugust@themacreources.com or Mr. Barrett Sleeman, CEO of NMCC at 604.495.6723 or barrettsleeman@hotmail.com for any additional questions, comments, or concerns.

Respectfully,

J. Steven Raugust, PG
Project Manager

Cc: Barrett Sleeman, P.Eng, New Mexico Copper Corporation

THEMAC RESOURCES

New Mexico Copper Corporation

Copper Flat Mine
Plan of Operations

Report Prepared for:

U.S. Department of the Interior
Bureau of Land Management
Las Cruces District Office
1800 Marquess Street
Las Cruces, NM 88005-3370

Report Submitted by:

NEW MEXICO COPPER CORPORATION
2425 San Pedro Dr. Suite 100
Albuquerque, NM 87110
Office: (505) 382-5770

December 2010

01358

Table of Contents

1 Project Summary 1-1
1.1 Introduction 1-1
1.2 Project Location 1-1
1.3 Project Background 1-1

2 Corporate Information 2-1
2.1 Name & Business Address of Individual Completing Application 2-1
2.2 Corporation Information 2-1
2.3 Federal Taxpayer ID Number 2-2
2.4 Registered Agent 2-2
2.5 List of BLM Claims and Serial Numbers 2-2
2.6 Land Status 2-2
2.7 Permits and Approvals 2-4
2.7.1 Federal Permits and Approvals 2-4
2.7.2 State Permit and Approvals 2-4

3 Proposed Operating Plan 3-1
3.1 Introduction 3-1
3.2 Proposed Plan 3-2
3.2.1 Open Pit 3-2
3.2.2 Waste Rock Disposal Area and Low-Grade Stockpile 3-4
3.2.3 Ore Processing 3-6
3.2.4 Haul Roads and On-Site Service Roads 3-11
3.2.5 Project Work Force and Schedule 3-12
3.2.6 Electrical Power 3-12
3.2.7 Water Supply 3-13
3.2.8 Fencing and Exclusionary Devices 3-15
3.2.9 Growth Media 3-16
3.2.10 Borrow Areas 3-16
3.2.11 Ancillary Facilities 3-16
3.2.12 Inter-Facility Disturbance 3-17
3.2.13 Transportation 3-17
3.3 Exploration Activities 3-18
3.4 Applicant Committed Environmental Protection Measures and Committed Practices 3-18
3.4.1 Air Quality 3-18
3.4.2 Water Resources 3-19
3.4.3 Erosion and Sediment Control 3-20
3.4.4 Wildlife 3-20
3.4.5 Cultural Resources 3-20
3.4.6 Protection of Survey Monuments 3-21
3.4.7 Health and Safety and Emergency Response 3-21
3.4.8 Fire Protection 3-22
3.4.9 Invasive, Non-native Species 3-22
3.4.10 Materials and Waste Management 3-22
3.4.11 Spill Contingency 3-25
3.4.12 Monitoring 3-26
3.4.13 Technical Updates 3-26
3.4.14 Growth Media/Cover Salvage and Storage 3-26
3.4.15 Sustainability 3-27

3.5 Operating Plans 3-27

4 Environmental Setting 4-1
4.1 Introduction 4-1
4.2 Geology 4-1
4.2.1 Regional Geologic Setting 4-1
4.2.2 Geology of Copper Flat Mine Site 4-2
4.2.3 Description of the Ore Body 4-4
4.3 Climate 4-6
4.4 Hydrology 4-7
4.4.1 Surface Water 4-7
4.4.2 Groundwater 4-12
4.5 Soils 4-19
4.6 Vegetation 4-20
4.6.1 Chihuahuan Desert Scrub (or Creosote Bush) Community 4-20
4.6.2 Desert Grassland 4-21
4.6.3 Pinion-Juniper Community 4-21
4.6.4 Aquatic Vegetation 4-21
4.6.5 Vegetative Productivity 4-22
4.7 Wildlife 4-23
4.7.1 Mammals 4-23
4.7.2 Birds 4-23
4.7.3 Reptiles 4-23
4.7.4 Invertebrates 4-24
4.7.5 Fisheries 4-24
4.8 Threatened, Endangered, or Candidate Species 4-24
4.8.1 Vegetation 4-24
4.8.2 Wildlife 4-24
4.9 Range Resources 4-25
4.10 Air Quality 4-26
4.11 Cultural Resources 4-26

5 Reclamation and Closure 5-1
5.1 Introduction 5-1
5.2 Statutory and Regulatory Requirements 5-1
5.3 Post-Mining Land Use 5-1
5.4 Summary of Disturbance 5-2
5.5 Reclamation Plan 5-2
5.6 Implementation 5-3
5.7 Environmental Considerations for Reclamation 5-4
5.7.1 Signs, Markers and Safeguarding 5-4
5.7.2 Wildlife and Domestic Animal Protection 5-4
5.7.3 Cultural Resources 5-5
5.7.4 Hydrologic Balance 5-5
5.7.5 Impoundments 5-7
5.7.6 Prevention of Mass Movement 5-7
5.7.7 Riparian Areas 5-7
5.7.8 Roads 5-8
5.7.9 Surface Facilities or Roads Not Subject to Reclamation 5-8
5.7.10 Drill Hole Plugging and Water Well Abandonment 5-8
5.7.11 Post-Closure Monitoring 5-9
5.8 Site Stabilization and Configuration 5-9
5.9 Plant Growth Media and Cover Materials 5-10
5.9.1 Removal and Storage 5-10

5.9.2 Placement 5-12
5.9.3 Amendments 5-13
5.10 Revegetation 5-13
5.10.1 Seed Mixtures 5-14
5.10.2 Planting Techniques 5-15
5.11 Revegetation Success 5-15
5.12 Reclamation Research 5-16
5.13 Concurrent Reclamation 5-17
5.14 Interim Reclamation 5-17
5.15 Interim Management Plan 5-17
5.15.1 Schedule of Anticipated Periods of Temporary Closure 5-18
5.15.2 Measures to Stabilize Excavations and Workings 5-18
5.15.3 Measures to Isolate or Control Toxic or Deleterious Materials 5-19
5.15.4 Storage or Removal of Equipment, Supplies, and Structures 5-19
5.15.5 Monitoring During Periods of Non-Operation 5-19
5.16 Facility-Specific Reclamation 5-20
5.16.1 Mine Pit 5-20
5.16.2 Waste Rock Disposal Areas and Low-Grade Stockpile 5-21
5.16.3 Plant Site 5-23
5.16.4 Tailings Impoundment 5-24
5.16.5 Ancillary Project Facilities 5-24
5.17 Estimated Reclamation Costs 5-26

6 Acknowledgment 6-1

7 Bibliography 7-1

List of Tables

Table 2-1: Legal Description of Proposed Project Area 2-2
Table 2-2: Summary of Proposed Disturbance 2-3
Table 2-3: Major Permits and Approvals Required 2-5
Table 3-1: Summary of NMCC Proposed Disturbance within the Plan Boundary 3-2
Table 3-2: Summary of Project Electrical Demand 3-13
Table 5-1: Waste Rock Disposal Facility Design Parameters 5-7
Table 5-2: Estimate of Available Soil from Newly Disturbed Areas 5-11
Table 5-3: Estimated Reclamation Cover Requirements 5-11
Table 5-4: Proposed Reclamation Seed Mixes 5-14

List of Figures

(Located at back of document)

Figure 1-1: Project Location Map
Figure 1-2: Regional Location
Figure 2-1: Land Status
Figure 3-1: Proposed Facility Layout
Figure 3-2: Proposed Facility Topography
Figure 3-3: Open Pit Cross-section
Figure 3-4: Typical Waste Rock Disposal Facilities Cross-sections
Figure 3-5: Proposed Process Circuit
Figure 3-6: Typical Haul Road Cross-section
Figure 4-1: Regional Surface Geology
Figure 4-2: Schematic Geologic Cross Section (A-A')
Figure 4-3: Geologic Structural Features of the Region
Figure 4-4: Geologic Schematic of the Hillsboro Mining District, New Mexico
Figure 4-5: Proposed Surface Water Sampling Locations
Figure 4-6: Proposed Parallel Profiles for Pit Lake Survey
Figure 4-7: Lower Rio Grande Basin
Figure 4-8: Conceptual Model of Groundwater Flow System
Figure 4-9: Spring and Stream Locations
Figure 4-10: Water Level Contours
Figure 4-11: Water Level Map of Copper Flat Pit Area
Figure 4-12: Conceptual Model of Pit Lake Monitoring Well Relationship with Water Quality Reports
Figure 4-13: Conceptual Design, Tailings Seepage Control
Figure 4-14 Regional Groundwater Well Locations
Figure 4-15 Proposed Monitoring Well Program
Figure 5-1: Proposed Project Schedule
Figure 5-2: Post-Reclamation Topography
Figure 5-3: Typical Reclaimed Road Cross-section

List of Appendices

(Located at back of document)

APPENDIX A: Claims List
APPENDIX B: Runoff Calculations
APPENDIX C: Mine Waste Management Plan
APPENDIX D: Tailings Impoundment Conceptual Design Report (Golder, 2010)
APPENDIX E: Preliminary Spill Contingency Plan
APPENDIX F: Quality Assurance Plan (Intera, 2010)

List of Acronyms

amsl	above mean sea level
ARD	acid rock drainage
AWRM	Active Water Resource Management
BATF	Bureau of Alcohol, Tobacco, and Firearms
bgs	below ground surface
BLM	Bureau of Land Management
BMP	Best Management Practice
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
CFQM	Copper Flat Quartz Monzonite
cfs	cubic feet per second
CO	carbon monoxide
DEIS	Draft Environmental Impact Statement
EA	Environmental Assessment
EAR	Environmental Assessment Report
EIS	Environmental Impact Statement
EMNRD	Energy, Minerals and Natural Resources Department
EPA	U.S. Environmental Protection Agency
ESA	Endangered Species Act
°F	degrees Fahrenheit
FCC	Federal Communications Commission
FEIS	Final Environmental Impact Statement
FLPMA	Federal Land Policy Management Act
ft	feet
gpm	gallons per minute
GWQB	Ground Water Quality Bureau
HSR	Human Systems Research
HSUs	hydrostratigraphic units
IHICS	Integrated Habitat Inventory Classification System
km	kilometers
kWh	kilowatt hours
LRGB	Lower Rio Grande Underground Water Basin
Ma	million years ago
mg/L	milligrams per liter
MMD	Mining and Mineral Division
MSDS	Material Safety Data Sheets
MSF	Middle Santa Fe Group hydrostratigraphic unit
MSHA	Mining Safety and Health Administration
NEPA	National Environmental Policy Act
NMCC	New Mexico Copper Corporation
NMED	New Mexico Environment Department
NMEMNRD	New Mexico Energy, Mineral and Natural Resources Department
NPDES	National Pollution Discharge Elimination System
NRC	National Response Center
NRHP	National Register of Historic Places
O&M	Operation & maintenance
OSE	Office of the State Engineer
PFEIS	Preliminary Final Environmental Impact Statement
PLS	pure live seed
PMP	probable maximum precipitation
PoO	Plan of Operations

ppm	parts per million
RCRA	Resource Conservation and Recovery Act
RMP	Resource Management Plan
ROD	Record of Decision
ROW	rights-of-way
SAG	semi-autogenous
SARA	Superfund Amendments and Reauthorization Act
SCP	Spill Contingency Plan
SCS	Soil Conservation Service
SHPO	State Historic Preservation Office
SMIO	State Mine Inspector's Office
TDS	Total dissolved solids
tpd	tons per day
TPQ	Threshold Planning Quantity
TSF	tailings storage facility
TSP	Total Suspended Particulates
USACE	U.S. Army Corp of Engineers
USF	Upper Santa Fe Group hydrostratigraphic unit
USFS	U.S. Department of Agriculture, Forest Service
USFWS	U.S. Fish and Wildlife Service
WQCC	New Mexico Water Quality Control Commission

1 Project Summary

1.1 Introduction

The Copper Flat Project (Project) is the proposed re-establishment of a poly-metallic mine and processing facility located near Hillsboro, New Mexico. The proposed Project would consist of an open pit mine, flotation mill, tailings impoundment, waste rock disposal areas, a low-grade ore stockpile, and ancillary facilities. In most respects, the facilities, disturbance and operations would be similar to the former operation.

The Project is owned and operated by the New Mexico Copper Corporation (NMCC), a wholly owned subsidiary of THEMAC Resources Group Limited (THEMAC), information for which is provided in Section 2.

1.2 Project Location

The Project is located in Sierra County, New Mexico, approximately 30 miles southwest of Truth or Consequences and five miles northeast of Hillsboro (**Figure 1-1**). The general area can be reached by traveling south 15 miles from Truth or Consequences on Interstate Highway 25, then 12 miles west on New Mexico Highway 152. The Project area lies two miles west-northwest from Highway 152. The regional location of the Project is shown on **Figure 1-2**.

1.3 Project Background

Development of the Copper Flat Project began in the 1970's by Quintana Mineral Corporation. An Environmental Assessment Report (EAR) was prepared for the Project in 1977 (Glover, 1977). The U.S. Department of the Interior, Bureau of Land Management, Las Cruces District Office (BLM) prepared an Environmental Assessment Record to analyze potential impacts resulting from granting rights-of-way (ROW) for utilities and access roads, as well as impacts resulting from the mining Project (BLM, 1978). The ROWs were approved by the BLM in the Environmental Assessment Record. Air quality, tailings discharge, and water discharge permits were issued by the State of New Mexico; however, the air permit was closed in 2002 due to inactivity, the groundwater discharge permit remains open, but cannot be renewed until a Stage 1 Abatement Plan for a small groundwater impact associated with the existing tailings impoundment has been approved by the New Mexico Environment Department (NMED) Ground Water Quality Bureau (GWQB). The New Mexico Energy Minerals and Natural Resources Department (EMNRD), Mining and Mineral Division (MMD) mining permit has also expired.

In 1982, the Copper Flat Partnership, Ltd. developed and operated the Project, which consisted of an open pit copper mine, a 15,000-ton per day flotation mill, and a 515-acre tailings impoundment. The Copper Flat mine officially commenced full, commercial production in April of 1982. In July 1982 the mine was shut down due to low copper prices and other economic considerations. In 1986 all on-

site surface facilities were removed and a BLM approved program of non-destructive reclamation was carried out. Most of the property's infrastructure, including building foundations, power lines and water pipelines were preserved for reuse in the future in the event copper prices recovered sufficiently to make re-establishing the Project economically viable.

In 1991, a proposed Plan of Operations was filed with the BLM by Gold Express Corporation to re-establish the Copper Flat Project. The BLM initiated an Environmental Assessment (EA) because federal land would be "newly" disturbed. New archaeological, biologic, threatened and endangered species, air quality, hydrologic and socioeconomic studies were conducted. However, it was determined in 1993 that an Environmental Impact Statement (EIS) would be required for the Project due to concerns related to several water quality issues, and the EA was never completed.

Alta Gold Company (Alta) acquired the Project in early 1994 and proposed to rebuild the Copper Flat mining facility essentially as it existed in 1982. Alta submitted an updated Plan of Operations (PoO), and associated environmental baseline data, to the BLM for initiation of the EIS process. The *Draft Environmental Impact Statement – Copper Flat Project* (DEIS) was completed by the BLM in 1996. A *Preliminary Final Environmental Impact Statement – Copper Flat Project* (PFEIS) was prepared by the BLM in 1999 following public comment on the DEIS. However, the EIS and Record of Decision (ROD) were never finalized due to Alta’s declaration of bankruptcy in early 1999.

2 Corporate Information

New Mexico Copper Corporation owns and controls the entire interest in the proposed Copper Flat Project. NMCC contact information is:

New Mexico Copper Corporation
2425 San Pedro, NE, Suite 100
Albuquerque, New Mexico 87110
505.382.5770

THEMAC Resources Group Limited (THEMAC), a Yukon corporation, owns and controls all of the shares of NMCC. THEMAC's contact information is:

THEMAC
1066 West Hastings Street, Suite 2000
Vancouver, British Columbia
Canada, V6E 3X2
604.495.6723

2.1 Name & Business Address of Individual Completing Application

Name:	Barrett G. Sleeman
Title:	Chief Executive Office, President
Business Name:	New Mexico Copper Corporation
Business Address:	2425 San Pedro, NE, Suite 100
	Albuquerque, New Mexico 87110
Telephone Number:	604.495.6723
e-mail:	barrettsleeman@hotmail.com

2.2 Corporation Information

Corporation Name:

New Mexico Copper Corporation
2425 San Pedro, NE, Suite 100
Albuquerque, New Mexico 87110
505.382.5770

Corporation Officer's Information:

Chief Executive Officer:	Barrett G. Sleeman
Chief Financial Officer:	Barrett G. Sleeman
Secretary:	Barrett G. Sleeman

2.3 Federal Taxpayer ID Number

Taxpayer ID Number: 80-0612011

2.4 Registered Agent

Registered Resident Agent:

Name:	Mark K. Adams
Business Address:	315 Paseo de Peralta Santa Fe, New Mexico 87501
Telephone Number:	505.954.3902
e-mail:	mkadams@rodey.com

2.5 List of BLM Claims and Serial Numbers

Proposed mining and related surface disturbance would be conducted on unpatented lode, placer, and mill-site claims owned or controlled by NMCC on BLM-administered lands or on private land controlled by NMCC. Claim names and BLM serial numbers are provided in

Appendix A.

There are no state lands or U.S. Department of Agriculture, Forest Service (USFS) lands located within the PoO boundary. **Table 2-1** presents the legal description of the project. The land status of the Project (including the existing disturbances attributed to previous operators) is presented on **Figure 2-1**.

Table 2-1: Legal Description of Proposed Project Area

Township	Range	Sections
15 South	7 West	25,26,27, 35, & 36
15 South	6 West	30 & 31
16 South	6 West	6

2.6 Land Status

The Copper Flat Project is comprised of contiguous and noncontiguous lands that include patented and unpatented mining claims (lode, placer, and mill site), and private parcels. The area inside the proposed PoO boundary is 2,190 acres. Activity at the Copper Flat Mine in 1982 disturbed approximately 358 acres of BLM-administered public lands and 331 acres of private lands.

The re-establishment of the Copper Flat Mine would thus affect 1395 acres, 910 acres of which have been previously disturbed and 485 acres which will be newly disturbed land (**Table 2-2**). Overall, the Copper Flat Project would disturb approximately 661 acres of unpatented mining claims on public land and 734 acres of private land controlled by NMCC (**Figure 2-1**). Approximately 65 percent of the area needed for the proposed PoO has been disturbed by prior operations, and approximately 90 percent of the ore would be mined from private land.

Table 2-2: Summary of Proposed Disturbance

Facility[1]	Existing Disturbance			Proposed Incremental Disturbance			Total Disturbance		
	Public	Private	Total	Public	Private	Total	Public	Private	Total
Roads									
Access Road	1.0	1.0	2.0	7.0	3.0	10.0	8.0	4.0	12.0
Haul Roads	5.0	16.0	21.0	2.0	15.0	17.0	7.0	31.0	38.0
Total Roads	**6.0**	**17.0**	**23.0**	**9.0**	**18.0**	**27.0**	**15.0**	**35.0**	**50.0**
Pits, Adits, Trenches									
Pits	11.0	91.0	102.0	1.0	16.0	17.0	12.0	107.0	119.0
Total Pits, Adits, Trenches	**11.0**	**91.0**	**102.0**	**1.0**	**16.0**	**17.0**	**12.0**	**107.0**	**119.0**
Tails									
Tailings Facility	131.0	341.0	472.0	22.0	53.0	75.0	153.0	394.0	547.0
Total Tails	**131.0**	**341.0**	**472.0**	**22.0**	**53.0**	**75.0**	**153.0**	**394.0**	**547.0**
Process Ponds									
Ponds	5.0	1.0	6.0	1.0	10.0	11.0	6.0	11.0	17.0
Total Ponds	**5.0**	**1.0**	**6.0**	**1.0**	**10.0**	**11.0**	**6.0**	**11.0**	**17.0**
Waste Rock Facilities									
Waste Rock Facilities	32.0	1.0	33.0	130.0	15.0	145.0	162.0	16.0	178.0
Total Waste Rock Facilities	**32.0**	**1.0**	**33.0**	**130.0**	**15.0**	**145.0**	**162.0**	**16.0**	**178.0**
Ancillary Facilities									
Misc.	122.0	78.0	200.0	13.0	42.0	55.0	135.0	120.0	255.0
Diversions	25.0	12.0	37.0	8.0	3.0	11.0	33.0	15.0	48.0
Topsoil Stockpiles	1.0	7.0	8.0	17.0	4.0	21.0	18.0	11.0	29.0
Stockpiles (Low-grade Ore)	21.0	1.0	22.0	12.0	0.0	12.0	33.0	1.0	34.0
Building Areas[2]	7.0	0.0	7.0	67.0	4.0	71.0	74.0	4.0	78.0
Total Yards	**176.0**	**98.0**	**274.0**	**117.0**	**53.0**	**170.0**	**293.0**	**151.0**	**444.0**
Exploration									
Roads, Trenches, Drill Pads, etc.	0.0	0.0	0.0	20.0	20.0	40.0	20.0	20.0	40.0
Total Exploration	**0.0**	**0.0**	**0.0**	**20.0**	**20.0**	**40.0**	**20.0**	**20.0**	**40.0**
Total	**361.0**	**549.0**	**910.0**	**300.0**	**185.0**	**485.0**	**661.0**	**734.0**	**1395.0**

Notes:

1. All acres are rounded up to the nearest 1 acre.

2. Mill plant sites, substation, reagent building, primary crusher, process water storage, concentrate storage, thickener facility, coarse ore stockpile, administration building, offices, shops, storage, assay lab, septic system.

Portions of the waste rock disposal areas, and the crushing facility and the mill facility would be located on public land subject to unpatented mining claims controlled by NMCC. Approximately 28 percent of the tailings impoundment and 10 percent of the open pit would be located on public land subject to mining claims controlled by NMCC.

Approximately 56 percent of the proposed disturbance on public land was disturbed by the previous operation. On the private land, approximately 77 percent of the surface needed for the mine has been disturbed by the prior operation. The majority of the tailings storage land is privately owned and controlled by NMCC.

2.7 Permits and Approvals

2.7.1 Federal Permits and Approvals

Alta initiated a National Environmental Policy Act (NEPA) review of the proposed Project in 1994 by notifying the BLM (Las Cruces District Office) that the company had purchased the Project from Gold Express and was assuming legal responsibility for the Plan of Operations initially submitted in 1991. The BLM then began the process of preparing an EIS. The DEIS was completed in 1996, and the PFEIS was completed in 1999. However, neither a Final EIS (FEIS) nor ROD was issued for the Project as a result of Alta's bankruptcy in 1999.

In January 1996, a Biological Assessment (BA) was prepared for submission to the U.S. Fish and Wildlife Service (USFWS) in accordance Section 7 (c) of the Endangered Species Act (ESA). This consultation process is required to ensure that any action authorized, funded or carried out by a federal agency would not adversely affect a federally listed threatened or endangered species. The major federal permits and approvals required are shown in **Table 2-3**.

2.7.2 State Permit and Approvals

A number of state permits would also be required for the Project. The New Mexico Environment Department (NMED) will issue most of these permits, including air quality permits and groundwater discharge permits. Alta submitted an application for a modification to the existing groundwater Discharge Permit (DP-001) for the Project in early 1995. However, DP-001 was suspended until a Stage 1 Abatement Plan for a small groundwater impact associated with the existing tailings impoundment has been submitted and approved. In addition, an application for a revised Air Quality Permit (No. 365-M-1) was also submitted by Alta in early 1995. This permit was closed in 2002 due to inactivity.

In addition to approval by the State under the New Mexico Mining Act, NMCC would secure a number of additional state and federal permits and approvals. These are also listed in **Table 2-3**.

Table 2-3: Major Permits and Approvals Required

Permit/Approval	Granting Agency
Federal	
Approval of Plan of Operations	U.S. Bureau of Land Management (BLM)
National Dredge and Fill Permit (Section 404)	U.S. Army Corp of Engineers (USACE)
FCC License	Federal Communications Commission (FCC)
MSHA Registration	Mining Safety and Health Administration (MSHA)
National Pollution Discharge Elimination System (NPDES), Including Stormwater Discharge	U.S. Environmental Protection Agency (EPA)
Explosives Permit	Bureau of Alcohol, Tobacco, and Firearms (BATF)
State	
Mining Permit	New Mexico Energy, Mineral and Natural Resources Department (NMEMNRD)- Mining Act Reclamation Bureau
Mine Registration	NMEMNRD – Mine Registration, Reporting, and Safeguarding Program
Water Pollution Control Permits	New Mexico Energy, Mineral and Natural Resources Department - Mining Act Reclamation Bureau
Permit to Construct (Air Quality)	New Mexico Environment Department - Air Quality Bureau
Permit to Operate (Air Quality)	New Mexico Environment Department - Air Quality Bureau
Permit to Appropriate Water	New Mexico State Engineer's Office
Permits for Dam Construction and Operations	New Mexico State Engineer's Office
Approval to Operate a Sanitary Landfill	New Mexico Environment Department - Solid Waste Bureau
Liquid Waste System Discharge Permit	New Mexico Environment Department - Groundwater Bureau
Tailings Discharge Permit	New Mexico Environment Department - Groundwater Bureau (DP-001)
Cultural Resources Clearance Surveys	State Historic Preservation Office
Endangered Plant Species Permit, if applicable	NMEMNRD Forestry Division

3 Proposed Operating Plan

3.1 Introduction

Relevant aspects of the planned operations are summarized in this section. The Proposed Action is the operation as proposed by Gold Express Corporation in 1991, adopted by Alta in 1994 (BLM, 1996), and modified and updated by NMCC in 2010. The proposed facility layout is shown on **Figure 3-1.** A topographic map of the project facilities is provided in **Figure 3-2**.

The operating plan discussed below includes an optional plan for placer mining of the alluvium beneath the proposed tailings storage facility (TSF). The excavated alluvium would be gravity separated to extract coarse gold and stockpiled for later use as reclamation cover material. Additional exploration sampling is being proposed to evaluate the feasibility of this option.

The mine design has many of the same mining plans and elements outlined by Gold Express and Alta Gold; all of these have been previously discussed in the DEIS and PFEIS that was being prepared in the late 1990s related to Alta's mine proposal—mainly focused on reactivating the mine plans and processes of Quintana of the early 1980s. Because most of the foundations of the facility infrastructure from previous operations remains in place and are central to the mining processes, alternate locations of many of the facilities were not considered practical.

The NMCC-proposed operation includes the following activities:

- Expand the project boundary to include additional land controlled by NMCC;
- Provide for exploration over entire proposed plan area;
- Expand the existing open pit;
- Construct haul and secondary mine roads;
- Construct, operate and reclaim three waste rock disposal facilities;
- Construct, operate and reclaim one or more low-grade ore stockpiles;
- Construct, operate and reclaim a mill and associated processing facilities;
- Construct, operate and reclaim a tailings impoundment facility;
- Construct ancillary buildings (administration offices, laboratory, truck shop, reagent building, substation and gatehouse, etc.);
- Secure and construct a suitable water supply network;
- Construct growth media stockpiles; and
- Construct and maintain surface water diversions. **Table 3-1** presents a summary of the proposed total disturbance.

Table 3-1: Summary of NMCC Proposed Disturbance within the Plan Boundary

Disturbance Type	Public Lands	Private Lands	Total
Tailings Storage Facility	**153**	**394**	**547**
Open Pit	**12**	**107**	**119**
Waste Rock Disposal Areas	**162**	**16**	**178**
Haul Roads	**7**	**31**	**38**
Access Roads	**8**	**4**	**12**
Stormwater Diversion Structures	**33**	**15**	**48**
Miscellaneous Areas[1]	**260**	**136**	**444**
Exploration	**20**	**20**	**40**
Total Disturbance	**661**	**734**	**1395**

Notes:
1. Includes mill areas, stockpiles and other miscellaneous disturbance areas (including inter-facility disturbance generally associated with construction activities).

3.2 Proposed Plan

3.2.1 Open Pit

The mining of new ore would entail expansion of the existing open pit. The ore body at Copper Flat is exposed at and near the surface and would be mined by conventional front end loader and shovel open pit methods in a manner similar to the previous operation. The open pit mine is currently proposed to operate on two (2), 10-hour shifts per day, seven (7) days per week, for at least 47 weeks per year. However, this production schedule is subject to change based on future economics of the project. Over the life of the Project, the mine would produce approximately 96 million tons of copper ore, 37 million tons of overburden and waste rock, and 19 million tons of low-grade copper ore (less than 0.20 percent copper). The low-grade copper ore would likely be processed during operations as blend material and/or at the end of the mine life. As such, it will require stockpiling until such time at it is suitable for milling and processing. The operation would process 17,500 short tons per day of ore through the copper sulfide flotation mill using standard technology similar to that of the previous

operation. While the operation would focus primarily on copper and molybdenum, other poly-metallic resources, including gold, silver, and possible rare-earth elements, may be economically extractable from the Copper Flat ore. These options resources are currently be evaluated.

Annually, the mining operation would produce an estimated 5.8 million tons of copper ore and 1.1 million tons of low-grade copper material. Waste rock production is estimated to average 2.2 million tons per year (ranging from 100,000 to 6.4 million tons annually), with tailings production estimated at 5.7 million tons annually. An operational life of approximately 17 years is currently projected.

Preproduction stripping of overburden was completed in 1982 during the previous operation. Approximately 3 million tons of overburden material was stripped and over 1.2 million tons of ore were mined from the existing pit during the early 1980s. Under the NMCC proposed PoO, the Copper Flat ore body would be mined by a multiple bench (30 foot high), open pit method. The existing pit would eventually be enlarged to 2,500 feet by 2,500 feet with an ultimate depth of 900 feet. The area of the pit would be expanded from 102 acres to 119 acres. The existing diversion of Greyback Wash south of the pit would not be altered with the proposed pit expansion. The working, inter-bench slope of the pit walls would average 1.1 horizontal:1.0 vertical, but would be optimized based on on-going evaluations of project economics and pit slope engineering. Safety benches would remain, and the overall final pit slope would be about 1.1H:1.0V (1H:1V). A typical cross-section of the proposed open pit is provided in **Figure 3-3**. Because the deposit cannot be mined sequentially, there is no plan to backfill the pit, although some of the overburden and waste rock would be used for pad preparation, plant site development, and in connection with the reclamation of disturbed area.

Material from the pit would be drilled and blasted, loaded and hauled to the primary crusher either in pit or out of pit, and then conveyed to the process mill, where the mineral values would be removed by conventional flotation processes. Future work will determine the viability of belt conveyance (either surface or underground) of crushed material if in pit crushing is chosen over out of pit. Overburden and waste rock would be placed on the ground surface in designated disposal areas, as discussed in Section 3.2.2.

Blasting would be limited to daylight hours and monitored by licensed blasters. Vehicular traffic on adjacent mine roads would be halted during blasting. Rotary diesel driven drills would be used for blast hole drilling. A small, rubber tired, compressed air operated wet drill in conformance with Mining Safety and Health Administration (MSHA) requirements would be used for secondary breakage when required. Safe seismic disturbance and air blast limits would be established to prevent damage to buildings.

Blasting agents would be stored in a secured area in compliance with applicable state and federal regulations. Ammonium nitrate and diesel fuel would be stored on site in bins and tanks. Detonators, detonating cord, boosters, caps and fuses would be stored apart from the batch plant area in secured separate magazines. The storage location for each of these facilities would be in previously disturbed areas between the plant site and the pit; safety and security would be the main factors considered in their final location.

Rock samples would be taken from blast holes. Based upon the assay values of these samples, the broken rock in the pit would be classified as "ore" or "waste." The rock would be loaded onto end

dump haul trucks for transport to the primary crusher, low-grade stockpile, or waste rock disposal area(s) depending on the assay classification.

Loading of both ore and waste rock would be accomplished by using diesel powered hydraulic shovels and/or front-end loaders. During the first years of operation, ore and waste rock haulage would be handled by a fleet of end-dump, diesel-powered haulage trucks of minimum 85-ton capacity. Additional units would be added to the fleet as the pit is deepened. A detailed list of mining equipment would be provided to the BLM as the mine plan is finalized.

Noise from the mine equipment would comply with and would be regulated under MSHA. Mining equipment would be fitted with mufflers, spark arresters, and engine enclosures to reduce noise and fire potential.

A 12.8 acre lake currently is located in the existing pit. The pit bottom is at about a 5,380 foot elevation at closure in 1986. Original ground surface elevation at the pit was approximately 5,580 feet. The water level elevation in the pit lake is about 5,420 feet, therefore, pumping of the pit-lake would be necessary prior to mining and continuously throughout the life of the mine. Minor drilling work in 1976 indicated that groundwater in the pit area is localized in larger fractures. Inflow to the pit during the previous operations ranged from 50 to 75 gallons per minute (gpm). As a result of seasonal precipitation, the pit water level has fluctuated by 1 to 5 feet per year; however, the water inflow into the pit would be used as make-up water and for dust suppression on the roads and dumps. If necessary, pit water could be temporarily stored in a reservoir in the plant area. Water removal from the pit would continue over the operational life of the mine through a sump or series of sumps located within the pit. Water removal would end once mining of the pit was completed.

The ultimate depth of the pit is estimated at 900 feet at an elevation of 4,720 feet. After pit-lake pumping activities end, a lake would reform as recharge refilled the local cone of depression developed from pit-lake pumping. The pit-lake would eventually be approximately 640 feet deep and cover about 75 surface acres. The size of the lake would fluctuate annually depending on precipitation and evaporation rates. At an average evaporation rate of 65 inches per year, the maximum water loss from the pit lake would be about 600 acre feet per year. Refilling of the pit would proceed over a number of years at a predicted recharge rate of 50 to 75 gpm or 80 to 120 acre feet per year.

The proposed plan also includes ongoing exploration drilling to define the copper ore body (infill and step out drilling as well as tests for possible deep extensions of the orebody) as well as to test for near-surface coarse gold vein and alluvial gold potential in the area of the mine.

3.2.2 Waste Rock Disposal Area and Low-Grade Stockpile

Waste rock disposal areas (dumps) would be located west, east, and north of the pit area in areas used for waste rock disposal area during previous mining. These disposal areas would be expanded under the current PoO to disturb approximately 178 acres. Prior to the expansion of existing disposal areas into previously undisturbed areas, reclamation materials (including suitable growth media and "topsoil") would be removed and stockpiled for future use in reclamation. Since a large portion of the waste rock disposal expansions would occur on previously disturbed areas, the amount of

reclamation materials available for pre-stripping in these areas may be limited. Water erosion controls, such as berms and diversion ditches, would be installed to divert runoff away from waste rock disposal areas. Water diversion ditches would also be used to control water inflow onto waste rock disposal piles containing partially oxidized and unoxidized material.

Total surface runoff from the waste rock disposal areas using a 25-year storm, 24-hour precipitation of 2.9 inches was estimated (**Appendix B**). These calculations were developed during the previous attempt to re-open the Copper Flat Mine, and would be updated to meet current regulatory requirements and design criteria. Runoff from the waste rock disposal areas and the low-grade ore stockpile would be controlled by diverting the runoff water into a collection ditch and then recycling it into the process water system. No discharge is expected to occur. The final grading plan for the waste rock disposal areas would be designed to eliminate surface water run on, enhance runoff, reduce infiltration, reduce visual impacts, and facilitate revegetation through back-grading or crowned grading. Thirty-foot wide catch benches would be left in place to interrupt surface sheet flow, and regrading would match the adjacent and nearby geomorphic land shapes. By the end of the mine life, the height of the largest disposal area, the East Waste Rock Disposal area, would be 60 feet higher than present at an elevation of 5,620 feet above sea level. Waste rock disposal areas would be designed to facilitate regrading during reclamation; however other constraints may require that portions of dumps be constructed in lift heights other than those corresponding to the vertical separation between slope breaks on the final slope faces. Typical cross-sections of the proposed waste rock disposal areas are provided in **Figure 3-4**.

The waste rock disposal areas would be regraded and surface runoff velocity dissipaters would be constructed to reduce velocities and minimize undue erosion and soil loss. Exact design parameters which are specific to the site climatology and soil conditions would be ascertained during revegetation testing and concurrent reclamation activities. Total material contained in the disposal areas at the end of the expected life of the project would be approximately 37 million tons.

The low-grade stockpile would be located immediately southeast of the open pit and include about 19 million tons of rock assaying less than 0.20 percent copper. This low-grade stockpile is expected to be milled at the end of the mine life.

Particulate dust from the waste rock disposal areas and low-grade stockpile would be controlled by wetting the area down exposed surfaces, as necessary, and is not anticipated to be a problem given the hardness of the rock and the coarseness of the material.

Under the NMCC proposed PoO, the partially oxidized (transitional materials) from the pit may be segregated into the North and West waste rock disposal areas (Figure 3-1), though the exact method of disposal (and possible segregation will be determined through the current geochemical testing program). The East Waste Rock Disposal area would contain only unoxidized waste rock. To minimize oxidation potential post closure, waste rock disposal areas would be covered with a layer of compacted material and suitable reclamation materials, and revegetated. A more detailed discussion of the geochemical characteristics and management of the mine waste materials is provided in **Appendix C**.

Additional monitoring wells may be installed along the toe of the East Waste Rock Disposal area to monitor groundwater quality downgradient of the area.

3.2.3 Ore Processing

Ore from the pit would be trucked to the plant area located to the east of the pit (**Figure 3-1**). The ore would be crushed and ground and organic reagents would be added to create froth and cause the copper minerals to adhere to the bubbles (BLM, 1996). The copper-laden froth would be collected and filtered to form a concentrate. The proposed plant would be a sulfide-flotation plant similar to that originally constructed at the site by Quintana Minerals (Copper Flat Partnership) in 1982, and would be typical of plants used at other similar deposits. It would include a molybdenum processing circuit similar to that designed by Quintana. No leaching processes, including cyanide leaching, would be used.

The plant facilities would be constructed at the site of the original plant and are expected to use most of the original concrete foundations. The plant site would occupy approximately 78 acres and would be located between the open pit and the tailings impoundment area (**Figure 3-1**). The plant site area would incorporate the following primary structures:

- Primary Crusher,
- Coarse Ore Stockpile,
- Concentrator Building,
- Thickener Facility,
- Process Water Storage Area,
- Reagent Building,
- Electrical Substation,
- Administration Office,
- Mine Office/Change House,
- Assay Office,
- Truck Shop/Warehouse,
- Small Vehicle Shop, and
- Gatehouse.

The sulfide flotation plant would be designed to process approximately 5.8 million tons of ore per year at a nominal throughput of 17,500 tons per day (assuming 93% availability). The flowsheet of the process circuit is included as **Figure 3-5**.

Scheduled operating time for the mill is currently proposed to consist of three (3), 8-hour shifts per day, 7 days per week, for at least 350 days/year. Saleable products would be copper concentrate and molybdenum concentrate. The copper concentrate would be shipped by truck to an off-site refinery or port facility. Gold and silver would be recovered as by-products of the hydrometallurgical refining process at the refinery. Molybdenum concentrate would be filtered, dried, packaged in drums, and shipped directly in trucks to purchasers for further refining.

3.2.3.1 *Primary Crushing Facilities*

The primary crusher is currently proposed to be located about 2,500 feet east of the pit (Note: NMCC is currently evaluating the feasibility of conducting in-pit crushing and conveying operations). Ore hauled from the pit would be dumped into a 42 × 65 inch gyratory crusher that would crush the mine run rock to a nominal size of less than 8 inches in diameter. Crusher discharge would be fed by apron feeder onto a belt conveyor for transport to the coarse ore stockpile located near the mill. Delivery of ore by truck would be on a schedule similar to the mining operations, while the crusher would likely operation on the mill schedule, with extra delivery from a nearby surge stockpile with a front end loader. Storage capacity of the coarse ore stockpile would be about 35,000 tons. The crusher would be located below ground level to limit noise and contain dust. Dust emissions would be controlled with suppressants, water, and dust collection equipment (i.e., bag houses) to meet air quality operating permit stipulations and health standards.

3.2.3.2 *Grinding*

Three draw chutes beneath the coarse ore stockpile would direct ore onto apron feeders which would feed it onto a belt conveyor for transport into a large diameter semi-autogenous (SAG) mill and/or roller crushers for the first stage of grinding. Reduction in the SAG mill would be a result of impact between the ore chunks themselves and between the ore chunks and the 5 inch steel grinding balls used in the mill. Reduction would be a combination of crushing and attrition. Water and various reagents would be added to the SAG mill feed to start the conditioning of the ore pulp for subsequent stages of treatment. Tonnage of the primary feed to the SAG mill would be about 17,500 tons per day.

The SAG mill would discharge onto a double deck vibrating screen. Undersize crushed ore from the screen would report to a cyclone feed sump. The oversize ore would be taken by belt conveyor to a cone crusher, where it would be crushed to less than 0.75 inch in diameter and returned by belt conveyor to the SAG mill. Intermediate size product would be returned directly to the SAG mill by conveyors. Ore from the cyclone feed sump would be pumped to a cluster of hydro-cyclones for material sizing. The fines would report to the first stage of flotation, and the oversize ore would report to two large ball mills for further grinding.

Dust control measures would be implemented in compliance with the air quality permit issued by the New Mexico Environment Department (NMED). Control technologies utilized would vary according to specific applications but would include bag houses, sprays and mists, foggers, and enclosed buildings.

3.2.3.3 *Flotation and Concentration*

Cyclone overflow from the feed sump would report to the first stage (rougher) flotation which would consist of ten ±1,500 cubic foot cell tanks connected in series. Each tank would be equipped with a mechanism that would agitate or stir and induce air into the ore pulp as it passed through the tank. Reagents would be added to the pulp to cause the copper bearing sulfide mineral particles to adhere to bubbles created by the induced air and frothing agents. Flotation reagents that would be used in the concentrator are described in Section 3.2.8 . Small amounts of other reagents may be used in the

process from time to time as part of an ongoing effort to improve metal recoveries and to cope with changing ore characteristics. The copper bearing sulfide laden bubbles would rise to the top of the cell and would be skimmed off.

The copper concentrate, which would average 28 percent copper, would be dewatered in a settling facility (thickener) to decant water, disk filtered, and stored for shipment. The copper concentrate would be loaded by a front end loader into 25-ton covered trucks with 10 ton towed trailers for transportation to a smelter or off-site copper refiner. Tailings from the copper flotation circuit would continue through the molybdenum flotation circuit where it would undergo a flotation process similar to that described for the copper flotation circuit.

Filtrate from both the copper flotation circuit and the molybdenum flotation circuit would be returned to concentrate thickeners. Thickener overflow would be returned to the plant reclaim water system. No smelting or refining would be conducted at the Copper Flat Project. The molybdenum concentrate would also be dried prior to packing into 55 gallon drums for shipment.

The crushing and concentrating plant complex would also include ancillary buildings such as offices, a truck shop, a substation, and a gatehouse. The ancillary buildings would all be prefabricated, standard, rigid framed structures. The administration building would be approximately 60 feet by 120 feet with a 12 foot eave height. The building would have central heating and air conditioning and would accommodate the plant administration, engineering, accounting, secretarial, and clerical personnel. Appropriate sanitary facilities would be provided for men and women.

The assay and laboratory offices would be 32 feet × 126 feet. Appropriate sanitary facilities would be provided. A small air compressor would be mounted on an exterior concrete pad for furnishing service air to the building. The gate house building would be 8 feet × 12 feet. A parking area for employee vehicles would be located adjacent to the main plant entry gate. The shop and warehouse building would be an equipment servicing facility. The reagent building would be a 60-foot × 72-foot building.

All mechanical, civil, structural and architectural designs would be in accordance with applicable standards and codes. The criteria used for design, equipment selection, layouts and construction were initially derived from the prior operation of Quintana Minerals and information from vendor and consultant recommendations. Equipment and fabricated items would be furnished with manufacturers' standard finish and retouched after erection. Safety painting would be in accordance with MSHA standards and New Mexico mining codes. Buildings and facilities would be painted in neutral colors to blend with the surrounding landscape.

The plant site surface drainage was originally designed to contain or control a 24-hour precipitation of 2.6 inches with a maximum 1 hour intensity of 2.0 inches. These calculations would be updated during the design phase of the project in accordance with current regulatory requirements and design criteria. Surface runoff from the area around the administration/mine office, concentrator, assay building, reagent storage and tailings thickener would be controlled by surface grading and directed to a containment pond.

3.2.3.4 *Tailings Impoundment*

An existing tailings impoundment facility at Copper Flat was constructed by Quintana Minerals to serve their 1982 mining operation. The impoundment received 1.2 million tons of material and was essentially reclaimed in 1986. The tailings impoundment remains in place and is located southeast of the former plant site. NMCC proposes to construct a new lined tailings impoundment facility over the area used by previous operations for tailings disposal. Tailings would be transported from the mill via slurry pipeline and deposited in the new impoundment. Ancillary facilities associated with the tailings impoundment facility would include a tailings slurry delivery system, a tailings solution reclaim and recycling system, and an underdrain seepage return system.

Approximately 95 million tons of tailings are expected to be impounded over the life of the project. Tailings deposition would be at the rate of approximately 17,500 tons per day (tpd). During progressive settlement, water would be decanted from the tailings impoundment and returned to the process circuit. The expected water recovery by reclaim systems would be around 70 percent.

3.2.3.4.1 Tailings Impoundment Design

A conceptual design report (Golder, 2010) for the proposed tailings impoundment is provided in **Appendix D**, and summarized herein. The starter dam from the earlier operations remains in place: however, in order to provide the required increase in storage capacity, while limiting future dam height and maintaining gravity delivery of tailings, the facility would be expanded approximately 1,000 feet to the east of the existing unlined impoundment. NMCC proposes to utilize the existing 1982 starter dam as a borrow source for the new starter embankment construction or allow the old starter dam to remain in place to form cells for more selective tailings disposal and utilize borrow from either mine waste or alluvial material behind the old starter dam to construct the proposed new starter dam. As noted above, this alluvial material is currently being evaluated for potential mineral resources.

Approximately 1.2 million tons of tailings were placed in the north cell of the Quintana tailings impoundment prior to the suspension of operations in 1982. The method of tailings embankment construction selected by Quintana was upstream raise construction with peripheral discharge of spigotted whole tailings. The proposed method of construction for the new tailings storage facility (TSF) is by centerline raises with cycloned tailings sand. The tailings surface would rise approximately 80 feet in the first two years of operation.

Initial construction would include a toe berm to buttress the tailings embankment and a starter dam for placement of the tailings header line and cyclones. Sand (cyclone underflow) would be placed on the embankment while the tailings slimes (cyclone overflow) would be discharged to the impoundment interior. A geomembrane liner would be placed beneath the starter dam and anchored on the crest of the toe berm. An underdrain system consisting of a filter compatible soil and drainage collection pipes would be placed on top of the geomembrane liner, beneath the sand dam footprint, to facilitate drainage and consolidation of the cycloned sand. The underdrain system would extend

into the impoundment interior in the area that would underlie the free water pond. Underdrainage would be routed to a lined underdrain collection pond located downstream of the toe berm.

The TSF is intended to be constructed in a phased manner. During initial construction phases, diversion ditches would be constructed to divert stormwater from upstream catchment areas within the area contributory to the impoundment. The contributory area is approximately equivalent to the ultimate TSF footprint, as only minor peripheral areas drain into the TSF. At final build out, minimal potential exists for surface water runon from external areas. Throughout most of the life of the facility, stormwater management requirements would be limited to direct precipitation.

Based on the rules and regulations of the New Mexico State Engineer, the Copper Flat TSF would be classified as a large dam having significant hazard potential. As such, the impoundment has been designed to contain the equivalent of 75 percent of the probable maximum precipitation (PMP) during operations. A spillway capable of passing 75 percent of the PMP would be required upon closure.

3.2.3.4.2 Tailings Impoundment Process

Following the flotation process, the remaining slurry, consisting primarily of non-valuable minerals, pyrite, and miscellaneous unfloated minerals, along with water, would flow into a tailings thickener for partial dewatering. The slurry would enter the tailings thickener at approximately 30 percent solids by weight, water would be removed by decanting, and the tailings would exit the thickener at 50 percent solids. Approximately 57 percent of the process water would be recovered in the tailings thickening operation. NMCC is considering additional water conservation measures and innovations which, if viable, would be added to the current process.

The thickened tailings would then flow by gravity through a 24 inch pipeline into the tailings impoundment. To contain possible spills or leaks, the tailings impoundment pipeline would be constructed between earthen berms. The pipeline foundation materials and berms would be sloped to direct any spillage or leakage to the tailings impoundment. Thickened tailings slurry would be distributed around the periphery of the impoundment by numerous spigots or hydrocyclones, which separate coarse material from the fines in the slurry. The coarse material deposited at the periphery of the impoundment would be used to construct embankment raises from the new starter embankment, while the fine silt and slimes would flow away from the upstream face of the raise toward the pool. As the finer material flows into the impoundment, gravitational settlement of solids would form beaches. Supernatant solution (the residual water in the tailings which seeps to and collects on the surface of the impoundment as the tailings settle and compress) and precipitation run-off would flow towards the impoundment low point formed by the beaches to form the free pool. Tailings deposition would be managed to force the pool away from the embankment towards an ultimate pool location. The tailings used to form the initial beaches would have a coefficient of permeability of approximately 1×10^{-6} cm/sec, after consolidation occurs, due to progressive loading.

Water reporting to the tailings impoundment would be recovered from the pool of water that would form in the impoundment, and returned to the mill process water system for reuse. Surface water resulting from precipitation could also contribute to the volume of water in this pool. The height of the embankment is designed to contain the normal operating volume of water completely within the impoundment, combined with the amount of surface water runoff from the 24-hour, 100-year precipitation event.

The size and location of the impoundment pool would vary during the life of the project. The size of the pool would be affected by predeposition grading in the impoundment, the amount of tailings deposited, precipitation, evaporation rates, seepage rates into the designed embankment seepage collection system, infiltration into underlying soils, and water recycling rates. The location of the pool would migrate within the impoundment area as tailings beaches form. Tailings deposition would be managed to force the pool away from the embankment toward the upstream reaches of the impoundment. The impoundment area would be fenced to restrict access.

3.2.3.5 *Tailings Impoundment Monitoring*

The tailings impoundment would be regulated by the New Mexico State Engineer's Office for safety of operations. The design and operation of the tailings impoundment dam would be subject to approval of the State Engineer's Office including the closure inspection. The State Engineer's Office requires monthly reports of the tonnages deposited into the impoundment along with readings of the piezometers, settlement devices, and settlement monuments that indicate movement.

The Groundwater Bureau of NMED requires a monthly report of tonnages of tails discharged along with analyses of the tailings to identify possible contaminants. Samples of water from new monitor wells proposed for downstream of the tailings dam would be analyzed monthly and the results sent to the Groundwater Bureau. These samples would be used to identify any leakage from the new, lined tailings impoundment. Abatement plans would be implemented should leakage and contamination be detected.

3.2.4 Haul Roads and On-Site Service Roads

For the most part, existing haul roads would be utilized to haul material to the crusher, stockpiles, and waste rock disposal areas. Some minor realignment of these roads may be necessary and road widths would vary. A cross-section of a typical haul road is provided in **Figure 3-6**.

Haul roads are not expected to create new disturbances, as they would be constructed on previously disturbed land. The on-site roads would be designed for easy access and traffic movement within the operations area. Waste rock and ore would be hauled to the disposal areas and mill using 85-ton (net load) haul trucks, depending on mine optimization and scheduling.

During operation of the Copper Flat Project, water trucks would be used, as needed, to control emissions of fugitive dust from the haul roads, as well as other roads within the project area. Wetting agents and binding agents, such as magnesium chloride, also may be used, if conditions warrant, to further control dust emissions.

3.2.5 Project Work Force and Schedule

The construction phase of the project is expected to take approximately 12 to 18 months. During this time, the work force for development of the Copper Flat mine would average about 120 to 130 persons per day during the construction period.

The estimated operational life required to recover the proven minerals (copper, molybdenum, gold, and silver) is 17 years. The maximum work force would be around170. Approximately 80 to 100 people would be employed in the office and mine; 40 to 70 people would be employed in the mill. The reclamation workforce would consist of up to 20 employees. NMCC anticipates hiring over 70 percent of the work force from local communities within a 75-mile radius of the mine. The mine would likely operate on two (2), 10-hour shifts per day, seven (7) days per week, for at least 47 weeks per year. The mill would likely operate on three (3), 8-hour shifts per day, 7 days per week, for at least 50 weeks per year. Administrative personnel would work a standard day shift, five (5) days per week, 50 weeks per year. These schedules are, however, subject to change based on future economics of the project.

3.2.6 Electrical Power

Power for the project would be furnished by the Sierra Electric Cooperative by means of an existing 115 kV transmission line that runs from the Caballo switching station near the junction of Interstate 25 (I-25) and Highway 152, and terminates within 300 feet of the mill facility at the site of the proposed mine substation (**Figure 1-2)**.

The 115-kV line was installed for the 1982 mine due to the limited capacity of the existing lines in the area, which supplied the community of Hillsboro and the surrounding rural areas. The existing 115-kV line is a wooden pole, H frame construction and would be in full accordance with state and federal electric codes. Tri-State Generation and Transmission owns the line and is responsible for maintenance. The substation would be reconstructed in the same area as it was in 1982, and fenced and constructed in accordance with BLM stipulations. NMCC would own the substation equipment and would be responsible for construction and maintenance. From the substation, the voltage would be stepped down by primary transformers and distributed throughout the mine site via an existing buried conduit system.

An existing 25-kV distribution line provides power to the production wells located east of the mine, booster stations on the fresh water pipeline, and the reclaim water pump stations at the tailings dam. Sierra Electric owns this line and is responsible for maintenance. The plant electrical load requirement is tabulated below (**Table 3-2**):

Table 3-2: Summary of Project Electrical Demand

	Demand (kWh/ton)
Primary Crushing	0.25
Total Grinding	17.48
Total Copper Flotation	1.74
Molybdenum Flotation	0.27
Thickening	0.05
Reagent Handling	0.05
Water System	2.05
Ancillaries	0.65
Total	**22.54**

Note: kWh – kilowatt hours

A new substation would need to be constructed at the site. An emergency generator is also included as backup power in the event of power loss to maintain critical systems and to aid in a controlled shut down. NMCC is analyzing the viability of solar power generation to partially offset the mine's energy demand, along with other energy and water conservation measures.

Because the configuration and size of the 25 kV distribution line, standard raptor proof protective designs would be incorporated into the line design and line upgrade, as presented in the Rural Electrification Administration guidelines and in the measures developed by Olendorff *et al.* (1981). This design would be used for the entire length of the distribution line within the mine area.

3.2.7 Water Supply

The total water demand for the Project would be approximately 6,400 gallons per minute (gpm) with the majority of the water used in the mill operation. Of this, about 4,400 gpm would be obtained from reclaimed process water and pit water pumping, and approximately 2,000 gpm would be fresh water make-up from the production wells.

The freshwater supply for the mine would come from four existing high capacity production wells located about eight miles east of the plant site on BLM-administered public land. These wells were drilled to depths of between 957 feet and 1,005 feet. All were 26 inches in diameter and were cased with 16-inch casing with the annular space packed with minus 3/8 inch washed gravel. The projected long-term capacities of the four production wells range from 1,000 to 1,800 gpm (Green and Halpenny, 1976). All roads, electrical supply and pump foundations are intact at the pumping field.

An existing 20-inch welded steel pipeline would transport the water from the booster station(s). The pipeline is buried a minimum of 2 feet deep from the well field to the point of entry to the project area. NMCC is preparing to conduct a detailed inspection and assessment of this pipeline to determine its condition and viability for use in the Project.

Pumping of the pit and reclaim water from the tailings impoundment is expected to provide about 400 to 800 gpm of the Project water requirements and reduce the amount of water withdrawn from the production wells. This water would generally be reused in processing and in dust suppression. The majority of the water from the pit would be used for dust suppression. Pump station #3 is located at the process water reservoir located below the tailings thickener. This station would deliver water to the process water reservoir or to the freshwater storage tank as needed. The process water reservoir would be fed by the tailings thickener overflow, reclaim water pumped back from the tailings barge pump system, and fresh water makeup as needed. It would be pumped from the reservoir to a steady head tank and flows by gravity back to the grinding circuit. A sump and pumping installation would be advanced with the pit excavation to remove infiltrated and surface runoff water collected within the pit. This water would be used in either pit operations or the concentrator.

The area encompassing the mine, mill, tailings impoundment, and water supply wells are within the Lower Rio Grande Underground Water Basin. Water rights are described in declarations, amended declarations, and supporting documents under New Mexico State Engineer File Nos. LRG-4652 through LRG-4652-S-17 and LRG-4654.

Water quality monitoring samples have been collected in the mine area from both surface and groundwater sources since 1976 and would continue to be collected throughout the life of the operation, during closure, and for a post closure period defined in the groundwater Discharge Permit.

3.2.7.1 *Stormwater*

The mining and concentrating process would not involve any discharge to surface water courses. Surface runoff (stormwater) from the mine and plant site area would be collected in containment (settling) ponds and recycled into the process water system. Stormwater outside the plant and mine site would not come in contact with the proposed operation due to existing diversion ditches, dams, and berms.

Sediment control in the mine area would be achieved by the use of seeding and mulching, silt fences, straw bale dams, diversion ditches with energy dissipaters, and rock check dams at appropriate locations during construction and operation. All sediment control structures would be monitored and maintained on a regular basis.

3.2.7.2 *Groundwater*

In 1982, the NMED, Ground Water Bureau, approved Ground Water Discharge Plan, DP 001. On June 26, 1992, the Ground Water Bureau confirmed the need to amend the permit, DP 001, in order to more closely define compliance and remedial actions. On August 20, 2008, the NMED sent a letter to the site owner at that time requiring a Stage 1 Abatement Plan (20.6.2.4101 NMAC). The purpose of the Stage 1 Abatement Plan is to provide the data necessary to select and design an effective abatement alternative. The requirements for the Stage 1 Abatement Plan are described in 20.6.2.4106 NMAC. The abatement plan proposal must include an investigation to define the extent and magnitude of any existing groundwater and surface water contamination and to characterize the

hydrogeology of the site. NMED's concerns regarding water resources at the Copper Flat site include:

- Groundwater impacts from the existing unlined tailings impoundment have been documented, but have not been fully characterized.
- Samples of pit lake water quality reveal exceedences of New Mexico Water Quality Control Commission (WQCC)standards, and NMED is concerned about migration of this water away from the pit, causing additional groundwater impacts as well as ongoing contact with wildlife.
- Acid leaching could be occurring due to ongoing ore exposure.

The surface and ground water of the Copper Flat area are described and analyzed in detail in the Hydrologic Assessment Report (Shomaker & Newcomer, 1993) and the Copper Flat Hydrogeological Report (SRK, 1995; ABC, 1996). Ongoing and future groundwater monitoring would be conducted as required by the State of New Mexico. A detailed description of the current baseline monitoring program for groundwater is presented in the report, Sampling and Analysis Plan for Copper Flat Mine (Intera, 2010), provided to the BLM under separate cover. Future monitoring and possible abatement activities would be coordinated with all relevant stakeholders to ensure the protection of groundwater resources.

3.2.8 Fencing and Exclusionary Devices

NMCC would construct BLM-approved barbed wire fencing to prevent livestock from entering the pit, waste rock disposal facilities, and tailing storage facilities, including the seepage collection pond. In areas where a higher level of security is needed, chain-link fences would be erected. Wildlife fences would be constructed around the lined ponds. Gates and/or cattle guards would be installed along roadways within the proposed Project Area as appropriate.

NMCC would monitor the fences on a regular basis and repairs would be made by NMCC as needed. BLM would be contacted immediately in the event that livestock manage to enter the proposed Project Area via a gate or opening in a fence. NMCC would assist as requested in moving these animals out of the proposed Project Area. At the time of closure, a plan would be developed between NMCC and the BLM for responsibility of long-term maintenance of range fences that would be left in place within the Plan boundary.

To the extent practicable, NMCC would investigate and utilize exclusionary devices, including, but not necessarily limited to bird balls and/or netting, to minimize the potential for avian wildlife contacting process pond waters that contain elevated chemical constituents in excess of ecological risk levels.

3.2.9 Growth Media

Available growth media would be salvaged and stored in stockpiles for reclamation. Section 3.4.14 presents further discussion on growth media salvage. Growth media would consist of soils stripped prior to surface disturbance activities. Any growth media remaining in a stockpile for one or more planting seasons would be seeded with an interim seed mix to stabilize the material by reducing erosion and minimizing establishment of undesirable weeds.

3.2.10 Borrow Areas

Construction-related borrow areas would be located within facility footprints. Borrow sources would be required for prepared sub-grade materials, drainage materials, pipe bedding materials, road surfacing materials, retarding layer materials, reclamation materials, growth materials and riprap. Precise locations and anticipated quantities of borrow materials have not yet been determined, but would be provided during the NEPA process, prior to PoO approval. Borrow areas may be revisited over the mine life.

3.2.11 Ancillary Facilities

The process area would also include ancillary buildings such as offices, a truck shop, warehouse, small vehicle shop, an electrical substation, and a gatehouse. The ancillary buildings would all be prefabricated, standard, rigid framed structures. Where practicable and economic, NMCC would consider alternative construction materials and techniques to improve the overall energy efficiency of the project. This may include renewable energy generation (solar, wind, etc.) for certain buildings.

The administration building would be approximately 60 feet by 120 feet with a 12 foot eave height. The building would have central heating and air conditioning and would accommodate the plant administration, engineering, accounting, secretarial, and clerical personnel. Appropriate sanitary facilities would be provided for men and women.

The assay and laboratory offices would be 32 feet by 126 feet. Appropriate sanitary facilities would be provided. A small air compressor would be mounted on an exterior concrete pad for furnishing service air to the building. The gate house building would be 8 feet by 12 feet. A parking area for employee vehicles would be located adjacent to the main plant entry gate. The shop and warehouse building would be an equipment servicing facility. The reagent building would be a 60-foot by 72-foot building.

All mechanical, civil, structural and architectural designs would be in accordance with applicable standards and codes. The criteria used for design, equipment selection, layouts and construction were derived from the prior operation(s) and information from vendor and consultant recommendations. Equipment and fabricated items would be furnished with manufacturers' standard finish and retouched after erection. Safety painting would be in accordance with MSHA standards and New Mexico mining codes. Buildings and facilities would be painted in neutral colors to blend with the surrounding landscape.

3.2.12 Inter-Facility Disturbance

As with most mining facilities, general ground disturbance occurs around and between structures and facilities as a result of construction and operation & maintenance (O&M). This inter-facility disturbance is in addition to the formal footprint created by design. In some cases, NMCC has elected to include disturbance buffer zones surrounding specific facilities (i.e., tailings impoundment, waste rock disposal areas, open pit area, etc.) in order to ensure that the full extent of disturbance associated with these facilities is accounted for, and that appropriate reclamation and bonding of these areas can be facilitated.

3.2.13 Transportation

Access from the site is by three miles of all-weather gravel road and 10 miles of paved highway (State Highway 152) east to I-25, near Caballo Reservoir. The 10 miles on State Highway 152 to I-25 to I-25 is mainly a straight and relatively flat road (and does not include any sharp turns or significantly adverse grades). I-25 is the primary north-south highway. Traffic associated with reestablishment of the Copper Flat Project would be broadly grouped as follows:

- **Concentrate Shipments**: Shipment of concentrates by trucks to smelters and/or port facilities would generally be via hydraulic dump trucks with 25-ton capacity towing 10-ton trailers. Copper concentrate would be thickened, filtered and trucked approximately 41miles to a railhead at Rincon, near Hatch, New Mexico on I-25, (or another site), and then transported by rail to a smelter, most likely in Arizona, and/or to port facilities. Alternatively, a possible rail loading point at the intersection of State Highways 26 and 27 south of the Project could be used. Molybdenum concentrate would be filtered, dried and bagged on site and then transported by truck or rail.
- **Incoming Supplies**: An average of 10 to 15 trips per day by trucks of vendors and equipment and service suppliers. Most deliveries, which would include equipment parts, reagents, oil, and miscellaneous office supplies, would be made during the day shift. Title 49 CFR regulates the transportation of hazardous materials in commerce. Anyone who offers for transportation, transports, packages, loads, unloads, or in any way assumes responsibility for marking, labeling, or handling of any regulated hazardous materials must comply with 49 CFR. In addition, carriers must comply with the Federal Motor Carrier Safety Regulations of the DOT (parts 383, 390 397, and 399). Hazardous materials required for operation of the Copper Flat Project include gasoline, diesel fuel, propane, and other petroleum products, explosives, solvents for degreasing of machinery and equipment, and laboratory chemicals. These materials would be purchased from various vendors and brought to the site by truck. NMCC would ensure that the Hillsboro volunteer fire department and the Sierra County fire district are aware of the nature of the materials routinely being transported to the site, and that they have appropriate response training in the event of a spill or other accident involving hazardous materials.

- **Employees and Visitors**: The majority of employees are expected to commute from Truth or Consequences or Hillsboro. An additional 15 to 20 trips could be expected by visitors and sales representatives. NMCC would encourage employee car pooling.

There are no present plans for a company operated employee transportation system. No railroad access or facilities, airstrips, or helicopter pads are planned in connection with the mine development or operations.

3.3 Exploration Activities

NMCC currently conducts exploration activities within the Plan area under previous authorizations by federal and state agencies. Current exploration and mineral evaluations have been focused on privately-owned, patented lands, within and on previously disturbed lands. Future exploration would generally remain in this same disturbed area, although some future exploration would likely include activities on BLM-administered lands.

Exploration disturbance generally includes access roads, drill pads, sumps, trenches, and staging areas. Exploration methods include both reverse circulation and core drilling, with minor trenching also planned. As part of the current mine PoO, NMCC requests an additional 15,000 linear feet of drill road and 100 drill pads for future exploration of the site. Placement of drillholes would be guided by reserve requirements, geotechnical studies, and geochemical sampling.

3.4 Applicant Committed Environmental Protection Measures and Committed Practices

NMCC would commit to the following practices to prevent undue and unnecessary degradation during the life of the Project. These practices, described briefly below, are to be considered part of the operating plan and procedures. More detailed information would be developed as the Project is advanced to more detailed design stages.

3.4.1 Air Quality

The Copper Flat Project would be designed to control both gaseous and particulate emissions and to meet all regulatory standards. Appropriate air quality permits would be obtained from the New Mexico Environment Department - Air Quality Bureau for the new Project facilities and land disturbance. As per NMED regulations, the project air quality operating permit must be authorized by the NMED prior to project commissioning.

Committed air quality practices would include dust control for mine unit operations. In general, the fugitive dust control program would provide for water application on haul roads and other disturbed areas; chemical dust suppressant application (such as magnesium chloride) where appropriate; and other dust control measures as per accepted and reasonable industry practice. Also, disturbed areas

would be seeded with an interim seed mix to minimize fugitive dust emissions from un-vegetated surfaces where appropriate.

Fugitive emissions in the process area would be controlled at the crusher and conveyor drop points through the use of water sprays and dry cartridge filter type dust collectors where necessary. Other process areas requiring dust and/or emission controls include the concentrate drying and packaging circuit, the various process plants, and the laboratory. Appropriate emission control equipment would be installed and operated in accordance with the construction and operating air permits.

The lime storage would be fitted with a baghouse for capture of fugitive dust during loading of the lime bin. The sample preparation lab would be equipped with fans and filters.

Deposition of tailings would be by spigotting and/or cyclone discharge. By this procedure, the surface would be wet, thereby eliminating or reducing fugitive dust. As necessary, control of fugitive dust in the vicinity of the tailings pond would be attained by watering, sprinkling, and vegetation. No gaseous contaminants above allowable standards are expected to be emitted to the atmosphere from the proposed operations.

Drilling operations would be done wet or with other efficient dust control measures as set by MSHA and NM Mine Inspection , and NM mining and exploration permit requirements. At a minimum, haul roads, waste rock disposal areas, and ore transfer points would be wetted down on a regular basis to minimize dust emissions. Dust abatement at the primary crusher, coarse ore stacker, and coarse ore reclaim feeders would utilize NMED and MSHA-approved Sonic Misting Systems (Best Available Control Technology).

Combustion emissions would result from the mobile mining machinery and support vehicles. All combustion equipment emits nitrogen dioxide (NO_2) and carbon monoxide (CO). The mobile mining equipment is diesel fuelled and also would emit particulate matter. Combustion emissions would be controlled by original equipment manufacturer pollution control devices. Fugitive emissions from ore and the flotation equipment are expected to be small due to the low volatility of the sulfur compounds present in the concentrate.

3.4.2 Water Resources

Process components would be designed, constructed, and operated in accordance with NMED regulations. The proposed process facilities would be zero discharge, and the TSF facilities would have engineered liner systems. The waste rock has been evaluated for potential to generate acid and/or mobilize deleterious constituents, and generally been found to produce neutral to slightly alkaline leachates with low concentrations of sulfate and dissolved metals (**Appendix C**). Waste rock with the potential to generate acid and/or mobilize deleterious constituents would be identified through laboratory analyses during mining and managed in the waste rock disposal facilities.

NMCC is in the process of preparing a stormwater management plan to identify more specific control measures and monitoring requirements. The actual locations and numbers of sediment

controls would be determined during final design and where appropriate during operations. Larger ponds would be designed and constructed in accordance with the requirements of the New Mexico State Engineer's Office. Sediment removed from the sediment control structures would be placed in the tailings impoundment or other approved locations.

3.4.3 Erosion and Sediment Control

Best management practices (BMPs) would be used to limit erosion and reduce sediment in precipitation runoff from proposed Project facilities and disturbed areas during construction, operations, and initial stages of reclamation. BMPs that would be used during construction and operation to minimize erosion and control sediment runoff and would include:

- Surface stabilization measures – dust control, mulching, riprap, temporary and permanent revegetation/reclamation, and placing growth media;
- Runoff control and conveyance measures – hardened channels, runoff diversions; and,
- Sediment traps and barriers – check dams, grade stabilization structures, sediment detention, sediment/silt fence and straw bale barriers, and sediment traps.

Revegetation of disturbed areas would reduce the potential for wind and water erosion. Following construction activities, areas such as cut and fill embankments and growth media/cover stockpiles would be seeded as soon as practicable and safe. Concurrent reclamation would be maximized to the extent practicable to accelerate revegetation of disturbed areas. All sediment and erosion control measures would be inspected periodically, and repairs performed as needed.

3.4.4 Wildlife

Land clearing and surface disturbance would be timed to prevent destruction of active bird nests or young of birds during the avian breeding season (April 1 to July 31) to comply with the Migratory Bird Treaty Act. If surface disturbing activities are unavoidable during the avian breeding and nesting season, NMCC would have a qualified biologist survey areas proposed for disturbance for the presence of active nests immediately prior to the disturbance. If active nests are located, or if other evidence of nesting is observed (mating pairs, territorial defense, carrying nesting material, transporting of food), the area would be avoided to prevent destruction or disturbance of nests until the birds are no longer present.

Operators would be trained to monitor the mining and process areas for the presence of larger wildlife such as deer and antelope. Mortality information would be collected. NMCC would establish wildlife protection policies that would prohibit feeding or harassment of wildlife.

3.4.5 Cultural Resources

Avoidance is the BLM-preferred treatment for preventing effects to historic properties [a historic property is any prehistoric or historic site eligible to the National Register of Historic Places

(NRHP)] or unevaluated cultural resources. If avoidance is not possible or is not adequate to prevent adverse effects, NMCC would undertake data recovery at any affected historic sites. Development of a treatment plan, data recovery, archeological documentation, and report preparation would be based on the "Secretary of the Interior's Standards and Guidelines for Archeology and Historic Preservation," 48 CFR § 44716 (September 29, 1983), as amended or replaced. If an unevaluated site could not be avoided, additional information would be gathered and the site would be evaluated. If the site does not meet eligibility criteria as defined by the New Mexico State Historic Preservation Office (SHPO), no further cultural work would be performed. If a site meets eligibility criteria, a data recovery plan or appropriate mitigation would be completed.

3.4.6 Protection of Survey Monuments

To the extent practicable, NMCC would protect all survey monuments, witness corners, reference monuments, bearing trees, and line trees against unnecessary or undue destruction or damage. If, in the course of operations, any monuments, corners, or accessories are destroyed, NMCC would immediately report the matter to the authorized officer. Prior to destruction or damage during surface disturbing activities, NMCC would contact the BLM to develop a plan for any necessary restoration or re-establishment activity of the affected monument. NMCC would bear the cost for the restoration or re-establishment activities including the fees for a New Mexico Professional Land Surveyor.

3.4.7 Health and Safety and Emergency Response

The development of the Copper Flat ore body would comply with environmental, and health and safety regulations of all governmental agencies including Mining Safety and Health Administration (MSHA) and the New Mexico Mining Act. The State agencies primarily involved are the NMED, the State Mine Inspector’s Office (SMIO), New Mexico Department of Energy, Minerals, and Natural Resources -Mining and Minerals Division (MMD), and the New Mexico State Engineer’s Office.

NMED has jurisdiction over ambient air quality, discharges to groundwater, surface water impacts, solid waste disposal, liquid waste disposal (sanitary facilities). The SMIO and MSHA have jurisdiction over health and safety within the mine; the State Engineer’s Office is concerned with the tailings dam construction, and operation, and water rights. The MMD is responsible for issuing a mining permit and is concerned with all issues related to the mining operation and reclamation.

As specified under SMIO and MSHA regulations, appropriate dust collection and noise abatement equipment would be installed at the mine. Noise levels in both the mine area and process area would also be subject to MSHA regulations.

All drinking water storage vessels would be enclosed in order to preserve the water's potable quality. Within the mine and mill area and the tailings impoundment, vehicular traffic and human movement would be controlled through the use of fences, locked gates, signs, and supervisory personnel.

Fencing would also discourage access by cattle. Livestock grazing is currently permitted in adjacent areas at the livestock owner's risk and would continue during mine operation in adjacent areas.

3.4.8 Fire Protection

As specified by MSHA, NMCC would institute a fire protection training program and have a rehearsed fire suppression plan. A fire protection system would be installed that would incorporate Sierra County and or State code requirements in the administration and warehouse complexes, truck shop, crushing plant, and process plant. Hydrants would be located near all buildings. A 100,000 gallon fire water reserve would be stored in a water storage tank located sufficiently above and near the mill and crushing area to provide adequate water pressure. A fuel break would be constructed around the facilities. A fire truck and water trucks, used for dust suppression, would be available in the event of a fire. An ambulance would be located on site in the event emergency transportation is required.

NMCC would promptly comply with any emergency directives and requirements of Sierra County and the BLM pertaining to industrial operations during the fire season.

3.4.9 Invasive, Non-native Species

NMCC recognizes the economic and environmental impact that can result from the establishment of noxious weeds and has committed to a proactive approach to weed control. A noxious weed monitoring and control plan would be implemented during construction and continuing through operations. The plan would contain a risk assessment, management strategies, provisions for annual monitoring and treatment evaluation, and provisions for treatment. The results from annual monitoring would be the basis for updating the plan and developing annual treatment programs.

3.4.10 Materials and Waste Management

Operations at the Copper Flat Project would result in the generation of nonhazardous and hazardous waste materials. The majority of waste would be "mine waste," including mill tailings and waste rock, which is currently excluded from regulation under the Resource Conservation and Recovery Act (RCRA). The management of these excluded wastes is discussed in Section 3.2.2. The management of regulated solid and hazardous waste is discussed in the following sections.

3.4.10.1 *Sanitary and Solid Waste Disposal*

Nonhazardous solid wastes that would be generated at the site include waste paper, wood, scrap metal, used tires, and other domestic trash. These materials would be disposed of in a permitted on site Class III sanitary landfill on private land, which would be approved by the State of New Mexico, or by other methods approved by the State and Sierra County.

Sanitary liquid wastes would be handled and disposed of through two existing septic tanks/leach fields permitted by NMED. The septic systems would be slightly modified, including enlargement of

the leach fields and placement of larger septic tanks. The washing facility for the mobile equipment would be equipped with a water/oil separator system. Waste oil and lubricants would be collected and transported off site by a buyer/contractor for recycling. Reagent drums would be recycled by the reagent supplier. Scrap metal would be sold to a dealer and transported off site.

Nonhazardous solid wastes from the laboratory would be disposed of in the landfill. Other wastes from the laboratory that exhibit a hazardous waste characteristic, including off specification commercial chemicals and assay wastes would be managed as hazardous waste.

Employee training would include appropriate landfill disposal practices such as the allowable wastes that can be placed in the landfill, management of used filters, oily rags, fluorescent light bulbs, aerosol cans, and other regulated substances. Used solvent, liquids drained from aerosol cans, accumulations of mercury fluorescent lights and used antifreeze may be regulated pursuant to RCRA. NMCC anticipates that the mine would fall in the “small generator” category. Signs would be installed at the landfill sites reminding employees of appropriate disposal practices.

3.4.10.2 *Reagent Management*

Reagents used as part of the copper/molybdenum concentrating process would include frothers, flotation promoters, flotation collectors, flocculants, flotation reagents, pH regulators, and filter and dewatering aids. These reagents would be delivered by truck from commercial sources to the mine site where facilities would be provided for off loading, storing, mixing, handling, and feeding. Reagents that are received dry would be mixed in agitation tanks and pumped to either outdoor storage tanks or liquid storage tanks inside the mill building from which they would be metered into the concentrating process.

Residual reagent concentrations in the tailings and reclaim water streams are expected to be present at very low levels since they would be added to water in amounts resulting in concentrations of approximately 3 parts per million (ppm). Also, normally 95 percent of the reagents would be adsorbed onto the copper or molybdenum mineral surface and floated off in the mineral froth. The reagent would then be subsequently consumed in the offsite smelting process. Assuming 95 percent of the reagents are adsorbed, the residual reagent reporting to the tailings stream drops to less than 0.15 ppm.

Frother reagents to be used at the mine include methyl isobutyl carbinol (MIBC). MIBC is biodegradable in low concentrations. The dosage rate would be 0.02 pound per ton of mill feed. The bulk of this reagent would report to the concentrate fraction and end up at the smelter. The reagent would be received in 20 ton capacity trucks and stored in a 16,000 gallon tank.

Lime used in alkalinity control in the flotation circuit would be received in pebble form in bulk by 20 ton capacity trucks and stored in a 200-ton capacity storage silo. The lime would then be slaked with water in a small mill and the resulting "milk of lime" would be pumped to the addition points in the grinding and flotation circuits for use as a pH regulator. It is anticipated that lime would be used at a

rate of 2.7 pounds per ton of mill feed to control pH of the flotation circuit. During the milling process, most of the lime would react with sulfide minerals to form gypsum.

Either sodium hydrosulfide (NaSH) or ammonium sulfide [$(NH_4)_2S$] would be added to the circuit process as a flotation collector and depressant to affect the copper molybdenum separation. These reagents are rapidly oxidized through contact with copper minerals and air bubbles entrained in flotation pulp and would be received in 500 pound drums either in liquid or dry pellet form. Pellets would be mixed with water and stored in tanks. Approximately 2,800 gallons of these reagents would be stored on-site at a time.

AEROFLOAT 238, used in flotation promoting, would be received in 50-gallon drums and have a plant storage capacity of 2,800 gallons. Flotation reagent Xanthate Z-11/Z-200 would also be used in the flotation process.

Number 1 diesel fuel would be used as a molybdenum collector and stored in one 5,000 gallon bermed above ground tank located onsite. AERODRI 100, used as a filter and dewatering aid, would arrive onsite in 500 pound drums. The reagent would be fed directly from the drums into the milling process. Use of small amounts (<100 pounds) of sulfuric acid would be limited to the laboratory.

Potential reagent spills would be contained by curbs in the reagent mixing and storage areas. A floor sump pump would be used to return the spilled material either to the storage tank or into the milling process as necessary. Material Safety Data Sheets (MSDS) for the reagents to be used would be on file at the site.

3.4.10.3 *Hazardous Materials Management*

The term "hazardous materials" is defined in 49 CFR§172.101; hazardous substances are defined in 40 CFR 302.4 and the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) as amended by the Superfund Amendments and Reauthorization Act (SARA) Title III. Hazardous materials would be transported to the Copper Flat Mine by DOT regulated transporters and stored on site in DOT approved containers. Spill containment structures would be provided for storage containers. Hazardous materials would be managed in accordance with regulations identified in 40 CFR § 262 Standards Applicable to Generators of Hazardous Waste.

Hazardous materials and substances that may be transported, stored, and used at the Copper Flat Mine in quantities less than the Threshold Planning Quantity (TPQ) designated by SARA Title III for emergency planning would include blasting components, petroleum products, and small quantities of solvents for laboratory use. Small quantities of hazardous materials not included in the above list may also be managed at the Copper Flat Project; such materials are contained in commercially produced paints, office products, and automotive maintenance products.

Blasting components, including ammonium nitrate and diesel fuel, would be stored onsite in bins and tanks, respectively. Detonators, detonating cord, boosters, caps, and fuses would be stored away from the batch plant in compliance with MSHA, New Mexico State Mine Inspector’s regulations,

and U.S. Department of Homeland Security requirements. Exact locations for these facilities have not been selected, however, safety and security would be the main factors considered in their locations.

Management of hazardous materials at the Copper Flat Project would comply with all applicable federal, state, and local requirements, including the inventorying and reporting requirements of Title III of CERCLA, also known as the Emergency Planning and Community Right to Know Act.

All petroleum products, kerosene, and reagents used in the mill would be stored in above ground tanks within a secondary containment area capable of holding 110 percent of the volume of the largest vessel in the area. A preliminary Spill Contingency Plan (SCP) addressing the general topics presented below is presented in **Appendix E**. The SCP would be reviewed and updated at a minimum of every 3 years and whenever major changes are made in the management of these materials. Inspection and maintenance schedules and procedures for the tanks, as well as all piping connecting the facility with the tailings pond, would be set forth in sections of the SCP addressing hazardous materials and petroleum products.

Hazardous wastes other than those from the laboratory would also be managed in the short term storage facility prior to their shipment to an offsite licensed disposal facility. These materials may include waste paints and thinners. Spent solvents and used oils would be returned to recycling facilities. Waste oil and lubricants would be collected and hauled offsite by a buyer/contractor for recycling. Solvents would be collected by a subcontractor and recycled offsite.

An ongoing inventory of all materials used at the mine site and mill would be provided on a monthly basis to the appropriate federal, state, and local regulatory agencies. The local fire department would be kept informed about materials stored onsite and appropriate emergency response.

3.4.11 Spill Contingency

NMCC has developed a preliminary spill contingency plan (SCP) (**Appendix E**) to prevent and minimize the impacts of a reagent or fuel spill. This plan describes the reporting and response that would take place in the event of a spill, release, or other upset condition, as well as procedures for cleanup and disposal. The plan would be posted and distributed to key site personnel and would be used as a guide in the training of employees. Also, the plan would address mitigation of potential spills associated with project facilities as well as activities of onsite contractors. The use, transportation, and storage of reagents and fuels would be covered in the plan. The emergency reporting procedures would be posted in key locations throughout the project area. Containment structures designed to prevent the migration of a spill are included in the design of the facilities. NMCC would be responsible for events at the mine site, while contract haulers (i.e., trucking companies) would be responsible for accidents and spills along the transportation routes.

Fuel and oil for the diesel and gasoline-powered equipment would be stored in above ground, sealed tanks in the processing facilities area. The tanks would be installed on lined pads and surrounded by berms to contain the volume of the largest tank in the event of rupture.

Reporting spills or releases of certain materials to the environment may be divided into four categories: 1) those requiring internal notification only; 2) those also requiring notification to the State of New Mexico; 3) those also requiring notification to the National Response Center (NRC) and the local Emergency Planning Committee pursuant to CERCLA or Superfund; and 4) those subject to Clean Water Act requirements only. Determining which of the above categories is appropriate for any particular spill or release depends on the material spilled or released, the amount spilled or released, and the circumstances of the spill or release.

3.4.12 Monitoring

Baseline monitoring of current environmental conditions is currently being conducted in accordance with the *Sampling and Analysis Plan – Copper Flat Mine* (Intera, 2010), previously provided to the BLM under separate cover, and was developed to collect local and regional baseline information and provide the basis for monitoring of regional impacts that may result from operation of the mine. The Copper Flat Monitoring Plan would be updated as detailed engineering for the proposed mine facilities is completed, and the monitoring requirements become more defined.

3.4.13 Technical Updates

During the course of operations, NMCC would periodically review and update as necessary the geochemical and hydrogeological predictions, mine waste characterization studies, and pit lake studies to incorporate new information accumulated during operations. NMCC would review the data every five years and make updates as necessary. These updates would provide quantitative predictions of water quality during the operational and post-closure period. Mitigation would be developed as necessary.

3.4.14 Growth Media/Cover Salvage and Storage

Any suitable growth media and cover material disturbed during construction or operation would be salvaged and stockpiled. A growth media management plan would be developed prior to construction activities.

Following stripping, growth media and cover would be stockpiled within the proposed disturbance areas. Growth media/cover stockpiles would be located such that mining operations would not disturb them. The surfaces of the stockpiles would be shaped after construction with overall slopes of 2.7H:1V or shallower to reduce erosion. To further minimize wind and water erosion, the soil stockpiles would be seeded after shaping with an interim seed mix developed in conjunction with the BLM. Diversion channels and/or berms would be constructed around the stockpiles, as needed, to prevent erosion from overland runoff. BMPs such as silt fences or staked straw bales would be used as necessary to contain sediment liberated from direct precipitation.

3.4.15 Sustainability

NMCC recognizes the social and economic impacts from "boom and bust cycles" that sometimes occur in connection with the mining industry. In addition, removal of facilities that may have post-mining uses is not in accordance with the overall environmental practice of conservation. NMCC would work with the local and regional communities to identify post-mining uses of the land and facilities to enhance opportunities to sustain the economy and culture in the post-mining phase of this project.

3.5 Operating Plans

Section 3809.401 of 43 CFR requires that the following operating plans be submitted with the Plan of Operations:

- **Water management**, including stormwater management, is discussed in Sections 3.2.3 and 3.2.7 (among others).
- Mine Waste Management Plan (**Rock Characterization and Handling Plan**) is provided in **Appendix C**;
- **Quality assurance plans**, some of which are located in **Appendix F**. The remaining quality assurance plans would be submitted to BLM prior to Plan of Operations approval;
- **Spill Contingency Plan** (SCP) located in **Appendix E** and briefly discussed in Section 3.4.11;
- **Reclamation Plan** presented in Section 5.5;
- Preliminary **Monitoring Plan** [*Sampling and Analysis Plan – Copper Flat Mine* (Intera, 2010)], previously submitted to the BLM under separate cover; and
- **Interim Management Plan** presented in Section 5.15.

4 Environmental Setting

4.1 Introduction

In accordance with 43 CFR § 3809.401(c), NMCC has prepared the following baseline environmental information to assist the BLM in analyzing potential environmental impacts as required by the NEPA and to determine if the NMCC plan of operations would prevent unnecessary or undue degradation. For the most part, this section contains a summary of the environmental setting of the mine area as described in the Copper Flat DEIS (BLM, 1996) and PFEIS (BLM, 1999). Additional details on the existing environment are provided in the various environmental baseline and impact reports prepared for the site since the mid-1970s, and are available upon request.

4.2 Geology

4.2.1 Regional Geologic Setting

The Copper Flat Mine lies within the Mexican Highlands portion of the Basin and Range Physiographic Province. It is located in the Hillsboro Mining District in the Las Animas Hills, which are part of the Animas Uplift, a horst on the western edge of the Rio Grande valley (Raugust, 2003). The Animas Uplift is separated from the Rio Grande by nearly 20 miles of Santa Fe Group alluvial sediments, referred to as the Palomas Basin of the Rio Grande valley. To the west of the Animas Uplift is the Warm Springs valley, a graben that parallels the Rio Grande valley (BLM, 1999; Raugust, 2003). Further west, the Black Mountains form the backbone of the Continental Divide, rising to about 9,000 feet above mean sea level (amsl). The surface geology of the Copper Flat region is shown in **Figure 4-1**, and a schematic geologic cross section is shown in **Figure 4-2**.

Basement rocks in the area consist of Precambrian granite and Paleozoic and Mesozoic sandstones, shales, limestones, and evaporites. Sedimentary units that crop out within the Animas Uplift include the Ordovician Montoya Limestone, the Silurian Fusselman Dolomite, and the Devonian Percha Shale. The Cretaceous-age Laramide orogeny, which was characterized by the intrusion of magma associated with the subduction of the Farallon plate beneath the North American plate, affected this region between 75 and 50 million years ago (Ma). Volcanic activity during the late Cretaceous and Tertiary periods resulted in localized flows, dikes, and intrusive bodies, some of which were associated with the development of the nearby Tertiary Emory and Good Sight-Cedar Hills cauldrons (**Figure 4-3**); later basaltic flows resulted from the tectonic activity associated with the formation of the Rio Grande rift. Tertiary and Quaternary alluvial sediments of the Santa Fe Group and more recent valley fill overlie the older Paleozoic and Mesozoic units in the area.

The geologic structure of the region is characterized by block and rift faulting (**Figure 4-3**). The Tertiary cauldrons associated with the earlier block faulting formed between 35 and 45 Ma. Rift faulting and associated north-south block faulting associated with continental extension and the formation of the Rio Grande rift began approximately 25 to 30 million years (Ma). The Las Animas

Hills are bounded by faults associated with rifting (Dunn, 1982). Continental extension continues to the present, as evidenced by north-south trending grabens represented by the Rio Grande and Warm Springs valleys.

4.2.2 Geology of Copper Flat Mine Site

4.2.2.1 *Stratigraphy*

As shown in **Figure 4-4**, the dominant geologic feature of the Animas Hills and Hillsboro district is the Copper Flat strato-volcano, a circular body of Cretaceous andesite that is 4 miles in diameter (Raugust, 2003). The andesite is generally fine-grained with phenocrysts of plagioclase (andesine) and amphibole in a groundmass of plagioclase and potassium feldspar and rare quartz. Some agglomerates or flow breccias are locally present, but the andesite is generally massive. Magnetite is a common association with the mafic phenocrysts, and accessory apatite is found in nearly every thin section (Dunn, 1984).

The strato-volcano is eroded to form a topographic low; the total depth of erosion is uncertain (SRK, 2010). To the east of the site, this andesite body is in fault contact with Santa Fe Group sediments, which are at least 2,000 feet (ft) thick in the area. Near-vertical faults characterize the contacts on the remaining perimeter of the andesite body; these faults juxtapose the andesite with Paleozoic sedimentary rocks. Drill holes indicate the andesite is more than 3,000 ft thick. This feature, combined with the concentric fault pattern, indicate that the local geology represents a deeply eroded Cretaceous-age volcanic complex (Dunn, 1982).

The core of the volcanic complex is a Cretaceous-age quartz monzonite stock that intruded into the center of the andesite body. Known as the Copper Flat Quartz Monzonite (CFQM), this irregular-shaped stock underlies a surface area of approximately 0.25 square miles and has been dated to approximately 75 million years before present (Raugust, 2003; BLM, 1999; and McLemore *et al.*, 2000). The monzonite crops out in only a few isolated areas, and the andesite at these contacts shows no obvious signs of contact metamorphism (Dunn, 1984). The CFQM is a medium-to coarse-grained, holocrystalline porphyry composed primarily of potassium feldspar, plagioclase, hornblende, and biotite; trace amounts of magnetite, apatite, zircon, and rutile are also present, along with localized mineralized zones containing pyrite, chalcopyrite, and molybdenite (McLemore *et al.*, 2000). About 15 percent of the monzonite is quartz, which occurs both as small phenocrysts and as part of the groundmass; however, quartz is absent in some parts of the stock (Dunn, 1984).

Numerous dikes, mostly latite, radiate from the CFQM stock, some nearly a mile in length. Most of the dikes trend to the northeast or northwest and represent late stage differentiation of the CFQM stock (Raugust, 2003). Immediately south of the quartz monzonite, the andesite is coarse-grained, perhaps indicating a shallow intrusive phase. An irregular mass of andesite breccia along the northwestern contact of the quartz monzonite contains potassium feldspar phenocrysts and andesitic rock fragments in a matrix of sericite with minor quartz; this may represent a pyroclastic unit. Magnetite, chlorite, epidote, and accessory apatite are also present in the andesite breccia (Dunn, 1984).

The southwestern edge of the andesite body was intruded by the Warm Springs Quartz Monzonite pluton, which dates to approximately 73 Ma (Hedlund, 1974). Unlike the CFQM and the andesite, this monzonite body is not cut by the latite dikes (SRK, 2010), indicating that the dikes were emplaced prior to the Warm Springs Quartz Monzonite.

The Sugarlump Tuff (35 Ma) and the Kneeling Nun Tuff (34 Ma) unconformably overlie the local andesite flows. These tuffs erupted from the Emory caldera, and indicate that the Copper Flat volcanic/intrusive complex was buried during the Oligocene and exhumed during Miocene uplift (around 21.7 ±3.6 Ma) (Kelley and Chapin, 1997). Both the andesite and the quartz monzonite intrusions are cut by black, scoriaceous basalt dikes. These dikes remain unaltered, and appear to be associated with locally abundant Pliocene alkali basalt flows from around 4 Ma (Seager *et al.*, 1984).

4.2.2.2 ***Structure***

Three principal structural zones are present at the site and surrounding area, the most prominent of which is a northeast-striking fault trend that includes the Hunter and parallel faults. In addition, west-northwest striking zones of structural weakness are marked by the Patten and Greer faults, and east-northeast striking zones are marked by the Olympia and Lewellyn faults. All faults have a near-vertical dip; the Hunter fault system dips 80°W, and both the Olympia and Lewellyn fault systems dip between 80°S and 90°S (SRK, 2010; Dunn, 1984). These three major fault zones appear to have been established prior to the emplacement of the CFQM and controlled subsequent igneous events and mineralization (SRK, 2010).

The CFQM emplacement is largely controlled by the three structural zones. The southern contact parallels and is cut by the Greer fault, although the contact is cut by the fault, and the southeastern and northwestern contacts are roughly parallel to the Olympia and Lewellyn faults, respectively. The elongate neck of the stock parallels the Hunter fault system. Whether there was movement along the fault zones before the emplacement of the stock has not been determined (SRK, 2010; Dunn, 1984).

Although the latite dikes strike in all the three principal fracture directions, most of the dikes strike northeast. A narrow zone of fault gouge commonly occurs along the contact between the dikes and the andesite, with the mineralization post-dating fault movement (Harley, 1934). The northeast fault zones contain a high proportion of wet gouge, often with no recognizable rock fragments. Underground exposures of the Hunter fault zone (in previously existing mine workings) material has the same consistency as wet concrete and has been observed to flow in underground headings. However, the material in the east-northeast fault zones contains only highly broken rock and little obvious gouge. The width of the fault zones in both systems varies along strike from less than a foot to nearly 25 ft in the Patten fault east of the Project. Despite intense brecciation, the total displacement along the faults does not appear to exceed a few tens of feet (Dunn, 1984). At the western edge of the site, a younger porphyritic dike was emplaced in a fault that had offset an early latite dike, indicating that fault movement occurred during the time that dikes were being emplaced (Dunn, 1984).

Post-dike movement is evident in all the three principal fault zones, and both the Hunter and Patten fault systems show signs of definite post-mineral movement. Fault movement has smeared sulfide deposits and offset the breccia pipe as well as the zones within the breccia pipe. Post-mineral

movement along faults has resulted in wide, strongly brecciated fault zones. Some of the post-mineral dikes have been emplaced within these fault zones (SRK, 2010; Dunn, 1984).

NMCC has mapped the pit area and diversion cuts in detail at 1 inch:40 ft (1:480) and has examined the pre-and post-mineral stress orientations in the andesites and CFQM. Findings indicate no significant difference in the stress fields before and after mineralization (SRK, 2010).

4.2.3 Description of the Ore Body

Copper Flat is an alkalic copper-gold mineralized breccia pipe, associated with and genetically-linked to an alkalic porphyry system. Copper Flat is situated along the eastern edge of the Cretaceous Arizona-Sonora-New Mexico porphyry copper belt, and, along with Tyrone, New Mexico, forms a linear mineralized feature known as the Santa Rita lineament (SRK, 2010; McLemore *et al.*, 2000). Copper Flat is the easternmost and one of the oldest known porphyry deposits in the southwestern U.S. (Hedlund, 1974; Dunn, 1982; Titley, 1982). Analogous deposits include Terrane Metal's Mount Milligan, British Colombia deposit and the Continental breccia pipe located near Hanover in the Central Mining district of New Mexico (SRK, 2010).

4.2.3.1 *Structure and Model*

Mineralization at the site is concentrated in a breccia pipe within the CFQM stock (Raugust, 2003; BLM, 1999). The eastern portion of the breccia pipe is outside the outline of the main mineralization; however, the rest of the breccia pipe is higher grade than the surrounding CFQM, hosting nearly half of the copper at the site, but only about one-third of the total resource tonnage (SRK, 2010). Drillholes spaced approximately 100 ft apart within the center of the deposit indicate the breccia pipe occurs as a single, continuous body, approximately 1,300 ft long by approximately 600 ft wide at the surface with the long axis perpendicular to the predominant northeast fracture direction. It is exposed in only a few places, but extends vertically to over 1,000 ft; veins of coarse pegmatitic material have been found at approximately 1,700 ft below ground surface (bgs) in one drillhole (Dunn, 1984).

Mineralized poly-metallic quartz veins, commonly associated with the dikes that radiate outward from the central stock, have been the target of historical mining activities in the Hillsboro district. The breccia pipe zone has been cut by numerous, randomly oriented, irregular veins that are thicker and coarser grained than the narrow fracture-controlled veinlets in the surrounding stock.

Mineralization appears to have been contemporaneous with pipe formation (SRK, 2010). The lack of rock flour or gouge in the matrix suggests that brecciation was not the result of tectonic movement, while the apparent lack of appreciable movement between the fragments and the gradational contact between the breccia and the zone of stockwork veining indicate that an explosive mechanism was not the source of the brecciation. Likewise, the process of mineralization stoping described by Locke (1926), which would have resulted in appreciable downward movement and mixing of the fragments, is not supported by field observations. Thus the mechanism responsible for the formation of the Copper Flat mineralized breccia pipe appears to be autobrecciation resulting from retrograde boiling, a phenomenon that occurs when the pressure of the mineralizing hydrothermal fluid exceeds the confining pressure (Phillips, 1973). The matrix of the breccia, the irregular veins in the surrounding

crackle breccias, and the open space filling in the breccias consist of hydrothermal minerals and part of the second stage mineralization occurred as replacement, which modified the original breccia texture (SRK, 2010).

Unlike most deposits in the southwestern U.S., Copper Flat shows very little supergene enrichment or the symmetrical and telescoped zoning of alteration types that is considered typical of most porphyry copper deposits. Instead, hypogene mineralization and alteration, including the formation of the breccia pipe, was the result of the final crystallization of the CFQM melt and related dikes (SRK, 2010).

The current model used by NMCC for further exploration at the site is based on Richards (2003), who interprets the area as an eroded volcano. According to this model, mineralization occurred at similar depths to that found at El Teniente in Chile; since the Copper Flat breccia pipe now crops out at the surface, this assumption indicates that approximately 0.5 to 2 kilometers (km) of volcanic rocks have been eroded from the central zone of mineralization. Fluid inclusion work by Norman *et al.* (1989) and McLemore *et al.* (2000) suggest that the breccia pipe and veins formed at a depth of 1 to 2 km bgs and at temperatures ranging from 226° to 360°C.

4.2.3.2 *Mineralization*

During the early mining days, a 20-to 50-foot leached oxide zone existed over the ore body, but this material was stripped during the mining activities that occurred in the early 1980s. Most of the remaining ore is unoxidized and consists primarily of chalcopyrite and pyrite with some molybdenite and traces of galena and sphalerite. Appreciable amounts of silver and gold are also present (BLM, 1999; SRK, 2010). The proven and probable reserves are estimated at more than 50 million tons of ore with 0.45 percent copper (Hydro Resources, 2002).

The breccia consists largely of fragments of mineralized CFQM, with locally abundant mineralized latite where dikes exposed in the CFQM projected into the brecciated zone. Andesite occurs only as mixed fragments partially in contact with intrusive CFQM and appears to represent the brecciation of andesite xenoliths in the CFQM (Dunn, 1984). The matrix contains varying proportions of quartz, biotite (phlogopite), potassium feldspar, pyrite, and chalcopyrite, with magnetite, molybdenite, fluorite, anhydrite, and calcite locally common. Apatite is a common accessory mineral. Much of the quartz-feldspar matrix has a pegmatitic texture. Breccia fragments are rimmed with either biotite or potassium feldspar, and the quartz and sulfide minerals have generally formed in the center of the matrix (Dunn, 1984).

The andesite in contact with the CFQM, dikes, and veins is typically altered into one of three types of mineral assemblages: biotite-potassic, potassic, or sericitic alteration (Fowler, 1982). The highest copper grades are associated with the biotite-potassic alteration, which is characterized by hydrothermal biotite, potassium feldspar, quartz, and pyrite, and which occurs in veinlets and as replacement assemblages in the monzonite (McLemore *et al.*, 2000).

The total sulfide content ranges from 1 percent (by volume) in the eastern part of the breccia pipe and the surrounding CFQM to 5 percent in the CFQM to the south and west (SRK, 2010). Sulfide content is highly variable within the breccia, with portions containing as much as 20 percent sulfide

minerals. Sulfide mineralization is restricted to the CFQM and breccia pipe, and drops abruptly at the andesite contact. Minor pyrite mineralization extends into the andesite along the pre-mineral dikes (SRK, 2010; Dunn, 1984). Pyrite and chalcopyrite are disseminated within the CFQM and also occur along fracture-controlled veinlets and as disseminations associated with mafic minerals. Typically, pyrite is more abundant than chalcopyrite in two areas (SRK, 2010):

- A narrow zone that surrounds and overlies the western end of the breccia pipe, which has the highest grade CFQM mineralization, characterized by abundant chalcopyrite in quartz-sulfide veinlets; and
- Outcrops to the southeast of the breccia and south of Greyback Wash, where disseminated chalcopyrite is present with no associated pyrite.

Molybdenite occurs occasionally in quartz veins or as thin coatings on fractures. Minor sphalerite and galena are present in both carbonate and quartz veinlets in the CFQM stock (Dunn, 1984).

4.3 Climate

The Copper Flat Mine lies within the belt of mid-latitude westerly winds, where the prevailing direction is from the west. Winds at the Truth or Consequences, New Mexico, airport, located about 30 miles northeast of the site, are generally from the northwest; however, the Black Range and foothills cause local variations in the winds. At Copper Flat, the wind direction is predominantly west to east, and secondarily north to south. Local wind speeds average about 10 to 15 miles per hour, although winds in excess of 50 miles per hour may occur at times. Temperature inversions are rare at Copper Flat, but are more common farther east along the Rio Grande valley, especially during the winter months. Vertical air dilution is generally good because of the area's high surface temperatures, creating strong daytime thermal mixing. Thermal mixing and moderate winds generally tend to suppress occasional nighttime inversions. The presence of higher winds and the lack of inversions contribute to a relatively clean atmosphere at the site since any pollutants are readily mixed and dispersed (BLM, 1999).

Temperature data for the site show a wide diurnal and seasonal variability, which is typical of dry climates. The warmest temperatures occur in June and July and the coldest temperatures usually occur in December and January. In spring and fall, daily maximum temperatures are moderate, typically averaging 65 to 85 degrees Fahrenheit (°F). Nights are cooler, with low temperatures averaging 32 to 50°F. Winter temperatures are frequently below freezing at night, but can be above 50°F during the day. During summer, temperatures can approach 100°F during the day. Daily temperature fluctuations of 30°F are common throughout the year (BLM, 1999).

Precipitation at the site averages about 13 inches per year (ranging from nearly 3 inches in 1956 to over 20 inches in 1986). As much as half of the annual precipitation occurs in the form of intense thunderstorms during July, August, and September, when moist air enters the region from the Gulf of Mexico. Summer thunderstorms can result in heavy rainfall and flash floods. Average monthly precipitation in January through June is typically 0.50 inch or less. Snowfall is possible from October through April, but most likely (greater than 1 inch) between December through February (BLM, 1996).

Evaporation exceeds precipitation in southwestern New Mexico. Pan evaporation data, the most commonly collected data, are correlated with lake evaporation (i.e., free water surface evaporation) to predict evaporation from reservoirs and lakes. Lake evaporation at the site is estimated to be approximately 58 to 65 inches per year, and pan evaporation is estimated to be approximately 80 to 90 inches per year (SRK, 1995).

4.4 Hydrology

4.4.1 Surface Water

The Copper Flat area falls within the Lower Rio Grande watershed, as defined by the New Mexico Water Quality Control Commission (WQCC). This watershed includes approximately 5,000 square miles in Catron, Socorro, Sierra, and Doña Ana Counties and is dominated by the Rio Grande and its tributaries as well as the two large reservoirs of Elephant Butte and Caballo. Numerous ephemeral tributaries feed into the Rio Grande from the west, but none contribute perennial flow to the Rio Grande.

The following sections provide background information about surface water resources in the vicinity of the Copper Flat Mine, and summarize pertinent historical data related to surface water sampling.

4.4.1.1 *Surface Water Characteristics of Site and Vicinity*

The site is drained by ephemeral streams (arroyos) within the Greenhorn Arroyo drainage basin, a 6th level sub-watershed defined by the Hydrologic Unit classification system (Seaber *et al*., 1987) that drains 29,414 acres of land on the eastern slope of the Animas Uplift to a single outlet into the Rio Grande (**Figure 4-5**). Flows within the Greenhorn Arroyo drainage basin are ephemeral, as they only occur in direct response to precipitation. As a result, this drainage, similar to others in the region, does not contribute any perennial surface water flow to the Rio Grande.

Numerous arroyos contribute to the trunk channel of Greenhorn Arroyo. Of these, Greyback Wash is the primary drainage through the site. Greyback Wash originates west of the site and drains eastward along the site axis until it converges with the trunk channel of Greenhorn Wash approximately 8 miles east of the site boundary (**Figure 4-5**). In pre-mining times, Greyback Wash drained directly through the mine area, but was later re-routed around the southern perimeter of the mine area for flood control purposes (Raugust, 2003). Newcomer and Finch (1993) measured flow rates in Greyback Wash of 12.5 gallons per minute (gpm) in March 1993 at a point east of the pit and former plant site. Three seeps have been identified along Greyback Wash (BLM, 1999). One seep with riparian vegetation is located near a buried storm water collection pond, a second is located downstream from the first seep and supports a small cottonwood/willow stand, and the third is south of the operations area (**Figure 4-5**).

Two creeks drain basins directly to the north and south of the Greenhorn Arroyo drainage basin: Las Animas Creek in the north and Percha Creek to the south (**Figure 4-5**). Both Las Animas and Percha Creeks have ephemeral, intermittent, and perennial reaches. Stream flow in Las Animas Creek varies from perennial to intermittent from the area near sampling site MAS (**Figure 4-5**) to Caballo

Reservoir (BLM, 1999). For example, Davie and Spiegel (1967) show flow rates ranging from about 450 to 900 gpm in the upper reach (T14S R7W, Sections 34 through 36, near sampling sites LAC-A and LAC-B in **Figure 4-5**) and middle reach (within T15S R5W) of the creek; according to Davie and Spiegel, these reaches are "losing reaches" of the creek. Stream flow in Percha Creek is intermittent in the Hillsboro reach and perennial in the area known as the Percha Box, a steep-walled reach of the drainage that has incised into Paleozoic bedrock (BLM, 1996) (**Figure 4-5**). SRK (1995) reported measurable stream flows just east of the Percha Box of roughly 200 to 250 gpm. This was the only reach of Percha Creek with measurable flows during the SRK sampling period. Though both Las Animas Creek and Percha Creek have perennial reaches, neither creek contributes perennial flow to the Lower Rio Grande Basin.

Two springs are located within the Greenhorn Arroyo drainage basin to the north and west of the site (**Figure 4-5**). Other unnamed seeps occur in the pit walls surrounding the pit lake after precipitation events; these are likely the result of fractured flow through the bedrock exposed in the pit wall. Several springs in the Percha Creek basin and one in the Las Animas Creek basin have been identified for sampling, but have been studied less than those within the Greenhorn Arroyo basin. As a result, there is little information on their flow rates or quality, although Newcomer and Finch (1993) did attempt to measure flow.

The open pit that was mined during the early 1980s now contains a lake. Since 1989, the pit lake has been sampled for water quality at various locations and depths, including samples collected by past operators of the mine, state regulatory agencies, and academic researchers studying the mine (BLM, 1999).

4.4.1.2 *Historical Data*

Existing surface water data relevant to the NMCC sampling plan are discussed in this section. Surface water at the site was most recently investigated by SRK (1995), who collected flow and water quality from Percha Creek and Las Animas Creek. Newcomer *et al.* (1993) performed a hydrologic assessment of the Greenhorn Arroyo drainage basin, measuring flow and water quality along Greyback Wash and at a number of seeps and springs. The oldest known surface water investigation at the site was performed by Davie and Spiegel (1967), who collected flow data for Las Animas Creek. Results of these investigations were compiled by Raugust (2003) and are also summarized in PFEIS (BLM, 1999).

4.4.1.2.1 Volumetric Flow

4.4.1.2.1.1 Streams

Flow rate data for streams at the site are limited by the generally intermittent nature of flows. Measurements of flows were made by Newcomer *et al*. (1993) and Adrian Brown Consultants (1996). Additional historical measurements were compiled in the PFEIS (BLM, 1999). These data are summarized in the *Sampling and Analysis Plan – Copper Flat Mine* (Intera, 2010), provided to the BLM under separate cover.

Greyback Wash is an ephemeral stream and generally flows only during periods of snow melt or rain events. Flow rates in Greyback Wash at SWQ-3 (**Figure 4-5**) were measured by Newcomer *et al*. (1993) to be 12.5 gpm (0.028 cubic feet per second [cfs]) in March of 1993.

Two measurements of flow rate are recorded for Las Animas Creek. Davie and Spiegel (1967) reported flows of between 1.0 and 2.0 cfs in the creek's upper reaches and between 1.0 and 1.5 cfs in its middle reaches (BLM, 1999). Adrian Brown Consultants made a single flow measurement of 245 gpm (0.546 cfs) at LAC-E (**Figure 4-5**) in 1996.

Volumetric flow in Percha Creek was measured at 13 locations by Adrian Brown Consultants (1996), from approximately ¼ mile upstream of the entry to Percha Box to approximately 5 miles downstream of the exit from Percha Box. Flow was found to be localized, occurring within and immediately to the east of Percha Box, and ranging from 456 gpm (1.02 cfs) to 119 gpm (0.265 cfs), with many reaches dry or with standing water only.

4.4.1.2.1.2 Springs and Seeps

Spring and seep flow rates are infrequently reported in the available literature for the site and surrounding areas. Several springs and seeps have been identified within the Greenhorn Arroyo drainage basin. Two springs, identified as BG-1 and BG-2, are located to the north and west of the site (**Figure 4-5**) and several unnamed seeps occur in the walls surrounding the pit lake. BG-1 and BG-2 were judged by Newcomer *et al*. (1993) to be ephemeral. The seeps along the pit walls are observed to flow in response to precipitation events, and, as mentioned above, are likely the results of fractured flow through the bedrock exposed in the pit wall. All known springs and seeps in the Greenhorn Arroyo drainage basin are upgradient of the proposed mine water discharge location. Other seeps and springs shown in **Figure 4-5** have not been measured in the past and thus have no associated historical flow information.

4.4.1.2.2 Water Quality

4.4.1.2.2.1 Streams

The surface water chemistry of Greyback Wash was initially investigated in 1977 at three locations as part of an environmental assessment prepared by the BLM in response to an application by Quintana Minerals Corporation for an open pit copper mine at the site (BLM, 1978). The three locations sampled in 1977 generally correspond to the sampling locations proposed in **Figure 4-5**, with one location upstream of the permit boundary, one within the site approximately 300 yards from the mine rim, and a third located where the arroyo leaves the site (BLM, 1978). Water samples were collected in January, March, and July of 1977.

WQCC standards for metals were not exceeded at any location in any of the 1977 sample events. Results for pH (7.6–8.1) were in the same range as samples collected later at these three locations. Total dissolved solids (TDS) results upstream of the site (720–1000 milligrams per liter [mg/L]) were comparable to those of samples collected later, but samples taken at locations within and downstream of the site were comparatively lower (800–1,320 mg/L) than the results for later sampling events such as those conducted by Newcomer *et al.* (1993) at SWQ-1 (upgradient of the pit

lake), SWQ-2 (downgradient of the pit lake but within the area of mining disturbance), and SWQ-3 (approximately 1 mile downgradient of the pit lake) (**Figure 4-5**). Field parameters measured by Newcomer *et al*. are shown in Table 8-1 of the *SAP* (Intera, 2010). Water quality in Greyback Wash upstream of the pit lake at SWQ-1 had a pH ranging from 7.4 to 8.3, sodium at 107 milligrams per liter (mg/L), bicarbonate values ranging from 400 to 500 mg/L, sulfate ranging from 275 to 300 mg/L, and TDS ranging from 780 to 965 mg/L. At SWQ-2, sodium concentration increased from the previous sampling event by BLM to 270 mg/L, sulfate increased to between 1,150 and 1,650 mg/L, TDS increased to between 2,300 and 3,300 mg/L, and pH and metal concentrations remained essentially unchanged. Water quality indicators at SWQ-3 fell within the range of values at SWQ-2.

Las Animas Creek water quality was examined by Adrian Brown Consultants (1996) and for the PFEIS (BLM, 1999). Adrian Brown Consultants obtained a single sample at LAC-E, with a pH of 7.81, sulfate concentration of 18 mg/L, and TDS of 300 mg/L. The PFEIS reports that Las Animas Creek water quality is dominated by calcium or sodium bicarbonate, with pH in the range 7.0 to 8.0, sulfate in the range 20 to 70 mg/L, and TDS in the range 300 to 400 mg/L. Occasionally, sodium and chloride are higher, with chloride concentrations as high as 300 to 400 mg/L, possibly due to agricultural practices along the creek (BLM, 1999).

Percha Creek water quality was examined by Adrian Brown Consultants (1996) and for the PFEIS (BLM, 1999). Adrian Brown Consultants sampled Percha Creek at the entry and exit to Percha Box, and 5,000 feet (ft) downstream from the exit from Percha Box, and measured field parameters at all seven locations in which water was found [Table 8-1 of the SAP (Intera, 2010)]. For the three samples submitted for laboratory analysis, pH ranged from 7.62 to 7.82, sulfate ranged from 63 to 71 mg/L, and TDS ranged from 336 to 406 mg/L. The PFEIS (BLM, 1999) reports that surface water flowing in Percha Creek has a chemistry dominated by calcium bicarbonate, with pH in the range of 7.0 to 8.0, sulfate in the range of 20 to 70 mg/L, and TDS in the range of 300 to 400 mg/L.

Sampling of the Caballo Reservoir, the receiving water for these drainages, during November 1994, showed the water to be dominated by sodium bicarbonate with bicarbonate values of 180 mg/L and sulfate values of 110 mg/L (SRK, 1995). As summarized in the PFEIS (BLM, 1999) chloride values were less than 100 mg/L and TDS was 440 mg/L. The water chemistry was within WQCC standards for metals, sulfate, chlorine, pH, and TDS. As a comparison, water samples from the Rio Grande at EI Paso, Texas were sodium sulfate-dominated with high TDS in the range of 800 to 1,000 mg/L, sulfate values of 200 to 340 mg/L, and bicarbonate values of around 100 mg/L (Wilson *et al*., 1981).

4.4.1.2.2.2 Springs and Seeps

Newcomer *et al*. (1993) sampled the BG-1 and BG-2 springs in April 1993 and Adrian Brown Consultants observed and sampled seeps in the pit wall in August 1997 (ABC, 1997). Field parameters and water chemistry analytical data for these locations are presented in Table 8-1 of the *SAP* (Intera, 2010), respectively. Samples from BG and BG-2 had pH ranging from 8.0 to 8.2, sodium ranging from 90 to 124 mg/L, bicarbonate ranging from 411 to 535 mg/L, sulfate ranging from 184 to 228 mg/L, and TDS ranging from 680 to 690 mg/L. The pit wall sample had a pH of 8.16, a sulfate content of 3,100 mg/L and TDS of 5,020 mg/L. On the basis of these results, ABC (1997) judged BG and BG-2 to be qualitatively similar to the Greyback Wash sample location SWQ-

1, while the pit wall location appears to have been subject to a similar process as the locations at SWQ-2 and SWQ-3.

4.4.1.2.2.3 Pit Lake

The 12.8-acre lake that has formed in the existing pit (**Figure 4-6**) is estimated to be about 40 ft deep, based on a pit bottom elevation of 5,380 ft above mean sea level (amsl) and water level elevation of 5,420 ft amsl as measured in 1986 (SRK, 2010). The water quality of the pit lake has been sampled at various depths and locations since the initial samples were collected on April 13, 1989, by the New Mexico Environment Improvement Board (Raugust, 2003); the latest samples were collected in January 2010. Raugust (2003) concluded that the collective data show several trends in the variability of water quality over time, mainly that evapo-concentration and buffering processes are influencing the quality of the lake water. Pit water has historically exceeded the WQCC standards for sulfate, chloride, TDS, manganese, and uranium (20.6.2.4103 of the New Mexico Administrative Code) and has occasionally dropped below the regulatory pH range of 6 to 9 s.u.

Analytical results of samples collected from 1989 to 1998 suggest that sulfate, chloride, TDS, manganese, and pH all increased over this period. For example, sulfate increased from a range of 2,250 to 3,000 mg/L to a range of 3,500 to 4,300 mg/L over this time period. Chloride increased from an average of around 100 mg/L to around 250 mg/L, which may be attributed to lower average annual precipitation and higher annual temperatures during this period (BLM, 1999). However, the sulfate-to-chloride ratio dropped during this time period, suggesting that sulfate rose at a slower rate than chloride due to the formation of gypsum and the subsequent buffering of the sulfate concentration in pit lake water by gypsum (gypsum is observed along the margins of the pit lake during the summer months, when the pit lake level has dropped). TDS ranged from 2,700 mg/L in 1991 (Newcomer *et al*., 1993) to about 6,000 mg/L in 1998 (Raugust, 2003). Manganese ranged from 1.8 to 4.3 mg/L (BLM, 1999). The measured pH values have generally increased over time to about 8.0 s.u. However, in 1992 and again in 2008, pH decreased to 4.4 and 4.5 (NMED GWQB, 2008), respectively, deviating from the overall trend of elevated pH values. The overall rise in the pH may be due to buffering by wall rock or groundwater alkalinity. There is no historical data available for uranium, other than a sample collected in 2004 that showed the water exceeded the WQCC standard (NMED GWQB, 2008).

Variability in the methods, locations, and depths from which samples were collected may explain many of the differences observed in pit water quality results. However, samples collected in January 2010 confirm that concentrations of sulfate, chloride, TDS, and manganese have increased. The 2010 sampling yielded a sulfate concentration of 5,200 mg/L, chloride concentration of 390 mg/L, TDS concentration of 7,770 mg/L, and manganese concentration of 41 mg/L, all of which were higher than previous measurements from the 1989 to 1998 period. In addition, concentrations of aluminum, copper, cobalt, iron, and fluoride in the 2010 sample all exceeded WQCC standards. In contrast, pH, the most widely variable parameter measured during the 1989 to 1998 period, was 6.3 in January 2010, within the acceptable range of 6 to 9.

Other key studies that discuss the water quality are summarized in SRK (1997) and include hydrogeologic and hydrogeochemical studies (SRK, 1995), post-closure pit water balance model calculations (SRK, 1997), water quality and host-rock geochemical studies (SRK, 1997), and post-hearing submittals that followed the 1997 New Mexico Mine Permit public hearing.

4.4.2 Groundwater

Groundwater is a major supply of water for domestic, agricultural, mining, and industrial use in southern New Mexico. The high evaporation rate during the long, hot summers coupled with low average annual precipitation in the area result in surface waters being an unreliable source of water on a year-round basis. The Rio Grande is the only significant nearby surface water resource. Intermittent streams that feed the Rio Grande, such as Las Animas Creek and Percha Creek in the site area, are local sources of water for at least part of the year. The Rio Grande and associated shallow alluvial deposits of its inner valley also served as the ultimate discharge zone for pre-development groundwater flow from the adjacent Greenhorn Arroyo, Las Animas Creek, and Percha Creek drainage basins (Hawley *et al*., 2005, Wilson *et al*. 1981). Additional water comes from shallow domestic and agricultural wells. This section provides a description of the regional and local groundwater along with a proposed sampling and analysis approach to characterizing baseline conditions of groundwater resources.

4.4.2.1 *Regional Hydrogeology*

The site is located in the Lower Rio Grande Underground Water Basin (LRGB), which extends from Elephant Butte Dam to the Texas Border near El Paso and is one of New Mexico's principal agricultural regions (**Figure 4-7**). The LRGB was declared by the NM State Engineer on September 11, 1980. As a result, the underground waters of the LRGB are administered by the State Engineer. A water master district that encompasses the Hot Springs, Las Animas Creek, and Lower Rio Grande Underground Water Basins was created to assist with water administration in the region.

Groundwater in the LRGB generally flows from the highlands on either side of the basin through bedrock and valley alluvium to the center of the basin and to the Rio Grande. **Figure 4-8** illustrates the conceptual model of groundwater flow at the site. The bedrock aquifer in the Paleozoic sedimentary rocks are recharged by rainfall and snowmelt through bedrock faults and bedding planes exposed in the highlands west of the Project site. This water generally flows along a hydraulic gradient toward the approximate center of the Rio Grande Valley. Occasionally, this deep regional flow discharges at the ground surface as springs along faults where the Paleozoic bedrock crops out within the valley. This occurs in at several locations within the Las Animas Creek and Percha Creek drainage basins (**Figure 4-9**). The water table elevation near the existing pit lies at approximately 5,450 to 5,500 feet (ft) above mean sea level (amsl). Groundwater near Caballo Reservoir lies at about 4,200 ft amsl, indicating a drop of 1,300 ft over approximately 14 to 15 miles.

Valley alluvium is generally recharged by precipitation along mountain fronts where the alluvial fans are exposed and by streams that flow out of the highlands and lose water to the alluvium as they flow toward the Rio Grande. Many intermittent streams in the area are "losing streams" over at least part

of their courses and provide recharge to the alluvial groundwater system. This alluvial groundwater then flows downgradient to the Rio Grande.

4.4.2.1.1 Hydrogeology of the Permit Area

Three aquifers exist in the project area, as shown schematically on **Figure 4-8**. The deepest aquifer is the crystalline bedrock aquifer that receives water from the highlands to the west of Animas Peak and carries this water along bedding planes, faults, and solution cavities toward the center of the LRGB. The crystalline bedrock aquifer consists of Cretaceous andesite and monzonite breccias underlain by Paleozoic rocks in the Animas Uplift area, Tertiary volcanic rocks to the west of the pit lake in the graben associated with the Animas uplift, and Paleozoic sedimentary rocks to the east of the pit lake area in the Palomas Basin. The Santa Fe Group aquifer system, which consists of interbedded sandstones, silts, and clays, overlies the Paleozoic bedrock units to the east of the pit lake area within the Palomas Basin. This aquifer system receives water from precipitation and from the losing reaches of streams. The uppermost aquifer at the site is the Quaternary alluvial aquifer along Las Animas and Percha Creeks (**Figure 4-9**). This alluvium is up to 40-ft thick in the Las Animas Creek area and carries water that is in hydraulic equilibrium with the water flowing in Las Animas Creek (BLM, 1999). The Percha Creek alluvial aquifer is less studied than the Las Animas Creek alluvial aquifer, and as a result, less historical data about its aquifer characteristics are available. The aquifers of greatest importance in terms of water supply in the area are within the Palomas Basin to the east of the pit lake and include the intermediate Santa Fe Group aquifer system and the alluvial aquifer associated with Las Animas Creek.

Figure 4-10 from the Adrian Brown Consultants (ABC) (1998b) presents a piezometric contour map showing the general configuration of groundwater level elevations at the site as interpreted at that time. Groundwater levels near the existing pit are approximately 5,450 ft amsl, and at Caballo Reservoir, the levels are about 4,200 ft amsl. The map indicates that groundwater flow is generally to the east toward Caballo Reservoir. Hydraulic gradients are relatively large (closely spaced contours) in the western portion of the site, reflecting lower transmissivity in the bedrock aquifer and in the western portion of the Palomas Basin in the Santa Fe Group aquifer system. The wider spacing of contours in the eastern portion of the site suggests that transmissivity of the Santa Fe Group aquifer increases toward Caballo reservoir. The widest spacing of contours (highest transmissivity) appears to occur in the area of the groundwater production well field (wells PW-1, 2, 3, and 4 on **Figure 4-10**). This area coincides with an interpreted graben structure, which reflects an increased thickness of the Santa Fe Group in this area.

4.4.2.1.2 Aquifer Characteristics in the General Plan Area

4.4.2.1.2.1 Crystalline Bedrock Aquifer Characteristics

Groundwater within the Hillsboro Mining District and the area of the present open pit occurs in andesitic volcanic rocks and quartz monzonite breccia intrusive rocks (**Figure 4-8**). The current pit lake was reported by SRK (1997) to be at an elevation of 5,442 ft amsl, which is about 50 to 100 ft below the pre-mining ground elevation [5,500 to 5,540 ft amsl reported in the PFEIS (BLM, 1999)].

Groundwater levels measured in the pit and tailings areas as of 1997 are shown on **Figure 4-11**. Newcomer *et al*. (1993) reported a pre-mining (1981) water level of 5,370 ft amsl in well GWQ-5, which is approximately 4,000 ft east-southeast from the pit and within the old plant site area. These authors also reported a water level of 5,360 ft amsl in the Hillscher West well (GWQ-6), which lies approximately 2,500 ft southeast from well GWQ-5. These limited groundwater elevation data suggest that the groundwater gradient in the andesitic volcanic rocks may be to the east or southeast from the current pit lake area as shown on **Figure 4-11**. Within 500 ft of the pit lake (see **Figure 4-12**), however, groundwater gradients are toward the pit lake, which may act as a local evaporative sink (BLM, 1999).

In January 2010, NMCC resurveyed the pit lake and as many of the groundwater monitoring wells established for the PFEIS as could be located. The pit lake elevation was 5,444 ft amsl in January 2010, revealing that the pit lake elevation remains below the pre-mining water level elevation of 5,500 to 5,540 ft amsl.

4.4.2.1.2.2 Santa Fe Group Aquifer System

Overview

Overlying the crystalline bedrock aquifer at the Project site is the Santa Fe Group aquifer system, a system that is locally represented by two hydrostratigraphic units (HSUs): (1) the Upper Santa Fe Group hydrostratigraphic unit (USF), and (2) the Middle Santa Fe Group hydrostratigraphic unit (MSF). As defined by Hawley and Kennedy (2004), these hydrostratigraphic units are mapable bodies of basin and valley fill that are grouped according to genesis and position in both lithostratigraphic and chronostratigraphic sequences. Informally, these HSUs comprise the major basin-fill aquifer zones, and correspond roughly to the upper (Palomas) and middle (Rincon valley) lithostratigraphic subdivisions of the Santa Fe Group used in local and regional geologic mapping (Hawley and Kennedy, 2004).

The Santa Fe Group is composed chiefly of coalescing alluvial fan deposits that are discontinuous and locally heterogeneous with inter-bedded sandstones, silts, and clays of varying percentages. The Upper Santa Fe Group Palomas Formation (Lozinsky and Hawley, 1986) represents the USF at the site. This formation grades eastward from the Animas Uplift from coarse alluvial fan material to braided-stream and deltaic sands and silts to clays near the Rio Grande. The interfingering with clays begins approximately 3 to 5 miles west of the current position of the Rio Grande and is responsible for the flowing wells common in this part of the site (Murray, 1959; **Figure 4-8**). A basalt flow dated at 4.2 million years before present caps the Palomas Formation gravels near Copper Flat (Seager *et al*., 1984).

The Middle Santa Fe Group Rincon Valley Formation (Seager and Hawley, 1973) is exposed near Hillsboro, New Mexico, where the reddish-brown clays and clayey silts characteristic of this basal unit are interbedded with basalts dated at 28 million years before present (Seager *et al*., 1984). The Rincon Valley Formation represents the MSF at the site and generally contains water, but the yield is low due to the low hydraulic conductivity of the clays. The Rincon Valley Formation lacustrine red

clays underlie the Palomas Formation and thicken southward toward Hatch, New Mexico, and the Rincon Basin (Wilson *et al*., 1981).

Tailings Dam Vicinity

The existing tailings impoundment facility overlies the old placer workings of Greyback Wash and Hunkidori Gulch (**Figure 4-9**). A study of these placer workings by Segerstrom and Antweiler (1975) showed that the placers were found in paleo-stream terrace alluvium approximately 25 to 30 ft thick that is underlain by a calcium carbonate horizon and reddish-brown clay. SRK (1995) and SHB (1980) confirmed and expanded the areal extent of this reddish-brown clay layer and determined that the top of the Palomas Formation is stratigraphically below the red clay layer. According to the studies completed by SRK and SHB, the clay layer and the 25 to 30 ft of paleo-stream terrace gravels that lie above the clay, have restricted the downward migration of water draining from the eastern half of the existing tailings. This clay layer has enabled a mound of water beneath the tailings impoundment to develop. This mounding of water, due to drainage of the existing tailings and meteoric infiltration over the years, became evident in some tailings dam monitor wells completed above the clay layer. The central and western sections of the existing tailings facility appear to communicate hydrologically with the USF that lies beneath the tailings area because the clay zone thins and disappears in this area, as shown in **Figure 4-13**. Groundwater issues as a result of tailings deposition by the previous operator are currently being dealt with through the Stage 1 Abatement Plan for the NMED. Further impacts would be mitigated by NMCC's proposed use of a synthetic liner system to prevent the downward migration of tailings seepage water.

The thickness of the Palomas Formation increases locally over a graben structure (labeled Dutch Gulch in **Figure 4-2**), which is reflected in higher transmissivity and relatively low hydraulic gradients in the USF. Based on a 7-day aquifer pumping test (ABC, 1996), the transmissivity of the USF in the tailings dam area is about 187 ft^2/day. East of the tailings area (see **Figure 4-2**) is a 10- to 30-foot thick clayey sand and gravel layer, underlain by a 25- to 100-foot-thick clay layer, which in turn is underlain by a silty sand and gravel layer (SRK, 1995). The lower silty sand and gravel layer is considered by ABC (1996) to be the USF and, based on drilling information, has a thickness of at least 200 ft. The hydraulic gradient in this area is about 30 ft per mile.

East of the graben structure, labeled as Dutch Gulch in **Figure 4-2**, the Palomas Formation (labeled Tsfp) thins and is interpreted to have significantly reduced transmissivity. The hydraulic gradient in this area ranges from about 130 to 330 ft/mile. The contact between the Palomas Formation and the underlying Rincon Valley Formation clay unit (labeled Tsf in **Figure 4-2**) is a highly irregular depositional contact. Locally, the Palomas Formation (USF) may be unsaturated, with the water table existing in the underlying Rincon Valley Formation (MSF) (BLM, 1999).

Production Well Field Vicinity

Farther to the east, the hydraulic gradient decreases from 330 ft/mile to about 34 ft/mile in the vicinity of the production well field (identified as PW wells on **Figure 4-14**). This suggests a progressive increase in transmissivity toward the area of the production well field. A graben structure below the production well field locally increases the thickness of the Palomas Formation to as much

as 1,000 ft (**Figure 4-2**). The transmissivity of the USF in the production well field area ranges from about 2,675 to 5,750 ft^2/day (SRK, 1995). Farther to the east, towards Caballo Reservoir, sands and gravels in the Palomas Formation are interbedded with clays of the ancient Rio Grande. As a consequence, the transmissivity decreases slightly and the hydraulic gradient Increases to 45 ft/mile. In this area, the USF appears to be confined, leading to artesian flow in wells along the lower reaches of both Las Animas Creek and Percha Creek.

Although the Palomas Formation is described as "sand and gravel" (Davie and Spiegel, 1967), there exist numerous discontinuous clay layers within the sequence. This causes the bulk vertical hydraulic conductivity of the USF to be much lower than the horizontal conductivity. As a consequence, groundwater in deeper portions of the USF can be semi-confined, leading to relatively high vertical hydraulic gradients. The low vertical hydraulic conductivity has two important effects on the groundwater flow system. First, within about 4 miles of Caballo Reservoir, confinement of groundwater is sufficient to create artesian conditions in deeper portions of the USF. Wells drilled to these depths have groundwater levels aboveground surface and produce flowing wells, the locations of which are shown on **Figure 4-14**. Flow rates for uncapped wells range between a few gallons per minute (gpm) to as high as 40 gpm.

The second effect of low vertical conductivity is to reduce downward leakage between the Quaternary alluvial aquifer in the Las Animas Creek drainage basin and the underlying USF. At the location of monitoring wells MW-9, 10, and 11, north of the production well field, the groundwater level in the USF is some 58 ft lower than the water level in the overlying Quaternary alluvial aquifer (ABC, 1996). This results in a downward vertical hydraulic gradient from the Quaternary alluvial aquifer in the vicinity of Las Animas Creek drainage basin to the USF approaching 1 ft/ft. Such downward gradients are interpreted to occur along a substantial length of Las Animas Creek (ABC, 1996). In spite of these gradients, the amount of surface water loss from the Quaternary alluvial aquifer in the Las Animas Creek drainage basin is not significant; suggesting that vertical hydraulic conductivity in the USF is relatively low. Analytical calculations (ABC, 1997) suggest that if the vertical conductivity were much greater than 1 ft/year (10^{-6} cm/second), the Las Animas surface water system would lose essentially all of its water and become an intermittent stream, which clearly does not occur.

The hydraulic connection between the USF and the alluvial aquifer of the Rio Grande has not been evaluated, but groundwater gradients at the site strongly suggest that water flows from the Palomas Formation to the floodplain alluvium of the Rio Grande.

An aquifer pumping test conducted at the locations of monitor wells MW-9, 10, and 11 suggests that the vertical conductivity of the USF is low in this area (ABC, 1997). Pumping of the wells screened in the USF at this location did not affect a well screened in the Quaternary alluvial aquifer in the Las Animas Creek drainage basin, even though the well screened in the USF had 22 ft of drawdown. Also, monitoring of water levels along Las Animas Creek by Alta (Goff, 1998) for wells screened in both aquifers showed that fluctuations in water levels observed in shallow wells (those screened in the Quaternary alluvial aquifer) are not mirrored in the deeper wells (wells screened in the USF). These data are presented in Appendix A-2 (Table A2-10) of the PFEIS (BLM, 1999).

4.4.2.1.2.3 Quaternary Alluvial Aquifer

The uppermost aquifer at the site is the Quaternary alluvial aquifer, which is composed of channel and floodplain gravels, sands, and silts. Locally, these units are generally 30 to 50 ft thick near the mouths of Las Animas and Percha Creeks (Davie and Spiegel, 1967). Cores from monitoring wells drilled along Las Animas Creek indicate that upper alluvial gravels extend from the surface to a depth of approximately 20 to 60 ft depending on the location along the creek (BLM, 1999). There are fewer data available for the thickness of these deposits in and along Percha Creek.

The Las Animas alluvial aquifer consists of local alluvial deposits adjacent to and underlying Las Animas Creek. Groundwater in this narrow, sinuous aquifer is in direct hydraulic communication with Las Animas Creek surface water. Surface water in the creek and groundwater in the aquifer form a single surface-to-groundwater flow system. Surface water flow from one location to the next may be related, in part, to the proportion of total system flow being carried by the aquifer at each location. Along its course, the Las Animas alluvial aquifer receives recharge by rainfall infiltration. Discharge from the aquifer occurs through evaporation and evapo-transpiration from riparian vegetation and existing well pumping. Between the Saladone well and an area of the Lower Animas Artesian well (**Figure 4-14**), the aquifer loses water to the underlying Palomas Basin alluvial aquifer by slow downward seepage. The total flow rate for surface flow plus flow in the alluvium of the creek drops from around 1,800 to 1,900 gpm to around 1,100 gpm, a loss of 800 gpm over the 8-mile stretch of creek bed. The loss is consistent with slow downward seepage of water at a rate of around 1 foot/year (ABC, 1997). This is the approximate saturated hydraulic conductivity of clay. In the area of the Lower Animas Artesian (**Figure 4-14**) the Las Animas surface/groundwater system may receive recharge from the USF. At Caballo Reservoir, all water in the Las Animas surface/groundwater system discharges to the reservoir. The nature of artesian conditions in the Percha Creek drainage basin have not been studied in as much detail, and therefore less historical data are available.

Upstream of the artesian wells, Las Animas Creek, the alluvial aquifer can be “perched” above the water table in the Santa Fe Group aquifer system by 20 to 60 ft of unsaturated to partially saturated alluvial sediments (SRK, 1995; ABC, 1997). The alluvial aquifer along Las Animas Creek in the lower reaches loses water to the Santa Fe Group aquifer system by slow downward seepage. The upper reach of Las Animas Creek near the Saladone Well (**Figure 4-14**) also may be perched above the intermediate aquifer (Minton, 1961).

4.4.2.1.3 Existing Baseline Groundwater Information

An enormous amount of site characterization data are available for the Project site because the mine was active in the past and was characterized by previous operators that either mined the site or worked on permit applications to mine the site. These historical data would be used in conjunction with the baseline groundwater quality data that would be collected under the procedures set forth in the *SAP* (Intera, 2010) to provide as thorough an understanding as possible of groundwater quality conditions prior to the re-initiation of mining at Copper Flat. Key resources that contain data to be used for the baseline groundwater analysis include: Groundwater monitoring well exceedences

provided by SRK (2010); the *SAP* (Intera, 2010); the PFEIS (BLM, 1999); the Hydrologic Assessment, Copper Flat Project Sierra County, New Mexico (Newcomer *et. al*, 1993); and The Natural Defenses of Copper Flat, Sierra County, New Mexico (Raugust, 2003). Proposed monitoring well locations are provided in **Figure 4-15**. A brief summary of the data available in these key reports follows.

The PFEIS (BLM, 1999) provides a summary of groundwater quality data. Summary tables for key wells and key constituents are provided in Table 9-2 of the *SAP* (Intera, 2010). The wells identified in this study are illustrated in **Figure 4-14**. The PFEIS (BLM, 1999) concluded that groundwater quality at the site was good and generally useable for domestic and agricultural purposes. This document also concluded that past mining in the Hillsboro District, the Copper Flat Mine tailings facility drainage, and the presence of an oxidized sulfide-bearing ore body have impacted groundwater within and immediately adjacent to the area of past mining, resulting in elevated total dissolved solids (TDS) and sulfate that exceed New Mexico Water Quality Control Commission (WQCC) Standards. These impacts were found to be localized within the immediate vicinity of the mine features or associated with wells completed in the ore body.

Newcomer *et al.* (1993) determined that the quality of groundwater at the site has changed little since the early 1980s and probably since the 1800s. The authors found that there have been some increases in TDS and sulfate in some wells along Greyback Wash below the mine site and down-gradient of the tailings dam, associated with mining and milling activities in the 1980s. Newcomer *et al.* (1993) determined that the only constituents exceeding the WQCC Standards were barium from a spring sample, and, cadmium and fluoride from a pit lake water sample.

Raugust (2003) compiled historical groundwater data and summarized groundwater quality conditions and, based on his data compilation and analysis, concluded:

- Groundwater pH measurements both up and downgradient of the pit lake range from 7 to 8.2.
- TDS and sulfate values are less than WQCC standards in the wells evaluated for this analysis; however, samples downgradient of the mine have increased gradually over time and are approaching the standards for TDS.
- Historical sampling of well GWQ-5, located east and downgradient of the pit lake, indicates that water quality in the vicinity of the pit lake may have been affected naturally by the presence of the ore body prior to mining in 1982.
- The groundwater upgradient of the mine pit lake is high quality with relatively high proportions of chloride and sulfate. Groundwater downgradient of the pit lake shows relatively higher proportions of bicarbonate and calcium and relatively lower proportions of sulfates.
- Pre-Quintana mining (June 15, 1981) groundwater data collected from wells downgradient of the pit lake show similar anions and cation distributions to post-Quintana mining activities (1996 and 1998). This indicates that groundwater quality downgradient of the ore body reflects the natural weathering of the Copper Flat porphyry system.

4.4.2.1.4 NMED Stage 1 Abatement Plan Requirements

On August 20, 2008, the NMED sent a letter to the site owner at that time requiring a Stage 1 Abatement Plan (20.6.2.4101 NMAC). The purpose of the Stage 1 Abatement Plan is to provide the data necessary to select and design an effective abatement alternative. The requirements for the Stage 1 Abatement Plan are described in 20.6.2.4106 NMAC. The abatement plan proposal must include an investigation to define the extent and magnitude of any existing groundwater and surface water contamination and to characterize the hydrogeology of the site. These requirements are similar to the EMNRD requirements for completing a Baseline Characterization Report, and these efforts would be conducted in parallel; therefore, the surface water and groundwater requirements of this SAP are relevant to both characterization efforts.

NMCC's meetings with the NMED concerning the abatement requirements have revealed the following key concerns on the part of the NMED:

- Groundwater impacts from the existing unlined tailings impoundment have been documented, but have not been fully characterized;
- Samples of pit lake water quality reveal exceedences of WQCC standards, and NMED is concerned about migration of this water away from the pit, causing additional groundwater impacts as well as ongoing contact with wildlife; and
- Acid leaching could be occurring due to ongoing ore exposure.

NMCC is currently working with NMED to address these issues.

4.5 Soils

A successful reclamation program is dependent, in part, upon the quantity and quality of soil available for use during the reclamation process. NMCC assessed the quantity and suitability of topsoil present at the site in two ways. First, NMCC reviewed current literature concerning soil characteristics, and second, NMCC determined site-specific soil characteristics. The findings are summarized in this section of the SAP. In addition, baseline soil surveys were completed on the project area as recently as the late 1990s, and are briefly summarized and referenced in the PFEIS (BLM, 1999).

The term "topsoil" refers to the A master soil horizon (Soil Survey Staff, 1999), which is the uppermost mineral horizon that contains organic matter and can be salvaged from the areas to be disturbed and is capable of supporting vegetation, or other soil material capable of supporting vegetation. This material is often referred to as "suitable top dressing" or "growth media." NMCC has reviewed previous literature describing the results of soil surveys completed at the site (BLM, 1999) and is aware that the presence of an A master soil horizon across the site is limited. The purpose of the soil survey and sampling proposed in this section of the SAP is to evaluate the presence of suitable top dressing. However, in the interest of conforming to the requirements of the Mine Act regulations, the term "topsoil" will be used throughout this section to refer to suitable top dressing and/or growth media.

General information about the soils present at the site was obtained from a Soil Conservation Service (SCS) survey completed by Neher (1984). The SCS (now the Natural Resources Conservation Service) mapped two major soil types that occur in the Copper Flat area:

1. The Luzena-Rock Outcrop association
2. The Scholle-Ildelfonso association

All but the easternmost portion of the proposed site is mapped as Luzena-Rock Outcrop association, which is typically present on the steeper slopes of hills and mountains. These soils are typically shallow, very gravelly and cobbly loams and clay loams. The Scholle-Ildelfonso association occurs on more gentle slopes of the piedmonts and mountain toes and is deep, well-drained, and formed in mixed alluvium. The resulting soil texture in these areas is primarily gravely loams and gravelly clay loams (SRK, 1996). The soils are thin and of low productive capacity. The soil textures are primarily gravelly loams and gravelly clay loams and are subject to continuing wind and water erosion. Along with the natural erosion, much of the Copper Flat landscape has been severely disturbed by historical placer mining and the 1982 mining operation. Over 65 percent of the areas targeted by the proposed operation were disturbed during the 1982 operation. Soils were replaced in the north cell of the tailings impoundment and over a portion of the plant site.

4.6 Vegetation

Plant species inventories were conducted in 1976, 1991, 1992 and 1994; newly initiated studies are being advanced to update and expand these previous surveys and inventories. Plant species lists are included in the 1993 EA (BLM, 1993). The pre-mining vegetation inventory is detailed in the 1977 EAR and the 1978 Environmental Assessment Record (BLM, 1978).

The Copper Flat area is within the Mexican Highlands section of the Basin and Range Physiographic Province, and more specifically defined as Southern Desertic Basins, Plains, and Mountains (NRCS 2010). This elevation transition causes an intermixing of environmental factors which has a direct correlation on the variety of vegetation in the area. The vegetation is composed primarily of two desert associations: Chihuahuan desert scrub and desert grassland. In the vicinity of Copper Flat, the low elevation flats and foothills are characterized by Chihuahuan desert scrub (which can be dominated by creosote bush). The highest elevations are predominantly desert grasslands with some scattering of juniper. The intervening area is dominated by desert grasses with a mixture of shrubs.

Much of the Project area has been disturbed by the mining activities of the prior 1982 operation . The dominant biotic communities within the Copper Flat area consist of creosote bush (i.e. Chihuahuan desert scrub) and desert grassland, on the fringes of some piñon-juniper (or juniper savanna) habitat (BLM, 1996).

4.6.1 Chihuahuan Desert Scrub (or Creosote Bush) Community

Grasses can dominate the landscape and may sometimes grow in pure stands. At the Project site, the grasses are associated with a wide variety of sub-dominant shrubs (yucca, *Yucca* spp.; three-leaf (or lemonade) sumac, *Rhus trilobata*; yerba-de-pasmo, *Baccharis pteronioides*; mesquite, *Prosopis*

glandulosa; feather dalea, (*Dalea formosa*); creosote bush, *Larrea tridentata*; sage, *Artemisia* spp.; catclaw, *Mimosa* sp.; rabbitbrush, *Chrysothamnus* spp. and broom snakeweed, *Gutierrezia sarothrae*), trees (Gambel oak, *Quercus gambelli*; Emory oak, *Quercus emory*; willow, *Salix gooddingi* and *Salix exigua*; and cottonwood, *Populus* spp.), and forbs (cactus, *Opuntia* spp.; locoweed, *Oxytropis lambertii* and *Astragalus* spp.; *Geranium* sp., *Solanum* spp., and *Haplopappus* sp.).

4.6.2 Desert Grassland

The desert grassland community in the area dominates the higher elevations of the rolling hills, in the gullies, ravines and washes, and on the slopes and low ridges. A number of grass species are characteristic of this community. The major genera are grama grasses (*Bouteloua* spp.), curly mesquite (*Hilaria* spp.), and three-awns (*Aristida* spp.). The grasses dominate the landscape and may grow in pure stands. At the Project site, the grasses are associated with a variety of sub-dominant shrubs (*Yucca* spp.; lemonade sumac, *Rhus trilobata*; *Baccharis pteronioides*; mesquite, *Prosopis glandulosa*; feather dalea (*Dalea formosa*); creosote bush, *Larrea tridentata*; sage, *Artemisia* spp.; catclaw, *Mimosa* sp., rabbitbrush, *Chrysothamnus* spp. and *Gutierrezia* sp.), trees (Gambel oak, *Quercus gambelli*; Emory oak, *Quercus emory*; willow, *Salix gooddingi* and *Salix exigua*; and cottonwood, *Populus* spp.), and forbs (cactus, *Opuntia* spp.; locoweed, *Oxytropis lambertii*; *Geranium* sp., *Solanum* spp., and *Haplopappus* sp.).

4.6.3 Pinion-Juniper Community

The piñon-juniper and juniper savanna communities occur between the desert grasslands and the coniferous forests at an elevation of about 5,500 feet. All of the sites occupied by this community are on the higher knolls, northern aspects, and in steep, rocky terrain. Although this community is represented by one-seed juniper (*Juniperus monosperma*), it is also known for its association with range forage plants.

4.6.4 Aquatic Vegetation

The presence of aquatic plants in the Copper Flat area is severely limited due to the temporary, intermittent character of Greyback Wash and the lack of other water. Isolated, limited quantities of aquatic plants occur at stock watering areas, in abandoned, caved-in mine shafts, in isolated rock crevices along drainages, and at seeps. The production and diversity is severely limited. Cattails (*Typha* sp.), sedges (*Carex* spp.) and algae (*Chlorophyta, Cladophora* sp., *Scenedesmus* sp., and *Spriogyra*; *Euglenophyta, Euglena viridis*; and *Bacillariophyta, Nitzschia* sp. and *Navicula* sp.) can be located in appropriate habitats. The algae exist only when water is present during the warmest summer months.

Three riparian areas associated with seeps in Greyback Gulch were identified in 1995 during the site investigations performed for the EIS (BLM, 1996) process. The first is located east of the East Waste Rock Disposal Area and north of the access road. This area supports a small group of cottonwoods and willows. The second seep is located south of the plant area and is fed by runoff from the road between the pit and plant area. This seep does not support willows or cottonwoods but provides

water to wildlife and livestock intermittently during the year. The third seep present in the immediate area of the proposed mine is located in Greyback Wash immediately east of the tailings thickener. The original stormwater collection pond is located adjacent to this area and it is believed that this pond, left open during reclamation activities in 1986 has been acting as a reservoir which has been draining into the riparian area through the original discharge pipe which was left in place. This area supports a small group of cottonwoods, willows and other herbaceous species.

One riparian area of relatively moderate functional value is located approximately 2.8 miles west of the mine site in Warm Spring Canyon (BLM, 1996). This small wetland covers less than 0.1 acre and supports several wetland species, including willow and tamarisk. Riparian habitat associated with Las Animas Creek, a perennial stream located approximately 4 miles northeast of the mine area, supports a variety of trees and shrubs including plains cottonwood, Arizona sycamore, walnut, mesquite, Apache plume, hackberry, Mormon tea and prickly pear. Percha Creek is a perennial stream located approximately 2.2 miles south of the mine site which supports a variety of riparian vegetation. Dominant species along this creek include willow, seep willow, ash, plains cottonwood, locust and walnut.

4.6.5 Vegetative Productivity

Foliar cover and forage productivity estimates for desert grassland and previously disturbed land present within the project area were based on visual observations made during field reconnaissance activities and data provided in the soil survey for the Sierra County area (NRCS 1984). An analysis of 12 vegetation plots was conducted by Glover prior to the 1982 disturbance (Glover, 1977). This work and nearby off-site range transects performed by the SCS (Sierra Soil and Water Conservation District, 1990) provided some historic estimates of the vegetative cover, density and productivity in the permit area prior to mining disturbance. Based on current ecological site descriptions, foliar cover for desert habitats within the general vicinity of the project area would be no more than approximately 30 percent (NRCS 2010). Correspondingly, vegetative productivity would range from a low of 150 pounds/acre in unfavorable years, to 450 or perhaps even 750 pounds/acre of forage during favorable years (NRCS 2010). Consequently, this is a very wide range in potential plant productivity and is highly subject to annual amounts of precipitation. Undisturbed desert grassland occurs in the tailings impoundment area, the East Waste Rock Disposal area, the North Waste Rock Disposal area, and the topsoil stockpiles.

Approximately 63 percent of the project area has been disturbed by previous mining operations. As of 1996, the average foliar cover for previously disturbed land is approximately 5 to 15 percent, with the highest foliar cover of approximately 15 percent occurring in the tailings impoundment area and the lowest foliar cover of less than five percent generally occurring at the pit, the West and North Waste Rock Disposal areas, and the Lean Ore Stockpile (Sierra Soil and Water Conservation District, 1990). The majority of previously disturbed land occurs in the tailings impoundment area, the pit, the Lean Ore Stock Pile area and the West Waste Rock Disposal area.

4.7 Wildlife

Wildlife inventories were conducted in 1976, 1991, 1992 and 1995; newly initiated studies are being advanced to update and expand these previous surveys and inventories. Wildlife species lists are included in the Copper Flat Project DEIS (Sierra Soil and Water Conservation District, 1990). The pre-mining wildlife inventory is detailed in the 1977 EAR (Glover, 1977), 1978 Environmental Assessment Record (BLM, 1978), DEIS, and PFEIS.

4.7.1 Mammals

There are a limited number of mammals occurring in the Copper Flat area, and the major factors believed responsible are: (a) low annual productivity of vegetative food and cover, (b) limited diversity in the plant communities present, and (c) lack of water. No aquatic mammals, amphibians nor fish have been observed in the Copper Flat area. No information is available on the myriad of invertebrates present in the area. Mammals that utilize the area are domestic cattle, deer, horses and several feral-domestic goats.

Mule deer harvest has stabilized since introduction of new regulations over the past 15 years. With the reclamation program of 1986, a small number of mule deer have frequented the mine site to feed on the reseeded grasses but move into the remote hills during the hunting season and into the lowlands during severe winters.

4.7.2 Birds

The numbers and species of birds vary widely with the seasons. Waterfowl sporadically use the existing pit lake, particularly during migration (BLM, 1996). Shorebird use of the lake is limited due to the lack of shallow foraging areas and appropriate habitat (BLM, 1996). A variety of raptors utilize the area of interest and the most common are: red-tailed hawk (*Bueto jamaicensis*), kestrel (*Falco sparverius*) and marsh hawk (or northern harrier) (*Circus cyaneus*). Golden eagles (*Aquila chrysaetos*) have been observed in the Copper Flat area. The Bald eagle (*Haliaeetus leucocephalus*) occasionally visits the Las Animas Creek area (8 km north of the mine site) during the winter and spring seasons. Historically, no active raptor nests nor regular eagle roosting sites were known to occur in the Copper Flat mining area. Based on a recent observation, this may not be true anymore. An active nest of the great horned owl (*Bubo virginianus*) was observed on a cliff face.

4.7.3 Reptiles

Six species of reptiles have been observed in the area; however, approximately 36 species of reptiles and amphibians are expected to occur in the greater district (BLM, 1996). By far, the most numerous are the different lizards. A variety of snakes, including rattlesnakes, are present in the area. The 1977 Environmental Assessment Report (Glover, 1977) and 1978 Environmental Assessment Record (BLM, 1978) present the reptilian species observed during environmental monitoring and probably represent the most abundant species within the area.

4.7.4 Invertebrates

A tremendous variety and abundance of invertebrates occur in the area of interest. The most numerous are beetles (Coleoptera). Other common orders are the bugs (Hemiptera and Homoptera), bees and wasps (Hymenoptera) and centipedes (Chilopoda). Butterflies and moths (Lepidoptera) are seen infrequently.

4.7.5 Fisheries

The only perennial aquatic environment at the mine site is the pit lake. No fish occur in the pit lake (BLM, 1978).

4.8 Threatened, Endangered, or Candidate Species

A Biological Assessment has been prepared in accordance with Section 7(c) of the Endangered Species Act to determine if any sensitive plant or animal species may be impacted by the proposed Project. The BLM, as lead agency for the EIS process, requested a Section 7 consultation from the U.S. Fish and Wildlife Service (USFWS). A total of four federally-listed and 15 federal candidate species were addressed in detail in the 1996 Biological Assessment (BLM, 1996).

Newly initiated threatened and endangered studies are being advanced on the project area to update and expand the previous studies and survey. Most of the species being targeted for review and for potential habitat are species of concern (or sensitive listed species), those that do not have official protection status. There are a couple of officially listed threatened and endangered species to be evaluated, which are discussed in the following sections.

4.8.1 Vegetation

Grama grass cactus (*Pediocactus papyracanthus*) was the only endangered or threatened species whose habitat might include the Copper Flat Project acres (BLM, 1996). The 1976 and 1992 searches and inventories did not reveal the presence of the grama grass cactus or any other sensitive plants (BLM, 1996). A couple of the plant species of concern to assess include Sandberg's pincushion cactus (*Escobaria sandbergii*) and the Pinos Altos fame flower (*Phemeranthus humilis = Talinum humile*). A state of New Mexico endangered cactus, Duncan's pincushion (*Escobaria duncanii = Coryphantha duncanii*) would also need some investigation. One of the only known locations for this cactus species is situated very close to the Copper Flat site.

4.8.2 Wildlife

Mining and other surface disturbance activities may affect species listed by the USFWS and New Mexico Department of Game and Fish as threatened, endangered, or candidate. A list of a number of endangered and threatened fauna that might occur in the assessment area is presented in the 1996 DEIS (BLM, 1996), 1996 BA (BLM, 1996), and 1999 PFEIS.

The peregrine falcon (*Falco peregrinus*) occurs commonly in the Rio Grande Valley and might occasionally be expected to hunt in the foothills east of the Black Range.

Bald eagles were seen flying in the vicinity of the site in 1995 and probably forage along Caballo and Elephant Butte reservoirs. Local riparian areas near the mine site could provide additional forage habitat, however these areas would not be considered optimal foraging habitat for eagles, and no records indicate that bald eagles use them for foraging or roosting.

The loggerhead shrike (*Lanius ludovicianus*) was observed during the field assessment in 1991. This species is very wide spread (habitat comprises 63 percent of BLM land in Sierra County).

The common black hawk has been recorded along Percha Creek; however, no nesting sites have been documented. Las Animas Creek could provide suitable habitat for this species.

The ferruginous hawk historically occupied the region and has been recorded within the creosote upland and grass mountain habitat near the location of the proposed project (IHICS, 1995). The area was surveyed in 1991 for the presence of nesting ferruginous hawks; no sign of nest hawks was observed in or near the Project at that time (Stinnett, 1991).

The northern goshawk is associated with a variety of forest type habitats which do not occur in the Project area. No sightings of this species have been reported in the vicinity of the Project.

Baird's sparrow, a state of New Mexico threatened species, is migratory in New Mexico and most commonly observed in the fall. This species has been observed in Sierra County, but foraging grassland habitat is limited in the Project area and no sightings have been recorded.

Habitat for six of the seven species of bats studied during the preparation of the EIS exists in the Project area, including the greater western mastiff bat, occult little brown bat, spotted bat, fringed myotis, Yuma myotis and pale Townsend's big-eared bat; however, some of these habitats would be considered marginal to support these species. The Townsend's big-eared bat has been documented roosting in the Tony House, located near the tailings facility. The detailed background information and the potential for occurrence pertaining to these seven sensitive bat species is presented in the Biological Assessment prepared for the Project.

The Texas horned lizard has been documented in Sierra County and is known to occur in and near the Project site.

The long-fin dace was documented in Percha Creek in 1995. This fish, a federal candidate-category 2 species is believed to have been introduced into Percha Creek, since it does not naturally occur east of the Continental Divide (Bison-M, 1995) (BLM, 1996).

Habitat requirements for a few other wildlife species of concern would be evaluated such as the western burrowing owl (*Athene cunicularia hypugae*), Gunnison's prairie dog (*Cynomys gunnisoni*), and pocket gophers (*Geomys* spp.).

4.9 Range Resources

Livestock grazing is allowed in areas adjacent to the mine area. However, the grazing Allotment (No. 6079) does not include the Project area at this time because of the need to exclude livestock from the area of mining activity.

4.10 Air Quality

The primary pollutant of interest at the mine site is fugitive dust since the emissions of other pollutants are quite small. Alta installed a PM_{10} monitoring station at the site in 1994 to collect baseline information at the site (Air Sciences, 1995). The DEIS utilized fine particulate data collected at Gold Hill by the New Mexico Air Quality Bureau from 1990 to 1992 to evaluate ambient air quality at Copper Flat (BLM, 1996). Although Gold Hill is located more than 20 miles west of the Project area, operations at Gold Hill are similar to those proposed for Copper Flat and it was assumed that data collected at Gold Hill would be representative of conditions at the Project site (BLM, 1996). High winds sometimes create local dust storms which result in higher short-term concentrations; nonetheless, Sierra County has been designated as an attainment area, which means that the area meets all applicable air quality standards. Because there are no significant pollution sources in the area, the overall air quality in the vicinity of the Project site is good (BLM, 1996).

The primary air quality impacts from the Project would be associated with particulate emissions. Modeling of these impacts indicated that the maximum values for 24-hour and annual concentrations of Total Suspended Particulates (TSP) would occur at the property boundary (BLM, 1996). The nearest Class I area is located more than 30 kilometers west of the Project and the models indicated that levels would fall below $1\mu g/m^3$ within less than 10 kilometers from the site. Therefore, there would be no significant impact from the Project on any Class I area (BLM, 1996).

NMCC installed one meteorological and two air quality monitoring stations at the site in August 2010 for the purposes of collecting more up-to-date information on current air quality.

4.11 Cultural Resources

Several cultural resources surveys have been conducted at the site since 1976. The initial surveys were conducted for the 1977 and 1978 EARs (Glover, 1977). A subsequent Class III (100-percent pedestrian coverage) cultural resources survey was conducted by Mariah Associates for Gold Express in 1991 (Evaskovich, 1991). In response to comments from the New Mexico State Historic Preservation Officer (SHPO) in August, 1995, Alta contracted with Human Systems Research (HSR) of Las Cruces to resurvey all of the undisturbed portions of the Project not covered by the 1991 survey. The results of this survey were filed with the SHPO in October 1995 (Sechrist, 1995). Because the HSR survey was conducted more than 10 years ago, the lead federal agency (BLM) for cultural resource compliance review and the SHPO would review the previous survey for sufficiency and consistency with current standards for survey investigations. This review would also take into consideration the probability for new sites to have become exposed in the interim, such as through active dune formation/movement. If it is determined that a new pedestrian survey does not need to be conducted prior to construction, then the fieldwork effort for cultural resources likely would be limited to revisiting previously recorded sites to evaluate their current condition, and to reassess potential effects to these resources from the Project.

A number of prehistoric and historic sites eligible for listing in the National Register of Historic Places have been identified at the Project area. Where possible, identified sites would be avoided by modifying the design of project components. For sites which might be impacted by the Project, and

for which avoidance is not feasible, NMCC would contract with qualified archaeologists to prepare a recovery plan to collect appropriate data, to minimize and mitigate adverse effects to cultural resources resulting from the Project. Following approval by the BLM and SHPO, the recovery plan would be implemented prior to construction.

5 Reclamation and Closure

5.1 Introduction

The Copper Flat Project site would be reclaimed to achieve a self-sustaining ecosystem appropriate for the climate, environment and land uses of the area. Careful consideration would be given to cooperation with neighbors in their land use requirements including cattle grazing, alternate energy generation such as wind and solar, and reestablishment and enhancement of original botanical and zoological species habitants.

The reclamation plan has been developed to meet the site specific characteristics of the mining operation and Project site. The objective of the reclamation plan is to return the Project site to conditions similar to those present before re-establishment of the mine. The mining operation and reclamation plan have been designed to use the most appropriate technology and BMPs to assure protection of the human health and safety, the environment, wildlife and domestic animals. The Project is designed to meet, without perpetual care, all applicable federal and state environmental requirements following closure.

5.2 Statutory and Regulatory Requirements

Reclamation of disturbed areas caused by the Project would be in compliance with federal and state regulations. Under the Federal Land Policy Management Act (FLPMA), the BLM is responsible for preventing undue or unnecessary degradation of federally-administered public lands which may result from operations authorized by the mining laws (43 CFR 3809). The New Mexico Mining Act requires the preparation of a reclamation plan for submittal and approval by the New Mexico Energy, Minerals and Natural Resources Department (NMEMNRD) and New Mexico Environmental Department (NMED). In addition, closure of the tailings embankment must also comply with requirements of the New Mexico State Engineer's Office.

Reclamation would be conducted concurrently with mining operations where feasible. At closure, final reclamation would be accomplished by a "close out" work force.

5.3 Post-Mining Land Use

Major land uses occurring in the vicinity of the Project site are mining, grazing, wildlife, watershed and recreation. Following closure, the Project area would continue to support mineral development, grazing, wildlife habitat, watershed, and to a lesser degree, recreation. Proposed reclamation of the site should result in a successful program to restore the area to the productive land uses discussed above. All post-closure land uses are in conformance with the previously defined BLM Caballo Planning Unit, the 1985 White Sands Resource Management Plan (RMP) and the Sierra County

Comprehensive Land Use Plan. Currently, the White Sands RMP is being revised, updated, and incorporated into the BLM's Tri-County RMP/EIS. The new Tri-County RMP includes Sierra, Otero, and Doña Ana Counties. This revision process began in 2005 and is still in a draft version going through public review. The BLM's analysis of public comments is scheduled for release in January of 2011.

Following closure, the pit would partially fill with water from sub-surface flow resulting in a permanent impoundment (SRK, 1995). Hydrogeologic and geochemical modeling indicates the post-closure pit lake water quality should be similar to that of the current pit lake (SRK, 1995). Possible post-closure uses for the pit include a water reservoir for agricultural and grazing purposes. The pit lake has also been proposed by the BLM as a possible location for a field-scale aquatic life laboratory, or other possible cultural uses yet to be identified.

5.4 Summary of Disturbance

Reconstruction would involve utilization of existing foundations and previously disturbed land where feasible. For the Proposed Action, approximately 65 percent of the proposed disturbance would take place on areas disturbed during the previous operations. New disturbance of previously undisturbed land would be kept to a minimum. Approximately 90 percent of the new disturbance would be related to the tailings and waste rock facilities.

Areas to be disturbed are divided into the following major mine components: open pit area, waste rock disposal areas and low-grade stockpile, tailings impoundment, and plant site. The utility corridor, access road and surface water diversions were developed during the previous operations and no further disturbance is anticipated associated with these facilities. The majority of the haul roads were also developed during previous operations and only minor additional disturbance would be related to haul road construction.

5.5 Reclamation Plan

The goal of the Copper Flat reclamation program is to minimize disturbance to the environment and to restore disturbed areas to a self-sustaining ecosystem consistent with applicable regulations, the post-mining land use and mine reclamation standards. The objectives of the Copper Flat reclamation program are:

- To meet or exceed applicable state and federal reclamation requirements through application of most appropriate technologies and BMPs.
- To minimize erosion and prevent contribution of suspended solids to streams and other bodies of water through employment of best management practices and contemporaneous reclamation, to the extent appropriate and practicable.
- To protect human health and safety, the environment, wildlife and domestic animals, cultural resources, the hydrologic balance, and extant riparian and wetland areas, including reclamation of any streams that may be impacted by the mining operations.

- To protect the quality of surface and ground water resources by minimizing pollutant formation, and on-site containment of any unavoidable toxicity.
- To preserve suitable topsoil and other approved topdressing material for use in reclamation, employing appropriate and BMPs for sampling, testing, replacement, and stabilization.
- To establish surface soil conditions most conducive to regeneration of a stable plant community through stripping, stockpiling, and reapplication of alluvial or soil material where feasible.
- To revegetate disturbed areas with a diverse mixture of appropriate plant species, in order to achieve a self-sustaining ecosystem or other approved post-mining land use.
- To identify any roads that may be disturbed by mining operations and which are not planned to be returned to use, consistent with the approved post-mining land use and applicable land owner approvals.
- To maintain public safety and site stability through appropriate recontouring and revegetation of disturbed areas within the permit area.
- To work with local and regional communities to identify post-mining uses of the land and facilities to enhance opportunities to sustain the economy and culture in the post-mining phase of this project.

Surface facilities, equipment and buildings related to the mining Project would be removed, foundations covered, and the plant site returned to conditions similar to those present before re-establishment of the mine. The topography, slopes and aspects of the disturbed and reclaimed areas would be developed to blend in with the present, existing physiographic forms of the Copper Flat area, as feasible.

5.6 Implementation

Contemporaneous reclamation of disturbed surface areas would be an integral part of the mining operation. Both public and private land would be reclaimed. At completion of mining activities, the site would be restored to conditions and standards to meet approved post-mining land uses. These uses would include native plant communities similar to surrounding undisturbed areas, wildlife habitat, and grazing land potentially suitable for livestock. The reclamation and restoration must be demonstrated to be sustainable without perpetual care. Closure of the site would be accomplished by the following activities:

- Pre-construction and Permitting: This is the stage wherein baseline data is collected to characterize the existing environment. The baseline data are used to formulate reclamation goals. This stage has been conducted since the late 1970s and currently new studies are being advanced to add to this existing database of studies to expand and update to current requirements.
- Construction: Where feasible, the existing soils and suitable alluvial material would be removed first from major disturbance areas (tailings impoundment, waste rock disposal

areas, etc.), stockpiled, protected, and used in the reclamation process. The revegetation test program would be initiated during this phase of the operation.

- Operations: Reclamation efforts would be implemented at the earliest feasible time in areas where activities are discontinued. This includes recontouring, scarifying, placement of soil, alluvial material, and other approved topdressing material, followed by revegetation. The revegetation test program and concurrent reclamation would be monitored during this phase to provide data that would be utilized to determine final closure methods to be implemented to achieve reclamation goals, subject to regulatory approval.
- Closure: Upon closure of the mining operations, unreclaimed facilities would be reclaimed according to the reclamation plan.
- Post-Closure Monitoring: Following the completion of reclamation and closure activities, the revegetation would be monitored for at least two growing seasons and meet Part 6 requirements under the New Mexico Mining Act. Groundwater would be monitored according to conditions set forth in the Ground Water Discharge Permit, which is currently being prepared by NMCC for submission to NMED.

A tentative project schedule, including reclamation schedule encompassing these five project stages, is presented in **Figure 5-1**. The schedule shown is approximate and could change due to a number of operational and economic conditions.

5.7 Environmental Considerations for Reclamation

The reclamation plan is designed to assure protection of human health and safety, the environment, wildlife and domestic animals.

5.7.1 Signs, Markers and Safeguarding

Measures such as signs, markers, fences and barricades would be used to protect the public, wildlife and domestic animals from potentially dangerous areas associated with the Project. Safety measures associated with the major Project components are discussed in more detail in Section 5.16.

5.7.2 Wildlife and Domestic Animal Protection

Reclamation of the Copper Flat Project would be conducted to achieve a stable configuration and access to unsafe areas would be restricted for protection of the public and animals.

The Project would result in the reclamation of over 910 acres of land disturbed by previous mining activities. This reclamation would be a beneficial impact to wildlife resources. However, because of the long-term loss of woody species, the reclamation of the previously disturbed land would mainly benefit those species typically associated with herbaceous vegetation. It is anticipated that the Project area would support a greater variety of species following closure due to the additional habitat diversity created by the mining and reclamation programs.

5.7.3 Cultural Resources

Cultural resources requiring protection, and any cemeteries or burial grounds (none are anticipated), shall be protected and/or avoided during reclamation activities. This includes any resources identified before or during Project activities.

5.7.4 Hydrologic Balance

Hydrogeologic studies have been completed to estimate the potential impacts to ground water from the tailings impoundment and to surface and ground water from acid mine drainage (ARD) from the overburden and waste rock piles (SRK, 1995). In addition, the predicted elevation and final chemistry of the pit lake was modeled (SRK, 1995). For the reasons set forth below, the potential for ARD from the Project is low.

5.7.4.1 *Acid Rock Drainage*

Although no major impacts have been identified associated with waste rock disposal from the previous operations, the potential for acid generation from some of the rocks has been identified. Studies were completed previously to evaluate the potential for acid generation and metal leaching from the various types of mine overburden, waste rock and tailings materials at the site (SRK, 1995) and additional studies and evaluations are underway to augment and update the information currently available.

The results of the ARD studies indicate that the potential for ARD from the tailings is considered low. The risk of ARD from the bulk of the existing and future waste rock is also considered low; however, some of the waste rock to be extracted would be partially oxidized (transitional) and this material has the potential to generate acid if not disposed of properly. Therefore, the transitional waste rock would be managed and reclaimed to alleviate the potential for ARD. Because of improved project economics, it is estimated that a major portion of the previously identified transitional material would now report to the tailings facility.

Proper waste management has been proven effective in alleviating the potential for ARD. The transitional waste rock would be segregated and placed in the west and north waste rock disposal areas for the Proposed Action as shown on **Figure 3-1**. The surface of the all waste rock disposal areas would be reclaimed in the same manner as proposed for disposal areas containing partially oxidize material. The disposal areas would be contoured to enhance run-off and covered to reduce infiltration.

The waste rock piles would be reclaimed by regrading, dozer compacting the surface and covering this surface with up to 12 inches of native soil. These measures would inhibit infiltration and reduce the quantity of water required to produce drainage. The waste rock disposal areas containing transitional material would be located adjacent to the pit lake. In the unlikely event acid drainage does occur, it would flow into the pit lake where it would be diluted by ground water inflow and

prevented from migrating into ground water. The high evaporation of the pit lake water causes ground water to flow into the pit, preventing any surface inflows from entering the ground water.

The quality of the current pit lake water appears to be impacted by oxidation of minerals exposed in the pit wall. Results of pit water sampling indicate that, although the water in the pit meets state surface water quality standards for livestock and wildlife use, it contains elevated concentrations of sulfate, fluoride, calcium, cadmium and manganese. A preliminary study has been completed to determine the post-closure pit water quality (SRK, 1995), and ongoing geochemical characterization work would update this study. The findings of the study indicate that the majority of the transition materials would be removed by the pit expansion, significantly reducing the surface area of these materials exposed in the pit walls in comparison to the present day condition of the open pit.

Run-off from the waste rock disposal areas would be collected in facilities constructed at each area.

5.7.4.2 *Suspended Solids*

Sediment control would be achieved by the use of BMPs. BMPs include regrading, seeding and mulching, silt fences, straw bale dams, diversion ditches with energy dissipaters, and rock check dams at appropriate locations during construction and operation. Diversion structures, including existing structures, would divert run-on away from disturbed areas. New diversion structures and sediment control features for the proposed PoO would be evaluated for 25-year, 24-hour and 100-year, 24-hour storms according to the criteria contained in **Appendix B**. All sediment control structures would be monitored and maintained on a regular basis.

During operations, all run-off from the plant site would be directed into a sediment pond located on the east side of the site adjacent to the make-up water pond. Following reclamation this pond would no longer be necessary for sediment control. The dike separating the sediment pond from the make-up water pond would be removed, the pond regraded to restore conditions similar to those currently existing, and the site revegetated.

5.7.4.3 *Diversions and Overland Flow*

Runoff from particular areas of the Copper Flat Project site was originally estimated using the climate data summarized in Section 4.3. The surface drainage of the Project site was designed to contain or control either a 25-year, 24-hour duration storm of 2.9 inches or a 24-hour precipitation of 2.6 inches with a maximum 1-hour intensity of 2.0 inches, depending on the area (**Appendix B**). NMCC is in the process of re-evaluating these design criteria with respect to current regulations and engineering standards. During reclamation most areas would be regraded and, where possible, the original drainages restored.

The diversions of surface water runoff around the waste rock disposal areas would remain in place. Ditches would be lined with rip rap, as needed, to protect the channels from erosion.

5.7.4.4 *Stream Diversions*

The watershed area to the west of the pit is drained by Greyback Wash, an ephemeral stream which is dry over most of its length except during the rainy season. Greyback Wash used to pass through the pit area. This drainage has been intercepted, diverted around the southern periphery of the pit, and returned to the original channel east of the pit area. This was accomplished by cutting a channel through the ridges and placing diversion dams in the tributary arroyos. Following closure of the previous operation, the diversion was left in place. The diversion would be left in place following closure of the proposed operation.

5.7.5 Impoundments

The tailings impoundment has been designed, constructed and maintained to minimize adverse impacts to the hydrologic balance and adjoining property and to assure the safety of the public. Reclamation and closure of the tailings impoundment is discussed in more detail in Section 5.16.4.

5.7.6 Prevention of Mass Movement

All slopes, impoundment embankments and waste rock disposal areas would be designed, constructed and maintained to prevent the potential for mass movement both during operations and following closure. The existing waste rock disposal areas were designed according to the parameters set forth in **Table 5-1** and were selected to minimize reclamation costs at the end of mine life using a 1.3:1 H:V lift face slope ratio as the constructed as-built slope angle, and a regraded lift slopes of not less than 2.5:1 H:V.

Table 5-1: Waste Rock Disposal Facility Design Parameters

Parameter	Value
Batter Angle (º)	37º
Berm Width (ft)	30 ft
Lift Height (ft)	30 ft
Road Width (ft)	80 ft
Road Grade (%)	10%
Slope (º)	22º

NMCC is currently working on the final designs for the proposed waste rock disposal facilities. To the extent practicable, they would be designed to meet these same criteria.

5.7.7 Riparian Areas

The Copper Flat mine area is primarily a terrestrial habitat. No wetlands and two riparian areas are present in the immediate area of the proposed mine. The riparian areas, located in Greyback Wash immediately south and east of the plant site, did not exist prior to the 1982 operation, as evidenced

by photographs. The riparian area south of the plant area is believed to have developed as a result of modifications of the flow in Greyback Gulch from culverts installed in 1983. It is believed that the eastern riparian area was created from flow collected in the stormwater collection pond and alterations of surface water flows in Greyback Gulch resulting from the construction of the land bridge for the tailings pipeline. Because the stormwater pond would be used in the proposed operation, NMCC would supply water from the freshwater supply during operations. Following operations, NMCC would endeavor to restore the storm water collection pond to a condition similar to that existing at present. However, the exact configuration which led to the creation of this wetland is not known and complete restoration may not be possible. As with upland vegetation and plant communities, wetland and riparian plant species would naturally become established at locations that are suitable for their survival, growth, and development. This would occur even if such locations and conditions are generated by human activities. The riparian and "wet" areas would be considered during the environmental evaluations and managed appropriately according to state and federal requirements.

5.7.8 Roads

Access to the site is via an existing county road (Gold Dust Rd./Co. Rd. Bo27) which would remain following closure. Prior to final closure, the State of New Mexico and the BLM would determine which other roads would be left intact around the site in order to conduct post-closure monitoring or provide adjacent landowner access. All other NMCC mine-related roads would be removed.

5.7.9 Surface Facilities or Roads Not Subject to Reclamation

A number of pre-1981, primitive roads currently exist within the proposed project boundary. Some of these roads would not be utilized during the currently proposed operation. As such, they are not subject to reclamation by NMCC.

5.7.10 Drill Hole Plugging and Water Well Abandonment

Mineral exploration and development drill holes, monitoring, and production wells subject to state regulations would be abandoned in accordance with applicable rules and regulations (NMAC 19.27.4 *et seq*.). Boreholes would be sealed to prevent cross contamination between aquifers and required shallow seals would be placed to prevent contamination by surface access.

Monitoring wells around the tailings impoundment would be maintained until NMCC is released from this requirement by the NMED, MMD, and BLM. These wells would then be plugged and abandoned according to applicable requirements.

5.7.11 Post-Closure Monitoring

Monitoring would be ongoing throughout the life of the operation, during closure and for a post-closure period. The BLM and state agencies would set post-closure monitoring requirements at mine closure.

Sampling of the water in the pit after mine closure would continue for a period of not less than five (5) years following mine closure to determine any changes in pit water quality.

The tailings dam/pond would be regulated by the New Mexico State Engineer's Office for safety of operations. A Discharge Permit that requires monitoring for seepage into the ground water would be required from the New Mexico Environmental Department (NMED), Ground Water Bureau. Following closure water samples from monitoring wells located downstream of the tailings dam, and in the plant and pit area would be taken and analyzed on a regular basis and the results sent to the Ground Water Bureau in accordance with monitoring requirements set forth in the Discharge Plan. These samples would identify any seepage from the tailings pond. The Discharge Plan Application contains abatement plans if leakage and contamination occurs.

5.8 Site Stabilization and Configuration

The Project site would be stabilized, to the extent practicable, to minimize future impact to the environment and protect air and water resources. The final surface configurations for the Proposed Action (**Figure 5-2**) would be suitable to achieve the post mining land uses as discussed in Section 5.3. All facilities, slopes, embankments, and roads would be designed, constructed, maintained and reclaimed to achieve stable configurations.

The topography, slopes and aspects of the disturbed areas would be developed to blend in with the surrounding topography as much as practicable. Where possible the size and shape of channels of new drainages would approximate former, natural drainages. All drainage channels, ditches and earthen water control structures would be revegetated and protected from erosion by riprap, sediment traps or other types of BMPs. Alluvial materials suitable for surface treatment would be salvaged from disturbed areas where safe and feasible operation of earthmoving equipment is possible, and would be stockpiled and protected for use in reclamation.

An attempt would be made to favor initial revegetation on north and east aspects of gentle slopes where additional moisture is available. A limited number of slopes might exceed a 2.5H:1V condition but most slopes would be restructured to resemble existing topography. The steeper slopes would be stabilized by physical media (boulders, alluvium, rock) as well as vegetative means to add to general diversity and stability.

Flatter disturbed areas (slopes of 4H:1V or less) would be minimally regraded to restore the natural drainage, and would be revegetated, except those in the tailings impoundment which would be regraded to direct surface water away from the top surface of the reclaimed tailings.

5.9 Plant Growth Media and Cover Materials

5.9.1 Removal and Storage

Suitable soil material available for reclamation from the previously mined and disturbed areas at the Project site is very limited. Efforts would be made to carefully strip, stockpile and improve the remaining growth media available on the site. Because the available soil from newly disturbed area is thin and of low productive capacity, the O and A horizons of soil material would be salvaged, where possible.

The O horizon is the uppermost soil layer and is composed of slightly decomposed organic materials. It contains a high percentage of microbial constituents found in soils which have been determined to be beneficial to plant life. The A horizon is the uppermost zone from which soluble salts and colloids have been leached and in which fully decomposed organic matter has accumulated. In those areas where the A horizon is shallow or indiscernible, suitable B horizon material would also be stripped and stockpiled. The B horizon is the layer in which material leached from the overlying A horizon is accumulated. It usually contains very little organic matter and is lower in microbial activity than the O and A horizons. However, due to the low organic matter content of the A horizon at this site, the A and B horizons do not differ substantially. For these reasons, the B horizon material would not be stockpiled separately from the O and A horizon soils.

Where salvageable soil exists, either on undisturbed or reclaimed areas, NMCC would salvage as much material as can be safely and practically recovered. However, the lack of reclamation cover material available from previously disturbed areas and the poor development of topsoil at the site may require the evaluation of alternative sources and types of materials for use as reclamation cover.

Samples of soil materials were collected and analyzed prior to disturbance in 1977 (Glover, 1977) and in undisturbed areas in 1996. Analyses of the 1977 samples indicate the soils collected were fertile, with the exception of soils from the Waste Rock Disposal Area being low in available phosphate. The 1996 sample taken from the North Waste Rock Disposal Area indicated similar results, but that taken north of the West Waste Rock Disposal Area showed poor fertility. Both samples were low in organic matter (Johnson, 1996).

Sampling in 1996 indicated soil depths of less than four inches exist under the proposed East Waste Rock Disposal Area. This limited thickness and abundant outcrop would preclude the salvage of any appreciable soil quantities from this area. The areas which would be disturbed by the West and North Waste Rock Disposal Areas were observed to have approximately eight inches salvageable soil. Soils in the undisturbed areas of the tailings impoundment were observed to average approximately 18 inches. This material would be salvaged by earthmoving equipment prior to tailings deposition. The estimated volumes of salvageable soil available in areas to be newly disturbed or redisturbed by the Project are shown in **Table** 5-2.

Table 5-2: Estimate of Available Soil from Newly Disturbed Areas

Facility	New Disturbance Footprint Area ($ft^2 \times 10^6$)	Salvage Thickness (inches)	Estimated Volume ($yd^3 \times 10^3$)
Proposed Plan			
West Waste Rock	0.36	~12	13.2
North Waste Rock	1.02	~12	37.8
East Waste Rock	4.98	0	0
Low-Grade Stockpile	0	0	0
Plant Area	7.4	~8	182.8
Tailings Impoundment	3.3	~18	181.5
Roads and Misc.	1.2	~6	21.78
Total	**18.26**		**437.08**

A comparison of estimated quantities of available cover material (**Table** 5-2) and potentially required cover material (**Table 5-3**) indicates that there could be a deficit of over 1.0 million cubic yards of cover material for the currently proposed reclamation plan. As part of the proposed operations, NMCC plans to salvage most of the near-surface alluvial materials from within the limits of the new tailings impoundment to mitigate this soil deficit. These materials are part of the Santa Fe formation gravels and alluvial basin fill and were used in the construction of the original starter embankment. In addition to soil samples, four samples of near surface alluvial materials were collected in the tailings impoundment area at depths between 5 and 20 feet below the original surface. Analyses indicate these materials are low in organic content, phosphorus, nitrogen and potassium. Evaluations are on-going in this area to evaluate this material for structural material (tailings impoundment construction), reclamation material, and mineral content.

Table 5-3: Estimated Reclamation Cover Requirements

Facility	Surface Area ($ft^2 \times 10^6$)	Cover Thickness (inches)	Volume ($yd^3 \times 10^3$)
West Waste Rock	0.8	~12	29.7
North Waste Rock	1.5	~12	56.3
East Waste Rock	5.37	~12	198.8
Low-Grade Stockpile	1.45	~12	53.6
Plant Area	7.4	~8	182.7
Tailings Impoundment	23.8	~12	882.5
Roads and Misc.	11.1	~6	205.7
Total	**51.42**		**1,609.3**

No areas unaffected by mining are currently proposed to be disturbed in order to obtain reclamation cover materials. Several borrow areas currently existing within the limits of the tailings impoundment would be the source of the excavated materials. Mine haul trucks and front end loaders would excavate the required materials during the construction period. Following stripping, suitable growth media and alluvial material would be salvaged and stockpiled. These locations were chosen to minimize haul distances and to limit erosion. The piles would be constructed with slopes varying from angle of repose to 3H:1V and to heights up to 40 feet. The different aspects and slopes of the stockpiles would be used in the test revegetation program to evaluate slope revegetation methods. Existing piles of these materials north of the impoundment demonstrate an ability to retain angle of repose slopes without undue erosion or instability.

Diversion ditches would be constructed around the stockpiles where necessary to minimize run-on erosion. To stabilize the portions of the growth media stockpiles not used in the revegetation test program, and minimize erosion and maintain biological viability, they would be seeded with an interim seed mix as recommended by the BLM. The interim vegetation cover established on the growth media stockpiles would further reduce soil erosion while providing micro-habitats for beneficial soil organisms.

Efforts would be made to salvage the existing vegetation on the areas that would be newly disturbed by the Project. Prior to and during soil salvage, woody plants and vegetation would be removed. The vegetation would be stored with the growth media to increase the organic matter content of the growth media.

5.9.2 Placement

The goal at Copper Flat is to salvage sufficient growth media and alluvial material to provide a 6 to 12-inch cover on areas to be revegetated, if reserves prove sufficient. Less than 12 inches of growth media was placed on the north cell of the tailings impoundment during the previous reclamation efforts. Analysis of the vegetation in that area demonstrates the effectiveness of that thickness of growth media for the purposes of developing a self sustaining ecosystem. Suitable growth media and alluvial materials would be salvaged and stockpiled from all disturbed areas as is feasible. **Table 5-3** shows the required cover volumes by facility.

The final details of the placement and use of these materials in reclamation would be approved by the state and BLM following analysis of the results of a test plot program which would be conducted during the mining operation. Furthermore, concurrent reclamation using this material would provide additional information regarding the success of the approved techniques and allow ongoing modifications to occur.

To ensure good contact with the subsoils, the surface would be roughened by ripping or disking prior to placement of the cover material. The cover material would be spread and graded with care taken to prevent a reduction in bulk density by limiting the number of passes. Following placement, the area would be walked with a dozer to lightly compact the soil.

5.9.3 Amendments

Soils and alluvial materials to be salvaged for reclamation cover are deficient in nitrogen, phosphorus and potassium and would require 4,000 to 8,000 pounds per acre of amendments to create fertile growth media (Johnson, 1996). Aerobically digested sanitized sewer sludge, cotton husks, feedlot cattle waste are possible natural materials which might be used, if available, to amend the growth media prior to placement on reclaimed areas. Composting of materials, if required, would be performed on site to better control the rate and amount of composting.

Other amendments may also be necessary. Ultimately, fertilizer and amendment requirements would be based on chemical analysis of disturbed/replaced soils, and the results of the test revegetation program and contemporaneous reclamation efforts. The application rates would be determined based on the uniformity of the soil characteristics and topography.

The amendments would be incorporated into the top four to six inches of the surface by harrowing. Repeated applications may be required based upon additional testing and vegetation monitoring.

5.10 Revegetation

The revegetation plan is designed to create a stable, self-sustaining plant community, and would be in conformance with the planned post-mining land uses of wildlife and grazing.

The dominant biotic communities of the Copper Flat area are Chihuahuan desert scrub (often dominated by creosote bush) and desert grassland. The desert grassland community is the major community at the site and is dominated by desert grasses with a mixture of shrubs. The Chihuahuan desert scrub community is found on low elevation flats and foothills and occurs on the eastern portion of the site.

Due to the general harshness of the Chihuahuan desert scrub community, most of the animal species using this habitat are small in size, such as reptiles, rodents, and rabbits. The desert grassland community supports a wide diversity of insects and provides suitable habitat for a variety of animals. Most of the grasses are important for livestock forage and provide watershed protection.

Due to the general lack of surface water, the Copper Flat area provides essentially no aquatic environment. Micro-aquatic ecosystems present along the drainage ways are unstable, and community production and diversity is severely limited.

To achieve the post-mining land use of wildlife and grazing, revegetation of the site would consist mainly of the establishment of grass, forb and shrub species characteristic of the desert grassland community. Plant species would be chosen based on their ability to provide satisfactory cover, and on their nutritional value and ability to support wildlife habitat. Riparian and water-loving plant species (willows, cottonwood, cattails, sedges, etc.) may be introduced in drainage channels and in shallow areas near the shoreline of the pit lake.

Diversity of plant species on revegetated, disturbed lands may be less than on undisturbed areas. However, the seed would contain native plant species (grasses, forbs, and shrubs) in a mix

approximating adjacent desert grassland community areas. The revegetation of the re-developed Project is anticipated to be similar to the site prior to re-development; however, over time, through the processes of natural plant community succession, the revegetation should approach a density and diversity similar to that of undisturbed areas adjacent to the disturbed land.

5.10.1 Seed Mixtures

The seed mixtures to be used would be determined by seed availability, compatibility with the vegetation of the surrounding areas, the soil and climatic conditions of the area, and by recommendations from the BLM and NMEMNRD. The reclamation success of the previously disturbed areas would be used as a guide in choosing the mixture. Suitable seed materials may be a limiting factor in revegetation of the site. The seed mixes shown in **Table 5-4** are example seed mixes derived from information provided by the NMEMNRD (and the BLM) for revegetation programs in the vicinity of the project. The species included in the list also focus on those that are more readily available. Not all of the species in the immediate vicinity of the project site are readily available from seed suppliers. The list presented herein is for the purposes of reclamation cost estimation and is not intended to represent a final list. The final seed mix would be approved following review of the revegetation test program results and may be modified with approval of the BLM and NMEMNRD.

Table 5-4: Proposed Reclamation Seed Mixes

Species	Application Rate (lbs. PLS/acre)
Drill Seed Mix	
Blue grama (*Bouteloua gracilis*)	0.6
Side-oats grama (*Bouteloua curtipendula*)	1.3
Indian ricegrass (*Oryzopsis hymenoides*)	1.2
New Mexico feathergrass (*Stipa neomexicana*)	1.0
Tobosa grass (*Pleuraphis mutica*)	1.2
Black grama (*Bouteloua eriopoda*)	0.6
Cane bluestem (*Bothriochloa barbinodis*)	1.0
Narrowleaf globemallow (*Sphaeralcea angustifolia*)	0.5
Four-wing saltbush (*Atriplex canescens*)	0.8
Broadcast Seed Mix	
Blue grama (*Bouteloua gracilis*)	0.6
Side-oats grama (*Bouteloua curtipendula*)	1.0
Sand dropseed (*Sporobolus cryptandrus*)	0.5
New Mexico feathergrass (*Stipa neomexicana*)	1.0
Silver bluestem (*Bothriochloa laguroides*)	1.0
Apache plume (*Fallugia paradoxa*)	1.0
Four-wing saltbush (*Atriplex canescens*)	1.0
Blanket flower (*Gaillardia pulchella*)	0.5
Narrowleaf globemallow (*Sphaeralcea angustifolia*)	0.1

5.10.2 Planting Techniques

Seeding would take place immediately after placement of the cover material, depending on when the cover material is put in place. Seeding should take place when summer moisture is available to encourage the warm season grasses. Consequently, soil placement and seeding are planned to occur prior to the monsoon season of July, August, and September. In the event that seeding occurs substantially later than soil placement, any compacted soil areas may require ripping or scarification. If determined necessary, compacted soils would be ripped or scarified to a depth of 6 to 12 inches prior to seeding. Field experience and changes in local precipitation patterns may alter the seeding schedule to other times of the year.

Seeding methods to be utilized at the site would depend on many factors including the topography, soil conditions and seed mixture. Typically, some combination of broadcast seeding, drill seeding and hydro-seeding is used for mine reclamation. It is expected that broadcast seeding, followed by harrowing to bury the seed to the proper depth would be the seeding method of choice. The presence of larger rocks and boulders in the alluvial materials to be used as reclamation cover would decrease the effectiveness of drill seeding and may preclude this method altogether. Alternatively, the presence of some larger rocks and boulders at the soil surface would create and generate micro-sites favorable to the establishment of vegetation. If drill seeding is not utilized, and broadcast seeding is the primary methodology utilized, then the seeding rates shown in **Table 5-4** would need to be summed (i.e. drill component summed to broadcast component), so that the total seeding rate is in the range of 12 to 16 pounds of pure live seed (PLS) per acre, approximately. Hydro-seeding may be used on steep, small areas where larger equipment cannot easily operate.

Mulch may not be required depending on the time of planting and the terrain. If necessary, a protective mulch such as alfalfa pellets or certified weed free straw would be applied. Hydro-mulch may be necessary in areas that required hydro-seeding. If hay mulch is used, it would be mechanically crimped or secured with a chemical tackifier to prevent erosion. Steep slopes may require erosion control matting or netting.

Weed control would be implemented only if necessary. Methods of weed control would be determined upon recommendation from the BLM and/or NMEMNRD.

5.11 Revegetation Success

Revegetation success would be determined by monitoring the vegetation parameters of ground cover, productivity, woody plant density, and plant species diversity. The results of these parameters in reclaimed areas would be compared to the same parameters in reference areas (i.e. control or undisturbed sites) or to an agreed upon revegetation standard. The reference area and revegetation standards would be based on the research program discussed in Section 5.12, and would be established through discussion by the BLM, NMEMNRD, and NMCC. The research program would be ongoing, including the collection of vegetation data. The collected vegetation data, stratified across the various plant communities situated within the permitted boundaries, would be carefully

evaluated. The collected vegetation data would eventually function as a guide towards determining ecologically suitable success standards.

Technical guidance procedures published by the NMEMNRD were utilized in the development of a sampling and analysis plan. There are a wide variety of standard and classic sources for field sampling methods in plant ecology (Bonham 1989; Barbour, Burk, and Pitts 1980), including references cited in the technical guidance procedures developed by the NMEMNRD. Any variations of or additions to the vegetation monitoring techniques would go through approval with NMEMNRD and/or BLM as needed. As may be appropriate and necessary to meet NMEMNRD requirements, herbaceous cover and productivity would be established within 90 percent of the reference area with a 90-percent statistical confidence level. Woody species (and at Copper Flat these are essentially all shrubs) would be established to the approved density with an 80 percent confidence level as defined by NMEMNRD. Diversity would be compared to existing reclaimed and/or reference areas relative to the physical environment of the areas to be reclaimed.

Observations would be conducted once per year at approximately the same time each year. Two seasons of successfully attaining the revegetation criteria would determine success of the revegetation program. In the event that an area does not meet the revegetation goals (or criteria), the area would be investigated and steps taken to correct the problem.

Analysis of the revegetation efforts on the north cell of the tailings impoundment demonstrates the effectiveness of the methods proposed here including the thickness of growth media used in this area should meet the objective of developing a self sustaining ecosystem.

5.12 Reclamation Research

As part of the reclamation plan, NMCC would conduct a revegetation test program to determine the most effective methods to meet revegetation standards as defined in their reclamation plan. The program would be flexible enough to allow modifications of proposed methodologies and to test new techniques. Conceptually, the test revegetation program would include test plots designed to evaluate different types and thicknesses of cover material, seed mixes, planting techniques, use of clean tailings fines to enhance water retention of soils, soil amendments and mulches. The program would also include test plots on slopes of different grades and aspects.

In addition, NMCC intends to maximize the amount of concurrent reclamation at the site. This would allow larger-scale testing of regrading, reclamation cover placement and revegetation techniques. The outer face of each raise of the tailings impoundment would be reclaimed by placement of a layer of alluvial cover up to eight inches thick followed by revegetation. It is also anticipated that the west and north waste rock disposal areas and portions of the east and south disposal areas would be completed prior to completion of mining, which would allow for concurrent reclamation of these areas.

5.13 Concurrent Reclamation

Because contemporaneous reclamation reduces erosion, provides early impact mitigation, limits costs and reduces final reclamation work, NMCC is committed to maximize this type of reclamation at the Copper Flat Project. Some of the Project facilities would be constructed in their final configuration. Others, such as individual lifts of the waste rock disposal areas and possibly some roads would be decommissioned prior to final mine closure. Areas such as these would be reclaimed concurrently with the active mining operation where feasible. Descriptions of design features which are intended to facilitate contemporaneous reclamation for specific project components are given below in Section 5.14.

5.14 Interim Reclamation

There is a possibility that continuous, full-scale production might be interrupted for short periods in response to economic considerations or unforeseen circumstances. In this event, interim reclamation would be initiated. Interim reclamation is outlined below.

- Rights-of-Way: The power lines and water pipeline would be inspected regularly and maintained as necessary. None of the facilities would be altered or removed. The main access road would receive regular maintenance. The internal roads would receive minimal maintenance.
- Pit: The pit area would be protected by fencing with a locked access gate. Monitoring of pit water would be ongoing.
- Tailings Facility: The tailings impoundment would be retained for potential future development. Limited care and maintenance of the reclaimed embankment face would be performed as necessary to continue stabilization of the area.
- Diversion Ditches: Diversion ditches would be inspected and maintained as necessary. Surface water runoff would be managed in accordance with the site NPDES permit requirements.
- Buildings: The process buildings, equipment and support facilities would be guarded and maintained as necessary. None of the buildings would be destroyed or modified.

5.15 Interim Management Plan

In accordance with 43 CFR § 3809.401(b)(5), NMCC has prepared the following *Interim Management Plan* to manage the project area during periods of temporary closure (including periods of seasonal closure, if necessary) to prevent unnecessary or undue degradation, and includes:

- Measures to stabilize excavations and workings;
- Measures to isolate and control toxic or deleterious materials;
- Provisions for the storage or removal of equipment, supplies, and structures;

- Measures to maintain the project area in a safe and clean condition;
- Plans for monitoring site conditions during periods of non-operation; and,
- A schedule of anticipated periods of temporary closure during which you would implement the interim management plan, including provisions for notifying BLM of unplanned or extended temporary closures.

This Interim Management Plan (a.k.a., temporary closure plan) is necessarily general due to the lack of detailed design information at the present time, and would be updated as necessary during the preparation of the mine feasibility study and NEPA process. Any updates would be submitted to BLM prior to construction.

5.15.1 Schedule of Anticipated Periods of Temporary Closure

The standard operating schedules at the Copper Flat Project would be 24 hours a day, 365 days a year for the mining activities and processing circuits. No temporary or interim closures of the facility are currently planned. However, it is possible that, due to mechanical or technical difficulties, unfavorable economic conditions, litigation or other unforeseen events, mining and processing facilities may have to be temporarily closed. In the event of an unplanned temporary closure, the following plan would be implemented:

- The BLM and MMD would be notified within 30 days of the temporary closure of the flotation mill and/or the concentrate circuit. This notification would include a description of the procedures and controls that have been or would be initiated to maintain the process components during the temporary closure period.
- NMCC would supply BLM/MMD with a list of supervisory personnel who would oversee the mine facility during the temporary closure period. This list also would include the number of support staff required in each department to maintain the facility during the closure period. Standard security procedures would remain in place for the duration of the temporary closure period. Access to the site would be allowed for appropriate regulatory agency personnel
- If the interim closure period exceeds 90 days, NMCC would begin to evaluate procedures required to carry out a permanent closure of the process components. These procedures would be reviewed and approved by the BLM and MMD. NMCC may petition the BLM and MMD for an extension that would delay permanent closure.

5.15.2 Measures to Stabilize Excavations and Workings

No additional measures would be necessary to stabilize excavations and workings during an unplanned temporary closure. Pit dewatering activities may cease during the temporary closure period, in which case, all dewatering pumps, pipelines and water storage tanks would be drained.

Interim reclamation procedures would be implemented as necessary to stabilize disturbed sites during the temporary closure period. These procedures would be coordinated with the BLM and the MMD.

Adequate storage capacity would be maintained in the process components to accommodate run-off resulting from the design storm event.

5.15.3 Measures to Isolate or Control Toxic or Deleterious Materials

NMCC would follow the waste rock management procedures described in the Plan of Operations to isolate waste rock as necessary during unplanned temporary closure. Explosives would continue to be stored and handled according to federal and state regulations. Hazardous materials would continue to be stored, handled and disposed of according to federal and state regulations.

5.15.4 Storage or Removal of Equipment, Supplies, and Structures

In the event of a temporary closure, it is anticipated that equipment, supplies and structures would not be removed or placed into storage. Some mobile equipment or bulk commodities may be relocated into buildings or covered with tarps to isolate them from the weather, depending on the anticipated duration of the temporary closure. In addition, the following steps would be taken:

- Additional reagents would not be introduced into any process component during the temporary unplanned closure period. Process piping and pumps would be drained if the process circuits are shut down. Stored equipment would be clearly identified as having contained process solutions.
- Any mine equipment remaining in operation during the temporary closure, including haul trucks, shovels, loaders, drills and personal vehicles would continue to be maintained according to standard company procedure.
- Following any temporary closure period, the integrity of the entire fluid management system would be evaluated before start-up is initiated. Solution tanks, pumps and piping would be visually inspected and repaired as necessary. The mineral processing circuit would be charged with process solution and visually inspected for evidence of leaks. Mine equipment would be inspected for compliance with appropriate federal and state mining regulations before mining activities re-commence. Pit dewatering would resume as soon as possible. Mining activities should not be affected by a temporary closure. The mine dewatering system would be visually inspected and repaired as necessary.

5.15.5 Monitoring During Periods of Non-Operation

All provisions of this plan and all other regulatory and permitting requirements would continue to be met during the temporary closure period. This would include all monitoring, notifications and reports submittal. Site monitoring and monitoring of leak detection systems for vessels and piping containing process solution would continue throughout the temporary closure period.

5.16 Facility-Specific Reclamation

5.16.1 Mine Pit

In 1982, approximately 3 million tons of overburden material was stripped and over 1.2 million tons of ore were mined from the open pit. Mining was initiated at the "5600" bench level and excavation had commenced on the "5380" bench at the time of shutdown.

Mining of the ore body would continue by a 30-foot high, multiple bench, open pit method. Under the Proposed Action, the pit would eventually be 2500 feet × 2500 feet) and would reach an ultimate depth of 900 feet at an elevation of 4,720 feet. The working slope of the pit walls would average approximately 1H:1V. Safety benches would remain at 80-foot intervals and the overall final pit slope would be about 1.1H:1.0V.

NMCC does not propose to backfill the pit because the backfilling operation would not allow sequential mining of the deposit and it would be economically unfeasible to backfill the pit following closure of the operation. The primary reason that post-closure backfilling is uneconomic is the time required to backfill the pit following plant closure. In the case of Copper Flat, this would require up to seven years during which no income would be realized. Furthermore, backfilling the pit would cover a mineral resource which could become economic with an increase in metal prices or the development of new processing technologies, and thus hinder future mineral exploration and mining of useful minerals.

Ground water inflow formed a lake in the former pit. The current water level is an elevation of about 5,420 feet; therefore, pit dewatering would again be necessary during operations. Following cessation of dewatering activities, a lake would again form in the pit. The post-closure pit water elevation is estimated to be at an elevation of approximately 5,250 feet. The depth of the lake would fluctuate a few feet depending on precipitation and the evaporation rate. Refilling would proceed over a number of years (SRK, 1995).

Possible post-closure uses for the pit include a water reservoir for agricultural and grazing purposes. Based on studies completed for Alta’s permitting processes of the mid- to late-1990s, pit water quality of the current lake, and modeling of post-closure pit water quality suggest that post-closure water quality should meet New Mexico surface water standards for these uses (SRK, 1995), and possibly also be suitable for other existing cultural uses as well as yet to be considered and otherwise unknown cultural uses. New studies are underway to build on this past work and evaluations.

Reclamation of the pit during operations would be limited to erosion control. At closure stable pit walls would be left in place, and unstable pit walls would be stabilized by blasting or other safe methods. Where safe, alluvial material would be placed on the benches above the projected water level, and the benches seeded. Roads and safety benches would be ripped and water barred to control surface water runoff. Disturbed areas around and adjacent to the pit would be covered with alluvial material and revegetated.

The ramp would be graded or ramps placed at different locations to allow escape routes for wildlife. The pit area and highwalls would be appropriately barricaded with physical barriers or fences and posted according to MSHA and New Mexico Mine Inspectors Office regulations. Access would be limited by a locked gate and the access road blocked with a physical barricade.

5.16.2 Waste Rock Disposal Areas and Low-Grade Stockpile

The primary waste rock disposal area for the Proposed Action is located east-northeast of the mill site on the east side of Animas Peak (**Figure 3-1**). Two smaller waste rock disposal areas would be located adjacent to the pit.

The present height of the east waste rock disposal area is at an elevation of approximately 5,560 feet. By the end of mine life, an upper lift would be developed at an elevation of 5,620 feet and a lower lift would be developed at an elevation of 5,290 feet. The west and north waste rock disposal piles and lean ore stockpile would be constructed by expanding the existing piles from their current elevation and constructing additional lifts at 50-foot intervals. Total waste material contained in the disposal areas at the end of the expected life of the property is estimated to be approximately 51 million tons.

The waste rock disposal areas would be regraded and reclaimed to blend into the surrounding topography to the extent practicable. Three types of waste rock have been identified at the site: oxidized waste rock, transitional waste rock and unoxidized waste rock (SRK, 1995). The potential for acid generation from the bulk of the waste materials is low, primarily due to the relatively low regional precipitation, and except due to exceptional summer storms the virtual lack of any off site runoff and finally-the rapid evaporation and adsorption of any available moisture. However, reclamation and surface water management measures designed for the partially oxidized materials would be used to promote runoff and reduce infiltration for all material types. Horizontal surfaces would be regraded and contoured to reduce infiltration of water and provide positive drainage to sediment collection points. Care would be taken to contour these areas to reduce the potential for ponding and infiltration. This would reduce the potential for oxidation within each disposal facility and the leaching of metals and residual oxidation products.

Partially oxidized waste rock represents the majority of the material in the existing West and North waste rock disposal areas. Testing of this material indicates it can produce acid in the presence of water (SRK, 1995). The majority of waste rock exposed on the East disposal area is unoxidized material.

Unoxidized quartz monzonite would comprise the bulk of future waste rock. Although this material has the potential to generate acid, both field observations and test results indicated that this material is, at most, slowly reactive (SRK, 1995). Transitional zone materials represent a limited portion of the total waste rock volume. The potential for acid generation from these materials is high, requiring special waste management, including, but not necessarily limited to encapsulation and/or blending with alkaline materials. Transitional waste rock would be segregated from the unoxidized waste rock

by visual inspection and field testing, if necessary, during mining and disposed of in the West and North disposal areas. NMCC is currently in the process of updating the geochemical characterization of all of these materials in order to more accurately predict their long-term behavior and prescribe suitable ARD mitigation measures, as necessary.

Although the bulk of the waste rock material does not indicate a high risk of environmental degradation, all of the waste rock disposal areas and any lean ore remaining in the lean ore pile would be reclaimed in a manner which has been determined to reduce infiltration and to alleviate the long term risk of acid generation and metals leaching (SRK, 1995). Following regrading, the surface of the disposal areas would be compacted with earthmoving equipment and covered with a layer of alluvial material and revegetated.

A study to determine the effectiveness of various cover materials to minimize infiltration into the waste rock disposal areas indicated that a layer 12 inches thick should reduce infiltration to negligible levels (SRK, 1995). The study utilized computer hydrologic modeling using default and calculated soil properties and synthetically generated climatic data for nearby locations. The effectiveness of the cover materials would be re-evaluated with site specific soil properties and climatological data during construction and operations to determine the optimum cost effective cover materials for the waste rock disposal areas.

During operations, the disposal area would be constructed in 50 foot lifts to facilitate regrading during reclamation such that slope faces do not exceed 2.5H:1V. Benches would be established at the existing lift elevations and, if indicated by the test revegetation program and concurrent reclamation, at intermediate intervals to reduce erosion. As each lift is completed, any portion not needed for access to other lifts would be regraded, covered and revegetated as soon as practicable.

To enhance revegetation, reduce erosion and minimize surface the waste rock disposal areas would be covered with suitable reclamation materials and revegetated contemporaneously with operations. This material would be roughened to reduce surface flow velocities and minimize erosion and sediment loss.

During operations, surface run-off from Animas Peak would be diverted around the disposal area to prevent surface run-on and infiltration into the waste rock. Diversion structures would be revegetated and/or protected by riprap to reduce erosion and left in place following closure.

The lean ore pad is located immediately southeast of the open pit and would include about 11 million tons of rock assaying 0.18 percent copper. Reclamation of this area would depend on the fate of this stock pile. If the low-grade stockpile is milled by the end of mine life, the pad area would be ripped, contoured for drainage control, covered with growth media and revegetated. If the low-grade stockpile remains following closure, the stockpile would be reclaimed in the same manner as the waste rock disposal areas. It would be regraded to slopes of less than 2.5H:1V and shaped to enhance run-off and prevent infiltration and ponding. The surface would be compacted with earth moving equipment, covered with a layer of alluvial material and the surface revegetated.

5.16.3 Plant Site

The plant site would occupy an area of approximately 78 acres and would be located between the open pit and the tailings impoundment area. The sulfide flotation plant would be similar to that constructed at the site for the previous operation. The plant facilities would be constructed at the site of the original plant, and it is expected that most of the original foundations would be used for the facilities, with adjustments being made based on economic considerations. All buildings would be prefabricated, standard, rigid-framed structures. Prior to construction, the material covering the foundations would be stripped and salvaged for future reclamation.

The following primary structures would be located at the plant site:

- Primary Crusher Installation,
- Concentrator Building,
- Reagent Building (60' × 72'),
- Electrical Substation,
- Administration Building (60' × 120' × 12'),
- Mine Office/Change House,
- Assay and Laboratory Offices (32' × 126'),
- Truck Shop/Warehouse Building,
- Small Vehicle Shop, and
- Gate House Building (8' × 12').

At closure, all surface facilities, equipment and buildings would be removed from the area. The concrete building slabs, footings and foundations would be broken and covered with waste rock material. All fuel tanks, reagent storage facilities would be removed from the site according to applicable federal and state laws. The general surface area would be shaped and contoured for surface drainage control, and covered with a minimum of 6 inches of stockpiled alluvium/growth media to conform to the surrounding topography to the extent practicable. Revegetation would occur as discussed in Section 5.10.

The tailings thickener and tailings reclaim pond would be backfilled regraded to minimize ponding prior to placement of alluvial material/growth media and revegetation. The stormwater collection pond is located adjacent to Greyback Wash east of the plant area. This pond, currently backfilled, is believed to be the source of water which created the riparian zone in Greyback Wash adjacent to it. NMCC would endeavor to maintain the riparian zone during operations when the stormwater pond would be used collect stormwater runoff by diverting water from the freshwater supply system. At closure, this pond would remain open with and the discharge pipe left in place in an attempt to recreate the current near surface hydrologic conditions which are supplying water to the riparian zone. The land bridge which conveys the tailings pipeline would also be left in place because this feature may be a contributing factor to the development of the riparian zone. The slopes of the land bridge would be stabilized and the top revegetated during reclamation.

5.16.4 Tailings Impoundment

A tailings impoundment located southeast of the plant site was designed to hold a total of 95 million tons of tailings (including tailings from 11 million tons of low-grade ore). Closure of the tailings impoundment would include:

- Final grading of embankment outslopes to establish erosion controls and controlled surface water drainage (best management practices);
- Placement of a soil or rock cover and revegetation of the embankment outslope;
- Placement of riprap and erosion controls in embankment surface water drainage facilities;
- Regrading or depositional modification of the impoundment surface to promote drainage to a permanent engineered spillway;
- Placement and vegetation of a soil cover over the tailings surface;
- Armoring of surface drainage channels and implementation of best management practices for erosion control; and
- Management of underdrainage.

Final grading of the impoundment surface can be accomplished with earthmoving equipment, or through modification of tailings disposal patterns during the final years of operation. Tailings discharge from selected locations can be used to relocate the supernatant pool to a location adjacent to the post-closure spillway, thereby reducing grading requirements and limiting earthmoving operations in areas where working conditions are expected to be difficult due to the presence of soft and saturated tailings. At the location of the spillway [see Drawing 9 in **Appendix D** (Golder, 2010)], a bedrock foundation is anticipated. If the spillway channel is erodible, grouted riprap or other erosion controls would be applied.

Consolidation seepage into the underdrain system can be anticipated to continue at declining rates for an indefinite period following the cessation of tailings disposal operations. Underdrainage would be pumped from the underdrain collection pond to the surface of the tailings impoundment where it can be evaporated. When underdrainage is reduced to an acceptably low flow rate, the underdrain pipes beneath the embankment can be sealed with grout and the underdrain collection pond can be decommissioned.

5.16.5 Ancillary Project Facilities

In general, all surface pipelines, poles, and commercial signage would be removed. Buried pipelines and electrical conduits would be left in place.

5.16.5.1 *Fences*

The tailings and mine area would be fenced to discourage access by people, wildlife and cattle. Existing fences may be left in place depending on the location and purpose. Fences used to restrict

access to potentially hazardous areas would remain in place. Other fences may remain to protect revegetation efforts. The BLM would determine the fate of fences on public lands. The remaining fences would be removed for salvage.

To prevent damage to newly seeded and revegetation areas, these areas would be protected by fencing or other appropriate measures for a period of time until revegetation is successful. It may be necessary to control small mammals as well as deer and domestic livestock. All fencing on public lands would be constructed to meet BLM requirements.

5.16.5.2 *Water Tanks*

The fresh water and process water tanks would be removed, their foundations buried in place and the sidehill cuts recontoured to approximate original topography. Following recontouring, the areas would have alluvial material placed up to 6 inches thick if the replaced fill material would not support vegetation. The areas would then be revegetated as described in Section 5.10.

5.16.5.3 *Roads*

A portion of the access road has been deeded to Sierra County and provides access through the mine site to private and public property adjacent to the west boundary of the Project. From the point where the mine access road leaves the county road north of the tailings impoundment, it would be narrowed to a standard two-lane road with a running surface approximately 30 feet wide. One culvert, located where the road crosses Greyback Wash would be left in place.

Prior to final closure, the State and BLM would determine which auxiliary roads and haul roads would be left intact. At this time, at a minimum, the road to the water tanks, haul roads, waste disposal access roads are expected to undergo reclamation.

Roads to be reclaimed would be recontoured to approximate original topography if constructed on sidehills or contoured and ripped if constructed in flat areas. Typical reclaimed cross-sections of the different road types are shown on **Figure 5-3**. Water bars would be constructed to reduce erosion. Recontoured areas would be covered with up to 6 inches of alluvial material if replace fill material would not support vegetation and revegetated as describe in Section 5.10.

5.16.5.4 *Electrical Power*

Power for the Project would be furnished by means of existing overhead power lines. The overhead lines would be removed from the mill site and disconnected from the 115kV line owned by Sierra Electrical Cooperative by removing the wires of the last span of the line. Pumping stations and electrical substations on the site would be removed, if no other post-closure land use is identified and approved. The disturbance associated with removal would be reclaimed by regrading and seeding. If renewable energy facilities are deployed at specific buildings, these will be removed and associated disturbances regarded and reseeded.

The existing 25 kV line that provides power to the production wells, booster stations on the fresh water pipeline and the reclaim water pump stations at the tailings dam would remain in place. Sierra Electric owns this power line and is responsible for maintenance.

5.16.5.5 *Water Supply*

Water would be supplied to the mine from four production wells located about seven miles east of the plant site. A 20-inch welded steel pipeline transports the water to the mine and is buried at a minimum depth of 2 feet from the well field to the point of entry to the Project area.

The buried pipeline is owned by the BLM and would remain in place. The production wells would remain in a condition suitable for other uses. All roads, power lines and foundations for the production wells are in place. No additional disturbance would occur during the project and the well area would be left as it currently exists after closure of the mine.

5.16.5.6 *Sanitary Solid Waste Disposal*

At closure the septic tanks and leach fields would be decommissioned. All solid wastes remaining on the site would be removed off-site for proper disposal. If a private landfill is permitted for on-site disposal of solid waste, the landfill would be closed according to NMED requirements.

5.17 Estimated Reclamation Costs

A reclamation bond is required by the BLM and State of New Mexico to guarantee the completion of Project reclamation. Following regulatory review of the proposed plan of operations and reclamation techniques presented herein, NMCC would prepare, *at a time specified by the BLM* [43 CFR § 3809.401(d)], a *detailed estimate of the cost to fully reclaim the operations* as required by 43 CFR § 3809.552. The estimated costs would be based on projected actual costs to reclaim the site assuming that all reclamation would occur following operations without the benefit of contemporaneous reclamation. Prior to commencement of operations, financial assurance in the amount of the estimated costs to reclaim the disturbance which would occur during the first five years of operations would be posted with the BLM.

6 Acknowledgment

I certify that I have personally examined and am familiar with the information submitted herein, and based on my inquiry of those individuals responsible for obtaining the information; I believe the submitted information is true, accurate, and complete.

Barrett Sleeman, President
New Mexico Copper Corporation

December 22, 2010
Date

7 Bibliography

Adrian Brown Consultants (ABC). 1996. *Copper Flat project hydrology impact evaluation report.*

Adrian Brown Consultants (ABC). (1997). Copper Flat hydrology impact evaluation post-hearing submittal exhibits, including revised appendices O, F, and L: Report 1356A.970326.

Adrian Brown Consultants (ABC). (1998b). Hydrologic impact evaluation for the proposed action, Copper Flat project: Report 1356A.981219. Prepared for Alta Gold Co., December 19, 1998.

Air Sciences Inc. (1995). *Baseline Monitoring Data for the Copper Flat Project.*

Barbour, M.G., J.H. Burk, and W.D. Pitts. (1980). Terrestrial Plant Ecology. The Benjamin/Cummings Publishing Company, Inc. Menlo Park, California.

Biota Information System of New Mexico (BISON-M). (1995). Biological database for New Mexico. The New Mexico Department of Game and Fish in cooperation with the Bureau of Land Management, U.S. Fish and Wildlife Service, U.S. Army Corps of Engineers, Bureau of Reclamation, U.S. Forest Service, and the University of New Mexico. Bonham, C.D. (1989). Measurements for Terrestrial Vegetation. John Wiley and Sons, New York.

Bureau of Land Management, Las Cruces. (1978). *Assessment Record on Quintana Minerals Corporation's Proposed Open Pit Copper Mine at Copper Flat.* Las Cruces.

Bureau of Land Management, Las Cruces. (1996). *Copper Flat Project Draft Environmental Impact Statement.* Las Cruces.

Bureau of Land Management, Las Cruces. (1996). *Biological Assessment for the Alta Gold Company Copper Flat Project.* Las Cruces: BLM, Las Cruces.

BLM, Las Cruces, New Mexico. (1993). *Environmental Assessment for Re-establishing the Copper Mine, Copper Flat, Mexico.*

Bureau of Land Management. (1999). Preliminary Final Environmental Impact Statement, Copper Flat Project: Las Cruces, N. Mex., U.S. Department of the Interior, 491 p. Prepared by ENSR, Fort Collins, Colo.

Davie, W., Jr., and Spiegel, Z. (1967). Las Animas Creek hydrographic survey report, geology and water resources of Las Animas Creek and vicinity, Sierra County, New Mexico: New Mexico State Engineering Report.Dunn, P. (1982). *Advances in Geology of the Porphry copper Deposites, Southwester North America.* Tucson: the University of Arizona Press.

Dunn, P. (1984). Geologic studies during the development of the Copper Flat porphyry deposit: Mining Engineering, February, 1984.Evaskovich, J., & Higgins, H. (1991). *A Class III Cultural Resources Inventory for a Proposed Copper Mine Expansion.* Mariah Associates, Inc.

Fowler, L.L. (1982). Brecciation, alteration, and mineralization at the Copper Flat porphyry copper deposit, Hillsboro, New Mexico: University of Arizona, Tucson, M.S. thesis, 133 p.Glover, F. A. (1977). *Environmental Assessment Report, Copper Flat Mine Development, Copper Flat, New Mexico.*

Goff. (1998).

Golder Associates, Inc. (2010). Copper Flat Project: Conceptual Design Report.

Greene, D.K., and Halpenny, L.C. (1976). Report on development of ground-water supply for Quintana Minerals Corporation Copper Flat Project, Hillsboro, New Mexico: Tucson, Water Development Corporation, 32 p.

Harley, G.T. (1934). The geology and ore deposits of Sierra County, New Mexico: Socorro, N. Mex., New Mexico School of Mines Bulletin 10.

Hawley, J.W. and Kennedy, J.F. (2004). Creation of a Digital Hydrogeologic Framework Model of the Mesilla Basin and Southern Jornada Del Muerto basin. WRRI Technical Completion report No. 332.

Hawley, J.W., Kennedy, J.F., Ortiz, M., and Carrasco, S. (2005). Digital Hydrogeologic Framework Model of the Rincon Valley and Adjacent areas of Dona Ana, Sierra, and Luna Counties, NM: Addendum to the Creation of a Digital Hydrogeologic Framework Model of the Mesilla Basin and Southern Jornada del Muerto Basin, New Mexico Water Resources Research Institute, New Mexico State University, Technical Report No. 332, June 2004, 12 p.

Hedlund, D.C. (1974). Age and structural setting of base-metal mineralization in the Hillsboro-San Lorenzo area, southwestern New Mexico *in* Siemers, C.R., Woodward, L.A., and Callender, J.F., eds., Silver Anniversary Guidebook; Ghost Ranch; North-Central New Mexico: New Mexico Geological Society Guidebook 25, p. 378–379.

Hydro Resources, Inc. (2002). Copper Flat: Albuquerque, N. Mex., Hydro Resources, Inc.

IHICS. (1995). Integrated Habitat Inventory Classification System Database.

Intera. (2010). Sampling and Analysis Plan for Copper Flat Mine. Prepared for New Mexico Copper Corporation. Submitted to Mining and Minerals Division of the New Mexico Energy, Minerals and Natural Resources Department. September 2010.

Johnson, R. D. (1996). *Copper Flat Revegetation Information - Technical Memo.*

Kelley, S.A., and Chapin, C.E. (1997). Cooling histories of mountain ranges in the southern Rio Grande rift based on apatite fission-track analysis—A reconnaissance survey: New Mexico Geology, v. 19, no. 1, p. 1–14.

Locke, Augustus. (1926). The formation of certain ore bodies by mineralization stoping: Economic Geology, v.21, p. 431-453.

Lozinsky, R.P. and J.W. Hawley. (1986). The Palomas Formation of south-central New Mexico -- a formal definition. New Mexico Geology. 8. 4, p: 73-82.

McLemore, V.T., Munroe, E.A., Heizler, M.T., McKee, C. (2000). Geology and evolution of the mineral deposits in the Hillsboro District, Sierra County, New Mexico *in* Geology and Ore Deposits 2000, The Great Basin and Beyond: Geological Society of Nevada, Program with abstracts, p. 63.

Minton. (1961).

Murray, C. R. (1959). Ground-water conditions in the nonthermal artesian-water basin south of Hot Springs, Sierra County, New Mexico: New Mexico State Engineering Technical Report 10.

Natural Resources Conservation Service (NRCS). (1984). Soil Survey of Sierra County Area, New Mexico. Natural Resources Conservation Service (NRCS). (2010). Ecological site descriptions, accessed online at: http://esis.sc.egov.usda.gov/ESIS/About.aspx.

Neher, R.E. (1984). Soil survey of Sierra County area, New Mexico: Washington, DC, U.S. Department of Agriculture, Soil Conservation Service, 80 p.

Newcomer, R.W., and Finch, S.T. (1993). Water quality and impacts of proposed mine and mill, Copper Flat Mine site, Sierra County, New Mexico, 30 p. Prepared for Gold Express Corporation.

Newcomer, R. W. Jr., Shomaker, J.W., and Finch, S.T., Jr. (1993). Hydrologic assessment, Copper Flat project, Sierra County, New Mexico. Prepared for Gold Express Corporation.

New Mexico Environment Department Groundwater Quality Bureau (NMED GWQB). (2008). Letter to Mr. George Lotspeich regarding Abatement plan required at Copper Flat Mine site, DP-1, August 20, 2 p.

Norman, D.I., Kyle, P.R., and Baron, C. (1989). Analysis of trace elements including rare earth elements in fluid inclusion liquids: Economic Geology, v.84, p. 162-166.

Olendorff, R.R., A.D. Miller, & R.N. Lehman. (1981). *Suggested Practices for Raptor Protection on Power Lines: The State of the Art in 1981*. Raptor Research Report No. 4, Raptor Research Foundation, Inc.

Phillips, W.J. (1973). Mechanical effects of retrograde boiling and its probable importance in the formation of some porphyry ore deposits: Institution of Mining Metallurgy Transactions, Sec. B, v. 82, p. 90-98.

Raugust, J.S. (2003). The natural defences of Copper Flat, Sierra County, New Mexico: New Mexico Bureau of Geology and Mineral Resources Open-file report 475, Socorro, N. Mex., New Mexico Institute of Mining and Technology.

Richards, J.P. (2003). Tectono-magmatic precursors for geophysical data over a copper gold porphyry Cu-(Mo-Au) deposit formation, *in* Journal of Economic Geology, v. 96, p. 1419–1431.

Seaber, P.R., Kapinos, F.P., and Knapp, G.L. (1987). Hydrologic unit maps: U.S. Geological Survey Water-Supply Paper 2294, 63 p.

Seager, W.R. and J.W. Hawley. (1973). Geology of Rincon quadrangle, New Mexico. New Mexico Bureau of Mines and Mineral Resources Bulletin 102. 56 p.

Seager, W.R., Shafiqullah, M., Hawley, J.W., and Marvin, R.F. (1984). New K-Ar dates from basalts and the evolution of the Southern Rio Grande Rift: Geological Society of America Bulletin, v. 95, p.87-99.Sechrist, & Laumbach. (1995). *Archeological Surveys of Areas in the Copper Flat Project Area Near Hillsboro, Sierra County, New Mexico.* Human Systems Research.

Segerstrom, K. and Antweiler, J.C., III. (1975). Placer-gold deposits of the Las Animas District, Sierra County, New Mexico: USGS OFR 75-206.

Sergent, Hauskins, and Beckwith (SHB). (1980). Geotechnical and design development report, tailings dam and disposal area, Quintana Minerals Corporation, Copper Flat Project, Golddust, New Mexico. Technical report prepared for Quintana Minerals.Shomaker, J. W., & Newcomer, B. (1993). *Hydrologic Assessment, Copper Flat Project, Sierra County, New Mexico.*

Sierra Soil and Water Conservation District. (1990). Range Condition Worksheets.

Soil Survey Staff. (1999). Soil taxonomy, a basic system of soil classification for making and interpreting soil surveys (2d ed.): Washington, D.C., U.S. Department of Agriculture Natural Resources Conservation Service Agriculture Handbook 436, U.S. Government Printing Office.SRK Consulting. (1995). *Copper Flat Hydrogeologic Studies.* Reno.

SRK Consulting. (1996). Copper Flat Mine, Mining permit application, v. 1, p. 2-12.

SRK Consulting. (1997a). Copper Flat post-hearing submittal exhibits: Steffen Robertson and Kirsten, Inc.

SRK Consulting. (1997b). Copper Flat Mine-Compilation of pit lake studies: Steffen Robertson and Kirsten, Inc., Project 68610. Prepared for Alta Gold Co.

SRK Consulting. (2010a). Preliminary Draft Copper Flat Plan of Operations, New Mexico Copper Corporation: SRK Consulting, Reno, Nevada

SRK Consulting. (2010b). NI-43-101 Preliminary Assessment, THEMAC Resources Group Limited, Copper Flat Project, Sierra County, New Mexico: Lakewood, Colo. Prepared by SRK Consulting for THEMAC Resource Group Limited, June 30, 2010.Stinnett, K. (1991). *Biological Assessment for Gold Express Corporation's Copper Flat Mining and Milling Operation, Sierra County, New Mexico.*

Titley, S.R. (1982). Geologic setting of porphyry copper deposits, southeastern Arizona, *in* Titley, S.R., ed., Advances in geology of the porphyry copper deposits, pp 37-58.Wilson, C.A., Orr, C.A, White, R.R., and Roybal, R.G. (1981). Water resources of the Rincon and Mesilla Valleys and adjacent areas, New Mexico: New Mexico State Engineering Technical Report 43.





NORTH

DESIGN: -	DRAWN: -	REVIEWED: -	
CHECKED: -	APPROVED: -	DATE: 12/2/2010	
FILE NAME PoO_Fig1-01_Location_JQG_20101202			

NEW MEXICO COPPER CORPORATION

COPPER FLAT MINE

PROJECT LOCATION

DRAWING NO. **FIGURE 1-1**	SHEET 1 OF 28	REVISION NO. **A**
JOB NO. **191000-03**		

Path: H:\Copper_Flat\New Mexico Copper Corp\191000_03_Copper_Flat_Permitting\040_Drafting\20101115\PoO_Fig1-01_Location_JQG_20101202.mxd



Figure 1-2
Regional Location
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\1_introduction\1-1_SiteLocationMap.mxd 07/22/2010



EXPLANATION

Public Land | Mine Boundary | Disturbance By Previous Operators (989 acres)

IF THE ABOVE BAR DOES NOT SCALE 1 INCH, THE DRAWING SCALE IS ALTERED

DESIGN: -	DRAWN: -	REVIEWED: -	
CHECKED: -	APPROVED: -	DATE: 12/1/2010	
FILE NAME: PoO_Fig2-01_Land_JQG_20101123			

NEW MEXICO COPPER CORPORATION

COPPER FLAT MINE

LAND STATUS AND EXISTING DISTURBANCE

DRAWING NO. FIGURE 2-1	SHEET 3 OF 28	REVISION NO. A
JOB NO. 191000-03		

Path: H:\Copper_Flat\New Mexico Copper Corp\191000_03_Copper_Flat_Permitting\040_Drafting\20101115\PoO_Fig2-01_Land_JQG_20101123.mxd



EXPLANATION

Public | Plant Facilities | Waste Rock | Tailings | Pit | Diversion | Access Road
Mine Boundary | Pond | Topsoil Stockpile | Ore Stockpile | Haul Road | Ancillary

IF THE ABOVE BAR DOES NOT SCALE 1 INCH, THE DRAWING SCALE IS ALTERED

DESIGN: -	DRAWN: -	REVIEWED: -	
CHECKED: -	APPROVED: -	DATE: 12/1/2010	
FILE NAME: PoO_Fig3-01_PropFacilities_JQG_20101123			

NEW MEXICO COPPER CORPORATION

COPPER FLAT MINE

DRAWING TITLE: **PROPOSED FACILITY LAYOUT**

DRAWING NO.	SHEET	REVISION NO.
FIGURE 3-1	4 OF 28	A
JOB NO. 191000-03		

Path: H:\Copper_Flat\New Mexico Copper Corp\191000_03_Copper_Flat_Permitting\040_Drafting\20101115\PoO_Fig3-01_PropFacilities_JQG_20101123.mxd

DV-03
6.1 ac
AN-06
2.4 ac
AN-10
3.5 ac
WRD-03
32.3 ac
WRD-01
2.6 ac
AN-07
70.7 ac
WRD-02
18.4 ac
SEDIMENT
COLLECITON
PONDS (5)
FRESH
WATER
STORAGE
AN-03
3 ac
WRD-04
123.2 ac
GM-01
3.9 ac
PIT-01
117.9 ac
STKP-01
33.2 ac
AN-09
69.2 ac
AN-01
43.9 ac
TAILINGS
THICKNER
MILL
MINE
SHOP
ADMIN
BUILDING
DV-01
4.6 ac
DV-02
35.8 ac
AN-12
6.1 ac
HR-01
36.6 ac
GM-02
10 ac
AN-04
11.2 ac
GM-03
13.4 ac
AN-02
16.7 ac
RD-01
10.8 ac
TLNG-01
545.5 ac
AN-05
46.8 ac
A
A'
B
B'
C
C'
D
D'
27
26
25
30
29
34
35
36
31
32
2
1
6
5
T15S/R7W
T15S/R6W
T16S/R7W
T16S/R6W
N
Feet
0 600 1,200 2,400
1 inch = 1,200 feet

EXPLANATION

Public
Plant Facilities
Waste Rock
Tailings
Pit
Diversion
Access Road
Mine Boundary
Pond
Topsoil Stockpile
Ore Stockpile
Haul Road
Ancillary

IF THE ABOVE BAR DOES NOT SCALE 1 INCH, THE DRAWING SCALE IS ALTERED

DESIGN: -	DRAWN: -	REVIEWED: -
CHECKED: -	APPROVED: -	DATE: 12/2/2010
FILE NAME: PoO_Fig3-02_PropTopo_JQG_20101130		

NEW MEXICO COPPER CORPORATION

COPPER FLAT MINE

DRAWING TITLE: **PROPOSED FACILITY TOPOGRAPHY**

DRAWING NO. **FIGURE 3-2**
SHEET 5 OF 28
JOB NO. **191000-03**
REVISION NO. **A**

Path: H:\Copper_Flat\New Mexico Copper Corp\191000_03_Copper_Flat_Permitting\040_Drafting\20101115\PoO_Fig3-02_PropTopo_JQG_20101130.mxd

A PROFILE



B PROFILE



FEET
0 250 500 1000
1 inch equals 500 feet

IF THE ABOVE BAR DOES NOT SCALE 1 INCH, THE DRAWING SCALE IS ALTERED

DESIGN: -	DRAWN: -	REVIEWED: -	
CHECKED: -	APPROVED: -	DATE: 12/1/2010	
FILE NAME: PoO_Sections_ML_JQG_20101130.dwg			

NEW MEXICO COPPER CORPORATION

COPPER FLAT MINE

DRAWING TITLE:
OPEN PIT AND WASTE ROCK DUMP CROSS SECTIONS

DRAWING NAME: FIGURE 3-3

REVISION NO. **A**

JOB NO: 191000-03

H:\Copper_Flat\New Mexico Copper Corp\191000_03_Copper_Flat_Permitting\040_Drafting\20101115\PoO_Sections_ML_JQG_20101130.dwg

01462

C PROFILE



D PROFILE



FEET

0 250 500 1000

1 inch equals 500 feet

IF THE ABOVE BAR DOES NOT SCALE 1 INCH, THE DRAWING SCALE IS ALTERED

DESIGN: -	DRAWN: -	REVIEWED: -	
CHECKED: -	APPROVED: -	DATE: 11/30/2010	
FILE NAME: PoO_Sections_ML_JQG_20101130.dwg			

NEW MEXICO COPPER CORPORATION

COPPER FLAT MINE

DRAWING TITLE:
ORE STOCKPILE AND WASTE ROCK DUMP CROSS SECTIONS

DRAWING NAME: FIGURE 3-4	REVISION NO. A
JOB NO: 191000-03	

H:\Copper_Flat\New Mexico Copper Corp\191000_03_Copper_Flat_Permitting\040_Drafting\20101115\PoO_Sections_ML_JQG_20101130.dwg



DESIGN: -	DRAWN: -	REVIEWED: -	
CHECKED: -	APPROVED: -	DATE: 12/6/2010	
FILE NAME: PoO_Fig3-05_ProposedProcessCircuit_JQG_20101201.dwg			

PREPARED FOR:

NEW MEXICO COPPER CORPORATION

COPPER FLAT PROJECT

DRAWING TITLE: PROPOSED PROCESS CIRCUIT

DRAWING NO. **FIGURE 3-5**

REVISION NO. **A**

JOB NO. **191000-03**

H:\Copper_Flat\New Mexico Copper Corp\191000_03_Copper_Flat_Permitting\040_Drafting\20101115\PoO_Fig3-05_ProposedProcessCircuit_JQG_20101201.dwg

FLAT ROADS

OPERATIONS CONFIGURATION

RECLAIMED CONFIGURATION

SIDEHILL ROADS



OPERATIONS CONFIGURATION



RECLAIMED CONFIGURATION

	PREPARED FOR: **NEW MEXICO COPPER CORP. COPPER FLAT PROJECT**	DRAWING TITLE: ROADS CONFIGURATION	
DESIGN: - DRAWN: - REVIEWED: -		DRAWING NO. **FIGURE 3-6**	REVISION NO. **A**
CHECKED: - APPROVED: - DATE: 12/2/2010		JOB NO. **191000-03**	
FILE NAME: PoO_Fig3-06_Roads_JQG_20101202.dwg			

H:\Copper_Flat\New Mexico Copper Corp\191000_03_Copper_Flat_Permitting\040_Drafting\20101115\PoO_Fig3-06_Roads_JQG_20101202.dwg



STRATIGRAPHY

TERTIARY - QUATERNARY	CRETACEOUS	PALEOZOIC AND PRECAMBRIAN
Quaternary Alluvium (Qvy+Qvo)	Late Cretaceous – Silicic Intrusives (Kli)	Paleozoic Siliclastic and Carbonate Sedimentary Rocks (pC through PM)
Tertiary Volcanics (TQb+Tv)	Cretaceous Latite – Andesite Intrusives (Kql+Kd+Kis)	
Tertiary Santa Fe Group (Tsfp+Tsf)	Andesite rocks near Copper Flat (Ka)	

LEGEND

NORMAL FAULT, BALL ON DOWNTHROWN SIDE; DASHED WHERE INFERRED, DOTTED WHERE BURIED.

CONTACT

A A' CROSS SECTION LOCATION

(see Figure 7-2 for cross section detail)

NORTH

0 5,825 11,650

FEET

SOURCES:
(1) HARLEY (1934)
(2) SEAGER ET AL. (1982)
(3) HEDLUND (1977)
(4) ALMINAS ET AL. (1978)

from BLM, 1999

Figure 4-1
Regional Surface Geology
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\7_geology\7-1_general_surface_geology.mxd 07/22/2010

01466

A

A'



LEGEND:

QUATERNARY
- Qvy
- Qvo
- Stream Alluvium

TERTIARY
- Tsfp
- Tsfp Clay
- Palomas Formation
- Tsf – Rincon Valley Formation
- Tv – Tertiary Volcanics

CRETACEOUS
- Ka
- Kis
- Volcanics and Intrusives

PALEOZOIC
- Bedrock Carbonate and Clastic Rocks

SOURCES:
(1) HARLEY (1934)
(2) SEAGER ET AL. (1982)
(3) HEDLUND (1977)
(4) ALMINAS ET AL. (1975)

SCALE IN FEET
VERTICAL 1500 – 0'
HORIZONTAL 6000 – 0'

(see Figure 7-1 for cross section location)

from BLM, 1999

Figure 4-2
Schematic Geologic Cross Section (A-A')
New Mexico Copper Corporation



from BLM, 1999

Figure 4-3
Geologic Structural Features of the Region
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\7_geology\7-3_geology_hillsboro.mxd 07/16/2010



from McLemore et al., 2000; Dunn, 1982; Hedlund, 1985

Figure 4-4
Geologic Schematic of the Hillsboro Mining District, New Mexico
New Mexico Copper Corporation



N
W E
S

Watersheds:
USGS Hydrologic Unit Map
Mine Boundary:
Tom Van Bebber
Imagery Information:
-USGS 7.5-Minutes County DOQQ mosaic
Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

0 3,500 7,000 14,000 21,000
Feet

Legend

- Stream Sample
- Spring Sample
- Proposed Mine Permit Boundary

Watersheds
- Caballo
- El Paso-Las Cruces
- Sub-Watershed

Figure 4-5
Proposed Surface Water Sampling Locations
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\8-SurfaceWater\8-1_surface_wtr_locations.mxd 08/31/2010



0 50 100 200

Feet

Imagery Information:
-USGS 7.5-Minutes County DOQQ mosaic
Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

Legend

Profile Line

Figure 4-6
Proposed Parallel Profiles for Pit Lake Survey

New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\9_groundwater\9-1_LRG_basins.mxd 07/30/2010



0 7.5 15 30

Miles

Basin Boundaries:
RGIS website/NMOSE
Imagery Information:
Landsat imagery from
University of Maryland NLCD

Legend

- City/Town
- Site Location
- Road
- OSE Declared Basin
- Lower Rio Grande
- Las Animas

Figure 4-7
Lower Rio Grande Basin
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\9_groundwater\9-1_LRG_basins.mxd 07/30/2010



from John W. Shomaker, Inc., 1993

Figure 4-8
Conceptual Model of Groundwater Flow System
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\7_geology\9-2_concep_hydrogeo.mxd 07/21/2010



N
W E
S

Watersheds:
USGS Hydrologic Unit Map
Mine Boundary:
Tom Van Bebber
Imagery Information:
-USGS 7.5-Minutes County DOQQ mosaic
Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

0 3,500 7,000 14,000 21,000
Feet

Legend

- Identified Spring
- Proposed Mine Permit Boundary

Watersheds
- Caballo
- El Paso-Las Cruces
- Sub-Watershed

Figure 4-9
Spring and Stream Locations
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\8-SurfaceWater\8-1_surface_wtr_locations.mxd 08/26/2010



4300 WATER TABLE ELEVATION

NORTH

0 8,000 16,000

FEET

from ABC, 1998B

Figure 4-10
Water Level Contours
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\9_groundwater\9-4_wtr-level-contours.mxd 07/29/2010







Figure 4-11
Water Level Map of Copper Flat Pit Area
New Mexico Copper Corporation

from ABC, 1997

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\9_groundwater\9-5_wtr-table-map.mxd 07/29/2010



	GWQ96-22		PIT LAKE		GWQ96-23	
	JULY '96	AUG '97	AUG '95	AUG '97	APR '97	AUG '97
pH	7.5	7.65	8.31	8.16	7.89	7.68
TDS	700	700	4707	5021	770	920
SO_4	250	230	3170	3100	150	410
Cu	<0.025	<0.025	<0.025	0.050	<0.025	<0.025
Fe	<0.05	<0.05	<0.025	<0.05	6.5	0.82

from SRK, 1998

Figure 4-12
Conceptual Model of Pit Lake Monitoring Well Relationship with Water Quality Reports

New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\9_groundwater\9-6_well_WQReports.mxd 07/29/2010



DETAIL A

from SRK, 1995

Figure 4-13
Conceptual Design,
Tailings Seepage Control
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\9_groundwater\9-7_seepage-control.mxd 07/29/2010



Well Locations:
SRK or OSE
Mine Boundary:
Tom Van Bebber
Imagery Information:
-USGS 7.5-Minutes County DOQQ mosaic
Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

0 3,000 6,000 12,000 18,000
Feet

Legend

- Road
- Project Well
- Proposed Mine Permit Boundary

NM OSE Wells (Use)

- Domestic
- Irrigation
- Stock

Figure 4-14
Regional Groundwater Well Locations
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\9_groundwater\9-9_Regional GWwells.mxd 09/07/2010



N
W E
S

Well Locations:
SRK or OSE
Mine Boundary:
Tom Van Bebber
Imagery Information:
-USGS 7.5-Minutes County DOQQ mosaic
Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

0 3,000 6,000 12,000 18,000
Feet

Legend

Proposed Monitoring Well
Aquifer
- Crystalline Bedrock
- Qauternary Alluvium
- Santa Fe Group
- Unknown

- Water Level Only
- Water Level & Water Quality
- Proposed Mine Permit Boundary
- Road

Figure 4-15
Proposed Monitoring Well Program
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\9_groundwater\9-10_ProposedGWwells.mxd 09/07/2010

01480

ID	Task Name
1	**Mine Permitting (Pre-Construction)**
2	**Mine Construction**
3	**Mine Operation**
4	**Waste Rock Disposal Areas**
5	West Waste Disposal
6	North Waste Disposal
7	East Waste Disposal
8	South Waste Disposal / Low-Grade Stockpile
9	**Tailings Impoundment Reclamation**
10	CoverlRevegetate Outer Embankment
11	Tailings Water Removal
12	GradelCover/RevegetateTailings Surface
13	Surface Pipeline Removal
14	**Pit Closure**
15	Highwall Stabilization
16	RamplHighwali Barricades
17	**Plant Area Reclamation**
18	Structure RemovallFoundation Burial
19	Regrade/Fill
20	Thickener Decommissioning
21	Septic System Decommissioning
22	**Road Reclamation**
23	Reduce Access Road Wdlh
24	Remove / Barricade Haul Roads
25	Recontour / Revegetate Water Storage Road
26	**Utilities Reclamation**
27	Remove Above Ground Water Pipeline
28	Plug Underground Water Supply Pipeline
29	Remove S~e Water Supply Pump Stations
30	Remove Plant Site Powerlines
31	Disconnect 115kV Line
32	**Monitoring/Research Testing**
33	Revegetation Test Program
34	Revegetation Monitoring
35	Groundwater Monitoring



* Schedule approximate and subject to change with approval.

Figure 5-1
COPPER FLAT PROJECT
TENTATIVE SCHEDULE

01481



EXPLANATION

- Public
- Mine Boundary

IF THE ABOVE BAR DOES NOT SCALE 1 INCH, THE DRAWING SCALE IS ALTERED

DESIGN: -	DRAWN: -	REVIEWED: -
CHECKED: -	APPROVED: -	DATE: 12/2/2010
FILE NAME: PoO_Fig5-02_ReclTopo_JQG_20101202		

NEW MEXICO COPPER CORPORATION

COPPER FLAT MINE

POST-RECLAMATION FACILITY TOPOGRAPHY

DRAWING NO. FIGURE 5-2	SHEET 27 OF 28	REVISION NO. A
JOB NO. 191000-03		

Path: H:\Copper_Flat\New Mexico Copper Corp\191000_03_Copper_Flat_Permitting\040_Drafting\20101115\PoO_Fig5-02_ReclTopo_JQG_20101202.mxd

APPENDIX A

Claims List

Unpatented Lode and Placer Claims:

Claim Name		Recorded Book	Page	B.L.M Serial No.
Olympia		H	761	NM MC 60057
GLUCK AUF		I	327	NM MC 60058
Taurus		J	682	NM MC 60059
Hercules		K	231	NM MC 60060
EL ORO No. 3		P	52	NM MC 60063
Saint Louis Republic		I	80	NM MC 60069
Delores		27	269	NM MC 60070
HIGHLANDS No. 1		T	405	NM MC 60071
HIGHLANDS No. 2		T	405	NM MC 60072
HIGHLANDS No. 3		T	406	NM MC 60073
THE WELLINGTON		T	406	NM MC 60074
Three Boys No. 1		T	176	NM MC 60080
BLUE MOON		R	631	NM MC 60081
The Leone		U	478	NM MC 60082
Dolores Placer		36	13	NM MC 60083
JONES HILL PLACER		27	212	NM MC 60084
Duke No. 1		40	23	NM MC 60085
Duke No. 2		40	24	NM MC 60086
Graveyard Placer		29	424	NM MC 60021
Old Cabin Placer		29	420	NM MC 60022
Rainey Season Placer		33	163	NM MC 60027
Desert Gold Placer		R	359	NM MC 60043
Gray Black Placer		R	554	NM MC 60044
Black Sand Group 9	No. 1 Placer (Amended)	46	173	NM MC 60045
Black Sand Group 10	No. 3 Placer (Amended)	46	185	NM MC 60046
Surprise No. 1 Lode		48	13	NM MC 60052
Surprise No. 2 Lode		48	102	NM MC 60053
Dutch-1 Lode		48	556	NM MC 60054
Dutch-2 Lode		48	558	NM MC 60055
Dutch-3 Lode		48	557	NM MC 60056
Renew No. 1 Lode		58	622	NM MC 106464
Renew No. 2 Lode		58	623	NM MC 106465
M. S. #1		34	146	NM MC 60093
M. S. #2		34	146	NM MC 60094
M. S. #3		34	147	NM MC 60095
M. S. #4		34	147	NM MC 60096
M. S. #5		34	148	NM MC 60097
M. S. #6		34	148	NM MC 60098
M. S. #8		34	149	NM MC 60099
M. S. #10		34	150	NM MC 60101
M. S. #11		34	151	NM MC 60102
M. S. #12		34	151	NM MC 60103
M. S. #13		34	152	NM MC 60104
M. S. #14		34	152	NM MC 60105
M. S. #15		34	153	NM MC 60106
M. S. #16		34	153	NM MC 60107
M. S. #17		34	154	NM MC 60108
M. S. #18		34	154	NM MC 60109
M. S. #20		34	155	NM MC 60110
M. S. #21		34	156	NM MC 60111
M. S. #22		34	156	NM MC 60112
M. S. #23		34	157	NM MC 60113
M. S. #25		34	158	NM MC 60114
M. S. #26		34	158	NM MC 60115
M. S. #29		34	160	NM MC 60118
M. S. #33		34	162	NM MC 60122

Unpatented Lode and Placer Claims:			
	Recorded		B.L.M
Claim Name	Book	Page	Serial No.
M. S. #38	34	164	NM MC 60123
M. S. #48	34	167	NM MC 60129
M. S. #49	34	168	NM MC 60130
M. S. #53	34	168	NM MC 60131
M. S. #102	34	176	NM MC 60138
M. S. #104	34	177	NM MC 60139
M. S. #105	34	276	NM MC 60140
M. S. #106	34	277	NM MC 60141
M. S. #107	34	178	NM MC 60142
M. S. 222	34	543	NM MC 60170
M. S. 223	34	543	NM MC 60171
M. S. 224	34	544	NM MC 60172
M. S. 225	34	544	NM MC 60173
M. S. 228	34	546	NM MC 60176
M. S. 264	34	563	NM MC 60194
M. S. 282	34	572	NM MC 60210
M. S. 288	34	575	NM MC 60216
M. S. 289	34	576	NM MC 60217
M. S. 290	34	576	NM MC 60218
M. S. 291	34	577	NM MC 60219
M. S. 292	34	577	NM MC 60220
M. S. 293	34	578	NM MC 60221
M. S. 316	34	589	NM MC 60240
M. S. 320	34	591	NM MC 60244
M. S. 322	34	592	NM MC 60246
M. S. 329	34	596	NM MC 60253
M. S. 330	34	596	NM MC 60254
M. S. 331	34	597	NM MC 60255
M. S. 337	34	12	NM MC 60261
M. S. 338	34	13	NM MC 60262
M. S. 339	34	13	NM MC 60263
M. S. 340	34	14	NM MC 60264
M. S. 341	34	14	NM MC 60265
M. S. 342	34	15	NM MC 60266
M. S. 345	34	16	NM MC 60267
M. S. 346	34	17	NM MC 60268
M. S. 347	34	17	NM MC 60269
M. S. 438	41	564	NM MC 60312
M. S. 439	41	606	NM MC 60313
M. S. 440	41	607	NM MC 60314
M. S. 441	41	714	NM MC 60315
M. S. 452	45	353	NM MC 60318
M. S. 453	45	354	NM MC 60319
M. S. 454	45	355	NM MC 60320
M. S. 455	45	356	NM MC 60321
M. S. 456	45	357	NM MC 60322
M. S. 458	45	359	NM MC 60324
M. S. 460	45	361	NM MC 60326
M. S. 461	45	362	NM MC 60327
M. S. 462	45	363	NM MC 60328
M. S. 463	45	364	NM MC 60329
M. S. 464	45	365	NM MC 60330
M. S. 465	45	366	NM MC 60331
M. S. 467	45	368	NM MC 60333
M. S. 468	45	369	NM MC 60334
M. S. 469	45	370	NM MC 60335

Unpatented Lode and Placer Claims:			
	Recorded		B.L.M
Claim Name	Book	Page	Serial No.
M. S. 470	45	371	NM MC 60336
M. S. 471	45	372	NM MC 60337
M. S. 472	45	373	NM MC 60338
M. S. 473	45	374	NM MC 60339
M. S. 474	45	375	NM MC 60340
M. S. 475	71	1927	NM MC 163361
M. S. 476	71	1928	NM MC 163362
M. S. 477	71	1929	NM MC 163363
M. S. 478	71	1930	NM MC 163364
ANIMAS #1 Placer	45	443	NM MC 60341
ANIMAS #2 Placer	45	444	NM MC 60342
The Betsy Ross	R	93	NM MC 60344
Wicks Extension No. 1	R	100	NM MC 60346
Anderson Extension No. 2	R	93	NM MC 60348
Crescent 101	41	358	NM MC 60349
Wicks Extension 100	41	359	NM MC 60350
Betsy Ross 101	41	360	NM MC 60351
Portland 101	41	361	NM MC 60352
Ready Pay Apex 100	41	362	NM MC 60353
Anderson Extension 101	41	363	NM MC 60354

Unpantented Millsite			
Claim Name	Book	Page	BLM Serial No.
Greer No. 2	47	611	NM MC 72821
Chatfield	47	521	NM MC 72822
Chatfield No. 3	47	523	NM MC 72823
Chatfield No. 4	47	762	NM MC 72824
Chatfield No. 5	47	763	NM MC 72825
Chatfield No. 6	47	764	NM MC 72826
Chatfield No. 9	53	521	NM MC 81353
Chatfield No. 10	53	522	NM MC 81354
Chatfield No. 25	56	689	NM MC 100695

Newly Located Unpatented Lodes		
Claim Name	**Book**	**Page**
CU 1	116	902
CU2	116	903
CU 3	116	904
CU 4	116	905
CU 5	116	906
CU 6	116	907
CU 7	116	908
CU 8	116	909
CU 9	116	910
CU 10	116	911
CU 11	116	912
CU 12	116	913
CU 13	116	914
CU 14	116	915
CU 15	116	916
CU 16	116	917
CU 17	116	918
CU 18	116	919
CU 19	116	920
CU 20	116	921
CU 21	116	922
CU 22	116	923
CU 23	116	924
CU 24	116	925
CU 25	116	926
CU 26	116	927
CU 27	116	928
CU 28	116	929
CU 29	116	930
CU 30	116	931
CU 31	116	932
CU 32	116	933
CU 33	116	934
CU 34	116	935
CU 35	116	936
CU 36	116	937
CU 37	116	938
CU 38	116	939
CU 39	116	940
CU 40	116	941
CU 41	116	942
CU 42	116	943
CU 43	116	944
CU 44	116	945

Patented Claims	
Claim Name	**Mineral Survey**
Feeder	M.S. 943C
Chance	M.S. 945A
Xmas	M.S. 945B
Extension	M.S. 945D
Smokey Jones	M.S. 1024
Little Jewess	M.S. 1715
Wisconsin	Lot No. 805
Copper King	Lot No. 733A
Ventura	Lot No. 733B
Castle Hill	Lot No. 733C
Copperopolis	Lot No. 736
83	Lot No. 806
Soudan	Lot No. 807
Stenberg	M.S. 2066
Allhutten	M.S. 2066
Craze Martin	M.S. 2066
Coppenhagen	M.S. 2067
Carl Sextus	M.S. 2067
Union Leader	M.S. 2067
Stockholm	M.S. 2067
Grass Flat	M.S. 2068
Sandow	M.S. 2068
Old Mac	M.S. 2068

Fee Lands	Lot
Township 15 South, Range 7 West	
Section 36	Part of Lot 1 (Parcel N)
Section 36	Part of Lot 4 (Parcel M)
Section 36	Part of Lot 6 (Parcel J)
Section 36	Lot 10 (Parcel L)
Section 36	Lot 11 (Parcel K)
Section 36	Part of N½SE¼ (Parcel I)
Section 36	Part of N½S½SE¼ (Parcel H)
Township 15 South, Range 6 West	
Section 31	Lot 3 (Parcel D)
Section 31	Lot 6 (Parcel G)
Section 31	Lot 7 (Parcel C)
Section 31	Part of NE¼SW ¼ (Parcel E)
Section 31	N½SE¼SW¼ (Parcel B)
Section 31	Part of S½SE¼NW¼ (Parcel F)
Section 31	Part of SE1/4 (Parcel A)
Township 16 South, Range 6 West	
Section 6	Part of Lot 3 (Parcel P)
Section 6	Part of Lot 4 (Parcel O)

APPENDIX B

Runoff Calculations

TECHNICAL MEMORANDUM

TO: Jeff Parshley

FROM: Pete Kowalewski

DATE: February 13, 1996

SUBJECT: **Design of Run-on Diversions at Alta Gold's Copper Flat Project using WASHED and FlowMaster (SRK #68603)**

1.0 INTRODUCTION

Alta Gold Company's (Alta) Copper Flat redevelopment project is located approximately 23 miles southwest of Truth or Consequences and 5 miles northeast of Hillsboro, in Sierra County, New Mexico. The mining project will result in the development of 4 waste/overburden disposal areas throughout the life of the mine. The purpose of this memorandum is to present sizing calculations performed for six diversion ditches designed to intercept site "run-on" from undisturbed areas.

The diversion ditches were sized using the programs WASHED and FlowMaster to convey surface water "run-on" to existing drainages where it will bypass the site. The diversion ditches were sized by calculating the catchment hydrologic parameters such as the catchment area, slope, time of concentration, etc...using a 1"=500' scale topographic map of the site. The data were then entered into the WASHED program, and its output was entered into the FlowMaster program to size the ditches. All of the diversion ditches were sized to pass the runoff resulting from the 100-year 24-hour storm while maintaining a minimum of 6 inches of freeboard.

2.0 COMPUTER PROGRAMS USED IN THE ANALYSES

Two computer programs were used in the diversion ditch sizing analyses. The two programs were: FlowMaster and WASHED. The following is a brief description of each of the programs:

FlowMaster is a pipe, ditch, and channel hydraulics utility program developed by Haestad Methods. The program calculates flow velocities, depth of flow, critical slopes, etc... using the Manning Equation for open channel flow, or the Manning or Hazen Williams Equation for pipe flow (not used in this application). Required inputs are the flow (Q), the channel geometry (trapezoidal, triangular, rectangular, etc...), the side slopes of the channel, the channel slope (gradient), and the Manning's roughness coefficient (n). The program will then calculate the resulting depth of flow, wetted perimeter, flow velocity, and whether the flow is sub-critical, critical, or super-critical (based on the calculated Froude Number).

WASHED is a small watershed hydrology program, developed by Hydrologic Systems, used to calculate runoff hydrographs resulting from specific storm events. The program has different options available for the calculation of the hydrographs, but the preferred method is the SCS Method for runoff determination. Multiple catchment areas can be modeled. Required inputs include the catchment area, hydraulic length, overland flow slope, SCS Curve Number (CN) for the catchment, and the distance from the catchment outlet to the point for which the hydrograph is desired.

3.0 SITE CLIMATOLOGY

The Copper Flat region receives approximately 13 inches of precipitation per year, with approximately 40 to 50 percent of the total received as infrequent but intense summer thunderstorms. Winter storms tend to produce limited rainfall due to the "rainshadow" effect of the mountains located to the west of the site.

The storm event used in the diversion design was the 100-year 24-hour storm event. The 100-year 24-hour storm for the Copper Flat site is documented as 4.0 inches of precipitation in Section 2.3 of the *Copper Flat Mine Hydrogeological Studies (05/12/95)* prepared by Steffen, Robertson, and Kirsten (Reno) and Adrian Brown Consultants, Inc.

4.0 DIVERSION DITCH SIZING

Each diversion ditch was sized to pass the flow resulting from the 100-year 24-hour storm occurring at the site, while maintaining a minimum freeboard of 6 inches. The following procedure was used to size the diversions:

1. The computer program, WASHED, was used to determine the peak flow resulting from the 100-year 24-hour storm occurring over the entire catchment area. For the purpose of these analyses, it was assumed that the Soil Conservation Service (SCS) curve number (CN) for each of the catchment areas was 72 (AMC-II).
2. The catchment area was separated into sub-catchments for the purpose of determining the development of flow in the diversion ditch.
3. The flow occurring in each segment was determined by using the peak flow from each contributing sub-catchment area. This assumption should be conservative with respect to determining the peak flow in the ditch, as it is assumed that if two sub-catchment areas are contributing to one segment, their peaks are simultaneous, when in reality, they should differ by the travel time from each of the sub-catchment areas.
4. The average slope of each of the flow segments was determined based on the topographic map of the site (scale 1"=500').
5. A proposed ditch cross-section was then entered into the computer program, FlowMaster. FlowMaster was used for each of the segments to determine the depth of flow and the flow velocity based on the anticipated peak flow for that segment.
6. It is assumed that the diversion ditch bottoms will be founded in rock, which most likely will be "roughened" due to the excavation of the ditches. The velocities in the ditches can therefore be significantly higher in these ditches than in ditches founded in soil material. There will be less erosion in the ditches founded in rock. A Manning's roughness coefficient (n) of 0.035 was used to reflect the roughened rock condition in the ditch bottoms.

The following results were obtained from the diversion ditch sizing analyses:

Northern Diversion - East Waste Rock Disposal Area

Diversion Ditch Contributing Areas	Peak Flow [100-YR 24-HR Storm] (cfs)
1	14.83
1,2	32.49
1,2,3	42.38
All	45.91

Contributing Areas	Ditch Slope (ft/ft)	Manning's n	Flow Depth (ft)	Flow Velocity (fps)
1	0.0200	0.035	0.66	3.99
1,2	0.0200	0.035	1.04	5.15

Northern Diversion - East Waste Rock Disposal Area (cont.)

1,2,3	0.0200	0.035	1.22	5.59
All	0.0229	0.035	1.23	6.00

Southern Diversion - East Waste Rock Disposal Area

Diversion Ditch Contributing Areas	Peak Flow [100-YR 24-HR Storm] (cfs)
1,4	26.49
1,3,4	35.67
1,3,4,5	51.91
All	73.81

Contributing Areas	Ditch Slope (ft/ft)	Manning's n	Flow Depth (ft)	Flow Velocity (fps)
1,4	0.0720	0.035	0.63	7.42
1,3,4	0.0700	0.035	0.76	8.12
1,3,4,5	0.0960	0.035	0.87	10.20
All	0.0960	0.035	1.07	11.40

Northern Diversion - Tailings Impoundment

Diversion Ditch Contributing Areas	Peak Flow [100-YR 24-HR Storm] (cfs)
1	7.42
1,2	14.13
All	18.01

Contributing Areas	Ditch Slope (ft/ft)	Manning's n	Flow Depth (ft)	Flow Velocity (fps)
1	0.0120	0.035	0.51	2.66
1,2	0.0120	0.035	0.74	3.31
All	0.0120	0.035	0.86	3.58

Southern Diversion - Tailings Impoundment

Diversion Ditch Contributing Area	Peak Flow [100-YR 24-HR Storm] (cfs)
1,2	13.42
1,2,3,4	51.91
All	72.40

Southern Diversion - Tailings Impoundment (cont.)

Contributing Area	Ditch Slope (ft/ft)	Manning's n	Flow Depth (ft)	Flow Velocity (fps)
1,2	0.0100	0.035	0.76	3.06
1,2,3,4	0.0100	0.035	1.67	4.65
All	0.0100	0.035	2.02	5.11

Northern Diversion - West Waste Rock Disposal Area

Diversion Ditch Contributing Area	Peak Flow [100-YR 24-HR Storm] (cfs)
1	3.89
1,2	12.01
1,2,3	22.60
All	41.67

Contributing Area	Ditch Slope (ft/ft)	Manning's n	Flow Depth (ft)	Flow Velocity (fps)
1	0.0200	0.035	0.29	2.49
1,2	0.0200	0.035	0.58	3.72
1,2,3	0.0200	0.035	0.84	4.59
All	0.0200	0.035	1.21	5.56

Eastern Diversion - North Waste Rock Disposal Area

Diversion Ditch Contributing Area	Peak Flow [100-YR 24-HR Storm] (cfs)
1	14.83
1,2	32.84
1,2,3	62.86
All	69.22

Contributing Area	Ditch Slope (ft/ft)	Manning's n	Flow Depth (ft)	Flow Velocity (fps)
1	0.0200	0.035	0.66	3.99
1,2	0.0200	0.035	1.05	5.16
1,2,3	0.1820	0.035	0.80	13.47
All	0.1000	0.035	1.02	11.34

Sketches showing the channel geometries and the contributing areas for each of the diversion ditches, as well as the output from the WASHED and FlowMaster programs are included in the Appendices.

5.0 DISCUSSION OF RESULTS

All of the diversions were designed to pass the runoff resulting from the 100-year 24-hour storm occurring over the diversion's entire contributory catchment area while maintaining 6 inches of freeboard. The ditches have all been designed as trapezoidal cross-sections with 1:1 (Horizontal:Vertical) sideslopes and 5-foot bottoms. The maximum required ditch depth is approximately 2.5 feet deep (Southern Diversion - Tailings Impoundment). Other channel geometries can achieve the same flow capacities, however, the trapezoidal cross-section was used for practical construction purposes.

6.0 REFERENCES

Fifield, Jerald S., *Course Notes - Practical* Approaches *For Effective Erosion and Sediment Control*; International Erosion Control Association, Denver, Colorado; February 1993.

Steffen, Robertson, and Kirsten and Adrian Brown Consultants, *Copper Flat Mine Hydrogeological Studies*; Reno, Nevada; May 12, 1995.

APPENDIX C

Mine Waste Management Plan

THEMAC RESOURCES
New Mexico Copper Corporation

Copper Flat Mine
Preliminary Mine Waste Management Plan

Submitted by:

NEW MEXICO COPPER CORPORATION
2425 San Pedro Dr. Suite 100
Albuquerque, NM 87110
Office: (505) 382-5770

December 2010

01497

TABLE OF CONTENTS

1 INTRODUCTION 1-1
1.1 Scope 1-1
1.2 Location 1-1
1.3 Background 1-3
1.4 Geology 1-3
1.5 Mineralization and Alteration 1-5
1.6 Weathering 1-6
1.7 Climate 1-6

2 OPERATIONAL WASTE ROCK MANAGEMENT 2-1
2.1 Objectives 2-1
2.2 Waste Rock Distribution 2-1
2.3 Summary of Field Observations Concerning Waste Rock Behavior 2-2
2.4 Summary of Geochemical Testing 2-2
2.5 Waste Rock Classification 2-3
2.5.1 Visual Observation 2-5
2.5.2 Confirmation Testing 2-5
2.6 Waste Handling 2-7
2.6.1 Waste Disposal Facilities 2-7
2.6.2 Waste Rock Management During Operations 2-8
2.7 Long-Term Management 2-10
2.8 Quality Assurance Testing 2-10
2.9 Field Kinetic Testing 2-11
2.10 Record Keeping 2-11
2.11 Cover Material Testing and Design 2-11
2.12 Contingency 2-11

3 OPERATIONAL TAILINGS MANAGEMENT PLAN 3-1
3.1 Tailings Disposal 3-1
3.2 Mitigation of ARD Potential 3-1
3.2.1 Tailings Embankment 3-1
3.2.2 Tailings Impoundment 3-2
3.2.3 Covering of Tailings 3-2

4 CONCLUSIONS 4-1
4.1 Waste Rock Characterization 4-1
4.1.1 Waste Rock Management 4-1
4.1.2 Tailings Characterization 4-1
4.1.3 Tailings Management 4-2

5 REFERENCES 5-1

LIST OF FIGURES

Figure 1.1: Project Location 1-2
Figure 1.2: Site Layout 1-4
Figure 2.1: Operational Waste Classification Flowchart 2-6

LIST OF APPENDICES

Appendix A: Waste Characterization Program
Appendix B: Tailings Characterization Program
Appendix C: Memo Regarding Soil Cover Performance Testing

1 INTRODUCTION

The following preliminary *Mine Waste Management Plan* was originally prepared as part of the Alta Gold Plan of Operations (PoO) submitted in 1998, and was based on geochemical characterization data developed at that time. The current owner and operator of the Copper Flat Mine, New Mexico Copper Corporation (NMCC), has initiated a supplemental geochemical characterization program based on the Nevada Bureau of Land Management (BLM) *Rock Characterization and Water Resources Analysis Guidance for Mining Activities* (Instruction Memorandum No. NV-2010-014, dated January 8, 2010), in order to provide the BLM (Las Cruces District Office) the appropriate rock and water resources data are necessary for the BLM to adequately analyze potential environmental impacts, as required by the National Environmental Policy Act (NEPA), and to determine if a Copper Flat PoO will prevent unnecessary or undue degradation. As these supplemental data are collected and analyzed, this mine waste management plan will be amended accordingly.

1.1 Scope

This report contains a mine waste management plan for the Copper Flat Project, located near Hillsboro, New Mexico. The report presents waste rock and tailings characterization data developed to assess waste behavior, and provides recommendations for operational waste rock classification and handling procedures to be employed at the project. The waste management plan addresses short- and long-term mitigation of acid-rock drainage (ARD) potential.

1.2 Location

The Copper Flat Project is located in southwestern New Mexico, approximately 30 miles southwest of Truth or Consequences and approximately 5 miles northeast of Hillsboro (Figure 1.1). The site is in the low hills between the Rio Grande River to the east and the Black Range Mountains to the west.





NORTH

DESIGN: -	DRAWN: -	REVIEWED: -	
CHECKED: -	APPROVED: -	DATE: 12/2/2010	
FILE NAME PoO_Fig1-01_Location_JQG_20101202			

NEW MEXICO COPPER CORPORATION

COPPER FLAT MINE

PROJECT LOCATION

DRAWING NO. **FIGURE 1.1**	SHEET 1 OF 28	REVISION NO. **A**
JOB NO. **191000-03**		

Path: H:\Copper_Flat\New Mexico Copper Corp\191000_03_Copper_Flat_Permitting\040_Drafting\20101115\PoO_Fig1-01_Location_JQG_20101202.mxd

1.3 Background

Under the currently proposed PoO, mining would be expanded in the existing open pit. The ore body would be mined by conventional front end loader and shovel open pit methods in a manner similar to the previous operation. Over the life of the Project, the mine would produce approximately 96 million tons of copper tailings and 37 million tons of overburden and waste rock. Overburden/waste rock production is estimated to average 2.2 million tons per year (ranging from 100,000 to 6.4 million tons annually), with tailings production estimated at 5.7 million tons annually. An operational life expectancy of approximately 17 years is currently projected.

Copper ore excavated from the existing open pit will be processed through a conventional floatation circuit to form a sulfide concentrate. No chemical leaching or roasting will be carried out on site.

Waste rock from the operation will be deposited on existing rock piles located to the west, north, east, and south of the existing pit (Figure 1.2). At the end of mine life all of these rock piles will be reclaimed using a revegetated soil cover.

NMCC proposes to construct a new, lined tailings impoundment facility over the existing unlined impoundment that was constructed in 1982 by the previous mine operator (Figure 1.2); Transport of tailings from the mill to the new impoundment will be via a pipeline. Ancillary facilities associated with the tailings facility will include a slurry and/or cyclone delivery system, a solution reclaim and recycling system, an embankment seepage return system, groundwater monitoring wells and an embankment stability monitoring system.

1.4 Geology

A detailed review of the geology of the Copper Flat deposit and surrounding area was originally presented in the report *Copper Flat Mine Compilation of Pit Lake Studies* (SRK, 1997), and updated in the *NI 43-101 Preliminary Assessment, THEMAC Resources Group Limited, Copper Flat Project, Sierra County, New Mexico* (SRK, 2010) and the *Sampling and Analysis Plan for Copper Flat Mine* (Intera, 2010). A brief summary of this information is presented below.



EXPLANATION

Public | Plant Facilities | Waste Rock | Tailings | Pit | Diversion | Access Road
Mine Boundary | Pond | Topsoil Stockpile | Ore Stockpile | Haul Road | Ancillary

IF THE ABOVE BAR DOES NOT SCALE 1 INCH, THE DRAWING SCALE IS ALTERED

DESIGN: -	DRAWN: -	REVIEWED: -	
CHECKED: -	APPROVED: -	DATE: 12/1/2010	
FILE NAME: PoO_Fig3-01_PropFacilities_JQG_20101123			

NEW MEXICO COPPER CORPORATION

COPPER FLAT MINE

DRAWING TITLE: **PROPOSED FACILITY LAYOUT**

DRAWING NO.	SHEET	REVISION NO.
FIGURE 1.2	4 OF 28	A
JOB NO. 191000-03		

Path: H:\Copper_Flat\New Mexico Copper Corp\191000_03_Copper_Flat_Permitting\040_Drafting\20101115\PoO_Fig3-01_PropFacilities_JQG_20101123.mxd

The Copper Flat deposit is located within a Cretaceous age caldera that was intruded into the Paleozoic marine sediments and Precambrian basement rocks exposed in the upthrusted Black Range and Animas Hills. Immediately to the east of the deposit, the edge of the Rio Grande Rift forms a major regional physiographic and geologic feature. To the east of the project site, the rift has created a major graben structure, which has been infilled with at least 2000 feet of gravelly alluvium of the Santa Fe Group.

The local geology consists of a near circular block of andesite intruded by a Cretaceous age quartz monzonite stock. Numerous latite dikes crosscut both the andesite and the quartz monzonite. A later andesite dike intruded the quartz monzonite. The bulk of the high-grade mineralization is hosted in a breccia pipe which developed in the quartz monzonite stock.

1.5 Mineralization and Alteration

The majority of the economic mineralization occurs as hypogene sulfides that are predominantly associated with the breccias. The breccias are either biotite or feldspar-rich, and higher chalcopyrite concentrations are associated with the biotite-rich material.

Sulfide content within the quartz monzonite varies from less than 1% up to 10% within the mineralized breccia, and up to 20% within some veins and biotite breccia. Coarse, crystalline pyrite is the most common sulfide. Chalcopyrite ($CuFeS_2$) is the most common copper mineral, with bornite (Cu_5FeS_4), tetrahedrite ($Cu_{10}(Cu, Zn, Fe)_2(As, Sb)_4S_{13}$), enargite ($Cu_3AsS_4$), and covellite (CuS) also present. Molybdenite (MoS_2) is a common accessory sulfide. Gangue minerals associated with the sulfides include quartz, feldspar, and biotite. Accessory minerals include calcite (up to 5%), fluorite, siderite, magnetite, sericite, epidote, and chlorite.

Although Copper Flat is classified as a copper porphyry deposit, it differs from classical porphyries in that it lacks an economic supergene enrichment blanket (Titley and Beane, 1981; Titley, 1982). A central potassic alteration zone, extending from the mineralized breccia south along the contact with the quartz monzonite, is characterized by secondary biotite and potassic feldspar. Anhydrite and, locally, gypsum are present as thin coatings on fractures. The entire monzonite stock and related dikes are argillised. The andesitic rocks exhibit propylitic alteration as evidenced by epidote-chlorite-calcite alteration, and minor disseminated pyrite (<1%).

1.6 Weathering

Despite the lack of a classical supergene enrichment blanket, the deposit does have a thin "oxide" zone, down to 10 feet below the original ground surface, in which all sulfides appear to be oxidized. A "transitional" zone in which sulfides are partially oxidized extends 10 to 20 feet below the oxide zone. Below the transitional zone is a "sulfide" zone in which fresh sulfides are visible.

All the rock below the 5480 bench (20-40 feet below the original surface) in the pit contains largely fresh sulfides, except along the Sternberg lode. The Sternberg lode on the west side of the pit is partially oxidized and is referred to as transitional material. This is a mineralized vein and a zone of structural weakness in which sulfides have been partially oxidized due to preferential weathering, and potentially as a result of historic *in-situ* acid leaching. As a result of natural processes and/or past mining activities, oxidation in the Sternburg lode area has been enhanced. Abundant amorphous to poorly crystalline copper and iron oxy-hydroxy-sulfate salts occur in this area. The salts that are soluble in water at surficial temperatures, are considered to be the main source of acidity at this location.

Some superficial oxidation and wallrock alteration has been observed in the pit walls. Nowhere is oxidation greater than a depth of 30 feet, even within or along faulted contacts (Dunn, 1982).

1.7 Climate

Climate stations for the Project area are located at Caballo Dam, approximately 13 miles east of the Project, and at Hillsboro, approximately 5 miles southwest. The climate at the Project is intermediate between these two locations. In addition, NMCC has installed one climate station with pan evaporation and two PM_{10} monitoring stations on both the east and west sides of the mine site. These have been in operation since August 1, 2010.

The climate at the Copper Flat Project is characterized by warm, sunny summers with daily temperatures commonly reaching 90 degrees Fahrenheit, and mild, sunny winters with high temperatures ranging from 55 to 65 degrees Fahrenheit. In the winter, most nighttime temperatures are below freezing. Daily temperature fluctuations of 30 degrees are common throughout the year.

The average annual precipitation in the region is approximately 13 inches, nearly 50% of which occurs as infrequent but intense summer thundershowers in July, August, and September. Because of their intensity and short duration, these storms generally create large amounts of runoff and little infiltration. Precipitation varies significantly on both a monthly and yearly basis.

Evaporation records for southwestern New Mexico indicate that evaporation exceeds precipitation (NOAA, 1982). These data are based on pan evaporation rates which are applicable to estimating evaporation from wetted surfaces and shallow pools. Pan evaporation rates are calibrated against lake evaporation data at specific sites. For the Project site, the conversion from pan evaporation to lake evaporation is approximately 0.72 (NOAA, 1982). Lake evaporation at the project site is estimated to be approximately 65 inches per year and the pan evaporation is 80-90 inches per year (NOAA, 1982).

2 OPERATIONAL WASTE ROCK MANAGEMENT

2.1 Objectives

The overall objective of this waste rock management plan (WRMP) is to mitigate acid-rock drainage (ARD) potential both during mining and following closure of the Project. Specific objectives of the WRMP are as follows:

- To enable classification of waste rock concurrently with or prior to its removal from the open pit;
- To enable disposal of waste rock according to its classification and management requirements;
- To develop conditions that will facilitate concurrent reclamation as well as end of mine closure and reclamation objectives (i.e., long-term ARD control); and
- To enable identification of materials with low-ARD potential that may be useful for facilities construction and/or site reclamation activities.

2.2 Waste Rock Distribution

The waste rock in the deposit generally comprises five lithologies:

- Quartz monzonite;
- Quartz breccia;
- Biotite breccia;
- Andesite; and
- Quartz veins.

Whereas all of these rock types are represented on the existing waste rock piles, future waste rock will be dominantly comprised of fresh, unoxidized quartz monzonite and, to a lesser extent, andesite.

The classification system is discussed in Section 2.5. Operational waste classification will be conducted primarily by visual methods; however, visual classification will be subject to confirmation testing. Confirmation testing and test frequency are discussed in Section 2.5.

2.3 Summary of Field Observations Concerning Waste Rock Behavior

Field observations indicate little oxidation and acid generation occurs at the site despite exposure of waste rock and pit walls since mining operations were suspended in 1982. Observed conditions are likely influenced by arid conditions. Mineralogical observations also suggest that the sulfides occur in a crystalline form that is less susceptible to oxidation.

The deposit includes a thin oxidized (and partially oxidized) cover over fresh quartz monzonite. Where oxidation of the overlying rock is complete, the waste rock will be inert with respect to acid generation. There are likely to be very limited quantities of oxidized waste rock produced during future operations.

Partially oxidized material occurs in a transition zone beneath the oxidized cover and underlying unoxidized quartz monzonite. This transitional material has been exposed to oxidizing conditions over geologic time. In the field, it typically exhibits a low paste pH and high paste conductivity, and is currently acid generating. This behavior can be observed in both exposed pit walls in the partially oxidized zone, and where the transitional waste was deposited on the waste rock piles.

Where unoxidized quartz monzonite was deposited on the waste rock piles, the material does not exhibit evidence of significant oxidation. Sulfide grains appear fresh. Field paste test results typically indicate near neutral pH and low paste conductivity. Field observations indicate that when exposed to weathering under field conditions, the quartz monzonite are, at most, slow to react. This is a function of:

- Coarse grain size of sulfides
- Crystallinity
- Disseminated texture of sulfides

2.4 Summary of Geochemical Testing

Appendix A contains a detailed discussion of the geochemical testing that was completed to evaluate the waste rock and tailings at Copper Flat. The geochemical test program included site visits and laboratory testing programs conducted in 1994 and 1997. In each phase of investigation, field testing (paste pH and conductivity) was performed. Samples were also collected of samples for laboratory testing that included:

- Acid base accounting;
- Total metals assay;
- Leach testing;
- Kinetic humidity column tests;
- Enhanced oxidation (NAG) tests.

The results of these tests are discussed in detail in Appendix A.

The primary observations that can be made on the basis of the geochemical testing programs are as follows:

- The future waste rock will be composed primarily of quartz monzonite. The majority of this waste rock can be expected to exhibit acid generating potential as indicated by both acid base accounting and NAG tests;
- While static and NAG tests indicate a net acid producing potential, kinetic tests indicate that the unoxidized material is slow to oxidize. Kinetic testing of unoxidized samples produced neutral to slightly alkaline leachates with low concentrations of sulfate and dissolved metals. The laboratory kinetic test behavior is consistent with observed field conditions.
- Partially oxidized material, or the transition waste rock, exhibits low paste pH and high conductivity. Leach testing of the transition material indicates soluble sulfate and metals loads that indicate acid generating behavior. It should be noted, however, that only limited quantities of similar material occur within the future mining area.

2.5 Waste Rock Classification

Results of the 1994 – 1996 field and laboratory testing programs indicated that although the waste rock from the deposit has the potential to generate acid, the majority of the future waste rock (unoxidized quartz monzonite) will be very slow to oxidize and produce acidity. The current testing program is intended to verify these results.

The quartz monzonite that was obtained from below the zone of oxidation and placed on the waste rock piles prior to 1982 exhibits a fresh appearance and generally neutral to alkaline pH. This material requires management to alleviate ARD potential; however, the ARD risks associated with the unoxidized waste rock are long-term risks

only. Operationally, the material can be considered as being inert (i.e., on the scale of ~ 20 years).

Low pH values are associated primarily with the transition waste materials that have been exposed to oxidizing conditions over geologic time and are currently generating acidity.

While acidic seepage has been observed at the site, it is believed to be associated with the transition material. It is also correlated, temporally, to periods of unusually heavy rainfall. Although this has the consequence of washing out acid generating metal sulfate salts, a significant dilution effect will also be experienced. The transition waste rock requires management to alleviate ARD potential. Due to its geochemical behavior, ARD mitigation measures for transition waste should be implemented concurrently with disposal

During the course of the waste characterization program, the waste was classified into four types by visual inspection: oxide material, transition material, and unoxidized waste that was further subdivided into low- and high- sulfide material.

The following waste rock classification and management system is proposed:

Waste Rock Type	**ARD Potential**	**Management Goal**
Oxide	Low	Use in concurrent reclamation, stockpile for use
Transition	Generally high	mitigate ARD potential concurrently with disposal
Low sulfide, unoxidized	Low	Use in concurrent reclamation, stockpile for use
High sulfide, unoxidized	Generally high in long term	Concurrent reclamation where feasible, implement long term ARD controls

Brief descriptions of waste classification methods and the frequency at which these methods will be applied are presented below. Detailed descriptions of the test procedures are contained in Appendix A.

2.5.1 Visual Observation

Figure 2.1 presents a flow chart that summarizes the waste rock classification program. All blasthole drill cuttings will be visually inspected by a qualified geologist or trained geological technician prior to blasting and removal from the pit.

Oxidized and transition waste rock can be distinguished from unoxidized (high and low sulfide) waste rock on the basis of visual characteristics. Both the oxide and transition waste rock exhibit strong iron oxide staining and may exhibit partial to complete destruction of original rock texture. In contrast, the high and low sulfide unoxidized waste rock has a fresh appearance and may contain abundant fresh sulfides.

Waste rock that exhibits an oxidized appearance will also be assessed for amount of visible sulfides in the sample. Transitional material will be any material that appears oxidized but contains sulfides. A lack of visible sulfides will be used to characterize oxide material. Material classified as oxidized will be subject to confirmation testing.

Materials that exhibit a fresh, unoxidized appearance will be subject to visual estimation of sulfide content in order to distinguish between high and low sulfide waste rock. Initially, a conservatively low sulfide content of 0.5 percent will be used as an indicator of low sulfide waste rock. Material classified as low sulfide waste rock will be subject to periodic conformation testing.

2.5.2 Confirmation Testing

Confirmation testing will be performed to confirm the effectiveness of visual waste classification. Confirmation testing will be performed to evaluate both oxide versus transition and low sulfide versus high sulfide designations. Confirmation testing will be completed on-site with a Leco Furnace.



SRK
STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

PROJECT NO.	DATE	REVISION
68612	07/98	A

FIGURE 2.1

OPERATIONAL WASTE CLASSIFICATION FLOWCHART

2.5.2.1 Oxide Versus Transition Waste Rock

To be classified as oxide, the material must exhibit a low sulfide sulfur content. Oxide waste rock samples will be periodically subjected to total sulfur and sulfate sulfur analyses. Based on the test results, the sulfide sulfur content of the sample will be calculated (as total less sulfate sulfur). Because weathering results in the consumption of neutralizing potential as well as oxidation of sulfides, partially oxidized materials with low sulfide sulfur content are commonly capable of acid generation. An initial sulfide sulfur cutoff value of 0.1 percent shall be used as an indicator of oxidized waste rock.

Confirmation testing of oxide versus transition waste rock will initially be conducted at a frequency of one confirmation test for each five blastholes designated as oxide waste rock. Subject to ongoing testing and field observation, this test frequency may be subject to revision.

2.5.2.2 Low Sulfide Unoxidized Versus High Sulfide Unoxidized Waste

A conservatively low total sulfur concentration of 0.2% will be used as a preliminary indicator of low sulfide waste rock. Based on static testing completed to data, a sample containing 0.2% total sulfur will typically exhibit an NP:AP ratio that is greater than 3:1. Subject to further testing and observation, this cutoff value may be adjusted to suit conditions.

Confirmation testing of low versus high sulfide waste rock will initially be conducted at a frequency of one test for each five blasthole samples designated as oxide waste. Subject to ongoing testing and field observation, this test frequency may be revised.

2.6 Waste Handling

2.6.1 Waste Disposal Facilities

Four waste rock disposal facilities will be developed to accommodate future waste rock. The existing West and North Dumps, which contain oxidized, transition and unoxidized waste rock, will be expanded to contain all waste rock types. The south and east disposal areas will be expanded to contain primarily unoxidized waste rock. Waste rock disposal facilities are shown on Figure 1.2.

2.6.2 Waste Rock Management During Operations

Most of the future waste rock will be low and high sulfide waste, with only small amounts of oxide and transition material encountered near the surface of the proposed pit expansion. The waste will primarily be quartz monzonite with lesser andesite. The breccias are primarily ore.

The general approach to waste rock management and the control of ARD is to control the flux of water through the waste rock. Future waste will be placed on existing waste rock piles in a manner that minimizes the potential for leaching of dissolved constituents. Surface water will be managed during operations to promote runoff from the waste rock and prevent surface water runon.

Management of future waste rock will include concurrent reclamation, where feasible, and will incorporate disposal practices that will facilitate reclamation and closure of the waste rock disposal facilities.

2.6.2.1 Oxidized Waste Rock

No restrictions will be imposed on the handling and placement of oxidized waste rock. To the extent practical, oxidized waste rock will be deposited on the outer slopes and surfaces of the waste rock disposal facility. Oxidized waste rock may be stockpiled in selected areas of the waste rock disposal facilities so that it may be used during reclamation. Given the relatively small volume of oxide waste rock that is anticipated to exist within the future pit limits, oxide waste rock may be managed as transition waste without confirmation testing.

2.6.2.2 Transition Waste Rock

Transition waste rock will be managed concurrently with disposal due to its leachable acidity and dissolved metal loads. Transition waste rock will be isolated in one portion of either the West or the North waste disposal area to minimize the footprint that is covered by this material.

A minimum of 6 feet of non-transition waste rock will be placed over transition waste to minimize contact transition material in the short term. Transition waste rock will be mined early in the operation. Consequently disposal areas will be covered with additional waste rock as the waste disposal facilities are developed.

2.6.2.3 Unoxidized High Sulfide Waste Rock

As discussed above, the unoxidized waste rock poses negligible short term risk of ARD or adverse drainage quality. No restrictions will be imposed on the placement of unoxidized waste rock, however, placement will be in a manner that facilitates reclamation. A reclamation cover, as discussed below, will be placed over the unoxidized waste rock.

The unoxidized waste rock will be end dumped in 50-foot lifts. Benches will be created at the base of each end dumped lift to facilitate post-mining regrading. Following regrading to 2.5H:1V slopes, minimum 10-foot wide erosion control benches will remain. All active unoxidized waste rock surfaces will be backsloped to promote drainage of surface water off the active waste rock disposal areas. Runoff will be directed to perimeter surface water collection ditches and sediment collection facilities.

2.6.2.4 Low Sulfide Waste Rock

No restrictions will be imposed on the handling and placement of low sulfide waste rock. Where practical, low-sulfide waste rock will be deposited on the outer slopes and surfaces of the waste rock disposal areas. Low-sulfide waste rock will be stockpiled in selected areas of the waste rock disposal facilities so that it may be used for reclamation.

2.6.2.5 Waste Flagging and Routing

Prior to blasting active benches in the open pit, mine geological staff will visually inspect the cuttings from each blasthole. The rock type, color, degree of oxidation, sulfide content and other pertinent features including blasthole cuttings sample numbers will be noted and transferred to bench plan maps. Where the rock is identified as oxide or low sulfide waste, samples will be collected for confirmation testing. Waste rock boundaries will be plotted on the active bench plans.

When blasting has been completed, waste boundaries will be field flagged on the active bench. Shovel operators will then selectively excavate the waste rock and inform haul truck operators as to the nature of the waste rock and its destination within the active waste rock disposal facilities. The operator will develop a workable waste flagging and routing plan prior to the commencement of mining operations. Mine staff

will maintain records of the volume of each waste type mined during each shift and its ultimate location within the waste rock disposal facilities.

2.7 Long-Term Management

Placement of a soil cover over the waste and implementation of permanent surface water management controls will minimize the flux of water through the waste rock and the potential for leaching of oxidation products in the long term. Preliminary cover studies presented in the report, *Hydrologeological Studies, Copper Flat Project* (SRK, 1995), and updated in the report *Copper Flat Mining Act Permit Application, Volume 4* (SRK, 1996) indicated that, for a wide range of cover materials and cover thicknesses, the flux of water through the waste rock piles will occur at a rate of a few gpm (<5gpm). A cover thickness of 12 inches was therefore proposed, based on *Hydrologic Evaluation of Landfill Performance* (HELP) modeling (Appendix C). This cover thickness will be re-evaluated during the supplemental investigations, and tested during operations in field trials, and modified based on the results.

Where possible, cover placement will be completed concurrently with mining. Inactive waste rock slopes will be regraded to 2.5H:1V slopes and compacted by dozer traffic. The cover material will be placed and revegetated, and permanent surface water management facilities will be constructed. At the end of mining, final active waste rock disposal area surfaces will be regraded, covered, and revegetated.

Routing of loaded haul trucks over the upper surface of each lift will mechanically degrade and compact the waste rock, and produce zones of reduced permeability. Permeability testing of a quartz monzonite waste rock sample that was subjected to equipment traffic during previous mining activities exhibited a remolded permeability of 1×10^{-6} cm/sec. The combination of cover placement, evaporation and waste rock compaction is expected to reduce the flux of water through the waste rock to minimal rates and alleviate the potential for significant impacts to water resources. Attenuation of acidity and dissolved constituents in the foundation of the waste rock disposal facilities will further reduce the potential for water quality impacts.

2.8 Quality Assurance Testing

Quality assurance testing will be periodically performed to verify that waste rock is being accurately classified. The operator will randomly select up to 10 archived blasthole samples per month which will be subjected to saturated paste pH, saturated

paste conductivity, and acid base accounting testing (totals sulfur, sulfate sulfur and NP testing). This testing will be performed at a state approved laboratory.

The samples will be classified with respect to ARD potential on the basis of NP/AP ratio. The samples will be located on the appropriate bench plan maps and the quality assurance test classification will be compared to the operational waste classification designation. Should the comparison indicate discrepancies in waste classification, a plan to determine the source of waste classification discrepancies and improve classification techniques will be prepared by the operator.

2.9 Field Kinetic Testing

The operator has committed to a program of kinetic testing during the mining operation. These tests will be conducted to support waste management planning, confirm and further refine mine waste geochemical behavior predictions. The proposed plan for ongoing kinetic testing is described in the report, *Copper Flat Closure Field Testing* (SRK, 1998).

2.10 Record Keeping

Maintenance and continuous updating of records for all waste classification, quality assurance, and kinetic testing is considered critical to the effective management of waste rock at Copper Flat. Data collected from blast hole sampling will also be maintained. This data will be important in assessing and modifying the waste rock classification scheme. All test data will be incorporated into monthly and annual reports that will be maintained on site and kept available for inspection.

2.11 Cover Material Testing and Design

Preliminary cover design and performance modeling has been completed to assess closure and reclamation requirements for long-term ARD control and protection of water resources. The operator will conduct field scale test of cover materials and cover designs during the mining operation. Testing programs are defined in *Copper Flat Closure Field Testing* (SRK, 1998). Final reclamation cover design will be based on the results of this work.

2.12 Contingency

Due to the arid conditions that prevail at the site, acidic seeps from the existing waste rock piles have been observed, but only on rare occasions following periods of high

rainfall. Surface water will be managed during operations to minimize the potential for seeps to develop. Any affected water that occurs during operations will be collected and utilized in ore processing.

3 OPERATIONAL TAILINGS MANAGEMENT PLAN

Unlike the historic facilities, NMCC proposes to line the future tailings impoundment and embankment in order to eliminate the potential migration of tailings process water into the underlying groundwater system. However, underdrain seepage will require active management until such time as the tailings have consolidated, and a suitable reclamation cover has been constructed to manage surface water runoff. Given the nature of the ore material being processed, surface exposure of sulfide-bearing tailings may require additional management to mitigate the potential production of ARD.

3.1 Tailings Disposal

The proposed Copper Flat tailings embankment will be constructed through cycloned sand deposition. A series of cyclones will be installed on the embankment crest. Cyclone underflow or sand will be deposited on the embankment while the cyclone overflow, consisting of the fine fraction of the tailings and the majority of the process water, will be spigotted into the lined tailings impoundment.

Tailings disposal practices will result in a well drained embankment composed of coarse tailings sand. In the impoundment, a lower-permeability, saturated tailings mass will be created. Geochemical testing (Appendix B) indicates that the tailings, like the waste rock, tend to react slowly when compared to tailings from other known copper deposits, such as Chino Mine (Ford *et al*., 1998; Newcomer *et al.,* 1998). The potential for development of ARD at the surface will be alleviated by covering the tailings, thereby limiting the flux of water into the impoundment.

3.2 Mitigation of ARD Potential

3.2.1 Tailings Embankment

Due to the unsaturated conditions that will be maintained during and after tailings disposal operations, the tailings embankment sand will be more susceptible to oxidation than the tailings slimes in the impoundment. As such, the implementation of ARD mitigation measures for the tailings embankment will be initiated concurrently with mining.

3.2.2 Tailings Impoundment

The fine grained tailings in the impoundment will remain saturated during operation of the tailings disposal facility. Little oxidation of the tailings can occur under these conditions. At closure, the potential for ARD from the tailings impoundment will be alleviated by several factors:

- The tailings overflow of slimes will have a low permeability. Typical fine tailings exhibit a permeability of 1×10^{-6} cm/sec or less following partial consolidation. Upon complete consolidation, the permeability of fine tailings will decrease. The physical properties of the tailings will limit the flux of water into the tailings and the potential for mobilization of oxidation products; and

- Because the tailings will be fine grained, they will exhibit high capillarity and will retain moisture. Moist porous solids are effective barriers to the diffusion of oxygen. The combination of low permeability and resistance to oxygen diffusion will alleviate development of ARD in the impoundment. Placement of the proposed native soil cover over the impoundment will enhance evapotranspiration, control tailings erosion, and further reduce the flux of water through the tailings mass.

3.2.3 Covering of Tailings

A cover composed of native soil materials will be placed on the embankment. As with the waste rock, a soil cover of 12 inches is proposed to limit infiltration to the tailings and promote run-off (Appendix C). Prior to final design, field cover testing and kinetic testing of tailings will be completed as described in *Copper Flat Project Field Testing* (SRK, 1998). Cover thickness and permeability requirements will be determined in conjunction with field testing.

4 CONCLUSIONS

4.1 Waste Rock Characterization

Field and laboratory testwork, completed by the previous project proponent, on waste rock and drill core samples from Copper Flat have been used to classify the material as:

- *Oxide*,
- *Low ARD potential*. All sulfide completely oxidized,
- *Transitional* – High ARD potential. Partial oxidation of sulfides and storage of acid generating and metal leaching capacity in soluble metal-sulfate minerals.
- *High Sulfide* – High potential to generate ARD. Fresh sulfides with little or no oxidation.
- *Low sulfide* – Low potential to generate ARD. Fresh sulfides with little or no oxidation.

Management of these wastes will vary proportional to class and geochemical behavior with respect to potential metal leaching and acid generation.

4.1.1 Waste Rock Management

For permanent mitigation, concurrent reclamation will be ongoing.

- *High Sulfide Waste Rock* – Similar mitigation to the Transition Waste Rock with collection of seepage and where practical concurrent reclamation.
- *Low Sulfide Waste Rock* – This material will be used in concurrent reclamation of more reactive material and adequately covered to mitigate long-term risk.

Full field testing will be undertaken during development for operational and final management of waste rock.

4.1.2 Tailings Characterization

Tailings laboratory characterizations found that, compared to other similar mineral deposits currently being mined, the Copper Flat tailings are considerably less reactive. This is supported by the field observation that, despite nearly 30 years of exposure to

atmospheric moisture and oxygen, no significant acid seeps or acid plumes have developed at the site, even though some leaching of the material has occurred.

4.1.3 Tailings Management

Mitigation of potential ARD from the tailings embankment will be undertaken concurrent with mining. Due to their unsaturated nature these tailings are anticipated to have a higher ARD potential than in the main body of the impoundment.

The majority of the tailings in the impoundment will, during the lifetime of the mine, be kept saturated and consequently will have a negligible ARD potential. Upon closure, the impoundment will be adequately covered so as to minimize ARD generation.

5 REFERENCES

Bureau of Land Management (BLM). 2010. *Rock Characterization and Water Resources Analysis Guidance for Mining Activities*. U.S. Department of the Interior, Bureau of Land Management, Nevada State Office. Instruction Memorandum No. NV-2010-014. January 8, 2010.

Dunn, P.G. 1982. Geology of the Copper Flat Porphyry Copper Deposit, Hillsboro, Sierra County, New Mexico. In: Titley, S. R. ed., *Advances in Geology of the Porphyry Copper Deposits, Southwestern North America*. The University of Arizona Press, Tucson, AZ. Pp. 313-326.

Ford, R.C., J.L. Clapper, and B.R. Romig. 1998. Stability of water treatment sludge, Climax Mine, Colorado. In: *Proceedings of the Fourth International Conference on Acid Rock Drainage, Vancouver, B.C., Canada, 1997*.

Intera. 2010. *Sampling and Analysis Plan for Copper Flat Mine*. Prepared for New Mexico Copper Corporation. Submitted to Mining and Minerals Division New Mexico Energy, Minerals and Natural Resources Department.

Miller, S., A. Robertson, and T. Donohue. 1997. Advances in Acid Drainage Prediction Using The Net Acid Generation (NAG) Test. In: *Proceedings of the Fourth International Conference on Acid Rock Drainage, Vancouver, B.C., Canada, 1997*, Vol. II. Pp. 535-547.

National Oceanic and Atmospheric Administration (NOAA). 1982. *Mean Monthly, Seasonal, and Annual Pan Evaporation for the United States.* NOAA Technical Report NWS 34, Washington, D.C.

Newcomer, R., R. Schmidt-Peterson, K. Johnejeack, and D. Blout. 1998. Seepage from older tailing ponds, Chino Mining Company, New Mexico: Part 1. In: *Tailings and Mine Waste '98.* Balkema, Rotterdam, 463-480.

SRK Consulting (U.S.), Inc. (SRK). 2010. *NI 43-101 Preliminary Assessment, THEMAC Resources Group Limited, Copper Flat Project, Sierra County, New Mexico.*

Steffen Robertson and Kirsten (U.S.), Inc. (SRK). 1995. *Hydrologeological Studies, Copper Flat Project.*

Steffen Robertson and Kirsten (U.S.), Inc. (SRK). 1996. *Copper Flat Mining Act Permit Application, Volume 4.*

Steffen Robertson and Kirsten (U.S.), Inc. (SRK). 1997. *Copper Flat Mine Compilation of Pit Lake Studies.*

Steffen Robertson and Kirsten (U.S.), Inc. (SRK). 1998. *Copper Flat Closure Field Testing.*

Titley, S.R. 1982. The style and progress of mineralization and alteration in porphyry copper systems, American southwest. In: Titley, S. R. ed., *Advances in Geology of the Porphyry Copper Deposits, Southwestern North America*. The University of Arizona Press, Tucson, AZ. Pp. 93-116.

Titley, S.R., and R.E. Beane. 1981. Porphyry copper deposits – Part I: Geologic settings, petrology, and tectogenesis. In: *Economic Geology*, 75th anniversary volume, p. 214–235.

Appendix A

Waste Rock Characterization

TABLE OF CONTENTS

1 INTRODUCTION....1

1.1 Work Carried Out As Part of the EIS....1
1.2 Work Carried Out As Part of the Waste Rock Management Plan....2

2 METHODS....3

2.1 Paste pH and Conductivity....3
2.2 Total Metals Concentrations....3
2.3 Acid Base Accounting....3
2.4 Net Acid Generation Tests (NAG)....4
2.5 Modified EPA 1312 Test....5
2.6 Humidity Column Tests....6

3 RESULTS OF WASTE ROCK TESTING PROGRAM....7

3.1 Metal Content and Mineralogy....7
3.2 EPA 1312....7
3.3 Paste pH and Conductivity....8
3.4 Acid Base Accounting....8
3.5 Net Acid Generation (NAG) Testing....9
3.6 Kinetic Tests....9
3.6.1 pH and Eh....10
3.6.2 Electrical Conductivity....10
3.6.3 Acidity and Alkalinity....11
3.6.4 Sulfate....11
3.6.5 Metals....11
3.6.6 Assessment of Oxidation and NP Depletion Rates....11

4 HYDROGEOCHEMISTRY....13

4.1 Surface water....13
4.2 Pit Lake....13
4.3 Groundwater....14
4.4 Seepage....14

5 ACID ROCK DRAINAGE CHARACTERISTICS OF THE EXISTING WASTE PILES....15

5.1 ARD Characteristics of Different Lithologies....15
5.1.1 Quartz Monzonite....15
5.1.2 Quartz Breccia....16
5.1.3 Biotite Breccia....16
5.1.4 Quartz Vein....16
5.1.5 Andesite....16
5.2 ARD Characteristics of Different Waste Rock Dumps....17

5.2.1 North Waste Rock Dump 17
5.2.2 West Waste Rock Dump 17
5.2.3 South Waste Rock Dump or Lean Ore Stockpile 18
5.2.4 East Waste Rock Dump 18

6 DISCUSSION 20

6.1 Soluble Contaminants 20
6.2 Acid Generation 20
6.3 Field Identification of Waste 21

7 CONCLUSIONS 23

LIST OF FIGURES

Figure A.3.1 Paste pH Frequency Distribution by Lithology
Figure A.3.2 Paste pH vs. Conductivity
Figure A.3.3 NP vs. AP for 1994 and 1997 Data
Figure A.3.4 NP vs. AP
Figure A.3.5 Total Sulfate/Total Sulfur (%) vs. Paste pH (SU)
Figure A.3.6 NAG pH Frequency Distribution by Lithology
Figure A.3.7 Paste pH vs. NNP, NAG
Figure A.3.8 Kinetic Test Results for pH vs. Time
Figure A.3.9 Kinetic Test Results for Electrical Conductivity vs. Time
Figure A.3.10 Kinetic Test Results Acidity and Alkalinity vs. Time
Figure A.3.11 Kinetic Test Results for Sulfate vs. Time
Figure A.3.12 Kinetic Test Results Copper vs. Time
Figure A.3.13 Kinetic Test Results for Iron vs. Time
Figure A.5.1 Histogram of Visible Sulfide for All Lithologies
Figure A.5.2 Histogram of Paste pH for All Dumps
Figure A.5.3 Histogram of Paste Conductivity for All Dumps
Figure A.5.4 Histogram of NAG Values for All Dumps
Figure A.5.5 Histogram of Visible Sulfide for All Dumps
Figure A.6.1 NP vs. AP by Weathering Status
Figure A.6.2 Sulfide vs. Sulfate by Weathering Status
Figure A.6.3 NAG pH vs. Total Sulfur
Figure A.6.4 Sulfate/Total Sulfur vs. Sulfide

LIST OF DRAWINGS

Drawing 68612-001 Location of Surface Samples

LIST OF TABLES

Table A.1.1 Numbers of Samples Analyzed in the Waste Rock Characterization Program

Table A.1.2 Number of Tests on Samples of Each Rock

Table A.3.1 Total Metals Concentrations in Waste Rock

Table A.3.2 Extractable Metals Concentrations in Waste Rock

Table A.3.3 Results of ABA Testing of Column Samples

Table A.3.4 Results of Humidity Column Test Work

Table A.4.1 Chemistry of West Dump Seep (August, 1997)

Table A.6.1 Waste Rock Classification System

APPENDICES

Appendix A.1: Testing Protocols

Appendix A.2: Paste pH and Conductivity Data, Acid Base Accounting Test Data, and Net Acid Generation Test Data

Appendix A.3: Humidity Column Test Data

1 INTRODUCTION

Two phases of waste rock characterization have been completed at the Copper Flat project in New Mexico. A preliminary assessment of the waste was conducted in 1994 for the Environmental Impact Statement (EIS). More detailed work was carried out in 1997 for use in development of this waste management plan. The numbers of tests completed in each phase of the waste rock characterization are listed in Table A.1.1.

1.1 Work Carried Out As Part of the EIS

The initial assessment of the waste rock dumps at Copper Flat (SRK, 1995; DEIS, 1996) was carried out in part to assess the current geochemical characteristics of waste rock from former operation sand to determine whether future waste rock has the potential for acid generation.

Nineteen samples were collected from the existing pit wall rock, waste rock piles, and drill core and cuttings. The locations of the surface samples are shown in Drawing 68612-001. Selected samples were subjected to:

- Paste pH and conductivity measurements to determine whether previous oxidation had produced acidic and/or soluble residues;
- Determination of total metals concentrations;
- Acid Base Accounting to assess the balance between potentially acid generating and potentially acid neutralizing minerals;
- Agitated leach extraction tests to measure the amount of immediately soluble metals;
- Humidity column testing to simulate long-term oxidation of the waste rock and evaluate drainage quality; and,
- Geotechnical testing to estimate the physical and hydraulic properties of compacted waste rock.

The conclusions of this work were that:

- Most of the material on the dumps had only superficial oxidation despite exposure to the atmosphere for over 14 years.

- No evidence of acid seeps was observed during 1994-5, although one seep had been reported in an earlier study (Newcomber et al., 1991) and another seep was identified in August 1997 after unusually heavy rainfall.
- The material on the East, South, and most of the North dumps was essentially "sulfide" material with little or no accumulation of secondary mineral salts. The West waste rock dump and the western portion of the North dump were more complex with a combination of "sulfide" and "transitional" ore.

1.2 Work Carried Out As Part of the Waste Rock Management Plan

In August 1997, field work was carried out with the aim of producing detailed geological and geochemical maps of the waste rock dumps and open pit. One hundred and twelve samples were collected from six-foot long channels along benches on the waste rock dumps. The locations of the 1997 samples are shown on Figure A.1.2. The material was characterized in the field by geological observation and by paste pH and TDS measurements. Twenty-eight samples were analyzed by Acid Base Accounting (ABA) tests and sixty-two samples were analyzed by Net Acid Generation (NAG) testing. Table A.1.2 shows the numbers of samples of each rock type analyzed by each procedure.

2 METHODS

The testing methods for samples collected in the waste rock characterization studies are summarized in the following sections. Detailed protocols are presented in Appendix A.1.

2.1 Paste pH and Conductivity

Paste pH and conductivity tests were conducted by mixing a sample of the fine grained portion of the waste with deionized water in a ratio of 1:2 by volume to produce a saturated paste. Measurements were then taken directly from the paste.

A paste pH greater than pH 7 indicates either that the sample is not generating acid, or that any acidity produced is being neutralized. A paste pH below 5.0 indicates that the material contains soluble acidity from prior oxidation. The conductivity measurement indicates the amount of immediately soluble salts present in the sample. The soluble acidity and salts are normally the products of earlier oxidation reactions. Their presence indicates that water contacting the material could leach oxidation products, even in the absence of further oxidation.

Paste pH and conductivity tests were conducted in the field (1996-1997 data) or at the SRK Laboratory in Lakewood, Colorado (1994-1995 data).

2.2 Total Metals Concentrations

Total metals concentrations in the waste rock were determined by Inductively Coupled Plasma (ICP) following the EPA 3051 digestion (USEPA 1982; 1995a,b). The purpose of the total metal analyses was to determine what metals are present in the waste rock. The ICP analysis does not indicate the amount, if any, of each metal that would be soluble under conditions likely to arise in the field.

ICP analyses were conducted at ACZ Laboratory in Steamboat Springs, Colorado.

2.3 Acid Base Accounting

Acid base accounting (ABA) tests were conducted to assess the potential for the waste rock to become acid generating. ABA tests indicate the balance of potentially acid generating minerals (sulfides) and potentially acid consuming minerals (generally carbonates) present in the rock. The test involves analyzing for total sulfur and sulfur species (total, sulfate, and pyritic sulfur) to determine the acid generation potential

(AP), and then titration with acid to assess the neutralizing potential (NP) of the material. The units of the NP and AP are kg $CaCO_3$ equivalent/ton of material (kg/T), or tons $CaCO_3$ equivalent/kiloton of material (T/KT). The method employed during the 1994 testing was the Sobek method. The modified Sobek technique (Sobek et al., 1978; SRK, 1989) was used to evaluate the 1996 samples.

The ABA characteristics of different samples can be compared using the difference between the NP and the AP values (the net neutralizing potential, or NNP). An NNP of greater than 20 kg/t indicates that a sample contains sufficient NP to buffer the acidity that could be produced as a result of oxidation, and therefore, has a low potential for acid generation. An NNP value of less than –20 kg/T is considered indicative that a sample has the potential for acid generation. Values between +20 kg/T and –20 kg/T have uncertain acid generating potential and may require kinetic testing to evaluate field behavior.

The ratio of NP:AP can also be used to evaluate acid generating potential. As a general guideline, an NP:AP greater than 3:1 indicates that a sample has a low potential for acid generation. A value below 1:1 indicates that, if the sample is exposed to oxidizing conditions, it has the potential for acid generation. Waste rock samples exhibiting NP:AP values between 1 and 3 typically require kinetic testing to evaluate field behavior.

However, both of these methods for evaluating ABA data are guidelines only. Other characteristics of the rock, such as the grain size, sulfide species and morphology and the form and occurrence of the neutralizing minerals, can influence the tendency for the material to produce or neutralize acidity.

A total of 46 ABA tests were conducted during the two phases of the waste characterization program. Testing of 1995 samples was conducted at ACZ Laboratory in Steamboat Springs, Colorado, whereas 1997 samples were analyzed at Sierra Environmental Monitoring Laboratory in Reno, Nevada.

2.4 Net Acid Generation Tests (NAG)

An alternative method for evaluating acid generating potential is the net acid generation (NAG) test. Whereas ABA tests indirectly estimate acid generating potential by comparing the sulfide sulfur content to the acid neutralizing potential of a sample, NAG tests determine the balance without the need for sulfur analyses.

The test is conducted by mixing the sample with hydrogen peroxide, and heating until the mixture stops boiling. After cooling, the pH of the sample is measured to obtain the "NAG pH". The NAG pH is then an estimate of the final pH of a sample if nearly all the sulfide present were oxidized, and is used in comparing the relative potential for generating acidity. The NAG pH is a qualitative indication of a sample's potential for acid generation; however, NAG pH values of 4.0 or greater are often indicative of low acid generating potential. The solution can then be titrated to neutrality with a standard base to determine the net acidity or acid generated (NAG) upon complete oxidation of the samples. The NAG is expressed as kg H_2SO_4 equivalent/ton, and is analogous to the NNP. Where the NAG is zero, net acid neutralizing potential is indicated. Positive NAG values indicate net acid generating potential.

The NAG test assumes complete oxidation of all the sulfide in a sample. Although sulfide oxidation is seldom complete, and the NAG test can underestimate the amount of sulfide in a sample, the result provides a realistic indication of the amount of sulfide that would react in field.

NAG tests were conducted on 62 samples representing all the rock types in the deposit. All NAG tests were carried out at the School of Engineering, University College of Wales, Cardiff, United Kingdom.

2.5 Modified EPA 1312 Test

The objective of this procedure is to characterize and quantify the soluble metal and salt content of waste samples. The test involves mixing a pulverized sample with a leaching solution, agitating the mixture, filtering the liquid and analyzing the liquid extract for pH, conductivity, acidity, alkalinity, sulfate and soluble metal concentrations (USEPA, 1994). The EPA test uses a liquid to solids ratio of 20:1. However, at the standard test ratio, constituent concentrations may be diluted and undetectable. The procedure was, therefore, modified to include a 2:1 ratio liquid to solids ratio. Deionized water was also substituted for the standard leach solution (deionized water pH adjusted with nitric and sulfuric acid) to simulate leaching with rain water.

The modified EPA 1312 tests were conducted at ACZ Laboratory in Steamboat Springs, Colorado.

2.6 Humidity Column Tests

Humidity column tests were carried out to simulate long term weathering of waste rock samples. Each sample was placed in a column of PVC pipe. Warm, moist air was passed through the sample for three days, followed by three days of dry air circulation. On the seventh day of each weekly cycle, the sample was irrigated and the leachate was collected. The pH, Eh, conductivity, acidity and alkalinity were measured directly, and a portion of each leachate sample was then sent for analyses of metal concentrations. Testing was continued for 21 weeks.

Humidity column tests were conducted at Cominco Engineering Services Laboratory (CESL) in Vancouver, British Columbia, Canada.

3 RESULTS OF WASTE ROCK TESTING PROGRAM

The following section presents the general findings of the geochemical testing program. Detailed data are presented in Appendices A.2 and A.3.

3.1 Metal Content and Mineralogy

The mineralogy of the samples was determined visually. The most common sulfide was coarse crystalline pyrite, which is present in concentrations of less than 1% throughout the quartz monzonite, and up to 10% to 20% locally within the mineralized breccia and some quartz veins. Other sulfides include chalcopyrite ($CuFeS_2$), the most common copper mineral, bornite ($CuFeS_2$), tetrahedrite ($Cu_{10}(Cu, Fe, Zn)_2(As,Sb)_4S_{13}$), enargite ($Cu_3AsS_4$), and covellite (CuS). Molybdenite (MoS_2) is the most common molybdenum mineral. Gangue minerals associated with the sulfide mineralization include quartz, feldspar, and biotite. Accessory minerals include calcite (up to 5%), fluorite, siderite, magnetite, sericite, epidote, and chlorite.

Table A.3.1 lists the results of ICP analysis of two samples of quartz monzonite waste rock. Sample PW-3 was collected from the northwest wall of the open pit and WD-1 was collected from the west waste rock pile. Both samples show a similar chemistry with high aluminum, manganese, copper, and iron concentrations. Copper, molybdenum, sulfur, silver, zinc and cadmium are enriched in the sample analyzed with respect to crustal abundance.

3.2 EPA 1312

Although the total metals concentrations in the waste rock are important, the concentrations of metal salts that are soluble is often of more concern. Table A.3.2 lists the results of EPA 1312 test on sample WD-1. It should be noted that this sample was selected for EPA method 1312 leach testing because it is a transition waste rock sample that exhibited low field pH. Therefore, the leachable constituent concentrations would be anticipated to be higher than those expected from fresh, unoxidized waste rock samples.

The leachate from the sample had a pH of 3 and high sulfate concentration (3050 mg/L). No alkalinity was detected. The leachate also had higher concentrations of aluminum, copper, and iron, than the other sample, reflecting soluble metals in the solid sample. In addition, nickel and zinc in the solid sample appear to be soluble. However, the soluble metals concentrations are generally low.

3.3 Paste pH and Conductivity

Paste pH was measured on 141 samples from the waste rock dumps. The range of pH values for each rock type is shown in Figure A.3.1. The andesite sample analyzed had a paste pH above 9. All other rock types show a range of values between 2 and 9, indicating that portions of each lithology have undergone varying degrees of sulfide oxidation.

Paste pH is plotted against paste conductivity in Figure A.3.2 and listed in Appendix A.2. There is a strong correlation between low paste pH and high paste conductivity, as would be expected. Conductivity values generally remain below 500 µS/cm above a pH of 6, but increase when pH is lower.

3.4 Acid Base Accounting

NP values are plotted against AP values for the two testing programs in Figure A.3.3. The 1994 samples have higher NP than the 1997 samples. The discrepancy is a result of the use of the more conservative modified Sobek procedure for determining NP on the 1997 samples. For the purposes of this report, only the 1997 data will be used.

Figure A.3.4 shows the relationship data between NP and AP by rock type for the 1997 samples, with the diagonal line indicating where NP is equal to AP. The figure shows that most samples contain less than 3% sulfide (equivalent to an AP of 93kg $CaCO_3$ eq./t), and generally have less NP than AP. Therefore, most samples have a "theoretical" potential for acid generation. The andesite appears to be an exception.

From the correlation of Sulfate/Total Sulfur and paste pH four fields can be identified (Figure A.3.5):

- *Low paste pH, high Sulfate/Total Sulfur Ratio*: This field is characterized by samples that have a high proportion of secondary sulfate salts that are acid generating. As can be observed relatively few samples fall into this field.
- *High paste pH, low Sulfate/Total Sulfur Ratio*: This field is characterized by samples that have a low proportion of secondary sulfate salts but high sulfide content. Whilst having the potential to generate appreciable amounts of acid they are not on immediate reaction acid-generating and require a long period of interaction with air and water in the presence of a catalyst to be so.
- *Low Paste pH, Low Sulfate/Total Sulfur Ratio*: This field is characterized by high sulfide samples.

- *High Paste pH, High Sulfate/Total Sulfur Ratio*: This field delineates the oxide ore samples.

ABA data is presented in Appendix A.2.

3.5 Net Acid Generation (NAG) Testing

NAG tests were conducted on 62 samples and the resulting NAG pH values are plotted according to rock type on Figure A.3.6. Samples of biotite breccia, quartz breccia, and quartz monzonite had NAG values that ranged from acidic to alkaline. This suggests that each of these lithologies contain a wide range of sulfide concentrations. Quartz vein material, in contrast, had NAG values indicating Net Acid Generation, reflecting the common association within the deposit of sulfides with quartz veins. Low paste pH correlates to high NAG and low negative NNP (Figure A.3.7).

NAG test data are presented in Appendix A.2.

3.6 Kinetic Tests

Humidity column tests were conducted on four different quartz monzonite samples and a quartz breccia sample:

- Two samples obtained from the sulfide waste rock stockpiles (SW-1 and LGSSP-2);
- One sample of quartz breccia with jarosite stains from the pit wall (PW-2); and,
- Two samples of unoxidized quartz monzonite waste obtained from archived drill core (IDC 24-22-241 and CF10-190-199).

Sulfide waste samples (SW-1 and LGSSP-2) are representative of previously mined unoxidized materials that have been exposed to weathering conditions since 1982. These samples contain fresh pyrite and chalcopyrite which coat fractures and are disseminated throughout the rock.

The pit wall sample (PW-2) was collected from partially oxidized cap rock located west of the pit. While the sample was highly oxidized, it contained residual disseminated pyrite and, locally, chalcopyrite.

The core samples (IDC 24-22-241 and CF10-190-199) are representative of unoxidized quartz monzonite waste that will be mined during future operations. These

samples were obtained from drilling at depth and have not been exposed to weathering or oxidizing conditions in the field. They contained fresh chalcopyrite and abundant fresh pyrite.

Results of ABA tests on the samples used for the humidity column tests are listed in Table A.3.3. Humidity column data are presented in Appendix A.3 and summarized in Figures 3.8 to 3.3.

3.6.1 pH and Eh

Figure A.3.8 illustrates leachate pH with time. For the initial 19 weeks of testing, all unoxidized quartz monzonite samples (all samples except column 2, PW-2) maintained a leachate pH in the range of 7.0 to 8.1. In column test PW-2, pH varied between 5.8 and 6.5 during the initial 19 weeks.

All samples show a sharp decrease in leachate pH in week 20. Because the pH depression was approximately equivalent in all tests, the laboratory was contacted to determine if the pH depression was attributable to laboratory operations as opposed to geochemical conditions. Independent investigations by the laboratory indicated that every column in the laboratory at that time (not just those for this project) experienced a similar leachate pH decrease. It was ultimately determined that the decrease in pH was the result of a decrease in pH of the deionized water used as inflow to the columns. Major servicing of the laboratory deionizing equipment caused the decreased pH of the deionized water in week 20.

The kinetic tests were resumed after a seven-week hiatus during which time the deionizing system was adjusted. The samples remained undisturbed during this period and were exposed to natural airflow that would have allowed oxidation to continue until the weekly cycles were resumed. Results for the last two weeks indicate that oxidation continued to occur at rates similar to those of the first 20 weeks.

3.6.2 Electrical Conductivity

Figure A.3.9 illustrates leachate conductivity versus time. Initially high conductivity was indicated for test LGSSP-2. This material was collected from the surface of the low grade sulfide stockpile and initial high leachate conductivity may result from leaching of secondary oxidation products. All the samples exhibit trends of decreasing leachate conductivity. By week 20, the conductivity of all test leachates was less than 100 μS/cm, suggesting limited oxidation or leaching of metals and sulfate. When the

tests were resumed at week 27, samples LGSSP-2 (surface waste) and C10-190-199-2 (fresh sulfide material) exhibited increased conductivities indicating oxidation and production of soluble salts during the hiatus.

3.6.3 Acidity and Alkalinity

Acidity production slowly increased after week 9 in all columns (Figure A.3.10), as alkalinity began decreasing (Figure A.3.10). Figure A.3.10 illustrates the low leachate alkalinity of sample PW-2 throughout the 29-week test due to the oxidized nature of the sample.

3.6.4 Sulfate

The time dependent plot for sulfate (Figure A.3.11) shows a rapid decrease in the sulfate concentration over the first 5 to 10 weeks. This is a result of the flushing of readily soluble sulfate salts present in the waste rock prior to testing. After about week 15 the sulfate concentrations reach a pseudo steady state. As was reflected in the conductivity, leachates from columns containing samples LGSSP-2, and C10-190-199-2 show an increase in sulfate as the result of accumulation of oxidation products during the seven week hiatus during which the columns were not operating. The other columns showed no significant increase, suggesting a slower rate of sulfate production and release.

3.6.5 Metals

After initial flushing of secondary oxidation salts, most metals were produced at a low rate throughout the test period, most below detection limits (Figures A.3.12 and A.3.13).

3.6.6 Assessment of Oxidation and NP Depletion Rates

Sulfate release rates and alkalinity release rates were calculated for each column test to assess the relative oxidation and acid neutralization dynamics. For these calculations it was assumed that 30% of the waste rock in the test columns is contacted by infiltrating waters and that all the sulfide and NP are available for reaction. Average concentrations for weeks 16 to 20, inclusive, were used to calculate rates of depletion of sulfide and NP. The results are summarized in Table A.3.4.

Based on the estimated time to deplete the NP, it will take on the order of several hundred years for the columns to become acid generating under the accelerated laboratory conditions. Field conditions and the designated mitigation measures are

anticipated to further prolong NP depletion. The results also suggest that the neutralizing potential originates predominantly from calcium and magnesium based carbonate minerals, with the possible exception of sample PW-2.

Also shown in Table A.3.4 are the specific sulfur release rates. The first rate is based on the specific release rate per unit mass of rock sample while the second rate has been normalized to the sulfide sulfur content of the sample. The release rates are in similar order of magnitude, indicating that all the samples are oxidizing at a slow rate. The most reactive sample appears to be LGSSP-2.

This could be explained by the higher pyrite content of total sulfides and finer grain size in this sample. Sulfate levels are negligible (0.01% out of 0.61% total sulfur) so the effects of secondary sulfates can be ruled out, although the presence of some sulfate indicates that at least a surface alteration has occurred on exposed pyrite.

4 HYDROGEOCHEMISTRY

The following section presents a brief discussion of local surface water and groundwater quality. Hydrogeological data are presented in detail in *Copper Flat Mine Hydrogeological Studies (SRK, 1995)* and *Copper Flat Project Hydrogeolgy Impact Evaluation (ABC, 1996).*

4.1 Surface water

There are three main water courses in the vicinity of the proposed mine; these are Percha Creek, Las Animas Creek and Greyback Arroyo. Percha Creek lies to the south of the mine and Las Animas to the north. Both of these creeks drain to the Caballo reservoir to the east of the mine. The Greyback Arroyo is currently diverted around the existing pit.

The surface water quality in Las Animas and Percha Creeks and the reservoir is broadly similar. They all contain low dissolved solids (300-440 mg/l) and pH is slightly alkaline (7.2-7.9). The chemistry is dominated by calcium-bicarbonate ions. Sulfate is low (mean of 65 mg/l) and dissolved metal concentrations are below detection limit. The Greyback Arroyo contains somewhat higher calcium concentration (450-510 mg/l, compared to around 60 mg/l in the other surface waters) and sulfate (1410-1740 mg/l). Alkalinity is also elevated (up to 508 mg/l $CaCO_3$ equivalent). Trace element concentrations are close to or less than detection limit. The Greyback Arroyo cuts through the copper porphyry deposit, and therefore may be expected to contain higher sulfate concentrations than the other streams in the region. Greyback is an ephemeral stream, and dissolved constituents will be concentrated by evaporation.

4.2 Pit Lake

The pit lake chemistry is dominated by calcium-sulfate ions; sulfate reaches concentrations of up to 3600 mg/l. The pH is generally slightly alkaline (pH 7-8.5) although pH values of less than 7 (with a minimum of 4.4) were recorded during 1992-93. Most dissolved trace element concentrations are low; however fluoride and manganese are both elevated (with concentrations up to 11 mg/l and 4.9 mg/l respectively). No evidence of stratification was observed on the four occasions that depth samples were collected (SRK, 1997).

The high TDS in the pit lake is probably due to the evaporation accumulation of sulfide oxidation products and dissolution of secondary minerals. Evaporative concentration has increased the dissolved salt load to the point where gypsum (hydrated calcium sulfate) is at saturation.

The lower pH levels reported for a part of the lake (pH 6-6.5) are influenced by the local presence of an acid seep originating from the NW side of the pit wall in the Sternberg lode. The few recorded low pH values may also be related to dissolution of acid volatile salts (such as jarosite) during pit lake level fluctuations.

The climate and nature of the pit lake are such that the pit will act as an evaporative sump, so there will be no groundwater flow out from the lake (ABC, 1996). Surface runoff from the waste rock dumps will be directed to flow into the pit lake, where it will be contained.

4.3 Groundwater

The groundwater at the Copper Flat site is dominated by the bicarbonate ion, providing a high buffering capacity. The pH ranges from 7.5 to 8.15, indicating slightly alkaline water. Sulfate concentrations tend to be low to moderate (80-400 mg/l) and dissolved metal concentrations are also low. Iron and manganese were relatively high in one of the samples (GWQ96-23A) collected in April 1997 (6.5 mg/l iron, 1.425 mg/l manganese). However more recent sampling results (August 1997) indicate very low iron and manganese (<1 mg/l of both elements).

4.4 Seepage

During the August 1997 sampling event, a seep was observed at the east toe of the west waste rock dump. A sample was collected and the results of analysis are tabulated in Table A.4.1. Although the seepage contains very high dissolved metals and low pH it is important to note that the flow was very low (much less than a gallon/minute (measured during sampling at ~0.2 gpm)) and the seepage will therefore be rapidly diluted and buffered by groundwater and/or surface water.

The upper part of the seepage channel was coated by chalcanthite ($CuSO_47H_2O$), langite ($Cu_4SO_4(OH)_6{}^2U_2O$), woodwardite ($Cu_4Al_2SO_4(OH)_{12}$ $2\text{-}4H_2O(?)$), goethite, cuprocopiapite ($(CuFe^{2+})$ $Fe^{3+}{}_4(SO_4)6(OH)_2$ $2OH_2O$) and amorphous Na-Ca-Mg-Cu-Zn--Fe-Mn salts. This indicates active buffering and evaporation, thus limiting metal and acid dispersion.

5 ACID ROCK DRAINAGE CHARACTERISTICS OF THE EXISTING WASTE PILES

5.1 ARD Characteristics of Different Lithologies

From whole rock analysis of waste rock samples (Table A.3.1), the primary constituents are Al, Ca, Fe, Mg and K. Trace metals of significance (> 10 ppm) are Ba, Cu, Co, Mn, Mo and Zn. Several million tons of waste rock are currently piled around the pit and along the southeast slope of Animas Peak. SRK has previously classified the waste rock in the area as oxidized, transitional and unoxidized (SRK, 1995). The basis for classification is the proportion of pyrite observed in the material, as well as its field behavior (as indicated by paste pH and conductivity).

The rock piles were initially classified (Draft EIS, 1996) on the proportion of each type of material present with the west pile being primarily transitional waste, the north rock pile being a combination of unoxidized and oxidized waste and the south and eastern rock piles comprising essentially unoxidized sulfide waste.

The ARD potential by lithology and by waste rock dump are discussed in the following sections.

5.1.1 Quartz Monzonite

The quartz monzonite frequently contains abundant pyrite and therefore may be a potential source of acid rock drainage. The paste pH measurements made on this lithology (94 taken in August 1997) ranged from 2.51 to 8.76 (Figure A.3.1). Several measurements were at the higher end of the range, suggesting that in some cases the monzonite may have some buffering capacity. However, the majority of the measurements were between pH 2 and 7, indicating initial acid generation. The net acid generation (NAG) results varied between 8 and 57 kg/T eq. H_2SO_4 (Figure A.3.6). Over 50 % of the tests generated a NAG value of between 20 and 40 kg/T eq. H_2SO_4. This indicates that the rock has potential to generate acid in certain circumstances. Observations indicate a visible pyrite content of between 0 and 8 %, with most samples containing around 3% (Figure A.5.1). This ties in well with the NAG test results.

5.1.2 Quartz Breccia

The quartz breccia is not as abundant as the quartz monzonite, which will form the bulk of the waste rock. Around 30 samples of this lithology were assessed for paste pH and paste EC (electrical conductivity, a measure of total dissolved solids). Nearly all the paste pH measurements were less than 7, and most of these were between pH 3 and 5 (Figure A.3.1). This was probably due to the dissolution of superficial salts. The NAG test results were similar to those of the quartz monzonite, with most measurements falling between 20 and 40 kg/T eq. H_2SO_4. However, more of the results from the quartz breccia were greater than 80 kg/T eq. H_2SO_4 (Figure A.3.6). One sample yielded a NAG potential of 223 kg/T eq. H_2SO_4, but this was exceptional. The visible sulfide in the quartz breccia was mostly between 3 and 4 %. The quartz breccia generally has a higher acid generating potential than the quartz monzonite.

5.1.3 Biotite Breccia

Ten measurements of paste pH were made on rock classified as biotite breccia. The paste pH values ranged from 2.45-7.38 (Figure A.3.1). All but one of these readings were less than pH 7 and the majority were less than pH 5. The biotite breccia generally has a greater proportion of sulfide than the other lithologies, with a quarter of the samples containing more than 6% visible sulfide. This is reflected by the NAG test results, which are up to 80 kg/T eq. H_2SO_4 (Figure A.3.6). However, only six NAG measurements were made on biotite breccia samples so it is inappropriate to make generalizations. This rock is considered an ore material and will be handled as such.

5.1.4 Quartz Vein

Six quartz vein samples were assessed for paste pH and percent visible sulfide. Of these only 3 NAG tests were possible. The paste pH measurements were dominated by acidic values, with ½ of the tests exhibiting a pH less than 3 (Figure A.3.1). Most of the samples contained around 5 % visible sulfide, one sample only contained around 1% (Figure A.5.1). The NAG test results were between 10 and 40 kg/t eq. H_2SO_4; these are slightly lower than may be expected for samples with relatively high sulfide content (Figure A.5.4).

5.1.5 Andesite

Only one andesitic sample was available for testwork. This reflects the relative scarcity of this lithology throughout the waste rock dumps. This sample yielded a very

high paste pH value of 9.14, which demonstrates its excellent buffering capacity. This sample was not assessed for net acid generation.

5.2 ARD Characteristics of Different Waste Rock Dumps

Locations of samples collected for paste pH and paste conductivity measurements and NAG values are shown on Drawing 68606-001, and the frequency of acid generator indicators, paste pH, conductivity, NAG value and visible sulfide abundance are provided in Figures A.5.2 - A.5.5, respectively.

5.2.1 North Waste Rock Dump

The north waste rock dump contains a mixture of unoxidized, oxidizing and oxidized waste rock. The paste pH measurements are generally lower than those for the other waste rock dumps due to the presence of transitional material. The range of paste pH values are from 2.5 to 6 (significantly, no values above pH 7 were recorded) and more than 50 % of the values were less than pH 3. This suggests a higher proportion of soluble salts relative to material from the other waste rock dumps.

The NAG test results were not exceptionally high although one sample generated a value of 223 kg/t eq. H_2SO_4. The remainder of the samples were between 9 and 75 kg/t eq. H_2SO_4. The sample which generated the high NAG value (NRD 5620 014) was also noted as containing 20 % visible pyrite, which is unusual for the Copper Flat waste rock. Most waste rock samples from this dump contained on the order of <2% visible pyrite.

From the results to date, the north waste rock dump appears to have the greatest potential to generate acid. This is probably because this dump contains a greater proportion of partially oxidized (transition) rocks than the other dumps.

5.2.2 West Waste Rock Dump

The west waste rock dump has been described as containing mostly partially oxidized, transitional waste rock (SRK 1995) but more detailed investigation in 1997 indicated that much of the rock is relatively fresh and the oxidation is very superficial.

The paste pH measurements ranged from pH 2.3 to 7.8. Generally the rocks on this dump were less reactive than those on the other dumps, with nearly 50 % of samples generating a paste pH greater than 5. The NAG test results ranged from 15 to 75 kg/t eq. H_2SO_4, with over 80 % of samples generating a potential of less than 40 kg/t eq.

H_2SO_4. This relates well to the proportion of visible sulfide in the rocks which was less than 2% in nearly 80% of the samples.

Field observations and all the test results to date indicate that the west waste rock dump has the lowest potential to generate acidity.

5.2.3 South Waste Rock Dump or Lean Ore Stockpile

The south waste rock dump reportedly contains rocks with a higher proportion of sulfide compared with the other waste rock dumps. However, the samples collected during August 1997 do not support this. All the samples evaluated contained less than 7 % visible sulfide (estimated) and the acid base accounting (ABA) revealed no samples with a sulfide content greater than 1.5 %. An earlier sampling round (SRK 1994) produced similar results; the highest measured sulfide content was just over 3%.

The NAG potential is relatively low; 90 % of samples evaluated generated a value of less than 40 kg/t eq. H_2SO_4, and the highest potential measured was only 43 kg/t eq. H_2SO_4. This confirms the low sulfide content of the samples analyzed.

The paste pH results ranged from pH 2.5 to 8.8; over a fifth of the samples generated an alkaline paste pH which may indicate some buffering capacity. Most (75%) of the samples showed very low reactivity, generating paste conductivity values of less than 500 μS/cm.

The evidence presented here suggests that the south waste rock dump has an overall low acid generating potential.

5.2.4 East Waste Rock Dump

The samples collected from the east waste rock dump contain on average around 2 % visible sulfide. Sulfide analysis resulted in a similar figure (although fewer samples were evaluated). Ore samples contained up to 10 % sulfides.

The NAG potential of the samples analyzed was relatively small; 80% were less than 30 kg/t eq. H_2SO_4. This reflects the sulfide content of the rocks.

The paste pH range was from 2.71 to 9.14. Most (65%) of the samples generated a pH less than 6. This suggests that there are soluble salts available for dissolution. The average sulfate to total sulfur ratio is around 35%, which indicates a relatively low degree of oxidation.

The east waste rock dump, in common with the south waste rock dump, is likely to have a relatively low potential for acid generation.

6 DISCUSSION

6.1 Soluble Contaminants

Results of the EPA 1312 test indicate that the soluble metal concentrations in transition waste rock are relatively high; however, the sample represents only a limited volume of future waste rock. Leachates from kinetic tests conducted on unoxidized quartz monzonite samples exhibit very low soluble metal and salt concentrations. These leachates are considered more representative of potential unoxidized waste rock drainage quality in the foreseeable future.

Soluble metal concentrations in the tailings can also be used to infer behavior of the waste rock because the tailings are composed of similar material that has been crushed, increasing the surface area that is available to oxidation. Therefore, the soluble concentrations in the tailings exposed to weathering for over 14 years may provide a "worst-case" indication of the soluble load in the waste rock. As can be seen in Table B1.2 in Appendix B, the extractable metal concentrations in the tailings, as determined by modified method 1312 testing, are low.

6.2 Acid Generation

The degree to which material has oxidized, or its "weathering status", can provide some indication of how the rock must be managed to alleviate ARD potential. The weathering status was identified visually by geologists according to the following classification (Table A.6.1):

- Oxide: No visible sulfides, loss of texture, strong oxide staining;
- Transitional: Visible sulfides, loss of texture, strong oxide staining;
- Low Sulfide: Few visible sulfides, fresh appearance, minor to no oxide staining; and,
- High sulfide: Abundant visible sulfides, fresh appearance, minor to no oxide staining.

Figure A.6.1 plots NP against AP according to weathering status of the material. The figure shows that oxidized material has low potential to generate acid since these samples have AP concentrations below 11, equivalent to a percent sulfide concentration of less than 0.4%.

This is also illustrated in Figure A.6.2. This figure plots the percent sulfur present as sulfide against percent sulfur as sulfate. The diagonal line in the figure is where concentrations of the two sulfur forms are equal. Samples having higher sulfate sulfur than sulfide sulfur are all oxide and transitional material. Samples plotting below the line are low and high sulfide material. This figure, along with Figure A.6.1, suggests that oxidized material will not pose an ARD problem. However, this material may contain soluble metals that could be leached from the rock in the short term.

For the transitional, low and high sulfide materials, there is evidence to suggest that some of the sulfides are less reactive than others. One piece of evidence is the waste rock piles themselves. During the 14 years of exposure, much of the sulfide has been oxidized to metal oxides that are stored in the rock. However, the waste still contains unoxidized sulfides, suggesting that there is some variability in the weathering rates of the sulfides. This is also illustrated in Figure A.3.1 by the wide range of paste pH values for every rock type, except andesite. The biotite breccia, quartz breccia, quartz monzonite, and quartz vein material all have paste pH values ranging from 2 to 9. If all the sulfides are uniformly distributed and had similar reactivity, the range of paste pH values would not be expected to be so broad.

Figure A.6.3 is a plot of NAG pH vs. total sulfur. NAG pH values range from 2 to 8 and have no relation to total sulfur concentrations. For example, samples with total sulfur contents of about 2.9% have NAG pH values either below 3 or greater than 6. This suggests variability in the reactivity of the sulfides contained in the samples.

Finally, of the waste rock humidity cells only LGSSP-2 became acidic during the 27 weeks of testing, despite containing very different materials. Since there is little neutralizing capacity in many of the kinetic test samples, the neutral drainage indicates low rates of sulfide oxidation in the cells. Thus, even under the relatively wet conditions of the humidity columns, the sulfides are slow to oxidize.

6.3 Field Identification of Waste

Results of the geochemical testing program indicate that field methods can be used to identify the different types of waste. The visual classification of oxide, transitional, low sulfide and high sulfide material correlated well to sulfate/total sulfur ratios, as shown in Figure A.6.4. Oxide samples have ratios above 75% and transitional material has ratios between 40% and 75%. Low and high sulfide values fall below 40% SO_4/S(T).

The figure also shows that low and high sulfide can be distinguished by sulfide concentrations. Three of the four low sulfide samples had sulfide concentrations below 0.6%. This means that during operations, low sulfide can be separated from high sulfide material based on visual estimation of sulfide concentration.

While the waste rock can be easily classified on the basis of visual inspection, periodic testing of sulfur content is recommended as a means of confirming the effectiveness of visual classification methods. Confirmation testing is recommended to evaluate the distinction between oxide and transition waste, and between low sulfide and unoxidized waste. Total sulfur analyses by Leco furnace are routinely used in waste management programs at many mine sites. Equating total sulfur content with sulfide sulfur content provides a rapid and highly conservative estimate of acid generating potential.

7 CONCLUSIONS

The primary conclusions of this work are:

- While a significant to moderate potential for acid generation is exhibited by the Copper Flat lithologies, the rate of sulfide oxidation is slow. Sulfide oxidation and acid generation has been and is active at the Copper Flat mine site. However, no environmental impact on surface streams or groundwater has been observed during this or any previous studies. Seasonal acidic and metal-sulfate rich seeps do form but tend to evaporate at the toe of the dumps.

- Available buffering through mineral-water reactions and from groundwater recharge is sufficient to neutralize generated acidity for much of the year. Acid seeps could develop during operations, after periods of heavy rainfall. However, these seeps will drain towards the pit area as either surface or sub-surface flow.

- Metal release from the lithologies is low and all kinetic leachates conformed to all applicable surface water and most groundwater standards.

- Sulfide oxidation is slow from the Copper Flat lithologies as evidenced by the abundance of sulfide minerals on the waste rock dump surfaces despite exposure since 1982.

Environmental concerns regarding waste rock at any mine site are generally two fold: leaching of soluble metals stored in the waste and generation of acidic drainage. At Copper Flat, leachable metals from the waste rock and tailings do not appear to be a concern, with the exception of the transition waste.

The results of the geochemical testing programs indicate that most of the waste rock at the site has the potential to generate acid, given sufficient time and exposure to oxidizing conditions. However, evidence from paste pH tests, NAG tests, and humidity columns suggest that the sulfides are not highly reactive. This is supported by the fact that much of the material on the waste rock dumps is neutral despite having been on the surface since 1982. This may be due to the coarse, crystalline nature of the sulfides at Copper Flat as well as arid site conditions. Crystalline minerals have a lower surface area and a more organized structure so consequently require more energy to oxidize. As a result they tend to be more stable than fine-grained semi-crystalline or subhedral minerals.

The rates of reactivity of the sulfides will need to be confirmed by humidity column tests on new waste rock generated from the pit. In the interim, waste can be managed using a conservative plan that includes visual classification and confirmatory measurement of the total sulfur content of the waste rock prior to its removal from the pit, with waste handling measures that address the short and long term management requirements. Once oxidation rates are obtained from the operational field test program then the humidity column test results reported here can be calibrated to a parameter that can be measured in the field, such as total sulfur, so as to refine the operational waste management plan



Figure A.3.1. Paste pH Frequency Distribution by Lithology



Figure A.3.2 - Paste pH vs. Conductivity



Figure A.3.3 - NP vs. AP for 1994 and 1997 data



Figure A.3.4 - NP vs. AP



Figure A.3.5 - Total Sufate/Total Sulfur (%) vs. paste pH (SU)



Figure A.3.6 - NAG pH Frequency Distribution by Lithology*

* No samples of andesite were analysed by NAG testing



Figure A.3.7 - Paste pH vs. NNP, NAG



Figure A.3.8 - Kinetic Test Results for pH vs Time



Figure A.3.9 - Kinetic Test Results for Electrical Conductivity vs Time



Figure A.3.10 - Kinetic Test Results Alkalinity and Acidity vs Time



Figure A.3.11 - Kinetic Test Results for Sulfate vs Time



Figure A.3.12 - Kinetic Test Results Copper vs Time



Figure A.3.13 - Kinetic Test Results for Iron vs Time



Figure A.5.1 - Percent Visible Sulfide Frequency Distribution by Lithology



Figure A.5.2 - Histogram of Paste pH for All Dumps



Figure A.5.3 - Paste Conductivity Frequency Distribution by Dump



Figure A.5.4 - NAG Frequency Distribution by Dump



Figure A.5.5 - Percent Visible Sulfide Frequency Distribution by Dump



Figure A.6.1 - NP vs. AP by Weathering Status



Figure A.6.2 - Sulfide vs. Sulfate by Weathering Status



Figure A.6.3 - NAG pH vs. Total Sulfur



Figure A.6.4 - Sulfate/Total Sulfur vs. Sulfide

Table A.1.1
Numbers of samples analysed in the Waste Rock Characterization Program

Test	Number of Samples Analyzed		
	Phase I EIS	Phase II WMP	Total
Paste pH/Conductivity	19	93	112
Total Metals (ICP)	2	0	2
Acid Base Accounting (ABA)	19	28	47
Net Acid Generating (NAG)	0	59	59
EPA 1312	1	0	1
Kinetic Testing	5	0	5
Physical Tests*	1	0	1

EIS = Environmental Impact Statement
WMP = Waste Management Plan
* Gradation, Modified Proctor, Hydraulic Conductivity

Table A.1.1
Numbers of Samples Analyzed in the Waste Rock Characterization Program

Test	Number of Samples Analyzed		
	Phase I EIS	Phase II WMP	Total
Paste pH/Conductivity	19	93	112
Total Metals (ICP)	2	0	2
Acid Base Accounting (ABA)	19	28	47
Net Acid Generating (NAG)	0	59	59
EPA 1312	1	0	1
Kinetic Testing	5	0	5
Physical Tests*	1	0	1

EIS = Environmental Impact Statement
WMP = Waste Management Plan
* Gradation, Modified Proctor, Hydraulic Conductivity

Table A.1.2
Number of Tests on Samples of Each Rock Type

	Rock Type					Total
	Quartz Monzonite	Quartz Breccia	Biotite Breccia	Andesite	Quartz Vein	
Number of Samples	91	8	24	2	6	131
Paste pH/Conductivity	91	8	24	1	6	130
Total Metals (ICP)	2	--	--	--	--	2
Acid Base Accounting (ABA)	31	2	10	1	2	46
Net Acid Generating (NAG)	33	6	17	--	3	59
EPA 1312	1	--	--	--	--	1
Kinetic Testing	5	--	--	--	--	5
Physical Tests*	1	--	--	--	--	1

EIS = Environmental Impact Statement
WMP = Waste Management Plan
* Gradation, Modified Proctor, Hydraulic Conductivity

Table A.3.2
Extractable Metals Concentrations in Waste Rock

Parameters (mg/L)	WD-1
pH	3
Conductivity (mmhos/cm)	5.6
Sulfate	3050
Acidity (as $CaCO_3$)	1050
Alkalinity (as $CaCO_3$)	0
Aluminum	151
Antimony	N/A
Arsenic	< 0.1
Barium	0.09
Boron	0.10
Cadmium	0.019
Calcium	314
Chloride	6
Chromium	0.03
Cobalt	0.29
Copper	13.6
Fluoride	1.2
Iron	102
Lead	< 0.021
Magnesium	23
Manganese	3.35
Mercury	< 0.0002
Molybdenum	<0.01
Nickel	0.11
Potassium	4
Selenium	< 0.1
Silver	< 0.01
Sodium	13
Vanadium	< 0.01
Zinc	0.87

Table A.3.3
Results of ABA Testing of Column Samples

Sample Number	SW-1	PW-2	LGSSP-2	C10-190-199-2	IDC-24-222-241
Rock Type	qm	qb	qm	qm	qm
Classification	oxidized	transitional	oxidized	unoxidized	unoxidized
Total Sulfur (%)	1.36	0.37	0.61	3.59	1.74
Sulfate (%)	0.01	0.01	0.01	0.07	0.01
Sulfide (%)	1.36	0.37	0.61	3.52	1.74
AP	42	11	19	110	54
NP	36	11	39	44	31
NNP	-6	0	20	-66	-23
NP:AP	0.86	1.00	2.05	0.40	0.57

Table A.3.4
Results of Kinetic Test Work

Sample Number	SW-1	PW-2	LGSSP-2	C10-190-199-2	IDC-24-222-241
Total Sulfur (%)	1.36	0.37	0.61	3.59	1.74
Sulfate (%)	0.01	0.01	0.01	0.07	0.01
Sulfide (%)	1.36	0.37	0.61	3.52	1.74
AP	42	11	19	110	54
NP	36	11	39	44	31
NNP	-6	0	20	-66	-23
NP:AP	0.86	1.00	2.05	0.40	0.57
Estimated Time to Depletion (years)					
NP (from stoichiometry)	286	220	126	253	389
AP (from sulfate)	1262	382	263	1051	2842
Pseudo Steady State Release Rate kg CaCO3 eq./tonne/week					

Table A.4.1

Chemistry of West Dump Seep (August, 1997)

Parameter	W-Waste All in mg/l unless otherwise stated
pH (std. units)	3.03
Alkalinity (mg/l $CaCO_3$ equiv.)	0.
Bicarbonate	0.
Carbonate	0.
Sulfate	22,100.
Total Dissolved Solids	25,440.
Chloride	16.
Fluoride	0.31
Nitrate_N	4.7
Iron	310.
Copper	1,800.
Arsenic	0.14
Aluminium	2,100.
Barium	<0.05
Beryllium	0.49
Boron	0.21
Calcium	410.
Cadmium	0.82
Cobalt	9.9
Nickel	1.3
Thallium	0.02
Manganese	170.
Zinc	38.
Molybdenum	0.28
Selenium	0.11
Magnesium	580.
Sodium	20.
Potassium	<1

Table A.6.1
Copper Flat Project
Waste Rock Classification System

Waste Rock Type	Criteria No. 1 Visual	Criteria No. 2 Paste pH (s.u.)	Criteria No. 3 Paste Conductivity (uS)	Criteria No. 4 AP (T/KT)	Criteria No. 4 NAG	Required Criteria
Oxidized	No visible sulfides, loss of texture, strong oxide staining	>5.0	<500	<1.6	0	(1, 2 and 3) or (1 and 4)
Transition	Visible sulfides, loss of texture, strong oxide staining	<5.0	>500	>1.6	>0	1
Unoxidized	Visible sulfides, fresh appearance, minor feox staining	>5.0	<500	>10	>0	1,2 and 3
Low sulfide	Few visible sulfides, fresh appearance	>5.0	<500	<10	0	1 through 4

Notes:
(1) AP criteria for identification of oxidized and transition waste based on a total or sulfide sulfur content of 0.05 percent
(2) NP of unoxidized waste is typically greater than 30 T/KT, therefore AP criteria for low sulfur waste is for an NP:AP ratio near 3:1 and sulfur content of 0.32 percent
(3) Acid producing potential (AP) by syulfur analysis and NAG are alternatives for criteria No. 4

N 720000

N 718000

N 716000

T15S, R7W

GRAYBACK GULCH

115 KV LINE

E 594000

E 592000

E 594500

E 596000

W.L. 5442.3

No.	DESCRIPTION	BY	DATE

REVISIONS

PREPARED FOR:

PREPARED BY:

SRK Consulting
Engineers and Scientists

REFERENCE

DESIGNED	JP	12/98
DRAWN	TAD	12/98
CHECKED		
APPROVED		
APPROVED		

TITLE: COPPER FLAT MINE
SAMPLE LOCATIONS
AND PIT GEOLOGY

DRAWING No.: 68612-001

SHEET No. 1 OF 1

SCALE: 1"=200'

PROJECT No.: 68612

DRAWING NAME: 68612-001

A

REVISION

APPENDIX A.1

TESTING PROTOCOLS

Paste pH and TDS
Acid Base Accounting
Modified EPA 1312 test
Humidity Columns
Net Acid Generation (NAG) Test

FIELD PASTE pH and CONDUCTIVITY

Objectives

- To determine the pH and conductivity of the pore water resulting from dissolution of secondary mineral phases on the surfaces of oxidized rock particles.
- To indicate whether oxidation, and accumulation of contaminants in the form of secondary mineral phases, has occurred in the waste rock prior to collection of the sample.

Principles of Test

Water is added to the sample to form a paste or slurry thus mobilizing secondary mineral phases and providing a medium accessible to the pH and conductivity or TDS probe. The probe is placed in the paste or slurry and the pH or conductivity value is read directly from the meter.

Equipment

1. pH meter equipped with a combination pH electrode.
2. Conductivity or TDS meter (in this case a Hanna Instruments field combined pH/ORP/temperature meter).
3. 50 mL beakers, or equivalent (disposable paper cups are recommended).
4. Spatula or stirring rod (eg. plastic coffee stirrers).
5. Litmus paper strips.

Reagents

1. Standard buffer solution, pH 4.00 and pH 7.00.
2. Standard electrolyte solutions (for calibration of conductivity meter).
3. Distilled (or deionized) water.

Procedure

1. Calibrate pH and conductivity or TDS meters using the standard solutions and following the instructions provided with the meters.

2. Obtain approximately 25 g of fines (particles smaller than 1 mm if possible) from the rock sample to be tested, and place in a fresh or decontaminated beaker or testing vessel.

3. Add approximately 25 ml of distilled water to sample. (More water may be required if the sample is very dry or extremely fine.)

4. Stir sample with fresh or cleaned spatula to form a paste or slurry. Paste should slide off spatula easily.

5. Tip the testing container to one side to allow a pool of water or slurry to collect in the corner. Dip each of the probes into the slurry, and allow the meter readings to stabilize. The conductivity reading should, however, be done first, as electrolyte from the combination pH probe may affect the conductivity of the solution.

6. Decontaminate probes and containers using distilled or de-ionized water.

7. Record the measurements in your field notebook along with a description of the rock type tested, and the general appearance of the sample.

Alternatives

For a coarser rock mixture, wet the surface of the rock with distilled water, and mix water with any surface coatings or fines. Place a piece of litmus paper over the wetted area. Compare the color of the litmus with the pH color-coded scale and record pH.

Calculations

Paste TDS is assessed by measuring Electrical Conductivity (EC) and then converting conductivity values to TDS using the equation (Hem, 1985):

$$0.59\left[EC, FScm^{-1}\right] = \left[TDS, mg/l\right]$$

Interpretation

High conductivity (or TDS) levels indicate there is a considerable store of contaminant salts. These are usually sulfates, but can be other metal salts. When a sample is collected over depth, it is not always clear whether the stored salts are due to oxidation at that point in the sediment profile, or if the salts were generated somewhere higher in the profile and moved downwards to the sample location. Look for stains along the flow path that may indicate if this is the case.

Low pH readings indicate oxidation and acid generation has occurred, usually at the location from which the sample was collected. Readings taken on uncrushed samples in the field or lab usually provide a much better indication of the extent of oxidation than crushed samples. This is because crushing can liberate neutralizing minerals thereby increasing the available neutralizing capacity of the sample.

References

Sobek, A.A., Schuller, W.A. Freeman, J.R. and Smith, R.M., 1978, Field and Laboratory Methods Applicable to Overburden and Minesoils, EPA 600/2-78-054, 203pp.

British Columbia AMD Task Force, 1989, Draft Acid Rock Drainage Technical Guide, Vol I, Crown Publications, Victoria, B.C.

MODIFIED ACID BASE ACCOUNTING (ABA)

Objectives

- To determine the balance between acid producing and acid consuming components of mine waste.

Principles of Test

The fundamental principals of acid base accounting comprise two distinct measurements:

1. Determination of the neutralization potential (NP) of a sample.

2. Calculation of the acid potential (AP) of the sample.

The difference between the two values, the net neutralization potential (Net NP), and the ratio (NP:AP) allow classification of the sample as potentially acid consuming or producing. To facilitate comparison of values, NP, AP, and Net NP are all expressed in units of tons $CaCO_3$ equivalent per kiloton.

In the original Sobek method of acid base accounting, the neutralization potential is determined by heating the sample and mixing for two hours. In the modified method, the neutralization potential is determined by treating a sample with excess standardized hydrochloric acid at ambient, or slightly above (25 - 30°C) ambient, temperatures for 24 hours. A fizz test is employed to provide a guide to the amount of acid to be initially added to the test. Acid is added as required during the acid-treatment stage to maintain sufficient acidity for reaction. After treatment, the unconsumed acid is titrated with standardized base to pH 8.3 to allow calculation of the calcium carbonate equivalent for the acid consumed.

For the calculation of the acid potential, the sample is analyzed for total and sulfate sulfur. Sulfide sulfur content is also measured or is calculated by the difference between the other two sulfur numbers. AP is determined from sulfide sulfur number, assuming: 1) total conversion of sulfide to sulfate; and, 2) production of 4 moles H^+ per mole of sulfide oxidized, assuming that all the sulfide is present as pyrite. In some cases, difficulties associated with the analytical procedures for sulfide analysis may

influence the estimation of the acid generation potential. For example, sulfate associated with the mineral barite is not readily distinguished from sulfide in a typical sulfate analysis, but does not contribute to the acid potential.

Equipment

1. Aluminum foil.
2. 250 mL Erlenmeyer flask.
3. Reciprocating shaking apparatus or other suitable agitation device.
4. Burette, 50 or 100 mL, one for each of the acid and the base solutions.
5. pH meter, equipped with a combination pH electrode.

Reagents

1. Distilled (or deionized) water, preferably CO2-free (store in container equipped with an ascarite tube)
2. Certified grade, 0.1 N hydrochloric acid, for standardization of bases
3. Approximately 0.1 N sodium hydroxide, standardized.
4. Approximately 0.5 N sodium hydroxide, standardized.
5. Approximately 0.1 N hydrochloric acid, standardized.
6. Approximately 0.5 N hydrochloric acid, standardized.
7. Approximately 25 percent strength hydrochloric acid, for fizz test.
8. Buffer solutions (pH 4.00 and 7.00) for calibration of pH meter.

Procedure

1. Crush and pulverize the sample to a target size of 80 percent minus 60 mesh (Tyler). Tailings samples should be tested at the received particle size.
2. Submit a sample of the test material for total sulfur and sulfate sulfur analyses.

3. Use certified 0.1 N hydrochloric acid to standardize the 0.1 N and 0.5 N sodium hydroxide solutions to standardize the 0.1 N and 0.5 N hydrochloric acid solutions.

4. Place approximately 0.5 g of pulverized sample on a piece of aluminum foil in a small shallow dish. Add one or two drops of 25 percent HCl to the sample. The presence of carbonate will be indicated by a bubbling or an audible "fizz". Rate the "fizz" as indicated in Table 1.

Volume and Normality of HCl for Use in NP

Determination on Basis of Fizz Rating (2g Sample)

Fizz Rating	HCl (mL, Normality)	
None	20	0.1
Slight	40	0.1
Moderate	40	0.5
Strong	80	0.5

5. Weigh 2.00 g of the sample (minus 60 mesh) into a 250 mL Erlenmeyer flask and, as a first approximation, add the volume and normality of HCl as indicated by the "fizz" rating shown above.

6. Agitate the contents of the flask for 24 hours by placing on a shaking apparatus. At least once in the treatment period, and preferably after approximately 6 hours of reaction, check the pH of the pulp. If the pH is above 2.0, add an appropriate volume of hydrochloric acid of the same strength originally added (generally between 1.5 to 2.0 ml). Record the amount added for back titration.

7. At the end of the shaking period, check the pulp pH. If the total volume and strength of acid was appropriate, the end pH will be in the range 1.5 - 2.0. If the pH is above this range, the amount of acid added is judged to be insufficient for reaction. If the pH is below the range, the amount of acid added is judged to be

too high, causing over reaction. In either case, repeat the test using the next higher or lower volume or strength of HCl as appropriate.

8 Titrate the contents of the flask using 0.1 N or 0.5 N NaOH (corresponding to the normality of HCl used in step 4) to pH 8.3. Titrate with NaOH until a constant reading of 8.3 remains for at least 30 seconds.

Calculations

1. The neutralization potential, NP, of the sample is given by:

$$NP = \frac{50a[x - (b/a)y]}{c}$$

where NP = neutralization potential in tonnes $CaC0_3$ equivalent per 1000 tonnes of material

a = normality of HCl

b = normality of Na0H

c = sample weight in grams

x = volume of HCl added in mL

y = volume of Na0H added to pH 7.0 in mL

2. The acid potential, AP, of the sample in kg CaC03 equivalent per ton, is given by:

$$AP = \text{Percent sulphide sulfur x } 31.25$$

where,

sulphide sulfur = total sulfur - sulfate sulfur

3. The net neutralization potential, Net NP, in kg CaC03 equivalent per ton of material is given by:

$$Net\ NP = NP - AP$$

Reporting of Results

The results of the test should be tabulated to provide the following information:

Sample description, paste pH, total sulfur analysis (% S_T), sulfate sulfur analysis (% $S(SO_4)$, NP (kg $CaC0_3$ equivalent per ton), AP (kg $CaC0_3$ equivalent per ton), Net NP (kg $CaC0_3$ equivalent per ton).

References

Lawrence, R.W., Poling, G.P. and Marchant, P.B., 1989. Investigation of predictive techniques for acid mine drainage. Report on DSS Contract No. 23440-7-9178/01-SQ, Energy Mines and Resources, Canada, MEND Report 1.16.1 (a).

Sobek, A.A., Schuller, W.A. Freeman, J.R. and Smith, R.M., 1978, Field and Laboratory Methods Applicable to Overburden and Minesoils, EPA 600/2-78-054, 203pp.

STATIC NET ACID GENERATION (NAG) TEST PROCEDURE

Objectives

- To determine the net acid remaining, if any, after complete oxidation of the materials with hydrogen peroxide and allowing complete reaction of the acid formed with the neutralizing components of the material. The NAG test provides a direct assessment of the potential for a material to produce acid after a period of exposure and weathering and is used to refine the results of the theoretical ABA predictions.

Principles of the Tests

After neutralization is completed, by reaction with hydrogen peroxide, the remaining H_2SO_4, if any, is titrated with sodium hydroxide. The amount of NaOH needed is equivalent to the NAG of the material (expressed in kg H_2SO_4/tonne material).

Sample Preparation

Tailings samples can be tested 'as received'.

Reagents

1. H2O2 - BDH 'Analar' Analytical Reagent 30% w/v (100 V), or equivalent, diluted 1:1 with deionized H2O to 15% a.

2. NaOH - 0.50M Standardized Solution.

3. NaOH - 0.10M Standardized Solution.

Procedure:

Add 250 mL of reagent 1 (15% H_2O_2) to 2.5 g of tailings (pulverized sample if testing waste rock) sample in a 500 mL wide mouth conical flask, or equivalent. Cover with a watch glass, and place in a fumehood or well-ventilated area [b]. The H_2O_2 should be at room temperature before commencing test.

Allow sample to react until 'boiling' or effervescing ceases. Heat sample on hot plate and gently boil until effervescence stops or for a minimum of 2 hours. Do not allow sample to boil dry - add deionized water if necessary.

Allow solution to cool to room temperature then record final pH (NAGpH).

Rinse the sample that has adhered to the sides of the flask down into the solution with deionized water. Add deionized water to give a final volume of 250 mL.

Titrate solution to pH 4.5 while stirring with appropriate NaOH concentration based on final NAG solution pH as follows:

NAG Solution pH	Reagent	NaOH Concentration
>2	3	0.10 M
≤2	2	0.50 M

[a] The pH of the H_2O_2 used in the NAG test should be checked to ensure it is between pH 4 and 7. If the pH is less than 4 then add dilute NaOH (use a solution made up by adding 1 g NaOH to 100 mL deionized H_2O) until the pH is greater than 4 (aim for a pH between 4 and 6). The pH is adjusted to greater than pH 4 to ensure that the phosphoric acid, used to stabilize H_2O_2 in some brands, is neutralized. The pH of the 15% H_2O_2 should always be checked to ensure that any stabilizing acid is neutralized, otherwise, false positive results may be obtained.

[b] The NAG reaction can be vigorous and sample solutions can 'boil' at temperatures of up to 120°C. Great care must be taken to place samples in a well-ventilated area or fume cupboard.

Calculations

The NAG capacity is determined by titration of the sample to determine the net amount of acid generated by peroxide oxidation.

Net Acid Generation:

$$NAG = \frac{49 \times V \times M}{W}$$

Where:

NAG = net acid generation (kg H_2SO_4/tonne)

V = volume of base NaOH titrated (mL)

M = molarity of base NaOH (moles/L)

W = weight of sample reacted (g)

NOTE: If NAG value exceeds 25 kg H_2SO_4 per tonne, repeat using a 1.00 g sample.

Interpretations

The NAG capacity is an independent measure of the acid generating potential of a sample. Materials should be classified based on the table given below.

SAMPLE CATEGORY	FINAL NAGpH	NAG VALUE kg H_2SO_4/t	NNP kg/ton $CaCO_3$
POTENTIALLY ACID FORMING			
Higher capacity	<4	>10	positive
Lower capacity	<4	≤10	negative
UNCERTAIN [1]	≥4	0	positive
NON-ACID FORMING [2]	≥4	0	positive

[1] Further evaluation including sulfur forms and mineralogy

[2] Acid consuming materials are identified by NNP values less than approximately -100

References

Miller, S., Robertson, A., and Donohue, T. (1997). Advances in Acid Drainage Prediction Using the Net Acid Generation (NAG) Test. In: *Proceedings of the Fourth International Conference on Acid Rock Drainage, Vancouver, B.C., Canada, 1997,* vol II, pp. 535-547.

Lewis, H.S., Susteyo, W., Miller, S.D., and Jeffery, J.J. (1997). Waste Rock Management Planning and Implementation at P.T. Freeport Indonesia Company's Mining Operations in Irian Jaya. In: *Proceedings of the Fourth International Conference on Acid Rock Drainage, Vancouver, B.C., Canada, 1997,* vol III, pp. 1361-1376.

EPA 1312 Leach Extraction Test

Objectives

- To characterize and quantify the soluble contaminant content of waste rock samples.

Principles of Test

The sample is mixed with distilled water, and is agitated in a flask to allow dissolution of the contained, soluble secondary mineral phases. The solution is collected at the end of the test, filtered, and analysed for immediate parameters (pH, alkalinity, acidity, sulfate, and conductivity) and for contained metals.

This test method is modified from the EPA method 1312 by using a ratio of water to solids of 2:1 or 3:1 rather than 20:1. The less dilution reduces the possibility of metal concentrations below detection.

Equipment

1. Erlenmeyer Flask (500 mL to 1 L, depending on sample size).

2. pH and conductivity meters.

3. Water filtering apparatus and filters.

4. Reciprocating shaking apparatus or other suitable agitation device.

Reagents

1. Distilled Water.

2. Calibration standards for pH and conductivity.

Procedure

1. Split a representative sample of approximately 200 to 500 g from the field sample, and determine exact weight. Place in Erlenmeyer Flask. The amount of sample is at the discretion of the technician, but should be increased if the particle sizes are large or the variation between the different particles is high.

2. Add distilled (or de-ionized) water to the sample to obtain a water to solids ratio of exactly 2:1 by weight. Cap the Erlenmeyer flask and place in agitation device.

3. Agitate the slurry for a total period of 23 hours. Terminate the agitation process and allow suspended solids to settle for one hour prior to termination of the test.

4. Remove the clear decant and filter the solution immediately, using a standard 0.45 µm millepore filter. Remove a small portion of the filtrate and determine the conductivity and pH.

5. Solution samples are submitted for analysis of immediate parameters (pH, alkalinity, acidity Eh, and conductivity) and for constituent concentrations (ICP metal scan and sulfate).

Note:Analytical procedures for radionuclide analyses generally require larger eluate concentrations. Therefore, a larger volume of solid will be required.

Interpretation

Soluble salt and radionuclide contents are calculated from the eluate constituent concentration and volume, and are reported per unit mass of waste rock.

Solubility controls on the solution concentrations should be checked by assessing saturation indices for the contaminants of concern. This may be done rapidly by using a geochemical equilibrium model such as MINTEQA2 or equivalent. Where saturation conditions are indicated, consecutive extraction tests should be performed to determine the total soluble component loading from the cumulative constituent release by the waste rock sample.

References

The field extraction test is modified from a number of different sources, including the EPA series of extraction tests.

Humidity Column Testing

Objectives

The intent of humidity column testing procedures is to simulate as many of the field conditions as is practical. These conditions include:

- representative particle size distributions for the fine fraction (less than 4") within the mine rock; and
- flushing rates encountered under normal circumstances in mine rock piles at the site;
- contact time between the leachate and the rock, usually the flowpath length.

To accomplish this, a large volume of rock is used for the testing, approximately 5 - 8 kg. The rock is graded to represent the 4-inch minus fraction of the rock contained in the rock piles. The site precipitation levels are evaluated on a surface area basis. The diameter of the column is adjusted (within a reasonable limit) to provide enough leachate for the analysis. The flow path (column length) should be approximately 1.5 times greater than the diameter of the column. During the column operation, water is trickled over the rock for 2 days. Air that is humidified by bubbling it through water at a temperature slightly above room temperature, is introduced at the bottom of the column for 5 days of each cycle. Usually the test is carried out for 20 weeks, with weekly analysis of key parameters (pH, alkalinity, acidity, conductivity, Eh, sulfate). Metals are typically measured on a weekly basis until "steady state" conditions have been achieved. After 10 weeks of testing, the frequency of metals analysis can be reduced to every other week, or less, depending on the test results to that time. A typical humidity column is shown in the figure below.

Procedure

1. Examine site precipitation records over a typical yearly period. If there is a seasonal rainy period, determine the average weekly precipitation during that period. Look at the pattern of this rainfall, i.e. is it a steady drizzle over a few days, or heavy rain over a few hours. The water addition rate to the column should follow this pattern as closely as is possible.

2. Calculate the rate of water addition to the column. Start with a minimum column diameter of 30 cm.

eg. rainfall = 10 mm/week over the rainy season
column = 30 cm diameter (0.152 metres radius)
SA column = pr2 = 3.14 (0.152)2 = 0.073
irrigation volume = 0.010 m/wk x 0.073 m2 = 0.00073 m3/wk = 0.73 L/wk

If this volume seems reasonable, use the 30 cm column. If it is not sufficient to satisfy the sample volume requirements for the weekly analyses, the column diameter should be increased until this is satisfied.

3. Once the column diameter has been determined, the rock sample height is obtained by multiplying the diameter by 1.5. The equipment should provide some freeboard above the rock column height (approximately 5 to 10 cm).

   The columns can be constructed out of almost any "inert" plastic cylinder. ABS or PVC pipe provides good strength and durability at a reasonable cost. Plexiglass also works well, but is usually expensive, especially for the large diameter columns.

   As illustrated in Figure D.5.1, the column must have a raised screen constructed about an 2 cm from the bottom, and a solid base through which the leachate is collected. All joints are sealed with a high quality flexible plumbing sealing. (There are supports in the void between the perforated base and the base plate). Humidified air is added through an additional port at the base of the column (not shown). Several layers of Teflon mesh areplaced above the perforated plate to prevent washing of fines from the sample into the collection zone. During the column operation, a clear plexiglass cover is placed over the column to prevent excessive evaporation losses.

4. Water addition

   Water is applied to the column using a peristaltic pump. This can be automated with a timer that pulses water, in a fine spray, over the surface of the rock. Water can also be applied as a continuous drip over one area of the column. Dispersal of water can be achieved in a number of ways, eg. glass rods, plastic tubing, or possibly plastic pellets. (Our experience is that glass wool provides a significant source of alkalinity, and should not be used.)

5. At the start of the test, the dry rock will absorb a considerable amount of water. For the first week, humidified air should be added continuously to the column, to

wet the surfaces of the rock and initiate the oxidation process. Once good water recovery (80%) has been achieved, the regular weekly cycle should commence. A typical cycle is described below.

a) Humid Aeration Cycle - for five days, humidified air is added at the base of the columns;

b) Flush Cycle - de-ionized water is added to the column over a two day period. Water is added via a continuous drip dissipated over the top surface of the rock column.

c) Leachate Collection - the column is allowed to drain for 4 hours after the flush cycle is terminated. At the end of the drain cycle the leachate is collected and analyzed.

The test should be run for at least 20 weeks. Test results should be evaluated periodically. After 20 weeks, if the results are inconclusive, the program may need to be extended.

6. Solution samples are submitted for analysis of immediate parameters (pH, alkalinity, acidity Eh, and conductivity) and for constituent concentrations (ICP metal scan and sulfate) on a weekly basis.



Humidity Column Design

APPENDIX A.2

PASTE pH AND CONDUCTIVITY DATA

ACID BASE ACCOUNTING DATA

and

NET ACID GENERATION DATA

1997 Surface Sample Analyses

Sample	Type	Lithology	Visible sulfide %	EC	Paste pH	NAG kg/T H_2SO_4	NAG pH	Sulfate %	Sulfide %	Sulfur Total %	SO_4/S %	AGP m/g $CaCO_3$	NP m/g $CaCO_3$	NNP	NP:AP
ERD 5500 001	T	QM	1	3140	3.63	29.60	5.11	0.71	0.74	1.45	48.97	45.3	18.9	-26.4	0.42
ERD 5500 002	HS	QB	4	19	7.94	15.48	2.48	0.44	2.46	2.9	15.17	53.1	62.5	9.4	1.18
ERD 5500 004	LS	QM	1	430	5.31										
ERD 5500 005	LS	QM	1	595	3.31										
ERD 5500 006	LS	QM	1.5	891	5.72										
ERD 5500 009	HS	BB	10	4000	2.71	80.75	6.30	0.6	2.3	2.9	20.69	91	9.1	-81.9	0.10
ERD 5500 010	LS	QM	1.5	471	4.55	19.99	3.92								
ERD 5500 012	HS	QM	2	1928	2.71										
ERD 5500 014	HS	QM	2	4370	2.73										
ERD 5510 002	LS	QM	1.5	257	4.71										
ERD 5560 001	O	AN			9.14			0.01	0.005	0.01	100.00	0.3	23.2	22.9	77.33
ERD 5560 002	HS	QM	8	467	6.76			0.3	2.6	2.9	10.34	90	23.7	-66.3	0.26
ERD 5560 006	HS	QB	2	1305	3.38										
ERD 5560 008	HS	QV	5	330	4.08			0.47	1.7	2.2	21.36	68	2	-66	0.03
ERD 5560 010	LS	QM	1.5	708	4.55	23.62	3.87								
ERD 5560 011	HS	QB	3	1565	4.54	22.05	4.07								
ERD 5600 001	LS	QM	1	450	4.44			0.1	0.43	0.53	18.87	17	0.1	-16.9	0.01
ERD 5600 003	HS	QB	3	4230	2.9	33.81	3.19	0.96	1.3	2.2	43.64	69	0.1	-68.9	0.00
ERD 5600 005	T	QB	0.5	2700	3.23	27.05	4.34								
ERD 5600 007	T	QM	0.5	174	6.88	14.31	2.68								
ERD 5600 009	T	QM	0.5	657	4.73										
ERD 5600 011	T	QM	0.5	847	5.43										
ERD 5600 012	T	QM	0.5	254	6.82										
ERD 5600 013	HS	QM	2	321	5.17										
ERD 5600 014	HS	BB	2	2080	3.55										
ERD 5600 070	HS	BB	4	227	4.92	11.27	2.45								
NRD 5620 001	HS	BB	4	41	5.05	10.68	3.41								
NRD 5620 001	HS	QB	5	1193	2.91	19.80	2.45								
NRD 5620 002	HS	QB	6	1717	2.68	77.62	2.98	0.3	2.6	2.9	10.34	90	23.7	-66.3	0.26
NRD 5620 003	HS	QM	4	1111	3.56	57.33	4.12	0.2	1.6	1.8	11.11	55	0.1	-54.9	0.00
NRD 5620 004	O	QM			4.75			0.17	0.1	0.18	94.44	5.6	0.1	-5.5	0.02
NRD 5620 005	T	QV	1	2170	2.81	9.60	4.81								
NRD 5620 006	HS	QM	2	260	3.68										
NRD 5620 007	HS	QM	2	1009	2.98										
NRD 5620 008	HS	QM	3	235	4.13	42.63	5.90	0.15	1.1	1.3	11.54	40	0.8	-39.2	0.02
NRD 5620 009	HS	QM	2	663	3.28										
NRD 5620 010	HS	QM	2	128	3.86										
NRD 5620 011	HS	QM	2	1219	2.68	39.69	3.51	0.28	0.92	1.2	23.33	36	0.1	-35.9	0.00
NRD 5620 012	HS	QB	4	997	2.75	58.80	4.08	0.2	1.6	1.8	11.11	57	0.1	-56.9	0.00
NRD 5620 013	HS	QM	2	2240	2.62										
NRD 5620 014	HS	QB	20	4860	2.5	223.44	3.65	0.9	6.2	7.1	12.68	220	0.1	-219.9	0.00
NRD 5620 015	HS	QB	2	1075	3.71										
NRD 5620 016	HS	QM	2	3390	2.51										

1997 Surface Sample Analyses

Sample	Type	Lithology	Visible sulfide %	EC	Paste pH	NAG kg/T H_2SO_4	NAG pH	Sulfate %	Sulfide %	Sulfur Total %	SO_4/S %	AGP m/g $CaCO_3$	NP m/g $CaCO_3$	NNP	NP:AP
NRD 5650 017	LS	QM	1	41.4	6.09	23.72	4.11	0.13	0.22	0.35	37.14	11	0.1	-10.9	0.01
NRD 5650 018	HS	QM	2	89	4.82										
NRD 5650 019	HS	QM	2	3620	2.79	46.35	4.40	0.1	1.3	1.4	7.14	45	0.1	-44.9	0.00
SRD 5470 006	HS	QM	2	63	5.94										
SRD 5470 010	LS	QM	1	196	7.05	8.72	2.51								
SRD 5470 011	HS	QV	5	2200	2.54	43.51	3.10	0.21	1.3	1.5	14.00	47	6.7	-40.3	0.14
SRD 5470 012	HS	QB	6	182	7.63			0.46	1.4	1.9	24.21	59	38.9	-20.1	0.66
SRD 5470 013	HS	QM	3	821	4.4										
SRD 5470 014	HS	QB	4	62.9	5.26	5.88	2.29								
SRD 5470 015	HS	QM	3	118.5	5.55										
SRD 5470 016	HS	QM	4	89.6	7.06										
SRD 5470 016	HS	QV	5	6570	2.66										
SRD 5470 017	HS	QB	4	27	5.02	21.56	2.27								
SRD 5470 018	HS	QB	5	1703	3.08										
SRD 5470 019	HS	QV	5	229	4.55										
SRD 5470 020	HS	QM	3	162	7.83	12.74	2.47	0.31	1.1	1.4	22.14	44	36.4	-7.6	0.83
SRD 5470 021	HS	QB	4	321	4.32										
SRD 5470 022	HS	QM	2	386	6.03										
SRD 5470 023	HS	QM	4	27	5.51										
SRD 5470 024	HS	QM	5	3970	2.52										
SRD 5470 025	HS	QM	3	172.2	5.21										
SRD 5470 027	HS	QM	2	3520	2.72	15.78	2.52								
SRD 5490 007	O	QM		42	8.76	19.70	3.32								
SRD 5500 001	HS	QM	2	831	5.31	8.23	4.10	0.37	0.7	1.1	33.64	33	34.2	1.2	1.04
SRD 5500 002	HS	BB	4	33	7.38	22.05	4.63								
SRD 5500 003	O	BB		58.7	4.75										
SRD 5500 004	HS	QB	4	231	5.5										
SRD 5500 005	HS	QV	5	292	6.05	19.01	3.96								
WRC 5440 30	HS	QM	2	227	4.1	15.88									
WRC 5440 31A	LS	QM	0.5		7.91			0.23	0.32	0.55	41.82	33	34.2	1.2	1.04
WRC 5440 31B	T	QM	0.5		8.35			0.21	0.11	0.32	65.63	10	10.1	0.1	1.01
WRC 5440 32	O	QM		347	6.55			0.19	0.05	0.24	79.17	7.5	9.6	2.1	1.28
WRC 5480 006	HS	QB	5	3680	3.7	31.46									
WRC 5480 007	HS	QB	5	1643	3.18	33.52									
WRC 5480 007	HS	QV	5	550	3.41	32.73									
WRC 5480 008	HS	QM	2	785	3.67	15.09									
WRC 5480 009	HS	BB	3	764	3.73	32.54									
WRC 5480 010	HS	BB	4	1338	3.76	28.71									
WRC 5480 012	LS	QB	1	589	4.01	33.81									
WRC 5480 013	LS	QM	1	297	6.95	15.19									
WRC 5480 014	T	QB	0.5	801	4.12	20.19		1.25	0.89	2.08	60.10	65	47.6	-17.4	0.73
WRC 5480 015	HS	QM	2	826	3.42										
WRC 5480 016	LS	QM	1	470	6.26										
WRC 5480 018	HS	QM	2	4840	3.02										

1997 Surface Sample Analyses

Sample	Type	Lithology	Visible sulfide %	EC	Paste pH	NAG kg/T H_2SO_4	NAG pH	Sulfate %	Sulfide %	Sulfur Total %	SO_4/S %	AGP m/g $CaCO_3$	NP m/g $CaCO_3$	NNP	NP:AP
WRC 5480 019	HS	QM	2	3020	2.66										
WRC 5480 020	HS	QM	2	878	3.96										
WRC 5480 021	HS	QM	2	1009	4.38										
WRC 5480 022	HS	QM	2	1850	2.97										
WRC 5480 023	HS	QM	2	1880	2.64										
WRC 5480 024	HS	QM	1.5	1190	2.71										
WRC 5480 025	LS	QM	1	637	8.6										
WRC 5480 026	LS	QM	1	129	9.65										
WRC 5480 027	HS	QM	2	1580	2.12										
WRC 5480 028	HS	QM	2	964	4.89										
WRC 5480 029	HS	QM	2	580	3.59										
WRC 5480 030	HS	QM	2	258	5.85										
WRC 5580 005	T	QV(Sternberg)pw2	2	19000	3.79										
WRD 4480 010	LS	QM	1	50	6.06										
WRD 5560 020	LS	QM	1	64	6.72										
WRD 5560 027	HS	QM	2	3990	2.56										
WRD 5560 028	HS	QM	2	730	2.95										
WRD 5560 029	HS	QM	2	1552	2.53										
WRD 5560 030	HS	QM	2	321	4.64										
WRD 5560 031	HS	QM	2	282	4.4										
WRD 5560 032	HS	QM	2	620	2.99										
WRD 5560 034	HS	QM	2	201	3.95										
WRD 5560 035	HS	QM	2	833	4.35										
WRD 5560 036	HS	QM	2	171	3.79										
WRD 5560 037	HS	QM	2	164	7.8										
WRD 5560 038	HS	QM	5	54	6.59	18.33	7.92	0.3	1.2	1.5	20.00	47	30.2	-16.8	0.64
WRD 5560 039	HS	QB	6	1848	2.81	72.13	3.92	0.1	2.1	2.2	4.55	70	0.1	-69.9	0.00
WRD 5560 040	HS	QB	3	456	3.97	36.46	2.98								
WRD 5560 041	HS	QB	4	2190	3.31	50.57	4.18	0.3	1.4	1.7	17.65	53	7.6	-45.4	0.14
WRD 5580 001	LS	QM	1	133	4	21.56	2.27	0.3	0.8	1.1	27.27	33	17.8	-15.2	0.54
WRD 5580 002	HS	QM	3	1422	2.77	34.01	6.00								
WRD 5580 004	O	QB			4.82			0.33	0.1	0.34	97.06	11	0.1	-10.9	0.01
WRD 5580 005	LS	QM	2	93	6.72	29.40	5.01								
WRD 5580 006	T	QM	0.5	212	3.2	30.77	5.06								
WRD 5580 007	HS	QB	2	345	3.02	31.07	4.87								
WRD 5580 008	HS	QB	2	230	5.55	29.01	5.15								
WRD 5580 009	HS	QM	2	325	3.14	28.62	5.01								
WRD 5580 011	HS	QM	2	8	5.6	28.03	5.29								
WRD 5580 012	HS	QM	2	305	5.4	29.11	5.1								
WRD 5580 013	HS	BB	7	2860	2.45	47.14	2.09								
WRD 5580 014	HS	BB	4	21	5	31.85	5.27	0.2	1.96	2.16	9.26	73.8	43.7	-30.1	0.59
WRD 5580 015	HS	QB	4	156	4.45	31.16	3.05								
WRD 5580 016	HS	QM	2	45.6	5.72	22.74	4.06								
WRD 5580 017	HS	QM	2	41	5.54	30.48	5.04								

1997 Surface Sample Analyses

Sample	Type	Lithology	Visible sulfide %	EC	Paste pH	NAG kg/T H_2SO_4	NAG pH	Sulfate %	Sulfide %	Sulfur Total %	SO_4/S %	AGP m/g $CaCO_3$	NP m/g $CaCO_3$	NNP	NP:AP
WRD 5580 018	HS	QM	2	112	6.4	32.93	5.55								
WRD 5580 019	HS	QM	2	42	6.14	19.60	3.91								
WRD 5580 021	HS	QM	2	65	5.87	19.89	3.98								
WRD 5580 022	HS	QM	2	170	5.61	39.79	3.00								
WRD 5580 023	HS	QM	2	103	7.67	21.17	4.63								
WRD 5580 024	HS	QM	1.5	183	5.39	21.56	4.07								
WRD 5580 025	HS	QM	1.5	42	5.74	15.78	2.52								
WRD 5580 026	HS	QM	2	84	6.1	34.79	6.42								
WRD 5580 033	HS	QM	1.5	237	3.82	38.71	7.74								
WRD 5580 042	HS	QB	5	1080	2.35	76.93	2.10	0.15	2.2	2.4	6.25	74	0.1	-73.9	0.00

KEY

Lithology QM= Quartz Monzonite QB= Quartz Breccia BB= Biotite Breccia QV = Quartz Vein AN = Andesite

Visible sulfide (%) = Observed pyrite/sulfide content in hand specimen

Type HS=High Sulfide (>2% visible sulfide) LS= Low Sulfide (<2% visible sulfide) T=Transitional (trace sulfide & acidic paste pH) O=Oxide (no observed sulfide)

NAG (eqkg H_2SO_4/T)= $\frac{49 \times \text{Volume of NaOH titrated} \times \text{molality of NaOH (0.1M)}}{\text{weight of sample (5g)}}$

Copper Flat Project
Static Test on Wall Rock and Drill Core from the Pit Area
1994 Sampling

Sample	Paste PH	Total	Sulfide	Sulfate	NP	AP	NNP	NP/AP
PW-1 SW pitwall transition	6.1	3.61	3.47	0.14	32	108.44	-76.44	0.3
PW-2 Oxidized pitwall	--	0.37	0.365	0.005	11	11.41	-0.41	0.96
PW-3 NW pitwall	2.6	2.2	2.195	0.005	0.1	68.59	-68.49	--
PW-4 NE pitwall	3.9	1.89	1.885	0.005	16	58.91	-42.91	0.27
IDC24-222-241, QM – core	--	1.74	1.735	0.005	31	54.22	-23.22	0.57
CF10-177-190, andesite – core	--	2.86	2.8	0.06	52	87.5	-35.5	0.59
CF10-190-199 QM—core	--	3.59	3.52	0.07	44	110	-66	0.4
CF10-214-220, QM – core	--	3.92	3.915	0.005	65	122.34	-57.34	0.53
H75-53-42, QM - reverse circ.	8.2	1.77	1.765	0.005	36	55.16	-19.16	0.65
H75-64-44, QM - reverse circ.	7.2	1.69	1.685	0.005	39	52.66	-13.66	0.74
H75-51-34, QM - reverse circ.	8.6	2.02	2.015	0.005	49	62.97	-13.97	0.78
H75-48-58, QM - reverse circ.	7.2	1.18	1.175	0.005	16	36.72	-20.72	0.44
H75-48-44, QM - reverse circ.	7.4	1.06	1.055	0.005	9	32.97	-23.97	0.27

SOURCE: *Copper Flat Mine - Compliation of Pit Lake Studies (SRK 1997)*

APPENDIX A.3

HUMIDITY COLUMN TEST DATA

Parameter	Cycle 1	Cycle 2	Cycle 3	Cycle 4	Cycle 5	Cycle 6	Cycle 7	Cycle 8	Cycle 9	Cycle 10	Cycle 11	Cycle 12	Cycle 13	Cycle 14	Cycle 15
Ag ug/l	1.	4.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Al mg/l	0.03	0.05	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
As ug/l	30.	30.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
B ug/l	50.	50.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
Ba ug/l	75.	60.	30.	15.	35.	45.	35.	40.	40.	45.	40.	45.	35.	35.	15.
Be ug/l	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Bi ug/l	6.	26.	2.	2.	2.	2.	2.	2.	2.	2.	2.	6.	2.	2.	2.
Ca mg/l	30.48	23.76	18.11	12.95	18.44	15.01	13.24	13.16	13.42	15.01	13.19	15.92	13.85	11.87	5.47
Cd ug/l	1.	2.	1.	1.	3.	1.	1.	3.	1.	1.	1.	1.	1.	1.	1.
Co ug/l	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
Cr ug/l	5.	20.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
Cu ug/l	14.	16.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.
Fe mg/l	0.04	0.06	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
K mg/l	1.56	1.47	0.65	0.13	0.47	0.61	0.12	0.79	0.9	0.22	0.68	0.94	0.34	0.75	0.18
Li ug/l	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
Mg mg/l	1.26	1.04	0.59	0.36	0.58	0.42	0.39	0.39	0.37	0.34	0.52	0.65	0.48	0.48	0.18
Mn mg/l	0.07	0.03	0.02	0.02	0.035	0.03	0.025	0.025	0.025	0.02	0.015	0.02	0.015	0.01	0.005
Mo ug/l	6.	4.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	4.
Na mg/l	5.24	4.63	2.19	1.26	2.38	1.79	1.65	1.82	1.27	1.57	2.34	2.98	2.05	2.12	0.52
Ni ug/l	10.	15.	10.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	10.
P ug/l	40.	110.	10.	10.	10.	10.	30.	10.	10.	10.	10.	10.	10.	30.	10.
Pb ug/l	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	8.	10.	2.	2.	2.
Sb ug/l	10.	34.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	4.	2.
Se ug/l	85.	150.	5.	5.	5.	5.	50.	25.	15.	15.	30.	40.	5.	30.	15.
Si mg/l	0.87	0.6	0.53	0.3	0.6	0.39	0.51	0.52	0.5	0.53	0.56	0.73	0.48	0.57	0.28
Sn ug/l	100.	174.	2.	2.	2.	2.	2.	2.	6.	22.	46.	2.	2.	80.	2.
Sr ug/l	124.	104.	50.	28.	44.	32.	32.	34.	34.	32.	34.	46.	36.	34.	18.
Ti ug/l	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.
V ug/l	2.	5.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Zn ug/l	28.	25.	12.	3.	9.	20.	11.	16.	1.	1.	2.	6.	8.	5.	9.
pH	7.73	7.8	7.55	7.4	7.85	7.64	7.52	7.53	7.54	7.59	7.61	7.63	7.72	7.51	7.16
Redox (mV)	300.	289.	307.	321.	295.	311.	318.	321.	341.	287.	272.	264.	265.	265.	296.
Conductivity (uS/cm)	132.	104.	70.	45.	69.	53.	45.	42.	41.	46.	50.	63.	49.	44.	19.
Alkalinity (mg $CaCO_3$/l)	43.	31.	24.	17.	26.	18.	16.	17.	17.	20.	19.	26.	19.	16.	10.
Acidity (pH 4.5)	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
Acidity (pH 8.3)	1.	2.	2.	2.	1.	1.	2.	1.	1.	2.	1.	2.9	2.	2.	3.
Cum Acidity (pH 8.3)	0.1	0.1	0.2	0.3	0.3	0.4	0.5	0.5	0.6	0.7	0.7	0.9	1.	1.1	1.2
Sulphate (mg/l)	9.	9.	5.	6.	8.	6.	5.	4.	4.	4.	5.	4.	3.	4.	2.
Cum Sulphate (mg/kg)	0.5	0.8	1.	1.2	1.6	1.9	2.2	2.4	2.6	2.8	3.	3.2	3.4	3.6	3.7
Water added (L)	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2
pH of water added	5.45	6.26	5.98	5.59	6.15	6.03	5.83	5.98	6.15	6.05	5.96	6.04	6.06	6.56	6.23
Leachate collected (L)	0.214	0.144	0.184	0.148	0.188	0.218	0.169	0.23	0.188	0.231	0.189	0.191	0.212	0.21	0.194
Cumulative Iron	0.04	0.1	0.11	0.12	0.13	0.14	0.15	0.16	0.17	0.18	0.19	0.2	0.21	0.22	0.23
Cumulative Copper	14.	30.	32.	34.	36.	38.	40.	42.	44.	46.	48.	50.	52.	54.	56.

Parameter	Cycle 16	Cycle 17	Cycle 18	Cycle 19	Cycle 20	Cycle 21	Cycle 22	Cycle 23	Cycle 24	Cycle 25	Cycle 26	Cycle 27	Cycle 28	Cycle 29
Ag ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Al mg/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
As ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
B ug/l	<0.10	<0.10	<0.10	<0.10	<0.10								<0.10	<0.10
Ba ug/l	0.014	0.022	0.018	0.046	0.033								0.061	0.057
Be ug/l	<0.005	<0.005	<0.005	<0.005	<0.005								<0.005	<0.005
Bi ug/l	<0.10	<0.1	<0.1	<0.1	<0.1								<0.1	<0.1
Ca mg/l	1.5	2.75	2.2	4.49	2.7								6.21	8.
Cd ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.010	<0.010
Co ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Cr ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Cu ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.010	<0.010
Fe mg/l	<0.030	<0.030	<0.030	<0.030	<0.030								<0.030	<0.030
K mg/l	<2.0	<2.0	<2.0	<2.0	<2.0								<2.0	<2.0
Li ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Mg mg/l	0.091	0.12	0.12	0.323	0.16								0.453	0.621
Mn mg/l	0.008	0.005	0.005	0.007	<0.005								0.016	0.012
Mo ug/l	<0.030	<0.030	<0.030	<0.030	<0.030								<0.030	<0.030
Na mg/l	<2.0	<2.0	<2.0	<2.0	<2.0								<2.0	<2.0
Ni ug/l	<0.020	<0.020	<0.020	<0.020	<0.020								<0.020	<0.020
P ug/l	<0.30	<0.30	<0.30	<0.30	<0.30								<0.30	<0.30
Pb ug/l	<0.050	<0.050	<0.050	<0.050	<0.050								<0.050	<0.050
Sb ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
Se ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
Si mg/l	0.143	0.207	0.171	0.377	0.231								0.432	0.596
Sn ug/l	<0.30	<0.30	<0.30	<0.30	<0.30								<0.30	<0.30
Sr ug/l	0.011	0.016	0.015	0.03	0.022								0.04	0.053
Ti ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.010	<0.010
V ug/l	<0.030	<0.030	<0.030	<0.030	<0.030								<0.030	<0.030
Zn ug/l	0.01	0.006	0.009	0.012	0.015								0.022	0.024
pH	7.08	7.29	7.23	7.4	6.64								7.59	7.69
Redox (mV)	304.	284.	295.	288.	281.								291.	293.
Conductivity (uS/cm)	10.	16.	15.	32.	19.								45.	58.
Alkalinity (mg $CaCO_3$/l)	6.	10.	7.	12.	8.								16.	20.
Acidity (pH 4.5)	0.	0.	0.	0.	0.								0.	0.
Acidity (pH 8.3)	5.	5.	6.	3.	6.								5.9	6.9
Cum Acidity (pH 8.3)	1.4	1.6	1.9	2.1	2.4								2.6	3.
Sulphate (mg/l)	2.	2.	2.	4.	3.								4.	4.
Cum Sulphate (mg/kg)	3.8	3.9	3.9	4.1	4.3								4.5	4.7
Water added (L)	0.2	0.2	0.2	0.2	0.2								0.2	0.2
pH of water added	5.92	5.57	5.66	6.09	5.23								5.93	5.7
Leachate collected (L)	0.151	0.175	0.198	0.181	0.205								0.185	0.216
Cumulative Iron	0.23	0.23	0.23	0.23	0.23								0.23	0.23
Cumulative Copper	56.	56.	56.	56.	56.								56.	56.

Laboratory Equipment Failure
Weeks 21-27
No Samples Collected

LGSSP-2 - Kinetic Test Data

Parameter	Cycle 1	Cycle 2	Cycle 3	Cycle 4	Cycle 5	Cycle 6	Cycle 7	Cycle 8	Cycle 9	Cycle 10	Cycle 11	Cycle 12	Cycle 13	Cycle 14	Cycle 15
Ag ug/l	7.	6.	1.	1.	1.	1.	1.	1.	1.	1.	2.	1.	1.	1.	1.
Al mg/l	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
As ug/l	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
B ug/l	60.	70.	40.	30.	10.	10.	30.	10.	10.	10.	10.	10.	10.	10.	10.
Ba ug/l	200.	105.	60.	55.	60.	40.	70.	75.	50.	90.	80.	60.	60.	75.	45.
Be ug/l	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Bi ug/l	6.	26.	2.	2.	2.	2.	2.	2.	2.	2.	8.	2.	2.	2.	2.
Ca mg/l	155.59	115.41	85.41	76.19	55.92	41.91	51.46	44.1	38.78	54.5	52.94	37.69	45.46	51.56	32.69
Cd ug/l	18.	13.	5.	1.	5.	1.	3.	5.	1.	1.	6.	1.	7.	1.	1.
Co ug/l	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
Cr ug/l	20.	25.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
Cu ug/l	82.	54.	28.	26.	16.	18.	34.	16.	14.	12.	10.	6.	10.	10.	6.
Fe mg/l	0.41	0.28	0.04	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.08	0.01	0.01	0.01	0.01
K mg/l	7.07	7.1	7.65	7.2	4.99	4.56	5.84	4.95	4.58	4.64	5.79	4.85	5.52	6.79	4.62
Li ug/l	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
Mg mg/l	16.36	11.17	8.56	7.12	4.48	2.92	4.14	3.22	2.68	4.25	4.34	2.58	3.58	4.32	2.2
Mn mg/l	0.04	0.035	0.02	0.01	0.03	0.015	0.01	0.015	0.005	0.01	0.015	0.01	0.005	0.005	0.005
Mo ug/l	242.	308.	288.	282.	176.	122.	140.	96.	74.	126.	126.	60.	90.	98.	66.
Na mg/l	7.5	7.94	7.2	6.55	3.88	2.91	3.15	2.04	1.79	2.48	2.69	1.54	2.31	2.5	1.63
Ni ug/l	5.	15.	10.	5.	5.	5.	5.	5.	5.	5.	10.	5.	5.	5.	5.
P ug/l	230.	270.	300.	340.	220.	200.	240.	190.	120.	200.	220.	180.	200.	270.	150.
Pb ug/l	32.	20.	2.	2.	2.	2.	2.	2.	2.	2.	2.	6.	12.	2.	2.
Sb ug/l	18.	22.	2.	2.	2.	2.	2.	2.	2.	2.	10.	2.	2.	2.	2.
Se ug/l	530.	405.	285.	245.	125.	30.	210.	145.	160.	225.	170.	110.	125.	115.	70.
Si mg/l	5.53	6.71	7.61	8.57	6.18	7.08	7.17	5.79	6.24	5.6	5.38	4.81	5.66	5.39	5.
Sn ug/l	574.	508.	2.	2.	2.	2.	26.	92.	60.	64.	90.	44.	44.	52.	2.
Sr ug/l	1,018.	680.	492.	418.	270.	178.	252.	204.	168.	262.	234.	142.	216.	224.	126.
Tl ug/l	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.
V ug/l	11.	10.	5.	4.	2.	1.	4.	1.	1.	1.	6.	3.	2.	2.	2.
Zn ug/l	28.	14.	12.	13.	6.	17.	13.	14.	1.	1.	1.	1.	9.	1.	3.
pH	8.07	8.1	8.09	8.16	8.11	8.13	8.13	8.05	8.21	8.03	8.04	8.01	8.07	7.96	8.02
Redox (mV)	325.	306.	318.	330.	310.	322.	335.	337.	344.	294.	281.	271.	268.	269.	296.
Conductivity (uS/cm)	979.	690.	533.	448.	308.	196.	261.	204.	170.	264.	279.	170.	226.	267.	151.
Alkalinity (mg $CaCO_3$/l)	53.	54.	58.	64.	54.	53.	58.	49.	54.	50.	51.	41.	54.	48.	49.
Acidity (pH 4.5)	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
Acidity (pH 8.3)	1.	1.	1.	1.	1.	1.	1.	1.	0.5	1.	1.	1.	1.	1.	1.
Cum Acidity (pH 8.3)	0.	0.1	0.1	0.1	0.1	0.2	0.2	0.2	0.3	0.3	0.3	0.4	0.4	0.5	0.5
Sulphate (mg/l)	432.	243.	155.	141.	82.	29.	64.	49.	21.	69.	69.	30.	48.	72.	16.
Cum Sulphate (mg/kg)	10.4	17.5	22.6	25.9	28.7	29.6	32.	33.6	34.2	36.8	39.5	40.5	42.3	45.7	46.2
Water added (L)	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2
pH of water added	5.45	6.26	5.98	5.59	6.15	6.03	5.83	5.98	6.15	6.05	5.96	6.04	6.06	6.56	6.23
Leachate collected (L)	0.102	0.122	0.139	0.101	0.144	0.119	0.162	0.138	0.112	0.158	0.165	0.153	0.158	0.198	0.127
Cumulative Iron	0.41	0.69	0.73	0.74	0.75	0.76	0.77	0.78	0.79	0.8	0.88	0.89	0.9	0.91	0.92
Cumulative Copper	82.	136.	164.	190.	206.	224.	258.	274.	288.	300.	310.	316.	326.	336.	342.

LGSSP-2 - Kinetic Test Data

Parameter	Cycle 16	Cycle 17	Cycle 18	Cycle 19	Cycle 20	Cycle 21	Cycle 22	Cycle 23	Cycle 24	Cycle 25	Cycle 26	Cycle 27	Cycle 28	Cycle 29
Ag ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Al mg/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
As ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
B ug/l	<0.10	<0.10	<0.10	<0.10	<0.10								<0.10	<0.10
Ba ug/l	0.058	0.048	0.037	0.038	0.044								0.101	0.084
Be ug/l	<0.005	<0.005	<0.005	<0.005	<0.005								<0.005	<0.005
Bi ug/l	<0.10	<0.10	<0.10	<0.10	<0.10								<0.10	<0.10
Ca mg/l	27.3	22.4	16.4	17.	14.6								66.2	65.3
Cd ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.010	<0.010
Co ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Cr ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Cu ug/l	0.019	0.016	0.011	0.011	<0.010								0.014	0.018
Fe mg/l	<0.030	<0.030	<0.030	<0.030	<0.030								<0.030	<0.030
K mg/l	4.	3.4	2.2	2.8	<2.0								4.4	4.2
Li ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Mg mg/l	2.7	2.11	1.49	1.55	1.29								6.2	6.19
Mn mg/l	<0.005	<0.005	<0.005	<0.005	<0.005								<0.005	<0.005
Mo ug/l	0.066	0.041	<0.030	0.03	<0.030								0.065	0.093
Na mg/l	<2.0	<2.0	<2.0	<2.0	<2.0								<2.0	<2.0
Ni ug/l	<0.020	<0.020	<0.020	<0.020	<0.020								<0.020	<0.020
P ug/l	<0.30	<0.30	<0.30	<0.30	<0.30								<0.30	<0.30
Pb ug/l	<0.050	<0.050	<0.050	<0.050	<0.050								<0.050	<0.050
Sb ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
Se ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
Si mg/l	5.55	4.58	3.18	3.22	2.26								4.12	5.03
Sn ug/l	<0.30	<0.30	<0.30	<0.30	<0.30								<0.30	<0.30
Sr ug/l	0.179	0.14	0.104	0.108	0.093								0.409	0.393
Ti ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.010	<0.010
V ug/l	<0.030	<0.030	<0.030	<0.030	<0.030								<0.030	<0.030
Zn ug/l	0.005	0.009	<0.005	<0.005	<0.005								0.008	0.005
pH	8.12	8.09	8.01	7.92	7.22								7.9	7.96
Redox (mV)	288.	298.	294.	290.	280.								313.	296.
Conductivity (uS/cm)	177.	138.	104.	109.	93.								402.	384.
Alkalinity (mg $CaCO_3$/l)	57.	48.	34.	38.	30.								36.	49.
Acidity (pH 4.5)	0.	0.	0.	0.	0.								0.	0.
Acidity (pH 8.3)	1.	1.	2.	2.	3.								3.	2.
Cum Acidity (pH 8.3)	0.5	0.5	0.6	0.7	0.8								1.	1.
Sulphate (mg/l)	20.	10.	11.	11.	8.								139.	124.
Cum Sulphate (mg/kg)	46.8	47.1	47.5	47.9	48.3								54.4	59.3
Water added (L)	0.2	0.2	0.2	0.2	0.2								0.2	0.2
pH of water added	5.92	5.57	5.66	6.09	5.23								5.93	5.7
Leachate collected (L)	0.127	0.131	0.16	0.158	0.203								0.183	0.67
Cumulative Iron	0.92	0.92	0.92	0.92	0.92								0.92	0.92
Cumulative Copper	342.	342.	342.	342.	342.								342.	342.

Laboratory Equipment Failure
Weeks 21-27
No Samples Collected

C10-190-199-2 - Kinetic Test Data

Parameter	Cycle 1	Cycle 2	Cycle 3	Cycle 4	Cycle 5	Cycle 6	Cycle 7	Cycle 8	Cycle 9	Cycle 10	Cycle 11	Cycle 12	Cycle 13	Cycle 14	Cycle 15
Ag ug/l	5.	5.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Al mg/l	0.01	0.04	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
As ug/l	10.	30.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
B ug/l	50.	30.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
Ba ug/l	50.	30.	45.	35.	15.	25.	15.	15.	15.	25.	20.	35.	35.	15.	30.
Be ug/l	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Bi ug/l	6.	16.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	8.
Ca mg/l	48.27	40.54	43.47	34.16	32.33	30.47	23.86	25.61	19.7	22.26	20.91	23.92	22.28	18.03	22.24
Cd ug/l	3.	8.	2.	1.	1.	3.	3.	3.	1.	1.	1.	1.	4.	4.	3.
Co ug/l	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
Cr ug/l	10.	15.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
Cu ug/l	52.	34.	24.	20.	14.	10.	8.	8.	6.	4.	2.	2.	4.	4.	2.
Fe mg/l	0.05	0.11	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
K mg/l	3.95	3.56	4.39	2.98	2.07	1.51	2.13	2.16	1.36	0.77	1.5	1.78	1.35	1.31	2.1
Li ug/l	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
Mg mg/l	4.25	3.86	4.68	3.49	3.06	2.59	2.22	2.35	1.47	1.79	1.83	2.5	2.3	2.04	2.4
Mn mg/l	0.11	0.065	0.05	0.035	0.045	0.04	0.035	0.035	0.025	0.025	0.025	0.025	0.025	0.02	0.03
Mo ug/l	10.	12.	6.	4.	6.	2.	2.	2.	2.	2.	2.	4.	2.	4.	4.
Na mg/l	3.83	4.18	4.35	3.16	2.22	2.01	1.98	1.78	1.24	1.01	1.09	1.82	1.61	1.66	1.87
Ni ug/l	5.	10.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
P ug/l	60.	100.	10.	30.	10.	10.	10.	30.	10.	10.	10.	10.	10.	10.	20.
Pb ug/l	6.	22.	2.	2.	2.	2.	2.	2.	2.	2.	6.	2.	2.	2.	4.
Sb ug/l	14.	22.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.
Se ug/l	205.	200.	80.	75.	40.	5.	50.	95.	95.	75.	15.	70.	10.	35.	60.
Si mg/l	0.85	0.7	1.02	0.82	0.71	0.78	0.9	0.81	0.57	0.53	0.5	0.66	0.3	0.41	0.74
Sn ug/l	66.	316.	2.	2.	148.	2.	18.	66.	24.	50.	2.	2.	8.	58.	2.
Sr ug/l	372.	320.	324.	244.	194.	184.	136.	150.	100.	110.	94.	132.	120.	80.	140.
Tl ug/l	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.
V ug/l	5.	6.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	2.
Zn ug/l	31.	29.	21.	16.	13.	13.	14.	8.	1.	1.	10.	30.	19.	17.	36.
pH	8.07	7.91	7.9	7.37	7.75	7.8	7.66	7.4	7.78	7.57	7.55	7.45	7.03	7.04	7.45
Redox (mV)	306.	297.	315.	327.	303.	320.	326.	329.	346.	292.	279.	276.	277.	281.	304.
Conductivity (uS/cm)	259.	225.	253.	181.	165.	142.	112.	114.	77.	89.	90.	114.	103.	86.	107.
Alkalinity (mg $CaCO_3$/l)	43.	30.	32.	22.	19.	25.	20.	21.	19.	17.	15.	15.	11.	10.	16.
Acidity (pH 4.5)	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
Acidity (pH 8.3)	1.	1.	1.	2.	1.	1.	2.	2.	0.5	2.	1.	2.	2.	2.	2.
Cum Acidity (pH 8.3)	0.	0.1	0.1	0.2	0.2	0.3	0.3	0.4	0.4	0.5	0.6	0.7	0.8	0.9	0.9
Sulphate (mg/l)	65.	58.	70.	57.	51.	33.	25.	26.	12.	17.	20.	30.	27.	20.	22.
Cum Sulphate (mg/kg)	3.2	5.5	7.8	9.5	12.	13.4	14.2	15.4	15.9	16.7	17.6	19.	20.3	21.2	22.1
Water added (L)	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2
pH of water added	5.45	6.26	5.98	5.59	6.15	6.03	5.83	5.98	6.15	6.05	5.96	6.04	6.06	6.56	6.23
Leachate collected (L)	0.228	0.175	0.149	0.139	0.224	0.19	0.158	0.198	0.195	0.219	0.215	0.208	0.219	0.206	0.194
Cumulative Iron	0.05	0.16	0.17	0.18	0.19	0.2	0.21	0.22	0.23	0.24	0.25	0.26	0.27	0.28	0.29
Cumulative Copper	52.	86.	110.	130.	144.	154.	162.	170.	176.	180.	182.	184.	188.	192.	194.

Parameter	Cycle 16	Cycle 17	Cycle 18	Cycle 19	Cycle 20	Cycle 21	Cycle 22	Cycle 23	Cycle 24	Cycle 25	Cycle 26	Cycle 27	Cycle 28	Cycle 29
Ag ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Al mg/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
As ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
B ug/l	<0.10	<0.10	<0.10	<0.10	<0.10								<0.10	<0.10
Ba ug/l	0.026	0.022	0.013	0.011	0.023								0.096	0.066
Be ug/l	<0.005	<0.005	<0.005	<0.005	<0.005								<0.005	<0.005
Bi ug/l	<0.10	<0.10	<0.10	<0.10	<0.10								<0.10	<0.10
Ca mg/l	11.8	10.8	4.76	3.15	14.3								45.3	50.7
Cd ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.010	<0.010
Co ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Cr ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Cu ug/l	0.017	0.015	0.012	0.015	0.016								0.036	0.034
Fe mg/l	<0.030	<0.030	<0.030	<0.030	<0.030								<0.030	<0.030
K mg/l	<2.0	<2.0	<2.0	<2.0	<2.0								<2.0	<2.0
Li ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Mg mg/l	2.05	1.75	0.749	0.456	1.48								6.05	7.52
Mn mg/l	0.032	0.029	0.013	0.012	0.035								0.083	0.089
Mo ug/l	<0.030	<0.030	<0.030	<0.030	<0.030								<0.030	<0.030
Na mg/l	<2.0	<2.0	<2.0	<2.0	<2.0								<2.0	<2.0
Ni ug/l	<0.020	<0.020	<0.020	<0.020	<0.020								<0.020	<0.020
P ug/l	<0.30	<0.30	<0.30	<0.30	<0.30								<0.30	<0.30
Pb ug/l	<0.050	<0.050	<0.050	<0.050	<0.050								<0.050	<0.050
Sb ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
Se ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
Si mg/l	0.541	0.547	0.275	0.169	0.346								0.614	0.679
Sn ug/l	<0.30	<0.30	<0.30	<0.30	<0.30								<0.30	<0.30
Sr ug/l	0.131	0.108	0.047	0.03	0.112								0.393	0.427
Ti ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.010	<0.010
V ug/l	<0.030	<0.030	<0.030	<0.030	<0.030								<0.030	<0.030
Zn ug/l	0.02	0.02	0.016	0.015	0.041								0.078	0.058
pH	7.52	7.64	7.27	6.87	6.66								7.49	7.41
Redox (mV)	309.	290.	301.	297.	290.								320.	307.
Conductivity (uS/cm)	95.	80.	37.	26.	104.								309.	335.
Alkalinity (mg $CaCO_3$/l)	15.	15.	8.	5.	8.								14.	15.
Acidity (pH 4.5)	0.	0.	0.	0.	0.								0.	0.
Acidity (pH 8.3)	3.	6.	2.	4.	4.								6.9	8.9
Cum Acidity (pH 8.3)	1.1	1.3	1.4	1.6	1.8								2.1	2.5
Sulphate (mg/l)	19.	14.	7.	6.	28.								118.	124.
Cum Sulphate (mg/kg)	22.9	23.5	23.8	24.1	25.3								30.2	35.5
Water added (L)	0.2	0.2	0.2	0.2	0.2								0.2	0.2
pH of water added	5.92	5.57	5.66	6.09	5.23								5.93	5.7
Leachate collected (L)	0.177	0.205	0.194	0.219	0.197								0.188	0.198
Cumulative Iron	0.29	0.29	0.29	0.29	0.29								0.29	0.29
Cumulative Copper	194.	194.	194.	194.	194.								194.	194.

Laboratory Equipment Failure
Weeks 21-27
No Samples Collected

Sample SW-1 - Kinetic Test Data

Parameter	Cycle 1	Cycle 2	Cycle 3	Cycle 4	Cycle 5	Cycle 6	Cycle 7	Cycle 8	Cycle 9	Cycle 10	Cycle 11	Cycle 12	Cycle 13	Cycle 14	Cycle 15
Ag ug/l	2.	4.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Al mg/l	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
As ug/l	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
B ug/l	20.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
Ba ug/l	50.	30.	20.	20.	10.	10.	20.	25.	25.	15.	20.	25.	15.	20.	15.
Be ug/l	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Bi ug/l	6.	6.	2.	2.	2.	2.	2.	2.	2.	2.	8.	2.	2.	2.	2.
Ca mg/l	53.15	45.51	34.83	36.28	31.01	23.67	23.36	24.87	30.06	23.22	23.31	30.56	20.57	22.22	17.45
Cd ug/l	2.	2.	1.	1.	1.	1.	7.	1.	1.	1.	4.	5.	1.	1.	5.
Co ug/l	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
Cr ug/l	15.	15.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
Cu ug/l	26.	16.	10.	12.	6.	2.	2.	2.	6.	2.	2.	2.	2.	2.	2.
Fe mg/l	0.08	0.08	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
K mg/l	2.98	2.71	2.19	2.94	2.35	1.69	1.41	1.07	2.17	0.15	1.7	2.14	1.98	1.47	1.28
Li ug/l	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
Mg mg/l	4.46	3.72	2.5	2.78	2.19	1.24	1.38	1.49	2.02	1.32	1.42	2.38	1.26	1.37	1.02
Mn mg/l	0.04	0.015	0.01	0.015	0.01	0.005	0.005	0.005	0.015	0.005	0.005	0.005	0.005	0.005	0.005
Mo ug/l	102.	84.	50.	62.	44.	26.	22.	32.	32.	14.	32.	32.	10.	26.	20.
Na mg/l	1.57	1.17	0.82	1.01	0.79	0.28	0.47	0.43	0.66	0.36	0.43	0.7	0.41	0.52	0.34
Ni ug/l	10.	10.	5.	10.	5.	5.	5.	5.	5.	5.	5.	15.	5.	5.	5.
P ug/l	120.	140.	40.	150.	100.	90.	180.	140.	130.	100.	140.	180.	50.	140.	80.
Pb ug/l	4.	8.	2.	2.	2.	2.	2.	2.	2.	2.	6.	2.	4.	2.	12.
Sb ug/l	14.	20.	2.	2.	2.	2.	2.	2.	2.	2.	6.	2.	2.	60.	2.
Se ug/l	210.	155.	65.	110.	25.	5.	80.	45.	80.	40.	70.	85.	20.	2.06	35.
Si mg/l	3.69	3.95	3.56	4.88	4.05	1.99	2.6	1.99	3.74	2.51	2.31	2.82	1.93	2.	1.98
Sn ug/l	300.	376.	2.	2.	2.	2.	80.	2.	44.	12.	2.	8.	50.	60.	2.
Sr ug/l	194.	166.	104.	110.	82.	56.	62.	68.	88.	56.	60.	78.	48.	2.	38.
Ti ug/l	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.
V ug/l	5.	6.	1.	1.	1.	1.	1.	1.	1.	1.	2.	1.	1.	1.	1.
Zn ug/l	27.	9.	7.	7.	4.	8.	4.	9.	1.	1.	7.	3.	11.	1.	4.
pH	7.65	7.73	7.87	7.91	8.04	7.65	7.69	7.66	8.	7.78	7.85	7.75	7.62	7.74	7.54
Redox (mV)	287.	265.	280.	305.	296.	302.	320.	317.	309.	260.	251.	241.	233.	233.	278.
Conductivity (uS/cm)	266.	231.	167.	174.	144.	95.	92.	105.	125.	84.	94.	138.	78.	84.	65.
Alkalinity (mg $CaCO_3$/l)	34.	29.	27.	37.	35.	21.	23.	18.	34.	26.	26.	26.	20.	22.	14.
Acidity (pH 4.5)	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
Acidity (pH 8.3)	0.5	2.	1.	2.	1.	0.5	2.	1.	1.	1.	1.	2.	2.	2.	4.
Cum Acidity (pH 8.3)	0.	0.1	0.2	0.2	0.2	0.2	0.3	0.3	0.4	0.4	0.5	0.6	0.6	0.7	0.9
Sulphate (mg/l)	77.	60.	32.	30.	24.	12.	11.	20.	14.	8.	11.	25.	8.	9.	6.
Cum Sulphate (mg/kg)	3.9	6.7	8.2	8.2	8.2	8.8	9.3	10.3	10.7	11.1	11.6	12.9	13.2	13.6	13.9
Water added (L)	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2
pH of water added	5.45	6.26	5.98	5.59	6.15	6.03	5.83	5.98	6.15	6.05	5.96	6.04	6.06	6.56	6.23
Leachate collected (L)	0.166	0.207	0.157	0.128	0.181	0.168	0.188	0.194	0.162	0.209	0.198	0.206	0.179	0.186	0.206
Cumulative Iron	0.08	0.16	0.17	0.18	0.19	0.2	0.21	0.22	0.23	0.24	0.25	0.26	0.27	0.28	0.29
Cumulative Copper	26.	42.	52.	64.	70.	72.	74.	76.	82.	84.	86.	88.	90.	92.	94.

Sample SW-1 - Kinetic Test Data

Parameter	Cycle 16	Cycle 17	Cycle 18	Cycle 19	Cycle 20	Cycle 21	Cycle 22	Cycle 23	Cycle 24	Cycle 25	Cycle 26	Cycle 27	Cycle 28	Cycle 29
Ag ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Al mg/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
As ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
B ug/l	<0.10	<0.10	<0.10	<0.10	<0.10								<0.10	<0.10
Ba ug/l	0.018	0.014	<0.010	0.012	0.013								0.021	0.021
Be ug/l	<0.005	<0.005	<0.005	<0.005	<0.005								<0.005	<0.005
Bi ug/l	<0.10	<0.10	<0.10	<0.10	<0.10								<0.10	<0.10
Ca mg/l	10.9	8.36	6.44	7.72	4.2								7.65	7.26
Cd ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.010	<0.010
Co ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Cr ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Cu ug/l	0.011	<0.010	<0.010	0.01	<0.010								0.011	0.012
Fe mg/l	<0.030	<0.031	<0.032	<0.033	<0.034								<0.035	<0.036
K mg/l	<2.0	<2.1	<2.2	<2.3	<2.4								<2.5	<2.6
Li ug/l	<0.015	<0.016	<0.017	<0.018	<0.019								<0.020	<0.021
Mg mg/l	1.14	0.766	0.636	0.782	0.414								0.851	0.775
Mn mg/l	<0.005	<0.005	0.005	0.006	0.007								0.022	0.013
Mo ug/l	<0.030	<0.031	<0.032	<0.033	<0.034								<0.035	<0.036
Na mg/l	<2.0	<2.1	<2.2	<2.3	<2.4								<2.5	<2.6
Ni ug/l	<0.020	<0.020	<0.020	<0.020	<0.020								<0.020	<0.020
P ug/l	<0.30	<0.30	<0.30	<0.30	<0.30								<0.30	<0.30
Pb ug/l	<0.050	<0.050	<0.050	<0.050	<0.050								<0.050	<0.050
Sb ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
Se ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
Si mg/l	1.99	1.33	1.25	1.38	0.705								0.581	0.928
Sn ug/l	<0.30	<0.31	<0.32	<0.33	<0.34								<0.35	<0.36
Sr ug/l	0.055	0.044	0.034	0.039	0.026								0.037	0.035
Ti ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.010	<0.010
V ug/l	<0.030	<0.030	<0.030	<0.030	<0.030								<0.030	<0.030
Zn ug/l	0.006	0.005	0.007	0.008	0.011								0.026	0.014
pH	7.79	7.64	7.55	7.44	6.54								7.2	7.32
Redox (mV)	261.	280.	283.	274.	260.								298.	277.
Conductivity (uS/cm)	73.	53.	40.	51.	27.								55.	49.
Alkalinity (mg $CaCO_3$/l)	13.	13.	16.	15.	9.								4.	4.
Acidity (pH 4.5)	0.													
Acidity (pH 8.3)	3.	3.	5.	5.	5.								10.9	11.9
Cum Acidity (pH 8.3)	1.	1.2	1.4	1.6	1.9								2.3	3.
Sulphate (mg/l)	5.	4.	4.	6.	4.								11.	6.
Cum Sulphate (mg/kg)	14.1	14.3	14.5	14.7	14.9								15.4	15.7
Water added (L)	0.2	0.2	0.2	0.2	0.2								0.2	0.2
pH of water added	5.92	5.57	5.66	6.09	5.23								5.93	5.7
Leachate collected (L)	0.171	0.178	0.188	0.177	0.211								0.175	0.22
Cumulative Iron	0.29	0.29	0.29	0.29	0.29								0.29	0.29
Cumulative Copper	94.	94.	94.	94.	94.								94.	94.

Laboratory Equipment Failure
Weeks 21-27
No Samples Collected

Sample PW-2 - Kinetic Test Data

Parameter	Cycle 1	Cycle 2	Cycle 3	Cycle 4	Cycle 5	Cycle 6	Cycle 7	Cycle 8	Cycle 9	Cycle 10	Cycle 11	Cycle 12	Cycle 13	Cycle 14	Cycle 15
Ag ug/l	36.	3.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Al mg/l	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
As ug/l	30.	20.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
B ug/l	10.	20.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
Ba ug/l	110.	75.	25.	45.	15.	60.	25.	25.	25.	30.	35.	60.	30.	35.	35.
Be ug/l	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Bi ug/l	26.	42.	2.	2.	2.	2.	2.	2.	2.	2.	8.	8.	2.	2.	16.
Ca mg/l	30.55	33.63	9.45	11.3	3.49	12.99	4.86	4.17	3.87	4.01	5.17	5.19	4.91	4.48	7.33
Cd ug/l	26.	25.	12.	1.	1.	8.	7.	7.	1.	1.	4.	1.	4.	1.	1.
Co ug/l	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
Cr ug/l	5.	10.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
Cu ug/l	302.2	280.	67.4	63.4	23.6	83.8	31.4	28.	42.4	43.6	62.6	81.8	59.8	69.	102.2
Fe mg/l	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
K mg/l	5.11	5.88	1.53	2.22	0.3	2.22	0.58	0.62	0.01	0.4	1.42	1.26	1.61	1.46	1.51
Li ug/l	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
Mg mg/l	1.6	2.03	0.44	0.52	0.11	0.58	0.18	0.15	0.13	0.13	0.27	0.26	0.19	0.22	0.37
Mn mg/l	0.1	0.145	0.045	0.055	0.02	0.07	0.03	0.02	0.025	0.03	0.035	0.04	0.035	0.035	0.065
Mo ug/l	24.	14.	8.	10.	2.	6.	2.	2.	2.	2.	6.	4.	2.	4.	6.
Na mg/l	1.29	1.64	0.38	0.55	0.06	0.56	0.18	0.16	0.12	0.13	0.23	0.2	0.2	0.39	0.33
Ni ug/l	5.	10.	5.	5.	5.	5.	5.	5.	5.	5.	5.	10.	5.	5.	5.
P ug/l	70.	80.	10.	10.	30.	30.	20.	30.	10.	10.	40.	10.	10.	10.	70.
Pb ug/l	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	28.	8.	2.	2.	2.
Sb ug/l	2.	16.	2.	2.	2.	2.	2.	2.	2.	2.	8.	2.	2.	2.	2.
Se ug/l	120.	125.	5.	5.	5.	5.	5.	5.	25.	10.	45.	5.	5.	10.	5.
Si mg/l	7.32	9.68	2.54	4.08	1.	4.73	1.54	1.42	1.4	1.46	1.76	1.79	1.28	1.41	1.71
Sn ug/l	2.	328.	88.	2.	2.	2.	2.	2.	58.	50.	2.	2.	34.	12.	2.
Sr ug/l	98.	114.	18.	20.	2.	30.	8.	10.	8.	6.	14.	12.	8.	10.	14.
Ti ug/l	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.
V ug/l	1.	3.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Zn ug/l	473.	492.	114.	126.	43.	176.	58.	51.	3.	1.	66.	96.	68.	64.	145.
pH	6.52	5.87	5.99	5.9	6.42	6.1	6.03	6.26	6.43	6.31	6.14	6.1	6.14	6.13	5.95
Redox (mV)	367.	332.	306.	321.	281.	335.	310.	316.	362.	297.	315.	307.	312.	315.	352.
Conductivity (uS/cm)	169.	193.	51.	57.	19.	63.	23.	17.	20.	21.	28.	29.	25.	27.	39.
Alkalinity (mg $CaCO_3$/l)	7.	3.	2.	3.	3.	2.	3.	2.	3.	3.	2.	2.	2.	2.	3.
Acidity (pH 4.5)	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
Acidity (pH 8.3)	8.	9.	4.	4.	3.	3.	2.	2.	2.	2.9	2.9	2.9	3.	3.	4.
Cum Acidity (pH 8.3)	0.4	0.9	1.	1.2	1.3	1.5	1.6	1.7	1.7	1.9	2.1	2.2	2.4	2.5	2.7
Sulphate (mg/l)	59.	66.	13.	15.	7.	15.	6.	5.	5.	5.	7.	7.	4.	6.	10.
Cum Sulphate (mg/kg)	2.6	6.3	6.9	7.4	7.7	8.4	8.7	9.	9.2	9.5	9.9	10.3	10.4	10.7	11.3
Water added (L)	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2
pH of water added	5.45	6.26	5.98	5.59	6.15	6.03	5.83	5.98	6.15	6.05	5.96	6.04	6.06	6.56	6.23
Leachate collected (L)	0.166	0.207	0.157	0.128	0.181	0.168	0.188	0.194	0.162	0.209	0.198	0.206	0.179	0.186	0.206
Cumulative Iron	0.01	0.02	0.03	0.04	0.05	0.06	0.07	0.08	0.09	0.1	0.11	0.12	0.13	0.14	0.15
Cumulative Copper	302.2	582.2	649.6	713.	736.6	820.4	851.8	879.8	922.2	965.8	1,028.4	1,110.2	1,170.	1,239.	1,341.2

Sample PW-2 - Kinetic Test Data

Parameter	Cycle 16	Cycle 17	Cycle 18	Cycle 19	Cycle 20	Cycle 21	Cycle 22	Cycle 23	Cycle 24	Cycle 25	Cycle 26	Cycle 27	Cycle 28	Cycle 29
Ag ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Al mg/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
As ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
B ug/l	<0.10	<0.10	<0.10	<0.10	<0.10								<0.10	<0.10
Ba ug/l	0.014	0.015	0.011	0.012	0.015								0.025	0.035
Be ug/l	<0.005	<0.005	<0.005	<0.005	<0.005								<0.005	<0.005
Bi ug/l	<0.10	<0.10	<0.10	<0.10	<0.10								<0.10	<0.10
Ca mg/l	1.06	1.09	0.51	0.548	0.761								1.02	2.02
Cd ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.010	<0.010
Co ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Cr ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Cu ug/l	28.1	24.4	16.5	16.4	17.								22.	32.
Fe mg/l	<0.030	<0.030	<0.030	<0.030	<0.030								<0.030	<0.030
K mg/l	<2.0	<2.0	<2.0	<2.0	<2.0								<2.0	<2.0
Li ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Mg mg/l	0.097	0.101	0.054	<0.050	0.093								0.086	0.188
Mn mg/l	0.02	0.021	0.013	0.017	0.019								0.03	0.044
Mo ug/l	<0.030	<0.030	<0.030	<0.030	<0.030								<0.030	<0.030
Na mg/l	<2.0	<2.0	<2.0	<2.0	<2.0								<2.0	<2.0
Ni ug/l	<0.020	<0.020	<0.020	<0.020	<0.020								<0.020	<0.020
P ug/l	<0.30	<0.30	<0.30	<0.30	<0.30								<0.30	<0.30
Pb ug/l	<0.050	<0.050	<0.050	<0.050	<0.050								<0.050	<0.050
Sb ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
Se ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
Si mg/l	0.685	0.991	0.377	0.458	0.567								0.364	0.686
Sn ug/l	<0.30	<0.30	<0.30	<0.30	<0.30								<0.30	<0.30
Sr ug/l	0.008	0.009	0.008	<0.001	0.011								0.007	0.013
Tl ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.010	<0.010
V ug/l	<0.030	<0.030	<0.030	<0.030	<0.030								<0.030	<0.030
Zn ug/l	0.038	0.04	0.023	0.027	0.04								0.058	0.077
pH	6.23	6.4	6.17	6.19	5.35								6.31	6.03
Redox (mV)	327.	326.	316.	308.	294.								340.	332.
Conductivity (uS/cm)	32.	12.	6.	6.	8.								11.	19.
Alkalinity (mg $CaCO_3$/l)	3.	3.	3.	2.	1.								2.	2.
Acidity (pH 4.5)	0.	0.	0.	0.	0.								0.	0.
Acidity (pH 8.3)	2.	2.	3.	4.	6.								11.9	11.9
Cum Acidity (pH 8.3)	2.9	3.	3.1	3.3	3.7								4.3	5.
Sulphate (mg/l)	3.	3.	3.	4.	4.								3.	4.
Cum Sulphate (mg/kg)	11.5	11.6	11.8	12.	12.2								12.4	12.6
Water added (L)	0.2	0.2	0.2	0.2	0.2								0.2	0.2
pH of water added	5.92	5.57	5.66	6.09	5.23								5.93	5.7
Leachate collected (L)	0.171	0.178	0.188	0.177	0.211								0.175	0.22
Cumulative Iron	0.15	0.15	0.15	0.15	0.15								0.15	0.15
Cumulative Copper	1,369.3	1,393.7	1,410.2	1,426.6	1,443.6								1,465.6	1,497.6

Laboratory Equipment Failure
Weeks 21-27
No Samples Collected

Appendix B

Tailings Characterization

TABLE OF CONTENTS

1.0 TESTING PROGRAM 2

2.0 CHARACTERISTICS AND BEHAVIOR OF FUTURE TAILINGS.....3

LIST OF TABLES

Table 1.1 Tailings Geochemical Analysis 1994 and 1996 Samples
Table 1.2 Total and Extractable Metals Concentrations

APPENDIX B

GEOCHEMICAL CHARACTERIZATION OF TAILINGS

1.0 TESTING PROGRAM

Tailings from previous mining operations at the Copper Flat project were sampled on two occasions. In conjunction with piezometer installation, two tailings samples were recovered with a split spoon sample in 1994 (T-10-12 and T-5-7). In 1996, five test pits were excavated in the existing impoundment and an additional 11 samples were obtained.

Tailings samples were analyzed for paste pH and conductivity values, and by Acid Base Accounting tests. Results are listed in Table 1.1. The tailings collected in 1996 are grouped according to their appearance in hand specimen. Yellow tailings are assumed to be derived from oxidized or transition materials and are given the label TTLS (transition tailings) while fresh gray tailings that are assumed to have been derived from unoxidized quartz monzonite are labeled UTLS (unoxidized tailings). Black tailings (BTLS) are assumed to be derived from biotite breccia.

The tailings samples are not currently generating acid. Paste pH values for all samples were all above 6.1. Paste conductivity was low and ranged from 298 to 686 μS/cm. On the basis of the paste results, the current reactivity of the existing tailings is low.

Based on ABA results, sulfide sulfur contents averaged 0.72 for the transition tailings and 0.95 for the unoxidized tailings collected in 1996. Based on sulfide sulfur content, five of the samples had NP:AP ratios below 1, indicating that these samples have moderate potential to produce acidity. All other samples show a weak acid producing potential.

The decrease in acid generating potential relative to waste rock samples (i.e. higher NP:AP ratios) is likely a result of sulfide removal during the concentration process. The tailings show no increase in neutralization potential relative to the waste rock samples, indicating that lime added during processing has little impact on the chemistry of the tailings.

Sample T-10-12 was analyzed for total metals concentrations using the EPA 3051 digestion and analysis by ICP. Results, listed in Table 1.2, indicate the sample had

high concentrations of aluminum (2,700 ppm), copper (1,600 ppm), iron (19,000), magnesium (1,800 ppm), potassium (1.400 ppm), and zinc (418 ppm). However, results of a modified EPA method 1312 leach indicated that these metals are not easily leached. These results confirm the limited oxidation that has occurred in the tailings, as indicated by the low paste conductivity. Therefore, the color of the tailings exhibited in drill hole and test pit samples is believed to be a result of the source of the materials. The designation of "transition" or "unoxidized" refers only to the nature of the ore from which the tailings were produced.

2.0 CHARACTERISTICS AND BEHAVIOR OF FUTURE TAILINGS

The majority of future ore will be unoxidized quartz monzonite, biotite breccia, and quartz breccia. Future tailings are anticipated to have geochemical properties similar to the UTLS tailings samples shown in Table 1.1. While a potential for acid generation is indicated, no evidence of acid generation was observed following 14 years of weathering under field conditions. Future tailings are anticipated to be equally slow in generating acid and releasing metals.

Table B.1.1
Tailings Geochemical Analysis - 1994 and 1996 Samples

Sample ID	pH (S.U.)	Paste Conductivity (µS/cm)	Sulfur				Neutralization Potential (T/KT)	AP (sulfide) (T/KT)	NNP (sulfide) (T/KT)	NP/AP (sulfide)	AP (pyrite) (T/KT)	NNP (pyrite) (T/KT)	NP/AP (pyrite)
			Total (%)	Sulfate (%)	Sulfide (%)	Pyrite (%)							
Transition Tailings													
P1-TTLS	6.6	466	1.12	0.47	0.65	0.58	36.00	20.31	15.69	1.77	18.13	17.88	1.99
P2-TTLS	7.1	483											
P3-TTLS	7.3	628	1.16	0.52	0.64	0.31	17.00	20.00	-3.00	0.85	9.69	7.31	1.75
P4-TTLS	7.3	651	1.31	0.45	0.86	0.54	27.00	26.88	0.12	1.00	16.88	10.13	1.60
P5-TTLS	7.5	547											
Mean	7.2	555	1.20	0.48	0.72	0.48	26.67	22.40	4.27	1.21	14.90	11.77	1.78
Unoxidized Tailings													
P1-TLS@12"	6.2	486	0.79	0.13	0.66	0.45	26.00	20.63	5.38	1.26	14.06	11.94	1.85
P1-UTLS	6.8	686	1.3	0.25	1.05	0.8	25.00	32.81	-7.81	0.76	18.75	6.25	1.33
P2-UTLS	7.7	643	1.15	0.19	0.96	0.75	25.00	30.00	-5.00	0.83	23.44	1.56	1.07
P3-UTLS	7.6	352											
P4-UTLS	7.2	357											
P5-UTLS	7.6	455	1.19	0.08	1.11	0.72	31.00	34.69	-3.69	0.89	22.50	8.50	1.38
Mean	7.2	497	1.11	0.16	0.95	0.63	26.75	29.53	-2.78	0.94	19.69	7.06	1.41
Black Tailings													
P5-BTLS	7.8	298	0.92	0.27	0.65	0.3	35.00	20.31	14.69	1.72	9.38	25.63	3.73
1994 Tailings Samples													
T-10-12	7.8		1.26	0.03	1.23	0.68	24	38.44	-14.44	0.62	21.25	2.75	1.13
T-5-7	7.5		1.1	0.18	0.92	0.53	31	28.75	2.25	1.08	16.56	14.44	1.87
Mean	7.7		1.18	0.11	1.08	0.61	27.50	33.59	-6.09	0.85	18.91	8.59	1.50

Notes:
Sulfide sulfur equals total sulfur minus sulfate sulfur
NNP equals net neutralization potential (NP-AP)

Table B.1.2
Total and Extractable Metals Concentrations in Tailings

Parameters	Total Metals in Solids ICP ppm	Extractable Metals EPA 1312 (mg/L)
Aluminum	2700	< 0.05
Antimony	< 0.5	N/A
Arsenic	1.3	< 0.1
Barium	52	0.10
Boron	< 2	0.07
Cadmium	1.8	< 0.005
Calcium	8500	300
Chloride	N/A	6
Chromium	5	< 0.01
Cobalt	13	< 0.02
Copper	1600	0.03
Fluoride	N/A	1.4
Iron	19000	< 0.02
Lead	15	< 0.021
Magnesium	1800	22
Manganese	251	1.50
Mercury	< 0.02	< 0.0002
Molybdenum	34	0.19
Nickel	3	< 0.02
Potassium	1400	44
Selenium	< 0.03	< 0.1
Silver	< 1	< 0.01
Sodium	200	44
Sulfate	N/A	940
Vanadium	7	< 0.01
Zinc	418	0.42

Appendix C

Field Scale Reclamation Cover Test Program

STEFFEN, ROBERTSON AND KIRSTEN
Consulting Engineers and Scientists

Suite 3000
7175 W. Jefferson Ave.
Lakewood, CO
USA 80235
E-mail: denver@srk.com
URL: http://www.srk.com/
Tel: (303) 985-1333
Fax: (303) 985-9947

MEMORANDUM

TO: Jeff Parshley, SRK - Reno

FROM: Pete Kowalewski, SRK - Denver

DATE: April 27, 1998

SUBJECT: **Copper Flat Closure Field Testing Program**

PROJ/PROP NO. **68606**

1.0 INTRODUCTION

In accordance with Item 23 of the Conditions for Approval of DP-001, Alta Gold Corporation (Alta) will conduct long term field testing of alternative soil covers to aid in the selection of cover designs for the tailings impoundment and waste rock dumps at the Copper Flat site. In addition to aiding in the selection of the most appropriate soil cover for the tailings and waste rock at the Copper Flat site, the field testing will provide for evaluation of several other issues at the Copper Flat site, including: acid generation potential, phytotoxicity and ecological risk, and the ability to successfully revegetate the alternative soil covers. The following is a conceptual plan detailing the proposed field testing to be performed after the commencement of operations at the site.

2.0 FIELD COVER TESTING

2.1 Test Cell Composition

The field testing will consist of a series of constructed test plots. Alternative covers will be tested over both tailings and, potentially, three different types of waste rock (unoxidized, transitional, and low sulfide), as cover performance and revegetative success may be influenced by the underlying waste material being covered (i.e. fine-grained tailings versus coarse-grained waste rock). Table 1 presents a matrix of all of the combinations of alternative soil covers and underlying waste materials that will be tested in the program.

Table 1. Matrix of Soil Cover and Underlying Waste Materials for Field Testing Program

Soil Cover	Underlying Waste Type			
	Tailings	Unoxidized Waste	Transitional Waste	Low Sulfide Waste
Control (No Cover)	x[2]	x[2]	x[3]	x[3]
12" Alluvium	x[2]	x[2]	x[3]	x[3]
24" Alluvium	x[2]	x[2]	x[3]	x[3]
24" Alluvium / Amended Tailings (Harrowed)[1]	x[2]	x[2]	x[3]	x[3]

Notes:
[1] Amendment of tailings may be achieved by blending lime, limestone, or a soil with high neutralizing potential, if necessary. Alluvium may provide some neutralizing potential for the tailings.
[2] Test cell will be monitored for surface water runoff, percolation, and moisture content
[3] Test cell will be monitored for surface water runoff and percolation only

As can be seen from Table 1, a total of 16 test cells are proposed for the field testing program. Eight of the 16 test plots will be instrumented to quantify runoff and percolation through the cover system only, while runoff, percolation, and moisture content will be measured in the remaining 8 test cells.

2.2 Test Plot Design

Figures 1 through 3 show conceptual plans for an individual test plot. Each test plot will have an area of approximately 300 square feet. Various covers will be placed over a minimum of 10 feet of tailings or waste rock. Both the bottom and surface of each cell will be graded to allow concentration of flow at central collection points on the cell floor and surface. A berm may be constructed on the surface of each plot to facilitate the concentration of surface flows. Grading of the floor of each cell will facilitate concentration of flow into a perforated pipe. Flows will be collected in pipes and routed to collection tanks for measurement of surface runoff and percolation, respectively.

2.3 Test Plot Instrumentation

The test plot will be instrumented to quantify surface runoff from the test plot, percolation occurring through the test plot, and moisture content within the soil profile. Surface runoff will be collected from the test plot and routed to a collection tank for measurement. Percolation occurring through the test plot will be routed to a collection tank as well, where it will be measured. The measurement of surface runoff will be performed after each rainfall at the site, while percolation measurement will be made at least once per week during the testing period. The frequency of recording both percolation and runoff measurement may be increased during wet periods.

Moisture content profiling of the test cells may be performed manually through the use of a nuclear moisture gauge or moisture probe, or in an automated fashion using moisture probes buried at various depths connected to a datalogger. Regardless of the method by which moisture profile data is collected,

data will be collected from a minimum of 5 pre-determined depths at least once a week for each test cell identified in Table 1 as requiring moisture profiling.

2.4 Weather Station Instrumentation

A weather station will be installed that is capable of measuring the following parameters: daily precipitation, maximum and minimum daily air temperature, daily maximum and minimum relative humidity, average daily wind speed, wind direction, and average daily incoming solar radiation. It is envisioned that data collection will be automated through the use of a datalogger to facilitate acquisition.

Daily evaporation will be measured through use of a National Weather Service Class A type evaporation pan. Measurements will be made by mine personnel.

2.5 Leachate Quality Testing

Leachate from the cover test plots will be analyzed to evaluate the geochemical behavior of the underlying materials. The first sample of leachate from each cell will be analyzed for pH, alkalinity/acidity, conductivity, sulfate, Eh, as well as a full range of dissolved metals, major cations and major anions. Thereafter, full chemical analyses will be repeated on an annual basis. During the course of testing, pH, alkalinity/acidity, and sulfate analyses will be performed at any point when there is sufficient leachate available for analysis. If leachate is consistently available (minimum volume of 1 liter), this sampling will be conducted quarterly.

2.6 Test Cell Bio-assay

Several tests will be required to assess the revegetative success of the test cells and the ecological risk posed by the uptake or fixation of heavy metals by roots and heavy metal accumulation in plant tissue. The testing proposed for this area of work includes: a random survey to assess live plant cover and total cover (live plant and litter), soil pH, total metals concentration of plant tissue and roots, soil organic matter content, total and plant available nitrogen, and soil fertility (includes analyses for phosphorous, magnesium, and potassium).

Testing of the plant matter and soil from the field test cells will be conducted once per year, preferably toward the end of the growing season. Samples will be taken from each test cell and send to a certified laboratory to perform the tests mentioned above. A visual survey of each test cell will be conducted toward the end of each growing season to assess the live plant cover and total cover available at each test cell.

2.7 Data Collection

All data collected manually will be recorded in a log book kept on site. Data gathered electronically will be downloaded from the recording device (or devices) and transferred to a diskette. Printed output of the electronic data (hard copies) will be kept in a file on site. Copies of the diskette may be archived for future reference.

3.0 ADDITIONAL TESTING FOR REVEGETATIVE SUCCESS

In addition to sampling the revegetated test cells, test plots will be established on the alluvium stockpiles to assess the ability to revegetate based on slope and aspect as well as seed mixture. The alluvium stockpile test plots will be tested in a manner consistent with the testing of the field test cells. At the commencement of the field testing, a soil sample will be taken from an adjacent area not impacted by mining, and a full suite of soil analyses will be conducted to determine the naturally occurring soil conditions.



NOTE:

1. CELL WILL NOT NECESSARILY BE CIRCULAR IN PLAN; CELL MAY BE SQUARE OR RECTANGLE, WITH MINIMUM SIDE LENGTH TO DEPTH RATIO OF 2:1.

SRK
STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

PROJECT NO.	DATE	REVISION
68606	01/98	A

FIGURE 1

TEST CELL CONCEPTUAL DESIGN
PLAN VIEW

* STA.#2 * J:\0686\68606\FIG01.DWG * NOV 23, 1998 * 3:19:51 PM *



STEFFEN ROBERTSON & KIRSTEN (U.S.) Consulting Engineers & Scientists		
PROJECT NO. 68606	DATE 01/98	REVISION A

FIGURE 2

TEST CELL CONCEPTUAL DESIGN
SECTION A–A'



STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

PROJECT NO.	DATE	REVISION
68606	01/98	A

FIGURE 3

TEST CELL CONCEPTUAL DESIGN
SECTION B–B'

APPENDIX D

Tailings Impoundment Conceptual Design Report (Golder, 2010)

REPORT

COPPER FLAT PROJECT

Conceptual Design Report

Submitted To: New Mexico Copper Corporation
Suite 100 - 2425 San Pedro Dr. NE
Albuquerque, NM 87110

Submitted By: Golder Associates Inc.
4730 N. Oracle Road
Suite 210
Tucson, AZ, 85705 USA

Distribution:
1 Electronic Copy – New Mexico Copper Corporation
1 Copy – Golder Associates

November 17, 2010 **103-92557**

A world of capabilities delivered locally

Golder Associates

01633

EXECUTIVE SUMMARY

Copper Flat is a porphyry copper mine that was briefly operated by Quintana Minerals Corp. (Quintana) in 1981 and 1982. After approximately 1 year of operation, mining was halted due to depressed copper prices, and the facility was decommissioned. New Mexico Copper Corporation (NMCC) has acquired an option on the Copper Flat property and is evaluating resuming mining and milling operations. Based on a recent NI 43-101 compliant preliminary economic assessment (PEA, [SRK, 2010]), the ore reserve has been increased from the 60 million tons identified by Quintana, to approximately 100 million tons. Ore will be mined at a rate of 17,500 tons per day (tpd). This report presents the conceptual design of a tailings storage facility (TSF) capable of supporting tailings disposal for the currently identified ore reserve.

During the 1981-82 operating period, high concentrations of total dissolved solids and sulfate were detected in groundwater immediately downgradient from the existing Quintana TSF. Local seepage of contaminated groundwater, which has been attributed to the existence of permeable geologic units in the TSF foundation, allowed process water and tailings seepage to migrate from the impoundment. Existing tailings are now drained and lie above the local groundwater table, however, leaching by meteoric water potentially contributes additional sulfate and dissolved solids to groundwater. Impacted groundwater and tailings from the 1981-82 operations are the subject of ongoing abatement actions. Groundwater compliance issues associated with the Quintana operation have led NMCC to propose construction of a lined TSF for future operations.

The starter dam from the earlier operations remains in place, however, in order to provide the required increase in storage capacity, while limiting future dam height and maintaining gravity delivery of tailings, the facility will be expanded approximately 1,000 feet to the east. It is assumed that the existing starter dam will be used as a borrow source for new embankment construction.

Approximately 1.2 million tons of tailings were placed in the north disposal cell prior to the suspension of operations in 1982. It is assumed that future TSF construction will require the incorporation of measures to mitigate potential groundwater impacts from existing tailings in order to meet groundwater contamination abatement actions. Several options for the management of existing tailings have been considered at a preliminary level. These include:

- Capping existing tailings in-place beneath a low permeability cover such as a geomembrane or composite cover;
- Utilize existing tailings as fine grained bedding fill for the future TSF geomembrane liner; and
- Place existing tailings inside the new TSF on top of the new geomembrane liner.

All options are considered to provide similar benefits relative to mitigating groundwater impacts associated with existing tailings.

The method of tailings embankment construction selected by Quintana was upstream raise construction with peripheral discharge of spigotted whole tailings. The proposed method of construction for the new TSF is by centerline raises with cycloned tailings sand. The tailings surface will rise approximately 80 feet in the first two years of operation. Centerline raising with cycloned sand was selected as the construction method because as a general rule, the tailings rate of rise should be less than 10 feet per year for upstream construction. NMCC's ability to develop a drained and consolidated foundation suitable for upstream raise construction using peripherally spigotted discharge of whole tailings is questionable due to the high rate of rise, which will not drop below 10 feet per year in the first 5 years of operation.

Initial construction will include a toe berm to buttress the tailings embankment and a starter dam for placement of the tailings header line and cyclones. Sand (cyclone underflow) will be placed on the embankment while the tailings slimes (cyclone overflow) will be discharged to the impoundment interior. The TSF geomembrane liner will be placed beneath the starter dam and anchored on the crest of the toe berm. An underdrain system consisting of a filter compatible soil and drainage collection pipes will be placed on top of the geomembrane liner, beneath the sand dam footprint, to facilitate drainage and consolidation of the cycloned sand. The underdrain system will extend into the impoundment interior in the area that will underlie the free water pond. Underdrainage will be routed to a lined underdrain collection pond located downstream of the toe berm.

The TSF can be constructed in a phased manner. During initial construction phases, diversion ditches can be constructed to divert stormwater from upstream catchment areas within the area contributory to the impoundment. The contributory area is approximately equivalent to the ultimate TSF footprint as only minor peripheral areas drain into the TSF. At final buildout, there is minimal potential for surface water runon from external areas. Throughout most of the life of the facility, stormwater management requirements will be limited to direct precipitation.

A review of available aerial photographs indicates no human habitations adjacent to the drainages below the proposed TSF. Based on the rules and regulations of the New Mexico State Engineer, the Copper Flat TSF would be classified as a large dam having significant hazard potential. The impoundment will be required to contain the equivalent of 75 percent of the probable maximum precipitation (PMP) during operations. A spillway capable of passing 75 percent of the PMP will be required upon closure.

Geotechnical investigation (SHB, 1980) of the existing TSF area was extensive, however, a portion of new TSF will occupy ground that has not been evaluated for geotechnical and hydrogeological conditions. A preliminary site investigation plan is presented in this conceptual design report.

Table of Contents

EXECUTIVE SUMMARY ES-1
1.0 INTRODUCTION 1
1.1 Scope of Work 1
1.2 Project History 1
2.0 SITE DESCRIPTION 2
2.1 Existing Conditions 2
2.2 TSF Area Geology and Foundation Conditions. 2
2.3 Climate 3
3.0 PROPOSED TAILINGS STORAGE FACILITY DESCRIPTION 4
3.1 TSF Geometry 4
3.2 Hazard Classification 5
3.3 Site Preparation 6
3.4 TSF Liner System 6
3.5 Underdrain System 7
3.6 Water Reclaim 7
3.7 Tailings Distribution 8
3.8 Surface Water, Underdrainage, Stormwater and Supernatant Management 8
3.8.1 Surface Water Diversion 8
3.8.2 Stormwater and Supernatant Management 9
4.0 CLOSURE AND RECLAMATION 10
5.0 DATA COLLECTION AND DESIGN STUDY REQUIREMENTS FOR ADVANCING TSF DESIGN 11
5.1 Geotechnical Investigation 11
5.1.1 Existing TSF Area 11
5.2 Tailings Characterization 11
5.3 Hydrogeological Characterization 12
5.4 Climatological Characterization 12
5.5 Engineering Studies 13
6.0 USE OF THIS REPORT 14
7.0 REFERENCES 15

List of Drawings

Drawing 1 Title Sheet
Drawing 2 General Site Layout
Drawing 3 Tailings Storage Facility Plan
Drawing 4 Tailings Storage Facility at Final Build-out
Drawing 5 Tailing Facility Storage Cross-Sections
Drawing 6 Tailings Storage Facility Underdrain Plan
Drawing 7 Tailings Storage Facility Details
Drawing 8 Height vs. Capacity Plot
Drawing 9 Tailings Storage Facility Conceptual Closure Plan

1.0 INTRODUCTION

1.1 Scope of Work

New Mexico Copper Corporation (NMCC) has acquired an option on the Copper Flat property, located near Hillsboro in Sierra County, New Mexico. Copper Flat is a porphyry copper deposit that was briefly mined by Quintana Resources in 1981 and 1982 before depressed copper prices forced the suspension of mining and milling operations. During the Quintana operation, the identified ore reserve was approximately 60 million tons. Further drilling completed since cessation of mining operations has increased the ore reserve from 60 million to approximately 100 million tons. NMCC has commissioned Golder Associates Inc. (Golder) to develop the conceptual design of a new tailings storage facility (TSF) capable of containing tailings from the expanded mining operation. Conceptual design of the new TSF, as well as plans for geotechnical investigation of the expanded TSF footprint and fulfilling data collection requirements necessary to advance the TSF design to feasibility and construction level are presented in this report.

1.2 Project History

The Quintana operation included open pit mining, conventional milling and off-site shipment of copper concentrate. Tailings were thickened to a solids content of 50 percent by weight (oral communication, Jack Bailey, 10/02/2010) and transported by gravity flow to the existing TSF located approximately 1 mile east of the open pit. Impoundment construction and operation were typical of the industry practices of the day. Whole tailings were discharged into the impoundment via a tailings header line and spigots placed peripheral to the impoundment. The TSF constructed for the Quintana operation remains in-place to this date. Remaining facilities include the starter embankment, internal splitter dikes, concrete decant towers and presumably, buried under drain pipes. Approximately 1.2 million tons of tailings were deposited in the existing north tailings cell.

The tailings thickener is reported to have been partially decommissioned and buried. The tailings delivery system has been removed. The Greyback Wash diversion, electrical supply lines, a water supply well field and water supply pipeline, groundwater monitoring wells and pumpback wells also remain. Milling and processing facilities were decommissioned and removed from the site.

During Quintana operations, elevated sulfate and dissolved solids were detected in groundwater in the vicinity of the existing tailings dam. Permeable foundation materials encountered during site investigation and construction of the TSF have been identified as the potential pathway for seepage from the TSF, Meteoric water leaching of tailings from the Quintana operation potentially contributes additional sulfate and dissolved solids to local groundwater. Impacted groundwater and the existing tailings are the subject of an ongoing abatement action. Management of existing tailings to mitigate existing and ongoing groundwater impacts is considered a parallel objective of TSF design.

2.0 SITE DESCRIPTION

2.1 Existing Conditions

The location of the proposed TSF is shown on Drawings 1 and 2. Elevation in the TSF basin area ranges from approximately 5,160 feet above mean sea level (amsl) near the base of the toe berm to over 5,500 feet on the ridges northwest of the impoundment footprint. Natural slopes range from 2 horizontal to 1 vertical (2H:1V) adjacent to the perimeter ridges to less than 10H:1V in the lower portion of the basin.

Previous disturbance of the TSF area is widespread. Existing features can be seen in the aerial photograph on Drawing 1. Drawing 2 shows the location of the proposed TSF projected on existing topography. Placer mining disturbance that predates the Quintana operation can be seen in most of the drainages in the TSF basin, and other drainages radiating from the mine area. More recent disturbance associated with the Quintana mining operation includes tailings deposits, the old starter dam and splitter dikes, construction material borrow areas and tailings delivery and reclaim water pipeline routes. Two concrete decant towers and concrete reclaim pipe foundations also remain in place and while not visible, buried reclaim water pipes also occur. A series of monitoring wells have been placed around the toe of the old starter dam.

The TSF site is located in the upper reaches of a shallow basin. The basin is bounded by low hills on the southwest, west and north sides such that the ultimate TSF will occupy most of the area that could contribute surface water runoff to the TSF. While diversions will be required in the early stages of the operation to divert stormwater runoff, peripheral areas contributing stormwater runon during the later stages of the future operations will be limited to a few acres on the northwest side of the TSF.

2.2 TSF Area Geology and Foundation Conditions.

The existing TSF site was extensively explored by Sargent, Hauskins and Beckwith (SHB) in 1979 and 1980 as part of the SHB design effort. No additional field work was conducted as part of conceptual design efforts. The upper layer of soils in the vicinity of the existing starter dam consists of sandy materials. Surficial sand is underlain by a wedge of silty clays, clayey and clayey silts that appears to thicken in a easterly direction. Gravels underlie the silts and clays and outcrop in the upper portion of the TSF basin. These gravels appear to have been the borrow source for the existing dam.

Permeable basalt was encountered in the lower portion of the tailings basin. The basalt is presumed to occupy a paleo-drainage cut in the local foundation soils. It can be seen in outcrop and subcrop south of the existing splitter dike and was intercepted in several exploratory boreholes completed in the central starter dam area. Due to its permeable nature, the basalt has been identified as the likely pathway for seepage and contaminants from the existing impoundment. This potential was identified during the design of the existing impoundment, and an attempt was made to cap the basalt with fine grained, low permeability soils to inhibit seepage.

2.3 Climate

The Copper Flat property experiences on the order of 10 to 13 inches per year of precipitation with the majority of rainfall occurring in the summer months associated with short duration, high intensity thunderstorms. Winter rains are associated with Pacific storms that generally migrate from west to east across the desert southwest. Summer temperatures exceed 100 degrees while winters are generally mild with limited snow and ground freezing.

In general, evaporation exceeds precipitation in desert lowlands across the region. It is anticipated that the tailings impoundment will be operated at net negative water balance, with periodic, temporary accumulation of stormwater from direct precipitation. Stormwater will be recovered with tailings supernatant water and reused in milling and processing. The effect of stormwater accumulation will be a reduction in raw make-up water requirements.

3.0 PROPOSED TAILINGS STORAGE FACILITY DESCRIPTION

3.1 TSF Geometry

The proposed method of tailings embankment construction is by the method of centerline raises. The basis for selection of this method is due to the high rate of tailings rise that will be experienced during the first 3 to 4 years of operation. Construction by upstream raises typically requires a rate of tailings rise of approximately 10 feet per year or less in order to allow consolidation and drainage of impounded tailings, and the development of conditions suitable for supporting upstream raises. The centerline method of construction using cycloned sand will allow the embankment to be constructed on a foundation of well drained sand.

A toe berm will be constructed around the periphery of the TSF which will serve as a buttress to the embankment outslopes. An internal starter dam is proposed for placement of the tailings discharge header pipe. Tailings will be delivered at a rate of 17,500 tpd at an anticipated solids content of 50 percent by weight. At 92 percent availability, the annual tailings deposition rate will be 5.88 million tons.

Cyclones on the tailings header line will be used to separate the sand fraction (cyclone underflow) from the whole tailings stream. Tailings sand will be used for embankment construction while the fine fraction of the tailings, the tailing slimes (cyclone overflow), will be discharged into the impoundment interior. The resulting tailings impoundment surface will slope away from the embankment and force tailings supernatant and stormwater into the interior of the impoundment. The locations of the toe berm and starter dam are shown on Drawing 3.

The crest elevation of the starter dam and toe berm have initially been set at 5,220 feet amsl. Adjustments to the height of these structures will be evaluated in detailed design studies. Starter dam height will be determined by the dry freeboard required to maintain stormwater storage capacity and the volume of sand that will be available for dam construction during operations. The availability of sand will be determined by the degree of ore milling. A finer grind will reduce sand content and could require a higher initial starter dam height while a coarser grind will provide more sand and allow an increased rate of sand deposition. Toe berm height will be influenced by the stability of the tailings embankment. The embankment sand and underdrain will be placed over a geomembrane liner. Interface friction at the liner/subgrade and the liner/underdrain interfaces will be reduced relative to the friction developed at a soil to tailings interface. The berm may be required to buttress the embankment toe to enhance stability. Toe berm and initial starter dam heights will be evaluated when tailings products representative of the future processing plan are available for evaluation and geotechnical testing.

Above the elevation of the initial starter dam and toe berm, these structures will be constructed parallel to existing topography with a constant height above foundation level. Progressive lateral extension of the tailings distribution points up the starter dam will enable the dam to be raised in level manner.

Tailings gradation data presented in the various reports prepared for Quintana are somewhat contradictory. Based on metallurgical pilot studies conducted for Quintana and reported by SHB (1980), the sand fraction (the plus 200 standard sieve fraction) of the tailings is approximately 30 percent with 95 percent finer than 65 mesh (208 microns). Measurements collected by Quintana mill personnel between May and June of 1982 (oral communication, Jack Bailey, 10/1/2010) showed a minus 65 mesh fraction of 84 to 89 percent, suggesting a courser tailings grind with a higher sand fraction was produced under operating conditions. The gradation presented in the SHB geohydrological study (SHB, 1981) indicates tailings that are 100 percent finer than 65 mesh with a sand fraction of 55 percent. Preliminary volumetric estimates indicate that embankment construction will require approximately 15 percent of future tailings, suggesting that the centerline approach is feasible. Evaluation of tailings samples produced in pilot or bench scale simulation of future milling and processing will be required to verify sand availability throughout the life of the operation.

The impoundment has been sized based on a post-deposition dry density of 85 pounds per cubic foot (pcf). The estimated maximum final tailings surface elevation is 5,375 feet amsl. The maximum toe to crest height of the tailings embankment will be approximately 215 feet. At final buildout, the TSF and underdrain collection pond will occupy an area of approximately 541 acres. The anticipated configuration of the TSF at the end of mining and milling operations is shown on Drawing 4. TSF cross sections are shown on Drawing 5.

The tailings surface will slope inward from peripheral points of deposition at approximately ½ to 1 percent forming a depression in the interior of the impoundment. The internal depression will serve as a storage area for supernatant solutions and stormwater.

Embankment outslopes shown on the drawings are 2.67H:1V. Outslopes may also be subject to modification based on geotechnical testing of tailings properties.

3.2 Hazard Classification

The rules and regulations of the New Mexico State Engineer indicate that the Copper Flat TSF will be classified as having significant hazard potential. According to the New Mexico Administrative Code (19.25.12.10 B NMAC):

> *Dams assigned the significant hazard potential classification are those dams where failure or misoperation results in no probable loss of human life but can cause economic loss, environmental damage, disruption of lifeline facilities, or can impact other concerns. Significant hazard potential classification dams are often located in predominantly rural or agricultural areas but could be located in populated areas with significant infrastructure.*

The TSF lies within the Greyback Wash drainage. Inspection of aerial photographs (Google Earth) indicates no human habitations in or adjacent to Greyback Wash between the TSF facility and Caballo Lake, into which Greyback Wash ultimately discharges. A dam breach and flood routing analysis will be required by the State Engineer (19.25.11.12 C (1) NMAC) to verify this classification.

The spillway design flood for dams with significant hazard potential (19.25.12.11 C(1) (c) is 75 percent of the probable maximum precipitation (PMP). A preliminary estimate of the PMP is on the order of 25 inches. The TSF and ore processing facilities will be operated as a closed, non-discharging system during tailings disposal operations and storage capacity for the design storm event will be maintained within the TSF. A permanent spillway capable of passing the design flood will be required at closure after the tailings surface has been regraded and a reclamation cover is in place.

3.3 Site Preparation

The TSF will be a geomembrane lined structure. Site preparation will include clear and grubbing, salvage and stockpiling of topsoil and grading to prepare a smooth surface for geomembrane liner installation.

It is anticipated that the existing starter dam and associated splitter dikes will be used as a fill material borrow source for the new toe berm and starter dam. Additional borrow areas for structural fill, liner bedding materials and drainage media will be developed within the TSF footprint where possible. Previous geotechnical investigation of the site indicates a range of fine grained soils and granular materials occur within the existing disturbance area.

Approximately 1.2 million tons of tailings were discharged into the existing TSF during the Quintana operation. Existing tailings deposits will be evaluated as a source of liner bedding fill material. If placed or “capped” under a low permeability TSF liner, the potential for leaching sulfate and dissolved solids from existing tailings in the future will be alleviated. Alternatively, existing tailings could be placed on the new TSF liner however, utilization of the tailings as liner bedding fill material is anticipated to be less costly and will provide similar benefits in terms of mitigating leaching potential.

The existing decant towers will be demolished. Demolition debris will be buried locally or placed in a waste rock disposal facility. Demolition requirements for buried decant pipelines will be evaluated as part of ongoing site investigation and design efforts.

Existing wells in the TSF expansion will require abandonment in accordance with New Mexico Environment Department (NMED) Office of the State Engineer (OSE) regulations. For wells that intercept groundwater, this will include removal of casings if possible, and sealing the entire well bore with cement or bentonite grout placed by tremmie pipe. Approximately 18 wells appear to lie within the TSF expansion area.

3.4 TSF Liner System

Proposed liner system details for the TSF and underdrain collection pond are shown on Drawings 6 and 7. The TSF liner will consist of an HDPE geomembrane placed on a minimum 6-inch thick layer of liner bedding fill. Beneath the starter dam and embankment underdrain, an 80 mil (0.080 inches) geomembrane is proposed while within the impoundment interior, the geomembrane thickness will be 60 mil. The underdrain collection pond liner will consist of a lower 60 mil and upper 80 mil HDPE

geomembranes separated by a drain net. The drain net will route potential leakage through the upper liner to a leakage collection and recovery sump.

Geomembrane liner will be placed on a minimum 6-inch thick layer of liner bedding fill. As noted above, the liner bedding fill can be constructed with existing tailings if they meet moisture content and compaction requirements. Additional liner bedding fill material can be derived from crushing and/or screening of selected native soils. A minus 3/8-inch material is suitable for protection of the liner.

3.5 Underdrain System

An underdrain will be placed beneath the starter dam and cycloned sand embankment. The underdrain system is shown on Drawing 6. The purpose of the embankment underdrain is to facilitate drainage and consolidation of cycloned sand placed in the tailings embankment. The underdrain will consist of graded sand and gravel that is filter compatible with the tailings sand. A series of perforated drain pipes will be placed within the underdrain layer to carry tailings drainage to the underdrain collection pond.

The under drain will be extended into the impoundment interior beneath the area that will be occupied by the supernatant pool. Production of drainage material that is filter compatible with the tailings slimes discharged into the impoundment interior will not be feasible. The impoundment underdrain will be separated from the tailings slimes by a geotextile filter fabric cover. Impoundment underdrainage will be routed to the underdrain collection pond in a piping system that is separate from the embankment under drain.

The pond layout presented as part of the conceptual design has a capacity of over 40 million gallons and represents the maximum potential construction area required for underdrain pond installation. Water balance and drainage analyses that will be completed during engineering design studies will be used to determine the underdrain collection pond size required to manage tailings underdrainage.

3.6 Water Reclaim

A water reclaim ramp with be constructed on top of the TSF liner system. The ramp will provide access to the free water pool for reclaim of supernatant solution and stormwater. The ramp will be raised and extended as deposition continues and the impoundment surface rises. The reclaim pump works will be progressively moved northward as the operation proceeds.

The ramp will be constructed with borrowed fill or waste rock from the mining operation. A cushioning layer will be placed beneath the initial ramp fill to protect the underlying geomembrane. The ramp presents an opportunity to dispose of potentially acid generating waste rock in an environment where ongoing tailings disposal will result in the ramp fill being encapsulated within low permeability tailings slimes.

3.7 Tailings Distribution

It is anticipated that a new thickener will be constructed at the location of the Quintana thickener (Drawing 2) and a tailings delivery pipeline will be routed to the impoundment through the existing tailings delivery pipeline cut. At the impoundment, a wye in the delivery pipeline will allow the tailings to be directed to the east and west to the starter dam crest. A series of discharge points and cyclones around the periphery of the impoundment will be used to direct cyclone underflow to the tailings embankment and cyclone overflow into the impoundment interior. Discharge will be cycled around the impoundment to raise the embankment in a level manner.

Regrading and compaction of the cycloned sand deposited on the dam crest will be conducted on a regular basis to densify the tailings embankment and achieve the design embankment outslope.

Drawing 8 presents a height versus capacity plot for the new TSF. There is potential to increase the capacity of the TSF beyond that shown on the plot, however, distribution of tailings above the elevation of 5,375 feet amsl is likely to require pumping of the whole tailings slurry. In addition, a tailings booster pump may be required in the later years of operation to maintain adequate pressure for cyclone operation.

3.8 Surface Water, Underdrainage, Stormwater and Supernatant Management

The intent of design is to allow the TSF to be operated as a zero discharge facility. Drainage from the tailings will be collected in an underdrain system, routed to a lined underdrain collection pond and recycled as process water. Potential runon from peripheral contributory areas will be prevented from contacting the tailings and diverted into natural drainages. Stormwater, which will result primarily from direct precipitation and supernatant will be contained within the impoundment.

3.8.1 Surface Water Diversion

During initial construction, perimeter diversions will be constructed across the west periphery of the impoundment. The approximately location of Phase 1 surface water diversions is shown on Drawing 3. As the impoundment is expanded in subsequent construction phases, diversion ditches will be relocated westward.

Potential runoff from peripheral areas west of the impoundment during the later stages of operation will be evaluated during design studies. Where runon is significant, diversion ditches will be investigated.

As noted above, at final buildout the TSF will occupy the majority of the area that can contribute surface water runon into the tailings impoundment. Only limited areas west of the impoundment might require late stage and post-closure diversion.

3.8.2 Stormwater and Supernatant Management

During operations, capacity will be maintained within the TSF for storage of direct precipitation and tailings supernatant. Upon discharge into the impoundment, tailings will form a beach sloping away from the point of discharge at ½ to 1 percent. The resulting depression on the tailings surface in the interior of the impoundment will be used for water storage. Additional storage capacity, if needed, will be developed by maintaining reserve freeboard on the tailings embankment crest.

A detailed water balance will be developed as part of the design studies to evaluate internal storage and embankment freeboard requirements. Water balance inputs include process water inflows, direct precipitation and runon. Losses include process water reclaim, beach and tailings pond evaporation, underdrainage and entrainment of process water within the tailings pore space. The rates of underdrainage, entrainment and tailings supernatantliberation on discharge will be determined through geotechnical testing of representative tailings samples.

Water storage requirements include:

- Dead storage (water that cannot be recovered by the reclaim system);
- Storage of the normal process water inventory to facilitate continuous operations;
- Normal stormwater storage which will vary on a seasonal basis due to changes in monthly precipitation and evaporation rates; and
- Storage for the design storm event, which is currently assumed to be 75 percent of the PMP.

The water balance will be coupled with a discharge model that will track the rate of tailings rise and simulate beach slopes and the topography of the tailings surface. The water balance and discharge model can then be used to estimate internal storage capacity and requirements for embankment freeboard through the life of the facility.

4.0 CLOSURE AND RECLAMATION

The conceptual closure plan for the TSF is illustrated on Drawing 9. The conceptual closure plan includes the following:

- Final grading of embankment outslopes to establish erosion controls and controlled surface water drainage (best management practices);
- Placement of a soil or rock cover and revegetation of the embankment outslope;
- Placement of riprap and erosion controls in embankment surface water drainage facilities;
- Regrading or depositional modification of the impoundment surface to promote drainage to a permanent spillway;
- Placement and vegetation of a soil cover over the tailings surface;
- Armoring of surface drainage channels and implementation of best management practices for erosion control; and
- Management of underdrainage.

Final grading of the impoundment surface can be accomplished with earthmoving equipment, or through modification of tailings disposal patterns during the final years of operation. Tailings discharge from selected locations can be used to relocate the supernatant pool to a location adjacent to the post-closure spillway, thereby reducing grading requirements and limiting earthmoving operations in areas where working conditions are expected to be difficult due to the presence of soft and saturated tailings. At the location of the spillway shown on Drawing 9, a bedrock foundation is anticipated. If the spillway channel is erodible, grouted riprap or other erosion controls will be applied.

Consolidation seepage into the underdrain system can be anticipated to continue at declining rates for an indefinite period following the cessation of tailings disposal operations. Underdrainage will be pumped from the underdrain collection pond to the surface of the tailings impoundment where it can be evaporated or used for reclamation cover irrigation. When underdrainage is reduced to an acceptably low flow rate, the underdrain pipes beneath the embankment can be sealed with grout and the underdrain collection pond can be decommissioned.

5.0 DATA COLLECTION AND DESIGN STUDY REQUIREMENTS FOR ADVANCING TSF DESIGN

The following defines work to be completed to advance the design of the new TSF to feasibility study and construction level.

5.1 Geotechnical Investigation

5.1.1 Existing TSF Area

The area occupied by the Quintana TSF area was extensively investigated by SHB (1980). Approximately 30 boreholes were drilled along the starter dam alignment. The majority of the borings were completed by hollow stem auger (HSA) and locally included in-situ permeability testing and diamond coring. Additional borings were completed in the impoundment interior. Test pits were excavated inside the impoundment on an approximate 500 foot by 500 foot grid.

Additional exploration will be undertaken in the area investigated by SHB to identify borrow areas for liner bedding fill and drainage media. This work is expected to require a test pit exploration program with native soil samples subjected to gradation analysis, Atterburg limits, permeability and compaction testing. This program will include sampling of existing tailings for compaction and permeability testing.

TSF Expansion Area investigation should include the following:

- A seismic velocity survey to evaluate the depth to bedrock and/or competent materials beneath the new embankment axis;
- Hollow stem auger drilling with standard penetration testing to obtain foundation material samples and measure in-situ density. Borehole spacing on the order of 300 to 500 feet is proposed along the new embankment axis.
- Selected HSA borings will be converted to core drilling to enable recovery of bedrock samples and support measurement of in-situ permeability by packer testing.
- Falling head or constant head permeability testing may also be performed in selected borings.
- Shelby tube and split spoon drive ring samples will be collected from selected intervals for analysis of in-situ density, natural moisture content and settlement potential.
- Test pit excavation will be performed in the expansion area to identify potential construction materials outside the previously explored area. Required materials include structural fill for the toe berm and starter dam, liner bedding fill and drain fill.

5.2 Tailings Characterization

NMCC reports that ore processing at Copper Flat will closely follow the process flow sheet developed by Quintana for 1981-82 operations. The characteristics of future tailings will impact operation of the new TSF. There are limited data concerning tailings properties from the Quintana operation, and production records (Oral communication, J. Bailey, 2010) indicate a coarser tailings product was produced during operations than would be predicted based on the pilot study tailings data presented in the original TSF design report (SHB, 1980).

Pilot or bench scale milling and flotation studies are recommended in support of final design studies to determine the physical and geochemical properties of future tailings. The primary objectives of the proposed study include:

- Evaluation of the partitioning of residual sulfides between cyclone underflow and overflow, and assessment of the acid generating and metal leaching potential of both the sand and slimes fractions;
- Determination of the gradation of future whole tailings and the quantity of sand that can be recovered for embankment construction;
- Evaluation of the flow characteristics of the whole tailings slurry;
- Measurement of the shear strength of tailings sand; and
- Measurement of the permeability of tailings sand and slimes under anticipated disposal conditions.

The milling and flotation test work should produce a sufficient quantity of tailings to enable a cyclone simulation to be performed in order to produce samples of both cyclone overflow and underflow. At minimum, the cyclone simulation will require a 55 gallon drum of tailings solids. The sand and slimes fractions produced in the simulation will be sufficient to support a full range of geotechnical and geochemical tests. Tailings should be subjected to the following tests:

- Gradation (sieve and hydrometer), Atterberg Limits, specific gravity (whole tailings, cyclone underflow and overflow);
- Compaction testing (cyclone underflow);
- Slurry consolidation testing (cyclone underflow and overflow);
- Staged triaxial consolidated, undrained shear strength testing with pore pressure measurement (cyclone underflow);
- Air drying (cyclone overflow);
- Shrinkage limit (cyclone overflow); and
- Acid base accounting, net acid generation (NAG), total metals, major oxides by x-ray florescence (XRF), leach extraction testing, and mineralogy by x-ray diffraction (XRD) (cyclone underflow and overflow).

5.3 Hydrogeological Characterization

Local monitoring wells that will be decommissioned during TSF expansion will require replacement in the area below the new toe berm and underdrain collection pond. Water level measurements and in-situ permeability tests conducted concurrently with drilling and well installation can be used in conjunction with existing data to evaluate hydrogeological conditions in the TSF expansion area.

5.4 Climatological Characterization

Estimation of normal precipitation and evaporation rates will be required to develop an impoundment water balance. It is assumed that a climatological model will be developed using a combination of locally collected weather data combined with regional weather records from National Weather Service monitoring stations.

5.5 Engineering Studies

The following is a listing of design studies that will be required to complete the design of the TSF:

- Foundation settlement analyses;
- Tailings drainage analyses;
- Seismic hazard analysis:
- Static and dynamic embankment stability analyses, including estimation of displacement under seismic loading;
- Seismic and static (monotonic loading, flow slide) liquefaction potential analyses;
- Evaluation of tailings sand availability, mass balance and deposition modeling;
- Liner seepage assessment;
- Foundation hydrogeological assessment;
- Water balance;
- Tailings basin hydrologic assessment for surface water diversion sizing;
- Estimation of design storm event (PMP) precipitation;
- Dam breach analysis as per OSE requirements.

6.0 USE OF THIS REPORT

This report has been prepared exclusively for the use of New Mexico Copper Corporation (NMCC) for specific application to the Copper Flat Project. No third party engineer or consultant shall be entitled to rely on any of the information, conclusions, or opinions contained in this report without prior written approval from NMCC or Golder Associates, Inc (Golder).

The conclusions and recommendations in this report have been prepared in a manner consistent with the level of care and skill ordinarily exercised by engineering professionals currently practicing under similar conditions, subject to the time limits and financial and physical constraints imposed on, or otherwise applicable to, Golder's analyses.

In preparing its conclusions and recommendations, Golder has relied upon information provided by the client. Golder is not responsible for errors or omissions in the information provided by NMCC.

GOLDER ASSOCIATES INC.

Eugene Muller, P.E.
Senior Engineer

David A. Kidd, P.E.
Principal, Geotechnical Practice Leader

GM/DAK/br

7.0 REFERENCES

Jack Bailey, October 1, 2010. Oral Communication, milling records, 65 mesh fraction, Quintana Minerals Corp, April through June 1982.

Google.Com, 2010, Google Earth images, 32^{o} 57'33" N, 107^{o} 29' 57 'W

Sargent Hauskins and Beckwith (SHB), 1981. *Geohydrological Evaluation for Submission of Discharge Plan, Copper Flat Project, Quintana Minerals Corporation, Sierra County, New Mexico*. SHB Report E80-194, June 21, 1981.

Sargent Hauskins and Beckwith (SHB), 1980. Tailings Dam and Disposal Area, Quintana Minerals Corporation, Copper Flats Project, Gold Dust, New Mexico (Final Geotechnical and Design Development Report), SHB Report E80-1030B, October 14, 1980.

SRK Consulting Inc., 2010. *NI 43-101 Preliminary Economic Assessment, THEMAC Resources Group Limited, Copper Flat Project, Sierra County, New Mexico*, SRK Report No. 191000.020, June 30, 2010

DRAWINGS

COPPER FLAT PROJECT
TAILINGS STORAGE FACILITY
CONCEPTUAL DESIGN STUDY
SIERRA COUNTY, NEW MEXICO



AERIAL PHOTOGRAPH OF PROPOSED TAILINGS DISPOSAL SITE

NOT TO SCALE



STATE OF NEW MEXICO

NOT TO SCALE

LIST OF DRAWINGS

DWG No.	DRAWING TITLE
1	TITLE SHEET
2	GENERAL SITE LAYOUT
3	TAILINGS STORAGE FACILITY PLAN
4	TAILINGS STORAGE FACILITY PLAN AT FINAL BUILD-OUT
5	TAILINGS STORAGE FACILITY CROSS-SECTIONS
6	TAILINGS STORAGE FACILITY UNDERDRAIN PLAN
7	TAILINGS STORAGE FACILITY DETAILS
8	TAILINGS STORAGE FACILITY HEIGHT VS CAPACITY PLOT
9	TAILINGS STORAGE FACILITY CONCEPTUAL CLOSURE PLAN

GENERAL NOTES

1. EXISTING FIVE (5) FOOT TOPOGRAPHY AND PERMIT BOUNDARY PROVIDED BY NEW MEXICO COPPER CORPORATION.
2. AERIAL PHOTOGRAPHY © GOOGLE 2010, NMRGIS 2010.
3. DRAWINGS PRESENT THE CONCEPTUAL DESIGN OF A PROPOSED NEW AND EXPANDED TAILINGS STORAGE FACILITY WITH A CAPACITY OF 100 MILLION TONS AT AN ASSUMED DRY DENSITY OF 85 POUND PER CUBIC FOOT.
4. FINAL DESIGN WILL BE COMPLETED IN ACCORDANCE WITH THE RULES AND REGULATIONS OF THE NEW MEXICO STATE ENGINEER, THE NEW MEXICO ENVIRONMENT DEPARTMENT (NMED) AND THE NEW MEXICO MINING AND MINERALS DIVISION (NM MMD).
5. AERIAL PHOTOGRAPH SHOWS EXISTING TAILINGS DISPOSAL AREA DISTURBANCE FROM MINING, MILLING AND TAILINGS DISPOSAL OPERATIONS CONDUCTED BY QUINTANA RESOURCES IN 1981-82.
6. EXISTING TAILINGS FROM THE QUINTANA 1981-82 OPERATIONS ARE THE SUBJECT OF AN ONGOING ABATEMENT ACTION. THE CONCEPTUAL DESIGN CONSIDERS CAPPING EXISTING TAILINGS BENEATH THE FUTURE IMPOUNDMENT LINER SYSTEM THROUGH THEIR INCORPORATION IN THE LINER BEDDING FILL LAYER, OR PLACEMENT OF EXISTING TAILINGS ON THE NEW IMPOUNDMENT LINER. ALTERNATIVES FOR MANAGEMENT OF EXISTING TAILINGS WILL BE DEVELOPED IN CONSULTATION WITH NMED.

DRAWING USE	CONCEPTUAL DESIGN NOT FOR CONSTRUCTION
PROJECT	COPPER FLAT PROJECT TAILINGS STORAGE FACILITY CONCEPTUAL DESIGN STUDY SIERRA COUNTY, NEW MEXICO
TITLE	**TITLE SHEET**

Golder Associates

PROJECT No.	103-92557		FILE No.	10392557A001
DESIGN	CDJ	10/25/10	SCALE AS SHOWN	REV. C
CADD	ANV	10/27/10	DRAWING	1
CHECK	GM	10/29/10		
REVIEW	DAK	11/17/10		

Drawing file: K:\2010 Projects\103-92557 Copper Flat\103925570001.dwg Nov 23, 2010 - 11:00am

LEGEND

PERMIT BOUNDARY

GENERAL NOTES

1. EXISTING FIVE (5) FOOT TOPOGRAPHY AND PERMIT BOUNDARY PROVIDED BY NEW MEXICO COPPER CORPORATION
2. DRAWINGS PRESENT THE CONCEPTUAL DESIGN OF A PROPOSED NEW AND EXPANDED TAILINGS STORAGE FACILITY WITH A CAPACITY OF 100 MILLION TONS AT AN ASSUMED DRY DENSITY OF 85 POUND PER CUBIC FOOT
3. FINAL DESIGN WILL BE COMPLETED IN ACCORDANCE WITH THE RULES AND REGULATIONS OF THE NEW MEXICO STATE ENGINEER, THE NEW MEXICO ENVIRONMENT DEPARTMENT (NMED) AND THE NEW MEXICO MINING AND MINERALS DIVISION (NM MMD).
4. TOPOGRAPHY IN THE MINE AREA AND TAILINGS STORAGE FACILITY REPRESENTS EXISTING CONDITIONS AND DISTURBANCE ASSOCIATED WITH QUINTANA 1981-82 MINING OPERATIONS
5. PROPOSED TAILINGS STORAGE FACILITY FOOTPRINT IS FOR A NEW FACILITY WITH A CAPACITY OF 100 MILLION TONS AT AN ASSUMED DRY DENSITY OF 85 POUND PER CUBIC FOOT

600 0 600 1200
SCALE FEET

DAVID ALAN KIRK
NEW MEXICO
13778
11-17-10
REGISTERED PROFESSIONAL ENGINEER

DRAWING USE
CONCEPTUAL DESIGN
NOT FOR CONSTRUCTION

PROJECT
COPPER FLAT PROJECT
TAILINGS STORAGE FACILITY
CONCEPTUAL DESIGN STUDY
SIERRA COUNTY, NEW MEXICO

TITLE
GENERAL SITE LAYOUT

Golder Associates

PROJECT No.		103-92557	FILE No.		10392557A002
DESIGN	CDJ	10/25/10	SCALE	AS SHOWN	REV. B
CADD	ANV	10/27/10	DRAWING		2
CHECK	GM	10/29/10			
REVIEW	DAK	11/17/10			

Drawing File: K:\2010 Projects\103-92557 Copper Flat\10392557A002.dwg Nov 23, 2010 - 11:14am



LEGEND

- EXISTING CONTOURS
- 5200 DESIGN CONTOURS
- PHASE 1 SURFACE WATER DIVERSION FLOW ARROW
- PERMIT BOUNDARY
- INITIAL CONSTRUCTION BOUNDARY
- FINAL TAILINGS BUILD-OUT
- 3/7 DETAIL CALL-OUT
- A/5 CROSS-SECTION CALL-OUT

NOTES

1. DRAWINGS PRESENT THE CONCEPTUAL DESIGN OF A NEW AND EXPANDED TAILINGS STORAGE FACILITY WITH A CAPACITY OF 100 MILLION TONS AT AN ASSUMED DRY DENSITY OF 85 POUND PER CUBIC FOOT.
2. FINAL DESIGN WILL BE COMPLETED IN ACCORDANCE WITH THE RULES AND REGULATIONS OF THE NEW MEXICO STATE ENGINEER, THE NEW MEXICO ENVIRONMENT DEPARTMENT (NMED) AND THE NEW MEXICO MINING AND MINERALS DIVISION (NM MMD).
3. EXISTING FIVE (5) FOOT TOPOGRAPHY AND PERMIT BOUNDARY PROVIDED BY NEW MEXICO COPPER CORPORATION.
4. TOPOGRAPHY IN THE VICINITY OF THE QUNITANA STARTER DAM AND TAILINGS CELLS APPROXIMATED BY GOLDER TO REPRESENT PRECONSTRUCTION TOPOGRAPHY FOLLOWING DEMOLITION (BORROW) OF THE EXISTING STARTER EMBANKMENT, RELOCATION OF EXISTING TAILINGS AND REGRADING IN FORMER BORROW AREAS AND EXISTING DISTURBANCE AREAS. TOPOGRAPHY IN OTHER LOCATIONS REPRESENTS EXISTING CONDITIONS. A SITE WIDE TAILINGS DISPOSAL FACILITY GRADING PLAN WILL BE DEVELOPED IN FUTURE DESIGN STUDIES.
5. EXISTING TAILINGS FROM THE QUINTANA 1981-82 OPERATIONS ARE THE SUBJECT OF AN ONGOING ABATEMENT ACTION. THE CONCEPTUAL DESIGN CONSIDERS CAPPING EXISTING TAILINGS BENEATH THE FUTURE IMPOUNDMENT LINER SYSTEM THROUGH THEIR INCORPORATION IN THE LINER BEDDING FILL LAYER, OR PLACEMENT OF EXISTING TAILINGS ON THE NEW IMPOUNDMENT LINER. ALTERNATIVES FOR MANAGEMENT OF EXISTING TAILINGS WILL BE DEVELOPED IN CONSULTATION WITH NMED.
6. PHASE 1 CONSTRUCTION LIMITS ARE APPROXIMATELY LOCATED. PHASE 1 AND SUBSEQUENT CONSTRUCTION PHASE LIMITS AND SURFACE WATER DIVERSION REQUIREMENTS WILL BE DETERMINED IN FUTURE ENGINEERING DESIGN STUDIES.
7. EMBANKMENT RAISES WILL BE CONSTRUCTED BY THE CENTERLINE RAISE METHOD USING CYCLONE UNDERFLOW (TAILINGS SAND). CYCLONE OVERFLOW (SLIMES) WILL BE DISCHARGED INTO THE INTERIOR OF THE TAILINGS STORAGE FACILITY.
8. DURING OPERATION, STORMWATER WILL BE CONTAINED WITHIN THE TAILINGS STORAGE FACILITY AND UTILIZED AS PROCESS MAKE-UP WATER. A PROJECT WATER BALANCE WILL BE DEVELOPED IN FUTURE ENGINEERING DESIGN STUDIES

DAVID ALAN KIDD NEW MEXICO 13778 REGISTERED PROFESSIONAL ENGINEER 11-17-10

400 0 400 800 SCALE FEET

DRAWING USE
CONCEPTUAL DESIGN NOT FOR CONSTRUCTION

PROJECT
COPPER FLAT PROJECT
TAILINGS STORAGE FACILITY
CONCEPTUAL DESIGN STUDY
SIERRA COUNTY, NEW MEXICO

TITLE
TAILINGS STORAGE FACILITY PLAN

Golder Associates

PROJECT No.		103-92557	FILE No.		10392557A003
DESIGN	CDJ	10/25/10	SCALE	AS SHOWN	REV. B
CADD	ANV	10/27/10	DRAWING		3
CHECK	GM	10/29/10			
REVIEW	DAK	11/17/10			

Drawing File: K:\2010 Projects\103-92557 Copper Flat\10392557A003.dwg Nov 22, 2010 - 11:15am



LEGEND

- EXISTING CONTOURS
- 5200 DESIGN CONTOURS
- PERMIT BOUNDARY
- A/5 CROSS-SECTION CALL-OUT

NOTES

1. DRAWINGS PRESENT THE CONCEPTUAL DESIGN OF A NEW AND EXPANDED TAILINGS STORAGE FACILITY WITH A CAPACITY OF 100 MILLION TONS AT AN ASSUMED DRY DENSITY OF 85 POUND PER CUBIC FOOT.
2. FINAL DESIGN WILL BE COMPLETED IN ACCORDANCE WITH THE RULES AND REGULATIONS OF THE NEW MEXICO STATE ENGINEER, THE NEW MEXICO ENVIRONMENT DEPARTMENT (NMED) AND THE NEW MEXICO MINING AND MINERALS DIVISION (NM MMD)
3. EXISTING FIVE (5) FOOT TOPOGRAPHY AND PERMIT BOUNDARY PROVIDED BY NEW MEXICO COPPER CORPORATION
4. FINAL EMBANKMENT CREST HEIGHT WILL BE APPROXIMATELY 5,375 FEET AMSL. TAILINGS SURFACE CONFIGURATION SHOWN REPRESENTS CONDITIONS AT THE CESSATION OF MINING OPERATIONS. APPROXIMATE LOCATION OF A POST-CLOSURE SPILLWAY SHOWN. TAILINGS DISCHARGE LOCATIONS MAY BE MODIFIED IN LATE STAGE OPERATIONS TO GRADE THE IMPOUNDMENT SURFACE AND FACILITATE POST-CLOSURE DRAINAGE TO THE PERMANENT SPILLWAY.
5. SELECTION OF A DESIGN STORM EVENT FOR STORMWATER STORAGE AND SPILLWAY CAPACITY WILL BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE NEW MEXICO STATE ENGINEER.

DAVID ALAN KIDD
NEW MEXICO
13778
REGISTERED PROFESSIONAL ENGINEER
11-17-10

400 0 400 800
SCALE FEET

DRAWING USE	CONCEPTUAL DESIGN NOT FOR CONSTRUCTION
PROJECT	COPPER FLAT PROJECT TAILINGS STORAGE FACILITY CONCEPTUAL DESIGN STUDY SIERRA COUNTY, NEW MEXICO
TITLE	**TAILINGS STORAGE FACILITY AT FINAL BUILD-OUT**

Golder Associates

PROJECT No.		103–92557	FILE No.		10392557A004
DESIGN	CDJ	10/25/10	SCALE	AS SHOWN	REV. C
CADD	ANV	10/27/10	DRAWING	4	
CHECK	GM	10/29/10			
REVIEW	DAK	11/17/10			

Drawing file: K:\2010 Projects\103-92557 Copper Flat\10392557A004.dwg Nov 22, 2010 - 11:15am



A/5 **CROSS SECTION A-A'**

SCALE 250 0 250 500 FEET



B/5 **CROSS SECTION B-B'**

SCALE 250 0 250 500 FEET



C/5 **CROSS SECTION C-C'**

SCALE 100 0 100 200 FEET

DRAWING USE
CONCEPTUAL DESIGN
NOT FOR CONSTRUCTION

PROJECT
COPPER FLAT PROJECT
TAILINGS STORAGE FACILITY
CONCEPTUAL DESIGN STUDY
SIERRA COUNTY, NEW MEXICO

TITLE
TAILING FACILITY STORAGE CROSS-SECTIONS

Golder Associates

PROJECT No.		103-92557	FILE No.		10392557A005
DESIGN	CDJ	10/25/10	SCALE	AS SHOWN	REV. C
CADD	ANV	10/27/10	DRAWING		5
CHECK	GM	10/29/10			
REVIEW	DAK	11/17/10			

Drawing File: K:\2010 Projects\103-92557 Copper Flat\10392557A005.dwg Nov 22, 2010 - 11:25am



LEGEND

- EXISTING CONTOURS
- 6200 DESIGN CONTOURS
- PHASE 1 SURFACE WATER DIVERSION FLOW ARROW
- PERMIT BOUNDARY
- PHASE 1 BOUNDARY
- FINAL TAILINGS BUILD-OUT
- PRIMARY UNDERDRAIN PIPE
- PRIMARY DRAIN PIPE
- UNDERDRAIN FILL
- 3/7 DETAIL CALL-OUT

NOTES

1. DRAWINGS PRESENT THE CONCEPTUAL DESIGN OF A NEW AND EXPANDED TAILINGS STORAGE FACILITY WITH A CAPACITY OF 100 MILLION TONS AT AN ASSUMED DRY DENSITY OF 85 POUND PER CUBIC FOOT.
2. FINAL DESIGN WILL BE COMPLETED IN ACCORDANCE WITH THE RULES AND REGULATIONS OF THE NEW MEXICO STATE ENGINEER, THE NEW MEXICO ENVIRONMENT DEPARTMENT (NMED) AND THE NEW MEXICO MINING AND MINERALS DIVISION (NM MMD)
3. EXISTING FIVE (5) FOOT TOPOGRAPHY AND PERMIT BOUNDARY PROVIDED BY NEW MEXICO COPPER CORPORATION
4. APPROXIMATE LIMITS OF UNDER DRAIN SYSTEM SHOWN. EMBANKMENT UNDERDRAIN WILL BE A GRADED SAND AND GRAVEL DRAIN THAT IS FILTER COMPATIBLE WITH CYCLONED TAILINGS SAND. IMPOUNDMENT UNDER DRAIN WILL BE GEOTEXTILE FABRIC WRAPPED. THE IMPOUNDMENT UNDERDRAIN WILL BE EXTENDED DURING PHASED CONSTRUCTION.

DAVID ALAN KIRBY NEW MEXICO 13778 REGISTERED PROFESSIONAL ENGINEER 11-17-10

400 0 400 800 SCALE FEET

DRAWING USE
CONCEPTUAL DESIGN NOT FOR CONSTRUCTION

PROJECT
COPPER FLAT PROJECT
TAILINGS STORAGE FACILITY
CONCEPTUAL DESIGN STUDY
SIERRA COUNTY, NEW MEXICO

TITLE
TAILINGS STORAGE FACILITY UNDERDRAIN PLAN

Golder Associates

PROJECT No.		103-92557	FILE No.	10392557AD06
DESIGN	CDJ	10/25/10	SCALE AS SHOWN	REV. B
CADD	ANV	10/27/10	DRAWING	6
CHECK	GM	10/29/10		
REVIEW	DAK	11/17/10		

Drawing File: K:\2010 Projects\103-92557 Copper Flat\10392557AD06.dwg Nov 23, 2010 - 11:26am



1/7 **IMPOUNDMENT LINER DETAIL**
NOT TO SCALE



2/7 **UNDERDRAIN AREA LINER DETAIL**
NOT TO SCALE



3/7 **EMBANKMENT AREA LINER DETAIL**
NOT TO SCALE



4/7 **POND LINER DETAIL**
NOT TO SCALE



5/7 **IMPOUNDMENT ANCHOR TRENCH DETAIL**
NOT TO SCALE



6/7 **POND ANCHOR TRENCH DETAIL**
NOT TO SCALE



7/7 **POND LEAK COLLECTION AND RECOVERY SYSTEM (LCRS) DETAIL**
NOT TO SCALE



8/7 **CYCLONED SAND EMBANKMENT DETAIL**
NOT TO SCALE



9/7 **PROCESS WATER RECLAIM RAMP DETAIL**
NOT TO SCALE

DAVID ALAN KIDD
NEW MEXICO
13778
11-17-10
REGISTERED PROFESSIONAL ENGINEER

DRAWING USE	CONCEPTUAL DESIGN NOT FOR CONSTRUCTION
PROJECT	COPPER FLAT PROJECT TAILINGS STORAGE FACILITY CONCEPTUAL DESIGN STUDY SIERRA COUNTY, NEW MEXICO
TITLE	TAILINGS STORAGE FACILITY DETAILS

Golder Associates

PROJECT No.	103-92557		FILE No.	10392557A007
DESIGN	CDJ	10/25/10	SCALE	AS SHOWN REV. C
CADD	ANV	10/27/10	DRAWING	7
CHECK	GM	10/28/10		
REVIEW	DAK	11/17/10		

Drawing File: K:\2010 Projects\103-92557 Copper Flat\10392557A007.dwg Nov 22, 2010 - 11:27am





NOTES

1. CAPACITY ESTIMATED USING EXISTING FIVE (5) FOOT TOPOGRAPHY PROVIDED BY NEW MEXICO COPPER CORPORATION AND A DRY DENSITY OF 85 PCF.
2. TAILING MAXIMUM ELEVATION IS 5,375 FT AMSL AT LOCATION OF DISCHARGE POINT.
3. RATE OF RISE IS CALCULATED FROM THE PRODUCTION RATE OF 17,500 TONS PER DAY AT 93% AVAILABILITY FOR AN ANNUAL PRODUCTION OF 5,940,375 TONS.
4. ASSUMED START-UP DATE 2015. ACTUAL START DATE TO BE DETERMINED.

DAVID A. LANKIDD
NEW MEXICO
13778
REGISTERED PROFESSIONAL ENGINEER
11-17-10

DRAWING USE
CONCEPTUAL DESIGN
NOT FOR CONSTRUCTION

PROJECT
COPPER FLAT PROJECT
TAILINGS STORAGE FACILITY
CONCEPTUAL DESIGN STUDY
SIERRA COUNTY, NEW MEXICO

TITLE
HEIGHT VS. CAPACITY PLOT

Golder Associates

PROJECT No.		103-92557	FILE No.	10392557A008	
DESIGN	CDJ	10/25/10	SCALE	N.T.S.	REV. C
CADD	ANV	10/27/10	DRAWING	8	
CHECK	GM	10/29/10			
REVIEW	DAK	11/17/10			

Drawing file: K:\2010 Projects\103-92557 Copper Flat\10392557A008.dwg Nov 23, 2010 — 11:26am





D/9 CROSS SECTION D-D'

SCALE 120 0 120 240 FEET



E/9 CROSS SECTION E-E'

SCALE (x5 VERTICAL EXAGGERATION) 50 0 50 100 FEET

LEGEND

- EXISTING CONTOURS
- 5200 DESIGN CONTOURS
- PERMIT BOUNDARY
- D/9 CROSS-SECTION CALL-OUT



NOTES

1. DRAWINGS PRESENT THE CONCEPTUAL DESIGN OF A NEW AND EXPANDED TAILINGS STORAGE FACILITY WITH A CAPACITY OF 100 MILLION TONS AT AN ASSUMED DRY DENSITY OF 85 POUND PER CUBIC FOOT.
2. FINAL DESIGN WILL BE COMPLETED IN ACCORDANCE WITH THE RULES AND REGULATIONS OF THE NEW MEXICO STATE ENGINEER, THE NEW MEXICO ENVIRONMENT DEPARTMENT (NMED) AND THE NEW MEXICO MINING AND MINERALS DIVISION (NM MMD)
3. EXISTING FIVE (5) FOOT TOPOGRAPHY AND PERMIT BOUNDARY PROVIDED BY NEW MEXICO COPPER CORPORATION.
4. FINAL EMBANKMENT CREST HEIGHT WILL BE APPROXIMATELY 5,375 FEET AMSL. TAILINGS SURFACE CONFIGURATION SHOWN REPRESENTS CONDITIONS AT THE CESSATION OF MINING OPERATIONS. APPROXIMATE LOCATION OF A POST-CLOSURE SPILLWAY SHOWN. TAILINGS DISCHARGE LOCATIONS MAY BE MODIFIED IN LATE STAGE OPERATIONS TO GRADE THE IMPOUNDMENT SURFACE AND FACILITATE POST-CLOSURE DRAINAGE TO THE PERMANENT SPILLWAY.
5. SELECTION OF A DESIGN STORM EVENT FOR STORMWATER STORAGE AND SPILLWAY CAPACITY WILL BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE NEW MEXICO STATE ENGINEER.
6. TAILINGS SURFACE REGRADED AT CLOSURE OR TAILINGS DEPOSITION PATTERNS MODIFIED DURING LATE STAGE OPERATION TO CONTOUR THE TAILINGS SURFACE.
7. UNDERDRAINING TO BE COLLECTED AND EVAPORATED ON IMPOUNDMENT SURFACE UNTIL UNDERDRAIN PIPES CAN BE PLUGGED AND UNDERDRAIN COLLECTION POND BACKFILLED.

DAVID ALAN KIDD NEW MEXICO 13778 REGISTERED PROFESSIONAL ENGINEER 11-17-10

DRAWING USE
CONCEPTUAL DESIGN NOT FOR CONSTRUCTION

PROJECT
COPPER FLAT PROJECT
TAILINGS STORAGE FACILITY
CONCEPTUAL DESIGN STUDY
SIERRA COUNTY, NEW MEXICO

TITLE
TAILINGS STORAGE FACILITY CONCEPTUAL CLOSURE PLAN

Golder Associates

PROJECT No.	103–92557		FILE No.	10392557A009	
DESIGN	CDJ	10/25/10	SCALE	AS SHOWN	REV. C
CADD	ANV	10/27/10	DRAWING	9	
CHECK	GM	10/29/10			
REVIEW	DAK	11/17/10			

Drawing file: K:\2010 Projects\103-92557 Copper Flat\10392557A009.dwg Nov 22, 2010 - 11:28am

APPENDIX E

Preliminary Spill Contingency Plan

New Mexico Copper Corporation

Copper Flat Project
Spill Contingency Plan

Report Prepared for:

U.S. Department of the Interior
Bureau of Land Management
Las Cruces District Office
1800 Marquess Street
Las Cruces, NM 88005-3370

Report Submitted by:

NEW MEXICO COPPER CORPORATION
2425 San Pedro Dr. Suite 100
Albuquerque, NM 87110
Office: (505) 382-5770

December 2010

TABLE OF CONTENTS

1 FACILITY INFORMATION AND EMERGENCY RESPONSE 1

1.1 Emergency Response Action Plan 1

1.2 Facility Information 1

1.3 Emergency Response Information 3
1.3.1 Notification / Reporting 3
1.3.2 Response Equipment List 5

2 HAZARD EVALUATION AND DISCHARGES 7

2.1 Hazard Evaluation 7
2.1.1 Reagents Used for Processing 7
2.1.2 Hazard Identification 7
2.1.3 Vulnerability Analysis 8
2.1.4 Worst Case Discharge 8

2.2 Discharge Detection Systems 8
2.2.1 Discharge Detection by Personnel 8

3 PLAN IMPLEMENTATION 10

3.1 Response Resources for Small, Medium, and Worst Case Spills 10
3.1.1 Fire Protection 10

3.2 Disposal Plans 11

3.3 Containment and Drainage Planning 11

3.4 Facility Self-Inspection 11
3.4.1 Tank Inspection 12
3.4.2 Secondary Containment Inspection 13

3.5 Response Training 13
3.5.1 Personnel Response Training Logs 13

4 SECURITY 14

5 ACRONYMS AND DEFINITIONS 15

TABLES

Table 2-1 General Spill Response Procedures
Table 3-1 Inspection Tasks Summary

APPENDICES

Appendix A Inspection Checklists and Reporting Forms (*Pending*)
Appendix B Training Outline (*Pending*)
Appendix C Spill Reporting Procedures (*Pending*)
Appendix D Facility Incident Command System (*Pending*)
Appendix E Emergency Contacts and Telephone Call List (*Pending*)
Appendix F Storage and Containment Inventories (*Pending*)

1 FACILITY INFORMATION AND EMERGENCY RESPONSE

This Spill Contingency Plan has been prepared pursuant to Title 43, Part 3809 of the Code of Federal Regulations (CFR) [43 CFR § 3809.401(b)(2)(vi)] which requires development of a contingency plan as part of the Plan of Operations for mining operations. This Plan establishes procedures for response to oil, fuel and hazardous material spills, including control, cleanup and reporting. NMCC has developed this Contingency Plan to respond to spills and to minimize the impacts from spills of oil, fuel, oil-related products, and hazardous substances to the environment.

NOTE: THIS PLAN WILL BE UPDATED AND RESUBMITTED TO THE BLM AS FINAL DESIGNS OF THE OPERATIONAL FACILITIES ARE COMPLETED, AND PRIOR TO ANY MINE-RELATED ACTIVITY AT THE SITE.

The Environmental Manager (EM) has primary responsibility for implementing the Contingency Plan. The EM or his/her designee will be present at the facility during normal working hours.

Secondary containment structures designed to prevent the migration of a spill are part of the design of Facility components and are included in the Plan. Fuel and oil for the diesel and gas-powered equipment will be stored in above-ground, sealed tanks in the processing area. The tanks will be installed on lined pads and surrounded by berms to contain the volume of the largest tank within the secondary containment in the event of a spill or release.

The Contingency Plan will be posted and distributed to site personnel and will be used as a guide in training employees. Emergency reporting procedures will be posted in key locations throughout the project area. NMCC will be responsible for events at the mine site, while contract haulers (i.e., trucking companies) will be responsible for accidents and spills along the transportation routes.

Reporting spills or releases of oil-related materials or hazardous materials to the environment is divided into four categories:

1) Releases requiring internal notification only;
2) Releases also requiring notification to the State of New Mexico;
3) Releases also requiring notification to the National Response Center (NRC) and the local Emergency Planning Committee pursuant to CERCLA or Superfund; and
4) Releases subject to Clean Water Act requirements only.

Determining which of the above categories is appropriate for any particular spill or release depends on the type of material, the amount released, and the circumstances of the spill or release.

1.1 Emergency Response Action Plan

An Emergency Response Plan, which addresses responses to hazardous material releases, large-scale non-hazardous material releases, and natural disasters, will be prepared for the Facility and maintained in the Environmental Department.

1.2 Facility Information

The Copper Flat Mine Project (Project) is located in Sierra County, New Mexico, approximately 30 miles southwest of Truth or Consequences near Hillsboro. The NMCC mailing address is:

New Mexico Copper Corporation

2425 San Pedro Dr. Suite 100
Albuquerque, NM 87110
Office: (505) 382-5770

The area comprised of mine operations components, the Copper Flat Mine Facility (Facility), is anticipated to use diesel fuel, gasoline, motor oil and other petroleum hydrocarbons and chemical reagents. Oil is anticipated to be stored entirely above-ground.

No navigable waters have been defined at the mine facility; however, an intermittent or ephemeral stream called Greyback Wash passes through the pit area and a few springs or seeps occur west of the pit and up-gradient, all of which are tributaries to the Greyback drainage basin to the west of the pit.

The ore body at the Copper Flat Mine Facility is exposed at the surface and will be mined by conventional open-pit methods. The site is located in a semi-arid region of New Mexico with a mean annual precipitation of about 12 inches.

Ore from the pit will be trucked to the plant area east of the pit. The proposed process involves crushing and grinding followed by the addition of non-toxic organic reagents to create a copper laden froth and filtering to form a concentrate. Ore will be crushed or ground and organic reagents added to create froth. Copper minerals will adhere to the bubbles of the froth. The copper will be collected and filtered to form a concentrate. The proposed mill/concentrator plant is a sulfide flotation plant. No leaching processes, including cyanide leaching, are to be used. No smelting will occur at the Project.

For the purpose of grouping oil containment and storage according to distinct areas, the mine site has been delineated by the following anticipated areas or components:

Fuel Storage Island

Fuel and oil for diesel and gas powered equipment will be stored in above-ground, sealed tanks in the processing facilities area. The tanks will be installed on lined pads, consisting of gravel underlain by a plastic liner. The pad area will be surrounded by berms to provide secondary containment for the largest vessel in case of rupture. Surface piping leads from each tank to the fuel dispensing area. The refueling hoses will be equipped with overflow prevention devices and secondary containment.

Bone Yard

The bone yard will contain empty drums which will have the lids removed. The drums will be labeled as to their former contents. The drum storage areas will have secondary containment systems to minimize the potential for spills of oil and grease to the ground surface.

Truck Shop

A garage at the truck shop will contain lube oil containers and oil and transmission fluid drums. The garage will have a cement floor and a containment wall.

Truck Wash

Truck washing will occur on a cement slab with wash water recycled. Overflows of wash water from the tanks will be minimized.

Shop and Warehouse Building

Numerous drums of unopened/unused oil, antifreeze, transmission fluid and acetone will be stored on racks or pallets in the storage areas of the shop and warehouse building. This building will be prefabricated, standard, rigid-framed equipment servicing facility. Secondary containment will be provided, but the drums will not generally be opened at the site, and are only stored until required by mine staff.

Mobile Tanks

Mobile tanks, consisting of emergency power units/trailers, trailers, and "lube" trucks, may be used to store miscellaneous types of oil and fuel. The trailers and lube trucks are used to service other vehicles and equipment throughout the mine site. Due to the transient nature of the mobile tanks, permanent secondary spill containment is not provided. However, mobile tanks will be positioned in areas that are not subject to periodic flooding or washout.

Explosives

Blasting will be done with primacord, ammonium nitrate and fuel oil (ANFO), and emulsion suitable for use where wet holes are encountered. The blasting contractor will mix the components for each blast on an as needed basis. Mixing of the components will be performed at the batch plant operated by the contractor.

Blasting agents will be stored in compliance with applicable MSHA regulations Ammonium nitrate and diesel fuel will be stored on-site in bins and tanks. Storage of detonators, detonating cord, boosters, caps and fuses will be in accordance with the MSHA and New Mexico State Mine Inspectors regulations for explosives. The storage locations for each of these facilities have not yet been selected, but safety and security will be the main factors considered in their location. An inventory of these components will be made. To avoid potential spills, transfer and loading of explosives will be observed at all times by specialized personnel with appropriate training.

Hazardous Materials

No extremely hazardous substances (as defined by 40 CFR § 355) will be used at the Facility. None of the reagents to be used at the facility milling operations are considered to be hazardous materials by the Comprehensive Environmental Response, Comprehension and Liability Act (CERCLA) definition. Hazardous substances identified in CERCLA include all chemicals on the following regulatory lists:

1. Clean Air Act list of hazardous air pollutants (HAPs).

2. Clean Water Act list of hazardous substances and priority pollutants.

3. Solid Waste Disposal Act list of hazardous wastes.

4. Toxic Substances Control Act list of imminent hazards.

1.3 Emergency Response Information

1.3.1 Notification / Reporting

Proper reporting of spills is very critical and must be done carefully and accurately in a timely manner. A spill event notification flow sheet and a call list with contact names and telephone numbers will be developed and submitted to the BLM prior to commencement of site activities. All spills of any quantity are to be reported to the EM for general reporting guidance.

Records and reports of spills and releases shall be maintained for a period of five years by the EM, and will be made available for inspection upon request by EPA or state agency personnel, as required by SPCC Plan regulations.

How to Report

All spills will be reported in accordance with spill event notification flow sheet (see cover pages of this document), followed by completion of a spill/release record (Appendix C) to be submitted to the EM.

In-House Verbal Reporting

After taking immediate action, the person discovering the spill must notify his/her supervisor. The supervisor will notify the Loss Control Department. Loss Control then notifies the EM. Notification will include the information listed below.

- Date and time of spill;
- Type of material spilled and estimated quantity;
- Location of spill;
- Media impacted (soil, surface water, groundwater);
- Damages or injuries;
- Names and numbers of all persons contacted;
- Reason (cause) for spill;
- Action to prevent recurrence (corrective actions);
- Equipment type, equipment number, and tank number;
- Amount of soil added to approved on-site disposal facility;
- Date cleanup action taken; and,
- Name/position/title of person responsible for cleanup action.

If the Loss Control Leader cannot be reached, the EM must be contacted directly. The EM will determine if it is a reportable spill or discharge. If it is determined to be reportable, the EM will report the event and information to the General Manager as soon as possible.

If the Loss Control, General Manager, EM, Maintenance Superintendent or Production Superintendent cannot be reached, the respondent must call Security, who has company and home phone numbers of these persons and other responsible persons.

The EM will notify the appropriate state and federal agencies concerning spills or releases as required. No one but the EM or designated representative, or the General Manager is authorized to call any government agencies concerning spills. This restriction is needed to ensure that only confirmed, accurate information is provided to the regulatory agencies.

In-House Written Reporting

For any spill or release of oil (oils, gasoline, diesel, etc.) outside of a containment area, a complete written report must be submitted to the Environmental Department as soon as possible (usually within 24 hours of the spill). This written report must address the same components for verbal in-house reporting (above) and any additional issues deemed important by operating personnel. The spill reporting form found in Appendix C has been designed to facilitate such written reporting of spills.

Reporting to State and Federal Agencies

The EM or designated representative will execute all reporting to the agencies under the direction of the General Manager. The EM or designated representative will do the following with respect to regulatory reporting:

1. Report immediately any "reportable" (100 gallons or more) oil spill to the State as well as any spill that enters or threatens to enter any river, stream, canal, sewer, drain, lake or pond.
2. Make necessary written reports to the State, National Response Center and other agencies as required. The National Response Center typically does not require a written report of the spill, although one may be requested in certain situations. Verbal notification to the agencies must be made as soon as possible, but not later than after the first working day after the release. In case the EM or designated representative cannot be contacted by the end of the first working day after the release, the verbal report must be made by the General Manager, giving the data listed for verbal in-house reporting. In New Mexico, reporting procedures are as follows:

- Any spill of oil or hazardous materials, which enters directly into water or has the potential to do so, requires immediate verbal notification. "Immediate" has been defined for this situation as "as soon as possible" after the release. The verbal notification may be made by calling the emergency contact telephone numbers as listed in Appendix E.

  During these calls, the state, federal, or local agencies will determine whether a follow-up written report is required. If required, this report would be due within ten (10) calendar days of the release. The required components of the written report will be discussed during the verbal notification. If required, this written report would go to the following as directed by the State:

  - Releases of oil, which do not enter directly into water and do not have the potential to do so, must be dealt with in the following manner: A release of greater than 100 gallons of oil requires verbal notification by the end of the first working day after the release. The EM or a designated representative performs this notification by calling the emergency contact telephone numbers as listed in Appendix E. All releases which fall into this category may require a written follow up report, due within ten (10) calendar days of the release. The required components of the written report will be discussed during the verbal notification. If required, this written report would go to the following as directed by the State:
  - Releases of oil greater than 1,000 gallons of oil into or upon navigable waters (or in this case, waters of the State) requires additional notification to the EPA Regional Director (40 CFR § 112.4(a)). The EM or a designated representative does this by contacting:

    United States EPA, Region 6
    1445 Ross Avenue (maps)
    Suite 1200
    Dallas, Texas 75202
    (214) 665-6444

    All releases which fall into this category require a written follow-up report, due within sixty (60) calendar days of the release. The required components of the written report will be discussed during the verbal notification.

1.3.2 Response Equipment List

General Spill Cleanup Materials

Spill cleanup materials will be kept in the Warehouse, and include:

- disposable gloves;
- chemical resistant disposable boots, coveralls;
- short-handled brooms;
- adsorbent rags;
- oil sorbent material;
- approved compatible storage container;
- large plastic bags;
- tape;
- floor sweep;
- soda ash
- short-handled shovels; and

- dustpans.

Large Equipment for Cleanup

The Facility will operate 24 hours a day, 365 days per year. Rubber tire loaders, track dozers, motor graders, and backhoes are available and will be dispatched as needed for spill cleanup.

2 HAZARD EVALUATION AND DISCHARGES

2.1 Hazard Evaluation

2.1.1 Reagents Used for Processing

Following the froth flotation process for the tailings, the remaining slurry, consisting primarily of gangue minerals, pyrite and miscellaneous other un-floated minerals, along with water, flows into a tailings thickener for partial dewatering. Surface runoff, including any potential spills, from the areas around the reagent storage and tailings thickener will be controlled by surface grading and directed to the containment pond. Filtrate from both the copper flotation circuit and the molybdenum flotation circuit will be returned to the concentrate thickeners. Thickener overflow will be returned to the plant reclaim water system.

The molybdenum concentrate will be dried prior to packing into 55-gallon drums for shipment off-site. Provisions have been made to enable the tailings to be diverted around the thickener and discharged directly into the disposal ponds in the event of emergency mechanical problems.

A list of the reagents to be used on the site is included in Appendix F. Flotation collectors, frother and flocculants that are received dry will be mixed in agitated tanks and pumped to outdoor storage tanks and day tanks inside the mill building from which they are metered into the process.

Residual reagent concentrations in the tailings and reclaim water streams are expected to be at very low levels. The collector and promoter flotation reagents (a type 1 reagent) will be added in amounts resulting in concentrations of approximately three parts per million (ppm). This is using an addition rate of 0.02 pounds of reagent per ton of ore and two tons of water to the flotation process. Normally, 95 percent of the reagents are adsorbed onto the copper mineral surface and floated off in the mineral froth. This reagent is subsequently consumed in the off-site smelting process thereby adding its BTU's to the reaction. Using this 95 percent adsorption factor, the residual reagent reporting to the tailing stream drops to <0.15 ppm.

The frother reagent MIBC (a Type 2 reagent) is to be biodegradable in low concentrations as stated by the manufacturer (see Union Carbide MSDS for MIBC). The anticipated dosage rate will be 0.02 pounds per ton of mill feed. The bulk of this reagent will also report to the concentrate fraction and end up at the smelter.

The flocculent reagent (a Type 1 reagent), to be added at 0.016 pounds per ton of mill feed, is also classified as being biodegradable and exhibits a low tolerance to exposure to high pH solutions. Given the 10 to 11 pH range this plant will normally operate at, this reagent will rapidly decompose.

Lime (a type 3 reagent) is used at a rate of 2.7 pounds per ton of mill feed to control pH of the flotation circuit, most of which reacts with sulfide minerals to form gypsum.

Sodium Hydrosulfide (NaHS, a type 3 reagent) will be added to the molybdenum circuit process to effect the copper molybdenum separation. This reagent is rapidly oxidized through contact with the copper minerals and air bubbles entrained in the flotation pulp.

2.1.2 Hazard Identification

A list of the reagents anticipated to be used at the facility is provided in Appendix F. Material Safety Data Sheets (MSDS) for the reagents to be used at the facility will be on file at the site. None of the reagents to be used at the facility milling operations are considered to be hazardous materials by the Comprehensive Environmental Response, Comprehension and Liability Act (CERCLA) definition. Hazardous substances identified in CERCLA include all chemicals on the following regulatory lists:

1. Clean Air Act list of hazardous air pollutants (HAPs).

2. Clean Water Act list of hazardous substances and priority pollutants.
3. Solid Waste Disposal Act list of hazardous wastes.
4. Toxic Substances Control Act list of imminent hazards.

Inventories of bulk storage containers and container storage areas, electrical transformers, and mobile service vehicles, including descriptions of secondary containment, are provided in tables in Appendix F.

2.1.3 Vulnerability Analysis

Reagent spills will be contained by curbs in the reagent mixing and storage areas. A floor sump pump will be used to return spilled material either to the storage tank or into the milling process as necessary.

2.1.4 Worst Case Discharge

A worst-case spill scenario would involve total failure of the primary and secondary containment or failure which would otherwise allow discharge of the contents of the primary containment. The volume of discharge from such a failure could potentially equal the total contents of the tank. The rate at which this flow would occur would depend on the type of product in the tank, the depth of product in the tank, and the size/area of the release opening. For the largest tank, it is conceivable that such flow could equal tens or hundreds of gallons per minute.

The possible spill pathways have been estimated based upon a review of the topographic maps and a mine site inspection. The lateral extent of a spill would be a function of the type of product released, amount of product released, whether the spill was concurrent with a precipitation event, adequacy of the secondary containment, and ground surface cover.

2.2 Discharge Detection Systems

2.2.1 Discharge Detection by Personnel

Small leaks and spills that are confined to small areas will be cleaned up as part of the facility's SOPs. In cases where a medium or large (worst-case) leak has occurred but is confined to facility property, cleanup will proceed as follows:

In the case of a medium spill, direct response measures include:

1. Stop the leak by plugging the leak and/or closing the valve and ensure that the spill is totally contained.
2. Clean up the spill in accordance with general spill response procedures (Table 2-1). Facility employees under the direction of the authorized person or direct Supervisor will conduct the cleanup operation.

In the case of a large spill, direct response measures include:

1. Terminate the source of the flow of petroleum or chemical product.
2. Dig a trench or dike or do whatever else is necessary to confine the area of the spill or to stop it from entering a waterway. Never clear away spills with water! Water tends to mobilize a spill. Instead, use the most appropriate oil-absorbent materials, such as those contained in the spill cleanup kits, to prevent petroleum products from flowing into watercourses.
3. Plug floor drains, place sorbent materials around the spill or take other actions to minimize environmental damage. Sorbent materials will be stocked at the main warehouse.

4. Immediately initiate reporting procedures. The Loss Control Department, Mine Manager or EM must be notified (by radio or phone). The Control Room Operator will follow the Dispatch Emergency Communication Procedures (Appendix D).
5. After the response measures and reporting functions have been accomplished, cleanup will begin in accordance with general spill response procedures (Table 2-1). Should facility personnel be unable to perform the appropriate cleanup operation, and it is necessary for cleanup to begin immediately, the General Manager will utilize outside contractors. Unauthorized site personnel must not notify contractors directly. The General Manager has assigned certain individuals the responsibility of contacting outside contractors with a facility contract.

Table 2-1: General Spill Response Procedures

Spill Event:	Incidental (collected within secondary containment)	Significant (breaching of secondary containment)	Significant (available personnel unable to contain spill after attempting direct response measures)
Close Valve/Discharge Equipment	•	•	•
Mobilize Mine Equipment to Containerize Spill		•	
Use Sorbent Materials to Facilitate Containment		•	
Notify General Manager			•
Excavate Contaminated Soil and Transfer to Landfill, Pump Liquid for Off-Site Disposal	•	•	•
Notify Environmental Department for Transfer Approval	•	•	•
Repair/Replace Tank/Piping/ Discharge Equipment as Necessary	•	•	•

3 PLAN IMPLEMENTATION

In the event of an oil, fuel or chemical reagent spill, facility personnel will implement control procedures as summarized in the following table and detailed in the following sections. Response measures have been designed to mitigate the possibility of oil reaching waters of the State. Response measures include containing the spill, stopping the leak, and cleaning up the spill with the most effective means available. Facility employees will undertake these measures immediately when there is any danger of oil entering any waters of the State and in case of any oil spill.

3.1 Response Resources for Small, Medium, and Worst Case Spills

Small leaks and spills that are confined to small areas will be cleaned up as part of the facility's SOPs. In cases where a medium or large (worst-case) leak has occurred but is confined to facility property, cleanup will proceed as indicated in Section 2.3.1. Spill response equipment and materials are listed in Section 1.3.2.

For spills on gravel or soil, it may be possible to absorb some of the liquid with absorptive material or remove some of the liquid before removing the gravel or soil. Following approval of the Environmental Department, all contaminated gravel or soil will be removed and transported to an approved facility for disposal.

Spills on solid surfaces may be collected with absorptive materials and then cleaned thoroughly with rags wetted with a non-hazardous solvent if needed. Sufficient quantities of sorbent material and other cleanup equipment will be maintained at the warehouse facility to provide for cleanup.

If there is a small amount of water with the spilled oil, the water and the oil may be absorbed in sand, sawdust, or commercial adsorbents and disposed of per the Environmental Department's directions. Any residual sediment or sludge will also be cleaned up and also disposed of per the Environmental Department's directions.

3.1.1 Fire Protection

A fire protection system will be installed in the administration and warehouse complexes, truck shop, crushing plant and process plant. This system will incorporate Sierra County Code requirements. Hydrants will be located near all buildings. A 100,000-gallon fire water reserve will be stored in a water storage tank located sufficiently above and near the mill and crushing area to provide adequate water pressure. A fuel break will be constructed around the facilities. Water trucks, used for dust suppression, will be available in the event of a fire. One mine rescue vehicle will be located on-site in the event emergency transportation is required.

NMCC will promptly comply with any emergency directives and requirements of Sierra County, and the BLM requirements pertaining to industrial operations during the fire season.

NMCC will train an in-house fire brigade in the proper use of fire suppression equipment. In addition, the Sierra County Fire Protection Officer will provide advice on methods to maximize the benefit of equipment and to provide assistance in training Project personnel in fire fighting procedures and drills. The Hillsboro Voluntary Fire Department will be advised as the nature of materials that will be transported through town on a routine basis. Sierra County presently has spill response capabilities and all trucking contractors will be in compliance with 49 CFR and U.S. Department of Transportation regulations, to aid in the reducing the potential for spills and accidents and for mitigating releases that may occur during transport of hazardous materials. In the event of a release, the contract transportation company would be responsible for response and cleanup. Additional specialized training is required for drivers of tank trucks, such as those transporting acid.

3.2 Disposal Plans

Spent cleanup material, residual spilled oil, and hydrocarbon-contaminated soil will be properly disposed of in accordance with applicable state and federal regulations either in an on-site facility or at an approved off-site facility authorized to accept the type of waste.

3.3 Containment and Drainage Planning

Spill prevention and spill control requirements for the Facility include the following:

Spill Prevention

- Inspection and maintenance of oil, fuel and chemical reagent storage containers and transfer points;
- Testing of primary storage containers;
- Facility personnel training on SCP Plan implementation;
- Security; and
- Oil and fuel transfer procedures.

Spill Control

- Facility drainage; and
- Structural controls and equipment (diversion and secondary containment).

Storage tanks determined to not be in conformance with appropriate spill prevention guidelines will be corrected as soon as possible. All oil products are to be stored in above-ground steel tanks and provided with secondary containment unless otherwise noted.

At oil or fuel transfer points, vendor personnel are required to remain with the transport vehicle and observe the tank filling at all times. As filling takes place, vendor personnel are required to remain attentive to the tank level indicators to prevent tank overfills. Connection of the tank fill lines takes place before the master flow control valve is opened. Piping to the tanks will be equipped with back flow prevention devices (check-valves). After filling, the master flow control valve will be closed before disconnecting the fill hoses. A bucket will be placed below the fill valves during tank filling to contain any discharge. A service vehicle will then evacuate this bucket, as necessary.

Secondary containment will be provided for all permanently located oil, fuel and chemical reagent storage tanks, as well as for fill and dispenser points, to minimize the potential for a discharge to reach waters of the State. Secondary containment for each storage tank will have sufficient capacity to contain the contents of the largest tank in a containment area and sufficient freeboard to allow for precipitation. The minimum total volume for uncovered secondary containment is the capacity of the largest tank within the secondary containment plus the depth of rain for the 100-year, 24-hour storm event for the site or region. Fill and dispenser points will have incidental spillage containment such as curbed concrete pads and sumps.

3.4 Facility Self-Inspection

The Facility will be inspected frequently for leaks, liquid accumulation, and need for preventive maintenance. Monthly inspection forms are provided in Appendix A. Completed inspection forms will be submitted to the Mine Manager and the EM. The Environmental Department will maintain all completed forms and checklists related to this Plan for a period of at least three years. The EM's designee will ensure each storage/transfer area is inspected monthly with responses to spills or preventative maintenance tasks to be completed as indicated in Table 3-1.

Table 3-1: Inspection Tasks Summary

Observation	Report Spill (Appendix C)	Implement Controls & Countermeasures	Close	Repair & Replace as Necessary	Pump and Transfer Off-Site for Disposal	Notify Environmental Department for Approval
Spill (outside secondary containment area)	●	●				
Open valves/Dispenser equipment			●	●		
Inoperative liquid level gauge				●		
Physical deterioration to tank/foundation/ Piping (i.e., rusting, pitted)				●		
Inadequate tank/pipeline support (i.e., no tank anchor straps)				●		
Ineffective secondary containment (i.e., no anchoring of liner, tear in liner)				●		
Presence of free liquid in secondary containment, overfill containment areas and sumps					●	●

3.4.1 Tank Inspection

All tanks will be visually inspected monthly by personnel designated by the EM. Visual inspections will be conducted with respect to the following:

- Ensure the tank fill valves and dispenser points are in the closed position when not in use.
- Inspect all valves for signs of leakage or deterioration.
- Check inlet and outlet piping, as well as tank flanges for leakage.
- Inspect pipe/tank supports, foundations and anchoring straps for wear.
- Check tank level indicators and dispenser equipment for proper operating condition.
- Inspect the tank shell surfaces for areas of rust or other signs of deterioration. Particular attention will be paid to areas with peeling paint (or other coating), welds, and seams.
- Check the surfaces below tanks and oil transfer points areas for obvious signs of leaks or spills, specifically stained or visibly damp soils.

- Inspect all sumps and other overfill containment areas located below oil transfer points, and empty liquid as necessary. Consider liquid to be oil-contaminated, and following approval of the Environmental Department, remove for off-site disposal/recycling by personnel authorized to conduct this type of activity.
- Examine tank shells, welds, rivets and bolts for wear and discoloration. Examine all above-ground valves and pipelines for the general condition of flange joints, expansion joints, valve glands and bodies, catch pans, pipeline supports, and condition of metal surfaces.
- Tanks or oil storage containers that appear to be unused or inactive shall be verified as such, and if so, any remaining product shall be removed and disposed of, and the tank triple-rinsed in accordance with facility Standard Operating Procedures (SOPs) or with the use of an outside service. The tank will be modified if necessary to prevent physical access, and labeled with a legible sign indicating "empty" and "do not use". If it is anticipated that the tank will no longer be used, procedures shall be implemented to remove the tank for disposal at an authorized facility.

Each aboveground container is inspected and/or tested for integrity on a regular schedule and whenever material repairs are made. NMCC provides training for personnel on performing container tests and inspections. Examples of integrity tests may include, but are not limited to: visual inspection, hydrostatic testing, radiographic testing, ultrasonic testing, acoustic emissions testing, or other systems of non-destructive testing. The frequency and type of testing and inspections depend on the container size, configuration, and design (e.g., shop-built, field-erected, skid-mounted, elevated, double-walled).

3.4.2 Secondary Containment Inspection

Secondary containments will be inspected on a routine schedule to document the condition of containment structure(s) and indicate any necessary repairs or maintenance.

Prior to draining or pumping any accumulated fluid from an oil storage containment area, verification of possible contamination will be conducted. A visual inspection of the accumulated water to determine whether or not a sheen is present will be considered sufficient verification that no contamination is present.

If a sheen is noted, the water will be collected and off-site disposal arranged as directed by the Environmental Department. If no sheen is observed, the water may be drained or pumped out of the containment area and applied to a designated on-site facility following approval of the Environmental Department.

3.5 Response Training

Key facility employees, who are directly involved with managing oil, fuel and/or chemical reagent storage and transfer operations, are regularly trained in implementing the Contingency Plan to minimize the number of human errors that cause oil spills. Employee training will be performed annually; new employees will be trained within one week of beginning work. An outline used to facilitate training of new employees and refresher training of existing employees is provided in Appendix B.

3.5.1 Personnel Response Training Logs

Records of response training will be maintained in the environmental master files.

4 SECURITY

Only authorized personnel will be allowed to enter the facility property. Tank locations that may require operations at night will be equipped with sufficient lighting to assist in security and provide visibility for operations to be performed. Tanks located in high traffic areas will be barricaded to minimize collisions from occurring.

5 ACRONYMS AND DEFINITIONS

The following definitions are presented below in order to understand the scope of this Plan. The definitions are from, and provided in, 40 CFR §112.2.

Oil: means oil of any kind or in any form, including, but not limited to petroleum, fuel oil, sludge, oil refuse, fats, greases, and oil mixed with other than dredged spoil. At the facility, oils stored include diesel fuel, gasoline, hydraulic oil, miscellaneous lube oils, grease, and motor oils.

Discharge: includes but is not limited to, any spilling, leaking, pumping, pouring, emitting, emptying, or dumping.

Reportable Spill: means a discharge of oil into or upon the navigable waters of the United States or adjoining shorelines in harmful quantities, as defined in 40 CFR §110, which states, discharges of oil that:

- Violate applicable water quality standards, or
- Cause a film or sheen upon or discoloration of the surface of the water or adjoining shorelines or cause a sludge or emulsion to be deposited beneath the surface of the water or upon adjoining shorelines (40 CFR §110.3).

At the facility, visual inspections using the second definition above will be used to determine whether a discharge constitutes a reportable spill event as detailed in Section 4 of the SPCC Plan.

Contract: means:

- A written contractual agreement with an oil spill removal organization(s) that identifies and ensures availability of the necessary personnel and equipment within appropriate response times; and/or
- A written certification by the owner or operator that the necessary personnel and equipment resources, owned or operated by the facility owner or operator, are available to respond to a discharge within appropriate response times.

Reportable spill events are regulated by the NMED, which requires notification within 24 hours if a discharge occurs in such quantity as may with reasonable probability injure or be detrimental to human health. In addition, as indicated in 40 CFR §112.4(a), whenever a facility has discharged more than 1,000 U.S. gallons of oil into or upon the navigable waters of the United States or adjoining shorelines in a single spill event, or discharged more than 42 U.S. gallons of oil in each of two discharges as described in 40 CFR § 112.1(b) into or upon the navigable waters of the United States or adjoining shorelines, occurring within any twelve month period, the owner or operator of such facility shall submit to the Regional Administrator, within 60 days, a detailed spill report.

Navigable waters (as defined in 40 CFR §110.1) are not present at the Copper Flat Mine Facility. Other waters in the vicinity include the intermittent stream Greyback Wash to the west of the pit and a few springs or seeps west of the pit.

Waters of the State, as defined by the State of New Mexico, include all interstate and intrastate waters, including natural ponds and lakes, playa lakes, reservoirs, perennial streams and their tributaries, intermittent streams, sloughs, prairie potholes and wetlands (WQCC 91-1, 1995). This State definition indicates additional waters that must be considered for impact by an oil spill at the facility.

Appendix A

Inspection Checklists and Reporting Forms

(*Pending*)

Appendix B

Training Outline

(*Pending*)

Appendix C

Spill Reporting Procedures

(*Pending*)

Appendix D

Facility Incident Command System

(*Pending*)

Appendix E

Emergency Contacts and Telephone Call List

(*Pending*)

Appendix F

Storage and Containment Inventories

(*Pending*)

APPENDIX F

Quality Assurance Plan

(Intera, 2010)

New Mexico Copper Corporation

Quality Assurance Project Plan

Copper Flat Mine Site

September 2010

Prepared for:
New Mexico Copper Corporation

Submitted to:
Mining and Minerals Division
New Mexico Energy, Minerals and Natural Resources Department

Prepared by:

INTERA

01688

TABLE OF CONTENTS

Abbreviations and Acronyms iii
1 Project Description and Management 1
1.1 Project Definition and Background 1
1.2 Quality Objectives and Criteria 1
1.2.1 Measurement Quality Objectives for Analytical Laboratory Data 1
1.2.2 Measurement Quality Objectives for Meteorological and Air Quality Data 3
1.2.3 Measurement Quality Objectives for Ecological Data 4
1.2.4 Measurement Quality Objectives for Cultural Resources Data 4
1.3 Project Organization 4
1.4 Special Training and Certification 4
1.4.1 Health and Safety Training 4
1.5 Documents and Records 5
1.5.1 Field Documentation 5
2 Data Generation and Acquisition 5
2.1 Sampling Design 5
2.2 Field Activities 6
2.3 Sample Handling and Custody 6
2.4 Laboratory QA/QC 7
2.5 Equipment Testing, Inspection, Maintenance, and Calibration 8
3 Inspection and Acceptance of Supplies and Consumables 8
4 Data Management 8
5 Assessment, Response Actions, and Reports to Management 9
6 Data Evaluation and Usability 9
6.1 Laboratory Data Verification 9
6.2 Laboratory Data Evaluation and Usability 10
7 Reconciliation with User Requirements 10
8 References 10

LIST OF FIGURES

Figure 1 INTERA Organizational Flow Chart
Figure 2 Parametrix Organizational Flow Chart

LIST OF TABLES

Table 1 Key Personnel and Responsibilities

Abbreviations and Acronyms

CFR	Code of Federal Regulations
COC	chain of custody
CPR	cardiopulmonary resuscitation
DQA	data quality assessment
EPA	United States Environmental Protection Agency
ER	equipment rinsate
FTL	field team leader
ID number	identification number
LCS	laboratory control sample
MDL	method detection limit
MMD	New Mexico Mining and Minerals Division
MQO	measurement quality objectives
MS	matrix spike
NMCC	New Mexico Copper Corporation
NMWQCC	New Mexico Water Quality Control Commission
OSHA	Occupational Safety and Health Administration
PARCC	precision, accuracy, representativeness, completeness, and comparability
PM	Project Manager
PPE	personal protective equipment
PRRL	project-required reporting limits
QA	quality assurance
QAPP	quality assurance project plan
QC	quality control
RPD	relative percent difference
SAP	sampling and analysis plan
Site	Copper Flat Mine Permit Area
SQL	sample quantitation limits

1 Project Description and Management

This document establishes the quality standards for products and services that have been established within the industry and through government regulations. New Mexico Copper Corporation (NMCC) and its contractors shall meet or exceed these quality standards throughout the duration of this project.

NMCC is currently initiating permitting activities for the re-opening of the Copper Flat Mine located approximately six miles northeast of Hillsboro, New Mexico, in Sierra County (Site). NMCC and its contractors will assess baseline conditions of for climate, vegetation, wildlife, topsoil, surface water, groundwater, and historical and cultural properties.

The project organizational flow chart for NMCC's geosciences and engineering contractor, INTERA Incorporated (INTERA) of Albuquerque, New Mexico, identifies key personnel and their functions (Figure 1). The INTERA Incorporated (INTERA) Program Manager, Cynthia Ardito, is responsible for project direction and quality assurance (QA) for this project. The Project Manager (PM), Peter Castiglia, is responsible for organizing and implementing field activities, project oversight, data management, and report preparation. Mr. Castiglia is also responsible for ensuring that the Quality Assurance Project Plan (QAPP) and Sampling and Analysis Plan (SAP) are appropriately developed and adhered to. The PM, Dr. John Sigda, is responsible for data analysis and modeling. Dr. Sigda will also provide technical support and will assist in data management and report preparation. INTERA's subcontractors include Class One Technical Services, Inc. of Albuquerque, New Mexico, for air quality services, and Hall Environmental Analysis Laboratories (HEAL) for analytical laboratory services. Subcontractor PMs will be responsible for QA, project oversight, data management, and coordination of field activities.

NMCC has contracted with Parametrix Incorporated of Albuquerque, New Mexico, for ecological and cultural resources services. Parametrix will be responsible for data collection for these resource areas. An organizational chart is included as Figure 2. The Parametrix PM, Mr. Jens Deichmann, is responsible for data collection and data quality. For geologic sampling, NMCC has contracted with SRK Consulting Engineers (SRK). The SRK PM is Mr. Mark Willow. The principal geochemist supporting Mr. Willow and overseeing the geologic sampling program is Dr. Robert Bowell.

1.1 Project Definition and Background

A 12-month baseline characterization of pre-mining site conditions must be completed prior to submittal of a Mine Permit Application to the New Mexico Energy, Minerals, and Natural Resources Department Mining and Minerals Division (MMD). As noted previously, this baseline characterization involves sampling, analysis, and assessment of site-specific climatic, vegetation, wildlife, soil, surface water, groundwater, and historical and cultural properties conditions. The MMD requires that a SAP be submitted for agency review. The SAP is a detailed work plan that describes how baseline data will be collected. The SAP must thoroughly describe the proposed sampling methodology and frequency, proposed data sources, and proposed sampling locations to document existing resource conditions within the permit boundary.

1.2 Quality Objectives and Criteria

The following sections present the measurement quality objectives (MQO) identified for this project.

1.2.1 Measurement Quality Objectives for Analytical Laboratory Data

All analytical results for water samples will be evaluated in accordance with precision, accuracy, representativeness, completeness, and comparability (PARCC) parameters to document the quality of the data

and promote data that are of sufficient quality to meet the project objectives. With regard to these PARCC parameters, precision and accuracy method blanks will be prepared at the frequency prescribed in the individual analytical method, or at a rate of 5 percent of the total samples if a frequency is not prescribed in the method. The subsections below describe each of the PARCC parameters and how they will be assessed for this task.

1.2.1.1 Precision

Precision is the degree of mutual agreement between individual measurements of the same property under similar conditions. Usually, combined field and laboratory precision is evaluated by collecting and analyzing field duplicates and then calculating the variance between the samples, typically as a relative percent difference (RPD).

$$RPD = \frac{|A - B|}{(A + B)} \times 100\%$$

where:

A = First duplicate concentration
B = Second duplicate concentration

Field sampling precision is evaluated by analyzing field duplicates. One duplicate groundwater sample will be collected during the initial groundwater sampling event to establish laboratory analytical precision at the onset of the investigation. The duplicate groundwater sample will be collected by completely filling two separate vials by alternating between the primary sample set and the replicate sample set in the order shown below:

- Fill vial #1 - primary sample set
- Fill vial #1 - replicate sample set
- Fill vial #2 - primary sample set
- Fill vial #2 - replicate sample set

Laboratory analytical precision is evaluated by analyzing matrix (laboratory) duplicates. Results for each laboratory duplicate pair will be used to determine the RPD in order to evaluate precision.

1.2.1.2 Accuracy

A program of sample spiking will be conducted to evaluate laboratory accuracy. This program will include analysis of matrix spike (MS), laboratory control samples (LCS) or blank spikes, and method blanks. The results for the spiked samples will be used to calculate the percent recovery for use in evaluating accuracy.

$$\text{Percent Recovery} = \frac{S - C}{T} \times 100\%$$

where:

S = Measured spike sample concentration
C = Sample concentration
T = True or actual concentration of the spike

Results that fall outside the accuracy goals will be further evaluated on the basis of the results of other quality control (QC) samples.

1.2.1.3 Representativeness

Representativeness expresses the degree to which sample data accurately and precisely represent: (1) the characteristics of a population, (2) variations in a parameter at a sampling point, or (3) an environmental condition that they are intended to represent.

Representativeness of data will also be promoted through the consistent application of established field and laboratory procedures. Equipment rinsate (ER) blanks and laboratory blanks will be evaluated for the presence of contaminants to aid in evaluating the representativeness of sample results. Data determined to be non-representative by comparison with existing data will be used only if accompanied by appropriate qualifiers.

1.2.1.4 Completeness

Completeness is a measure of the percentage of project-specific data that are valid. Valid data will be obtained when samples are collected and analyzed in accordance with QC procedures as outlined in this QAPP and when none of the QC criteria that affect data usability are exceeded. When all data evaluation is completed, the percent completeness value will be calculated by dividing the number of useable sample results by the total number of sample results planned for this investigation.

As discussed further in Section 8.0, completeness will also be evaluated as part of the data quality assessment process (EPA, 2000b). This evaluation will help assess whether any limitations are associated with the decisions to be made based on the data collected.

1.2.1.5 Comparability

Comparability expresses the confidence with which one data set can be compared with another. Comparability of data will be achieved by consistently following standard field and laboratory procedures and by using standard measurement units in reporting analytical data.

1.2.1.6 Detection and Quantitation Limits

The method detection limit (MDL) is the minimum concentration of an analyte that can be reliably distinguished from background noise for a specific analytical method. The quantitation limit represents the lowest concentration of an analyte that can be accurately reproduced in a sample matrix. Project-required reporting limits (PRRL) are contractually specified minimum quantitation limits for specific analytical methods and sample matrices, such as soil or water, and are typically several times the MDL to allow for matrix effects. PRRLs, which are established in the project scope of work for subcontract laboratories, are set to establish minimum criteria for laboratory performance. Actual laboratory quantitation limits may be substantially lower.

For this project, analytical methods have been selected so that the PRRL for each target analyte is below the applicable regulatory screening criteria, the New Mexico Water Quality Control Commission (NMWQCC) Standards for groundwater. Also, sample concentrations will be reported as estimated values if concentrations are less than PRRLs but greater than MDLs. The MDL for each analyte will be listed as the detection limit in the laboratory's electronic data deliverable.

1.2.2 Measurement Quality Objectives for Meteorological and Air Quality Data

Laboratory and field quality assurance procedures for meteorological and air quality data are described in detail in Section 2 of the Sampling and Analysis Plan (SAP). Please refer to Section 2.8 of this SAP for more information.

1.2.3 Measurement Quality Objectives for Ecological Data

A single field crew chief will be assigned to ensure data collection is consistent between crews. This individual will review a sub-set of the field forms following each field day. Formalized data collection training will also be completed prior to field sampling. All field botanists will be familiar with plant systematics and techniques to identify plants using taxonomic keys. Plant species not readily identifiable in the field will be collected and preserved for identification at the University of New Mexico Herbarium.

Vegetation material produced during the previous growing season will be discarded before placing samples into a paper bag. Rocks, soil, and/or litter will not be placed into sample bags. Biomass production will only be calculated as an actual dry-weight sample. No double sampling or estimations will occur.

Field data entered into an electronic format such as MS Excel or Access will be evaluated for integrity, consistency, and completeness before data analysis. Oversights or incorrect entries will be corrected. A sub-set of the field forms will be compared to the electronic version for an accuracy assessment. If significant differences are identified, a thorough re-evaluation of each of the forms will be completed.

For wildlife data, field biologists will have a minimum of a BA/BS in Biology and five to ten years of field experience conducting a wide variety of animal surveys ranging from reptiles and amphibians, to birds, mammals, insects, and other invertebrates. This includes experience in recognizing and identifying signs of wildlife. All findings and results will be reviewed by senior scientists.

1.2.4 Measurement Quality Objectives for Cultural Resources Data

Reporting will follow the standards in BLM manual H-8100-1, Chapter 1.B.1 and Appendix 2 (2005). In addition, work will be performed in compliance with all aspects of the NMAC, including NMAC 4.10.15.

1.3 Project Organization

Table 1 presents the roles and responsibilities for key personnel who will be involved in the investigation at the Site. In some cases, more than one responsibility has been assigned to one person.

1.4 Special Training and Certification

This section outlines the training and certifications required to complete the activities described in this QAPP. The following sections describe the requirements for personnel working on-site.

1.4.1 Health and Safety Training

INTERA Personnel who collect water and sediment samples from the Site are required to meet the Occupational Safety and Health Administration (OSHA) training requirements defined in Title 29 of the Code of Federal Regulations (CFR) Part 1910.120(e). These requirements include (1) 40 hours of formal off-site instruction, (2) a minimum of three days of actual on-site field experience under the supervision of a trained and experienced field supervisor, and (3) 8 hours of annual refresher training. Field personnel who directly supervise employees engaged in work at the site shall also receive at least 8 additional hours of specialized supervisor training. The supervisor training covers health and safety program requirements, training requirements, personal protective equipment (PPE) requirements, the spill containment program, and health-hazard monitoring procedures and techniques. Every member of the field team will maintain current certification in the American Red Cross “Multimedia First Aid,” and “Cardiopulmonary Resuscitation (CPR) Modular,” or equivalent.

Copies of health and safety training records, including course completion certificates for the initial and refresher health and safety training, specialized supervisor training, and first aid and CPR training, are maintained in corporate files.

1.5 Documents and Records

Documentation is critical for evaluating the success of any environmental data collection activity. The following sections discuss the requirements for documenting field activities and for preparing laboratory data packages. This section also describes reports that will be generated as a result of this project.

1.5.1 Field Documentation

Field personnel will use permanently bound field logbooks with sequentially numbered pages to record and document field activities. The logbooks will list a contract name and number, the project number, the site name, the names of subcontractors, the client, and the PM. At a minimum, the following will be recorded in the field logbook:

- Names and affiliations of all on-site personnel or visitors
- Weather conditions during the field activity
- Summary of daily activities and significant events
- Notes of conversations with coordinating officials
- References to other field logbooks or forms that contain specific information
- Discussions of problems encountered and their resolutions
- Discussions of deviations from the SAP or other governing documents
- Descriptions of all photographs taken

The field team may also use the field forms during certain sampling or data collection activities to document field activities. The same level of detail will be required for all field forms used during this investigation. Copies of the completed field forms will be stored in the project file.

2 Data Generation and Acquisition

This section describes the requirements for the following:

- Sampling Design (Section 2.1)
- Field Activities (Section 2.2)
- Sample Handling and Custody (Section 2.3)
- Laboratory Quality Assurance/Quality Control (QA/QC) (Section 2.4)
- Equipment Testing, Inspection, Maintenance, and Calibration (Section 2.5)

2.1 Sampling Design

Samples or data will be collected as outlined in the SAP. The SAP for this project is a collection of quarterly or one-time field sampling or data collection events that were prepared by NMCC and its contractors. Field activities will be implemented to optimize the time spent in the field by adhering to established scientific methods and procedures, leading coordinated field schedules, and sharing data with contractors to minimize duplication of data.

Data collected from these field activities will be used in the mine permitting process. This baseline data will also be useful in the design of mine facilities and as a reference during site reclamation activities.

2.2 Field Activities

Field activities have been broken into eight separate activities. These activities, which are outlined in the SAP, will be used to establish the baseline conditions at the Site:

- Climatological factors – The purpose of the monitoring program will be to collect baseline climatological data representative of the Site that satisfies the criteria of the New Mexico Surface Mining Act and the U.S. Environmental Protection Agency (EPA) on-site meteorological program guidance for dispersion modeling
- Vegetation survey – The purpose of the survey is to delineate current vegetation stratified according to disturbance history and to describe specific vegetation attributes for plant communities delineated within the Site. In addition, the survey will identify the presence of potential habitat for threatened and endangered species.
- Wildlife survey – Delineate and map current habitat, describe wildlife use of the area, complete a bird species inventory, complete a threatened or endangered species survey by comparing known records and habitat requirements with current field conditions to determine the likelihood of occurrence of all federal and state listed wildlife species, and determine species distribution by habitat and season.
- Soil survey and sampling – To determine the suitability of in-place soils in areas of proposed disturbance for use as a topdressing material during reclamation.
- Surface water sampling – To characterize the volumetric flow and water quality of seeps, springs, streams, and the pit lake.
- Groundwater sampling – To obtain necessary data to evaluate quantity and quality of all aquifers at the Site that could be impacted by mining activities, address data gaps identified during evaluation of the Draft EIS (BLM, 1996), meet the requirements set forth in the regulations in NMAC Title 19, Chapter 10, Part 6, and to meet the guidelines set forth in MMD's draft Guidance Document for Part 6 New Mining Operations Permitting under the New Mexico Mining Act.
- Historical and cultural properties survey – To locate and assess all cultural resources and historic properties within the area of potential effects.

2.3 Sample Handling and Custody

The following section describes sample handling procedures, including sample identification and labeling, documentation, chain of custody (COC), and shipping. This section applies to water, sediment, and geologic samples that are submitted to an analytical laboratory. Other sample handling and custody procedures for vegetation and other resources are described, where appropriate, in the SAP.

Each sample collected at the Site will be identified using a unique sample identification (ID) number. The description of the sample type and the point name will be recorded on the COC form, as well as in the field notes. Note that field duplicates and ERs will be given a unique sample ID. The association between primary, duplicate, and ER samples will be noted on the COC form.

A sample label will be affixed to each sample container. The label will be completed with the following information written in indelible ink: project name and location, sample ID number, date and time of collection,

preservative used (if applicable), collector's initials, and analysis requested. After labeling, each sample will be refrigerated or placed in a cooler containing ice.

Documentation of sample collection will be completed in permanent black or blue ink in the field logbook. All entries will be legible. The field team leader (FTL) and sampling personnel are responsible for proper documentation of all Site activities.

Standard sample custody procedures will be used to maintain and document sample integrity during collection, transportation, storage, and analysis. COC procedures provide an accurate written record that traces the possession of individual samples from the time of collection in the field to the time of acceptance at the laboratory.

The COC form will be placed in a waterproof plastic bag and taped to the inside of the shipping container used to transport the samples. The laboratory sample custodian will receive all incoming samples, sign the accompanying COC forms, and retain copies of the forms as permanent record. The laboratory sample custodian will record all pertinent information concerning the samples, including the persons delivering the samples, the date and time received, sample condition at the time of receipt (sealed, unsealed, or broken container; temperature; or other relevant remarks).

All samples will be either hand delivered or shipped to an accredited laboratory. Samples may need to be shipped to the laboratory in order to have them analyzed before the expiration of a particular sample's holding time.

2.4 Laboratory QA/QC

This section applies to water, sediment, and geologic samples submitted to accredited analytical laboratories. To ensure quality of laboratory analysis, the analytical laboratory will be required to analyze QA/QC samples as specified by the analytical methods. The laboratory will analyze method blanks, MSs, and LCSs.

Method blanks will be prepared at the frequency prescribed in the individual analytical method or at a rate of 5 percent of the total samples if a frequency is not prescribed in the method.

MSs will be analyzed at a frequency of 5 percent for soil and aqueous samples. The percent recoveries will be calculated for each of the spiked analytes and used to evaluate analytical accuracy. The RPD between spiked samples will be calculated to evaluate precision.

LCSs, or blank spikes, will be analyzed at the frequency prescribed in the analytical method or at a rate of 5 percent of the total samples if a frequency is not prescribed in the method. If percent recovery results for the LCS or blank spike are outside of the established goals, laboratory-specific protocols will be followed to gauge the usability of the data.

Sample quantitation limits (SQL), also referred to as practical quantitation limits, are PRRLs adjusted for the characteristics of individual samples. The PRRLs are chemical-specific levels that a laboratory should be able to routinely detect and quantitate in a given sample matrix. The PRRL is defined in the analytical method or in laboratory method documentation, and incorporates precision (reproducibility) assumptions for the analysis. The SQL takes into account changes in the preparation and analytical methodology that may alter the ability to detect an analyte, including changes such as use of a smaller sample aliquot or dilution of the sample extract. Physical characteristics such as sample matrix and percent moisture that may alter the ability to detect the analyte are also considered. The laboratory will calculate and report SQLs for all environmental samples.

The laboratory activities are overseen by a comprehensive quality assurance program to assure that laboratory practices and results adhere to its policies. The laboratory will provide a standard QA/QC report with all reports. This includes surrogate recoveries, spike recoveries, and method blanks.

The laboratory participates in the Wibby Environmental, third party, proficiency testing program. Wibby is accredited by A2LA and NIST/NVLAP. Results of all proficiency results are sent, by Wibby, to both the laboratory and to their accrediting authorities. The laboratory will also perform proficiency testing on a semiannual basis for all accredited tests. Water proficiencies in the water supply and water pollution studies will be performed in addition to soil proficiencies in hazardous waste pollution studies.

Proficiency results are reviewed by the laboratory manager and all personnel involved in reporting the data. Results that are marked as "check for error" and "unacceptable" are thoroughly reviewed and corrective actions are written for "unacceptable" data.

2.5 Equipment Testing, Inspection, Maintenance, and Calibration

All equipment used during the investigation will be properly tested, inspected, maintained, and calibrated. Samples collected during this investigation will be analyzed using both field and laboratory equipment. Calibration of the field equipment shall be recorded in the field logbook after each calibration event. The calibration procedure for each piece of field equipment used will be outlined in the final report.

The laboratory's QA plan and written operating procedures describing specific testing, inspection, maintenance, and calibration procedures for equipment will be followed. If required, maintenance procedures and schedules will be performed and documented.

3 Inspection and Acceptance of Supplies and Consumables

PMs have primary responsibility for identifying the types and quantities of supplies and consumables needed to complete projects and are responsible for identifying acceptance criteria for these items.

Supplies and consumables can be received either at the contractor's office or at a work site. When supplies are received at an office, the PM or FTL will sort them according to vendor, check packing slips against purchase orders, and inspect the condition of all supplies before they are accepted for use on a project. If an item does not meet the acceptance criteria, deficiencies will be noted on the packing slip and purchase order and the item will then be returned to the vendor for replacement or repair.

Procedures for receiving supplies and consumables in the field are similar. When supplies are received, the PM or FTL will inspect all items against the acceptance criteria. Any deficiencies or problems will be noted in the field logbook and deficient items will be returned for immediate replacement.

Analytical laboratories are required to provide certified clean containers for all analyses. These containers must meet EPA standards as described in *Specifications and Guidance for Obtaining Contaminant-Free Sampling Containers* (EPA, 1992).

4 Data Management

All field and analytical data collected during this investigation will be provided to MMD in the Baseline Characterization Report. Field data will be recorded in the logbook and/or field forms and will be included in the appendices. Analytical data will be summarized, tabulated, analyzed, and provided in the body of the final

report. The original laboratory data will be provided in an appendix of the final report. Some data may be presented graphically.

5 Assessment, Response Actions, and Reports to Management

NMCC and MMD will oversee collection of environmental data using the appropriate assessment and audit activities. Any problems encountered during an assessment of field investigation or laboratory activities will require appropriate corrective action to ensure that the problems are resolved. The corrective actions will be discussed with MMD and will be implemented after approval from MMD is received. NMCC will perform routine audits of their subcontractor's performance. In addition, the subcontractor's project managers will ensure that the work done under their assigned tasks complies with the QAPP and will report non compliance, problems, or other issues to NMCC in a timely manner agreed upon between NMCC and its subcontractors.

Effective management of environmental data collection requires: 1) timely assessment and review of all activities, and 2) open communication, interaction, and feedback among all project participants. NMCC and its contractors will use verbal communication with MMD oversight personnel, electronic communication, and monthly status reports to address any project-specific quality issues and to facilitate timely communication of these issues. NMCC and its contractors will develop a communications protocol to communicate with the MMD and solicit the MMD for concurrence with these communication procedures.

6 Data Evaluation and Usability

This section describes the procedures that are planned to review and evaluate field and laboratory data. This section also discusses procedures for verifying that the data are sufficient to meet MQOs for the project.

Review and evaluation of the data generated during field and laboratory activities are essential to obtaining defensible data of acceptable quality. Project team personnel will review field data to identify inconsistencies or anomalous values. Any inconsistencies discovered will be resolved as soon as possible by seeking clarification from field personnel responsible for data collection. All field personnel will be responsible for following the sampling and documentation procedures described in this SAP so that defensible and justifiable data are obtained.

Data values that are significantly different from the population are called "outliers." A systematic effort will be made to identify any outliers or errors before field personnel report the data. Outliers can result from improper sampling or measurement methodology, data transcription errors, calculation errors, or natural causes. Outliers that result from errors found during data verification will be identified and corrected; outliers that cannot be attributed to errors in sampling, measurement, transcription, or calculation will be clearly identified in project reports.

6.1 Laboratory Data Verification

Laboratory personnel will verify analytical data at the time of analysis and reporting and through subsequent reviews of the raw data for any nonconformances to the requirements of the analytical method. Laboratory personnel will make a systematic effort to identify any outliers or errors before they report the data. Outliers that result from errors found during data verification will be identified and corrected; outliers that cannot be attributed to errors in analysis, transcription, or calculation will be clearly identified in the case narrative section of the analytical data package.

6.2 Laboratory Data Evaluation and Usability

All laboratory data will be evaluated. The data evaluation strategy will not be a full data validation process, but will determine if the analytical results are within the QC limits set for the project. As part of this evaluation, the data usability will be assessed.

7 Reconciliation with User Requirements

After environmental data have been reviewed and evaluated in accordance with the procedures described in Section 7.0, the data must be further evaluated to assess whether MQOs have been met.

To the extent possible, EPA's data quality assessment (DQA) process will be followed to verify that the type, quality, and quantity of data collected are appropriate for their intended use. DQA methods and procedures are outlined in EPA's *Guidance for Data Quality Assessment, Practical Methods for Data Analysis* (EPA, 2000b). The DQA process includes five steps: (1) review the sampling objectives and sampling design, (2) conduct a preliminary data review, (3) select a statistical test, (4) verify the assumptions of the statistical test, and (5) draw conclusions from the data. In the case of water, sediment, and geologic samples, no statistical analysis is planned at this time. Statistical analyses planned for ecological and cultural resources data are defined in Sections 4, 5, and 10 of the SAP.

When the five-step DQA process is not completely followed because the sampling objectives are qualitative, data quality and data usability will be systematically assessed. This assessment will include:

- A review of the sampling design and sampling methods to verify that these were implemented as planned and are adequate to support project objectives.
- A review of project-specific data quality indicators for PARCC and project reporting limits to evaluate whether acceptance criteria have been met.
- A review of project-specific sampling objectives to assess whether they have been achieved by the data collected.
- An evaluation of any limitations associated with the decisions to be made based on the data collected (for example, if data completeness is only 90 percent compared to a project-specific completeness objective of 95 percent, the data may still be usable to support a decision, but at a lower level of confidence).

The final report for the project will discuss any potential impacts of these reviews on data usability and will clearly define any limitations associated with the data.

8 References

American Society for Testing and Materials (ASTM), 2000, Standard practice for description and identification of soils (visual-manual procedure): ASTM Standard D 2488-00.

Bureau of Land Management (BLM), 1996, Draft environmental impact statement (DEIS), Copper Flat Project: Las Cruces, N. Mex., U.S. Department of the Interior. Prepared by ENSR, Fort Collins, Colo.

Environmental Protection Agency (EPA), 1992, Specifications and guidance for obtaining contaminant-free sampling containers: Washington, DC, Office of Solid Waste and Emergency Response, EPA/A540/R-93/051. December.

———.2000a, Data quality objectives process for hazardous waste site investigations, EPA QA/G-4HW: Washington, DC, Office of Environmental Information, EPA/600/R-00/007. January.

———.2000b, Guidance for data quality assessment, practical methods for data analysis, EPA QA/G-9, QA00 Update: Washington, DC, Office of Environmental Information, EPA/600/R-96/084. July.

———.2000c, Guidance for the data quality objectives process, EPA QA/G-4: Washington, DC, Office of Environmental Information, EPA/600/R-96/055. August.

Figures



Figure 1. Project Organization



Figure 2. Parametrix Organizational Chart

Table

Table 1
INTERA Key Personnel and Responsibilities

Name	Organization	Role	Responsibilities	Contact Information
Ms. Cindy Ardito	INTERA	Program Quality Assurance (QA) Officer	Participates in development of technical approach. Reviews technical deliverables. Provides technical oversight during data collection	INTERA Inc. 6000 Uptown Blvd. NE, Suite 220 Albuquerque, NM 87110 (505) 246-1600, (505) 246-2600 FAX ext. 1206 cardito@intera.com
Mr. Peter Castiglia	INTERA	Project Manager/ Technical Lead	Responsible for overall project execution and for coordination with regulatory agencies and contractors. Actively participates in Data Quality Objective process. Provides management and technical oversight during data collection.	INTERA Inc. 6000 Uptown Blvd. NE, Suite 220 Albuquerque, NM 87110 (505) 246-1600, (505) 246-2600 FAX ext. 1217 pcastiglia@intera.com
Mr. Lee Dalton	INTERA	Field Team Leader (FTL) – Groundwater	Responsible for directing day-to-day field activities conducted by INTERA and subcontractor personnel. Verifies that field sampling and measurement procedures follow the Sampling and Analysis Plan. Provides project manager with regular reports on status of field activities.	INTERA Inc. 6000 Uptown Blvd. NE, Suite 220 Albuquerque, NM 87110 (505) 246-1600, (505) 246-2600 FAX ext. 1213 ldalton@intera.com
Mr. Justin Jayne	INTERA	Field Team Leader (FTL) – Surface Water	Responsible for directing day-to-day field activities conducted by INTERA and subcontractor personnel. Verifies that field sampling and measurement procedures follow the Sampling and Analysis Plan. Provides project manager with regular reports on status of field activities.	INTERA Inc. 6000 Uptown Blvd. NE, Suite 220 Albuquerque, NM 87110 (505) 246-1600, (505) 246-2600 FAX ext. 1220 jjayne@intera.com
Ms. Angela Persico	INTERA	On-Site Safety Officer	Responsible for implementing health and safety plan for determining appropriate site control measures and personal protection levels. Conducts safety briefings for INTERA and subcontractor personnel and site visitors. Can suspend operations that threaten health and safety.	INTERA Inc. 6000 Uptown Blvd. NE, Suite 220 Albuquerque, NM 87110 (505) 246-1600, (505) 246-2600 FAX ext. 1207 apersico@intera.com
Ms. Angela Persico Mr. Spencer Whitman Mr. Konrad Clark Ms. Annelia Tinklenberg	INTERA	Field Sampler(s)	Responsible for collecting representative samples and conducting necessary field activities specified in Sampling and Analysis Plan. Works under supervision of field team leader. Ensures proper sampling and handling procedures.	INTERA Inc. 6000 Uptown Blvd. NE, Suite 220 Albuquerque, NM 87110 (505) 246-1600, (505) 246-2600 FAX

Name	Organization	Role	Responsibilities	Contact Information
Mr. Bob Powell	Class One Technical Services, Inc.	Project Manager	Responsible for overall project execution and for coordination with regulatory agencies and contractors. Actively participates in Data Quality Objective process. Provides management and technical oversight during data collection by Class One Technical Services.	Class One Technical Services, Inc. 3500 Comanche Rd. NE Suite G Albuquerque, NM 87107 (505) 830-9680
Mr. Jens Deichmann	Parametrix	Project Manager – Ecological and Cultural Resources	Responsible for coordination with regulatory agencies and contractors. Actively participates in Data Quality Objective process. Provides management and technical oversight during data collection by Parametrix.	Parametrix Incorporated 8801 Jefferson NE; Bldg. 2 Albuquerque, NM 87113 (505) 998-5552 jdeichmann@parametrix.com
Mr. Chris Parrish	Parametrix	FTL - Cultural Resources	Responsible for directing day-to-day field activities conducted for cultural resources by Parametrix and subcontractor personnel. Verifies that field sampling and measurement procedures follow the Sampling and Analysis Plan. Provides project manager with regular reports on status of field activities.	Parametrix Incorporated 8801 Jefferson NE; Bldg. 2 Albuquerque, NM 87113 (505) 821-4700
Mr. Jim Nellessen	Parametrix	FTL – Natural Resources	Responsible for directing day-to-day field activities conducted for natural resources by Parametrix and subcontractor personnel. Verifies that field sampling and measurement procedures follow the Sampling and Analysis Plan. Provides project manager with regular reports on status of field activities.	Parametrix Incorporated 8801 Jefferson NE; Bldg. 2 Albuquerque, NM 87113 (505) 821-4700
Mr. Chad McKenna	Parametrix	Technical Lead – Geographic Information Systems (GIS)	Responsible for directing day-to-day activities conducted for GIS by Parametrix and subcontractor personnel. Verifies that GIS data collection procedures follow the Sampling and Analysis Plan. Provides project manager with regular reports on status of GIS data.	Parametrix Incorporated 8801 Jefferson NE; Bldg. 2 Albuquerque, NM 87113 (505) 821-4700
Mr. Mark Willow	SRK Consulting	Project Manager – Geologic Sampling	Responsible for coordination with regulatory agencies and contractors. Actively participates in Data Quality Objective process. Provides management and technical oversight during data collection by SRK.	SRK Consulting 250 Neil Road, Suite 300 Reno, Nevada 89502 (775) 828-6800 mwillow@srk.com
Dr. Robert Bowell	SRK Consulting	Technical Lead – Geologic Sampling	Responsible for directing day-to-day activities conducted for geologic by SRK and subcontractor personnel. Verifies that geologic data collection procedures follow the Sampling and Analysis Plan. Provides project manager with regular reports on status of geologic data collection and results.	SRK Consulting (UK) Ltd. 5th Floor, Churchill House 17 Churchill Way Cardiff, CF10 2HH, UK +44 (0) 29 2034 8150 egrbowel@srk.co.uk

5-13-201

NEW MEXICO
ENVIRONMENT DEPARTMENT

Ground Water Quality Bureau

1190 St. Francis Drive
P.O. Box 5469, Santa Fe, NM 87502
Phone (505) 827-2918 Fax (505) 827-2965
www.nmenv.state.nm.us

SUSANA MARTINEZ
Governor
JOHN A. SANCHEZ
Lieutenant Governor

DAVE MARTIN
Secretary
RAJ SOLOMON, P.E.
Deputy Secretary

May 13, 2011

Jens Deichmann,
Copper Flat Mine
New Mexico Copper Corporation
2425 San Pedro NE Suite100
Albuquerque, NM 87110

RE: Administrative Completeness Determination and Applicant's Public Notice Requirements, DP-1, Copper Flat Mine

Dear Mr. Deichmann:

The New Mexico Environment Department (NMED) received a Ground Water Discharge Permit Application for the above referenced facility on March 31, 2011. Pursuant to Section 20.6.2.3108 NMAC of the New Mexico Water Quality Control Commission Regulations (20.6.2 NMAC), NMED determined on May 3, 2011 that your application is administratively complete.

Within 30 days of receipt of this letter, you must provide public notice. Instructions and materials needed to complete the public notice are enclosed.

A technical reviewer will contact you within the next few months if additional information is needed to process your application. If you have a deadline of concern in the interim or any questions, please call the Ground Water Quality Bureau at (505) 827-2900.

Sincerely,

for William C. Olson, Chief
Ground Water Quality Bureau

enc: Instructions for Completing Public Notice Requirements
Affidavit
Public Notice Flyer
Text for Newspaper Display Ad
Public Notice Sign
Invoice ($15 fee for sign) if not attached, the invoice will be mailed separately

INSTRUCTIONS FOR COMPLETING PUBLIC NOTICE REQUIREMENTS

Discharge Permit DP- 1 ¤ New ¤ Modification X Renewal & Modification

Within 30 days of the date NMED deemed your Discharge Permit application administratively complete, you must provide public notice as follows:

1. **Post sign(s) at the facility.**
   Enclosed is a sign 2 x 3 feet in size (or multiple signs if required) which must be posted **at or near the facility** in a conspicuous location approved by NMED. An invoice for the sign(s) is enclosed. NMED approves the following sign posting location(s):
   At the road pull out on the SE side of the NM Hwy 152, near the Geronimo Trail Scenic Byway sign

2. **Post a public notice flyer off-site.**
   The enclosed public notice flyer which must be posted **off-site** at a location conspicuous to the public and approved by NMED. NMED approves the following flyer posting location:
   Hillsboro Community Center

3. **Mail a public notice flyer to property owners within 1/3 mile.**
   A copy of the enclosed public notice flyer must be sent by 1st class mail to the owners of record of all properties within 1/3 mile from the boundary of the property where the discharge site is located. If there are no properties within 1/3 mile other than properties owned by the applicant, then the flyer must be mailed to the owners of record of the nearest adjacent properties.

   The names and addresses of property owners can be obtained from the county tax assessor's office. The list of property owners' names and addresses must be submitted to NMED.

4. **Mail a public notice flyer to the owner of the discharge site.**
   A copy of the enclosed flyer must be sent via certified mail, return receipt requested, to the owner(s) of the discharge site(s), if the applicant is not the owner. The list of owners' names and addresses and the certified mail receipts must be submitted to NMED.

5. **Place a display ad in the newspaper.**
   A display ad 3 x 4 inches in size must be published for one day in a newspaper of general circulation in the location of the proposed discharge. The ad may **not** be placed in the classified or legal section. The text for the ad is enclosed. NMED approves publishing the ad in the following newspaper:
   Sierra County Sentinel

PROOF OF NOTICE. Within 15 days of completing the above requirements, the applicant must submit the following items as proof of notice to NMED:

Affidavit regarding the sign posting and mailing (form enclosed).
List of names and addresses to whom the public notice flyer was mailed.
List of names and addresses of owners of discharge sites.
Certified mail receipts for mailing to discharge site owner(s), if required.
Copy of newspaper ad.

Send to NMED Ground Water Quality Bureau, PO Box 5469, Santa Fe, NM 87502.

Reviewer's Initials and Date FV 5/10/11

PUBLIC NOTICE
Discharge Permit Application

Copper Flat Mine, DP-1

DP-1, Copper Flat Mine, Jens Deichmann, proposes to renew and modify the Discharge Permit for the discharge of up to 2,875,873 gallons per day of mine tailings, process water, and domestic wastewater to a mine tailing impoundment. Potential contaminants from this type of discharge include sulfate, nitrate, total dissolved solids, and metals. The facility is located approximately 6 miles NE of Hillsboro, in Section 31, T15S, R036W, Sections 25, 26, 27, 35, and 36, T15S, R07W, and Section 6, T16S, R06W, Sierra County. Ground water beneath the site is at a depth of approximately 40 - 50 feet and has a total dissolved solids concentration of approximately 500 - 800 milligrams per liter.

The applicant is seeking a Discharge Permit for the proposed discharge. Provided the applicant has met applicable requirements, the New Mexico Environment Department (NMED) will propose a Discharge Permit containing limitations, monitoring requirements, and other conditions intended to protect ground water quality for present and potential future use. Information in this public notice was provided by the applicant and will be verified by the New Mexico Environment Department during the permit application review process. NMED will accept comments and statements of interest regarding the application and will create a facility specific mailing list for persons who wish to receive future notices.

You may send comments or statements of interest to:

Greg Huey, DP-1
Ground Water Quality Bureau
PO Box 5469
Santa Fe, NM 87502.

For additional information, please call:
505-827-2900

Applicant
Jens Deichmann
Copper Flat Mine
New Mexico Copper Corporation
2425 San Pedro NE Suite 100
Albuquerque, NM 87110

Public Notice Synopsis, DP-1
(for sign and newspaper display ad)

Newspaper display ad must be at least 3 inches by 4 inches in size and must be published for at least one day in a section other than the classifieds or legals.

PUBLIC NOTICE / NOTICIA PUBLICA

Discharge Permit Application / Aplicación para Permiso para Descargar: For up to 2,875,873 gallons per day of mine tailings,process water, and domestic wastewater to a mine tailing impoundment / Para un máximo de 2.875.873 galones por día de desechos mineras, agua procesada, y aguas residuales domésticas a un embalse de relaves de minas.

Applicant & Discharge Location / Solicitante & Sitio de Descarga: Copper Flat Mine, approximately 6 miles NE of Hillsboro

For More Information / Para Más Información (DP-1):
Ground Water Quality Bureau / Sección de Agua Subterránea
NM Environment Department / Departamento del Medio Ambiente

(505) 827-2900 www.nmenv.state.nm.us (public notices)

Information in this public notice was provided by the applicants and will be verified by NMED during the permit application review process.

5-30-2011

Huey, Greg, NMENV

From: Jens Deichmann [jens@nmcopper.com]
Sent: Monday, May 30, 2011 10:27 PM
To: Eustice, Chris, EMNRD; Huey, Greg, NMENV; Menetrey, Mary Ann, NMENV; holland.shepard@state.nm.us; Jankowitz, Rachel J., DGF
Subject: Tuesday meeting: 9:30

Good evening. I hope you had a good holiday weekend.
I'm not sure who all will be there so limited the distribution to those I thought might be.
I have a few things I'd like to cover and then available for any questions you might have about progress on the project

1. Open houses next week
2. 3rd party RFP
3. Cooperating agency agreements
4. NMCC - BLM cost recovery agreement
5. Meeting between BLM and cooperating agencies, once agreement signed, to agree on RFP scope, and can we (NMCC and individual state agencies discuss ahead of time particular interests for the SOW?
6. Status of baseline studies by NMCC contractors
7. Status of abatement plan review

Thanks for taking the time to meet tomorrow.
Jens
--
Jens Deichmann
New Mexico Copper Corp.
505-681-2536

5-30-2011

5-31-2011

001

Huey, Greg, NMENV

From: Huey, Greg, NMENV
Sent: Tuesday, May 31, 2011 4:51 PM
To: 'maxyeh@windstream.net'
Subject: RE: Comment on NMCC permit for waste water discharge

Mr. Yeh,

Thank you for your participation and sharing your concerns regarding NMCC's application for a discharge permit at the Copper Flat Mine.

The open house meetings to be conducted next week are independently sponsored by NMCC to answer questions that the public may have. NMED is not officially involved with these meetings, but I intend to be present on Tuesday at the Caballo meeting, and I have given my business cards to the NMCC representative and asked him to give my contact information to anyone that may wish to speak with NMED about the process.

New Mexico law provides the opportunity for any person to request a public hearing during the permitting phase of the project approval:
http://www.nmcpr.state.nm.us/nmac/_title20/T20C006.htm

Currently I'm performing the technical review of the Discharge Permit application. Once the draft Discharge Permit has undergone internal review, a second public notice will be published inviting comments on the draft permit. At that time members of the public may petition the NMED Secretary for a public hearing. The second public notice will be issued in a few months, once the permit has undergone the internal review process. I will add you to our concerned parties list and assure that you are notified at that time.

I have added your comments to the public record. However, I do have a few points of clarification based on your statement. Water will not be discharged into the pit lake. Under mining operations, mill tailings and process water are to be discharged to a lined tailing pond. This liner will be constructed from hdpe and designed to prevent any contaminated solutions from contacting ground water. It is actually proposed to remove water from the pit lake and use this water in the milling process.

A comprehensive study is currently underway to determine the present status of surface and ground water in the area. This will involve a water budget that will answer your question about water quantity in the area and how pumping will impact this system.

Please contact me with any further questions. I appreciate your participation and will be sure to keep you informed throughout this process.

Greg Huey
Mining Environmental Compliance Section
NMED - Ground Water Quality Bureau
Office (505) 827-1046
Mobile (505) 670-1878
Fax (505) 827-2965
http://www.nmenv.state.nm.us/gwb/

-----Original Message-----

To: Greg Huey, DP-1
Ground Water Quality Bureau
NM Environment Department
P.O. Box 5469
Santa Fe, NM 87502
From: Max Yeh
P.O. Box 156
Hillsboro, NM 88042
Date: May 28, 2011
Re: Public Comment on NMCC's application for a discharge permit at Copper Flats Mine, Sierra County

The posted announcement of NMCC's application for a discharge permit at Copper Flats Mine states that 2.8 million gallons of toxic water will be discharged into the pit lake a day. I have two concerns about this statement: 1) the possibility that the consequential enlargement of the pit lake will negatively impact both surface water and groundwater quality; and 2) the inordinately large amount of water use, essentially transforming quality groundwater into deteriorated surface water, will impact the quantity of water available for other uses.

1) At present the pit area and the pit lake is only 12.8 acres, with the pit lake much less than $1/5^{th}$ of that. A discharge of 8.l6 acre ft/day would raise the level of the lake at least 2 ft on the first day of such discharge, approaching 1 foot a day as the water spreads out. The enlargement of the surface area increases, of course, evaporation and thus the concentration of toxicity.

It is highly unlikely that the natural alkalinity of the surface minerals will be sufficient to neutralize the acidity of the pit lake, so that the discharge will unbalance the situation described by Raugust and Lemore in 2004. Raugust and Lemore described a historical situation in which groundwater levels of LDS and sulfates were increasing. One can expect such levels to increase further and more rapidly because of the increased size and toxic levels of the pit lake.

Raugust and Lemore note that during the 3-month period of mining in 1981, monitoring showed no adverse effects of the operation, but this is a very problematic conclusion, first, because the period of operation was quite short and the amount of discharge much smaller and second, because there was only one monitoring well in place before 1996, so the data seems insufficient for that claim.

2) My second concern, with the quantity of water this discharge uses, may not be in the purview of the NMED and perhaps should be addressed to the Office of the State Engineer; however, it seems pertinent in considering the issuance of the permit. Some coordination between the departments was one of the recommendations of the Governor's Blue Ribbon Task Force report of 2010 in water issues. There are two concerns in regard to the source of this water. The projected use would increase by 20% of the total groundwater use in Sierra County. It would be the equivalent of increasing the population of Sierra County by 28,000 persons, so that when the mine operates it would be like tripling the population in the County.
If all this amount of water is not withdrawn from the ground source but if part of it is recycled, the water use may be sustainable, but the practice would increase the problem of water degradation since the discharged water would be increasingly more toxic, dedounding on my first concern.

6-6-2011

01720

STATE OF NEW MEXICO
Environment Department

SUSANA MARTINEZ, GOVERNOR
David Martin, *Cabinet Secretary*
Raj Solomon, P.E., *Deputy Secretary*

NEWS RELEASE
June 6, 2011

Contact: Jill Turner, Communications Coordinator (505)222-9548 / jill.turner@state.nm.us

Environment Department Receives Stage 1 Abatement Plan to Investigate Surface and Ground Water Contamination at Copper Flat Mine near Hillsboro

The New Mexico Environment Department's Ground Water Quality Bureau received a Stage 1 Abatement Plan proposal from New Mexico Copper Corporation to investigate surface and ground water contamination at the Copper Flat Mine. The facility is located approximately 5 miles northeast of Hillsboro on NM Highway 152.

Water quality monitoring of monitoring wells and an open pit pool at the facility showed concentrations of total dissolved solids (TDS), sulfate, chloride, manganese, and uranium in exceedence of New Mexico ground water standards during past investigations. The depth to ground water at the site ranges from 0 to 50 feet. In a letter to New Mexico Copper Corporation, NMED required that an Abatement Plan proposal be submitted within 60 days of notification.

The Stage 1 Abatement Plan submitted by the company proposes collecting soil, surface water and ground water samples and installing additional ground water monitoring wells to define the extent of soil and ground water pollution.

New Mexico Water Quality Control Commission regulations require responsible parties to remediate surface and ground water pollution. After the investigation is completed, a Stage 2 Abatement Plan proposal will be submitted to NMED. A public notice of the Stage 2 Abatement Plan proposal will be issued by New Mexico Copper Corporation within 30 days of submitting the proposal to NMED. The public will have an opportunity to comment on the Stage 2 Abatement Plan proposal and request a hearing or meeting. NMED will seek written comments from the public within 60 days of determining that the cleanup proposal is administratively complete.

###

6-17-2011

Huey, Greg, NMENV

From: maxyeh@windstream.net
Sent: Friday, June 17, 2011 5:21 PM
To: Huey, Greg, NMENV
Subject: Re: Exploratory Permit for Copper Flats Mine

Dear Mr. Huey,

Look, I'm sorry I jumped on you for mistaking Benseal and EZ-Mud. I think you associated the two because one of the common practices for plugging drill holes is to mix the two so that as the EZ-Mud emulsion dries out it forms a kind of hardened plastic plug of bentonite. What exercised me was that NMCC's application did not even specify Benseal but some other brand of clay and silicate mixture, so that your reference to Benseal was like just assuming "standard practice" without referring to the application, where in answer to 5b NMCC says it will store the mud and additives and then dump it all back in the hole. Yet the department passed on it, apparently. The application did not mention disposal of the stuff in some other way.

It is not EZ-Mud that bothers me; though you should know that it is not a benign substance. It is a long chain polyacrylimide, and while mining suppliers who want to sell the stuff never mention it in their MSDS, chemical companies who make the stuff put "Associated with cancer" in their MSDS. National and international cancer organizations classify it as a "probable human carcinogen." Lab tests show it is cancer causing in rats.

You may think it benign because, as you mention, it is used in drilling water wells and even in clarifying drinking water, but in both cases its use is mitigated by the fact that its use precedes water treatment. Chlorine breaks it down, and whether that breakdown releases chlorine gas or not, I don't know. That is the reason, I suspect, that when it is used in drilling the refused is removed and properly disposed of. But none of this was in NMCC application and not bothersome to the ED, apparently.

What bothers me is the assumption that "standard practice" is ok and passable. In a comparison of mining company predictions on water quality (in EIS documents) to actual results of hardrock mining, a recent study says that 100% of the company's predictions claimed water quality compliance, of which 76% turned out to exceed quality standards. In these failed predictions, 64% of the mitigation measures failed. That means that of the mines studied, almost 50% became what the ED should consider disasters.

I really think the ED should have standards better than "standard practice,"
and I hope that you agree.

Max
----- Original Message -----
From: "Huey, Greg, NMENV" <greg.huey@state.nm.us>
To: <maxyeh@windstream.net>
Sent: Tuesday, June 14, 2011 11:00 AM
Subject: RE: Exploratory Permit for Copper Flats Mine

Mr. Yeh,

My apologies, in my response I referred to the Holeplug material by mistake.

You are correct that EZ-Mud is a shale inhibitor. The approval of this chemical by the department is standard practice, as we have no record of ground water contamination resulting from the use of this product. EZ-Mud is

a common drilling mud used to coat the bore hole and prevent migration of fluids from the hole into the surrounding aquifer, and it is used in the development of water quality monitoring, drinking water, and production wells in addition to drilling of exploration bore holes. All cuttings are removed from the hole and disposed of in an approved manner, and plugging the hole with bentonite prevents the migration of any residual material.

Please call me at (505) 827-1046 to discuss this matter in greater detail.

Thank you,

Greg Huey
Mining Environmental Compliance Section
NMED - Ground Water Quality Bureau
Office (505) 827-1046
Mobile (505) 670-1878
Fax (505) 827-2965
http://www.nmenv.state.nm.us/gwb/

-----Original Message-----
From: maxyeh@windstream.net [mailto:maxyeh@windstream.net]
Sent: Monday, June 13, 2011 4:19 PM
To: Huey, Greg, NMENV
Cc: Ruiz, Thomas, NMENV
Subject: Re: Exploratory Permit for Copper Flats Mine

Dear Mr. Huey,

Thanks for answering my query to Mr. Ruiz.

I do realize that the permitting process for the Exploration permit is over and done with.

But for the record, I would like to record here that EZ-Mud is NOT Benseal, at least not according to NMCC's application itself. See Appendix C of the application, wherein you will find the MSDS for EZ-Mud. It is not used to seal drill holes but is a shale inhibitor whose substance is (to quote Halliburton) "Hydrotreated light petroleum distillate." Please email fdunexchem@halliburton.com for confirmation. You can assertain for yourself how toxic the substance is for groundwater.

Since writing my concerns to Mr. Ruiz, I have talked to technicians at the company who have assured me that the original application was revised to the effect that EZ-Mud will not be put back into the drill holes but be disposed of in other ways (hopefully without damaging the ground water now or in the future). Whether this is being done or not, I cannot say, but I expect the Environment Department to be on top of these things.

Why, may I ask, was the permit issued by the Department with such an error in it?

Max
----- Original Message -----
From: "Huey, Greg, NMENV" <greg.huey@state.nm.us>

To: <maxyeh@windstream.net>
Sent: Monday, June 13, 2011 3:03 PM
Subject: FW: Exploratory Permit for Copper Flats Mine

Mr. Yeh,

Your message to Mr. Ruiz at the NM Environment Department has been brought to my attention and will be added to the Copper Flat Mine permanent record.

I've attached the Materials Safety Data Sheet for Benseal (i.e. EZ Mud). Benseal is composed of bentonite clay and silica, and is used to seal bore holes to prevent interaction between the ground surface and a ground water aquifer that has been drilled through. There are no petroleum products in this material. The NM State Engineer requires that all bore holes be plugged using this or similar products in order to protect ground water quality from surface contamination.

The methods proposed by New Mexico Copper Corporation for subsurface exploration have been reviewed by the NM State Engineer, NM Environment Department, and NM Mining & Minerals Division, and a permit has been approved for this exploration. You may request to review these records either in person or in writing by contacting each department.

Thank you once again for your interest in this site. I will continue to keep you informed of any developments.

Greg Huey
Mining Environmental Compliance Section
NMED - Ground Water Quality Bureau
Office (505) 827-1046
Mobile (505) 670-1878
Fax (505) 827-2965
http://www.nmenv.state.nm.us/gwb/

-----Original Message-----
From: maxyeh@windstream.net [mailto:maxyeh@windstream.net]
Sent: Wednesday, June 08, 2011 11:24 AM
To: Ruiz, Thomas, NMENV
Subject: Exploratory Permit for Copper Flats Mine

Dear Mr. Ruiz,

I have just looked over the SIO25EM, Copper Flat 2 Project, Exploration Permit Application, and noticed that the issue of ground water is unaddressed in the answers to the questions of the application. This issue is of some concern because the applicant's answer to 5B states that drilling mud and additives will be disposed of in the drill holes. Since ground water is said by the applicant to be at a depth from 5 to 50 feet and since gthe test holes will be much greater, the drilling mud and additives will be into ground water. The applicant proposes using EZ Mud, which is a petroleum distillate which is a pollutant. The applicant also proposes the use of Soda Ash, which is hazardous to aquatic life. I strongly urge that

you bring these facts to the attention of the reviewers of the permit application.
Max

HALLIBURTON

MATERIAL SAFETY DATA SHEET

Product Trade Name: **BENSEAL®**

Revision Date: 25-Mar-2010

1. CHEMICAL PRODUCT AND COMPANY IDENTIFICATION

Product Trade Name: BENSEAL®
Synonyms: None
Chemical Family: Mineral
Application: Viscosifier

Manufacturer/Supplier
Baroid Fluid Services
Product Service Line of Halliburton
P.O. Box 1675
Houston, TX 77251
Telephone: (281) 871-4000
Emergency Telephone: (281) 575-5000

Prepared By
Chemical Compliance
Telephone: 1-580-251-4335
e-mail: fdunexchem@halliburton.com

2. COMPOSITION/INFORMATION ON INGREDIENTS

SUBSTANCE	CAS Number	PERCENT	ACGIH TLV-TWA	OSHA PEL-TWA
Bentonite	1302-78-9	60 - 100%	Not applicable	Not applicable
Crystalline silica, tridymite	15468-32-3	0 - 1%	0.05 mg/m^3	1/2 x $\frac{10\ mg/m^3}{\%SiO2 + 2}$
Crystalline silica, cristobalite	14464-46-1	0 - 1%	0.025 mg/m^3	1/2 x $\frac{10\ mg/m^3}{\%SiO2 + 2}$
Crystalline silica, quartz	14808-60-7	1 - 5%	0.025 mg/m^3	$\frac{10\ mg/m^3}{\%SiO2 + 2}$

More restrictive exposure limits may be enforced by some states, agencies, or other authorities.

3. HAZARDS IDENTIFICATION

Hazard Overview

CAUTION! - ACUTE HEALTH HAZARD
May cause eye and respiratory irritation.

DANGER! - CHRONIC HEALTH HAZARD
Breathing crystalline silica can cause lung disease, including silicosis and lung cancer. Crystalline silica has also been associated with scleroderma and kidney disease.

This product contains quartz, cristobalite, and/or tridymite which may become airborne without a visible cloud. Avoid breathing dust. Avoid creating dusty conditions. Use only with adequate ventilation to keep exposures below recommended exposure limits. Wear a NIOSH certified, European Standard EN 149, or equivalent respirator when using this product. Review the Material Safety Data Sheet (MSDS) for this product, which has been provided to your employer.

4. FIRST AID MEASURES

Inhalation — If inhaled, remove from area to fresh air. Get medical attention if respiratory irritation develops or if breathing becomes difficult.

Skin — Wash with soap and water. Get medical attention if irritation persists.

Eyes — In case of contact, immediately flush eyes with plenty of water for at least 15 minutes and get medical attention if irritation persists.

Ingestion — Under normal conditions, first aid procedures are not required.

Notes to Physician — Treat symptomatically.

5. FIRE FIGHTING MEASURES

Flash Point/Range (F):	Not Determined
Flash Point/Range (C):	Not Determined
Flash Point Method:	Not Determined
Autoignition Temperature (F):	Not Determined
Autoignition Temperature (C):	Not Determined
Flammability Limits in Air - Lower (%):	Not Determined
Flammability Limits in Air - Upper (%):	Not Determined

Fire Extinguishing Media — All standard firefighting media.

Special Exposure Hazards — Not applicable.

Special Protective Equipment for Fire-Fighters — Not applicable.

NFPA Ratings:	Health 0, Flammability 0, Reactivity 0
HMIS Ratings:	Health 0*, Flammability 0, Reactivity 0

6. ACCIDENTAL RELEASE MEASURES

Personal Precautionary Measures — Use appropriate protective equipment. Avoid creating and breathing dust.

Environmental Precautionary Measures — None known.

Procedure for Cleaning / Absorption	Collect using dustless method and hold for appropriate disposal. Consider possible toxic or fire hazards associated with contaminating substances and use appropriate methods for collection, storage and disposal.

7. HANDLING AND STORAGE

Handling Precautions	This product contains quartz, cristobalite, and/or tridymite which may become airborne without a visible cloud. Avoid breathing dust. Avoid creating dusty conditions. Use only with adequate ventilation to keep exposure below recommended exposure limits. Wear a NIOSH certified, European Standard En 149, or equivalent respirator when using this product. Material is slippery when wet.
Storage Information	Use good housekeeping in storage and work areas to prevent accumulation of dust. Close container when not in use. Do not reuse empty container. Product has a shelf life of 60 months.

8. EXPOSURE CONTROLS/PERSONAL PROTECTION

Engineering Controls	Use approved industrial ventilation and local exhaust as required to maintain exposures below applicable exposure limits listed in Section 2.
Personal Protective Equipment	If engineering controls and work practices cannot prevent excessive exposures, the selection and proper use of personal protective equipment should be determined by an industrial hygienist or other qualified professional based on the specific application of this product.
Respiratory Protection	Wear a NIOSH certified, European Standard EN 149, or equivalent respirator when using this product.
Hand Protection	Normal work gloves.
Skin Protection	Wear clothing appropriate for the work environment. Dusty clothing should be laundered before reuse. Use precautionary measures to avoid creating dust when removing or laundering clothing.
Eye Protection	Wear safety glasses or goggles to protect against exposure.
Other Precautions	None known.

9. PHYSICAL AND CHEMICAL PROPERTIES

Physical State:	Solid
Color:	Various
Odor:	Mild earthy
pH:	8-10
Specific Gravity @ 20 C (Water=1):	2.6
Density @ 20 C (lbs./gallon):	62
Bulk Density @ 20 C (lbs/ft3):	63- 73
Boiling Point/Range (F):	Not Determined
Boiling Point/Range (C):	Not Determined
Freezing Point/Range (F):	Not Determined
Freezing Point/Range (C):	Not Determined
Vapor Pressure @ 20 C (mmHg):	Not Determined
Vapor Density (Air=1):	Not Determined
Percent Volatiles:	Not Determined
Evaporation Rate (Butyl Acetate=1):	Not Determined
Solubility in Water (g/100ml):	Insoluble
Solubility in Solvents (g/100ml):	Not Determined

9. PHYSICAL AND CHEMICAL PROPERTIES

VOCs (lbs./gallon):	Not Determined
Viscosity, Dynamic @ 20 C (centipoise):	Not Determined
Viscosity, Kinematic @ 20 C (centistrokes):	Not Determined
Partition Coefficient/n-Octanol/Water:	Not Determined
Molecular Weight (g/mole):	Not Determined

10. STABILITY AND REACTIVITY

Stability Data:	Stable
Hazardous Polymerization:	Will Not Occur
Conditions to Avoid	None anticipated
Incompatibility (Materials to Avoid)	Hydrofluoric acid.
Hazardous Decomposition Products	Amorphous silica may transform at elevated temperatures to tridymite (870 C) or cristobalite (1470 C).
Additional Guidelines	Not Applicable

11. TOXICOLOGICAL INFORMATION

Principle Route of Exposure	Eye or skin contact, inhalation.
Inhalation	Inhaled crystalline silica in the form of quartz or cristobalite from occupational sources is carcinogenic to humans (IARC, Group 1). There is sufficient evidence in experimental animals for the carcinogenicity of tridymite (IARC, Group 2A). Breathing silica dust may cause irritation of the nose, throat, and respiratory passages. Breathing silica dust may not cause noticeable injury or illness even though permanent lung damage may be occurring. Inhalation of dust may also have serious chronic health effects (See "Chronic Effects/Carcinogenicity" subsection below).
Skin Contact	May cause mechanical skin irritation.
Eye Contact	May cause eye irritation.
Ingestion	None known
Aggravated Medical Conditions	Individuals with respiratory disease, including but not limited to asthma and bronchitis, or subject to eye irritation, should not be exposed to quartz dust.

Chronic Effects/Carcinogenicity

Silicosis: Excessive inhalation of respirable crystalline silica dust may cause a progressive, disabling, and sometimes-fatal lung disease called silicosis. Symptoms include cough, shortness of breath, wheezing, non-specific chest illness, and reduced pulmonary function. This disease is exacerbated by smoking. Individuals with silicosis are predisposed to develop tuberculosis.

Cancer Status: The International Agency for Research on Cancer (IARC) has determined that crystalline silica inhaled in the form of quartz or cristobalite from occupational sources can cause lung cancer in humans (Group 1 - carcinogenic to humans) and has determined that there is sufficient evidence in experimental animals for the carcinogenicity of tridymite (Group 2A - possible carcinogen to humans). Refer to IARC Monograph 68, Silica, Some Silicates and Organic Fibres (June 1997) in conjunction with the use of these minerals. The National Toxicology Program classifies respirable crystalline silica as "Known to be a human carcinogen". Refer to the 9th Report on Carcinogens (2000). The American Conference of Governmental Industrial Hygienists (ACGIH) classifies crystalline silica, quartz, as a suspected human carcinogen (A2).

There is some evidence that breathing respirable crystalline silica or the disease silicosis is associated with an increased incidence of significant disease endpoints such as scleroderma (an immune system disorder manifested by scarring of the lungs, skin, and other internal organs) and kidney disease.

Other Information

For further information consult "Adverse Effects of Crystalline Silica Exposure" published by the American Thoracic Society Medical Section of the American Lung Association, American Journal of Respiratory and Critical Care Medicine, Volume 155, pages 761-768 (1997).

Toxicity Tests

Oral Toxicity:	Not determined
Dermal Toxicity:	Not determined
Inhalation Toxicity:	Not determined
Primary Irritation Effect:	Not determined
Carcinogenicity	Refer to IARC Monograph 68, Silica, Some Silicates and Organic Fibres (June 1997).
Genotoxicity:	Not determined
Reproductive / Developmental Toxicity:	Not determined

12. ECOLOGICAL INFORMATION

Mobility (Water/Soil/Air) Not determined

Persistence/Degradability Not determined

Bio-accumulation Not Determined

Ecotoxicological Information

Acute Fish Toxicity: TLM96: 10000 ppm (Oncorhynchus mykiss)
Acute Crustaceans Toxicity: Not determined

Acute Algae Toxicity:	Not determined
Chemical Fate Information	Not determined
Other Information	Not applicable

13. DISPOSAL CONSIDERATIONS

Disposal Method	If practical, recover and reclaim, recycle, or reuse by the guidelines of an approved local reuse program. Should contaminated product become a waste, dispose of in a licensed industrial landfill according to federal, state, and local regulations.
Contaminated Packaging	Follow all applicable national or local regulations.

14. TRANSPORT INFORMATION

Land Transportation

DOT
Not restricted

Canadian TDG
Not restricted

ADR
Not restricted

Air Transportation

ICAO/IATA
Not restricted

Sea Transportation

IMDG
Not restricted

Other Shipping Information

Labels: None

15. REGULATORY INFORMATION

US Regulations

US TSCA Inventory	All components listed on inventory or are exempt.
EPA SARA Title III Extremely Hazardous Substances	Not applicable
EPA SARA (311,312) Hazard Class	Acute Health Hazard Chronic Health Hazard
EPA SARA (313) Chemicals	This product does not contain a toxic chemical for routine annual "Toxic Chemical Release Reporting" under Section 313 (40 CFR 372).

EPA CERCLA/Superfund Reportable Spill Quantity	Not applicable.
EPA RCRA Hazardous Waste Classification	If product becomes a waste, it does NOT meet the criteria of a hazardous waste as defined by the US EPA.
California Proposition 65	The California Proposition 65 regulations apply to this product.
MA Right-to-Know Law	One or more components listed.
NJ Right-to-Know Law	One or more components listed.
PA Right-to-Know Law	One or more components listed.

Canadian Regulations

Canadian DSL Inventory	All components listed on inventory.
WHMIS Hazard Class	D2A Very Toxic Materials Crystalline silica

16. OTHER INFORMATION

The following sections have been revised since the last issue of this MSDS
Not applicable

Additional Information	For additional information on the use of this product, contact your local Halliburton representative. For questions about the Material Safety Data Sheet for this or other Halliburton products, contact Chemical Compliance at 1-580-251-4335.
Disclaimer Statement	This information is furnished without warranty, expressed or implied, as to accuracy or completeness. The information is obtained from various sources including the manufacturer and other third party sources. The information may not be valid under all conditions nor if this material is used in combination with other materials or in any process. Final determination of suitability of any material is the sole responsibility of the user.

*****END OF MSDS*****

6-23-2011

NEW MEXICO
ENVIRONMENT DEPARTMENT

Resource Protection Division

Harold Runnels Building
1190 Saint Francis Drive (87505)
P.O. Box 5469, Santa Fe, NM 87502-5469
Phone (505) 827-2855 Fax (505) 827-0310
www.nmenv.state.nm.us

SUSANA MARTINEZ
Governor
JOHN A. SANCHEZ
Lieutenant Governor

CERTIFIED MAIL-RETURN RECEIPT REQUESTED

June 23, 2011

J. Steven Raugust, PG
New Mexico Copper Corporation
2425 San Pedro Drive NE, Suite 100
Albuquerque, NM 87110

RE: Request for Additional Information: Site-Wide Stage 1 Abatement Plan Proposal for the Copper Flat Mine Facility

Dear Mr. Raugust:

The New Mexico Environment Department (NMED) has reviewed the "Stage 1 Abatement Plan for the Copper Flat Mine" proposal (Proposal), dated March 31, 2011 for the Copper Flat Mine Facility. Pursuant to Section 20.6.2.4109 NMAC of the New Mexico Water Quality Control Commission (WQCC) Regulations, NMED requests additional information be submitted to facilitate final review and approval of the Proposal.

Specific Comments

1. Section 2.3.2.1 (Crystalline Bedrock Aquifer Characteristics) states that the pre-mining **ground elevation** was reported by the BLM in 1999 as ranging from 5,500 to 5,540 ft amsl. It then states that the "pit lake elevation was 5,444 ft amsl in January 2010, revealing that the pit lake elevation remains below the pre-mining **water level elevation** of 5,500 to 5,540 ft amsl." These statements appear to be contradictory and must be clarified. It should also be noted that providing a 60 ft range in water elevation without specific reference to well(s) or data point locations makes interpretation such as this speculative.

2. Section 2 provides a "Site" description, including climate, geologic conditions, and hydrologic conditions. Many conflicting and or generalized comments are present throughout this section. In particular, it is unclear what is defined as the "Site". Based on Figure 1-1, the Site appears to include only the proposed permit area, although following statements such as "The Rio Grande is a significant water resource at the Site," and "The uppermost aquifer at the Site is the Quaternary alluvial aquifer along Las Animas and Percha

Creeks," on page 4 lend confusion. Although regional characterization is important, the Proposal must be refined and clarified to eliminate confusion regarding the area of investigation and concern.

3. Section 2.3 discusses the hydrologic conditions at the Site. Several figures are referenced to illustrate various components of the geologic and hydrologic systems present. Section 2.3.1 states that three aquifers exist in the Site area and that they are shown schematically on Figure 2-4. However, only two aquifers are evident on Figure 2-4, and apparently only one within the mine area although the location of the surface facilities is not shown and the large scale makes interpretation difficult. It is stated that Figure 2-5 is indicative of ground water elevations at the site, although Figure 2-5 and the text fail to indicate which of the three aquifers is represented in this diagram. A similar lack of clarity is provided in Figure 2-6, which is described as representative of the ground water gradient in andesitic rocks. This map shows ground water contours to the east beyond the Tailing Impoundment, yet it is unclear if the andesitic rocks extend this far to the east. Is the crystalline bedrock aquifer coincident with, or in communication with, the Santa Fe Group aquifer? Figure 2-7 is cited as a demonstration of a ground water gradient toward the Pit Lake, however this generalized schematic provides no numerical scale or data supporting the assumption. Although the scale of Figure 2-9 provides a detailed representation of the upper subsurface geology beneath the eastern end of the Tailing Impoundment, it fails to show relevant monitoring wells and screened intervals and which aquifers are present. Clarification of these issues must be provided.

   In addition, Section 4.3 references Figures 4-3, 4-4, and 4-5 as representing ground water wells within the crystalline bedrock aquifer, the Quaternary alluvial aquifer, and the Santa Fe Group aquifer systems. While these figures display the location of existing ground water monitoring wells, no information is given regarding within which aquifer each well is completed.

   NMED requests that NMCC provide cross sections, potentiometric surface maps and ground water monitoring well location maps that clearly show the depth and extent of the various aquifers at the site, the location of surface facilities (Open Pit, Waste Rock Piles, Tailing Impoundment, etc.) geologic units, and the location of pertinent monitoring wells and their screened intervals. Cross sections should be orientated in both north-south and east-west directions. New figures must be provided at a scale that allows for detailed evaluation and interpretation of the existing conditions at the Site, including the limits of known ground water impacts.

4. Section 3.2.1.1 (Streams) lists several sources of surface water data for the area. Data are available from the NMED Surface Water Quality Bureau (SWQB) for Las Animas Creek and Percha Creek, and these data must be incorporated into the "Stage 1 Abatement Investigation Report." Contact James Hogan of the SWQB at (505) 476-3671 to obtain this information.

5. Section 4.1 (Surface Water Monitoring) provides the plans for operation of the automated flow and sampling systems. Transducers are proposed to be programmed to take measurements every 30 minutes and activate the samplers accordingly. Runoff events in this

area are extremely flashy, with short-term peak flows that may last only a matter of hours, depending on patterns and amount of precipitation. Transducer measuring intervals should be reduced to 15 minutes in order to assure the capture of the rising leg and peak of an abrupt precipitation event.

6. Section 4.2 (Pit Lake Characterization) provides a plan for determining whether the Pit Lake is thermally or chemically stratified. The plan proposes to collect up to 3 samples, but then to submit a composite sample of varying depths for analysis. The proposal must provide for submittal of a composite sample for analysis in addition to each of the 3 individual samples when a thermocline is present in the Pit Lake.

7. Section 5.1.2 (Ground Water Impacts in the Tailing Dam Area) proposes one additional well pair to better characterize the lateral extent of the tailing seepage. NMED withholds approval of this well pair location pending review of the detailed figures requested in Specific Comment 3 above. Additional wells may be necessary to fully determine the nature and extent of ground water contamination at the Site.

8. Section 5.3.7 (Fate and Transport Modeling) discusses expansion of the waste rock facilities and proposes modeling efforts to determine the potential for impacts from existing and future waste rock facilities. Additional wells will be necessary to monitor for impacts to water quality from the waste rock facilities. NMED understands that NMCC will conduct exploratory drilling in the area of the existing and proposed waste rock facilities and may convert some of these bore holes into monitoring wells. NMCC should consult with NMED regarding the depth, location and construction of monitoring wells.

   NMCC should be aware that, pending analysis of the ongoing waste rock characterization, liners may be required for new waste rock facilities to prevent leachate from entering the underlying vadose zone. The section makes the comparison between water in the Pit Lake and potential waste rock leachate. These conclusions should be withheld until after completion of waste rock characterization and analysis of those data.

NMED requests that NMCC respond to these Specific Comments within 30 days of the date of this letter. NMED requests that a meeting be arranged at your earliest convenience to discuss these comments. If you have any questions, please contact Greg Huey at (505) 827-1046, or Kurt Vollbrecht at (505) 827-0195.

Sincerely,

James H. Davis, Ph.D.
Director, Resource Protection Division

JHD:gh

cc: Mary Ann Menetrey, Program Manager, GWQB MECS
Tannis Fox, General Council, NMED OGC
Charles Thomas, Director, EMNRD Mining and Minerals Division
James Bearzi, Bureau Chief, NMED SWQB

THEMAC
RESOURCES
New Mexico Copper Corporation

RECEIVED
LAS CRUCES DISTRICT OFFICE
2010 DEC 29 PM 2:31
LAS CRUCES, NM 88005

December 29, 2010

New Mexico Copper Corporation
2425 San Pedro Dr, NE, Suite 100
Albuquerque, New Mexico 87110
(505) 382-5770

Mr. Michael Smith
Geologist
US Department of the Interior
Bureau of Land Management
Las Cruces District Office
1800 Marquess Street
Las Cruces, New Mexico 88005

Re: Submittal of the Plan of Operations for the Copper Flat Mine, Sierra County, New Mexico per 43 CFR 3809 Requirements.

Dear Mr. Smith:

New Mexico Copper Corporation (NMCC) is pleased to submit the Copper Flat Mine Plan of Operations (PoO). NMCC is proposing the re-establishment of a polymetallic mine and processing facility located near Hillsboro, New Mexico. The proposed mine would consist of an open pit mine, flotation mill, tailings impoundment, waste rock disposal areas, a low-grade ore stockpile, and ancillary facilities. NMCC is submitting this PoO per the 43 CFR 3809 requirements.

NMCC looks forward to working with the BLM to bring this facility back into production in accordance to all applicable federal and state regulations. Please contact me at 505.382.5770 or steve.raugust@themacreources.com or Mr. Barrett Sleeman, CEO of NMCC at 604.495.6723 or barrettsleeman@hotmail.com for any additional questions, comments, or concerns.

Respectfully,

J. Steven Raugust, PG
Project Manager

Cc: Barrett Sleeman, P.Eng, New Mexico Copper Corporation

THEMAC RESOURCES
New Mexico Copper Corporation

RECEIVED
LAS CRUCES DISTRICT OFFICE
2011 JUN 24 AM 11:42
LAS CRUCES, NM 88005

June 24, 2011

New Mexico Copper Corporation
2425 San Pedro Dr, NE, Suite 100
Albuquerque, New Mexico 87110
(505) 382-5770

Mr. Michael Smith
Geologist
US Department of the Interior
Bureau of Land Management
Las Cruces District Office
1800 Marquess Street
Las Cruces, New Mexico 88005

Re: Submittal of the Revised Plan of Operations for the Copper Flat Mine, Sierra County, New Mexico (BLM Reference NMNM 125986)

Dear Mr. Smith:

New Mexico Copper Corporation (NMCC) is pleased to re-submit the Copper Flat Mine Plan of Operations (MPO) originally submitted on December 29, 2010. The project has the BLM Reference Number of NMNM 125986. NMCC has developed resolutions to the BLM comments conveyed to NMCC by certified mail on February 4, 2011. These resolutions are tabulated in the Summary of NMCC Resolutions to the BLM MPO Comments dated February 4, 2011, which is attached to this cover letter NMCC is submitting this revised MPO per the 43 CFR 3809 requirements.

NMCC looks forward to working with the BLM to bring this facility back into production in accordance to all applicable federal and state regulations. Please contact myself or Mr. Ferol Baker, NMCC's General Manager at 505.382.5770 or via steve@nmcopper.com or ferol@nmcopper.com, respectively for any additional questions, comments or concerns.

Respectfully,

J. Steven Raugust, PG
Permitting Manager - Engineering

Cc: Ferol Baker, New Mexico Copper Corporation
Barrett Sleeman, P.Eng, New Mexico Copper Corporation

Summary of NMCC Resolutions to BLM MPO Comments dated February 4, 2011

#	BLM Comment	NMCC Response
1	Placer mining questions - Will any of the proposed placer mining occur on Federal land? If so, provide a detailed description of the proposed operation. Include a description of the area of placer operations, proposed depth of excavation, production and processing equipment requirements, access routes, sources of water, and duration of placer operations. Provide a map of placer activity showing locations of excavation areas, waste sediment stockpiles, processing facilities and access routes.	Proposed facility layout: Discussed in Section 3.1, illustrated in Figures 3-1 and 3-2.
2	Provide general schedule of operations - Provide additional information regarding the general schedule of operations from start to closure. Include the estimated duration of each phase of the mining operations (site preparation, production, mineral benefaction, reclamation, monitoring) during the projected 17-year mine life. At a minimum, reference Figure 5-1 in this section, the addtion of a schedule in table format would also be appropriate.	Project phases presented in Section 3.2.1, detailed schedule in Figure 5-1, additional details in section 5.6
3	Detailed mining equipment list for preliminary equipment inventory - Complete detailed list of mining equipment so a preliminary equipment inventory can be propared. Also include any necessary equipment not discussed in this section, such as dozers and road graders.	Section 3.2.1: Table 3-2 provides a list of major pieces of mining equipment
4	Waste rock disposal and low-grade stockpile: Up-date the runoff calculations to meet regulatory requirements and design criteria. Provide additional details regarding the runoff collection system (ie placement and estimated size of collection ditches, and the method by which water will be diverted into the process water system). Describe short-term (ie, not final reclamation) BMPs to minimize sediment loading from the waste-rock piles (ie, silt fencing, straw application, etc.)	Discussed in Section 3.2.1, detail provided in Appendix B
5	Specific ore processing: Specifiy the dimensions and construction of all buildings planned for the project. Specify the number and exact purpose of the ancillary buildings referred to on page 3-8 and map the locations and purposes of all buildings planned for the operation on figure 3-1.	Discussed in Section 3.2.3, Table 3-3 presents Primary Plant Site Structures and Facilities, Figure 3-2 presents buildings

#	BLM Comment	NMCC Response
6	Ore processes - in-pit crushing and conveying. Plan modifications expected as optimizations and cost refinements are completed. - When does NMCC anticipate completing the feasibility study for in-pit crushing and conveying? Can this be incorporated into the current MPO, or will a plan modification be submitted?	Primary Crushing Facilities described in section 3.2.3.1
7	Tailings impoundment - Complete determinations regarding the source of materials for the new tailings dam and whether the existing dam will remain in place	Discussion of Tailings Impoundment and impoundment design - section 3.2.3.4, 3.2.3.4.1, detail provided in Appendix D
8	Water supply. Provide the legal locations of the eight wells on BLM land proposed for use in the MPO. Also provide a map showing the location of the wells and the 20-inch pipeline (with existing valves and manholes) relative to the proposed operation.	Water supply discussed in Section 3.2.7. Table 3-6 presents Production & Monitoring Well Legal Locations
9	Water supply: complete the planned inspection of the 20 inch pipeline to assure suitability for use	Description of planned waterline testing in Section 3.2.7
10	Water supply: Provide an estimate of total water use and an inventory of projected water use by activity (ie dust suppression, milling, floatation, etc.). Include estimated volumes of make-up water from pit de-watering and thickener overflow recycling.	Table 3-5 Project Water Demand table
11	Exploration activity: Specify if exploration activities on Federal lands will be limited to the permit areas defined on Figures 2-1 and 3-1. If exploratory drilling is planned on Federal surface or mineral estate outside of this boundary, specify the locations of the proposed drillholes and access routes.	Description in Section 3.3, Illustration in Figures 2-2 and 3-1.
12	Invasive species - Provide details on noxious week prevention and monitoring programs. Include information on BMPs to minimize noxious weed infestation, monitoring strategies, mitigation measures if an on-site infestation is detected.	Discussed in 3.4.9
13	Reagents. Specify the planned retaining volume of the berm for the No.1 diesel fuel tank and map the location of reagent mixing and storage area. Describe the construction of the reagent mixing and storage area including the construction of the flooring. Provide details on the plastic liners (composition & thickness) and proposed depth of gravel cover for the fuel tank linings.	Discussed in 3.4.10.2, Table 3-7 presents Copper Flat Project Materials Management
14	Hazardous materials management - Specify the volumes of diesel fuel and ammonia nitrate that will be stored on site, and the number of bins, tanks, and explosive sheds that will be placed on BLM land. Map the locations of these storage facilities.	Diesel volume discussed in section 3.4.10.2, Explosives discussed in section 3.4.10.3, map with location of storage facilities is Figure 3-1

#	BLM Comment	NMCC Response
15	Reclamation: Finalize designs for the proposed waste rock facilities so BLM engineers may evaluate your proposal.	Discussed in Section 5.9.1, Table 5-1 presents Waste rock disposal facility design parameters, Appendix D provides additional detail
16	Reclamation: Complete evaluations of tailings impoundment area to determine if the gravels and allluvial fill will be used for reclamation, impoundment construction, and/or placer operations. If material from the impoundment area will be used for reclamation on Federal lands, describe BMPs to minimize invasive or noxious weed contamination or possible transfer of hazardous materials or contaminated soils to Federal lands.	Discussed in section 5.9.1, Additional detail Appendix D
17	Reclamation: Any natural soil amendments used will have to be certified free of invasive and noxious weeds.	Affirmed, section 5.9.3
18	Reclamation: Proposed seed mix is being evaluated by BLM wildlife and range staff and may be modified if necessary.	Affirmed, section 5.10.1
19	Reclamation:Interim reclamation - Buildings, is this a proposal to maintain an on-site resident security guard during interrruptions in operations?	Affirmed, section 5.14
20	Reclamation: The reference "SRK 1995" is not listed in the bibliography, are you referring to the "Copper Flat Mine Hydrogeologic Studies" report of May 1995? This report does not make a convincing argument that the pit lake level will be below hydrostatic.	Bibliography corrected, pit lake level discussed in Section 5.7.4
21	Plant site: Why is it necessary to leave foundations and footing buried on the public land? What would be the total volume of concrete left on site after operations are completed?	NMCC has agreed to break, excavate, and remove concrete foundations from public land, Section 5.16.3
22	Reclamation: Figure 5-3 need to be included	The correct figure is now included, now Figure 3-6, discussed in section 5.16.5.3
23	Estimated reclamation costs - Reclamation bonding will likely be deferred to the NM MMD	Affirmed, section 5.17

THEMAC RESOURCES

New Mexico Copper Corporation

Copper Flat Mine
Plan of Operations

Report Prepared for:

U.S. Department of the Interior
Bureau of Land Management
Las Cruces District Office
1800 Marquess Street
Las Cruces, NM 88005-3370

Report Submitted by:

NEW MEXICO COPPER CORPORATION
2425 San Pedro Dr. Suite 100
Albuquerque, NM 87110
Office: (505) 382-5770

December 2010
Revised June 2011

01745

Table of Contents

1 Project Summary 1-1
1.1 Introduction 1-1
1.2 Project Location 1-1
1.3 Project Background 1-1

2 Corporate Information 2-1
2.1 Corporation Information 2-1
2.2 Registered Agent 2-2
2.3 List of BLM Claims and Serial Numbers 2-2
2.4 Land Status 2-2
2.5 Permits and Approvals 2-4
2.5.1 Federal Permits, Approvals and Consultations 2-4
2.5.2 State Permit and Approvals 2-4

3 Proposed Operating Plan 3-1
3.1 Introduction 3-1
3.2 Proposed Plan 3-2
3.2.1 Open Pit 3-2
3.2.2 Waste Rock Disposal Area and Low-Grade Stockpile 3-6
3.2.3 Ore Processing 3-7
3.2.4 Haul Roads and On-Site Service Roads 3-14
3.2.5 Project Work Force and Schedule 3-14
3.2.6 Electrical Power 3-14
3.2.7 Water Supply 3-15
3.2.8 Fencing and Exclusionary Devices 3-18
3.2.9 Growth Media 3-19
3.2.10 Borrow Areas 3-19
3.2.11 Ancillary Facilities 3-19
3.2.12 Inter-Facility Disturbance 3-20
3.2.13 Transportation 3-20
3.3 Exploration Activities 3-21
3.4 Applicant Committed Environmental Protection Measures and Committed Practices 3-21
3.4.1 Air Quality 3-22
3.4.2 Water Resources 3-23
3.4.3 Erosion and Sediment Control 3-23
3.4.4 Wildlife 3-23
3.4.5 Cultural Resources 3-24
3.4.6 Protection of Survey Monuments 3-24
3.4.7 Health and Safety and Emergency Response 3-24
3.4.8 Fire Protection 3-25
3.4.9 Invasive, Non-native Species 3-25
3.4.10 Materials and Waste Management 3-26
3.4.11 Spill Contingency 3-31
3.4.12 Monitoring 3-31
3.4.13 Technical Updates 3-31
3.4.14 Growth Media/Cover Salvage and Storage 3-32
3.4.15 Sustainability 3-32
3.5 Operating Plans 3-32

4 Environmental Setting 4-1
4.1 Introduction 4-1
4.2 Geology 4-1

4.2.1 Regional Geologic Setting 4-1
4.2.2 Geology of Copper Flat Mine Site 4-2
4.2.3 Description of the Ore Body 4-4
4.3 Climate 4-6
4.4 Hydrology 4-7
4.4.1 Surface Water 4-7
4.4.2 Groundwater 4-12
4.5 Soils 4-19
4.6 Vegetation 4-20
4.6.1 Chihuahuan Desert Scrub (or Creosote Bush) Community 4-21
4.6.2 Desert Grassland 4-21
4.6.3 Pinion-Juniper Community 4-21
4.6.4 Aquatic Vegetation 4-21
4.6.5 Vegetative Productivity 4-22
4.7 Wildlife 4-23
4.7.1 Mammals 4-23
4.7.2 Birds 4-23
4.7.3 Reptiles 4-23
4.7.4 Invertebrates 4-24
4.7.5 Fisheries 4-24
4.8 Threatened, Endangered, or Candidate Species 4-24
4.8.1 Vegetation 4-24
4.8.2 Wildlife 4-24
4.9 Range Resources 4-26
4.10 Air Quality 4-26
4.11 Cultural Resources 4-26

5 Reclamation and Closure 5-1
5.1 Introduction 5-1
5.2 Statutory and Regulatory Requirements 5-1
5.3 Post-Mining Land Use 5-1
5.4 Summary of Disturbance 5-2
5.5 Reclamation Plan 5-2
5.6 Implementation 5-3
5.7 Environmental Considerations for Reclamation 5-4
5.7.1 Signs, Markers and Safeguarding 5-4
5.7.2 Wildlife and Domestic Animal Protection 5-4
5.7.3 Cultural Resources 5-5
5.7.4 Hydrologic Balance 5-5
5.7.5 Impoundments 5-7
5.7.6 Prevention of Mass Movement 5-7
5.7.7 Riparian Areas 5-7
5.7.8 Roads 5-8
5.7.9 Surface Facilities or Roads Not Subject to Reclamation 5-8
5.7.10 Drill Hole Plugging and Water Well Abandonment 5-8
5.7.11 Post-Closure Monitoring 5-8
5.8 Site Stabilization and Configuration 5-9
5.9 Plant Growth Media and Cover Materials 5-9
5.9.1 Removal and Storage 5-9
5.9.2 Placement 5-12
5.9.3 Amendments 5-12
5.10 Revegetation 5-13
5.10.1 Seed Mixtures 5-13
5.10.2 Planting Techniques 5-14
5.11 Revegetation Success 5-15
5.12 Reclamation Research 5-16

5.13 Concurrent Reclamation....5-16
5.14 Interim Reclamation....5-16
5.15 Interim Management Plan....5-17
5.15.1 Schedule of Anticipated Periods of Temporary Closure....5-18
5.15.2 Measures to Stabilize Excavations and Workings....5-18
5.15.3 Measures to Isolate or Control Toxic or Deleterious Materials....5-18
5.15.4 Storage or Removal of Equipment, Supplies, and Structures....5-19
5.15.5 Monitoring During Periods of Non-Operation....5-19
5.16 Facility-Specific Reclamation....5-19
5.16.1 Mine Pit....5-19
5.16.2 Waste Rock Disposal Areas and Low-Grade Stockpile....5-20
5.16.3 Plant Site....5-22
5.16.4 Tailings Impoundment....5-23
5.16.5 Ancillary Project Facilities....5-24
5.17 Estimated Reclamation Costs....5-25
6 Acknowledgment....6-1
7 Bibliography....7-1

List of Tables

Table 2-1: Legal Description of Proposed Project Area....2-2
Table 2-2: Summary of Proposed Disturbance....2-3
Table 2-3: Major Permits and Approvals Required....2-5
Table 3-1: Summary of NMCC Proposed Disturbance within the Plan Boundary....3-2
Table 3-2: Major Pieces of Mining Equipment....3-5
Table 3-3: Primary Plant Site Structures and Facilities....3-8
Table 3-4: Summary of Project Electrical Demand....3-15
Table 3-5: Project Water Demand....3-15
Table 3-6: Production and Monitoring Well Legal Locations....3-16
Table 3-7: Copper Flat Project Materials Management....3-28
Table 5-1: Estimated Available Topsoil from Newly Disturbed Areas....5-10
Table 5-2: Estimated Reclamation Cover Requirements....5-11
Table 5-3: Proposed Reclamation Seed Mixes....5-14

List of Figures

(Located at back of document)

Figure 1-1: Project Location Map
Figure 1-2: Regional Location
Figure 2-1: Local Area Layout
Figure 2-2: Land Status and Existing Disturbance
Figure 3-1: Proposed Facility Layout
Figure 3-2: Proposed Plant Site Layout
Figure 3-3: Proposed Facility Topography
Figure 3-4: Open Pit Cross-section
Figure 3-5: Proposed Process Circuit
Figure 3-6: Typical Road Configuration and Reclamation
Figure 4-1: Regional Surface Geology
Figure 4-2: Schematic Geologic Cross Section (A-A')
Figure 4-3: Geologic Structural Features of the Region
Figure 4-4: Geologic Schematic of the Hillsboro Mining District, New Mexico
Figure 4-5: Proposed Surface Water Sampling Locations
Figure 4-6: Proposed Parallel Profiles for Pit Lake Survey
Figure 4-7: Lower Rio Grande Basin
Figure 4-8: Conceptual Model of Groundwater Flow System
Figure 4-9: Spring and Stream Locations
Figure 4-10: Water Level Contours
Figure 4-11: Water Level Map of Copper Flat Pit Area
Figure 4-12: Conceptual Model of Pit Lake Monitoring Well Relationship with Water Quality Reports
Figure 4-13: Conceptual Design, Tailings Seepage Control
Figure 4-14 Regional Groundwater Well Locations
Figure 4-15 Proposed Monitoring Well Program
Figure 5-1: Proposed Project Schedule
Figure 5-2: Post-Reclamation Topography

List of Appendices

(Located at back of document)

APPENDIX A: Claims List
APPENDIX B: Preliminary Design Report: Copper Flat Waste Rock Disposal Facilities
APPENDIX C: Mine Waste Management Plan
APPENDIX D: Tailings Impoundment Conceptual Design Report (Golder, 2010), incl. Borrow Sources and Stockpile Evaluations
APPENDIX E: Preliminary Spill Contingency Plan
APPENDIX F: Quality Assurance Plan (Intera, 2010)

List of Acronyms

amsl	above mean sea level
ARD	acid rock drainage
AWRM	Active Water Resource Management
BATF	Bureau of Alcohol, Tobacco, and Firearms
bgs	below ground surface
BLM	Bureau of Land Management
BMP	Best Management Practice
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
CFQM	Copper Flat Quartz Monzonite
cfs	cubic feet per second
CO	carbon monoxide
DEIS	Draft Environmental Impact Statement
EA	Environmental Assessment
EAR	Environmental Assessment Report
EIS	Environmental Impact Statement
EMNRD	Energy, Minerals and Natural Resources Department
EPA	U.S. Environmental Protection Agency
ESA	Endangered Species Act
°F	degrees Fahrenheit
FCC	Federal Communications Commission
FEIS	Final Environmental Impact Statement
FLPMA	Federal Land Policy Management Act
ft	feet
gpm	gallons per minute
GWQB	Ground Water Quality Bureau
HSR	Human Systems Research
HSUs	hydrostratigraphic units
IHICS	Integrated Habitat Inventory Classification System
km	kilometers
kWh	kilowatt hours
LRGB	Lower Rio Grande Underground Water Basin
Ma	million years ago
mg/L	milligrams per liter
MMD	Mining and Mineral Division
MSDS	Material Safety Data Sheets
MSF	Middle Santa Fe Group hydrostratigraphic unit
MSHA	Mining Safety and Health Administration
NEPA	National Environmental Policy Act
NMCC	New Mexico Copper Corporation
NMED	New Mexico Environment Department
NMEMNRD	New Mexico Energy, Mineral and Natural Resources Department
NPDES	National Pollution Discharge Elimination System
NRC	National Response Center
NRHP	National Register of Historic Places
O&M	Operation & maintenance
OSE	Office of the State Engineer
PFEIS	Preliminary Final Environmental Impact Statement
PLS	pure live seed
PMP	probable maximum precipitation
MPO	Mine Plan of Operations

ppm	parts per million
RCRA	Resource Conservation and Recovery Act
RMP	Resource Management Plan
ROD	Record of Decision
ROW	rights-of-way
SAG	semi-autogenous
SARA	Superfund Amendments and Reauthorization Act
SCP	Spill Contingency Plan
SCS	Soil Conservation Service
SHPO	State Historic Preservation Office
SMIO	State Mine Inspector's Office
TDS	Total dissolved solids
tpd	tons per day
TPQ	Threshold Planning Quantity
TSF	tailings storage facility
TSP	Total Suspended Particulates
USACE	U.S. Army Corp of Engineers
USF	Upper Santa Fe Group hydrostratigraphic unit
USFS	U.S. Department of Agriculture, Forest Service
USFWS	U.S. Fish and Wildlife Service
WQCC	New Mexico Water Quality Control Commission

1 Project Summary

1.1 Introduction

The Copper Flat Project (Project) is the proposed re-establishment of a poly-metallic mine and processing facility located near Hillsboro, New Mexico. The proposed Project would consist of an open pit mine, flotation mill, tailings impoundment, waste rock disposal areas, a low-grade ore stockpile, and ancillary facilities. In most respects, the facilities, disturbance and operations would be similar to the former operation.

The Project is owned and operated by the New Mexico Copper Corporation (NMCC), a wholly owned subsidiary of THEMAC Resources Group Limited (THEMAC), information for which is provided in Section 2.

1.2 Project Location

The Project is located in Sierra County, New Mexico, approximately 30 miles southwest of Truth or Consequences and five miles northeast of Hillsboro (**Figure 1-1**). The general area can be reached by traveling south 15 miles from Truth or Consequences on Interstate Highway 25, then 12 miles west on New Mexico Highway 152. The Project area lies two miles west-northwest from Highway 152. The regional location of the Project is shown on **Figure 1-2**.

1.3 Project Background

Development of the Copper Flat Project began in the 1970's by Quintana Mineral Corporation. An Environmental Assessment Report (EAR) was prepared for the Project in 1977 (Glover, 1977). The U.S. Department of the Interior, Bureau of Land Management, Las Cruces District Office (BLM) prepared an Environmental Assessment Record to analyze potential impacts resulting from granting rights-of-way (ROW) for utilities and access roads, as well as impacts resulting from the mining Project (BLM, 1978). The ROWs were approved by the BLM in the Environmental Assessment Record and air quality, tailings discharge, and water discharge permits were issued by the State of New Mexico. The air permit was closed in 2002 due to inactivity, and while the groundwater discharge permit remains open, it cannot be renewed until a Stage 1 Abatement Plan for a small groundwater impact associated with the existing tailings impoundment has been approved by the New Mexico Environment Department (NMED) Ground Water Quality Bureau (GWQB). The New Mexico Energy Minerals and Natural Resources Department (EMNRD), Mining and Mineral Division (MMD) mining permit has also expired.

In 1982, the Copper Flat Partnership, Ltd. developed and operated the Project, which consisted of an open pit copper mine, a 15,000-ton per day flotation mill, and a 515-acre tailings impoundment. The Copper Flat mine officially commenced full commercial production in April, 1982. In July 1982 the mine was shut down due to low copper prices and other economic considerations. In 1986 all on-site

surface facilities were removed and a BLM approved program of non-destructive reclamation was carried out. Most of the property's infrastructure, including building foundations, power lines and water pipelines were preserved for reuse in the future in the event copper prices recovered sufficiently to make re-establishing the Project economically viable.

In 1991, a proposed Plan of Operations was filed with the BLM by Gold Express Corporation to re-establish the Copper Flat Project. The BLM initiated an Environmental Assessment (EA) because federal land would be "newly" disturbed. New archaeological, biological, threatened and endangered species, air quality, hydrologic and socioeconomic studies were conducted. However, it was determined in 1993 that an Environmental Impact Statement (EIS) would be required for the Project due to concerns related to several water quality issues, and the EA was never completed.

Alta Gold Company (Alta) acquired the Project in early 1994 and proposed to rebuild the Copper Flat mining facility essentially as it existed in 1982. Alta submitted an updated Mine Plan of Operations (MPO) and associated environmental baseline data to the BLM for initiation of the EIS process. The *Draft Environmental Impact Statement – Copper Flat Project* (DEIS) was completed by the BLM in 1996. A *Preliminary Final Environmental Impact Statement – Copper Flat Project* (PFEIS) was prepared by the BLM in 1999 following public comment on the DEIS. However, the EIS and Record of Decision (ROD) were never finalized due to Alta's declaration of bankruptcy in early 1999.

2 Corporate Information

New Mexico Copper Corporation owns and controls the entire interest in the proposed Copper Flat Project. NMCC contact information is:

New Mexico Copper Corporation
2425 San Pedro, NE, Suite 100
Albuquerque, New Mexico 87110
505.382.5770

THEMAC Resources Group Limited (THEMAC), a Yukon corporation, owns and controls all of the shares of NMCC. THEMAC's contact information is:

THEMAC Resources Group, Ltd.
1066 West Hastings Street, Suite 2000
Vancouver, British Columbia
Canada, V6E 3X2
604.806.6110

Name & Business Address of Individual Completing Application

Name:	Barrett G. Sleeman
Title:	Chief Executive Officer and President
Business Name:	New Mexico Copper Corporation
Business Address:	2425 San Pedro, NE, Suite 100 Albuquerque, New Mexico 87110
Telephone Number:	505.382.5770
e-mail:	barrett@nmcopper.com

2.1 Corporation Information

Corporation Name:

New Mexico Copper Corporation
2425 San Pedro, NE, Suite 100
Albuquerque, New Mexico 87110
505.382.5770

Corporation Officer's Information:

Chief Executive Officer:	Barrett G. Sleeman
Chief Financial Officer:	Steve Vanry
Secretary:	J. Stephen Law and Salvador Miranda

Federal Taxpayer ID Number: 80-0612011

2.2 Registered Agent

Registered Resident Agent:

Name:	Mark K. Adams
Business Address:	315 Paseo de Peralta Santa Fe, New Mexico 87501
Telephone Number:	505.954.3902
e-mail:	madams@rodey.com

2.3 List of BLM Claims and Serial Numbers

Proposed mining and related surface disturbance would be conducted on unpatented lode, placer, and mill-site claims owned or controlled by NMCC on BLM-administered lands or on private land controlled by NMCC. Claim names and BLM serial numbers are provided in **Appendix A**.

There are no state lands or U.S. Department of Agriculture, Forest Service (USFS) lands located within the MPO boundary. **Table 2-1** presents the legal description of the project, including the water supply wells and pipeline corridor.

Table 2-1: Legal Description of Proposed Project Area

Township	Range	Sections
15 South	7 West	25,26,27, 35, & 36
15 South	6 West	25, 26, 27, 30, 31, 32, 33, & 34
15 South	5 West	30 & 31
16 South	6 West	6

Note: Project Area includes production water wells and pipeline corridor in addition to mine property boundary.

2.4 Land Status

The Copper Flat Project is comprised of contiguous and noncontiguous lands that include patented and unpatented mining claims (lode, placer, and mill site), and private parcels. In addition, a right-of-way to the east of the mine site is being established for the conveyance of water from the NMCC production wells to the mine site (**Figure 2-1**). The area inside the proposed MPO boundary is 2,190 acres. Activity at the Copper Flat Mine in 1982 disturbed approximately 361 acres of BLM-administered public lands and 549 acres of private lands.

The re-establishment of the Copper Flat Mine would affect nearly 1,586 acres, 910 acres of which have been previously disturbed and 676 acres which would be newly disturbed land (**Table 2-2**). Overall, the Copper Flat Project would disturb approximately 745 acres of unpatented mining claims on public land and 841 acres of private land controlled by NMCC (**Figure 2-2**). Approximately 57 percent of the area needed for the proposed MPO has been disturbed by prior operations, and approximately 90 percent of the ore would be mined from private land.

Table 2-2: Summary of Proposed Disturbance

Facility[1]	Existing Disturbance			Proposed Incremental Disturbance			Total Disturbance		
	Public	Private	Total	Public	Private	Total	Public	Private	Total
Roads									
Access Road	1	1	2	6	3	9	7	4	11
Haul Roads	5	16	21	4	22	26	9	38	47
Total Roads	**6**	**17**	**23**	**10**	**25**	**35**	**16**	**42**	**58**
Pits, Adits, Trenches									
Pits	11	91	102	1	16	17	12	107	119
Total Pits, Adits, Trenches	**11**	**91**	**102**	**1**	**16**	**17**	**12**	**107**	**119**
Tails									
Tailings Facility	131	341	472	22	53	75	153	394	547
Total Tails	**131**	**341**	**472**	**22**	**53**	**75**	**153**	**394**	**547**
Process Ponds									
Ponds	5	1	6	1	13	14	6	14	20
Total Ponds	**5**	**1**	**6**	**1**	**13**	**14**	**6**	**14**	**20**
Waste Rock Facilities									
Waste Rock Facilities	32	1	33	128	49	177	160	50	210
Total Waste Rock Facilities	**32**	**1**	**33**	**128**	**49**	**177**	**160**	**50**	**210**
Ancillary Facilities									
Misc.	122	78	200	47	70	117	169	148	317
Diversions	25	12	37	8	3	11	33	15	48
Topsoil Stockpiles	1	7	8	26	37	63	27	44	71
Stockpiles (Low-grade Ore)	21	1	22	45	2	47	66	3	69
Building Areas[2]	7	0	7	76	4	80	83	4	87
Total Yards	**176**	**98**	**274**	**202**	**116**	**318**	**378**	**214**	**592**
Exploration									
Roads, Trenches, Drill Pads, etc.	0	0	0	20	20	40	20	20	40
Total Exploration	**0**	**0**	**0**	**20**	**20**	**40**	**20**	**20**	**40**
Total	**361**	**549**	**910**	**384**	**292**	**676**	**745**	**841**	**1586**

Notes:

1. All acres are rounded up to the nearest 1 acre.

2. Mill plant sites, substation, reagent building, primary crusher, process water storage, concentrate storage, thickener facility, coarse ore stockpile, administration building, offices, shops, storage, assay lab, septic system.

Portions of the waste rock disposal areas, as well as the crushing facility and the mill facility, would be located on public land subject to unpatented mining claims controlled by NMCC. Approximately 28 percent of the tailings impoundment and 10 percent of the open pit would be located on public land subject to mining claims controlled by NMCC.

Approximately 49 percent of the proposed disturbance on public land was disturbed by the previous operation. On the private land, approximately 65 percent of the surface needed for the mine has been disturbed by the prior operation. The majority of the tailings storage land is privately owned and controlled by NMCC.

2.5 Permits and Approvals

2.5.1 Federal Permits, Approvals and Consultations

A National Environmental Policy Act (NEPA) review of the proposed Project was initiated in 1994 when Alta Gold notified the BLM (Las Cruces District Office) that the company had purchased the Project from Gold Express and was assuming legal responsibility for the Plan of Operations initially submitted in 1991. The BLM then began the process of preparing an EIS. The DEIS was completed in 1996, and the PFEIS was completed in 1999. However, neither a Final EIS (FEIS) nor ROD was issued for the Project as a result of Alta's bankruptcy in 1999.

. Consultation with the U.S. Fish and Wildlife Service (USFWS), in accordance Section 7 (c) of the Endangered Species Act (ESA), is required to ensure that any action authorized, funded or carried out by a federal agency would not adversely affect a federally listed threatened or endangered species.

The major federal permits and approvals required are shown in **Table 2-3**.

2.5.2 State Permit and Approvals

A number of state permits would also be required for the Project. The New Mexico Environment Department (NMED) would issue most of these permits, including air quality permits and groundwater discharge permits. Alta submitted an application for a modification to the existing groundwater Discharge Permit (DP-001) for the Project in early 1995. However, DP-001 was suspended until a Stage 1 Abatement Plan for a small groundwater impact associated with the existing tailings impoundment has been submitted and approved. In addition, an application for a revised Air Quality Permit (No. 365-M-1) was also submitted by Alta in early 1995. This permit was closed in 2002 due to inactivity.

In addition to approval by the State under the New Mexico Mining Act, NMCC would be required to secure a number of additional state and federal permits and approvals. These are also listed in **Table 2-3**.

Table 2-3: Major Permits and Approvals Required

Permit/Approval	Granting Agency
Federal	
Approval of Plan of Operations	U.S. Bureau of Land Management (BLM)
National Dredge and Fill Permit (Section 404)	U.S. Army Corp of Engineers (USACE)
FCC License	Federal Communications Commission (FCC)
MSHA Registration	Mining Safety and Health Administration (MSHA)
National Pollution Discharge Elimination System (NPDES), Including Stormwater Discharge	U.S. Environmental Protection Agency (EPA)
Explosives Permit	Bureau of Alcohol, Tobacco, and Firearms (BATF)
Endangered Species Surveys	U.S. Fish and Wildlife Service
State	
Mining Permit	New Mexico Energy, Mineral and Natural Resources Department (NMEMNRD)- Mining Act Reclamation Bureau
Mine Registration	NMEMNRD – Mine Registration Reporting, and Safeguarding Program – Mine Registration
Permit to Construct (Air Quality)	New Mexico Environment Department - Air Quality Bureau
Permit to Operate (Air Quality)	New Mexico Environment Department - Air Quality Bureau
Permit to Appropriate Water	New Mexico State Engineer's Office
Permits for Dam Construction and Operations	New Mexico State Engineer's Office
Approval to Operate a Sanitary Landfill	New Mexico Environment Department - Solid Waste Bureau
Liquid Waste System Discharge Permit	New Mexico Environment Department - Groundwater Bureau
Groundwater Discharge Permit	New Mexico Environment Department - Groundwater Bureau (DP-001)
Cultural Resources Clearance Surveys	New Mexico Department of Cultural Affairs - Historic Preservation Division
Endangered Plant Species Surveys	Natural Heritage New Mexico
Endangered Wildlife Species Surveys	New Mexico Department of Game and Fish

3 Proposed Operating Plan

3.1 Introduction

Relevant aspects of the planned operations are summarized in this section. The Proposed Action is the operation as proposed by Gold Express Corporation in 1991, adopted by Alta in 1994 (BLM, 1996), and modified and updated by NMCC in 2010. The proposed project layout is shown on **Figure 3-1**, while a detail of the plant site layout is presented in **Figure 3-2.** A topographic map of the project facilities is provided in **Figure 3-3**.

The mine design has many of the same mining plans and elements outlined by Gold Express and Alta Gold; all of these have been previously discussed in the DEIS and PFEIS that was being prepared in the late 1990s related to Alta's mine proposal—mainly focused on reactivating the mine plans and processes of Quintana of the early 1980s.

The NMCC-proposed operation includes the following activities:

- Expand the project boundary to include additional land controlled by NMCC;
- Provide for exploration over entire proposed plan area;
- Expand the existing open pit;
- Construct haul and secondary mine roads;
- Construct, operate and reclaim waste rock disposal facilities;
- Construct, operate and reclaim low-grade ore stockpiles;
- Construct, operate and reclaim the mill and associated processing facilities;
- Construct, operate and reclaim the tailings impoundment facility;
- Construct ancillary buildings (administration offices, laboratory, truck shop, reagent building, substation and gatehouse, etc.);
- Secure and construct a suitable water supply network;
- Construct growth media stockpiles; and
- Construct and maintain surface water diversions.

Table 3-1: Summary of NMCC Proposed Disturbance within the Plan Boundary

Disturbance Type	Public Lands (acres)	Private Lands (acres)	Total (acres)
Tailings Storage Facility	153	394	547
Open Pit	12	107	119
Waste Rock Disposal Facilities	160	50	210
Haul Roads	9	38	47
Access Roads	7	4	11
Stormwater Diversion Structures	33	15	48
Miscellaneous Areas[1]	351	213	564
Exploration	20	20	40
Total Disturbance	745	841	1586

Notes:
1. Includes mill areas, stockpiles and other miscellaneous disturbance areas (including inter-facility disturbance generally associated with construction activities).

3.2 Proposed Plan

3.2.1 Open Pit

The mining of new ore would entail expansion of the existing open pit. A portion of the ore body at Copper Flat is exposed at and near the surface and would be mined by conventional truck and shovel open pit methods in a manner similar to the previous operation. The open pit mine is currently proposed to operate 24 hours per day, seven days per week, 365 days per year. However, this production schedule is subject to change based on future economics of the project. Over the life of the Project, the mine would produce approximately 96 million tons of copper ore, 37 million tons of waste rock, and 19 million tons of low-grade copper ore (less than 0.20 percent copper). The low-grade copper ore would likely be processed during operations as blend material and/or at the end of the mine life, depending on economic conditions at the time. As such, it would require stockpiling until such time at it is suitable for milling and processing. The operation would process at a nominal throughput of 17,500 short tons per day of ore through the copper sulfide flotation mill using

standard technology similar to that of the previous operation. While the operation would focus primarily on copper and molybdenum, other poly-metallic resources, including gold, silver, and possible rare-earth elements, may be economically extractable from the Copper Flat ore. These options resources are currently being evaluated.

Annually, the mining operation would process an estimated 5.8 million tons of copper ore and 1.1 million tons of low-grade copper material. Waste rock production is estimated to average 2.2 million tons per year (ranging from 100,000 to 6.4 million tons annually), with tailings production estimated at 5.7 million tons annually. An operational life of approximately 17 years is currently projected.

The durations of each of the phases of the Copper Flat Project are estimated as follows:

- Pre-construction (Permitting) 2 Years
- Construction (Site preparation) 2 Years
- Operations (Mineral beneficiation) 17 Years
- Closure/Reclamation 3 Years
- Post-Closure Monitoring 12 Years

Post-closure monitoring period includes final abandonment of monitoring wells and reclamation of access roads needed for monitoring. Additional details of the project schedule are discussed in Section 5.6 and illustrated in **Figure 5-1**.

Preproduction stripping of overburden was completed in 1982 during the previous operation. Approximately 3 million tons of overburden material was stripped and over 1.2 million tons of ore were mined from the existing pit during the early 1980s. Under the NMCC proposed MPO, the Copper Flat ore body would be mined by a multiple bench, open pit method. The existing pit would eventually be enlarged to approximately 2,500 feet by 2,500 feet with an ultimate depth of approximately 900 feet. The area of the pit would be expanded from 102 acres to 119 acres. The existing diversion of Greyback Wash south of the pit would not be altered with the proposed pit expansion. The working, inter-bench slope of the pit walls would average 45 degrees, but would be optimized based on on-going evaluations of project economics and pit slope engineering. Safety benches would remain as required by regulation. A typical cross-section of the proposed open pit is provided in **Figure 3-4**. Because the deposit cannot be mined sequentially, there is no plan to backfill the pit, although some benign waste rock would be used for pad preparation, plant site development, and in connection with the reclamation of disturbed area.

Ore material from the pit would be drilled and blasted, loaded and hauled to the primary crusher either in pit or out of pit, and then conveyed to the process mill, where the mineral values would be removed by conventional flotation processes. Future work will determine the viability of belt conveyance (either surface or underground) of crushed material if in-pit crushing is chosen over out-of-pit crushing. Waste rock would be placed on the ground surface in designated disposal areas, as discussed in Section 3.2.2.

Blasting would be limited to daylight hours and performed by licensed blasters. Rotary diesel driven drills, electric powered and/or down the hole hammer drills would be used for blast hole drilling.

Wet drills, in conformance with Mining Safety and Health Administration (MSHA) requirements, would be used for secondary breakage when necessary. Safe seismic disturbance and air blast limits would be established to prevent damage to buildings.

Blasting agents would be stored in a secured area in compliance with applicable state and federal regulations. Ammonium nitrate and diesel fuel would be stored on site in bins and tanks. Detonators, detonating cord, boosters, caps and fuses would be stored apart from the batch plant area in secured separate magazines. The storage location for each of these facilities would be in previously disturbed areas between the plant site and the pit; safety and security would be the main factors considered in their final location.

Cuttings samples would be taken from blast holes. Based upon the assay values of these samples, the broken rock in the pit would be classified as "ore" or "waste." The broken rock would be loaded onto end dump haul trucks for transport to the primary crusher, low-grade stockpile, or waste rock disposal area(s) depending on the assay classification.

Loading of both ore and waste rock would be accomplished by using hydraulic shovels and/or front-end loaders. During the first years of operation, ore and waste rock haulage would be handled by a fleet of end-dump, diesel-powered haulage trucks of minimum 85-ton capacity. Additional units may be added to the fleet as the pit is deepened. A preliminary equipment inventory is provided in **Table 3-2**.

Noise from the mine equipment would comply with, and would be regulated under MSHA. Mining equipment would be fitted with mufflers, spark arresters, and other fire prevention and safety equipment.

A 12.8 acre lake currently is located in the existing pit. The pit bottom was at about a 5,380 foot elevation at closure in 1986. Original ground surface elevation at the pit was approximately 5,580 feet. The water level elevation in the pit lake is currently about 5,420 feet. Pumping of the pit-lake will be necessary prior to mining and continuously throughout the life of the mine. Minor drilling work in 1976 indicated that groundwater in the pit area is localized in the larger fractures. Inflow to the pit during the previous operations ranged from 50 to 75 gallons per minute (gpm). As a result of seasonal precipitation, the pit water level has fluctuated by 1 to 5 feet per year. The water inflow into the pit will be used as make-up water and for dust suppression on the roads and dumps. If necessary, pit water could be temporarily stored in a reservoir in the plant area. Water removal from the pit will continue over the operational life of the mine through a sump or series of sumps located within the pit. Water removal will end once mining of the pit is completed.

The currently designed ultimate depth of the pit is estimated at 900 feet at an elevation of 4,720 feet. After pit-lake pumping activities end, a lake will reform as recharge refills the local cone of depression developed from pit-lake pumping. The pit-lake will eventually be approximately 640 feet deep and cover 75 surface acres. The size of the lake will fluctuate annually depending on precipitation and evaporation rates. At an average evaporation rate of 65 inches per year, the maximum water loss from the pit lake would be about 600 acre feet per year. Refilling of the pit would proceed over a number of years at a predicted recharge rate of 50 to 75 gpm or 80 to 120 acre

feet per year. These estimates will be refined as the geo-hydrology of the area is better understood as a result of studies performed by NMCC.

Table 3-2: Major Pieces of Mining Equipment

Number	Item	Type (or equivalent)
2	Hydraulic Shovels	Terex RH90-C
11	Trucks	Caterpillar 777
1	Loader	Caterpillar 992G
1	Loader	988B
1	Track Dozer	Cat D8 class
2	Tire Dozers	Cat 834 class
1	Grader	Cat 16G class
1	8,000-Gal. Water Truck	773A
1	Backhoe	
2	Blast Holes	
2	Drill Rigs	Atlas Copco DM45
4	Light Plants	
1	1-Ton Flat Bed	
1	Service Truck	
1	Fuel truck	
1	Tire truck	
4	Mechanic's trucks	
8	Pickup trucks	
1	Shop and equipment	
2	Truck-mounted cranes	
1	Modular office building & Equip.	
1	Fire Truck	
1	Office Trailer & Equip.	
1	Crane	
2	Forklifts	
1	834 RT Dozer	
6	Light-Weight Plant Vehicles	
1	Ambulance	

The proposed plan also includes ongoing exploration drilling to define the copper ore body (infill and step out drilling as well as tests for possible deep extensions of the orebody) as well as to test for near-surface coarse gold vein and alluvial gold potential in the area of the mine.

3.2.2 Waste Rock Disposal Area and Low-Grade Stockpile

Waste rock disposal facilities (WRDFs) would be located adjacent to the open pit, in areas used for waste rock disposal by the previous operator. These disposal areas would be expanded under the current MPO to cover approximately 210 acres (**Appendix B)**. Prior to the expansion of existing disposal areas into previously undisturbed areas, reclamation materials (including suitable growth media and "topsoil") would be removed and stockpiled for future use in reclamation. Since a large portion of the waste rock disposal expansions would occur on previously disturbed areas, the amount of reclamation materials available for pre-stripping in these areas may be limited. Water erosion controls, such as berms and diversion ditches, would be installed to divert runoff away from the WRDFs. Water diversion ditches would also be used to control water inflow onto waste rock disposal piles containing partially oxidized and unoxidized material.

Runoff from the WRDFs and the low-grade ore stockpile would be controlled by diverting the runoff water into collection ditches and then recycling it into the process water system. No discharge is expected to occur. The final grading plan for the WRDFs would be designed to eliminate surface water run on, enhance runoff, reduce infiltration, minimize visual impacts, and facilitate revegetation through back-grading or crowned grading. Catch benches would be left in place to interrupt surface sheet flow, and regrading would approximate the adjacent and nearby geomorphic land shapes. At the end of the mine life, the height of the largest disposal area would be 340 feet higher than present, at an elevation of 5,900 feet above sea level. The WRDFs are designed to facilitate regrading during reclamation. Typical cross-sections of the proposed WRDFs are provided in **Appendix B**.

The WRDFs would be regraded and surface runoff velocity dissipaters would be constructed to reduce velocities and minimize undue erosion and soil loss. Exact design parameters which are specific to the site climatology and soil conditions would be ascertained during revegetation testing and concurrent reclamation activities. However, preliminary designs, including additional details regarding the runoff collection systems and best management practices to minimize sediment loading from the WRDFs is presented in **Appendix B.** Total material contained in the disposal areas at the end of the expected life of the project would be approximately 37 million tons.

The low-grade stockpile would cover an area of approximately 69 acres and include about 19 million tons of rock assaying less than 0.20 percent copper. If, for economic reasons this low-grade stockpile is not milled, it will be reclaimed at the end of the mine life.

Particulate dust from the WRDFs and low-grade stockpile is not anticipated to be a problem given the hardness of the rock and the coarseness of the material.

Under the NMCC proposed MPO, the partially oxidized (transitional materials) from the pit may be segregated into the North and West WRDFs (**Figure 3-1**), though the exact method of disposal (and possible segregation) will be determined through the current geochemical testing program. The East WRDF would contain only unoxidized waste rock. To minimize oxidation potential post closure, WRDFs would be covered with a layer of compacted material and suitable reclamation materials, and revegetated. A more detailed discussion of the geochemical characteristics and management of the mine waste materials are provided in **Appendix C**.

Additional monitoring wells may be installed along the toe of the East WRDF area to monitor groundwater quality downgradient of the area.

3.2.3 Ore Processing

Ore from the pit would be trucked to the plant area located to the east of the pit (**Figure 3-1**). The ore would be crushed and ground and organic reagents would be added to create froth and cause the copper minerals to adhere to the bubbles (BLM, 1996). The copper-laden froth would be collected and filtered to form a concentrate. The proposed plant would be a sulfide-flotation plant similar to that originally constructed at the site by Quintana Minerals (Copper Flat Partnership) in 1982, and would be typical of plants used at other similar deposits. It would include a molybdenum processing circuit similar to that designed by Quintana. No leaching processes, including cyanide leaching, would be used.

For the most part, the plant facilities would be constructed at the site of the original Quintana plant site, and, to the extent practicable, would use most of the original concrete foundations (**Figure 3-2**). The plant site would occupy approximately 87 acres and would be located between the open pit and the tailings impoundment area (**Figure 3-1**). **Table 3-3** provides a list of the plant site area primary structures (including approximate dimensions and construction materials).

The sulfide flotation plant would be designed to process approximately 5.8 million tons of ore per year at a nominal throughput of 17,500 tons per day (assuming 93% availability). The flow sheet of the process circuit is included as **Figure 3-5**.

Scheduled operating time for the mill is currently proposed at 24 hours per day, seven days per week, 365 days per year. Saleable products would be copper concentrate and molybdenum concentrate. The copper concentrate would be shipped by truck to an off-site refinery or port facility. Gold and silver would be recovered as by-products of the hydrometallurgical refining process at the refinery. Molybdenum concentrate would be filtered, dried, packaged in drums, and shipped directly in trucks to purchasers for further refining.

Table 3-3: Primary Plant Site Structures and Facilities

Facility	Length (ft)	Width (ft)	Height (ft)	Diameter (ft)	Slab (ft)	Construction Type
Primary Crusher	90	30	103	--	0.83	Metal roof, metal siding
Ball Bins	109	51		--	1.00	Concrete
Electric Substation	94	68		--	1.00	slab only
Concentrator Building – Grinding Area	192	145	32	--	1.00	Metal roof, metal siding
Concentrator Building – Flotation Area	22	26	44	--	0.66	Metal roof, metal siding
Concentrator Building – Maintenance Office	13	12	14	--	0.50	Metal roof, metal siding
Concentrate Thickeners (2)	--	--	--	50	--	Tank walls - metal
Reagent Building	60	50	26	--	0.50	Metal roof, metal siding
Assay & Metallurgical Laboratory	180	40	16	--	0.50	Metal roof, metal siding
Tailings Thickener				350	-	Thickener
Concentrate Stockpile	154	103		--	0.66	Concrete
Wash Pad	58	33	0	--	0.83	Concrete
Change House	180	40	20.5	--	0.50	Metal roof, metal siding
Administration Building	120	60	14	--	0.50	Metal roof, metal siding
Truck Repair Warehouse	340	90		--	1.00	Metal roof, metal siding
Small Vehicle Repair Building	90	30	40	--	0.83	Metal roof, metal siding
Reagent Storage and Lime Handling	100	52	24	--	0.83	Metal roof, block walls
Lime Mill	27	22.5	8.5	--	0.50	Metal roof, metal siding
Lime Silo	18	24	25	20		Metal
Lime Slurry Tank	--	--		11		(18x18)
Shops and Warehouse (1st story)	180	90	25	--	1.00	Metal roof, metal siding
Shops and Warehouse (2nd story)	50	30	48	--	-	Metal roof, metal siding
Mechanical Equipment/Repair Bays and Warehouse	180	90	43	--	1.00	Metal roof, metal siding
Tire/ Lube	90	60	41	--	1.00	Metal roof, metal siding
Flammable Material Storage Bldg.	25	17	9	--	0.67	Metal roof, metal siding
Filter Deck	24	20	33	--	0.66	Metal roof, metal siding
Gatehouse	8	12	10	--	0.50	Metal roof, metal siding
Acid Storage Building	16	12		--	0.50	Metal roof, metal siding
Records & Receiving Office	41	20	12	--	0.50	Metal roof, metal siding
Freshwater/Fire Tank (1)	--	--	24	34		Metal
Diesel Tanks (2)	--	--	24	42	--	3' berm
Process water tank (1)	--	--	26	20		Metal
Fresh water pump station tanks - 6	--	--	18	17		Metal

Equipment in the concentrator building is expected to consist of the following:

- 42 × 65 in. gyratory crusher,
- 32 ft. dia. × 14 ft. long, 10,000 hp semi-autogenous (SAG) mill,
- 2-8 × 20 ft. double deck vibrating screens,
- 4.5 ft omnicone crusher,
- 10-26 in. cyclones,
- 18 ft. dia. × 28 ft. long, 6,000 hp ball mill,
- 10-1,500 ft^3 bulk rougher cells,
- 13-300 ft^3 cleaner cells,
- 50 ft. dia. bulk concentrate thickener with auto-lift rakes,
- 50 ft. dia. copper concentrate thickener with rakes,
- 350 ft. dia. tailings thickener with auto-lift rakes,
- 20 × 18 in., 800 hp cyclone feed pump,
- 12 ft. dia. × 14 ft. drum belt filter (copper),
- 4.5 ft. dia. × 5 ft. drum belt filter (moly),
- 8-100 ft. molybdenum rougher cells,
- KW-100 tower mill-moly regrind,
- 7-24 ft^3 cleaners,
- 5-18 ft^3 cleaners,
- 5-15 ft^3 cleaners,
- 150 tph recycle crusher, and
- UTM-600 tower mill.

3.2.3.1 *Primary Crushing Facilities*

The primary crusher is currently proposed to be located about 2,500 feet east of the pit. Ore hauled from the pit would be dumped into the primary crusher that would crush the mine run rock to a nominal size of less than 8 inches in diameter. Crusher discharge would be fed by apron feeder onto a belt conveyor for transport to the coarse ore stockpile located near the mill. Delivery of ore by truck would be on a schedule similar to the mining operations, while the crusher would likely operate on the mill schedule, with extra delivery from a nearby surge stockpile with a front end loader. Storage capacity of the coarse ore stockpile would be about 35,000 tons. The crusher would be located below ground level to limit noise and contain dust. Dust emissions would be controlled with suppressants, water, and dust collection equipment (i.e., bag houses) to meet air quality operating permit stipulations and health standards.

3.2.3.2 *Grinding*

Three draw chutes beneath the coarse ore stockpile would direct ore onto apron feeders and feed ore onto a belt conveyor for transport into a large diameter semi-autogenous (SAG) mill and/or roller crushers for the first stage of grinding. Reduction in the SAG mill would be a result of impact between the ore chunks themselves and between the ore chunks and the 5 inch steel grinding balls used in the mill. Reduction would be a combination of crushing and attrition. Water and various

reagents would be added to the SAG mill feed to start the conditioning of the ore pulp for subsequent stages of treatment. Tonnage of the primary feed to the SAG mill would be a nominal 17,500 tons per day.

The SAG mill would discharge onto a double deck vibrating screen. Undersize crushed ore from the screen would report to a cyclone feed sump. The oversize ore would be taken by belt conveyor to a cone crusher, where it would be crushed to less than 0.75 inch in diameter and returned by belt conveyor to the SAG mill. Intermediate size product would be returned directly to the SAG mill by conveyors. Ore from the cyclone feed sump would be pumped to a cluster of hydro-cyclones for material sizing. The fines would report to the first stage of flotation, and the oversize ore would report to two large ball mills for further grinding.

Dust control measures would be implemented in compliance with the air quality permit issued by the New Mexico Environment Department (NMED). Control technologies utilized would vary according to specific applications but would include bag houses, sprays and mists, foggers, and enclosed buildings.

3.2.3.3 *Flotation and Concentration*

Cyclone overflow from the feed sump would report to the first stage (rougher) flotation cells connected in series. Each cell would be equipped with a mechanism that would agitate or stir and induce air into the ore pulp as it passed through the tank. Reagents would be added to the pulp to cause the copper bearing sulfide mineral particles to adhere to bubbles created by the induced air and frothing agents. Flotation reagents that would be used in the concentrator are described in Section 3.2.8. Small amounts of other reagents may be used in the process from time to time as part of an ongoing effort to improve metal recoveries and to cope with changing ore characteristics. The copper bearing sulfide laden bubbles would rise to the top of the cell to be skimmed off. The copper/molybdenum concentrate floated off of the primary rougher would be routed to the molybdenum plant where the copper would be depressed and the molybdenum would be floated up, graded-filtered, and dried. The copper concentrate, which would average about 28 percent copper, would be dewatered in a settling facility (thickener) to decant water, then disk filtered, and stored for shipment. The copper and molybdenum concentrates would be loaded by a front end loader into covered trucks for transportation to a smelter or off-site refiner. Filtrate from both the copper flotation circuit and the molybdenum flotation circuit would be returned to concentrate thickeners. Thickener overflow would be returned to the plant reclaim water system. No smelting or refining would be conducted at the Copper Flat Project. The molybdenum concentrate would also be dried prior to packing into 55 gallon drums for shipment.

The crushing and concentrating plant complex would include buildings such as offices, a truck shop, a substation, and a gatehouse. The buildings would all be prefabricated, standard, rigid framed structures. The administration building would be approximately 60 feet by 120 feet with a 14 foot eave height. The building would have central heating and air conditioning and would accommodate the plant administration, engineering, accounting, secretarial, and clerical personnel. Appropriate sanitary facilities would be provided for men and women.

The assay and laboratory offices would be 40 feet × 180 feet. Appropriate sanitary facilities would be provided. A small air compressor would be mounted on an exterior concrete pad for furnishing service air to the building. The gate house building would be 8 feet × 12 feet. A parking area for employee vehicles would be located adjacent to the main plant entry gate. The shop and warehouse building would be an equipment servicing facility. The reagent building would be a 60-foot × 50-foot building. See **Table 3-3** for additional details on buildings.

All mechanical, civil, structural and architectural designs would be in accordance with applicable standards and codes. The criteria used for design, equipment selection, layouts and construction were initially derived from the prior operation of Quintana Minerals and information from vendor and consultant recommendations. Equipment and fabricated items would be furnished with manufacturers' standard finish and retouched after erection. Safety painting would be in accordance with MSHA standards and New Mexico mining codes. Buildings and facilities would be painted in neutral colors to blend with the surrounding landscape.

The plant site surface drainage was originally designed to contain or control a 24-hour precipitation event of 2.6 inches with a maximum 1 hour intensity of 2.0 inches. These calculations would be verified during the engineering design phase of the project in accordance with current regulatory requirements and design criteria. Surface runoff from the area around the administration/mine office, concentrator, assay building, reagent storage and tailings thickener would be controlled by surface grading and directed to a containment pond.

3.2.3.4 *Tailings Impoundment*

An existing tailings impoundment facility at Copper Flat was constructed by Quintana Minerals to serve their 1982 mining operation. The impoundment received 1.2 million tons of material and was essentially reclaimed in 1986. The tailings impoundment remains in place and is located southeast of the former plant site. NMCC proposes to construct a new lined tailings impoundment facility over the area used by previous operations for tailings disposal. Tailings would be transported from the mill via slurry pipeline and deposited in the new impoundment. Ancillary facilities associated with the tailings impoundment facility would include a tailings slurry delivery system, a tailings solution reclaim and recycling system (barge pump system), and an underdrain seepage return system.

Approximately 95 million tons of tailings are expected to be impounded over the life of the project. Tailings deposition would be approximately 17,500 tons per day (tpd). During progressive settlement, water would be pumped from the tailings impoundment and returned to the process circuit. The total expected water recovery by reclaim systems (thickener and tailings impoundment recycling) would be a nominal 70 percent.

3.2.3.4.1 Tailings Impoundment Design

A conceptual design report (Golder, 2010) for the proposed tailings impoundment, including determinations regarding the source of materials for the new tailings dam, is provided in **Appendix D**, and summarized herein. The new impoundment would be expanded approximately 1,000 feet to the east of the existing unlined impoundment. NMCC proposes to utilize the existing 1982 starter

dam as a borrow source for the new starter embankment construction, and supplemented with mine waste and alluvial material as described in **Appendix D**.

The proposed method of construction for the new tailings storage facility (TSF) is by centerline raises with cycloned tailings sand. The tailings surface would rise approximately 80 feet in the first two years of operation.

Initial construction would include a toe berm to buttress the tailings embankment and a starter dam for placement of the tailings header line and cyclones. Sand (cyclone underflow) would be placed on the embankment while the tailings slimes (cyclone overflow) would be discharged to the impoundment interior. A geomembrane liner would be placed beneath the starter dam and anchored on the crest of the toe berm. An underdrain system consisting of a filter compatible soil and drainage collection pipes would be placed on top of the geomembrane liner and beneath the sand dam footprint to facilitate drainage and consolidation of the cycloned sand. The underdrain system would extend into the impoundment interior in the area that would underlie the free water pond. Underdrainage would be routed to a lined underdrain collection pond located downstream of the toe berm.

The TSF is intended to be constructed in a phased manner. During initial construction phases, diversion ditches would be constructed to divert stormwater from upstream catchment areas within the area contributory to the impoundment. The contributory area is approximately equivalent to the ultimate TSF footprint, as only minor peripheral areas drain into the TSF. At final build out, minimal potential exists for surface water runon from external areas. Throughout most of the life of the facility, stormwater management requirements would be limited to direct precipitation.

Based on the rules and regulations of the New Mexico Office of the State Engineer, the Copper Flat TSF would be classified as a large dam having significant hazard potential. As such, the impoundment has been designed to contain the equivalent of 75 percent of the probable maximum precipitation (PMP) during operations. A spillway capable of passing 75 percent of the PMP would be required upon closure.

3.2.3.4.2 Tailings Impoundment Process

Following the flotation process, the remaining slurry, consisting primarily of non-valuable minerals, pyrite, miscellaneous unfloated minerals and water, would flow into a tailings thickener for partial dewatering. The slurry would enter the tailings thickener at approximately 30 percent solids by weight. Water would be removed by decanting and the tailings would exit the thickener at 50 percent solids. Approximately 57 percent of the process water would be recovered in the tailings thickening operation. NMCC is considering additional water conservation measures and innovations which, if viable, would be added to the current process.

The thickened tailings would then flow by gravity through a 24 inch pipeline into the tailings impoundment. To contain possible spills or leaks, the tailings impoundment pipeline would be constructed between earthen berms. The pipeline foundation materials and berms would be sloped to

direct any spillage or leakage to the tailings impoundment. Thickened tailings slurry would be distributed around the periphery of the impoundment by numerous spigots or hydrocyclones, which separate coarse material from the fines in the slurry. The coarse material deposited at the periphery of the impoundment would be used to construct embankment rises from the new starter embankment. The fine silt and slimes would flow away from the upstream face of the raised embankment toward the pool. As the finer material flows into the impoundment, gravitational settlement of solids would form beaches. Supernatant solution (the residual water in the tailings which seeps to and collects on the surface of the impoundment as the tailings settle and compress) and precipitation run-off would flow towards the impoundment low point formed by the beaches to form the free pool. Tailings deposition would be managed to force the pool away from the embankment towards an ultimate pool location. The tailings used to form the initial beaches would have a permeability coefficient of approximately 1×10^{-6} cm/sec, after consolidation occurs, due to progressive loading.

Water reporting to the tailings impoundment would be recovered from the pool of water that would form in the impoundment and be returned to the mill process water system for reuse. Stormwater runoff could also contribute to the volume of water in this pool. The height of the embankment is designed to contain the normal operating volume of water completely within the impoundment, combined with the amount of stormwater runoff from 75 percent of the PMP, which is estimated to be about 25 inches (Golder, 2010 – **Appendix D**).

The size and location of the impoundment pool would vary during the life of the project. The size of the pool would be affected by pre-deposition grading in the impoundment, the amount of tailings deposited, precipitation, evaporation rates, seepage rates into the designed embankment seepage collection system, infiltration into underlying soils, and water recycling rates. The location of the pool would migrate within the impoundment area as tailings beaches form. Tailings deposition would be managed to force the pool away from the embankment toward the upstream reaches of the impoundment. The impoundment area would be fenced to restrict access.

3.2.3.5 *Tailings Impoundment Monitoring*

The tailings impoundment would be regulated by the New Mexico Office of the State Engineer, Dam Safety Bureau for safety of operations. The design and operation of the tailings impoundment dam would be subject to approval of the Office of the State Engineer including the closure inspection. The State Engineer's Office requires monthly reports of the tonnages deposited into the impoundment along with readings of the piezometers, settlement devices, and settlement monuments that monitor movement.

The Groundwater Quality Bureau of NMED requires a monthly report of tonnages of tails discharged along with analyses of the tailings to identify possible contaminants. Samples of water from new monitor wells proposed for downstream of the tailings dam would be analyzed monthly and the results sent to the Groundwater Quality Bureau. These samples would be used to identify any leakage from the new, lined tailings impoundment. Abatement plans would be implemented should leakage and contamination be detected.

3.2.4 Haul Roads and On-Site Service Roads

For the most part, existing haul roads would be utilized to haul material to the crusher, stockpiles, and waste rock disposal areas. Some minor realignment of these roads may be necessary and road widths would vary. A cross-section of a typical haul road is provided in **Figure 3-6**.

Haul roads are not expected to create new disturbances, as they would be constructed on previously disturbed land. The on-site roads would be designed for easy access and traffic movement within the operations area. Waste rock and ore would be hauled to the disposal areas and mill using conventional mining haul trucks, depending on mine optimization and scheduling.

During operation of the Copper Flat Project, water trucks would be used, as needed, to control emissions of fugitive dust from the haul roads, as well as other roads within the project area. Wetting agents and binding agents, such as magnesium chloride, may also be used to control dust if conditions warrant.

3.2.5 Project Work Force and Schedule

The construction phase of the project is expected to take approximately 12 to 18 months. During this time, the work force for development of the Copper Flat mine would average about 120 to 130 persons per day.

The estimated operational life required to recover the proven minerals (copper, molybdenum, gold, and silver) is 17 years. The maximum work force would be around 170. Approximately 80 to 100 people would be employed in the office and mine; 40 to 70 people would be employed in the mill. The reclamation workforce would consist of up to 20 employees. NMCC anticipates hiring over 70 percent of the work force from local communities within a 75-mile radius of the mine. The mine would likely operate 24 hours per day, 7 days per week, 365 days per year. The mill would likely operate on that same schedule. Administrative personnel would work a standard day shift, five (5) days per week, 50 weeks per year. These schedules are subject to change based on future economics of the project.

3.2.6 Electrical Power

Power for the project would be furnished by the Sierra Electric Cooperative by means of an existing 115 kV transmission line that runs from the Caballo switching station near the junction of Interstate 25 (I-25) and Highway 152, and terminates within 300 feet of the mill facility at the site of the proposed mine substation (**Figure 1-2)**.

The 115-kV line was installed for the 1982 mine due to the limited capacity of the existing lines in the area, which supplied the community of Hillsboro and the surrounding rural areas. The existing 115-kV line is a wooden pole, H frame construction and will be in full accordance with state and federal electric codes. Tri-State Generation and Transmission owns the line and is responsible for maintenance. The substation would be reconstructed in the same location it was in 1982, fenced and constructed in accordance with BLM stipulations. NMCC would own the substation equipment and would be responsible for construction and maintenance. From the substation, the voltage would be stepped down by primary transformers and distributed throughout the mine.

An existing 25-kV distribution line provides power to the production wells located east of the mine, booster stations on the fresh water pipeline, and the reclaim water pump stations at the tailings dam. Sierra Electric owns this line and is responsible for maintenance. The plant electrical load requirement is tabulated below (**Table 3-4**):

Table 3-4: Summary of Project Electrical Demand

	Demand (kWh/ton)
Primary Crushing	0.25
Total Grinding	17.48
Total Copper Flotation	1.74
Molybdenum Flotation	0.27
Thickening	0.05
Reagent Handling	0.05
Water System	2.05
Ancillaries	0.65
Total	**22.54**

Note: kWh – kilowatt hours

A new substation would be constructed at the site. An emergency generator is also included as backup power in the event of power loss to maintain critical systems and to aid in a controlled shut down. NMCC is analyzing the viability of solar power generation to partially offset the mine's energy demand, along with other energy and water conservation measures.

Because the configuration and size of the 25 kV distribution line, standard raptor proof protective designs would be incorporated into the line design and line upgrade, as presented in the Rural Electrification Administration guidelines and in the measures developed by Olendorff *et al*. (1981). This design would be used for the entire length of the distribution line within the mine area.

3.2.7 Water Supply

The total water demand for the Project would be approximately 6,400 gallons per minute (gpm) with the majority of the water used in the ore processing operation (**Table 3-5**).

Table 3-5: Project Water Demand

Activity	Demand (gpm)
Ore Processing (17, 500 tpd)	6,268
Dust Suppression (2 truckloads/hr × 12 hr/d × 360 d/yr)	131
Domestic/Sewerage Use	1
TOTAL	**6,400**

Of this demand, approximately 4,400 gpm would be obtained from reclaimed process water (thickener overflow and impoundment recycling) and pit water pumping (dewatering). Approximately 2,000 gpm would be freshwater make-up.

The freshwater supply for the mine would come from four existing high capacity production wells located about eight miles east of the plant site on BLM-administered public land (**Figure 2-1**). These wells were drilled to depths of between 957 feet and 1,005 feet. All are 26 inches in diameter and cased with 16-inch casing with the annular space packed with minus 3/8 inch washed gravel. The projected long-term capacities of the four production wells range from 1,000 to 1,800 gpm (Green and Halpenny, 1976). Most of the roads, electrical supply and pump foundations are intact at the pumping field. The legal locations of the production wells (and monitoring wells) proposed for use in the plan of operations are provided in **Table 3-6**:

Table 3-6: Production and Monitoring Well Legal Locations

Well Name	Designation	Township	Range	Section
PW-1	Production wells	15S	5W	30
PW-2		15S	5W	31
PW-3		15S	5W	30
PW-4		15S	5W	31
GWQ-1	Monitoring Wells	15S	6W	31
GWQ-2		15S	6W	30
GWQ-7		15S	6W	31
GWQ-8		15S	6W	31
GWQ-9		15S	6W	31
Irwin Well		15S	6W	31
MW-1		16S	6W	04
MW-2		16S	6W	09
MW-4		15S	6W	31
MW-5		15S	5W	30
MW-6		15S	6W	25
MW-8		15S	6W	28
Dolores Well		15S	7W	25
McCravey Greyback		15S	6W	30
Pit Lake	Pit Lake	15S	7W	26, 35

An existing 20-inch welded steel pipeline would transport the water from the booster station(s) (**Figure 2-1**). The pipeline is buried a minimum of two feet deep from the well field to the point of entry to the project area. NMCC is preparing to conduct a detailed inspection and assessment of this pipeline to determine its condition and viability for use in the Project. NMCC currently anticipates conducting hydrostatic and possibly ultrasonic testing of the pipeline. NMCC will submit the results of the inspections to the BLM upon completion of the work. If testing indicates the need for repair or replacement of the pipeline, NMCC will do what is necessary to bring the facility into proper working order.

Water pumped from the pit and recycled from the process circuit would reduce the amount of water withdrawn from the production wells. This water would generally be reused in processing and in

dust suppression. Pump station #3 is located at the process water reservoir located below the tailings thickener. This station would deliver water to the process water reservoir or to the freshwater storage tank as needed. The process water reservoir would be fed by the tailings thickener overflow, reclaim water pumped back from the tailings barge pump system, and fresh water makeup as needed. It would be pumped from the reservoir to a steady head tank and flows by gravity back to the grinding circuit. A sump and pumping installation would be advanced with the pit excavation to remove infiltrated and surface runoff water collected within the pit. This water would be used in either pit operations or the concentrator.

The area encompassing the mine, mill, tailings impoundment, and water supply wells are within the Lower Rio Grande Underground Water Basin. Water rights are described in declarations, amended declarations, and supporting documents under New Mexico State Engineer File Nos. LRG-4652 through LRG-4652-S-17 and LRG-4654.

Water quality monitoring samples have been collected in the mine area from both surface and groundwater sources since 1976 and would continue to be collected throughout the life of the operation, during closure, and for a post closure period defined in the groundwater Discharge Permit.

3.2.7.1 *Stormwater*

The mining and concentrating process would not involve any discharge to surface water courses. Surface runoff (stormwater) from the mine and plant site area would be collected in containment (settling) ponds and recycled into the process water system. Stormwater outside the plant and mine site would not come in contact with the proposed operation due to existing diversion ditches, dams, and berms.

Sediment control in the mine area would be achieved by the use of seeding and mulching, silt fences, straw bale dams, diversion ditches with energy dissipaters, and rock check dams at appropriate locations during construction and operation. All sediment control structures would be monitored and maintained on a regular basis.

3.2.7.2 *Groundwater*

In 1982, the NMED Ground Water Quality Bureau approved a Ground Water Discharge Plan, DP 001. On June 26, 1992, the Ground Water Quality Bureau confirmed the need to amend the permit, DP 001, in order to more closely define compliance and remedial actions. On August 20, 2008, the NMED sent a letter to the site owner at that time requiring a Stage 1 Abatement Plan (20.6.2.4101 NMAC). The purpose of the Stage 1 Abatement Plan is to provide the data necessary to select and design an effective abatement alternative. The requirements for the Stage 1 Abatement Plan are described in 20.6.2.4106 NMAC. The Abatement Plan proposal must include an investigation to define the extent and magnitude of any existing groundwater and surface water contamination and to characterize the hydrogeology of the site. NMED's concerns regarding water resources at the Copper Flat site include:

- Groundwater impacts from the existing unlined tailings impoundment have been documented, but have not been fully characterized.
- Samples of pit lake water quality reveal exceedences of New Mexico Water Quality Control Commission (WQCC) standards, and NMED is concerned about migration of this water away from the pit, causing additional groundwater impacts as well as ongoing contact with wildlife.
- Acid leaching could be occurring due to ongoing ore exposure.

The surface and ground water of the Copper Flat area are described and analyzed in detail in the Hydrologic Assessment Report (Shomaker & Newcomer, 1993) and the Copper Flat Hydrogeological Report (SRK, 1995; ABC, 1996). Ongoing and future groundwater monitoring would be conducted as required by the State of New Mexico. A detailed description of the current baseline monitoring program for groundwater is presented in the Sampling and Analysis Plan for Copper Flat Mine (Intera, 2010), provided to the BLM under separate cover. Future monitoring and possible abatement activities would be coordinated with all relevant stakeholders to ensure the protection of groundwater resources.

3.2.8 Fencing and Exclusionary Devices

NMCC would construct BLM-approved barbed wire fencing to prevent livestock from entering the pit, waste rock disposal facilities, and tailing storage facilities, including the seepage collection pond. In areas where a higher level of security is needed, chain-link fences would be erected. Wildlife fences would be constructed around the lined ponds. Gates and/or cattle guards would be installed along roadways within the proposed Project Area as appropriate.

NMCC would monitor the fences on a regular basis and repairs would be made by NMCC as needed. BLM would be contacted immediately in the event that livestock manage to enter the proposed Project Area via a gate or opening in a fence. NMCC would assist as requested in moving these animals out of the proposed Project Area. At the time of closure, if livestock grazing is the approved post-mining land use, a plan would be developed between NMCC and the BLM for responsibility of long-term maintenance of range fences that would be left in place within the Plan boundary.

To the extent practicable, NMCC would investigate and utilize exclusionary devices, including, but not necessarily limited to bird balls and/or netting, to minimize the potential for avian wildlife contacting process pond waters that contain elevated chemical constituents in excess of ecological risk levels.

3.2.9 Growth Media

Available growth media would be salvaged and stored in stockpiles for reclamation. Section 3.4.14 presents further discussion on growth media salvage. Growth media would consist of soils stripped prior to surface disturbance activities. Any growth media remaining in a stockpile for one or more planting seasons would be seeded with an interim seed mix to stabilize the material by reducing erosion and minimizing establishment of undesirable weeds.

3.2.10 Borrow Areas

Construction-related borrow areas would be located within facility footprints (Appendix D, Borrow Sources and Stockpile Evaluations). Borrow sources would be required for prepared sub-grade materials, drainage materials, pipe bedding materials, road surfacing materials, retarding layer materials, reclamation materials, growth materials and riprap. Precise locations and anticipated quantities of borrow materials have not yet been determined, but would be provided during the NEPA process, prior to MPO approval. Borrow areas may be revisited over the mine life.

3.2.11 Ancillary Facilities

The process area would also include several ancillary buildings such as offices, a truck shop, warehouse, small vehicle shop, an electrical substation, and a gatehouse. The buildings would all be prefabricated, standard, rigid framed structures or block walls with metal roofing. Where practicable and economic, NMCC would consider alternative construction materials and techniques to improve the overall energy efficiency of the project. This may include renewable energy generation (solar, wind, etc.) for certain buildings.

The administration building would be approximately 60 feet by 120 feet with a 14 foot eave height. The building would have central heating and air conditioning and would accommodate the plant administration, engineering, accounting, secretarial, and clerical personnel. Appropriate sanitary facilities would be provided for men and women.

The assay and laboratory offices would be 40 feet by 180 feet. Appropriate sanitary facilities would be provided. A small air compressor would be mounted on an exterior concrete pad for furnishing service air to the building. The gate house building would be eight feet by 12 feet. A parking area for employee vehicles would be located adjacent to the main plant entry gate. The shop and warehouse building would be an equipment servicing facility. See **Table 3-3** for additional information on site structures.

All mechanical, civil, structural and architectural designs would be in accordance with applicable standards and codes. The criteria used for design, equipment selection, layouts and construction were derived from the prior operation(s) and information from vendor and consultant recommendations. Equipment and fabricated items would be furnished with manufacturers' standard finish and

retouched after erection. Safety painting would be in accordance with MSHA and/or OSHA standards (as applicable) and New Mexico mining codes. Buildings and facilities would be painted in neutral colors to blend with the surrounding landscape.

3.2.12 Inter-Facility Disturbance

As with most mining facilities, general ground disturbance occurs around and between structures and facilities as a result of construction, operation & maintenance (O&M). This inter-facility disturbance is in addition to the formal footprint created by design. In some cases, NMCC has elected to include disturbance buffer zones surrounding specific facilities (i.e., tailings impoundment, waste rock disposal areas, open pit area, etc.) in order to ensure that the full extent of disturbance associated with these facilities is accounted for and that appropriate reclamation and bonding of these areas can be facilitated.

3.2.13 Transportation

Access from the site is by three miles of all-weather gravel road and 10 miles of paved highway (State Highway 152) east to I-25, near Caballo Reservoir. The 10 miles on State Highway 152 to I-25 to I-25 is mainly a straight and relatively flat road (and does not include any sharp turns or significantly adverse grades). I-25 is the primary north-south highway. Traffic associated with reestablishment of the Copper Flat Project would be broadly grouped as follows:

- **Concentrate Shipments**: Shipment of concentrates by trucks to smelters and/or port facilities would generally be via hydraulic dump trucks with 25-ton capacity towing 10-ton trailers. Copper concentrate would be thickened, filtered and trucked approximately 41miles to a railhead at Rincon, near Hatch, New Mexico on I-25, (or another site), and then transported by rail to a smelter, most likely in Arizona, and/or to port facilities. Alternatively, a possible rail loading point at the intersection of State Highways 26 and 27 south of the Project could be used. Molybdenum concentrate would be filtered, dried and bagged on site and then transported by truck or rail.
- **Incoming Supplies**: Venders, equipment and service suppliers are anticipated to take, in total, an average of 10 to 15 trips per day by truck to the mine. Most deliveries, including equipment parts, reagents, oil, and miscellaneous office supplies, would be made during the day shift. Title 49 CFR regulates the transportation of hazardous materials in commerce. Anyone who transports, packages, loads, unloads, or in any way assumes responsibility for marking, labeling, or handling of any regulated hazardous materials must comply with 49 CFR. In addition, carriers must comply with the Federal Motor Carrier Safety Regulations of the DOT (parts 383, 390 397, and 399). Hazardous materials required for operation of the Copper Flat Project include gasoline, diesel fuel, propane, and other petroleum products, explosives, solvents for degreasing of machinery and equipment, and laboratory chemicals. These materials would be purchased from various vendors and brought to the site by truck. NMCC would ensure that the Hillsboro volunteer fire department and the Sierra County fire district are aware of the nature of the materials routinely being transported to the site, and

that they have appropriate response training in the event of a spill or other accident involving hazardous materials.

- **Employees and Visitors**: The majority of employees are expected to commute from Truth or Consequences or Hillsboro. An additional 15 to 20 trips could be expected by visitors and sales representatives. NMCC would encourage car and van pools. .

There are no present plans for a company operated employee transportation system. No railroad access or facilities, airstrips, or helicopter pads are planned in connection with the mine development or operations.

3.3 Exploration Activities

NMCC is currently conducting exploration activities to identify new reserves or expand existing reserves within the Plan area under previous authorizations by federal and state agencies. Current exploration and mineral evaluations have been focused within and on previously disturbed federally-administered land and privately-owned, patented lands. Future exploration would likely include activities outside of the main disturbed lands on BLM-administered lands within the currently proposed Project boundary and permit areas, as defined in **Figures 2-2** and **3-1**. Exploration disturbance would generally include construction of access roads, drill pads, sumps, trenches, surface sampling, bulk sampling, and staging areas. Exploration methods include both reverse circulation and core drilling, with minor trenching also planned. Exploration activities may also include water exploration and monitor well installation.

Exact locations of the exploration disturbance have not been determined. However, as part of the current mine MPO, NMCC requests an additional 15,000 linear feet of drill road (average width of 20 ft) and 100 drill pads (average dimensions of 100 ft × 100 ft), and up to 150 drillholes (average diameter of 5 in.; average depth of 1,200 ft bgs) for future exploration of the site. Placement of drillholes would be guided by reserve requirements, geotechnical studies, and geochemical sampling. The roads and pads would be sited as much as possible to avoid any identified cultural resources. Sections 3.4.4 and 3.4.5 describe the measures that would be undertaken to protect or mitigate impact to biological and cultural resources, respectively. If additional disturbance for exploration activities is necessary, an amendment to the MPO and revision to the reclamation bond cost would be prepared and submitted to BLM for review and approval.

3.4 Applicant Committed Environmental Protection Measures and Committed Practices

NMCC would commit to the following practices to prevent undue and unnecessary degradation during the life of the Project. These practices, described briefly below, are to be considered part of the operating plan and procedures. More detailed information would be developed as the Project is advanced to more detailed design stages.

3.4.1 Air Quality

The Copper Flat Project would be designed to control both gaseous and particulate emissions and to meet all regulatory standards. Appropriate air quality permits would be obtained from the New Mexico Environment Department - Air Quality Bureau for the new Project facilities and land disturbance. As per NMED regulations, the project air quality operating permit must be authorized by the NMED prior to project commissioning.

Committed air quality practices would include dust control for mine unit operations. In general, the fugitive dust control program would provide for water application on haul roads and other disturbed areas; chemical dust suppressant application (such as magnesium chloride) where appropriate; and other dust control measures as per accepted and reasonable industry practice. Also, disturbed areas would be seeded with an interim seed mix to minimize fugitive dust emissions from un-vegetated surfaces where appropriate.

Fugitive emissions in the process area would be controlled at the crusher and conveyor drop points through the use of water sprays and dry cartridge filter type dust collectors where necessary. Other process areas requiring dust and/or emission controls include the concentrate drying and packaging circuit, the various process plants, and the laboratory. Appropriate emission control equipment would be installed and operated in accordance with the construction and operating air permits.

The lime storage would be fitted with a baghouse for capture of fugitive dust during loading of the lime bin. The sample preparation lab would be equipped with fans and filters.

Deposition of tailings would be by spigotting and/or cyclone discharge. By this procedure, the surface would be wet, thereby eliminating or reducing fugitive dust. As necessary, control of fugitive dust in the vicinity of the tailings pond would be attained by watering, sprinkling, and vegetation. No gaseous contaminants above allowable standards are expected to be emitted to the atmosphere from the proposed operations.

Drilling operations would be done wet or with other efficient dust control measures as set by MSHA and NM Mine Inspection , and NM mining and exploration permit requirements. At a minimum, haul roads, waste rock disposal areas, and ore transfer points would be wetted down on a regular basis to minimize dust emissions. Dust abatement at the primary crusher, coarse ore stacker, and coarse ore reclaim feeders would utilize NMED and MSHA-approved Sonic Misting Systems (Best Available Control Technology).

Combustion emissions would result from the mobile mining machinery and support vehicles. All combustion equipment emits nitrogen dioxide (NO_2) and carbon monoxide (CO). The mobile mining equipment is diesel fuelled and also would emit particulate matter. Combustion emissions would be controlled by original equipment manufacturer pollution control devices. Fugitive emissions from ore and the flotation equipment are expected to be small due to the low volatility of the sulfur compounds present in the concentrate.

3.4.2 Water Resources

Process components would be designed, constructed, and operated in accordance with NMED regulations. The proposed process facilities would be zero discharge, and the TSF facilities would have engineered liner systems. The waste rock has been evaluated for potential to generate acid and/or mobilize deleterious constituents, and generally been found to produce neutral to slightly alkaline leachates with low concentrations of sulfate and dissolved metals (**Appendix C**). Waste rock with the potential to generate acid and/or mobilize deleterious constituents would be identified through laboratory analyses during mining and managed in the waste rock disposal facilities.

NMCC is in the process of preparing a stormwater management plan to identify more specific control measures and monitoring requirements. The actual locations and numbers of sediment controls would be determined during final design and where appropriate during operations. Larger ponds would be designed and constructed in accordance with the requirements of the New Mexico State Engineer's Office. Sediment removed from the sediment control structures would be placed in the tailings impoundment or other approved locations.

3.4.3 Erosion and Sediment Control

Best management practices (BMPs) would be used to limit erosion and reduce sediment in precipitation runoff from proposed Project facilities and disturbed areas during construction, operations, and initial stages of reclamation. BMPs that would be used during construction and operation to minimize erosion and control sediment runoff and would include:

- Surface stabilization measures – dust control, mulching, riprap, temporary and permanent revegetation/reclamation, and placing growth media;
- Runoff control and conveyance measures – hardened channels, runoff diversions; and,
- Sediment traps and barriers – check dams, grade stabilization structures, sediment detention, sediment/silt fence and straw bale barriers, and sediment traps.

Revegetation of disturbed areas would reduce the potential for wind and water erosion. Following construction activities, areas such as cut and fill embankments and growth media/cover stockpiles would be seeded as soon as practicable and safe. Concurrent reclamation would be maximized to the extent practicable to accelerate revegetation of disturbed areas. All sediment and erosion control measures would be inspected periodically, and repairs performed as needed.

3.4.4 Wildlife

Land clearing and surface disturbance would be timed to prevent destruction of active bird nests or birds' young during the avian breeding season (March 1 to August 31) to comply with the Migratory Bird Treaty Act. If surface disturbing activities are unavoidable during the avian breeding and nesting season, NMCC would have a qualified biologist survey areas proposed for disturbance for the presence of active nests immediately prior to the disturbance. If active nests are located, or if

other evidence of nesting is observed (mating pairs, territorial defense, carrying nesting material, transporting of food), the area would be avoided to prevent destruction or disturbance of nests until the birds are no longer present.

Operators would be trained to monitor the mining and process areas for the presence of larger wildlife such as deer and antelope. Mortality information would be collected. NMCC would establish wildlife protection policies that would prohibit feeding or harassment of wildlife.

3.4.5 Cultural Resources

Avoidance is the BLM-preferred management response for preventing impacts to historic properties [a historic property is any prehistoric or historic site eligible to the National Register of Historic Places (NRHP)] or unevaluated cultural resources. If avoidance is not possible or is not adequate to prevent adverse effects, NMCC would undertake data recovery from such sites. Development of a treatment plan, data recovery, archeological documentation, and report preparation would be based on the Secretary of the Interior's "Standards and Guidelines for Archeology and Historic Preservation," 48 CFR § 44716 (September 29, 1983), as amended or replaced. If an unevaluated site could not be avoided, additional information would be gathered and the site would be evaluated. If the site does not meet eligibility criteria as defined by the New Mexico State Historic Preservation Office (SHPO), no further cultural work would be performed. If a site meets eligibility criteria, a data recovery plan or appropriate mitigation would be completed.

3.4.6 Protection of Survey Monuments

To the extent practicable, NMCC would protect all survey monuments, witness corners, reference monuments, bearing trees, and line trees against unnecessary or undue destruction or damage. If, in the course of operations, any monuments, corners, or accessories are destroyed, NMCC would immediately report the matter to the authorized officer. Prior to destruction or damage during surface disturbing activities, NMCC would contact the BLM to develop a plan for any necessary restoration or re-establishment activity of the affected monument. NMCC would bear the cost for the restoration or re-establishment activities.

3.4.7 Health and Safety and Emergency Response

The development of the Copper Flat ore body would comply with environmental, and health and safety regulations of all governmental agencies including Mining Safety and Health Administration (MSHA) and the New Mexico Mining Act. The State agencies primarily involved are the NMED, the State Mine Inspector's Office (SMIO), New Mexico Department of Energy, Minerals, and Natural Resources -Mining and Minerals Division (MMD), and the New Mexico Office of the State Engineer.

NMED has jurisdiction over ambient air quality, discharges to groundwater, surface water impacts, solid waste disposal, and liquid waste disposal (sanitary facilities). The SMIO and MSHA have

jurisdiction over health and safety within the mine; the State Engineer's Office is concerned with the tailings dam construction and operation, and the administration of water rights. The MMD is responsible for issuing a mining permit and is concerned with all issues related to mine operations and reclamation.

As specified under SMIO and MSHA regulations, appropriate dust collection and noise abatement equipment would be installed at the mine. Noise levels in both the mine area and process area would also be subject to MSHA regulations.

All drinking water storage vessels would be enclosed in order to preserve the water's potable quality. Within the mine and mill area and the tailings impoundment, vehicular traffic and human movement would be controlled through the use of fences, locked gates, signs, and supervisory personnel. Fencing would also discourage access by cattle. Livestock grazing is currently permitted in adjacent properties at the livestock owner's risk and would continue during mine operation in adjacent areas.

3.4.8 Fire Protection

As specified by MSHA, NMCC would institute a fire protection training program and have a rehearsed fire suppression plan. A fire protection system would be installed that would incorporate Sierra County and or State code requirements in the administration and warehouse complexes, truck shop, crushing plant, and process plant. Hydrants would be located near all buildings. A 100,000 gallon fire water reserve would be stored in a water storage tank located sufficiently above and near the mill and crushing area to provide adequate water pressure. A fuel break would be constructed around the facilities. A fire truck and water trucks, used for dust suppression, would be available in the event of a fire. An ambulance would be located on site in the event emergency transportation is required.

NMCC would promptly comply with any emergency directives and requirements of Sierra County and the BLM pertaining to industrial operations during the fire season.

3.4.9 Invasive, Non-native Species

NMCC recognizes the economic and environmental impact that can result from the establishment of noxious weeds and has committed to a proactive approach to weed control. A noxious weed survey would be completed prior to any earth moving disturbance. Areas of concern for noxious weed would be flagged by a weed scientist or qualified biologist to alert all personnel to avoid those areas, as practicable. Information and training regarding noxious weeds management and identification would be provided to all personnel affiliated with the implementation and maintenance of the project.

A noxious weed monitoring and control plan would be implemented during construction and continuing through operations. The plan would contain a risk assessment, management strategies, provisions for annual monitoring and treatment evaluation, and provisions for treatment. The results

from annual monitoring would be the basis for updating the plan and developing annual treatment programs.

In general, all vehicle and heavy equipment that may have been exposed to noxious weeds would be cleaned with power or high-pressure washer prior to entering or leaving the Project Area. Vehicle cleaning would eliminate the transport of vehicle-borne weed seed, roots, or rhizomes. To eliminate the transport of soil-borne noxious weed seeds, roots or rhizomes infested soils or material would be stockpiled adjacent to the areas from which they were stripped. Appropriate measures would be taken to avoid wind or water erosion of the affected stockpile. All interim and final seed mixes, hay, straw, and hay/straw products would be certified weed-free for New Mexico and BLM-identified noxious weeds.

Weed monitoring would be conducted for the life of the operation or until the site is released and the reclamation financial surety is released. If the spread of noxious weed is noted, weed control procedures would be determined in consultation with BLM personnel and would be in compliance with BLM Handbooks and applicable laws and regulations.

Mixing of herbicides and rinsing of herbicide containers and spray equipment would be conducted only in areas that are a safe distance from environmentally sensitive areas and points of entry to bodies of water (storm drains, irrigation ditches, streams, lakes, or wells).

3.4.10 Materials and Waste Management

Operations at the Copper Flat Project would result in the generation of nonhazardous and hazardous waste materials. The majority of waste would be "mine waste," including mill tailings and waste rock, which is currently excluded from regulation under the Resource Conservation and Recovery Act (RCRA). The management of these excluded wastes is discussed in Section 3.2.2. The management of regulated solid and hazardous waste is discussed in the following sections.

3.4.10.1 *Sanitary and Solid Waste Disposal*

Nonhazardous solid wastes that would be generated at the site include waste paper, wood, scrap metal, and other domestic trash. These materials would be disposed of in a permitted on site Class III sanitary landfill on private land, which would be approved by the State of New Mexico, or by other methods approved by the State and Sierra County.

Sanitary liquid wastes would be handled and disposed of through two existing septic tanks/leach fields permitted by NMED. The septic systems would be slightly modified, including enlargement of the leach fields and placement of larger septic tanks. The washing facility for the mobile equipment would be equipped with a water/oil separator system. Waste oil and lubricants would be collected and transported off site by a buyer/contractor for recycling. Reagent drums would be recycled by the reagent supplier. Scrap metal would be sold to a dealer and transported off site.

Nonhazardous solid wastes from the laboratory would be disposed of in the landfill. Other wastes from the laboratory that exhibit a hazardous waste characteristic, including off specification commercial chemicals and assay wastes would be managed as hazardous waste.

Employee training would include appropriate landfill disposal practices such as the allowable wastes that can be placed in the landfill, management of used filters, oily rags, fluorescent light bulbs, aerosol cans, and other regulated substances. Used solvent, liquids drained from aerosol cans, accumulations of mercury fluorescent lights and used antifreeze may be regulated pursuant to RCRA. NMCC anticipates that the mine would fall in the "small generator" category. Signs would be installed at the landfill sites reminding employees of appropriate disposal practices.

3.4.10.2 *Reagent Management*

Reagents used as part of the copper/molybdenum concentrating process would include frothers, flotation promoters, flotation collectors, flocculants, flotation reagents, pH regulators, and filter and dewatering aids. A preliminary list of the proposed reagents to be use during operations is provided in **Table 3-7**. These reagents would be delivered by truck from commercial sources to the mine site where facilities would be provided for off loading, storing, mixing, handling, and feeding. Reagents that are received dry would be mixed in agitation tanks and pumped to either outdoor storage tanks or liquid storage tanks inside the mill building from which they would be metered into the concentrating process.

Residual reagent concentrations in the tailings and reclaim water streams are expected to be present at very low levels since they would be added to water in amounts resulting in concentrations of approximately 3 parts per million (ppm). Also, normally 95 percent of the reagents would be adsorbed onto the copper or molybdenum mineral surface and floated off in the mineral froth. The reagent would then be subsequently consumed in the offsite smelting process. Assuming 95 percent of the reagents are adsorbed, the residual reagent reporting to the tailings stream drops to less than 0.15 ppm.

Frother reagents to be used at the mine include methyl isobutyl carbinol (MIBC). MIBC is biodegradable in low concentrations. The dosage rate would be 0.02 pound per ton of mill feed. The bulk of this reagent would report to the concentrate fraction and end up at the smelter. The reagent would be received in 20 ton capacity trucks and stored in a 16,000 gallon tank.

Lime used in alkalinity control in the flotation circuit would be received in pebble form in bulk by 20 ton capacity trucks and stored in a 200-ton capacity storage silo. The lime would then be slaked with water in a small mill and the resulting "milk of lime" would be pumped to the addition points in the grinding and flotation circuits for use as a pH regulator. It is anticipated that lime would be used at a rate of 2.7 pounds per ton of mill feed to control pH of the flotation circuit. During the milling process, most of the lime would react with sulfide minerals to form gypsum.

Table 3-7: Copper Flat Project Materials Management

Reagent	Chemical Abstract Service (CAS #)	Type	Use	Annual Quantity (lbs)
Lime	1305-62-0	Caustic powder; Non-Combustible solid; incompatible with acids	pH Control	15,700,000
Xanthate Z-11/Z-200	140-93-2	Fugitive dust potential	Flotation Reagent	58,000
AEROFLOAT 238 (Sodium Hydroxide)	001310-73-2	Caustic alkali liquid; corrosive; incompatible with strong oxidizing agents and mineral acids	Flotation Promoter	116,000
MIBC (Methyl isobutyl carbinole)	108-11-2	Class II combustible liquid	Moly. Frother	116,000
Ammonium Sulfide[1]	12135-76-1	Poison, corrosive, flammable liquid; incompatible with numerous chemicals[2]	Flotation Reagent	1,400,000
Unnamed Flocculent (similar to SUPERFLOC polyacrylamide or acrylamide-acrylic)	-	Organic Polymer	Flocculent Thickener	17,400
AERODRI 100 (Ethanol, Sodium dioctyl sulfosuccinate, 2-Ethylhenanol)	000064-17-5, 000577-11-7, 000104-76-7	Flammable liquid; incompatible with strong acids, alkalines, and strong oxidizing agents	Filter Aid Dewatering Aid	92,800
Sodium Hydrosulfide[2]	16721-80-5	Highly corrosive; incompatible with chemicals listed for ammonium sulfide	Flotation Reagent Depressant, Cation Exchange	1,400,000
Fuel Oil (Diesel #1) Dryer Fuel (Diesel #1)	8008-20-6	Flammable liquid	Moly. Collection, Truck Operation	150,000
Sulfuric Acid	7664-93-9	Strong Acid	Lab Use	<100
Water Treatment Chemicals & Antiscalant Reagents		NALCO9731 NALCO9735 (or equivalent)		

[1] Either ammonium sulfide or sodium hydrosulfide would be used as a flotation reagent.

[2] Chemicals include acids, alcohols, carbonates, esters, halogenated organics, ketones, organic sulfides, aldehydes, amides, combustibles, flammables, hydrazine isocyanates, organic peroxides, phenols, nitrites, organic nitro compounds, organophosphates, explosives, polymerizable compounds, epoxides, and oxidizing agents.

Either sodium hydrosulfide (NaSH) or ammonium sulfide [$(NH_4)_2S$] would be added to the circuit process as a flotation collector and depressant to affect the copper molybdenum separation. These reagents are rapidly oxidized through contact with copper minerals and air bubbles entrained in flotation pulp. These reagents would be transferred from a delivery truck to an appropriate on-site holding tank. Number 1 diesel fuel would be used as a molybdenum collector. Diesel fuel tanks onsite would be installed in conformance with applicable New Mexico Environment Department Petroleum Storage Tank Bureau regulations for New Storage Tank Systems in 20.5.4 NMAC. The expected volume of diesel for the site is less than 500,000 gallons, to be contained in two (2) 248,690 gallon above ground storage tanks (ASTs), 24 feet high, with a diameter of 42 feet. As required, secondary containment shall be constructed with a capacity of at least 110% of the size of the largest

AST in the containment area plus the volume displaced by the other AST(s). The geo-synthetic membrane for secondary containment shall have a minimum thickness of 60 mils.

Fuel oil would be kept in a 7,106 gallon capacity tank, 10 ft tall with an 11-ft diameter, also surrounded by secondary containment according to 20.5.4 NMAC. The geo-synthetic membrane for secondary containment shall have a minimum thickness of 60 mils.

NMCC plans to store less than 2,000 gallons of antiscalants in appropriate ASTs that meet industry standards. The antiscalants proposed would likely be NALCO9731 or NALCO9735 (or equivalent).

Reagents would be maintained in the reagent building, a structure made with 8" concrete block walls and a metal roof, 3,000 ft^2 in size, slab on grade construction, with a 6-inch concrete floor. On-site reagent storage is expected to be similar to the storage and processing employed by Quintana in 1982, as follows:

Lime storage: A 200-ton capacity silo, 24-ft tall and 20-ft in diameter would funnel lime into a lime feed pump tank and from there into two holding tanks;

Xantate (K.Amyl) (or equivalent): Flotation reagent Xanthate would be kept in drums and transferred to a mixing tank, then to a holding tank, and finally to the head tank;

AEROFLOAT 238 (or equivalent): used in flotation promoting, would be received in 50-gallon drums and have a plant storage capacity of 2,800 gallons. Aerofloat would be kept in drums and transferred to a mixing tank, then to a holding tank, and finally to a head tank.

MIBC (or equivalent): MIBC would be transferred from trucks to a holding tank, and, as needed, to a head tank.

AERODRI 100, used as a filter and dewatering aid, would arrive onsite in 500 pound drums. The reagent would be fed directly from the drums into the milling process. Use of small amounts (<100 pounds) of sulfuric acid would be limited to the laboratory.

Potential reagent spills would be contained by curbs in the reagent mixing and storage areas. A floor sump pump would be used to return the spilled material either to the storage tank or into the milling process as necessary. Material Safety Data Sheets (MSDS) for the reagents to be used would be readily available, in accordance with MSHA's *Hazard Communication for the Mining Industry* (30 CFR Part 47).

3.4.10.3 *Hazardous Materials Management*

The term "hazardous materials" is defined in 49 CFR§172.101; hazardous substances are defined in 40 CFR 302.4 and the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) as amended by the Superfund Amendments and Reauthorization Act (SARA) Title III. Hazardous materials would be transported to the Copper Flat Mine by DOT regulated transporters and stored on site in DOT approved containers. Spill containment structures would be provided for

storage containers. Hazardous materials would be managed in accordance with regulations identified in 40 CFR § 262 Standards Applicable to Generators of Hazardous Waste.

Hazardous materials and substances that may be transported, stored, and used at the Copper Flat Mine in quantities less than the Threshold Planning Quantity (TPQ) designated by SARA Title III for emergency planning would include blasting components, petroleum products, and small quantities of solvents for laboratory use. Small quantities of hazardous materials not included in the above list may also be managed at the Copper Flat Project; such materials are contained in commercially produced paints, office products, and automotive maintenance products.

Blasting components, including ammonium nitrate and diesel fuel, would be stored onsite in bins and tanks (see above), respectively. NMCC currently anticipates utilizing two explosives magazines (one for boosters and one for blasting caps), each no larger than 8 ft × 8 ft, with 1,000-pound capacities. In addition, NMCC would utilize one, 75-ton capacity, 3,000 ft^3 silo for storage of ammonium nitrate. All explosive materials would be stored away from the plant site in compliance with MSHA, New Mexico State Mine Inspector's regulations, and U.S. Department of Homeland Security requirements. The location of these facilities is indicated on **Figure 3-1**.

Management of hazardous materials at the Copper Flat Project would comply with all applicable federal, state, and local requirements, including the inventorying and reporting requirements of Title III of CERCLA, also known as the Emergency Planning and Community Right to Know Act.

All petroleum products, kerosene, and reagents used in the mill would be stored in above ground tanks within a secondary containment area capable of holding 110 percent of the volume of the largest vessel in the area. A preliminary Spill Contingency Plan (SCP) addressing the general topics presented below is presented in **Appendix E**. The SCP would be reviewed and updated at a minimum of every 3 years and whenever major changes are made in the management of these materials. Inspection and maintenance schedules and procedures for the tanks, as well as all piping connecting the facility with the tailings pond, would be set forth in sections of the SCP addressing hazardous materials and petroleum products.

Fuel and oil for diesel and gas powered equipment would be stored in above-ground, sealed tanks in the processing facilities area. The tanks would be installed on lined pads, consisting of gravel underlain by a plastic liner. The pad area would be surrounded by berms to provide secondary containment for the largest vessel in case of rupture. Surface piping leads from each tank to the fuel dispensing area. The refueling hoses would be equipped with overflow prevention devices and secondary containment.

Hazardous wastes other than those from the laboratory would also be managed in the short term storage facility prior to their shipment to an offsite licensed disposal facility. These materials may include waste paints and thinners. Spent solvents and used oils would be returned to recycling facilities. Waste oil and lubricants would be collected and hauled offsite by a buyer/contractor for recycling. Solvents would be collected by a subcontractor and recycled offsite.

An ongoing inventory of all materials used at the mine site and mill would be provided on a monthly basis to the appropriate federal, state, and local regulatory agencies. The local fire department would be kept informed about materials stored onsite and appropriate emergency response.

3.4.11 Spill Contingency

NMCC has developed a preliminary spill contingency plan (SCP) (**Appendix E**) to prevent and minimize the impacts of a reagent or fuel spill. This plan describes the reporting and response that would take place in the event of a spill, release, or other upset condition, as well as procedures for cleanup and disposal. The plan would be posted and distributed to key site personnel and would be used as a guide in the training of employees. Also, the plan would address mitigation of potential spills associated with project facilities as well as activities of onsite contractors. The use, transportation, and storage of reagents and fuels would be covered in the plan. The emergency reporting procedures would be posted in key locations throughout the project area. Containment structures designed to prevent the migration of a spill are included in the design of the facilities. NMCC would be responsible for events at the mine site, while contract haulers (i.e., trucking companies) would be responsible for accidents and spills along the transportation routes.

Fuel and oil for the diesel and gasoline-powered equipment would be stored in above ground, sealed tanks in the processing facilities area. The tanks would be installed on lined pads and surrounded by berms to contain the volume of the largest tank in the event of rupture.

Reporting spills or releases of certain materials to the environment may be divided into four categories: 1) those requiring internal notification only; 2) those also requiring notification to the State of New Mexico; 3) those also requiring notification to the National Response Center (NRC) and the local Emergency Planning Committee pursuant to CERCLA or Superfund; and 4) those subject to Clean Water Act requirements only. Determining which of the above categories is appropriate for any particular spill or release depends on the material spilled or released, the amount spilled or released, and the circumstances of the spill or release.

3.4.12 Monitoring

Baseline monitoring of current environmental conditions is currently being conducted in accordance with the *Sampling and Analysis Plan – Copper Flat Mine* (Intera, 2010), previously provided to the BLM under separate cover, and was developed to collect local and regional baseline information and provide the basis for monitoring of regional impacts that may result from operation of the mine. The Copper Flat Monitoring Plan would be updated as detailed engineering for the proposed mine facilities is completed, and the monitoring requirements become more defined.

3.4.13 Technical Updates

During the course of operations, NMCC would periodically review and update as necessary the geochemical and hydrogeological predictions, mine waste characterization studies, and pit lake studies to incorporate new information accumulated during operations. NMCC would review the

data every five years and make updates as necessary. These updates would provide quantitative predictions of water quality during the operational and post-closure period. Mitigation would be developed as necessary.

3.4.14 Growth Media/Cover Salvage and Storage

Any suitable growth media and cover material disturbed during construction or operation would be salvaged and stockpiled. A growth media management plan would be developed prior to construction activities.

Following stripping, growth media and cover would be stockpiled within the proposed disturbance areas. Growth media/cover stockpiles would be located such that mining operations would not disturb them. The surfaces of the stockpiles would be shaped after construction with overall slopes of 2.7H:1V or shallower to reduce erosion. To further minimize wind and water erosion, the soil stockpiles would be seeded after shaping with an interim seed mix developed in conjunction with the BLM. Diversion channels and/or berms would be constructed around the stockpiles, as needed, to prevent erosion from overland runoff. BMPs such as silt fences or staked straw bales would be used as necessary to contain sediment liberated from direct precipitation.

3.4.15 Sustainability

NMCC recognizes the social and economic impacts from "boom and bust cycles" that sometimes occur in connection with the mining industry. In addition, removal of facilities that may have post-mining uses is not in accordance with the overall environmental practice of conservation. NMCC would work with the local and regional communities to identify post-mining uses of the land and facilities to enhance opportunities to sustain the economy and culture in the post-mining phase of this project.

3.5 Operating Plans

Section 3809.401 of 43 CFR requires that the following operating plans be submitted with the Plan of Operations:

- **Water management**, including stormwater management, is discussed in Sections 3.2.3 and 3.2.7 (among others).
- Mine Waste Management Plan (**Rock Characterization and Handling Plan**) is provided in **Appendix C**;
- **Quality assurance plans**, some of which are located in **Appendix F**. The remaining quality assurance plans would be submitted to BLM prior to Plan of Operations approval;
- **Spill Contingency Plan** (SCP) located in **Appendix E** and briefly discussed in Section 3.4.11;
- **Reclamation Plan** presented in Section 5.5;
- Preliminary **Monitoring Plan** [*Sampling and Analysis Plan – Copper Flat Mine* (Intera, 2010)], previously submitted to the BLM under separate cover; and
- **Interim Management Plan** presented in Section 5.15.

4 Environmental Setting

4.1 Introduction

In accordance with 43 CFR § 3809.401(c), NMCC has prepared the following baseline environmental information to assist the BLM in analyzing potential environmental impacts as required by the NEPA and to determine if the NMCC plan of operations would prevent unnecessary or undue degradation. For the most part, this section contains a summary of the environmental setting of the mine area as described in the Copper Flat DEIS (BLM, 1996) and PFEIS (BLM, 1999). Additional details on the existing environment are provided in the various environmental baseline and impact reports prepared for the site since the mid-1970s, and are available upon request.

4.2 Geology

4.2.1 Regional Geologic Setting

The Copper Flat Mine lies within the Mexican Highlands portion of the Basin and Range Physiographic Province. It is located in the Hillsboro Mining District in the Las Animas Hills, which are part of the Animas Uplift, a horst on the western edge of the Rio Grande valley (Raugust, 2003). The Animas Uplift is separated from the Rio Grande by nearly 20 miles of Santa Fe Group alluvial sediments, referred to as the Palomas Basin of the Rio Grande valley. To the west of the Animas Uplift is the Warm Springs valley, a graben that parallels the Rio Grande valley (BLM, 1999; Raugust, 2003). Further west, the Black Mountains form the backbone of the Continental Divide, rising to about 9,000 feet above mean sea level (amsl). The surface geology of the Copper Flat region is shown in **Figure 4-1**, and a schematic geologic cross section is shown in **Figure 4-2**.

Basement rocks in the area consist of Precambrian granite and Paleozoic and Mesozoic sandstones, shales, limestones, and evaporites. Sedimentary units that crop out within the Animas Uplift include the Ordovician Montoya Limestone, the Silurian Fusselman Dolomite, and the Devonian Percha Shale. The Cretaceous-age Laramide orogeny, which was characterized by the intrusion of magma associated with the subduction of the Farallon plate beneath the North American plate, affected this region between 75 and 50 million years ago (Ma). Volcanic activity during the late Cretaceous and Tertiary periods resulted in localized flows, dikes, and intrusive bodies, some of which were associated with the development of the nearby Tertiary Emory and Good Sight-Cedar Hills cauldrons (**Figure 4-3**); later basaltic flows resulted from the tectonic activity associated with the formation of the Rio Grande rift. Tertiary and Quaternary alluvial sediments of the Santa Fe Group and more recent valley fill overlie the older Paleozoic and Mesozoic units in the area.

The geologic structure of the region is characterized by block and rift faulting (**Figure 4-3**). The Tertiary cauldrons associated with the earlier block faulting formed between 35 and 45 Ma. Rift faulting and associated north-south block faulting associated with continental extension and the formation of the Rio Grande rift began approximately 25 to 30 million years (Ma). The Las Animas

Hills are bounded by faults associated with rifting (Dunn, 1982). Continental extension continues to the present, as evidenced by north-south trending grabens represented by the Rio Grande and Warm Springs valleys.

4.2.2 Geology of Copper Flat Mine Site

4.2.2.1 *Stratigraphy*

As shown in **Figure 4-4**, the dominant geologic feature of the Animas Hills and Hillsboro district is the Copper Flat strato-volcano, a circular body of Cretaceous andesite that is 4 miles in diameter (Raugust, 2003). The andesite is generally fine-grained with phenocrysts of plagioclase (andesine) and amphibole in a groundmass of plagioclase and potassium feldspar and rare quartz. Some agglomerates or flow breccias are locally present, but the andesite is generally massive. Magnetite is a common association with the mafic phenocrysts, and accessory apatite is found in nearly every thin section (Dunn, 1984).

The strato-volcano is eroded to form a topographic low; the total depth of erosion is uncertain (SRK, 2010). To the east of the site, this andesite body is in fault contact with Santa Fe Group sediments, which are at least 2,000 feet (ft) thick in the area. Near-vertical faults characterize the contacts on the remaining perimeter of the andesite body; these faults juxtapose the andesite with Paleozoic sedimentary rocks. Drill holes indicate the andesite is more than 3,000 ft thick. This feature, combined with the concentric fault pattern, indicate that the local geology represents a deeply eroded Cretaceous-age volcanic complex (Dunn, 1982).

The core of the volcanic complex is a Cretaceous-age quartz monzonite stock that intruded into the center of the andesite body. Known as the Copper Flat Quartz Monzonite (CFQM), this irregular-shaped stock underlies a surface area of approximately 0.25 square miles and has been dated to approximately 75 million years before present (Raugust, 2003; BLM, 1999; and McLemore *et al.*, 2000). The monzonite crops out in only a few isolated areas, and the andesite at these contacts shows no obvious signs of contact metamorphism (Dunn, 1984). The CFQM is a medium-to coarse-grained, holocrystalline porphyry composed primarily of potassium feldspar, plagioclase, hornblende, and biotite; trace amounts of magnetite, apatite, zircon, and rutile are also present, along with localized mineralized zones containing pyrite, chalcopyrite, and molybdenite (McLemore *et al.*, 2000). About 15 percent of the monzonite is quartz, which occurs both as small phenocrysts and as part of the groundmass; however, quartz is absent in some parts of the stock (Dunn, 1984).

Numerous dikes, mostly latite, radiate from the CFQM stock, some nearly a mile in length. Most of the dikes trend to the northeast or northwest and represent late stage differentiation of the CFQM stock (Raugust, 2003). Immediately south of the quartz monzonite, the andesite is coarse-grained, perhaps indicating a shallow intrusive phase. An irregular mass of andesite breccia along the northwestern contact of the quartz monzonite contains potassium feldspar phenocrysts and andesitic rock fragments in a matrix of sericite with minor quartz; this may represent a pyroclastic unit. Magnetite, chlorite, epidote, and accessory apatite are also present in the andesite breccia (Dunn, 1984).

The southwestern edge of the andesite body was intruded by the Warm Springs Quartz Monzonite pluton, which dates to approximately 73 Ma (Hedlund, 1974). Unlike the CFQM and the andesite, this monzonite body is not cut by the latite dikes (SRK, 2010), indicating that the dikes were emplaced prior to the Warm Springs Quartz Monzonite.

The Sugarlump Tuff (35 Ma) and the Kneeling Nun Tuff (34 Ma) unconformably overlie the local andesite flows. These tuffs erupted from the Emory caldera, and indicate that the Copper Flat volcanic/intrusive complex was buried during the Oligocene and exhumed during Miocene uplift (around 21.7 ±3.6 Ma) (Kelley and Chapin, 1997). Both the andesite and the quartz monzonite intrusions are cut by black, scoriaceous basalt dikes. These dikes remain unaltered, and appear to be associated with locally abundant Pliocene alkali basalt flows from around 4 Ma (Seager *et al.*, 1984).

4.2.2.2 ***Structure***

Three principal structural zones are present at the site and surrounding area, the most prominent of which is a northeast-striking fault trend that includes the Hunter and parallel faults. In addition, west-northwest striking zones of structural weakness are marked by the Patten and Greer faults, and east-northeast striking zones are marked by the Olympia and Lewellyn faults. All faults have a near-vertical dip; the Hunter fault system dips 80°W, and both the Olympia and Lewellyn fault systems dip between 80°S and 90°S (SRK, 2010; Dunn, 1984). These three major fault zones appear to have been established prior to the emplacement of the CFQM and controlled subsequent igneous events and mineralization (SRK, 2010).

The CFQM emplacement is largely controlled by the three structural zones. The southern contact parallels and is cut by the Greer fault, although the contact is cut by the fault, and the southeastern and northwestern contacts are roughly parallel to the Olympia and Lewellyn faults, respectively. The elongate neck of the stock parallels the Hunter fault system. Whether there was movement along the fault zones before the emplacement of the stock has not been determined (SRK, 2010; Dunn, 1984).

Although the latite dikes strike in all the three principal fracture directions, most of the dikes strike northeast. A narrow zone of fault gouge commonly occurs along the contact between the dikes and the andesite, with the mineralization post-dating fault movement (Harley, 1934). The northeast fault zones contain a high proportion of wet gouge, often with no recognizable rock fragments. Underground exposures of the Hunter fault zone (in previously existing mine workings) material has the same consistency as wet concrete and has been observed to flow in underground headings. However, the material in the east-northeast fault zones contains only highly broken rock and little obvious gouge. The width of the fault zones in both systems varies along strike from less than a foot to nearly 25 ft in the Patten fault east of the Project. Despite intense brecciation, the total displacement along the faults does not appear to exceed a few tens of feet (Dunn, 1984). At the western edge of the site, a younger porphyritic dike was emplaced in a fault that had offset an early latite dike, indicating that fault movement occurred during the time that dikes were being emplaced (Dunn, 1984).

Post-dike movement is evident in all the three principal fault zones, and both the Hunter and Patten fault systems show signs of definite post-mineral movement. Fault movement has smeared sulfide deposits and offset the breccia pipe as well as the zones within the breccia pipe. Post-mineral

movement along faults has resulted in wide, strongly brecciated fault zones. Some of the post-mineral dikes have been emplaced within these fault zones (SRK, 2010; Dunn, 1984).

NMCC has mapped the pit area and diversion cuts in detail at 1 inch:40 ft (1:480) and has examined the pre-and post-mineral stress orientations in the andesites and CFQM. Findings indicate no significant difference in the stress fields before and after mineralization (SRK, 2010).

4.2.3 Description of the Ore Body

Copper Flat is an alkalic copper-gold mineralized breccia pipe, associated with and genetically-linked to an alkalic porphyry system. Copper Flat is situated along the eastern edge of the Cretaceous Arizona-Sonora-New Mexico porphyry copper belt, and, along with Tyrone, New Mexico, forms a linear mineralized feature known as the Santa Rita lineament (SRK, 2010; McLemore *et al.*, 2000). Copper Flat is the easternmost and one of the oldest known porphyry deposits in the southwestern U.S. (Hedlund, 1974; Dunn, 1982; Titley, 1982). Analogous deposits include Terrane Metal's Mount Milligan, British Colombia deposit and the Continental breccia pipe located near Hanover in the Central Mining district of New Mexico (SRK, 2010).

4.2.3.1 *Structure and Model*

Mineralization at the site is concentrated in a breccia pipe within the CFQM stock (Raugust, 2003; BLM, 1999). The eastern portion of the breccia pipe is outside the outline of the main mineralization; however, the rest of the breccia pipe is higher grade than the surrounding CFQM, hosting nearly half of the copper at the site, but only about one-third of the total resource tonnage (SRK, 2010). Drillholes spaced approximately 100 ft apart within the center of the deposit indicate the breccia pipe occurs as a single, continuous body, approximately 1,300 ft long by approximately 600 ft wide at the surface with the long axis perpendicular to the predominant northeast fracture direction. It is exposed in only a few places, but extends vertically to over 1,000 ft; veins of coarse pegmatitic material have been found at approximately 1,700 ft below ground surface (bgs) in one drillhole (Dunn, 1984).

Mineralized poly-metallic quartz veins, commonly associated with the dikes that radiate outward from the central stock, have been the target of historical mining activities in the Hillsboro district. The breccia pipe zone has been cut by numerous, randomly oriented, irregular veins that are thicker and coarser grained than the narrow fracture-controlled veinlets in the surrounding stock.

Mineralization appears to have been contemporaneous with pipe formation (SRK, 2010). The lack of rock flour or gouge in the matrix suggests that brecciation was not the result of tectonic movement, while the apparent lack of appreciable movement between the fragments and the gradational contact between the breccia and the zone of stockwork veining indicate that an explosive mechanism was not the source of the brecciation. Likewise, the process of mineralization stoping described by Locke (1926), which would have resulted in appreciable downward movement and mixing of the fragments, is not supported by field observations. Thus the mechanism responsible for the formation of the Copper Flat mineralized breccia pipe appears to be autobrecciation resulting from retrograde boiling, a phenomenon that occurs when the pressure of the mineralizing hydrothermal fluid exceeds the confining pressure (Phillips, 1973). The matrix of the breccia, the irregular veins in the surrounding

crackle breccias, and the open space filling in the breccias consist of hydrothermal minerals and part of the second stage mineralization occurred as replacement, which modified the original breccia texture (SRK, 2010).

Unlike most deposits in the southwestern U.S., Copper Flat shows very little supergene enrichment or the symmetrical and telescoped zoning of alteration types that is considered typical of most porphyry copper deposits. Instead, hypogene mineralization and alteration, including the formation of the breccia pipe, was the result of the final crystallization of the CFQM melt and related dikes (SRK, 2010).

The current model used by NMCC for further exploration at the site is based on Richards (2003), who interprets the area as an eroded volcano. According to this model, mineralization occurred at similar depths to that found at El Teniente in Chile; since the Copper Flat breccia pipe now crops out at the surface, this assumption indicates that approximately 0.5 to 2 kilometers (km) of volcanic rocks have been eroded from the central zone of mineralization. Fluid inclusion work by Norman *et al.* (1989) and McLemore *et al*. (2000) suggest that the breccia pipe and veins formed at a depth of 1 to 2 km bgs and at temperatures ranging from 226° to 360°C.

4.2.3.2 *Mineralization*

During the early mining days, a 20-to 50-foot leached oxide zone existed over the ore body, but this material was stripped during the mining activities that occurred in the early 1980s. Most of the remaining ore is unoxidized and consists primarily of chalcopyrite and pyrite with some molybdenite and traces of galena and sphalerite. Appreciable amounts of silver and gold are also present (BLM, 1999; SRK, 2010). The proven and probable reserves are estimated at more than 50 million tons of ore with 0.45 percent copper (Hydro Resources, 2002).

The breccia consists largely of fragments of mineralized CFQM, with locally abundant mineralized latite where dikes exposed in the CFQM projected into the brecciated zone. Andesite occurs only as mixed fragments partially in contact with intrusive CFQM and appears to represent the brecciation of andesite xenoliths in the CFQM (Dunn, 1984). The matrix contains varying proportions of quartz, biotite (phlogopite), potassium feldspar, pyrite, and chalcopyrite, with magnetite, molybdenite, fluorite, anhydrite, and calcite locally common. Apatite is a common accessory mineral. Much of the quartz-feldspar matrix has a pegmatitic texture. Breccia fragments are rimmed with either biotite or potassium feldspar, and the quartz and sulfide minerals have generally formed in the center of the matrix (Dunn, 1984).

The andesite in contact with the CFQM, dikes, and veins is typically altered into one of three types of mineral assemblages: biotite-potassic, potassic, or sericitic alteration (Fowler, 1982). The highest copper grades are associated with the biotite-potassic alteration, which is characterized by hydrothermal biotite, potassium feldspar, quartz, and pyrite, and which occurs in veinlets and as replacement assemblages in the monzonite (McLemore *et al.*, 2000).

The total sulfide content ranges from 1 percent (by volume) in the eastern part of the breccia pipe and the surrounding CFQM to 5 percent in the CFQM to the south and west (SRK, 2010). Sulfide content is highly variable within the breccia, with portions containing as much as 20 percent sulfide

minerals. Sulfide mineralization is restricted to the CFQM and breccia pipe, and drops abruptly at the andesite contact. Minor pyrite mineralization extends into the andesite along the pre-mineral dikes (SRK, 2010; Dunn, 1984). Pyrite and chalcopyrite are disseminated within the CFQM and also occur along fracture-controlled veinlets and as disseminations associated with mafic minerals. Typically, pyrite is more abundant than chalcopyrite in two areas (SRK, 2010):

- A narrow zone that surrounds and overlies the western end of the breccia pipe, which has the highest grade CFQM mineralization, characterized by abundant chalcopyrite in quartz-sulfide veinlets; and
- Outcrops to the southeast of the breccia and south of Greyback Wash, where disseminated chalcopyrite is present with no associated pyrite.

Molybdenite occurs occasionally in quartz veins or as thin coatings on fractures. Minor sphalerite and galena are present in both carbonate and quartz veinlets in the CFQM stock (Dunn, 1984).

4.3 Climate

The Copper Flat Mine lies within the belt of mid-latitude westerly winds, where the prevailing direction is from the west. Winds at the Truth or Consequences, New Mexico, airport, located about 30 miles northeast of the site, are generally from the northwest; however, the Black Range and foothills cause local variations in the winds. At Copper Flat, the wind direction is predominantly west to east, and secondarily north to south. Local wind speeds average about 10 to 15 miles per hour, although winds in excess of 50 miles per hour may occur at times. Temperature inversions are rare at Copper Flat, but are more common farther east along the Rio Grande valley, especially during the winter months. Vertical air dilution is generally good because of the area's high surface temperatures, creating strong daytime thermal mixing. Thermal mixing and moderate winds generally tend to suppress occasional nighttime inversions. The presence of higher winds and the lack of inversions contribute to a relatively clean atmosphere at the site since any pollutants are readily mixed and dispersed (BLM, 1999).

Temperature data for the site show a wide diurnal and seasonal variability, which is typical of dry climates. The warmest temperatures occur in June and July and the coldest temperatures usually occur in December and January. In spring and fall, daily maximum temperatures are moderate, typically averaging 65 to 85 degrees Fahrenheit (°F). Nights are cooler, with low temperatures averaging 32 to 50°F. Winter temperatures are frequently below freezing at night, but can be above 50°F during the day. During summer, temperatures can approach 100°F during the day. Daily temperature fluctuations of 30°F are common throughout the year (BLM, 1999).

Precipitation at the site averages about 13 inches per year (ranging from nearly 3 inches in 1956 to over 20 inches in 1986). As much as half of the annual precipitation occurs in the form of intense thunderstorms during July, August, and September, when moist air enters the region from the Gulf of Mexico. Summer thunderstorms can result in heavy rainfall and flash floods. Average monthly precipitation in January through June is typically 0.50 inch or less. Snowfall is possible from October through April, but most likely (greater than 1 inch) between December through February (BLM, 1996).

Evaporation exceeds precipitation in southwestern New Mexico. Pan evaporation data, the most commonly collected data, are correlated with lake evaporation (i.e., free water surface evaporation) to predict evaporation from reservoirs and lakes. Lake evaporation at the site is estimated to be approximately 58 to 65 inches per year, and pan evaporation is estimated to be approximately 80 to 90 inches per year (SRK, 1995).

4.4 Hydrology

4.4.1 Surface Water

The Copper Flat area falls within the Lower Rio Grande watershed, as defined by the New Mexico Water Quality Control Commission (WQCC). This watershed includes approximately 5,000 square miles in Catron, Socorro, Sierra, and Doña Ana Counties and is dominated by the Rio Grande and its tributaries as well as the two large reservoirs of Elephant Butte and Caballo. Numerous ephemeral tributaries feed into the Rio Grande from the west, but none contribute perennial flow to the Rio Grande.

The following sections provide background information about surface water resources in the vicinity of the Copper Flat Mine, and summarize pertinent historical data related to surface water sampling.

4.4.1.1 *Surface Water Characteristics of Site and Vicinity*

The site is drained by ephemeral streams (arroyos) within the Greenhorn Arroyo drainage basin, a 6th level sub-watershed defined by the Hydrologic Unit classification system (Seaber *et al*., 1987) that drains 29,414 acres of land on the eastern slope of the Animas Uplift to a single outlet into the Rio Grande (**Figure 4-5**). Flows within the Greenhorn Arroyo drainage basin are ephemeral, as they only occur in direct response to precipitation. As a result, this drainage, similar to others in the region, does not contribute any perennial surface water flow to the Rio Grande.

Numerous arroyos contribute to the trunk channel of Greenhorn Arroyo. Of these, Greyback Wash is the primary drainage through the site. Greyback Wash originates west of the site and drains eastward along the site axis until it converges with the trunk channel of Greenhorn Wash approximately 8 miles east of the site boundary (**Figure 4-5**). In pre-mining times, Greyback Wash drained directly through the mine area, but was later re-routed around the southern perimeter of the mine area for flood control purposes (Raugust, 2003). Newcomer and Finch (1993) measured flow rates in Greyback Wash of 12.5 gallons per minute (gpm) in March 1993 at a point east of the pit and former plant site. Three seeps have been identified along Greyback Wash (BLM, 1999). One seep with riparian vegetation is located near a buried storm water collection pond, a second is located downstream from the first seep and supports a small cottonwood/willow stand, and the third is south of the operations area (**Figure 4-5**).

Two creeks drain basins directly to the north and south of the Greenhorn Arroyo drainage basin: Las Animas Creek in the north and Percha Creek to the south (**Figure 4-5**). Both Las Animas and Percha Creeks have ephemeral, intermittent, and perennial reaches. Stream flow in Las Animas Creek varies from perennial to intermittent from the area near sampling site MAS (**Figure 4-5**) to Caballo

Reservoir (BLM, 1999). For example, Davie and Spiegel (1967) show flow rates ranging from about 450 to 900 gpm in the upper reach (T14S R7W, Sections 34 through 36, near sampling sites LAC-A and LAC-B in **Figure 4-5**) and middle reach (within T15S R5W) of the creek; according to Davie and Spiegel, these reaches are "losing reaches" of the creek. Stream flow in Percha Creek is intermittent in the Hillsboro reach and perennial in the area known as the Percha Box, a steep-walled reach of the drainage that has incised into Paleozoic bedrock (BLM, 1996) (**Figure 4-5**). SRK (1995) reported measurable stream flows just east of the Percha Box of roughly 200 to 250 gpm. This was the only reach of Percha Creek with measurable flows during the SRK sampling period. Though both Las Animas Creek and Percha Creek have perennial reaches, neither creek contributes perennial flow to the Lower Rio Grande Basin.

Two springs are located within the Greenhorn Arroyo drainage basin to the north and west of the site (**Figure 4-5**). Other unnamed seeps occur in the pit walls surrounding the pit lake after precipitation events; these are likely the result of fractured flow through the bedrock exposed in the pit wall. Several springs in the Percha Creek basin and one in the Las Animas Creek basin have been identified for sampling, but have been studied less than those within the Greenhorn Arroyo basin. As a result, there is little information on their flow rates or quality, although Newcomer and Finch (1993) did attempt to measure flow.

The open pit that was mined during the early 1980s now contains a lake. Since 1989, the pit lake has been sampled for water quality at various locations and depths, including samples collected by past operators of the mine, state regulatory agencies, and academic researchers studying the mine (BLM, 1999).

4.4.1.2 *Historical Data*

Existing surface water data relevant to the NMCC sampling plan are discussed in this section. Surface water at the site was most recently investigated by SRK (1995), who collected flow and water quality from Percha Creek and Las Animas Creek. Newcomer *et al.* (1993) performed a hydrologic assessment of the Greenhorn Arroyo drainage basin, measuring flow and water quality along Greyback Wash and at a number of seeps and springs. The oldest known surface water investigation at the site was performed by Davie and Spiegel (1967), who collected flow data for Las Animas Creek. Results of these investigations were compiled by Raugust (2003) and are also summarized in PFEIS (BLM, 1999).

4.4.1.2.1 Volumetric Flow

4.4.1.2.1.1 Streams

Flow rate data for streams at the site are limited by the generally intermittent nature of flows. Measurements of flows were made by Newcomer *et al*. (1993) and Adrian Brown Consultants (1996). Additional historical measurements were compiled in the PFEIS (BLM, 1999). These data are summarized in the *Sampling and Analysis Plan – Copper Flat Mine* (Intera, 2010), provided to the BLM under separate cover.

Greyback Wash is an ephemeral stream and generally flows only during periods of snow melt or rain events. Flow rates in Greyback Wash at SWQ-3 (**Figure 4-5**) were measured by Newcomer *et al*. (1993) to be 12.5 gpm (0.028 cubic feet per second [cfs]) in March of 1993.

Two measurements of flow rate are recorded for Las Animas Creek. Davie and Spiegel (1967) reported flows of between 1.0 and 2.0 cfs in the creek's upper reaches and between 1.0 and 1.5 cfs in its middle reaches (BLM, 1999). Adrian Brown Consultants made a single flow measurement of 245 gpm (0.546 cfs) at LAC-E (**Figure 4-5**) in 1996.

Volumetric flow in Percha Creek was measured at 13 locations by Adrian Brown Consultants (1996), from approximately ¼ mile upstream of the entry to Percha Box to approximately 5 miles downstream of the exit from Percha Box. Flow was found to be localized, occurring within and immediately to the east of Percha Box, and ranging from 456 gpm (1.02 cfs) to 119 gpm (0.265 cfs), with many reaches dry or with standing water only.

4.4.1.2.1.2 Springs and Seeps

Spring and seep flow rates are infrequently reported in the available literature for the site and surrounding areas. Several springs and seeps have been identified within the Greenhorn Arroyo drainage basin. Two springs, identified as BG and BG-2, are located to the north and west of the site (**Figure 4-5**) and several unnamed seeps occur in the walls surrounding the pit lake. BG and BG-2 were judged by Newcomer *et al*. (1993) to be ephemeral. The seeps along the pit walls are observed to flow in response to precipitation events, and, as mentioned above, are likely the results of fractured flow through the bedrock exposed in the pit wall. All known springs and seeps in the Greenhorn Arroyo drainage basin are upgradient of the proposed mine water discharge location. Other seeps and springs shown in **Figure 4-5** have not been measured in the past and thus have no associated historical flow information.

4.4.1.2.2 Water Quality

4.4.1.2.2.1 Streams

The surface water chemistry of Greyback Wash was initially investigated in 1977 at three locations as part of an environmental assessment prepared by the BLM in response to an application by Quintana Minerals Corporation for an open pit copper mine at the site (BLM, 1978). The three locations sampled in 1977 generally correspond to the sampling locations proposed in **Figure 4-5**, with one location upstream of the permit boundary, one within the site approximately 300 yards from the mine rim, and a third located where the arroyo leaves the site (BLM, 1978). Water samples were collected in January, March, and July of 1977.

WQCC standards for metals were not exceeded at any location in any of the 1977 sample events. Results for pH (7.6–8.1) were in the same range as samples collected later at these three locations. Total dissolved solids (TDS) results upstream of the site (720–1000 milligrams per liter [mg/L]) were comparable to those of samples collected later, but samples taken at locations within and downstream of the site were comparatively lower (800–1,320 mg/L) than the results for later sampling events such as those conducted by Newcomer *et al.* (1993) at SWQ-1 (upgradient of the pit

lake), SWQ-2 (downgradient of the pit lake but within the area of mining disturbance), and SWQ-3 (approximately 1 mile downgradient of the pit lake) (**Figure 4-5**). Field parameters measured by Newcomer *et al*. are shown in Table 8-1 of the *SAP* (Intera, 2010). Water quality in Greyback Wash upstream of the pit lake at SWQ-1 had a pH ranging from 7.4 to 8.3, sodium at 107 milligrams per liter (mg/L), bicarbonate values ranging from 400 to 500 mg/L, sulfate ranging from 275 to 300 mg/L, and TDS ranging from 780 to 965 mg/L. At SWQ-2, sodium concentration increased from the previous sampling event by BLM to 270 mg/L, sulfate increased to between 1,150 and 1,650 mg/L, TDS increased to between 2,300 and 3,300 mg/L, and pH and metal concentrations remained essentially unchanged. Water quality indicators at SWQ-3 fell within the range of values at SWQ-2.

Las Animas Creek water quality was examined by Adrian Brown Consultants (1996) and for the PFEIS (BLM, 1999). Adrian Brown Consultants obtained a single sample at LAC-E, with a pH of 7.81, sulfate concentration of 18 mg/L, and TDS of 300 mg/L. The PFEIS reports that Las Animas Creek water quality is dominated by calcium or sodium bicarbonate, with pH in the range 7.0 to 8.0, sulfate in the range 20 to 70 mg/L, and TDS in the range 300 to 400 mg/L. Occasionally, sodium and chloride are higher, with chloride concentrations as high as 300 to 400 mg/L, possibly due to agricultural practices along the creek (BLM, 1999).

Percha Creek water quality was examined by Adrian Brown Consultants (1996) and for the PFEIS (BLM, 1999). Adrian Brown Consultants sampled Percha Creek at the entry and exit to Percha Box, and 5,000 feet (ft) downstream from the exit from Percha Box, and measured field parameters at all seven locations in which water was found [Table 8-1 of the SAP (Intera, 2010)]. For the three samples submitted for laboratory analysis, pH ranged from 7.62 to 7.82, sulfate ranged from 63 to 71 mg/L, and TDS ranged from 336 to 406 mg/L. The PFEIS (BLM, 1999) reports that surface water flowing in Percha Creek has a chemistry dominated by calcium bicarbonate, with pH in the range of 7.0 to 8.0, sulfate in the range of 20 to 70 mg/L, and TDS in the range of 300 to 400 mg/L.

Sampling of the Caballo Reservoir, the receiving water for these drainages, during November 1994, showed the water to be dominated by sodium bicarbonate with bicarbonate values of 180 mg/L and sulfate values of 110 mg/L (SRK, 1995). As summarized in the PFEIS (BLM, 1999) chloride values were less than 100 mg/L and TDS was 440 mg/L. The water chemistry was within WQCC standards for metals, sulfate, chlorine, pH, and TDS. As a comparison, water samples from the Rio Grande at EI Paso, Texas were sodium sulfate-dominated with high TDS in the range of 800 to 1,000 mg/L, sulfate values of 200 to 340 mg/L, and bicarbonate values of around 100 mg/L (Wilson *et al*., 1981).

4.4.1.2.2.2 Springs and Seeps

Newcomer *et al*. (1993) sampled the BG and BG-2 springs in April 1993 and Adrian Brown Consultants observed and sampled seeps in the pit wall in August 1997 (ABC, 1997). Field parameters and water chemistry analytical data for these locations are presented in Table 8-1 of the *SAP* (Intera, 2010), respectively. Samples from BG and BG-2 had pH ranging from 8.0 to 8.2, sodium ranging from 90 to 124 mg/L, bicarbonate ranging from 411 to 535 mg/L, sulfate ranging from 184 to 228 mg/L, and TDS ranging from 680 to 690 mg/L. The pit wall sample had a pH of 8.16, a sulfate content of 3,100 mg/L and TDS of 5,020 mg/L. On the basis of these results, ABC (1997) judged BG and BG-2 to be qualitatively similar to the Greyback Wash sample location SWQ-

1, while the pit wall location appears to have been subject to a similar process as the locations at SWQ-2 and SWQ-3.

4.4.1.2.2.3 Pit Lake

The 12.8-acre lake that has formed in the existing pit (**Figure 4-6**) is estimated to be about 40 ft deep, based on a pit bottom elevation of 5,380 ft above mean sea level (amsl) and water level elevation of 5,420 ft amsl as measured in 1986 (SRK, 2010). The water quality of the pit lake has been sampled at various depths and locations since the initial samples were collected on April 13, 1989, by the New Mexico Environment Improvement Board (Raugust, 2003); the latest samples were collected in January 2010. Raugust (2003) concluded that the collective data show several trends in the variability of water quality over time, mainly that evapo-concentration and buffering processes are influencing the quality of the lake water. Pit water has historically exceeded the WQCC standards for sulfate, chloride, TDS, manganese, and uranium (20.6.2.4103 of the New Mexico Administrative Code) and has occasionally dropped below the regulatory pH range of 6 to 9 s.u.

Analytical results of samples collected from 1989 to 1998 suggest that sulfate, chloride, TDS, manganese, and pH all increased over this period. For example, sulfate increased from a range of 2,250 to 3,000 mg/L to a range of 3,500 to 4,300 mg/L over this time period. Chloride increased from an average of around 100 mg/L to around 250 mg/L, which may be attributed to lower average annual precipitation and higher annual temperatures during this period (BLM, 1999). However, the sulfate-to-chloride ratio dropped during this time period, suggesting that sulfate rose at a slower rate than chloride due to the formation of gypsum and the subsequent buffering of the sulfate concentration in pit lake water by gypsum (gypsum is observed along the margins of the pit lake during the summer months, when the pit lake level has dropped). TDS ranged from 2,700 mg/L in 1991 (Newcomer *et al*., 1993) to about 6,000 mg/L in 1998 (Raugust, 2003). Manganese ranged from 1.8 to 4.3 mg/L (BLM, 1999). The measured pH values have generally increased over time to about 8.0 s.u. However, in 1992 and again in 2008, pH decreased to 4.4 and 4.5 (NMED GWQB, 2008), respectively, deviating from the overall trend of elevated pH values. The overall rise in the pH may be due to buffering by wall rock or groundwater alkalinity. There is no historical data available for uranium, other than a sample collected in 2004 that showed the water exceeded the WQCC standard (NMED GWQB, 2008).

Variability in the methods, locations, and depths from which samples were collected may explain many of the differences observed in pit water quality results. However, samples collected in January 2010 confirm that concentrations of sulfate, chloride, TDS, and manganese have increased. The 2010 sampling yielded a sulfate concentration of 5,200 mg/L, chloride concentration of 390 mg/L, TDS concentration of 7,770 mg/L, and manganese concentration of 41 mg/L, all of which were higher than previous measurements from the 1989 to 1998 period. In addition, concentrations of aluminum, copper, cobalt, iron, and fluoride in the 2010 sample all exceeded WQCC standards. In contrast, pH, the most widely variable parameter measured during the 1989 to 1998 period, was 6.3 in January 2010, within the acceptable range of 6 to 9.

Other key studies that discuss the water quality are summarized in SRK (1997) and include hydrogeologic and hydrogeochemical studies (SRK, 1995), post-closure pit water balance model calculations (SRK, 1997), water quality and host-rock geochemical studies (SRK, 1997), and post-hearing submittals that followed the 1997 New Mexico Mine Permit public hearing.

4.4.2 Groundwater

Groundwater is a major supply of water for domestic, agricultural, mining, and industrial use in southern New Mexico. The high evaporation rate during the long, hot summers coupled with low average annual precipitation in the area result in surface waters being an unreliable source of water on a year-round basis. The Rio Grande is the only significant nearby surface water resource. Intermittent streams that feed the Rio Grande, such as Las Animas Creek and Percha Creek in the site area, are local sources of water for at least part of the year. The Rio Grande and associated shallow alluvial deposits of its inner valley also served as the ultimate discharge zone for pre-development groundwater flow from the adjacent Greenhorn Arroyo, Las Animas Creek, and Percha Creek drainage basins (Hawley *et al*., 2005, Wilson *et al*. 1981). Additional water comes from shallow domestic and agricultural wells. This section provides a description of the regional and local groundwater along with a proposed sampling and analysis approach to characterizing baseline conditions of groundwater resources.

4.4.2.1 *Regional Hydrogeology*

The site is located in the Lower Rio Grande Underground Water Basin (LRGB), which extends from Elephant Butte Dam to the Texas Border near El Paso and is one of New Mexico's principal agricultural regions (**Figure 4-7**). The LRGB was declared by the NM State Engineer on September 11, 1980. As a result, the underground waters of the LRGB are administered by the State Engineer. A water master district that encompasses the Hot Springs, Las Animas Creek, and Lower Rio Grande Underground Water Basins was created to assist with water administration in the region.

Groundwater in the LRGB generally flows from the highlands on either side of the basin through bedrock and valley alluvium to the center of the basin and to the Rio Grande. **Figure 4-8** illustrates the conceptual model of groundwater flow at the site. The bedrock aquifer in the Paleozoic sedimentary rocks are recharged by rainfall and snowmelt through bedrock faults and bedding planes exposed in the highlands west of the Project site. This water generally flows along a hydraulic gradient toward the approximate center of the Rio Grande Valley. Occasionally, this deep regional flow discharges at the ground surface as springs along faults where the Paleozoic bedrock crops out within the valley. This occurs in at several locations within the Las Animas Creek and Percha Creek drainage basins (**Figure 4-9**). The water table elevation near the existing pit lies at approximately 5,450 to 5,500 feet (ft) above mean sea level (amsl). Groundwater near Caballo Reservoir lies at about 4,200 ft amsl, indicating a drop of 1,300 ft over approximately 14 to 15 miles.

Valley alluvium is generally recharged by precipitation along mountain fronts where the alluvial fans are exposed and by streams that flow out of the highlands and lose water to the alluvium as they flow toward the Rio Grande. Many intermittent streams in the area are "losing streams" over at least part

of their courses and provide recharge to the alluvial groundwater system. This alluvial groundwater then flows downgradient to the Rio Grande.

4.4.2.1.1 Hydrogeology of the Permit Area

Three aquifers exist in the project area, as shown schematically on **Figure 4-8**. The deepest aquifer is the crystalline bedrock aquifer that receives water from the highlands to the west of Animas Peak and carries this water along bedding planes, faults, and solution cavities toward the center of the LRGB. The crystalline bedrock aquifer consists of Cretaceous andesite and monzonite breccias underlain by Paleozoic rocks in the Animas Uplift area, Tertiary volcanic rocks to the west of the pit lake in the graben associated with the Animas uplift, and Paleozoic sedimentary rocks to the east of the pit lake area in the Palomas Basin. The Santa Fe Group aquifer system, which consists of interbedded sandstones, silts, and clays, overlies the Paleozoic bedrock units to the east of the pit lake area within the Palomas Basin. This aquifer system receives water from precipitation and from the losing reaches of streams. The uppermost aquifer at the site is the Quaternary alluvial aquifer along Las Animas and Percha Creeks (**Figure 4-9**). This alluvium is up to 40-ft thick in the Las Animas Creek area and carries water that is in hydraulic equilibrium with the water flowing in Las Animas Creek (BLM, 1999). The Percha Creek alluvial aquifer is less studied than the Las Animas Creek alluvial aquifer, and as a result, less historical data about its aquifer characteristics are available. The aquifers of greatest importance in terms of water supply in the area are within the Palomas Basin to the east of the pit lake and include the intermediate Santa Fe Group aquifer system and the alluvial aquifer associated with Las Animas Creek.

Figure 4-10 from the Adrian Brown Consultants (ABC) (1998b) presents a piezometric contour map showing the general configuration of groundwater level elevations at the site as interpreted at that time. Groundwater levels near the existing pit are approximately 5,450 ft amsl, and at Caballo Reservoir, the levels are about 4,200 ft amsl. The map indicates that groundwater flow is generally to the east toward Caballo Reservoir. Hydraulic gradients are relatively large (closely spaced contours) in the western portion of the site, reflecting lower transmissivity in the bedrock aquifer and in the western portion of the Palomas Basin in the Santa Fe Group aquifer system. The wider spacing of contours in the eastern portion of the site suggests that transmissivity of the Santa Fe Group aquifer increases toward Caballo reservoir. The widest spacing of contours (highest transmissivity) appears to occur in the area of the groundwater production well field (wells PW-1, 2, 3, and 4 on **Figure 4-10**). This area coincides with an interpreted graben structure, which reflects an increased thickness of the Santa Fe Group in this area.

4.4.2.1.2 Aquifer Characteristics in the General Plan Area

4.4.2.1.2.1 Crystalline Bedrock Aquifer Characteristics

Groundwater within the Hillsboro Mining District and the area of the present open pit occurs in andesitic volcanic rocks and quartz monzonite breccia intrusive rocks (**Figure 4-8**). The current pit lake was reported by SRK (1997) to be at an elevation of 5,442 ft amsl, which is about 50 to 100 ft below the pre-mining ground elevation [5,500 to 5,540 ft amsl reported in the PFEIS (BLM, 1999)]. Groundwater levels measured in the pit and tailings areas as of 1997 are shown on **Figure 4-11**.

Newcomer *et al*. (1993) reported a pre-mining (1981) water level of 5,370 ft amsl in well GWQ-5, which is approximately 4,000 ft east-southeast from the pit and within the old plant site area. These authors also reported a water level of 5,360 ft amsl in the Hillscher West well (GWQ-6), which lies approximately 2,500 ft southeast from well GWQ-5. These limited groundwater elevation data suggest that the groundwater gradient in the andesitic volcanic rocks may be to the east or southeast from the current pit lake area as shown on **Figure 4-11**. Within 500 ft of the pit lake (see **Figure 4-12**), however, groundwater gradients are toward the pit lake, which may act as a local evaporative sink (BLM, 1999).

In January 2010, NMCC resurveyed the pit lake and as many of the groundwater monitoring wells established for the PFEIS as could be located. The pit lake elevation was 5,444 ft amsl in January 2010, revealing that the pit lake elevation remains below the pre-mining water level elevation of 5,500 to 5,540 ft amsl.

4.4.2.1.2.2 Santa Fe Group Aquifer System

Overview

Overlying the crystalline bedrock aquifer at the Project site is the Santa Fe Group aquifer system, a system that is locally represented by two hydrostratigraphic units (HSUs): (1) the Upper Santa Fe Group hydrostratigraphic unit (USF), and (2) the Middle Santa Fe Group hydrostratigraphic unit (MSF). As defined by Hawley and Kennedy (2004), these hydrostratigraphic units are mapable bodies of basin and valley fill that are grouped according to genesis and position in both lithostratigraphic and chronostratigraphic sequences. Informally, these HSUs comprise the major basin-fill aquifer zones, and correspond roughly to the upper (Palomas) and middle (Rincon valley) lithostratigraphic subdivisions of the Santa Fe Group used in local and regional geologic mapping (Hawley and Kennedy, 2004).

The Santa Fe Group is composed chiefly of coalescing alluvial fan deposits that are discontinuous and locally heterogeneous with inter-bedded sandstones, silts, and clays of varying percentages. The Upper Santa Fe Group Palomas Formation (Lozinsky and Hawley, 1986) represents the USF at the site. This formation grades eastward from the Animas Uplift from coarse alluvial fan material to braided-stream and deltaic sands and silts to clays near the Rio Grande. The interfingering with clays begins approximately 3 to 5 miles west of the current position of the Rio Grande and is responsible for the flowing wells common in this part of the site (Murray, 1959; **Figure 4-8**). A basalt flow dated at 4.2 million years before present caps the Palomas Formation gravels near Copper Flat (Seager *et al*., 1984).

The Middle Santa Fe Group Rincon Valley Formation (Seager and Hawley, 1973) is exposed near Hillsboro, New Mexico, where the reddish-brown clays and clayey silts characteristic of this basal unit are interbedded with basalts dated at 28 million years before present (Seager *et al*., 1984). The Rincon Valley Formation represents the MSF at the site and generally contains water, but the yield is low due to the low hydraulic conductivity of the clays. The Rincon Valley Formation lacustrine red clays underlie the Palomas Formation and thicken southward toward Hatch, New Mexico, and the Rincon Basin (Wilson *et al*., 1981).

Tailings Impoundment Vicinity

The existing tailings impoundment facility overlies the old placer workings of Greyback Wash and Hunkidori Gulch (**Figure 4-9**). A study of these placer workings by Segerstrom and Antweiler (1975) showed that the placers were found in paleo-stream terrace alluvium approximately 25 to 30 ft thick that is underlain by a calcium carbonate horizon and reddish-brown clay. SRK (1995) and SHB (1980) confirmed and expanded the areal extent of this reddish-brown clay layer and determined that the top of the Palomas Formation is stratigraphically below the red clay layer. According to the studies completed by SRK and SHB, the clay layer and the 25 to 30 ft of paleo-stream terrace gravels that lie above the clay, have restricted the downward migration of water draining from the eastern half of the existing tailings. This clay layer has enabled a mound of water beneath the tailings impoundment to develop. This mounding of water, due to drainage of the existing tailings and meteoric infiltration over the years, became evident in some tailings dam monitor wells completed above the clay layer. The central and western sections of the existing tailings facility appear to communicate hydrologically with the USF that lies beneath the tailings area because the clay zone thins and disappears in this area, as shown in **Figure 4-13**. Groundwater issues as a result of tailings deposition by the previous operator are currently being dealt with through the Stage 1 Abatement Plan for the NMED. Further impacts would be mitigated by NMCC's proposed use of a synthetic liner system to prevent the downward migration of tailings seepage water.

The thickness of the Palomas Formation increases locally over a graben structure (labeled Dutch Gulch in **Figure 4-2**), which is reflected in higher transmissivity and relatively low hydraulic gradients in the USF. Based on a 7-day aquifer pumping test (ABC, 1996), the transmissivity of the USF in the tailings dam area is about 187 ft^2/day. East of the tailings area (see **Figure 4-2**) is a 10- to 30-foot thick clayey sand and gravel layer, underlain by a 25- to 100-foot-thick clay layer, which in turn is underlain by a silty sand and gravel layer (SRK, 1995). The lower silty sand and gravel layer is considered by ABC (1996) to be the USF and, based on drilling information, has a thickness of at least 200 ft. The hydraulic gradient in this area is about 30 ft per mile.

East of the graben structure, labeled as Dutch Gulch in **Figure 4-2**, the Palomas Formation (labeled Tsfp) thins and is interpreted to have significantly reduced transmissivity. The hydraulic gradient in this area ranges from about 130 to 330 ft/mile. The contact between the Palomas Formation and the underlying Rincon Valley Formation clay unit (labeled Tsf in **Figure 4-2**) is a highly irregular depositional contact. Locally, the Palomas Formation (USF) may be unsaturated, with the water table existing in the underlying Rincon Valley Formation (MSF) (BLM, 1999).

Production Well Field Vicinity

Farther to the east, the hydraulic gradient decreases from 330 ft/mile to about 34 ft/mile in the vicinity of the production well field (identified as PW wells on **Figure 4-14**). This suggests a progressive increase in transmissivity toward the area of the production well field. A graben structure below the production well field locally increases the thickness of the Palomas Formation to as much as 1,000 ft (**Figure 4-2**). The transmissivity of the USF in the production well field area ranges from about 2,675 to 5,750 ft^2/day (SRK, 1995). Farther to the east, towards Caballo Reservoir, sands and

gravels in the Palomas Formation are interbedded with clays of the ancient Rio Grande. As a consequence, the transmissivity decreases slightly and the hydraulic gradient Increases to 45 ft/mile. In this area, the USF appears to be confined, leading to artesian flow in wells along the lower reaches of both Las Animas Creek and Percha Creek.

Although the Palomas Formation is described as "sand and gravel" (Davie and Spiegel, 1967), there exist numerous discontinuous clay layers within the sequence. This causes the bulk vertical hydraulic conductivity of the USF to be much lower than the horizontal conductivity. As a consequence, groundwater in deeper portions of the USF can be semi-confined, leading to relatively high vertical hydraulic gradients. The low vertical hydraulic conductivity has two important effects on the groundwater flow system. First, within about 4 miles of Caballo Reservoir, confinement of groundwater is sufficient to create artesian conditions in deeper portions of the USF. Wells drilled to these depths have groundwater levels aboveground surface and produce flowing wells, the locations of which are shown on **Figure 4-14**. Flow rates for uncapped wells range between a few gallons per minute (gpm) to as high as 40 gpm.

The second effect of low vertical conductivity is to reduce downward leakage between the Quaternary alluvial aquifer in the Las Animas Creek drainage basin and the underlying USF. At the location of monitoring wells MW-9, 10, and 11, north of the production well field, the groundwater level in the USF is some 58 ft lower than the water level in the overlying Quaternary alluvial aquifer (ABC, 1996). This results in a downward vertical hydraulic gradient from the Quaternary alluvial aquifer in the vicinity of Las Animas Creek drainage basin to the USF approaching 1 ft/ft. Such downward gradients are interpreted to occur along a substantial length of Las Animas Creek (ABC, 1996). In spite of these gradients, the amount of surface water loss from the Quaternary alluvial aquifer in the Las Animas Creek drainage basin is not significant; suggesting that vertical hydraulic conductivity in the USF is relatively low. Analytical calculations (ABC, 1997) suggest that if the vertical conductivity were much greater than 1 ft/year (10^{-6} cm/second), the Las Animas surface water system would lose essentially all of its water and become an intermittent stream, which clearly does not occur.

The hydraulic connection between the USF and the alluvial aquifer of the Rio Grande has not been evaluated, but groundwater gradients at the site strongly suggest that water flows from the Palomas Formation to the floodplain alluvium of the Rio Grande.

An aquifer pumping test conducted at the locations of monitor wells MW-9, 10, and 11 suggests that the vertical conductivity of the USF is low in this area (ABC, 1997). Pumping of the wells screened in the USF at this location did not affect a well screened in the Quaternary alluvial aquifer in the Las Animas Creek drainage basin, even though the well screened in the USF had 22 ft of drawdown. Also, monitoring of water levels along Las Animas Creek by Alta (Goff, 1998) for wells screened in both aquifers showed that fluctuations in water levels observed in shallow wells (those screened in the Quaternary alluvial aquifer) are not mirrored in the deeper wells (wells screened in the USF). These data are presented in Appendix A-2 (Table A2-10) of the PFEIS (BLM, 1999).

4.4.2.1.2.3 Quaternary Alluvial Aquifer

The uppermost aquifer at the site is the Quaternary alluvial aquifer, which is composed of channel and floodplain gravels, sands, and silts. Locally, these units are generally 30 to 50 ft thick near the mouths of Las Animas and Percha Creeks (Davie and Spiegel, 1967). Cores from monitoring wells drilled along Las Animas Creek indicate that upper alluvial gravels extend from the surface to a depth of approximately 20 to 60 ft depending on the location along the creek (BLM, 1999). There are fewer data available for the thickness of these deposits in and along Percha Creek.

The Las Animas alluvial aquifer consists of local alluvial deposits adjacent to and underlying Las Animas Creek. Groundwater in this narrow, sinuous aquifer is in direct hydraulic communication with Las Animas Creek surface water. Surface water in the creek and groundwater in the aquifer form a single surface-to-groundwater flow system. Surface water flow from one location to the next may be related, in part, to the proportion of total system flow being carried by the aquifer at each location. Along its course, the Las Animas alluvial aquifer receives recharge by rainfall infiltration. Discharge from the aquifer occurs through evaporation and evapo-transpiration from riparian vegetation and existing well pumping. Between the Saladone well and an area of the Lower Animas Artesian well (**Figure 4-14**), the aquifer loses water to the underlying Palomas Basin alluvial aquifer by slow downward seepage. The total flow rate for surface flow plus flow in the alluvium of the creek drops from around 1,800 to 1,900 gpm to around 1,100 gpm, a loss of 800 gpm over the 8-mile stretch of creek bed. The loss is consistent with slow downward seepage of water at a rate of around 1 foot/year (ABC, 1997). This is the approximate saturated hydraulic conductivity of clay. In the area of the Lower Animas Artesian (**Figure 4-14**) the Las Animas surface/groundwater system may receive recharge from the USF. At Caballo Reservoir, all water in the Las Animas surface/groundwater system discharges to the reservoir. The nature of artesian conditions in the Percha Creek drainage basin have not been studied in as much detail, and therefore less historical data are available.

Upstream of the artesian wells, Las Animas Creek, the alluvial aquifer can be "perched" above the water table in the Santa Fe Group aquifer system by 20 to 60 ft of unsaturated to partially saturated alluvial sediments (SRK, 1995; ABC, 1997). The alluvial aquifer along Las Animas Creek in the lower reaches loses water to the Santa Fe Group aquifer system by slow downward seepage. The upper reach of Las Animas Creek near the Saladone Well (**Figure 4-14**) also may be perched above the intermediate aquifer (Minton, 1961).

4.4.2.1.3 Existing Baseline Groundwater Information

An enormous amount of site characterization data are available for the Project site because the mine was active in the past and was characterized by previous operators that either mined the site or worked on permit applications to mine the site. These historical data would be used in conjunction with the baseline groundwater quality data that would be collected under the procedures set forth in the *SAP* (Intera, 2010) to provide as thorough an understanding as possible of groundwater quality conditions prior to the re-initiation of mining at Copper Flat. Key resources that contain data to be used for the baseline groundwater analysis include: Groundwater monitoring well exceedences provided by SRK (2010); the *SAP* (Intera, 2010); the PFEIS (BLM, 1999); the Hydrologic

Assessment, Copper Flat Project Sierra County, New Mexico (Newcomer *et. al*, 1993); and The Natural Defenses of Copper Flat, Sierra County, New Mexico (Raugust, 2003). Proposed monitoring well locations are provided in **Figure 4-15**. A brief summary of the data available in these key reports follows.

The PFEIS (BLM, 1999) provides a summary of groundwater quality data. Summary tables for key wells and key constituents are provided in Table 9-2 of the *SAP* (Intera, 2010). The wells identified in this study are illustrated in **Figure 4-14**. The PFEIS (BLM, 1999) concluded that groundwater quality at the site was good and generally useable for domestic and agricultural purposes. This document also concluded that past mining in the Hillsboro District, the Copper Flat Mine tailings facility drainage, and the presence of an oxidized sulfide-bearing ore body have impacted groundwater within and immediately adjacent to the area of past mining, resulting in elevated total dissolved solids (TDS) and sulfate that exceed New Mexico Water Quality Control Commission (WQCC) Standards. These impacts were found to be localized within the immediate vicinity of the mine features or associated with wells completed in the ore body.

Newcomer *et al.* (1993) determined that the quality of groundwater at the site has changed little since the early 1980s and probably since the 1800s. The authors found that there have been some increases in TDS and sulfate in some wells along Greyback Wash below the mine site and down-gradient of the tailings dam, associated with mining and milling activities in the 1980s. Newcomer *et al*. (1993) determined that the only constituents exceeding the WQCC Standards were barium from a spring sample, and, cadmium and fluoride from a pit lake water sample.

Raugust (2003) compiled historical groundwater data and summarized groundwater quality conditions and, based on his data compilation and analysis, concluded:

- Groundwater pH measurements both up and downgradient of the pit lake range from 7 to 8.2.
- TDS and sulfate values are less than WQCC standards in the wells evaluated for this analysis; however, samples downgradient of the mine have increased gradually over time and are approaching the standards for TDS.
- Historical sampling of well GWQ-5, located east and downgradient of the pit lake, indicates that water quality in the vicinity of the pit lake may have been affected naturally by the presence of the ore body prior to mining in 1982.
- The groundwater upgradient of the mine pit lake is high quality with relatively high proportions of chloride and sulfate. Groundwater downgradient of the pit lake shows relatively higher proportions of bicarbonate and calcium and relatively lower proportions of sulfates.
- Pre-Quintana mining (June 15, 1981) groundwater data collected from wells downgradient of the pit lake show similar anions and cation distributions to post-Quintana mining activities (1996 and 1998). This indicates that groundwater quality downgradient of the ore body reflects the natural weathering of the Copper Flat porphyry system.

4.4.2.1.4 NMED Stage 1 Abatement Plan Requirements

On August 20, 2008, the NMED sent a letter to the site owner at that time requiring a Stage 1 Abatement Plan (20.6.2.4101 NMAC). The purpose of the Stage 1 Abatement Plan is to provide the data necessary to select and design an effective abatement alternative. The requirements for the Stage 1 Abatement Plan are described in 20.6.2.4106 NMAC. The abatement plan proposal must include an investigation to define the extent and magnitude of any existing groundwater and surface water contamination and to characterize the hydrogeology of the site. These requirements are similar to the EMNRD requirements for completing a Baseline Characterization Report, and these efforts would be conducted in parallel; therefore, the surface water and groundwater requirements of this SAP are relevant to both characterization efforts.

NMCC's meetings with the NMED concerning the abatement requirements have revealed the following key concerns on the part of the NMED:

- Groundwater impacts from the existing unlined tailings impoundment have been documented, but have not been fully characterized;
- Samples of pit lake water quality reveal exceedences of WQCC standards, and NMED is concerned about migration of this water away from the pit, causing additional groundwater impacts as well as ongoing contact with wildlife; and
- Acid leaching could be occurring due to ongoing ore exposure.

NMCC is currently working with NMED to address these issues.

4.5 Soils

A successful reclamation program is dependent, in part, upon the quantity and quality of soil available for use during the reclamation process. NMCC assessed the quantity and suitability of topsoil present at the site in two ways. First, NMCC reviewed current literature concerning soil characteristics, and second, NMCC determined site-specific soil characteristics. The findings are summarized in this section of the SAP. In addition, baseline soil surveys were completed on the project area as recently as the late 1990s, and are briefly summarized and referenced in the PFEIS (BLM, 1999).

The term "topsoil" refers to the A master soil horizon (Soil Survey Staff, 1999), which is the uppermost mineral horizon that contains organic matter and can be salvaged from the areas to be disturbed and is capable of supporting vegetation, or other soil material capable of supporting vegetation. This material is often referred to as "suitable top dressing" or "growth media." NMCC has reviewed previous literature describing the results of soil surveys completed at the site (BLM, 1999) and is aware that the presence of an A master soil horizon across the site is limited. The purpose of the soil survey and sampling proposed in this section of the SAP is to evaluate the presence of suitable top dressing. However, in the interest of conforming to the requirements of the Mine Act regulations, the term "topsoil" is used throughout this section to refer to suitable top dressing and/or growth media.

General information about the soils present at the site was obtained from a Soil Conservation Service (SCS) survey completed by Neher (1984). The SCS (now the Natural Resources Conservation Service) mapped two major soil types that occur in the Copper Flat area:

1. The Luzena-Rock Outcrop association
2. The Scholle-Ildelfonso association

All but the easternmost portion of the proposed site is mapped as Luzena-Rock Outcrop association, which is typically present on the steeper slopes of hills and mountains. These soils are typically shallow, very gravelly and cobbly loams and clay loams. The Scholle-Ildelfonso association occurs on more gentle slopes of the piedmonts and mountain toes and is deep, well-drained, and formed in mixed alluvium. The resulting soil texture in these areas is primarily gravely loams and gravelly clay loams (SRK, 1996). The soils are thin and of low productive capacity. The soil textures are primarily gravelly loams and gravelly clay loams and are subject to continuing wind and water erosion. Along with the natural erosion, much of the Copper Flat landscape has been severely disturbed by historical placer mining and the 1982 mining operation. Over 65 percent of the areas targeted by the proposed operation were disturbed during the 1982 operation. Soils were replaced in the north cell of the tailings impoundment and over a portion of the plant site.

4.6 Vegetation

Plant species inventories were conducted in 1976, 1991, 1992 and 1994; newly initiated studies are being advanced to update and expand these previous surveys and inventories. Plant species lists are included in the 1993 EA (BLM, 1993). The pre-mining vegetation inventory is detailed in the 1977 EAR and the 1978 Environmental Assessment Record (BLM, 1978).

The Copper Flat area is within the Mexican Highlands section of the Basin and Range Physiographic Province, and more specifically defined as Southern Desertic Basins, Plains, and Mountains (NRCS 2010). This elevation transition causes an intermixing of environmental factors which has a direct correlation on the variety of vegetation in the area. The vegetation is composed primarily of two desert associations: Chihuahuan desert scrub and desert grassland. In the vicinity of Copper Flat, the low elevation flats and foothills are characterized by Chihuahuan desert scrub (which can be dominated by creosote bush). The highest elevations are predominantly desert grasslands with some scattering of juniper. The intervening area is dominated by desert grasses with a mixture of shrubs.

Much of the Project area has been disturbed by the mining activities of the prior 1982 operation. The dominant biotic communities within the Copper Flat area consist of creosote bush (i.e. Chihuahuan desert scrub) and desert grassland, on the fringes of some piñon-juniper (or juniper savanna) habitat (BLM, 1996).

4.6.1 Chihuahuan Desert Scrub (or Creosote Bush) Community

Grasses can dominate the landscape and may sometimes grow in pure stands. At the Project site, the grasses are associated with a wide variety of sub-dominant shrubs (yucca, *Yucca* spp.; three-leaf (or lemonade) sumac, *Rhus trilobata*; yerba-de-pasmo, *Baccharis pteronioides*; mesquite, *Prosopis glandulosa*; feather dalea, (*Dalea formosa*); creosote bush, *Larrea tridentata*; sage, *Artemisia* spp.; catclaw, *Mimosa* sp.; rabbitbrush, *Chrysothamnus* spp. and broom snakeweed, *Gutierrezia sarothrae*), trees (Gambel oak, *Quercus gambelli*; Emory oak, *Quercus emory*; willow, *Salix gooddingi* and *Salix exigua*; and cottonwood, *Populus* spp.), and forbs (cactus, *Opuntia* spp.; locoweed, *Oxytropis lambertii* and *Astragalus* spp.; *Geranium* sp., *Solanum* spp., and *Haplopappus* sp.).

4.6.2 Desert Grassland

The desert grassland community in the area dominates the higher elevations of the rolling hills, in the gullies, ravines and washes, and on the slopes and low ridges. A number of grass species are characteristic of this community. The major genera are grama grasses (*Bouteloua* spp.), curly mesquite (*Hilaria* spp.), and three-awns (*Aristida* spp.). The grasses dominate the landscape and may grow in pure stands. At the Project site, the grasses are associated with a variety of sub-dominant shrubs (*Yucca* spp.; lemonade sumac, *Rhus trilobata*; *Baccharis pteronioides*; mesquite, *Prosopis glandulosa*; feather dalea (*Dalea formosa*); creosote bush, *Larrea tridentata*; sage, *Artemisia* spp.; catclaw, *Mimosa* sp., rabbitbrush, *Chrysothamnus* spp. and *Gutierrezia* sp.), trees (Gambel oak, *Quercus gambelli*; Emory oak, *Quercus emory*; willow, *Salix gooddingi* and *Salix exigua*; and cottonwood, *Populus* spp.), and forbs (cactus, *Opuntia* spp.; locoweed, *Oxytropis lambertii*; *Geranium* sp., *Solanum* spp., and *Haplopappus* sp.).

4.6.3 Pinion-Juniper Community

The piñon-juniper and juniper savanna communities occur between the desert grasslands and the coniferous forests at an elevation of about 5,500 feet. All of the sites occupied by this community are on the higher knolls, northern aspects, and in steep, rocky terrain. Although this community is represented by one-seed juniper (*Juniperus monosperma*), it is also known for its association with range forage plants.

4.6.4 Aquatic Vegetation

The presence of aquatic plants in the Copper Flat area is severely limited due to the temporary, intermittent character of Greyback Wash and the lack of other water. Isolated, limited quantities of aquatic plants occur at stock watering areas, in abandoned, caved-in mine shafts, in isolated rock crevices along drainages, and at seeps. The production and diversity is severely limited. Cattails (*Typha* sp.), sedges (*Carex* spp.) and algae (*Chlorophyta*, *Cladophora* sp., *Scenedesmus* sp., and *Spriogyra*; *Euglenophyta*, *Euglena viridis*; and *Bacillariophyta*, *Nitzschia* sp. and *Navicula* sp.) can

be located in appropriate habitats. The algae exist only when water is present during the warmest summer months.

Three riparian areas associated with seeps in Greyback Gulch were identified in 1995 during the site investigations performed for the EIS (BLM, 1996) process. The first is located east of the East Waste Rock Disposal Area and north of the access road. This area supports a small group of cottonwoods and willows. The second seep is located south of the plant area and is fed by runoff from the road between the pit and plant area. This seep does not support willows or cottonwoods but provides water to wildlife and livestock intermittently during the year. The third seep present in the immediate area of the proposed mine is located in Greyback Wash immediately east of the tailings thickener. The original stormwater collection pond is located adjacent to this area and it is believed that this pond, left open during reclamation activities in 1986 has been acting as a reservoir which has been draining into the riparian area through the original discharge pipe which was left in place. This area supports a small group of cottonwoods, willows and other herbaceous species.

One riparian area of relatively moderate functional value is located approximately 2.8 miles west of the mine site in Warm Spring Canyon (BLM, 1996). This small wetland covers less than 0.1 acre and supports several wetland species, including willow and tamarisk. Riparian habitat associated with Las Animas Creek, a perennial stream located approximately 4 miles northeast of the mine area, supports a variety of trees and shrubs including plains cottonwood, Arizona sycamore, walnut, mesquite, Apache plume, hackberry, Mormon tea and prickly pear. Percha Creek is a perennial stream located approximately 2.2 miles south of the mine site which supports a variety of riparian vegetation. Dominant species along this creek include willow, seep willow, ash, plains cottonwood, locust and walnut.

4.6.5 Vegetative Productivity

Foliar cover and forage productivity estimates for desert grassland and previously disturbed land present within the project area were based on visual observations made during field reconnaissance activities and data provided in the soil survey for the Sierra County area (NRCS, 1984). An analysis of 12 vegetation plots was conducted by Glover prior to the 1982 disturbance (Glover, 1977). This work and nearby off-site range transects performed by the SCS (Sierra Soil and Water Conservation District, 1990) provided some historic estimates of the vegetative cover, density and productivity in the permit area prior to mining disturbance. Based on current ecological site descriptions, foliar cover for desert habitats within the general vicinity of the project area would be no more than approximately 30 percent (NRCS, 2010). Correspondingly, vegetative productivity would range from a low of 150 pounds/acre in unfavorable years, to 450 or perhaps even 750 pounds/acre of forage during favorable years (NRCS, 2010). Consequently, this is a very wide range in potential plant productivity and is highly subject to annual amounts of precipitation. Undisturbed desert grassland occurs in the tailings impoundment area, the East Waste Rock Disposal area, the North Waste Rock Disposal area, and the topsoil stockpiles.

Approximately 65 percent of the project area has been disturbed by previous mining operations. As of 1996, the average foliar cover for previously disturbed land is approximately 5 to 15 percent, with the highest foliar cover of approximately 15 percent occurring in the tailings impoundment area and

the lowest foliar cover of less than five percent generally occurring at the pit, the West and North Waste Rock Disposal areas, and the Lean Ore Stockpile (Sierra Soil and Water Conservation District, 1990). The majority of previously disturbed land occurs in the tailings impoundment area, the pit, the Lean Ore Stock Pile area and the West Waste Rock Disposal area.

4.7 Wildlife

Wildlife inventories were conducted in 1976, 1991, 1992 and 1995; newly initiated studies are being advanced to update and expand these previous surveys and inventories. Wildlife species lists are included in the Copper Flat Project DEIS (Sierra Soil and Water Conservation District, 1990). The pre-mining wildlife inventory is detailed in the 1977 EAR (Glover, 1977), 1978 Environmental Assessment Record (BLM, 1978), DEIS, and PFEIS.

4.7.1 Mammals

There are a limited number of mammals occurring in the Copper Flat area, and the major factors believed responsible are: (a) low annual productivity of vegetative food and cover, (b) limited diversity in the plant communities present, and (c) lack of water. No aquatic mammals, amphibians nor fish have been observed in the Copper Flat area. No information is available on the myriad of invertebrates present in the area. Mammals that utilize the area are domestic cattle, deer, horses and several feral-domestic goats.

Mule deer harvest has stabilized since introduction of new regulations over the past 15 years. With the reclamation program of 1986, a small number of mule deer have frequented the mine site to feed on the reseeded grasses but move into the remote hills during the hunting season and into the lowlands during severe winters.

4.7.2 Birds

The numbers and species of birds vary widely with the seasons. Waterfowl sporadically use the existing pit lake, particularly during migration (BLM, 1996). Shorebird use of the lake is limited due to the lack of shallow foraging areas and appropriate habitat (BLM, 1996). A variety of raptors utilize the area of interest and the most common are: red-tailed hawk (*Bueto jamaicensis*), kestrel (*Falco sparverius*) and marsh hawk (or northern harrier) (*Circus cyaneus*). Golden eagles (*Aquila chrysaetos*) have been observed in the Copper Flat area. The Bald eagle (*Haliaeetus leucocephalus*) occasionally visits the Las Animas Creek area (8 km north of the mine site) during the winter and spring seasons. Historically, no active raptor nests nor regular eagle roosting sites were known to occur in the Copper Flat mining area. Based on a recent observation, this may not be true anymore. An active nest of the great horned owl (*Bubo virginianus*) was observed on a cliff face.

4.7.3 Reptiles

Six species of reptiles have been observed in the area; however, approximately 36 species of reptiles and amphibians are expected to occur in the greater district (BLM, 1996). By far, the most numerous are the different lizards. A variety of snakes, including rattlesnakes, are present in the area. The 1977

Environmental Assessment Report (Glover, 1977) and 1978 Environmental Assessment Record (BLM, 1978) present the reptilian species observed during environmental monitoring and probably represent the most abundant species within the area.

4.7.4 Invertebrates

A tremendous variety and abundance of invertebrates occur in the area of interest. The most numerous are beetles (Coleoptera). Other common orders are the bugs (Hemiptera and Homoptera), bees and wasps (Hymenoptera) and centipedes (Chilopoda). Butterflies and moths (Lepidoptera) are seen infrequently.

4.7.5 Fisheries

The only perennial aquatic environment at the mine site is the pit lake. No fish occur in the pit lake (BLM, 1978).

4.8 Threatened, Endangered, or Candidate Species

A Biological Assessment has been prepared in accordance with Section 7(c) of the Endangered Species Act to determine if any sensitive plant or animal species may be impacted by the proposed Project. The BLM, as lead agency for the EIS process, requested a Section 7 consultation from the U.S. Fish and Wildlife Service (USFWS). A total of four federally-listed and 15 federal candidate species were addressed in detail in the 1996 Biological Assessment (BLM, 1996).

Newly initiated threatened and endangered studies are being advanced on the project area to update and expand the previous studies and survey. Most of the species being targeted for review and for potential habitat are species of concern (or sensitive listed species), those that do not have official protection status. There are a couple of officially listed threatened and endangered species to be evaluated, which are discussed in the following sections.

4.8.1 Vegetation

Grama grass cactus (*Pediocactus papyracanthus*) was the only endangered or threatened species whose habitat might include the Copper Flat Project acres (BLM, 1996). The 1976 and 1992 searches and inventories did not reveal the presence of the grama grass cactus or any other sensitive plants (BLM, 1996). A couple of the plant species of concern to assess include Sandberg's pincushion cactus (*Escobaria sandbergii*) and the Pinos Altos fame flower (*Phemeranthus humilis = Talinum humile*). A state of New Mexico endangered cactus, Duncan's pincushion (*Escobaria duncanii = Coryphantha duncanii*) would also need some investigation. One of the only known locations for this cactus species is situated very close to the Copper Flat site.

4.8.2 Wildlife

Mining and other surface disturbance activities may affect species listed by the USFWS and New Mexico Department of Game and Fish as threatened, endangered, or candidate. A list of a number of

endangered and threatened fauna that might occur in the assessment area is presented in the 1996 DEIS (BLM, 1996), 1996 BA (BLM, 1996), and 1999 PFEIS.

The peregrine falcon (*Falco peregrinus*) occurs commonly in the Rio Grande Valley and might occasionally be expected to hunt in the foothills east of the Black Range.

Bald eagles were seen flying in the vicinity of the site in 1995 and probably forage along Caballo and Elephant Butte reservoirs. Local riparian areas near the mine site could provide additional forage habitat, however these areas would not be considered optimal foraging habitat for eagles, and no records indicate that bald eagles use them for foraging or roosting.

The loggerhead shrike (*Lanius ludovicianus*) was observed during the field assessment in 1991. This species is very wide spread (habitat comprises 63 percent of BLM land in Sierra County).

The common black hawk has been recorded along Percha Creek; however, no nesting sites have been documented. Las Animas Creek could provide suitable habitat for this species.

The ferruginous hawk historically occupied the region and has been recorded within the creosote upland and grass mountain habitat near the location of the proposed project (IHICS, 1995). The area was surveyed in 1991 for the presence of nesting ferruginous hawks; no sign of nest hawks was observed in or near the Project at that time (Stinnett, 1991).

The northern goshawk is associated with a variety of forest type habitats which do not occur in the Project area. No sightings of this species have been reported in the vicinity of the Project.

Baird's sparrow, a state of New Mexico threatened species, is migratory in New Mexico and most commonly observed in the fall. This species has been observed in Sierra County, but foraging grassland habitat is limited in the Project area and no sightings have been recorded.

Habitat for six of the seven species of bats studied during the preparation of the EIS exists in the Project area, including the greater western mastiff bat, occult little brown bat, spotted bat, fringed myotis, Yuma myotis and pale Townsend's big-eared bat; however, some of these habitats would be considered marginal to support these species. The Townsend's big-eared bat has been documented roosting in the Tony House, located near the tailings facility. The detailed background information and the potential for occurrence pertaining to these seven sensitive bat species is presented in the Biological Assessment prepared for the Project.

The Texas horned lizard has been documented in Sierra County and is known to occur in and near the Project site.

The long-fin dace was documented in Percha Creek in 1995. This fish, a federal candidate-category 2 species is believed to have been introduced into Percha Creek, since it does not naturally occur east of the Continental Divide (Bison-M, 1995) (BLM, 1996).

Habitat requirements for a few other wildlife species of concern would be evaluated such as the western burrowing owl (*Athene cunicularia hypugae*), Gunnison's prairie dog (*Cynomys gunnisoni*), and pocket gophers (*Geomys* spp.).

4.9 Range Resources

Livestock grazing is allowed in areas adjacent to the mine area. However, the grazing Allotment (No. 6079) does not include the Project area at this time because of the need to exclude livestock from the area of mining activity.

4.10 Air Quality

The primary pollutant of interest at the mine site is fugitive dust since the emissions of other pollutants are quite small. Alta installed a PM_{10} monitoring station at the site in 1994 to collect baseline information at the site (Air Sciences, 1995). The DEIS utilized fine particulate data collected at Gold Hill by the New Mexico Air Quality Bureau from 1990 to 1992 to evaluate ambient air quality at Copper Flat (BLM, 1996). Although Gold Hill is located more than 20 miles west of the Project area, operations at Gold Hill are similar to those proposed for Copper Flat and it was assumed that data collected at Gold Hill would be representative of conditions at the Project site (BLM, 1996). High winds sometimes create local dust storms which result in higher short-term concentrations; nonetheless, Sierra County has been designated as an attainment area, which means that the area meets all applicable air quality standards. Because there are no significant pollution sources in the area, the overall air quality in the vicinity of the Project site is good (BLM, 1996).

The primary air quality impacts from the Project would be associated with particulate emissions. Modeling of these impacts indicated that the maximum values for 24-hour and annual concentrations of Total Suspended Particulates (TSP) would occur at the property boundary (BLM, 1996). The nearest Class I area is located more than 30 kilometers west of the Project and the models indicated that levels would fall below $1 \mu g/m^3$ within less than 10 kilometers from the site. Therefore, there would be no significant impact from the Project on any Class I area (BLM, 1996).

NMCC installed one meteorological and two air quality monitoring stations at the site in August 2010 for the purposes of collecting more up-to-date information on current air quality.

4.11 Cultural Resources

Several cultural resources surveys have been conducted at the site since 1976. The initial surveys were conducted for the 1977 and 1978 EARs (Glover, 1977). A subsequent Class III (100-percent pedestrian coverage) cultural resources survey was conducted by Mariah Associates for Gold Express in 1991 (Evaskovich, 1991). In response to comments from the New Mexico State Historic Preservation Officer (SHPO) in August, 1995, Alta contracted with Human Systems Research (HSR) of Las Cruces to resurvey all of the undisturbed portions of the Project not covered by the 1991 survey. The results of this survey were filed with the SHPO in October 1995 (Sechrist, 1995). Because the HSR survey was conducted more than 10 years ago, the lead federal agency (BLM) for cultural resource compliance review and the SHPO would review the previous survey for sufficiency and consistency with current standards for survey investigations. This review would also take into consideration the probability for new sites to have become exposed in the interim, such as through active dune formation/movement. If it is determined that a new pedestrian survey does not need to be conducted prior to construction, then the fieldwork effort for cultural resources likely would be

limited to revisiting previously recorded sites to evaluate their current condition, and to reassess potential effects to these resources from the Project.

A number of prehistoric and historic sites eligible for listing in the National Register of Historic Places have been identified at the Project area. Where possible, identified sites would be avoided by modifying the design of project components. For sites which might be impacted by the Project, and for which avoidance is not feasible, NMCC would contract with qualified archaeologists to prepare a recovery plan to collect appropriate data, to minimize and mitigate adverse effects to cultural resources resulting from the Project. Following approval by the BLM and SHPO, the recovery plan would be implemented prior to construction.

5 Reclamation and Closure

5.1 Introduction

The Copper Flat Project site would be reclaimed to achieve a self-sustaining ecosystem appropriate for the climate, environment and land uses of the area. Careful consideration would be given to cooperation with neighbors in their land use requirements including cattle grazing, alternate energy generation such as wind and solar, and reestablishment and enhancement of original botanical and zoological species habitants.

The reclamation plan has been developed to meet the site specific characteristics of the mining operation and Project site. The objective of the reclamation plan is to return the Project site to conditions similar to those present before re-establishment of the mine. The mining operation and reclamation plan have been designed to use the most appropriate technology and BMPs to assure protection of the human health and safety, the environment, wildlife and domestic animals. The Project is designed to meet, without perpetual care, all applicable federal and state environmental requirements following closure.

5.2 Statutory and Regulatory Requirements

Reclamation of disturbed areas caused by the Project would be in compliance with federal and state regulations. Under the Federal Land Policy Management Act (FLPMA), the BLM is responsible for preventing undue or unnecessary degradation of federally-administered public lands which may result from operations authorized by the mining laws (43 CFR 3809). The New Mexico Mining Act requires the preparation of a reclamation plan for submittal and approval by the New Mexico Energy, Minerals and Natural Resources Department (NMEMNRD) and New Mexico Environmental Department (NMED). In addition, closure of the tailings embankment must also comply with requirements of the New Mexico State Engineer's Office.

Reclamation would be conducted concurrently with mining operations where feasible. At closure, final reclamation would be accomplished by a "close out" work force.

5.3 Post-Mining Land Use

Major land uses occurring in the vicinity of the Project site are mining, grazing, wildlife, watershed and recreation. Following closure, the Project area would continue to support mineral development, grazing, wildlife habitat, watershed, and to a lesser degree, recreation. Proposed reclamation of the site should result in a successful program to restore the area to the productive land uses discussed above. All post-closure land uses are in conformance with the previously defined BLM Caballo Planning Unit, the 1985 White Sands Resource Management Plan (RMP) and the Sierra County Comprehensive Land Use Plan. Currently, the White Sands RMP is being revised, updated, and incorporated into the BLM's Tri-County RMP/EIS. The new Tri-County RMP includes Sierra,

Otero, and Doña Ana Counties. This revision process began in 2005; the Preliminary Draft EIS was issued in September 2011.

Following closure, the pit would partially fill with water from sub-surface flow resulting in a permanent impoundment (SRK, 1995). Hydrogeologic and geochemical modeling indicates the post-closure pit lake water quality should be similar to that of the current pit lake (SRK, 1995). Possible post-closure uses for the pit include a water reservoir for agricultural and grazing purposes. The pit lake has also been proposed by the BLM as a possible location for a field-scale aquatic life laboratory, or other possible cultural uses yet to be identified.

5.4 Summary of Disturbance

Reconstruction would involve utilization of existing foundations and previously disturbed land where feasible. For the Proposed Action, approximately 57 percent of the proposed disturbance would take place on areas disturbed during the previous operations. New disturbance of previously undisturbed land would be kept to a minimum. Approximately 37 percent of the new disturbance would be related to the tailings and waste rock facilities.

Areas to be disturbed are divided into the following major mine components: open pit area, waste rock disposal areas and low-grade stockpile, tailings impoundment, and plant site. The utility corridor, access road and surface water diversions were developed during the previous operations and no further disturbance is anticipated associated with these facilities. The majority of the haul roads were also developed during previous operations and only minor additional disturbance would be related to haul road construction.

5.5 Reclamation Plan

The goal of the Copper Flat reclamation program is to minimize disturbance to the environment and to restore disturbed areas to a self-sustaining ecosystem consistent with applicable regulations, the post-mining land use and mine reclamation standards. The objectives of the Copper Flat reclamation program are:

- To meet or exceed applicable state and federal reclamation requirements through application of most appropriate technologies and BMPs.
- To minimize erosion and prevent contribution of suspended solids to streams and other bodies of water through employment of best management practices and contemporaneous reclamation, to the extent appropriate and practicable.
- To protect human health and safety, the environment, wildlife and domestic animals, cultural resources, the hydrologic balance, and extant riparian and wetland areas, including reclamation of any streams that may be impacted by the mining operations.
- To protect the quality of surface and ground water resources by minimizing pollutant formation, and on-site containment of any unavoidable toxicity.

- To preserve suitable topsoil and other approved topdressing material for use in reclamation, employing appropriate and BMPs for sampling, testing, replacement, and stabilization.
- To establish surface soil conditions most conducive to regeneration of a stable plant community through stripping, stockpiling, and reapplication of alluvial or soil material where feasible.
- To revegetate disturbed areas with a diverse mixture of appropriate plant species, in order to achieve a self-sustaining ecosystem or other approved post-mining land use.
- To identify any roads that may be disturbed by mining operations and which are not planned to be returned to use, consistent with the approved post-mining land use and applicable land owner approvals.
- To maintain public safety and site stability through appropriate recontouring and revegetation of disturbed areas within the permit area.
- To work with local and regional communities to identify post-mining uses of the land and facilities to enhance opportunities to sustain the economy and culture in the post-mining phase of this project.

Surface facilities, equipment and buildings related to the mining Project would be removed, foundations covered, and the plant site returned to conditions similar to those present before re-establishment of the mine. The topography, slopes and aspects of the disturbed and reclaimed areas would be developed to blend in with the present, existing physiographic forms of the Copper Flat area, as feasible.

5.6 Implementation

Contemporaneous reclamation of disturbed surface areas would be an integral part of the mining operation. Both public and private land would be reclaimed. At completion of mining activities, the site would be restored to conditions and standards to meet approved post-mining land uses. These uses would include native plant communities similar to surrounding undisturbed areas, wildlife habitat, and grazing land potentially suitable for livestock. The reclamation and restoration must be demonstrated to be sustainable without perpetual care. Closure of the site would be accomplished by the following activities:

- Pre-construction and Permitting: This is the stage wherein baseline data is collected to characterize the existing environment. The baseline data are used to formulate reclamation goals. This stage has been conducted since the late 1970s and currently new studies are being advanced to add to this existing database of studies to expand and update to current requirements.
- Construction: Where feasible, the existing soils and suitable alluvial material would be removed first from major disturbance areas (tailings impoundment, waste rock disposal areas, etc.), stockpiled, protected, and used in the reclamation process. The revegetation test program would be initiated during this phase of the operation.

- Operations: Reclamation efforts would be implemented at the earliest feasible time in areas where activities are discontinued. This includes recontouring, scarifying, placement of soil, alluvial material, and other approved topdressing material, followed by revegetation. The revegetation test program and concurrent reclamation would be monitored during this phase to provide data that would be utilized to determine final closure methods to be implemented to achieve reclamation goals, subject to regulatory approval.
- Closure: Upon closure of the mining operations, unreclaimed facilities would be reclaimed according to the reclamation plan.
- Post-Closure Monitoring: Following the completion of reclamation and closure activities, the revegetation would be monitored for at least two growing seasons and meet Part 6 requirements under the New Mexico Mining Act. Groundwater would be monitored according to conditions set forth in the Ground Water Discharge Permit, which was prepared by NMCC for submission to NMED, and is currently undergoing technical review.

A tentative project schedule, including reclamation schedule encompassing these five project stages, is presented in **Figure 5-1**. The schedule shown is approximate and could change due to a number of operational and economic conditions.

5.7 Environmental Considerations for Reclamation

The reclamation plan is designed to assure protection of human health and safety, the environment, wildlife and domestic animals.

5.7.1 Signs, Markers and Safeguarding

Measures such as signs, markers, fences and barricades would be used to protect the public, wildlife and domestic animals from potentially dangerous areas associated with the Project. Safety measures associated with the major Project components are discussed in more detail in Section 5.16.

5.7.2 Wildlife and Domestic Animal Protection

Reclamation of the Copper Flat Project would be conducted to achieve a stable configuration and access to unsafe areas would be restricted for protection of the public and animals.

The Project would result in the reclamation of over 910 acres of land disturbed by previous mining activities. This reclamation would be a beneficial impact to wildlife resources. However, because of the long-term loss of woody species, the reclamation of the previously disturbed land would mainly benefit those species typically associated with herbaceous vegetation. It is anticipated that the Project area would support a greater variety of species following closure due to the additional habitat diversity created by the mining and reclamation programs.

5.7.3 Cultural Resources

Cultural resources requiring protection, and any cemeteries or burial grounds (none are anticipated), shall be protected and/or avoided during reclamation activities. This includes any resources identified before or during Project activities.

5.7.4 Hydrologic Balance

Preliminary hydrogeologic studies were completed in the 1990's to estimate the potential impacts to groundwater from the tailings impoundment and to surface and groundwater from acid mine drainage (ARD) from the waste rock piles (SRK, 1995). In addition, the predicted elevation and final chemistry of the pit lake was modeled (SRK, 1995). Like many pit lakes in the arid American Southwest, the Copper Flat pit lake is expected to act as an evaporative sink such that groundwater flows into the pit and only leaves by evaporation to the atmosphere. The hydrologic impact assessment report, currently being updated by NMCC, will directly address the future hydraulic relationship between the pit lake and adjacent aquifers through the site conceptual model, including a pit water balance study. Simulation of time-varying groundwater heads, pit water level and flow rates between the adjacent aquifers and the pit lake will be conducted using a numerical flow model to be constructed from the conceptual model. The pit water balance and history of measured water levels in the existing pit will be used to help calibrate the numerical model. Predictive simulations will simulate the ultimate pit and adjacent aquifers from cessation of mine operations to re-establishment of the equilibrium pit lake stage.

For the reasons set forth below, the potential for ARD from the Project is considered low.

5.7.4.1 *Acid Rock Drainage*

Although no major impacts have been identified associated with waste rock disposal from the previous operations, the potential for acid generation from some of the rocks has been identified. Studies were completed previously to evaluate the potential for acid generation and metal leaching from the various types of mine overburden, waste rock and tailings materials at the site (SRK, 1995) and additional studies and evaluations are underway to augment and update the information currently available.

The results of the ARD studies indicate that the potential for ARD from the tailings is considered low. The risk of ARD from the bulk of the existing and future waste rock is also considered low; however, some of the waste rock to be extracted would be partially oxidized (transitional) and this material has the potential to generate acid if not disposed of properly. Therefore, the transitional waste rock would be managed and reclaimed to alleviate the potential for ARD. Because of improved project economics, it is estimated that a major portion of the previously identified transitional material would now report to the tailings facility.

Proper waste management has been proven effective in alleviating the potential for ARD. The transitional waste rock would be segregated and placed in the west and north waste rock disposal

areas for the Proposed Action as shown on **Figure 3-1**. The surface of the all waste rock disposal areas would be reclaimed in the same manner as proposed for disposal areas containing partially oxidize material. The disposal areas would be contoured to enhance run-off and covered to reduce infiltration.

The waste rock piles would be reclaimed by regrading, dozer compacting the surface and covering this surface with up to 12 inches of native soil. These measures would inhibit infiltration and reduce the quantity of water required to produce drainage. The waste rock disposal areas containing transitional material would be located adjacent to the pit lake. In the unlikely event acid drainage does occur, it would flow into the pit lake where it would be diluted by ground water inflow and prevented from migrating into ground water. The high evaporation of the pit lake water causes ground water to flow into the pit, preventing any surface inflows from entering the ground water.

The quality of the current pit lake water appears to be impacted by oxidation of minerals exposed in the pit wall. Results of pit water sampling indicate that, although the water in the pit meets state surface water quality standards for livestock and wildlife use, it contains elevated concentrations of sulfate, fluoride, calcium, cadmium and manganese. A preliminary study has been completed to determine the post-closure pit water quality (SRK, 1995), and ongoing geochemical characterization work would update this study. The findings of the study indicate that the majority of the transition materials would be removed by the pit expansion, significantly reducing the surface area of these materials exposed in the pit walls in comparison to the present day condition of the open pit.

Run-off from the waste rock disposal areas would be collected in facilities constructed at each area.

5.7.4.2 *Suspended Solids*

Sediment control would be achieved by the use of BMPs. BMPs include regrading, seeding and mulching, silt fences, straw bale dams, diversion ditches with energy dissipaters, and rock check dams at appropriate locations during construction and operation. Diversion structures, including existing structures, would divert run-on away from disturbed areas. New diversion structures and sediment control features for the proposed MPO would be evaluated according to the criteria contained in **Appendix B**. All sediment control structures would be monitored and maintained on a regular basis.

During operations, all run-off from the plant site would be directed into a sediment pond located on the east side of the site adjacent to the make-up water pond. Following reclamation this pond would no longer be necessary for sediment control. The dike separating the sediment pond from the make-up water pond would be removed, the pond regraded to restore conditions similar to those currently existing, and the site revegetated.

5.7.4.3 *Diversions and Overland Flow*

Runoff from particular areas of the Copper Flat Project site was originally estimated using the climate data summarized in Section 4.3. The surface drainage of the Project site was designed to contain or control the 100-year/24-hour storm event (**Appendix B**). NMCC is in the process of re-

evaluating these design criteria with respect to current regulations and engineering standards. During reclamation most areas would be regraded and, where possible, the original drainages restored.

The diversions of surface water runoff around the waste rock disposal areas would remain in place. Ditches would be lined with rip rap, as needed, to protect the channels from erosion.

5.7.4.4 *Stream Diversions*

The watershed area to the west of the pit is drained by Greyback Wash, an ephemeral stream which is dry over most of its length except during the rainy season. Greyback Wash used to pass through the pit area. This drainage has been intercepted, diverted around the southern periphery of the pit, and returned to the original channel east of the pit area. This was accomplished by cutting a channel through the ridges and placing diversion dams in the tributary arroyos. Following closure of the previous operation, the diversion was left in place. The diversion would be left in place following closure of the proposed operation.

5.7.5 Impoundments

The tailings impoundment has been designed, constructed and maintained to minimize adverse impacts to the hydrologic balance and adjoining property and to assure the safety of the public. Reclamation and closure of the tailings impoundment is discussed in more detail in Section 5.16.4.

5.7.6 Prevention of Mass Movement

All slopes, impoundment embankments and WRDFs would be designed, constructed and maintained to prevent the potential for mass movement both during operations and following closure. Details of WRDF design are presented in **Appendix B**; and for the tailings impoundment in **Appendix D**.

5.7.7 Riparian Areas

The Copper Flat mine area is primarily a terrestrial habitat. No wetlands and two riparian areas are present in the immediate area of the proposed mine. The riparian areas, located in Greyback Wash immediately south and east of the plant site, did not exist prior to the 1982 operation, as evidenced by photographs. The riparian area south of the plant area is believed to have developed as a result of modifications of the flow in Greyback Gulch from culverts installed in 1983. It is believed that the eastern riparian area was created from flow collected in the stormwater collection pond and alterations of surface water flows in Greyback Gulch resulting from the construction of the land bridge for the tailings pipeline. Because the stormwater pond would be used in the proposed operation, NMCC would supply water from the freshwater supply during operations. Following operations, NMCC would endeavor to restore the storm water collection pond to a condition similar to that existing at present. However, the exact configuration which led to the creation of this wetland is not known and complete restoration may not be possible. As with upland vegetation and plant communities, wetland and riparian plant species would naturally become established at locations that are suitable for their survival, growth, and development. This would occur even if such locations and

conditions are generated by human activities. The riparian and "wet" areas would be considered during the environmental evaluations and managed appropriately according to state and federal requirements.

5.7.8 Roads

Access to the site is via an existing county road (Gold Dust Rd./Co. Rd. Bo27) which would remain following closure. Prior to final closure, the State of New Mexico and the BLM would determine which other roads would be left intact around the site in order to conduct post-closure monitoring or provide adjacent landowner access. All other NMCC mine-related roads would be removed.

5.7.9 Surface Facilities or Roads Not Subject to Reclamation

A number of pre-1981, primitive roads currently exist within the proposed project boundary. Some of these roads would not be utilized during the currently proposed operation. As such, they are not subject to reclamation by NMCC.

5.7.10 Drill Hole Plugging and Water Well Abandonment

Mineral exploration and development drill holes, monitoring, and production wells subject to state regulations would be abandoned in accordance with applicable rules and regulations (NMAC 19.27.4 *et seq*.). Boreholes would be sealed to prevent cross contamination between aquifers and required shallow seals would be placed to prevent contamination by surface access.

Monitoring wells around the tailings impoundment would be maintained until NMCC is released from this requirement by the NMED, MMD, and BLM. These wells would then be plugged and abandoned according to applicable requirements.

5.7.11 Post-Closure Monitoring

Monitoring would be ongoing throughout the life of the operation, during closure and for a post-closure period. The BLM and state agencies would set post-closure monitoring requirements at mine closure.

Sampling of the water in the pit after mine closure would continue for a period of not less than twelve (12) years following mine closure to determine any changes in pit water quality.

The tailings dam/pond would be regulated by the New Mexico State Engineer's Office for safety of operations. A Discharge Permit that requires monitoring for seepage into the ground water would be required from the New Mexico Environmental Department (NMED), Ground Water Bureau. Following closure water samples from monitoring wells located downstream of the tailings dam, and in the plant and pit area would be taken and analyzed on a regular basis and the results sent to the Ground Water Bureau in accordance with monitoring requirements set forth in the Discharge Plan.

These samples would identify any seepage from the tailings pond. The Discharge Plan Application contains abatement plans if leakage and contamination occurs.

5.8 Site Stabilization and Configuration

The Project site would be stabilized, to the extent practicable, to minimize future impact to the environment and protect air and water resources. The final surface configurations for the Proposed Action (**Figure 5-2**) would be suitable to achieve the post mining land uses as discussed in Section 5.3. All facilities, slopes, embankments, and roads would be designed, constructed, maintained and reclaimed to achieve stable configurations.

The topography, slopes and aspects of the disturbed areas would be developed to blend in with the surrounding topography as much as practicable. Where possible the size and shape of channels of new drainages would approximate former, natural drainages. All drainage channels, ditches and earthen water control structures would be revegetated and protected from erosion by riprap, sediment traps or other types of BMPs. Alluvial materials suitable for surface treatment would be salvaged from disturbed areas where safe and feasible operation of earthmoving equipment is possible, and would be stockpiled and protected for use in reclamation.

An attempt would be made to favor initial revegetation on north and east aspects of gentle slopes where additional moisture is available. A limited number of slopes might exceed a 3H:1V condition but most slopes would be restructured to resemble existing topography. The steeper slopes would be stabilized by physical media (boulders, alluvium, rock) as well as vegetative means to add to general diversity and stability.

Flatter disturbed areas (slopes of 4H:1V or less) would be minimally regraded to restore the natural drainage, and would be revegetated, except those in the tailings impoundment which would be regraded to direct surface water away from the top surface of the reclaimed tailings.

5.9 Plant Growth Media and Cover Materials

5.9.1 Removal and Storage

Suitable soil material available for reclamation from the previously mined and disturbed areas at the Project site is very limited. Efforts would be made to carefully strip, stockpile and improve the remaining growth media available on the site. Because the available soil from newly disturbed areas is thin and of low productive capacity, the O and A horizons of soil material would be salvaged, where possible.

The O horizon is the uppermost soil layer and is composed of slightly decomposed organic materials. It contains a high percentage of microbial constituents found in soils which have been determined to be beneficial to plant life. The A horizon is the uppermost zone from which soluble salts and colloids have been leached and in which fully decomposed organic matter has accumulated. In those areas where the A horizon is shallow or indiscernible, suitable B horizon material would also be stripped

and stockpiled. The B horizon is the layer in which material leached from the overlying A horizon is accumulated. It usually contains very little organic matter and is lower in microbial activity than the O and A horizons. However, due to the low organic matter content of the A horizon at this site, the A and B horizons do not differ substantially. For these reasons, the B horizon material would not be stockpiled separately from the O and A horizon soils.

Where salvageable soil exists, either on undisturbed or reclaimed areas, NMCC would salvage as much material as can be safely and practically recovered. However, the lack of reclamation cover material available from previously disturbed areas and the poor development of topsoil (top dressing) at the site will require the evaluation of alternative sources and types of materials for use as reclamation cover. A preliminary evaluation of cover material sources and stockpile alternatives is provided in Appendix D, following the tailings impoundment conceptual design.

Samples of soil materials were collected and analyzed prior to disturbance in 1977 (Glover, 1977) and in undisturbed areas in 1996. Analyses of the 1977 samples indicate the soils collected were fertile, with the exception of soils from the WRDFs being low in available phosphate. The 1996 sample taken from the North WRDF indicated similar results, but that taken north of the West WRDF showed poor fertility. Both samples were low in organic matter (Johnson, 1996).

The estimated volumes of salvageable cover material available in areas to be newly disturbed or redisturbed by the Project are shown in

Table 5-1: Estimated Available Topsoil from Newly Disturbed Areas

Facility	Surface Area (acres)	Estimated Available Cover Material (yd^3)
West WRDF	16.3	3,538
North WRDF	69.9	21,384
East WRDF	122	99,072
Low-Grade Stockpile	64.3	37,913
Plant Area	78	182,800
Tailings Impoundment	547	542,000
Roads and Misc.	50	21,780
Total	**911.5**	**908,487**

A comparison of estimated quantities of available cover material (**Table 5-1**) and potentially required cover material (**Table 5-2**) indicates that there could be a deficit of almost 2.0 million cubic yards of cover material for the currently proposed reclamation plan. As part of the proposed operations, NMCC plans to salvage most of the near-surface alluvial materials from within the limits of the tailings impoundment to mitigate this soil deficit. These materials are part of the Santa Fe formation gravels and alluvial basin fill and were used in the construction of the original starter

embankment. An evaluation of the borrow sources and stockpile alternatives for reclamation cover materials is provided in **Appendix D**, following the conceptual tailings design.

Table 5-2: Estimated Reclamation Cover Requirements

Facility	Surface Area (acres)	Top Dressing Cover Requirement (yd^3)	Reclamation Cover Requirement (yd^3)
West WRDF	16.3	13,151	65,755
North WRDF	69.9	56,400	282,005
East WRDF	122	99,072	495,360
Low-Grade Stockpile	64.3	54,611*	--
Plant Area	78	62,920	--
Tailings Impoundment	547	438,000	2,062,509**
Roads and Misc.	50	40,333	--
Total	**911.5**	**764,487**	**2,905,629**

*The Low-Grade Stockpile does not require reclamation cover, as it is anticipated to be processed and removed at the end of mining; however, the disturbance footprint of the stockpile would require some top dressing in order to facilitate revegetation.

** (Golder, 2011a)

No areas unaffected by mining are currently proposed to be disturbed in order to obtain reclamation cover materials. Several borrow areas currently existing within the limits of the tailings impoundment would be the source of the excavated materials. Mine haul trucks and front end loaders would excavate the required materials during the construction period. Following stripping, suitable growth media and alluvial material would be salvaged and stockpiled. These locations were chosen to minimize haul distances and to limit erosion. The piles would be constructed with 3H:1V slopes. The different aspects and slopes of the stockpiles would be used in the test revegetation program to evaluate slope revegetation methods.

Diversion ditches would be constructed around the reclamation material stockpiles, where necessary, to minimize run-on erosion. To stabilize the portions of the stockpiles not used in the revegetation test program, and minimize erosion and maintain biological viability, they would be seeded with an interim, weed-free seed mix as recommended by the BLM. The interim vegetation cover established on the growth media stockpiles would further reduce soil erosion while providing micro-habitats for beneficial soil organisms. In addition, the interim revegetation of the stockpiles would minimize the potential for the establishment of invasive, non-native weed species.

Efforts would be made to salvage the existing vegetation on the areas that would be newly disturbed by the Project. Prior to and during soil salvage, woody plants and vegetation would be removed. The vegetation would be stored with the growth media to increase the organic matter content of the growth media.

5.9.2 Placement

The goal at Copper Flat is to salvage sufficient growth media and alluvial material to provide a 6 to 12-inch cover on areas to be revegetated, if reserves prove sufficient. Less than 12 inches of growth media was placed on the north cell of the tailings impoundment during the previous reclamation efforts. Analysis of the vegetation in that area demonstrates the effectiveness of that thickness of growth media for the purposes of developing a self sustaining ecosystem. Suitable growth media and alluvial materials would be salvaged and stockpiled from all disturbed areas as is feasible. **Table 5-2** shows the required cover volumes by facility.

The final details of the placement and use of these materials in reclamation would be approved by the state and BLM following analysis of the results of a test-plot program which would be conducted during the mining operation. Furthermore, concurrent reclamation using this material would provide additional information regarding the success of the approved techniques and allow ongoing modifications to occur.

To ensure good contact with the subsoils, the surface would be roughened by ripping or disking prior to placement of the cover material. The cover material would be spread and graded with care taken to prevent a reduction in bulk density by limiting the number of passes. Following placement, the area would be walked with a dozer to lightly compact the soil.

5.9.3 Amendments

Soils and alluvial materials to be salvaged for reclamation cover are deficient in nitrogen, phosphorus and potassium and would require 4,000 to 8,000 pounds per acre of amendments to create fertile growth media (Johnson, 1996). Aerobically digested sanitized sewer sludge, cotton husks, feedlot cattle waste are possible natural materials which might be used, if available, to amend the growth media prior to placement on reclaimed areas. Composting of materials, if required, would be performed on site to better control the rate and amount of composting. Any natural soil amendments used would be certified free of invasive and noxious weeds.

Other amendments may also be necessary. Ultimately, fertilizer and amendment requirements would be based on chemical analysis of disturbed/replaced soils, and the results of the test revegetation program and contemporaneous reclamation efforts. The application rates would be determined based on the uniformity of the soil characteristics and topography.

The amendments would be incorporated into the top four to six inches of the surface by harrowing. Repeated applications may be required based upon additional testing and vegetation monitoring.

5.10 Revegetation

The revegetation plan is designed to create a stable, self-sustaining plant community, and would be in conformance with the planned post-mining land uses of wildlife and grazing.

The dominant biotic communities of the Copper Flat area are Chihuahuan desert scrub (often dominated by creosote bush) and desert grassland. The desert grassland community is the major community at the site and is dominated by desert grasses with a mixture of shrubs. The Chihuahuan desert scrub community is found on low elevation flats and foothills and occurs on the eastern portion of the site.

Due to the general harshness of the Chihuahuan desert scrub community, most of the animal species using this habitat are small in size, such as reptiles, rodents, and rabbits. The desert grassland community supports a wide diversity of insects and provides suitable habitat for a variety of animals. Most of the grasses are important for livestock forage and provide watershed protection.

Due to the general lack of surface water, the Copper Flat area provides essentially no aquatic environment. Micro-aquatic ecosystems present along the drainage ways are unstable, and community production and diversity is severely limited.

To achieve the post-mining land use of wildlife and grazing, revegetation of the site would consist mainly of the establishment of grass, forb and shrub species characteristic of the desert grassland community. Plant species would be chosen based on their ability to provide satisfactory cover, and on their nutritional value and ability to support wildlife habitat. Riparian and water-loving plant species (willows, cottonwood, cattails, sedges, etc.) may be introduced in drainage channels and in shallow areas near the shoreline of the pit lake.

Diversity of plant species on revegetated, disturbed lands may be less than on undisturbed areas. However, the seed would contain native plant species (grasses, forbs, and shrubs) in a mix approximating adjacent desert grassland community areas. The revegetation of the re-developed Project is anticipated to be similar to the site prior to re-development; however, over time, through the processes of natural plant community succession, the revegetation should approach a density and diversity similar to that of undisturbed areas adjacent to the disturbed land.

5.10.1 Seed Mixtures

The seed mixtures to be used would be determined by seed availability, compatibility with the vegetation of the surrounding areas, the soil and climatic conditions of the area, and by recommendations from the BLM and NMEMNRD. The reclamation success of the previously disturbed areas would be used as a guide in choosing the mixture. Suitable seed materials may be a limiting factor in revegetation of the site. The seed mixes shown in **Table 5-3 a**re example seed mixes derived from information provided by the NMEMNRD (and the BLM) for revegetation programs in the vicinity of the project. The species included in the list also focus on those that are more readily available. Not all of the species in the immediate vicinity of the project site are readily available from seed suppliers. The list presented is for the purpose of reclamation cost estimation and

is not intended to represent a final list. The final seed mix would be approved following review of the revegetation test program results and may be modified with approval of the BLM and NMEMNRD.

Table 5-3: Proposed Reclamation Seed Mixes

Species	Application Rate (lbs. PLS/acre)
Drill Seed Mix	
Blue grama (*Bouteloua gracilis*)	0.6
Side-oats grama (*Bouteloua curtipendula*)	1.3
Indian ricegrass (*Oryzopsis hymenoides*)	1.2
New Mexico feathergrass (*Stipa neomexicana*)	1.0
Tobosa grass (*Pleuraphis mutica*)	1.2
Black grama (*Bouteloua eriopoda*)	0.6
Cane bluestem (*Bothriochloa barbinodis*)	1.0
Narrowleaf globemallow (*Sphaeralcea angustifolia*)	0.5
Four-wing saltbush (*Atriplex canescens*)	0.8
Broadcast Seed Mix	
Blue grama (*Bouteloua gracilis*)	0.6
Side-oats grama (*Bouteloua curtipendula*)	1.0
Sand dropseed (*Sporobolus cryptandrus*)	0.5
New Mexico feathergrass (*Stipa neomexicana*)	1.0
Silver bluestem (*Bothriochloa laguroides*)	1.0
Apache plume (*Fallugia paradoxa*)	1.0
Four-wing saltbush (*Atriplex canescens*)	1.0
Blanket flower (*Gaillardia pulchella*)	0.5
Narrowleaf globemallow (*Sphaeralcea angustifolia*)	0.1

5.10.2 Planting Techniques

Seeding would take place immediately after placement of the cover material, depending on when the cover material is put in place. Seeding should take place when summer moisture is available to encourage the warm season grasses. Consequently, soil placement and seeding are planned to occur prior to the monsoon season of July, August, and September. In the event that seeding occurs substantially later than soil placement, any compacted soil areas may require ripping or scarification. If determined necessary, compacted soils would be ripped or scarified to a depth of 6 to 12 inches prior to seeding. Field experience and changes in local precipitation patterns may alter the seeding schedule to other times of the year.

Seeding methods to be utilized at the site would depend on many factors including the topography, soil conditions and seed mixture. Typically, some combination of broadcast seeding, drill seeding and hydro-seeding is used for mine reclamation. It is expected that broadcast seeding, followed by harrowing to bury the seed to the proper depth would be the seeding method of choice. The presence

of larger rocks and boulders in the alluvial materials to be used as reclamation cover would decrease the effectiveness of drill seeding and may preclude this method altogether. Alternatively, the presence of some larger rocks and boulders at the soil surface would create and generate micro-sites favorable to the establishment of vegetation. If drill seeding is not utilized, and broadcast seeding is the primary methodology utilized, then the seeding rates shown in **Table 5-3** would need to be summed (i.e. drill component summed to broadcast component), so that the total seeding rate is in the range of 12 to 16 pounds of pure live seed (PLS) per acre, approximately. Hydro-seeding may be used on steep, small areas where larger equipment cannot easily operate.

Mulch may not be required depending on the time of planting and the terrain. If necessary, a protective mulch such as alfalfa pellets or certified weed free straw would be applied. Hydro-mulch may be necessary in areas that required hydro-seeding. If hay mulch is used, it would be mechanically crimped or secured with a chemical tackifier to prevent erosion. Steep slopes may require erosion control matting or netting.

Weed control would be implemented only if necessary. Methods of weed control would be determined upon recommendation from the BLM and/or NMEMNRD.

5.11 Revegetation Success

Revegetation success would be determined by monitoring the vegetation parameters of ground cover, productivity, woody plant density, and plant species diversity. The results of these parameters in reclaimed areas would be compared to the same parameters in reference areas (i.e. control or undisturbed sites) or to an agreed upon revegetation standard. The reference area and revegetation standards would be based on the research program discussed in Section 5.12, and would be established through discussion by the BLM, NMEMNRD, and NMCC. The research program would be ongoing, including the collection of vegetation data. The collected vegetation data, stratified across the various plant communities situated within the permitted boundaries, would be carefully evaluated. The collected vegetation data would eventually function as a guide towards determining ecologically suitable success standards.

Technical guidance procedures published by the NMEMNRD were utilized in the development of a sampling and analysis plan. There are a wide variety of standard and classic sources for field sampling methods in plant ecology (Bonham 1989; Barbour, Burk, and Pitts 1980), including references cited in the technical guidance procedures developed by the NMEMNRD. Any variations of or additions to the vegetation monitoring techniques would go through approval with NMEMNRD and/or BLM as needed. As may be appropriate and necessary to meet NMEMNRD requirements, herbaceous cover and productivity would be established within 90 percent of the reference area with a 90-percent statistical confidence level. Woody species (and at Copper Flat these are essentially all shrubs) would be established to the approved density with an 80 percent confidence level as defined by NMEMNRD. Diversity would be compared to existing reclaimed and/or reference areas relative to the physical environment of the areas to be reclaimed.

Observations would be conducted once per year at approximately the same time each year. Two seasons of successfully attaining the revegetation criteria would determine success of the revegetation program. In the event that an area does not meet the revegetation goals (or criteria), the area would be investigated and steps taken to correct the problem.

Analysis of the revegetation efforts on the north cell of the tailings impoundment demonstrates the effectiveness of the methods proposed here including the thickness of growth media used in this area should meet the objective of developing a self sustaining ecosystem.

5.12 Reclamation Research

As part of the reclamation plan, NMCC would conduct a revegetation test program to determine the most effective methods to meet revegetation standards as defined in their reclamation plan. The program would be flexible enough to allow modifications of proposed methodologies and to test new techniques. Conceptually, the test revegetation program would include test plots designed to evaluate different types and thicknesses of cover material, seed mixes, planting techniques, use of clean tailings fines to enhance water retention of soils, soil amendments and mulches. The program would also include test plots on slopes of different grades and aspects.

In addition, NMCC intends to maximize the amount of concurrent reclamation at the site. This would allow larger-scale testing of regrading, reclamation cover placement and revegetation techniques. The outer face of each raise of the tailings impoundment would be reclaimed by placement of a layer of alluvial cover up to eight inches thick followed by revegetation. It is also anticipated that the west and north waste rock disposal areas and portions of the east and south disposal areas would be completed prior to completion of mining, which would allow for concurrent reclamation of these areas.

5.13 Concurrent Reclamation

Because contemporaneous reclamation reduces erosion, provides early impact mitigation, limits costs and reduces final reclamation work, NMCC is committed to maximize this type of reclamation at the Copper Flat Project. Some of the Project facilities would be constructed in their final configuration. Others, such as individual lifts of the waste rock disposal areas and possibly some roads would be decommissioned prior to final mine closure. Areas such as these would be reclaimed concurrently with the active mining operation where feasible. Descriptions of design features which are intended to facilitate contemporaneous reclamation for specific project components are given below in Section 5.14.

5.14 Interim Reclamation

There is a possibility that continuous, full-scale production might be interrupted for short periods in response to economic considerations or unforeseen circumstances. In this event, interim reclamation would be initiated. Interim reclamation is outlined below.

- Rights-of-Way: The power lines and water pipeline would be inspected regularly and maintained as necessary. None of the facilities would be altered or removed. The main access road would receive regular maintenance. The internal roads would receive minimal maintenance.
- Pit: The pit area would be protected by fencing with a locked access gate. Monitoring of pit water would be ongoing.
- Tailings Facility: The tailings impoundment would be retained for potential future development. Limited care and maintenance of the reclaimed embankment face would be performed as necessary to continue stabilization of the area.
- Diversion Ditches: Diversion ditches would be inspected and maintained as necessary. Surface water runoff would be managed in accordance with the site NPDES permit requirements.
- Buildings: The process buildings, equipment and support facilities would be guarded by an on-site resident security guard and maintained as necessary. None of the buildings would be destroyed or modified.

5.15 Interim Management Plan

In accordance with 43 CFR § 3809.401(b)(5), NMCC has prepared the following *Interim Management Plan* to manage the project area during periods of temporary closure (including periods of seasonal closure, if necessary) to prevent unnecessary or undue degradation, and includes:

- Measures to stabilize excavations and workings;
- Measures to isolate and control toxic or deleterious materials;
- Provisions for the storage or removal of equipment, supplies, and structures;
- Measures to maintain the project area in a safe and clean condition;
- Plans for monitoring site conditions during periods of non-operation; and,
- A schedule of anticipated periods of temporary closure during which you would implement the interim management plan, including provisions for notifying BLM of unplanned or extended temporary closures.

This Interim Management Plan (a.k.a., temporary closure plan) is necessarily general due to the lack of detailed design information at the present time, and would be updated as necessary during the preparation of the mine feasibility study and NEPA process. Any updates would be submitted to BLM prior to construction.

5.15.1 Schedule of Anticipated Periods of Temporary Closure

The standard operating schedules at the Copper Flat Project would be 24 hours a day, 365 days a year for the mining activities and processing circuits. No temporary or interim closures of the facility are currently planned. However, it is possible that, due to mechanical or technical difficulties, unfavorable economic conditions, litigation or other unforeseen events, mining and processing facilities may have to be temporarily closed. In the event of an unplanned temporary closure, the following plan would be implemented:

- The BLM, MMD and NMED would be notified within 30 days of the temporary closure of the flotation mill and/or the concentrate circuit. This notification would include a description of the procedures and controls that have been or would be initiated to maintain the process components during the temporary closure period.
- NMCC would supply BLM/MMD/NMED with a list of supervisory personnel who would oversee the mine facility during the temporary closure period. This list also would include the number of support staff required in each department to maintain the facility during the closure period. Standard security procedures would remain in place for the duration of the temporary closure period. Access to the site would be allowed for appropriate regulatory agency personnel
- If the interim closure period exceeds 90 days, NMCC would begin to evaluate procedures required to carry out a permanent closure of the process components. These procedures would be reviewed and approved by the BLM and MMD. NMCC may petition the BLM, MMD and NMED for an extension that would delay permanent closure.

5.15.2 Measures to Stabilize Excavations and Workings

No additional measures would be necessary to stabilize excavations and workings during an unplanned temporary closure. Pit dewatering activities may cease during the temporary closure period, in which case, all dewatering pumps, pipelines and water storage tanks would be drained.

Interim reclamation procedures would be implemented as necessary to stabilize disturbed sites during the temporary closure period. These procedures would be coordinated with the BLM, MMD and NMED.

Adequate storage capacity would be maintained in the process components to accommodate run-off resulting from the design storm event.

5.15.3 Measures to Isolate or Control Toxic or Deleterious Materials

NMCC would follow the waste rock management procedures described in the Plan of Operations to isolate waste rock as necessary during unplanned temporary closure. Contract explosives handlers would remove all explosives from site in accordance with federal and state regulations. Hazardous materials would continue to be stored, handled and disposed of according to federal and state regulations.

5.15.4 Storage or Removal of Equipment, Supplies, and Structures

In the event of a temporary closure, it is anticipated that equipment, supplies and structures would not be removed or placed into storage. Some mobile equipment or bulk commodities may be relocated into buildings or covered with tarps to isolate them from the weather, depending on the anticipated duration of the temporary closure. In addition, the following steps would be taken:

- Additional reagents would not be introduced into any process component during the temporary unplanned closure period. Process piping and pumps would be drained if the process circuits are shut down. Stored equipment would be clearly identified as having contained process solutions.
- Any mine equipment remaining in operation during the temporary closure, including haul trucks, shovels, loaders, drills and personnel vehicles would continue to be maintained according to standard company procedure.
- Following any temporary closure period, the integrity of the entire fluid management system would be evaluated before start-up is initiated. Solution tanks, pumps and piping would be visually inspected and repaired as necessary. The mineral processing circuit would be charged with process solution and visually inspected for evidence of leaks. Mine equipment would be inspected for compliance with appropriate federal and state mining regulations before mining activities re-commence. Pit dewatering would resume as soon as possible. Mining activities should not be affected by a temporary closure. The mine dewatering system would be visually inspected and repaired as necessary.

5.15.5 Monitoring During Periods of Non-Operation

All provisions of this plan and all other regulatory and permitting requirements would continue to be met during the temporary closure period. This would include all monitoring, notifications and reports submittal. Site monitoring and monitoring of leak detection systems for vessels and piping containing process solution would continue throughout the temporary closure period.

5.16 Facility-Specific Reclamation

5.16.1 Mine Pit

In 1982, approximately 3 million tons of overburden material was stripped and over 1.2 million tons of ore were mined from the open pit. Mining was initiated at the “5600” bench level and excavation had commenced on the “5380” bench at the time of shutdown.

Mining of the ore body would continue by a 30-foot high, multiple bench, open pit method. Under the Proposed Action, the pit would eventually be 2500 feet × 2500 feet) and would reach an ultimate depth of 900 feet at an elevation of 4,720 feet. The working slope of the pit walls would average approximately 1H:1V. Safety benches would remain at 80-foot intervals and the overall final pit slope would be about 1.1H:1.0V.

NMCC does not propose to backfill the pit. Backfilling operation would not allow sequential mining of the deposit, may cover future mineral resources, and it would be economically unfeasible following closure of the operation. The primary reason that post-closure backfilling is uneconomic is the time required to backfill the pit following plant closure. In the case of Copper Flat, this would require up to seven years during which no income would be realized. Furthermore, backfilling the pit would cover a mineral resource which could become economic with an increase in metal prices or the development of new processing technologies, and thus hinder future mineral exploration and mining of useful minerals.

Ground water inflow formed a lake in the former pit. The current water level is an elevation of about 5,420 feet; therefore, pit dewatering would again be necessary during operations. Following cessation of dewatering activities, a lake would again form in the pit. The post-closure pit water elevation is estimated to be at an elevation of approximately 5,250 feet. The depth of the lake would fluctuate a few feet depending on precipitation and the evaporation rate. Refilling would proceed over a number of years (SRK, 1995).

Possible post-closure uses for the pit include a water reservoir for agricultural and grazing purposes. Based on studies completed for Alta's permitting processes of the mid- to late-1990s, pit water quality of the current lake, and modeling of post-closure pit water quality suggest that post-closure water quality should meet New Mexico surface water standards for these uses (SRK, 1995), and possibly also be suitable for other existing cultural uses as well as yet to be considered and otherwise unknown cultural uses. New studies are underway to build on this past work and evaluations.

Reclamation of the pit during operations would be limited to erosion control. At closure stable pit walls would be left in place, and unstable pit walls would be stabilized by blasting or other safe methods. Where safe, alluvial material would be placed on the benches above the projected water level, and the benches seeded. Roads and safety benches would be ripped and water barred to control surface water runoff. Disturbed areas around and adjacent to the pit would be covered with alluvial material and revegetated.

The ramp would be graded or ramps placed at different locations to allow escape routes for wildlife. The pit area and highwalls would be appropriately barricaded with physical barriers or fences and posted according to MSHA and New Mexico Mine Inspectors Office regulations. Access would be limited by a locked gate and the access road blocked with a physical barricade.

5.16.2 Waste Rock Disposal Areas and Low-Grade Stockpile

The primary waste rock disposal facility for the Proposed Action is located east-northeast of the mill site on the east side of Animas Peak (**Figure 3-1**). Two smaller WRDFs would be located adjacent to the pit.

The present height of the East WRDF is at an elevation of approximately 5,560 feet. By the end of mine life, an upper lift would be developed at an elevation of 5,630 feet and a lower lift would be

developed at an elevation of 5,320 feet. The West and North WRDFs would be constructed by expanding the existing piles from their current elevation and constructing additional lifts up to 200-ft thick (Golder, 2011b). Total waste material contained in the disposal areas at the end of the expected life of the property is estimated to be approximately 37 million tons.

The waste rock disposal areas would be regraded and reclaimed to blend into the surrounding topography to the extent practicable. Three types of waste rock have been identified at the site: oxidized waste rock, transitional waste rock and unoxidized waste rock (SRK, 1995). The potential for acid generation from the bulk of the waste materials is low, primarily due to the relatively low regional precipitation, and except due to exceptional summer storms the virtual lack of any off site runoff and finally-the rapid evaporation and adsorption of any available moisture. However, reclamation and surface water management measures designed for the partially oxidized materials would be used to promote runoff and reduce infiltration for all material types. Horizontal surfaces would be regraded and contoured to reduce infiltration of water and provide positive drainage to sediment collection points. Care would be taken to contour these areas to reduce the potential for ponding and infiltration. This would reduce the potential for oxidation within each disposal facility and the leaching of metals and residual oxidation products.

Partially oxidized waste rock represents the majority of the material in the existing West and North WRDFs. Testing of this material indicates it can produce acid in the presence of water (SRK, 1995). The majority of waste rock exposed on the East WRDF is unoxidized material.

Unoxidized quartz monzonite would comprise the bulk of future waste rock. Although this material has the potential to generate acid, both field observations and test results indicated that this material is, at most, slowly reactive (SRK, 1995). Transitional zone materials represent a limited portion of the total waste rock volume. The potential for acid generation from these materials is high, requiring special waste management, including, but not necessarily limited to encapsulation and/or blending with alkaline materials. Transitional waste rock would be segregated from the unoxidized waste rock by visual inspection and field testing, if necessary, during mining and disposed of in the West and North WRDFs. NMCC is currently in the process of updating the geochemical characterization of all of these materials in order to more accurately predict their long-term behavior and prescribe suitable ARD mitigation measures, as necessary.

Although the bulk of the waste rock material does not indicate a high risk of environmental degradation, all of the WRDFs and any low-grade ore remaining in the low-grade ore stockpile would be reclaimed in a manner which has been determined to reduce infiltration and to alleviate the long-term risk of acid generation and metals leaching (SRK, 1995). Following regrading, the surface of the disposal areas would be compacted with earthmoving equipment and covered with a layer of alluvial material and revegetated.

During operations, the WRDFs would be constructed in up to 200-ft lifts to facilitate regrading during reclamation such that overall slope faces do not exceed 3.0H:1.0V. Benches would be established at the existing lift elevations and, if indicated by the test revegetation program and

concurrent reclamation, at intermediate intervals to reduce erosion. As each lift is completed, any portion not needed for access to other lifts would be regraded, covered and revegetated as soon as practicable.

To enhance revegetation, reduce erosion and minimize surface the waste rock disposal areas would be covered with suitable reclamation materials and revegetated contemporaneously with operations. This material would be roughened to reduce surface flow velocities and minimize erosion and sediment loss.

During operations, surface run-off from Animas Peak would be diverted around the disposal area to prevent surface run-on and infiltration into the waste rock. Diversion structures would be revegetated and/or protected by riprap to reduce erosion and left in place following closure.

The low-grade ore stockpile is located immediately north of the process plant area and would include about 19 million tons of rock assaying lower than 0.20 percent copper. Reclamation of this area would depend on the fate of this stockpile. If the low-grade ore stockpile is milled by the end of mine life, the pad area would be ripped, contoured for drainage control, covered with growth media and revegetated. If the low-grade stockpile remains following closure, the stockpile would be reclaimed in the same manner as the WRDFs; it would be regraded to overall slopes of 3.0H:1.0V and shaped to enhance run-off and prevent infiltration and ponding. The surface would be compacted with earth moving equipment, covered with a layer of alluvial material and the surface revegetated.

5.16.3 Plant Site

At closure, all surface facilities, equipment and buildings would be removed from the area. For buildings located on public land administered by the BLM, the concrete foundations would be broken, excavated, and disposed of is a suitable location on adjacent private land. The concrete building slabs, footings and foundations for facilities located on private land controlled by NMCC would be broken, covered with waste rock material and available growth media, regraded, and revegetated. All fuel tanks, reagent storage facilities would be removed from the site according to applicable federal and state laws. The general surface area would be shaped and contoured for surface drainage control, and covered with a minimum of 6 inches of stockpiled alluvium/growth media to conform to the surrounding topography to the extent practicable. Revegetation would occur as discussed in Section 5.10.

The tailings thickener and tailings reclaim pond would be backfilled regraded to minimize ponding prior to placement of alluvial material/growth media and revegetation. The stormwater collection pond is located adjacent to Greyback Wash east of the plant area. This pond, currently backfilled, is believed to be the source of water which created the riparian zone in Greyback Wash adjacent to it. NMCC would endeavor to maintain the riparian zone during operations when the stormwater pond would be used collect stormwater runoff by diverting water from the freshwater supply system. At closure, this pond would remain open with and the discharge pipe left in place in an attempt to recreate the current near surface hydrologic conditions which are supplying water to the riparian zone. The land bridge which conveys the tailings pipeline would also be left in place because this feature may be a contributing factor to the development of the riparian zone. The slopes of the land bridge would be stabilized and the top revegetated during reclamation.

5.16.4 Tailings Impoundment

A tailings impoundment located southeast of the plant site was designed to hold a total of 95 million tons of tailings (including tailings from 11 million tons of low-grade ore). Closure of the tailings impoundment would include:

- Final grading of embankment outslopes to establish erosion controls and controlled surface water drainage (best management practices);
- Placement of a soil or rock cover and revegetation of the embankment outslope;
- Placement of riprap and erosion controls in embankment surface water drainage facilities;
- Regrading or depositional modification of the impoundment surface to promote drainage to a permanent engineered spillway;
- Placement and vegetation of a soil cover over the tailings surface;
- Armoring of surface drainage channels and implementation of best management practices for erosion control; and
- Management of underdrainage.

Final grading of the impoundment surface can be accomplished with earthmoving equipment, or through modification of tailings disposal patterns during the final years of operation. Tailings discharge from selected locations can be used to relocate the supernatant pool to a location adjacent to the post-closure spillway, thereby reducing grading requirements and limiting earthmoving operations in areas where working conditions are expected to be difficult due to the presence of soft and saturated tailings. At the location of the spillway [see Drawing 9 in **Appendix D** (Golder, 2010)], a bedrock foundation is anticipated. If the spillway channel is erodible, grouted riprap or other erosion controls would be applied.

Consolidation seepage into the underdrain system can be anticipated to continue at declining rates for an indefinite period following the cessation of tailings disposal operations. Underdrainage would

be pumped from the underdrain collection pond to the surface of the tailings impoundment where it can be evaporated. When underdrainage is reduced to an acceptably low flow rate, the underdrain pipes beneath the embankment can be sealed with grout and the underdrain collection pond can be decommissioned.

5.16.5 Ancillary Project Facilities

In general, all surface pipelines, poles, and commercial signage would be removed. Buried pipelines and electrical conduits would be left in place.

5.16.5.1 *Fences*

The tailings and mine area would be fenced to discourage access by people, wildlife and cattle. Existing fences may be left in place depending on the location and purpose. Fences used to restrict access to potentially hazardous areas would remain in place. Other fences may remain to protect revegetation efforts. The BLM would determine the fate of fences on public lands. The remaining fences would be removed for salvage.

To prevent damage to newly seeded and revegetation areas, these areas would be protected by fencing or other appropriate measures for a period of time until revegetation is successful. It may be necessary to control small mammals as well as deer and domestic livestock. All fencing on public lands would be constructed to meet BLM requirements.

5.16.5.2 *Water Tanks*

The fresh water and process water tanks would be removed, their foundations buried in place and the sidehill cuts recontoured to approximate original topography. Following recontouring, the areas would have alluvial material placed up to 6 inches thick if the replaced fill material would not support vegetation. The areas would then be revegetated as described in Section 5.10.

5.16.5.3 *Roads*

A portion of the access road has been deeded to Sierra County and provides access through the mine site to private and public property adjacent to the west boundary of the Project. From the point where the mine access road leaves the county road north of the tailings impoundment, it would be narrowed to a standard two-lane road with a running surface approximately 30 feet wide. One culvert, located where the road crosses Greyback Wash would be left in place.

Prior to final closure, the State and BLM would determine which auxiliary roads and haul roads would be left intact. At this time, at a minimum, the road to the water tanks, haul roads, waste disposal access roads are expected to undergo reclamation.

Roads to be reclaimed would be recontoured to approximate original topography if constructed on sidehills or contoured and ripped if constructed in flat areas. Typical reclaimed cross-sections of the different road types are shown on **Figure 3-6**. Water bars would be constructed to reduce erosion.

Recontoured areas would be covered with up to 6 inches of alluvial material if replace fill material would not support vegetation and revegetated as describe in Section 5.10.

5.16.5.4 *Electrical Power*

Power for the Project would be furnished by means of existing overhead power lines. The overhead lines would be removed from the mill site and disconnected from the 115kV line owned by Sierra Electrical Cooperative by removing the wires of the last span of the line. Pumping stations and electrical substations on the site would be removed, if no other post-closure land use is identified and approved. The disturbance associated with removal would be reclaimed by regrading and seeding. If renewable energy facilities are deployed at specific buildings, these would be removed and associated disturbances regarded and reseeded.

The existing 25 kV line that provides power to the production wells, booster stations on the fresh water pipeline and the reclaim water pump stations at the tailings dam would remain in place. Sierra Electric owns this power line and is responsible for maintenance.

5.16.5.5 *Water Supply*

Water would be supplied to the mine from four production wells located about seven miles east of the plant site. A 20-inch welded steel pipeline transports the water to the mine and is buried at a minimum depth of 2 feet from the well field to the point of entry to the Project area.

The buried pipeline is owned by the BLM and would remain in place. The production wells would remain in a condition suitable for other uses. All roads, power lines and foundations for the production wells are in place. No additional disturbance would occur during the project and the well area would be left as it currently exists after closure of the mine.

5.16.5.6 *Sanitary Solid Waste Disposal*

At closure the septic tanks and leach fields would be decommissioned. All solid wastes remaining on the site would be removed off-site for proper disposal. If a private landfill is permitted for on-site disposal of solid waste, the landfill would be closed according to NMED requirements.

5.17 Estimated Reclamation Costs

A reclamation bond is required by the BLM and State of New Mexico to guarantee the completion of Project reclamation. Following regulatory review of the proposed plan of operations and reclamation techniques presented herein, NMCC would prepare, *at a time specified by the BLM* [43 CFR § 3809.401(d)], a *detailed estimate of the cost to fully reclaim the operations* as required by 43 CFR § 3809.552. The estimated costs would be based on projected actual costs to reclaim the site assuming that all reclamation would occur following operations without the benefit of contemporaneous reclamation. Prior to commencement of operations, financial assurance in the amount of the estimated costs to reclaim the disturbance which would occur during the first five years of operations would be posted with the New Mexico Energy, Minerals and Natural Resources Department, Mining and Minerals Division.

6 Acknowledgment

I certify that I have personally examined and am familiar with the information submitted herein, and based on my inquiry of those individuals responsible for obtaining the information; I believe the submitted information is true, accurate, and complete.

Barrett Sleeman, President
New Mexico Copper Corporation

December 22, 2010
Date

7 Bibliography

Adrian Brown Consultants (ABC). 1996. *Copper Flat project hydrology impact evaluation report*.

Adrian Brown Consultants (ABC). (1997). Copper Flat hydrology impact evaluation post-hearing submittal exhibits, including revised appendices O, F, and L: Report 1356A.970326.

Adrian Brown Consultants (ABC). (1998b). Hydrologic impact evaluation for the proposed action, Copper Flat project: Report 1356A.981219. Prepared for Alta Gold Co., December 19, 1998.

Air Sciences Inc. (1995). *Baseline Monitoring Data for the Copper Flat Project.*

Barbour, M.G., J.H. Burk, and W.D. Pitts. (1980). Terrestrial Plant Ecology. The Benjamin/Cummings Publishing Company, Inc. Menlo Park, California.

Biota Information System of New Mexico (BISON-M). (1995). Biological database for New Mexico. The New Mexico Department of Game and Fish in cooperation with the Bureau of Land Management, U.S. Fish and Wildlife Service, U.S. Army Corps of Engineers, Bureau of Reclamation, U.S. Forest Service, and the University of New Mexico. Bonham, C.D. (1989). Measurements for Terrestrial Vegetation. John Wiley and Sons, New York.

Bureau of Land Management, Las Cruces. (1978). *Assessment Record on Quintana Minerals Corporation's Proposed Open Pit Copper Mine at Copper Flat.* Las Cruces.

Bureau of Land Management, Las Cruces. (1996). *Copper Flat Project Draft Environmental Impact Statement.* Las Cruces.

Bureau of Land Management, Las Cruces. (1996). *Biological Assessment for the Alta Gold Company Copper Flat Project.* Las Cruces: BLM, Las Cruces.

BLM, Las Cruces, New Mexico. (1993). *Environmental Assessment for Re-establishing the Copper Mine, Copper Flat, Mexico*.

Bureau of Land Management. (1999). Preliminary Final Environmental Impact Statement, Copper Flat Project: Las Cruces, N. Mex., U.S. Department of the Interior, 491 p. Prepared by ENSR, Fort Collins, Colo.

Davie, W., Jr., and Spiegel, Z. (1967). Las Animas Creek hydrographic survey report, geology and water resources of Las Animas Creek and vicinity, Sierra County, New Mexico: New Mexico State Engineering Report.Dunn, P. (1982). *Advances in Geology of the Porphry copper Deposites, Southwester North America.* Tucson: the University of Arizona Press.

Dunn, P. (1984). Geologic studies during the development of the Copper Flat porphyry deposit: Mining Engineering, February, 1984.Evaskovich, J., & Higgins, H. (1991). *A Class III Cultural Resources Inventory for a Proposed Copper Mine Expansion.* Mariah Associates, Inc.

Fowler, L.L. (1982). Brecciation, alteration, and mineralization at the Copper Flat porphyry copper deposit, Hillsboro, New Mexico: University of Arizona, Tucson, M.S. thesis, 133 p.Glover, F. A. (1977). *Environmental Assessment Report, Copper Flat Mine Development, Copper Flat, New Mexico.*

Goff. (1998).

Golder Associates, Inc. (2010). Copper Flat Project: Conceptual Design Report.

Golder Associates, Inc. (2011a). Copper Flat Project: Borrow Source and Stockpile Evaluation. Technical Memorandum prepared for New Mexico Copper Corporation. June 16, 2011.

Golder Associates, Inc. (2011b). Preliminary Design Report: Copper Flat Waste Rock Disposal Facilities. Prepared for New Mexico Copper Corporation. June 22, 2011.

Greene, D.K., and Halpenny, L.C. (1976). Report on development of ground-water supply for Quintana Minerals Corporation Copper Flat Project, Hillsboro, New Mexico: Tucson, Water Development Corporation, 32 p.

Harley, G.T. (1934). The geology and ore deposits of Sierra County, New Mexico: Socorro, N. Mex., New Mexico School of Mines Bulletin 10.

Hawley, J.W. and Kennedy, J.F. (2004). Creation of a Digital Hydrogeologic Framework Model of the Mesilla Basin and Southern Jornada Del Muerto basin. WRRI Technical Completion report No. 332.

Hawley, J.W., Kennedy, J.F., Ortiz, M., and Carrasco, S. (2005). Digital Hydrogeologic Framework Model of the Rincon Valley and Adjacent areas of Dona Ana, Sierra, and Luna Counties, NM: Addendum to the Creation of a Digital Hydrogeologic Framework Model of the Mesilla Basin and Southern Jornada del Muerto Basin, New Mexico Water Resources Research Institute, New Mexico State University, Technical Report No. 332, June 2004, 12 p.

Hedlund, D.C. (1974). Age and structural setting of base-metal mineralization in the Hillsboro-San Lorenzo area, southwestern New Mexico *in* Siemers, C.R., Woodward, L.A., and Callender, J.F., eds., Silver Anniversary Guidebook; Ghost Ranch; North-Central New Mexico: New Mexico Geological Society Guidebook 25, p. 378–379.

Hydro Resources, Inc. (2002). Copper Flat: Albuquerque, N. Mex., Hydro Resources, Inc.

IHICS. (1995). Integrated Habitat Inventory Classification System Database.

Intera. (2010). Sampling and Analysis Plan for Copper Flat Mine. Prepared for New Mexico Copper Corporation. Submitted to Mining and Minerals Division of the New Mexico Energy, Minerals and Natural Resources Department. September 2010.

Johnson, R. D. (1996). *Copper Flat Revegetation Information - Technical Memo.*

Kelley, S.A., and Chapin, C.E. (1997). Cooling histories of mountain ranges in the southern Rio Grande rift based on apatite fission-track analysis—A reconnaissance survey: New Mexico Geology, v. 19, no. 1, p. 1–14.

Locke, Augustus. (1926). The formation of certain ore bodies by mineralization stoping: Economic Geology, v.21, p. 431-453.

Lozinsky, R.P. and J.W. Hawley. (1986). The Palomas Formation of south-central New Mexico -- a formal definition. New Mexico Geology. 8. 4, p: 73-82.

McLemore, V.T., Munroe, E.A., Heizler, M.T., McKee, C. (2000). Geology and evolution of the mineral deposits in the Hillsboro District, Sierra County, New Mexico *in* Geology and Ore Deposits 2000, The Great Basin and Beyond: Geological Society of Nevada, Program with abstracts, p. 63.

Minton. (1961).

Murray, C. R. (1959). Ground-water conditions in the nonthermal artesian-water basin south of Hot Springs, Sierra County, New Mexico: New Mexico State Engineering Technical Report 10.

Natural Resources Conservation Service (NRCS). (1984). Soil Survey of Sierra County Area, New Mexico. Natural Resources Conservation Service (NRCS). (2010). Ecological site descriptions, accessed online at: http://esis.sc.egov.usda.gov/ESIS/About.aspx.

Neher, R.E. (1984). Soil survey of Sierra County area, New Mexico: Washington, DC, U.S. Department of Agriculture, Soil Conservation Service, 80 p.

Newcomer, R.W., and Finch, S.T. (1993). Water quality and impacts of proposed mine and mill, Copper Flat Mine site, Sierra County, New Mexico, 30 p. Prepared for Gold Express Corporation.

Newcomer, R. W. Jr., Shomaker, J.W., and Finch, S.T., Jr. (1993). Hydrologic assessment, Copper Flat project, Sierra County, New Mexico. Prepared for Gold Express Corporation.

New Mexico Environment Department Groundwater Quality Bureau (NMED GWQB). (2008). Letter to Mr. George Lotspeich regarding Abatement plan required at Copper Flat Mine site, DP-1, August 20, 2 p.

Norman, D.I., Kyle, P.R., and Baron, C. (1989). Analysis of trace elements including rare earth elements in fluid inclusion liquids: Economic Geology, v.84, p. 162-166.

Olendorff, R.R., A.D. Miller, & R.N. Lehman. (1981). *Suggested Practices for Raptor Protection on Power Lines: The State of the Art in 1981*. Raptor Research Report No. 4, Raptor Research Foundation, Inc.

Phillips, W.J. (1973). Mechanical effects of retrograde boiling and its probable importance in the formation of some porphyry ore deposits: Institution of Mining Metallurgy Transactions, Sec. B, v. 82, p. 90-98.

Raugust, J.S. (2003). The natural defences of Copper Flat, Sierra County, New Mexico: New Mexico Bureau of Geology and Mineral Resources Open-file report 475, Socorro, N. Mex., New Mexico Institute of Mining and Technology.

Richards, J.P. (2003). Tectono-magmatic precursors for geophysical data over a copper gold porphyry Cu-(Mo-Au) deposit formation, *in* Journal of Economic Geology, v. 96, p. 1419–1431.

Seaber, P.R., Kapinos, F.P., and Knapp, G.L. (1987). Hydrologic unit maps: U.S. Geological Survey Water-Supply Paper 2294, 63 p.

Seager, W.R. and J.W. Hawley. (1973). Geology of Rincon quadrangle, New Mexico. New Mexico Bureau of Mines and Mineral Resources Bulletin 102. 56 p.

Seager, W.R., Shafiqullah, M., Hawley, J.W., and Marvin, R.F. (1984). New K-Ar dates from basalts and the evolution of the Southern Rio Grande Rift: Geological Society of America Bulletin, v. 95, p.87-99.Sechrist, & Laumbach. (1995). *Archeological Surveys of Areas in the Copper Flat Project Area Near Hillsboro, Sierra County, New Mexico.* Human Systems Research.

Segerstrom, K. and Antweiler, J.C., III. (1975). Placer-gold deposits of the Las Animas District, Sierra County, New Mexico: USGS OFR 75-206.

Sergent, Hauskins, and Beckwith (SHB). (1980). Geotechnical and design development report, tailings dam and disposal area, Quintana Minerals Corporation, Copper Flat Project, Golddust, New Mexico. Technical report prepared for Quintana Minerals.Shomaker, J. W., & Newcomer, B. (1993). *Hydrologic Assessment, Copper Flat Project, Sierra County, New Mexico.*

Sierra Soil and Water Conservation District. (1990). Range Condition Worksheets.

Soil Survey Staff. (1999). Soil taxonomy, a basic system of soil classification for making and interpreting soil surveys (2d ed.): Washington, D.C., U.S. Department of Agriculture Natural Resources Conservation Service Agriculture Handbook 436, U.S. Government Printing Office.SRK Consulting. (1995). *Copper Flat Hydrogeologic Studies.* Reno.

SRK Consulting. (1995). Copper Flat Mine, Hydrogeological Studies: Steffen Robertson and Kirsten, Inc.

SRK Consulting. (1996). Copper Flat Mine, Mining Permit Application, v. 1, p. 2-12.

SRK Consulting. (1997a). Copper Flat post-hearing submittal exhibits: Steffen Robertson and Kirsten, Inc.

SRK Consulting. (1997b). Copper Flat Mine-Compilation of pit lake studies: Steffen Robertson and Kirsten, Inc., Project 68610. Prepared for Alta Gold Co.

SRK Consulting. (2010a). Preliminary Draft Copper Flat Plan of Operations, New Mexico Copper Corporation: SRK Consulting, Reno, Nevada

SRK Consulting. (2010b). NI-43-101 Preliminary Assessment, THEMAC Resources Group Limited, Copper Flat Project, Sierra County, New Mexico: Lakewood, Colo. Prepared by SRK Consulting for THEMAC Resource Group Limited, June 30, 2010.Stinnett, K. (1991). *Biological Assessment for Gold Express Corporation's Copper Flat Mining and Milling Operation, Sierra County, New Mexico.*

Titley, S.R. (1982). Geologic setting of porphyry copper deposits, southeastern Arizona, *in* Titley, S.R., ed., Advances in geology of the porphyry copper deposits, pp 37-58.Wilson, C.A., Orr, C.A, White, R.R., and Roybal, R.G. (1981). Water resources of the Rincon and Mesilla Valleys and adjacent areas, New Mexico: New Mexico State Engineering Technical Report 43.





NORTH

DESIGN: -	DRAWN: -	REVIEWED: -	
CHECKED: -	APPROVED: -	DATE: 12/2/2010	
FILE NAME PoO_Fig1-01_Location_JQG_20101202			

NEW MEXICO COPPER CORPORATION

COPPER FLAT MINE

PROJECT LOCATION

DRAWING NO. **FIGURE 1-1**	SHEET 1 OF 28	REVISION NO. **A**
JOB NO. **191000-03**		

Path: H:\Copper_Flat\New Mexico Copper Corp\191000_03_Copper_Flat_Permitting\040_Drafting\20101115\PoO_Fig1-01_Location_JQG_20101202.mxd



Figure 1-2
Regional Location
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\1_introduction\1-1_SiteLocationMap.mxd 07/22/2010



Land Owner
- Private
- Public - BLM
- State - New Mexico

- Mine Plan Boundary
- Disturbance By Previous Operators (989 acres)
- Pipeline

Well and Water Rights Owner
- Frost & Gray
- Hydro

IF THE ABOVE BAR DOES NOT SCALE 1 INCH, THE DRAWING SCALE IS ALTERED

DESIGN: -	DRAWN: -	REVIEWED: -	
CHECKED: -	APPROVED: -	DATE: 5/6/2011	
FILE NAME PoO_Fig2-01_Regional_JQG_20110421			

NEW MEXICO COPPER CORPORATION

COPPER FLAT MINE

LOCAL AREA LAYOUT

DRAWING NO.	SHEET	REVISION NO.
FIGURE 2-1		A
JOB NO. 191000-03		

Path: H:\Copper_Flat\New Mexico Copper Corp\191000_03_Copper_Flat_Permitting\040_Drafting\20101115\PoO_Fig2-01_Regional_JQG_20110421.mxd



EXPLANATION

Public Land | Mine Boundary | Disturbance By Previous Operators (989 acres)

IF THE ABOVE BAR DOES NOT SCALE 1 INCH, THE DRAWING SCALE IS ALTERED

DESIGN: -	DRAWN: -	REVIEWED: -	
CHECKED: -	APPROVED: -	DATE: 4/15/2011	
FILE NAME: PoO_Fig2-02_Land_JQG_20110415			

NEW MEXICO COPPER CORPORATION

COPPER FLAT MINE

LAND STATUS AND EXISTING DISTURBANCE

DRAWING NO.	SHEET	REVISION NO.
FIGURE 2-2		A
JOB NO. 191000-03		

Path: H:\Copper_Flat\New Mexico Copper Corp\191000_03_Copper_Flat_Permitting\040_Drafting\20101115\PoO_Fig2-02_Land_JQG_20110415.mxd



EXPLANATION

- Public
- Mine Boundary
- Plant Facilities
- Pond
- Waste Rock
- Topsoil Stockpile
- Tailings
- Ore Stockpile
- Pit
- Haul Road
- Diversion
- Ancillary
- Access Road
- Private Exploration Area
- Public Exploration Area

IF THE ABOVE BAR DOES NOT SCALE 1 INCH, THE DRAWING SCALE IS ALTERED

DESIGN: -	DRAWN: -	REVIEWED: -	
CHECKED: -	APPROVED: -	DATE: 6/22/2011	

FILE NAME: PoO_Fig3-01_PropFacilities_JQG_20110622

NEW MEXICO COPPER CORPORATION

COPPER FLAT MINE

DRAWING TITLE: **PROPOSED FACILITY LAYOUT**

DRAWING NO. **FIGURE 3-1**

JOB NO. **191000-03**

REVISION NO. **A**

Path: H:\Copper_Flat\New Mexico Copper Corp\191000_03_Copper_Flat_Permitting\040_Drafting\20110621_Response_to_Comments\PoO_Fig3-01_PropFacilities_JQG_20110622.mxd



EXPLANATION

Public
Plant Facilities
Topsoil Stockpile
Pit
Ancillary
Private Exploration Area
Mine Boundary
Pond
Tailings
Haul Road
Access Road
Public Exploration Area
Waste Rock
Ore Stockpile
Diversion

IF THE ABOVE BAR DOES NOT SCALE 1 INCH, THE DRAWING SCALE IS ALTERED

DESIGN: -	DRAWN: -	REVIEWED: -
CHECKED: -	APPROVED: -	DATE: 6/22/2011
FILE NAME: PoO_Fig3-02_Plant_JQG_20110622		

NEW MEXICO COPPER CORPORATION

COPPER FLAT MINE

DRAWING TITLE: **PROPOSED PLANT SITE LAYOUT**

DRAWING NO. **FIGURE 3-2**

REVISION NO. **A**

JOB NO. **191000-03**

Path: H:\Copper_Flat\New Mexico Copper Corp\191000_03_Copper_Flat_Permitting\040_Drafting\20110621_Response_to_Comments\PoO_Fig3-02_Plant_JQG_20110622.mxd

01853



EXPLANATION

Public | Plant Facilities | Waste Rock | Tailings | Pit | Diversion | Access Road
Mine Boundary | Pond | Topsoil Stockpile | Ore Stockpile | Haul Road | Ancillary

IF THE ABOVE BAR DOES NOT SCALE 1 INCH, THE DRAWING SCALE IS ALTERED

DESIGN: -	DRAWN: -	REVIEWED: -	
CHECKED: -	APPROVED: -	DATE: 6/22/2011	
FILE NAME: PoO_Fig3-03_PropTopo_JQG_20110622			

NEW MEXICO COPPER CORPORATION

COPPER FLAT MINE

DRAWING TITLE: **PROPOSED FACILITY TOPOGRAPHY**

DRAWING NO. **FIGURE 3-3**

REVISION NO. **A**

JOB NO. **191000-03**

Path: H:\Copper_Flat\New Mexico Copper Corp\191000_03_Copper_Flat_Permitting\040_Drafting\20110621_Response_to_Comments\PoO_Fig3-03_PropTopo_JQG_20110622.mxd





FEET
0 250 500 1000
1 inch equals 500 feet

IF THE ABOVE BAR DOES NOT SCALE 1 INCH, THE DRAWING SCALE IS ALTERED

DESIGN: -	DRAWN: -	REVIEWED: -	
CHECKED: -	APPROVED: -	DATE: 6/22/2011	
FILE NAME: PoO_Fig3-04_Sections_JQG_20110622.dwg			

NEW MEXICO COPPER CORPORATION

COPPER FLAT MINE

DRAWING TITLE: **OPEN PIT CROSS SECTIONS**

DRAWING NAME: FIGURE 3-4

JOB NO: 191000-03

REVISION NO. **A**

H:\Copper_Flat\New Mexico Copper Corp\191000_03_Copper_Flat_Permitting\040_Drafting\20110621_Response_to_Comments\PoO_Fig3-04_Sections_JQG_20110622.dwg



DESIGN: -	DRAWN: -	REVIEWED: -	
CHECKED: -	APPROVED: -	DATE: 6/22/2011	
FILE NAME: PoO_Fig3-05_ProcessCircuit_JQG_20110622.dwg			

PREPARED FOR:

NEW MEXICO COPPER CORPORATION

COPPER FLAT PROJECT

DRAWING TITLE: PROPOSED PROCESS CIRCUIT

DRAWING NO. **FIGURE 3-5**

REVISION NO. **A**

JOB NO. **191000-03**

H:\Copper_Flat\New Mexico Copper Corp\191000_03_Copper_Flat_Permitting\040_Drafting\20110621_Response_to_Comments\PoO_Fig3-05_ProcessCircuit_JQG_20110622.dwg

FLAT ROADS



OPERATIONS CONFIGURATION



RECLAIMED CONFIGURATION

SIDEHILL ROADS



OPERATIONS CONFIGURATION



RECLAIMED CONFIGURATION

	PREPARED FOR: **NEW MEXICO COPPER CORP. COPPER FLAT PROJECT**	DRAWING TITLE: TYPICAL ROAD CONFIGURATION AND RECLAMATION	
DESIGN: - DRAWN: - REVIEWED: -		DRAWING NO. **FIGURE 3-6**	REVISION NO. **A**
CHECKED: - APPROVED: - DATE: 6/22/2011		JOB NO. **191000-03**	
FILE NAME: PoO_Fig3-06_Roads_JQG_20110622.dwg			

H:\Copper_Flat\New Mexico Copper Corp\191000_03_Copper_Flat_Permitting\040_Drafting\20110621_Response_to_Comments\PoO_Fig3-06_Roads_JQG_20110622.dwg



STRATIGRAPHY

TERTIARY - QUATERNARY	CRETACEOUS	PALEOZOIC AND PRECAMBRIAN
Quaternary Alluvium (Qvy+Qvo)	Late Cretaceous – Silicic Intrusives (Kli)	Paleozoic Siliclastic and Carbonate Sedimentary Rocks (pC through PM)
Tertiary Volcanics (TQb+Tv)	Cretaceous Latite – Andesite Intrusives (Kql+Kd+Kis)	
Tertiary Santa Fe Group (Tsfp+Tsf)	Andesite rocks near Copper Flat (Ka)	

LEGEND

NORMAL FAULT, BALL ON DOWNTHROWN SIDE; DASHED WHERE INFERRED, DOTTED WHERE BURIED.

CONTACT

A A' CROSS SECTION LOCATION

(see Figure 7-2 for cross section detail)

NORTH

0 5,825 11,650

FEET

SOURCES:

(1) HARLEY (1934)
(2) SEAGER ET AL. (1982)
(3) HEDLUND (1977)
(4) ALMINAS ET AL. (1978)

from BLM, 1999

Figure 4-1
Regional Surface Geology
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\7_geology\7-1_general_surface_geology.mxd 07/22/2010

A

A'



LEGEND:

QUATERNARY
- Qvy
- Qvo
- Stream Alluvium

TERTIARY
- Tsfp
- Tsfp Clay
- Palomas Formation
- Tsf – Rincon Valley Formation
- Tv – Tertiary Volcanics

CRETACEOUS
- Ka
- Kis
- Volcanics and Intrusives

PALEOZOIC
- Bedrock Carbonate and Clastic Rocks

SOURCES:
(1) HARLEY (1934)
(2) SEAGER ET AL. (1982)
(3) HEDLUND (1977)
(4) ALMINAS ET AL. (1975)

SCALE IN FEET
1500 VERTICAL 0'
6000 HORIZONTAL 0'

(see Figure 7-1 for cross section location)

from BLM, 1999

Figure 4-2
Schematic Geologic Cross Section (A-A')
New Mexico Copper Corporation



Figure 4-3
Geologic Structural Features of the Region
New Mexico Copper Corporation

from BLM, 1999

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\7_geology\7-3_geology_hillsboro.mxd 07/16/2010



from McLemore et al., 2000; Dunn, 1982; Hedlund, 1985

Figure 4-4
Geologic Schematic of the Hillsboro Mining District, New Mexico
New Mexico Copper Corporation



N
W E
S

Watersheds:
USGS Hydrologic Unit Map
Mine Boundary:
Tom Van Bebber
Imagery Information:
-USGS 7.5-Minutes County DOQQ mosaic
Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

0 3,500 7,000 14,000 21,000
Feet

Legend

- Stream Sample
- Spring Sample
- Proposed Mine Permit Boundary

Watersheds
- Caballo
- El Paso-Las Cruces
- Sub-Watershed

Figure 4-5
Proposed Surface Water Sampling Locations
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\8-SurfaceWater\8-1_surface_wtr_locations.mxd 08/31/2010



0 50 100 200

Feet

Imagery Information:
-USGS 7.5-Minutes County DOQQ mosaic
Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

Legend

Profile Line

Figure 4-6
Proposed Parallel Profiles for Pit Lake Survey

New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\9_groundwater\9-1_LRG_basins.mxd 07/30/2010



0 7.5 15 30

Miles

Basin Boundaries:
RGIS website/NMOSE
Imagery Information:
Landsat imagery from
University of Maryland NLCD

Legend

- City/Town
- Site Location
- Road
- OSE Declared Basin
- Lower Rio Grande
- Las Animas

Figure 4-7
Lower Rio Grande Basin
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\9_groundwater\9-1_LRG_basins.mxd 07/30/2010



from John W. Shomaker, Inc., 1993

Figure 4-8
Conceptual Model of Groundwater Flow System
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\7_geology\9-2_concep_hydrogeo.mxd 07/21/2010



N
W E
S

Watersheds:
USGS Hydrologic Unit Map
Mine Boundary:
Tom Van Bebber
Imagery Information:
-USGS 7.5-Minutes County DOQQ mosaic
Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

0 3,500 7,000 14,000 21,000
Feet

Legend

- Identified Spring
- Proposed Mine Permit Boundary

Watersheds
- Caballo
- El Paso-Las Cruces
- Sub-Watershed

Figure 4-9
Spring and Stream Locations
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\8-SurfaceWater\8-1_surface_wtr_locations.mxd 08/26/2010



—4300— WATER TABLE ELEVATION

NORTH

0 8,000 16,000
FEET

from ABC, 1998B

Figure 4-10
Water Level Contours
New Mexico Copper Corporation



LEGEND

- 4500 — INDEX CONTOUR
- STREAM
- ROADS
- WELL
- WINDMILL
- SPRING
- MOUNTAIN PEAK
- SURFACE WATER
- 5900 — 100' GROUNDWATER CONTOUR
- 5900? — EQUIPOTENTIAL LINES INFERRED FROM TOPOGRAPHY

from ABC, 1997

Figure 4-11
Water Level Map of
Copper Flat Pit Area
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\9_groundwater\9-5_wtr-table-map.mxd 07/29/2010



	GWQ96-22		PIT LAKE		GWQ96-23	
	JULY '96	AUG '97	AUG '95	AUG '97	APR '97	AUG '97
pH	7.5	7.65	8.31	8.16	7.89	7.68
TDS	700	700	4707	5021	770	920
SO_4	250	230	3170	3100	150	410
Cu	<0.025	<0.025	<0.025	0.050	<0.025	<0.025
Fe	<0.05	<0.05	<0.025	<0.05	6.5	0.82

from SRK, 1998

Figure 4-12
Conceptual Model of Pit Lake Monitoring Well Relationship with Water Quality Reports

New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\9_groundwater\9-6_well_WQReports.mxd 07/29/2010



DETAIL A

from SRK, 1995

Figure 4-13
Conceptual Design,
Tailings Seepage Control
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\9_groundwater\9-7_seepage-control.mxd 07/29/2010



N
W E
S

Well Locations:
SRK or OSE
Mine Boundary:
Tom Van Bebber
Imagery Information:
-USGS 7.5-Minutes County DOQQ mosaic
Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

0 3,000 6,000 12,000 18,000
Feet

Legend

- Road
- Project Well
- Proposed Mine Permit Boundary

NM OSE Wells (Use)
- Domestic
- Irrigation
- Stock

Figure 4-14
Regional Groundwater Well Locations
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\9_groundwater\9-9_Regional GWwells.mxd 09/07/2010

01871



N
W E
S

Well Locations:
SRK or OSE
Mine Boundary:
Tom Van Bebber
Imagery Information:
-USGS 7.5-Minutes County DOQQ mosaic
Sierra County, 2009
Projection Information:
-New Mexico State Plane West, NAD 1927

0 3,000 6,000 12,000 18,000
Feet

Legend

Proposed Monitoring Well
Aquifer
- Crystalline Bedrock
- Qauternary Alluvium
- Santa Fe Group
- Unknown

- Water Level Only
- Water Level & Water Quality
- Proposed Mine Permit Boundary
- Road

Figure 4-15
Proposed Monitoring Well Program
New Mexico Copper Corporation

S:\Projects\NMC-001_New Mexico Copper Corporation\GIS\Maps\SAP_7-2010\9_groundwater\9-10_ProposedGWwells.mxd 09/07/2010

01872

ID	Task Name
1	**Mine Permitting (Pre-Construction)**
2	**Mine Construction**
3	**Mine Operation**
4	**Waste Rock Disposal Areas**
5	West Waste Disposal
6	North Waste Disposal
7	East Waste Disposal
8	South Waste Disposal / Low-Grade Stockpile
9	**Tailings Impoundment Reclamation**
10	CoverlRevegetate Outer Embankment
11	Tailings Water Removal
12	GradelCover/RevegetateTailings Surface
13	Surface Pipeline Removal
14	**Pit Closure**
15	Highwall Stabilization
16	RamplHighwali Barricades
17	**Plant Area Reclamation**
18	Structure RemovallFoundation Burial
19	Regrade/Fill
20	Thickener Decommissioning
21	Septic System Decommissioning
22	**Road Reclamation**
23	Reduce Access Road Width
24	Remove / Barricade Haul Roads
25	Recontour / Revegetate Water Storage Road
26	**Utilities Reclamation**
27	Remove Above Ground Water Pipeline
28	Plug Underground Water Supply Pipeline
29	Remove S~e Water Supply Pump Stations
30	Remove Plant Site Powerlines
31	Disconnect 115kV Line
32	**Monitoring/Research Testing**
33	Revegetation Test Program
34	Revegetation Monitoring
35	Groundwater Monitoring



* Schedule approximate and subject to change with approval.

Figure 5-1
COPPER FLAT PROJECT
TENTATIVE SCHEDULE

01873



EXPLANATION

- Public
- Mine Boundary

IF THE ABOVE BAR DOES NOT SCALE 1 INCH, THE DRAWING SCALE IS ALTERED

DESIGN: -	DRAWN: -	REVIEWED: -
CHECKED: -	APPROVED: -	DATE: 6/22/2011
FILE NAME: PoO_Fig5-02_ReclTopo_JQG_20100622		

NEW MEXICO COPPER CORPORATION

COPPER FLAT MINE

POST-RECLAMATION FACILITY TOPOGRAPHY

DRAWING NO. FIGURE 5-2	SHEET 27 OF 28	REVISION NO. A
JOB NO. 191000-03		

Path: H:\Copper_Flat\New Mexico Copper Corp\191000_03_Copper_Flat_Permitting\040_Drafting\20110621_Response_to_Comments\PoO_Fig5-02_ReclTopo_JQG_20100622.mxd

APPENDIX A

Claims List

Unpatented Lode and Placer Claims:				
Claim Name		Recorded Book	Page	B.L.M Serial No.
Olympia		H	761	NM MC 60057
GLUCK AUF		I	327	NM MC 60058
Taurus		J	682	NM MC 60059
Hercules		K	231	NM MC 60060
EL ORO No. 3		P	52	NM MC 60063
Saint Louis Republic		I	80	NM MC 60069
Delores		27	269	NM MC 60070
HIGHLANDS No. 1		T	405	NM MC 60071
HIGHLANDS No. 2		T	405	NM MC 60072
HIGHLANDS No. 3		T	406	NM MC 60073
THE WELLINGTON		T	406	NM MC 60074
Three Boys No. 1		T	176	NM MC 60080
BLUE MOON		R	631	NM MC 60081
The Leone		U	478	NM MC 60082
Dolores Placer		36	13	NM MC 60083
JONES HILL PLACER		27	212	NM MC 60084
Duke No. 1		40	23	NM MC 60085
Duke No. 2		40	24	NM MC 60086
Graveyard Placer		29	424	NM MC 60021
Old Cabin Placer		29	420	NM MC 60022
Rainey Season Placer		33	163	NM MC 60027
Desert Gold Placer		R	359	NM MC 60043
Gray Black Placer		R	554	NM MC 60044
Black Sand Group 9	No. 1 Placer (Amended)	46	173	NM MC 60045
Black Sand Group 10	No. 3 Placer (Amended)	46	185	NM MC 60046
Surprise No. 1 Lode		48	13	NM MC 60052
Surprise No. 2 Lode		48	102	NM MC 60053
Dutch-1 Lode		48	556	NM MC 60054
Dutch-2 Lode		48	558	NM MC 60055
Dutch-3 Lode		48	557	NM MC 60056
Renew No. 1 Lode		58	622	NM MC 106464
Renew No. 2 Lode		58	623	NM MC 106465
M. S. #1		34	146	NM MC 60093
M. S. #2		34	146	NM MC 60094
M. S. #3		34	147	NM MC 60095
M. S. #4		34	147	NM MC 60096
M. S. #5		34	148	NM MC 60097
M. S. #6		34	148	NM MC 60098
M. S. #8		34	149	NM MC 60099
M. S. #10		34	150	NM MC 60101
M. S. #11		34	151	NM MC 60102
M. S. #12		34	151	NM MC 60103
M. S. #13		34	152	NM MC 60104
M. S. #14		34	152	NM MC 60105
M. S. #15		34	153	NM MC 60106
M. S. #16		34	153	NM MC 60107
M. S. #17		34	154	NM MC 60108
M. S. #18		34	154	NM MC 60109
M. S. #20		34	155	NM MC 60110
M. S. #21		34	156	NM MC 60111
M. S. #22		34	156	NM MC 60112
M. S. #23		34	157	NM MC 60113
M. S. #25		34	158	NM MC 60114
M. S. #26		34	158	NM MC 60115
M. S. #29		34	160	NM MC 60118
M. S. #33		34	162	NM MC 60122

Unpatented Lode and Placer Claims:			
	Recorded		B.L.M
Claim Name	Book	Page	Serial No.
M. S. #38	34	164	NM MC 60123
M. S. #48	34	167	NM MC 60129
M. S. #49	34	168	NM MC 60130
M. S. #53	34	168	NM MC 60131
M. S. #102	34	176	NM MC 60138
M. S. #104	34	177	NM MC 60139
M. S. #105	34	276	NM MC 60140
M. S. #106	34	277	NM MC 60141
M. S. #107	34	178	NM MC 60142
M. S. 222	34	543	NM MC 60170
M. S. 223	34	543	NM MC 60171
M. S. 224	34	544	NM MC 60172
M. S. 225	34	544	NM MC 60173
M. S. 228	34	546	NM MC 60176
M. S. 264	34	563	NM MC 60194
M. S. 282	34	572	NM MC 60210
M. S. 288	34	575	NM MC 60216
M. S. 289	34	576	NM MC 60217
M. S. 290	34	576	NM MC 60218
M. S. 291	34	577	NM MC 60219
M. S. 292	34	577	NM MC 60220
M. S. 293	34	578	NM MC 60221
M. S. 316	34	589	NM MC 60240
M. S. 320	34	591	NM MC 60244
M. S. 322	34	592	NM MC 60246
M. S. 329	34	596	NM MC 60253
M. S. 330	34	596	NM MC 60254
M. S. 331	34	597	NM MC 60255
M. S. 337	34	12	NM MC 60261
M. S. 338	34	13	NM MC 60262
M. S. 339	34	13	NM MC 60263
M. S. 340	34	14	NM MC 60264
M. S. 341	34	14	NM MC 60265
M. S. 342	34	15	NM MC 60266
M. S. 345	34	16	NM MC 60267
M. S. 346	34	17	NM MC 60268
M. S. 347	34	17	NM MC 60269
M. S. 438	41	564	NM MC 60312
M. S. 439	41	606	NM MC 60313
M. S. 440	41	607	NM MC 60314
M. S. 441	41	714	NM MC 60315
M. S. 452	45	353	NM MC 60318
M. S. 453	45	354	NM MC 60319
M. S. 454	45	355	NM MC 60320
M. S. 455	45	356	NM MC 60321
M. S. 456	45	357	NM MC 60322
M. S. 458	45	359	NM MC 60324
M. S. 460	45	361	NM MC 60326
M. S. 461	45	362	NM MC 60327
M. S. 462	45	363	NM MC 60328
M. S. 463	45	364	NM MC 60329
M. S. 464	45	365	NM MC 60330
M. S. 465	45	366	NM MC 60331
M. S. 467	45	368	NM MC 60333
M. S. 468	45	369	NM MC 60334
M. S. 469	45	370	NM MC 60335

Unpatented Lode and Placer Claims:			
	Recorded		B.L.M
Claim Name	Book	Page	Serial No.
M. S. 470	45	371	NM MC 60336
M. S. 471	45	372	NM MC 60337
M. S. 472	45	373	NM MC 60338
M. S. 473	45	374	NM MC 60339
M. S. 474	45	375	NM MC 60340
M. S. 475	71	1927	NM MC 163361
M. S. 476	71	1928	NM MC 163362
M. S. 477	71	1929	NM MC 163363
M. S. 478	71	1930	NM MC 163364
ANIMAS #1 Placer	45	443	NM MC 60341
ANIMAS #2 Placer	45	444	NM MC 60342
The Betsy Ross	R	93	NM MC 60344
Wicks Extension No. 1	R	100	NM MC 60346
Anderson Extension No. 2	R	93	NM MC 60348
Crescent 101	41	358	NM MC 60349
Wicks Extension 100	41	359	NM MC 60350
Betsy Ross 101	41	360	NM MC 60351
Portland 101	41	361	NM MC 60352
Ready Pay Apex 100	41	362	NM MC 60353
Anderson Extension 101	41	363	NM MC 60354

Unpantented Millsite			
Claim Name	Book	Page	BLM Serial No.
Greer No. 2	47	611	NM MC 72821
Chatfield	47	521	NM MC 72822
Chatfield No. 3	47	523	NM MC 72823
Chatfield No. 4	47	762	NM MC 72824
Chatfield No. 5	47	763	NM MC 72825
Chatfield No. 6	47	764	NM MC 72826
Chatfield No. 9	53	521	NM MC 81353
Chatfield No. 10	53	522	NM MC 81354
Chatfield No. 25	56	689	NM MC 100695

Newly Located Unpatented Lodes		
Claim Name	**Book**	**Page**
CU 1	116	902
CU2	116	903
CU 3	116	904
CU 4	116	905
CU 5	116	906
CU 6	116	907
CU 7	116	908
CU 8	116	909
CU 9	116	910
CU 10	116	911
CU 11	116	912
CU 12	116	913
CU 13	116	914
CU 14	116	915
CU 15	116	916
CU 16	116	917
CU 17	116	918
CU 18	116	919
CU 19	116	920
CU 20	116	921
CU 21	116	922
CU 22	116	923
CU 23	116	924
CU 24	116	925
CU 25	116	926
CU 26	116	927
CU 27	116	928
CU 28	116	929
CU 29	116	930
CU 30	116	931
CU 31	116	932
CU 32	116	933
CU 33	116	934
CU 34	116	935
CU 35	116	936
CU 36	116	937
CU 37	116	938
CU 38	116	939
CU 39	116	940
CU 40	116	941
CU 41	116	942
CU 42	116	943
CU 43	116	944
CU 44	116	945

Patented Claims	
Claim Name	**Mineral Survey**
Feeder	M.S. 943C
Chance	M.S. 945A
Xmas	M.S. 945B
Extension	M.S. 945D
Smokey Jones	M.S. 1024
Little Jewess	M.S. 1715
Wisconsin	Lot No. 805
Copper King	Lot No. 733A
Ventura	Lot No. 733B
Castle Hill	Lot No. 733C
Copperopolis	Lot No. 736
83	Lot No. 806
Soudan	Lot No. 807
Stenberg	M.S. 2066
Allhutten	M.S. 2066
Craze Martin	M.S. 2066
Coppenhagen	M.S. 2067
Carl Sextus	M.S. 2067
Union Leader	M.S. 2067
Stockholm	M.S. 2067
Grass Flat	M.S. 2068
Sandow	M.S. 2068
Old Mac	M.S. 2068

Fee Lands	Lot
Township 15 South, Range 7 West	
Section 36	Part of Lot 1 (Parcel N)
Section 36	Part of Lot 4 (Parcel M)
Section 36	Part of Lot 6 (Parcel J)
Section 36	Lot 10 (Parcel L)
Section 36	Lot 11 (Parcel K)
Section 36	Part of N½SE¼ (Parcel I)
Section 36	Part of N½S½SE¼ (Parcel H)
Township 15 South, Range 6 West	
Section 31	Lot 3 (Parcel D)
Section 31	Lot 6 (Parcel G)
Section 31	Lot 7 (Parcel C)
Section 31	Part of NE¼SW ¼ (Parcel E)
Section 31	N½SE¼SW¼ (Parcel B)
Section 31	Part of S½SE¼NW¼ (Parcel F)
Section 31	Part of SE1/4 (Parcel A)
Township 16 South, Range 6 West	
Section 6	Part of Lot 3 (Parcel P)
Section 6	Part of Lot 4 (Parcel O)

APPENDIX B

Preliminary Design Report:
Copper Flat Waste Rock Disposal Facilities

REPORT

PRELIMINARY DESIGN REPORT

Copper Flat Waste Rock Disposal Facilities

Submitted To: New Mexico Copper Corp
Suite 100 - 2425 San Pedro Dr. NE
Albuquerque, NM 87110

Submitted By: Golder Associates Inc.
4730 N. Oracle Road, Suite 210
Tucson, AZ 85705 USA

Distribution:
2 Copies – New Mexico Copper Corp.
2 Copies – Golder Associates Inc.

June 22, 2011 **103-92557.004 Rev. 2**

A world of capabilities delivered locally

Golder Associates

Golder, Golder Associates and the GA globe design are trademarks of Golder Associates Corporation

Table of Contents

1.0 INTRODUCTION 1
1.1 Scope 1
1.2 Background Information 1
2.0 WRDF DESIGN 2
2.1 WRDF Geometry and Capacity 2
2.2 Site Preparation 2
2.2.1 Top Dressing Stripping 2
2.2.2 Reclamation Cover Salvage 3
2.3 WRDF and Low Grade Ore Stockpile Sequencing 4
2.4 Reclamation Material Stockpiles 4
3.0 SURFACE WATER MANAGEMENT 6
3.1.1 Methodology 6
3.1.2 Runon Control 6
3.1.3 Stormwater and Sediment Collection 7
3.1.4 Stormwater Pond Design 8
4.0 USE OF THIS REPORT 9
5.0 REFERENCES 10

List of Tables

Table 1 Summary of Waste Rock Disposal Facility Capacity
Table 2 Estimated Top Dressing Salvage Quantities
Table 3 Summary of Top Dressing and Reclamation Cover Requirements
Table 4 Summary of Peak Discharge Estimates for Conveyance and Diversion Structures
Table 5 Summary of Stormwater Storage Requirements

List of Figures

Figure 1 Location Plan
Figure 2 Waste Rock Disposal Facility Plan
Figure 3 Waste Rock Disposal Facility Sections
Figure 4 Surface Water Management Plan
Figure 5 Diversion and Conveyance Ditch Details
Figure 6 Stormwater Collection Pond Sections and Details

List of Appendices

Appendix A Hydrologic Data and Calculations
Appendix A.1 Stormwater Pond Sizing Calculations
Appendix A.2 Conveyance and Diversion Ditch Sizing

1.0 INTRODUCTION

1.1 Scope

This report presents the preliminary design of the waste rock disposal facilities (WRDFs) and low grade ore stockpile at the Copper Flat Project. The WRDFs are sized to contain future waste rock and low grade ore based on quantities presented in the Copper Flat Mine Plan of Operations (NMCC, 2010). The report presents WRDF layouts and surface water management planning. Reclamation planning and reclamation construction material management are also discussed. Designs have been developed to preliminary level in an attempt to supplement information presented in the Mine Plan of Operations (MPO). WRDF designs will be advanced when site investigation activities have been completed and detailed engineering studies are commissioned.

1.2 Background Information

The Copper Flat project was briefly operated by Quintana Minerals Corporation in the period between 1982 and 1986. During this time, open pit pre-stripping operations were completed and waste rock disposal was initiated in the existing West and North WRDFs. Low grade ore was also stockpiled in the existing low grade ore stockpile. Existing facilities will be operated and expanded under the current MPO, and a new East WRDF will be developed when the West and North WRDFs reach capacity.

Future operations will result in the placement of approximately 37 million tons of waste rock in existing and new WRDFs. Approximately 19 million tons of low grade ore will be temporarily placed in the low grade ore stockpile and milled at the end of open pit mining operations. Estimated waste rock and low grade ore quantities cover future operations and do not include materials placed during the 1982-96 mining operation. Mine waste and low grade ore quantities are based on the mine plan presented in *NI 43-101 Preliminary Assessment, THEMAC Resources Group Limited, Copper Flat Project, Sierra County, New Mexico* (SRK, 2010). Facilities capable of containing estimated waste rock and low grade ore quantities and surface water management facilities required to divert external runoff away from disturbance areas and convey WRDF runoff to stormwater and sediment collection ponds are presented in this report.

2.0 WRDF DESIGN

2.1 WRDF Geometry and Capacity

The location of the Copper Flat Project and the current arrangement of facilities are shown on Figure 1. Topography shown on Figure 1 represents existing conditions and shows the site as it remains following closure of the 1982-86 mining operations. The existing West and North WRDFs, and the low grade ore stockpile are shown. Other disturbance areas from the previous mining operation include the open pit and the process facilities area.

Layouts for the proposed West, North and East WRDFs are shown on Figure 2. The capacities of the future waste rock disposal facilities are summarized in Table 1. A swell factor of 25 percent is assumed for WRDF sizing.

Table 1: Summary of WRDF Storage Capacity

Facility	Storage Capacity (tons)
West WRDF	1,180,000
North WRDF	7,090,000
East WRDF	28,850,000
Total WRDF Storage Capacity	**37,120,000**
Low Grade Ore Stockpile	19,000,000

Notes:
1) Contingency capacity of 20 percent included in design layouts.
2) Capacities do not include existing waste rock and reflect future storage requirements.

Waste rock disposal facilities are designed with overall slopes of 3 horizontal to 1 vertical (3H:1V) to facilitate regrading at closure. WRDF cross sections are shown on Figure 3. It is assumed that waste rock will be placed in lifts up to 200-feet high at angle of repose with bench setbacks to maintain the overall slope 3H:1V slope to facilitate regrading at closure. Construction in this manner will require bottom-up development of the WRDFs and will facilitate progressive reclamation. In addition, construction in this manner could reduce stockpiling requirements by allowing materials from higher elevation in the WRDFs be transported directly to completed lower slopes where reclamation cover can be placed progressively.

2.2 Site Preparation

Site preparation activities are anticipated to include clearing, top dressing stripping and reclamation cover material borrowing.

2.2.1 Top Dressing Stripping

Topsoil resources at Copper Flat are limited due to extensive disturbance during previous mining operations. Top dressing will consist of available topsoil plus additional alluvial and colluvial materials that will be used to supplement available topsoil and support revegetation efforts. Supplemental top dressing material is anticipated to be collected from alluvial and colluvial materials, such as those that occur in the footprint of the East WRDF.

Top dressing will be recovered from all previously undisturbed areas beneath the expanded footprint of the WRDFs. Little topsoil is likely to be present in the vicinity of the West and North WRDFs where slopes are steep, the depth to bedrock is limited, and disturbance from the 1982-1986 mining operation is relatively extensive. Estimated topsoil recovery volumes summarized in Table 2 assume stripping of the upper 6 inches in undisturbed areas. Top dressing requirements are summarized in Table 3.

Table 2: Estimated top dressing stripping quantities

Facility	Existing Disturbance (ac)	Projected Ultimate Footprint Area (ac)	Estimated Topsoil Salvage (cy)
West WRDF	11.9	16.3	3,538
North WRDF	20.5	69.9	21,384
East WRDF	0	122	99,072
Low Grade Ore Stockpile	20.7	67.7	37,913
Total			

Notes:
1) cy = cubic yards
2) ac= acres
3) No topsoil salvage assumed in existing disturbance area

2.2.2 Reclamation Cover Salvage

Future closure requirements for the WRDFs at Copper Flat are assumed to be similar to those currently applied at Tyrone, New Mexico, where a 2.5 to 3-foot thick native material cover is being placed. Reclamation cover requirements for Copper Flat assume a cover consisting of 6-inches of top dressing over 2.5-feet of native alluvial or colluvial cover fill. It is assumed that reclamation cover materials will be preferentially recovered from undisturbed WRDF footprint areas. As noted above, the depth to bedrock is anticipated to be minimal in the West and North WRDF areas and little reclamation cover material is expected to be available. Thicker alluvial and colluvial deposits are anticipated to occur in the vicinity of the East WRDF, and it is assumed that most cover material will be borrowed from the foundation of the East WRDF.

Table 3: Summary of top dressing and reclamation cover requirements

Facility	Top Dressing Cover Requirements (cy)	Reclamation Cover Requirements (cy)
West WRDF	13,151	65,755
North WRDF	56,400	282,005
East WRDF	99,072	495,360
Low Grade Ore Stockpile	54,611	To be processed
Total	223,234	843,120

Notes:
1) cy = cubic yards
2) Assumes 6 inches of top dressing cover over 2.5 feet of reclamation cover
3) Reclamation cover requirements assumes 2.5 feet of native material cover

Availability of waste rock cover material will be verified during site investigation activities. Estimated reclamation cover requirements for the WRDF's are summarized in Table 3. It is assumed that the low

grade ore stockpile will be processed when mining operations in the pit have been completed. If economic conditions preclude processing, the low grade ore stockpile will be regraded to a stable configuration and reclamation cover will be applied.

2.3 WRDF and Low Grade Ore Stockpile Sequencing

Initial waste rock disposal operations will be conducted in the West WRDF followed by the North WRDF which lies closest to the open pit. When the West and North WRDFs reach capacity, waste rock disposal will commence in the East WRDF. The anticipated sequence of construction and reclamation of the WRDF's and low grade ore stockpile is summarized below:

- Salvage top dressing and reclamation cover material from the West WRDF and the low grade ore stockpile. Stockpile salvaged material in the vicinity of East WRDF.
- Commence waste rock disposal in the West WRDF, commence low grade ore stockpiling.
- When the West WRDF nears capacity, commence top dressing and cover material salvage in the North WRDF. Reclamation materials will be stockpiled in the vicinity of the East WRDF.
- Initiate waste rock disposal in the North WRDF. Regrade and reclaim the west WRDF.
- When the North WRDF nears capacity, commence top dressing and cover material salvage in the East Stockpile. Reclamation materials will be stockpiled in the vicinity of the East WRDF.
- Commence waste rock disposal in the East WRD, regrade and reclaim the North WRDF.
- Commence recovery and processing of low grade ore, regrade and reclaim the East WRDF.
- Place top dressing in the footprint of the low grade ore stockpile.

2.4 Reclamation Material Stockpiles

It is assumed that any top dressing and reclamation cover materials salvaged from the West and North WRDFs can be temporarily stockpiled within the footprint of the East WRDF. These materials will be recovered during progressive reclamation of the West and North WRDFs as they near ultimate capacity.

Prior to initiation of waste rock disposal in the East WRDF, top dressing salvage operations will be completed within the proposed footprint. Given the relative scarcity of potential borrow areas within the permit area, it is assumed that the majority of the reclamation cover material required for closure of the WRDFs will be obtained from within the East WRDF and low grade ore stockpile footprints.

A stockpile will be required for all or a portion of the top dressing and reclamation cover materials for the East WRFD and low grade ore stockpile. Based on the estimated material quantities presented in Table 3, reclamation of the East WRDF and low grade ore stockpile will require approximately 649,000 cubic yards (cy) of top dressing and cover material. It is assumed that reclamation materials for the West and North WRDFs will not require a life of mine stockpile outside areas that will be disturbed by

waste rock disposal and low grade ore placement. Therefore, the WRDF reclamation material stockpile has been sized to contain materials required for the East WRDF and low grade ore stockpile. The WRDF reclamation material stockpile as shown on Figure 2 has the capacity to contain approximately 700,000 cy of material. Progressive reclamation of WRDF slopes may allow a reduction in the amount of material requiring storage in the stockpile.

3.0 SURFACE WATER MANAGEMENT

The proposed surface water management plan for the WRDFs and low grade ore stockpile is shown on Figure 4. Stormwater contacting waste rock and generated sediment will be routed to either the open pit or constructed stormwater and sediment collection ponds. Collected water will be utilized as process make-up water. Surface water runoff from upgradient catchment areas contributory to the WRDFs will be diverted away from the waste rock where diversion is feasible and released. Runoff from minor undisturbed areas that cannot be diverted will be collected in the conveyance ditches and routed to the stormwater ponds.

3.1.1 Methodology

Preliminary sizing for runoff diversion and stormwater conveyance ditches is based on carrying the 100-year storm discharge with a dry freeboard of one foot. Because the contributory catchments in the WRDF areas are relatively small, short duration, high intensity precipitation events will result in peak discharge rates. Diversion ditch capacity is based on the 100-year storm duration that is equivalent to the time of concentration for each individual catchment. Peak flow estimates for diversion and conveyance structures were estimated using the rational method and precipitation depth versus duration estimates presented in the National Oceanic and Atmospheric Administration (NOAA) Atlas 14, Version 5.

Preliminary stormwater pond capacity is based on the runoff associated with the 100-year, 24-hour storm event. At Copper Flat, the NOAA estimated 100-year, 24-hour storm depth is 3.73 inches at the 90 percent confidence level. HEC-HMS (U.S. Army Corps of Engineers, 2008) was used to estimate runoff volumes for the 100-year, 24-hour storm.

3.1.2 Runon Control

Runoff diversion ditches will be located as shown on Figure 4. Runoff from the West and East diversions will be released into the Greyback Wash diversion. Runoff north of West and North WRDFs will be released into natural drainages.

Table 4 summarizes catchment area, time of concentration, rainfall intensity and peak discharge estimates for WRDF area diversion ditches. Hydrologic calculations are contained in Appendix 1. Diversion ditch dimensions are shown on Figure 5.

Table 4: Summary of peak 100-yr storm flow estimates for conveyance and diversion structures

Facility	Catchment Area (ac)	Time of Concentration (minutes)	Rainfall Intensity for Peak Discharge (in/hr)	Peak Discharge (cfs)
Diversion 1	8.9	4.4	8.51	32.3
Diversion 2	122.1	24.9	3.84	199.3
Diversion 3	61.6	18.9	4.35	113.9
Conveyance 1	18.0	34.4	3.10	19.5
Conveyance 2	60.0	58.8	2.23	52.7
Conveyance 3	16.5	12.6	5.62	35.5
Conveyance 4	33.4	12.6	5.62	75.0
Conveyance 5	213.0	55.6	2.23	171.7
Conveyance 6	46.5	35.2	3.10	50.4

Notes:
1) ac = acres
2) in/hr = inches per hour
3) cfs = cubic feet per second

Diversions 1 and 2 will divert runoff from upgradient undisturbed areas around the West and North WRDFs. Diversion 1 will discharge into the existing Greyback Wash Diversion while Diversion 2 will discharge to an unnamed drainage to the north. Diversion 3 will divert undisturbed area runoff from the east side of the East WRDF and discharge into the Greyback Wash Diversion. Diversion ditches will be riprap lined where they are constructed over erodible materials.

3.1.3 Stormwater and Sediment Collection

Stormwater conveyance ditches and collection pond locations are shown on Figure 4. Conveyance ditch dimensions and a typical stormwater pond section are shown on Figure 5. Stormwater pond and conveyance ditch capacity may be modified during final design studies, however, the general arrangement of surface water management facilities is expected to remain as shown.

During mining operations, local groundwater drawdown associated with pit dewatering will result in the pit acting as a groundwater sink. Runoff from portions of the West and North WRDFs will be intercepted in Conveyance Ditches 1 and 2 and routed to the open pit. Waste rock runoff reporting to the pit will be recovered as part of normal pit dewatering operations. In the event of a 100-year, 24-hour storm, these areas will contribute approximately 14.2 acre-feet (ac-ft) of runoff to the open pit. During future feasibility and design studies, trade-off analyses will be performed to compare the capital and operating costs of pumping stormwater from the open pit versus constructing additional stormwater ponds.

Waste rock runoff that does not report to the open pit will be collected in stormwater ponds and utilized as process make-up water. Conveyance Ditches 3 and 4 will intercept runoff from portions of the North WRDF and low grade ore stockpile which will be routed to Stormwater Pond 1. Conveyance Ditches

5 and 6 will intercept runoff from the low grade ore stockpile and East WRDF which will be routed to Stormwater Pond 2. Peak discharge estimates for conveyance ditches are shown in Table 4. Conveyance ditches will be riprap lined where they are constructed over erodible materials.

3.1.4 Stormwater Pond Design

There are no prescriptive design criteria for the construction of retention structures for runoff from waste rock disposal facilities in New Mexico. Stormwater ponds at Copper Flat are assumed to be unlined structures equipped with a reclaim pump. Unlined ponds will facilitate equipment entry and periodic removal of sediment to maintain stormwater storage capacity. It is assumed that collected stormwater will be pumped to the process facilities for use as process make-up water after suspended solids have been allowed to settle. Details of stormwater pond reclaim works will be developed during final design studies.

Table 5: Summary of Stormwater Pond Storage Requirements

Facility	Catchment Area (ac)	100-Year 24-Hour Storm Runoff Volume (ac-ft)
Stormwater Pond 1	**77.2**	9.2
Stormwater Pond 2	213.0	22.5

Notes:
1) ac = acres
2) ac-ft = acre-feet

Preliminary layouts for stormwater ponds are shown on Figure 4. Table 5 includes a summary of storage capacity requirements for stormwater ponds shown on Figure 4. Figure 5 contains typical stormwater pond construction details. Ponds will be constructed with berm/embankment heights that do not require a dam safety permit.

4.0 USE OF THIS REPORT

This preliminary design document has been prepared exclusively for the use of New Mexico Copper Corporation (NMCC) for the specific application to the Copper Flat Project. No third-party engineer or consultant shall be entitled to rely on any of the information, conclusions, or opinions contained in this report without the written approval of Golder Associates Inc. or NMCC.

Golder Associates Inc. sincerely appreciates the opportunity to support NMCC on the Copper Flat Project. Please contact either of the undersigned with any questions or comments on the information contained in this report.

GOLDER ASSOCIATES INC.

David A. Kidd, PE
Principal/Practice Leader

Gene Muller
Senior Engineer

DAK/GM/br

5.0 REFERENCES

New Mexico Copper Corporation, 2010. *Copper Flat Mine Plan of Operations*. Report prepared for the USDA, BLM, December, 2010

SRK Consulting Inc., 2010. *NI 43-101 Preliminary Assessment, THEMAC Resources Group Limited, Copper Flat Project, Sierra County, New Mexico*. Report prepared for New Mexico Copper Corporation, May 6, 2010.

FIGURES



AERIAL PHOTOGRAPH OF PROPOSED MINE AND WASTE ROCK DISPOSAL FACILITIES

NOT TO SCALE



STATE OF NEW MEXICO

NOT TO SCALE

REFERENCES

1. JULY 1, 2005 AERIAL PHOTOGRAPHY © GOOGLE 2010, NMRGIS 2011.

PROJECT
New Mexico Copper Corporation

COPPER FLAT PROJECT
WASTE ROCK DISPOSAL FACILITIES
PRELIMINARY DESIGN
SIERRA COUNTY, NEW MEXICO

TITLE

SITE LOCATION PLAN

Golder Associates

PROJECT No.		103-92557	FILE No.	10392557C001
DESIGN	WK	06/13/11	SCALE	NOT TO SCALE
CADD	NIL	06/13/11		
CHECK	GM	06/15/11		**FIGURE 1**
REVIEW	DAK	06/15/11		

K:\2010 Projects\103-92557 Copper Flat\C-Preliminary Design\10392557C001.dwg | Layout: 10392557C001 | Modified: nlocascio 06/16/2011 11:25 AM | Plotted: nlocascio 06/16/2011



LEGEND

- 5200 — EXISTING CONTOURS
- PERMIT BOUNDARY
- 5200 — DESIGN CONTOURS
- DESIGN BREAKLINES
- EXISTING SURFACE WATER DIVERSION DITCH
- A / 3 — SECTION CALL-OUT, SECTION ID, SECTION LOCATION

NOTES

1. WASTE ROCK DISPOSAL FACILITIES ARE SHOWN IN APPROXIMATE POST-RECLAMATION/REGRADED CONFIGURATION.

REFERENCES

1. 5-FT. CONTOUR INTERVAL SURFACE TOPOGRAPHY PROVIDED BY NEW MEXICO COPPER CORPORATION, INC.

750 0 750
SCALE FEET

PROJECT
New Mexico Copper Corporation
COPPER FLAT PROJECT
WASTE ROCK DISPOSAL FACILITIES
PRELIMINARY DESIGN
SIERRA COUNTY, NEW MEXICO

TITLE
WASTE ROCK DISPOSAL FACILITY PLAN

Golder Associates

PROJECT No.		103-92557	FILE No.	10392557C002
DESIGN	WK	06/13/11	SCALE	AS SHOWN
CADD	NIL	06/13/11		
CHECK	GM	06/15/11		
REVIEW	DAK	06/15/11		

FIGURE 2

01896

K:\2010 Projects\103-92557 Copper Flat\C-Preliminary Design\10392557C002.dwg | Layout: 10392557C002 | Modified: nlocascio 06/22/2011 2:26 PM | Plotted: nlocascio 06/22/2011 2:26 PM



A/3 WEST WRDF CROSS-SECTION A

SCALE 250 0 250 FEET



B/3 NORTH WRDF CROSS-SECTION B

SCALE 250 0 250 FEET



C/3 EAST WRDF CROSS-SECTION C

SCALE 250 0 250 FEET



D/3 LOW GRADE ORE STOCKPILE CROSS-SECTION D

SCALE 250 0 250 FEET

NOTES

1. WASTE ROCK DISPOSAL FACILITIES AS SHOWN IN CROSS-SECTIONS ARE IN APPROXIMATE POST-RECLAMATION/REGRADED CONFIGURATION.

PROJECT
New Mexico Copper Corporation

COPPER FLAT PROJECT
WASTE ROCK DISPOSAL FACILITIES
PRELIMINARY DESIGN
SIERRA COUNTY, NEW MEXICO

TITLE
WASTE ROCK DISPOSAL FACILITY CROSS-SECTIONS

Golder Associates

PROJECT No.		103-92557	FILE No.	10392557C003
DESIGN	WK	06/13/11	SCALE	AS SHOWN
CADD	NIL	06/13/11		
CHECK	GM	06/15/11		
REVIEW	DAK	06/15/11		

FIGURE 3

01897

K:\2010 Projects\103-92557 Copper Flat\C-Preliminary Design\10392557C003.dwg | Layout: 10392557C003 | Modified: nlocascio 06/16/2011 11:30 AM | Plotted: nlocascio 06/22/2011



LEGEND

- EXISTING CONTOURS (5200)
- PERMIT BOUNDARY
- DESIGN CONTOURS (5200)
- DESIGN BREAKLINES
- EXISTING SURFACE WATER DIVERSION DITCH
- PROPOSED SURFACE WATER DIVERSION DITCH
- PROPOSED STORM WATER CONVEYANCE DITCH

REFERENCES

1. 5-FT. CONTOUR INTERVAL SURFACE TOPOGRAPHY PROVIDED BY NEW MEXICO COPPER CORPORATION, INC.

750 0 750
SCALE FEET

PROJECT
New Mexico Copper Corporation

COPPER FLAT PROJECT
WASTE ROCK DISPOSAL FACILITIES
PRELIMINARY DESIGN
SIERRA COUNTY, NEW MEXICO

TITLE

SURFACE WATER MANAGEMENT PLAN

Golder Associates

PROJECT No.		103-92557	FILE No.	10392557C004
DESIGN	WK	06/13/11	SCALE	AS SHOWN
CADD	NIL	06/13/11		
CHECK	GM	06/15/11		
REVIEW	DAK	06/15/11		

FIGURE 4

01898

K:\2010 Projects\103-92557 Copper Flat\C-Preliminary Design\10392557C004.dwg | Layout: 10392557C002 | Modified: nlocascio 06/16/2011 2:08 PM | Plotted: nlocascio 06/22/2011 2:08 PM



Channel ID	Peak Discharge (cfs)	Max Normal Flow Depth (ft)	Construction Depth (ft)
Diversion 1	32.3	0.7	1.7
Diversion 2	199.3	2.1	3.1
Diversion 3	113.9	1.5	2.5
Conveyance 1	19.5	0.6	1.6
Conveyance 2	52.7	1.0	2.0
Conveyance 3	35.5	0.8	1.8
Conveyance 4	75.0	1.2	2.2
Conveyance 5	171.7	1.9	2.9
Conveyance 6	50.4	1.0	2.0

Notes: 1.) Bottom Width 10 ft
2.) Side Slopes 2H:1V

A/5 TYPICAL DIVERSION AND CONVEYANCE DETAIL



B/5 TYPICAL STORMWATER POND SECTION

PROJECT
New Mexico Copper Corporation
COPPER FLAT PROJECT
WASTE ROCK DISPOSAL FACILITIES
PRELIMINARY DESIGN
SIERRA COUNTY, NEW MEXICO

TITLE
SURFACE WATER MANAGEMENT DETAILS

Golder Associates

PROJECT No.		103-92557	FILE No.	10392557C005
DESIGN	WK	06/13/11	SCALE	NOT TO SCALE
CADD	NIL	06/13/11		
CHECK	GM	06/15/11		FIGURE 5
REVIEW	DAK	06/15/11		

01899

K:\2010 Projects\103-92557 Copper Flat\C-Preliminary Design\10392557C005.dwg | Layout: 5 SURFACE WATER MANAGEMENT DETAILS | Modified: nlocascio 06/16/2011 2:18 PM | Plotted: nlocascio 06/16/2011

APPENDIX A
HYDROLOGIC DATA AND CALCULATIONS

APPENDIX A.1
STORMWATER POND SIZING CALCULATIONS

CALCULATIONS

Date:	April 12, 2011	**Made by:**	WK
Project No.:	103-92557	**Checked by:**	GM
Subject:	WRDF Surface Water Hydrology	**Reviewed by:**	AK
Project Short Title:	**COPPER FLAT APPENDIX A.1**		

1.0 OBJECTIVE

Perform a hydrologic analysis of the Copper Flat WRDF areas to determine stormwater storage requirements for the 100-year design storm event. Stormwater ponds are shown on Figure 3 of the preliminary Design Report Copper Flat Waste Rock Disposal Facilities (Golder Associates, 2011), and Figure A.1.

2.0 METHOD

- Sub-basin areas were determined using topography provided by New Mexico Copper Corporation., 2009 (5' contours) - see Sub-Basin Areas on Figure A.1, Page 3.
- SCS LAG Equation.
- SCS Curve Number method.
- Peak discharge values were calculated using HEC-HMS computer model.

3.0 ASSUMPTIONS

- 100-year, 24-hour Precipitation Depth: 3.73 inches (*NOAA On-line Atlas* pages 4-7)
- Curve Numbers: (*TR-55*)
  - Undisturbed Native Ground – 85
  - Compacted Cover – 92
  - Stockpile Areas – 70
- Antecedent Moisture Conditions II
- Hydraulic Length and Slope extracted from topography.

4.0 CALCULATIONS`

- Lag time was calculated for each Sub-basin.
  - $t_L = [L^{0.8} (s+1)^{0.7}] / [1900 (Y)^{0.5}]$
    - L = Length of the longest drainage path in feet.
    - S = (1000/CN) - 10
    - CN =curve number
    - Y = The average watershed slope in %

Golder Associates Inc.
4730 N. Oracle Road, Suite 210
Tucson, AZ 85705 USA
Tel: (520) 888-8818 Fax: (520) 888-8817 www.golder.com

Golder Associates: Operations in Africa, Asia, Australasia, Europe, North America and South America

Golder, Golder Associates and the GA globe design are trademarks of Golder Associates Corporation

- Time of concentration (t_C) calculated for each sub-basin concentration point (CP). See lag time and curve number calculation sheet on pages 8-9.
  - $t_L = 0.6 * t_C$
- SCS Type II storm distribution was used to determine peak flow and volume of runoff for the different concentration points.

5.0 CONCLUSIONS

- See HEC-HMS schematic and results on pages 10.

TABLE 1: HEC-HMS RESULTS

Location	Sub-Basin Area (sq. mi)	Curve Number	Lag Time (min)	Volume (acre-ft)
SWP-1	0.12055	74.4	8	9.18
SWP-2	0.33282	71.9	34	22.50

6.0 REFERENCES

Chow, Maidment & Mays. 1988. Applied Hydrology, McGraw-Hill Inc.

Golder Associates, 2011. Preliminary Design Report, Copper Flat Waste Rock Disposal Facilities.

Natural Resources Conservation Service (NRCS 1972), National Engineering Handbook, Section 4, Hydrology, United States Department of Agriculture, reprinted 1972.

Natural Resources Conservation Service (NRCS 1986), Technical release 55, Urban Hydrology for Small Watersheds, United States Department of Agriculture, June, 1986.

National Weather Service, 2011. *National Oceanic and Atmospheric Administration Atlas 14, Volume 1, Version 5.* Retrieved May 11, 2011 from< http://hdsc.nws.noaa.gov/hdsc/pfds/pfds_printpage.html?lat=32.9751&lon=-107.5225&data=depth&units=english&series=pds#top/>.

U.S. Army Corps of Engineers, 2008. *Hydrologic Modeling System*, *Version 3.4.0*, Hydrologic Engineering Center (USACE). August, 2009.

NOAA Atlas 14, Volume 1, Version 5
Location name: New Mexico, US*
Coordinates: 32.9751, -107.5225
Elevation: 5871ft*
* source: Google Maps

POINT PRECIPITATION FREQUENCY ESTIMATES

Sanja Perica, Sarah Dietz, Sarah Heim, Lillian Hiner, Kazungu Maitaria, Deborah Martin, Sandra Pavlovic, Ishani Roy, Carl Trypaluk, Dale Unruh, Fenglin Yan, Michael Yekta, Tan Zhao, Geoffrey Bonnin, Daniel Brewer, Li-Chuan Chen, Tye Parzybok, John Yarchoan

NOAA, National Weather Service, Silver Spring, Maryland

PF_tabular | PF_graphical | Maps_&_aerials

PF tabular

PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches)[1]

Duration	Average recurrence interval(years)									
	1	2	5	10	25	50	100	200	500	1000
5-min	0.222 (0.196–0.250)	0.286 (0.255–0.322)	0.382 (0.339–0.430)	0.454 (0.403–0.511)	0.553 (0.489–0.622)	0.630 (0.556–0.709)	0.709 (0.624–0.802)	0.792 (0.695–0.899)	0.903 (0.788–1.03)	0.993 (0.862–1.14)
10-min	0.339 (0.299–0.380)	0.436 (0.388–0.490)	0.581 (0.516–0.654)	0.691 (0.614–0.777)	0.842 (0.744–0.948)	0.959 (0.846–1.08)	1.08 (0.949–1.22)	1.21 (1.06–1.37)	1.38 (1.20–1.57)	1.51 (1.31–1.74)
15-min	0.420 (0.370–0.472)	0.540 (0.481–0.607)	0.720 (0.639–0.811)	0.857 (0.761–0.964)	1.04 (0.923–1.17)	1.19 (1.05–1.34)	1.34 (1.18–1.51)	1.50 (1.31–1.70)	1.70 (1.49–1.95)	1.87 (1.63–2.15)
30-min	0.566 (0.499–0.635)	0.728 (0.648–0.818)	0.970 (0.861–1.09)	1.15 (1.02–1.30)	1.41 (1.24–1.58)	1.60 (1.41–1.80)	1.80 (1.59–2.04)	2.01 (1.77–2.28)	2.30 (2.00–2.62)	2.52 (2.19–2.90)
60-min	0.700 (0.618–0.786)	0.901 (0.802–1.01)	1.20 (1.07–1.35)	1.43 (1.27–1.61)	1.74 (1.54–1.96)	1.98 (1.75–2.23)	2.23 (1.96–2.52)	2.49 (2.19–2.83)	2.84 (2.48–3.24)	3.12 (2.71–3.59)
2-hr	0.805 (0.721–0.905)	1.03 (0.926–1.16)	1.37 (1.22–1.53)	1.64 (1.46–1.83)	2.00 (1.77–2.24)	2.30 (2.03–2.57)	2.62 (2.28–2.92)	2.96 (2.56–3.29)	3.42 (2.92–3.81)	3.80 (3.21–4.24)
3-hr	0.867 (0.783–0.970)	1.10 (0.997–1.24)	1.44 (1.30–1.62)	1.72 (1.53–1.92)	2.09 (1.86–2.33)	2.40 (2.13–2.67)	2.73 (2.39–3.03)	3.07 (2.67–3.41)	3.55 (3.05–3.96)	3.95 (3.36–4.41)
6-hr	1.00 (0.910–1.11)	1.27 (1.15–1.41)	1.63 (1.47–1.81)	1.91 (1.72–2.12)	2.31 (2.07–2.55)	2.62 (2.33–2.89)	2.96 (2.61–3.26)	3.30 (2.89–3.64)	3.78 (3.27–4.18)	4.17 (3.58–4.62)
12-hr	1.15 (1.04–1.27)	1.45 (1.32–1.60)	1.84 (1.67–2.03)	2.15 (1.94–2.37)	2.57 (2.30–2.83)	2.89 (2.59–3.18)	3.24 (2.88–3.57)	3.60 (3.17–3.97)	4.07 (3.55–4.50)	4.46 (3.86–4.95)
24-hr	1.37 (1.22–1.54)	1.72 (1.53–1.93)	2.15 (1.91–2.41)	2.49 (2.21–2.79)	2.96 (2.61–3.31)	3.34 (2.93–3.73)	3.73 (3.26–4.17)	4.14 (3.59–4.64)	4.70 (4.05–5.30)	5.15 (4.40–5.83)
2-day	1.56 (1.39–1.75)	1.96 (1.75–2.19)	2.44 (2.17–2.73)	2.83 (2.52–3.16)	3.37 (2.98–3.77)	3.79 (3.34–4.24)	4.24 (3.71–4.76)	4.71 (4.09–5.30)	5.36 (4.60–6.06)	5.88 (5.00–6.70)
3-day	1.70 (1.51–1.90)	2.12 (1.89–2.37)	2.64 (2.35–2.96)	3.06 (2.72–3.42)	3.64 (3.22–4.07)	4.10 (3.61–4.59)	4.58 (4.01–5.14)	5.08 (4.41–5.73)	5.79 (4.97–6.56)	6.36 (5.40–7.25)
4-day	1.83 (1.63–2.05)	2.28 (2.04–2.55)	2.84 (2.53–3.18)	3.29 (2.93–3.67)	3.91 (3.46–4.37)	4.40 (3.88–4.93)	4.92 (4.30–5.52)	5.46 (4.74–6.15)	6.22 (5.34–7.06)	6.83 (5.81–7.81)
7-day	2.15 (1.93–2.38)	2.68 (2.41–2.98)	3.31 (2.97–3.68)	3.81 (3.42–4.23)	4.50 (4.01–5.00)	5.04 (4.48–5.61)	5.60 (4.94–6.24)	6.18 (5.42–6.92)	6.98 (6.06–7.86)	7.62 (6.54–8.63)
10-day	2.42 (2.17–2.69)	3.02 (2.71–3.37)	3.75 (3.35–4.18)	4.32 (3.86–4.83)	5.12 (4.55–5.72)	5.75 (5.08–6.43)	6.41 (5.62–7.18)	7.09 (6.18–7.97)	8.04 (6.93–9.11)	8.79 (7.51–10.0)
20-day	3.09 (2.78–3.42)	3.85 (3.47–4.27)	4.72 (4.25–5.23)	5.38 (4.83–5.96)	6.26 (5.61–6.94)	6.93 (6.18–7.70)	7.62 (6.76–8.48)	8.30 (7.33–9.27)	9.22 (8.07–10.4)	9.93 (8.63–11.2)
30-day	3.77 (3.41–4.14)	4.69 (4.25–5.16)	5.69 (5.17–6.27)	6.46 (5.85–7.11)	7.45 (6.73–8.22)	8.19 (7.37–9.05)	8.94 (8.01–9.90)	9.68 (8.63–10.7)	10.6 (9.44–11.9)	11.4 (10.0–12.7)
45-day	4.60 (4.16–5.08)	5.71 (5.18–6.31)	6.87 (6.22–7.60)	7.73 (6.99–8.55)	8.83 (7.96–9.78)	9.63 (8.66–10.7)	10.4 (9.34–11.6)	11.2 (9.98–12.5)	12.2 (10.8–13.7)	12.9 (11.4–14.6)
60-day	5.34 (4.83–5.90)	6.64 (6.01–7.34)	7.99 (7.22–8.82)	8.97 (8.10–9.91)	10.2 (9.21–11.3)	11.1 (10.0–12.3)	12.0 (10.8–13.3)	12.9 (11.5–14.3)	14.0 (12.4–15.6)	14.8 (13.0–16.6)

[1] Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS).

Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values.

Please refer to NOAA Atlas 14 document for more information.

Back to Top

PF graphical



NOAA/NWS/OHD/HDSC

Created (GMT): Wed May 11 22:59:37 2011

Back to Top

Maps & aerials

Small scale terrain





Large scale map



Large scale aerial



COPPER FLAT
HYDROLOGIC AND HYDRAULIC CALCULATIONS

CALCULATION OF TIME OF CONCENTRATION (t_c)
COPPER FLAT, NEW MEXICO

AMC II MOISTURE CONDITIONS

Sub-Basin ID	Undisturbed Area (ac)	CN	Compacted Cover Area (ac)	CN	Stockpile Area (ac)	CN	Wt. CN	S	L (ft)	H1 (ft)	H2 (ft)	Y (%)	Lag (hr)	t_c (hr)	t_c (min)	Lag (min)	Area (mi^2)
W-1	0.00	85	0.00	92	17.95	70	70.0	4.286	2,212	5,660	5,540	5.42	0.34	0.57	34.4	21	0.02804
N-1	0.00	85	23.20	92	37.43	70	78.4	2.752	5,668	5,830	5,530	5.29	0.58	0.97	58.1	35	0.09474
N-2	0.00	85	0.00	92	3.49	70	70.0	4.286	798	5,825	5,750	9.40	0.12	0.19	11.5	7	0.00546
SWP-1	22.40	85	0.00	92	54.75	70	74.4	3.449	2,317	6,165	5,475	29.78	0.13	0.22	13.5	8	0.12055
SWP-2	26.91	85	0.00	92	186.09	70	71.9	3.909	7,245	6,165	5,280	12.21	0.56	0.94	56.2	34	0.33282

Curve Number Estimation:

Undisturbed Native Ground
Arid and semiarid rangelands
Cover type = Desert Shrub / Pinyon-Juniper
Antecedent condition = II
Hydrologic condition = Poor
Hydrologic soil group = C
Curve number = **85**

Compacted Cover
Arid and semiarid rangelands
Cover type = Fill
Antecedent condition = II
Hydrologic condition = Poor
Hydrologic soil group = D
Curve number = **92**

Stockpile
Ore
Cover type = Development Rock
Antecedent condition = II
Hydrologic condition = Poor
Hydrologic soil group = D
Curve number = **70**

Notes:

ac = acres
CN = curve number
Wt. CN =weighted curve number
S = soil and cover parameter
L = length of longest flow path (feet)
H1 = elevation at top of longest flow path (feet)
H2 = elevation at bottom of longest flow path (feet)
Y = H1-H2/L x 100 = slope (%)
Lag = Lag time (hours)
t_c = time of concentration (hr or min)

Hydrologic Condition:
Poor: <30% ground cover
Fair: 30 to 70% ground cover
Good: >70% ground cover

COPPER FLAT
HYDROLOGIC AND HYDRAULIC CALCULATIONS

Sub-basin ID	Terrain	Concentration Point ID	Area (ft^2)	Area (acres)	Area (mi^2)
WEST WRDF	Stockpile	W-1	781,703.65	17.95	0.0280
NORTH WRDF-1	Compacted	N-1	1,010,717.94	23.20	0.0363
NORTH WRDF-2	Stockpile	N-1	1,630,438.36	37.43	0.0585
NORTH WRDF-3	Stockpile	N-2	152,153.74	3.49	0.0055
NORTH WRDF-4	Stockpile	SWP-1	1,190,371.95	27.33	0.0427
NORTH WRDF-5	Undisturbed Native	SWP-1	975,914.83	22.40	0.0350
EAST WRDF-1	Undisturbed Native	SWP-2	907,173.19	20.83	0.0325
EAST WRDF-2	Stockpile	SWP-2	5,530,069.13	126.95	0.1984
EAST WRDF-3	Undisturbed Native	SWP-2	265,000.60	6.08	0.0095
LGOS-1	Stockpile	SWP-1	1,194,564.86	27.42	0.0428
LGOS-2	Stockpile	SWP-2	2,576,136.51	59.14	0.0924
DIV-3	Undisturbed Native	GREYBACK	2,683,966.00	61.62	0.0963

COPPER FLAT
HYDROLOGIC AND HYDRAULIC CALCULATIONS
100YR-24HR STORM VOLUMES





LEGEND

- 5200 — EXISTING CONTOURS
- PERMIT BOUNDARY
- 5200 — DESIGN CONTOURS
- SUB-BASIN BOUNDARY LINE
- EXISTING SURFACE WATER DIVERSION DITCH
- PROPOSED SURFACE WATER DIVERSION DITCH
- PROPOSED STORM WATER CONVEYANCE DITCH
- LGOS-1 / 19.16 — EXISTING SUB-BASIN IDENTIFIER (HEC MODEL); SUB-BASIN AREA (ACRES)
- W-1 — CONCENTRATION POINT

REFERENCES

1. 5-FT. CONTOUR INTERVAL SURFACE TOPOGRAPHY PROVIDED BY NEW MEXICO COPPER CORPORATION, INC.

750 0 750
SCALE FEET

PROJECT
New Mexico Copper Corporation
COPPER FLAT PROJECT
WASTE ROCK DISPOSAL FACILITIES
PRELIMINARY DESIGN
SIERRA COUNTY, NEW MEXICO

TITLE
HYDROLOGIC CATCHMENT BOUNDARIES

Golder Associates

PROJECT No.		103-92557	FILE No.	10392557C101
DESIGN	WK	06/13/11	SCALE	AS SHOWN
CADD	NIL	06/13/11		
CHECK	GM	06/15/11		
REVIEW	DAK	06/15/11		

FIGURE A.1

01911

K:\2010 Projects\103-92557 Copper Flat\C-Preliminary Design\10392557C101.dwg | Layout: A.1 HYDROLOGIC CATCHMENT BOUNDARIES | Modified: WKnudson 06/22/2011 4:03 PM | Plotted: nlocascio 06/22/2011

APPENDIX A.2
CONVEYANCE AND DIVERSION DITCH SIZING

CALCULATIONS

Date:	June 12, 2011	**Made by:**	WK
Project No.:	103-92557	**Checked by:**	GM
Subject:	WRDF Diversion Channel Design	**Reviewed by:**	
Project Short Title:	**COPPER FLAT APPENDIX A.2**		

1.0 OBJECTIVE

Determine peak flow rates for diversion and stormwater conveyance ditches at the Copper Flat Project waste rock disposal facility. Ditch locations are shown on Figure 3 of the preliminary Design Report Copper Flat Waste Rock Disposal Facilities (Golder Associates, 2011), anf Figure A.1.

2.0 METHOD

- Sub-basin areas were determined using topography provided by New Mexico Copper Corporation., 2009 (5' contours) - see Sub-Basin Areas on Figure A.1.
- SCS Lag Equation
- Rational Method to determine 100 year peak discharge rates.
- Manning's Equation for channel sizing.

3.0 ASSUMPTIONS

- Time of concentration was calculated using SCS lag equation, see lag time and curve number calculation sheet on pages 4-5.
- Point Precipitation Frequency Estimates: 100 year recurrence interval (*NOAA On-line Atlas* pages 6-10)
- Rational Method basin Coefficients (conservative estimates):
  - Undisturbed Native Ground – 0.43
  - Compacted Cover – 0.46
  - Stockpile Areas – 0.35
- Channels:
  - Manning's "N" = 0.041 (Riprap).
  - Bottom width 10 ft.
  - Side Slopes = 2H: 1V.
  - Minimum channel bed slopes for ditch sizing - 2%.

4.0 CALCULATIONS

- Lag time was calculated for each Sub-basin.
  - $t_L = [L^{0.8} (s+1)^{0.7}] / [1900 (Y)^{0.5}]$

Golder Associates Inc.
4730 N. Oracle Road, Suite 210
Tucson, AZ 85705 USA
Tel: (520) 888-8818 Fax: (520) 888-8817 www.golder.com

Golder Associates: Operations in Africa, Asia, Australasia, Europe, North America and South America

Golder, Golder Associates and the GA globe design are trademarks of Golder Associates Corporation

- L = Length of the longest drainage path in feet.
- S = (1000/CN) - 10
- CN =curve number .
- Y = The average watershed slope in %

- Time of concentration (t_C) calculated for each sub-basin concentration point (CP).
  - $t_L = 0.6 * t_C$
- Rational Method was used to determine peak flow of runoff for the different concentration points.
  - Q = CiA
    - Q = peak flow rate (cfs)
    - C = Basin Coefficient
    - i = rainfall intensity (inches/hour), the point precipitation in inches divided by the storm duration in hours.
    - A = Area (acres)
- Storm duration ≥ t_C
- Maximum water surface elevations and maximum capacity were calculated for each diversion channel using Bentley FlowMaster. See FlowMaster outputs on page 11.

5.0 CONCLUSIONS / RESULTS

5.1 Channel Flow Rates

Facility	Catchment Area (ac)	Time of Concentration (minutes)	Rainfall Intensity for Peak Discharge (in/hr)	Peak Discharge (cfs)
Diversion 1	8.9	4.4	8.51	32.27
Diversion 2	122.1	24.9	3.84	199.27
Diversion 3	61.62	18.9	4.35	113.91
Conveyance 1	18.0	34.4	3.10	19.47
Conveyance 2	60.6	58.8	2.23	52.73
Conveyance 3	16.5	12.6	5.62	35.49
Conveyance 4	33.4	12.6	5.62	71.90
Conveyance 5	213.0	55.6	2.23	171.71
Conveyance 6	46.5	35.2	3.10	50.44

5.2 Channel Sizing

Channel ID	Max Normal Flow Depth (ft)	Construction Depth (ft)
Diversion 1	0.7	1.7
Diversion 2	2.1	3.1
Diversion 3	1.5	2.5
Conveyance 1	0.6	1.6
Conveyance 2	1.0	2.0
Conveyance 3	0.8	1.8
Conveyance 4	1.2	2.2
Conveyance 5	1.9	2.9
Conveyance 6	1.0	2.0

Notes: 1.) Bottom width 10-feet 2.) Side slopes 2H:1V
3.) Constructed depth includes a minimum of 1 foot of freeboard

6.0 REFERENCES

Bentley Flowmaster, Bentley Systems Inc. Service Version 8i, 2009.

Chow, Maidment & Mays. 1988. Applied Hydrology, McGraw-Hill Inc.

Golder Associates, 2011. Preliminary Design Report, Copper Flat Waste Rock Disposal Facilities.

Natural Resources Conservation Service (NRCS 1972), National Engineering Handbook, Section 4, Hydrology, United States Department of Agriculture, reprinted 1972.

Natural Resources Conservation Service (NRCS 1986), Technical release 55, Urban Hydrology for Small Watersheds, United States Department of Agriculture, June, 1986.

National Weather Service, 2011. *National Oceanic and Atmospheric Administration Atlas 14, Volume 1, Version 5.* Retrieved May 11, 2011 from< http://hdsc.nws.noaa.gov/hdsc/pfds/pfds_map_cont.html?bkmrk=nm .

U.S. Army Corps of Engineers, 2008. *Hydrologic Modeling System, Version 3.4.0*, Hydrologic Engineering Center (USACE). August, 2009.

COPPER FLAT
HYDROLOGIC AND HYDRAULIC CALCULATIONS

CALCULATION OF TIME OF CONCENTRATION (t_c)
COPPER FLAT, NEW MEXICO

RATIONAL METHOD

Sub-Basin ID	Undisturbed Area (ac)	Wt. CN	S	L (ft)	H1 (ft)	H2 (ft)	Y (%)	Lag (hr)	t_c (hr)	t_c (min)	Lag (min)	Area (mi^2)	Rational method Inputs: Area (acre)	C	Intensity (in/hr)	Q (cfs)
DIVERSION 1	8.92	85.0	1.765	622	5,754	5,645	17.53	0.04	0.07	4.4	3	0.01394	8.92	0.43	8.51	32.27
DIVERSION 2	122.10	85.0	1.765	4,530	6,250	5,655	13.14	0.25	0.41	24.9	15	0.19078	122.10	0.43	3.84	199.27
DIVERSION 3	61.62	85.0	1.765	3,000	5,640	5,285	11.83	0.19	0.31	18.9	11	0.09627	61.62	0.43	4.35	113.91
Conveyance 1	17.95	70.0	4.286	2,212	5,660	5,540	5.42	0.34	0.57	34.4	21	0.02804	17.95	0.35	3.10	19.47
Conveyance 2	60.63	78.0	2.821	5,668	5,830	5,530	5.29	0.59	0.98	58.8	35	0.09474	60.63	0.39	2.23	52.73
Conveyance 3	16.47	76.7	3.038	2,317	6,165	5,475	29.78	0.13	0.21	12.6	8	0.02573	16.47	0.38	5.62	35.49
Conveyance 4	33.36	76.7	3.038	2,317	6,165	5,475	29.78	0.13	0.21	12.6	8	0.05213	33.36	0.38	5.62	71.90
Conveyance 5	213.00	72.3	3.831	7,245	6,165	5,280	12.21	0.56	0.93	55.6	33	0.33282	213.00	0.36	2.23	171.71
Conveyance 6	46.49	70.0	4.286	3,441	5,640	5,280	10.46	0.35	0.59	35.2	21	0.07264	46.49	0.35	3.10	50.44

Curve Number Estimation:

Undisturbed Native Ground
Arid and semiarid rangelands

Cover type =	Desert Shrub / Pinyon-Juniper
Antecedent condition =	II
Hydrologic condition =	Poor
Hydrologic soil group =	C
C =	**0.43**

Compacted Cover
Arid and semiarid rangelands

Cover type =	Fill
Antecedent condition =	II
Hydrologic condition =	Poor
Hydrologic soil group =	D
C =	**0.46**

Stockpile
Ore

Cover type =	Broken Rock
Antecedent condition =	II
Hydrologic condition =	Poor
Hydrologic soil group =	D
C =	**0.35**

Notes:

ac	= acres
C	= Rational Methon coefficient
Wt. CN	=weighted curve number
S	= soil and cover parameter
L	= length of longest flow path (feet)
H1	= elevation at top of longest flow path (feet)
H2	= elevation at bottom of longest flow path (feet)
Y	= H1-H2/L x 100 = slope (%)
Lag	= Lag time (hours)
t_c	= time of concentration (hr or min)

Hydrologic Condition:
Poor: <30% ground cover
Fair: 30 to 70% ground cover
Good: >70% ground cover

COPPER FLAT
HYDROLOGIC AND HYDRAULIC CALCULATIONS

Sub-basin ID	Terrain	Concentration Point ID	Area (ft^2)	Area (acres)	Area (mi^2)
DIVERSION 1	Undisturbed Native	DIVERSION 1	388,665.74	8.92	0.0139
DIVERSION 2	Undisturbed Native	DIVERSION 2	5,318,693.82	122.10	0.1908
DIVERSION 3	Undisturbed Native	DIVERSION 3	2,683,966.00	61.62	0.0963
Conveyance 1	Stockpile	Conveyance 1	781,703.65	17.95	0.0280
Conveyance 2	Undisturbed Native	Conveyance 2	2,641,154.69	60.63	0.0947
Conveyance 3	Undisturbed Native	Conveyance 3	717,306.98	16.47	0.0257
Conveyance 4	Stockpile	Conveyance 4	1,453,214.08	33.36	0.0521
Conveyance 5	Undisturbed Native	Conveyance 5	9,278,414.76	213.00	0.3328
Conveyance 6	Stockpile	Conveyance 6	2,025,112.43	46.49	0.0726

HYDROLOGIC AND HYDRAULIC CALCULATIONS

PRECIPITATION VALUES
COPPER FLAT, NEW MEXICO

100-YEAR STORM EVENT

Inputs				NOAA
Time (min)	Time (hr)	P (in)	Intensity (i) (in/hr)	Intensity (i) (in/hr)
5	0.08	0.709	8.51	8.51
10	0.17	1.08	6.48	6.47
12.6	0.21	1.18	5.62	
13	0.22	1.2	5.54	
15	0.25	1.34	5.36	5.35
20	0.33	1.45	4.35	
25	0.42	1.6	3.84	
30	0.50	1.8	3.60	3.6
35	0.58	1.81	3.10	
45	0.75	2.04	2.72	
60	1	2.23	2.23	2.23
1440	24	3.73	na	



Note: Intensity based on NOAA Point Precipitation Frequency Estimate (attached)

NOAA Atlas 14, Volume 1, Version 5
Location name: New Mexico, US*
Coordinates: 32.9751, -107.5225
Elevation: 5871ft*
* source: Google Maps

POINT PRECIPITATION FREQUENCY ESTIMATES

Sanja Perica, Sarah Dietz, Sarah Heim, Lillian Hiner, Kazungu Maitaria, Deborah Martin, Sandra Pavlovic, Ishani Roy, Carl Trypaluk, Dale Unruh, Fenglin Yan, Michael Yekta, Tan Zhao, Geoffrey Bonnin, Daniel Brewer, Li-Chuan Chen, Tye Parzybok, John Yarchoan

NOAA, National Weather Service, Silver Spring, Maryland

PF_tabular | PF_graphical | Maps_&_aerials

PF tabular

PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches/hour)[1]

Duration	Average recurrence interval(years)									
	1	2	5	10	25	50	100	200	500	1000
5-min	2.66 (2.35–3.00)	3.43 (3.06–3.86)	4.58 (4.07–5.16)	5.45 (4.84–6.13)	6.64 (5.87–7.46)	7.56 (6.67–8.51)	8.51 (7.49–9.62)	9.50 (8.34–10.8)	10.8 (9.46–12.4)	11.9 (10.3–13.7)
10-min	2.03 (1.79–2.28)	2.62 (2.33–2.94)	3.49 (3.10–3.92)	4.15 (3.68–4.66)	5.05 (4.46–5.69)	5.75 (5.08–6.47)	6.47 (5.69–7.33)	7.24 (6.34–8.21)	8.25 (7.19–9.41)	9.07 (7.88–10.4)
15-min	1.68 (1.48–1.89)	2.16 (1.92–2.43)	2.88 (2.56–3.24)	3.43 (3.04–3.86)	4.17 (3.69–4.70)	4.76 (4.19–5.35)	5.35 (4.70–6.06)	5.98 (5.24–6.78)	6.82 (5.94–7.78)	7.50 (6.51–8.61)
30-min	1.13 (0.998–1.27)	1.46 (1.30–1.64)	1.94 (1.72–2.18)	2.31 (2.05–2.60)	2.81 (2.48–3.16)	3.20 (2.82–3.60)	3.60 (3.17–4.08)	4.03 (3.53–4.57)	4.59 (4.00–5.24)	5.05 (4.38–5.80)
60-min	0.700 (0.618–0.786)	0.901 (0.802–1.01)	1.20 (1.07–1.35)	1.43 (1.27–1.61)	1.74 (1.54–1.96)	1.98 (1.75–2.23)	2.23 (1.96–2.52)	2.49 (2.19–2.83)	2.84 (2.48–3.24)	3.12 (2.71–3.59)
2-hr	0.402 (0.360–0.452)	0.516 (0.463–0.580)	0.683 (0.612–0.764)	0.818 (0.728–0.912)	1.00 (0.885–1.12)	1.15 (1.01–1.28)	1.31 (1.14–1.46)	1.48 (1.28–1.64)	1.71 (1.46–1.91)	1.90 (1.60–2.12)
3-hr	0.289 (0.261–0.323)	0.367 (0.332–0.411)	0.481 (0.432–0.538)	0.571 (0.510–0.638)	0.697 (0.620–0.777)	0.800 (0.708–0.888)	0.907 (0.795–1.01)	1.02 (0.890–1.14)	1.18 (1.02–1.32)	1.32 (1.12–1.47)
6-hr	0.168 (0.152–0.186)	0.212 (0.192–0.235)	0.272 (0.246–0.301)	0.319 (0.287–0.353)	0.386 (0.345–0.426)	0.438 (0.389–0.482)	0.493 (0.435–0.544)	0.551 (0.483–0.608)	0.631 (0.545–0.698)	0.697 (0.597–0.772)
12-hr	0.095 (0.087–0.106)	0.120 (0.109–0.133)	0.153 (0.138–0.169)	0.178 (0.161–0.196)	0.213 (0.191–0.235)	0.240 (0.215–0.264)	0.269 (0.239–0.296)	0.298 (0.263–0.329)	0.338 (0.295–0.374)	0.371 (0.321–0.411)
24-hr	0.057 (0.051–0.064)	0.072 (0.064–0.080)	0.090 (0.080–0.100)	0.104 (0.092–0.116)	0.123 (0.109–0.138)	0.139 (0.122–0.155)	0.155 (0.136–0.174)	0.172 (0.150–0.193)	0.196 (0.169–0.221)	0.215 (0.183–0.243)
2-day	0.033 (0.029–0.036)	0.041 (0.036–0.046)	0.051 (0.045–0.057)	0.059 (0.052–0.066)	0.070 (0.062–0.078)	0.079 (0.070–0.088)	0.088 (0.077–0.099)	0.098 (0.085–0.110)	0.112 (0.096–0.126)	0.123 (0.104–0.139)
3-day	0.024 (0.021–0.026)	0.029 (0.026–0.033)	0.037 (0.033–0.041)	0.043 (0.038–0.047)	0.051 (0.045–0.056)	0.057 (0.050–0.064)	0.064 (0.056–0.071)	0.071 (0.061–0.080)	0.080 (0.069–0.091)	0.088 (0.075–0.101)
4-day	0.019 (0.017–0.021)	0.024 (0.021–0.027)	0.030 (0.026–0.033)	0.034 (0.030–0.038)	0.041 (0.036–0.045)	0.046 (0.040–0.051)	0.051 (0.045–0.058)	0.057 (0.049–0.064)	0.065 (0.056–0.074)	0.071 (0.061–0.081)
7-day	0.013 (0.011–0.014)	0.016 (0.014–0.018)	0.020 (0.018–0.022)	0.023 (0.020–0.025)	0.027 (0.024–0.030)	0.030 (0.027–0.033)	0.033 (0.029–0.037)	0.037 (0.032–0.041)	0.042 (0.036–0.047)	0.045 (0.039–0.051)
10-day	0.010 (0.009–0.011)	0.013 (0.011–0.014)	0.016 (0.014–0.017)	0.018 (0.016–0.020)	0.021 (0.019–0.024)	0.024 (0.021–0.027)	0.027 (0.023–0.030)	0.030 (0.026–0.033)	0.033 (0.029–0.038)	0.037 (0.031–0.042)
20-day	0.006 (0.006–0.007)	0.008 (0.007–0.009)	0.010 (0.009–0.011)	0.011 (0.010–0.012)	0.013 (0.012–0.014)	0.014 (0.013–0.016)	0.016 (0.014–0.018)	0.017 (0.015–0.019)	0.019 (0.017–0.022)	0.021 (0.018–0.023)
30-day	0.005 (0.005–0.006)	0.007 (0.006–0.007)	0.008 (0.007–0.009)	0.009 (0.008–0.010)	0.010 (0.009–0.011)	0.011 (0.010–0.013)	0.012 (0.011–0.014)	0.013 (0.012–0.015)	0.015 (0.013–0.016)	0.016 (0.014–0.018)
45-day	0.004 (0.004–0.005)	0.005 (0.005–0.006)	0.006 (0.006–0.007)	0.007 (0.006–0.008)	0.008 (0.007–0.009)	0.009 (0.008–0.010)	0.010 (0.009–0.011)	0.010 (0.009–0.012)	0.011 (0.010–0.013)	0.012 (0.011–0.014)
60-day	0.004 (0.003–0.004)	0.005 (0.004–0.005)	0.006 (0.005–0.006)	0.006 (0.006–0.007)	0.007 (0.006–0.008)	0.008 (0.007–0.009)	0.008 (0.007–0.009)	0.009 (0.008–0.010)	0.010 (0.009–0.011)	0.010 (0.009–0.012)

[1] Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS).

Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values.

Please refer to NOAA Atlas 14 document for more information.

Back to Top

PF graphical



NOAA/NWS/OHD/HDSC

Created (GMT): Mon Jun 13 22:02:22 2011

Back to Top

Maps & aerials

Small scale terrain





Large scale map



Large scale aerial



Trapezoidal Channel (103-92557 Copper Flat.fm8) Report

Label	Discharge (ft³/s)	Normal Depth (ft)	Velocity (ft/s)	Flow Type
Diversion 1	32.27	0.74	3.80	Subcritical
Diversion 2	199.27	2.08	6.78	Subcritical
Diversion 3	113.91	1.52	5.73	Subcritical
Conveyance Ditch 1	19.47	0.55	3.19	Subcritical
Conveyance Ditch 2	52.73	0.98	4.48	Subcritical
Conveyance Ditch 3	35.49	0.78	3.92	Subcritical
Conveyance Ditch 4	74.97	1.20	5.02	Subcritical
Conveyance Ditch 5	171.70	1.91	6.49	Subcritical
Conveyance Ditch 6	50.44	0.96	4.42	Subcritical

Roughness Coefficient	Channel Slope (ft/ft)	Left Side Slope (ft/ft (H:V))	Right Side Slope (ft/ft (H:V))	Bottom Width (ft)
0.041	0.02000	2.00	2.00	10.00
0.041	0.02000	2.00	2.00	10.00
0.041	0.02000	2.00	2.00	10.00
0.041	0.02000	2.00	2.00	10.00
0.041	0.02000	2.00	2.00	10.00
0.041	0.02000	2.00	2.00	10.00
0.041	0.02000	2.00	2.00	10.00
0.041	0.02000	2.00	2.00	10.00
0.041	0.02000	2.00	2.00	10.00

01923

APPENDIX C

Mine Waste Management Plan

THEMAC RESOURCES
New Mexico Copper Corporation

Copper Flat Mine
Preliminary Mine Waste Management Plan

Submitted by:

NEW MEXICO COPPER CORPORATION
2425 San Pedro Dr. Suite 100
Albuquerque, NM 87110
Office: (505) 382-5770

December 2010

TABLE OF CONTENTS

1 INTRODUCTION 1-1
1.1 Scope 1-1
1.2 Location 1-1
1.3 Background 1-3
1.4 Geology 1-3
1.5 Mineralization and Alteration 1-5
1.6 Weathering 1-6
1.7 Climate 1-6

2 OPERATIONAL WASTE ROCK MANAGEMENT 2-1
2.1 Objectives 2-1
2.2 Waste Rock Distribution 2-1
2.3 Summary of Field Observations Concerning Waste Rock Behavior 2-2
2.4 Summary of Geochemical Testing 2-2
2.5 Waste Rock Classification 2-3
2.5.1 Visual Observation 2-5
2.5.2 Confirmation Testing 2-5
2.6 Waste Handling 2-7
2.6.1 Waste Disposal Facilities 2-7
2.6.2 Waste Rock Management During Operations 2-8
2.7 Long-Term Management 2-10
2.8 Quality Assurance Testing 2-10
2.9 Field Kinetic Testing 2-11
2.10 Record Keeping 2-11
2.11 Cover Material Testing and Design 2-11
2.12 Contingency 2-11

3 OPERATIONAL TAILINGS MANAGEMENT PLAN 3-1
3.1 Tailings Disposal 3-1
3.2 Mitigation of ARD Potential 3-1
3.2.1 Tailings Embankment 3-1
3.2.2 Tailings Impoundment 3-2
3.2.3 Covering of Tailings 3-2

4 CONCLUSIONS 4-1
4.1 Waste Rock Characterization 4-1
4.1.1 Waste Rock Management 4-1
4.1.2 Tailings Characterization 4-1
4.1.3 Tailings Management 4-2

5 REFERENCES 5-1

LIST OF FIGURES

Figure 1.1: Project Location 1-2
Figure 1.2: Site Layout 1-4
Figure 2.1: Operational Waste Classification Flowchart 2-6

LIST OF APPENDICES

Appendix A: Waste Characterization Program
Appendix B: Tailings Characterization Program
Appendix C: Memo Regarding Soil Cover Performance Testing

1 INTRODUCTION

The following preliminary *Mine Waste Management Plan* was originally prepared as part of the Alta Gold Plan of Operations (PoO) submitted in 1998, and was based on geochemical characterization data developed at that time. The current owner and operator of the Copper Flat Mine, New Mexico Copper Corporation (NMCC), has initiated a supplemental geochemical characterization program based on the Nevada Bureau of Land Management (BLM) *Rock Characterization and Water Resources Analysis Guidance for Mining Activities* (Instruction Memorandum No. NV-2010-014, dated January 8, 2010), in order to provide the BLM (Las Cruces District Office) the appropriate rock and water resources data are necessary for the BLM to adequately analyze potential environmental impacts, as required by the National Environmental Policy Act (NEPA), and to determine if a Copper Flat PoO will prevent unnecessary or undue degradation. As these supplemental data are collected and analyzed, this mine waste management plan will be amended accordingly.

1.1 Scope

This report contains a mine waste management plan for the Copper Flat Project, located near Hillsboro, New Mexico. The report presents waste rock and tailings characterization data developed to assess waste behavior, and provides recommendations for operational waste rock classification and handling procedures to be employed at the project. The waste management plan addresses short- and long-term mitigation of acid-rock drainage (ARD) potential.

1.2 Location

The Copper Flat Project is located in southwestern New Mexico, approximately 30 miles southwest of Truth or Consequences and approximately 5 miles northeast of Hillsboro (Figure 1.1). The site is in the low hills between the Rio Grande River to the east and the Black Range Mountains to the west.



DESIGN: -	DRAWN: -	REVIEWED: -	**NEW MEXICO COPPER CORPORATION**	**PROJECT LOCATION**
CHECKED: -	APPROVED: -	DATE: 12/2/2010	**COPPER FLAT MINE**	DRAWING NO. **FIGURE 1.1** / SHEET 1 OF 28 / REVISION NO. **A**
FILE NAME PoO_Fig1-01_Location_JQG_20101202				JOB NO. **191000-03**

Path: H:\Copper_Flat\New Mexico Copper Corp\191000_03_Copper_Flat_Permitting\040_Drafting\20101115\PoO_Fig1-01_Location_JQG_20101202.mxd

1.3 Background

Under the currently proposed PoO, mining would be expanded in the existing open pit. The ore body would be mined by conventional front end loader and shovel open pit methods in a manner similar to the previous operation. Over the life of the Project, the mine would produce approximately 96 million tons of copper tailings and 37 million tons of overburden and waste rock. Overburden/waste rock production is estimated to average 2.2 million tons per year (ranging from 100,000 to 6.4 million tons annually), with tailings production estimated at 5.7 million tons annually. An operational life expectancy of approximately 17 years is currently projected.

Copper ore excavated from the existing open pit will be processed through a conventional floatation circuit to form a sulfide concentrate. No chemical leaching or roasting will be carried out on site.

Waste rock from the operation will be deposited on existing rock piles located to the west, north, east, and south of the existing pit (Figure 1.2). At the end of mine life all of these rock piles will be reclaimed using a revegetated soil cover.

NMCC proposes to construct a new, lined tailings impoundment facility over the existing unlined impoundment that was constructed in 1982 by the previous mine operator (Figure 1.2); Transport of tailings from the mill to the new impoundment will be via a pipeline. Ancillary facilities associated with the tailings facility will include a slurry and/or cyclone delivery system, a solution reclaim and recycling system, an embankment seepage return system, groundwater monitoring wells and an embankment stability monitoring system.

1.4 Geology

A detailed review of the geology of the Copper Flat deposit and surrounding area was originally presented in the report *Copper Flat Mine Compilation of Pit Lake Studies* (SRK, 1997), and updated in the *NI 43-101 Preliminary Assessment, THEMAC Resources Group Limited, Copper Flat Project, Sierra County, New Mexico* (SRK, 2010) and the *Sampling and Analysis Plan for Copper Flat Mine* (Intera, 2010). A brief summary of this information is presented below.



EXPLANATION

- Public
- Mine Boundary
- Plant Facilities
- Pond
- Waste Rock
- Topsoil Stockpile
- Tailings
- Ore Stockpile
- Pit
- Haul Road
- Diversion
- Ancillary
- Access Road
- Private Exploration Area
- Public Exploration Area

IF THE ABOVE BAR DOES NOT SCALE 1 INCH, THE DRAWING SCALE IS ALTERED

DESIGN: -	DRAWN: -	REVIEWED: -	
CHECKED: -	APPROVED: -	DATE: 6/22/2011	

FILE NAME: PoO_Fig3-01_PropFacilities_JQG_20110622

NEW MEXICO COPPER CORPORATION

COPPER FLAT MINE

DRAWING TITLE: **PROPOSED FACILITY LAYOUT**

DRAWING NO. **FIGURE 1.2**

JOB NO. **191000-03**

REVISION NO. **A**

Path: H:\Copper_Flat\New Mexico Copper Corp\191000_03_Copper_Flat_Permitting\040_Drafting\20110621_Response_to_Comments\PoO_Fig3-01_PropFacilities_JQG_20110622.mxd

The Copper Flat deposit is located within a Cretaceous age caldera that was intruded into the Paleozoic marine sediments and Precambrian basement rocks exposed in the upthrusted Black Range and Animas Hills. Immediately to the east of the deposit, the edge of the Rio Grande Rift forms a major regional physiographic and geologic feature. To the east of the project site, the rift has created a major graben structure, which has been infilled with at least 2000 feet of gravelly alluvium of the Santa Fe Group.

The local geology consists of a near circular block of andesite intruded by a Cretaceous age quartz monzonite stock. Numerous latite dikes crosscut both the andesite and the quartz monzonite. A later andesite dike intruded the quartz monzonite. The bulk of the high-grade mineralization is hosted in a breccia pipe which developed in the quartz monzonite stock.

1.5 Mineralization and Alteration

The majority of the economic mineralization occurs as hypogene sulfides that are predominantly associated with the breccias. The breccias are either biotite or feldspar-rich, and higher chalcopyrite concentrations are associated with the biotite-rich material.

Sulfide content within the quartz monzonite varies from less than 1% up to 10% within the mineralized breccia, and up to 20% within some veins and biotite breccia. Coarse, crystalline pyrite is the most common sulfide. Chalcopyrite ($CuFeS_2$) is the most common copper mineral, with bornite (Cu_5FeS_4), tetrahedrite ($Cu_{10}(Cu, Zn, Fe)_2(As, Sb)_4S_{13}$), enargite ($Cu_3AsS_4$), and covellite (CuS) also present. Molybdenite (MoS_2) is a common accessory sulfide. Gangue minerals associated with the sulfides include quartz, feldspar, and biotite. Accessory minerals include calcite (up to 5%), fluorite, siderite, magnetite, sericite, epidote, and chlorite.

Although Copper Flat is classified as a copper porphyry deposit, it differs from classical porphyries in that it lacks an economic supergene enrichment blanket (Titley and Beane, 1981; Titley, 1982). A central potassic alteration zone, extending from the mineralized breccia south along the contact with the quartz monzonite, is characterized by secondary biotite and potassic feldspar. Anhydrite and, locally, gypsum are present as thin coatings on fractures. The entire monzonite stock and related dikes are argillised. The andesitic rocks exhibit propylitic alteration as evidenced by epidote-chlorite-calcite alteration, and minor disseminated pyrite (<1%).

1.6 Weathering

Despite the lack of a classical supergene enrichment blanket, the deposit does have a thin "oxide" zone, down to 10 feet below the original ground surface, in which all sulfides appear to be oxidized. A "transitional" zone in which sulfides are partially oxidized extends 10 to 20 feet below the oxide zone. Below the transitional zone is a "sulfide" zone in which fresh sulfides are visible.

All the rock below the 5480 bench (20-40 feet below the original surface) in the pit contains largely fresh sulfides, except along the Sternberg lode. The Sternberg lode on the west side of the pit is partially oxidized and is referred to as transitional material. This is a mineralized vein and a zone of structural weakness in which sulfides have been partially oxidized due to preferential weathering, and potentially as a result of historic *in-situ* acid leaching. As a result of natural processes and/or past mining activities, oxidation in the Sternburg lode area has been enhanced. Abundant amorphous to poorly crystalline copper and iron oxy-hydroxy-sulfate salts occur in this area. The salts that are soluble in water at surficial temperatures, are considered to be the main source of acidity at this location.

Some superficial oxidation and wallrock alteration has been observed in the pit walls. Nowhere is oxidation greater than a depth of 30 feet, even within or along faulted contacts (Dunn, 1982).

1.7 Climate

Climate stations for the Project area are located at Caballo Dam, approximately 13 miles east of the Project, and at Hillsboro, approximately 5 miles southwest. The climate at the Project is intermediate between these two locations. In addition, NMCC has installed one climate station with pan evaporation and two PM_{10} monitoring stations on both the east and west sides of the mine site. These have been in operation since August 1, 2010.

The climate at the Copper Flat Project is characterized by warm, sunny summers with daily temperatures commonly reaching 90 degrees Fahrenheit, and mild, sunny winters with high temperatures ranging from 55 to 65 degrees Fahrenheit. In the winter, most nighttime temperatures are below freezing. Daily temperature fluctuations of 30 degrees are common throughout the year.

The average annual precipitation in the region is approximately 13 inches, nearly 50% of which occurs as infrequent but intense summer thundershowers in July, August, and September. Because of their intensity and short duration, these storms generally create large amounts of runoff and little infiltration. Precipitation varies significantly on both a monthly and yearly basis.

Evaporation records for southwestern New Mexico indicate that evaporation exceeds precipitation (NOAA, 1982). These data are based on pan evaporation rates which are applicable to estimating evaporation from wetted surfaces and shallow pools. Pan evaporation rates are calibrated against lake evaporation data at specific sites. For the Project site, the conversion from pan evaporation to lake evaporation is approximately 0.72 (NOAA, 1982). Lake evaporation at the project site is estimated to be approximately 65 inches per year and the pan evaporation is 80-90 inches per year (NOAA, 1982).

2 OPERATIONAL WASTE ROCK MANAGEMENT

2.1 Objectives

The overall objective of this waste rock management plan (WRMP) is to mitigate acid-rock drainage (ARD) potential both during mining and following closure of the Project. Specific objectives of the WRMP are as follows:

- To enable classification of waste rock concurrently with or prior to its removal from the open pit;
- To enable disposal of waste rock according to its classification and management requirements;
- To develop conditions that will facilitate concurrent reclamation as well as end of mine closure and reclamation objectives (i.e., long-term ARD control); and
- To enable identification of materials with low-ARD potential that may be useful for facilities construction and/or site reclamation activities.

2.2 Waste Rock Distribution

The waste rock in the deposit generally comprises five lithologies:

- Quartz monzonite;
- Quartz breccia;
- Biotite breccia;
- Andesite; and
- Quartz veins.

Whereas all of these rock types are represented on the existing waste rock piles, future waste rock will be dominantly comprised of fresh, unoxidized quartz monzonite and, to a lesser extent, andesite.

The classification system is discussed in Section 2.5. Operational waste classification will be conducted primarily by visual methods; however, visual classification will be subject to confirmation testing. Confirmation testing and test frequency are discussed in Section 2.5.

2.3 Summary of Field Observations Concerning Waste Rock Behavior

Field observations indicate little oxidation and acid generation occurs at the site despite exposure of waste rock and pit walls since mining operations were suspended in 1982. Observed conditions are likely influenced by arid conditions. Mineralogical observations also suggest that the sulfides occur in a crystalline form that is less susceptible to oxidation.

The deposit includes a thin oxidized (and partially oxidized) cover over fresh quartz monzonite. Where oxidation of the overlying rock is complete, the waste rock will be inert with respect to acid generation. There are likely to be very limited quantities of oxidized waste rock produced during future operations.

Partially oxidized material occurs in a transition zone beneath the oxidized cover and underlying unoxidized quartz monzonite. This transitional material has been exposed to oxidizing conditions over geologic time. In the field, it typically exhibits a low paste pH and high paste conductivity, and is currently acid generating. This behavior can be observed in both exposed pit walls in the partially oxidized zone, and where the transitional waste was deposited on the waste rock piles.

Where unoxidized quartz monzonite was deposited on the waste rock piles, the material does not exhibit evidence of significant oxidation. Sulfide grains appear fresh. Field paste test results typically indicate near neutral pH and low paste conductivity. Field observations indicate that when exposed to weathering under field conditions, the quartz monzonite are, at most, slow to react. This is a function of:

- Coarse grain size of sulfides
- Crystallinity
- Disseminated texture of sulfides

2.4 Summary of Geochemical Testing

Appendix A contains a detailed discussion of the geochemical testing that was completed to evaluate the waste rock and tailings at Copper Flat. The geochemical test program included site visits and laboratory testing programs conducted in 1994 and 1997. In each phase of investigation, field testing (paste pH and conductivity) was performed. Samples were also collected of samples for laboratory testing that included:

- Acid base accounting;
- Total metals assay;
- Leach testing;
- Kinetic humidity column tests;
- Enhanced oxidation (NAG) tests.

The results of these tests are discussed in detail in Appendix A.

The primary observations that can be made on the basis of the geochemical testing programs are as follows:

- The future waste rock will be composed primarily of quartz monzonite. The majority of this waste rock can be expected to exhibit acid generating potential as indicated by both acid base accounting and NAG tests;
- While static and NAG tests indicate a net acid producing potential, kinetic tests indicate that the unoxidized material is slow to oxidize. Kinetic testing of unoxidized samples produced neutral to slightly alkaline leachates with low concentrations of sulfate and dissolved metals. The laboratory kinetic test behavior is consistent with observed field conditions.
- Partially oxidized material, or the transition waste rock, exhibits low paste pH and high conductivity. Leach testing of the transition material indicates soluble sulfate and metals loads that indicate acid generating behavior. It should be noted, however, that only limited quantities of similar material occur within the future mining area.

2.5 Waste Rock Classification

Results of the 1994 – 1996 field and laboratory testing programs indicated that although the waste rock from the deposit has the potential to generate acid, the majority of the future waste rock (unoxidized quartz monzonite) will be very slow to oxidize and produce acidity. The current testing program is intended to verify these results.

The quartz monzonite that was obtained from below the zone of oxidation and placed on the waste rock piles prior to 1982 exhibits a fresh appearance and generally neutral to alkaline pH. This material requires management to alleviate ARD potential; however, the ARD risks associated with the unoxidized waste rock are long-term risks

only. Operationally, the material can be considered as being inert (i.e., on the scale of ~ 20 years).

Low pH values are associated primarily with the transition waste materials that have been exposed to oxidizing conditions over geologic time and are currently generating acidity.

While acidic seepage has been observed at the site, it is believed to be associated with the transition material. It is also correlated, temporally, to periods of unusually heavy rainfall. Although this has the consequence of washing out acid generating metal sulfate salts, a significant dilution effect will also be experienced. The transition waste rock requires management to alleviate ARD potential. Due to its geochemical behavior, ARD mitigation measures for transition waste should be implemented concurrently with disposal

During the course of the waste characterization program, the waste was classified into four types by visual inspection: oxide material, transition material, and unoxidized waste that was further subdivided into low- and high- sulfide material.

The following waste rock classification and management system is proposed:

Waste Rock Type	ARD Potential	Management Goal
Oxide	Low	Use in concurrent reclamation, stockpile for use
Transition	Generally high	mitigate ARD potential concurrently with disposal
Low sulfide, unoxidized	Low	Use in concurrent reclamation, stockpile for use
High sulfide, unoxidized	Generally high in long term	Concurrent reclamation where feasible, implement long term ARD controls

Brief descriptions of waste classification methods and the frequency at which these methods will be applied are presented below. Detailed descriptions of the test procedures are contained in Appendix A.

2.5.1 Visual Observation

Figure 2.1 presents a flow chart that summarizes the waste rock classification program. All blasthole drill cuttings will be visually inspected by a qualified geologist or trained geological technician prior to blasting and removal from the pit.

Oxidized and transition waste rock can be distinguished from unoxidized (high and low sulfide) waste rock on the basis of visual characteristics. Both the oxide and transition waste rock exhibit strong iron oxide staining and may exhibit partial to complete destruction of original rock texture. In contrast, the high and low sulfide unoxidized waste rock has a fresh appearance and may contain abundant fresh sulfides.

Waste rock that exhibits an oxidized appearance will also be assessed for amount of visible sulfides in the sample. Transitional material will be any material that appears oxidized but contains sulfides. A lack of visible sulfides will be used to characterize oxide material. Material classified as oxidized will be subject to confirmation testing.

Materials that exhibit a fresh, unoxidized appearance will be subject to visual estimation of sulfide content in order to distinguish between high and low sulfide waste rock. Initially, a conservatively low sulfide content of 0.5 percent will be used as an indicator of low sulfide waste rock. Material classified as low sulfide waste rock will be subject to periodic conformation testing.

2.5.2 Confirmation Testing

Confirmation testing will be performed to confirm the effectiveness of visual waste classification. Confirmation testing will be performed to evaluate both oxide versus transition and low sulfide versus high sulfide designations. Confirmation testing will be completed on-site with a Leco Furnace.



SRK
STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

PROJECT NO.	DATE	REVISION
68612	07/98	A

FIGURE 2.1

OPERATIONAL WASTE CLASSIFICATION FLOWCHART

2.5.2.1 Oxide Versus Transition Waste Rock

To be classified as oxide, the material must exhibit a low sulfide sulfur content. Oxide waste rock samples will be periodically subjected to total sulfur and sulfate sulfur analyses. Based on the test results, the sulfide sulfur content of the sample will be calculated (as total less sulfate sulfur). Because weathering results in the consumption of neutralizing potential as well as oxidation of sulfides, partially oxidized materials with low sulfide sulfur content are commonly capable of acid generation. An initial sulfide sulfur cutoff value of 0.1 percent shall be used as an indicator of oxidized waste rock.

Confirmation testing of oxide versus transition waste rock will initially be conducted at a frequency of one confirmation test for each five blastholes designated as oxide waste rock. Subject to ongoing testing and field observation, this test frequency may be subject to revision.

2.5.2.2 Low Sulfide Unoxidized Versus High Sulfide Unoxidized Waste

A conservatively low total sulfur concentration of 0.2% will be used as a preliminary indicator of low sulfide waste rock. Based on static testing completed to data, a sample containing 0.2% total sulfur will typically exhibit an NP:AP ratio that is greater than 3:1. Subject to further testing and observation, this cutoff value may be adjusted to suit conditions.

Confirmation testing of low versus high sulfide waste rock will initially be conducted at a frequency of one test for each five blasthole samples designated as oxide waste. Subject to ongoing testing and field observation, this test frequency may be revised.

2.6 Waste Handling

2.6.1 Waste Disposal Facilities

Four waste rock disposal facilities will be developed to accommodate future waste rock. The existing West and North Dumps, which contain oxidized, transition and unoxidized waste rock, will be expanded to contain all waste rock types. The south and east disposal areas will be expanded to contain primarily unoxidized waste rock. Waste rock disposal facilities are shown on Figure 1.2.

2.6.2 Waste Rock Management During Operations

Most of the future waste rock will be low and high sulfide waste, with only small amounts of oxide and transition material encountered near the surface of the proposed pit expansion. The waste will primarily be quartz monzonite with lesser andesite. The breccias are primarily ore.

The general approach to waste rock management and the control of ARD is to control the flux of water through the waste rock. Future waste will be placed on existing waste rock piles in a manner that minimizes the potential for leaching of dissolved constituents. Surface water will be managed during operations to promote runoff from the waste rock and prevent surface water runon.

Management of future waste rock will include concurrent reclamation, where feasible, and will incorporate disposal practices that will facilitate reclamation and closure of the waste rock disposal facilities.

2.6.2.1 Oxidized Waste Rock

No restrictions will be imposed on the handling and placement of oxidized waste rock. To the extent practical, oxidized waste rock will be deposited on the outer slopes and surfaces of the waste rock disposal facility. Oxidized waste rock may be stockpiled in selected areas of the waste rock disposal facilities so that it may be used during reclamation. Given the relatively small volume of oxide waste rock that is anticipated to exist within the future pit limits, oxide waste rock may be managed as transition waste without confirmation testing.

2.6.2.2 Transition Waste Rock

Transition waste rock will be managed concurrently with disposal due to its leachable acidity and dissolved metal loads. Transition waste rock will be isolated in one portion of either the West or the North waste disposal area to minimize the footprint that is covered by this material.

A minimum of 6 feet of non-transition waste rock will be placed over transition waste to minimize contact transition material in the short term. Transition waste rock will be mined early in the operation. Consequently disposal areas will be covered with additional waste rock as the waste disposal facilities are developed.

2.6.2.3 Unoxidized High Sulfide Waste Rock

As discussed above, the unoxidized waste rock poses negligible short term risk of ARD or adverse drainage quality. No restrictions will be imposed on the placement of unoxidized waste rock, however, placement will be in a manner that facilitates reclamation. A reclamation cover, as discussed below, will be placed over the unoxidized waste rock.

The unoxidized waste rock will be end dumped in 50-foot lifts. Benches will be created at the base of each end dumped lift to facilitate post-mining regrading. Following regrading to 2.5H:1V slopes, minimum 10-foot wide erosion control benches will remain. All active unoxidized waste rock surfaces will be backsloped to promote drainage of surface water off the active waste rock disposal areas. Runoff will be directed to perimeter surface water collection ditches and sediment collection facilities.

2.6.2.4 Low Sulfide Waste Rock

No restrictions will be imposed on the handling and placement of low sulfide waste rock. Where practical, low-sulfide waste rock will be deposited on the outer slopes and surfaces of the waste rock disposal areas. Low-sulfide waste rock will be stockpiled in selected areas of the waste rock disposal facilities so that it may be used for reclamation.

2.6.2.5 Waste Flagging and Routing

Prior to blasting active benches in the open pit, mine geological staff will visually inspect the cuttings from each blasthole. The rock type, color, degree of oxidation, sulfide content and other pertinent features including blasthole cuttings sample numbers will be noted and transferred to bench plan maps. Where the rock is identified as oxide or low sulfide waste, samples will be collected for confirmation testing. Waste rock boundaries will be plotted on the active bench plans.

When blasting has been completed, waste boundaries will be field flagged on the active bench. Shovel operators will then selectively excavate the waste rock and inform haul truck operators as to the nature of the waste rock and its destination within the active waste rock disposal facilities. The operator will develop a workable waste flagging and routing plan prior to the commencement of mining operations. Mine staff

will maintain records of the volume of each waste type mined during each shift and its ultimate location within the waste rock disposal facilities.

2.7 Long-Term Management

Placement of a soil cover over the waste and implementation of permanent surface water management controls will minimize the flux of water through the waste rock and the potential for leaching of oxidation products in the long term. Preliminary cover studies presented in the report, *Hydrologeological Studies, Copper Flat Project* (SRK, 1995), and updated in the report *Copper Flat Mining Act Permit Application, Volume 4* (SRK, 1996) indicated that, for a wide range of cover materials and cover thicknesses, the flux of water through the waste rock piles will occur at a rate of a few gpm (<5gpm). A cover thickness of 12 inches was originally proposed, based on *Hydrologic Evaluation of Landfill Performance* (HELP) modeling (Appendix C). The current understanding is that a cover thickness of three (3) feet may be necessary for most facilities. This cover thickness will be re-evaluated during the supplemental investigations, and tested during operations in field trials, and modified based on the results.

Where possible, cover placement will be completed concurrently with mining. Inactive waste rock slopes will be regraded to 3H:1V slopes and compacted by dozer traffic. The cover material will be placed and revegetated, and permanent surface water management facilities will be constructed. At the end of mining, final active waste rock disposal area surfaces will be regraded, covered, and revegetated.

Routing of loaded haul trucks over the upper surface of each lift will mechanically degrade and compact the waste rock, and produce zones of reduced permeability. Permeability testing of a quartz monzonite waste rock sample that was subjected to equipment traffic during previous mining activities exhibited a remolded permeability of 1×10^{-6} cm/sec. The combination of cover placement, evaporation and waste rock compaction is expected to reduce the flux of water through the waste rock to minimal rates and alleviate the potential for significant impacts to water resources. Attenuation of acidity and dissolved constituents in the foundation of the waste rock disposal facilities will further reduce the potential for water quality impacts.

2.8 Quality Assurance Testing

Quality assurance testing will be periodically performed to verify that waste rock is being accurately classified. The operator will randomly select up to 10 archived blasthole samples per month which will be subjected to saturated paste pH, saturated

paste conductivity, and acid base accounting testing (totals sulfur, sulfate sulfur and NP testing). This testing will be performed at a state approved laboratory.

The samples will be classified with respect to ARD potential on the basis of NP/AP ratio. The samples will be located on the appropriate bench plan maps and the quality assurance test classification will be compared to the operational waste classification designation. Should the comparison indicate discrepancies in waste classification, a plan to determine the source of waste classification discrepancies and improve classification techniques will be prepared by the operator.

2.9 Field Kinetic Testing

The operator has committed to a program of kinetic testing during the mining operation. These tests will be conducted to support waste management planning, confirm and further refine mine waste geochemical behavior predictions. The proposed plan for ongoing kinetic testing is described in the report, *Copper Flat Closure Field Testing* (SRK, 1998).

2.10 Record Keeping

Maintenance and continuous updating of records for all waste classification, quality assurance, and kinetic testing is considered critical to the effective management of waste rock at Copper Flat. Data collected from blast hole sampling will also be maintained. This data will be important in assessing and modifying the waste rock classification scheme. All test data will be incorporated into monthly and annual reports that will be maintained on site and kept available for inspection.

2.11 Cover Material Testing and Design

Preliminary cover design and performance modeling has been completed to assess closure and reclamation requirements for long-term ARD control and protection of water resources. The operator will conduct field scale test of cover materials and cover designs during the mining operation. Testing programs are defined in *Copper Flat Closure Field Testing* (SRK, 1998). Final reclamation cover design will be based on the results of this work.

2.12 Contingency

Due to the arid conditions that prevail at the site, acidic seeps from the existing waste rock piles have been observed, but only on rare occasions following periods of high

rainfall. Surface water will be managed during operations to minimize the potential for seeps to develop. Any affected water that occurs during operations will be collected and utilized in ore processing.

3 OPERATIONAL TAILINGS MANAGEMENT PLAN

Unlike the historic facilities, NMCC proposes to line the future tailings impoundment and embankment in order to eliminate the potential migration of tailings process water into the underlying groundwater system. However, underdrain seepage will require active management until such time as the tailings have consolidated, and a suitable reclamation cover has been constructed to manage surface water runoff. Given the nature of the ore material being processed, surface exposure of sulfide-bearing tailings may require additional management to mitigate the potential production of ARD.

3.1 Tailings Disposal

The proposed Copper Flat tailings embankment will be constructed through cycloned sand deposition. A series of cyclones will be installed on the embankment crest. Cyclone underflow or sand will be deposited on the embankment while the cyclone overflow, consisting of the fine fraction of the tailings and the majority of the process water, will be spigotted into the lined tailings impoundment.

Tailings disposal practices will result in a well drained embankment composed of coarse tailings sand. In the impoundment, a lower-permeability, saturated tailings mass will be created. Geochemical testing (Appendix B) indicates that the tailings, like the waste rock, tend to react slowly when compared to tailings from other known copper deposits, such as Chino Mine (Ford *et al*., 1998; Newcomer *et al.,* 1998). The potential for development of ARD at the surface will be alleviated by covering the tailings, thereby limiting the flux of water into the impoundment.

3.2 Mitigation of ARD Potential

3.2.1 Tailings Embankment

Due to the unsaturated conditions that will be maintained during and after tailings disposal operations, the tailings embankment sand will be more susceptible to oxidation than the tailings slimes in the impoundment. As such, the implementation of ARD mitigation measures for the tailings embankment will be initiated concurrently with mining.

3.2.2 Tailings Impoundment

The fine grained tailings in the impoundment will remain saturated during operation of the tailings disposal facility. Little oxidation of the tailings can occur under these conditions. At closure, the potential for ARD from the tailings impoundment will be alleviated by several factors:

- The tailings overflow of slimes will have a low permeability. Typical fine tailings exhibit a permeability of 1×10^{-6} cm/sec or less following partial consolidation. Upon complete consolidation, the permeability of fine tailings will decrease. The physical properties of the tailings will limit the flux of water into the tailings and the potential for mobilization of oxidation products; and

- Because the tailings will be fine grained, they will exhibit high capillarity and will retain moisture. Moist porous solids are effective barriers to the diffusion of oxygen. The combination of low permeability and resistance to oxygen diffusion will alleviate development of ARD in the impoundment. Placement of the proposed native soil cover over the impoundment will enhance evapotranspiration, control tailings erosion, and further reduce the flux of water through the tailings mass.

3.2.3 Covering of Tailings

A cover composed of native soil materials will be placed on the embankment. As with the waste rock, a soil cover of 12 inches is proposed to limit infiltration to the tailings and promote run-off (Appendix C). Prior to final design, field cover testing and kinetic testing of tailings will be completed as described in *Copper Flat Project Field Testing* (SRK, 1998). Cover thickness and permeability requirements will be determined in conjunction with field testing.

4 CONCLUSIONS

4.1 Waste Rock Characterization

Field and laboratory testwork, completed by the previous project proponent, on waste rock and drill core samples from Copper Flat have been used to classify the material as:

- *Oxide*,
- *Low ARD potential*. All sulfide completely oxidized,
- *Transitional* – High ARD potential. Partial oxidation of sulfides and storage of acid generating and metal leaching capacity in soluble metal-sulfate minerals.
- *High Sulfide* – High potential to generate ARD. Fresh sulfides with little or no oxidation.
- *Low sulfide* – Low potential to generate ARD. Fresh sulfides with little or no oxidation.

Management of these wastes will vary proportional to class and geochemical behavior with respect to potential metal leaching and acid generation.

4.1.1 Waste Rock Management

For permanent mitigation, concurrent reclamation will be ongoing.

- *High Sulfide Waste Rock* – Similar mitigation to the Transition Waste Rock with collection of seepage and where practical concurrent reclamation.
- *Low Sulfide Waste Rock* – This material will be used in concurrent reclamation of more reactive material and adequately covered to mitigate long-term risk.

Full field testing will be undertaken during development for operational and final management of waste rock.

4.1.2 Tailings Characterization

Tailings laboratory characterizations found that, compared to other similar mineral deposits currently being mined, the Copper Flat tailings are considerably less reactive. This is supported by the field observation that, despite nearly 30 years of exposure to

atmospheric moisture and oxygen, no significant acid seeps or acid plumes have developed at the site, even though some leaching of the material has occurred.

4.1.3 Tailings Management

Mitigation of potential ARD from the tailings embankment will be undertaken concurrent with mining. Due to their unsaturated nature these tailings are anticipated to have a higher ARD potential than in the main body of the impoundment.

The majority of the tailings in the impoundment will, during the lifetime of the mine, be kept saturated and consequently will have a negligible ARD potential. Upon closure, the impoundment will be adequately covered so as to minimize ARD generation.

5 REFERENCES

Bureau of Land Management (BLM). 2010. *Rock Characterization and Water Resources Analysis Guidance for Mining Activities*. U.S. Department of the Interior, Bureau of Land Management, Nevada State Office. Instruction Memorandum No. NV-2010-014. January 8, 2010.

Dunn, P.G. 1982. Geology of the Copper Flat Porphyry Copper Deposit, Hillsboro, Sierra County, New Mexico. In: Titley, S. R. ed., *Advances in Geology of the Porphyry Copper Deposits, Southwestern North America*. The University of Arizona Press, Tucson, AZ. Pp. 313-326.

Ford, R.C., J.L. Clapper, and B.R. Romig. 1998. Stability of water treatment sludge, Climax Mine, Colorado. In: *Proceedings of the Fourth International Conference on Acid Rock Drainage, Vancouver, B.C., Canada, 1997*.

Intera. 2010. *Sampling and Analysis Plan for Copper Flat Mine*. Prepared for New Mexico Copper Corporation. Submitted to Mining and Minerals Division New Mexico Energy, Minerals and Natural Resources Department.

Miller, S., A. Robertson, and T. Donohue. 1997. Advances in Acid Drainage Prediction Using The Net Acid Generation (NAG) Test. In: *Proceedings of the Fourth International Conference on Acid Rock Drainage, Vancouver, B.C., Canada, 1997*, Vol. II. Pp. 535-547.

National Oceanic and Atmospheric Administration (NOAA). 1982. *Mean Monthly, Seasonal, and Annual Pan Evaporation for the United States.* NOAA Technical Report NWS 34, Washington, D.C.

Newcomer, R., R. Schmidt-Peterson, K. Johnejeack, and D. Blout. 1998. Seepage from older tailing ponds, Chino Mining Company, New Mexico: Part 1. In: *Tailings and Mine Waste '98.* Balkema, Rotterdam, 463-480.

SRK Consulting (U.S.), Inc. (SRK). 2010. *NI 43-101 Preliminary Assessment, THEMAC Resources Group Limited, Copper Flat Project, Sierra County, New Mexico*.

Steffen Robertson and Kirsten (U.S.), Inc. (SRK). 1995. *Hydrologeological Studies, Copper Flat Project*.

Steffen Robertson and Kirsten (U.S.), Inc. (SRK). 1996. *Copper Flat Mining Act Permit Application, Volume 4*.

Steffen Robertson and Kirsten (U.S.), Inc. (SRK). 1997. *Copper Flat Mine Compilation of Pit Lake Studies*.

Steffen Robertson and Kirsten (U.S.), Inc. (SRK). 1998. *Copper Flat Closure Field Testing*.

Titley, S.R. 1982. The style and progress of mineralization and alteration in porphyry copper systems, American southwest. In: Titley, S. R. ed., *Advances in Geology of the Porphyry Copper Deposits, Southwestern North America*. The University of Arizona Press, Tucson, AZ. Pp. 93-116.

Titley, S.R., and R.E. Beane. 1981. Porphyry copper deposits – Part I: Geologic settings, petrology, and tectogenesis. In: *Economic Geology*, 75th anniversary volume, p. 214–235.

Appendix A

Waste Rock Characterization

TABLE OF CONTENTS

1 INTRODUCTION....1

1.1 Work Carried Out As Part of the EIS....1
1.2 Work Carried Out As Part of the Waste Rock Management Plan....2

2 METHODS....3

2.1 Paste pH and Conductivity....3
2.2 Total Metals Concentrations....3
2.3 Acid Base Accounting....3
2.4 Net Acid Generation Tests (NAG)....4
2.5 Modified EPA 1312 Test....5
2.6 Humidity Column Tests....6

3 RESULTS OF WASTE ROCK TESTING PROGRAM....7

3.1 Metal Content and Mineralogy....7
3.2 EPA 1312....7
3.3 Paste pH and Conductivity....8
3.4 Acid Base Accounting....8
3.5 Net Acid Generation (NAG) Testing....9
3.6 Kinetic Tests....9
3.6.1 pH and Eh....10
3.6.2 Electrical Conductivity....10
3.6.3 Acidity and Alkalinity....11
3.6.4 Sulfate....11
3.6.5 Metals....11
3.6.6 Assessment of Oxidation and NP Depletion Rates....11

4 HYDROGEOCHEMISTRY....13

4.1 Surface water....13
4.2 Pit Lake....13
4.3 Groundwater....14
4.4 Seepage....14

5 ACID ROCK DRAINAGE CHARACTERISTICS OF THE EXISTING WASTE PILES....15

5.1 ARD Characteristics of Different Lithologies....15
5.1.1 Quartz Monzonite....15
5.1.2 Quartz Breccia....16
5.1.3 Biotite Breccia....16
5.1.4 Quartz Vein....16
5.1.5 Andesite....16
5.2 ARD Characteristics of Different Waste Rock Dumps....17

5.2.1 North Waste Rock Dump 17
5.2.2 West Waste Rock Dump 17
5.2.3 South Waste Rock Dump or Lean Ore Stockpile 18
5.2.4 East Waste Rock Dump 18

6 DISCUSSION 20

6.1 Soluble Contaminants 20
6.2 Acid Generation 20
6.3 Field Identification of Waste 21

7 CONCLUSIONS 23

LIST OF FIGURES

Figure A.3.1 Paste pH Frequency Distribution by Lithology
Figure A.3.2 Paste pH vs. Conductivity
Figure A.3.3 NP vs. AP for 1994 and 1997 Data
Figure A.3.4 NP vs. AP
Figure A.3.5 Total Sulfate/Total Sulfur (%) vs. Paste pH (SU)
Figure A.3.6 NAG pH Frequency Distribution by Lithology
Figure A.3.7 Paste pH vs. NNP, NAG
Figure A.3.8 Kinetic Test Results for pH vs. Time
Figure A.3.9 Kinetic Test Results for Electrical Conductivity vs. Time
Figure A.3.10 Kinetic Test Results Acidity and Alkalinity vs. Time
Figure A.3.11 Kinetic Test Results for Sulfate vs. Time
Figure A.3.12 Kinetic Test Results Copper vs. Time
Figure A.3.13 Kinetic Test Results for Iron vs. Time
Figure A.5.1 Histogram of Visible Sulfide for All Lithologies
Figure A.5.2 Histogram of Paste pH for All Dumps
Figure A.5.3 Histogram of Paste Conductivity for All Dumps
Figure A.5.4 Histogram of NAG Values for All Dumps
Figure A.5.5 Histogram of Visible Sulfide for All Dumps
Figure A.6.1 NP vs. AP by Weathering Status
Figure A.6.2 Sulfide vs. Sulfate by Weathering Status
Figure A.6.3 NAG pH vs. Total Sulfur
Figure A.6.4 Sulfate/Total Sulfur vs. Sulfide

LIST OF DRAWINGS

Drawing 68612-001 Location of Surface Samples (Figure A.1.2)

LIST OF TABLES

Table A.1.1 Numbers of Samples Analyzed in the Waste Rock Characterization Program

Table A.1.2 Number of Tests on Samples of Each Rock

Table A.3.1 Total Metals Concentrations in Waste Rock

Table A.3.2 Extractable Metals Concentrations in Waste Rock

Table A.3.3 Results of ABA Testing of Column Samples

Table A.3.4 Results of Humidity Column Test Work

Table A.4.1 Chemistry of West Dump Seep (August, 1997)

Table A.6.1 Waste Rock Classification System

APPENDICES

Appendix A.1: Testing Protocols

Appendix A.2: Paste pH and Conductivity Data, Acid Base Accounting Test Data, and Net Acid Generation Test Data

Appendix A.3: Humidity Column Test Data

1 INTRODUCTION

Two phases of waste rock characterization have been completed at the Copper Flat project in New Mexico. A preliminary assessment of the waste was conducted in 1994 for the Environmental Impact Statement (EIS). More detailed work was carried out in 1997 for use in development of this waste management plan. The numbers of tests completed in each phase of the waste rock characterization are listed in Table A.1.1.

1.1 Work Carried Out As Part of the EIS

The initial assessment of the waste rock dumps at Copper Flat (SRK, 1995; DEIS, 1996) was carried out in part to assess the current geochemical characteristics of waste rock from former operation sand to determine whether future waste rock has the potential for acid generation.

Nineteen samples were collected from the existing pit wall rock, waste rock piles, and drill core and cuttings. The locations of the surface samples are shown in Drawing 68612-001. Selected samples were subjected to:

- Paste pH and conductivity measurements to determine whether previous oxidation had produced acidic and/or soluble residues;
- Determination of total metals concentrations;
- Acid Base Accounting to assess the balance between potentially acid generating and potentially acid neutralizing minerals;
- Agitated leach extraction tests to measure the amount of immediately soluble metals;
- Humidity column testing to simulate long-term oxidation of the waste rock and evaluate drainage quality; and,
- Geotechnical testing to estimate the physical and hydraulic properties of compacted waste rock.

The conclusions of this work were that:

- Most of the material on the dumps had only superficial oxidation despite exposure to the atmosphere for over 14 years.

- No evidence of acid seeps was observed during 1994-5, although one seep had been reported in an earlier study (Newcomber et al., 1991) and another seep was identified in August 1997 after unusually heavy rainfall.
- The material on the East, South, and most of the North dumps was essentially "sulfide" material with little or no accumulation of secondary mineral salts. The West waste rock dump and the western portion of the North dump were more complex with a combination of "sulfide" and "transitional" ore.

1.2 Work Carried Out As Part of the Waste Rock Management Plan

In August 1997, field work was carried out with the aim of producing detailed geological and geochemical maps of the waste rock dumps and open pit. One hundred and twelve samples were collected from six-foot long channels along benches on the waste rock dumps. The locations of the 1997 samples are shown on Figure A.1.2. The material was characterized in the field by geological observation and by paste pH and TDS measurements. Forty-six samples were analyzed by Acid Base Accounting (ABA) tests and fifty-nine samples were analyzed by Net Acid Generation (NAG) testing. Table A.1.2 shows the numbers of samples of each rock type analyzed by each procedure.

2 METHODS

The testing methods for samples collected in the waste rock characterization studies are summarized in the following sections. Detailed protocols are presented in Appendix A.1.

2.1 Paste pH and Conductivity

Paste pH and conductivity tests were conducted by mixing a sample of the fine grained portion of the waste with deionized water in a ratio of 1:2 by volume to produce a saturated paste. Measurements were then taken directly from the paste.

A paste pH greater than pH 7 indicates either that the sample is not generating acid, or that any acidity produced is being neutralized. A paste pH below 5.0 indicates that the material contains soluble acidity from prior oxidation. The conductivity measurement indicates the amount of immediately soluble salts present in the sample. The soluble acidity and salts are normally the products of earlier oxidation reactions. Their presence indicates that water contacting the material could leach oxidation products, even in the absence of further oxidation.

Paste pH and conductivity tests were conducted in the field (1996-1997 data) or at the SRK Laboratory in Lakewood, Colorado (1994-1995 data).

2.2 Total Metals Concentrations

Total metals concentrations in the waste rock were determined by Inductively Coupled Plasma (ICP) following the EPA 3051 digestion (USEPA 1982; 1995a,b). The purpose of the total metal analyses was to determine what metals are present in the waste rock. The ICP analysis does not indicate the amount, if any, of each metal that would be soluble under conditions likely to arise in the field.

ICP analyses were conducted at ACZ Laboratory in Steamboat Springs, Colorado.

2.3 Acid Base Accounting

Acid base accounting (ABA) tests were conducted to assess the potential for the waste rock to become acid generating. ABA tests indicate the balance of potentially acid generating minerals (sulfides) and potentially acid consuming minerals (generally carbonates) present in the rock. The test involves analyzing for total sulfur and sulfur species (total, sulfate, and pyritic sulfur) to determine the acid generation potential

(AP), and then titration with acid to assess the neutralizing potential (NP) of the material. The units of the NP and AP are kg $CaCO_3$ equivalent/ton of material (kg/T), or tons $CaCO_3$ equivalent/kiloton of material (T/KT). The method employed during the 1994 testing was the Sobek method. The modified Sobek technique (Sobek et al., 1978; SRK, 1989) was used to evaluate the 1996 samples.

The ABA characteristics of different samples can be compared using the difference between the NP and the AP values (the net neutralizing potential, or NNP). An NNP of greater than 20 kg/t indicates that a sample contains sufficient NP to buffer the acidity that could be produced as a result of oxidation, and therefore, has a low potential for acid generation. An NNP value of less than –20 kg/T is considered indicative that a sample has the potential for acid generation. Values between +20 kg/T and –20 kg/T have uncertain acid generating potential and may require kinetic testing to evaluate field behavior.

The ratio of NP:AP can also be used to evaluate acid generating potential. As a general guideline, an NP:AP greater than 3:1 indicates that a sample has a low potential for acid generation. A value below 1:1 indicates that, if the sample is exposed to oxidizing conditions, it has the potential for acid generation. Waste rock samples exhibiting NP:AP values between 1 and 3 typically require kinetic testing to evaluate field behavior.

However, both of these methods for evaluating ABA data are guidelines only. Other characteristics of the rock, such as the grain size, sulfide species and morphology and the form and occurrence of the neutralizing minerals, can influence the tendency for the material to produce or neutralize acidity.

A total of 46 ABA tests were conducted during the two phases of the waste characterization program. Testing of 1995 samples was conducted at ACZ Laboratory in Steamboat Springs, Colorado, whereas 1997 samples were analyzed at Sierra Environmental Monitoring Laboratory in Reno, Nevada.

2.4 Net Acid Generation Tests (NAG)

An alternative method for evaluating acid generating potential is the net acid generation (NAG) test. Whereas ABA tests indirectly estimate acid generating potential by comparing the sulfide sulfur content to the acid neutralizing potential of a sample, NAG tests determine the balance without the need for sulfur analyses.

The test is conducted by mixing the sample with hydrogen peroxide, and heating until the mixture stops boiling. After cooling, the pH of the sample is measured to obtain the "NAG pH". The NAG pH is then an estimate of the final pH of a sample if nearly all the sulfide present were oxidized, and is used in comparing the relative potential for generating acidity. The NAG pH is a qualitative indication of a sample's potential for acid generation; however, NAG pH values of 4.0 or greater are often indicative of low acid generating potential. The solution can then be titrated to neutrality with a standard base to determine the net acidity or acid generated (NAG) upon complete oxidation of the samples. The NAG is expressed as kg H_2SO_4 equivalent/ton, and is analogous to the NNP. Where the NAG is zero, net acid neutralizing potential is indicated. Positive NAG values indicate net acid generating potential.

The NAG test assumes complete oxidation of all the sulfide in a sample. Although sulfide oxidation is seldom complete, and the NAG test can underestimate the amount of sulfide in a sample, the result provides a realistic indication of the amount of sulfide that would react in field.

NAG tests were conducted on 59 samples representing all the rock types in the deposit. All NAG tests were carried out at the School of Engineering, University College of Wales, Cardiff, United Kingdom.

2.5 Modified EPA 1312 Test

The objective of this procedure is to characterize and quantify the soluble metal and salt content of waste samples. The test involves mixing a pulverized sample with a leaching solution, agitating the mixture, filtering the liquid and analyzing the liquid extract for pH, conductivity, acidity, alkalinity, sulfate and soluble metal concentrations (USEPA, 1994). The EPA test uses a liquid to solids ratio of 20:1. However, at the standard test ratio, constituent concentrations may be diluted and undetectable. The procedure was, therefore, modified to include a 2:1 ratio liquid to solids ratio. Deionized water was also substituted for the standard leach solution (deionized water pH adjusted with nitric and sulfuric acid) to simulate leaching with rain water.

The modified EPA 1312 tests were conducted at ACZ Laboratory in Steamboat Springs, Colorado.

2.6 Humidity Column Tests

Humidity column tests were carried out to simulate long term weathering of waste rock samples. Each sample was placed in a column of PVC pipe. Warm, moist air was passed through the sample for three days, followed by three days of dry air circulation. On the seventh day of each weekly cycle, the sample was irrigated and the leachate was collected. The pH, Eh, conductivity, acidity and alkalinity were measured directly, and a portion of each leachate sample was then sent for analyses of metal concentrations. Testing was continued for 21 weeks.

Humidity column tests were conducted at Cominco Engineering Services Laboratory (CESL) in Vancouver, British Columbia, Canada.

3 RESULTS OF WASTE ROCK TESTING PROGRAM

The following section presents the general findings of the geochemical testing program. Detailed data are presented in Appendices A.2 and A.3.

3.1 Metal Content and Mineralogy

The mineralogy of the samples was determined visually. The most common sulfide was coarse crystalline pyrite, which is present in concentrations of less than 1% throughout the quartz monzonite, and up to 10% to 20% locally within the mineralized breccia and some quartz veins. Other sulfides include chalcopyrite ($CuFeS_2$), the most common copper mineral, bornite ($CuFeS_2$), tetrahedrite ($Cu_{10}(Cu, Fe, Zn)_2(As,Sb)_4S_{13}$), enargite ($Cu_3AsS_4$), and covellite (CuS). Molybdenite (MoS_2) is the most common molybdenum mineral. Gangue minerals associated with the sulfide mineralization include quartz, feldspar, and biotite. Accessory minerals include calcite (up to 5%), fluorite, siderite, magnetite, sericite, epidote, and chlorite.

Table A.3.1 lists the results of ICP analysis of two samples of quartz monzonite waste rock. Sample PW-3 was collected from the northwest wall of the open pit and WD-1 was collected from the west waste rock pile. Both samples show a similar chemistry with high aluminum, manganese, copper, and iron concentrations. Copper, molybdenum, sulfur, silver, zinc and cadmium are enriched in the sample analyzed with respect to crustal abundance.

3.2 EPA 1312

Although the total metals concentrations in the waste rock are important, the concentrations of metal salts that are soluble is often of more concern. Table A.3.2 lists the results of EPA 1312 test on sample WD-1. It should be noted that this sample was selected for EPA method 1312 leach testing because it is a transition waste rock sample that exhibited low field pH. Therefore, the leachable constituent concentrations would be anticipated to be higher than those expected from fresh, unoxidized waste rock samples.

The leachate from the sample had a pH of 3 and high sulfate concentration (3050 mg/L). No alkalinity was detected. The leachate also had higher concentrations of aluminum, copper, and iron, than the other sample, reflecting soluble metals in the solid sample. In addition, nickel and zinc in the solid sample appear to be soluble. However, the soluble metals concentrations are generally low.

3.3 Paste pH and Conductivity

Paste pH was measured on 141 samples from the waste rock dumps. The range of pH values for each rock type is shown in Figure A.3.1. The andesite sample analyzed had a paste pH above 9. All other rock types show a range of values between 2 and 9, indicating that portions of each lithology have undergone varying degrees of sulfide oxidation.

Paste pH is plotted against paste conductivity in Figure A.3.2 and listed in Appendix A.2. There is a strong correlation between low paste pH and high paste conductivity, as would be expected. Conductivity values generally remain below 500 μS/cm above a pH of 6, but increase when pH is lower.

3.4 Acid Base Accounting

NP values are plotted against AP values for the two testing programs in Figure A.3.3. The 1994 samples have higher NP than the 1997 samples. The discrepancy is a result of the use of the more conservative modified Sobek procedure for determining NP on the 1997 samples. For the purposes of this report, only the 1997 data will be used.

Figure A.3.4 shows the relationship data between NP and AP by rock type for the 1997 samples, with the diagonal line indicating where NP is equal to AP. The figure shows that most samples contain less than 3% sulfide (equivalent to an AP of 93kg $CaCO_3$ eq./t), and generally have less NP than AP. Therefore, most samples have a "theoretical" potential for acid generation. The andesite appears to be an exception.

From the correlation of Sulfate/Total Sulfur and paste pH four fields can be identified (Figure A.3.5):

- *Low paste pH, high Sulfate/Total Sulfur Ratio*: This field is characterized by samples that have a high proportion of secondary sulfate salts that are acid generating. As can be observed relatively few samples fall into this field.
- *High paste pH, low Sulfate/Total Sulfur Ratio*: This field is characterized by samples that have a low proportion of secondary sulfate salts but high sulfide content. Whilst having the potential to generate appreciable amounts of acid they are not on immediate reaction acid-generating and require a long period of interaction with air and water in the presence of a catalyst to be so.
- *Low Paste pH, Low Sulfate/Total Sulfur Ratio*: This field is characterized by high sulfide samples.

- *High Paste pH, High Sulfate/Total Sulfur Ratio*: This field delineates the oxide ore samples.

ABA data is presented in Appendix A.2.

3.5 Net Acid Generation (NAG) Testing

NAG tests were conducted on 59 samples and the resulting NAG pH values are plotted according to rock type on Figure A.3.6. Samples of biotite breccia, quartz breccia, and quartz monzonite had NAG values that ranged from acidic to alkaline. This suggests that each of these lithologies contain a wide range of sulfide concentrations. Quartz vein material, in contrast, had NAG values indicating Net Acid Generation, reflecting the common association within the deposit of sulfides with quartz veins. Low paste pH correlates to high NAG and low negative NNP (Figure A.3.7).

NAG test data are presented in Appendix A.2.

3.6 Kinetic Tests

Humidity column tests were conducted on five samples; four (4) different quartz monzonite samples and one (1) quartz breccia sample:

- Two samples obtained from the sulfide waste rock stockpiles (SW-1 and LGSSP-2);
- One sample of quartz breccia with jarosite stains from the pit wall (PW-2); and,
- Two samples of unoxidized quartz monzonite waste obtained from archived drill core (IDC 24-22-241 and CF10-190-199).

Sulfide waste samples (SW-1 and LGSSP-2) are representative of previously mined unoxidized materials that have been exposed to weathering conditions since 1982. These samples contain fresh pyrite and chalcopyrite which coat fractures and are disseminated throughout the rock.

The pit wall sample (PW-2) was collected from partially oxidized cap rock located west of the pit. While the sample was highly oxidized, it contained residual disseminated pyrite and, locally, chalcopyrite.

The core samples (IDC 24-22-241 and CF10-190-199) are representative of unoxidized quartz monzonite waste that will be mined during future operations. These

samples were obtained from drilling at depth and have not been exposed to weathering or oxidizing conditions in the field. They contained fresh chalcopyrite and abundant fresh pyrite.

Results of ABA tests on the samples used for the humidity column tests are listed in Table A.3.3. Humidity column data are presented in Appendix A.3 and summarized in Figures 3.8 to 3.13.

3.6.1 pH and Eh

Figure A.3.8 illustrates leachate pH with time. For the initial 19 weeks of testing, all unoxidized quartz monzonite samples (all samples except column 2, PW-2) maintained a leachate pH in the range of 7.0 to 8.1. In column test PW-2, pH varied between 5.8 and 6.5 during the initial 19 weeks.

All samples show a sharp decrease in leachate pH in week 20. Because the pH depression was approximately equivalent in all tests, the laboratory was contacted to determine if the pH depression was attributable to laboratory operations as opposed to geochemical conditions. Independent investigations by the laboratory indicated that every column in the laboratory at that time (not just those for this project) experienced a similar leachate pH decrease. It was ultimately determined that the decrease in pH was the result of a decrease in pH of the deionized water used as inflow to the columns. Major servicing of the laboratory deionizing equipment caused the decreased pH of the deionized water in week 20.

The kinetic tests were resumed after a seven-week hiatus during which time the deionizing system was adjusted. The samples remained undisturbed during this period and were exposed to natural airflow that would have allowed oxidation to continue until the weekly cycles were resumed. Results for the last two weeks indicate that oxidation continued to occur at rates similar to those of the first 20 weeks.

3.6.2 Electrical Conductivity

Figure A.3.9 illustrates leachate conductivity versus time. Initially high conductivity was indicated for test LGSSP-2. This material was collected from the surface of the low grade sulfide stockpile and initial high leachate conductivity may result from leaching of secondary oxidation products. All the samples exhibit trends of decreasing leachate conductivity. By week 20, the conductivity of all test leachates was less than 100 μS/cm, suggesting limited oxidation or leaching of metals and sulfate. When the

tests were resumed at week 27, samples LGSSP-2 (surface waste) and C10-190-199-2 (fresh sulfide material) exhibited increased conductivities indicating oxidation and production of soluble salts during the hiatus.

3.6.3 Acidity and Alkalinity

Acidity production slowly increased after week 9 in all columns (Figure A.3.10), as alkalinity began decreasing (Figure A.3.10). Figure A.3.10 illustrates the low leachate alkalinity of sample PW-2 throughout the 29-week test due to the oxidized nature of the sample.

3.6.4 Sulfate

The time dependent plot for sulfate (Figure A.3.11) shows a rapid decrease in the sulfate concentration over the first 5 to 10 weeks. This is a result of the flushing of readily soluble sulfate salts present in the waste rock prior to testing. After about week 15 the sulfate concentrations reach a pseudo steady state. As was reflected in the conductivity, leachates from columns containing samples LGSSP-2, and C10-190-199-2 show an increase in sulfate as the result of accumulation of oxidation products during the seven week hiatus during which the columns were not operating. The other columns showed no significant increase, suggesting a slower rate of sulfate production and release.

3.6.5 Metals

After initial flushing of secondary oxidation salts, most metals were produced at a low rate throughout the test period, most below detection limits (Figures A.3.12 and A.3.13).

3.6.6 Assessment of Oxidation and NP Depletion Rates

Sulfate release rates and alkalinity release rates were calculated for each column test to assess the relative oxidation and acid neutralization dynamics. For these calculations it was assumed that 30% of the waste rock in the test columns is contacted by infiltrating waters and that all the sulfide and NP are available for reaction. Average concentrations for weeks 16 to 20, inclusive, were used to calculate rates of depletion of sulfide and NP. The results are summarized in Table A.3.4.

Based on the estimated time to deplete the NP, it will take on the order of several hundred years for the columns to become acid generating under the accelerated laboratory conditions. Field conditions and the designated mitigation measures are

anticipated to further prolong NP depletion. The results also suggest that the neutralizing potential originates predominantly from calcium and magnesium based carbonate minerals, with the possible exception of sample PW-2.

Also shown in Table A.3.4 are the specific sulfur release rates. The first rate is based on the specific release rate per unit mass of rock sample while the second rate has been normalized to the sulfide sulfur content of the sample. The release rates are in similar order of magnitude, indicating that all the samples are oxidizing at a slow rate. The most reactive sample appears to be LGSSP-2.

This could be explained by the higher pyrite content of total sulfides and finer grain size in this sample. Sulfate levels are negligible (0.01% out of 0.61% total sulfur) so the effects of secondary sulfates can be ruled out, although the presence of some sulfate indicates that at least a surface alteration has occurred on exposed pyrite.

4 HYDROGEOCHEMISTRY

The following section presents a brief discussion of local surface water and groundwater quality. Hydrogeological data are presented in detail in *Copper Flat Mine Hydrogeological Studies (SRK, 1995)* and *Copper Flat Project Hydrogeolgy Impact Evaluation (ABC, 1996).*

4.1 Surface water

There are three main water courses in the vicinity of the proposed mine; these are Percha Creek, Las Animas Creek and Greyback Arroyo. Percha Creek lies to the south of the mine and Las Animas to the north. Both of these creeks drain to the Caballo reservoir to the east of the mine. The Greyback Arroyo is currently diverted around the existing pit.

The surface water quality in Las Animas and Percha Creeks and the reservoir is broadly similar. They all contain low dissolved solids (300-440 mg/l) and pH is slightly alkaline (7.2-7.9). The chemistry is dominated by calcium-bicarbonate ions. Sulfate is low (mean of 65 mg/l) and dissolved metal concentrations are below detection limit. The Greyback Arroyo contains somewhat higher calcium concentration (450-510 mg/l, compared to around 60 mg/l in the other surface waters) and sulfate (1410-1740 mg/l). Alkalinity is also elevated (up to 508 mg/l $CaCO_3$ equivalent). Trace element concentrations are close to or less than detection limit. The Greyback Arroyo cuts through the copper porphyry deposit, and therefore may be expected to contain higher sulfate concentrations than the other streams in the region. Greyback is an ephemeral stream, and dissolved constituents will be concentrated by evaporation.

4.2 Pit Lake

The pit lake chemistry is dominated by calcium-sulfate ions; sulfate reaches concentrations of up to 3600 mg/l. The pH is generally slightly alkaline (pH 7-8.5) although pH values of less than 7 (with a minimum of 4.4) were recorded during 1992-93. Most dissolved trace element concentrations are low; however fluoride and manganese are both elevated (with concentrations up to 11 mg/l and 4.9 mg/l respectively). No evidence of stratification was observed on the four occasions that depth samples were collected (SRK, 1997).

The high TDS in the pit lake is probably due to the evaporation accumulation of sulfide oxidation products and dissolution of secondary minerals. Evaporative concentration has increased the dissolved salt load to the point where gypsum (hydrated calcium sulfate) is at saturation.

The lower pH levels reported for a part of the lake (pH 6-6.5) are influenced by the local presence of an acid seep originating from the NW side of the pit wall in the Sternberg lode. The few recorded low pH values may also be related to dissolution of acid volatile salts (such as jarosite) during pit lake level fluctuations.

The climate and nature of the pit lake are such that the pit will act as an evaporative sump, so there will be no groundwater flow out from the lake (ABC, 1996). Surface runoff from the waste rock dumps will be directed to flow into the pit lake, where it will be contained.

4.3 Groundwater

The groundwater at the Copper Flat site is dominated by the bicarbonate ion, providing a high buffering capacity. The pH ranges from 7.5 to 8.15, indicating slightly alkaline water. Sulfate concentrations tend to be low to moderate (80-400 mg/l) and dissolved metal concentrations are also low. Iron and manganese were relatively high in one of the samples (GWQ96-23A) collected in April 1997 (6.5 mg/l iron, 1.425 mg/l manganese). However more recent sampling results (August 1997) indicate very low iron and manganese (<1 mg/l of both elements).

4.4 Seepage

During the August 1997 sampling event, a seep was observed at the east toe of the west waste rock dump. A sample was collected and the results of analysis are tabulated in Table A.4.1. Although the seepage contains very high dissolved metals and low pH it is important to note that the flow was very low (much less than a gallon/minute (measured during sampling at ~0.2 gpm)) and the seepage will therefore be rapidly diluted and buffered by groundwater and/or surface water.

The upper part of the seepage channel was coated by chalcanthite ($CuSO_47H_2O$), langite ($Cu_4SO_4(OH)_6{}^2U_2O$), woodwardite ($Cu_4Al_2SO_4(OH)_{12}$ $2\text{-}4H_2O(?)$), goethite, cuprocopiapite ($(CuFe^{2+})$ $Fe^{3+}{}_4(SO_4)6(OH)_2$ $2OH_2O$) and amorphous Na-Ca-Mg-Cu-Zn--Fe-Mn salts. This indicates active buffering and evaporation, thus limiting metal and acid dispersion.

5 ACID ROCK DRAINAGE CHARACTERISTICS OF THE EXISTING WASTE PILES

5.1 ARD Characteristics of Different Lithologies

From whole rock analysis of waste rock samples (Table A.3.1), the primary constituents are Al, Ca, Fe, Mg and K. Trace metals of significance (> 10 ppm) are Ba, Cu, Co, Mn, Mo and Zn. Several million tons of waste rock are currently piled around the pit and along the southeast slope of Animas Peak. SRK has previously classified the waste rock in the area as oxidized, transitional and unoxidized (SRK, 1995). The basis for classification is the proportion of pyrite observed in the material, as well as its field behavior (as indicated by paste pH and conductivity).

The rock piles were initially classified (Draft EIS, 1996) on the proportion of each type of material present with the west pile being primarily transitional waste, the north rock pile being a combination of unoxidized and oxidized waste and the south and eastern rock piles comprising essentially unoxidized sulfide waste.

The ARD potential by lithology and by waste rock dump are discussed in the following sections.

5.1.1 Quartz Monzonite

The quartz monzonite frequently contains abundant pyrite and therefore may be a potential source of acid rock drainage. The paste pH measurements made on this lithology (94 taken in August 1997) ranged from 2.51 to 8.76 (Figure A.3.1). Several measurements were at the higher end of the range, suggesting that in some cases the monzonite may have some buffering capacity. However, the majority of the measurements were between pH 2 and 7, indicating initial acid generation. The net acid generation (NAG) results varied between 8 and 57 kg/T eq. H_2SO_4 (Figure A.3.6). Over 50 % of the tests generated a NAG value of between 20 and 40 kg/T eq. H_2SO_4. This indicates that the rock has potential to generate acid in certain circumstances. Observations indicate a visible pyrite content of between 0 and 8 %, with most samples containing around 3% (Figure A.5.1). This ties in well with the NAG test results.

5.1.2 Quartz Breccia

The quartz breccia is not as abundant as the quartz monzonite, which will form the bulk of the waste rock. Around 30 samples of this lithology were assessed for paste pH and paste EC (electrical conductivity, a measure of total dissolved solids). Nearly all the paste pH measurements were less than 7, and most of these were between pH 3 and 5 (Figure A.3.1). This was probably due to the dissolution of superficial salts. The NAG test results were similar to those of the quartz monzonite, with most measurements falling between 20 and 40 kg/T eq. H_2SO_4. However, more of the results from the quartz breccia were greater than 80 kg/T eq. H_2SO_4 (Figure A.3.6). One sample yielded a NAG potential of 223 kg/T eq. H_2SO_4, but this was exceptional. The visible sulfide in the quartz breccia was mostly between 3 and 4 %. The quartz breccia generally has a higher acid generating potential than the quartz monzonite.

5.1.3 Biotite Breccia

Ten measurements of paste pH were made on rock classified as biotite breccia. The paste pH values ranged from 2.45-7.38 (Figure A.3.1). All but one of these readings were less than pH 7 and the majority were less than pH 5. The biotite breccia generally has a greater proportion of sulfide than the other lithologies, with a quarter of the samples containing more than 6% visible sulfide. This is reflected by the NAG test results, which are up to 80 kg/T eq. H_2SO_4 (Figure A.3.6). However, only six NAG measurements were made on biotite breccia samples so it is inappropriate to make generalizations. This rock is considered an ore material and will be handled as such.

5.1.4 Quartz Vein

Six quartz vein samples were assessed for paste pH and percent visible sulfide. Of these only 3 NAG tests were possible. The paste pH measurements were dominated by acidic values, with ½ of the tests exhibiting a pH less than 3 (Figure A.3.1). Most of the samples contained around 5 % visible sulfide, one sample only contained around 1% (Figure A.5.1). The NAG test results were between 10 and 40 kg/t eq. H_2SO_4; these are slightly lower than may be expected for samples with relatively high sulfide content (Figure A.5.4).

5.1.5 Andesite

Only one andesitic sample was available for testwork. This reflects the relative scarcity of this lithology throughout the waste rock dumps. This sample yielded a very

high paste pH value of 9.14, which demonstrates its excellent buffering capacity. This sample was not assessed for net acid generation.

5.2 ARD Characteristics of Different Waste Rock Dumps

Locations of samples collected for paste pH and paste conductivity measurements and NAG values are shown on Drawing 68606-001, and the frequency of acid generator indicators, paste pH, conductivity, NAG value and visible sulfide abundance are provided in Figures A.5.2 - A.5.5, respectively.

5.2.1 North Waste Rock Dump

The north waste rock dump contains a mixture of unoxidized, oxidizing and oxidized waste rock. The paste pH measurements are generally lower than those for the other waste rock dumps due to the presence of transitional material. The range of paste pH values are from 2.5 to 6 (significantly, no values above pH 7 were recorded) and more than 50 % of the values were less than pH 3. This suggests a higher proportion of soluble salts relative to material from the other waste rock dumps.

The NAG test results were not exceptionally high although one sample generated a value of 223 kg/t eq. H_2SO_4. The remainder of the samples were between 9 and 75 kg/t eq. H_2SO_4. The sample which generated the high NAG value (NRD 5620 014) was also noted as containing 20 % visible pyrite, which is unusual for the Copper Flat waste rock. Most waste rock samples from this dump contained on the order of <2% visible pyrite.

From the results to date, the north waste rock dump appears to have the greatest potential to generate acid. This is probably because this dump contains a greater proportion of partially oxidized (transition) rocks than the other dumps.

5.2.2 West Waste Rock Dump

The west waste rock dump has been described as containing mostly partially oxidized, transitional waste rock (SRK 1995) but more detailed investigation in 1997 indicated that much of the rock is relatively fresh and the oxidation is very superficial.

The paste pH measurements ranged from pH 2.3 to 7.8. Generally the rocks on this dump were less reactive than those on the other dumps, with nearly 50 % of samples generating a paste pH greater than 5. The NAG test results ranged from 15 to 75 kg/t eq. H_2SO_4, with over 80 % of samples generating a potential of less than 40 kg/t eq.

H_2SO_4. This relates well to the proportion of visible sulfide in the rocks which was less than 2% in nearly 80% of the samples.

Field observations and all the test results to date indicate that the west waste rock dump has the lowest potential to generate acidity.

5.2.3 South Waste Rock Dump or Lean Ore Stockpile

The south waste rock dump reportedly contains rocks with a higher proportion of sulfide compared with the other waste rock dumps. However, the samples collected during August 1997 do not support this. All the samples evaluated contained less than 7 % visible sulfide (estimated) and the acid base accounting (ABA) revealed no samples with a sulfide content greater than 1.5 %. An earlier sampling round (SRK 1994) produced similar results; the highest measured sulfide content was just over 3%.

The NAG potential is relatively low; 90 % of samples evaluated generated a value of less than 40 kg/t eq. H_2SO_4, and the highest potential measured was only 43 kg/t eq. H_2SO_4. This confirms the low sulfide content of the samples analyzed.

The paste pH results ranged from pH 2.5 to 8.8; over a fifth of the samples generated an alkaline paste pH which may indicate some buffering capacity. Most (75%) of the samples showed very low reactivity, generating paste conductivity values of less than 500 μS/cm.

The evidence presented here suggests that the south waste rock dump has an overall low acid generating potential.

5.2.4 East Waste Rock Dump

The samples collected from the east waste rock dump contain on average around 2 % visible sulfide. Sulfide analysis resulted in a similar figure (although fewer samples were evaluated). Ore samples contained up to 10 % sulfides.

The NAG potential of the samples analyzed was relatively small; 80% were less than 30 kg/t eq. H_2SO_4. This reflects the sulfide content of the rocks.

The paste pH range was from 2.71 to 9.14. Most (65%) of the samples generated a pH less than 6. This suggests that there are soluble salts available for dissolution. The average sulfate to total sulfur ratio is around 35%, which indicates a relatively low degree of oxidation.

The east waste rock dump, in common with the south waste rock dump, is likely to have a relatively low potential for acid generation.

6 DISCUSSION

6.1 Soluble Contaminants

Results of the EPA 1312 test indicate that the soluble metal concentrations in transition waste rock are relatively high; however, the sample represents only a limited volume of future waste rock. Leachates from kinetic tests conducted on unoxidized quartz monzonite samples exhibit very low soluble metal and salt concentrations. These leachates are considered more representative of potential unoxidized waste rock drainage quality in the foreseeable future.

Soluble metal concentrations in the tailings can also be used to infer behavior of the waste rock because the tailings are composed of similar material that has been crushed, increasing the surface area that is available to oxidation. Therefore, the soluble concentrations in the tailings exposed to weathering for over 14 years may provide a "worst-case" indication of the soluble load in the waste rock. As can be seen in Table B1.2 in Appendix B, the extractable metal concentrations in the tailings, as determined by modified method 1312 testing, are low.

6.2 Acid Generation

The degree to which material has oxidized, or its "weathering status", can provide some indication of how the rock must be managed to alleviate ARD potential. The weathering status was identified visually by geologists according to the following classification (Table A.6.1):

- Oxide: No visible sulfides, loss of texture, strong oxide staining;
- Transitional: Visible sulfides, loss of texture, strong oxide staining;
- Low Sulfide: Few visible sulfides, fresh appearance, minor to no oxide staining; and,
- High sulfide: Abundant visible sulfides, fresh appearance, minor to no oxide staining.

Figure A.6.1 plots NP against AP according to weathering status of the material. The figure shows that oxidized material has low potential to generate acid since these samples have AP concentrations below 11, equivalent to a percent sulfide concentration of less than 0.4%.

This is also illustrated in Figure A.6.2. This figure plots the percent sulfur present as sulfide against percent sulfur as sulfate. The diagonal line in the figure is where concentrations of the two sulfur forms are equal. Samples having higher sulfate sulfur than sulfide sulfur are all oxide and transitional material. Samples plotting below the line are low and high sulfide material. This figure, along with Figure A.6.1, suggests that oxidized material will not pose an ARD problem. However, this material may contain soluble metals that could be leached from the rock in the short term.

For the transitional, low and high sulfide materials, there is evidence to suggest that some of the sulfides are less reactive than others. One piece of evidence is the waste rock piles themselves. During the 14 years of exposure, much of the sulfide has been oxidized to metal oxides that are stored in the rock. However, the waste still contains unoxidized sulfides, suggesting that there is some variability in the weathering rates of the sulfides. This is also illustrated in Figure A.3.1 by the wide range of paste pH values for every rock type, except andesite. The biotite breccia, quartz breccia, quartz monzonite, and quartz vein material all have paste pH values ranging from 2 to 9. If all the sulfides are uniformly distributed and had similar reactivity, the range of paste pH values would not be expected to be so broad.

Figure A.6.3 is a plot of NAG pH vs. total sulfur. NAG pH values range from 2 to 8 and have no relation to total sulfur concentrations. For example, samples with total sulfur contents of about 2.9% have NAG pH values either below 3 or greater than 6. This suggests variability in the reactivity of the sulfides contained in the samples.

Finally, of the waste rock humidity cells only LGSSP-2 became acidic during the 27 weeks of testing, despite containing very different materials. Since there is little neutralizing capacity in many of the kinetic test samples, the neutral drainage indicates low rates of sulfide oxidation in the cells. Thus, even under the relatively wet conditions of the humidity columns, the sulfides are slow to oxidize.

6.3 Field Identification of Waste

Results of the geochemical testing program indicate that field methods can be used to identify the different types of waste. The visual classification of oxide, transitional, low sulfide and high sulfide material correlated well to sulfate/total sulfur ratios, as shown in Figure A.6.4. Oxide samples have ratios above 75% and transitional material has ratios between 40% and 75%. Low and high sulfide values fall below 40% SO_4/S(T).

The figure also shows that low and high sulfide can be distinguished by sulfide concentrations. Three of the four low sulfide samples had sulfide concentrations below 0.6%. This means that during operations, low sulfide can be separated from high sulfide material based on visual estimation of sulfide concentration.

While the waste rock can be easily classified on the basis of visual inspection, periodic testing of sulfur content is recommended as a means of confirming the effectiveness of visual classification methods. Confirmation testing is recommended to evaluate the distinction between oxide and transition waste, and between low sulfide and unoxidized waste. Total sulfur analyses by Leco furnace are routinely used in waste management programs at many mine sites. Equating total sulfur content with sulfide sulfur content provides a rapid and highly conservative estimate of acid generating potential.

7 CONCLUSIONS

The primary conclusions of this work are:

- While a significant to moderate potential for acid generation is exhibited by the Copper Flat lithologies, the rate of sulfide oxidation is slow. Sulfide oxidation and acid generation has been and is active at the Copper Flat mine site. However, no environmental impact on surface streams or groundwater has been observed during this or any previous studies. Seasonal acidic and metal-sulfate rich seeps do form but tend to evaporate at the toe of the dumps.

- Available buffering through mineral-water reactions and from groundwater recharge is sufficient to neutralize generated acidity for much of the year. Acid seeps could develop during operations, after periods of heavy rainfall. However, these seeps will drain towards the pit area as either surface or sub-surface flow.

- Metal release from the lithologies is low and all kinetic leachates conformed to all applicable surface water and most groundwater standards.

- Sulfide oxidation is slow from the Copper Flat lithologies as evidenced by the abundance of sulfide minerals on the waste rock dump surfaces despite exposure since 1982.

Environmental concerns regarding waste rock at any mine site are generally two fold: leaching of soluble metals stored in the waste and generation of acidic drainage. At Copper Flat, leachable metals from the waste rock and tailings do not appear to be a concern, with the exception of the transition waste.

The results of the geochemical testing programs indicate that most of the waste rock at the site has the potential to generate acid, given sufficient time and exposure to oxidizing conditions. However, evidence from paste pH tests, NAG tests, and humidity columns suggest that the sulfides are not highly reactive. This is supported by the fact that much of the material on the waste rock dumps is neutral despite having been on the surface since 1982. This may be due to the coarse, crystalline nature of the sulfides at Copper Flat as well as arid site conditions. Crystalline minerals have a lower surface area and a more organized structure so consequently require more energy to oxidize. As a result they tend to be more stable than fine-grained semi-crystalline or subhedral minerals.

The rates of reactivity of the sulfides will need to be confirmed by humidity column tests on new waste rock generated from the pit. In the interim, waste can be managed using a conservative plan that includes visual classification and confirmatory measurement of the total sulfur content of the waste rock prior to its removal from the pit, with waste handling measures that address the short and long term management requirements. Once oxidation rates are obtained from the operational field test program then the humidity column test results reported here can be calibrated to a parameter that can be measured in the field, such as total sulfur, so as to refine the operational waste management plan



N

L E G E N D

- H75-51 — SAMPLED DRILL HOLE COLLAR LOCATION (APPROXIMATE)
- PW-1 ▲ — SURFACE GRAB SAMPLE LOCATION
- • — SAMPLE LOCATION

300 150 0 300 600
SCALE IN FEET

McLAIN HARBERS CO., INC.
AERIAL MAPPING & SURVEYING
720 West Prince Road
Tucson, Arizona 85705

THIS IS A PHOTOGRAMMETRIC (DTM) COMPILED TOPOGRAPHIC MAP AT 1"=200' 5' CONTOUR INTERVAL. MAPPING INFORMATION SHOULD BE FIELD VERIFIED PRIOR TO FINAL ENGINEERING OR CONSTRUCTION. JOB#6-40 PHOTO DATE 10-11-94

* STA.#2 * J:\0686\68606\DWG02-1.DWG.DWG * OCT 13, 1998 * 1:49:05 PM *

ENGINEER	No.	DESCRIPTION	BY	DATE

REVISIONS

PREPARED FOR: ALTA GOLD COMPANY

PREPARED BY: SRK Consulting *Engineers and Scientists*

TITLE: WASTE ROCK SAMPLE LOCATION MAP

SCALE: AS SHOWN

DRAWING No.: FIGURE A.1.2

REVISION: A

PROJECT No.: 68606

REFERENCE				
		DESIGNED		10/98
		DRAWN		10/98
		CHECKED		10/98
		APPROVED		10/98
		APPROVED		



Figure A.3.1. Paste pH Frequency Distribution by Lithology



Figure A.3.2 - Paste pH vs. Conductivity



Figure A.3.3 - NP vs. AP for 1994 and 1997 data



Figure A.3.4 - NP vs. AP



Figure A.3.5 - Total Sufate/Total Sulfur (%) vs. paste pH (SU)



Figure A.3.6 - NAG pH Frequency Distribution by Lithology*

* No samples of andesite were analysed by NAG testing



Figure A.3.7 - Paste pH vs. NNP, NAG



Figure A.3.8 - Kinetic Test Results for pH vs Time



Figure A.3.9 - Kinetic Test Results for Electrical Conductivity vs Time



Figure A.3.10 - Kinetic Test Results Alkalinity and Acidity vs Time



Figure A.3.11 - Kinetic Test Results for Sulfate vs Time



Figure A.3.12 - Kinetic Test Results Copper vs Time



Figure A.3.13 - Kinetic Test Results for Iron vs Time



Figure A.5.1 - Percent Visible Sulfide Frequency Distribution by Lithology



Figure A.5.2 - Histogram of Paste pH for All Dumps



Figure A.5.3 - Paste Conductivity Frequency Distribution by Dump



Figure A.5.4 - NAG Frequency Distribution by Dump



Figure A.5.5 - Percent Visible Sulfide Frequency Distribution by Dump



Figure A.6.1 - NP vs. AP by Weathering Status



Figure A.6.2 - Sulfide vs. Sulfate by Weathering Status



Figure A.6.3 - NAG pH vs. Total Sulfur



Figure A.6.4 - Sulfate/Total Sulfur vs. Sulfide

Table A.1.1
Numbers of samples analysed in the Waste Rock Characterization Program

Test	Number of Samples Analyzed		
	Phase I EIS	Phase II WMP	Total
Paste pH/Conductivity	19	93	112
Total Metals (ICP)	2	0	2
Acid Base Accounting (ABA)	19	28	47
Net Acid Generating (NAG)	0	59	59
EPA 1312	1	0	1
Kinetic Testing	5	0	5
Physical Tests*	1	0	1

EIS = Environmental Impact Statement
WMP = Waste Management Plan
* Gradation, Modified Proctor, Hydraulic Conductivity

Table A.1.1
Numbers of Samples Analyzed in the Waste Rock Characterization Program

Test	Number of Samples Analyzed		
	Phase I EIS	Phase II WMP	Total
Paste pH/Conductivity	19	93	112
Total Metals (ICP)	2	0	2
Acid Base Accounting (ABA)	19	28	47
Net Acid Generating (NAG)	0	59	59
EPA 1312	1	0	1
Kinetic Testing	5	0	5
Physical Tests*	1	0	1

EIS = Environmental Impact Statement
WMP = Waste Management Plan
* Gradation, Modified Proctor, Hydraulic Conductivity

Table A.1.2
Number of Tests on Samples of Each Rock Type

	Rock Type					Total
	Quartz Monzonite	Quartz Breccia	Biotite Breccia	Andesite	Quartz Vein	
Number of Samples	91	8	24	2	6	131
Paste pH/Conductivity	91	8	24	1	6	130
Total Metals (ICP)	2	--	--	--	--	2
Acid Base Accounting (ABA)	31	2	10	1	2	46
Net Acid Generating (NAG)	33	6	17	--	3	59
EPA 1312	1	--	--	--	--	1
Kinetic Testing	5	--	--	--	--	5
Physical Tests*	1	--	--	--	--	1

EIS = Environmental Impact Statement
WMP = Waste Management Plan
* Gradation, Modified Proctor, Hydraulic Conductivity

Table A.3.1
Total Metals Concentrations in Waste Rock

Parameters (ppm)	Sample Number	
	WD-1	PW-3
Aluminum	1890	2950
Antimony	< 0.10	<0.10
Arsenic	0.4	1.9
Barium	10	24
Boron	<2	<2
Cadmium	<0.5	<0.5
Calcium	700	700
Chromium	<1	<1
Cobalt	11	9
Copper	186	226
Iron	41600	40800
Lead	2	4
Magnesium	200	800
Manganese	8	39
Mercury	<0.02	<0.02
Molybdenum	7	57
Nickel	<2	3
Phosphorus (%)	0.01	0.04
Potassium	1200	1300
Selenium	3.9	9.0
Silver	<1	<1
Sodium	200	200
Vanadium	1	5
Zinc	7	14

Table A.3.2
Extractable Metals Concentrations in Waste Rock

Parameters (mg/L)	WD-1
pH	3
Conductivity (mmhos/cm)	5.6
Sulfate	3050
Acidity (as $CaCO_3$)	1050
Alkalinity (as $CaCO_3$)	0
Aluminum	151
Antimony	N/A
Arsenic	< 0.1
Barium	0.09
Boron	0.10
Cadmium	0.019
Calcium	314
Chloride	6
Chromium	0.03
Cobalt	0.29
Copper	13.6
Fluoride	1.2
Iron	102
Lead	< 0.021
Magnesium	23
Manganese	3.35
Mercury	< 0.0002
Molybdenum	<0.01
Nickel	0.11
Potassium	4
Selenium	< 0.1
Silver	< 0.01
Sodium	13
Vanadium	< 0.01
Zinc	0.87

Table A.3.3
Results of ABA Testing of Column Samples

Sample Number	SW-1	PW-2	LGSSP-2	C10-190-199-2	IDC-24-222-241
Rock Type	qm	qb	qm	qm	qm
Classification	oxidized	transitional	oxidized	unoxidized	unoxidized
Total Sulfur (%)	1.36	0.37	0.61	3.59	1.74
Sulfate (%)	0.01	0.01	0.01	0.07	0.01
Sulfide (%)	1.36	0.37	0.61	3.52	1.74
AP	42	11	19	110	54
NP	36	11	39	44	31
NNP	-6	0	20	-66	-23
NP:AP	0.86	1.00	2.05	0.40	0.57

Table A.3.4
Results of Kinetic Test Work

Sample Number	SW-1	PW-2	LGSSP-2	C10-190-199-2	IDC-24-222-241
Total Sulfur (%)	1.36	0.37	0.61	3.59	1.74
Sulfate (%)	0.01	0.01	0.01	0.07	0.01
Sulfide (%)	1.36	0.37	0.61	3.52	1.74
AP	42	11	19	110	54
NP	36	11	39	44	31
NNP	-6	0	20	-66	-23
NP:AP	0.86	1.00	2.05	0.40	0.57
Estimated Time to Depletion (years)					
NP (from stoichiometry)	286	220	126	253	389
AP (from sulfate)	1262	382	263	1051	2842
Pseudo Steady State Release Rate kg CaCO3 eq./tonne/week					

Table A.4.1

Chemistry of West Dump Seep (August, 1997)

Parameter	W-Waste All in mg/l unless otherwise stated
pH (std. units)	3.03
Alkalinity (mg/l $CaCO_3$ equiv.)	0.
Bicarbonate	0.
Carbonate	0.
Sulfate	22,100.
Total Dissolved Solids	25,440.
Chloride	16.
Fluoride	0.31
Nitrate_N	4.7
Iron	310.
Copper	1,800.
Arsenic	0.14
Aluminium	2,100.
Barium	<0.05
Beryllium	0.49
Boron	0.21
Calcium	410.
Cadmium	0.82
Cobalt	9.9
Nickel	1.3
Thallium	0.02
Manganese	170.
Zinc	38.
Molybdenum	0.28
Selenium	0.11
Magnesium	580.
Sodium	20.
Potassium	<1

Table A.6.1
Copper Flat Project
Waste Rock Classification System

Waste Rock Type	Criteria No. 1 Visual	Criteria No. 2 Paste pH (s.u.)	Criteria No. 3 Paste Conductivity (uS)	Criteria No. 4 AP (T/KT)	Criteria No. 4 NAG	Required Criteria
Oxidized	No visible sulfides, loss of texture, strong oxide staining	>5.0	<500	<1.6	0	(1, 2 and 3) or (1 and 4)
Transition	Visible sulfides, loss of texture, strong oxide staining	<5.0	>500	>1.6	>0	1
Unoxidized	Visible sulfides, fresh appearance, minor feox staining	>5.0	<500	>10	>0	1,2 and 3
Low sulfide	Few visible sulfides, fresh appearance	>5.0	<500	<10	0	1 through 4

Notes:
(1) AP criteria for identification of oxidized and transition waste based on a total or sulfide sulfur content of 0.05 percent
(2) NP of unoxidized waste is typically greater than 30 T/KT, therefore AP criteria for low sulfur waste is for an NP:AP ratio near 3:1 and sulfur content of 0.32 percent
(3) Acid producing potential (AP) by syulfur analysis and NAG are alternatives for criteria No. 4

APPENDIX A.1

TESTING PROTOCOLS

Paste pH and TDS
Acid Base Accounting
Modified EPA 1312 test
Humidity Columns
Net Acid Generation (NAG) Test

FIELD PASTE pH and CONDUCTIVITY

Objectives

- To determine the pH and conductivity of the pore water resulting from dissolution of secondary mineral phases on the surfaces of oxidized rock particles.
- To indicate whether oxidation, and accumulation of contaminants in the form of secondary mineral phases, has occurred in the waste rock prior to collection of the sample.

Principles of Test

Water is added to the sample to form a paste or slurry thus mobilizing secondary mineral phases and providing a medium accessible to the pH and conductivity or TDS probe. The probe is placed in the paste or slurry and the pH or conductivity value is read directly from the meter.

Equipment

1. pH meter equipped with a combination pH electrode.
2. Conductivity or TDS meter (in this case a Hanna Instruments field combined pH/ORP/temperature meter).
3. 50 mL beakers, or equivalent (disposable paper cups are recommended).
4. Spatula or stirring rod (eg. plastic coffee stirrers).
5. Litmus paper strips.

Reagents

1. Standard buffer solution, pH 4.00 and pH 7.00.
2. Standard electrolyte solutions (for calibration of conductivity meter).
3. Distilled (or deionized) water.

Procedure

1. Calibrate pH and conductivity or TDS meters using the standard solutions and following the instructions provided with the meters.

2. Obtain approximately 25 g of fines (particles smaller than 1 mm if possible) from the rock sample to be tested, and place in a fresh or decontaminated beaker or testing vessel.

3. Add approximately 25 ml of distilled water to sample. (More water may be required if the sample is very dry or extremely fine.)

4. Stir sample with fresh or cleaned spatula to form a paste or slurry. Paste should slide off spatula easily.

5. Tip the testing container to one side to allow a pool of water or slurry to collect in the corner. Dip each of the probes into the slurry, and allow the meter readings to stabilize. The conductivity reading should, however, be done first, as electrolyte from the combination pH probe may affect the conductivity of the solution.

6. Decontaminate probes and containers using distilled or de-ionized water.

7. Record the measurements in your field notebook along with a description of the rock type tested, and the general appearance of the sample.

Alternatives

For a coarser rock mixture, wet the surface of the rock with distilled water, and mix water with any surface coatings or fines. Place a piece of litmus paper over the wetted area. Compare the color of the litmus with the pH color-coded scale and record pH.

Calculations

Paste TDS is assessed by measuring Electrical Conductivity (EC) and then converting conductivity values to TDS using the equation (Hem, 1985):

$$0.59\left[EC, FScm^{-1}\right] = \left[TDS, mg/l\right]$$

Interpretation

High conductivity (or TDS) levels indicate there is a considerable store of contaminant salts. These are usually sulfates, but can be other metal salts. When a sample is collected over depth, it is not always clear whether the stored salts are due to oxidation at that point in the sediment profile, or if the salts were generated somewhere higher in the profile and moved downwards to the sample location. Look for stains along the flow path that may indicate if this is the case.

Low pH readings indicate oxidation and acid generation has occurred, usually at the location from which the sample was collected. Readings taken on uncrushed samples in the field or lab usually provide a much better indication of the extent of oxidation than crushed samples. This is because crushing can liberate neutralizing minerals thereby increasing the available neutralizing capacity of the sample.

References

Sobek, A.A., Schuller, W.A. Freeman, J.R. and Smith, R.M., 1978, Field and Laboratory Methods Applicable to Overburden and Minesoils, EPA 600/2-78-054, 203pp.

British Columbia AMD Task Force, 1989, Draft Acid Rock Drainage Technical Guide, Vol I, Crown Publications, Victoria, B.C.

MODIFIED ACID BASE ACCOUNTING (ABA)

Objectives

- To determine the balance between acid producing and acid consuming components of mine waste.

Principles of Test

The fundamental principals of acid base accounting comprise two distinct measurements:

1. Determination of the neutralization potential (NP) of a sample.

2. Calculation of the acid potential (AP) of the sample.

The difference between the two values, the net neutralization potential (Net NP), and the ratio (NP:AP) allow classification of the sample as potentially acid consuming or producing. To facilitate comparison of values, NP, AP, and Net NP are all expressed in units of tons $CaCO_3$ equivalent per kiloton.

In the original Sobek method of acid base accounting, the neutralization potential is determined by heating the sample and mixing for two hours. In the modified method, the neutralization potential is determined by treating a sample with excess standardized hydrochloric acid at ambient, or slightly above (25 - 30°C) ambient, temperatures for 24 hours. A fizz test is employed to provide a guide to the amount of acid to be initially added to the test. Acid is added as required during the acid-treatment stage to maintain sufficient acidity for reaction. After treatment, the unconsumed acid is titrated with standardized base to pH 8.3 to allow calculation of the calcium carbonate equivalent for the acid consumed.

For the calculation of the acid potential, the sample is analyzed for total and sulfate sulfur. Sulfide sulfur content is also measured or is calculated by the difference between the other two sulfur numbers. AP is determined from sulfide sulfur number, assuming: 1) total conversion of sulfide to sulfate; and, 2) production of 4 moles H^+ per mole of sulfide oxidized, assuming that all the sulfide is present as pyrite. In some cases, difficulties associated with the analytical procedures for sulfide analysis may

influence the estimation of the acid generation potential. For example, sulfate associated with the mineral barite is not readily distinguished from sulfide in a typical sulfate analysis, but does not contribute to the acid potential.

Equipment

1. Aluminum foil.
2. 250 mL Erlenmeyer flask.
3. Reciprocating shaking apparatus or other suitable agitation device.
4. Burette, 50 or 100 mL, one for each of the acid and the base solutions.
5. pH meter, equipped with a combination pH electrode.

Reagents

1. Distilled (or deionized) water, preferably CO2-free (store in container equipped with an ascarite tube)
2. Certified grade, 0.1 N hydrochloric acid, for standardization of bases
3. Approximately 0.1 N sodium hydroxide, standardized.
4. Approximately 0.5 N sodium hydroxide, standardized.
5. Approximately 0.1 N hydrochloric acid, standardized.
6. Approximately 0.5 N hydrochloric acid, standardized.
7. Approximately 25 percent strength hydrochloric acid, for fizz test.
8. Buffer solutions (pH 4.00 and 7.00) for calibration of pH meter.

Procedure

1. Crush and pulverize the sample to a target size of 80 percent minus 60 mesh (Tyler). Tailings samples should be tested at the received particle size.
2. Submit a sample of the test material for total sulfur and sulfate sulfur analyses.

3. Use certified 0.1 N hydrochloric acid to standardize the 0.1 N and 0.5 N sodium hydroxide solutions to standardize the 0.1 N and 0.5 N hydrochloric acid solutions.

4. Place approximately 0.5 g of pulverized sample on a piece of aluminum foil in a small shallow dish. Add one or two drops of 25 percent HCl to the sample. The presence of carbonate will be indicated by a bubbling or an audible "fizz". Rate the "fizz" as indicated in Table 1.

Volume and Normality of HCl for Use in NP

Determination on Basis of Fizz Rating (2g Sample)

Fizz Rating	HCl (mL, Normality)	
None	20	0.1
Slight	40	0.1
Moderate	40	0.5
Strong	80	0.5

5. Weigh 2.00 g of the sample (minus 60 mesh) into a 250 mL Erlenmeyer flask and, as a first approximation, add the volume and normality of HCl as indicated by the "fizz" rating shown above.

6. Agitate the contents of the flask for 24 hours by placing on a shaking apparatus. At least once in the treatment period, and preferably after approximately 6 hours of reaction, check the pH of the pulp. If the pH is above 2.0, add an appropriate volume of hydrochloric acid of the same strength originally added (generally between 1.5 to 2.0 ml). Record the amount added for back titration.

7. At the end of the shaking period, check the pulp pH. If the total volume and strength of acid was appropriate, the end pH will be in the range 1.5 - 2.0. If the pH is above this range, the amount of acid added is judged to be insufficient for reaction. If the pH is below the range, the amount of acid added is judged to be

too high, causing over reaction. In either case, repeat the test using the next higher or lower volume or strength of HCl as appropriate.

8 Titrate the contents of the flask using 0.1 N or 0.5 N NaOH (corresponding to the normality of HCl used in step 4) to pH 8.3. Titrate with NaOH until a constant reading of 8.3 remains for at least 30 seconds.

Calculations

1. The neutralization potential, NP, of the sample is given by:

$$NP = \frac{50a[x - (b/a)y]}{c}$$

where NP = neutralization potential in tonnes $CaC0_3$ equivalent per 1000 tonnes of material

a = normality of HCl

b = normality of Na0H

c = sample weight in grams

x = volume of HCl added in mL

y = volume of Na0H added to pH 7.0 in mL

2. The acid potential, AP, of the sample in kg CaC03 equivalent per ton, is given by:

AP = Percent sulphide sulfur x 31.25

where,

sulphide sulfur = total sulfur - sulfate sulfur

3. The net neutralization potential, Net NP, in kg CaC03 equivalent per ton of material is given by:

$Net\ NP = NP - AP$

Reporting of Results

The results of the test should be tabulated to provide the following information:

Sample description, paste pH, total sulfur analysis (% S_T), sulfate sulfur analysis (% $S(SO_4)$, NP (kg $CaC0_3$ equivalent per ton), AP (kg $CaC0_3$ equivalent per ton), Net NP (kg $CaC0_3$ equivalent per ton).

References

Lawrence, R.W., Poling, G.P. and Marchant, P.B., 1989. Investigation of predictive techniques for acid mine drainage. Report on DSS Contract No. 23440-7-9178/01-SQ, Energy Mines and Resources, Canada, MEND Report 1.16.1 (a).

Sobek, A.A., Schuller, W.A. Freeman, J.R. and Smith, R.M., 1978, Field and Laboratory Methods Applicable to Overburden and Minesoils, EPA 600/2-78-054, 203pp.

STATIC NET ACID GENERATION (NAG) TEST PROCEDURE

Objectives

- To determine the net acid remaining, if any, after complete oxidation of the materials with hydrogen peroxide and allowing complete reaction of the acid formed with the neutralizing components of the material. The NAG test provides a direct assessment of the potential for a material to produce acid after a period of exposure and weathering and is used to refine the results of the theoretical ABA predictions.

Principles of the Tests

After neutralization is completed, by reaction with hydrogen peroxide, the remaining H_2SO_4, if any, is titrated with sodium hydroxide. The amount of NaOH needed is equivalent to the NAG of the material (expressed in kg H_2SO_4/tonne material).

Sample Preparation

Tailings samples can be tested 'as received'.

Reagents

1. H2O2 - BDH 'Analar' Analytical Reagent 30% w/v (100 V), or equivalent, diluted 1:1 with deionized H2O to 15% a.

2. NaOH - 0.50M Standardized Solution.

3. NaOH - 0.10M Standardized Solution.

Procedure:

Add 250 mL of reagent 1 (15% H_2O_2) to 2.5 g of tailings (pulverized sample if testing waste rock) sample in a 500 mL wide mouth conical flask, or equivalent. Cover with a watch glass, and place in a fumehood or well-ventilated area [b]. The H_2O_2 should be at room temperature before commencing test.

Allow sample to react until 'boiling' or effervescing ceases. Heat sample on hot plate and gently boil until effervescence stops or for a minimum of 2 hours. Do not allow sample to boil dry - add deionized water if necessary.

Allow solution to cool to room temperature then record final pH (NAGpH).

Rinse the sample that has adhered to the sides of the flask down into the solution with deionized water. Add deionized water to give a final volume of 250 mL.

Titrate solution to pH 4.5 while stirring with appropriate NaOH concentration based on final NAG solution pH as follows:

NAG Solution pH	Reagent	NaOH Concentration
>2	3	0.10 M
≤2	2	0.50 M

[a] The pH of the H_2O_2 used in the NAG test should be checked to ensure it is between pH 4 and 7. If the pH is less than 4 then add dilute NaOH (use a solution made up by adding 1 g NaOH to 100 mL deionized H_2O) until the pH is greater than 4 (aim for a pH between 4 and 6). The pH is adjusted to greater than pH 4 to ensure that the phosphoric acid, used to stabilize H_2O_2 in some brands, is neutralized. The pH of the 15% H_2O_2 should always be checked to ensure that any stabilizing acid is neutralized, otherwise, false positive results may be obtained.

[b] The NAG reaction can be vigorous and sample solutions can 'boil' at temperatures of up to 120°C. Great care must be taken to place samples in a well-ventilated area or fume cupboard.

Calculations

The NAG capacity is determined by titration of the sample to determine the net amount of acid generated by peroxide oxidation.

Net Acid Generation:

$$NAG = \frac{49 \times V \times M}{W}$$

Where:

NAG = net acid generation (kg H_2SO_4/tonne)

V = volume of base NaOH titrated (mL)

M = molarity of base NaOH (moles/L)

W = weight of sample reacted (g)

NOTE: If NAG value exceeds 25 kg H_2SO_4 per tonne, repeat using a 1.00 g sample.

Interpretations

The NAG capacity is an independent measure of the acid generating potential of a sample. Materials should be classified based on the table given below.

SAMPLE CATEGORY	FINAL NAGpH	NAG VALUE kg H_2SO_4/t	NNP kg/ton $CaCO_3$
POTENTIALLY ACID FORMING			
Higher capacity	<4	>10	positive
Lower capacity	<4	≤10	negative
UNCERTAIN [1]	≥4	0	positive
NON-ACID FORMING [2]	≥4	0	positive

[1] Further evaluation including sulfur forms and mineralogy

[2] Acid consuming materials are identified by NNP values less than approximately -100

References

Miller, S., Robertson, A., and Donohue, T. (1997). Advances in Acid Drainage Prediction Using the Net Acid Generation (NAG) Test. In: *Proceedings of the Fourth International Conference on Acid Rock Drainage, Vancouver, B.C., Canada, 1997*, vol II, pp. 535-547.

Lewis, H.S., Susteyo, W., Miller, S.D., and Jeffery, J.J. (1997). Waste Rock Management Planning and Implementation at P.T. Freeport Indonesia Company's Mining Operations in Irian Jaya. In: *Proceedings of the Fourth International Conference on Acid Rock Drainage, Vancouver, B.C., Canada, 1997*, vol III, pp. 1361-1376.

EPA 1312 Leach Extraction Test

Objectives

- To characterize and quantify the soluble contaminant content of waste rock samples.

Principles of Test

The sample is mixed with distilled water, and is agitated in a flask to allow dissolution of the contained, soluble secondary mineral phases. The solution is collected at the end of the test, filtered, and analysed for immediate parameters (pH, alkalinity, acidity, sulfate, and conductivity) and for contained metals.

This test method is modified from the EPA method 1312 by using a ratio of water to solids of 2:1 or 3:1 rather than 20:1. The less dilution reduces the possibility of metal concentrations below detection.

Equipment

1. Erlenmeyer Flask (500 mL to 1 L, depending on sample size).

2. pH and conductivity meters.

3. Water filtering apparatus and filters.

4. Reciprocating shaking apparatus or other suitable agitation device.

Reagents

1. Distilled Water.

2. Calibration standards for pH and conductivity.

Procedure

1. Split a representative sample of approximately 200 to 500 g from the field sample, and determine exact weight. Place in Erlenmeyer Flask. The amount of sample is at the discretion of the technician, but should be increased if the particle sizes are large or the variation between the different particles is high.

2. Add distilled (or de-ionized) water to the sample to obtain a water to solids ratio of exactly 2:1 by weight. Cap the Erlenmeyer flask and place in agitation device.

3. Agitate the slurry for a total period of 23 hours. Terminate the agitation process and allow suspended solids to settle for one hour prior to termination of the test.

4. Remove the clear decant and filter the solution immediately, using a standard 0.45 µm millepore filter. Remove a small portion of the filtrate and determine the conductivity and pH.

5. Solution samples are submitted for analysis of immediate parameters (pH, alkalinity, acidity Eh, and conductivity) and for constituent concentrations (ICP metal scan and sulfate).

Note:Analytical procedures for radionuclide analyses generally require larger eluate concentrations. Therefore, a larger volume of solid will be required.

Interpretation

Soluble salt and radionuclide contents are calculated from the eluate constituent concentration and volume, and are reported per unit mass of waste rock.

Solubility controls on the solution concentrations should be checked by assessing saturation indices for the contaminants of concern. This may be done rapidly by using a geochemical equilibrium model such as MINTEQA2 or equivalent. Where saturation conditions are indicated, consecutive extraction tests should be performed to determine the total soluble component loading from the cumulative constituent release by the waste rock sample.

References

The field extraction test is modified from a number of different sources, including the EPA series of extraction tests.

Humidity Column Testing

Objectives

The intent of humidity column testing procedures is to simulate as many of the field conditions as is practical. These conditions include:

- representative particle size distributions for the fine fraction (less than 4") within the mine rock; and
- flushing rates encountered under normal circumstances in mine rock piles at the site;
- contact time between the leachate and the rock, usually the flowpath length.

To accomplish this, a large volume of rock is used for the testing, approximately 5 - 8 kg. The rock is graded to represent the 4-inch minus fraction of the rock contained in the rock piles. The site precipitation levels are evaluated on a surface area basis. The diameter of the column is adjusted (within a reasonable limit) to provide enough leachate for the analysis. The flow path (column length) should be approximately 1.5 times greater than the diameter of the column. During the column operation, water is trickled over the rock for 2 days. Air that is humidified by bubbling it through water at a temperature slightly above room temperature, is introduced at the bottom of the column for 5 days of each cycle. Usually the test is carried out for 20 weeks, with weekly analysis of key parameters (pH, alkalinity, acidity, conductivity, Eh, sulfate). Metals are typically measured on a weekly basis until "steady state" conditions have been achieved. After 10 weeks of testing, the frequency of metals analysis can be reduced to every other week, or less, depending on the test results to that time. A typical humidity column is shown in the figure below.

Procedure

1. Examine site precipitation records over a typical yearly period. If there is a seasonal rainy period, determine the average weekly precipitation during that period. Look at the pattern of this rainfall, i.e. is it a steady drizzle over a few days, or heavy rain over a few hours. The water addition rate to the column should follow this pattern as closely as is possible.

2. Calculate the rate of water addition to the column. Start with a minimum column diameter of 30 cm.

eg. rainfall = 10 mm/week over the rainy season
column = 30 cm diameter (0.152 metres radius)
SA column = pr2 = 3.14 (0.152)2 = 0.073
irrigation volume = 0.010 m/wk x 0.073 m2 = 0.00073 m3/wk = 0.73 L/wk

If this volume seems reasonable, use the 30 cm column. If it is not sufficient to satisfy the sample volume requirements for the weekly analyses, the column diameter should be increased until this is satisfied.

3. Once the column diameter has been determined, the rock sample height is obtained by multiplying the diameter by 1.5. The equipment should provide some freeboard above the rock column height (approximately 5 to 10 cm).

   The columns can be constructed out of almost any "inert" plastic cylinder. ABS or PVC pipe provides good strength and durability at a reasonable cost. Plexiglass also works well, but is usually expensive, especially for the large diameter columns.

   As illustrated in Figure D.5.1, the column must have a raised screen constructed about an 2 cm from the bottom, and a solid base through which the leachate is collected. All joints are sealed with a high quality flexible plumbing sealing. (There are supports in the void between the perforated base and the base plate). Humidified air is added through an additional port at the base of the column (not shown). Several layers of Teflon mesh areplaced above the perforated plate to prevent washing of fines from the sample into the collection zone. During the column operation, a clear plexiglass cover is placed over the column to prevent excessive evaporation losses.

4. Water addition

   Water is applied to the column using a peristaltic pump. This can be automated with a timer that pulses water, in a fine spray, over the surface of the rock. Water can also be applied as a continuous drip over one area of the column. Dispersal of water can be achieved in a number of ways, eg. glass rods, plastic tubing, or possibly plastic pellets. (Our experience is that glass wool provides a significant source of alkalinity, and should not be used.)

5. At the start of the test, the dry rock will absorb a considerable amount of water. For the first week, humidified air should be added continuously to the column, to

wet the surfaces of the rock and initiate the oxidation process. Once good water recovery (80%) has been achieved, the regular weekly cycle should commence. A typical cycle is described below.

a) Humid Aeration Cycle - for five days, humidified air is added at the base of the columns;

b) Flush Cycle - de-ionized water is added to the column over a two day period. Water is added via a continuous drip dissipated over the top surface of the rock column.

c) Leachate Collection - the column is allowed to drain for 4 hours after the flush cycle is terminated. At the end of the drain cycle the leachate is collected and analyzed.

The test should be run for at least 20 weeks. Test results should be evaluated periodically. After 20 weeks, if the results are inconclusive, the program may need to be extended.

6. Solution samples are submitted for analysis of immediate parameters (pH, alkalinity, acidity Eh, and conductivity) and for constituent concentrations (ICP metal scan and sulfate) on a weekly basis.



Humidity Column Design

APPENDIX A.2

PASTE pH AND CONDUCTIVITY DATA

ACID BASE ACCOUNTING DATA

and

NET ACID GENERATION DATA

1997 Surface Sample Analyses

Sample	Type	Lithology	Visible sulfide %	EC	Paste pH	NAG kg/T H_2SO_4	NAG pH	Sulfate %	Sulfide %	Sulfur Total %	SO_4/S %	AGP m/g $CaCO_3$	NP m/g $CaCO_3$	NNP	NP:AP
ERD 5500 001	T	QM	1	3140	3.63	29.60	5.11	0.71	0.74	1.45	48.97	45.3	18.9	-26.4	0.42
ERD 5500 002	HS	QB	4	19	7.94	15.48	2.48	0.44	2.46	2.9	15.17	53.1	62.5	9.4	1.18
ERD 5500 004	LS	QM	1	430	5.31										
ERD 5500 005	LS	QM	1	595	3.31										
ERD 5500 006	LS	QM	1.5	891	5.72										
ERD 5500 009	HS	BB	10	4000	2.71	80.75	6.30	0.6	2.3	2.9	20.69	91	9.1	-81.9	0.10
ERD 5500 010	LS	QM	1.5	471	4.55	19.99	3.92								
ERD 5500 012	HS	QM	2	1928	2.71										
ERD 5500 014	HS	QM	2	4370	2.73										
ERD 5510 002	LS	QM	1.5	257	4.71										
ERD 5560 001	O	AN			9.14			0.01	0.005	0.01	100.00	0.3	23.2	22.9	77.33
ERD 5560 002	HS	QM	8	467	6.76			0.3	2.6	2.9	10.34	90	23.7	-66.3	0.26
ERD 5560 006	HS	QB	2	1305	3.38										
ERD 5560 008	HS	QV	5	330	4.08			0.47	1.7	2.2	21.36	68	2	-66	0.03
ERD 5560 010	LS	QM	1.5	708	4.55	23.62	3.87								
ERD 5560 011	HS	QB	3	1565	4.54	22.05	4.07								
ERD 5600 001	LS	QM	1	450	4.44			0.1	0.43	0.53	18.87	17	0.1	-16.9	0.01
ERD 5600 003	HS	QB	3	4230	2.9	33.81	3.19	0.96	1.3	2.2	43.64	69	0.1	-68.9	0.00
ERD 5600 005	T	QB	0.5	2700	3.23	27.05	4.34								
ERD 5600 007	T	QM	0.5	174	6.88	14.31	2.68								
ERD 5600 009	T	QM	0.5	657	4.73										
ERD 5600 011	T	QM	0.5	847	5.43										
ERD 5600 012	T	QM	0.5	254	6.82										
ERD 5600 013	HS	QM	2	321	5.17										
ERD 5600 014	HS	BB	2	2080	3.55										
ERD 5600 070	HS	BB	4	227	4.92	11.27	2.45								
NRD 5620 001	HS	BB	4	41	5.05	10.68	3.41								
NRD 5620 001	HS	QB	5	1193	2.91	19.80	2.45								
NRD 5620 002	HS	QB	6	1717	2.68	77.62	2.98	0.3	2.6	2.9	10.34	90	23.7	-66.3	0.26
NRD 5620 003	HS	QM	4	1111	3.56	57.33	4.12	0.2	1.6	1.8	11.11	55	0.1	-54.9	0.00
NRD 5620 004	O	QM			4.75			0.17	0.1	0.18	94.44	5.6	0.1	-5.5	0.02
NRD 5620 005	T	QV	1	2170	2.81	9.60	4.81								
NRD 5620 006	HS	QM	2	260	3.68										
NRD 5620 007	HS	QM	2	1009	2.98										
NRD 5620 008	HS	QM	3	235	4.13	42.63	5.90	0.15	1.1	1.3	11.54	40	0.8	-39.2	0.02
NRD 5620 009	HS	QM	2	663	3.28										
NRD 5620 010	HS	QM	2	128	3.86										
NRD 5620 011	HS	QM	2	1219	2.68	39.69	3.51	0.28	0.92	1.2	23.33	36	0.1	-35.9	0.00
NRD 5620 012	HS	QB	4	997	2.75	58.80	4.08	0.2	1.6	1.8	11.11	57	0.1	-56.9	0.00
NRD 5620 013	HS	QM	2	2240	2.62										
NRD 5620 014	HS	QB	20	4860	2.5	223.44	3.65	0.9	6.2	7.1	12.68	220	0.1	-219.9	0.00
NRD 5620 015	HS	QB	2	1075	3.71										
NRD 5620 016	HS	QM	2	3390	2.51										

1997 Surface Sample Analyses

Sample	Type	Lithology	Visible sulfide %	EC	Paste pH	NAG kg/T H_2SO_4	NAG pH	Sulfate %	Sulfide %	Sulfur Total %	SO_4/S %	AGP m/g $CaCO_3$	NP m/g $CaCO_3$	NNP	NP:AP
NRD 5650 017	LS	QM	1	41.4	6.09	23.72	4.11	0.13	0.22	0.35	37.14	11	0.1	-10.9	0.01
NRD 5650 018	HS	QM	2	89	4.82										
NRD 5650 019	HS	QM	2	3620	2.79	46.35	4.40	0.1	1.3	1.4	7.14	45	0.1	-44.9	0.00
SRD 5470 006	HS	QM	2	63	5.94										
SRD 5470 010	LS	QM	1	196	7.05	8.72	2.51								
SRD 5470 011	HS	QV	5	2200	2.54	43.51	3.10	0.21	1.3	1.5	14.00	47	6.7	-40.3	0.14
SRD 5470 012	HS	QB	6	182	7.63			0.46	1.4	1.9	24.21	59	38.9	-20.1	0.66
SRD 5470 013	HS	QM	3	821	4.4										
SRD 5470 014	HS	QB	4	62.9	5.26	5.88	2.29								
SRD 5470 015	HS	QM	3	118.5	5.55										
SRD 5470 016	HS	QM	4	89.6	7.06										
SRD 5470 016	HS	QV	5	6570	2.66										
SRD 5470 017	HS	QB	4	27	5.02	21.56	2.27								
SRD 5470 018	HS	QB	5	1703	3.08										
SRD 5470 019	HS	QV	5	229	4.55										
SRD 5470 020	HS	QM	3	162	7.83	12.74	2.47	0.31	1.1	1.4	22.14	44	36.4	-7.6	0.83
SRD 5470 021	HS	QB	4	321	4.32										
SRD 5470 022	HS	QM	2	386	6.03										
SRD 5470 023	HS	QM	4	27	5.51										
SRD 5470 024	HS	QM	5	3970	2.52										
SRD 5470 025	HS	QM	3	172.2	5.21										
SRD 5470 027	HS	QM	2	3520	2.72	15.78	2.52								
SRD 5490 007	O	QM		42	8.76	19.70	3.32								
SRD 5500 001	HS	QM	2	831	5.31	8.23	4.10	0.37	0.7	1.1	33.64	33	34.2	1.2	1.04
SRD 5500 002	HS	BB	4	33	7.38	22.05	4.63								
SRD 5500 003	O	BB		58.7	4.75										
SRD 5500 004	HS	QB	4	231	5.5										
SRD 5500 005	HS	QV	5	292	6.05	19.01	3.96								
WRC 5440 30	HS	QM	2	227	4.1	15.88									
WRC 5440 31A	LS	QM	0.5		7.91			0.23	0.32	0.55	41.82	33	34.2	1.2	1.04
WRC 5440 31B	T	QM	0.5		8.35			0.21	0.11	0.32	65.63	10	10.1	0.1	1.01
WRC 5440 32	O	QM		347	6.55			0.19	0.05	0.24	79.17	7.5	9.6	2.1	1.28
WRC 5480 006	HS	QB	5	3680	3.7	31.46									
WRC 5480 007	HS	QB	5	1643	3.18	33.52									
WRC 5480 007	HS	QV	5	550	3.41	32.73									
WRC 5480 008	HS	QM	2	785	3.67	15.09									
WRC 5480 009	HS	BB	3	764	3.73	32.54									
WRC 5480 010	HS	BB	4	1338	3.76	28.71									
WRC 5480 012	LS	QB	1	589	4.01	33.81									
WRC 5480 013	LS	QM	1	297	6.95	15.19									
WRC 5480 014	T	QB	0.5	801	4.12	20.19		1.25	0.89	2.08	60.10	65	47.6	-17.4	0.73
WRC 5480 015	HS	QM	2	826	3.42										
WRC 5480 016	LS	QM	1	470	6.26										
WRC 5480 018	HS	QM	2	4840	3.02										

1997 Surface Sample Analyses

Sample	Type	Lithology	Visible sulfide %	EC	Paste pH	NAG kg/T H_2SO_4	NAG pH	Sulfate %	Sulfide %	Sulfur Total %	SO_4/S %	AGP m/g $CaCO_3$	NP m/g $CaCO_3$	NNP	NP:AP
WRC 5480 019	HS	QM	2	3020	2.66										
WRC 5480 020	HS	QM	2	878	3.96										
WRC 5480 021	HS	QM	2	1009	4.38										
WRC 5480 022	HS	QM	2	1850	2.97										
WRC 5480 023	HS	QM	2	1880	2.64										
WRC 5480 024	HS	QM	1.5	1190	2.71										
WRC 5480 025	LS	QM	1	637	8.6										
WRC 5480 026	LS	QM	1	129	9.65										
WRC 5480 027	HS	QM	2	1580	2.12										
WRC 5480 028	HS	QM	2	964	4.89										
WRC 5480 029	HS	QM	2	580	3.59										
WRC 5480 030	HS	QM	2	258	5.85										
WRC 5580 005	T	QV(Sternberg)pw2	2	19000	3.79										
WRD 4480 010	LS	QM	1	50	6.06										
WRD 5560 020	LS	QM	1	64	6.72										
WRD 5560 027	HS	QM	2	3990	2.56										
WRD 5560 028	HS	QM	2	730	2.95										
WRD 5560 029	HS	QM	2	1552	2.53										
WRD 5560 030	HS	QM	2	321	4.64										
WRD 5560 031	HS	QM	2	282	4.4										
WRD 5560 032	HS	QM	2	620	2.99										
WRD 5560 034	HS	QM	2	201	3.95										
WRD 5560 035	HS	QM	2	833	4.35										
WRD 5560 036	HS	QM	2	171	3.79										
WRD 5560 037	HS	QM	2	164	7.8										
WRD 5560 038	HS	QM	5	54	6.59	18.33	7.92	0.3	1.2	1.5	20.00	47	30.2	-16.8	0.64
WRD 5560 039	HS	QB	6	1848	2.81	72.13	3.92	0.1	2.1	2.2	4.55	70	0.1	-69.9	0.00
WRD 5560 040	HS	QB	3	456	3.97	36.46	2.98								
WRD 5560 041	HS	QB	4	2190	3.31	50.57	4.18	0.3	1.4	1.7	17.65	53	7.6	-45.4	0.14
WRD 5580 001	LS	QM	1	133	4	21.56	2.27	0.3	0.8	1.1	27.27	33	17.8	-15.2	0.54
WRD 5580 002	HS	QM	3	1422	2.77	34.01	6.00								
WRD 5580 004	O	QB			4.82			0.33	0.1	0.34	97.06	11	0.1	-10.9	0.01
WRD 5580 005	LS	QM	2	93	6.72	29.40	5.01								
WRD 5580 006	T	QM	0.5	212	3.2	30.77	5.06								
WRD 5580 007	HS	QB	2	345	3.02	31.07	4.87								
WRD 5580 008	HS	QB	2	230	5.55	29.01	5.15								
WRD 5580 009	HS	QM	2	325	3.14	28.62	5.01								
WRD 5580 011	HS	QM	2	8	5.6	28.03	5.29								
WRD 5580 012	HS	QM	2	305	5.4	29.11	5.1								
WRD 5580 013	HS	BB	7	2860	2.45	47.14	2.09								
WRD 5580 014	HS	BB	4	21	5	31.85	5.27	0.2	1.96	2.16	9.26	73.8	43.7	-30.1	0.59
WRD 5580 015	HS	QB	4	156	4.45	31.16	3.05								
WRD 5580 016	HS	QM	2	45.6	5.72	22.74	4.06								
WRD 5580 017	HS	QM	2	41	5.54	30.48	5.04								

1997 Surface Sample Analyses

Sample	Type	Lithology	Visible sulfide %	EC	Paste pH	NAG kg/T H_2SO_4	NAG pH	Sulfate %	Sulfide %	Sulfur Total %	SO_4/S %	AGP	NP	NNP	NP:AP
												m/g $CaCO_3$			
WRD 5580 018	HS	QM	2	112	6.4	32.93	5.55								
WRD 5580 019	HS	QM	2	42	6.14	19.60	3.91								
WRD 5580 021	HS	QM	2	65	5.87	19.89	3.98								
WRD 5580 022	HS	QM	2	170	5.61	39.79	3.00								
WRD 5580 023	HS	QM	2	103	7.67	21.17	4.63								
WRD 5580 024	HS	QM	1.5	183	5.39	21.56	4.07								
WRD 5580 025	HS	QM	1.5	42	5.74	15.78	2.52								
WRD 5580 026	HS	QM	2	84	6.1	34.79	6.42								
WRD 5580 033	HS	QM	1.5	237	3.82	38.71	7.74								
WRD 5580 042	HS	QB	5	1080	2.35	76.93	2.10	0.15	2.2	2.4	6.25	74	0.1	-73.9	0.00

KEY

Lithology QM= Quartz Monzonite QB= Quartz Breccia BB= Biotite Breccia QV = Quartz Vein AN = Andesite

Visible sulfide (%) = Observed pyrite/sulfide content in hand specimen

Type HS=High Sulfide (>2% visible sulfide) LS= Low Sulfide (<2% visible sulfide) T=Transitional (trace sulfide & acidic paste pH) O=Oxide (no observed sulfide)

NAG (eqkg H_2SO_4/T)= $\frac{49 \times \text{Volume of NaOH titrated} \times \text{molality of NaOH (0.1M)}}{\text{weight of sample (5g)}}$

Copper Flat Project
Static Test on Wall Rock and Drill Core from the Pit Area
1994 Sampling

Sample	Paste PH	Total	Sulfide	Sulfate	NP	AP	NNP	NP/AP
PW-1 SW pitwall transition	6.1	3.61	3.47	0.14	32	108.44	-76.44	0.3
PW-2 Oxidized pitwall	--	0.37	0.365	0.005	11	11.41	-0.41	0.96
PW-3 NW pitwall	2.6	2.2	2.195	0.005	0.1	68.59	-68.49	--
PW-4 NE pitwall	3.9	1.89	1.885	0.005	16	58.91	-42.91	0.27
IDC24-222-241, QM – core	--	1.74	1.735	0.005	31	54.22	-23.22	0.57
CF10-177-190, andesite – core	--	2.86	2.8	0.06	52	87.5	-35.5	0.59
CF10-190-199 QM—core	--	3.59	3.52	0.07	44	110	-66	0.4
CF10-214-220, QM – core	--	3.92	3.915	0.005	65	122.34	-57.34	0.53
H75-53-42, QM - reverse circ.	8.2	1.77	1.765	0.005	36	55.16	-19.16	0.65
H75-64-44, QM - reverse circ.	7.2	1.69	1.685	0.005	39	52.66	-13.66	0.74
H75-51-34, QM - reverse circ.	8.6	2.02	2.015	0.005	49	62.97	-13.97	0.78
H75-48-58, QM - reverse circ.	7.2	1.18	1.175	0.005	16	36.72	-20.72	0.44
H75-48-44, QM - reverse circ.	7.4	1.06	1.055	0.005	9	32.97	-23.97	0.27

SOURCE: *Copper Flat Mine - Compliation of Pit Lake Studies (SRK 1997)*

APPENDIX A.3

HUMIDITY COLUMN TEST DATA

Parameter	Cycle 1	Cycle 2	Cycle 3	Cycle 4	Cycle 5	Cycle 6	Cycle 7	Cycle 8	Cycle 9	Cycle 10	Cycle 11	Cycle 12	Cycle 13	Cycle 14	Cycle 15
Ag ug/l	1.	4.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Al mg/l	0.03	0.05	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
As ug/l	30.	30.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
B ug/l	50.	50.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
Ba ug/l	75.	60.	30.	15.	35.	45.	35.	40.	40.	45.	40.	45.	35.	35.	15.
Be ug/l	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Bi ug/l	6.	26.	2.	2.	2.	2.	2.	2.	2.	2.	2.	6.	2.	2.	2.
Ca mg/l	30.48	23.76	18.11	12.95	18.44	15.01	13.24	13.16	13.42	15.01	13.19	15.92	13.85	11.87	5.47
Cd ug/l	1.	2.	1.	1.	3.	1.	1.	3.	1.	1.	1.	1.	1.	1.	1.
Co ug/l	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
Cr ug/l	5.	20.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
Cu ug/l	14.	16.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.
Fe mg/l	0.04	0.06	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
K mg/l	1.56	1.47	0.65	0.13	0.47	0.61	0.12	0.79	0.9	0.22	0.68	0.94	0.34	0.75	0.18
Li ug/l	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
Mg mg/l	1.26	1.04	0.59	0.36	0.58	0.42	0.39	0.39	0.37	0.34	0.52	0.65	0.48	0.48	0.18
Mn mg/l	0.07	0.03	0.02	0.02	0.035	0.03	0.025	0.025	0.025	0.02	0.015	0.02	0.015	0.01	0.005
Mo ug/l	6.	4.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	4.
Na mg/l	5.24	4.63	2.19	1.26	2.38	1.79	1.65	1.82	1.27	1.57	2.34	2.98	2.05	2.12	0.52
Ni ug/l	10.	15.	10.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	10.
P ug/l	40.	110.	10.	10.	10.	10.	30.	10.	10.	10.	10.	10.	10.	30.	10.
Pb ug/l	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	8.	10.	2.	2.	2.
Sb ug/l	10.	34.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	4.	2.
Se ug/l	85.	150.	5.	5.	5.	5.	50.	25.	15.	15.	30.	40.	5.	30.	15.
Si mg/l	0.87	0.6	0.53	0.3	0.6	0.39	0.51	0.52	0.5	0.53	0.56	0.73	0.48	0.57	0.28
Sn ug/l	100.	174.	2.	2.	2.	2.	2.	2.	6.	22.	46.	2.	2.	80.	2.
Sr ug/l	124.	104.	50.	28.	44.	32.	32.	34.	34.	32.	34.	46.	36.	34.	18.
Ti ug/l	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.
V ug/l	2.	5.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Zn ug/l	28.	25.	12.	3.	9.	20.	11.	16.	1.	1.	2.	6.	8.	5.	9.
pH	7.73	7.8	7.55	7.4	7.85	7.64	7.52	7.53	7.54	7.59	7.61	7.63	7.72	7.51	7.16
Redox (mV)	300.	289.	307.	321.	295.	311.	318.	321.	341.	287.	272.	264.	265.	265.	296.
Conductivity (uS/cm)	132.	104.	70.	45.	69.	53.	45.	42.	41.	46.	50.	63.	49.	44.	19.
Alkalinity (mg $CaCO_3$/l)	43.	31.	24.	17.	26.	18.	16.	17.	17.	20.	19.	26.	19.	16.	10.
Acidity (pH 4.5)	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
Acidity (pH 8.3)	1.	2.	2.	2.	1.	1.	2.	1.	1.	2.	1.	2.9	2.	2.	3.
Cum Acidity (pH 8.3)	0.1	0.1	0.2	0.3	0.3	0.4	0.5	0.5	0.6	0.7	0.7	0.9	1.	1.1	1.2
Sulphate (mg/l)	9.	9.	5.	6.	8.	6.	5.	4.	4.	4.	5.	4.	3.	4.	2.
Cum Sulphate (mg/kg)	0.5	0.8	1.	1.2	1.6	1.9	2.2	2.4	2.6	2.8	3.	3.2	3.4	3.6	3.7
Water added (L)	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2
pH of water added	5.45	6.26	5.98	5.59	6.15	6.03	5.83	5.98	6.15	6.05	5.96	6.04	6.06	6.56	6.23
Leachate collected (L)	0.214	0.144	0.184	0.148	0.188	0.218	0.169	0.23	0.188	0.231	0.189	0.191	0.212	0.21	0.194
Cumulative Iron	0.04	0.1	0.11	0.12	0.13	0.14	0.15	0.16	0.17	0.18	0.19	0.2	0.21	0.22	0.23
Cumulative Copper	14.	30.	32.	34.	36.	38.	40.	42.	44.	46.	48.	50.	52.	54.	56.

Parameter	Cycle 16	Cycle 17	Cycle 18	Cycle 19	Cycle 20	Cycle 21	Cycle 22	Cycle 23	Cycle 24	Cycle 25	Cycle 26	Cycle 27	Cycle 28	Cycle 29
Ag ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Al mg/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
As ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
B ug/l	<0.10	<0.10	<0.10	<0.10	<0.10								<0.10	<0.10
Ba ug/l	0.014	0.022	0.018	0.046	0.033								0.061	0.057
Be ug/l	<0.005	<0.005	<0.005	<0.005	<0.005								<0.005	<0.005
Bi ug/l	<0.10	<0.1	<0.1	<0.1	<0.1								<0.1	<0.1
Ca mg/l	1.5	2.75	2.2	4.49	2.7								6.21	8.
Cd ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.010	<0.010
Co ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Cr ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Cu ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.010	<0.010
Fe mg/l	<0.030	<0.030	<0.030	<0.030	<0.030								<0.030	<0.030
K mg/l	<2.0	<2.0	<2.0	<2.0	<2.0								<2.0	<2.0
Li ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Mg mg/l	0.091	0.12	0.12	0.323	0.16								0.453	0.621
Mn mg/l	0.008	0.005	0.005	0.007	<0.005								0.016	0.012
Mo ug/l	<0.030	<0.030	<0.030	<0.030	<0.030								<0.030	<0.030
Na mg/l	<2.0	<2.0	<2.0	<2.0	<2.0								<2.0	<2.0
Ni ug/l	<0.020	<0.020	<0.020	<0.020	<0.020								<0.020	<0.020
P ug/l	<0.30	<0.30	<0.30	<0.30	<0.30								<0.30	<0.30
Pb ug/l	<0.050	<0.050	<0.050	<0.050	<0.050								<0.050	<0.050
Sb ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
Se ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
Si mg/l	0.143	0.207	0.171	0.377	0.231								0.432	0.596
Sn ug/l	<0.30	<0.30	<0.30	<0.30	<0.30								<0.30	<0.30
Sr ug/l	0.011	0.016	0.015	0.03	0.022								0.04	0.053
Ti ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.010	<0.010
V ug/l	<0.030	<0.030	<0.030	<0.030	<0.030								<0.030	<0.030
Zn ug/l	0.01	0.006	0.009	0.012	0.015								0.022	0.024
pH	7.08	7.29	7.23	7.4	6.64								7.59	7.69
Redox (mV)	304.	284.	295.	288.	281.								291.	293.
Conductivity (uS/cm)	10.	16.	15.	32.	19.								45.	58.
Alkalinity (mg $CaCO_3$/l)	6.	10.	7.	12.	8.								16.	20.
Acidity (pH 4.5)	0.	0.	0.	0.	0.								0.	0.
Acidity (pH 8.3)	5.	5.	6.	3.	6.								5.9	6.9
Cum Acidity (pH 8.3)	1.4	1.6	1.9	2.1	2.4								2.6	3.
Sulphate (mg/l)	2.	2.	2.	4.	3.								4.	4.
Cum Sulphate (mg/kg)	3.8	3.9	3.9	4.1	4.3								4.5	4.7
Water added (L)	0.2	0.2	0.2	0.2	0.2								0.2	0.2
pH of water added	5.92	5.57	5.66	6.09	5.23								5.93	5.7
Leachate collected (L)	0.151	0.175	0.198	0.181	0.205								0.185	0.216
Cumulative Iron	0.23	0.23	0.23	0.23	0.23								0.23	0.23
Cumulative Copper	56.	56.	56.	56.	56.								56.	56.

Laboratory Equipment Failure
Weeks 21-27
No Samples Collected

LGSSP-2 - Kinetic Test Data

Parameter	Cycle 1	Cycle 2	Cycle 3	Cycle 4	Cycle 5	Cycle 6	Cycle 7	Cycle 8	Cycle 9	Cycle 10	Cycle 11	Cycle 12	Cycle 13	Cycle 14	Cycle 15
Ag ug/l	7.	6.	1.	1.	1.	1.	1.	1.	1.	1.	2.	1.	1.	1.	1.
Al mg/l	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
As ug/l	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
B ug/l	60.	70.	40.	30.	10.	10.	30.	10.	10.	10.	10.	10.	10.	10.	10.
Ba ug/l	200.	105.	60.	55.	60.	40.	70.	75.	50.	90.	80.	60.	60.	75.	45.
Be ug/l	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Bi ug/l	6.	26.	2.	2.	2.	2.	2.	2.	2.	2.	8.	2.	2.	2.	2.
Ca mg/l	155.59	115.41	85.41	76.19	55.92	41.91	51.46	44.1	38.78	54.5	52.94	37.69	45.46	51.56	32.69
Cd ug/l	18.	13.	5.	1.	5.	1.	3.	5.	1.	1.	6.	1.	7.	1.	1.
Co ug/l	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
Cr ug/l	20.	25.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
Cu ug/l	82.	54.	28.	26.	16.	18.	34.	16.	14.	12.	10.	6.	10.	10.	6.
Fe mg/l	0.41	0.28	0.04	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.08	0.01	0.01	0.01	0.01
K mg/l	7.07	7.1	7.65	7.2	4.99	4.56	5.84	4.95	4.58	4.64	5.79	4.85	5.52	6.79	4.62
Li ug/l	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
Mg mg/l	16.36	11.17	8.56	7.12	4.48	2.92	4.14	3.22	2.68	4.25	4.34	2.58	3.58	4.32	2.2
Mn mg/l	0.04	0.035	0.02	0.01	0.03	0.015	0.01	0.015	0.005	0.01	0.015	0.01	0.005	0.005	0.005
Mo ug/l	242.	308.	288.	282.	176.	122.	140.	96.	74.	126.	126.	60.	90.	98.	66.
Na mg/l	7.5	7.94	7.2	6.55	3.88	2.91	3.15	2.04	1.79	2.48	2.69	1.54	2.31	2.5	1.63
Ni ug/l	5.	15.	10.	5.	5.	5.	5.	5.	5.	5.	10.	5.	5.	5.	5.
P ug/l	230.	270.	300.	340.	220.	200.	240.	190.	120.	200.	220.	180.	200.	270.	150.
Pb ug/l	32.	20.	2.	2.	2.	2.	2.	2.	2.	2.	2.	6.	12.	2.	2.
Sb ug/l	18.	22.	2.	2.	2.	2.	2.	2.	2.	2.	10.	2.	2.	2.	2.
Se ug/l	530.	405.	285.	245.	125.	30.	210.	145.	160.	225.	170.	110.	125.	115.	70.
Si mg/l	5.53	6.71	7.61	8.57	6.18	7.08	7.17	5.79	6.24	5.6	5.38	4.81	5.66	5.39	5.
Sn ug/l	574.	508.	2.	2.	2.	2.	26.	92.	60.	64.	90.	44.	44.	52.	2.
Sr ug/l	1,018.	680.	492.	418.	270.	178.	252.	204.	168.	262.	234.	142.	216.	224.	126.
Tl ug/l	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.
V ug/l	11.	10.	5.	4.	2.	1.	4.	1.	1.	1.	6.	3.	2.	2.	2.
Zn ug/l	28.	14.	12.	13.	6.	17.	13.	14.	1.	1.	1.	1.	9.	1.	3.
pH	8.07	8.1	8.09	8.16	8.11	8.13	8.13	8.05	8.21	8.03	8.04	8.01	8.07	7.96	8.02
Redox (mV)	325.	306.	318.	330.	310.	322.	335.	337.	344.	294.	281.	271.	268.	269.	296.
Conductivity (uS/cm)	979.	690.	533.	448.	308.	196.	261.	204.	170.	264.	279.	170.	226.	267.	151.
Alkalinity (mg $CaCO_3$/l)	53.	54.	58.	64.	54.	53.	58.	49.	54.	50.	51.	41.	54.	48.	49.
Acidity (pH 4.5)	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
Acidity (pH 8.3)	1.	1.	1.	1.	1.	1.	1.	1.	0.5	1.	1.	1.	1.	1.	1.
Cum Acidity (pH 8.3)	0.	0.1	0.1	0.1	0.1	0.2	0.2	0.2	0.3	0.3	0.3	0.4	0.4	0.5	0.5
Sulphate (mg/l)	432.	243.	155.	141.	82.	29.	64.	49.	21.	69.	69.	30.	48.	72.	16.
Cum Sulphate (mg/kg)	10.4	17.5	22.6	25.9	28.7	29.6	32.	33.6	34.2	36.8	39.5	40.5	42.3	45.7	46.2
Water added (L)	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2
pH of water added	5.45	6.26	5.98	5.59	6.15	6.03	5.83	5.98	6.15	6.05	5.96	6.04	6.06	6.56	6.23
Leachate collected (L)	0.102	0.122	0.139	0.101	0.144	0.119	0.162	0.138	0.112	0.158	0.165	0.153	0.158	0.198	0.127
Cumulative Iron	0.41	0.69	0.73	0.74	0.75	0.76	0.77	0.78	0.79	0.8	0.88	0.89	0.9	0.91	0.92
Cumulative Copper	82.	136.	164.	190.	206.	224.	258.	274.	288.	300.	310.	316.	326.	336.	342.

LGSSP-2 - Kinetic Test Data

Parameter	Cycle 16	Cycle 17	Cycle 18	Cycle 19	Cycle 20	Cycle 21	Cycle 22	Cycle 23	Cycle 24	Cycle 25	Cycle 26	Cycle 27	Cycle 28	Cycle 29
Ag ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Al mg/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
As ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
B ug/l	<0.10	<0.10	<0.10	<0.10	<0.10								<0.10	<0.10
Ba ug/l	0.058	0.048	0.037	0.038	0.044								0.101	0.084
Be ug/l	<0.005	<0.005	<0.005	<0.005	<0.005								<0.005	<0.005
Bi ug/l	<0.10	<0.10	<0.10	<0.10	<0.10								<0.10	<0.10
Ca mg/l	27.3	22.4	16.4	17.	14.6								66.2	65.3
Cd ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.010	<0.010
Co ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Cr ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Cu ug/l	0.019	0.016	0.011	0.011	<0.010								0.014	0.018
Fe mg/l	<0.030	<0.030	<0.030	<0.030	<0.030								<0.030	<0.030
K mg/l	4.	3.4	2.2	2.8	<2.0								4.4	4.2
Li ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Mg mg/l	2.7	2.11	1.49	1.55	1.29								6.2	6.19
Mn mg/l	<0.005	<0.005	<0.005	<0.005	<0.005								<0.005	<0.005
Mo ug/l	0.066	0.041	<0.030	0.03	<0.030								0.065	0.093
Na mg/l	<2.0	<2.0	<2.0	<2.0	<2.0								<2.0	<2.0
Ni ug/l	<0.020	<0.020	<0.020	<0.020	<0.020								<0.020	<0.020
P ug/l	<0.30	<0.30	<0.30	<0.30	<0.30								<0.30	<0.30
Pb ug/l	<0.050	<0.050	<0.050	<0.050	<0.050								<0.050	<0.050
Sb ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
Se ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
Si mg/l	5.55	4.58	3.18	3.22	2.26								4.12	5.03
Sn ug/l	<0.30	<0.30	<0.30	<0.30	<0.30								<0.30	<0.30
Sr ug/l	0.179	0.14	0.104	0.108	0.093								0.409	0.393
Ti ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.010	<0.010
V ug/l	<0.030	<0.030	<0.030	<0.030	<0.030								<0.030	<0.030
Zn ug/l	0.005	0.009	<0.005	<0.005	<0.005								0.008	0.005
pH	8.12	8.09	8.01	7.92	7.22								7.9	7.96
Redox (mV)	288.	298.	294.	290.	280.								313.	296.
Conductivity (uS/cm)	177.	138.	104.	109.	93.								402.	384.
Alkalinity (mg $CaCO_3$/l)	57.	48.	34.	38.	30.								36.	49.
Acidity (pH 4.5)	0.	0.	0.	0.	0.								0.	0.
Acidity (pH 8.3)	1.	1.	2.	2.	3.								3.	2.
Cum Acidity (pH 8.3)	0.5	0.5	0.6	0.7	0.8								1.	1.
Sulphate (mg/l)	20.	10.	11.	11.	8.								139.	124.
Cum Sulphate (mg/kg)	46.8	47.1	47.5	47.9	48.3								54.4	59.3
Water added (L)	0.2	0.2	0.2	0.2	0.2								0.2	0.2
pH of water added	5.92	5.57	5.66	6.09	5.23								5.93	5.7
Leachate collected (L)	0.127	0.131	0.16	0.158	0.203								0.183	0.67
Cumulative Iron	0.92	0.92	0.92	0.92	0.92								0.92	0.92
Cumulative Copper	342.	342.	342.	342.	342.								342.	342.

Laboratory Equipment Failure
Weeks 21-27
No Samples Collected

C10-190-199-2 - Kinetic Test Data

Parameter	Cycle 1	Cycle 2	Cycle 3	Cycle 4	Cycle 5	Cycle 6	Cycle 7	Cycle 8	Cycle 9	Cycle 10	Cycle 11	Cycle 12	Cycle 13	Cycle 14	Cycle 15
Ag ug/l	5.	5.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Al mg/l	0.01	0.04	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
As ug/l	10.	30.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
B ug/l	50.	30.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
Ba ug/l	50.	30.	45.	35.	15.	25.	15.	15.	15.	25.	20.	35.	35.	15.	30.
Be ug/l	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Bi ug/l	6.	16.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	8.
Ca mg/l	48.27	40.54	43.47	34.16	32.33	30.47	23.86	25.61	19.7	22.26	20.91	23.92	22.28	18.03	22.24
Cd ug/l	3.	8.	2.	1.	1.	3.	3.	3.	1.	1.	1.	1.	4.	4.	3.
Co ug/l	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
Cr ug/l	10.	15.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
Cu ug/l	52.	34.	24.	20.	14.	10.	8.	8.	6.	4.	2.	2.	4.	4.	2.
Fe mg/l	0.05	0.11	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
K mg/l	3.95	3.56	4.39	2.98	2.07	1.51	2.13	2.16	1.36	0.77	1.5	1.78	1.35	1.31	2.1
Li ug/l	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
Mg mg/l	4.25	3.86	4.68	3.49	3.06	2.59	2.22	2.35	1.47	1.79	1.83	2.5	2.3	2.04	2.4
Mn mg/l	0.11	0.065	0.05	0.035	0.045	0.04	0.035	0.035	0.025	0.025	0.025	0.025	0.025	0.02	0.03
Mo ug/l	10.	12.	6.	4.	6.	2.	2.	2.	2.	2.	2.	4.	2.	4.	4.
Na mg/l	3.83	4.18	4.35	3.16	2.22	2.01	1.98	1.78	1.24	1.01	1.09	1.82	1.61	1.66	1.87
Ni ug/l	5.	10.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
P ug/l	60.	100.	10.	30.	10.	10.	10.	30.	10.	10.	10.	10.	10.	10.	20.
Pb ug/l	6.	22.	2.	2.	2.	2.	2.	2.	2.	2.	6.	2.	2.	2.	4.
Sb ug/l	14.	22.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.
Se ug/l	205.	200.	80.	75.	40.	5.	50.	95.	95.	75.	15.	70.	10.	35.	60.
Si mg/l	0.85	0.7	1.02	0.82	0.71	0.78	0.9	0.81	0.57	0.53	0.5	0.66	0.3	0.41	0.74
Sn ug/l	66.	316.	2.	2.	148.	2.	18.	66.	24.	50.	2.	2.	8.	58.	2.
Sr ug/l	372.	320.	324.	244.	194.	184.	136.	150.	100.	110.	94.	132.	120.	80.	140.
Tl ug/l	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.
V ug/l	5.	6.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	2.
Zn ug/l	31.	29.	21.	16.	13.	13.	14.	8.	1.	1.	10.	30.	19.	17.	36.
pH	8.07	7.91	7.9	7.37	7.75	7.8	7.66	7.4	7.78	7.57	7.55	7.45	7.03	7.04	7.45
Redox (mV)	306.	297.	315.	327.	303.	320.	326.	329.	346.	292.	279.	276.	277.	281.	304.
Conductivity (uS/cm)	259.	225.	253.	181.	165.	142.	112.	114.	77.	89.	90.	114.	103.	86.	107.
Alkalinity (mg $CaCO_3$/l)	43.	30.	32.	22.	19.	25.	20.	21.	19.	17.	15.	15.	11.	10.	16.
Acidity (pH 4.5)	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
Acidity (pH 8.3)	1.	1.	1.	2.	1.	1.	2.	2.	0.5	2.	1.	2.	2.	2.	2.
Cum Acidity (pH 8.3)	0.	0.1	0.1	0.2	0.2	0.3	0.3	0.4	0.4	0.5	0.6	0.7	0.8	0.9	0.9
Sulphate (mg/l)	65.	58.	70.	57.	51.	33.	25.	26.	12.	17.	20.	30.	27.	20.	22.
Cum Sulphate (mg/kg)	3.2	5.5	7.8	9.5	12.	13.4	14.2	15.4	15.9	16.7	17.6	19.	20.3	21.2	22.1
Water added (L)	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2
pH of water added	5.45	6.26	5.98	5.59	6.15	6.03	5.83	5.98	6.15	6.05	5.96	6.04	6.06	6.56	6.23
Leachate collected (L)	0.228	0.175	0.149	0.139	0.224	0.19	0.158	0.198	0.195	0.219	0.215	0.208	0.219	0.206	0.194
Cumulative Iron	0.05	0.16	0.17	0.18	0.19	0.2	0.21	0.22	0.23	0.24	0.25	0.26	0.27	0.28	0.29
Cumulative Copper	52.	86.	110.	130.	144.	154.	162.	170.	176.	180.	182.	184.	188.	192.	194.

Parameter	Cycle 16	Cycle 17	Cycle 18	Cycle 19	Cycle 20	Cycle 21	Cycle 22	Cycle 23	Cycle 24	Cycle 25	Cycle 26	Cycle 27	Cycle 28	Cycle 29
Ag ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Al mg/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
As ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
B ug/l	<0.10	<0.10	<0.10	<0.10	<0.10								<0.10	<0.10
Ba ug/l	0.026	0.022	0.013	0.011	0.023								0.096	0.066
Be ug/l	<0.005	<0.005	<0.005	<0.005	<0.005								<0.005	<0.005
Bi ug/l	<0.10	<0.10	<0.10	<0.10	<0.10								<0.10	<0.10
Ca mg/l	11.8	10.8	4.76	3.15	14.3								45.3	50.7
Cd ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.010	<0.010
Co ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Cr ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Cu ug/l	0.017	0.015	0.012	0.015	0.016								0.036	0.034
Fe mg/l	<0.030	<0.030	<0.030	<0.030	<0.030								<0.030	<0.030
K mg/l	<2.0	<2.0	<2.0	<2.0	<2.0								<2.0	<2.0
Li ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Mg mg/l	2.05	1.75	0.749	0.456	1.48								6.05	7.52
Mn mg/l	0.032	0.029	0.013	0.012	0.035								0.083	0.089
Mo ug/l	<0.030	<0.030	<0.030	<0.030	<0.030								<0.030	<0.030
Na mg/l	<2.0	<2.0	<2.0	<2.0	<2.0								<2.0	<2.0
Ni ug/l	<0.020	<0.020	<0.020	<0.020	<0.020								<0.020	<0.020
P ug/l	<0.30	<0.30	<0.30	<0.30	<0.30								<0.30	<0.30
Pb ug/l	<0.050	<0.050	<0.050	<0.050	<0.050								<0.050	<0.050
Sb ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
Se ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
Si mg/l	0.541	0.547	0.275	0.169	0.346								0.614	0.679
Sn ug/l	<0.30	<0.30	<0.30	<0.30	<0.30								<0.30	<0.30
Sr ug/l	0.131	0.108	0.047	0.03	0.112								0.393	0.427
Ti ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.010	<0.010
V ug/l	<0.030	<0.030	<0.030	<0.030	<0.030								<0.030	<0.030
Zn ug/l	0.02	0.02	0.016	0.015	0.041								0.078	0.058
pH	7.52	7.64	7.27	6.87	6.66								7.49	7.41
Redox (mV)	309.	290.	301.	297.	290.								320.	307.
Conductivity (uS/cm)	95.	80.	37.	26.	104.								309.	335.
Alkalinity (mg $CaCO_3$/l)	15.	15.	8.	5.	8.								14.	15.
Acidity (pH 4.5)	0.	0.	0.	0.	0.								0.	0.
Acidity (pH 8.3)	3.	6.	2.	4.	4.								6.9	8.9
Cum Acidity (pH 8.3)	1.1	1.3	1.4	1.6	1.8								2.1	2.5
Sulphate (mg/l)	19.	14.	7.	6.	28.								118.	124.
Cum Sulphate (mg/kg)	22.9	23.5	23.8	24.1	25.3								30.2	35.5
Water added (L)	0.2	0.2	0.2	0.2	0.2								0.2	0.2
pH of water added	5.92	5.57	5.66	6.09	5.23								5.93	5.7
Leachate collected (L)	0.177	0.205	0.194	0.219	0.197								0.188	0.198
Cumulative Iron	0.29	0.29	0.29	0.29	0.29								0.29	0.29
Cumulative Copper	194.	194.	194.	194.	194.								194.	194.

Laboratory Equipment Failure
Weeks 21-27
No Samples Collected

Sample SW-1 - Kinetic Test Data

Parameter	Cycle 1	Cycle 2	Cycle 3	Cycle 4	Cycle 5	Cycle 6	Cycle 7	Cycle 8	Cycle 9	Cycle 10	Cycle 11	Cycle 12	Cycle 13	Cycle 14	Cycle 15
Ag ug/l	2.	4.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Al mg/l	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
As ug/l	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
B ug/l	20.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
Ba ug/l	50.	30.	20.	20.	10.	10.	20.	25.	25.	15.	20.	25.	15.	20.	15.
Be ug/l	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Bi ug/l	6.	6.	2.	2.	2.	2.	2.	2.	2.	2.	8.	2.	2.	2.	2.
Ca mg/l	53.15	45.51	34.83	36.28	31.01	23.67	23.36	24.87	30.06	23.22	23.31	30.56	20.57	22.22	17.45
Cd ug/l	2.	2.	1.	1.	1.	1.	7.	1.	1.	1.	4.	5.	1.	1.	5.
Co ug/l	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
Cr ug/l	15.	15.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
Cu ug/l	26.	16.	10.	12.	6.	2.	2.	2.	6.	2.	2.	2.	2.	2.	2.
Fe mg/l	0.08	0.08	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
K mg/l	2.98	2.71	2.19	2.94	2.35	1.69	1.41	1.07	2.17	0.15	1.7	2.14	1.98	1.47	1.28
Li ug/l	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
Mg mg/l	4.46	3.72	2.5	2.78	2.19	1.24	1.38	1.49	2.02	1.32	1.42	2.38	1.26	1.37	1.02
Mn mg/l	0.04	0.015	0.01	0.015	0.01	0.005	0.005	0.005	0.015	0.005	0.005	0.005	0.005	0.005	0.005
Mo ug/l	102.	84.	50.	62.	44.	26.	22.	32.	32.	14.	32.	32.	10.	26.	20.
Na mg/l	1.57	1.17	0.82	1.01	0.79	0.28	0.47	0.43	0.66	0.36	0.43	0.7	0.41	0.52	0.34
Ni ug/l	10.	10.	5.	10.	5.	5.	5.	5.	5.	5.	5.	15.	5.	5.	5.
P ug/l	120.	140.	40.	150.	100.	90.	180.	140.	130.	100.	140.	180.	50.	140.	80.
Pb ug/l	4.	8.	2.	2.	2.	2.	2.	2.	2.	2.	6.	2.	4.	2.	12.
Sb ug/l	14.	20.	2.	2.	2.	2.	2.	2.	2.	2.	6.	2.	2.	60.	2.
Se ug/l	210.	155.	65.	110.	25.	5.	80.	45.	80.	40.	70.	85.	20.	2.06	35.
Si mg/l	3.69	3.95	3.56	4.88	4.05	1.99	2.6	1.99	3.74	2.51	2.31	2.82	1.93	2.	1.98
Sn ug/l	300.	376.	2.	2.	2.	2.	80.	2.	44.	12.	2.	8.	50.	60.	2.
Sr ug/l	194.	166.	104.	110.	82.	56.	62.	68.	88.	56.	60.	78.	48.	2.	38.
Ti ug/l	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.
V ug/l	5.	6.	1.	1.	1.	1.	1.	1.	1.	1.	2.	1.	1.	1.	1.
Zn ug/l	27.	9.	7.	7.	4.	8.	4.	9.	1.	1.	7.	3.	11.	1.	4.
pH	7.65	7.73	7.87	7.91	8.04	7.65	7.69	7.66	8.	7.78	7.85	7.75	7.62	7.74	7.54
Redox (mV)	287.	265.	280.	305.	296.	302.	320.	317.	309.	260.	251.	241.	233.	233.	278.
Conductivity (uS/cm)	266.	231.	167.	174.	144.	95.	92.	105.	125.	84.	94.	138.	78.	84.	65.
Alkalinity (mg $CaCO_3$/l)	34.	29.	27.	37.	35.	21.	23.	18.	34.	26.	26.	26.	20.	22.	14.
Acidity (pH 4.5)	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
Acidity (pH 8.3)	0.5	2.	1.	2.	1.	0.5	2.	1.	1.	1.	1.	2.	2.	2.	4.
Cum Acidity (pH 8.3)	0.	0.1	0.2	0.2	0.2	0.2	0.3	0.3	0.4	0.4	0.5	0.6	0.6	0.7	0.9
Sulphate (mg/l)	77.	60.	32.	30.	24.	12.	11.	20.	14.	8.	11.	25.	8.	9.	6.
Cum Sulphate (mg/kg)	3.9	6.7	8.2	8.2	8.2	8.8	9.3	10.3	10.7	11.1	11.6	12.9	13.2	13.6	13.9
Water added (L)	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2
pH of water added	5.45	6.26	5.98	5.59	6.15	6.03	5.83	5.98	6.15	6.05	5.96	6.04	6.06	6.56	6.23
Leachate collected (L)	0.166	0.207	0.157	0.128	0.181	0.168	0.188	0.194	0.162	0.209	0.198	0.206	0.179	0.186	0.206
Cumulative Iron	0.08	0.16	0.17	0.18	0.19	0.2	0.21	0.22	0.23	0.24	0.25	0.26	0.27	0.28	0.29
Cumulative Copper	26.	42.	52.	64.	70.	72.	74.	76.	82.	84.	86.	88.	90.	92.	94.

Sample SW-1 - Kinetic Test Data

Parameter	Cycle 16	Cycle 17	Cycle 18	Cycle 19	Cycle 20	Cycle 21	Cycle 22	Cycle 23	Cycle 24	Cycle 25	Cycle 26	Cycle 27	Cycle 28	Cycle 29
Ag ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Al mg/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
As ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
B ug/l	<0.10	<0.10	<0.10	<0.10	<0.10								<0.10	<0.10
Ba ug/l	0.018	0.014	<0.010	0.012	0.013								0.021	0.021
Be ug/l	<0.005	<0.005	<0.005	<0.005	<0.005								<0.005	<0.005
Bi ug/l	<0.10	<0.10	<0.10	<0.10	<0.10								<0.10	<0.10
Ca mg/l	10.9	8.36	6.44	7.72	4.2								7.65	7.26
Cd ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.010	<0.010
Co ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Cr ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Cu ug/l	0.011	<0.010	<0.010	0.01	<0.010								0.011	0.012
Fe mg/l	<0.030	<0.031	<0.032	<0.033	<0.034								<0.035	<0.036
K mg/l	<2.0	<2.1	<2.2	<2.3	<2.4								<2.5	<2.6
Li ug/l	<0.015	<0.016	<0.017	<0.018	<0.019								<0.020	<0.021
Mg mg/l	1.14	0.766	0.636	0.782	0.414								0.851	0.775
Mn mg/l	<0.005	<0.005	0.005	0.006	0.007								0.022	0.013
Mo ug/l	<0.030	<0.031	<0.032	<0.033	<0.034								<0.035	<0.036
Na mg/l	<2.0	<2.1	<2.2	<2.3	<2.4								<2.5	<2.6
Ni ug/l	<0.020	<0.020	<0.020	<0.020	<0.020								<0.020	<0.020
P ug/l	<0.30	<0.30	<0.30	<0.30	<0.30								<0.30	<0.30
Pb ug/l	<0.050	<0.050	<0.050	<0.050	<0.050								<0.050	<0.050
Sb ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
Se ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
Si mg/l	1.99	1.33	1.25	1.38	0.705								0.581	0.928
Sn ug/l	<0.30	<0.31	<0.32	<0.33	<0.34								<0.35	<0.36
Sr ug/l	0.055	0.044	0.034	0.039	0.026								0.037	0.035
Ti ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.010	<0.010
V ug/l	<0.030	<0.030	<0.030	<0.030	<0.030								<0.030	<0.030
Zn ug/l	0.006	0.005	0.007	0.008	0.011								0.026	0.014
pH	7.79	7.64	7.55	7.44	6.54								7.2	7.32
Redox (mV)	261.	280.	283.	274.	260.								298.	277.
Conductivity (uS/cm)	73.	53.	40.	51.	27.								55.	49.
Alkalinity (mg $CaCO_3$/l)	13.	13.	16.	15.	9.								4.	4.
Acidity (pH 4.5)	0.													
Acidity (pH 8.3)	3.	3.	5.	5.	5.								10.9	11.9
Cum Acidity (pH 8.3)	1.	1.2	1.4	1.6	1.9								2.3	3.
Sulphate (mg/l)	5.	4.	4.	6.	4.								11.	6.
Cum Sulphate (mg/kg)	14.1	14.3	14.5	14.7	14.9								15.4	15.7
Water added (L)	0.2	0.2	0.2	0.2	0.2								0.2	0.2
pH of water added	5.92	5.57	5.66	6.09	5.23								5.93	5.7
Leachate collected (L)	0.171	0.178	0.188	0.177	0.211								0.175	0.22
Cumulative Iron	0.29	0.29	0.29	0.29	0.29								0.29	0.29
Cumulative Copper	94.	94.	94.	94.	94.								94.	94.

Laboratory Equipment Failure
Weeks 21-27
No Samples Collected

Sample PW-2 - Kinetic Test Data

Parameter	Cycle 1	Cycle 2	Cycle 3	Cycle 4	Cycle 5	Cycle 6	Cycle 7	Cycle 8	Cycle 9	Cycle 10	Cycle 11	Cycle 12	Cycle 13	Cycle 14	Cycle 15
Ag ug/l	36.	3.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Al mg/l	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
As ug/l	30.	20.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
B ug/l	10.	20.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
Ba ug/l	110.	75.	25.	45.	15.	60.	25.	25.	25.	30.	35.	60.	30.	35.	35.
Be ug/l	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Bi ug/l	26.	42.	2.	2.	2.	2.	2.	2.	2.	2.	8.	8.	2.	2.	16.
Ca mg/l	30.55	33.63	9.45	11.3	3.49	12.99	4.86	4.17	3.87	4.01	5.17	5.19	4.91	4.48	7.33
Cd ug/l	26.	25.	12.	1.	1.	8.	7.	7.	1.	1.	4.	1.	4.	1.	1.
Co ug/l	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
Cr ug/l	5.	10.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
Cu ug/l	302.2	280.	67.4	63.4	23.6	83.8	31.4	28.	42.4	43.6	62.6	81.8	59.8	69.	102.2
Fe mg/l	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
K mg/l	5.11	5.88	1.53	2.22	0.3	2.22	0.58	0.62	0.01	0.4	1.42	1.26	1.61	1.46	1.51
Li ug/l	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
Mg mg/l	1.6	2.03	0.44	0.52	0.11	0.58	0.18	0.15	0.13	0.13	0.27	0.26	0.19	0.22	0.37
Mn mg/l	0.1	0.145	0.045	0.055	0.02	0.07	0.03	0.02	0.025	0.03	0.035	0.04	0.035	0.035	0.065
Mo ug/l	24.	14.	8.	10.	2.	6.	2.	2.	2.	2.	6.	4.	2.	4.	6.
Na mg/l	1.29	1.64	0.38	0.55	0.06	0.56	0.18	0.16	0.12	0.13	0.23	0.2	0.2	0.39	0.33
Ni ug/l	5.	10.	5.	5.	5.	5.	5.	5.	5.	5.	5.	10.	5.	5.	5.
P ug/l	70.	80.	10.	10.	30.	30.	20.	30.	10.	10.	40.	10.	10.	10.	70.
Pb ug/l	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	28.	8.	2.	2.	2.
Sb ug/l	2.	16.	2.	2.	2.	2.	2.	2.	2.	2.	8.	2.	2.	2.	2.
Se ug/l	120.	125.	5.	5.	5.	5.	5.	5.	25.	10.	45.	5.	5.	10.	5.
Si mg/l	7.32	9.68	2.54	4.08	1.	4.73	1.54	1.42	1.4	1.46	1.76	1.79	1.28	1.41	1.71
Sn ug/l	2.	328.	88.	2.	2.	2.	2.	2.	58.	50.	2.	2.	34.	12.	2.
Sr ug/l	98.	114.	18.	20.	2.	30.	8.	10.	8.	6.	14.	12.	8.	10.	14.
Ti ug/l	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.
V ug/l	1.	3.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
Zn ug/l	473.	492.	114.	126.	43.	176.	58.	51.	3.	1.	66.	96.	68.	64.	145.
pH	6.52	5.87	5.99	5.9	6.42	6.1	6.03	6.26	6.43	6.31	6.14	6.1	6.14	6.13	5.95
Redox (mV)	367.	332.	306.	321.	281.	335.	310.	316.	362.	297.	315.	307.	312.	315.	352.
Conductivity (uS/cm)	169.	193.	51.	57.	19.	63.	23.	17.	20.	21.	28.	29.	25.	27.	39.
Alkalinity (mg $CaCO_3$/l)	7.	3.	2.	3.	3.	2.	3.	2.	3.	3.	2.	2.	2.	2.	3.
Acidity (pH 4.5)	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
Acidity (pH 8.3)	8.	9.	4.	4.	3.	3.	2.	2.	2.	2.9	2.9	2.9	3.	3.	4.
Cum Acidity (pH 8.3)	0.4	0.9	1.	1.2	1.3	1.5	1.6	1.7	1.7	1.9	2.1	2.2	2.4	2.5	2.7
Sulphate (mg/l)	59.	66.	13.	15.	7.	15.	6.	5.	5.	5.	7.	7.	4.	6.	10.
Cum Sulphate (mg/kg)	2.6	6.3	6.9	7.4	7.7	8.4	8.7	9.	9.2	9.5	9.9	10.3	10.4	10.7	11.3
Water added (L)	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2
pH of water added	5.45	6.26	5.98	5.59	6.15	6.03	5.83	5.98	6.15	6.05	5.96	6.04	6.06	6.56	6.23
Leachate collected (L)	0.166	0.207	0.157	0.128	0.181	0.168	0.188	0.194	0.162	0.209	0.198	0.206	0.179	0.186	0.206
Cumulative Iron	0.01	0.02	0.03	0.04	0.05	0.06	0.07	0.08	0.09	0.1	0.11	0.12	0.13	0.14	0.15
Cumulative Copper	302.2	582.2	649.6	713.	736.6	820.4	851.8	879.8	922.2	965.8	1,028.4	1,110.2	1,170.	1,239.	1,341.2

Sample PW-2 - Kinetic Test Data

Parameter	Cycle 16	Cycle 17	Cycle 18	Cycle 19	Cycle 20	Cycle 21	Cycle 22	Cycle 23	Cycle 24	Cycle 25	Cycle 26	Cycle 27	Cycle 28	Cycle 29
Ag ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Al mg/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
As ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
B ug/l	<0.10	<0.10	<0.10	<0.10	<0.10								<0.10	<0.10
Ba ug/l	0.014	0.015	0.011	0.012	0.015								0.025	0.035
Be ug/l	<0.005	<0.005	<0.005	<0.005	<0.005								<0.005	<0.005
Bi ug/l	<0.10	<0.10	<0.10	<0.10	<0.10								<0.10	<0.10
Ca mg/l	1.06	1.09	0.51	0.548	0.761								1.02	2.02
Cd ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.010	<0.010
Co ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Cr ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Cu ug/l	28.1	24.4	16.5	16.4	17.								22.	32.
Fe mg/l	<0.030	<0.030	<0.030	<0.030	<0.030								<0.030	<0.030
K mg/l	<2.0	<2.0	<2.0	<2.0	<2.0								<2.0	<2.0
Li ug/l	<0.015	<0.015	<0.015	<0.015	<0.015								<0.015	<0.015
Mg mg/l	0.097	0.101	0.054	<0.050	0.093								0.086	0.188
Mn mg/l	0.02	0.021	0.013	0.017	0.019								0.03	0.044
Mo ug/l	<0.030	<0.030	<0.030	<0.030	<0.030								<0.030	<0.030
Na mg/l	<2.0	<2.0	<2.0	<2.0	<2.0								<2.0	<2.0
Ni ug/l	<0.020	<0.020	<0.020	<0.020	<0.020								<0.020	<0.020
P ug/l	<0.30	<0.30	<0.30	<0.30	<0.30								<0.30	<0.30
Pb ug/l	<0.050	<0.050	<0.050	<0.050	<0.050								<0.050	<0.050
Sb ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
Se ug/l	<0.20	<0.20	<0.20	<0.20	<0.20								<0.20	<0.20
Si mg/l	0.685	0.991	0.377	0.458	0.567								0.364	0.686
Sn ug/l	<0.30	<0.30	<0.30	<0.30	<0.30								<0.30	<0.30
Sr ug/l	0.008	0.009	0.008	<0.001	0.011								0.007	0.013
Tl ug/l	<0.010	<0.010	<0.010	<0.010	<0.010								<0.010	<0.010
V ug/l	<0.030	<0.030	<0.030	<0.030	<0.030								<0.030	<0.030
Zn ug/l	0.038	0.04	0.023	0.027	0.04								0.058	0.077
pH	6.23	6.4	6.17	6.19	5.35								6.31	6.03
Redox (mV)	327.	326.	316.	308.	294.								340.	332.
Conductivity (uS/cm)	32.	12.	6.	6.	8.								11.	19.
Alkalinity (mg $CaCO_3$/l)	3.	3.	3.	2.	1.								2.	2.
Acidity (pH 4.5)	0.	0.	0.	0.	0.								0.	0.
Acidity (pH 8.3)	2.	2.	3.	4.	6.								11.9	11.9
Cum Acidity (pH 8.3)	2.9	3.	3.1	3.3	3.7								4.3	5.
Sulphate (mg/l)	3.	3.	3.	4.	4.								3.	4.
Cum Sulphate (mg/kg)	11.5	11.6	11.8	12.	12.2								12.4	12.6
Water added (L)	0.2	0.2	0.2	0.2	0.2								0.2	0.2
pH of water added	5.92	5.57	5.66	6.09	5.23								5.93	5.7
Leachate collected (L)	0.171	0.178	0.188	0.177	0.211								0.175	0.22
Cumulative Iron	0.15	0.15	0.15	0.15	0.15								0.15	0.15
Cumulative Copper	1,369.3	1,393.7	1,410.2	1,426.6	1,443.6								1,465.6	1,497.6

Laboratory Equipment Failure
Weeks 21-27
No Samples Collected

Appendix B

Tailings Characterization

TABLE OF CONTENTS

1.0 TESTING PROGRAM 2

2.0 CHARACTERISTICS AND BEHAVIOR OF FUTURE TAILINGS 3

LIST OF TABLES

Table 1.1 Tailings Geochemical Analysis 1994 and 1996 Samples
Table 1.2 Total and Extractable Metals Concentrations

APPENDIX B

GEOCHEMICAL CHARACTERIZATION OF TAILINGS

1.0 TESTING PROGRAM

Tailings from previous mining operations at the Copper Flat project were sampled on two occasions. In conjunction with piezometer installation, two tailings samples were recovered with a split spoon sample in 1994 (T-10-12 and T-5-7). In 1996, five test pits were excavated in the existing impoundment and an additional 11 samples were obtained.

Tailings samples were analyzed for paste pH and conductivity values, and by Acid Base Accounting tests. Results are listed in Table 1.1. The tailings collected in 1996 are grouped according to their appearance in hand specimen. Yellow tailings are assumed to be derived from oxidized or transition materials and are given the label TTLS (transition tailings) while fresh gray tailings that are assumed to have been derived from unoxidized quartz monzonite are labeled UTLS (unoxidized tailings). Black tailings (BTLS) are assumed to be derived from biotite breccia.

The tailings samples are not currently generating acid. Paste pH values for all samples were all above 6.1. Paste conductivity was low and ranged from 298 to 686 μS/cm. On the basis of the paste results, the current reactivity of the existing tailings is low.

Based on ABA results, sulfide sulfur contents averaged 0.72 for the transition tailings and 0.95 for the unoxidized tailings collected in 1996. Based on sulfide sulfur content, five of the samples had NP:AP ratios below 1, indicating that these samples have moderate potential to produce acidity. All other samples show a weak acid producing potential.

The decrease in acid generating potential relative to waste rock samples (i.e. higher NP:AP ratios) is likely a result of sulfide removal during the concentration process. The tailings show no increase in neutralization potential relative to the waste rock samples, indicating that lime added during processing has little impact on the chemistry of the tailings.

Sample T-10-12 was analyzed for total metals concentrations using the EPA 3051 digestion and analysis by ICP. Results, listed in Table 1.2, indicate the sample had

high concentrations of aluminum (2,700 ppm), copper (1,600 ppm), iron (19,000), magnesium (1,800 ppm), potassium (1.400 ppm), and zinc (418 ppm). However, results of a modified EPA method 1312 leach indicated that these metals are not easily leached. These results confirm the limited oxidation that has occurred in the tailings, as indicated by the low paste conductivity. Therefore, the color of the tailings exhibited in drill hole and test pit samples is believed to be a result of the source of the materials. The designation of "transition" or "unoxidized" refers only to the nature of the ore from which the tailings were produced.

2.0 CHARACTERISTICS AND BEHAVIOR OF FUTURE TAILINGS

The majority of future ore will be unoxidized quartz monzonite, biotite breccia, and quartz breccia. Future tailings are anticipated to have geochemical properties similar to the UTLS tailings samples shown in Table 1.1. While a potential for acid generation is indicated, no evidence of acid generation was observed following 14 years of weathering under field conditions. Future tailings are anticipated to be equally slow in generating acid and releasing metals.

Table B.1.1
Tailings Geochemical Analysis - 1994 and 1996 Samples

Sample ID	pH (S.U.)	Paste Conductivity (µS/cm)	Sulfur				Neutralization Potential (T/KT)	AP (sulfide) (T/KT)	NNP (sulfide) (T/KT)	NP/AP (sulfide)	AP (pyrite) (T/KT)	NNP (pyrite) (T/KT)	NP/AP (pyrite)
			Total (%)	Sulfate (%)	Sulfide (%)	Pyrite (%)							
Transition Tailings													
P1-TTLS	6.6	466	1.12	0.47	0.65	0.58	36.00	20.31	15.69	1.77	18.13	17.88	1.99
P2-TTLS	7.1	483											
P3-TTLS	7.3	628	1.16	0.52	0.64	0.31	17.00	20.00	-3.00	0.85	9.69	7.31	1.75
P4-TTLS	7.3	651	1.31	0.45	0.86	0.54	27.00	26.88	0.12	1.00	16.88	10.13	1.60
P5-TTLS	7.5	547											
Mean	7.2	555	1.20	0.48	0.72	0.48	26.67	22.40	4.27	1.21	14.90	11.77	1.78
Unoxidized Tailings													
P1-TLS@12"	6.2	486	0.79	0.13	0.66	0.45	26.00	20.63	5.38	1.26	14.06	11.94	1.85
P1-UTLS	6.8	686	1.3	0.25	1.05	0.8	25.00	32.81	-7.81	0.76	18.75	6.25	1.33
P2-UTLS	7.7	643	1.15	0.19	0.96	0.75	25.00	30.00	-5.00	0.83	23.44	1.56	1.07
P3-UTLS	7.6	352											
P4-UTLS	7.2	357											
P5-UTLS	7.6	455	1.19	0.08	1.11	0.72	31.00	34.69	-3.69	0.89	22.50	8.50	1.38
Mean	7.2	497	1.11	0.16	0.95	0.63	26.75	29.53	-2.78	0.94	19.69	7.06	1.41
Black Tailings													
P5-BTLS	7.8	298	0.92	0.27	0.65	0.3	35.00	20.31	14.69	1.72	9.38	25.63	3.73
1994 Tailings Samples													
T-10-12	7.8		1.26	0.03	1.23	0.68	24	38.44	-14.44	0.62	21.25	2.75	1.13
T-5-7	7.5		1.1	0.18	0.92	0.53	31	28.75	2.25	1.08	16.56	14.44	1.87
Mean	7.7		1.18	0.11	1.08	0.61	27.50	33.59	-6.09	0.85	18.91	8.59	1.50

Notes:
Sulfide sulfur equals total sulfur minus sulfate sulfur
NNP equals net neutralization potential (NP-AP)

Table B.1.2
Total and Extractable Metals Concentrations in Tailings

Parameters	Total Metals in Solids ICP ppm	Extractable Metals EPA 1312 (mg/L)
Aluminum	2700	< 0.05
Antimony	< 0.5	N/A
Arsenic	1.3	< 0.1
Barium	52	0.10
Boron	< 2	0.07
Cadmium	1.8	< 0.005
Calcium	8500	300
Chloride	N/A	6
Chromium	5	< 0.01
Cobalt	13	< 0.02
Copper	1600	0.03
Fluoride	N/A	1.4
Iron	19000	< 0.02
Lead	15	< 0.021
Magnesium	1800	22
Manganese	251	1.50
Mercury	< 0.02	< 0.0002
Molybdenum	34	0.19
Nickel	3	< 0.02
Potassium	1400	44
Selenium	< 0.03	< 0.1
Silver	< 1	< 0.01
Sodium	200	44
Sulfate	N/A	940
Vanadium	7	< 0.01
Zinc	418	0.42

Appendix C

Field Scale Reclamation Cover Test Program

STEFFEN, ROBERTSON AND KIRSTEN
Consulting Engineers and Scientists

Suite 3000
7175 W. Jefferson Ave.
Lakewood, CO
USA 80235
E-mail: denver@srk.com
URL: http://www.srk.com/
Tel: (303) 985-1333
Fax: (303) 985-9947

MEMORANDUM

TO: Jeff Parshley, SRK - Reno

FROM: Pete Kowalewski, SRK - Denver

DATE: April 27, 1998

SUBJECT: **Copper Flat Closure Field Testing Program**

PROJ/PROP NO. **68606**

1.0 INTRODUCTION

In accordance with Item 23 of the Conditions for Approval of DP-001, Alta Gold Corporation (Alta) will conduct long term field testing of alternative soil covers to aid in the selection of cover designs for the tailings impoundment and waste rock dumps at the Copper Flat site. In addition to aiding in the selection of the most appropriate soil cover for the tailings and waste rock at the Copper Flat site, the field testing will provide for evaluation of several other issues at the Copper Flat site, including: acid generation potential, phytotoxicity and ecological risk, and the ability to successfully revegetate the alternative soil covers. The following is a conceptual plan detailing the proposed field testing to be performed after the commencement of operations at the site.

2.0 FIELD COVER TESTING

2.1 Test Cell Composition

The field testing will consist of a series of constructed test plots. Alternative covers will be tested over both tailings and, potentially, three different types of waste rock (unoxidized, transitional, and low sulfide), as cover performance and revegetative success may be influenced by the underlying waste material being covered (i.e. fine-grained tailings versus coarse-grained waste rock). Table 1 presents a matrix of all of the combinations of alternative soil covers and underlying waste materials that will be tested in the program.

Table 1. Matrix of Soil Cover and Underlying Waste Materials for Field Testing Program

Soil Cover	Underlying Waste Type			
	Tailings	Unoxidized Waste	Transitional Waste	Low Sulfide Waste
Control (No Cover)	x[2]	x[2]	x[3]	x[3]
12" Alluvium	x[2]	x[2]	x[3]	x[3]
24" Alluvium	x[2]	x[2]	x[3]	x[3]
24" Alluvium / Amended Tailings (Harrowed)[1]	x[2]	x[2]	x[3]	x[3]

Notes:
[1] Amendment of tailings may be achieved by blending lime, limestone, or a soil with high neutralizing potential, if necessary. Alluvium may provide some neutralizing potential for the tailings.
[2] Test cell will be monitored for surface water runoff, percolation, and moisture content
[3] Test cell will be monitored for surface water runoff and percolation only

As can be seen from Table 1, a total of 16 test cells are proposed for the field testing program. Eight of the 16 test plots will be instrumented to quantify runoff and percolation through the cover system only, while runoff, percolation, and moisture content will be measured in the remaining 8 test cells.

2.2 Test Plot Design

Figures 1 through 3 show conceptual plans for an individual test plot. Each test plot will have an area of approximately 300 square feet. Various covers will be placed over a minimum of 10 feet of tailings or waste rock. Both the bottom and surface of each cell will be graded to allow concentration of flow at central collection points on the cell floor and surface. A berm may be constructed on the surface of each plot to facilitate the concentration of surface flows. Grading of the floor of each cell will facilitate concentration of flow into a perforated pipe. Flows will be collected in pipes and routed to collection tanks for measurement of surface runoff and percolation, respectively.

2.3 Test Plot Instrumentation

The test plot will be instrumented to quantify surface runoff from the test plot, percolation occurring through the test plot, and moisture content within the soil profile. Surface runoff will be collected from the test plot and routed to a collection tank for measurement. Percolation occurring through the test plot will be routed to a collection tank as well, where it will be measured. The measurement of surface runoff will be performed after each rainfall at the site, while percolation measurement will be made at least once per week during the testing period. The frequency of recording both percolation and runoff measurement may be increased during wet periods.

Moisture content profiling of the test cells may be performed manually through the use of a nuclear moisture gauge or moisture probe, or in an automated fashion using moisture probes buried at various depths connected to a datalogger. Regardless of the method by which moisture profile data is collected,

data will be collected from a minimum of 5 pre-determined depths at least once a week for each test cell identified in Table 1 as requiring moisture profiling.

2.4 Weather Station Instrumentation

A weather station will be installed that is capable of measuring the following parameters: daily precipitation, maximum and minimum daily air temperature, daily maximum and minimum relative humidity, average daily wind speed, wind direction, and average daily incoming solar radiation. It is envisioned that data collection will be automated through the use of a datalogger to facilitate acquisition.

Daily evaporation will be measured through use of a National Weather Service Class A type evaporation pan. Measurements will be made by mine personnel.

2.5 Leachate Quality Testing

Leachate from the cover test plots will be analyzed to evaluate the geochemical behavior of the underlying materials. The first sample of leachate from each cell will be analyzed for pH, alkalinity/acidity, conductivity, sulfate, Eh, as well as a full range of dissolved metals, major cations and major anions. Thereafter, full chemical analyses will be repeated on an annual basis. During the course of testing, pH, alkalinity/acidity, and sulfate analyses will be performed at any point when there is sufficient leachate available for analysis. If leachate is consistently available (minimum volume of 1 liter), this sampling will be conducted quarterly.

2.6 Test Cell Bio-assay

Several tests will be required to assess the revegetative success of the test cells and the ecological risk posed by the uptake or fixation of heavy metals by roots and heavy metal accumulation in plant tissue. The testing proposed for this area of work includes: a random survey to assess live plant cover and total cover (live plant and litter), soil pH, total metals concentration of plant tissue and roots, soil organic matter content, total and plant available nitrogen, and soil fertility (includes analyses for phosphorous, magnesium, and potassium).

Testing of the plant matter and soil from the field test cells will be conducted once per year, preferably toward the end of the growing season. Samples will be taken from each test cell and send to a certified laboratory to perform the tests mentioned above. A visual survey of each test cell will be conducted toward the end of each growing season to assess the live plant cover and total cover available at each test cell.

2.7 Data Collection

All data collected manually will be recorded in a log book kept on site. Data gathered electronically will be downloaded from the recording device (or devices) and transferred to a diskette. Printed output of the electronic data (hard copies) will be kept in a file on site. Copies of the diskette may be archived for future reference.

3.0 ADDITIONAL TESTING FOR REVEGETATIVE SUCCESS

In addition to sampling the revegetated test cells, test plots will be established on the alluvium stockpiles to assess the ability to revegetate based on slope and aspect as well as seed mixture. The alluvium stockpile test plots will be tested in a manner consistent with the testing of the field test cells. At the commencement of the field testing, a soil sample will be taken from an adjacent area not impacted by mining, and a full suite of soil analyses will be conducted to determine the naturally occurring soil conditions.



NOTE:

1. CELL WILL NOT NECESSARILY BE CIRCULAR IN PLAN; CELL MAY BE SQUARE OR RECTANGLE, WITH MINIMUM SIDE LENGTH TO DEPTH RATIO OF 2:1.

SRK
STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

PROJECT NO.	DATE	REVISION
68606	01/98	A

FIGURE 1

TEST CELL CONCEPTUAL DESIGN
PLAN VIEW

* STA.#2 * J:\0686\68606\FIG01.DWG * NOV 23, 1998 * 3:19:51 PM *



STEFFEN ROBERTSON & KIRSTEN (U.S.) Consulting Engineers & Scientists		
PROJECT NO. 68606	DATE 01/98	REVISION A

FIGURE 2

TEST CELL CONCEPTUAL DESIGN
SECTION A–A'



STEFFEN ROBERTSON & KIRSTEN (U.S.)
Consulting Engineers & Scientists

PROJECT NO.	DATE	REVISION
68606	01/98	A

FIGURE 3

TEST CELL CONCEPTUAL DESIGN
SECTION B–B'

APPENDIX D

Tailings Impoundment

Conceptual Design Report (Golder, 2010)

Borrow Sources and Stockpile Evaluations

REPORT

COPPER FLAT PROJECT

Conceptual Design Report

Submitted To: New Mexico Copper Corporation
Suite 100 - 2425 San Pedro Dr. NE
Albuquerque, NM 87110

Submitted By: Golder Associates Inc.
4730 N. Oracle Road
Suite 210
Tucson, AZ, 85705 USA

Distribution:
1 Electronic Copy – New Mexico Copper Corporation
1 Copy – Golder Associates

November 17, 2010 **103-92557**

A world of capabilities delivered locally

Golder Associates

02062

EXECUTIVE SUMMARY

Copper Flat is a porphyry copper mine that was briefly operated by Quintana Minerals Corp. (Quintana) in 1981 and 1982. After approximately 1 year of operation, mining was halted due to depressed copper prices, and the facility was decommissioned. New Mexico Copper Corporation (NMCC) has acquired an option on the Copper Flat property and is evaluating resuming mining and milling operations. Based on a recent NI 43-101 compliant preliminary economic assessment (PEA, [SRK, 2010]), the ore reserve has been increased from the 60 million tons identified by Quintana, to approximately 100 million tons. Ore will be mined at a rate of 17,500 tons per day (tpd). This report presents the conceptual design of a tailings storage facility (TSF) capable of supporting tailings disposal for the currently identified ore reserve.

During the 1981-82 operating period, high concentrations of total dissolved solids and sulfate were detected in groundwater immediately downgradient from the existing Quintana TSF. Local seepage of contaminated groundwater, which has been attributed to the existence of permeable geologic units in the TSF foundation, allowed process water and tailings seepage to migrate from the impoundment. Existing tailings are now drained and lie above the local groundwater table, however, leaching by meteoric water potentially contributes additional sulfate and dissolved solids to groundwater. Impacted groundwater and tailings from the 1981-82 operations are the subject of ongoing abatement actions. Groundwater compliance issues associated with the Quintana operation have led NMCC to propose construction of a lined TSF for future operations.

The starter dam from the earlier operations remains in place, however, in order to provide the required increase in storage capacity, while limiting future dam height and maintaining gravity delivery of tailings, the facility will be expanded approximately 1,000 feet to the east. It is assumed that the existing starter dam will be used as a borrow source for new embankment construction.

Approximately 1.2 million tons of tailings were placed in the north disposal cell prior to the suspension of operations in 1982. It is assumed that future TSF construction will require the incorporation of measures to mitigate potential groundwater impacts from existing tailings in order to meet groundwater contamination abatement actions. Several options for the management of existing tailings have been considered at a preliminary level. These include:

- Capping existing tailings in-place beneath a low permeability cover such as a geomembrane or composite cover;
- Utilize existing tailings as fine grained bedding fill for the future TSF geomembrane liner; and
- Place existing tailings inside the new TSF on top of the new geomembrane liner.

All options are considered to provide similar benefits relative to mitigating groundwater impacts associated with existing tailings.

The method of tailings embankment construction selected by Quintana was upstream raise construction with peripheral discharge of spigotted whole tailings. The proposed method of construction for the new TSF is by centerline raises with cycloned tailings sand. The tailings surface will rise approximately 80 feet in the first two years of operation. Centerline raising with cycloned sand was selected as the construction method because as a general rule, the tailings rate of rise should be less than 10 feet per year for upstream construction. NMCC's ability to develop a drained and consolidated foundation suitable for upstream raise construction using peripherally spigotted discharge of whole tailings is questionable due to the high rate of rise, which will not drop below 10 feet per year in the first 5 years of operation.

Initial construction will include a toe berm to buttress the tailings embankment and a starter dam for placement of the tailings header line and cyclones. Sand (cyclone underflow) will be placed on the embankment while the tailings slimes (cyclone overflow) will be discharged to the impoundment interior. The TSF geomembrane liner will be placed beneath the starter dam and anchored on the crest of the toe berm. An underdrain system consisting of a filter compatible soil and drainage collection pipes will be placed on top of the geomembrane liner, beneath the sand dam footprint, to facilitate drainage and consolidation of the cycloned sand. The underdrain system will extend into the impoundment interior in the area that will underlie the free water pond. Underdrainage will be routed to a lined underdrain collection pond located downstream of the toe berm.

The TSF can be constructed in a phased manner. During initial construction phases, diversion ditches can be constructed to divert stormwater from upstream catchment areas within the area contributory to the impoundment. The contributory area is approximately equivalent to the ultimate TSF footprint as only minor peripheral areas drain into the TSF. At final buildout, there is minimal potential for surface water runon from external areas. Throughout most of the life of the facility, stormwater management requirements will be limited to direct precipitation.

A review of available aerial photographs indicates no human habitations adjacent to the drainages below the proposed TSF. Based on the rules and regulations of the New Mexico State Engineer, the Copper Flat TSF would be classified as a large dam having significant hazard potential. The impoundment will be required to contain the equivalent of 75 percent of the probable maximum precipitation (PMP) during operations. A spillway capable of passing 75 percent of the PMP will be required upon closure.

Geotechnical investigation (SHB, 1980) of the existing TSF area was extensive, however, a portion of new TSF will occupy ground that has not been evaluated for geotechnical and hydrogeological conditions. A preliminary site investigation plan is presented in this conceptual design report.

Table of Contents

EXECUTIVE SUMMARY ES-1
1.0 INTRODUCTION 1
1.1 Scope of Work 1
1.2 Project History 1
2.0 SITE DESCRIPTION 2
2.1 Existing Conditions 2
2.2 TSF Area Geology and Foundation Conditions. 2
2.3 Climate 3
3.0 PROPOSED TAILINGS STORAGE FACILITY DESCRIPTION 4
3.1 TSF Geometry 4
3.2 Hazard Classification 5
3.3 Site Preparation 6
3.4 TSF Liner System 6
3.5 Underdrain System 7
3.6 Water Reclaim 7
3.7 Tailings Distribution 8
3.8 Surface Water, Underdrainage, Stormwater and Supernatant Management 8
3.8.1 Surface Water Diversion 8
3.8.2 Stormwater and Supernatant Management 9
4.0 CLOSURE AND RECLAMATION 10
5.0 DATA COLLECTION AND DESIGN STUDY REQUIREMENTS FOR ADVANCING TSF DESIGN 11
5.1 Geotechnical Investigation 11
5.1.1 Existing TSF Area 11
5.2 Tailings Characterization 11
5.3 Hydrogeological Characterization 12
5.4 Climatological Characterization 12
5.5 Engineering Studies 13
6.0 USE OF THIS REPORT 14
7.0 REFERENCES 15

List of Drawings

Drawing 1 Title Sheet
Drawing 2 General Site Layout
Drawing 3 Tailings Storage Facility Plan
Drawing 4 Tailings Storage Facility at Final Build-out
Drawing 5 Tailing Facility Storage Cross-Sections
Drawing 6 Tailings Storage Facility Underdrain Plan
Drawing 7 Tailings Storage Facility Details
Drawing 8 Height vs. Capacity Plot
Drawing 9 Tailings Storage Facility Conceptual Closure Plan

1.0 INTRODUCTION

1.1 Scope of Work

New Mexico Copper Corporation (NMCC) has acquired an option on the Copper Flat property, located near Hillsboro in Sierra County, New Mexico. Copper Flat is a porphyry copper deposit that was briefly mined by Quintana Resources in 1981 and 1982 before depressed copper prices forced the suspension of mining and milling operations. During the Quintana operation, the identified ore reserve was approximately 60 million tons. Further drilling completed since cessation of mining operations has increased the ore reserve from 60 million to approximately 100 million tons. NMCC has commissioned Golder Associates Inc. (Golder) to develop the conceptual design of a new tailings storage facility (TSF) capable of containing tailings from the expanded mining operation. Conceptual design of the new TSF, as well as plans for geotechnical investigation of the expanded TSF footprint and fulfilling data collection requirements necessary to advance the TSF design to feasibility and construction level are presented in this report.

1.2 Project History

The Quintana operation included open pit mining, conventional milling and off-site shipment of copper concentrate. Tailings were thickened to a solids content of 50 percent by weight (oral communication, Jack Bailey, 10/02/2010) and transported by gravity flow to the existing TSF located approximately 1 mile east of the open pit. Impoundment construction and operation were typical of the industry practices of the day. Whole tailings were discharged into the impoundment via a tailings header line and spigots placed peripheral to the impoundment. The TSF constructed for the Quintana operation remains in-place to this date. Remaining facilities include the starter embankment, internal splitter dikes, concrete decant towers and presumably, buried under drain pipes. Approximately 1.2 million tons of tailings were deposited in the existing north tailings cell.

The tailings thickener is reported to have been partially decommissioned and buried. The tailings delivery system has been removed. The Greyback Wash diversion, electrical supply lines, a water supply well field and water supply pipeline, groundwater monitoring wells and pumpback wells also remain. Milling and processing facilities were decommissioned and removed from the site.

During Quintana operations, elevated sulfate and dissolved solids were detected in groundwater in the vicinity of the existing tailings dam. Permeable foundation materials encountered during site investigation and construction of the TSF have been identified as the potential pathway for seepage from the TSF, Meteoric water leaching of tailings from the Quintana operation potentially contributes additional sulfate and dissolved solids to local groundwater. Impacted groundwater and the existing tailings are the subject of an ongoing abatement action. Management of existing tailings to mitigate existing and ongoing groundwater impacts is considered a parallel objective of TSF design.

2.0 SITE DESCRIPTION

2.1 Existing Conditions

The location of the proposed TSF is shown on Drawings 1 and 2. Elevation in the TSF basin area ranges from approximately 5,160 feet above mean sea level (amsl) near the base of the toe berm to over 5,500 feet on the ridges northwest of the impoundment footprint. Natural slopes range from 2 horizontal to 1 vertical (2H:1V) adjacent to the perimeter ridges to less than 10H:1V in the lower portion of the basin.

Previous disturbance of the TSF area is widespread. Existing features can be seen in the aerial photograph on Drawing 1. Drawing 2 shows the location of the proposed TSF projected on existing topography. Placer mining disturbance that predates the Quintana operation can be seen in most of the drainages in the TSF basin, and other drainages radiating from the mine area. More recent disturbance associated with the Quintana mining operation includes tailings deposits, the old starter dam and splitter dikes, construction material borrow areas and tailings delivery and reclaim water pipeline routes. Two concrete decant towers and concrete reclaim pipe foundations also remain in place and while not visible, buried reclaim water pipes also occur. A series of monitoring wells have been placed around the toe of the old starter dam.

The TSF site is located in the upper reaches of a shallow basin. The basin is bounded by low hills on the southwest, west and north sides such that the ultimate TSF will occupy most of the area that could contribute surface water runoff to the TSF. While diversions will be required in the early stages of the operation to divert stormwater runoff, peripheral areas contributing stormwater runon during the later stages of the future operations will be limited to a few acres on the northwest side of the TSF.

2.2 TSF Area Geology and Foundation Conditions.

The existing TSF site was extensively explored by Sargent, Hauskins and Beckwith (SHB) in 1979 and 1980 as part of the SHB design effort. No additional field work was conducted as part of conceptual design efforts. The upper layer of soils in the vicinity of the existing starter dam consists of sandy materials. Surficial sand is underlain by a wedge of silty clays, clayey and clayey silts that appears to thicken in a easterly direction. Gravels underlie the silts and clays and outcrop in the upper portion of the TSF basin. These gravels appear to have been the borrow source for the existing dam.

Permeable basalt was encountered in the lower portion of the tailings basin. The basalt is presumed to occupy a paleo-drainage cut in the local foundation soils. It can be seen in outcrop and subcrop south of the existing splitter dike and was intercepted in several exploratory boreholes completed in the central starter dam area. Due to its permeable nature, the basalt has been identified as the likely pathway for seepage and contaminants from the existing impoundment. This potential was identified during the design of the existing impoundment, and an attempt was made to cap the basalt with fine grained, low permeability soils to inhibit seepage.

2.3 Climate

The Copper Flat property experiences on the order of 10 to 13 inches per year of precipitation with the majority of rainfall occurring in the summer months associated with short duration, high intensity thunderstorms. Winter rains are associated with Pacific storms that generally migrate from west to east across the desert southwest. Summer temperatures exceed 100 degrees while winters are generally mild with limited snow and ground freezing.

In general, evaporation exceeds precipitation in desert lowlands across the region. It is anticipated that the tailings impoundment will be operated at net negative water balance, with periodic, temporary accumulation of stormwater from direct precipitation. Stormwater will be recovered with tailings supernatant water and reused in milling and processing. The effect of stormwater accumulation will be a reduction in raw make-up water requirements.

3.0 PROPOSED TAILINGS STORAGE FACILITY DESCRIPTION

3.1 TSF Geometry

The proposed method of tailings embankment construction is by the method of centerline raises. The basis for selection of this method is due to the high rate of tailings rise that will be experienced during the first 3 to 4 years of operation. Construction by upstream raises typically requires a rate of tailings rise of approximately 10 feet per year or less in order to allow consolidation and drainage of impounded tailings, and the development of conditions suitable for supporting upstream raises. The centerline method of construction using cycloned sand will allow the embankment to be constructed on a foundation of well drained sand.

A toe berm will be constructed around the periphery of the TSF which will serve as a buttress to the embankment outslopes. An internal starter dam is proposed for placement of the tailings discharge header pipe. Tailings will be delivered at a rate of 17,500 tpd at an anticipated solids content of 50 percent by weight. At 92 percent availability, the annual tailings deposition rate will be 5.88 million tons.

Cyclones on the tailings header line will be used to separate the sand fraction (cyclone underflow) from the whole tailings stream. Tailings sand will be used for embankment construction while the fine fraction of the tailings, the tailing slimes (cyclone overflow), will be discharged into the impoundment interior. The resulting tailings impoundment surface will slope away from the embankment and force tailings supernatant and stormwater into the interior of the impoundment. The locations of the toe berm and starter dam are shown on Drawing 3.

The crest elevation of the starter dam and toe berm have initially been set at 5,220 feet amsl. Adjustments to the height of these structures will be evaluated in detailed design studies. Starter dam height will be determined by the dry freeboard required to maintain stormwater storage capacity and the volume of sand that will be available for dam construction during operations. The availability of sand will be determined by the degree of ore milling. A finer grind will reduce sand content and could require a higher initial starter dam height while a coarser grind will provide more sand and allow an increased rate of sand deposition. Toe berm height will be influenced by the stability of the tailings embankment. The embankment sand and underdrain will be placed over a geomembrane liner. Interface friction at the liner/subgrade and the liner/underdrain interfaces will be reduced relative to the friction developed at a soil to tailings interface. The berm may be required to buttress the embankment toe to enhance stability. Toe berm and initial starter dam heights will be evaluated when tailings products representative of the future processing plan are available for evaluation and geotechnical testing.

Above the elevation of the initial starter dam and toe berm, these structures will be constructed parallel to existing topography with a constant height above foundation level. Progressive lateral extension of the tailings distribution points up the starter dam will enable the dam to be raised in level manner.

Tailings gradation data presented in the various reports prepared for Quintana are somewhat contradictory. Based on metallurgical pilot studies conducted for Quintana and reported by SHB (1980), the sand fraction (the plus 200 standard sieve fraction) of the tailings is approximately 30 percent with 95 percent finer than 65 mesh (208 microns). Measurements collected by Quintana mill personnel between May and June of 1982 (oral communication, Jack Bailey, 10/1/2010) showed a minus 65 mesh fraction of 84 to 89 percent, suggesting a courser tailings grind with a higher sand fraction was produced under operating conditions. The gradation presented in the SHB geohydrological study (SHB, 1981) indicates tailings that are 100 percent finer than 65 mesh with a sand fraction of 55 percent. Preliminary volumetric estimates indicate that embankment construction will require approximately 15 percent of future tailings, suggesting that the centerline approach is feasible. Evaluation of tailings samples produced in pilot or bench scale simulation of future milling and processing will be required to verify sand availability throughout the life of the operation.

The impoundment has been sized based on a post-deposition dry density of 85 pounds per cubic foot (pcf). The estimated maximum final tailings surface elevation is 5,375 feet amsl. The maximum toe to crest height of the tailings embankment will be approximately 215 feet. At final buildout, the TSF and underdrain collection pond will occupy an area of approximately 541 acres. The anticipated configuration of the TSF at the end of mining and milling operations is shown on Drawing 4. TSF cross sections are shown on Drawing 5.

The tailings surface will slope inward from peripheral points of deposition at approximately ½ to 1 percent forming a depression in the interior of the impoundment. The internal depression will serve as a storage area for supernatant solutions and stormwater.

Embankment outslopes shown on the drawings are 2.67H:1V. Outslopes may also be subject to modification based on geotechnical testing of tailings properties.

3.2 Hazard Classification

The rules and regulations of the New Mexico State Engineer indicate that the Copper Flat TSF will be classified as having significant hazard potential. According to the New Mexico Administrative Code (19.25.12.10 B NMAC):

> *Dams assigned the significant hazard potential classification are those dams where failure or misoperation results in no probable loss of human life but can cause economic loss, environmental damage, disruption of lifeline facilities, or can impact other concerns. Significant hazard potential classification dams are often located in predominantly rural or agricultural areas but could be located in populated areas with significant infrastructure.*

The TSF lies within the Greyback Wash drainage. Inspection of aerial photographs (Google Earth) indicates no human habitations in or adjacent to Greyback Wash between the TSF facility and Caballo Lake, into which Greyback Wash ultimately discharges. A dam breach and flood routing analysis will be required by the State Engineer (19.25.11.12 C (1) NMAC) to verify this classification.

The spillway design flood for dams with significant hazard potential (19.25.12.11 C(1) (c) is 75 percent of the probable maximum precipitation (PMP). A preliminary estimate of the PMP is on the order of 25 inches. The TSF and ore processing facilities will be operated as a closed, non-discharging system during tailings disposal operations and storage capacity for the design storm event will be maintained within the TSF. A permanent spillway capable of passing the design flood will be required at closure after the tailings surface has been regraded and a reclamation cover is in place.

3.3 Site Preparation

The TSF will be a geomembrane lined structure. Site preparation will include clear and grubbing, salvage and stockpiling of topsoil and grading to prepare a smooth surface for geomembrane liner installation.

It is anticipated that the existing starter dam and associated splitter dikes will be used as a fill material borrow source for the new toe berm and starter dam. Additional borrow areas for structural fill, liner bedding materials and drainage media will be developed within the TSF footprint where possible. Previous geotechnical investigation of the site indicates a range of fine grained soils and granular materials occur within the existing disturbance area.

Approximately 1.2 million tons of tailings were discharged into the existing TSF during the Quintana operation. Existing tailings deposits will be evaluated as a source of liner bedding fill material. If placed or “capped” under a low permeability TSF liner, the potential for leaching sulfate and dissolved solids from existing tailings in the future will be alleviated. Alternatively, existing tailings could be placed on the new TSF liner however, utilization of the tailings as liner bedding fill material is anticipated to be less costly and will provide similar benefits in terms of mitigating leaching potential.

The existing decant towers will be demolished. Demolition debris will be buried locally or placed in a waste rock disposal facility. Demolition requirements for buried decant pipelines will be evaluated as part of ongoing site investigation and design efforts.

Existing wells in the TSF expansion will require abandonment in accordance with New Mexico Environment Department (NMED) Office of the State Engineer (OSE) regulations. For wells that intercept groundwater, this will include removal of casings if possible, and sealing the entire well bore with cement or bentonite grout placed by tremmie pipe. Approximately 18 wells appear to lie within the TSF expansion area.

3.4 TSF Liner System

Proposed liner system details for the TSF and underdrain collection pond are shown on Drawings 6 and 7. The TSF liner will consist of an HDPE geomembrane placed on a minimum 6-inch thick layer of liner bedding fill. Beneath the starter dam and embankment underdrain, an 80 mil (0.080 inches) geomembrane is proposed while within the impoundment interior, the geomembrane thickness will be 60 mil. The underdrain collection pond liner will consist of a lower 60 mil and upper 80 mil HDPE

geomembranes separated by a drain net. The drain net will route potential leakage through the upper liner to a leakage collection and recovery sump.

Geomembrane liner will be placed on a minimum 6-inch thick layer of liner bedding fill. As noted above, the liner bedding fill can be constructed with existing tailings if they meet moisture content and compaction requirements. Additional liner bedding fill material can be derived from crushing and/or screening of selected native soils. A minus 3/8-inch material is suitable for protection of the liner.

3.5 Underdrain System

An underdrain will be placed beneath the starter dam and cycloned sand embankment. The underdrain system is shown on Drawing 6. The purpose of the embankment underdrain is to facilitate drainage and consolidation of cycloned sand placed in the tailings embankment. The underdrain will consist of graded sand and gravel that is filter compatible with the tailings sand. A series of perforated drain pipes will be placed within the underdrain layer to carry tailings drainage to the underdrain collection pond.

The under drain will be extended into the impoundment interior beneath the area that will be occupied by the supernatant pool. Production of drainage material that is filter compatible with the tailings slimes discharged into the impoundment interior will not be feasible. The impoundment underdrain will be separated from the tailings slimes by a geotextile filter fabric cover. Impoundment underdrainage will be routed to the underdrain collection pond in a piping system that is separate from the embankment under drain.

The pond layout presented as part of the conceptual design has a capacity of over 40 million gallons and represents the maximum potential construction area required for underdrain pond installation. Water balance and drainage analyses that will be completed during engineering design studies will be used to determine the underdrain collection pond size required to manage tailings underdrainage.

3.6 Water Reclaim

A water reclaim ramp with be constructed on top of the TSF liner system. The ramp will provide access to the free water pool for reclaim of supernatant solution and stormwater. The ramp will be raised and extended as deposition continues and the impoundment surface rises. The reclaim pump works will be progressively moved northward as the operation proceeds.

The ramp will be constructed with borrowed fill or waste rock from the mining operation. A cushioning layer will be placed beneath the initial ramp fill to protect the underlying geomembrane. The ramp presents an opportunity to dispose of potentially acid generating waste rock in an environment where ongoing tailings disposal will result in the ramp fill being encapsulated within low permeability tailings slimes.

3.7 Tailings Distribution

It is anticipated that a new thickener will be constructed at the location of the Quintana thickener (Drawing 2) and a tailings delivery pipeline will be routed to the impoundment through the existing tailings delivery pipeline cut. At the impoundment, a wye in the delivery pipeline will allow the tailings to be directed to the east and west to the starter dam crest. A series of discharge points and cyclones around the periphery of the impoundment will be used to direct cyclone underflow to the tailings embankment and cyclone overflow into the impoundment interior. Discharge will be cycled around the impoundment to raise the embankment in a level manner.

Regrading and compaction of the cycloned sand deposited on the dam crest will be conducted on a regular basis to densify the tailings embankment and achieve the design embankment outslope.

Drawing 8 presents a height versus capacity plot for the new TSF. There is potential to increase the capacity of the TSF beyond that shown on the plot, however, distribution of tailings above the elevation of 5,375 feet amsl is likely to require pumping of the whole tailings slurry. In addition, a tailings booster pump may be required in the later years of operation to maintain adequate pressure for cyclone operation.

3.8 Surface Water, Underdrainage, Stormwater and Supernatant Management

The intent of design is to allow the TSF to be operated as a zero discharge facility. Drainage from the tailings will be collected in an underdrain system, routed to a lined underdrain collection pond and recycled as process water. Potential runon from peripheral contributory areas will be prevented from contacting the tailings and diverted into natural drainages. Stormwater, which will result primarily from direct precipitation and supernatant will be contained within the impoundment.

3.8.1 Surface Water Diversion

During initial construction, perimeter diversions will be constructed across the west periphery of the impoundment. The approximately location of Phase 1 surface water diversions is shown on Drawing 3. As the impoundment is expanded in subsequent construction phases, diversion ditches will be relocated westward.

Potential runoff from peripheral areas west of the impoundment during the later stages of operation will be evaluated during design studies. Where runon is significant, diversion ditches will be investigated.

As noted above, at final buildout the TSF will occupy the majority of the area that can contribute surface water runon into the tailings impoundment. Only limited areas west of the impoundment might require late stage and post-closure diversion.

3.8.2 Stormwater and Supernatant Management

During operations, capacity will be maintained within the TSF for storage of direct precipitation and tailings supernatant. Upon discharge into the impoundment, tailings will form a beach sloping away from the point of discharge at ½ to 1 percent. The resulting depression on the tailings surface in the interior of the impoundment will be used for water storage. Additional storage capacity, if needed, will be developed by maintaining reserve freeboard on the tailings embankment crest.

A detailed water balance will be developed as part of the design studies to evaluate internal storage and embankment freeboard requirements. Water balance inputs include process water inflows, direct precipitation and runon. Losses include process water reclaim, beach and tailings pond evaporation, underdrainage and entrainment of process water within the tailings pore space. The rates of underdrainage, entrainment and tailings supernatantliberation on discharge will be determined through geotechnical testing of representative tailings samples.

Water storage requirements include:

- Dead storage (water that cannot be recovered by the reclaim system);
- Storage of the normal process water inventory to facilitate continuous operations;
- Normal stormwater storage which will vary on a seasonal basis due to changes in monthly precipitation and evaporation rates; and
- Storage for the design storm event, which is currently assumed to be 75 percent of the PMP.

The water balance will be coupled with a discharge model that will track the rate of tailings rise and simulate beach slopes and the topography of the tailings surface. The water balance and discharge model can then be used to estimate internal storage capacity and requirements for embankment freeboard through the life of the facility.

4.0 CLOSURE AND RECLAMATION

The conceptual closure plan for the TSF is illustrated on Drawing 9. The conceptual closure plan includes the following:

- Final grading of embankment outslopes to establish erosion controls and controlled surface water drainage (best management practices);
- Placement of a soil or rock cover and revegetation of the embankment outslope;
- Placement of riprap and erosion controls in embankment surface water drainage facilities;
- Regrading or depositional modification of the impoundment surface to promote drainage to a permanent spillway;
- Placement and vegetation of a soil cover over the tailings surface;
- Armoring of surface drainage channels and implementation of best management practices for erosion control; and
- Management of underdrainage.

Final grading of the impoundment surface can be accomplished with earthmoving equipment, or through modification of tailings disposal patterns during the final years of operation. Tailings discharge from selected locations can be used to relocate the supernatant pool to a location adjacent to the post-closure spillway, thereby reducing grading requirements and limiting earthmoving operations in areas where working conditions are expected to be difficult due to the presence of soft and saturated tailings. At the location of the spillway shown on Drawing 9, a bedrock foundation is anticipated. If the spillway channel is erodible, grouted riprap or other erosion controls will be applied.

Consolidation seepage into the underdrain system can be anticipated to continue at declining rates for an indefinite period following the cessation of tailings disposal operations. Underdrainage will be pumped from the underdrain collection pond to the surface of the tailings impoundment where it can be evaporated or used for reclamation cover irrigation. When underdrainage is reduced to an acceptably low flow rate, the underdrain pipes beneath the embankment can be sealed with grout and the underdrain collection pond can be decommissioned.

5.0 DATA COLLECTION AND DESIGN STUDY REQUIREMENTS FOR ADVANCING TSF DESIGN

The following defines work to be completed to advance the design of the new TSF to feasibility study and construction level.

5.1 Geotechnical Investigation

5.1.1 Existing TSF Area

The area occupied by the Quintana TSF area was extensively investigated by SHB (1980). Approximately 30 boreholes were drilled along the starter dam alignment. The majority of the borings were completed by hollow stem auger (HSA) and locally included in-situ permeability testing and diamond coring. Additional borings were completed in the impoundment interior. Test pits were excavated inside the impoundment on an approximate 500 foot by 500 foot grid.

Additional exploration will be undertaken in the area investigated by SHB to identify borrow areas for liner bedding fill and drainage media. This work is expected to require a test pit exploration program with native soil samples subjected to gradation analysis, Atterburg limits, permeability and compaction testing. This program will include sampling of existing tailings for compaction and permeability testing.

TSF Expansion Area investigation should include the following:

- A seismic velocity survey to evaluate the depth to bedrock and/or competent materials beneath the new embankment axis;
- Hollow stem auger drilling with standard penetration testing to obtain foundation material samples and measure in-situ density. Borehole spacing on the order of 300 to 500 feet is proposed along the new embankment axis.
- Selected HSA borings will be converted to core drilling to enable recovery of bedrock samples and support measurement of in-situ permeability by packer testing.
- Falling head or constant head permeability testing may also be performed in selected borings.
- Shelby tube and split spoon drive ring samples will be collected from selected intervals for analysis of in-situ density, natural moisture content and settlement potential.
- Test pit excavation will be performed in the expansion area to identify potential construction materials outside the previously explored area. Required materials include structural fill for the toe berm and starter dam, liner bedding fill and drain fill.

5.2 Tailings Characterization

NMCC reports that ore processing at Copper Flat will closely follow the process flow sheet developed by Quintana for 1981-82 operations. The characteristics of future tailings will impact operation of the new TSF. There are limited data concerning tailings properties from the Quintana operation, and production records (Oral communication, J. Bailey, 2010) indicate a coarser tailings product was produced during operations than would be predicted based on the pilot study tailings data presented in the original TSF design report (SHB, 1980).

Pilot or bench scale milling and flotation studies are recommended in support of final design studies to determine the physical and geochemical properties of future tailings. The primary objectives of the proposed study include:

- Evaluation of the partitioning of residual sulfides between cyclone underflow and overflow, and assessment of the acid generating and metal leaching potential of both the sand and slimes fractions;
- Determination of the gradation of future whole tailings and the quantity of sand that can be recovered for embankment construction;
- Evaluation of the flow characteristics of the whole tailings slurry;
- Measurement of the shear strength of tailings sand; and
- Measurement of the permeability of tailings sand and slimes under anticipated disposal conditions.

The milling and flotation test work should produce a sufficient quantity of tailings to enable a cyclone simulation to be performed in order to produce samples of both cyclone overflow and underflow. At minimum, the cyclone simulation will require a 55 gallon drum of tailings solids. The sand and slimes fractions produced in the simulation will be sufficient to support a full range of geotechnical and geochemical tests. Tailings should be subjected to the following tests:

- Gradation (sieve and hydrometer), Atterberg Limits, specific gravity (whole tailings, cyclone underflow and overflow);
- Compaction testing (cyclone underflow);
- Slurry consolidation testing (cyclone underflow and overflow);
- Staged triaxial consolidated, undrained shear strength testing with pore pressure measurement (cyclone underflow);
- Air drying (cyclone overflow);
- Shrinkage limit (cyclone overflow); and
- Acid base accounting, net acid generation (NAG), total metals, major oxides by x-ray florescence (XRF), leach extraction testing, and mineralogy by x-ray diffraction (XRD) (cyclone underflow and overflow).

5.3 Hydrogeological Characterization

Local monitoring wells that will be decommissioned during TSF expansion will require replacement in the area below the new toe berm and underdrain collection pond. Water level measurements and in-situ permeability tests conducted concurrently with drilling and well installation can be used in conjunction with existing data to evaluate hydrogeological conditions in the TSF expansion area.

5.4 Climatological Characterization

Estimation of normal precipitation and evaporation rates will be required to develop an impoundment water balance. It is assumed that a climatological model will be developed using a combination of locally collected weather data combined with regional weather records from National Weather Service monitoring stations.

5.5 Engineering Studies

The following is a listing of design studies that will be required to complete the design of the TSF:

- Foundation settlement analyses;
- Tailings drainage analyses;
- Seismic hazard analysis:
- Static and dynamic embankment stability analyses, including estimation of displacement under seismic loading;
- Seismic and static (monotonic loading, flow slide) liquefaction potential analyses;
- Evaluation of tailings sand availability, mass balance and deposition modeling;
- Liner seepage assessment;
- Foundation hydrogeological assessment;
- Water balance;
- Tailings basin hydrologic assessment for surface water diversion sizing;
- Estimation of design storm event (PMP) precipitation;
- Dam breach analysis as per OSE requirements.

6.0 USE OF THIS REPORT

This report has been prepared exclusively for the use of New Mexico Copper Corporation (NMCC) for specific application to the Copper Flat Project. No third party engineer or consultant shall be entitled to rely on any of the information, conclusions, or opinions contained in this report without prior written approval from NMCC or Golder Associates, Inc (Golder).

The conclusions and recommendations in this report have been prepared in a manner consistent with the level of care and skill ordinarily exercised by engineering professionals currently practicing under similar conditions, subject to the time limits and financial and physical constraints imposed on, or otherwise applicable to, Golder's analyses.

In preparing its conclusions and recommendations, Golder has relied upon information provided by the client. Golder is not responsible for errors or omissions in the information provided by NMCC.

GOLDER ASSOCIATES INC.

Eugene Muller, P.E.
Senior Engineer

David A. Kidd, P.E.
Principal, Geotechnical Practice Leader

GM/DAK/br

7.0 REFERENCES

Jack Bailey, October 1, 2010. Oral Communication, milling records, 65 mesh fraction, Quintana Minerals Corp, April through June 1982.

Google.Com, 2010, Google Earth images, 32° 57'33" N, 107° 29' 57 'W

Sargent Hauskins and Beckwith (SHB), 1981. *Geohydrological Evaluation for Submission of Discharge Plan, Copper Flat Project, Quintana Minerals Corporation, Sierra County, New Mexico*. SHB Report E80-194, June 21, 1981.

Sargent Hauskins and Beckwith (SHB), 1980. Tailings Dam and Disposal Area, Quintana Minerals Corporation, Copper Flats Project, Gold Dust, New Mexico (Final Geotechnical and Design Development Report), SHB Report E80-1030B, October 14, 1980.

SRK Consulting Inc., 2010. *NI 43-101 Preliminary Economic Assessment, THEMAC Resources Group Limited, Copper Flat Project, Sierra County, New Mexico*, SRK Report No. 191000.020, June 30, 2010

DRAWINGS

COPPER FLAT PROJECT
TAILINGS STORAGE FACILITY
CONCEPTUAL DESIGN STUDY
SIERRA COUNTY, NEW MEXICO



AERIAL PHOTOGRAPH OF PROPOSED TAILINGS DISPOSAL SITE

NOT TO SCALE



STATE OF NEW MEXICO

NOT TO SCALE

LIST OF DRAWINGS

DWG No.	DRAWING TITLE
1	TITLE SHEET
2	GENERAL SITE LAYOUT
3	TAILINGS STORAGE FACILITY PLAN
4	TAILINGS STORAGE FACILITY PLAN AT FINAL BUILD-OUT
5	TAILINGS STORAGE FACILITY CROSS-SECTIONS
6	TAILINGS STORAGE FACILITY UNDERDRAIN PLAN
7	TAILINGS STORAGE FACILITY DETAILS
8	TAILINGS STORAGE FACILITY HEIGHT VS CAPACITY PLOT
9	TAILINGS STORAGE FACILITY CONCEPTUAL CLOSURE PLAN

GENERAL NOTES

1. EXISTING FIVE (5) FOOT TOPOGRAPHY AND PERMIT BOUNDARY PROVIDED BY NEW MEXICO COPPER CORPORATION.
2. AERIAL PHOTOGRAPHY © GOOGLE 2010, NMRGIS 2010.
3. DRAWINGS PRESENT THE CONCEPTUAL DESIGN OF A PROPOSED NEW AND EXPANDED TAILINGS STORAGE FACILITY WITH A CAPACITY OF 100 MILLION TONS AT AN ASSUMED DRY DENSITY OF 85 POUND PER CUBIC FOOT.
4. FINAL DESIGN WILL BE COMPLETED IN ACCORDANCE WITH THE RULES AND REGULATIONS OF THE NEW MEXICO STATE ENGINEER, THE NEW MEXICO ENVIRONMENT DEPARTMENT (NMED) AND THE NEW MEXICO MINING AND MINERALS DIVISION (NM MMD).
5. AERIAL PHOTOGRAPH SHOWS EXISTING TAILINGS DISPOSAL AREA DISTURBANCE FROM MINING, MILLING AND TAILINGS DISPOSAL OPERATIONS CONDUCTED BY QUINTANA RESOURCES IN 1981-82.
6. EXISTING TAILINGS FROM THE QUINTANA 1981-82 OPERATIONS ARE THE SUBJECT OF AN ONGOING ABATEMENT ACTION. THE CONCEPTUAL DESIGN CONSIDERS CAPPING EXISTING TAILINGS BENEATH THE FUTURE IMPOUNDMENT LINER SYSTEM THROUGH THEIR INCORPORATION IN THE LINER BEDDING FILL LAYER, OR PLACEMENT OF EXISTING TAILINGS ON THE NEW IMPOUNDMENT LINER. ALTERNATIVES FOR MANAGEMENT OF EXISTING TAILINGS WILL BE DEVELOPED IN CONSULTATION WITH NMED.

DRAWING USE	CONCEPTUAL DESIGN NOT FOR CONSTRUCTION
PROJECT	COPPER FLAT PROJECT TAILINGS STORAGE FACILITY CONCEPTUAL DESIGN STUDY SIERRA COUNTY, NEW MEXICO
TITLE	**TITLE SHEET**

Golder Associates

PROJECT No.	103-92557		FILE No.	10392557A001	
DESIGN	CDJ	10/25/10	SCALE	AS SHOWN	REV. C
CADD	ANV	10/27/10	DRAWING	1	
CHECK	GM	10/29/10			
REVIEW	DAK	11/17/10			

Drawing file: K:\2010 Projects\103-92557 Copper Flat\10392557A001.dwg Nov 23, 2010 - 11:05am

LEGEND

PERMIT BOUNDARY

GENERAL NOTES

1. EXISTING FIVE (5) FOOT TOPOGRAPHY AND PERMIT BOUNDARY PROVIDED BY NEW MEXICO COPPER CORPORATION
2. DRAWINGS PRESENT THE CONCEPTUAL DESIGN OF A PROPOSED NEW AND EXPANDED TAILINGS STORAGE FACILITY WITH A CAPACITY OF 100 MILLION TONS AT AN ASSUMED DRY DENSITY OF 85 POUND PER CUBIC FOOT
3. FINAL DESIGN WILL BE COMPLETED IN ACCORDANCE WITH THE RULES AND REGULATIONS OF THE NEW MEXICO STATE ENGINEER, THE NEW MEXICO ENVIRONMENT DEPARTMENT (NMED) AND THE NEW MEXICO MINING AND MINERALS DIVISION (NM MMD).
4. TOPOGRAPHY IN THE MINE AREA AND TAILINGS STORAGE FACILITY REPRESENTS EXISTING CONDITIONS AND DISTURBANCE ASSOCIATED WITH QUINTANA 1981-82 MINING OPERATIONS
5. PROPOSED TAILINGS STORAGE FACILITY FOOTPRINT IS FOR A NEW FACILITY WITH A CAPACITY OF 100 MILLION TONS AT AN ASSUMED DRY DENSITY OF 85 POUND PER CUBIC FOOT

600 0 600 1200
SCALE FEET

DAVID ALAN KIRK
NEW MEXICO
13778
11-17-10
REGISTERED PROFESSIONAL ENGINEER

DRAWING USE	CONCEPTUAL DESIGN NOT FOR CONSTRUCTION
PROJECT	COPPER FLAT PROJECT TAILINGS STORAGE FACILITY CONCEPTUAL DESIGN STUDY SIERRA COUNTY, NEW MEXICO
TITLE	GENERAL SITE LAYOUT

Golder Associates

PROJECT No.		103-92557	FILE No.	10392557A002
DESIGN	CDJ	10/25/10	SCALE AS SHOWN	REV. B
CADD	ANV	10/27/10	DRAWING	2
CHECK	GM	10/29/10		
REVIEW	DAK	11/17/10		

Drawing File: K:\2010 Projects\103-92557 Copper Flat\103925574002.dwg Nov 23, 2010 - 11:14am

02083



LEGEND

- EXISTING CONTOURS
- 5200 DESIGN CONTOURS
- PHASE 1 SURFACE WATER DIVERSION FLOW ARROW
- PERMIT BOUNDARY
- INITIAL CONSTRUCTION BOUNDARY
- FINAL TAILINGS BUILD-OUT
- 3/7 DETAIL CALL-OUT
- A/5 CROSS-SECTION CALL-OUT

NOTES

1. DRAWINGS PRESENT THE CONCEPTUAL DESIGN OF A NEW AND EXPANDED TAILINGS STORAGE FACILITY WITH A CAPACITY OF 100 MILLION TONS AT AN ASSUMED DRY DENSITY OF 85 POUND PER CUBIC FOOT.
2. FINAL DESIGN WILL BE COMPLETED IN ACCORDANCE WITH THE RULES AND REGULATIONS OF THE NEW MEXICO STATE ENGINEER, THE NEW MEXICO ENVIRONMENT DEPARTMENT (NMED) AND THE NEW MEXICO MINING AND MINERALS DIVISION (NM MMD).
3. EXISTING FIVE (5) FOOT TOPOGRAPHY AND PERMIT BOUNDARY PROVIDED BY NEW MEXICO COPPER CORPORATION.
4. TOPOGRAPHY IN THE VICINITY OF THE QUNITANA STARTER DAM AND TAILINGS CELLS APPROXIMATED BY GOLDER TO REPRESENT PRECONSTRUCTION TOPOGRAPHY FOLLOWING DEMOLITION (BORROW) OF THE EXISTING STARTER EMBANKMENT, RELOCATION OF EXISTING TAILINGS AND REGRADING IN FORMER BORROW AREAS AND EXISTING DISTURBANCE AREAS. TOPOGRAPHY IN OTHER LOCATIONS REPRESENTS EXISTING CONDITIONS. A SITE WIDE TAILINGS DISPOSAL FACILITY GRADING PLAN WILL BE DEVELOPED IN FUTURE DESIGN STUDIES.
5. EXISTING TAILINGS FROM THE QUINTANA 1981-82 OPERATIONS ARE THE SUBJECT OF AN ONGOING ABATEMENT ACTION. THE CONCEPTUAL DESIGN CONSIDERS CAPPING EXISTING TAILINGS BENEATH THE FUTURE IMPOUNDMENT LINER SYSTEM THROUGH THEIR INCORPORATION IN THE LINER BEDDING FILL LAYER, OR PLACEMENT OF EXISTING TAILINGS ON THE NEW IMPOUNDMENT LINER. ALTERNATIVES FOR MANAGEMENT OF EXISTING TAILINGS WILL BE DEVELOPED IN CONSULTATION WITH NMED.
6. PHASE 1 CONSTRUCTION LIMITS ARE APPROXIMATELY LOCATED. PHASE 1 AND SUBSEQUENT CONSTRUCTION PHASE LIMITS AND SURFACE WATER DIVERSION REQUIREMENTS WILL BE DETERMINED IN FUTURE ENGINEERING DESIGN STUDIES.
7. EMBANKMENT RAISES WILL BE CONSTRUCTED BY THE CENTERLINE RAISE METHOD USING CYCLONE UNDERFLOW (TAILINGS SAND). CYCLONE OVERFLOW (SLIMES) WILL BE DISCHARGED INTO THE INTERIOR OF THE TAILINGS STORAGE FACILITY.
8. DURING OPERATION, STORMWATER WILL BE CONTAINED WITHIN THE TAILINGS STORAGE FACILITY AND UTILIZED AS PROCESS MAKE-UP WATER. A PROJECT WATER BALANCE WILL BE DEVELOPED IN FUTURE ENGINEERING DESIGN STUDIES

DAVID ALAN KIDD NEW MEXICO 13778 REGISTERED PROFESSIONAL ENGINEER 11-17-10

400 0 400 800 SCALE FEET

DRAWING USE: CONCEPTUAL DESIGN NOT FOR CONSTRUCTION

PROJECT: COPPER FLAT PROJECT
TAILINGS STORAGE FACILITY
CONCEPTUAL DESIGN STUDY
SIERRA COUNTY, NEW MEXICO

TITLE: **TAILINGS STORAGE FACILITY PLAN**

Golder Associates

PROJECT No.		103-92557	FILE No.		10392557A003
DESIGN	CDJ	10/25/10	SCALE	AS SHOWN	REV. B
CADD	ANV	10/27/10	DRAWING	3	
CHECK	GM	10/29/10			
REVIEW	DAK	11/17/10			

Drawing file: K:\2010 Projects\103-92557 Copper Flat\10392557A003.dwg Nov 22, 2010 - 11:15am

02084



LEGEND

- EXISTING CONTOURS
- 5200 DESIGN CONTOURS
- PERMIT BOUNDARY
- A/5 CROSS-SECTION CALL-OUT

NOTES

1. DRAWINGS PRESENT THE CONCEPTUAL DESIGN OF A NEW AND EXPANDED TAILINGS STORAGE FACILITY WITH A CAPACITY OF 100 MILLION TONS AT AN ASSUMED DRY DENSITY OF 85 POUND PER CUBIC FOOT.
2. FINAL DESIGN WILL BE COMPLETED IN ACCORDANCE WITH THE RULES AND REGULATIONS OF THE NEW MEXICO STATE ENGINEER, THE NEW MEXICO ENVIRONMENT DEPARTMENT (NMED) AND THE NEW MEXICO MINING AND MINERALS DIVISION (NM MMD)
3. EXISTING FIVE (5) FOOT TOPOGRAPHY AND PERMIT BOUNDARY PROVIDED BY NEW MEXICO COPPER CORPORATION
4. FINAL EMBANKMENT CREST HEIGHT WILL BE APPROXIMATELY 5,375 FEET AMSL. TAILINGS SURFACE CONFIGURATION SHOWN REPRESENTS CONDITIONS AT THE CESSATION OF MINING OPERATIONS. APPROXIMATE LOCATION OF A POST-CLOSURE SPILLWAY SHOWN. TAILINGS DISCHARGE LOCATIONS MAY BE MODIFIED IN LATE STAGE OPERATIONS TO GRADE THE IMPOUNDMENT SURFACE AND FACILITATE POST-CLOSURE DRAINAGE TO THE PERMANENT SPILLWAY.
5. SELECTION OF A DESIGN STORM EVENT FOR STORMWATER STORAGE AND SPILLWAY CAPACITY WILL BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE NEW MEXICO STATE ENGINEER.

DAVID ALAN KIDD
NEW MEXICO
13778
REGISTERED PROFESSIONAL ENGINEER
11-17-10

SCALE 400 0 400 800 FEET

DRAWING USE	CONCEPTUAL DESIGN NOT FOR CONSTRUCTION
PROJECT	COPPER FLAT PROJECT TAILINGS STORAGE FACILITY CONCEPTUAL DESIGN STUDY SIERRA COUNTY, NEW MEXICO
TITLE	**TAILINGS STORAGE FACILITY AT FINAL BUILD-OUT**

Golder Associates

PROJECT No.		103–92557	FILE No.		10392557A004
DESIGN	CDJ	10/25/10	SCALE	AS SHOWN	REV. C
CADD	ANV	10/27/10	DRAWING	4	
CHECK	GM	10/29/10			
REVIEW	DAK	11/17/10			

Drawing file: K:\2010 Projects\103-92557 Copper Flat\10392557A004.dwg Nov 22, 2010 - 11:15am



A/5 CROSS SECTION A-A'

SCALE 250 0 250 500 FEET



B/5 CROSS SECTION B-B'

SCALE 250 0 250 500 FEET



C/5 CROSS SECTION C-C'

SCALE 100 0 100 200 FEET

DAVID ALAN KIDD NEW MEXICO 13778 REGISTERED PROFESSIONAL ENGINEER 11-17-10

DRAWING USE
CONCEPTUAL DESIGN NOT FOR CONSTRUCTION

PROJECT
COPPER FLAT PROJECT
TAILINGS STORAGE FACILITY
CONCEPTUAL DESIGN STUDY
SIERRA COUNTY, NEW MEXICO

TITLE
TAILING FACILITY STORAGE CROSS-SECTIONS

Golder Associates

PROJECT No.	103-92557		FILE No.	10392557A005	
DESIGN	CDJ	10/25/10	SCALE	AS SHOWN	REV. C
CADD	ANV	10/27/10	DRAWING	5	
CHECK	GM	10/29/10			
REVIEW	DAK	11/17/10			

Drawing File: K:\2010 Projects\103-92557 Copper Flat\10392557A005.dwg Nov 22, 2010 - 11:25am



LEGEND

- EXISTING CONTOURS
- 6200 DESIGN CONTOURS
- PHASE 1 SURFACE WATER DIVERSION FLOW ARROW
- PERMIT BOUNDARY
- PHASE 1 BOUNDARY
- FINAL TAILINGS BUILD-OUT
- PRIMARY UNDERDRAIN PIPE
- PRIMARY DRAIN PIPE
- UNDERDRAIN FILL
- 3/7 DETAIL CALL-OUT

NOTES

1. DRAWINGS PRESENT THE CONCEPTUAL DESIGN OF A NEW AND EXPANDED TAILINGS STORAGE FACILITY WITH A CAPACITY OF 100 MILLION TONS AT AN ASSUMED DRY DENSITY OF 85 POUND PER CUBIC FOOT.
2. FINAL DESIGN WILL BE COMPLETED IN ACCORDANCE WITH THE RULES AND REGULATIONS OF THE NEW MEXICO STATE ENGINEER, THE NEW MEXICO ENVIRONMENT DEPARTMENT (NMED) AND THE NEW MEXICO MINING AND MINERALS DIVISION (NM MMD)
3. EXISTING FIVE (5) FOOT TOPOGRAPHY AND PERMIT BOUNDARY PROVIDED BY NEW MEXICO COPPER CORPORATION
4. APPROXIMATE LIMITS OF UNDER DRAIN SYSTEM SHOWN. EMBANKMENT UNDERDRAIN WILL BE A GRADED SAND AND GRAVEL DRAIN THAT IS FILTER COMPATIBLE WITH CYCLONED TAILINGS SAND. IMPOUNDMENT UNDER DRAIN WILL BE GEOTEXTILE FABRIC WRAPPED. THE IMPOUNDMENT UNDERDRAIN WILL BE EXTENDED DURING PHASED CONSTRUCTION.

DAVID ALAN KIRD NEW MEXICO 13778 REGISTERED PROFESSIONAL ENGINEER 11-17-10

400 0 400 800 SCALE FEET

DRAWING USE
CONCEPTUAL DESIGN NOT FOR CONSTRUCTION

PROJECT
COPPER FLAT PROJECT
TAILINGS STORAGE FACILITY
CONCEPTUAL DESIGN STUDY
SIERRA COUNTY, NEW MEXICO

TITLE
TAILINGS STORAGE FACILITY UNDERDRAIN PLAN

Golder Associates

PROJECT No.	103-92557		FILE No.	10392557A006
DESIGN	CDJ	10/25/10	SCALE AS SHOWN	REV. B
CADD	ANV	10/27/10	DRAWING	6
CHECK	GM	10/29/10		
REVIEW	DAK	11/17/10		

Drawing File: K:\2010 Projects\103-92557 Copper Flat\10392557A006.dwg Nov 23, 2010 - 11:26am



1/7 **IMPOUNDMENT LINER DETAIL**
NOT TO SCALE



2/7 **UNDERDRAIN AREA LINER DETAIL**
NOT TO SCALE



3/7 **EMBANKMENT AREA LINER DETAIL**
NOT TO SCALE



4/7 **POND LINER DETAIL**
NOT TO SCALE



5/7 **IMPOUNDMENT ANCHOR TRENCH DETAIL**
NOT TO SCALE



6/7 **POND ANCHOR TRENCH DETAIL**
NOT TO SCALE



7/7 **POND LEAK COLLECTION AND RECOVERY SYSTEM (LCRS) DETAIL**
NOT TO SCALE



8/7 **CYCLONED SAND EMBANKMENT DETAIL**
NOT TO SCALE



9/7 **PROCESS WATER RECLAIM RAMP DETAIL**
NOT TO SCALE

DAVID ALAN KIDD
NEW MEXICO
13778
11-17-10
REGISTERED PROFESSIONAL ENGINEER

DRAWING USE	CONCEPTUAL DESIGN NOT FOR CONSTRUCTION
PROJECT	COPPER FLAT PROJECT TAILINGS STORAGE FACILITY CONCEPTUAL DESIGN STUDY SIERRA COUNTY, NEW MEXICO
TITLE	TAILINGS STORAGE FACILITY DETAILS

Golder Associates

PROJECT No.	103-92557		FILE No.	10392557AD07
DESIGN	CDJ	10/25/10	SCALE	AS SHOWN REV. C
CADD	ANV	10/27/10	DRAWING	7
CHECK	GM	10/28/10		
REVIEW	DAK	11/17/10		

Drawing File: K:\2010 Projects\103-92557 Copper Flat\10392557AD07.dwg Nov 22, 2010 - 11:27am





NOTES

1. CAPACITY ESTIMATED USING EXISTING FIVE (5) FOOT TOPOGRAPHY PROVIDED BY NEW MEXICO COPPER CORPORATION AND A DRY DENSITY OF 85 PCF.
2. TAILING MAXIMUM ELEVATION IS 5,375 FT AMSL AT LOCATION OF DISCHARGE POINT.
3. RATE OF RISE IS CALCULATED FROM THE PRODUCTION RATE OF 17,500 TONS PER DAY AT 93% AVAILABILITY FOR AN ANNUAL PRODUCTION OF 5,940,375 TONS.
4. ASSUMED START-UP DATE 2015. ACTUAL START DATE TO BE DETERMINED.

DRAWING USE
CONCEPTUAL DESIGN
NOT FOR CONSTRUCTION

PROJECT
COPPER FLAT PROJECT
TAILINGS STORAGE FACILITY
CONCEPTUAL DESIGN STUDY
SIERRA COUNTY, NEW MEXICO

TITLE
HEIGHT VS. CAPACITY PLOT

Golder Associates

PROJECT No.		103-92557	FILE No.	10392557A008	
DESIGN	CDJ	10/25/10	SCALE	N.T.S.	REV. C
CADD	ANV	10/27/10	DRAWING	8	
CHECK	GM	10/29/10			
REVIEW	DAK	11/17/10			

Drawing file: K:\2010 Projects\103-92557 Copper Flat\10392557A008.dwg Nov 23, 2010 — 11:26am





D/9 CROSS SECTION D-D'

SCALE 120 0 120 240 FEET



E/9 CROSS SECTION E-E'

SCALE (x5 VERTICAL EXAGGERATION) 50 0 50 100 FEET

LEGEND

- EXISTING CONTOURS
- 5200 DESIGN CONTOURS
- PERMIT BOUNDARY
- D/9 CROSS-SECTION CALL-OUT



NOTES

1. DRAWINGS PRESENT THE CONCEPTUAL DESIGN OF A NEW AND EXPANDED TAILINGS STORAGE FACILITY WITH A CAPACITY OF 100 MILLION TONS AT AN ASSUMED DRY DENSITY OF 85 POUND PER CUBIC FOOT.
2. FINAL DESIGN WILL BE COMPLETED IN ACCORDANCE WITH THE RULES AND REGULATIONS OF THE NEW MEXICO STATE ENGINEER, THE NEW MEXICO ENVIRONMENT DEPARTMENT (NMED) AND THE NEW MEXICO MINING AND MINERALS DIVISION (NM MMD)
3. EXISTING FIVE (5) FOOT TOPOGRAPHY AND PERMIT BOUNDARY PROVIDED BY NEW MEXICO COPPER CORPORATION.
4. FINAL EMBANKMENT CREST HEIGHT WILL BE APPROXIMATELY 5,375 FEET AMSL. TAILINGS SURFACE CONFIGURATION SHOWN REPRESENTS CONDITIONS AT THE CESSATION OF MINING OPERATIONS. APPROXIMATE LOCATION OF A POST-CLOSURE SPILLWAY SHOWN. TAILINGS DISCHARGE LOCATIONS MAY BE MODIFIED IN LATE STAGE OPERATIONS TO GRADE THE IMPOUNDMENT SURFACE AND FACILITATE POST-CLOSURE DRAINAGE TO THE PERMANENT SPILLWAY.
5. SELECTION OF A DESIGN STORM EVENT FOR STORMWATER STORAGE AND SPILLWAY CAPACITY WILL BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE NEW MEXICO STATE ENGINEER.
6. TAILINGS SURFACE REGRADED AT CLOSURE OR TAILINGS DEPOSITION PATTERNS MODIFIED DURING LATE STAGE OPERATION TO CONTOUR THE TAILINGS SURFACE.
7. UNDERDRAINING TO BE COLLECTED AND EVAPORATED ON IMPOUNDMENT SURFACE UNTIL UNDERDRAIN PIPES CAN BE PLUGGED AND UNDERDRAIN COLLECTION POND BACKFILLED.

DAVID ALAN KIDD NEW MEXICO 13778 REGISTERED PROFESSIONAL ENGINEER 11-17-10

DRAWING USE
CONCEPTUAL DESIGN NOT FOR CONSTRUCTION

PROJECT
COPPER FLAT PROJECT
TAILINGS STORAGE FACILITY
CONCEPTUAL DESIGN STUDY
SIERRA COUNTY, NEW MEXICO

TITLE
TAILINGS STORAGE FACILITY CONCEPTUAL CLOSURE PLAN

Golder Associates

PROJECT No.	103–92557		FILE No.	10392557A009	
DESIGN	CDJ	10/25/10	SCALE	AS SHOWN	REV. C
CADD	ANV	10/27/10	DRAWING	9	
CHECK	GM	10/29/10			
REVIEW	DAK	11/17/10			

Drawing file: K:\2010 Projects\103-92557 Copper Flat\10392557A009.dwg Nov 22, 2010 - 11:28am

TECHNICAL MEMORANDUM

Date: June 16, 2011
To: Mr. Steve Raugust
Project No.: 103-92557.005
Company: New Mexico Copper Corp
Suite 100 - 2425 San Pedro Dr. NE
Albuquerque, NM 87110

From: Gene Muller, Senior Engineer
David A. Kidd, P.E.
RE: **COPPER FLAT PROJECT - BORROW SOURCE AND STOCKPILE EVALUATION**



1.0 INTRODUCTION

1.1 Background Information

The Copper Flat project is a proposed porphyry copper mining operation located in Sierra County, New Mexico, east of the town of Hillsboro. The location of the project is shown on Figure 1. Site investigation of the tailings storage facility (TSF) was initiated in 1979 on behalf of Quintana Minerals Corporation (Quintana). Quintana initiated mining operations at the property in 1982 and in 1986, after completing mine pre-stripping operations and processing approximately 1.2 million tons of ore, the operation was closed for economic reasons.

An extensive site investigation study was conducted by Sergent Hauskins and Beckwith (SHB) in 1979 and 1980 (SHB, 1980) for the TSF in the configuration required for the then approved Mine Plan of Operations (MPO). Quintana constructed the initial phase of the tailings storage facility, consisting of a starter dam and central splitter dike, and deposited approximately 1.2 million tons of tailings in the north impoundment cell. The TSF was reclaimed but the starter dam and splitter dike remain in place in the configurations that existed in 1986 following project shut down.

New Mexico Copper Corp (NMCC) proposes initiating mining operations at Copper Flat with limited changes to the MPO developed by Quintana. Changes include an increase in mineable ore reserves from 60 to approximately 100 million tons, and a corresponding increase in waste rock disposal requirements. These changes will necessitate enlargement and redesign of the TSF, and expansion of the waste rock disposal facilities and low grade ore stockpile.

To date, requirements for the new TSF have been evaluated at conceptual design level (Golder, 2010). Site investigation activities to support TSF design and expansion are planned, however, access to public lands for subsurface exploration and geotechnical investigation has not yet been granted. The footprint of the expanded TSF will be extended to the south approximately 1000 feet while the north, east and west boundaries will correspond to those of the 1980 design.

Golder Associates Inc.
4730 N. Oracle Road, Suite 210
Tucson, AZ 85705 USA
Tel: (520) 888-8818 Fax: (520) 888-8817 www.golder.com

Golder Associates: Operations In Africa, Asia, Australasia, Europe, North America and South America

Golder, Golder Associates and the GA globe design are trademarks of Golder Associates Corporation

1.2 Scope

This report presents an evaluation of borrow material availability for construction and reclamation of the expanded TSF at Copper Flat. Stockpiles required to store the various construction materials through the life of the operation are also presented. The report addresses the following anticipated material requirements:

- Structural fill materials for toe berm and starter dam construction;
- Drainage materials to enhance dam stability and promote tailings consolidation;
- Liner bedding fill to protect the impoundment geomembrane liner;
- Reclamation cover material; and
- Top dressing.

Stockpiles required to contain selected construction and reclamation materials that must be recovered from the TFS area prior to liner placement and burial with tailings are identified.

1.3 Bases Considered in Borrow Material Evaluation

Material requirements for TSF construction and reclamation are based on a material take-off of the conceptual TSF design (Golder, 2010) as presented in the Copper Flat Mine Plan of Operations (NMCC, 2010).

Access to the public land in the TSF expansion has not been granted and geotechnical investigation activities in the TSF expansion area have not been completed. Therefore, borrow sources have been identified on the basis of site investigation and geotechnical testing completed by SHB in 1980 (SHB, 1980).

Reclamation construction and associated fill material requirements for the TSF are assumed to be similar to those approved for TSF reclamation in Tyrone, New Mexico, where a 2.5 to 3-foot thick reclamation cover has been required.

Drainage material requirements are based on the conceptual design and review of the Office of the New Mexico State Engineer (OSE) dam safety regulations.

1.4 Contingency

It is recognized that construction material quantities estimated on the basis of the conceptual design may vary when final design studies are completed, however, the primary change would be associated with structural fill requirements for starter dam and toe berm construction. Locating borrow sources for structural fill materials is not considered problematic at Copper Flat, as suitable granular materials occur extensively within the construction footprint.

Changes in the configuration of the starter dam and toe berm should not significantly impact the quantities of other materials (drainage material, liner bedding and reclamation cover) that will be needed through the life of the facility. Little change in the ultimate footprint is expected as a result of modification to the toe berm or starter dam configurations.

It is also recognized that site investigation in the tailings expansion area may identify additional sources of construction and reclamation materials within the TSF permit area and footprint. While additional or alternative borrow areas may be identified within the TSF footprint, the need to stockpile materials outside the TSF will not change.

2.0 BORROW SOURCE EVALUATION

Figure 2 presents the TSF area in its current configuration with the existing starter dam and splitter dike, Tailings from the 1982 to 1986 operation were placed to the north of the splitter dike. Exploration sites from the SHB site investigation conducted in 1979 and 1980 are shown overlain on current topography.

SHP completed approximately 30 exploration bore holes in the starter dam area and approximately 70 test pits in the area located upstream from the starter dam. Under the 1982 design, borrow requirements for TSF construction consisted primarily of structural embankment fill and drainage materials. Earthwork requirements for the proposed, redesigned and enlarged TSF include:

- Top dressing;
- Reclamation cover material;
- Liner bedding fill;
- Structural embankment fill;
- Drainage materials (drain gravel); and
- Riprap and Erosion control materials.

Table 1: Schedule of Construction Material Requirements

Material	Phase 1 Cubic Yards	To Final Buildout Cubic Yards	Total	Notes
Topsoil	207,946	334,742	542,688	Place in North and West Stockpiles until reclamation
Reclamation Cover	See Note 2	2,062,509	2,062,509	Place in North and West Stockpiles until reclamation
Liner Bedding Fill	429,930	395,074	825,004	Stockpile Internally, stockpiled quantities subject to material requirements
Structural Embankment Fill	2,124,450	324,511	2,448,961	Available all construction phases in TSF area
Drainage Materials	483,333	77,778	561,111	Available all construction phases in TSF area

Notes:
1 Approximately 882,000 cubic yards of Phase 1 structural fill will be recovered from the existing starter dam.
2 Reclamation Cover material is assumed to be derived from inside the TSF. Reclamation cover can be collected during one or more construction phases.

Table 1 presents a summary of construction material requirements for TSF construction and reclamation based on the conceptual design. The borrow sources and handling of the various construction and reclamation materials are discussed in the following report sections.

2.1 Top Dressing Salvage and Stockpiling

The footprint of the proposed TSF and underdrain collection pond will cover approximately 550 acres at final build-out. Areas disturbed by the 1982-1986 operations cover approximately 105 acres. These include the footprint areas of the old starter dam and splitter dike and the south cell tailings disposal area.

Assuming 6-inches of top dressing over the entire TSF at closure, approximately 438,000 cubic yards (cy) of top dressing will be required. The majority of top dressing stripping operations will be required in the initial construction phase. Additional topdressing salvage will be required as the tailings surface rises and the TSF liner system is extended westward. A top dressing stockpile will be required outside the TSF footprint until reclamation commences.

It is assumed that top dressing will be recovered from undisturbed areas to avoid potential contamination with tailings from the Quintana operation. During site investigation activities, the location of old tailings deposits will be confirmed and areas where top dressing stripping is to be undertaken will be delineated. Stripping up to a depth of nine inches in undisturbed areas will generate approximately 542,000 cy of topdressing, a quantity sufficient to cover the TSF and potentially supplement shortages in other areas disturbed during the Quintana operation.

2.2 Reclamation Cover Fill

As noted above, reclamation cover requirements for TSF reclamation are assumed to be similar to those approved for use at Tyrone, New Mexico, which consist of a 2.5 to 3-foot thick cover of native soils (Gila Conglomerate) over the TSF. Cover material estimates and stockpile requirements for the Copper Flat TSF assume a 3-foot thick cover consisting of 6-inches of top dressing and 2.5-feet of alluvial and colluvial cover fill. Alluvial and colluvial gravels suitable for reclamation cover occur over approximately 70 percent of the surface area inside the existing TSF footprint.

Because the TSF dam will be constructed by centerline methods, reclamation material cannot be placed on the dam, or tailings surface, until tailings deposition is complete. At final build-out of the TSF will cover an area of approximately 511 acres and will require approximately 2.06 million cy of alluvial/colluvial cover material. It is assumed that reclamation cover material will be collected and stockpiled outside the TSF footprint during one or more construction phases because there are limited borrow sources outside the TSF and within the project permit area.

If NMCC expands the permit area to include external borrow sources for reclamation fill, stockpiling reclamation cover fill will not be necessary.

2.3 Liner Bedding Fill Material

To date, a lined tailings disposal facility has not been constructed in the State of New Mexico and no precedent exists on which to base the thickness, gradation and hydraulic conductivity requirements for a bedding layer for a TSF geomembrane liner.

The thickness of a liner bedding layer is anticipated to range from 6 to 12 inches and be dependent upon the function of the bedding layer (i.e., liner protection or hydraulic barrier).

If NMCC will be required to construct a composite liner system consisting of a geomembrane and low permeability soil bedding layer, typical requirements for gold heap leach pads and process solution ponds include 12-inches of material with a maximum hydraulic conductivity of 10^{-6} centimeters per second (cm/sec). To achieve hydraulic conductivity requirements, bedding fill will need to be composed of clayey soils with a fines fraction (minus 200 standard sieve) of approximately 40 percent coupled with moderate plasticity.

Bedding layers that serve only as a geomembrane protective layer can be constructed with granular materials. Arizona mandates a minimum 6-inch layer of minus 3/8-inch material as a protective layer for lined non-stormwater ponds. These materials are typically produced by crushing and/or screening of local borrows materials.

Materials suitable for either liner bedding requirement occur within the area explored by SHB in 1979-80. Silty clays occur in the area immediately west of the existing starter dam while clays of moderate to high plasticity occur near the south abutment and south of the splitter dike along the centerline of the existing starter dam. Materials suitable for construction of granular bedding can be produced by selective borrowing and screening of alluvial and colluvial materials that cover much of the existing TSF area.

Regardless of the material properties and source of the liner bedding fill layer, some stockpiling of liner bedding fill will be required during construction of the TSF. However, since the material will be utilized during phased construction, temporary liner bedding fill stockpiles inside the TSF footprint can be utilized.

2.4 Structural Embankment Fill

The majority of structural fill required to construct the starter dam and toe berm will be required during initial Phase 1 construction. Based on the conceptual TSF design, starter dam and toe berm will require approximately 2.12 million cy for initial construction, and approximately 0.33 million cy to extend the perimeter berm and starter in subsequent construction phases. It is assumed that the old starter dam and splitter dike will be used as a source of structural fill, thereby reducing new Phase 1 borrow source requirements to approximately 1.2 million cy.

Structural fill materials are readily available within the TSF footprint. It is anticipated that additional borrow sources will be identified in the TSF expansion area when site exploration activities are completed.

The need to stockpile structural fill materials is not anticipated as suitable materials occur westward across the TSF footprint. These materials will be exposed and available throughout phased construction.

2.5 Riprap and Erosion Control Materials

While detailed design of diversion ditches, permanent conveyance channels, energy dissipation structures and spillways has not been performed, it is anticipated that these structures will require armoring for temporary and permanent erosion control. To date, sources suitable for providing riprap have not been identified in the TSF. It is assumed that these materials will be obtained from unmineralized waste rock or the proposed permanent spillway cut. No significant stockpile requirements are expected for erosion control materials.

3.0 STOCKPILES

To summarize the borrow material discussion, external stockpiles will be required for reclamation cover fill and top dressing obtained from within the TSF. These stockpiles will remain active until reclamation construction has been completed. Depending upon the material property requirements of the liner bedding fill layer, an internal stockpile may be required to temporarily store liner bedding fill obtained from borrow sources inside initial construction areas. Drainage materials and structural fill are not anticipated to require permanent or temporary stockpiles.

The material storage requirements for top dressing and reclamation fill are a combined 2.61 million cy. Two external stockpile locations have been identified in the vicinity of the TSF within the permit area. The West Stockpile lies in a small drainage and will require an underdrain system to permit runoff from upgradient areas to pass beneath the stockpile. As shown on Figure 2, the capacity of the West Stockpile is approximately 2.1 million cy. The North Stockpile lies north of Greyback Wash and has a capacity of approximately 1.9 million cy as shown.

To minimize haul distance, it is anticipated that the stockpiles will contain both top dressing and reclamation cover material and will therefore require zoned construction to facilitate recovery of selected materials as needed during reclamation construction. Stockpile design will be completed as part of final TSF design when detailed material storage estimates can be produced.

4.0 DISPOSITION OF EXISTING TAILINGS

Approximately 1.2 million tons of tailings were placed in the north cell of the old TSF between 1982 and 1986. This disposition of old tailings has not been determined, however, two alternatives have been

identified in which the tailings can be utilized as construction material while mitigating potential impacts associated with leaching of sulfate:

- Utilize the tailings as fine grained liner bedding fill; or
- Incorporate the tailings in the structural fill for the starter dam.

If used as liner bedding fill, placement under the geomembrane liner will effectively cap the old tailings and minimize their exposure to infiltration and leaching. Because the new starter dam will be constructed over the future liner system, incorporation of the old tailings the structural fill will put the old tailings within the new containment.

The proposed site exploration plan includes collection of old tailings samples. Use of the tailings as liner bedding or structural fill will be evaluated by geotechnical testing.

5.0 CLOSING

Construction material availability will be reevaluated when geotechnical investigation of the expanded TSF site has been completed. Suitable and sufficient materials for TSF construction exist within the area explored by SHB in 1979-80. More convenient borrow locations may be identified in the TSF expansion area. External stockpile requirements are not expected to change if additional internal borrow sources are identified.

6.0 REFERENCES

Golder Associates Inc., 2010, Copper Flat project Conceptual Design Report. Report prepared for New Mexico Copper Corporation, November, 2010

New Mexico Copper Corporation. 2010, Copper Flat Mine Plan of Operations, Report prepared for U.S. Department of the Interior, Bureau of Land Management

Sergent, Hauskins and Beckwith, 1980, Final Geotechnical and Design Development Report. Report prepared for Quintana Minerals Corporation

Attachments: Figure 1 - Site Location Plan
Figure 2 - Tailings Impoundment Borrow Source and Stockpile Plan

GM/DAK/br

FIGURES



AERIAL PHOTOGRAPH OF PROPOSED TAILINGS DISPOSAL SITE

NOT TO SCALE



STATE OF NEW MEXICO

NOT TO SCALE

PROJECT	COPPER FLAT PROJECT TAILINGS STORAGE FACILITY BORROW SOURCE EVALUATION SIERRA COUNTY, NEW MEXICO
TITLE	**SITE LOCATION MAP**

Golder Associates

PROJECT No.		103-92557	FILE No.	10392557B003
DESIGN	GM	06/02/11	SCALE	NOT TO SCALE
CADD	NIL	06/01/11		1
CHECK	GM	06/02/11		
REVIEW	DAK	06/02/11		

02099

K:\2010 Projects\103-92557 Copper Flat\B-Unassigned\10392557B003.dwg | Layout: 10392557B003 | Modified: nlocascio 06/02/2011 1:53 PM | Plotted: nlocascio 06/16/2011

LEGEND

- EXISTING GROUND CONTOUR (FT. AMSL)
- PERMIT BOUNDARY
- GEOTECHNICAL DRILL HOLE (BY OTHERS)
- TEST PIT (BY OTHERS)
- PAIRED TEST PIT AND GEOTECHNICAL DRILL HOLE (BY OTHERS)
- GEOTECHNICAL DRILL HOLE WITH FALLING HEAD TEST (BY OTHERS)
- TSF FOOTPRINT
- SLOPE INDICATOR
- TAILINGS FROM 1982 TO 1986 OPERATIONS (NO TOP DRESSING STRIPPING)
- FUTURE TOP DRESSING STRIPPING LIMITS
- BORROW AREA - HIGH PLASTICITY CLAYS
- BORROW AREA - FINE GRAVELS, SILTY GRAVELS
- BORROW AREA - STRUCTURAL FILL, RECLAMATION COVER FILL, DRAIN GRAVELS

NOTES

1. TOPOGRAPHY IN THE MINE AREA AND TAILINGS STORAGE FACILITY REPRESENTS EXISTING CONDITIONS AND DISTURBANCE ASSOCIATED WITH QUINTANA 1981-82 MINING OPERATIONS.
2. LINER BEDDING FILL CAN BE STOCKPILED WITHIN THE TSF CONSTRUCTION LIMITS.
3. AREAS SUBJECT TO 1982-1986 TAILINGS DEPOSITION WILL BE EXCLUDED FROM TOP DRESSING STRIPPING OPERATIONS. EXTENT OF TAILINGS TO BE VERIFIED DURING SITE INVESTIGATION FOR EXPANDED FACILITY.

REFERENCES

1. EXISTING FIVE (5) FOOT TOPOGRAPHY AND PERMIT BOUNDARY PROVIDED BY NEW MEXICO COPPER CORPORATION.
2. SITE EXPLORATION LOCATIONS FROM FINAL DESIGN DEVELOPMENT AND GEOTECHNICAL REPORT, SERGENT HAUSKINS AND BECKWITH, 1980. EXPLORATION SITES ARE PROJECTED ON CURRENT TOPOGRAPHY.
3. BORROW MATERIAL REQUIREMENTS BASED ON CONCEPTUAL DESIGN REPORT, GOLDER ASSOCIATES INC., NOVEMBER 2010.

400 0 400 800
SCALE FEET

PROJECT
COPPER FLAT PROJECT
TAILINGS STORAGE FACILITY
BORROW SOURCE EVALUATION
SIERRA COUNTY, NEW MEXICO

TITLE
BORROW AND STOCKPILE PLAN

Golder Associates

PROJECT No.		103-92557	FILE No.	10392557B002
DESIGN	GM	06/02/11	SCALE	AS SHOWN
CADD	NIL	06/01/11	FIGURE	
CHECK	GM	06/02/11		2
REVIEW	DAK	06/02/11		

K:\2010 Projects\103-92557 Copper Flat\Drawings\wet\103925702002.dwg | Layout:2 BORROW AND STOCKPILE PLAN | Modified: rdocarsk 06/02/2011 1:51 PM | Plotted: rdocarsk 06/16/2011

APPENDIX E

Preliminary Spill Contingency Plan

New Mexico Copper Corporation

Copper Flat Project
Spill Contingency Plan

Report Prepared for:

U.S. Department of the Interior
Bureau of Land Management
Las Cruces District Office
1800 Marquess Street
Las Cruces, NM 88005-3370

Report Submitted by:

NEW MEXICO COPPER CORPORATION
2425 San Pedro Dr. Suite 100
Albuquerque, NM 87110
Office: (505) 382-5770

December 2010

02102

TABLE OF CONTENTS

1 FACILITY INFORMATION AND EMERGENCY RESPONSE 1

1.1 Emergency Response Action Plan 1

1.2 Facility Information 1

1.3 Emergency Response Information 3
1.3.1 Notification / Reporting 3
1.3.2 Response Equipment List 5

2 HAZARD EVALUATION AND DISCHARGES 7

2.1 Hazard Evaluation 7
2.1.1 Reagents Used for Processing 7
2.1.2 Hazard Identification 7
2.1.3 Vulnerability Analysis 8
2.1.4 Worst Case Discharge 8

2.2 Discharge Detection Systems 8
2.2.1 Discharge Detection by Personnel 8

3 PLAN IMPLEMENTATION 10

3.1 Response Resources for Small, Medium, and Worst Case Spills 10
3.1.1 Fire Protection 10

3.2 Disposal Plans 11

3.3 Containment and Drainage Planning 11

3.4 Facility Self-Inspection 11
3.4.1 Tank Inspection 12
3.4.2 Secondary Containment Inspection 13

3.5 Response Training 13
3.5.1 Personnel Response Training Logs 13

4 SECURITY 14

5 ACRONYMS AND DEFINITIONS 15

TABLES

Table 2-1 General Spill Response Procedures
Table 3-1 Inspection Tasks Summary

APPENDICES

Appendix A Inspection Checklists and Reporting Forms (*Pending*)
Appendix B Training Outline (*Pending*)
Appendix C Spill Reporting Procedures (*Pending*)
Appendix D Facility Incident Command System (*Pending*)
Appendix E Emergency Contacts and Telephone Call List (*Pending*)
Appendix F Storage and Containment Inventories (*Pending*)

1 FACILITY INFORMATION AND EMERGENCY RESPONSE

This Spill Contingency Plan has been prepared pursuant to Title 43, Part 3809 of the Code of Federal Regulations (CFR) [43 CFR § 3809.401(b)(2)(vi)] which requires development of a contingency plan as part of the Plan of Operations for mining operations. This Plan establishes procedures for response to oil, fuel and hazardous material spills, including control, cleanup and reporting. NMCC has developed this Contingency Plan to respond to spills and to minimize the impacts from spills of oil, fuel, oil-related products, and hazardous substances to the environment.

NOTE: THIS PLAN WILL BE UPDATED AND RESUBMITTED TO THE BLM AS FINAL DESIGNS OF THE OPERATIONAL FACILITIES ARE COMPLETED, AND PRIOR TO ANY MINE-RELATED ACTIVITY AT THE SITE.

The Environmental Manager (EM) has primary responsibility for implementing the Contingency Plan. The EM or his/her designee will be present at the facility during normal working hours.

Secondary containment structures designed to prevent the migration of a spill are part of the design of Facility components and are included in the Plan. Fuel and oil for the diesel and gas-powered equipment will be stored in above-ground, sealed tanks in the processing area. The tanks will be installed on lined pads and surrounded by berms to contain the volume of the largest tank within the secondary containment in the event of a spill or release.

The Contingency Plan will be posted and distributed to site personnel and will be used as a guide in training employees. Emergency reporting procedures will be posted in key locations throughout the project area. NMCC will be responsible for events at the mine site, while contract haulers (i.e., trucking companies) will be responsible for accidents and spills along the transportation routes.

Reporting spills or releases of oil-related materials or hazardous materials to the environment is divided into four categories:

1) Releases requiring internal notification only;
2) Releases also requiring notification to the State of New Mexico;
3) Releases also requiring notification to the National Response Center (NRC) and the local Emergency Planning Committee pursuant to CERCLA or Superfund; and
4) Releases subject to Clean Water Act requirements only.

Determining which of the above categories is appropriate for any particular spill or release depends on the type of material, the amount released, and the circumstances of the spill or release.

1.1 Emergency Response Action Plan

An Emergency Response Plan, which addresses responses to hazardous material releases, large-scale non-hazardous material releases, and natural disasters, will be prepared for the Facility and maintained in the Environmental Department.

1.2 Facility Information

The Copper Flat Mine Project (Project) is located in Sierra County, New Mexico, approximately 30 miles southwest of Truth or Consequences near Hillsboro. The NMCC mailing address is:

New Mexico Copper Corporation

2425 San Pedro Dr. Suite 100
Albuquerque, NM 87110
Office: (505) 382-5770

The area comprised of mine operations components, the Copper Flat Mine Facility (Facility), is anticipated to use diesel fuel, gasoline, motor oil and other petroleum hydrocarbons and chemical reagents. Oil is anticipated to be stored entirely above-ground.

No navigable waters have been defined at the mine facility; however, an intermittent or ephemeral stream called Greyback Wash passes through the pit area and a few springs or seeps occur west of the pit and up-gradient, all of which are tributaries to the Greyback drainage basin to the west of the pit.

The ore body at the Copper Flat Mine Facility is exposed at the surface and will be mined by conventional open-pit methods. The site is located in a semi-arid region of New Mexico with a mean annual precipitation of about 12 inches.

Ore from the pit will be trucked to the plant area east of the pit. The proposed process involves crushing and grinding followed by the addition of non-toxic organic reagents to create a copper laden froth and filtering to form a concentrate. Ore will be crushed or ground and organic reagents added to create froth. Copper minerals will adhere to the bubbles of the froth. The copper will be collected and filtered to form a concentrate. The proposed mill/concentrator plant is a sulfide flotation plant. No leaching processes, including cyanide leaching, are to be used. No smelting will occur at the Project.

For the purpose of grouping oil containment and storage according to distinct areas, the mine site has been delineated by the following anticipated areas or components:

Fuel Storage Island

Fuel and oil for diesel and gas powered equipment will be stored in above-ground, sealed tanks in the processing facilities area. The tanks will be installed on lined pads, consisting of gravel underlain by a plastic liner. The pad area will be surrounded by berms to provide secondary containment for the largest vessel in case of rupture. Surface piping leads from each tank to the fuel dispensing area. The refueling hoses will be equipped with overflow prevention devices and secondary containment.

Bone Yard

The bone yard will contain empty drums which will have the lids removed. The drums will be labeled as to their former contents. The drum storage areas will have secondary containment systems to minimize the potential for spills of oil and grease to the ground surface.

Truck Shop

A garage at the truck shop will contain lube oil containers and oil and transmission fluid drums. The garage will have a cement floor and a containment wall.

Truck Wash

Truck washing will occur on a cement slab with wash water recycled. Overflows of wash water from the tanks will be minimized.

Shop and Warehouse Building

Numerous drums of unopened/unused oil, antifreeze, transmission fluid and acetone will be stored on racks or pallets in the storage areas of the shop and warehouse building. This building will be prefabricated, standard, rigid-framed equipment servicing facility. Secondary containment will be provided, but the drums will not generally be opened at the site, and are only stored until required by mine staff.

Mobile Tanks

Mobile tanks, consisting of emergency power units/trailers, trailers, and "lube" trucks, may be used to store miscellaneous types of oil and fuel. The trailers and lube trucks are used to service other vehicles and equipment throughout the mine site. Due to the transient nature of the mobile tanks, permanent secondary spill containment is not provided. However, mobile tanks will be positioned in areas that are not subject to periodic flooding or washout.

Explosives

Blasting will be done with primacord, ammonium nitrate and fuel oil (ANFO), and emulsion suitable for use where wet holes are encountered. The blasting contractor will mix the components for each blast on an as needed basis. Mixing of the components will be performed at the batch plant operated by the contractor.

Blasting agents will be stored in compliance with applicable MSHA regulations Ammonium nitrate and diesel fuel will be stored on-site in bins and tanks. Storage of detonators, detonating cord, boosters, caps and fuses will be in accordance with the MSHA and New Mexico State Mine Inspectors regulations for explosives. The storage locations for each of these facilities have not yet been selected, but safety and security will be the main factors considered in their location. An inventory of these components will be made. To avoid potential spills, transfer and loading of explosives will be observed at all times by specialized personnel with appropriate training.

Hazardous Materials

No extremely hazardous substances (as defined by 40 CFR § 355) will be used at the Facility. None of the reagents to be used at the facility milling operations are considered to be hazardous materials by the Comprehensive Environmental Response, Comprehension and Liability Act (CERCLA) definition. Hazardous substances identified in CERCLA include all chemicals on the following regulatory lists:

1. Clean Air Act list of hazardous air pollutants (HAPs).

2. Clean Water Act list of hazardous substances and priority pollutants.

3. Solid Waste Disposal Act list of hazardous wastes.

4. Toxic Substances Control Act list of imminent hazards.

1.3 Emergency Response Information

1.3.1 Notification / Reporting

Proper reporting of spills is very critical and must be done carefully and accurately in a timely manner. A spill event notification flow sheet and a call list with contact names and telephone numbers will be developed and submitted to the BLM prior to commencement of site activities. All spills of any quantity are to be reported to the EM for general reporting guidance.

Records and reports of spills and releases shall be maintained for a period of five years by the EM, and will be made available for inspection upon request by EPA or state agency personnel, as required by SPCC Plan regulations.

How to Report

All spills will be reported in accordance with spill event notification flow sheet (see cover pages of this document), followed by completion of a spill/release record (Appendix C) to be submitted to the EM.

In-House Verbal Reporting

After taking immediate action, the person discovering the spill must notify his/her supervisor. The supervisor will notify the Loss Control Department. Loss Control then notifies the EM. Notification will include the information listed below.

- Date and time of spill;
- Type of material spilled and estimated quantity;
- Location of spill;
- Media impacted (soil, surface water, groundwater);
- Damages or injuries;
- Names and numbers of all persons contacted;
- Reason (cause) for spill;
- Action to prevent recurrence (corrective actions);
- Equipment type, equipment number, and tank number;
- Amount of soil added to approved on-site disposal facility;
- Date cleanup action taken; and,
- Name/position/title of person responsible for cleanup action.

If the Loss Control Leader cannot be reached, the EM must be contacted directly. The EM will determine if it is a reportable spill or discharge. If it is determined to be reportable, the EM will report the event and information to the General Manager as soon as possible.

If the Loss Control, General Manager, EM, Maintenance Superintendent or Production Superintendent cannot be reached, the respondent must call Security, who has company and home phone numbers of these persons and other responsible persons.

The EM will notify the appropriate state and federal agencies concerning spills or releases as required. No one but the EM or designated representative, or the General Manager is authorized to call any government agencies concerning spills. This restriction is needed to ensure that only confirmed, accurate information is provided to the regulatory agencies.

In-House Written Reporting

For any spill or release of oil (oils, gasoline, diesel, etc.) outside of a containment area, a complete written report must be submitted to the Environmental Department as soon as possible (usually within 24 hours of the spill). This written report must address the same components for verbal in-house reporting (above) and any additional issues deemed important by operating personnel. The spill reporting form found in Appendix C has been designed to facilitate such written reporting of spills.

Reporting to State and Federal Agencies

The EM or designated representative will execute all reporting to the agencies under the direction of the General Manager. The EM or designated representative will do the following with respect to regulatory reporting:

1. Report immediately any "reportable" (100 gallons or more) oil spill to the State as well as any spill that enters or threatens to enter any river, stream, canal, sewer, drain, lake or pond.
2. Make necessary written reports to the State, National Response Center and other agencies as required. The National Response Center typically does not require a written report of the spill, although one may be requested in certain situations. Verbal notification to the agencies must be made as soon as possible, but not later than after the first working day after the release. In case the EM or designated representative cannot be contacted by the end of the first working day after the release, the verbal report must be made by the General Manager, giving the data listed for verbal in-house reporting. In New Mexico, reporting procedures are as follows:

- Any spill of oil or hazardous materials, which enters directly into water or has the potential to do so, requires immediate verbal notification. "Immediate" has been defined for this situation as "as soon as possible" after the release. The verbal notification may be made by calling the emergency contact telephone numbers as listed in Appendix E.

  During these calls, the state, federal, or local agencies will determine whether a follow-up written report is required. If required, this report would be due within ten (10) calendar days of the release. The required components of the written report will be discussed during the verbal notification. If required, this written report would go to the following as directed by the State:

  - Releases of oil, which do not enter directly into water and do not have the potential to do so, must be dealt with in the following manner: A release of greater than 100 gallons of oil requires verbal notification by the end of the first working day after the release. The EM or a designated representative performs this notification by calling the emergency contact telephone numbers as listed in Appendix E. All releases which fall into this category may require a written follow up report, due within ten (10) calendar days of the release. The required components of the written report will be discussed during the verbal notification. If required, this written report would go to the following as directed by the State:

    New Mexico Environment Department
    PO Box 5469
    Santa Fe, New Mexico 87502-5469

  - Releases of oil greater than 1,000 gallons of oil into or upon navigable waters (or in this case, waters of the State) requires additional notification to the EPA Regional Director (40 CFR § 112.4(a)). The EM or a designated representative does this by contacting:

    United States EPA, Region 6
    1445 Ross Avenue (maps)
    Suite 1200
    Dallas, Texas 75202
    (214) 665-6444

    All releases which fall into this category require a written follow-up report, due within sixty (60) calendar days of the release. The required components of the written report will be discussed during the verbal notification.

1.3.2 Response Equipment List

General Spill Cleanup Materials: Spill cleanup materials will be kept in the Warehouse, and include:

- disposable gloves;
- chemical resistant disposable boots, coveralls;
- short-handled brooms;
- adsorbent rags;
- oil sorbent material;
- approved compatible storage container;
- large plastic bags;
- tape;
- floor sweep;
- soda ash
- short-handled shovels; and

- dustpans.

Large Equipment for Cleanup

The Facility will operate 24 hours a day, 365 days per year. Rubber tire loaders, track dozers, motor graders, and backhoes are available and will be dispatched as needed for spill cleanup.

2 HAZARD EVALUATION AND DISCHARGES

2.1 Hazard Evaluation

2.1.1 Reagents Used for Processing

Following the froth flotation process for the tailings, the remaining slurry, consisting primarily of gangue minerals, pyrite and miscellaneous other un-floated minerals, along with water, flows into a tailings thickener for partial dewatering. Surface runoff, including any potential spills, from the areas around the reagent storage and tailings thickener will be controlled by surface grading and directed to the containment pond. Filtrate from both the copper flotation circuit and the molybdenum flotation circuit will be returned to the concentrate thickeners. Thickener overflow will be returned to the plant reclaim water system.

The molybdenum concentrate will be dried prior to packing into 55-gallon drums for shipment off-site. Provisions have been made to enable the tailings to be diverted around the thickener and discharged directly into the disposal ponds in the event of emergency mechanical problems.

A list of the reagents to be used on the site is included in Appendix F. Flotation collectors, frother and flocculants that are received dry will be mixed in agitated tanks and pumped to outdoor storage tanks and day tanks inside the mill building from which they are metered into the process.

Residual reagent concentrations in the tailings and reclaim water streams are expected to be at very low levels. The collector and promoter flotation reagents (a type 1 reagent) will be added in amounts resulting in concentrations of approximately three parts per million (ppm). This is using an addition rate of 0.02 pounds of reagent per ton of ore and two tons of water to the flotation process. Normally, 95 percent of the reagents are adsorbed onto the copper mineral surface and floated off in the mineral froth. This reagent is subsequently consumed in the off-site smelting process thereby adding its BTU's to the reaction. Using this 95 percent adsorption factor, the residual reagent reporting to the tailing stream drops to <0.15 ppm.

The frother reagent MIBC (a Type 2 reagent) is to be biodegradable in low concentrations as stated by the manufacturer (see Union Carbide MSDS for MIBC). The anticipated dosage rate will be 0.02 pounds per ton of mill feed. The bulk of this reagent will also report to the concentrate fraction and end up at the smelter.

The flocculent reagent (a Type 1 reagent), to be added at 0.016 pounds per ton of mill feed, is also classified as being biodegradable and exhibits a low tolerance to exposure to high pH solutions. Given the 10 to 11 pH range this plant will normally operate at, this reagent will rapidly decompose.

Lime (a type 3 reagent) is used at a rate of 2.7 pounds per ton of mill feed to control pH of the flotation circuit, most of which reacts with sulfide minerals to form gypsum.

Sodium Hydrosulfide (NaHS, a type 3 reagent) will be added to the molybdenum circuit process to effect the copper molybdenum separation. This reagent is rapidly oxidized through contact with the copper minerals and air bubbles entrained in the flotation pulp.

2.1.2 Hazard Identification

A list of the reagents anticipated to be used at the facility is provided in Appendix F. Material Safety Data Sheets (MSDS) for the reagents to be used at the facility will be on file at the site. None of the reagents to be used at the facility milling operations are considered to be hazardous materials by the Comprehensive Environmental Response, Comprehension and Liability Act (CERCLA) definition. Hazardous substances identified in CERCLA include all chemicals on the following regulatory lists:

1. Clean Air Act list of hazardous air pollutants (HAPs).

2. Clean Water Act list of hazardous substances and priority pollutants.
3. Solid Waste Disposal Act list of hazardous wastes.
4. Toxic Substances Control Act list of imminent hazards.

Inventories of bulk storage containers and container storage areas, electrical transformers, and mobile service vehicles, including descriptions of secondary containment, are provided in tables in Appendix F.

2.1.3 Vulnerability Analysis

Reagent spills will be contained by curbs in the reagent mixing and storage areas. A floor sump pump will be used to return spilled material either to the storage tank or into the milling process as necessary.

2.1.4 Worst Case Discharge

A worst-case spill scenario would involve total failure of the primary and secondary containment or failure which would otherwise allow discharge of the contents of the primary containment. The volume of discharge from such a failure could potentially equal the total contents of the tank. The rate at which this flow would occur would depend on the type of product in the tank, the depth of product in the tank, and the size/area of the release opening. For the largest tank, it is conceivable that such flow could equal tens or hundreds of gallons per minute.

The possible spill pathways have been estimated based upon a review of the topographic maps and a mine site inspection. The lateral extent of a spill would be a function of the type of product released, amount of product released, whether the spill was concurrent with a precipitation event, adequacy of the secondary containment, and ground surface cover.

2.2 Discharge Detection Systems

2.2.1 Discharge Detection by Personnel

Small leaks and spills that are confined to small areas will be cleaned up as part of the facility's SOPs. In cases where a medium or large (worst-case) leak has occurred but is confined to facility property, cleanup will proceed as follows:

In the case of a medium spill, direct response measures include:

1. Stop the leak by plugging the leak and/or closing the valve and ensure that the spill is totally contained.
2. Clean up the spill in accordance with general spill response procedures (Table 2-1). Facility employees under the direction of the authorized person or direct Supervisor will conduct the cleanup operation.

In the case of a large spill, direct response measures include:

1. Terminate the source of the flow of petroleum or chemical product.
2. Dig a trench or dike or do whatever else is necessary to confine the area of the spill or to stop it from entering a waterway. Never clear away spills with water! Water tends to mobilize a spill. Instead, use the most appropriate oil-absorbent materials, such as those contained in the spill cleanup kits, to prevent petroleum products from flowing into watercourses.
3. Plug floor drains, place sorbent materials around the spill or take other actions to minimize environmental damage. Sorbent materials will be stocked at the main warehouse.

4. Immediately initiate reporting procedures. The Loss Control Department, Mine Manager or EM must be notified (by radio or phone). The Control Room Operator will follow the Dispatch Emergency Communication Procedures (Appendix D).
5. After the response measures and reporting functions have been accomplished, cleanup will begin in accordance with general spill response procedures (Table 2-1). Should facility personnel be unable to perform the appropriate cleanup operation, and it is necessary for cleanup to begin immediately, the General Manager will utilize outside contractors. Unauthorized site personnel must not notify contractors directly. The General Manager has assigned certain individuals the responsibility of contacting outside contractors with a facility contract.

Table 2-1: General Spill Response Procedures

Spill Event:	Incidental (collected within secondary containment)	Significant (breaching of secondary containment)	Significant (available personnel unable to contain spill after attempting direct response measures)
Close Valve/Discharge Equipment	•	•	•
Mobilize Mine Equipment to Containerize Spill		•	
Use Sorbent Materials to Facilitate Containment		•	
Notify General Manager			•
Excavate Contaminated Soil and Transfer to Landfill, Pump Liquid for Off-Site Disposal	•	•	•
Notify Environmental Department for Transfer Approval	•	•	•
Repair/Replace Tank/Piping/ Discharge Equipment as Necessary	•	•	•

3 PLAN IMPLEMENTATION

In the event of an oil, fuel or chemical reagent spill, facility personnel will implement control procedures as summarized in the following table and detailed in the following sections. Response measures have been designed to mitigate the possibility of oil reaching waters of the State. Response measures include containing the spill, stopping the leak, and cleaning up the spill with the most effective means available. Facility employees will undertake these measures immediately when there is any danger of oil entering any waters of the State and in case of any oil spill.

3.1 Response Resources for Small, Medium, and Worst Case Spills

Small leaks and spills that are confined to small areas will be cleaned up as part of the facility's SOPs. In cases where a medium or large (worst-case) leak has occurred but is confined to facility property, cleanup will proceed as indicated in Section 2.3.1. Spill response equipment and materials are listed in Section 1.3.2.

For spills on gravel or soil, it may be possible to absorb some of the liquid with absorptive material or remove some of the liquid before removing the gravel or soil. Following approval of the Environmental Department, all contaminated gravel or soil will be removed and transported to an approved facility for disposal.

Spills on solid surfaces may be collected with absorptive materials and then cleaned thoroughly with rags wetted with a non-hazardous solvent if needed. Sufficient quantities of sorbent material and other cleanup equipment will be maintained at the warehouse facility to provide for cleanup.

If there is a small amount of water with the spilled oil, the water and the oil may be absorbed in sand, sawdust, or commercial adsorbents and disposed of per the Environmental Department's directions. Any residual sediment or sludge will also be cleaned up and also disposed of per the Environmental Department's directions.

3.1.1 Fire Protection

A fire protection system will be installed in the administration and warehouse complexes, truck shop, crushing plant and process plant. This system will incorporate Sierra County Code requirements. Hydrants will be located near all buildings. A 100,000-gallon fire water reserve will be stored in a water storage tank located sufficiently above and near the mill and crushing area to provide adequate water pressure. A fuel break will be constructed around the facilities. Water trucks, used for dust suppression, will be available in the event of a fire. One mine rescue vehicle will be located on-site in the event emergency transportation is required.

NMCC will promptly comply with any emergency directives and requirements of Sierra County, and the BLM requirements pertaining to industrial operations during the fire season.

NMCC will train an in-house fire brigade in the proper use of fire suppression equipment. In addition, the Sierra County Fire Protection Officer will provide advice on methods to maximize the benefit of equipment and to provide assistance in training Project personnel in fire fighting procedures and drills. The Hillsboro Voluntary Fire Department will be advised as the nature of materials that will be transported through town on a routine basis. Sierra County presently has spill response capabilities and all trucking contractors will be in compliance with 49 CFR and U.S. Department of Transportation regulations, to aid in the reducing the potential for spills and accidents and for mitigating releases that may occur during transport of hazardous materials. In the event of a release, the contract transportation company would be responsible for response and cleanup. Additional specialized training is required for drivers of tank trucks, such as those transporting acid.

3.2 Disposal Plans

Spent cleanup material, residual spilled oil, and hydrocarbon-contaminated soil will be properly disposed of in accordance with applicable state and federal regulations either in an on-site facility or at an approved off-site facility authorized to accept the type of waste.

3.3 Containment and Drainage Planning

Spill prevention and spill control requirements for the Facility include the following:

Spill Prevention

- Inspection and maintenance of oil, fuel and chemical reagent storage containers and transfer points;
- Testing of primary storage containers;
- Facility personnel training on SCP Plan implementation;
- Security; and
- Oil and fuel transfer procedures.

Spill Control

- Facility drainage; and
- Structural controls and equipment (diversion and secondary containment).

Storage tanks determined to not be in conformance with appropriate spill prevention guidelines will be corrected as soon as possible. All oil products are to be stored in above-ground steel tanks and provided with secondary containment unless otherwise noted.

At oil or fuel transfer points, vendor personnel are required to remain with the transport vehicle and observe the tank filling at all times. As filling takes place, vendor personnel are required to remain attentive to the tank level indicators to prevent tank overfills. Connection of the tank fill lines takes place before the master flow control valve is opened. Piping to the tanks will be equipped with back flow prevention devices (check-valves). After filling, the master flow control valve will be closed before disconnecting the fill hoses. A bucket will be placed below the fill valves during tank filling to contain any discharge. A service vehicle will then evacuate this bucket, as necessary.

Secondary containment will be provided for all permanently located oil, fuel and chemical reagent storage tanks, as well as for fill and dispenser points, to minimize the potential for a discharge to reach waters of the State. Secondary containment for each storage tank will have sufficient capacity to contain the contents of the largest tank in a containment area and sufficient freeboard to allow for precipitation. The minimum total volume for uncovered secondary containment is the capacity of the largest tank within the secondary containment plus the depth of rain for the 100-year, 24-hour storm event for the site or region. Fill and dispenser points will have incidental spillage containment such as curbed concrete pads and sumps.

3.4 Facility Self-Inspection

The Facility will be inspected frequently for leaks, liquid accumulation, and need for preventive maintenance. Monthly inspection forms are provided in Appendix A. Completed inspection forms will be submitted to the Mine Manager and the EM. The Environmental Department will maintain all completed forms and checklists related to this Plan for a period of at least three years. The EM's designee will ensure each storage/transfer area is inspected monthly with responses to spills or preventative maintenance tasks to be completed as indicated in Table 3-1.

Table 3-1: Inspection Tasks Summary

Observation	Report Spill (Appendix C)	Implement Controls & Countermeasures	Close	Repair & Replace as Necessary	Pump and Transfer Off-Site for Disposal	Notify Environmental Department for Approval
Spill (outside secondary containment area)	●	●				
Open valves/Dispenser equipment			●	●		
Inoperative liquid level gauge				●		
Physical deterioration to tank/foundation/ Piping (i.e., rusting, pitted)				●		
Inadequate tank/pipeline support (i.e., no tank anchor straps)				●		
Ineffective secondary containment (i.e., no anchoring of liner, tear in liner)				●		
Presence of free liquid in secondary containment, overfill containment areas and sumps					●	●

3.4.1 Tank Inspection

All tanks will be visually inspected monthly by personnel designated by the EM. Visual inspections will be conducted with respect to the following:

- Ensure the tank fill valves and dispenser points are in the closed position when not in use.
- Inspect all valves for signs of leakage or deterioration.
- Check inlet and outlet piping, as well as tank flanges for leakage.
- Inspect pipe/tank supports, foundations and anchoring straps for wear.
- Check tank level indicators and dispenser equipment for proper operating condition.
- Inspect the tank shell surfaces for areas of rust or other signs of deterioration. Particular attention will be paid to areas with peeling paint (or other coating), welds, and seams.
- Check the surfaces below tanks and oil transfer points areas for obvious signs of leaks or spills, specifically stained or visibly damp soils.

- Inspect all sumps and other overfill containment areas located below oil transfer points, and empty liquid as necessary. Consider liquid to be oil-contaminated, and following approval of the Environmental Department, remove for off-site disposal/recycling by personnel authorized to conduct this type of activity.
- Examine tank shells, welds, rivets and bolts for wear and discoloration. Examine all above-ground valves and pipelines for the general condition of flange joints, expansion joints, valve glands and bodies, catch pans, pipeline supports, and condition of metal surfaces.
- Tanks or oil storage containers that appear to be unused or inactive shall be verified as such, and if so, any remaining product shall be removed and disposed of, and the tank triple-rinsed in accordance with facility Standard Operating Procedures (SOPs) or with the use of an outside service. The tank will be modified if necessary to prevent physical access, and labeled with a legible sign indicating "empty" and "do not use". If it is anticipated that the tank will no longer be used, procedures shall be implemented to remove the tank for disposal at an authorized facility.

Each aboveground container is inspected and/or tested for integrity on a regular schedule and whenever material repairs are made. NMCC provides training for personnel on performing container tests and inspections. Examples of integrity tests may include, but are not limited to: visual inspection, hydrostatic testing, radiographic testing, ultrasonic testing, acoustic emissions testing, or other systems of non-destructive testing. The frequency and type of testing and inspections depend on the container size, configuration, and design (e.g., shop-built, field-erected, skid-mounted, elevated, double-walled).

3.4.2 Secondary Containment Inspection

Secondary containments will be inspected on a routine schedule to document the condition of containment structure(s) and indicate any necessary repairs or maintenance.

Prior to draining or pumping any accumulated fluid from an oil storage containment area, verification of possible contamination will be conducted. A visual inspection of the accumulated water to determine whether or not a sheen is present will be considered sufficient verification that no contamination is present.

If a sheen is noted, the water will be collected and off-site disposal arranged as directed by the Environmental Department. If no sheen is observed, the water may be drained or pumped out of the containment area and applied to a designated on-site facility following approval of the Environmental Department.

3.5 Response Training

Key facility employees, who are directly involved with managing oil, fuel and/or chemical reagent storage and transfer operations, are regularly trained in implementing the Contingency Plan to minimize the number of human errors that cause oil spills. Employee training will be performed annually; new employees will be trained within one week of beginning work. An outline used to facilitate training of new employees and refresher training of existing employees is provided in Appendix B.

3.5.1 Personnel Response Training Logs

Records of response training will be maintained in the environmental master files.

4 SECURITY

Only authorized personnel will be allowed to enter the facility property. Tank locations that may require operations at night will be equipped with sufficient lighting to assist in security and provide visibility for operations to be performed. Tanks located in high traffic areas will be barricaded to minimize collisions from occurring.

5 ACRONYMS AND DEFINITIONS

The following definitions are presented below in order to understand the scope of this Plan. The definitions are from, and provided in, 40 CFR §112.2.

Oil: means oil of any kind or in any form, including, but not limited to petroleum, fuel oil, sludge, oil refuse, fats, greases, and oil mixed with other than dredged spoil. At the facility, oils stored include diesel fuel, gasoline, hydraulic oil, miscellaneous lube oils, grease, and motor oils.

Discharge: includes but is not limited to, any spilling, leaking, pumping, pouring, emitting, emptying, or dumping.

Reportable Spill: means a discharge of oil into or upon the navigable waters of the United States or adjoining shorelines in harmful quantities, as defined in 40 CFR §110, which states, discharges of oil that:

- Violate applicable water quality standards, or
- Cause a film or sheen upon or discoloration of the surface of the water or adjoining shorelines or cause a sludge or emulsion to be deposited beneath the surface of the water or upon adjoining shorelines (40 CFR §110.3).

At the facility, visual inspections using the second definition above will be used to determine whether a discharge constitutes a reportable spill event as detailed in Section 4 of the SPCC Plan.

Contract: means:

- A written contractual agreement with an oil spill removal organization(s) that identifies and ensures availability of the necessary personnel and equipment within appropriate response times; and/or
- A written certification by the owner or operator that the necessary personnel and equipment resources, owned or operated by the facility owner or operator, are available to respond to a discharge within appropriate response times.

Reportable spill events are regulated by the NMED, which requires notification within 24 hours if a discharge occurs in such quantity as may with reasonable probability injure or be detrimental to human health. In addition, as indicated in 40 CFR §112.4(a), whenever a facility has discharged more than 1,000 U.S. gallons of oil into or upon the navigable waters of the United States or adjoining shorelines in a single spill event, or discharged more than 42 U.S. gallons of oil in each of two discharges as described in 40 CFR § 112.1(b) into or upon the navigable waters of the United States or adjoining shorelines, occurring within any twelve month period, the owner or operator of such facility shall submit to the Regional Administrator, within 60 days, a detailed spill report.

Navigable waters (as defined in 40 CFR §110.1) are not present at the Copper Flat Mine Facility. Other waters in the vicinity include the intermittent stream Greyback Wash to the west of the pit and a few springs or seeps west of the pit.

Waters of the State, as defined by the State of New Mexico, include all interstate and intrastate waters, including natural ponds and lakes, playa lakes, reservoirs, perennial streams and their tributaries, intermittent streams, sloughs, prairie potholes and wetlands (WQCC 91-1, 1995). This State definition indicates additional waters that must be considered for impact by an oil spill at the facility.

Appendix A

Inspection Checklists and Reporting Forms

(*Pending*)

Appendix B

Training Outline

(*Pending*)

Appendix C

Spill Reporting Procedures

(*Pending*)

Appendix D

Facility Incident Command System

(*Pending*)

Appendix E

Emergency Contacts and Telephone Call List

(*Pending*)

Appendix F

Storage and Containment Inventories

(*Pending*)

APPENDIX F

Quality Assurance Plan

(Intera, 2010)

New Mexico Copper Corporation

Quality Assurance Project Plan

Copper Flat Mine Site

September 2010

Prepared for:
New Mexico Copper Corporation

Submitted to:
Mining and Minerals Division
New Mexico Energy, Minerals and Natural Resources Department

Prepared by:

INTERA

02127

TABLE OF CONTENTS

Abbreviations and Acronyms iii

1 Project Description and Management 1

1.1 Project Definition and Background 1

1.2 Quality Objectives and Criteria 1

1.2.1 Measurement Quality Objectives for Analytical Laboratory Data 1
1.2.2 Measurement Quality Objectives for Meteorological and Air Quality Data 3
1.2.3 Measurement Quality Objectives for Ecological Data 4
1.2.4 Measurement Quality Objectives for Cultural Resources Data 4

1.3 Project Organization 4

1.4 Special Training and Certification 4

1.4.1 Health and Safety Training 4

1.5 Documents and Records 5

1.5.1 Field Documentation 5

2 Data Generation and Acquisition 5

2.1 Sampling Design 5

2.2 Field Activities 6

2.3 Sample Handling and Custody 6

2.4 Laboratory QA/QC 7

2.5 Equipment Testing, Inspection, Maintenance, and Calibration 8

3 Inspection and Acceptance of Supplies and Consumables 8

4 Data Management 8

5 Assessment, Response Actions, and Reports to Management 9

6 Data Evaluation and Usability 9

6.1 Laboratory Data Verification 9

6.2 Laboratory Data Evaluation and Usability 10

7 Reconciliation with User Requirements 10

8 References 10

LIST OF FIGURES

Figure 1 INTERA Organizational Flow Chart
Figure 2 Parametrix Organizational Flow Chart

LIST OF TABLES

Table 1 Key Personnel and Responsibilities

Abbreviations and Acronyms

CFR	Code of Federal Regulations
COC	chain of custody
CPR	cardiopulmonary resuscitation
DQA	data quality assessment
EPA	United States Environmental Protection Agency
ER	equipment rinsate
FTL	field team leader
ID number	identification number
LCS	laboratory control sample
MDL	method detection limit
MMD	New Mexico Mining and Minerals Division
MQO	measurement quality objectives
MS	matrix spike
NMCC	New Mexico Copper Corporation
NMWQCC	New Mexico Water Quality Control Commission
OSHA	Occupational Safety and Health Administration
PARCC	precision, accuracy, representativeness, completeness, and comparability
PM	Project Manager
PPE	personal protective equipment
PRRL	project-required reporting limits
QA	quality assurance
QAPP	quality assurance project plan
QC	quality control
RPD	relative percent difference
SAP	sampling and analysis plan
Site	Copper Flat Mine Permit Area
SQL	sample quantitation limits

1 Project Description and Management

This document establishes the quality standards for products and services that have been established within the industry and through government regulations. New Mexico Copper Corporation (NMCC) and its contractors shall meet or exceed these quality standards throughout the duration of this project.

NMCC is currently initiating permitting activities for the re-opening of the Copper Flat Mine located approximately six miles northeast of Hillsboro, New Mexico, in Sierra County (Site). NMCC and its contractors will assess baseline conditions of for climate, vegetation, wildlife, topsoil, surface water, groundwater, and historical and cultural properties.

The project organizational flow chart for NMCC's geosciences and engineering contractor, INTERA Incorporated (INTERA) of Albuquerque, New Mexico, identifies key personnel and their functions (Figure 1). The INTERA Incorporated (INTERA) Program Manager, Cynthia Ardito, is responsible for project direction and quality assurance (QA) for this project. The Project Manager (PM), Peter Castiglia, is responsible for organizing and implementing field activities, project oversight, data management, and report preparation. Mr. Castiglia is also responsible for ensuring that the Quality Assurance Project Plan (QAPP) and Sampling and Analysis Plan (SAP) are appropriately developed and adhered to. The PM, Dr. John Sigda, is responsible for data analysis and modeling. Dr. Sigda will also provide technical support and will assist in data management and report preparation. INTERA's subcontractors include Class One Technical Services, Inc. of Albuquerque, New Mexico, for air quality services, and Hall Environmental Analysis Laboratories (HEAL) for analytical laboratory services. Subcontractor PMs will be responsible for QA, project oversight, data management, and coordination of field activities.

NMCC has contracted with Parametrix Incorporated of Albuquerque, New Mexico, for ecological and cultural resources services. Parametrix will be responsible for data collection for these resource areas. An organizational chart is included as Figure 2. The Parametrix PM, Mr. Jens Deichmann, is responsible for data collection and data quality. For geologic sampling, NMCC has contracted with SRK Consulting Engineers (SRK). The SRK PM is Mr. Mark Willow. The principal geochemist supporting Mr. Willow and overseeing the geologic sampling program is Dr. Robert Bowell.

1.1 Project Definition and Background

A 12-month baseline characterization of pre-mining site conditions must be completed prior to submittal of a Mine Permit Application to the New Mexico Energy, Minerals, and Natural Resources Department Mining and Minerals Division (MMD). As noted previously, this baseline characterization involves sampling, analysis, and assessment of site-specific climatic, vegetation, wildlife, soil, surface water, groundwater, and historical and cultural properties conditions. The MMD requires that a SAP be submitted for agency review. The SAP is a detailed work plan that describes how baseline data will be collected. The SAP must thoroughly describe the proposed sampling methodology and frequency, proposed data sources, and proposed sampling locations to document existing resource conditions within the permit boundary.

1.2 Quality Objectives and Criteria

The following sections present the measurement quality objectives (MQO) identified for this project.

1.2.1 Measurement Quality Objectives for Analytical Laboratory Data

All analytical results for water samples will be evaluated in accordance with precision, accuracy, representativeness, completeness, and comparability (PARCC) parameters to document the quality of the data

and promote data that are of sufficient quality to meet the project objectives. With regard to these PARCC parameters, precision and accuracy method blanks will be prepared at the frequency prescribed in the individual analytical method, or at a rate of 5 percent of the total samples if a frequency is not prescribed in the method. The subsections below describe each of the PARCC parameters and how they will be assessed for this task.

1.2.1.1 Precision

Precision is the degree of mutual agreement between individual measurements of the same property under similar conditions. Usually, combined field and laboratory precision is evaluated by collecting and analyzing field duplicates and then calculating the variance between the samples, typically as a relative percent difference (RPD).

$$RPD = \frac{|A - B|}{(A + B)} \times 100\%$$

where:

A = First duplicate concentration
B = Second duplicate concentration

Field sampling precision is evaluated by analyzing field duplicates. One duplicate groundwater sample will be collected during the initial groundwater sampling event to establish laboratory analytical precision at the onset of the investigation. The duplicate groundwater sample will be collected by completely filling two separate vials by alternating between the primary sample set and the replicate sample set in the order shown below:

- Fill vial #1 - primary sample set
- Fill vial #1 - replicate sample set
- Fill vial #2 - primary sample set
- Fill vial #2 - replicate sample set

Laboratory analytical precision is evaluated by analyzing matrix (laboratory) duplicates. Results for each laboratory duplicate pair will be used to determine the RPD in order to evaluate precision.

1.2.1.2 Accuracy

A program of sample spiking will be conducted to evaluate laboratory accuracy. This program will include analysis of matrix spike (MS), laboratory control samples (LCS) or blank spikes, and method blanks. The results for the spiked samples will be used to calculate the percent recovery for use in evaluating accuracy.

$$\text{Percent Recovery} = \frac{S - C}{T} \times 100\%$$

where:

S = Measured spike sample concentration
C = Sample concentration
T = True or actual concentration of the spike

Results that fall outside the accuracy goals will be further evaluated on the basis of the results of other quality control (QC) samples.

1.2.1.3 Representativeness

Representativeness expresses the degree to which sample data accurately and precisely represent: (1) the characteristics of a population, (2) variations in a parameter at a sampling point, or (3) an environmental condition that they are intended to represent.

Representativeness of data will also be promoted through the consistent application of established field and laboratory procedures. Equipment rinsate (ER) blanks and laboratory blanks will be evaluated for the presence of contaminants to aid in evaluating the representativeness of sample results. Data determined to be non-representative by comparison with existing data will be used only if accompanied by appropriate qualifiers.

1.2.1.4 Completeness

Completeness is a measure of the percentage of project-specific data that are valid. Valid data will be obtained when samples are collected and analyzed in accordance with QC procedures as outlined in this QAPP and when none of the QC criteria that affect data usability are exceeded. When all data evaluation is completed, the percent completeness value will be calculated by dividing the number of useable sample results by the total number of sample results planned for this investigation.

As discussed further in Section 8.0, completeness will also be evaluated as part of the data quality assessment process (EPA, 2000b). This evaluation will help assess whether any limitations are associated with the decisions to be made based on the data collected.

1.2.1.5 Comparability

Comparability expresses the confidence with which one data set can be compared with another. Comparability of data will be achieved by consistently following standard field and laboratory procedures and by using standard measurement units in reporting analytical data.

1.2.1.6 Detection and Quantitation Limits

The method detection limit (MDL) is the minimum concentration of an analyte that can be reliably distinguished from background noise for a specific analytical method. The quantitation limit represents the lowest concentration of an analyte that can be accurately reproduced in a sample matrix. Project-required reporting limits (PRRL) are contractually specified minimum quantitation limits for specific analytical methods and sample matrices, such as soil or water, and are typically several times the MDL to allow for matrix effects. PRRLs, which are established in the project scope of work for subcontract laboratories, are set to establish minimum criteria for laboratory performance. Actual laboratory quantitation limits may be substantially lower.

For this project, analytical methods have been selected so that the PRRL for each target analyte is below the applicable regulatory screening criteria, the New Mexico Water Quality Control Commission (NMWQCC) Standards for groundwater. Also, sample concentrations will be reported as estimated values if concentrations are less than PRRLs but greater than MDLs. The MDL for each analyte will be listed as the detection limit in the laboratory's electronic data deliverable.

1.2.2 Measurement Quality Objectives for Meteorological and Air Quality Data

Laboratory and field quality assurance procedures for meteorological and air quality data are described in detail in Section 2 of the Sampling and Analysis Plan (SAP). Please refer to Section 2.8 of this SAP for more information.

1.2.3 Measurement Quality Objectives for Ecological Data

A single field crew chief will be assigned to ensure data collection is consistent between crews. This individual will review a sub-set of the field forms following each field day. Formalized data collection training will also be completed prior to field sampling. All field botanists will be familiar with plant systematics and techniques to identify plants using taxonomic keys. Plant species not readily identifiable in the field will be collected and preserved for identification at the University of New Mexico Herbarium.

Vegetation material produced during the previous growing season will be discarded before placing samples into a paper bag. Rocks, soil, and/or litter will not be placed into sample bags. Biomass production will only be calculated as an actual dry-weight sample. No double sampling or estimations will occur.

Field data entered into an electronic format such as MS Excel or Access will be evaluated for integrity, consistency, and completeness before data analysis. Oversights or incorrect entries will be corrected. A sub-set of the field forms will be compared to the electronic version for an accuracy assessment. If significant differences are identified, a thorough re-evaluation of each of the forms will be completed.

For wildlife data, field biologists will have a minimum of a BA/BS in Biology and five to ten years of field experience conducting a wide variety of animal surveys ranging from reptiles and amphibians, to birds, mammals, insects, and other invertebrates. This includes experience in recognizing and identifying signs of wildlife. All findings and results will be reviewed by senior scientists.

1.2.4 Measurement Quality Objectives for Cultural Resources Data

Reporting will follow the standards in BLM manual H-8100-1, Chapter 1.B.1 and Appendix 2 (2005). In addition, work will be performed in compliance with all aspects of the NMAC, including NMAC 4.10.15.

1.3 Project Organization

Table 1 presents the roles and responsibilities for key personnel who will be involved in the investigation at the Site. In some cases, more than one responsibility has been assigned to one person.

1.4 Special Training and Certification

This section outlines the training and certifications required to complete the activities described in this QAPP. The following sections describe the requirements for personnel working on-site.

1.4.1 Health and Safety Training

INTERA Personnel who collect water and sediment samples from the Site are required to meet the Occupational Safety and Health Administration (OSHA) training requirements defined in Title 29 of the Code of Federal Regulations (CFR) Part 1910.120(e). These requirements include (1) 40 hours of formal off-site instruction, (2) a minimum of three days of actual on-site field experience under the supervision of a trained and experienced field supervisor, and (3) 8 hours of annual refresher training. Field personnel who directly supervise employees engaged in work at the site shall also receive at least 8 additional hours of specialized supervisor training. The supervisor training covers health and safety program requirements, training requirements, personal protective equipment (PPE) requirements, the spill containment program, and health-hazard monitoring procedures and techniques. Every member of the field team will maintain current certification in the American Red Cross “Multimedia First Aid,” and “Cardiopulmonary Resuscitation (CPR) Modular,” or equivalent.

Copies of health and safety training records, including course completion certificates for the initial and refresher health and safety training, specialized supervisor training, and first aid and CPR training, are maintained in corporate files.

1.5 Documents and Records

Documentation is critical for evaluating the success of any environmental data collection activity. The following sections discuss the requirements for documenting field activities and for preparing laboratory data packages. This section also describes reports that will be generated as a result of this project.

1.5.1 Field Documentation

Field personnel will use permanently bound field logbooks with sequentially numbered pages to record and document field activities. The logbooks will list a contract name and number, the project number, the site name, the names of subcontractors, the client, and the PM. At a minimum, the following will be recorded in the field logbook:

- Names and affiliations of all on-site personnel or visitors
- Weather conditions during the field activity
- Summary of daily activities and significant events
- Notes of conversations with coordinating officials
- References to other field logbooks or forms that contain specific information
- Discussions of problems encountered and their resolutions
- Discussions of deviations from the SAP or other governing documents
- Descriptions of all photographs taken

The field team may also use the field forms during certain sampling or data collection activities to document field activities. The same level of detail will be required for all field forms used during this investigation. Copies of the completed field forms will be stored in the project file.

2 Data Generation and Acquisition

This section describes the requirements for the following:

- Sampling Design (Section 2.1)
- Field Activities (Section 2.2)
- Sample Handling and Custody (Section 2.3)
- Laboratory Quality Assurance/Quality Control (QA/QC) (Section 2.4)
- Equipment Testing, Inspection, Maintenance, and Calibration (Section 2.5)

2.1 Sampling Design

Samples or data will be collected as outlined in the SAP. The SAP for this project is a collection of quarterly or one-time field sampling or data collection events that were prepared by NMCC and its contractors. Field activities will be implemented to optimize the time spent in the field by adhering to established scientific methods and procedures, leading coordinated field schedules, and sharing data with contractors to minimize duplication of data.

Data collected from these field activities will be used in the mine permitting process. This baseline data will also be useful in the design of mine facilities and as a reference during site reclamation activities.

2.2 Field Activities

Field activities have been broken into eight separate activities. These activities, which are outlined in the SAP, will be used to establish the baseline conditions at the Site:

- Climatological factors – The purpose of the monitoring program will be to collect baseline climatological data representative of the Site that satisfies the criteria of the New Mexico Surface Mining Act and the U.S. Environmental Protection Agency (EPA) on-site meteorological program guidance for dispersion modeling
- Vegetation survey – The purpose of the survey is to delineate current vegetation stratified according to disturbance history and to describe specific vegetation attributes for plant communities delineated within the Site. In addition, the survey will identify the presence of potential habitat for threatened and endangered species.
- Wildlife survey – Delineate and map current habitat, describe wildlife use of the area, complete a bird species inventory, complete a threatened or endangered species survey by comparing known records and habitat requirements with current field conditions to determine the likelihood of occurrence of all federal and state listed wildlife species, and determine species distribution by habitat and season.
- Soil survey and sampling – To determine the suitability of in-place soils in areas of proposed disturbance for use as a topdressing material during reclamation.
- Surface water sampling – To characterize the volumetric flow and water quality of seeps, springs, streams, and the pit lake.
- Groundwater sampling – To obtain necessary data to evaluate quantity and quality of all aquifers at the Site that could be impacted by mining activities, address data gaps identified during evaluation of the Draft EIS (BLM, 1996), meet the requirements set forth in the regulations in NMAC Title 19, Chapter 10, Part 6, and to meet the guidelines set forth in MMD's draft Guidance Document for Part 6 New Mining Operations Permitting under the New Mexico Mining Act.
- Historical and cultural properties survey – To locate and assess all cultural resources and historic properties within the area of potential effects.

2.3 Sample Handling and Custody

The following section describes sample handling procedures, including sample identification and labeling, documentation, chain of custody (COC), and shipping. This section applies to water, sediment, and geologic samples that are submitted to an analytical laboratory. Other sample handling and custody procedures for vegetation and other resources are described, where appropriate, in the SAP.

Each sample collected at the Site will be identified using a unique sample identification (ID) number. The description of the sample type and the point name will be recorded on the COC form, as well as in the field notes. Note that field duplicates and ERs will be given a unique sample ID. The association between primary, duplicate, and ER samples will be noted on the COC form.

A sample label will be affixed to each sample container. The label will be completed with the following information written in indelible ink: project name and location, sample ID number, date and time of collection,

preservative used (if applicable), collector's initials, and analysis requested. After labeling, each sample will be refrigerated or placed in a cooler containing ice.

Documentation of sample collection will be completed in permanent black or blue ink in the field logbook. All entries will be legible. The field team leader (FTL) and sampling personnel are responsible for proper documentation of all Site activities.

Standard sample custody procedures will be used to maintain and document sample integrity during collection, transportation, storage, and analysis. COC procedures provide an accurate written record that traces the possession of individual samples from the time of collection in the field to the time of acceptance at the laboratory.

The COC form will be placed in a waterproof plastic bag and taped to the inside of the shipping container used to transport the samples. The laboratory sample custodian will receive all incoming samples, sign the accompanying COC forms, and retain copies of the forms as permanent record. The laboratory sample custodian will record all pertinent information concerning the samples, including the persons delivering the samples, the date and time received, sample condition at the time of receipt (sealed, unsealed, or broken container; temperature; or other relevant remarks).

All samples will be either hand delivered or shipped to an accredited laboratory. Samples may need to be shipped to the laboratory in order to have them analyzed before the expiration of a particular sample's holding time.

2.4 Laboratory QA/QC

This section applies to water, sediment, and geologic samples submitted to accredited analytical laboratories. To ensure quality of laboratory analysis, the analytical laboratory will be required to analyze QA/QC samples as specified by the analytical methods. The laboratory will analyze method blanks, MSs, and LCSs.

Method blanks will be prepared at the frequency prescribed in the individual analytical method or at a rate of 5 percent of the total samples if a frequency is not prescribed in the method.

MSs will be analyzed at a frequency of 5 percent for soil and aqueous samples. The percent recoveries will be calculated for each of the spiked analytes and used to evaluate analytical accuracy. The RPD between spiked samples will be calculated to evaluate precision.

LCSs, or blank spikes, will be analyzed at the frequency prescribed in the analytical method or at a rate of 5 percent of the total samples if a frequency is not prescribed in the method. If percent recovery results for the LCS or blank spike are outside of the established goals, laboratory-specific protocols will be followed to gauge the usability of the data.

Sample quantitation limits (SQL), also referred to as practical quantitation limits, are PRRLs adjusted for the characteristics of individual samples. The PRRLs are chemical-specific levels that a laboratory should be able to routinely detect and quantitate in a given sample matrix. The PRRL is defined in the analytical method or in laboratory method documentation, and incorporates precision (reproducibility) assumptions for the analysis. The SQL takes into account changes in the preparation and analytical methodology that may alter the ability to detect an analyte, including changes such as use of a smaller sample aliquot or dilution of the sample extract. Physical characteristics such as sample matrix and percent moisture that may alter the ability to detect the analyte are also considered. The laboratory will calculate and report SQLs for all environmental samples.

The laboratory activities are overseen by a comprehensive quality assurance program to assure that laboratory practices and results adhere to its policies. The laboratory will provide a standard QA/QC report with all reports. This includes surrogate recoveries, spike recoveries, and method blanks.

The laboratory participates in the Wibby Environmental, third party, proficiency testing program. Wibby is accredited by A2LA and NIST/NVLAP. Results of all proficiency results are sent, by Wibby, to both the laboratory and to their accrediting authorities. The laboratory will also perform proficiency testing on a semiannual basis for all accredited tests. Water proficiencies in the water supply and water pollution studies will be performed in addition to soil proficiencies in hazardous waste pollution studies.

Proficiency results are reviewed by the laboratory manager and all personnel involved in reporting the data. Results that are marked as "check for error" and "unacceptable" are thoroughly reviewed and corrective actions are written for "unacceptable" data.

2.5 Equipment Testing, Inspection, Maintenance, and Calibration

All equipment used during the investigation will be properly tested, inspected, maintained, and calibrated. Samples collected during this investigation will be analyzed using both field and laboratory equipment. Calibration of the field equipment shall be recorded in the field logbook after each calibration event. The calibration procedure for each piece of field equipment used will be outlined in the final report.

The laboratory's QA plan and written operating procedures describing specific testing, inspection, maintenance, and calibration procedures for equipment will be followed. If required, maintenance procedures and schedules will be performed and documented.

3 Inspection and Acceptance of Supplies and Consumables

PMs have primary responsibility for identifying the types and quantities of supplies and consumables needed to complete projects and are responsible for identifying acceptance criteria for these items.

Supplies and consumables can be received either at the contractor's office or at a work site. When supplies are received at an office, the PM or FTL will sort them according to vendor, check packing slips against purchase orders, and inspect the condition of all supplies before they are accepted for use on a project. If an item does not meet the acceptance criteria, deficiencies will be noted on the packing slip and purchase order and the item will then be returned to the vendor for replacement or repair.

Procedures for receiving supplies and consumables in the field are similar. When supplies are received, the PM or FTL will inspect all items against the acceptance criteria. Any deficiencies or problems will be noted in the field logbook and deficient items will be returned for immediate replacement.

Analytical laboratories are required to provide certified clean containers for all analyses. These containers must meet EPA standards as described in *Specifications and Guidance for Obtaining Contaminant-Free Sampling Containers* (EPA, 1992).

4 Data Management

All field and analytical data collected during this investigation will be provided to MMD in the Baseline Characterization Report. Field data will be recorded in the logbook and/or field forms and will be included in the appendices. Analytical data will be summarized, tabulated, analyzed, and provided in the body of the final

report. The original laboratory data will be provided in an appendix of the final report. Some data may be presented graphically.

5 Assessment, Response Actions, and Reports to Management

NMCC and MMD will oversee collection of environmental data using the appropriate assessment and audit activities. Any problems encountered during an assessment of field investigation or laboratory activities will require appropriate corrective action to ensure that the problems are resolved. The corrective actions will be discussed with MMD and will be implemented after approval from MMD is received. NMCC will perform routine audits of their subcontractor's performance. In addition, the subcontractor's project managers will ensure that the work done under their assigned tasks complies with the QAPP and will report non compliance, problems, or other issues to NMCC in a timely manner agreed upon between NMCC and its subcontractors.

Effective management of environmental data collection requires: 1) timely assessment and review of all activities, and 2) open communication, interaction, and feedback among all project participants. NMCC and its contractors will use verbal communication with MMD oversight personnel, electronic communication, and monthly status reports to address any project-specific quality issues and to facilitate timely communication of these issues. NMCC and its contractors will develop a communications protocol to communicate with the MMD and solicit the MMD for concurrence with these communication procedures.

6 Data Evaluation and Usability

This section describes the procedures that are planned to review and evaluate field and laboratory data. This section also discusses procedures for verifying that the data are sufficient to meet MQOs for the project.

Review and evaluation of the data generated during field and laboratory activities are essential to obtaining defensible data of acceptable quality. Project team personnel will review field data to identify inconsistencies or anomalous values. Any inconsistencies discovered will be resolved as soon as possible by seeking clarification from field personnel responsible for data collection. All field personnel will be responsible for following the sampling and documentation procedures described in this SAP so that defensible and justifiable data are obtained.

Data values that are significantly different from the population are called "outliers." A systematic effort will be made to identify any outliers or errors before field personnel report the data. Outliers can result from improper sampling or measurement methodology, data transcription errors, calculation errors, or natural causes. Outliers that result from errors found during data verification will be identified and corrected; outliers that cannot be attributed to errors in sampling, measurement, transcription, or calculation will be clearly identified in project reports.

6.1 Laboratory Data Verification

Laboratory personnel will verify analytical data at the time of analysis and reporting and through subsequent reviews of the raw data for any nonconformances to the requirements of the analytical method. Laboratory personnel will make a systematic effort to identify any outliers or errors before they report the data. Outliers that result from errors found during data verification will be identified and corrected; outliers that cannot be attributed to errors in analysis, transcription, or calculation will be clearly identified in the case narrative section of the analytical data package.

6.2 Laboratory Data Evaluation and Usability

All laboratory data will be evaluated. The data evaluation strategy will not be a full data validation process, but will determine if the analytical results are within the QC limits set for the project. As part of this evaluation, the data usability will be assessed.

7 Reconciliation with User Requirements

After environmental data have been reviewed and evaluated in accordance with the procedures described in Section 7.0, the data must be further evaluated to assess whether MQOs have been met.

To the extent possible, EPA's data quality assessment (DQA) process will be followed to verify that the type, quality, and quantity of data collected are appropriate for their intended use. DQA methods and procedures are outlined in EPA's *Guidance for Data Quality Assessment, Practical Methods for Data Analysis* (EPA, 2000b). The DQA process includes five steps: (1) review the sampling objectives and sampling design, (2) conduct a preliminary data review, (3) select a statistical test, (4) verify the assumptions of the statistical test, and (5) draw conclusions from the data. In the case of water, sediment, and geologic samples, no statistical analysis is planned at this time. Statistical analyses planned for ecological and cultural resources data are defined in Sections 4, 5, and 10 of the SAP.

When the five-step DQA process is not completely followed because the sampling objectives are qualitative, data quality and data usability will be systematically assessed. This assessment will include:

- A review of the sampling design and sampling methods to verify that these were implemented as planned and are adequate to support project objectives.
- A review of project-specific data quality indicators for PARCC and project reporting limits to evaluate whether acceptance criteria have been met.
- A review of project-specific sampling objectives to assess whether they have been achieved by the data collected.
- An evaluation of any limitations associated with the decisions to be made based on the data collected (for example, if data completeness is only 90 percent compared to a project-specific completeness objective of 95 percent, the data may still be usable to support a decision, but at a lower level of confidence).

The final report for the project will discuss any potential impacts of these reviews on data usability and will clearly define any limitations associated with the data.

8 References

American Society for Testing and Materials (ASTM), 2000, Standard practice for description and identification of soils (visual-manual procedure): ASTM Standard D 2488-00.

Bureau of Land Management (BLM), 1996, Draft environmental impact statement (DEIS), Copper Flat Project: Las Cruces, N. Mex., U.S. Department of the Interior. Prepared by ENSR, Fort Collins, Colo.

Environmental Protection Agency (EPA), 1992, Specifications and guidance for obtaining contaminant-free sampling containers: Washington, DC, Office of Solid Waste and Emergency Response, EPA/A540/R-93/051. December.

———.2000a, Data quality objectives process for hazardous waste site investigations, EPA QA/G-4HW: Washington, DC, Office of Environmental Information, EPA/600/R-00/007. January.

———.2000b, Guidance for data quality assessment, practical methods for data analysis, EPA QA/G-9, QA00 Update: Washington, DC, Office of Environmental Information, EPA/600/R-96/084. July.

———.2000c, Guidance for the data quality objectives process, EPA QA/G-4: Washington, DC, Office of Environmental Information, EPA/600/R-96/055. August.

Figures



Figure 1. Project Organization



Figure 2. Parametrix Organizational Chart

Table

Table 1
INTERA Key Personnel and Responsibilities

Name	Organization	Role	Responsibilities	Contact Information
Ms. Cindy Ardito	INTERA	Program Quality Assurance (QA) Officer	Participates in development of technical approach. Reviews technical deliverables. Provides technical oversight during data collection	INTERA Inc. 6000 Uptown Blvd. NE, Suite 220 Albuquerque, NM 87110 (505) 246-1600, (505) 246-2600 FAX ext. 1206 cardito@intera.com
Mr. Peter Castiglia	INTERA	Project Manager/ Technical Lead	Responsible for overall project execution and for coordination with regulatory agencies and contractors. Actively participates in Data Quality Objective process. Provides management and technical oversight during data collection.	INTERA Inc. 6000 Uptown Blvd. NE, Suite 220 Albuquerque, NM 87110 (505) 246-1600, (505) 246-2600 FAX ext. 1217 pcastiglia@intera.com
Mr. Lee Dalton	INTERA	Field Team Leader (FTL) – Groundwater	Responsible for directing day-to-day field activities conducted by INTERA and subcontractor personnel. Verifies that field sampling and measurement procedures follow the Sampling and Analysis Plan. Provides project manager with regular reports on status of field activities.	INTERA Inc. 6000 Uptown Blvd. NE, Suite 220 Albuquerque, NM 87110 (505) 246-1600, (505) 246-2600 FAX ext. 1213 ldalton@intera.com
Mr. Justin Jayne	INTERA	Field Team Leader (FTL) – Surface Water	Responsible for directing day-to-day field activities conducted by INTERA and subcontractor personnel. Verifies that field sampling and measurement procedures follow the Sampling and Analysis Plan. Provides project manager with regular reports on status of field activities.	INTERA Inc. 6000 Uptown Blvd. NE, Suite 220 Albuquerque, NM 87110 (505) 246-1600, (505) 246-2600 FAX ext. 1220 jjayne@intera.com
Ms. Angela Persico	INTERA	On-Site Safety Officer	Responsible for implementing health and safety plan for determining appropriate site control measures and personal protection levels. Conducts safety briefings for INTERA and subcontractor personnel and site visitors. Can suspend operations that threaten health and safety.	INTERA Inc. 6000 Uptown Blvd. NE, Suite 220 Albuquerque, NM 87110 (505) 246-1600, (505) 246-2600 FAX ext. 1207 apersico@intera.com
Ms. Angela Persico Mr. Spencer Whitman Mr. Konrad Clark Ms. Annelia Tinklenberg	INTERA	Field Sampler(s)	Responsible for collecting representative samples and conducting necessary field activities specified in Sampling and Analysis Plan. Works under supervision of field team leader. Ensures proper sampling and handling procedures.	INTERA Inc. 6000 Uptown Blvd. NE, Suite 220 Albuquerque, NM 87110 (505) 246-1600, (505) 246-2600 FAX

Name	Organization	Role	Responsibilities	Contact Information
Mr. Bob Powell	Class One Technical Services, Inc.	Project Manager	Responsible for overall project execution and for coordination with regulatory agencies and contractors. Actively participates in Data Quality Objective process. Provides management and technical oversight during data collection by Class One Technical Services.	Class One Technical Services, Inc. 3500 Comanche Rd. NE Suite G Albuquerque, NM 87107 (505) 830-9680
Mr. Jens Deichmann	Parametrix	Project Manager – Ecological and Cultural Resources	Responsible for coordination with regulatory agencies and contractors. Actively participates in Data Quality Objective process. Provides management and technical oversight during data collection by Parametrix.	Parametrix Incorporated 8801 Jefferson NE; Bldg. 2 Albuquerque, NM 87113 (505) 998-5552 jdeichmann@parametrix.com
Mr. Chris Parrish	Parametrix	FTL - Cultural Resources	Responsible for directing day-to-day field activities conducted for cultural resources by Parametrix and subcontractor personnel. Verifies that field sampling and measurement procedures follow the Sampling and Analysis Plan. Provides project manager with regular reports on status of field activities.	Parametrix Incorporated 8801 Jefferson NE; Bldg. 2 Albuquerque, NM 87113 (505) 821-4700
Mr. Jim Nellessen	Parametrix	FTL – Natural Resources	Responsible for directing day-to-day field activities conducted for natural resources by Parametrix and subcontractor personnel. Verifies that field sampling and measurement procedures follow the Sampling and Analysis Plan. Provides project manager with regular reports on status of field activities.	Parametrix Incorporated 8801 Jefferson NE; Bldg. 2 Albuquerque, NM 87113 (505) 821-4700
Mr. Chad McKenna	Parametrix	Technical Lead – Geographic Information Systems (GIS)	Responsible for directing day-to-day activities conducted for GIS by Parametrix and subcontractor personnel. Verifies that GIS data collection procedures follow the Sampling and Analysis Plan. Provides project manager with regular reports on status of GIS data.	Parametrix Incorporated 8801 Jefferson NE; Bldg. 2 Albuquerque, NM 87113 (505) 821-4700
Mr. Mark Willow	SRK Consulting	Project Manager – Geologic Sampling	Responsible for coordination with regulatory agencies and contractors. Actively participates in Data Quality Objective process. Provides management and technical oversight during data collection by SRK.	SRK Consulting 250 Neil Road, Suite 300 Reno, Nevada 89502 (775) 828-6800 mwillow@srk.com
Dr. Robert Bowell	SRK Consulting	Technical Lead – Geologic Sampling	Responsible for directing day-to-day activities conducted for geologic by SRK and subcontractor personnel. Verifies that geologic data collection procedures follow the Sampling and Analysis Plan. Provides project manager with regular reports on status of geologic data collection and results.	SRK Consulting (UK) Ltd. 5th Floor, Churchill House 17 Churchill Way Cardiff, CF10 2HH, UK +44 (0) 29 2034 8150 egrbowel@srk.co.uk

6-28-2011

02149

NEW MEXICO
ENVIRONMENT DEPARTMENT

Ground Water Quality Bureau

PUBLIC RECORDS RELEASE FORM

* Please complete a form for each facility requested.

Pre-Review

Reviewers Name: Judy Majoras **Facility requested:** Copper Flat **DP#** 1

Number of files given out: **C-** 1-7 **M-** 1-3 **Maps, designs, etc.:** DP 1 APP & Application, 2011

Records Inspection (On-site)

Date: 6/28/11 **Time:** 1:20 am/pm **Company:** Percha/Animas watershed Association **Phone #:** 575 895 5113

Name: Judy Majoras **Signature:** Judy Majoras

I acknowledge I have read and agree to the attached Notice of Right to Inspect Records

Copy Service (Off-site) N/A

Records Check-Out:

Date: _____ **Time:** _____ am/pm **Company:** _____ **Phone #:** _____

Name: _____ **Signature:** _____

I acknowledge I have read and agree to the attached Notice of Right to Inspect Records

Estimated date of return: _____

Records Check-In:

Date: _____ **Time:** _____ am/pm **Company:** _____ **Phone #:** _____

Name: _____ **Signature:** _____

Post-Review

Reviewers Name: Judy Majoras **Facility requested:** Copper Flat **DP#** 1

Number of files given out: **C-** 1-7 **M-** 1-3 **Maps, designs, etc.:** DP & APP application 2011

Documents returned in good condition (circle)? (Yes) No

02150

6-28-2011

New Mexico Environmental Department
Ground Water Quality Bureau

Acknowledgement of Receipt

Acknowledgement of Receipt of Check/Cash

I hereby acknowledge receipt of Check No. #2135 Dated. 6/28/11
or cash, received in the amount of $ 15.00 from NM Copper Corp
for Copper Flat Mine DP-1 1535
(Facility Name) (DP No.) (AI ID)

GROUND WATE
JUN 29 2011
BUREAU

Copy Made for Check Processing _____ Date _____
For Central File Activity _____

Submitted to ASD by: _____ Date: _____

Received in ASD by: _____ Date: _____

Filing Fee [ ] New Facility [ ] Renewal [ ]

Modification [ ] Other [X] (Explain) Poster fee

Organization Code _____ Application FY _____

To be Deposited in the Ground Water Section Discharge Plan Fees.

Full Payment [ ] or Annual Increment [ ]

THIS CHECK IS DELIVERED IN CONNECTION WITH THE FOLLOWING ACCOUNT (S)

DATE		AMOUNT
TOTAL OF INVOICES		
LESS ___ % DISCOUNT		
LESS		
TOTAL DEDUCTIONS		
AMOUNT OF CHECK		

NEW MEXICO COPPER CORP
2425 SAN PEDRO DR NE SUITE 100
ALBUQUERQUE, NM 87110

2135
95-681/1070

DATE 6/28/2011

PAY TO THE ORDER OF State of New Mexico Environment Dept $ 15 00

Fifteen dollars & zero cents DOLLARS

Security Features Details on Back.

BANK of the WEST Coronado Office 1-800-488-2265

FOR Groundwater public notice poster fee

MP

02152

6-28-2011

GROUND WATER
JUN 29 2011
BUREAU

AFFIDAVIT OF PUBLIC NOTICE COMPLETION
New Permit or Permit Modification

DP- 1

I certify, under penalty of law, that I have fulfilled the Ground Water Discharge Permit public notice requirements of Section 20.6.2.3108(B) NMAC.

- ✓ I posted a sign for 30 days displaying a synopsis of the public notice in English and in Spanish at or near the proposed facility in a conspicuous public location (or multiple locations) approved by NMED.
- ✓ I posted a public notice flyer at a conspicuous off-site location approved by NMED.
- ✓ I placed a synopsis of the public notice in English and in Spanish in a newspaper approved by NMED. A copy of the newspaper page containing the synopsis is enclosed.
- ✓ I sent the public notice flyer via 1st class mail to *(check box)*:
  - ☑ owners of all properties within a 1/3 mile of the boundary of the property of the proposed discharge locations – mailing list is enclosed.
  - ☐ owners of all adjacent property (if applicant owns all property within 1/3 mile) – mailing list is enclosed.
  - ☐ owner of the property of the proposed discharge locations (if applicant is not the owner) – mailing address is enclosed.

I am aware that there are significant penalties for false certification including the possibility of fines.

Signature of Applicant

JENS W. DEICHMANN
Printed Name

Permitting Manager - Regulatory
Title

28 June 2011
Date

REMINDER: *Please remit the bottom portion of the poster fee invoice and a check ($15) for the poster fee with this affidavit.*

02154

Land Owners within 0.3 miles of mine boundary, sent public notice re: discharge permit via Fist Class Mail on 5-25-11 and 5-27-11

Ladder Ranch
Atten: Steve Dobrott
HC 31, Box 95
Caballo, NM 87931

Hillsboro Pitchfork Ranch, LLC
Atten: Mr. Cunningham
10571 Oral Zumwalt Way
Missoula MT, 59803

Ryan and Wendy Fancher
PO Box 344
Radium Springs, NM 88054

Ryan and Wendy Fancher
(a 2nd mailing to a 2nd address because Mark Adams didn't know which was better)
12400 Fort Bayard Rd.
Las Cruces, NM 88007

Landowners of Sections 23 and 26, T15S, R7W:

NV Brower and WL Easton,
308 Ave F
Redondo Beach, CA 90277

RETURNED: 5-28-11
ATTEMPTED, UNABLE TO FORWARD

BLM
Las Cruces District Office
Atten: Mike Smith
1800 Marquess Street
Las Cruces, NM 88005-3370

itself
ing it
at the
nly to
ct the
state,
state's
less of
nation,
like an
ve the
vival.
Mitch
eid got
doors,
gs like
exten-
OT Act
It's cer-
hey did
lt bene-
er mind
ing the
he pres-
wonder-
s giving
on his
conflict
congres-
hat war
ast even

month.

In the end, the state serves only itself, and demands that you serve it too. Like any parasite, it will happily kill its host to feed itself. The only possible escape is to pry its rotten teeth out of our collective hides, throw it to the ground, and stomp on it. Hard.

-0-

On the local front, have you seen our roads lately? Pretty pathetic, if you ask me. Except for that nice stretch along Main and Broadway that the state had re-surfaced last year, it's not safe to drive small vehicles on in some places without the fear of falling through to whatever's on the other side of the planet from New Mexico.

Truth or Consequences has one of the highest tax rates in the state. I'd like to know what we're getting for our hard-earned money that the city so blithely takes from us. Hopefully, with the commission discussing a budget to send to Santa Fe soon, a serious effort will be made to address the deteriorating condition of our streets. - PK

Veggies & More

and feel good?

What is it about ourselves that leaves that impression on people? I think it has to do with your heart. The love you have to share. The relationship you have with Christ that comes out of you.

The hard part is to practice the art of oozing with everyone, not just the select few. We have to leave our judgments behind. We don't know what it is like to walk in someone else's shoes, so we have to be sensitive to their feelings.. .even when we don't feel like it. We have to be considerate to all, even those that may not "get it."

I'm sure you know the people I am talking about; the ones who catch you at church or the store and start talking to you when you are obviously in a hurry, the people who provide extremely poor customer service and treat you badly, and let's not forget the people

for a possible career change.

Classifieds Get Results.

PUBLIC NOTICE / NOTICIA PUBLICA

Discharge Permit Application / Aplicación para Permiso para Descargar: For up to 2,875,873 gallons per day of mine tailings,process water, and domestic wastewater to a mine tailing impoundment / Para un máximo de 2.875.873 galones por día de desechos mineras, agua procesada, y aguas residuales domésticas a un embalse de relaves de minas.

Applicant & Discharge Location / Solicitante & Sitio de Descarga:
Copper Flat Mine, approximately 6 miles NE of Hillsboro

For More Information / Para Más Información (DP-1):
Ground Water Quality Bureau / Sección de Agua Subterránea
NM Environment Department / Departamento del Medio Ambiente

(505) 827-2900 www.nmenv.state.nm.us (public notices)

Information in this public notice was provided by the applicants and will be verified by NMED during the permit application review process.

6/3

PLAZA
(575) 744-5140
TOLL FREE 1-877-744-5140
Se Habla Español
EARL GREER Owner/Broker (505) 350-1155
CINDY TORRES Owner/Broker 740-0010
DONNA BULLINGTON
JOHN DIAMOND

7-6-2011

THEMAC RESOURCES
New Mexico Copper Corporation
2425 San Pedro, NE, Suite 100
Albuquerque, New Mexico 87110

GROUND WATER
BUREAU JUL 08 2011
GROUND WATER
BUREAU JUL 08 2011
BUREAU

July 6, 2011

Greg Huey
NMED/Ground Water Bureau
Harold Runnels Bldg.
1190 St Francis Drive
PO Box 5469
Santa Fe, NM 87502-5469

RE: Response to NMED June 23, 2011 Request for Additional Information: Site-Wide Stage I Abatement Plan Proposal for the Copper Flat Mine Facility

Mr. Huey:

Thank you for taking the time to meet with us regarding NMED's request for additional information for the above-referenced Stage I Abatement Plan Proposal yesterday, July 5, 2011. We understand that this meeting to discuss comments fulfills NMED's requirement that NMCC respond within 30 days of your June 23rd letter.

As we discussed, NMCC will prepare an Amendment to our Proposed Stage I Abatement Plan Proposal to address outstanding information requests. We will plan to submit this Amendment within 60 days the date of this letter. Our Amendment will address NMED Specific Comments based on available data, to include:

1. Clarification of the pre-mining ground elevation and pre-mining water level elevations with specific reference to wells or data point locations.
2. Clarification of the definition of the "site" vs. the region in the Abatement Plan.
3. Additional figures at a more appropriate scale for evaluation of the site including, as available within our 60 day timeframe:
    a. Cross sections
    b. Potentiometric surface maps and well location maps that clearly allow for evaluation of the different aquifer characteristics at the site
    c. Any other maps or figures that will better assist you in evaluating our proposal.
4. Verification that we have obtained surface water data for the area from the Surface Water Quality Bureau and will reference it in relevant reports.
5. Further clarification regarding our plans to keep automated flow and sampling systems at the site programmed to take measurements every 15 minutes during the heaviest rainfall season of the year.

6. Clarification on the sampling plan for Pit Lake Characterization and on collected pit lake data.
7. Iso-contour maps for known ground water impact near the tailing dam and further clarification on the location of the additional well proposed to better characterize the lateral extent of the tailing seepage.
8. Clarification regarding NMCC plans to monitor waste rock disposal facilities.

Thank you again for your time. If you have any questions or clarifications regarding these responses, please do not hesitate to contact me at 505-400-7925.

Best regards,

Katie Lee

Katie Lee
Project Scientist
New Mexico Copper Corporation

7-13-2011

Huey, Greg, NMENV

From: Huey, Greg, NMENV
Sent: Wednesday, July 13, 2011 3:16 PM
To: 'Katie Lee'
Cc: Vollbrecht, Kurt, NMENV
Subject: RE: NMCC Stage I Abatement Plan RFI response

Katie,

NMED hereby grants an extension to NMCC until September 15, 2011 for submittal of the Stage 1 Abatement Plan Amendment.

Thank you,

Greg Huey
Mining Environmental Compliance Section
NMED - Ground Water Quality Bureau
Office (505) 827-1046
Mobile (505) 670-1878
Fax (505) 827-2965
http://www.nmenv.state.nm.us/gwb/

From: Katie Lee [mailto:katie@nmcopper.com]
Sent: Tuesday, July 12, 2011 4:09 PM
To: Huey, Greg, NMENV; Vollbrecht, Kurt, NMENV; Steve Raugust
Subject: NMCC Stage I Abatement Plan RFI response

Greg and Kurt,

With this email, NMCC would like to respectfully request an extension to allow the submission of our Stage I Abatement Plan Amendment to be turned in to you on September 15, 2011. This will give our consultant needed time to prepare the information NMED requested in your June 23, 2011 letter.

Best regards,
--
Katie Lee
Project Scientist
New Mexico Copper Corporation
(a wholly owned subsidiary of THEMAC Resources Group, LTD.)

Mobile: 505.400.7925
www.themacresourcesgroup.com

This e-mail and any attachment may be confidential and privileged or otherwise protected from disclosure. It is solely intended for the person(s) named above. If you are not the intended recipient, any reading, use, disclosure, copying or distribution of all or parts of this e-mail or associated attachments is strictly prohibited. If you are not an intended recipient, please notify the sender immediately by replying to this message or by telephone and delete this e-mail and any attachments permanently from your system.

Huey, Greg, NMENV

From: mikesmit@blm.gov
Sent: Friday, August 19, 2011 12:53 PM
To: Huey, Greg, NMENV; Vollbrecht, Kurt, NMENV; jamontoy@blm.gov; Eustice, Chris, EMNRD; Mathis, Patrick L., DGF
Subject: Copper Flat Coordination meeting, August 31 1300 - 1430 at BLM Socorro Office.

Everyone has said they can meet on August 31 instead of August 30, so let's set the meeting for 1300-1430 on Wednesday, August 31. I've spoken to the Socorro FO and they will only have the Fire Ready-Room available on that day, so let's all hope a wildfire doesn't start in the Socorro District.

To reiterate our goals - we are near the point of starting the Environmental Impact Analysis for this project, so we need to start defining resource areas that will have to be addressed. At the end of this meeting, the BLM and Co-Ops should have defined the parameters for a Statement of Work (SOW) that will allow the development of a detailed RFP to address the issues identified. There will be the usual issues such as archeology, wildlife, T&E species etc. and some specifics related to mining in general and this project in particular. Here are some preliminary issues I can think of:

1. Water use - the effect of planned drawdowns on private wells, stream baseflow, etc.
2. Potential for acid rock drainage
3. Increased traffic on SR 152
4. Long-term effects of pit lake to wildlife (migratory birds, etc.)

Regards,

Michael Smith
Geologist - BLM
Las Cruces District Office
1800 Marquess Street
Las Cruces, NM 88005
575-525-4421
mikesmit@blm.gov

9-1-2011

Huey, Greg, NMENV

From: Huey, Greg, NMENV
Sent: Thursday, September 01, 2011 11:32 AM
To: 'Katie Lee'; Vollbrecht, Kurt, NMENV
Cc: Steve Finch; Steve Raugust
Subject: RE: NMCC Stage I Abatement Plan Amendment

Katie,

The October 14, 2011 deadline for the State 1 Abatement Plan Amendment for the Copper Flat Mine is approved.

Thank you,

Greg Huey
Mining Environmental Compliance Section
NMED - Ground Water Quality Bureau
Office (505) 827-1046
Mobile (505) 670-1878
Fax (505) 827-2965
http://www.nmenv.state.nm.us/gwb/

From: Katie Lee [mailto:klee@themacresourcesgroup.com]
Sent: Thursday, September 01, 2011 9:02 AM
To: Vollbrecht, Kurt, NMENV; Huey, Greg, NMENV
Cc: Steve Finch; Steve Raugust
Subject: NMCC Stage I Abatement Plan Amendment

Kurt and Greg,

As I just discussed with Greg, we are respectfully requesting an extension on the deadline to turn in our Stage I Abatement Plan Amendment for the New Mexico Copper Flat. Due to some difficulty with the architecture of our database and a datum issue with our newest survey data, we would like to submit our Amendment on Friday, October 14, 2011.

If this would not cause any inconvenience, it will give us some time to compile all of our data and present it in a copacetic and consistent manner. In addition, we would greatly appreciate your flexibility.

Best regards,
--
Katie Lee
Project Scientist
Copper Flat Mine
THEMAC Resources Group, Ltd.

Mobile: 505.400.7925
www.themacresourcesgroup.com

This e-mail and any attachment may be confidential and privileged or otherwise protected from disclosure. It is solely intended for the person(s) named above. If you are not the intended recipient, any reading, use, disclosure, copying or distribution of all or parts of this e-mail or associated attachments is strictly prohibited. If you are not an intended recipient, please notify the sender immediately by replying to this message or by telephone and delete this e-mail and any attachments permanently from your system.

9-9-2011

BLM MOU NM-NML0000-2011-004

MEMORANDUM OF UNDERSTANDING

between:
U.S. Department of the Interior - Bureau of Land Management,
Las Cruces District Office
and
New Mexico Environment Department

concerning:
Relationship as a Cooperating Agency
for the Copper Flat Mine Environmental Impact Statement

I. Purpose. This Memorandum of Understanding (MOU) establishes a cooperating agency relationship between the Bureau of Land Management's Las Cruces District Office (BLM) and New Mexico Environment Department (Cooperator) for the purpose of preparing the Copper Flat Mine Environmental Impact Statement (EIS). The BLM is the lead Federal agency for development of the Copper Flat Mine EIS. The BLM acknowledges that the Cooperator has jurisdiction by State law and special expertise applicable to the EIS effort, as defined at 40 CFR 1508.15 and 1508.26. This MOU describes responsibilities and procedures agreed to by the New Mexico Environment Department as a Cooperating Agency and the BLM (the Parties).

The cooperating agency relationship established through this MOU shall be governed by all applicable statutes, regulations, and policies, including the Council on Environmental Quality's National Environmental Policy Act (NEPA) regulations (in particular, 40 CFR 1501.6 and 1508.5), the BLM's planning regulations (in particular, 43 CFR 1601.0-5, 1610.3-1, and 1610.4), the Department of the Interior Manual (516 DM 2.5) and applicable New Mexico law.

II. Objective. The objectives of this MOU are:

A. To designate the New Mexico Environment Department as a Cooperating Agency in the EIS process.

B. To provide a framework for cooperation and coordination between the BLM and the Cooperator that will ensure successful completion of the EIS, in a timely, efficient, and thorough manner.

C. To recognize that the BLM is the lead agency with responsibility for the completion of the EIS and the Record of Decision.

D. To describe the respective responsibilities, jurisdictional authority, and expertise of each of the Parties in the EIS process.

III. Authority.

A. The authorities of the BLM to enter into and engage in the activities described within this MOU include, but are not limited to:

a. National Environmental Policy Act of 1969 (42 U.S.C. 4321 et seq.)
b. Federal Land Policy and Management Act of 1976 (43 U.S.C. 1701 et seq.)

B. Regulations implementing the above authorities:

a. Council on Environmental Quality regulations (40 CFR 1501 et seq.)
b. Bureau of Land Management planning regulations (43 CFR 1601 et seq.)

C. The authorities of the New Mexico Environment Department to enter into this MOU include, but are not limited to, the Water Quality Act , NMSA 1978, §§ 74-6-1 to 17 and the Water Quality Control Commission (WQCC) Regulations outlined in Title 20 Chapter 6 Part 2 of the New Mexico Administrative Code.

IV. Procedure.

A. BLM Responsibilities:

1. As lead agency, the BLM retains final responsibility for the content of all NEPA documents, which include the Draft EIS, the Proposed Final EIS, and the Record of Decision. The BLM's responsibilities include determining the purpose of and need for the EIS, selecting alternatives for analysis, identifying effects of the proposed alternatives, selecting the preferred alternative, and determining appropriate mitigation measures. In meeting these responsibilities, the BLM will follow all applicable statutory and regulatory requirements.

2. To the fullest extent consistent with its responsibilities as lead agency, the BLM will consider the comments, recommendations, data, or analyses provided by the Cooperator in the EIS process, giving particular consideration to those topics on which the Cooperator is acknowledged to possess jurisdiction by law or special expertise.

3. To the fullest extent practicable, after consideration of the effect such releases may have on the BLM's ability to withhold this information from other parties, the BLM will provide the Cooperator with copies of documents underlying the EIS relevant to the Cooperator's responsibilities, including technical reports, data, analyses, comments received, working drafts related to environmental reviews, and Draft and Final EISs. The BLM will provide the Cooperator with the planning schedule, including review time frames, and with any changes to the schedule as early as practicable. The Cooperator will review the Draft and proposed Final EIS during the public review of these documents.

4. BLM will carefully consider whether proposed meetings or other activities would waive the Unfunded Mandates Reform Act exception to the Federal Advisory Committee Act (2 U.S.C. 1534(b) and 5 U.S.C App.).

B. Cooperating Agency Responsibilities:

The New Mexico Environment Department is a Cooperating Agency in this EIS process and is recognized to have jurisdiction by law and special expertise in the following areas:

a. The New Mexico Environment Department Ground Water Quality Bureau (GWQB) conducts all of the discharge permitting, spill response, water pollution abatement and public participation activities for mining facilities in New Mexico in accordance with the Water Quality Act NMSA 1978, §§ 74-6-1 to 17 and the WQCC Regulations outlined in Title 20 Chapter 6 Part 2 of the New Mexico Administrative Code.

b. The New Mexico Environment Department GWQB has extensive relevant expertise due to its legislative authority and statutory mandate to protect New Mexico's public health and the environment through regulation and pollution prevention, and special expertise in evaluating proposed mining operations with the goal of ensuring that water quality standards are met.

1. The Cooperator will provide information, comments, and technical expertise to the BLM regarding those elements of the EIS, and the data and analyses supporting them, in which it has jurisdiction or special expertise or for which the BLM requests its assistance. In particular, the Cooperator will provide information on the following topics:

   a. Ground water quality, ground water quality monitoring and pollution prevention;

   b. Mine operations, mine closure and post mining reclamation;

   c. Other such information that is relevant to planning issues or data needs.

2. The Cooperator will request periodic briefings on the status and progress of the EIS. The Cooperator will provide comments and input in their areas of jurisdictional responsibility or special expertise, including, but not limited to, providing guidance on public involvement strategies, identifying data needs, suggesting management actions to resolve issues, identifying effects of alternatives, suggesting mitigation measures, and providing comments on working drafts of the EIS and supporting documents. Comments and input will be in writing to the extent possible.

C. Responsibilities of the Parties:

1. The Parties agree to participate in this EIS process in good faith and make all reasonable efforts to resolve disagreements.

2. The Parties agree to develop and comply with the schedules, which include dates for EIS milestones and timeframes for Cooperator's reviews and submissions.

3. Each Party agrees to fund its own expenses associated with the Copper Flat Mine EIS process, except that the BLM may contract with a Cooperator for technical studies within its jurisdiction or special expertise.

V. Other Provisions.

A. Authorities Not Altered. Nothing in this MOU alters, limits, or supersedes the authorities and responsibilities of any Party on any matter within their respective jurisdictions. Nothing in this MOU shall require any of the Parties to perform beyond its respective authority.

B. Financial Obligations. Nothing in this MOU shall require any of the Parties to assume any obligation or expend any sum in excess of authorization and appropriations available.

C. Immunity and Defenses Retained. Each Party retains all immunities and defenses provided by law with respect to any action based on or occurring as a result of this MOU.

D. Conflict of Interest. The Parties agree not to utilize any individual or organization for purposes of EIS development, environmental analysis, or Cooperator representation, including officials, employees, or third party contractors, having a financial interest in the outcome of the Copper Flat Mine EIS. Questions regarding potential conflicts of interest should be referred to BLM HQ or Field Ethics Counselors for resolution.

E. Documenting Disagreement or Inconsistency. Where the BLM and one or more Cooperators disagree on substantive elements of the EIS (such as designation of the alternatives to be analyzed or analysis of effects), and these disagreements cannot be resolved, the BLM will include a summary of the Cooperator's views in the Draft EIS and the Proposed Final EIS. The BLM will also describe substantial inconsistencies between its proposed action(s) and the objectives of State, local, or tribal land use plans and policies.

F. Management of Information. The Cooperator acknowledges that all supporting materials and draft documents may become part of the administrative record and may be subject to the requirements of the Freedom of Information Act (FOIA) and other Federal statutes. The BLM acknowledges that the Cooperator's treatment of these materials and drafts may be subject to the requirements of the New Mexico

Inspection of Public Records Act, NMSA 1978, Sections 14-2-1 to -12 (IPRA). The Parties agree that the BLM will share supporting materials and draft documents with the Cooperator. The Cooperator generally believes that IPRA does not require disclosure of draft documents, including certain supporting materials depending on their contents. The Cooperator shall notify BLM of any IPRA request for, or that includes, supporting materials or draft documents. Cooperator shall provide such notice as soon as practicable and in any event prior to disclosure of such materials or documents. If such disclosure by Cooperator takes place, thenceforward the BLM at its discretion may withhold from the Cooperator those documents that might be available for public release under IPRA. Notwithstanding any of the foregoing, nothing in this section or in this Agreement shall be interpreted so as to interfere with Cooperator's ability to obtain from any third party or contractor involved in EIS development information that is necessary or desirable for the performance or understanding of, or that is relied upon or referred to in, the New Mexico Environment Department Discharge Application.

G. Conflict Resolution. The Parties agree to make reasonable efforts to resolve procedural or substantive conflicts, and may agree to initiate an Alternative Dispute Resolution (ADR) process. The Parties acknowledge that BLM retains final responsibility for the decisions identified in the Copper Flat Mine EIS and Record of Decision.

H. Coordination with NEPA Contractor. Cooperators may provide information and comments directly to the NEPA contractor and collaborate with contractor's technical staff and subcontractors on matters within the Cooperator's jurisdiction or special expertise. The Cooperator acknowledges that it is not authorized to provide technical or policy direction regarding the performance of this contract, with regard to the development of the EIS. The BLM acknowledges that the work that the contractor will do for the development of and analysis in the EIS may overlap with the work that must be done in the development of the ground water Discharge Permit. The Parties agree that the Cooperator may use the contractor for technical review of portions of the ground water discharge permit application or Stage 1 Abatement Plan; and that the work done by the contractor in service of the development of and analysis in the EIS may be used by contractor or Cooperator in the development of and analysis of a ground water Discharge Permit or Stage 1 Abatement Plan.

VI. Agency Representatives.

Each Party will designate a representative and alternate representative to ensure coordination between the Cooperator and the BLM during the EIS process. Each Party may change its representative at will by providing written notice to the other Party.

NMED Representative
Name: Greg Huey, Environmental Scientist
Phone Number: (505) 827-1046
Email Address: greg.huey@state.nm.us
Mailing Address: 1190 Saint Francis Drive, Santa Fe, NM 87502

NMED Alternate Representative
Name: Kurt Vollbrecht, Geologist
Phone Number: (505) 827-0195
Email Address: kurt.vollbrecht@state.nm.us
Mailing Address: 1190 Saint Francis Drive, Santa Fe, NM 87502

NMED Alternate Representative
Name: Clint Marshall, Geologist
Phone Number: (505) 827-0027
Email Address: clint.marshall@state.nm.us
Mailing Address: 1190 Saint Francis Drive, Santa Fe, NM 87502

BLM Representative
Name: Mike Smith
Phone Number: 575-525-4421
Email Address: mikesmith@blm.gov
Mailing Address: 1800 Marquess St. Las Cruces, NM 88005

BLM Alternate Representative
Name: Jennifer Montoya
Phone Number: 575-525-4316
Email Address: jamontoya@blm.gov
Mailing Address: 1800 Marquess St. Las Cruces, NM 88005

VII. Administration.

A. Approval. This MOU becomes effective upon signature by the authorized officials of the BLM and the Cooperator.

B. Amendment. This MOU may be amended through written agreement of the signatories.

C. Termination. If not terminated earlier, this MOU will end when the Record of Decision for the Copper Flat Mine EIS is approved by the BLM State Director. Any Party may end its participation in this MOU by providing written notice to the other Party.

APPROVED:

F. David Martin, Secretary
New Mexico Environment Department

9-9-11
Date

Bill Childress, District Manager
Bureau of Land Management
Las Cruces District Office

August 30, 2011
Date

9-13-2011

NEW MEXICO
ENVIRONMENT DEPARTMENT

Ground Water Quality Bureau

SUSANA MARTINEZ
Governor
JOHN A. SANCHEZ
Lieutenant Governor

1190 St. Francis Drive
P.O. Box 5469, Santa Fe, NM 87502
Phone (505) 827-2918 Fax (505) 827-2965
www.nmenv.state.nm.us



CERTIFIED MAIL – RETURN RECIEPT REQUESTED

September 13, 2011

Mike Smith
Geologist
Bureau of Land Management
1800 Marquess Street
Las Cruces, NM 88005

RE: Memorandum of Understanding between NMED and BLM for the Copper Flat Mine Environmental Impact Statement

Dear Mr. Smith,

The Memorandum of Understanding between the New Mexico Environment Department and the Bureau of Land Management for development of an Environmental Impact Statement at the Copper Flat Mine, signed September 9, 2011, is attached. Thank you for your cooperation in developing the document. I look forward to working with you on this project.

Sincerely,

Gregory Huey
Copper Flat Mine Permit Lead
Mining Environmental Compliance Section
Ground Water Quality Bureau

cc: Chris Eustice, Chino Permit Lead, MMD

BLM MOU NM-NML0000-2011-004

MEMORANDUM OF UNDERSTANDING

between:
U.S. Department of the Interior - Bureau of Land Management,
Las Cruces District Office
and
New Mexico Environment Department

concerning:
Relationship as a Cooperating Agency
for the Copper Flat Mine Environmental Impact Statement

I. Purpose. This Memorandum of Understanding (MOU) establishes a cooperating agency relationship between the Bureau of Land Management's Las Cruces District Office (BLM) and New Mexico Environment Department (Cooperator) for the purpose of preparing the Copper Flat Mine Environmental Impact Statement (EIS). The BLM is the lead Federal agency for development of the Copper Flat Mine EIS. The BLM acknowledges that the Cooperator has jurisdiction by State law and special expertise applicable to the EIS effort, as defined at 40 CFR 1508.15 and 1508.26. This MOU describes responsibilities and procedures agreed to by the New Mexico Environment Department as a Cooperating Agency and the BLM (the Parties).

The cooperating agency relationship established through this MOU shall be governed by all applicable statutes, regulations, and policies, including the Council on Environmental Quality's National Environmental Policy Act (NEPA) regulations (in particular, 40 CFR 1501.6 and 1508.5), the BLM's planning regulations (in particular, 43 CFR 1601.0-5, 1610.3-1, and 1610.4), the Department of the Interior Manual (516 DM 2.5) and applicable New Mexico law.

II. Objective. The objectives of this MOU are:

A. To designate the New Mexico Environment Department as a Cooperating Agency in the EIS process.

B. To provide a framework for cooperation and coordination between the BLM and the Cooperator that will ensure successful completion of the EIS, in a timely, efficient, and thorough manner.

C. To recognize that the BLM is the lead agency with responsibility for the completion of the EIS and the Record of Decision.

D. To describe the respective responsibilities, jurisdictional authority, and expertise of each of the Parties in the EIS process.

III. Authority.

A. The authorities of the BLM to enter into and engage in the activities described within this MOU include, but are not limited to:

a. National Environmental Policy Act of 1969 (42 U.S.C. 4321 et seq.)
b. Federal Land Policy and Management Act of 1976 (43 U.S.C. 1701 et seq.)

B. Regulations implementing the above authorities:

a. Council on Environmental Quality regulations (40 CFR 1501 et seq.)
b. Bureau of Land Management planning regulations (43 CFR 1601 et seq.)

C. The authorities of the New Mexico Environment Department to enter into this MOU include, but are not limited to, the Water Quality Act , NMSA 1978, §§ 74-6-1 to 17 and the Water Quality Control Commission (WQCC) Regulations outlined in Title 20 Chapter 6 Part 2 of the New Mexico Administrative Code.

IV. Procedure.

A. BLM Responsibilities:

1. As lead agency, the BLM retains final responsibility for the content of all NEPA documents, which include the Draft EIS, the Proposed Final EIS, and the Record of Decision. The BLM's responsibilities include determining the purpose of and need for the EIS, selecting alternatives for analysis, identifying effects of the proposed alternatives, selecting the preferred alternative, and determining appropriate mitigation measures. In meeting these responsibilities, the BLM will follow all applicable statutory and regulatory requirements.

2. To the fullest extent consistent with its responsibilities as lead agency, the BLM will consider the comments, recommendations, data, or analyses provided by the Cooperator in the EIS process, giving particular consideration to those topics on which the Cooperator is acknowledged to possess jurisdiction by law or special expertise.

3. To the fullest extent practicable, after consideration of the effect such releases may have on the BLM's ability to withhold this information from other parties, the BLM will provide the Cooperator with copies of documents underlying the EIS relevant to the Cooperator's responsibilities, including technical reports, data, analyses, comments received, working drafts related to environmental reviews, and Draft and Final EISs. The BLM will provide the Cooperator with the planning schedule, including review time frames, and with any changes to the schedule as early as practicable. The Cooperator will review the Draft and proposed Final EIS during the public review of these documents.

02176

4. BLM will carefully consider whether proposed meetings or other activities would waive the Unfunded Mandates Reform Act exception to the Federal Advisory Committee Act (2 U.S.C. 1534(b) and 5 U.S.C App.).

B. Cooperating Agency Responsibilities:

The New Mexico Environment Department is a Cooperating Agency in this EIS process and is recognized to have jurisdiction by law and special expertise in the following areas:

a. The New Mexico Environment Department Ground Water Quality Bureau (GWQB) conducts all of the discharge permitting, spill response, water pollution abatement and public participation activities for mining facilities in New Mexico in accordance with the Water Quality Act NMSA 1978, §§ 74-6-1 to 17 and the WQCC Regulations outlined in Title 20 Chapter 6 Part 2 of the New Mexico Administrative Code.

b. The New Mexico Environment Department GWQB has extensive relevant expertise due to its legislative authority and statutory mandate to protect New Mexico's public health and the environment through regulation and pollution prevention, and special expertise in evaluating proposed mining operations with the goal of ensuring that water quality standards are met.

1. The Cooperator will provide information, comments, and technical expertise to the BLM regarding those elements of the EIS, and the data and analyses supporting them, in which it has jurisdiction or special expertise or for which the BLM requests its assistance. In particular, the Cooperator will provide information on the following topics:

   a. Ground water quality, ground water quality monitoring and pollution prevention;

   b. Mine operations, mine closure and post mining reclamation;

   c. Other such information that is relevant to planning issues or data needs.

2. The Cooperator will request periodic briefings on the status and progress of the EIS. The Cooperator will provide comments and input in their areas of jurisdictional responsibility or special expertise, including, but not limited to, providing guidance on public involvement strategies, identifying data needs, suggesting management actions to resolve issues, identifying effects of alternatives, suggesting mitigation measures, and providing comments on working drafts of the EIS and supporting documents. Comments and input will be in writing to the extent possible.

02177

C. Responsibilities of the Parties:

1. The Parties agree to participate in this EIS process in good faith and make all reasonable efforts to resolve disagreements.

2. The Parties agree to develop and comply with the schedules, which include dates for EIS milestones and timeframes for Cooperator's reviews and submissions.

3. Each Party agrees to fund its own expenses associated with the Copper Flat Mine EIS process, except that the BLM may contract with a Cooperator for technical studies within its jurisdiction or special expertise.

V. Other Provisions.

A. Authorities Not Altered. Nothing in this MOU alters, limits, or supersedes the authorities and responsibilities of any Party on any matter within their respective jurisdictions. Nothing in this MOU shall require any of the Parties to perform beyond its respective authority.

B. Financial Obligations. Nothing in this MOU shall require any of the Parties to assume any obligation or expend any sum in excess of authorization and appropriations available.

C. Immunity and Defenses Retained. Each Party retains all immunities and defenses provided by law with respect to any action based on or occurring as a result of this MOU.

D. Conflict of Interest. The Parties agree not to utilize any individual or organization for purposes of EIS development, environmental analysis, or Cooperator representation, including officials, employees, or third party contractors, having a financial interest in the outcome of the Copper Flat Mine EIS. Questions regarding potential conflicts of interest should be referred to BLM HQ or Field Ethics Counselors for resolution.

E. Documenting Disagreement or Inconsistency. Where the BLM and one or more Cooperators disagree on substantive elements of the EIS (such as designation of the alternatives to be analyzed or analysis of effects), and these disagreements cannot be resolved, the BLM will include a summary of the Cooperator's views in the Draft EIS and the Proposed Final EIS. The BLM will also describe substantial inconsistencies between its proposed action(s) and the objectives of State, local, or tribal land use plans and policies.

F. Management of Information. The Cooperator acknowledges that all supporting materials and draft documents may become part of the administrative record and may be subject to the requirements of the Freedom of Information Act (FOIA) and other Federal statutes. The BLM acknowledges that the Cooperator's treatment of these materials and drafts may be subject to the requirements of the New Mexico

Inspection of Public Records Act, NMSA 1978, Sections 14-2-1 to -12 (IPRA). The Parties agree that the BLM will share supporting materials and draft documents with the Cooperator. The Cooperator generally believes that IPRA does not require disclosure of draft documents, including certain supporting materials depending on their contents. The Cooperator shall notify BLM of any IPRA request for, or that includes, supporting materials or draft documents. Cooperator shall provide such notice as soon as practicable and in any event prior to disclosure of such materials or documents. If such disclosure by Cooperator takes place, thenceforward the BLM at its discretion may withhold from the Cooperator those documents that might be available for public release under IPRA. Notwithstanding any of the foregoing, nothing in this section or in this Agreement shall be interpreted so as to interfere with Cooperator's ability to obtain from any third party or contractor involved in EIS development information that is necessary or desirable for the performance or understanding of, or that is relied upon or referred to in, the New Mexico Environment Department Discharge Application.

G. Conflict Resolution. The Parties agree to make reasonable efforts to resolve procedural or substantive conflicts, and may agree to initiate an Alternative Dispute Resolution (ADR) process. The Parties acknowledge that BLM retains final responsibility for the decisions identified in the Copper Flat Mine EIS and Record of Decision.

H. Coordination with NEPA Contractor. Cooperators may provide information and comments directly to the NEPA contractor and collaborate with contractor's technical staff and subcontractors on matters within the Cooperator's jurisdiction or special expertise. The Cooperator acknowledges that it is not authorized to provide technical or policy direction regarding the performance of this contract, with regard to the development of the EIS. The BLM acknowledges that the work that the contractor will do for the development of and analysis in the EIS may overlap with the work that must be done in the development of the ground water Discharge Permit. The Parties agree that the Cooperator may use the contractor for technical review of portions of the ground water discharge permit application or Stage 1 Abatement Plan; and that the work done by the contractor in service of the development of and analysis in the EIS may be used by contractor or Cooperator in the development of and analysis of a ground water Discharge Permit or Stage 1 Abatement Plan.

VI. Agency Representatives.

Each Party will designate a representative and alternate representative to ensure coordination between the Cooperator and the BLM during the EIS process. Each Party may change its representative at will by providing written notice to the other Party.

NMED Representative
Name: Greg Huey, Environmental Scientist
Phone Number: (505) 827-1046
Email Address: greg.huey@state.nm.us
Mailing Address: 1190 Saint Francis Drive, Santa Fe, NM 87502

NMED Alternate Representative
Name: Kurt Vollbrecht, Geologist
Phone Number: (505) 827-0195
Email Address: kurt.vollbrecht@state.nm.us
Mailing Address: 1190 Saint Francis Drive, Santa Fe, NM 87502

NMED Alternate Representative
Name: Clint Marshall, Geologist
Phone Number: (505) 827-0027
Email Address: clint.marshall@state.nm.us
Mailing Address: 1190 Saint Francis Drive, Santa Fe, NM 87502

BLM Representative
Name: Mike Smith
Phone Number: 575-525-4421
Email Address: mikesmith@blm.gov
Mailing Address: 1800 Marquess St. Las Cruces, NM 88005

BLM Alternate Representative
Name: Jennifer Montoya
Phone Number: 575-525-4316
Email Address: jamontoya@blm.gov
Mailing Address: 1800 Marquess St. Las Cruces, NM 88005

VII. Administration.

A. Approval. This MOU becomes effective upon signature by the authorized officials of the BLM and the Cooperator.

B. Amendment. This MOU may be amended through written agreement of the signatories.

C. Termination. If not terminated earlier, this MOU will end when the Record of Decision for the Copper Flat Mine EIS is approved by the BLM State Director. Any Party may end its participation in this MOU by providing written notice to the other Party.

APPROVED:

F. David Martin, Secretary
New Mexico Environment Department

9-9-11
Date

Bill Childress, District Manager
Bureau of Land Management
Las Cruces District Office

August 30, 2011
Date

10/4/11

10-4-2011

SHARE# 12-521-0000-0019

BLM MOU NM-NML0000-2011-005

MEMORANDUM OF UNDERSTANDING

between:
U.S. Department of the Interior - Bureau of Land Management,
Las Cruces District Office
and
New Mexico Energy, Minerals and Natural Resources Department

concerning:
Relationship as a Cooperating Agency
for the Copper Flat Mine Environmental Impact Statement

I. Purpose. This Memorandum of Understanding (MOU) establishes a cooperating agency relationship between the Bureau of Land Management's Las Cruces District Office (BLM) and New Mexico Energy, Minerals and Natural Resources Department (Cooperator) for the purpose of preparing the Copper Flat Mine Environmental Impact Statement (EIS). The BLM is the lead Federal agency for development of the Copper Flat Mine EIS. The BLM acknowledges that the Cooperator has jurisdiction by State law and special expertise applicable to the EIS effort, as defined at 40 CFR 1508.15 and 1508.26. Cooperator also is required to conduct an environmental evaluation (EE) pursuant to 19.10.6.605(D) NMAC. This MOU describes responsibilities and procedures agreed to by the New Mexico Energy, Minerals and Natural Resources Department as a Cooperating Agency and the BLM (the Parties).

The cooperating agency relationship established through this MOU shall be governed by all applicable statutes, regulations, and policies, including the Council on Environmental Quality's National Environmental Policy Act (NEPA) regulations (in particular, 40 CFR 1501.6 and 1508.5), the BLM's planning regulations (in particular, 43 CFR 1601.0-5, 1610.3-1, and 1610.4), the Department of the Interior Manual (516 DM 2.5) and applicable New Mexico law.

II. Objective. The objectives of this MOU are:

A. To designate New Mexico Energy, Minerals and Natural Resources Department as a Cooperating Agency in the EIS process.

B. To provide a framework for cooperation and coordination between the BLM and the Cooperator that will ensure successful completion of the EIS, hydrologic balance, and EE, in a timely, efficient, and thorough manner.

C. To recognize that the BLM is the lead agency with responsibility for the completion of the EIS and the Record of Decision.

D. To describe the respective responsibilities, jurisdictional authority, and expertise of each of the Parties in the EIS process.

III. Authority.

A. The authorities of the BLM to enter into and engage in the activities described within this MOU include, but are not limited to:

1. National Environmental Policy Act of 1969 (42 U.S.C. 4321 et seq.)
2. Federal Land Policy and Management Act of 1976 (43 U.S.C. 1701 et seq.)

B. Regulations implementing the above authorities:

1. Council on Environmental Quality regulations (40 CFR 1501 et seq.)
2. Bureau of Land Management planning regulations (43 CFR 1601 et seq.)

C. The authorities of New Mexico Energy, Minerals and Natural Resources Department to enter into this MOU include, but are not limited to:

1. NMSA 1978, §§ 69-36-1 to 20 (New Mexico Mining Act)
2. Title 19, Chapter 10 NMAC (New Mexico Rules)

IV. Procedure.

A. BLM Responsibilities:

1. As lead agency, the BLM retains final responsibility for the content of all NEPA documents, which include the Draft EIS, the Proposed Final EIS, and the Record of Decision. The BLM's responsibilities include determining the purpose of and need for the EIS, selecting alternatives for analysis, identifying effects of the proposed alternatives, selecting the preferred alternative, and determining appropriate mitigation measures. In meeting these responsibilities, the BLM will follow all applicable statutory and regulatory requirements.

2. To the fullest extent consistent with its responsibilities as lead agency, the BLM will consider the comments, recommendations, data, or analyses provided by the Cooperator in the EIS process, giving particular consideration to those topics on which the Cooperator is acknowledged to possess jurisdiction by law or special expertise.

3. To the fullest extent practicable, after consideration of the effect such releases may have on the BLM's ability to withhold this information from other parties, the BLM will provide the Cooperator with copies of documents underlying the EIS relevant to the Cooperator's responsibilities, including technical reports, data, analyses, comments received, working drafts related to environmental reviews, and Draft and Final EISs. BLM will provide the Cooperator with the planning schedule,

including review time frames, and with any changes to the schedule as early as practicable. The Cooperator will review the Draft and proposed Final EIS during the public review of these documents.

B. Cooperating Agency Responsibilities:

1. New Mexico Energy, Minerals and Natural Resources Department is a Cooperating Agency in this EIS process and is recognized to have jurisdiction by law and special expertise in the following area:

   a. Environmental effects of exploration and mining;

   b. Reclamation of lands that have been subject to same.

2. The Cooperator will provide information, comments, and technical expertise to the BLM regarding those elements of the EIS, and the data and analyses supporting them, in which it has jurisdiction or special expertise or for which the BLM requests its assistance. In particular, the Cooperator will provide information on the following topics:

   a. Soils, vegetation, hydrology, erosional and mass stability;

   b. Reclamation costs and financial assurance;

   c. Post mine land use.

3. The Cooperator will request periodic briefings on the status and progress of the EIS. The Cooperator will provide comments and input in their areas of jurisdictional responsibility or special expertise during and after these briefings. Comments and input will be in writing to the extent possible.

C. Responsibilities of the Parties:

1. The Parties agree to participate in this EIS process in good faith and make all reasonable efforts to resolve disagreements.

2. The Parties agree to develop and comply with the schedules, which includes dates for EIS milestones and timeframes for Cooperator's reviews and submissions.

3. Each Party agrees to fund its own expenses associated with the Copper Flat Mine EIS process, except that the BLM may contract with a Cooperator for technical studies within its jurisdiction or special expertise.

4. The Parties agree to carefully consider whether proposed meetings or other activities would waive the Unfunded Mandates Reform Act exception to the Federal Advisory Committee Act (2 U.S.C. 1534(b) and 5 U.S.C. App.).

V. Other Provisions.

A. Authorities Not Altered. Nothing in this MOU alters, limits, or supersedes the authorities and responsibilities of any Party on any matter within their respective jurisdictions. Nothing in this MOU shall require either of the Parties to perform beyond its respective authority.

B. Financial Obligations. Nothing in this MOU shall require any of the Parties to assume any obligation or expend any sum in excess of authorization and appropriations available.

C. Immunity and Defenses Retained. Each Party retains all immunities and defenses provided by law with respect to any action based on or occurring as a result of this MOU.

D. Conflict of Interest. The Parties agree not to utilize any individual or organization for purposes of EIS development, environmental analysis, or Cooperator representation, including officials, employees, or third party contractors, having a financial interest in the outcome of the Copper Flat Mine EIS. Questions regarding potential conflicts of interest should be referred to BLM HQ or Field Ethics Counselors for resolution.

E. Documenting Disagreement or Inconsistency. Where the BLM and one or more Cooperators disagree on substantive elements of the EIS (such as designation of the alternatives to be analyzed or analysis of effects), and these disagreements cannot be resolved, the BLM will include a summary of the Cooperator's views in the Draft EIS and the Proposed Final EIS. The BLM will also describe substantial inconsistencies between its proposed action(s) and the objectives of State, local, or tribal land use plans and policies.

F. Management of Information. The Cooperator acknowledges that all supporting materials and draft documents may become part of the administrative record and may be subject to the requirements of the Freedom of Information Act (FOIA) and other Federal statutes. The BLM acknowledges that the Cooperator's treatment of these materials and drafts may be subject to the requirements of the New Mexico Inspection of Public Records Act, NMSA 1978, Sections 14-2-1 to -12 (IPRA). While the Cooperator believes that IPRA does not require disclosure of draft documents or, depending on their content, certain of the supporting materials, if a court of competent jurisdiction or the Governor of the State of New Mexico or her designee instructs the Cooperator to do so, the Cooperator will disclose such documents and materials. The Parties agree that the BLM will share with the Cooperator supporting materials and drafts documents, but that if such disclosure by Cooperator takes place, thenceforward the BLM at its discretion may withhold from the Cooperator those documents that might be available for public release under IPRA. Notwithstanding any of the foregoing, nothing in this section or in this Agreement shall be interpreted so as to interfere with Cooperator's ability to obtaining from any third party or contractor

involved in EIS or EE development information that is necessary or desirable for the performance or understanding of, or that is relied upon or referred to in, the EE.

G. Conflict Resolution. The Parties agree to make reasonable efforts to resolve procedural or substantive conflicts, and may agree to initiate an Alternative Dispute Resolution (ADR) process. The Parties acknowledge that BLM retains final responsibility for the decisions identified in the Copper Flat Mine EIS and Record of Decision.

H. Coordination with NEPA Contractor. Cooperators may provide information and comments directly to the NEPA contractor and collaborate with contractor's technical staff and subcontractors on matters within the Cooperator's jurisdiction or special expertise. The Cooperator acknowledges that it is not authorized to provide technical or policy direction regarding the performance of this contract, with regard to the development of the EIS. The BLM acknowledges that the work that the contractor will do for the development of and analysis in the EIS overlaps considerably with the work that must be done in the development of the EE. The Parties agree that Cooperator may use the contractor for the development of the EE; that the Cooperator may provide technical or policy direction regarding the development of and analysis in the EE, provided that such direction does not conflict with direction given by the BLM; and that the work done by the contractor in service of the development of and analysis in the EIS may be used by contractor and/or Cooperator in the development of and analysis in the EE.

VI. Agency Representatives.

Each Party will designate a representative and alternate representative to ensure coordination between the Cooperator and the BLM during the EIS process. Each Party may change its representative at will by providing written notice to the other Party.

Cooperative Agency Representative
Name: Holland Shepherd
Phone Number: (505) 476-3437
Email Address: holland.shepherd@state.nm.us
Mailing Address: 1220 South St. Francis Drive, Santa Fe, NM 87505

Cooperative Agency Alternate Representative
Name: Chris Eustice
Phone Number: (505) 476-3438
Email Address: chris.eustice@state.nm.us
Mailing Address: 1220 South St. Francis Drive, Santa Fe, NM 87505

BLM Representative
Name: Mike Smith
Phone Number: (575) 525-4421
Email Address: msmith@blm.gov
Mailing Address: 1800 Marquess St., Las Cruces, NM 88005

BLM Alternate Representative
Name: Jennifer Montoya
Phone Number: (575) 525-4316
Email Address: jamontoya@blm.gov
Mailing Address: 1800 Marquess St., Las Cruces, NM 88005

VII. Administration.

A. Approval. This MOU becomes effective upon signature by the authorized officials of the BLM and the Cooperator.

B. Amendment. This MOU may be amended through written agreement of the signatories.

C. Termination. If not terminated earlier, this MOU will end when the Record of Decision for the Copper Flat Mine EIS is approved by the BLM State Director. Either Party may end its participation in this MOU by providing written notice to the other Party.

APPROVED:

Cabinet Secretary or Designee
New Mexico Energy, Minerals and
Natural Resources Department
Mining and Minerals Division

10-4-11
Date

Bill Childress, District Manager
Bureau of Land Management
Las Cruces District Office

9/21/2011
Date

10-14-2011

THEMAC RESOURCES

GROUND WATER
OCT 17 2011
BUREAU

October 14, 2011

Greg Huey
New Mexico Environment Department
GWQB-MECS
Harold L. Runnels Building
1190 St Francis Drive
Santa Fe, New Mexico 87505

Re: New Mexico Copper Corporation's Amendment to the Stage I Abatement Plan Proposal for the Copper Flat Mine

Mr. Huey,

We are pleased to submit the attached Amendment to the Stage I Abatement Plan for the Copper Flat Mine. This report amends our previously proposed plan dated March 31, 2011 and titled *Stage I Abatement Plan for the Copper Flat Mine*. We believe this submission will satisfy NMED's June 23, 2011 request for additional information.

If you have any questions, please do not hesitate to contact me at 505-400-7925. We look forward to working with you.

Best regards,

Katie Lee

Katie Lee
Project Scientist
THEMAC Resources Group, Ltd.

Attachments

AMENDMENT TO THE STAGE I ABATEMENT PLAN PROPOSAL FOR THE COPPER FLAT MINE

prepared by

JOHN SHOMAKER & ASSOCIATES, INC.
Water-Resource and Environmental Consultants
2611 Broadbent Parkway NE
Albuquerque, New Mexico 87107
505-345-3407
www.shomaker.com

prepared for

New Mexico Copper Corporation
2425 San Pedro Dr. NE, Suite 100
Albuquerque, New Mexico 87110

October 14, 2011

AMENDMENT TO THE STAGE I ABATEMENT PLAN PROPOSAL FOR THE COPPER FLAT MINE

prepared by

JOHN SHOMAKER & ASSOCIATES, INC.
Water-Resource and Environmental Consultants
2611 Broadbent Parkway NE
Albuquerque, New Mexico 87107
505-345-3407
www.shomaker.com

prepared for

New Mexico Copper Corporation
2425 San Pedro Dr. NE, Suite 100
Albuquerque, New Mexico 87110

October 14, 2011

CONTENTS

page

A. INTRODUCTION 1
A.1 Proposed Amendments 1
B. AMENDED SECTION 2.3 - HYDROLOGIC CONDITIONS 3
B.1 Area of Investigation 3
B.2 Hydrogeologic Setting 3
B.2.1 Surface Water and Recharge 5
B.2.2 Geologic Units and Structure 6
B.2.3 Groundwater Flow Direction 8
B.2.4 Aquifer Characteristics 8
B.2.5 Water-Quality Trends 10
B.3 Extent of Groundwater Impacts 11
B.3.1 Pit Lake 12
B.3.2 Waste Rock Pile(s) 13
B.3.3 Tailings Impoundment 13
B.4 Hydrogeologic Conceptual Model 14
C. PROPOSED SITE INVESTIGATION WORKPLAN 15
C.1 Pit Lake 15
C.2 Waste Rock Pile(s) 16
C.3 Tailings Impoundment Facility 17
D. PROPOSED MONITORING PLAN 17
D.1 Pit Lake 17
D.2 Waste Rock Pile(s) 18
D.3 Tailings Impoundment Facility 19
E. REFERENCES 20

TABLES

page

Table 1. References for final Stage 1 Abatement Plan proposal 2

Table 2. Summary of wells and well data for the Stage 1 Abatement Plan area of investigation, Copper Flat Mine, Sierra County, New Mexico 4

Table 3. Geologic units and their characteristics 6

Table 4. Summary of hydraulic conductivity (permeability) estimates from wells in the vicinity of the pit and waste rock piles 9

Table 5. Summary of hydraulic properties estimated from wells in the vicinity of the tailings impoundment 10

Table 6. Identified constituents of concern for the pit lake 12

Table 7. Proposed monitoring plan for Copper Flat pit lake area 18

Table 8. Proposed monitoring plan for Copper Flat waste rock pile area 18

Table 9. Proposed monitoring plan for Copper Flat Mine tailings impoundment area 19

ILLUSTRATIONS

(follow text)

Figure 1. Regional map showing locations of Copper Flat Mine permit area, watersheds, and geographical features, Sierra County, New Mexico.

Figure 2. Map of proposed Stage 1 Abatement Plan area of investigation, Copper Flat Mine facilities, and monitoring points locations, Copper Flat Mine, Sierra County, New Mexico.

Figure 3. Geologic map showing distribution of hydrogeologic units within the area of investigation and lines of section for tailings impoundment area Copper Flat Mine, Sierra County, New Mexico.

Figure 4. Graph of daily precipitation at Hillsboro, New Mexico for the time period 1980 to 2010, Sierra County, New Mexico.

Figure 5. Hydrogeologic cross-sections PA-PA' and PX-PX', Copper Flat Mine pit lake area, Sierra County, New Mexico.

Figure 6. Hydrogeologic cross-sections PB-PB', Copper Flat Mine pit lake area, Sierra County, New Mexico.

Figure 7. North to south hydrogeologic cross-section TB-TB', Copper Flat Mine tailings impoundment area, Sierra County, New Mexico.

Figure 8. West to east hydrogeologic cross-section TA-TA', Copper Flat Mine tailings impoundment area, Sierra County, New Mexico.

Figure 9. Water-level elevation contour map for Stage 1 Abatement Plan area of investigation, Copper Flat Mine, Sierra County, New Mexico.

Figure 10. Aerial photograph showing water-level elevation contours and direction of groundwater flow for the Copper Flat Mine pit lake area, Sierra County, New Mexico.

Figure 11. Map showing depth to water in the Copper Flat Mine permit boundary facilities, Sierra County, New Mexico.

Figure 12. Graph showing historical water levels for monitoring wells NP-1 through NP-5, Copper Flat Mine tailings facility, Sierra County, New Mexico.

Figure 13. Graph of sulfate versus chloride concentrations for Copper Flat Mine pit lake, Sierra County, New Mexico.

Figure 14. Time-series sulfate concentration plot for SWQ-1, SWQ-2, SWQ-3 and GWQ-3, Copper Flat Mine, Sierra County, New Mexico.

Figure 15. Time-series sulfate and TDS concentrations plot for monitoring well NP-3, Copper Flat Mine tailings impoundment area, Sierra County, New Mexico.

Figure 16. Map showing locations of waste-rock piles, surface-water and groundwater monitoring points, and potential waste-rock leachate migration pathways, Copper Flat Mine, Sierra County, New Mexico.

Figure 17. Map showing lateral extent of sulfate plume associated with Copper Flat Mine tailings impoundment facility and proposed monitoring wells, Sierra County, New Mexico.

APPENDICES

(follow illustrations)

Appendix A. Revised tables from Stage 1 Abatement Plan dated March 31, 2011 (INTERA, 2011)

Table A-1. Pit lake water-quality data

Table A-2. Surface-water-quality data

Table A-3. Groundwater-quality data

Appendix B. Construction diagrams for GWQ-5R, GWQ11-24(A,B), and GWQ11-25(A,B)

AMENDMENT TO THE STAGE I ABATEMENT PLAN PROPOSAL FOR THE COPPER FLAT MINE

A. INTRODUCTION

New Mexico Copper Corporation (NMCC) submitted a Stage 1 Abatement Plan proposal for the Copper Flat Mine to the New Mexico Environment Department (NMED). A general location map of the Copper Flat Mine is shown as Figure 1. The proposed plan was prepared by INTERA on March 31, 2011 and titled *Stage 1 Abatement Plan for the Copper Flat Mine*. On June 23, 2011, the NMED requested additional information before approving the proposed plan.

NMCC contracted John Shomaker & Associates, Inc. (JSAI) to address NMED requests for additional information and to amend the proposed Stage 1 Abatement Plan for the Copper Flat Mine.

A.1 Proposed Amendments

The following amendments were made to the Stage 1 Abatement Plan proposal:

1. Identify the proposed Stage 1 Abatement Plan area of investigation. The area of investigation is the NMCC permit area plus a 1-mile buffer. Figure 2 shows the proposed Stage 1 Abatement Plan area of investigation.
2. Provide maps and illustrations that better define the extent of known vadose zone and groundwater contamination.
3. Revise Section 2.3 (hydrogeologic description of site).
4. Amended and supplemented Section 4 (ongoing investigation activities) with a revised monitoring plan specific to the proposed Stage 1 Abatement Plan area of investigation.
5. Amended and supplemented Section 5 (proposed characterization activities) with a revised investigation plan specific to the proposed Stage 1 Abatement Plan area of investigation.

There are components of the proposed Stage 1 Abatement Plan prepared by INTERA (2011) that are revised and replaced by this amendment. Table 1 is a list referencing which sections from the original Stage 1 Abatement proposal and this amendment report fulfill the requirements of NMAC 20.6.2.4106 C (Stage 1 Abatement Plan contents).

Table 1. References for final Stage 1 Abatement Plan proposal

SECTION (NMAC 20.6.2.4106 C)	REFERENCE	
	original INTERA proposal (March 31, 2011)	**JSAI amendments (October 4, 2011)**
C.(1) Description of Site	Sections 2.1, 2.2, and *2.3*	Section B amendment replaces INTERA Section 2.3)
C.(2) Site Investigation Workplan (a) Site Hydrogeology (b) Surface Water Hydrology	*Section 5.0*	Section C amendment replaces INTERA Section 5.0
C.(3) Monitoring Program	*Section 4.0*	Section D amendment replaces INTERA Section 4.0
C.(4) Quality Assurance Plan	Section 6.0	no amendments
C.(5) Site Health and Safety Plan	Section 7.0	no amendments
C.(6) Stage 1 Abatement Plan Schedule	Sections 8.0 and 9.0	Section D amendment replaces INTERA Sections 8.0 and 9.0
C.(1), (2), and (3)	*Tables 4.1 – 4.3 and Appendix B*	Appendix A Tables A-1 – A-3 replace INTERA Tables 4.1 – 4.3 and Appendix B

italic items listed were replaced with amendments

A summary of items removed from the original Stage 1 Abatement Plan proposal includes the following:

1. Groundwater and surface water monitoring outside of the proposed Stage 1 Abatement Plan area of investigation shown on Figure 2.
2. Geochemical modeling of pit lake system will be replaced by water-quality characterization.
3. Analysis of pit lake hydraulics: this task is already completed (see Section B).
4. Geologic block model of tailings impoundment: this task is completed and included as cross-sections presented in this amendment (Figs. 7 and 8).

A summary of items added to the proposed Stage 1 Abatement Plan includes the following:

1. Proposed monitoring well drilling and testing.
2. Proposed monitoring plan for each facility (pit, waste rock piles, and tailings impoundment).
3. Pit lake water balance and water-quality characterization.
4. Use data collected from the proposed monitoring plan to refine the hydrogeologic conceptual model for each facility. Rate of potential transport will be addressed in the refined conceptual model.

B. AMENDED SECTION 2.3 - HYDROLOGIC CONDITIONS

The hydrologic setting and hydrogeologic conditions at Copper Flat Mine have been described in detail by previous studies performed by Newcomer and Finch (1993), SRK (1996), Adrian-Brown Consultants (1996), and Raugust (2003). In addition, there are numerous geologic reports, such as Harley (1934), Hedlund (1975), and Dunn (1982) that provide good detail on the structure and subsurface geology. Previous studies were combined with the analysis of recent data collected by INTERA (2010 to current) and JSAI (2011) to amend Section 2.3 of the Copper Flat Mine Stage 1 Abatement Plan.

B.1 Area of Investigation

The area of investigation is defined as the area within a 1-mile buffer zone of the current Copper Flat Mine permit boundary (Fig. 2). The site map, shown as Figure 2, also shows the locations of monitoring points used for the Stage 1 Abatement Plan, existing mine facilities, and other geographic features. Figure 1 distinguishes the region from the area of investigation. The area of investigation includes all existing mine facilities, the potential area of impact, and adequate area of investigation upgradient and downgradient of the potential areas of impact. For the Copper Flat Mine property, potential areas of impact include tailings impoundment, waste rock piles, and pit lake.

B.2 Hydrogeologic Setting

The area of investigation is encompassed in the upper watershed of Grayback Arroyo (Fig. 2). There are two hydrogeologic regions shown on Figures 1 and 3, and described below:

1) Andesite volcano within the Animas Uplift. The center of the andesite volcano contains a monzonite intrusion, which is referred to as Copper Flat (Harley, 1934). The Copper Flat open pit was excavated in 1982 by Quintana Minerals. The associated waste rock facilities are placed on andesite rocks (Figs. 2 and 3).

2) The Palomas Basin contains the Santa Fe Group sediments. The Palomas (geologic) Basin is part of the sediment-filled down-dropped blocks formed by the Rio Grande Rift. The tailings impoundment facility is located on the western margin of the Palomas Basin.

The area of investigation contains three established surface-water monitoring points along Grayback Arroyo, pit-lake monitoring, and 47 wells (Fig. 2). The wells can be grouped into monitoring wells and water-supply wells (domestic, stock, mine supply, etc.). Table 2 is a list of wells and their specifics.

Table 2. Summary of wells and well data for the Stage 1 Abatement Plan area of investigation, Copper Flat Mine, Sierra County, New Mexico

well name	well type	facility area	year drilled	casing diameter (inches)	total depth (ft bmp)	screen interval (ft bgl)	measuring-point elevation (2011 survey) (ft amsl)	geologic unit	depth to water measurement date	depth to water (ft bmp)	water-level elevation (ft amsl)
GWQ-1	supply	background region	1972	12 + 14	401	na	5,195.24	Santa Fe Group	6/15/1981	72.00	5,123.24
GWQ-2	supply	background region	1932	8	500	na	5,227.44	Santa Fe Group	11/15/1982	60.00	5,167.44
GWQ-3	supply	waste rock pile	1932	40 x 43	33	na	5,252.60	alluvium/andesite	9/29/2011	18.71	5,233.89
GWQ-4	supply	background region	1948	5	150	na	5,565.85	andesite	11/10/1982	35.00	5,530.85
GWQ-5R	monitoring	waste rock pile	2011	4	120	in progress	*5,410.00*	andesite	9/29/2011	98.91	*5,311.09*
GWQ-6(N)	supply	background region			85		5,395.36	andesite	6/9/1981	26.95	5,368.41
GWQ-6(S)	supply	background region					5,382.77	andesite			
GWQ-7	supply	tailings impoundment	1932	8	500	na	5,181.60	Santa Fe Group	6/15/1981	77.00	5,104.60
GWQ-8	supply	background region	1931	8	157	na	5,216.94	Santa Fe Group	11/15/1982	68.00	5,148.94
GWQ-9	supply	tailings impoundment	1971	14 + 16	767	na	5,208.13	Santa Fe Group	4/15/1972	60.00	5,148.13
GWQ-10	monitoring	tailings impoundment	1981	3	120	na	5,213.29	Santa Fe Group	9/27/2010	23.19	5,190.10
GWQ-11	monitoring	tailings impoundment	1981	3	70	na	5,196.44	alluvium/Santa Fe Group	5/4/2011	20.02	5,176.42
GWQ-12	monitoring	tailings impoundment	1981	3	137	na	5,237.28	Santa Fe Group	5/4/2011	79.71	5,157.57
GWQ94-13	monitoring	tailings impoundment	1994	5	106	74 to 104.5	5,200.47	Santa Fe Group	5/4/2011	13.02	5,187.45
GWQ94-14	monitoring	tailings impoundment	1994	5	159	127.5 to 157.5	5,192.69	Santa Fe Group	5/4/2011	6.42	5,186.27
GWQ94-15	monitoring	tailings impoundment	1994	5	149	112 to 142	5,183.07	Santa Fe Group	5/4/2011	4.92	5,178.15
GWQ94-16	monitoring	tailings impoundment	1994	5	46	25 to 45	5,197.41	alluvium	5/4/2011	21.76	5,175.65
GWQ94-17	monitoring	tailings impoundment	1994	5	151	120 to 150	5,198.13	Santa Fe Group	9/27/2010	10.11	5,188.02
GWQ94-18	monitoring	tailings impoundment	1994	4	51	10 to 50	5,194.83	alluvium	10/15/1994	dry	
GWQ94-19	monitoring	tailings impoundment	1994	4	53	10 to 50	5,203.36	alluvium	9/27/2010	52.22	5,151.14
GWQ94-20	monitoring	tailings impoundment	1994	4	338	288 to 338	5,203.49	Santa Fe Group	1/27/2010	18.05	5,185.44
GWQ94-21A	monitoring	tailings impoundment	1996	2	263	213 to 263	5,192.71	Santa Fe Group	11/7/1994	4.58	5,188.13
GWQ94-21B	monitoring	tailings impoundment	1996	2	315	285 to 315	5,192.22	Santa Fe Group	11/7/1994	3.95	5,188.27
GWQ96-22A	monitoring	pit/waste rock pile	1996	2	244	174 to 244	5,596.17	andesite	8/28/2011	54.63	5,541.54
GWQ96-22B	monitoring	pit/waste rock pile	1996	2	380	340 to 380	5,595.95	andesite	8/28/2011	54.59	5,541.36
GWQ96-23A	monitoring	pit/waste rock pile	1996	2	101	50 to 100	5,489.84	monzonite	8/28/2011	40.71	5,449.13
GWQ96-23B	monitoring	pit/waste rock pile	1996	2	251	150 to 250	5,489.70	monzonite	8/28/2011	40.87	5,448.83
GWQ11-24A	monitoring	pit/waste rock pile	2011	2	90	60 to 90	*5,514.80*	andesite	8/28/2011	49.86	*5,464.94*
GWQ11-24B	monitoring	pit/waste rock pile	2011	2	250	230 to 250	*5,514.80*	andesite	8/28/2011	56.69	*5,458.11*
GWQ11-25A	monitoring	pit/waste rock pile	2011	2	100	70 to 100	*5,532.00*	monzonite	8/28/2011	50.91	*5,481.09*
GWQ11-25B	monitoring	pit/waste rock pile	2011	2	242	222 to 242	*5,532.00*	monzonite	8/28/2011	62.90	*5,469.10*
IW-1	monitoring	tailings impoundment	1982	4	49	__ to 49	5,198.99	alluvium	6/24/2010	dry	
IW-2	monitoring	tailings impoundment	1982	4	46	__ to 45	5,208.01	alluvium	5/4/2011	39.01	5,169.00
IW-3	monitoring	tailings impoundment	1982	4	45	__ to 45	5,213.17	alluvium	6/24/2010	dry	
NP-1	monitoring	tailings impoundment	1981	4	106	__ to 106	5,188.75	Santa Fe Group	5/4/2011	30.8	5,157.95
NP-2	monitoring	tailings impoundment	1981	4	110	__ to 110	5,192.54	Santa Fe Group	5/4/2011	32.92	5,159.62
NP-3	monitoring	tailings impoundment	1981	4	100	__ to 100	5,199.73	Santa Fe Group	5/4/2011	12.02	5,187.71
NP-4	monitoring	tailings impoundment	1981	4	117	__ to 117	5,225.73	Santa Fe Group	5/4/2011	35.22	5,190.51
NP-5	monitoring	tailings impoundment	1981	4	39	24 to 39	5,198.81	basalt	5/4/2011	22.63	5,176.18
MW-4	supply	background region	1975	6	1,500	123 to 1,500	*5,125.00*	Santa Fe Group	6/9/1981	123.27	5,001.73
Pague	supply	background region			26		5,550.81	andesite	5/4/2011	11.69	5,539.12
Dolores	supply	background region			56		5,397.51	andesite	11/10/1982	29.7	5,367.81
Paxton Well	supply	background region	1932	40 x 40	30		5,500.00	andesite	11/10/1982	7.6	5,492.40
LRG-4156	supply	background region	1956	6	150		5,431.06	andesite	1956	60	5,371.06
LRG-4158	supply	background region	1955	6	150	na	5,533.03	limestone	11/11/2010	47.01	5,486.02
McCravey-G	supply	background region	1931	8	500	na	5,201.53	Santa Fe Group	11/15/1982	40	5,161.53
LRG-4159	supply	background region	2002	6	200	5 to 200	5,719.70	andesite	11/4/2010	13.56	5,706.14

ft bmp - feet below measuring point
ft bgl - feet below ground level
ft amsl - feet above mean sea level
italic measuring-point elevations are estimated
na - not available

B.2.1 Surface Water and Recharge

Precipitation and evaporation in the study area are examined using data from regional meteorological stations. The station at Hillsboro, New Mexico has over 80 years of record and is located about 4 miles from the Copper Flat Mine pit. The Hillsboro station is also at a similar elevation (5,270 ft amsl) to the Copper Flat Mine site. The range of variability of annual precipitation between wet and dry climatic conditions ranges from about 5 to 20 inches per year (in./yr). The average annual precipitation is approximately 13 inches.

The frequency and magnitude of rainfall-runoff events is examined in the statistical distribution of daily precipitation at the Hillsboro station. Daily precipitation of 1 inch or more occurs, on average, twice per year. Storm events of magnitude 2 inches can be expected to occur every 5 years, and the 100-year storm event is about 3.5 inches. Daily precipitation data from the Hillsboro station is shown on Figure 4.

Evaporation has previously been estimated to range between 60 and 65 in./yr. NMCC has installed a weather station and Class A evaporation pan at the mine site. The data will be used to further understand frequency and magnitude of storm-water runoff and to develop water budgets for the mine site and associated facilities.

The area of investigation is within Grayback Arroyo watershed. Grayback Arroyo is an ephemeral stream channel that drains the andesite rock of the Hillsboro Hills and is the primary drainage for the Copper Flat Mine pit area (Fig. 2). Some alluvium can be found along Grayback Arroyo east of Copper Flat Mine pit (Fig. 3). Storm-water runoff from Grayback Arroyo infiltrates alluvium and Santa Fe Group sediments east of Copper Flat. A diversion channel was constructed to divert storm-water around the Copper Flat Mine pit (Fig. 2).

After mining, the pit partially filled with storm water and groundwater. From available water-level data and aerial photographs, it appears the Copper Flat Mine pit filled to its current water level within a few years after mining stopped. A significant portion of the pit filling was related to storm-water runoff and above-average precipitation. Details regarding the pit lake can be referenced from Newcomer and Finch (1993), Shomaker (1993), SRK (1997), and Raugust (2003).

Surface-water monitoring points within the area of investigation include SWQ-1, SWQ-2, SWQ-3, pit lake, and pit wall seepage (Fig. 2). Historical data have been collected from each of these surface-water monitoring points (see Appendix A). SWQ-1 is located upstream of the mine facilities in Grayback Arroyo. SWQ-2 and SWQ-3 are in Grayback Arroyo below the mine pit and waste rock facilities. The pit lake and pit wall seepage monitoring points are within the pit footprint.

B.2.2 Geologic Units and Structure

There are three hydrogeologic units within the Copper Flat Mine site area:

1. alluvium along Grayback Arroyo and colluvium
2. Santa Fe Group sediments
3. andesite and monzonite rocks of the Animas Uplift

A summary of the geologic units and their characteristics is presented in Table 3. The distribution of geologic units is shown on Figure 3, and the subsurface conditions are illustrated on the hydrogeologic cross-sections presented as Figures 5 through 8.

Table 3. Geologic units and their characteristics

geologic unit	description	thickness (ft)	range in estimated hydraulic conductivity (ft/day)
alluvium [1]	sand and gravel in Grayback Arroyo	< 50	10 to 100
colluvium [2]	fan deposits of poorly sorted angular sand and gravel	< 50	1 to 10
Santa Fe Group sediments [3]	highly stratified gravel, sand, silt, and clay	1 to 2,000	0.01 to 10
andesite [4]	fine-grained porphyritic rock with plagioclase phenocrysts	> 3,000	<0.01
monzonite [4]	quartz monzonite with fracture controlled sulfide mineralization; other common minerals include magnetite, fluorite, calcite, and apatite	> 3,000	0.01 to 0.1

[1] - Dunn (1982); Finch et al. (2008)
[2] - Hedlund (1975)
[3] - Seager et al. (1982); Hawley and Kennedy (2004)
[4] - Dunn (1982); SRK (1997); JSAI (work in progress)

The principal water-bearing sediments of the Palomas Basin are (1) alluvial-fan deposits, and fluvial sands and gravels of the Santa Fe Group, and (2) saturated alluvium in the principal drainages. Alluvium is found east of the Copper Flat Mine in Grayback arroyo, and primarily consists of sand and gravel. Thickness of the alluvium ranges between 5 and 50 ft. Alluvium may be locally and seasonally saturated north of the tailings impoundment, and downgradient of the waste rock piles along Grayback Arroyo. Colluvium overlies the andesite and Santa Fe Group sediments, but is only known to be locally saturated near the center of the tailings dam.

The sediments of the Santa Fe Group are stratified, contain a wide variety of grain sizes, and, in general, dip to the east. This distribution of fine-grained sand and clay and of coarser sand and gravel is reflected in the logs of wells in the tailings facility area. North-to-south and east-to-west hydrogeologic cross-sections of the tailings facility area were constructed (see Figs. 7 and 8). The Santa Fe Group sediments are over 500 ft thick beneath the tailings facility.

Hydrogeologic conditions beneath the tailings dam are complicated by varying thickness of colluviums, thick clay layers in the Santa Fe Group sediments, and basalt and volcaniclastics interbedded in the Santa Fe Group sediments (see Figs. 7 and 8). These varying lithologies and sediment grain sizes create preferential flow paths and barriers to groundwater flow. The preferential flow paths are primarily related to coarser-grained colluvium and Santa Fe Group sediments.

The hills surrounding Copper Flat Mine, referred to as Hillsboro Hills, consists of Cretaceous-age andesite flows, breccias, and volcaniclastic rocks that were erupted from an andesite volcano (McLemore, 2001; Raugust and McLemore, 2004). The andesite is a near circular body approximately 4 miles in diameter and over 3,000 ft in depth (Dunn, 1982). The Copper Flat Mine quartz monzonite porphyry intruded the vent of the volcano, and then dikes and mineralized veins intruded the monzonite porphyry and radiate outwards from the porphyry into fault and fracture zones in the andesite. The porphyry copper deposit is a low-grade deposit that is concentrated within a breccia pipe in the Copper Flats quartz monzonite stock and contains copper sulfide and oxide minerals. Distribution of the monzonite can be referenced from the geologic map (Fig. 3) and pit lake cross-sections (Figs. 5 and 6). The permeability of the andesite is extremely low, where as the permeability of the monzonite rocks averages 0.1 ft/day due to localized secondary porosity from fracturing (see Section B.2.4).

B.2.3 Groundwater Flow Direction

The direction of groundwater flow is from west to east, except in the vicinity of the Copper Flat pit lake where a hydrologic sink exists due to evaporative losses. Groundwater-elevation contours are shown on Figure 9, and data used to construct the water-level elevation contours are listed in Table 2. The groundwater-elevation contours indicate groundwater flow from the andesite to the alluvium and Santa Fe Group sediments. Groundwater contours around the pit lake and direction of groundwater flow are shown on Figure 10. Between June and September 2011, evaporative effects decreased the pit lake elevation from 5,443.80 to 5,442.74 ft amsl. The four nested piezometers around the pit provide the data needed to prove the pit lake is a hydrologic sink; two of the nested piezometers were drilled in 2011 (GWQ11-24(A,B) located south of the pit lake and GWQ11-25(A,B) north of the pit lake (Figs. 2 and 10)). There appears to be a hydraulic discontinuity east of the tailings impoundment dam (Figs. 8 and 9).

Depth to water varies significantly due to topography and geologic unit (see Fig. 11). Monitoring wells surrounding the pit lake and waste rock piles typically have a depth to water of 40 to 80 ft. Depth to water in the Grayback Arroyo is approximately 10 to 20 ft bgl, as indicated by GWQ-3, which is a 3.3 ft by 3.6 ft hand-dug concrete cistern (Figs. 2 and 16). Water levels beneath the tailings impoundment significantly rose during operation in 1983; see hydrograph for monitoring wells NP-1 through NP-5 presented as Figure 12. The water-level rise beneath the tailings impoundment is the result of a groundwater mound created by infiltration at the tailings dam and the north to south trending fault approximately 800 ft east of the tailings impoundment. The fault acts as a barrier to groundwater flow (Fig. 8).

B.2.4 Aquifer Characteristics

Source of aquifer test data come from 1) pumping and specific-capacity tests performed on supply wells, 2) injection and slug tests performed on Copper Flat Mine pit lake piezometers, and 3) pumping test performed by Adrian-Brown Consultants (1994) on monitoring wells below the tailings dam.

Hydraulic conductivity values were derived from slug tests performed on wells GWQ96-22 and GWQ96-23 (SRK, 1997). The slug test analysis estimated an extremely low range in hydraulic conductivity of 0.00003 to 0.003 ft/day for the unfractured andesite and quartz monzonite rocks. JSAI (in progress) has evaluated injection tests performed on GWQ-5R (Fig. 2), GWQ11-24, and GWQ11-25 (Figs. 2 and 10). A summary of the hydraulic conductivity estimates is presented as Table 4, and construction diagrams can be referenced from Appendix B.

Table 4. Summary of hydraulic conductivity (permeability) estimates from wells in the vicinity of the pit and waste rock piles

borehole and zone	depth interval (ft)	geologic unit	apparent permeability	
			(cm/sec)	(ft/day)
GWQ-5R, Zone 1	64-100	andesite	~0	~0
GWQ11-24, Zone 1	100-147	monzonite	7×10^{-6}	0.02
GWQ11-24, Zone 2	150-197	monzonite	3.0×10^{-5}	0.085
GWQ11-24, Zone 3	204-251	monzonite	4.9×10^{-5}	0.14
GWQ11-25, Zone 1	100-148	monzonite	~0	~0
GWQ11-25, Zone 2	150-198	monzonite	2.9×10^{-5}	0.081
GWQ11-25, Zone 3	207-251	monzonite	2.6×10^{-5}	0.074

cm/sec - centimeters per second

A representative range of effective bulk hydraulic conductivity for the fractured rock surrounding the pit lake is about 0.05 to 0.1 ft/day. The andesite rocks appear to have an order of magnitude lower hydraulic conductivity than the fractured monzonite as evidenced by the slow recovery of GWQ-5R, which was dry upon well completion on September 6, 2011, but has recovered to an elevation of 5,311 ft amsl on September 29, 2011 (or approximately 23 feet of recovery).

Pumping and specific capacity tests were performed on mine-supply wells MW-4 (Water Development Corporation, 1975), GWQ-1 (Water Development Corporation, 1980), GWQ-7 (W.K. Summers & Associates, 1981), GWQ-9 (Water Development Corporation, 1980). All of these wells are in the vicinity of the tailings facility (Fig. 2). A summary of the hydraulic properties derived from the wells tested in the tailings impoundment area is listed in Table 5.

Table 5. Summary of hydraulic properties estimated from wells in the vicinity of the tailings impoundment

well	pumping rate (gpm)	specific capacity (gpm/ft)	aquifer thickness tested (ft)	transmissivity (ft^2/day)	horizontal hydraulic conductivity (ft/day)
MW-4	60	0.24	1,377	80	0.06
GWQ-1	119	1.57	328	1,540	4.7
GWQ-7	21	2.33	423	440	1.0
GWQ-9	60	0.44	700	1,710	2.4
GWQ94-17	23	0.19	146	200	1.4

gpm - gallons per minute

Adrian-Brown Consultants (1994) performed a 76-hour constant-rate pumping test on GWQ94-17 located below the tailings impoundment (Fig. 2). Neighboring monitoring wells were used as observation wells during the pumping test. The pumping well, GWQ94-17 was pumped at a rate of 23 gallons per minute (gpm). The water levels in the pumping and observation wells never fully recovered to the pre-pumping level, indicating boundary effects from dewatering the groundwater mound observed beneath the tailings dam. Furthermore, the pumping test data confirmed the clay zones observed in the upper Santa Fe Group sediments (see Figs. 7 and 8) act as vertical barriers to groundwater flow.

B.2.5 Water-Quality Trends

Water-quality trends for the Copper Flat Mine area are best identified by changes in sulfate and total dissolved solids (TDS) concentrations. The primary areas of interest for water-quality trends include 1) the pit lake, 2) surface-water runoff in Grayback Arroyo, 3) alluvium and fractured rock along Grayback Arroyo downstream of the waste rock piles, and 4) downgradient of the tailings impoundment.

As shown by time-series graphs presented in Raugust (2003) and the Stage 1 Abatement Plan (INTERA, 2011), the sulfate and TDS concentrations in the pit lake have increased since the late 1980s. The increase in pit lake sulfate and TDS concentrations since the early 1990s is due to evaporation instead of pit wall seepage. Figure 13 is a plot of pit lake sulfate and chloride

concentrations. The observed trend between sulfate and chloride increases linearly with respect to time. If the increasing sulfate concentrations were due to pit wall seepage, sulfate concentrations would increase without an increase in chloride (pit wall seepage has low chloride concentration; see Appendix A). Furthermore, if the increase in sulfate concentrations was due to pit wall seepage and evaporation, the trend on Figure 13 would show sulfate concentrations increasing at a rate greater than the chloride concentrations.

Surface water quality monitoring points SWQ-2 and SWQ-3 have shown increases in sulfate concentration over the last several decades. Figure 14 is a sulfate concentration time-series graph for SWQ-1, SWQ-2, SWQ-3, and GWQ-3. From Figure 14 it appears sulfate concentration has increased over time in Grayback Arroyo surface water downstream of the waste rock piles. However, an increase sulfate concentration is also observed in upgradient monitoring point SWQ-1.

Well GWQ-3 is downstream of SWQ-3 and the waste rock piles, and should be representative of groundwater along Grayback Arroyo. GWQ-3 sulfate concentrations resembled similar values to SWQ-2 in the early 1980s (Fig. 14), but there are no recent data to determine if sulfate concentrations have changed since the 1980s.

Monitoring well NP-3 is located directly downgradient of the tailings impoundment, and has good historical dataset for evaluating trends. Figure 15 is a sulfate and TDS concentration time-series plot for monitoring well NP-3. After the construction and operation of the tailings impoundment in 1983, sulfate and TDS concentrations increased in NP-3 (Fig. 15). As indicated by the 2010 and 2011 sampling events, sulfate and TDS concentrations have remained fairly constant in NP-3. The groundwater mound created by the tailings impoundment (Fig. 11) shows a similar pattern of stability. The lack of change in depth to water and sulfate concentrations are evidence that the sulfate-rich groundwater mound is relatively stable and has not moved.

B.3 Extent of Groundwater Impacts

The extent of groundwater impacts can be identified using data from the existing monitoring network. Available water-quality data for the wells surrounding the mine facilities are listed in Appendix A tables. Table A1 lists water-quality data from the pit lake, Table A2 lists surface-water-quality data, and Table A3 lists groundwater-quality data.

B.3.1 Pit Lake

The pit lake quality has been affected by minor influxes of pit wall seepage and concentration of dissolved constituents from evaporation. The pit lake has buffering capacity to maintain neutral pH (6.00 to 7.72), although high precipitation periods and subsequent pit wall seepage can temporarily exceed the pit lake buffering capacity (see 1990s data in Appendix A). Table 6 lists the constituents of concern (COC) identified from the pit lake chemistry data in Appendix A. The primary COCs are TDS, sulfate, and pH. Pit lake chemistry data from 2010 and 2011 demonstrate that the pit lake is not stratified, and that depth sampling is not necessary (see Appendix A).

Piezometer nests GWQ96-22(A,B) and GWQ96-23(A,B) provide adequate monitoring of upgradient (GWQ96-22(A,B)) and downgradient (GWQ96-23(A,B)) groundwater-quality conditions. Figures 5 and 6 show the distribution of 2011 sulfate concentrations, and, along with the water-level elevation contours (Fig. 10), indicate the pit lake is a hydraulic sink with no impacts to groundwater. Recently constructed nested piezometers GWQ11-24(A,B) and GWQ11-25(A,B) have not been sampled, so the groundwater quality north and south of the pit has not be characterized.

Table 6. Identified constituents of concern for the pit lake

constituent of concern	range in observed concentration (mg/L)
aluminum	0.13 to 5.5
cadmium	0.056 to 0.064
cobalt	0.34 to 0.39
copper	0.11 to 11.0
manganese	39 to 45
selenium	0.019 to 0.030
zinc	5.0 to 6.8
alkalinity	< 20 to 41
chloride	380 to 420
fluoride	15 to 18
sulfate	5,200 to 6,200
total dissolved solids (TDS)	7,770 to 8,700

mg/L - milligrams per liter

B.3.2 Waste Rock Pile(s)

Surface water quality sampling points SWQ-2 and SWQ-3 may provide an indication of water-quality impacts from the waste rock piles. A statistical analysis of the data would need to be performed to determine if a statistically significant increase in concentration has occurred and to determine the difference between pre- and post-mining concentrations from Copper Flat Mine. The primary COCs are sulfate, TDS, and pH. Metal concentrations in surface-water samples have been low or not detectable, and pH has been above neutral in the 7 to 8 range (see Appendix A).

Discharges to groundwater from potential waste rock pile leachate would occur via storm-water runoff. Figure 16 shows the current potential storm-water runoff and migration pathways for each waste rock pile and mill site fill. The pit footprint will capture runoff from nearby waste rock piles to the north and northwest, and Grayback Arroyo will receive runoff from the waste rock piles east of the pit capture area. GWQ-3 is located in Grayback Arroyo, and is the best location downstream of the waste rock pile for detecting discharges to groundwater from the waste rock piles. All of the available data from GWQ-3 were collected in the 1980s, and additional data are needed to determine if groundwater-quality conditions have changed. For future mining operations, the surface runoff from the waste rock piles will be controlled as shown in the Mine Plan of Operations submitted to the Bureau of Land Management (BLM) in June 2011 and currently under review by the NMED.

B.3.3 Tailings Impoundment

The groundwater monitoring network for the tailings impoundment has adequately defined the horizontal and vertical extent of groundwater impacts, except for the lateral extent on the east and downgradient side (see Figs. 7, 8, and 14). The eastern most monitoring wells, GWQ94-21A and GWQ94-21B are completed too deep to characterize the lateral extent of groundwater impacts.

B.4 Hydrogeologic Conceptual Model

The hydrogeologic conceptual model for the Stage 1 Abatement area of investigation can be divided into two segments 1) pit and waste rock piles area underlain by low permeability andesite and monzonite rocks, and 2) the tailings impoundment area underlain by alluvium and Santa Fe Group sediments.

The pit lake is a hydrologic sink with no discharges to groundwater. The andesite rocks acts as a hydraulic container for the more fractured monzonite rocks. Prior to the pit lake, groundwater discharged from the andesite and monzonite rocks due to the alluvium along Grayback Arroyo. The waste rock piles are more permeable than the underlying rock, and infiltrated precipitation will drain off at the waste rock-bedrock interface. The runoff from the waste rock piles will be intercepted by the mine pit and the mill site fill to Grayback Arroyo. As a result, the waste rock and mill site fill may be contributing to increased TDS in downgradient surface-water quality, but significant discharges to groundwater have not been adequately evaluated from the existing groundwater monitoring network (see data for GWQ-3 and GWQ-8 in Appendix A).

The tailings impoundment created a groundwater mound and discharges of increased sulfate and TDS to groundwater. Preferential pathways for the seepage include the alluvium, fractured basalt, and coarser-grained Santa Fe Group sediments. Clay layers in the Santa Fe Group sediments act as vertical barriers to groundwater flow. The sulfate plume appears to be stable (the groundwater mound has not subsided) and downgradient migration is limited by a barrier boundary fault.

C. PROPOSED SITE INVESTIGATION WORKPLAN

A good portion of the proposed site investigation workplan has been completed in 2010 and 2011, such as the drilling and testing of piezometer nests in the pit lake area, collection of additional water-level and water-quality data in the area of investigation, and evaluation of current hydrogeologic conditions (such as Section B of this amendment report). The proposed site investigation workplan is designed to characterize potential water-quality issues and define extent of impacts related to the existing mine facilities (pit, waste rock piles, and tailings impoundment).

C.1 Pit Lake

In addition to the two existing piezometer nests, in 2011 NMCC had two more piezometer nests installed north and south of the pit lake (Fig. 2). The four piezometer nests (GWQ96-22(A,B), GWQ96-23(A,B), GWQ11-24(A,B), and GWQ11-25(A,B)) allow for monitoring upgradient, offgradient, and downgradient of the pit lake, as well as with respect to aquifer depth. No additional drilling is proposed for pit lake characterization.

The proposed pit lake investigation includes the following:

1. Collect four quarters of water-quality data from the pit lake, pit wall seepage, and surrounding piezometers.

2. Collect four quarters of water-level data from the pit lake and surrounding piezometer nests.

3. Develop a revised water balance for the pit lake using water-quality data, on-site climate data, and pit lake elevation data.

4. Perform an analysis of the pit lake chemistry to determine if there are past, current, and future issues with meeting the applicable surface water-quality standards.

C.2 Waste Rock Pile(s)

A preliminary waste rock pile characterization study was performed by Newcomer and Finch (1993), and more detailed evaluations of waste-rock characterization were performed by SRK (1998). Currently SRK is finishing where it left off in 1998 by performing material tests on 70 samples collected in 2010. Details of the SRK waste rock pile characterization can be referenced from appendix f in the proposed Stage 1 Abatement Plan (INTERA, 2011).

The proposed waste rock investigation plan includes the following:

1. Results from the waste rock characterization will be compared to water-quality results obtained from surface-water runoff samples SWQ-1, SWQ-2, SWQ-3, and groundwater sampled from the pit area piezometer nests and downgradient wells GWQ-1, GWQ-3, GWQ-5R, and GWQ-8.

2. The historical surface water quality data will be statistically evaluated for significant increases in concentrations of TDS and sulfate. Trend analysis and geochemical analysis of other water-quality parameters will be used to verify statistically significant increases in sulfate and TDS. The purpose of the investigation is to determine if the increases in sulfate and TDS in surface water and downgradient groundwater are attributed to the waste rock pile(s) or some other influence such as climate, salt build up in soils, etc. Characterization of background chemistry will be incorporated into the analysis.

3. Collect samples from GWQ-1, GWQ-3, GWQ-5R, and GWQ-8. The groundwater-quality data will help characterize the extent of lateral and vertical groundwater impacts if the leachate from the waste rock piles is determined to be associated with increases of sulfate and TDS in downgradient groundwater.

NMCC is currently working on BLM access for the wells GWQ-1 and GWQ-8. NMCC will also have to establish BLM access to GWQ-3, now that this report has identified it as potential aid in assessing and monitoring water quality downgradient of the mine site. NMCC will not be able to gauge or sample these wells until the BLM access has been granted and in the case of GWQ-8, a cultural resources evaluation completed.

C.3 Tailings Impoundment Facility

Proposed investigation for the tailings impoundment facility includes the drilling of one or two monitoring wells downgradient of the known extent of the sulfate plume. Downgradient monitoring wells GWQ94-14 and GWQ94-21 are too deep to assess the lateral extent of the sulfate plume (Fig. 7). Proposed monitoring well locations are shown on Figures 7 and 17; the actual locations may depend on land ownership and access, and may slightly vary from the proposed location.

The proposed tailings impoundment investigation plan includes:

1. Install the first monitoring well (proposed monitoring well A) located east of GWQ94-21, but west of the fault zone shown on Figure 7. If proposed monitoring well A does not define the eastward extent of the sulfate plume, proposed monitoring well B will be drilled east of the projected fault zone. A 60-ft screen interval is proposed for monitoring well A to accommodate the possibility of the groundwater mound lowered to the pre-tailings water-level elevation.

2. Data from existing and proposed monitoring wells will be used to assess the sulfate plume extent and stability. Known aquifer properties, water-level trends, and vertical head distribution will be used to assess the stability of the sulfate plume and potential tracer velocity under current conditions.

D. PROPOSED MONITORING PLAN

Sampling methods and protocol defined in the NMCC Sampling and Analysis Plan (SAP), prepared for baseline studies, will be employed. The proposed Stage 1 Abatement monitoring plan is based on the identified COCs, and the need for further characterization within the area of investigation.

D.1 Pit Lake

Monitoring plan includes collection of data from 1) pit lake, 2) surrounding piezometer nests, and 3) on site weather station. Four quarters of data are needed from the new wells GWQ11-24(A,B), GWQ11-25(A,B). The proposed pit lake monitoring plan includes sample analyses for pH, acidity, general chemistry, and the remaining constituents listed in Table 6. The proposed pit lake area monitoring plan is summarized in Table 7. Another 6 months of weather station data collection will help define the pit lake water balance.

Table 7. Proposed monitoring plan for Copper Flat pit lake area

monitoring point	4th QTR 2011	1st QTR 2012	2nd QTR 2012	3rd QTR 2012
GWQ96-22(A,B)	WL, WQ	WL	WL	WL
GWQ96-23(A,B)	WL, WQ	WL	WL	WL
GWQ11-24(A,B)	WL, WQ	WL, WQ	WL, WQ	WL, WQ
GWQ11-25(A,B)	WL, WQ	WL, WQ	WL, WQ	WL, WQ
pit lake	WL, WQ	WL, WQ	WL, WQ	WL, WQ
pit wall seepage (if present)	WQ	WQ	WQ	WQ

WQ - water-quality analysis (Table 6 constituents plus calcium, magnesium, sodium, potassium, and field parameters of temperature, specific conductance, and pH)
WL - water level

D.2 Waste Rock Pile(s)

Most of the proposed waste rock pile investigation will be based on existing data and results from studies already in progress by SRK. However, there is a need for current data from downgradient wells. Table 8 lists the proposed groundwater monitoring program for the waste rock pile investigation. Proposed data collected from the pit lake area (Table 7) would also be incorporated into the waste rock pile investigation.

NMCC also has automated samplers for collection of storm-water runoff from SWQ-1, SWQ-2, and SWQ-3. If events occur and are samples collected, the data will be incorporated into the investigation.

Table 8. Proposed monitoring plan for Copper Flat waste rock pile area

monitoring point	4th QTR 2011*	1st QTR 2012*	2nd QTR 2012*	3rd QTR 2012*
GWQ-5R	WL, WQ	WL, WQ	WL, WQ	WL, WQ
GWQ-3	WL, WQ	WL, WQ	WL, WQ	WL, WQ
GWQ-1	WL, WQ	WL, WQ	WL, WQ	WL, WQ
GWQ-8	WL, WQ	WL, WQ	WL, WQ	WL, WQ

* access and schedule dependent on land owner permission or BLM right-of-way permitting (including evaluation of cultural resource issues, etc.)
WQ - water-quality analysis (total dissolved solids (TDS), sulfate, chloride, alkalinity, calcium, magnesium, sodium, potassium, and field parameters of temperature, specific conductance, and pH)
WL - water level

D.3 Tailings Impoundment Facility

There are numerous monitoring wells in the vicinity of the tailings impoundment, and many of these are no longer needed for characterization and investigation of the sulfate plume. The proposed sampling plan for the tailings impoundment investigation includes the wells and parameters listed in Table 9. Several of the wells listed in Table 9 are currently dry, but data would be needed from these points if water were present. Access to MW-4 will depend on permitting from the land owner, and drilling, construction, and data collection from proposed monitoring well B is dependent on what is found at proposed monitoring well A.

Table 9. Proposed monitoring plan for Copper Flat Mine tailings impoundment area

monitoring point	4th QTR 2011*	1st QTR 2012*	2nd QTR 2012*	3rd QTR 2012*
IW-1	WL, WQ	WL, WQ	WL, WQ	WL, WQ
IW-2	WL, WQ	WL, WQ	WL, WQ	WL, WQ
IW-3	WL, WQ	WL, WQ	WL, WQ	WL, WQ
GWQ94-13	WL, WQ	WL, WQ	WL, WQ	WL, WQ
GWQ94-14	WL, WQ	WL, WQ	WL, WQ	WL, WQ
GWQ94-16	WL, WQ	WL, WQ	WL, WQ	WL, WQ
GWQ94-18	WL, WQ	WL, WQ	WL, WQ	WL, WQ
GWQ94-19	WL, WQ	WL, WQ	WL, WQ	WL, WQ
NP-3	WL, WQ	WL, WQ	WL, WQ	WL, WQ
MW-4	WL, WQ	WL, WQ	WL, WQ	WL, WQ
proposed MW-A	WL, WQ	WL, WQ	WL, WQ	WL, WQ
proposed MW-B	WL, WQ	WL, WQ	WL, WQ	WL, WQ

* access and schedule dependent on land owner permission or BLM right-of-way permitting (including evaluation of cultural resource issues, etc.)

WQ - water-quality analysis (total dissolved solids (TDS), sulfate, chloride, alkalinity, calcium, magnesium, sodium, potassium, and field parameters of temperature, specific conductance, and pH)

WL - water level

E. REFERENCES

Adrian-Brown Consultants, 1994, Tailings Dam area pumping test: consultant's report prepared by Adrian-Brown Consultants for Steffen Robertson and Kirsten, Reno Nevada

Adrian Brown Consultants, Inc., 1996, Copper Flat Project Hydrologic Impact Evaluation: Consultant's report prepared for Alta Gold, September 26, 1996

Dunn, P. G., 1982, Geology of the Copper Flat Porphyry Copper Deposit, Hillsboro, Sierra County, New Mexico: In Advances in Geology of the Porphyry Copper Deposits Southwestern North America, Spencer R. Titley, Editor, University of Arizona Press, Tucson, Arizona, pp. 313-325.

Finch, S. T., McCoy, A., and Melis, E., 2008, Geologic controls on ground-water flow in the Mimbres Basin, Southwestern New Mexico: New Mexico Geological Society Guidebook, 59th Field Conference, Geology of the Gila Wilderness – Silver City area, pp. 189-198

Harley, G. T., 1934, The Geology and Ore Deposits of Sierra County, New Mexico: New Mexico School of Mines, State Bureau of Mines and Mineral Resources Bulletin No. 10, pp. 160- 170.

Hawley, J.W., and Kennedy, J.F., 2004, Creation of a digital hydrogeologic framework model of the Mesilla Basin and Southern Jornada Del Muerto Basin: New Mexico Water Resources Research Institute Technical Completion Report No. 332, 105 p. plus CD.

Hedlund, D. C., 1975, Geologic map of the Hillsboro quadrangle, Sierra and Grant Counties, New Mexico: U.S. Geological Survey Open-File Report 75-108, 19 p.

INTERA (2010 to current), work in progress for New Mexico Copper Corporation

INTERA, 2011, Stage 1 Abatement Plan for the Copper Flat Mine: Consultant's report prepared for New Mexico Copper Corporation, March 31, 2001, Volume 1 of 2.

[JSAI] John Shomaker & Associates, Inc., 2011, work in progress for New Mexico Copper Corporation

McLemore, V., 2001, Geology and evolution of the Copper Flat porphyry system, Sierra County, New Mexico:

Newcomer, R. W., and Finch, S. T., 1993, Water quality and impacts of proposed mine and mill, Copper Flat Mine Site, Sierra County, New Mexico: Consultant's report prepared by John W. Shomaker, Inc. for Gold Express Corporation, 31 p.

Raugust, J. S., 2003, The Natural Defense of Copper Flat Sierra County, New Mexico: New Mexico Bureau of Geology and Mineral Resources Open-File Report 475

Raugust, S., and McLemore, V., 2004, The Natural Defenses of Copper Flat, Sierra County, New Mexico: American Society of Mining and Reclamation, 2004 National Meeting of the American Society of Mining and Reclamation and the 25th West Virginia Surface Mine Drainage Task Forces, April 18-24, 2004, pp. 1508 -1531

Seager, W. R., Clemons, R. E., Hawley, J. W., and Kelley, R. E., 1982, Geology of northwest part of Las Cruces 1° to 2° sheet, New Mexico: New Mexico Bureau of Mines and Mineral Resources Bulletin 97, 38 p.

Shomaker, J. W., 1993, Effects of pumping for water supply and mine dewatering, Copper Flat Project, Sierra County, New Mexico: Consultant's report prepared by John W. Shomaker, Inc. for Gold Express Corporation, 19 p.

SRK, 1996, Geochemical review of waste rock, pit lake water quality and tailings: Consultant's report prepared by Steffen Robertson and Kirsten, Inc. prepared for Alta Gold Co.

SRK, 1997, Copper Flat Mine Compilation of Pit Lake Studies: Consultant's report prepared by Steffen Robertson and Kirsten, Inc. prepared for Alta Gold Co., December 1997.

SRK, 1998, Copper Flat Waste Rock Management Plan: Consultant's report prepared by Steffen Robertson and Kirsten, Inc. prepared for Alta Gold Co.

Water Development Corporation, 1975, Letter report regarding the drilling and testing of Mine Supply Well MW-4, prepared for Quintana Minerals Corporation, July 10, 1975.

Water Development Corporation, 1980, Letter report regarding the testing of Inspiration North (IDW-2) and South (IDW-1) wells, prepared for Quintana Minerals Corporation, August 14, 1975.

W.K. Summers & Associates, 1981, Step pumping test of water well GWQ-7, Copper Flat, New Mexico: consultant's report prepared by W.K. Summers & Associates prepared for Quintana Minerals Corporation, T or C, New Mexico, 61 p.

ILLUSTRATIONS



Figure 1. Regional map showing locations of Copper Flat Mine permit area, watersheds, and geographical features, Sierra County, New Mexico.



Figure 2. Map of proposed Stage 1 Abatement Plan area of investigation, Copper Flat Mine facilities, and monitoring point locations, Copper Flat Mine, Sierra County, New Mexico.



Figure 3. Geologic map showing distribution of hydrogeologic units within the area of investigation and lines of section for tailings impoundment area, Copper Flat Mine, Sierra County, New Mexico.



Figure 4. Graph of daily precipitation at Hillsboro, New Mexico for the time period 1980 to 2010.



Figure 5. Hydrogeologic cross-sections PA-PA' and PX-PX', Copper Flat Mine pit lake area, Sierra County, New Mexico.



Figure 6. Hydrogeologic cross-section PB-PB', Copper Flat Mine pit lake area, Sierra County, New Mexico.



Figure 7. West to east geologic cross-section TA-TA' showing Copper Flat Mine tailings area, Sierra County, New Mexico.



Figure 8. North to south geologic cross-section TB-TB' showing Copper Flat Mine tailings area, Sierra County, New Mexico.



Figure 9. Water-level elevation contour map for Stage 1 Abatement Plan area of investigation, Copper Flat Mine, Sierra County, New Mexico.

JOHN SHOMAKER & ASSOCIATES, INC.

02228



Figure 10. Aerial photograph showing water-level elevation contours and direction of groundwater flow for the Copper Flat Mine pit lake area, Sierra County, New Mexico.



Figure 11. Map showing depth to water in the Copper Flat Mine permit boundary facilities, Sierra County, New Mexico.



Figure 12. Graph showing historical water levels for monitoring wells NP-1 through NP-5, Copper Flat Mine tailings facility, Sierra County, New Mexico.



Figure 13. Graph of sulfate versus chloride concentrations for Copper Flat Mine pit lake, Sierra County, New Mexico.



Figure 14. Time-series sulfate concentration plot for SWQ-1, SWQ-2, SWQ-3, and GWQ-3, Copper Flat Mine, Sierra County, New Mexico.



Figure 15. Time-series sulfate and total dissolved solids (TDS) concentrations plot for monitoring well NP-3, Copper Flat Mine tailings impoundment area, Sierra County, New Mexico.



Figure 16. Map showing locations of waste-rock piles, surface-water and groundwater monitoring points, and potential waste-rock leachate migration pathways, Copper Flat Mine, Sierra County, New Mexico.



Figure 17. Map showing lateral extent of sulfate plume associated with Copper Flat Mine tailings impoundment facility and proposed monitoring wells, Sierra County, New Mexico.

APPENDICES

Appendix A.

Revised tables from Stage 1 Abatement Plan dated March 31, 2011 (INTERA, 2011)

Table A-1. Pit lake water-quality data

Table A-2. Surface-water-quality data

Table A-3. Groundwater-quality data

Appendix A.

Table A-1. Pit lake water-quality data

sample location	analysis date	silver (mg/L)	aluminum (mg/L)	arsenic (mg/L)	barium (mg/L)	beryllium (mg/L)	boron (mg/L)	cadmium (mg/L)	cobalt (mg/L)	chromium (mg/L)	copper (mg/L)	iron (mg/L)	mercury (mg/L)	manganese (mg/L)	molybdenum (mg/L)	nickel (mg/L)	lead (mg/L)	antimony (mg/L)	selenium (mg/L)	thallium (mg/L)
PL-WQ	4/3/1989	<0.1	<0.1		<0.1	<0.1	<0.1	<0.1	<0.05	<0.1	<0.1	<0.1		1.10	<0.1	<0.1	<0.1			
PL-WQ	11/14/1990																			
PL-WQ	2/11/1991	0.03		<0.001	<0.01			0.035		0.06		0.18	0.0004	1.84			0.006		<0.001	
PL-WQ	7/19/1991	<0.02		<0.002	<0.01			<0.005		<0.02		0.27	<0.0002	2.03			<0.005		<0.001	
PL-WQ	8/29/1991										0.64									
PL-WQ	11/26/1991										0.08									
PL-WQ	3/15/1992																			
PL-WQ	5/25/1992																			
PL-WQ	7/16/1992																			
PL-WQ	10/8/1992																			
PL-WQ	11/27/1992																			
PL-WQ	12/15/1992										3.21									
PL-WQ	2/25/1993																			
PL-WQ	9/23/1993										0.00			0.02						
PL-WQ	3/17/1994	<0.02									0.09			4.43						
PL-WQ	9/22/1994																			
PL-WQ	12/12/1994	<0.025	<0.05	<0.005	<0.1	<0.002	<0.1	0.017	<0.05	<0.025	0.03	<0.05	<0.001	3.60	<0.05	<0.05	<0.005	<0.005	<0.005	<0.005
PL-WQ	12/19/1994	<0.025	<0.05	<0.005	<0.1	<0.002	<0.1	0.017	<0.05	<0.025	0.03	<0.05	<0.001	3.40	<0.05	<0.05	<0.005	<0.005	<0.005	<0.005
PL-WQ	1/29/1995																			
PL-WQ	3/29/1995																			
PL-WQ	6/27/1995																			
PL-WQ	9/21/1995	<0.025	0.13	<0.005	<0.05	<0.002	<0.1	0.014	<0.05	<0.025	<0.025	<0.05	<0.001	3.00	<0.05	<0.05	<0.005	<0.005	<0.25	<0.005
PL-WQ	1/10/1996																			
PL-WQ	4/3/1996																			
PL-WQ	9/25/1996																			
PL-WQ	1/15/1997																			
PL-NW	6/20/2008																			
PL-E	6/20/2008																			
PL-WQ (0 ft)	1/30/2010	<0.025	5.50	0.006	<0.010	0.017	<0.20	0.056	0.37	<0.030	11.00	1.30	<0.00020	41.00	<0.040	0.067	<0.025	<0.0025	0.031	<0.0050
PL-WQ-03 (3 ft)	9/10/2010	<0.005	1.70	<0.001	0.012	0.016	0.13	0.063	0.34	<0.006	2.00	0.03	<0.0002	45.00	0.015	0.067	<0.005	<0.001	0.021	<0.005
PL-WQ-01 (28 ft)	9/10/2010	<0.0050	1.60	<0.001	0.012	0.016	0.13	0.064	0.35	<0.006	1.90	0.03	<0.0002	44.00	0.015	0.068	0.0054	<0.001	0.022	<0.001
PL-WQ-04 (comp)	9/10/2010	<0.005	1.60	<0.001	0.011	0.015	0.13	0.061	0.33	<0.006	1.90	0.02	<0.0002	43.00	0.015	0.065	0.0056	<0.001	0.023	<0.005
PL-WQ-05 (7ft)	1/20/2011	<0.025	0.48	<0.001	0.010	0.016	<0.2	0.062	0.39	<0.03	0.61	<0.1	<0.0002	42.00	<0.04	0.069	<0.025	<0.001	0.025	<0.001
PL-WQ-06 (17 ft)	1/20/2011	<0.025	0.51	<0.001	0.011	0.016	<0.2	0.062	0.38	<0.03	0.59	<0.1	<0.0002	44.00	<0.04	0.066	<0.025	<0.001	0.025	<0.005
PL-WQ-07 (26 ft)	1/20/2011	<0.025	0.54	<0.005	0.012	0.016	<0.2	0.061	0.39	<0.03	0.64	<0.1	<0.0002	39.00	<0.04	0.068	0.026	<0.005	0.031	<0.005
PL-WQ-08 (comp)	1/20/2011	<0.025	0.48	<0.005	0.010	0.015	<0.2	0.060	0.37	<0.03	0.59	<0.1	<0.0002	44.00	<0.04	0.066	<0.025	<0.005	0.030	<0.005
PL-WQ-09 (1 ft)	4/14/2011	<0.0050	0.13	<0.0010	0.012	0.010	0.16	0.059	0.34	< 0.006	0.11	< 0.020	< 0.00020	44.00	0.025	0.061	< 0.0050	< 0.0010	0.019	< 0.0010
PL-WQ-10 (3 ft)	4/14/2011	<0.0050	0.13	<0.0010	0.012	0.010	0.16	0.057	0.33	< 0.0060	0.11	< 0.020	< 0.00020	41.00	0.023	0.058	< 0.0050	< 0.0010	0.019	< 0.0010
PL-WQ-11 (16 ft)	4/14/2011	<0.0050	0.13	<0.0010	0.012	0.010	0.16	0.058	0.34	< 0.0060	0.12	< 0.020	< 0.00020	41.00	0.024	0.059	0.0055	< 0.0010	0.020	< 0.0010
PL-WQ-12 (comp)	4/14/2011	<0.0050	0.13	<0.0010	0.012	0.010	0.16	0.059	0.34	< 0.0060	0.12	< 0.020	< 0.00020	42.00	0.024	0.060	< 0.0050	< 0.0010	0.023	< 0.0010
pit wall seepage	2/25/1993		3720.00								684.00	375.00		142.00						
pit wall seepage	8/19/2010	<0.25	540.00	0.0016	<0.1	0.140	<0.2	0.140	1.50	<0.3	80.00	1600.00	<0.001	24.00	<0.4	<0.5	<0.25	<0.01	0.086	<0.0010

Notes: no data are available for blank cells (not analyzed)
outlier values in gray shading

Appendix A.

Table A-1. Pit lake water-quality data

sample location	analysis date	uranium (mg/L)	vadium (mg/L)	zinc (mg/L)	pH (std. units)	specific conductance (µS/cm)	total dissolved solids (mg/L)	total alkalinity (mg/L as CaCO3)	nitrate as total N (mg/L)	total cyanide (mg/L)	calcium (mg/L)	magnesium (mg/L)	sodium (mg/L)	potassium (mg/L)	carbote (mg/L)	bicarbote (mg/L)	chloride (mg/L)	sulfate (mg/L)	fluoride (mg/L)	ammonia (mg/L)	total suspended solids	comments
PL-WQ	4/3/1989			0.4			3,546				640	129	165	11		96	47	2,240				
PL-WQ	11/14/1990						4,064										102	2,770				
PL-WQ	2/11/1991				7.20	3,980	2,711		0.1		600	157.3	224	16.4	0	55	80	2,437	4.8			
PL-WQ	7/19/1991				7.76	6,340	4,520		0.03		684	209.1	248	20.3	0	88	89	2,920	6.3			
PL-WQ	8/29/1991				7.61		4,384										89	2,674				
PL-WQ	11/26/1991				7.61		4,175										87	2,540				
PL-WQ	3/15/1992				4.88		3,819										85	2,857				
PL-WQ	5/25/1992				4.82		3,846										90	2,665				
PL-WQ	7/16/1992				4.36		4,229										76	2,397				
PL-WQ	10/8/1992				4.85		4,258										90	2,706				
PL-WQ	11/27/1992				6.26		3,900										731	2,500				
PL-WQ	12/15/1992				6.04		4,151										89	2,902				
PL-WQ	2/25/1993				6.29		3,951										92	2,748				
PL-WQ	9/23/1993			0.0	6.71		4,468										111	1,566				
PL-WQ	3/17/1994			1.0	7.46		3,179										101	2,670				
PL-WQ	9/22/1994				8.04		5,124										141					
PL-WQ	12/12/1994			0.1	7.71	4,720	4,600		<5		580	250	350	17	0	102	140	2,910	8.1			
PL-WQ	12/19/1994			0.1	7.52	4,690	4,380		<5		550	250	320	18	0	104	130	2,970	8.1			
PL-WQ	1/29/1995				7.69		4,675										218	2,906				
PL-WQ	3/29/1995				7.53		4,891										109	2,610				
PL-WQ	6/27/1995						5,640										161	2,924				
PL-WQ	9/21/1995			0.1	8.31	5,230	5,230		<5		620	300	430	21	0	122	150	3,170	10.0			
PL-WQ	1/10/1996				7.90		5,398										183	3,452				
PL-WQ	4/3/1996				7.95		5,378										189	3,304				
PL-WQ	9/25/1996				8.26		6,041										200	3,290				
PL-WQ	1/15/1997				8.05		5,772										216	3,509				
PL-NW	6/20/2008				4.43		7,540	<2.5			504	485	624	23	<2.5	<3	259	4,520				NMED
PL-E	6/20/2008				4.43		7,950	<2.5			508	495	638	24	<2.5	<3	230	4,460				NMED
PL-WQ (0 ft)	1/30/2010			6.4	6.00	5,700	7,770	<20	<2.0		540	570	690	25	<2.0	<20	390	5,200	18.0			
PL-WQ-03 (3 ft)	9/10/2010	0.12	<0.05	6.8	6.71	6,700	8,390	<20	<1.0		580	640	760	26	<2	<20	400	5,600	17.0		<10	
PL-WQ-01 (28 ft)	9/10/2010	0.12	<0.05	6.7	6.67	6,600	8,400	<20	<1.0		570	630	750	26	<2	<20	400	6,200	18.0		<10	
PL-WQ-04 (comp)	9/10/2010	0.11	<0.05	6.6	6.70	6,700	8,340	<20	<1.0		560	610	730	26	<2	<20	380	6,000	15.0		<10	
PL-WQ-05 (7ft)	1/20/2011	0.11	<0.25	5.8	7.17	7,900	8,170	31	<0.1		570	640	740	29	<2	31	380	5,700	15.0	<1	<10	
PL-WQ-06 (17 ft)	1/20/2011	0.11	<0.25	5.7	7.19	8,000	8,120	31	<0.1		570	640	740	29	<2	31	380	5,600	16.0	<1	12	
PL-WQ-07 (26 ft)	1/20/2011	0.11	<0.25	6.0	7.18	8,000	8,210	30	<0.1		590	660	760	29	<2	30	400	5,900	16.0	<1	<10	
PL-WQ-08 (comp)	1/20/2011	0.11	<0.25	5.3	7.23	8,000	7,780	30	<0.1		520	590	680	28	<2	30	380	5,500	16.0	<1	14	
PL-WQ-09 (1 ft)	4/14/2011	0.11	< 0.050	5.2	7.62	7,800	8,590	41	< 0.10		610	680	800	32	< 2.0	41	420	5,600	17.0	< 1.0	< 10	
PL-WQ-10 (3 ft)	4/14/2011	0.12	< 0.050	5.0	7.68	7,800	8,700	41	< 0.10		600	670	790	32	< 2.0	41	420	5,800	16.0	< 1.0	< 10	
PL-WQ-11 (16 ft)	4/14/2011	0.12	< 0.050	5.1	7.69	7,800	8,600	41	< 0.10		590	660	770	32	< 2.0	41	400	5,700	16.0	< 1.0		
PL-WQ-12 (comp)	4/14/2011	0.11	< 0.050	5.0	7.72	7,800	8,390	41	0.1		600	670	780	32	< 2.0	41	410	5,700	16.0	< 1.0	< 10	
pit wall seepage	2/25/1993			51.0	1.90				0.9		446	236	93	3.1		<1	35	10,000	11.1			
pit wall seepage	8/19/2010	1.40	<2.5	12.0	2.00	6,500	13,900	<20	<1.0	<0.005	470	190	<50	<50	<2	<20	21	11,000	51.0			

Notes: no data are available for blank cells (not analyzed)
outlier values in gray shading

Appendix A.
Table A-2. Surface-water-quality data

sample location	analysis date	silver (mg/L)	aluminum (mg/L)	arsenic (mg/L)	barium (mg/L)	beryllium (mg/L)	boron (mg/L)	cadmium (mg/L)	cobalt (mg/L)	chromium (mg/L)	copper (mg/L)	iron (mg/L)	mercury (mg/L)	manganese (mg/L)	molybdenum (mg/L)	nickel (mg/L)	lead (mg/L)	antimony (mg/L)	selenium (mg/L)	thallium (mg/L)	uranium (mg/L)	vanadium (mg/L)	zinc (mg/L)	pH (std. units)	specific conductance (µS/cm)	total dissolved solids (mg/L)	total alkalinity (mg/L as CaCO3)	nitrate as total N (mg/L)	total cyanide (mg/L)	calcium (mg/L)	magnesium (mg/L)	sodium (mg/L)	potassium (mg/L)	carbonate (mg/L)	bicarbonate (mg/L)	chloride (mg/L)	sulfate (mg/L)	fluoride (mg/L)	original order
SWQ-1	12/28/1982							<0.005			<0.05	<0.01	<0.001	<0.05	<0.05				<0.005					8.00		250		0.90	<0.01							10.0	68	0.3	1
SWQ-1	2/21/1983							<0.005			<0.05	<0.01	<0.001	<0.05	<0.05				<0.005					8.00		470		4.40	<0.01							20.0	161	0.3	2
SWQ-1	7/16/1992																							7.37		965										47.2	298		3
SWQ-1	11/27/1992																							8.31		545										16.7	181		4
SWQ-1	2/25/1993																							8.34		844										28.9	323		5
SWQ-1	4/1/1993	<0.01	<0.1	<0.005	<0.5		0.02	<0.002	<0.05	<0.02	<0.01	<0.05	<0.001	<0.02	<0.02	<0.01	<0.02		<0.005				<0.01	8.30	1,150	782	360	0.00	<0.01	109	36	107	1.8	0	430	27.0	276	0.5	6
SWQ-2	10/27/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	<0.05	0.004	<0.05	<0.05		<0.02		<0.005					8.70		1,060		6.60	<0.01	175						46.0	460	0.8	7
SWQ-2	2/25/1982							<0.005			<0.05	0.13	<0.001	<0.05	<0.05				<0.005					8.10		1,360		4.20	<0.01							80.0	658	0.7	8
SWQ-2	5/12/1982							<0.005			<0.05	<0.01	<0.001	<0.05	<0.05				<0.005					7.90		1,380		3.00	<0.01							108.0	700	0.7	9
SWQ-2	2/21/1983							<0.005			<0.05	<0.01	<0.001	<0.05	<0.05				<0.005					8.40		990		0.80	<0.01							68.0	445	0.7	10
SWQ-2	5/13/1983							<0.005			<0.05	<0.01	<0.001	<0.05	<0.05				<0.005					8.40		1,120		0.30	<0.01							84.0	517	0.8	11
SWQ-2	8/9/1983							<0.005			<0.05	<0.01	<0.001	0.06	<0.05				<0.005					8.00		1,620		<0.20	<0.01							142.0	675	0.7	12
SWQ-2	11/1/1983							<0.005			<0.05	<0.01	<0.001	<0.05	<0.05				<0.005					8.20		1,170		0.30	<0.01							72.0	553	0.8	13
SWQ-2	12/23/1983							<0.005			<0.05	<0.01	<0.001	<0.05	<0.05				<0.005					8.00		1,180		11.20	<0.01							82.0	550	0.5	14
SWQ-2	3/16/1984							<0.005			<0.05	<0.01	<0.001	<0.05	<0.05				<0.005					8.30		1,140		5.30	<0.01							68.0	515	0.8	15
SWQ-2	5/30/1984							<0.005			<0.05	<0.01	<0.001	<0.05	<0.05				<0.005					8.10		1,420		0.40	<0.01							94.0	720	0.8	16
SWQ-2	9/12/1984							<0.005			<0.05	<0.01	<0.001	<0.05	<0.05				<0.005					8.10		1,190		0.40	<0.01							80.0	577	0.9	17
SWQ-2	11/27/1984							<0.005			<0.05	<0.01	<0.001	<0.05	<0.05				<0.005					8.20		1,360		<0.20	<0.01							88.0	675	0.8	18
SWQ-2	5/17/1985																							8.00		1,640										102.0	770		19
SWQ-2	11/13/1985																							7.90		1,590										94.0	770		20
SWQ-2	10/13/1986																							7.90		1,840										136.0	830		21
SWQ-2	7/19/1991	<0.02		<0.002	<0.01			<0.005		<0.02		<0.05	<0.0002	<0.02			<0.005		<0.001					7.57	4,310	3,019		12.74		561	129	264	10.9	0	362	216.7	1,586	0.6	22
SWQ-2	7/16/1992																							7.57		2,305										93.4	1,155		23
SWQ-2	10/8/1992																							7.53		2,685										130.7	1,471		24
SWQ-2	12/15/1992																							7.61		3,108										192.5	1,613		25
SWQ-2	2/25/1993																							7.58		2,713										135.9	1,459		26
SWQ-2	3/31/1993	<0.01	<0.1	<0.005	<0.5		0.08	<0.002	<0.05	<0.02	0.01	<0.05	<0.001	0.03	<0.02	<0.01	<0.02		0.008				0.01	7.70	3,150	2,720	300	14.50	<0.01	436	83	279	2.1	0	376	123.0	1,460	0.6	27
SWQ-2	6/23/1994																							8.87		3,958										197.3	2,369		28
SWQ-2	1/29/1995																							7.64		2,653										89.2	1,286		29
SWQ-2	3/29/1995																							7.83		2,866										83.9	1,388		30
SWQ-2	6/27/1995																							7.74		3,235										127.3	1,877		31
SWQ-2	9/21/1995																							7.58		500										31.1	271		32
SWQ-2	1/10/1996																							7.37		3,991										167.2	2,337		33
SWQ-2	4/3/1996																							8.06		4,464										222.6	2,566		34
SWQ-2	9/25/1996																							7.66		3,997										143.7	1,987		35
SWQ-2	1/15/1997																							7.43		3,436										148.0	1,356		36
SWQ-2	8/25/2010	<0.005	1.5	<0.001	0.010	<0.002	<0.04	<0.002	<0.006	<0.006	0.09	0.67	<0.0002		<0.008	<0.01	<0.005	<0.001	<0.001	<0.001	<0.001	<0.05	<0.01	7.42	89	78	21	<1.00	<0.01	6.5		3.3	1.9	<2	21	0.7	11	0.6	37
SWQ-2	4/28/2011	<0.005	<0.02	<0.001	0.019	<0.002	<0.04	<0.002	<0.006	<0.006	0.01	<0.02	<0.0002		0.008	<0.01	<0.005	<0.001	0.002	<0.001	<0.001	<0.05	<0.01							79		41	2.9						38
SWQ-2	5/4/2011																												<0.01										39
SWQ-2A	10/27/1981	<0.02	<0.01	<0.01	<0.2		<0.01	<0.005	<0.02	<0.01	<0.05	<0.05	<0.001	<0.05	<0.05		<0.02		<0.005					8.20		830		0.30	<0.01	107						46.0	360	0.6	40
SWQ-2A	2/25/1982							<0.005			<0.05	0.10	<0.001	<0.05	<0.05				<0.005					8.40		800		0.20	<0.01							50.0	320	0.7	41
SWQ-3	7/19/1991	<0.02		<0.002	0.030			<0.005		<0.02		0.14	<0.0002	<0.02			<0.005		<0.001					7.52	3,120	2,191		1.39		334	85	190	7.4	0		143.9	1,108	0.7	42
SWQ-3	8/29/1991										0.02													7.82		3,596								0		231.3	1,884		43
SWQ-3	11/26/1991										0.00													7.71		2,857										141.1	1,419		44
SWQ-3	3/15/1992																							8.08		2,393										99.2	1,248		45
SWQ-3	5/25/1992																							8.07		2,380										102.9	1,185		46
SWQ-3	7/16/1992																							7.66		3,364										128.7	1,654		47

Appendix A.
Table A-2. Surface-water-quality data

sample location	analysis date	silver (mg/L)	aluminum (mg/L)	arsenic (mg/L)	barium (mg/L)	beryllium (mg/L)	boron (mg/L)	cadmium (mg/L)	cobalt (mg/L)	chromium (mg/L)	copper (mg/L)	iron (mg/L)	mercury (mg/L)	manganese (mg/L)	molybdenum (mg/L)	nickel (mg/L)	lead (mg/L)	antimony (mg/L)	selenium (mg/L)	thallium (mg/L)	uranium (mg/L)	vanadium (mg/L)	zinc (mg/L)	pH (std. units)	specific conductance (µS/cm)	total dissolved solids (mg/L)	total alkalinity (mg/L as CaCO3)	nitrate as total N (mg/L)	total cyanide (mg/L)	calcium (mg/L)	magnesium (mg/L)	sodium (mg/L)	potassium (mg/L)	carbonate (mg/L)	bicarbonate (mg/L)	chloride (mg/L)	sulfate (mg/L)	fluoride (mg/L)	original order
SWQ-3	10/8/1992																							7.49		3,611										174.4	1,667		48
SWQ-3	11/27/1992																							8.35		1,866										160.5	952		49
SWQ-3	12/15/1992																							8.15		3,436										221.6	1,549		50
SWQ-3	2/25/1993																							8.01		2,974										150.7	1,574		51
SWQ-3	3/31/1993	<0.01	<0.1	<0.005	<0.5		0.06	<0.002	<0.05	<0.02	0.01	<0.05	<0.001	<0.02	<0.02	<0.01	<0.02		<0.005				<0.01	8.10	3,330	2,950	310	6.90	<0.01	445	109	271	2.2	0	409	135.0	1,580	1.0	52
SWQ-3	9/28/1993																							8.13		4,432										226.9	1,254		53
SWQ-3	6/23/1994																							8.37		2,934										157.4	1,712		54
SWQ-3	1/29/1995																							7.93		3,185										237.6	1,672		55
SWQ-3	3/29/1995																							8.23		3,216										100.6	1,710		56
SWQ-3	6/27/1995																							7.51		3,393										200.3	1,792		57
SWQ-3	9/21/1995																							8.73		3,741										178.5	2,382		58
SWQ-3	1/10/1996																							7.78		3,666										112.0	1,937		59
SWQ-3	4/3/1996																									3,635										157.0	2,236		60
SWQ-3	9/25/1996																							7.64		2,568										96.7	1,153		61
SWQ-3	1/15/1997																							8.13		3,436										148.0	1,356		62
SWQ-3	8/19/2010	<0.005	<0.02	<0.001	0.062	<0.002	0.14	<0.002	<0.006	<0.006	0.06	0.06	<0.0002	0.14	0.05	<0.01	<0.005	<0.001	0.013	<0.001	0.029	<0.05	0.02	8.00	4,100	4,500	250	<1.00	<0.005	530	190	490	5.7	<2	250	130.0	2,900	1.5	64
SWQ-3	10/21/2010	<0.005	<0.02	<0.005	0.053	<0.002	0.09	<0.002	<0.006	<0.006	0.02	0.05	<0.0002	0.03	0.03	<0.01	<0.005	<0.001	0.016	<0.001	0.027	<0.05	0.48	7.99	4,600	5,080	530	<1.00		630	260	520	4.3	<2	530	93.0	3,100	1.3	65
SWQ-3	1/27/2011																							7.81	3,868														63
SWQ-3	4/27/2011	<0.005	0.079	<0.001	0.032	<0.002	0.08	<0.002	<0.006	<0.006	0.01	0.03	<0.033	0.03	0.02	<0.01	<0.005	<0.001	0.007	<0.001	0.012	<0.05	0.03	7.92	4,400	4,590	430	0.15	<0.01	610	210	410	3.8	<2	430	74.0	2,900	1.4	66

Appendix A.
Table A-3. Groundwater-quality data

sample location	analysis date	silver (mg/L)	aluminum (mg/L)	arsenic (mg/L)	barium (mg/L)	beryllium (mg/L)	boron (mg/L)	cadmium (mg/L)	cobalt (mg/L)	chromium (mg/L)	copper (mg/L)	iron (mg/L)	mercury (mg/L)	manganese (mg/L)	molybdenum (mg/L)	nickel (mg/L)	lead (mg/L)	antimony (mg/L)	selenium (mg/L)	thallium (mg/L)	uranium (mg/L)	vanadium (mg/L)	zinc (mg/L)	pH (std. units)	specific conductance (µS/cm)	total dissolved solids (mg/L)	total alkalinity (mg/L as CaCO3)	nitrate as total N (mg/L)	total cyanide (mg/L)	calcium (mg/L)	magnesium (mg/L)	sodium (mg/L)	potassium (mg/L)	carbonate (mg/L)	bicarbonate (mg/L)	chloride (mg/L)	sulfate (mg/L)	fluoride (mg/L)	total suspended solids
GWQ-1	2/2/1981											1.70												7.90		520				74	20	60		0	276	20	156		
GWQ-1	3/27/1981			<0.01							<0.05						<0.02						0.16					5.50	<0.01										0.6	
GWQ-1	6/11/1981	<0.025	<0.05	<0.005	<0.1	<0.002	<0.1	<0.0005	<0.05	<0.025	<0.025	<0.05	<0.001	<0.03	<0.05	<0.05	<0.005	<0.005	<0.005	<0.005			<0.05																
GWQ-1	6/15/1981	<0.02	<0.25	<0.002	<0.2		0.076	<0.005	<0.05	<0.05	<0.02	<0.05	<0.001	<0.02	<0.1	<0.05	<0.02		0.0022	<0.005			0.12	7.40	700	500		3.75	<0.01	81	12	49	3.06	0	251	22	117	0.5	
GWQ-1	2/25/1982							<0.005			<0.05	0.14	<0.001	0.063	<0.05				<0.005					7.90		410		0.20	<0.01							22	84	0.3	
GWQ-1	3/30/1989	<0.1	<0.1		<0.1	<0.1	<0.1	<0.1	<0.05	<0.1	<0.1	<0.1		<0.05	<0.1	<0.1	<0.1						<0.1			512				84	16	61	3		280	20	133		
GWQ-1	7/19/1991	<0.02		0.003	0.01			<0.005		<0.02	<0.02	<0.05	<0.0002	<0.02			<0.005		<0.002					7.34	799	543		5.19		88	18	40	2.7	0	262	21	136	0.6	
GWQ-1	3/31/1993	<0.01	<0.01	<0.005	<0.5		0.03	<0.002	<0.05	<0.02	<0.01	<0.05	<0.001	<0.02	<0.02	<0.01	<0.02		<0.005				<0.01	7.70	822	536	230	4.90	<0.01	82	21	67	2.1	0	297	22	160	0.5	
GWQ-1	5/25/1994	<0.025	0.025	<0.005	<0.1			<0.0005		<0.025	<0.025	<0.05	<0.001	<0.03		<0.05	<0.005	<0.005	<0.005				<0.05	7.90	760	614		4.30		80	18	55	2.7	0	270	22	150	0.5	
GWQ-1	7/21/1994	<0.025	<0.05	<0.005	<0.1	<0.002	<0.1	<0.0005	<0.05	<0.025	<0.025	<0.05	<0.001	<0.03	<0.05	<0.05	<0.005	0.0052	<0.005	<0.005			<0.05	7.97	861	558		4.20		95	19	66	2.7	0	278	25	162	0.5	
GWQ-3	3/27/1981			<0.01							<0.05						<0.02						0.16					5.50	<0.01									0.6	
GWQ-3	6/15/1981	<0.02	<0.01	0.004	<0.2		0.108	<0.005	<0.05	<0.01	<0.05	<0.1	<0.001	<0.05	<0.05	<0.05	0.073		0.0037				0.32	7.00	1,100	868		0.10	<0.01	146	33	95	1.7	0	327	32	383	0.7	
GWQ-3	2/25/1982							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.90		1,040		0.40	<0.01							56	490	0.6	
GWQ-3	5/12/1982							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.90		930		0.20	<0.01							56	410	0.7	
GWQ-3	6/30/1982							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.60		860		0.40	<0.01							48	365	0.7	
GWQ-3	12/23/1982							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.50		990		0.20	<0.01							64	340	0.7	
GWQ-3	2/21/1983							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.70		970		0.20	<0.01							68	428	0.7	
GWQ-3	5/13/1983							<0.005			<0.05	<0.1	<0.001	<0.05	0.11				<0.005					8.00		980		0.30	<0.01							82	437	0.6	
GWQ-3	8/9/1983							<0.005			<0.05	0.11	<0.001	<0.05	<0.05				<0.005					7.80		1,060		<0.2	<0.01							78	385	0.7	
GWQ-3	11/1/1983							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.00		1,240		0.30	<0.01							90	529	0.7	
GWQ-3	3/16/1984							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.20		1,190		3.40	<0.01							74	530	0.3	
GWQ-6	6/15/1981	<0.02	<0.01	<0.01	<0.2		0.135	<0.005	<0.05	<0.01	<0.02	<0.1	<0.001	0.11	<0.05	<0.05	<0.02		0.0046				<0.025	7.30	600	400		3.30	<0.01	68	11	57	2.4	0	309	33	41	1.1	
GWQ-6	2/25/1982							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.30		810		0.50	<0.01							102	220	1.1	
GWQ-6	4/1/1993	<0.01	<0.1	<0.005	0.6		0.09	<0.002	<0.05	<0.02	0.03	5.05	<0.001	0.36	<0.02	<0.01	<0.02		<0.005				0.03	7.70	597	304	310	1.10	<0.01	49	14	53	3.1	0	322	22	10	0.8	
GWQ-7	2/2/1981											3.80												7.90		530				74	27	51		0	278	20	156		
GWQ-7	3/27/1981			<0.01							<0.05						<0.02						0.28					1.40	<0.01									0.6	
GWQ-7	4/6/1981			0.003							<0.05						<0.01						0.24					0.90	0.36									0.6	
GWQ-7	6/15/1981	<0.02	<0.01	<0.002	<0.2		<0.1	<0.005	<0.05	<0.01	<0.02	<0.05	<0.001	<0.02	<0.05	<0.05	<0.05		<0.0005				0.38	7.20	700	496		1.10	<0.01	88	24	61	2.33	0	285	25	165	0.5	
GWQ-7	8/7/1981											0.02												7.40		475				80	19	139			268	100	150		
GWQ-7	8/10/1981			<0.01							<0.05	1.70					<0.02						0.63	7.70		490		1.20	<0.01	68	21	48			229	24	162	0.6	
GWQ-7	10/23/1981	<0.02	<0.01	<0.01	<0.02		<0.1	<0.005	<0.02	<0.01	<0.05	0.14	<0.001	<0.05	<0.05	<0.05	<0.02		<0.005				0.41			500		1.30	<0.01	71						26	162	0.5	
GWQ-7	11/6/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	<0.1	<0.001	<0.05	<0.05	<0.05	<0.02		<0.005				0.19	8.10		480		1.20	<0.01	71						24	158	0.8	
GWQ-7	2/25/1982							<0.005			<0.05	0.17	<0.001	<0.05	<0.05				<0.005					8.00		510		0.80	<0.01							26	162	0.5	
GWQ-7	12/28/1982							<0.005			<0.05	0.26	<0.001	0.16	<0.05				<0.005					8.10		250		<0.2	<0.01							20	40	0.3	
GWQ-7	2/21/1983							<0.005			<0.05	<0.1	<0.001	0.27	<0.05				<0.005					8.30		250		2.80	<0.01							22	47	0.4	
GWQ-7	3/16/1983													<0.05																								
GWQ-7	5/13/1983							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.10		470		1.20	<0.01							20	158	0.6	
GWQ-7	8/9/1983							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.00		490		1.00	<0.01							22	130	0.6	
GWQ-7	11/1/1983							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.10		500		1.80	<0.01							22	137	0.6	
GWQ-7	3/16/1984							<0.005			<0.05	<0.1	<0.001	<0.05	0.08				<0.005					8.30		450		1.00	<0.01							20	140	0.8	
GWQ-7	5/30/1984							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.70		470		0.90	0.02							20	154	0.6	
GWQ-7	9/12/1984							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.00		500		1.40	<0.01							20	128	0.6	
GWQ-7	11/27/1984							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.70		490		1.40	<0.01							18	144	0.6	
GWQ-7	5/17/1985																							7.90		500										20	144		
GWQ-7	11/13/1985																							7.80		450										18	137		
GWQ-7	5/23/1986																							7.90		490										22	142		
GWQ-7	10/8/1986																							7.40		460										22	116		
GWQ-7	3/30/1989	<0.1	<0.1		<0.1	<0.1	<0.1	<0.1	<0.05	<0.1	<0.1	<0.1		<0.05	<0.1	<0.1	<0.1						0.10			492				80	22	47	2		278	16	131		
GWQ-7	3/30/1993	<0.01	<0.1	<0.005	<0.5		0.04	<0.002	<0.05	<0.02	<0.01	<0.05	<0.001	<0.02	<0.02	<0.01	<0.02		<0.005				0.10	7.80	752	482	250	1.38	<0.01	68	31	52	1.6	0	298	21	138	0.6	
GWQ-7	5/25/1994	<0.025	0.25	<0.005	<0.1			0.00058		<0.025	0.11	0.72	<0.001	1.1		<0.05	<0.005	<0.005	<0.005				<0.05	7.26	*2,630*	*2,420*		<1		490	51	80	14	0	480	20	*1,300*	2.1	
GWQ-7	7/21/1994	<0.025	<0.05	<0.005	<0.1	<0.002	<0.1	<0.0005	<0.05	<0.025	<0.025	1.20	<0.001	0.21	<0.05	<0.05	<0.005	<0.005	<0.005	<0.005			<0.05	7.72	660	224		<1		*14*	8	47	13	0	349	22	<5	16.0	
GWQ-8	6/4/1976						<0.1					0.00		0.003										7.48	780	560		16.80		122	16	76	1.72		241	17	114	0.5	
GWQ-8	2/2/1981											1.70												7.90		520		60.00		74	20				276	20	156		
GWQ-8	8/19/1981	<0.02	<0.25	<0.004	<1		0.076	<0.01	<0.05	<0.05	<0.05	<0.1	<1	0.047	<0.1	<0.05	<0.05		0.004				0.69	7.42		608		2.80	<0.05	73	12	84	4.2	<1	283	24	134	0.6	

Appendix A.
Table A-3. Groundwater-quality data

sample location	analysis date	silver (mg/L)	aluminum (mg/L)	arsenic (mg/L)	barium (mg/L)	beryllium (mg/L)	boron (mg/L)	cadmium (mg/L)	cobalt (mg/L)	chromium (mg/L)	copper (mg/L)	iron (mg/L)	mercury (mg/L)	manganese (mg/L)	molybdenum (mg/L)	nickel (mg/L)	lead (mg/L)	antimony (mg/L)	selenium (mg/L)	thallium (mg/L)	uranium (mg/L)	vanadium (mg/L)	zinc (mg/L)	pH (std. units)	specific conductance (µS/cm)	total dissolved solids (mg/L)	total alkalinity (mg/L as CaCO3)	nitrate as total N (mg/L)	total cyanide (mg/L)	calcium (mg/L)	magnesium (mg/L)	sodium (mg/L)	potassium (mg/L)	carbonate (mg/L)	bicarbonate (mg/L)	chloride (mg/L)	sulfate (mg/L)	fluoride (mg/L)	total suspended solids
GWQ-8	2/25/1982							<0.005			<0.05	<0.1	<0.001	0.17	<0.05				<0.005					7.60		380		0.30	<0.01							38	220	1.0	
GWQ-8	3/31/1993	<0.01	<0.05	<0.005	0.042		0.03	<0.0005	<0.01	<0.01	0.01	<0.05	<0.0002	<0.01	<0.02	<0.01	<0.002		<0.005				0.09	7.60	1,110	764	240	6.30	<0.01	132	18	94	1.8	0	298	38	283	0.5	
GWQ-8	5/25/1994	<0.025	<0.025	<0.005	<0.1		<0.1	<0.0005	<0.05	<0.025	<0.025	0.24	<0.001	<0.03	<0.05	<0.05	<0.005	<0.005	<0.005				<0.05	7.97	1,060	792		5.30		120	20	76	2.4	0	272	41	290	0.5	
GWQ-9	6/4/1976						<0.1					0.00		0.001										8.60	480	350		4.00		69	15	30	1.56		188	20	34	0.4	
GWQ-9	2/2/1981											1.80												7.90		510				73	24	49		0	273	20	156		
GWQ-9	3/27/1981			<0.01							<0.05						<0.02						0.16					1.40	<0.01								0.6	
GWQ-9	4/6/1981			0.002							<0.05						<0.01						0.13					1.20	0.15								0.6	
GWQ-9	8/7/1981											0.06												7.40		450				80	19	129			268	100	140		
GWQ-9	8/10/1981			<0.01							<0.05	0.49					0.033						0.96	8.00		470		1.40	<0.01	76	20	47			268	22	148	0.5	
GWQ-9	10/8/1981	<0.02	<0.25	<0.004	<1		0.044	<0.01	<0.05	<0.05	<0.05	<0.1	<1	<0.02	<0.1	<0.05	<0.05		<0.002				0.35	7.22		476		0.96	<0.05	52	17	71	3.3	<1	302	22	133	0.6	
GWQ-9	2/25/1982							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.30		430		0.90	<0.01							26	160	0.5	
GWQ-9	12/28/1982							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.80		480		1.00	<0.01							20	150	0.5	
GWQ-9	2/21/1983							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.00		480		1.40	<0.01							20	161	0.5	
GWQ-9	5/13/1983							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.20		460		1.10	<0.01							20	158	0.5	
GWQ-9	8/9/1983							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.00		480		0.90	<0.01							20	135	0.5	
GWQ-9	11/1/1983							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.20		460		0.80	<0.01							18	132	0.5	
GWQ-9	3/16/1984							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.10		460		1.70	<0.01							18	132	0.7	
GWQ-9	5/30/1984							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.60		450		0.90	<0.01							18	154	0.5	
GWQ-9	9/12/1984							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.00		470		1.30	<0.01							20	132	0.5	
GWQ-9	11/27/1984							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.90		470		1.50	<0.01							16	132	0.5	
GWQ-9	5/17/1985																							8.00		490										20	149		
GWQ-9	11/13/1985																							7.80		450										20	142		
GWQ-9	5/23/1986																							7.90		490										36	137		
GWQ-9	10/8/1986																							7.60		460										20	125		
GWQ-10	4/6/1981			0.002				<0.01			<0.05		<1				<0.01						0.12					4.60	0.02				8.25				0.5	
GWQ-10	8/10/1981	<0.02	10.2	<0.004	<1		0.016	<0.01	<0.05	<0.05	<0.05	2.31	<1	1.18	<0.1	<0.05	<0.05		<0.002				0.23	7.48		528		0.22	<0.05	74	11	59	8.32	<1	219	24	143	1.1	
GWQ-10	10/27/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	<0.01	<0.001	<0.05	<0.05	<0.05	<0.02		<0.005				0.25	8.20		520		1.10	<0.01	68						22	168	0.6	
GWQ-10	10/30/1981	<0.02	<0.25	<0.005	<1		0.77	<0.01	<0.05	<0.05	<0.05	<1	<0.001	<0.02	<0.1	<0.02	<0.05		<0.002				0.24	8.10		588		0.66	<0.05	72						23	122	1.0	
GWQ-10	11/6/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	<0.1	<0.001	<0.05	<0.05	<0.05	<0.02		<0.005				0.28	7.90		500		2.00	<0.01	84						22	162	0.7	
GWQ-10	11/13/1981	<0.001	0.37	<0.005	0.25		0.037	0.001		<0.005			<0.0005	0.5	<0.01	<0.05	<0.005		0.01	<0.005			0.90	7.75	700	509		1.80	0.001	70	17	39	2.34		276	23	141	0.6	
GWQ-10	11/17/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	<0.1	<0.001	<0.05	<0.05	<0.05	<0.02		<0.005				0.28	7.90		500		1.80	<0.01	70						26	156	0.6	
GWQ-10	11/23/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	<0.1	<0.001	<0.05	<0.05	<0.05	<0.02		<0.005				0.37	7.70		650		1.80	<0.01							26	161	0.6	
GWQ-10	12/7/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	<0.1	<0.001	<0.05	<0.05	<0.05	<0.02		<0.005				0.87	8.20		490		1.80	<0.01	67						24	168	0.5	
GWQ-10	12/15/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	<0.1	<0.001	<0.05	<0.05	<0.05	<0.02		<0.005				0.44	7.90		550		2.60	<0.01	89						24	181	0.7	
GWQ-10	12/22/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	<0.1	<0.001	<0.05	<0.05	<0.05	<0.02		<0.005				0.35	8.10		480		2.50	<0.01	85						24	168	0.5	
GWQ-10	1/5/1982	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	0.13	<0.001	<0.05	<0.05	<0.05	<0.02		<0.005				0.31	7.50		430		2.90	<0.01	80						22	174	0.6	
GWQ-10	1/26/1982							<0.005			<0.05	<0.1	<0.001	<0.05	<0.1				<0.005					7.80		490		2.30	<0.01							24	162	0.6	
GWQ-10	2/22/1982							<0.005			<0.05	0.12	<0.001	<0.05	<0.05				<0.005					7.60		510		2.10	<0.01							24	161	0.6	
GWQ-10	4/26/1982							<0.005			<0.05	0.41	<0.001	<0.05	<0.05				<0.005					7.40		840		2.00	<0.01							20	168	0.6	
GWQ-10	5/17/1982							<0.005			<0.05	0.10	<0.001	<0.05	<0.05				<0.005					7.70		490		2.30	<0.01							28	175	0.6	
GWQ-10	6/8/1982							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.00		500		2.20	<0.01							22	162	0.5	
GWQ-10	6/30/1982							<0.005			<0.05	0.62	<0.001	<0.05	<0.05				<0.005					8.00		510		3.30	<0.01							20	160	0.6	
GWQ-10	9/2/1982							<0.001						<0.05	<0.01				<0.005					7.30	690	506		2.25		83	17	58	2.73		278	22	143	0.5	
GWQ-10	12/23/1982							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.50		500		1.70	<0.01							26	138	0.6	
GWQ-10	2/21/1983							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.90		470		2.40	<0.01							24	161	0.6	
GWQ-10	5/13/1983							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.00		480		2.40	0.02							32	161	0.6	
GWQ-10	8/9/1983							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.90		510		2.40	<0.01							36	142	0.6	
GWQ-10	11/1/1983							<0.005			<0.05	0.17	<0.001	<0.05	<0.05				<0.005					8.10		500		4.80	<0.01							34	125	0.6	
GWQ-10	3/16/1984							<0.005			<0.05	0.11	<0.001	<0.05	<0.05				<0.005					8.20		500		3.50	<0.01							42	128	0.5	
GWQ-10	5/30/1984							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.50		530		3.30	<0.01							56	161	0.5	
GWQ-10	9/12/1984							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.80		580		4.20								68	158	0.5	
GWQ-10	11/27/1984							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.70		580		4.90	<0.01							64	163	0.6	
GWQ-10	5/17/1985																							7.80		570										52	163		
GWQ-10	11/13/1985																							7.70		500										42	149		

Appendix A.
Table A-3. Groundwater-quality data

sample location	analysis date	silver (mg/L)	aluminum (mg/L)	arsenic (mg/L)	barium (mg/L)	beryllium (mg/L)	boron (mg/L)	cadmium (mg/L)	cobalt (mg/L)	chromium (mg/L)	copper (mg/L)	iron (mg/L)	mercury (mg/L)	manganese (mg/L)	molybdenum (mg/L)	nickel (mg/L)	lead (mg/L)	antimony (mg/L)	selenium (mg/L)	thallium (mg/L)	uranium (mg/L)	vanadium (mg/L)	zinc (mg/L)	pH (std. units)	specific conductance (µS/cm)	total dissolved solids (mg/L)	total alkalinity (mg/L as CaCO3)	nitrate as total N (mg/L)	total cyanide (mg/L)	calcium (mg/L)	magnesium (mg/L)	sodium (mg/L)	potassium (mg/L)	carbonate (mg/L)	bicarbonate (mg/L)	chloride (mg/L)	sulfate (mg/L)	fluoride (mg/L)	total suspended solids
GWQ-10	5/23/1986																							7.90		560									58	151		
GWQ-10	10/8/1986																							7.50		550									54	137		
GWQ-10	3/4/1987	<0.1	<0.1		<0.1	<0.1	<0.1	<0.1	<0.05	<0.1	<0.1	<0.1		<0.05	<0.1	<0.1	<0.1	0.9					<0.1		740	568				90	21	74	2.34		256	59	150		
GWQ-10	5/25/1987																																			154		
GWQ-10	1/12/1988	<0.1	<0.1		<0.1	<0.1	<0.1	<0.1	<0.05	<0.1	<0.1	<0.1		<0.05	<0.1	<0.1	<0.1						<0.1			648				116	24	64	3		243	79	173		
GWQ-10	4/4/1988																									552									65	171		
GWQ-10	8/23/1988																									692									63	179		
GWQ-10	2/9/1989																									618									76	181		
GWQ-10	6/1/1989																									604									68	163		
GWQ-10	11/30/1989																									620									72	162		
GWQ-10	11/14/1990																									635									93	178		
GWQ-10	2/11/1991			<0.001																						696									78	214		
GWQ-10	7/19/1991	<0.02		0.002	0.02			<0.005		<0.02		0.07	<0.0002	<0.02			<0.005		0.002					8.05	975	645		3.88		106	24	47	3.9	0	242	83	167	0.5	
GWQ-10	8/29/1991																							7.44		665									85	192		
GWQ-10	11/26/1991																							7.46		648									58	171		
GWQ-10	3/15/1992																							7.85		641									83	192		
GWQ-10	5/25/1992																							7.41		621									84	169		
GWQ-10	7/16/1992																							7.51		626									76	167		
GWQ-10	10/8/1992																							7.43		659									83	161		
GWQ-10	11/27/1992																							7.89		654									80	174		
GWQ-10	12/15/1992																							7.48		582									91	169		
GWQ-10	2/25/1993																							7.39		620									96	176		
GWQ-10	3/30/1993	<0.01	<0.1	<0.005	<0.5		0.04	<0.002	<0.05	<0.02	<0.01	<0.05	<0.001	<0.02	<0.02	<0.01	<0.02		<0.005				0.11	7.80	1,020	642	200	3.90	<0.01	104	27	71	2.3	0	254	94	183	0.5	
GWQ-10	9/28/1993																							7.70		693									96	143		
GWQ-10	5/26/1994	<0.025	0.85	<0.005	<0.1			<0.0005		<0.025	0.026	1.10	<0.001	0.059		<0.05	<0.005	<0.005	<0.005				0.55	7.82	1,050	1,000		3.50		100	25	56	3.1	0	232	92	175	0.5	
GWQ-10	6/23/1994																							7.97		671									104	192		
GWQ-10	7/23/1994	<0.025	<0.05	<0.005	<0.1	<0.002	<0.1	<0.0005	<0.05	<0.025	<0.025	<0.05	<0.001	<0.03	<0.05	<0.05	<0.005	<0.005	<0.005	<0.005			<0.05	7.97	1,050	696		3.50		110	26	66	2.8	0	238	98	184	0.5	
GWQ-10	9/22/1994																							7.45		668									89	156		
GWQ-10	1/29/1995																							7.52		672									88	66		
GWQ-10	3/29/1995																							7.67		622									85	176		
GWQ-10	6/27/1995																							7.29		677									85	169		
GWQ-10	9/21/1995																							7.42		693									91	187		
GWQ-10	1/10/1996																							7.29		654									98	198		
GWQ-10	4/3/1996																							6.95		628									97	218		
GWQ-10	9/25/1996																							7.56		679									86	191		
GWQ-10	1/15/1997																							7.59		746									91	204		
GWQ-11	8/10/1981	<0.02	<0.25	<0.004	<1		0.092	<0.01	<0.05	<0.05	<0.05	1.14	<1	0.45	<0.1	<0.05	<0.05		0.006				<0.05	7.38		612		1.02	<0.05	68	14	48	7.88	<1	237	37	123	0.9	
GWQ-11	10/27/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	<0.1	<0.001	<0.05	<0.05	<0.05	<0.02		<0.005				0.17	8.10		550		0.70	<0.01	72						36	183	1.0	
GWQ-11	10/30/1981	<0.02	<0.25	<0.005	<1		0.55	<0.01	<0.05	<0.05	<0.05	<0.1	<0.001	<0.02	<0.1	<0.02	<0.05		<0.011				0.23	8.40		536		0.61	<0.05							39	101	1.0	
GWQ-11	11/6/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	<0.1	<0.001	<0.05	<0.05	<0.05	<0.02		<0.005				0.29	8.10		520		1.50	<0.01	67						36	168	1.0	
GWQ-11	11/13/1981	<0.001	<0.25	<0.005	0.2		0.041	0.001		<0.005			<0.0005	<0.05	0.12	<0.05	<0.005		0.023				0.79	7.70	700	544		1.33	<0.001	83	17	44	3.9		241	38	156	1.0	
GWQ-11	11/17/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	<0.1	<0.001	<0.05	<0.05	<0.05	<0.02		<0.005				0.64	8.00		520		1.30	<0.01	71						36	165	1.0	
GWQ-11	11/23/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	<0.1	<0.001	<0.05	<0.05	<0.05	<0.02		<0.005				0.53	7.80		570		1.70	<0.01	67						36	181	0.9	
GWQ-11	12/7/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	<0.1	0.0064	<0.05	<0.05	<0.05	<0.02		<0.005				1.60	7.90		560		1.60	<0.01	57						56	184	0.9	
GWQ-11	12/15/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	<0.1	<0.001	<0.05	<0.05	<0.05	<0.02		<0.005				1.10	7.90		570		1.50	<0.01	85						38	191	1.0	
GWQ-11	12/22/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	0.27	<0.001	0.093	<0.05	<0.05	<0.02		<0.005				0.42	8.00		530		1.90	<0.01	82						40	185	0.5	
GWQ-11	1/5/1982	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	0.14	<0.001	<0.05	<0.05	<0.05	<0.02		<0.005				0.44	7.50		480		2.50	<0.01	79						40	174	1.0	
GWQ-11	1/26/1982							<0.005			<0.05	<0.1	<0.001	<0.05	<0.1				<0.005					7.90		500		1.70	<0.01							40	168	1.0	
GWQ-11	2/22/1982							<0.005			<0.05	0.11	<0.001	<0.05	<0.05				<0.005					7.70		510		1.40	<0.01							38	168	0.9	
GWQ-11	4/26/1982							<0.005			<0.05	0.36	<0.001	<0.05	0.05				<0.005					7.60		510		1.30	<0.01							40	165	0.8	
GWQ-11	5/17/1982							<0.005			<0.05	0.11	<0.001	<0.05	<0.05				<0.005					7.80		510		1.90	<0.01							44	185	0.8	
GWQ-11	6/8/1982							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.90		530		1.70	<0.01							44	185	0.8	
GWQ-11	6/30/1982							<0.005			<0.05	0.39	<0.001	<0.05	<0.05				<0.005					7.90		590		2.30	<0.01							44	198	0.8	
GWQ-11	9/2/1982							<0.001						<0.05	<0.01				<0.005					7.30	940	700		1.94		111	28	58	3.51		226	52	248	0.8	

Appendix A.
Table A-3. Groundwater-quality data

sample location	analysis date	silver (mg/L)	aluminum (mg/L)	arsenic (mg/L)	barium (mg/L)	beryllium (mg/L)	boron (mg/L)	cadmium (mg/L)	cobalt (mg/L)	chromium (mg/L)	copper (mg/L)	iron (mg/L)	mercury (mg/L)	manganese (mg/L)	molybdenum (mg/L)	nickel (mg/L)	lead (mg/L)	antimony (mg/L)	selenium (mg/L)	thallium (mg/L)	uranium (mg/L)	vanadium (mg/L)	zinc (mg/L)	pH (std. units)	specific conductance (µS/cm)	total dissolved solids (mg/L)	total alkalinity (mg/L as CaCO3)	nitrate as total N (mg/L)	total cyanide (mg/L)	calcium (mg/L)	magnesium (mg/L)	sodium (mg/L)	potassium (mg/L)	carbonate (mg/L)	bicarbonate (mg/L)	chloride (mg/L)	sulfate (mg/L)	fluoride (mg/L)	total suspended solids
GWQ-11	12/23/1982							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.50		650		1.60	<0.01							52	235	0.8	
GWQ-11	2/21/1983							<0.005			<0.05	0.38	<0.001	<0.05	<0.05				<0.005					8.00		600		1.70	<0.01							44	218	0.8	
GWQ-11	5/13/1983							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.10		570		1.90	0.01							44	206	0.8	
GWQ-11	8/9/1983							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.90		580		2.00	<0.01							46	168	0.8	
GWQ-11	11/1/1983							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.00		580		4.80	<0.01							46	174	0.8	
GWQ-11	3/16/1984							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.30		540		3.80	<0.01							52	184	0.6	
GWQ-11	5/30/1984							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.50		550		1.90	<0.01							58	195	0.8	
GWQ-11	9/12/1984							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.90		590		2.30	<0.01							60	181	0.8	
GWQ-11	11/27/1984							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.70		570		2.30	<0.01							60	165	0.8	
GWQ-11	5/17/1985																							7.80		640										64	197		
GWQ-11	11/13/1985																							7.70		600										62	183		
GWQ-11	5/23/1986																							7.80		650										66	210		
GWQ-11	10/8/1986																							7.60		560										70	200		
GWQ-11	3/4/1987	<0.1	<0.1		<0.1	<0.1	<0.1	<0.1	<0.05	<0.1	<0.1	<0.1		<0.05	<0.1	<0.1	<0.1	1.1					<0.1	6.70	820	696				108	26	62	3.51		220	69	200		
GWQ-11	5/25/1987																																				230		
GWQ-11	1/12/1988	<0.1	<0.1		<0.1	<0.1	<0.1	<0.1	<0.05	<0.1	<0.1	<0.1		<0.05	<0.1	<0.1	<0.1						<0.1			718				128	31	63	4		214	77	253		
GWQ-11	4/4/1988																									694										75	278		
GWQ-11	8/23/1988																									772										73	294		
GWQ-11	2/9/1989																									730										77	258		
GWQ-11	6/1/1989																									708										70	238		
GWQ-11	11/30/1989																									732										80	254		
GWQ-11	11/14/1990																									746										104	257		
GWQ-11	2/11/1991			<0.001																						790										89	233		
GWQ-11	7/19/1991	<0.02		0.004	0.1			<0.005		<0.02		<0.05	<0.0002	<0.02			<0.002		0.002					7.36	1,100	785		3.93		123	34	40	3.9	0	221	90	210	0.7	
GWQ-11	8/29/1991																							7.46		771										93	279		
GWQ-11	11/26/1991																							7.29		770										89	241		
GWQ-11	3/15/1992																							7.91		765										65	260		
GWQ-11	5/25/1992																							7.45		761										96	258		
GWQ-11	10/8/1992																							7.42		755										96	227		
GWQ-11	11/27/1992																							7.85		763										96	248		
GWQ-11	12/15/1992										0.017													7.59		741										98	220		
GWQ-11	2/25/1993																							7.64		762										104	273		
GWQ-11	3/30/1993	<0.01	0.2	<0.005	<0.5		0.04	<0.002	<0.05	<0.02	<0.01	0.33	<0.001	0.03	<0.02	<0.01	<0.02		<0.005				0.03	7.70	1,170	776	180	4.10	<0.01	126	34	68	2.9	0	227	104	271	0.5	
GWQ-11	9/28/1993																							7.57		800										106	208		
GWQ-11	5/25/1994	<0.025	0.14	<0.005	<0.1			<0.0005		<0.025	<0.025	0.16	<0.001	<0.03		<0.05	<0.005	<0.005	<0.005				<0.05	7.88	1,130	820		3.80		120	34	55	3.5	0		110	260	0.7	
GWQ-11	6/23/1994																							7.42		802										117	275		
GWQ-11	7/22/1994	<0.025	<0.05	<0.005	<0.1	<0.002	<0.1	<0.0005	<0.05	<0.025	<0.025	<0.05	<0.001	<0.03	<0.05	<0.05	<0.005	0.0055	<0.005	<0.005			<0.05	7.70	1,210	808		3.80		140	37	66	3.4	0		116	272	0.7	
GWQ-11	9/22/1994																							7.37		816										112	235		
GWQ-11	1/29/1995																							7.60		861										200	159		
GWQ-11	3/29/1995																							7.96		793										99	137		
GWQ-11	6/27/1995																							7.67		835										102	279		
GWQ-11	9/21/1995																							7.58		865										112	290		
GWQ-11	1/10/1996																							7.36		777										121	288		
GWQ-11	4/3/1996																							7.38		767										119	277		
GWQ-11	9/25/1996																							7.78		835										116	230		
GWQ-11	1/15/1997																							7.68		860										127	304		
GWQ94-13	11/15/1994	<0.025	<0.05	<0.005	<0.1	<0.002	<0.1	<0.0005	<0.05	<0.025	<0.025	0.11	<0.001	<0.03	<0.05	<0.05	<0.005	<0.005	<0.005	<0.005			<0.05	7.74	2,026	1,570		4.60		270	56	110	3.9	0	159	190	720	0.4	
GWQ94-13	7/1/1996	<0.05	<0.025	<0.005	<0.05	<0.002	<0.05	<0.0005	<0.05	<0.025	<0.025	<0.05	<0.001	<0.03	<0.05	<0.05	<0.005	<0.002	0.0068	<0.001			<0.05	7.76	2,000	1,520		5.20		290	62	120	3.6	0	156	200	620	0.3	
GWQ94-13	7/2/2010	<0.005	<0.020	<0.001	0.04	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006	<0.02	0.00026	<0.002	<0.008	<0.01	<0.005	<0.001	0.024	<0.001	0.0016	<0.05	<0.01	8.00	2,200	1,730	120	5.90		320	62	110	3.4	<2	120	290	770	0.4	10
GWQ94-13	10/5/2010	<0.005	<0.02	<0.005	0.038	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006	<0.02	<0.0002	<0.002	<0.008	<0.01	<0.005	<0.001	0.024	<0.001	0.0015	<0.05	<0.01	7.39	2,100	1,670	120	5.80		300	62	110	3.4	<2	120	280	760	0.3	<10
GWQ94-13	5/11/2011	<0.005	<0.02	0.0038	0.037	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006	<0.02	<0.0002	<0.002	<0.008	<0.01	<0.005	<0.001	0.028	<0.001	0.0017	<0.05	0.04	7.66	2,100	1,670	130	6.50	<0.005	310	61	120	3.3	<2	130	290	800	0.3	<10
GWQ94-14	11/14/1994	<0.025	<0.05	<0.005	<0.1	<0.002	<0.1	<0.0005	<0.05	<0.025	<0.025	<0.05	<0.001	<0.03	<0.05	<0.05	<0.005	<0.005	<0.005	<0.005			<0.05	7.95	745	560		1.30		81	23	46	1.9	0	279	22	140	0.5	
GWQ94-14	6/30/1996	<0.05	<0.025	<0.005	<0.05	<0.002	<0.05	<0.0005	<0.05	<0.025	<0.025	<0.05	<0.001	<0.03	<0.05	<0.05	<0.005	<0.002	<0.005	<0.001			<0.05	8.44	641	520		1.50		87	23	51	1.9	5	261	26	140	0.5	
GWQ94-14	1/29/2010	<0.005	<0.02	0.0032	0.045	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006	<0.02	<0.0002	<0.002	<0.008	<0.01	<0.005	<0.0025	0.0068	<0.0025			0.01	8.00	820	550	210	2.20	<0.005	96	26	49	2	<2	210	50	150	0.5	

Appendix A.
Table A-3. Groundwater-quality data

sample location	analysis date	silver (mg/L)	aluminum (mg/L)	arsenic (mg/L)	barium (mg/L)	beryllium (mg/L)	boron (mg/L)	cadmium (mg/L)	cobalt (mg/L)	chromium (mg/L)	copper (mg/L)	iron (mg/L)	mercury (mg/L)	manganese (mg/L)	molybdenum (mg/L)	nickel (mg/L)	lead (mg/L)	antimony (mg/L)	selenium (mg/L)	thallium (mg/L)	uranium (mg/L)	vanadium (mg/L)	zinc (mg/L)	pH (std. units)	specific conductance (µS/cm)	total dissolved solids (mg/L)	total alkalinity (mg/L as CaCO3)	nitrate as total N (mg/L)	total cyanide (mg/L)	calcium (mg/L)	magnesium (mg/L)	sodium (mg/L)	potassium (mg/L)	carbonate (mg/L)	bicarbonate (mg/L)	chloride (mg/L)	sulfate (mg/L)	fluoride (mg/L)	total suspended solids
GWQ94-14	6/29/2010	<0.005	<0.020	0.0023	0.048	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006	<0.02	<0.0002	<0.002	<0.008	<0.01	<0.005	<0.001	0.0052	<0.001	0.0014	<0.05	<0.01	8.00	820	573	210	2.30		98	25	45	1.7	<2	210	49	150	0.5	<10
GWQ94-14	10/5/2010	<0.005	<0.02	0.0024	0.045	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006	<0.02	<0.0002	<0.002	<0.008	<0.01	<0.005	<0.001	0.0053	<0.001	0.0013	<0.05	<0.01	7.57	840	563	210	2.20		94	27	47	1.7	<2	210	50	150	0.5	<10
GWQ94-14	5/13/2011	<0.005	<0.02	0.0028	0.045	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006	<0.02	<0.0002	<0.002	<0.008	<0.01	<0.005	<0.001	0.0061	<0.001	0.0015	<0.05	0.05	7.84	840	570	210	2.20	0.012	97	27	49	1.8	<2	210	48	150	0.6	<10
GWQ94-15	11/14/1994	<0.025	<0.05	<0.005	<0.1	<0.002	<0.1	<0.0005	<0.05	<0.025	<0.025	<0.05	<0.001	<0.03	<0.05	<0.05	<0.005	<0.005	<0.005	<0.005			<0.05	7.74	1,058	790		2.10		110	29	68	2.5	0	265	110	180	0.5	
GWQ94-15	7/1/1996	<0.05	<0.025	<0.005	<0.05	<0.002	<0.05	<0.0005	<0.05	<0.025	<0.025	0.41	<0.001	<0.03	<0.05	<0.05	<0.005	<0.002	<0.005	<0.001			<0.05	7.31	1,190	780		2.50		140	38	77	2.4	0	227	130	240	0.4	
GWQ94-15	1/29/2010	<0.005	<0.020	0.0042	0.058	<0.002	<0.040	<0.002	<0.0060	<0.0060	<0.006	<0.02	<0.0002	<0.002	<0.008	<0.01	<0.005	<0.0025	0.021	<0.0025			0.02	7.00	1,500	1,080	160	4.10	<0.005	180	47	84	3	<2	160	170	420	0.3	
GWQ94-15	6/29/2010	<0.005	<0.020	<0.0010	0.059	<0.002	<0.040	<0.002	<0.0060	<0.0060	<0.006	<0.02	<0.0002	0.0049	<0.008	<0.01	<0.005	<0.001	0.0095	<0.001	0.0017	<0.05	<0.01	8.00	1,100	805	180	2.70		140	34	60	2.1	<2	180	110	260	0.4	<10
GWQ94-15	10/1/2010	<0.005	<0.02	<0.001	0.056	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006	<0.02	<0.0002	<0.002	<0.008	<0.01	<0.005	<0.001	0.012	<0.001	0.0018	<0.05	<0.01	7.52	1,100	794	190	2.70	<0.01	130	37	65	2.2	<2	190	110	260	0.4	<10
GWQ94-15	5/13/2011	<0.005	<0.02	0.0036	0.056	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006	<0.02	<0.0002	<0.002	<0.008	<0.01	<0.005	<0.001	0.012	<0.001	0.0018	<0.05	<0.01	7.74	1,200	808	190	2.80	<0.005	130	38	68	2.3	<2	190	120	270	0.4	<10
GWQ94-16	11/13/1994	<0.025	<0.05	<0.005	<0.1	<0.002	<0.1	<0.0005	<0.05	<0.025	<0.025	<0.05	<0.001	0.038	<0.05	<0.05	<0.005	<0.005	<0.005	<0.005			<0.05	7.55	1,600	1,140		3.80		190	51	78	3.7	0	199	190	410	0.7	
GWQ94-16	7/1/1996	<0.05	<0.025	<0.005	<0.05	<0.002	<0.05	<0.0005	<0.05	<0.025	<0.025	0.22	<0.001	<0.03	<0.05	<0.05	<0.005	<0.002	<0.005	<0.001			<0.05	7.95	1,620	1,160		3.70		200	54	80	3.4	0	193	200	500	0.6	
GWQ94-16	6/29/2010	<0.005	<0.02	0.0022	0.039	<0.002	0.048	<0.002	<0.006	<0.006	<0.006	<0.02	<0.0002	<0.002	<0.008	<0.01	<0.005	<0.001	0.011	<0.001	0.0025	<0.05	<0.01	8.00	1,600	1,190	180	3.70		210	50	74	3.1	<2	180	180	440	0.6	<10
GWQ94-16	9/30/2010	<0.005	<0.02	0.0024	0.038	<0.002	0.053	<0.002	<0.006	<0.006	<0.006	<0.02	<0.0002	<0.002	<0.008	<0.01	<0.005	<0.001	0.015	<0.001	0.0024	<0.05	<0.01	7.50	1,500	1,170	180	3.90	<0.01	200	51	78	3.1	<2	180	190	440	0.7	<10
GWQ94-16	5/10/2011	<0.005	<0.02	0.0026	0.038	<0.002	0.056	<0.002	<0.006	<0.006	<0.006	<0.02	<0.0002	<0.002	<0.008	<0.01	<0.005	<0.001	0.012	<0.001	0.0023	<0.05	0.01	7.58	1,600	1,150	180	4.00	<0.01	200	49	74	3.1	<2	180	190	430	0.6	<10
GWQ94-17	11/15/1994	<0.025	<0.05	<0.005	<0.1	<0.002	<0.1	<0.0005	<0.05	<0.025	<0.025	<0.05	<0.001	<0.03	<0.05	<0.05	<0.005	<0.005	<0.005	<0.005			<0.05	7.71	1,147	820		2.40		120	33	62	2.4	0	232	110	240	0.5	
GWQ94-17	6/30/1996	<0.05	<0.025	<0.005	<0.05	<0.002	<0.05	<0.0005	<0.05	<0.025	<0.025	0.06	<0.001	<0.03	<0.05	<0.05	<0.005	<0.002	<0.005	<0.001			<0.05	8.56	925	690		2.00		120	28	61	2	7	227	81	190	0.5	
GWQ94-17	7/6/2010	<0.005	<0.02	0.0022	0.047	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006	<0.02	<0.0002	<0.002	<0.008	<0.01	<0.005	<0.001	0.0062	<0.001	0.0016	<0.05	<0.01	8.00	880	629	200	2.00		110	27	49	1.8	<2	200	68	180	0.5	61
GWQ94-20	11/15/1994	<0.025	<0.05	<0.005	<0.1	<0.002	0.11	<0.0005	<0.05	<0.025	<0.025	<0.05	<0.001	0.42	<0.05	<0.05	<0.005	<0.005	<0.005	<0.005			<0.05	7.66	588	370		1.00		48	10	67	3.2	0	296	19	40	0.4	
GWQ94-20	6/30/1996	<0.05	<0.025	<0.005	0.12	<0.002	0.086	<0.0005	<0.05	<0.025	<0.025	<0.05	<0.001	<0.03	<0.05	<0.05	<0.005	<0.002	<0.005	<0.001			<0.05	8.79	597	390		<1		58	10	75	3.1	19	273	21	56	0.3	
GWQ94-21A	11/13/1994	<0.025	<0.05	<0.005	<0.1	<0.002	<0.1	<0.0005	<0.05	<0.025	<0.025	<0.05	<0.001	0.20	<0.05	<0.05	<0.005	<0.005	<0.005	<0.005			<0.05	7.25	672	480		1.00		82	23	39	2.1	0	267	18	130	0.6	
GWQ94-21A	6/30/1996	<0.05	<0.025	<0.005	<0.05	<0.002	<0.05	<0.0005	<0.05	<0.025	<0.025	<0.05	<0.001	<0.03	<0.05	<0.05	<0.005	<0.002	<0.005	<0.001			<0.05	8.22	649	470		1.10		86	22	37	1.5	0	268	16	120	0.5	
GWQ94-21B	11/13/1994	<0.025	<0.05	<0.005	<0.1	<0.002	<0.1	<0.0005	<0.05	<0.025	<0.025	<0.05	<0.001	0.37	<0.05	<0.05	<0.005	<0.005	<0.005	<0.005			<0.05	7.57	669	440		<1		71	18	56	2.6	0	255	19	130	0.4	
GWQ94-21B	6/30/1996	<0.05	<0.025	<0.005	<0.05	<0.002	<0.05	<0.0005	<0.05	<0.025	<0.025	<0.05	<0.001	<0.03	<0.05	<0.05	<0.005	<0.002	<0.005	<0.001			<0.05	8.60	648	470		1.10		87	22	40	1.7	10	256	17	120	0.5	
GWQ96-22A	7/13/1996	<0.05	<0.025	<0.005	<0.05	<0.002	<0.05	<0.0005	<0.05	<0.025	<0.025	<0.05	<0.001	0.08	<0.05	<0.05	<0.005	<0.003	<0.005	<0.001			<0.05	7.50	1,040	700		<1		71	7	150	2.5	0	124	89	250	3.3	
GWQ96-22A	4/9/1997										<0.025	6.50	<0.001	2.80					<0.005					7.58	930	770										20	150	0.8	
GWQ96-22A	8/8/1997	<0.025	0.028	<0.005	0.057	<0.002	0.23	<0.002	<0.05	<0.025	<0.05	0.13		0.53	<0.05	<0.05	<0.005		<0.005	<0.001			<0.05	7.65	1,140	700		<1		73	8	170	6.2	0	177	89	230	2.2	
GWQ96-22A	1/30/2010	<0.005	<0.02	0.0029	0.094	<0.002	0.28	<0.002	<0.006	<0.006	<0.006	2.10	<0.0002	0.74	<0.008	<0.01	<0.005	<0.0025	<0.0025	<0.0025			<0.01	8.00	920	557	320	<1	<0.005	51	4	160	2.8	<2	320	81	44	2.6	
GWQ96-22A	7/1/2010	<0.005	<0.02	0.0035	0.079	<0.002	0.28	<0.002	<0.006	<0.006	<0.006	0.02	<0.0002	0.65	<0.008	<0.01	<0.005	<0.001	0.0011	<0.001	<0.001	<0.05	<0.01	8.00	920	573	310	<1		53	4	150	2.8	<2	310	70	52	2.7	19
GWQ96-22A	10/7/2010	<0.005	<0.02	0.0035	0.084	<0.002	0.28	<0.002	<0.006	<0.006	<0.006	0.32	<0.0002	0.49	<0.008	<0.01	<0.005	<0.001	<0.001	<0.001	<0.001	<0.05	<0.01	8.00	720	564	340	<1		49	4	150	2.8	<2	340	75	34	2.7	11
GWQ96-22B	7/13/1996	<0.05	<0.025	<0.005	0.096	<0.002	0.12	<0.0005	<0.05	<0.025	<0.025	<0.05	<0.001	0.41	<0.05	<0.05	<0.005	<0.003	<0.005	<0.001			<0.05	7.75	1,070	650		<1		66	10	130	10	0	141	210	79	1.8	
GWQ96-22B	10/7/2010	<0.005	<0.02	0.0057	0.11	<0.002	0.24	<0.002	<0.006	<0.006	<0.006	9.30	<0.0002	1.20	<0.008	<0.01	<0.005	<0.001	0.0011	<0.001	<0.001	<0.05	<0.01	7.52	1,200	730	480	2.10		72	6	200	3.6	<2	480	110	<0.5	3.0	25
GWQ96-23A	7/14/1996	<0.05	0.28	<0.005	0.064	<0.002	<0.05	<0.0005	<0.05	<0.025	<0.025	0.26	<0.001	0.05	<0.05	<0.05	<0.005	<0.003	<0.005	<0.001			<0.05	7.95	760	520		<1		59	18	98	4.2	0	280	22	140	0.8	
GWQ96-23A	4/9/1997										<0.025	0.10	<0.001	0.75					<0.005						850	580										16	170	1.4	
GWQ96-23A	8/8/1997	<0.025	0.036	<0.005	0.13	<0.002	0.067	<0.002	<0.05	<0.025	<0.025	0.82		1.60	<0.05	<0.05	<0.005		<0.005	<0.001			<0.05	7.68	1,310	920		<1		130	36	72	2.5	0	328	18	410	1.2	
GWQ96-23A	1/30/2010	<0.005	<0.02	0.0027	0.091	<0.002	0.074	<0.002	<0.006	<0.006	<0.006	0.66	<0.0002	0.63	<0.008	<0.01	<0.005	<0.0025	<0.0025	<0.0025			<0.01	8.00	1,100	689	640	<1		150	45	69	1.6	<2	640	12	6	1.7	
GWQ96-23A	7/1/2010	<0.005	<0.02	0.0011	0.13	<0.002	0.068	<0.002	<0.006	<0.006	<0.006	0.05	<0.0002	0.37	<0.008	<0.01	<0.005	<0.001	0.0014	<0.001	0.0025	<0.05	<0.01	8.00	1,200	804	510	<1		150	40	81	1.5	<2	510	14	140	1.5	13
GWQ96-23A	10/6/2010	<0.005	<0.02	<0.001	0.087	<0.002	0.08	<0.002	<0.006	<0.006	<0.006	0.31	<0.0002	0.41	<0.008	<0.01	<0.005	<0.001	0.0013	<0.001	0.0037	<0.05	<0.01	7.89	1,200	769	580	<1		140	45	80	1.3	<2	580	12	99	1.6	<10
GWQ96-23A	5/12/2011	<0.005	<0.02	<0.001	0.078	<0.002	0.071	<0.002	<0.006	<0.006	<0.006	0.04	<0.0002	0.29	<0.008	<0.01	<0.005	<0.001	0.0012	<0.001	0.003	<0.05	0.02	8.16	1,100	752	600	<0.1	<0.005	150	42	78	1.3	<2	600	13	74	1.7	<10
GWQ96-23B	7/14/1996	<0.05	7.4	<0.005	0.093	<0.002	0.058	<0.0005	<0.05	<0.025	<0.025	3.70	<0.001	0.13	<0.05	<0.05	<0.005	<0.003	<0.005	<0.001			<0.05	8.15	780	550		<1		67	20	79	4	0	234	20	170	1.1	
GWQ96-23B	10/6/2010	<0.005	<0.02	<0.001	0.1	<0.002	0.14	<0.002	<0.006	<0.006	<0.006	1.40	<0.0002	0.36	<0.008	<0.01	<0.005	<0.001	0.0011	<0.001	<0.001	<0.05	<0.01	7.85	900	554	480	<1		78	22	110	1.6	<2	480	19	<0.5	2.1	<10
GWQ96-23B	5/12/2011	<0.005	<0.02	<0.001	0.11	<0.002	0.14	<0.002	<0.006	<0.006	<0.006	0.93	<0.0002	0.34	<0.008	<0.01	<0.005	<0.001	0.0014	<0.001	<0.001	<0.05	0.07	7.99	890	556	490	<0.1	<0.005	81	22	110	1.7	<2	490	17	<0.5	2.1	24
IW-1	3/4/1987																							6.60	3,950	3,802		<0.1	<0.005	564		274	3.12		193	575	1,901		
IW-1	7/19/1991	<0.02		<0.002	<0.01			<0.005		<0.02	<0.02	<0.05	0.0005	<0.02			<0.005		0.015					7.87	6,460	4,235		9.06		636	182	375	7	0	222	633	1,985	0.7	
IW-1	8/29/1991																							7.13		4,120										642	1,918		
IW-1	11/26/1991																							7.53		3,979										615	1,634		
IW-1	3/15/1992																							7.88		4,026										611	2,201		
IW-1	5/25/1992																							7.09		4,155										598	2,203		
IW-1	7/16/1992																							7.12		4,297										585	1,775		
IW-1	10/8/1992																							6.96		3,996										617	1,727		
IW-1	11/27/1992																							7.71		4,004										605	1,717		
IW-1	12/15/1992																							7.40		3,969										609	1,415		
IW-1	9/28/1993																							7.12		3,661										521	1,150		
IW-1	3/17/1994																							7.00		3,684										405	1,569		
IW-1	5/24/1994	<0.025	0.94	<0.005	<0.1			<0.0005		<0.025	<0.025	1.00	<0.001	<0.03		<0.05	<0.005	<0.005	<0.005	<0.005			0.05	7.84	3,920	3,500		5.80		550	170	250	2.9	0	248	470	1,500	0.7	

Appendix A.
Table A-3. Groundwater-quality data

sample location	analysis date	silver (mg/L)	aluminum (mg/L)	arsenic (mg/L)	barium (mg/L)	beryllium (mg/L)	boron (mg/L)	cadmium (mg/L)	cobalt (mg/L)	chromium (mg/L)	copper (mg/L)	iron (mg/L)	mercury (mg/L)	manganese (mg/L)	molybdenum (mg/L)	nickel (mg/L)	lead (mg/L)	antimony (mg/L)	selenium (mg/L)	thallium (mg/L)	uranium (mg/L)	vanadium (mg/L)	zinc (mg/L)	pH (std. units)	specific conductance (µS/cm)	total dissolved solids (mg/L)	total alkalinity (mg/L as CaCO3)	nitrate as total N (mg/L)	total cyanide (mg/L)	calcium (mg/L)	magnesium (mg/L)	sodium (mg/L)	potassium (mg/L)	carbonate (mg/L)	bicarbonate (mg/L)	chloride (mg/L)	sulfate (mg/L)	fluoride (mg/L)	total suspended solids
IW-1	6/23/1994																							7.69		3,555									474	1,444		
IW-1	7/22/1994	<0.025	<0.05	<0.005	<0.1	<0.002	0.1	<0.0005	<0.05	<0.025	<0.025	<0.05	<0.001	<0.03	<0.05	<0.05	<0.005	<0.005	0.018	0.0063			<0.05	7.51	4,100	3,450		5.90		570	200	280	2.5	0	256	431	1,480	0.7	
IW-1	9/22/1994																							7.05		3,466									436	1,348		
IW-1	1/29/1995																							7.18		3,395									663	1,479		
IW-1	3/29/1995																							7.49		3,465									419	1,351		
IW-1	6/27/1995																							6.99		3,599									446	1,680		
IW-1	9/21/1995																							6.82		35									459	1,711		
IW-1	1/10/1996																							7.23		3,437									442	1,596		
IW-1	9/25/1996																							7.17		3,551									568	1,493		
IW-1	1/15/1997																							7.44		36									410	1,695		
IW-2	9/2/1982							<0.001						<0.05	<0.01				<0.005					7.30	4,250	4,010		1.38		320	174	720	234		185	409	2,252	1.2	
IW-2	5/25/1994	<0.025	22	<0.005	0.12	<0.002		<0.0005		0.046	<0.025	16.00	<0.001	0.77		0.097	0.0073	<0.005	<0.005				0.08	7.75	2,890	2,400		1.50		430	94	290	3.2	0	534	340	1,000	0.7	
IW-2	7/22/1994	<0.025	<0.05	<0.005	<0.1	<0.002	0.15	<0.0005	<0.05	<0.025	<0.025	<0.05	<0.001	0.036	<0.05	<0.05	<0.005	<0.005	0.014	0.0073			<0.05	7.78	3,400	2,390		<1		390	110	360	1.3	0	300	380	1,040	0.7	
IW-2	1/31/2010	<0.005	0.13	0.0092	0.024	<0.002	0.075	<0.002	0.0065	<0.006	<0.006	1.30	<0.0002	1.6	0.02	<0.01	<0.005	<0.0025	0.033	<0.0025			<0.01	8.00	3,200	2,770	260	<2	<0.005	390	120	290	1.6	<2	260	600	1,200	0.7	
IW-2	6/29/2010	<0.005	<0.02	<0.001	0.029	<0.002	0.061	<0.002	<0.006	<0.006	<0.006	0.87	0.00048	2.2	0.024	<0.01	<0.005	<0.001	0.029	<0.001	0.006	<0.05	<0.01	7.00	3,400	2,700	250	<2		390	110	260	1.8	<2	250	580	1,100	0.7	31,000
IW-2	9/30/2010	<0.005	0.044	<0.001	0.028	<0.002	0.073	<0.002	<0.006	<0.006	<0.006	0.41	<0.0002	2.2	0.02	<0.01	<0.005	<0.001	0.037	<0.001	0.0057	<0.05	0.02	7.36	3,000	2,280	250	<2	<0.01	360	110	270	1.6	<2	250	500	1,000	0.7	71,000
IW-2	5/9/2011	<0.005	<0.02	<0.001	0.037	<0.002	0.081	<0.002	0.017	<0.006	<0.006	0.36	<0.0002	3.6	0.021	<0.01	<0.005	0.0032	0.031	<0.001	0.0062	<0.05	0.02	7.31	3,200	2,360	240	1.70	<0.01	370	110	260	2.3	<2	240	520	1,100	0.6	20,000
IW-3	9/2/1982							<0.001						<0.05	<0.01				<0.005					7.20	1,700	1,562		4.12		234	42	168	3.51		179	159	707	0.4	
IW-3	2/25/1993																							7.27		3,892									590	1,739		
IW-3	5/26/1994	<0.025	32	<0.005	0.2			<0.0005		0.059	6	22.00	<0.001	0.35		0.19	0.077	<0.005	<0.005				0.15	7.83	1,790	1,870		5.70		240	51	69	4	0	341	209	415	0.5	
IW-3	7/23/1994	<0.025	<0.05	<0.005	<0.1	<0.002	<0.1	<0.0005	<0.05	<0.025	0.058	<0.05	<0.001	0.13	0.062	<0.05	<0.005	0.0055	0.011	<0.005			<0.05	7.76	1,860	1,300		5.00		200	66	89	3.5	0	255	206	437	0.5	
IW-3	4/3/1996																							7.04		3,364									433	1,566		
MW-4	6/13/1975																							7.90	620					46	10	73	4.4	0	226	15	110	0.6	
MW-4	7/20/1994	<0.025	<0.05	<0.005	<0.1	<0.002	<0.1	<0.0005	<0.05	<0.025	<0.025	<0.05	<0.001	<0.03	<0.05	<0.05	<0.005	<0.005	<0.005	<0.005			<0.05	8.34	408	256		<1		15	13	56	3.4	2	139	17	66	0.3	
NP-1	10/8/1981	<0.02	<0.25	<0.004	<1		<0.004	<0.01	<0.05	<0.05	<0.05	0.27	<1	0.92	<0.1	<0.05	<0.05		0.003				0.40	7.60		496		0.47	<0.05	56	14	62	8.25	<1	266	25	108	0.8	
NP-1	11/4/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	<0.1	<0.001	0.6	<0.05	<0.05	<0.02		<0.005				0.14	8.10		470		0.30	0.04	54						28	148	1.0	
NP-1	11/13/1981	<0.001	<0.25	<0.005	0.2		0.044	0.006		<0.005			<0.0005	1.34	0.011	<0.05	<0.005		0.029				0.44	7.65	625	470		0.09	0.001	72	19	39	5.85		274	24	131	0.8	
NP-1	11/17/1981	<0.02	<0.01	<0.005	0.24		<0.1	<0.005	<0.02	<0.01	0.069	<0.1	<0.001	1.4	0.06	<0.05	<0.02		<0.005				3.90	8.00		460		0.20	<0.01	59						24	154	0.8	
NP-1	11/23/1981	<0.02	<0.01	<0.01	0.02		<0.1	<0.005	<0.02	<0.02	<0.05	<0.1	<0.001	1.2	<0.05	<0.05	<0.02		<0.005				4.10	7.70		530		0.20	<0.01	58						26	146	0.8	
NP-1	12/7/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	<0.1	<0.001	1.2	<0.05	<0.05	<0.02		<0.005				5.10	7.30		490		0.20	<0.01	58						24	158	0.8	
NP-1	12/15/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	<0.1	<0.001	1.2	<0.05	<0.05	<0.02		<0.005				5.30	7.80		480		<0.2	<0.01	68						24	151	0.8	
NP-1	12/22/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	<0.1	<0.001	1	<0.05	<0.05	<0.02		<0.005				4.10	7.80		450		0.30	<0.01	66						22	149	0.8	
NP-1	1/5/1982	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	0.14	0.0012	0.71	<0.05	<0.05	<0.02		<0.02				4.10	7.60		400		0.70	<0.01	67						22	163	0.8	
NP-1	1/26/1982							<0.005			<0.05	<0.1	<0.001	0.45	<0.1				<0.005					7.90		440		0.50	<0.01							22	154	0.7	
NP-1	2/22/1982							<0.005			0.48	0.83	<0.001	0.26	<0.05				<0.005					7.90		460		0.60	<0.01							24	158	0.7	
NP-1	4/26/1982							<0.005			<0.05	1.20	<0.001	0.16	<0.05				<0.005					7.90		440		0.70	<0.01							26	154	0.6	
NP-1	5/24/1982											<0.1		0.28																									
NP-1	5/28/1982											<0.1		0.22																									
NP-1	6/8/1982							<0.005			<0.05	<0.1	<0.001	0.25	<0.05				<0.005					7.50		500		1.10	<0.01							20	162	0.6	
NP-1	6/30/1982							<0.005			<0.05	<0.1	<0.001	0.18	<0.05				<0.005					7.70		500		1.10	<0.01							18	143	0.6	
NP-1	10/27/1982							<0.005			<0.05	0.45	<0.001	0.058	<0.05				<0.005					7.70		470		1.30	<0.01							20	151	0.7	
NP-1	2/21/1983							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.70		490		1.30	<0.01							18	156	0.7	
NP-1	5/13/1983							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.90		470		1.10	<0.01							24	149	0.6	
NP-1	8/9/1983							<0.005			<0.05	0.22	<0.001	<0.05	<0.05				<0.005					7.80		480		1.10	<0.01							22	130	0.6	
NP-1	11/1/1983							<0.005			<0.05	0.14	<0.001	<0.05	<0.05				<0.005					7.80		500		2.10	<0.01							18	125	0.6	
NP-1	3/16/1984							<0.005			<0.05	<0.1	0.0083	<0.05	<0.05				<0.005					8.20		480		1.80	<0.01							22	124	0.6	
NP-1	4/9/1984												<0.001																									
NP-1	5/30/1984							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.50		510		0.70	<0.01							22	154	0.6	
NP-1	9/12/1984							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.70		480		1.10	<0.01							22	137	0.6	
NP-1	11/27/1984							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.80		480		1.10	<0.01							16	144	0.6	
NP-1	5/17/1985																							7.60		510										20	144		
NP-1	11/13/1985																							7.30		480										16	149		
NP-1	5/23/1986																							7.60		500										18	142		
NP-1	10/8/1986																							7.40		470										22	107		

Appendix A.
Table A-3. Groundwater-quality data

sample location	analysis date	silver (mg/L)	aluminum (mg/L)	arsenic (mg/L)	barium (mg/L)	beryllium (mg/L)	boron (mg/L)	cadmium (mg/L)	cobalt (mg/L)	chromium (mg/L)	copper (mg/L)	iron (mg/L)	mercury (mg/L)	manganese (mg/L)	molybdenum (mg/L)	nickel (mg/L)	lead (mg/L)	antimony (mg/L)	selenium (mg/L)	thallium (mg/L)	uranium (mg/L)	vanadium (mg/L)	zinc (mg/L)	pH (std. units)	specific conductance (µS/cm)	total dissolved solids (mg/L)	total alkalinity (mg/L as CaCO3)	nitrate as total N (mg/L)	total cyanide (mg/L)	calcium (mg/L)	magnesium (mg/L)	sodium (mg/L)	potassium (mg/L)	carbonate (mg/L)	bicarbonate (mg/L)	chloride (mg/L)	sulfate (mg/L)	fluoride (mg/L)	total suspended solids
NP-1	3/30/1989	<0.1	<0.1		<0.1	<0.1	<0.1	<0.1	<0.05	<0.1	<0.1	<0.1		<0.05	<0.1	<0.1	<0.1						2.60			492				88	23	46	3		279	15	137		
NP-1	7/19/1991	<0.02		0.003	0.02			<0.005		<0.02		0.59	<0.0002	<0.02			0.007		<0.002					8.04	761	530		0.99		81	24	31	2	0	256	22	133	0.6	
NP-1	8/29/1991																							7.69		501									21	141		
NP-1	11/26/1991																							7.12		1,484									23	137		
NP-1	3/15/1992																							7.80		510									22	146		
NP-1	5/25/1992																							7.49		608									29	128		
NP-1	7/16/1992																							7.50		487									22	142		
NP-1	10/8/1992																							7.35		517									22	129		
NP-1	11/27/1992																							7.85		498									21	142		
NP-1	12/15/1992																							7.58		502									24	125		
NP-1	2/25/1993																							7.42		510									23	138		
NP-1	3/30/1993	<0.01	<0.1	<0.005	<0.5		0.03	<0.002	<0.05	<0.02	<0.01	0.17	<0.001	<0.02	<0.02	<0.01	<0.02		<0.005				1.13	7.70	767	496	240	1.10	<0.01	79	27	52	1.8	0	306	22	145	0.6	
NP-1	9/28/1993																							7.48		508									36	110		
NP-1	3/17/1994																							7.30		516									24	134		
NP-1	5/24/1994	<0.025	0.83	0.005	<0.1			0.0096		<0.025	<0.025	9.50	<0.001	0.1		<0.05	0.016	<0.005	<0.005				5.70	7.53	680	510		1.10		79	23	48	2.5	0	263	22	130	0.6	
NP-1	6/23/1994																							7.50		453									40	142		
NP-1	7/21/1994	<0.025	<0.05	<0.005	<0.1	<0.002	<0.1	<0.0005	<0.05	<0.025	<0.025	0.05	<0.001	0.27	<0.05	<0.05	<0.005	<0.005	<0.005	<0.005			4.90	7.87	698	464		<1		71	23	47	2.2	0	249	23	133	0.7	
NP-1	9/22/1994																							7.49		488									24	119		
NP-1	1/29/1995																							7.94		407									26	125		
NP-1	3/29/1995																							7.98		392									23	86		
NP-1	6/27/1995																							8.02		385									24	114		
NP-1	9/21/1995																							7.96		373									27	145		
NP-1	1/10/1996																							7.73		277									26	109		
NP-1	4/3/1996																							7.89		300									26	123		
NP-1	9/25/1996																							8.22		320									24	94		
NP-1	1/15/1997																							8.42		318									26	109		
NP-1	1/31/2010	<0.005	<0.020	<0.0025	0.037	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006	0.10	<0.0002	0.0088	<0.008	<0.01	<0.005	<0.0025	0.0055	<0.0025			0.38	8.00	780	514	220	1.40	<0.005	87	29	52	2	<2	220	38	140	0.6	
NP-1	6/28/2010	<0.005	<0.020	0.0034	0.043	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006	<0.02	<0.0002	<0.002	<0.008	<0.01	<0.005	<0.001	0.0045	<0.001	0.0019	<0.05	0.05	8.00	790	548	230	1.40		90	26	46	1.9	<2	230	37	150	0.6	<10
NP-1	10/5/2010	<0.005	0.14	0.0035	0.041	<0.002	0.04	<0.002	<0.006	<0.006	<0.006	<0.02	<0.0002	<0.002	<0.008	<0.01	<0.005	<0.001	0.0045	<0.001	0.0018	<0.05	0.06	7.63	800	537	220	4.90		86	28	50	1.9	<2	220	35	140	0.6	13
NP-2	10/8/1981	<0.02	<0.25	0.024	<1		0.08	<0.01	<0.05	<0.05	<0.05	<0.1	<1	0.62	<0.1	<0.05	<0.05		<0.002				0.31	7.39		476		0.23	<0.05	46	15	94	9.57	<1	159	45	198	1.8	
NP-2	11/6/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	<0.1	<0.001	0.39	0.21	<0.05	<0.02		<0.005				1.70	7.60		450		0.40	<0.01	53						35	164	1.4	
NP-2	11/13/1981	<0.001	<0.25	<0.005	<0.1		0.04	<0.001		<0.005			<0.0005	0.79	0.04	<0.01	<0.005		0.017				3.18	7.65	675	466		0.25	0.0026	65	19	60	3.9		221	31	162	1.1	
NP-2	11/23/1981	<0.02	<0.01	<0.01	0.02		<0.1	<0.005	<0.02	<0.02	<0.05	<0.1	<0.001	0.54	0.06	<0.05	<0.02		<0.005				3.50	7.70		520		0.70	<0.01	57						30	156	0.9	
NP-2	12/7/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	<0.1	<0.001	0.54	0.06	<0.05	<0.02		<0.005				4.40	7.50		490		0.60	<0.01	53						30	160	0.8	
NP-2	12/15/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	<0.1	<0.001	0.52	0.072	<0.05	<0.02		<0.005				2.90	8.00		480		0.50	<0.01	62						32	161	0.9	
NP-2	12/22/1981	<0.02	<0.01	<0.01	0.21		<0.1	<0.005	<0.02	<0.01	<0.05	0.12	<0.001	0.51	0.053	<0.05	<0.02		<0.005				2.80	8.00		440		0.80	<0.01	73						32	161	0.6	
NP-2	1/5/1982	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	0.14	<0.001	0.49	0.07	<0.05	<0.02		<0.02				3.20	7.60		400		0.90	<0.01	65						28	158	0.9	
NP-2	1/26/1982							<0.005			<0.05	<0.1	<0.001	0.34	<0.1				<0.005					8.00		450		1.10	<0.01							24	160	0.7	
NP-2	2/22/1982							<0.005			0.069	0.37	<0.001	0.3	<0.05				<0.005					8.00		440		0.80	<0.01							30	151	0.7	
NP-2	4/26/1982							<0.005			<0.05	1.20	<0.001	0.29	<0.05				<0.005					8.00		450		2.40	<0.01							42	149	1.0	
NP-2	5/18/1982							0.015			<0.05	0.68	<0.001	0.078	<0.05				<0.005					7.90		460		1.80	<0.01							34	128	0.6	
NP-2	5/24/1982											<0.1		<0.05																									
NP-2	5/28/1982											<0.1		<0.05																									
NP-2	6/8/1982							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.80		490		0.90	<0.01							26	158	0.5	
NP-2	6/30/1982							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.80		490		1.40	<0.01							26	133	0.6	
NP-2	9/2/1982							<0.001						<0.05	<0.01				<0.005					7.40	650	468		1.66		74	18	58	1.95		316	26	127	0.5	
NP-2	10/27/1982							<0.005			<0.05	0.29	<0.001	<0.05	<0.05				<0.005					7.90		440		1.60	<0.01							26	120	0.6	
NP-2	2/21/1983							<0.005			<0.05	0.12	<0.001	<0.05	<0.05				<0.005					7.80		440		1.60	<0.01							24	127	0.6	
NP-2	5/13/1983							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.10		460		1.50	<0.01							24	139	0.6	
NP-2	8/9/1983							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.90		560		1.60	<0.01							36	148	0.6	
NP-2	11/1/1983							<0.005			<0.05	0.17	<0.001	<0.05	<0.05				<0.005					8.00		470		2.30	<0.01							24	111	0.6	
NP-2	3/16/1984							<0.005			<0.05	<0.1	0.001	<0.05	<0.05				<0.005					8.20		500		1.60	<0.01							30	146	0.8	
NP-2	5/30/1984							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.70		520		1.40	<0.01							32	175	0.6	
NP-2	9/12/1984							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.80		470		1.70	<0.01							22	134	0.6	

Appendix A.
Table A-3. Groundwater-quality data

sample location	analysis date	silver (mg/L)	aluminum (mg/L)	arsenic (mg/L)	barium (mg/L)	beryllium (mg/L)	boron (mg/L)	cadmium (mg/L)	cobalt (mg/L)	chromium (mg/L)	copper (mg/L)	iron (mg/L)	mercury (mg/L)	manganese (mg/L)	molybdenum (mg/L)	nickel (mg/L)	lead (mg/L)	antimony (mg/L)	selenium (mg/L)	thallium (mg/L)	uranium (mg/L)	vanadium (mg/L)	zinc (mg/L)	pH (std. units)	specific conductance (µS/cm)	total dissolved solids (mg/L)	total alkalinity (mg/L as CaCO3)	nitrate as total N (mg/L)	total cyanide (mg/L)	calcium (mg/L)	magnesium (mg/L)	sodium (mg/L)	potassium (mg/L)	carbonate (mg/L)	bicarbonate (mg/L)	chloride (mg/L)	sulfate (mg/L)	fluoride (mg/L)	total suspended solids
NP-2	11/27/1984							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.90		470		1.70	<0.01							20	125	0.6	
NP-2	5/17/1985																							7.80		480										22	120		
NP-2	11/13/1985																							7.40		460										22	115		
NP-2	5/23/1986																							7.60		480										28	113		
NP-2	10/8/1986																							7.40		430										24	100		
NP-2	3/30/1989	<0.1	<0.1		<0.1	<0.1	<0.1	<0.1	<0.05	<0.1	<0.1	<0.1		0.06	<0.1	<0.1	<0.1						0.50			376				52	18	65	3		183	29	124		
NP-2	7/19/1991	<0.02		<0.002	<0.01			<0.005		<0.02	<0.02	<0.05	<0.0002	<0.02			<0.005		0.018					7.55	726	453		0.02		34	24	48	0.8	0	56	61	181	0.6	
NP-2	8/29/1991																							8.11		471										63	198		
NP-2	11/26/1991																							7.45		460										63	170		
NP-2	3/15/1992											<0.05												8.07		467										68	194		
NP-2	5/25/1992											<0.05												8.34		456										67	162		
NP-2	7/16/1992											<0.05												8.13		479										65	184		
NP-2	10/8/1992																							8.26		494										78	179		
NP-2	11/27/1992																							8.38		451										64	179		
NP-2	12/15/1992											<0.05												8.43		612										83	167		
NP-2	2/25/1993																							8.62		475										78	197		
NP-2	3/30/1993	<0.01	0.5	<0.005	0.6		0.1	<0.002	<0.05	<0.02	0.01	1.85	<0.001	0.07	<0.02	<0.01	<0.02		0.005				0.67	7.70	1,910	1,310	240	3.30	<0.01	163	61	163	0.9	0	289	239	436	1.3	
NP-2	9/28/1993																							7.92		1,170										207	300		
NP-2	3/17/1994																							7.65		971										118	301		
NP-2	5/24/1994	<0.025	4.6	<0.005	<0.1			0.00097		<0.025	<0.025	4.50	<0.001	0.19		<0.05	0.0079	<0.005	<0.005				4.10	8.03	1,250	878		<0.1		120	47	100	2.3	0	261	130	300	1.0	
NP-2	6/23/1994																							7.69		848										124	268		
NP-2	7/22/1994	<0.025	<0.05	<0.005	<0.1	<0.002	<0.1	<0.0005	<0.05	<0.025	<0.025	<0.05	<0.001	<0.03	<0.05	<0.05	<0.005	0.0059	<0.005	<0.005			1.20	7.88	1,360	878		1.50		120	43	120	1.3	0	270	128	299	0.9	
NP-2	9/22/1994																							7.55		963										124	253		
NP-2	1/29/1995																							7.57		791										94	121		
NP-2	3/29/1995																							7.69		1,164										91	229		
NP-2	6/27/1995																							7.93		778										96	247		
NP-2	9/21/1995																							7.36		722										87	212		
NP-2	1/10/1996																							7.10		632										79	173		
NP-2	4/3/1996																							7.23		603										77	169		
NP-2	9/25/1996																							7.68		598										57	118		
NP-2	1/15/1997																							7.44		536										56	148		
NP-2	1/31/2010	<0.005	<0.02	0.0032	0.058	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006	0.09	<0.0002	0.19	<0.008	<0.01	<0.005	<0.0025	0.017	<0.0025			1.10	8.00	1,100	746	160	2.50	<0.005	120	35	75	2.4	<2	160	150	210	0.5	
NP-2	6/28/2010	<0.005	<0.02	<0.001	0.057	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006	<0.02	<0.0002	0.021	<0.008	<0.01	<0.005	<0.001	0.012	<0.001	0.0017	<0.05	0.26	7.00	1,200	846	170	2.70		130	35	71	2.2	<2	170	170	260	0.4	740
NP-3	10/8/1981	<0.02	<0.25	0.005	<1		0.188	<0.01	<0.05	<0.05	<0.05	<0.1	<1	0.81	<0.1	<0.05	<0.05		0.005				1.25	6.98		460		<0.05	<0.05	41	10	79	9.71	<1	211	29	95	1.6	
NP-3	10/27/1981	<0.02	<0.01	<0.01	0.2		<0.1	<0.005	<0.02	<0.01	<0.05	0.39	<0.001	1	0.16	<0.05	<0.02		<0.005				0.98	8.00		390		0.40	<0.01	41						28	148	1.9	
NP-3	10/30/1981	<0.02	<0.25	<0.005	<1		0.29	<0.01	<0.05	<0.05	<0.05	<0.1	<0.001	1.03	<0.1	<0.02	<0.05		<0.002				0.93	7.89		428		<0.05	<0.05							31	102	1.6	
NP-3	11/6/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	<0.1	<0.001	0.47	0.26	<0.05	<0.02		<0.005				1.10	7.90		380		0.20	<0.01	39						28	140	1.6	
NP-3	11/13/1981	0.023	<0.25	0.009	<0.1		0.034	<0.001		<0.005			<0.0005	1.01	0.065	<0.05	<0.005		0.023				1.59	7.60	600	446		0.16		55	13	44	5.85		190	27	141	1.4	
NP-3	11/17/1981	<0.02	<0.01	<0.01	0.24		<0.1	<0.005	<0.02	<0.01	<0.05	<0.1	<0.001	1	0.2	<0.05	<0.02		<0.005				1.20	8.10		390		<0.2	<0.01	44						26	144	1.4	
NP-3	11/23/1981	<0.01	<0.01	<0.01	0.02		<0.1	<0.005	<0.02	<0.02	<0.05	<0.1	<0.001	0.96	0.15	<0.05	<0.02		<0.005				1.90	7.80		460		0.20	<0.01	47						26	144	1.2	
NP-3	12/7/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	<0.1	<0.001	0.78	0.13	<0.05	<0.02		<0.005				3.50	7.90		450		<0.2	<0.01	47						28	153	1.1	
NP-3	12/15/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	<0.1	<0.001	0.87	0.094	<0.05	<0.02		<0.005				2.50	7.80		450		0.20	<0.01	56						26	149	1.1	
NP-3	12/22/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	<0.1	<0.001	0.76	0.1	<0.05	<0.02		<0.005				2.10	7.90		410		0.20	<0.01	73						26	149	0.9	
NP-3	1/5/1982	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	0.31	<0.001	0.72	0.01	<0.05	<0.02		<0.02				1.70	7.70		360		0.20	<0.01	56						26	154	1.1	
NP-3	1/26/1982							<0.005			<0.05	<0.1	<0.001	0.7	<0.1				<0.005					8.10		400		0.20	<0.01							30	151	1.0	
NP-3	2/22/1982							<0.005			<0.05	0.14	<0.001	0.66	<0.05				<0.005					8.00		420		<0.2	<0.01							28	137	0.9	
NP-3	4/26/1982							<0.005			<0.05	0.24	<0.001	0.4	<0.05				<0.005					7.90		410		<0.2	<0.01							28	146	0.8	
NP-3	5/24/1982											<0.1		0.053																									
NP-3	5/28/1982											<0.1		0.063																									
NP-3	6/8/1982							<0.005			<0.05	<0.1	<0.001	0.1	<0.05				<0.005					7.90		500		1.90	<0.01							30	150	0.5	
NP-3	6/30/1982							<0.005			<0.05	<0.1	<0.001	0.081	<0.05				<0.005					7.90		510		1.80	<0.01							26	128	0.5	
NP-3	9/2/1982							<0.001						<0.05	<0.01				<0.005					7.50	750	498		1.94		77	15	64	3.9		308	28	124	0.5	
NP-3	10/27/1982							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.00		450		1.60	<0.01							26	132	0.6	
NP-3	2/21/1983							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.20		410		1.40	<0.01							26	131	0.5	

Appendix A.
Table A-3. Groundwater-quality data

sample location	analysis date	silver (mg/L)	aluminum (mg/L)	arsenic (mg/L)	barium (mg/L)	beryllium (mg/L)	boron (mg/L)	cadmium (mg/L)	cobalt (mg/L)	chromium (mg/L)	copper (mg/L)	iron (mg/L)	mercury (mg/L)	manganese (mg/L)	molybdenum (mg/L)	nickel (mg/L)	lead (mg/L)	antimony (mg/L)	selenium (mg/L)	thallium (mg/L)	uranium (mg/L)	vanadium (mg/L)	zinc (mg/L)	pH (std. units)	specific conductance (µS/cm)	total dissolved solids (mg/L)	total alkalinity (mg/L as CaCO3)	nitrate as total N (mg/L)	total cyanide (mg/L)	calcium (mg/L)	magnesium (mg/L)	sodium (mg/L)	potassium (mg/L)	carbonate (mg/L)	bicarbonate (mg/L)	chloride (mg/L)	sulfate (mg/L)	fluoride (mg/L)	total suspended solids
NP-3	5/13/1983							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.00		500		2.10	<0.01							64	139	0.5	
NP-3	8/9/1983							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.80		630		2.30	<0.01							114	100	0.5	
NP-3	11/1/1983							<0.005			<0.05	0.14	<0.001	<0.05	<0.05				<0.005					7.90		760		3.80	<0.01							162	163	0.5	
NP-3	3/16/1984							<0.005			<0.05	<0.1	0.001	<0.05	<0.05				<0.005					8.10		870		3.20	<0.01							228	216	0.6	
NP-3	5/30/1984							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.80		1,060		2.90	<0.01							248	292	0.4	
NP-3	9/12/1984							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.70		1,140		3.10	<0.01							270	292	0.4	
NP-3	11/27/1984							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.80		1,150		3.50	<0.01							290	348	0.4	
NP-3	5/17/1985																							7.70		1,470										310	453		
NP-3	11/13/1985																							7.20		1,520										288	541		
NP-3	5/23/1986																							7.50		1,590										282	624		
NP-3	10/8/1986																							7.40		1,710										272	620		
NP-3	3/3/1987																																				695		
NP-3	3/4/1987																							6.80	1,850	1,882				320	67	117	4.29		188	283	695		
NP-3	5/25/1987																																				736		
NP-3	1/12/1988	<0.1	<0.1		<0.1	<0.1	<0.1	<0.1	<0.05	<0.1	<0.1	<0.1		0.57	<0.1	<0.1	<0.1						1.10			1,584				268	57	142	38		30	359	755		
NP-3	4/4/1988																									1,772										254	587		
NP-3	8/23/1988																									1,744										251	835		
NP-3	2/9/1989																									1,583										254	763		
NP-3	6/1/1989																									1,596										241	714		
NP-3	11/30/1989																									1,600										159	743		
NP-3	11/14/1990																									1,675										229	822		
NP-3	2/11/1991			<0.001																						1,551										256	971		
NP-3	7/19/1991	<0.02		<0.002	<0.01			<0.005		<0.02	<0.02	0.28	0.0002	0.08			<0.005		0.011					8.29	2,520	1,663		0.23		287	53	190	7	0	192	239	820	0.7	
NP-3	8/29/1991																							7.84		1,616										254	854		
NP-3	11/26/1991																							7.08		1,613										248	745		
NP-3	3/15/1992																							7.63		1,644										228	921		
NP-3	5/25/1992																							7.85		1,607										216	753		
NP-3	7/16/1992																							7.26		1,578										226	802		
NP-3	10/8/1992																							7.69		1,445										212	799		
NP-3	11/27/1992																							7.49		1,640										255	796		
NP-3	12/15/1992										0.01													7.75		1,558										223	545		
NP-3	2/25/1993																							7.65		1,580										219	794		
NP-3	3/30/1993	<0.01	0.1	<0.005	<0.5		0.02	<0.002	<0.05	<0.02	0.01	4.99	<0.001	0.32	<0.02	<0.01	<0.02		<0.005				6.98	7.40	2,070	1,560			<0.01	296	35	129	4.1	0	29	205	825	0.5	
NP-3	9/28/1993										<0.001	<0.05		0.24									1.04	7.88		1,544										210	619		
NP-3	3/17/1994										0.012	0.24		0.33									2.58	7.46		1,609										170	747		
NP-3	6/23/1994																							7.77		1,628										206	779		
NP-3	7/22/1994	<0.025	<0.05	<0.005	<0.1	<0.002	<0.1	<0.0005	<0.05	<0.025	<0.025	<0.05	<0.001	0.61	<0.05	<0.05	<0.005	<0.005	<0.005	<0.005			1.80	7.83	2,160	1,620		<1		320	73	120	4.5	0	118	194	796	0.3	
NP-3	9/22/1994																							7.65		1,691										196	707		
NP-3	1/29/1995																							7.45		1,623										*566*	652		
NP-3	3/29/1995																							7.48		1,639										186	558		
NP-3	6/27/1995																							7.38		1,607										203	717		
NP-3	9/21/1995																							7.50		1,557										208	822		
NP-3	1/10/1996																							7.32		1,464										209	724		
NP-3	4/3/1996																							7.29		1,415										208	723		
NP-3	9/25/1996																							7.72		1,472										191	537		
NP-3	1/15/1997																							7.51		1,478										207	657		
NP-3	7/8/2010	<0.005	<0.02	<0.0010	0.03	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006	0.05	<0.0002	0.031	<0.008	<0.01	<0.005	<0.001	0.023	<0.001	0.0014	<0.05	0.44	8.00	2,100	1,740	120	6.80		310	60	120	3.6	<2	120	270	790	0.4	100
NP-3	10/7/2010	<0.005	<0.02	<0.005	0.031	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006	0.10	<0.0002	0.015	<0.008	<0.01	<0.005	<0.001	0.023	<0.001	0.0015	<0.05	0.31	7.57	2,000	1,660	120	5.60		290	60	110	3.5	<2	120	290	830	0.3	97
NP-3	5/11/2011	<0.005	<0.02	0.0029	0.032	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006	0.04	<0.0002	0.022	<0.008	<0.01	<0.005	<0.001	0.027	<0.001	0.0015	<0.05	0.24	7.69	2,100	1,640	130	6.20	<0.005	300	57	120	3.3	<2	130	270	790	0.3	400
NP-4	4/26/1982							<0.005			0.051	3.80	<0.001	0.6	0.07				<0.005					8.60		410		0.60	<0.01							46	132	1.5	
NP-4	5/17/1982							<0.005			<0.05	0.11	<0.001	<0.05	<0.05				<0.005					9.40		310		1.30	<0.01							46	138	1.0	
NP-4	5/24/1982											<0.1		<0.05																									
NP-4	5/28/1982											<0.1		<0.05																									
NP-4	6/8/1982							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.40		420		4.50	<0.01							26	140	0.5	

Appendix A.
Table A-3. Groundwater-quality data

sample location	analysis date	silver (mg/L)	aluminum (mg/L)	arsenic (mg/L)	barium (mg/L)	beryllium (mg/L)	boron (mg/L)	cadmium (mg/L)	cobalt (mg/L)	chromium (mg/L)	copper (mg/L)	iron (mg/L)	mercury (mg/L)	manganese (mg/L)	molybdenum (mg/L)	nickel (mg/L)	lead (mg/L)	antimony (mg/L)	selenium (mg/L)	thallium (mg/L)	uranium (mg/L)	vanadium (mg/L)	zinc (mg/L)	pH (std. units)	specific conductance (µS/cm)	total dissolved solids (mg/L)	total alkalinity (mg/L as CaCO3)	nitrate as total N (mg/L)	total cyanide (mg/L)	calcium (mg/L)	magnesium (mg/L)	sodium (mg/L)	potassium (mg/L)	carbonate (mg/L)	bicarbonate (mg/L)	chloride (mg/L)	sulfate (mg/L)	fluoride (mg/L)	total suspended solids
NP-4	6/30/1982							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					9.50		270		<0.2	<0.01							28	115	0.4	
NP-4	9/2/1982							<0.001						<0.05	<0.01				<0.005					8.50	410	252		0.03		7	4	71	3.9		63	29	107	0.4	
NP-4	10/27/1982							0.0061			<0.05	0.34	<0.001	<0.05	<0.05				<0.005					8.90		230		<0.2	<0.01							36	108	0.4	
NP-4	2/21/1983							<0.005			<0.05	0.28	0.001	<0.05	<0.05				<0.005					9.30		250		0.20	<0.01							48	115	0.4	
NP-4	5/13/1983							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.90		340		<0.2	<0.01							76	134	0.4	
NP-4	8/9/1983							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.80		430		<0.2	<0.01							94	156	0.3	
NP-4	11/1/1983							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.20		530		0.60	<0.01							114	206	0.3	
NP-4	3/16/1984							<0.005			<0.05	<0.1	0.001	<0.05	<0.05				<0.005					8.00		540		0.20	<0.01							126	256	0.6	
NP-4	5/30/1984							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.00		630		<0.2	<0.01							134	320	0.3	
NP-4	9/12/1984							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.00		760		0.90	<0.01							134	339	0.3	
NP-4	11/27/1984							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.50		740		0.20	<0.01							140	354	0.3	
NP-4	5/17/1985																							8.20		770										146	348		
NP-4	11/13/1985																							8.00		690										142	292		
NP-4	5/23/1986																							8.00		690										136	300		
NP-4	10/8/1986																							7.80		660										134	290		
NP-4	5/25/1987																																				279		
NP-4	1/12/1988	<0.1	<0.1		<0.1	<0.1	<0.1	<0.1	<0.05	<0.1	<0.1	<0.1		0.06	<0.1	<0.1	<0.1						0.10			612				76	21	86	5		24	137	256		
NP-4	4/4/1988																									610										130	329		
NP-4	8/23/1988																									688										132	292		
NP-4	2/9/1989																									604										130	267		
NP-4	6/1/1989																									580										116	244		
NP-4	11/30/1989																									572										97	237		
NP-4	11/14/1990																									262										153	255		
NP-4	2/11/1991			<0.001																						676										126	289		
NP-4	7/19/1991	<0.02		<0.002	0.28			<0.005		<0.02		5.14	<0.0002	<0.02			<0.005		<0.002					7.81	802	532		0.07		63	21	67	3.1	0	55	112	199	0.4	
NP-4	8/29/1991																							8.37		532										111	232		
NP-4	11/26/1991																							8.54		522										99	194		
NP-4	3/15/1992																							8.85		465										103	217		
NP-4	5/25/1992																							8.62		439										106	171		
NP-4	7/16/1992																							7.64		458										94	177		
NP-4	10/8/1992																							9.01		535										103	183		
NP-4	11/27/1992																							8.12		495										98	202		
NP-4	12/15/1992																							9.52		424										84	151		
NP-4	2/25/1993																							9.85		349										77	151		
NP-4	3/31/1993	<0.01	0.3	<0.005	<0.5		0.04	<0.002	<0.05	<0.02	0.01	0.62	0.009	0.84	<0.02	<0.01	<0.02		<0.005				2.41	7.60	813	504	230	3.70	<0.01	76	17	79	2.2	0	275	45	134	0.5	
NP-4	9/28/1993																							8.20		437										57	109		
NP-4	5/26/1994	<0.025	3.5	<0.005	<0.1			0.0034		<0.025	<0.025	15.00	<0.001	0.16		<0.05	0.018	<0.005	<0.005				12.00	8.10	800	666		4.30		73	15	62	3	0	320	39	131	0.5	
NP-4	6/23/1994																							8.13		498										49	134		
NP-4	7/23/1994	<0.025	<0.05	<0.005	<0.1	<0.002	<0.1	<0.0005	<0.05	<0.025	<0.025	<0.05	<0.001	<0.03	<0.05	<0.05	<0.005	0.01	<0.005	<0.005			0.51	7.90	828	536		4.60		88	16	72	2.5	0	279	34	120	0.5	
NP-4	9/22/1994																							7.73		547										37	111		
NP-4	1/29/1995																							7.88		447										35	111		
NP-4	3/29/1995																							7.86		494										34	122		
NP-4	6/27/1995																							7.37		487										33	134		
NP-4	9/21/1995																							7.51		509										35	132		
NP-4	1/10/1996																							7.35		483										35	123		
NP-4	4/3/1996																							7.19		475										26	123		
NP-4	9/25/1996																							7.75		504										32	126		
NP-4	1/15/1997																							7.43		2,651										98	1,113		
NP-4	1/31/2010	<0.005	<0.02	<0.0025	0.036	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006	0.04	<0.0002	0.0098	<0.008	<0.01	<0.005	<0.0025	0.0057	<0.0025			1.30	8.00	900	626	210	7.40	<0.005	100	18	79	2.4	<2	210	40	190	0.5	
NP-4	7/2/2010	<0.005	<0.02	<0.001	0.039	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006	<0.02	<0.0002	0.002	<0.008	<0.01	<0.005	<0.001	0.0043	<0.001	0.0023	<0.05	0.82	8.00	910	640	210	7.50		110	18	70	2.1	<2	210	39	190	0.5	140
NP-5	11/4/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	<0.1	<0.001	0.1	<0.05	<0.05	<0.02		<0.005				0.14	8.00		570		4.10	<0.01	86						50	196	1.3	
NP-5	11/13/1981	<0.001	0.239	<0.005	0.218		0.07	<0.001		<0.005	<0.1		<0.0005	0.14	0.015	0.019	<0.005		0.014				<0.05	7.70	650	488		3.56	0.001	89	14	44	5.07		187	38	162	1.3	
NP-5	11/17/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	<0.1	<0.001	0.3	0.07	<0.05	<0.02		<0.005				0.19	8.00		500		2.70	<0.01	72						42	158	1.3	
NP-5	11/23/1981	<0.1	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.02	<0.05	<0.1	<0.001	0.091	<0.05	<0.05	<0.02		<0.005				0.21	7.80		580		4.00	<0.01	73						36	161	1.2	

Appendix A.
Table A-3. Groundwater-quality data

sample location	analysis date	silver (mg/L)	aluminum (mg/L)	arsenic (mg/L)	barium (mg/L)	beryllium (mg/L)	boron (mg/L)	cadmium (mg/L)	cobalt (mg/L)	chromium (mg/L)	copper (mg/L)	iron (mg/L)	mercury (mg/L)	manganese (mg/L)	molybdenum (mg/L)	nickel (mg/L)	lead (mg/L)	antimony (mg/L)	selenium (mg/L)	thallium (mg/L)	uranium (mg/L)	vanadium (mg/L)	zinc (mg/L)	pH (std. units)	specific conductance (µS/cm)	total dissolved solids (mg/L)	total alkalinity (mg/L as CaCO3)	nitrate as total N (mg/L)	total cyanide (mg/L)	calcium (mg/L)	magnesium (mg/L)	sodium (mg/L)	potassium (mg/L)	carbonate (mg/L)	bicarbonate (mg/L)	chloride (mg/L)	sulfate (mg/L)	fluoride (mg/L)	total suspended solids
NP-5	12/7/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	<0.1	<0.001	<0.05	<0.05	<0.05	<0.02		<0.005				0.24	7.90		510		3.10	<0.01	66						34	172	1.2	
NP-5	12/15/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	<0.1	<0.001	0.08	<0.05	<0.05	<0.02		<0.005				0.37	7.80		500		3.30	<0.01	90						36	168	1.2	
NP-5	12/22/1981	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	<0.1	<0.001	<0.05	<0.05	<0.05	<0.02		<0.005				0.32	7.90		460		3.80	<0.01	101						36	161	1.1	
NP-5	1/5/1982	<0.02	<0.01	<0.01	<0.2		<0.1	<0.005	<0.02	<0.01	<0.05	0.18	<0.001	<0.05	<0.05	<0.05	<0.02		<0.02				0.40	7.70		420		4.10	<0.01	87						34	163	1.1	
NP-5	1/26/1982							<0.005			<0.05	<0.01	<0.001	<0.05	<0.1				<0.005					8.00		440		2.90	<0.01							32	158	1.1	
NP-5	2/22/1982							<0.005			<0.05	0.12	<0.001	<0.05	<0.05				<0.005					8.00		450		2.00	<0.01							32	150	1.0	
NP-5	4/26/1982							<0.005			0.31	3.80	<0.001	6.9	<0.05				<0.005					7.90		450		1.10	0.04							30	154	1.1	
NP-5	5/17/1982							<0.005			<0.05	0.14	<0.001	<0.05	<0.05				<0.005					8.00		490		6.70	<0.01							36	165	1.1	
NP-5	5/24/1982											<0.1		<0.05																								
NP-5	5/28/1982											<0.1		<0.05																								
NP-5	6/8/1982							<0.005			<0.05	0.44	<0.001	<0.05	<0.05				<0.005					8.10		420		4.50	<0.01							30	150	0.9	
NP-5	6/30/1982							<0.005			<0.05	0.36	<0.001	<0.05	<0.05				<0.005					8.10		460		3.90	<0.01							28	133	0.9	
NP-5	9/2/1982							<0.001						<0.05	<0.01				<0.005					7.60	650	472		4.20		73	22	46	3.9		206	34	137	0.8	
NP-5	10/27/1982							<0.005			<0.05	0.21	<0.001	<0.05	<0.05				<0.005					8.00		440		3.70	<0.01							34	139	0.8	
NP-5	2/21/1983							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.30		420		1.30	<0.01							26	139	0.5	
NP-5	5/13/1983							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.90		290		0.20	<0.01							70	134	0.4	
NP-5	8/9/1983							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.10		460		3.70	<0.01							26	108	0.8	
NP-5	11/1/1983							<0.005			<0.05	0.10	<0.001	<0.05	<0.05				<0.005					8.20		440		5.20	<0.01							30	111	0.8	
NP-5	3/16/1984							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.00		380		3.00	<0.01							26	130	0.4	
NP-5	5/30/1984							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					7.80		400		2.90	<0.01							22	139	0.8	
NP-5	9/12/1984							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.00		420		3.40	<0.01							28	125	0.8	
NP-5	11/27/1984							<0.005			<0.05	<0.1	<0.001	<0.05	<0.05				<0.005					8.20		420		3.20	<0.01							28	120	0.8	
NP-5	5/17/1985																							7.90		450										28	130		
NP-5	11/13/1985																							7.80		400										24	134		
NP-5	5/23/1986																							7.90		430										28	120		
NP-5	10/8/1986																							7.80		420										28	113		
NP-5	3/30/1989	<0.1	<0.1		<0.1	<0.1	<0.1	<0.1	<0.05	<0.1	<0.1	<0.1		<0.05	<0.1	<0.1	<0.1						0.40			458				82	22	39	3		211	32	125		
NP-5	8/29/1991																							7.68		499										39	152		
NP-5	11/26/1991																							7.00		472										38	130		
NP-5	3/15/1992																							7.89		456										47	141		
NP-5	5/25/1992																							7.80		490										76	131		
NP-5	7/16/1992																							7.63		476										38	132		
NP-5	10/8/1992																							7.64		431										39	133		
NP-5	11/27/1992																							8.01		475										117	134		
NP-5	12/15/1992										0.025													7.80		402										40	104		
NP-5	2/25/1993																							7.65		487										41	141		
NP-5	3/30/1993	<0.01	0.2	<0.005	<0.5		0.04	<0.002	<0.05	<0.02	<0.01	0.29	<0.001	0.02	<0.02	<0.01	<0.02		<0.005				0.19	7.80	746	488	200	4.00	<0.01	76	26	43	2.5	0	221	39	146	0.8	
NP-5	9/28/1993																							7.79		518										48	109		
NP-5	5/24/1994	<0.025	1.1	<0.005	<0.1			<0.0005		<0.025	<0.025	1.20	<0.001	0.086		<0.05	0.0077	<0.005	<0.005				2.30	7.84	680	520		3.40		86	26	40	3.4	0	211	41	130	0.7	
NP-5	6/23/1994																							7.66		466										54	142		
NP-5	7/23/1994	<0.025	<0.05	<0.005	<0.1	<0.002	<0.1	<0.0005	<0.05	<0.025	<0.025	<0.05	<0.001	<0.03	<0.05	<0.05	<0.005	<0.005	<0.005	<0.005			<0.05	7.89	749	494		3.30		79	24	45	3.1	0	206	41	131	0.7	
NP-5	9/22/1994																							7.73		526										43	118		
NP-5	1/29/1995																							7.99		490										44	101		
NP-5	3/29/1995																							7.94		449										42	131		
NP-5	6/27/1995																							7.64		525										43	119		
NP-5	9/21/1995																							7.71		483										44	135		
NP-5	1/10/1996																							8.04		406										42	137		
NP-5	4/3/1996																							7.67		405										32	130		
NP-5	9/25/1996																							8.09		504										43	129		
NP-5	1/15/1997																							7.76		498										46	141		
NP-5	6/28/2010	<0.005	<0.02	0.0014	0.018	<0.002	<0.04	<0.002	<0.006	<0.006	<0.006	<0.02	<0.0002	<0.002	<0.008	<0.01	<0.005	<0.001	0.0067	<0.001	0.0013	<0.05	0.29	8.00	900	623	160	3.90		100	31	44	2.9	<2	160	80	180	0.7	23
NP-5	9/30/2010	<0.005	<0.02	0.0015	0.018	<0.002	0.041	<0.002	<0.006	<0.006	<0.006	<0.02	<0.0002	0.005	<0.008	<0.01	<0.005	<0.001	0.0079	<0.001	0.0013	<0.05	0.20	7.72	910	629	170	4.00	<0.01	99	33	46	2.8	<2	170	83	170	0.7	31
NP-5	5/10/2011	<0.005	<0.02	0.0018	0.019	<0.002	0.042	<0.002	<0.006	<0.006	<0.006	<0.02	<0.0002	<0.002	<0.008	<0.01	<0.005	<0.001	0.0076	<0.001	0.0013	<0.05	0.26	7.76	940	636	160	4.10	<0.01	100	32	45	2.9	<2	160	79	180	0.6	130

Notes: outlier values in gray shading

Appendix B.

Construction diagrams for GWQ-5R, GWQ11-24(A,B), and GWQ11-25(A,B)



Well completion diagram for replacement monitoring well GWQ-5R.
LRG-15080 POD 3, completed September 1, 2011.



Well completion diagram of nested piezometer GWQ11-24.
LRG-15080 POD 1, completed August 5, 2011.



Well completion diagram of nested piezometer GWQ11-25.
LRG-15080 POD 2, completed August 28, 2011.

10-19-2011

Copper Flat Mine status meeting proposed agenda and call-in information

2 messages

Jens Deichmann <jdeichmann@themacresourcesgroup.com> **Wed, Oct 19, 2011 at 4:58 PM**

To: "Myers, Kevin, OSE" <kevin.myers@state.nm.us>, "Huey, Greg, NMENV" <greg.huey@state.nm.us>, "Eustice, Chris, EMNRD" <chris.eustice@state.nm.us>, "Hennessey, Joseph, OSE" <Joseph.Hennessey@state.nm.us>, "Vollbrecht, Kurt, NMENV" <kurt.vollbrecht@state.nm.us>, "Jankowitz, Rachel J., DGF" <rachel.jankowitz@state.nm.us>, "Kliphuis, Trais, NMENV" <trais.kliphuis@state.nm.us>, Doug Haywood <dhaywood@blm.gov>, Mike Smith <mikesmit@blm.gov>, "Shepherd, Holland, EMNRD" <holland.shepherd@state.nm.us>
Cc: Steve Raugust <sraugust@themacresourcesgroup.com>, Ferol Baker <fbaker@themacresourcesgroup.com>

Here are the agenda items we propose for tomorrow's meeting. Of course we will want to include any that you might have as well.

1. Brief recap of progress in last month, remaining work to be be accomplished in field
2. Discuss Fish Bone Diagram and activity and deliverable sequencing and interdependency
3. The timing of the BDR and the PAP submittals as well as the expectations and level of effort for the PAP
4. The level of effort and content of the Closure Closeout Plan (PAP Reclamation Designs)
5. Progress on the MPO review for the Groundwater Discharge Plan
6. State agency expectation of involvement in 3rd Party NEPA contractor selection
7. Other

Call 1-888-757-27902. Enter participant pass code 187864
Thanks, Jens
--
Jens Deichmann
Permitting Manager - Regulatory
Copper Flat Mine
THEMAC Resources Group, LTD.
2425 San Pedro NE
Albuquerque, NM 87110
Office: 505.382.5770
Mobile: 505-681-2536
Fax: 505-881-4616
www.themacresourcesgroup.com
This e-mail and any attachment may be confidential and privileged or otherwise protected from disclosure. It is solely intended for the person(s) named above. If you are not the intended recipient, any reading, use, disclosure, copying or distribution of all or parts of this e-mail or associated attachments is strictly prohibited. If you are not an intended recipient, please notify the sender immediately by replying to this message or by telephone and delete this e-mail and any attachments permanently from your system.

Steve Raugust <sraugust@themacresourcesgroup.com> **Wed, Oct 19, 2011 at 5:25 PM**
To: Jens Deichmann <jdeichmann@themacresourcesgroup.com>

11-03-2011

Meeting between NMED, NMCC & MMD to discuss progress of NMED technical review of the Copper Flat Mine Plan of Operations

November 3, 2011

Draft Comments on the Cu+ Flat Mine Plan of Operations, June, 2011.

43 CFR 3809

1. Page 3-3 and 5-8 state that post closure monitoring will be conducted for 5 years. MMD requires 12 years of monitoring before FA may be released, and GWQB may require additional ground water monitoring.
2. Page 3-3: Waste Rock for pad preparation, plant site development & reclamation? K waste only. Analysis required. materials Handling Plan - ORE, mineralized W.R., W.R.
3. Page 3-6: liner may be required for any expansion of WRDF. Analysis required.
4. Page 3-7: spill contingency plan required.
5. Page 3-9: surge stockpile? Size? Location? Low grade pile blended?
6. Page 3-10:Concentrates loaded by front end loader? Dry stack? Handling plan required.
7. Page3-13: plans for new monitoring wells should be submitted for NMED approval. - APP adendum
8. Page 3-14: use process water for dust control? What are the WQ characteristics of the process water?
9. Page 3-19: Need to determine Borrow Areas.
10. Page 5-4 states that NMCC is currently preparing a Ground Water Discharge Permit. Actually, NMCC has submitted a Discharge Permit **application** and GWQB is currently conducting a technical review of that application in preparation for writing a Draft Discharge Permit.
11. Page 5-7: Wetland Alterations: approval from USACE?
12. Page 5-9: exceed 2.5:1 slope?
13. Page 5-18: include NMED
14. Page 5-25: joint FA between NMED & MMD?
15. Appendix D: NMCC acknowledges 2.5' of cover & 6" top dressing required. →
16. Appendix D: proposal to use old tailing material as dam construction material or liner bedding.
17. Appendix E: ERP for reagents? Pg 3-27
18. Need results of feasibility study for tailing design plan. Specific plans will be required for Draft DP preparation.
19. Results of WRP studies required for final WRP design & approval of build out.

P.L. Leak detection

Q4 2011

Q1 2012

Q3 2012

Q2 2013

MPO
MOU
CR
Inter-Agency Agreement
RFP
NOI
EIS

Initial Dam Construction and Operation Permit

Pre-Feasibility Study

Baseline Data Collection

BDR

Existing Data
Flow / Seepage Study
Artesian Well Study
Pit Lake Study
Conceptual Model

Pre-Feasibility Groundwater Model

Met Testing

2011 Drilling Program
Updated Geochemistry
Updated Block Model

Updated Reserve and Mine Plan

Detailed Tailings Facility Design

Feasibility Study Q1 - Q3 2012

Revision to Proposed Action?

Final Dam Construction Permit

Abatement Monitoring

Reinstatement of GW Discharge Permit

Stage 1 Abatement Plan Groundwater Discharge Permit

Cultural Resources Mitigation - Data Recovery

MMD Public Hearing and Comments

Revised Stage 1 Abatement Plan

Scoping Meetings (w/ 45 day comment period)

Golder Designs
MPO 3809
Pre-Feas 43101

PAP to MMD

BLM Review of Pre-Feas Results

Proposed Action

Pit Wall / Waste Rock

Geochemistry Static Test Results

Geologic Block Model

Dewatering Projections / Drawdown Impacts

Aquifer Test and Calibrations

Final Groundwater Model

Draft EIS

Air Quality Permit

BLM Public Hearing (w/ Comment Period)

EIS ROD

State
Federal
Both

02262

11-8-2011

Huey, Greg, NMENV

From: Haywood, Doug [dhaywood@blm.gov]
Sent: Tuesday, November 08, 2011 7:14 AM
To: Huey, Greg, NMENV
Subject: FW: Due date for the Copper flat mine proposal selection.

Interesting, your email just kicked back. Let me try it again.

Douglas

From: Haywood, Doug
Sent: Tuesday, November 08, 2011 7:08 AM
To: 'greg.huey@state.nm.us'; Montoya, Jennifer A
Subject: Due date for the Copper flat mine proposal selection.

Greg,

Sorry about the email. You have to love advances in technology! BLM needs your response by COB on Friday November 11, 2011. I will compile them on Monday and if we are all in agreement or with minor difference then BLM will select a contractor then, if there are some major concerns then I will schedule a conference call for Tuesday morning November 15, 2011. If you have any questions drop me a line.

Thanks,

Douglas Haywood
BLM Project Manager
575-525-4498

11-8-2011

02265

Huey, Greg, NMENV

From: Haywood, Doug [dhaywood@blm.gov]
Sent: Tuesday, November 08, 2011 6:53 AM
To: Eustice, Chris, EMNRD
Cc: Shepherd, Holland, EMNRD; Vollbrecht, Kurt, NMENV; Ennis, David, EMNRD; Huey, Greg, NMENV; Smith, Michael A; Montoya, Jennifer A
Subject: RE: Proposals for Copper Flat EIS and EE

Chris,

For the short term, would you please just provide me with your priority ranking in an email. If there are areas that you feel really strong about one way or the other also include a little note so that BLM makes sure that we take that into account when making the final decision. I will compile/compare everyone's list on Monday November 14, 2011 or earlier if I get all the results back sooner. If there is one company that makes it to the top of the list then we will just go with it. If there are major conflicting items then I will schedule a conference call for Tuesday morning November 15, 2011 to iron out any concerns. If you have any questions please drop me a line.

Thanks,

Douglas Haywood
BLM Project Manager
575-525-4498

From: Eustice, Chris, EMNRD [mailto:chris.eustice@state.nm.us]
Sent: Friday, November 04, 2011 4:06 PM
To: Haywood, Doug
Cc: Shepherd, Holland, EMNRD; Vollbrecht, Kurt, NMENV; Ennis, David, EMNRD; Huey, Greg, NMENV; Smith, Michael A
Subject: FW: Proposals for Copper Flat EIS and EE

Doug,

MMD and NMED have received the three proposals for the EIS and EE at Copper Flat. MMD's understanding is we are to get to you (BLM) our recommendation in seven (7) calendar days, next Friday (11/11/11) at close of business. How would you prefer receiving MMD's and NMED's recommendations? Would you like to discuss the proposals via conference call or other means, or were you expecting something more formal, in writing perhaps?

Please advise.

Chris Eustice
Sr. Environmental Engineer
MMD, Mining Act Reclamation Bureau
1220 South St. Francis Drive
Santa Fe, NM 87505
505.476.3438

11-15-2011

Find A Way! Newsletter

Copper Flat

NOVEMBER 15, 2011

VOLUME 1, ISSUE 1

Site Update

Fence Closing

Jens Deichmann and Ann Carpenter are working with the BLM Las Cruces Office, in order to close off public access to the North Gate. "It's a safety concern for the public," Deichmann said.

Exploration Program

The Copper Flat geology team has organized themselves around a 10 on 4 off schedule, so that the team is working at the same time. Their yeomen's efforts in October completed the backlog of core and RQD logging and sent the samples into Skyline, beating their original completion schedule by about a week. We celebrated with pie...for days!!!

Pre-Feasibility Assistance

The site team is currently focused on assisting Ed with his Pre-Feasibility and Feasibility requests, relogging historic core for breccia details, logging RQD from core photos for additional pit slope study work, and readying their work focus to pull samples for metallurgical, density and geochem test work.

SPECIAL COVERAGE

- Permitting Briefing
- Community Update
- Upcoming Events
- Restaurant Picks

LEFT, RIGHT, ABOVE: THE TUNNELS HAVE BEEN SECURED. IT WAS A VERY SUCCESSFUL PROCESS, YIELDING A GREAT DEAL OF INFORMATION ABOUT THE SHAPE OF THE INFRASTRUCTURE.

Pre-Feasibility Wrap-Up

Ed Fidler is driving a hard deadline on the Pre-Feasibility work. As part of that effort, an engineering crew representing M3 conducted a site vist at Copper Flat, with a focus on studying the newly exposed foundations and crushing-related infrastructure that Rich Hasler successfully exposed and readied for the visit. Rich's hard work with the excavation contractors was able to help Ed keep this site evaluation moving forward as scheduled.

After a 'grueling' day in the field, everyone relaxed at the site office and ate pie from Pie-o-neer Café, Pie Town, NM (approx. 80 miles west of Socorro on Hwy 60).

Engineering work is wrapping up and the compilation and writing efforts have begun on the Pre-Feasibility Report, due in December 2011.



Permitting

Production Well Video

Rogers and Co Downhole Video was contracted to record video of the production wells. This work was essential for the Pumping Test, and also will support right of ways, conditions for re-entry, and rehabilitation of the wells. Andrew Feltman oversaw the activities. "It went great," Andrew said. "We were able to see inside the wells, getting information on the condition they're in and original construction specs. Plus, it was two really nice days in the sunshine."

Pipeline Inspection

Katie Lee, with Livingston Associates, was able to expose the pipeline, taking a look at its integrity for feasibility purposes. According to Steve Raugust, the one-mile segment of pipeline on State land appears to be in great shape. "They'll take a little clean-up work , but they can be reused with some redevelopment work," Steve said.

Third-Party EIS Contractor

We anticipate selecting the 3rd Party EIS contractor by November 14th. "We are poised to negotiate a contract quickly thereafter," Jens Deichmann said. "The next step will be scheduling the Scoping Meetings in TorC and Hillsboro."

CLOCKWISE FROM TOP: ROGERS AND CO PREPARES TO RECORD; INTERNAL VIEW OF PIPELINE; KATIE LEE OVERSSES PIPELINE INSPECTION; EXPOSURE OF PIPELINE; ROGERS VIEWS THE LIVE FEED.

Culinary Corner

The Pie-o-neer Café in Pie Town, NM (approx. 80 miles west of Socorro) has the best pies in the west!!

A favorite dining spot in TorC is Maria's on the west side of town, about a mile east of the Williamsburg entrance to I-25.

The Albuquerque team recently tried Patricia's Café, on San Mateo and Candelaria. Everyone enjoyed the homestyle New Mexican cuisine.

Notice of Intent

The team is eagerly waiting to hear if the NOI has been transferred from the BLM Las Cruces Office to the BLM State Office, which was supposed to have occurred on November 4. Review by the State office is expected to be completed fairly quickly, followed by transmittal to the Washington DC BLM office.

Copper Flat Community

Site T-Shirts
Christine Sumner designed T-shirts for the Copper Flat Site Team. Each shirt has a Copper Flat Logo on the front, and the person's favorite number along with his / her most common statement along with "Property of Copper Flat" on the back. The site team challenges the Albuquerque office to create t-shirts as well. Let the games begin!

Veteran's Day Giving
Spearheaded by Jens Deichmann, the NMCC team is planning a clothing drive to donate to disabled / homeless Veterans' organizations.

Day of the Tread Outing
Steve Raugust, Jens Deichmann, and Zack Gorstein, participated in the *Day of the Tread* bike ride, to benefit Tingley Hospital. All three made it through the 100 mile ride, although Jens left the other two behind. "It was my first century," Zack said. "I couldn't have done it without the encouragement of my Copper Flat Family."

NMCC Stock Certificates
Steve Raugust received a phone call from a man named John Petushin, who had stock certificates for New Mexico Copper Corporation. After some research, we found that the stock was issued under an old NMCC, which was formed in 1936 and existed for 50 years, and is unrelated to the current NMCC. John generously volunteered to mail us the stock certificates for our use, as they were not redeemable anyway.

Crystal's Baby Photos
Crystal finally got around to sending Matthew's birth announcement (she's been focused on a lot of things this past summer-fall) with great photos of Matthew, including this one.

CLOCKWISE FROM TOP: STEVE DEALS WITH A TOUGH CASE OF HELMET-HAIR; A PHOTO OF ONE OF THE STOCK CERTIFICATES OF THE FORMER NMCC; FRONT AND BACK SHOTS OF THE GEO TEAM'S T-SHIRTS; CRYSTAL'S 4-MONTH OLD BABY MATTHEW; ZACK PREPARES AT THE STARTING LINE FOR A LONG RIDE.

Company Events

Christmas Holidays
We are tentatively planning on wrapping up site activities on December 15th, and returning January 5th. We still plan on having night watchmen at the site during this down time. We wish everyone a Happy Holiday season.

Dr. Chavez at Site
Dr. Bill Chavez will be at site November 18th for a mapping exercise with the Copper Flat Geo-Team and his graduate students. The exercise will target mapping from the north side of the pit and waste dumps to the north.

Conventions
Some of the NMCC team will be attending two regional mining conventions:

- SME conference in Tucson, February 19-22, 2012
- NWMA meeting in Reno, November 29—Dec 2, 2011

Regional Events

Spaceport Industry Day
Virgin Galactic hosted an Industry Day on 10/18 and set up a display table to meet with the 150 attendees, most of whom were potential contractors from all over the Country. Combining forces with the Mesilla Valley Economic Development Alliance (MVEDA), SCEDO was joined by Xacta Printing (the first local Virgin Galactic supplier), Tom Burris; Superintendent of Schools and D. Rush; CEO of Sierra Vista Hospital. Copper Flat is working with Virgin Galactic to create joint job training programs.

Old-Fashioned Christmas
MainStreet Truth or Consequences will hold its 4th annual Old-Fashioned Christmas Festival on December 9, 2011. Many businesses will be open for shopping and will provide hot food, hot drinks and sweet treats for the public. Live music will once again be a big part of the event this year, with bands performing at multiple venues throughout downtown.

Weekend of Lights Festival
On December 10, 2011, The Elephant Butte Chamber of Commerce will host the 17th annual Weekend of Lights Festival Luminaria Beach Walk and Floating Lights Parade, to benefit the Make A Wish Foundation. The event will feature thousands of twinkly Christmas lights and luminarias, campfires, an abundance of free delicious food and beverages, live music, hayrides, Santa and a stunning lighted boat parade. The event begins at 5 pm.

Happy Thanksgiving!



TorC Art Hop
TorC hosts an Art Hop on the second Saturday of each month, in which downtown art galleries, shops and restaurants will be open from 6 pm to 9 pm.

Third Thursday Speaker Series
On November 17, from 7 to 8 pm, the Geronimo Springs Museum will host The "Mexican Indians" Who Accompanied Onate: Old Friends and Allies or a Case of Mistaken Identity?

RIGHT: A LARGE AUDIENCE GATHERED FOR THE VIRGIN GALACTIC INDUSTRY DAY ON OCTOBER 18.

12-14-2011

Agency NMCC Meeting – 14 December 2011

1. General permitting Status
    a. NEPA: NOI, Scoping meetings
    b. ROWs
        i. Aquifer test: Gravel quarry, NPDES
        ii. GWQB NOI
        iii. Pipeline, production wells
    c. Baseline Data Report
        i. Clarification of Cultural Resource report content
        ii. Schedule for submittal of draft
2. Fishbone diagram – evolving form
3. Community update meetings 15 Dec. Hillsboro and 16 Dec. TorC
4. Reclamation planning guidance documents

12-16-2011

Huey, Greg, NMENV

From: Katie Lee [klee@themacresourcesgroup.com]
Sent: Friday, December 16, 2011 1:39 PM
To: Vollbrecht, Kurt, NMENV
Cc: Jens Deichmann; Denise Weston; Huey, Greg, NMENV; Steve Raugust
Subject: Re: Proposed discharge questions

Thank you Kurt!

kl

On 12/16/2011 11:41 AM, Vollbrecht, Kurt, NMENV wrote:
Hi Katie,

This looks good. I would follow up with EPA on any constituents they may want you to add to the analytical list. The list provided meets NMED needs. The only other comment I have, is that I have to clarify that "it is unlikely that NMED will require a discharge permit" for the activities we are discussing. I'm not the decider on such matters and we can't really say definitively prior to receipt and review of the NOI.

Let me know if you have questions.

Kurt Vollbrecht, Geologist
New Mexico Environment Department
Ground Water Quality Bureau
Mining Environmental Compliance Section
(505) 827-0195

From: Katie Lee [mailto:klee@themacresourcesgroup.com]
Sent: Friday, December 16, 2011 9:53 AM
To: Vollbrecht, Kurt, NMENV
Cc: Jens Deichmann; Denise Weston; Huey, Greg, NMENV; Steve Raugust
Subject: Re: Proposed discharge questions

Hi Kurt,

Thank you for following up on my questions about NMED requirements for our proposed discharges associated with sampling and eventually conducting an aquifer test at our production wells in Sierra County via email 12-13-11. I am just going to reiterate what we plan to do in a little more detail here and if I have any of this incorrect, please let us know.

As I understand it, NMED concurs with our plan to follow these steps:

1. Pump the production wells we plan to sample until selected field parameters (which may be temperature, specific conductance or DO) stabilize or until three casing volumes have been purged, whichever occurs first. Direct purged water into an onsite temporary above ground tank such as a frac tank.
2. Upon appropriate purging, collect a representative groundwater sample and submit it for appropriate laboratory analysis. We plan to analyze sampled water for the same list of constituents in our Sampling and Analysis Plan (September 2010) and may also analyze for constituents the EPA may request if we choose to pursue an NPDES permit for discharges from the pumping test. These analyses are presented in the attached excel document.
3. Per your request, once laboratory results are received, NMCC will prepare a Notice of Intent (NOI) to

discharge for NMED review, to be sent as a pdf to you and Greg Huey. NMCC will request permission for the proposed discharge of the purged water held in the tanks and the proposed discharge of water for the subsequent aquifer test in the NOI.
4. Upon NMED approval, NMCC will discharge the purged water according to the submitted NOI. We anticipate proposing to discharge purged water and water extracted during our pumping test at the same time to the gravel quarry four miles east of the production wells, although this plan could vary depending on laboratory results and logistics.

NMCC will obtain all necessary state and federal permits before completing these proposed actions. If the laboratory results from groundwater sampling indicate purged water is not suitable for discharge to the surface, NMCC will handle it in an appropriate manner.

We understand, based on the results of previous groundwater analyses from these wells, that NMED will not require a Discharge Permit for these proposed discharges. We further understand that we may not discharge these waters without first submitting a Notice of Intent to discharge to the NMED and receiving approval upon review of that NOI.

We are planning to purge and sample only the wells necessary to complete our proposed aquifer test. If we find no difficulties with Production Well 1 and Production Well 3, we will only purge and sample these 2 wells. Based on our proposed purging plan, this will generate approximately 20,000 gallons per well or less, for a total purged volume of 40,000 gallons or less.

Thank you again for your time and review. We look forward to working with you. Please let me know if I've misunderstood any of NMED's requirements or if you have any questions.

Best regards,

Katie Lee
Project Scientist
Copper Flat Mine
THEMAC Resources Group, Ltd.

Mobile: 505.400.7925
Office phone: 505.830.6919
www.themacresourcesgroup.com

This e-mail and any attachment may be confidential and privileged or otherwise protected from disclosure. It is solely intended for the person(s) named above. If you are not the intended recipient, any reading, use, disclosure, copying or distribution of all or parts of this e-mail or associated attachments is strictly prohibited. If you are not an intended recipient, please notify the sender immediately by replying to this message or by telephone and delete this e-mail and any attachments permanently from your system.

On 12/13/2011 11:37 AM, Vollbrecht, Kurt, NMENV wrote:
HI Katie,

I'll summarize our discussion from yesterday regarding an acceptable pathway for NMCC to follow with regards to a proposal to discharge both purge water and pump test water to the gravel quarry you mention below.

NMCC intends to purge the production wells and containerize the water in frac tanks while samples are submitted for analysis. Following receipt of analytical data, NMCC will prepare and submit a Notice of Intent to Discharge to NMED for both the purge water and the pump test water. The NOI should include the production well analytical data, a description of the materials present in the gravel pit (geologic formations including mineralogy) and a discussion regarding the volume of the combined discharge and the capacity and infiltration capabilities of the quarry as well as other information required under a NOI (form attached).

Assuming the quarry material is inert and the water quality in the production wells meets standards NMED would likely not require a permit for the proposed discharge. Following the NMED response to the NOI, NMCC could proceed with discharge assuming all other agency requirements have been met (and assuming the information in the NOI shows that there would be no potential impact to water quality...).

I'd recommend sending a PDF of the completed NOI to myself and Greg once it is prepared so we can expedite the process.

Let me know if I've summarized our discussion correctly or if you have other questions (or if the plan has changed).

Kurt Vollbrecht, Geologist
New Mexico Environment Department
Ground Water Quality Bureau
Mining Environmental Compliance Section
(505) 827-0195

From: Katie Lee [mailto:klee@themacresourcesgroup.com]
Sent: Friday, December 09, 2011 2:21 PM
To: Vollbrecht, Kurt, NMENV
Cc: Jens Deichmann; Denise Weston
Subject: Proposed discharge questions

Hi Kurt,

Glad to speak with you on the phone this morning. As we discussed, New Mexico Copper continues to work with the BLM regarding our right of way applications and supporting documentation for our proposed aquifer test. We have identified a gravel quarry on state land about 4 miles east of our production wells where water from purging or pumping the production wells could be discharged for infiltration without causing it to pool, run off or enter any waterways. We have received the appropriate right of way grant from the state land office to use this quarry in this way.

We understand from our communications with you that a NOI would be sufficient to allow NMED to evaluate and hopefully permit our proposed discharge of up to 150 acre feet of water over the course of a 14 day aquifer test.

Our question is this: if we are granted a right of way by the BLM that would allow us to purge and collect ground water samples from the four production wells several weeks or a few months in advance of the proposed aquifer test, would NMED require a NOI for that discharge? We estimate we'd be purging about 20,000 gallons (approximately 3 casing volumes) from each of the production wells for a total of about 80,000 gallons. We would propose to truck this water to the same gravel quarry for infiltration there.

If you have any questions about what I've tried to explain here, please let me know.

--
Katie Lee
Project Scientist
Copper Flat Mine
THEMAC Resources Group, Ltd.

Mobile: 505.400.7925
Office phone: 505.830.6919
www.themacresourcesgroup.com

1. **Name and mailing address of person proposing to discharge:**

_____ **Work Phone:** _____

_____ **Cell/Home Phone:** _____

_____ **Fax:** _____

_____ **Email:** _____

2. **Name of facility:**

_____

3. **Physical location of discharge (if applicable, give street address, township, range, section, distance from closest town or landmark, directions to facility, location map):**

_____

_____

_____

4. **Type of operation generating the discharge (e.g., truck wash, food processing plant, restaurant, etc.):**

_____

5. **Source(s) of the discharge. Describe how the wastewater, sludge, or other discharges processed and/or disposed at your facility are generated. Identify all sources. Attach additional pages if needed:**

_____

_____

_____

6. **Expected contaminants in the discharge (e.g., nitrate-nitrogen, metals, organic compounds, salts, etc.) Include estimated concentration if known, and copies of results of laboratory analyses, if available:**

_____

7. **Describe all components of wastewater processing, treatment, storage, and disposal system (e.g., grease interceptor, lagoon, septic tank/leachfield, etc.) Include sizes, site layout map, plans and specifications, etc. if available:**

_____

_____

_____

8. **Estimated maximum daily discharge volume in gallons per day (or other units):**

_____

9. **Estimated depth to ground water (ft):** _____

Signature: _____ **Title:** _____

Printed name: _____ **Date:** _____

Please return this form to:

NMED Ground Water Quality Bureau
P.O. Box 5469
Santa Fe, New Mexico 87502-5469

Telephone: 505-827-2900
Fax: 505-827-2965

1-10-2012

Huey, Greg, NMENV

From: Jens Deichmann [jdeichmann@themacresourcesgroup.com]
Sent: Tuesday, January 10, 2012 3:53 PM
To: Eustice, Chris, EMNRD; Shepherd, Holland, EMNRD; Huey, Greg, NMENV; Vollbrecht, Kurt, NMENV; Jankowitz, Rachel J., DGF; Myers, Kevin, OSE; Perez, Norma, NMENV; Mendoza, Andrea J., OSE
Subject: Publication of the BLM NOI
Attachments: Copper Flat Federal Register NOI 1-9-12.pdf

I just wanted to let you all know that the Notice of Intent to conduct and EIS on Copper Flat was published yesterday in the Federal Register (see attached).
We are preparing our plans for the mine tour next Tuesday in coordination with Doug Haywood. If you have anything in particular you would like to see or learn about, please let Doug and me know.
Thanks, Jens

Jens Deichmann
Permitting Manager - Regulatory
Copper Flat Mine
THEMAC Resources Group, LTD.
2425 San Pedro NE
Albuquerque, NM 87110
Office: 505.830.6920
Mobile: 505.681.2536
Fax: 505.881.4616
www.themacresourcesgroup.com
This e-mail and any attachment may be confidential and privileged or otherwise protected from disclosure. It is solely intended for the person(s) named above. If you are not the intended recipient, any reading, use, disclosure, copying or distribution of all or parts of this e-mail or associated attachments is strictly prohibited. If you are not an intended recipient, please notify the sender immediately by replying to this message or by telephone and delete this e-mail and any attachments permanently from your system.

participate in the scoping process and, if eligible, may request or be requested by the BLM to participate as a cooperating agency. The BLM will also brief county commissioners, Congressional delegations and grazing permittees during the EIS process.

You may submit comments on issues and planning criteria in writing to the BLM using one of the methods listed in the **ADDRESSES** section above. To be most helpful, please submit comments by the close of the 30-day scoping period or within 15 days after the last public meeting, whichever is later. Before including your address, phone number, email address, or other personal identifying information in your comment, you should be aware that your entire comment—including your personal identifying information—may be made publicly available at any time. While you can ask in your comment to withhold your personal identifying information from public review, we cannot guarantee that we will be able to do so.

The public is also encouraged to help identify any other management questions and concerns that should be addressed in the EIS.

The BLM will use an interdisciplinary approach to develop the EIS in order to consider the variety of resource issues and concerns identified. Specialists with expertise in the following disciplines will be involved in the NEPA process: Range management, wildlife biology, archaeology, riparian, soils, and outdoor recreation.

Authority: 40 CFR 1501.7, 43 CFR 1610.2.

Loretta Chandler,

Field Manager, BLM Owyhee Field Office.

[FR Doc. 2012–125 Filed 1–6–12; 8:45 am]

BILLING CODE 4310–GG–P

DEPARTMENT OF THE INTERIOR

Bureau of Land Management

[LLNML00000 L51100000.GN0000.LVEMG11CG230]

Notice of Intent To Prepare an Environmental Impact Statement for the Proposed Copper Flat Mine Plan of Operations, Sierra County, NM

AGENCY: Bureau of Land Management, Interior.

ACTION: Notice of Intent.

SUMMARY: In compliance with the National Environmental Policy Act (NEPA) of 1969, as amended, and the Federal Land Policy and Management Act of 1976, as amended, the Bureau of Land Management (BLM) Las Cruces District Office, Las Cruces, New Mexico, intends to prepare an Environmental Impact Statement (EIS) and by this notice is announcing the beginning of the scoping process to solicit public comments and identify issues.

DATES: This notice initiates the public scoping process for the EIS. Comments on issues may be submitted in writing until February 8, 2012. The date(s) and location(s) of any scoping meetings will be announced at least 15 days in advance through local media, newspapers and the BLM Web site at: *http://www.blm.gov/nm/st/en/fo/Las_Cruces_District_Office.html.* To be included in the Draft EIS, all comments must be received prior to the close of the scoping period or 15 days after the last public meeting, whichever is later. We will provide additional opportunities for public participation upon publication of the Draft EIS.

ADDRESSES: You may submit comments related to the Copper Flat EIS Project by any of the following methods:

- *Email: dhaywood@blm.gov.*
- *Fax:* (575) 525–4412.
- *Mail:* BLM Las Cruces District Office, 1800 Marquess Street, Las Cruces, NM 88005.

Documents pertinent to this proposal may be examined at the Las Cruces District Office.

FOR FURTHER INFORMATION CONTACT: Michael Smith, Geologist; telephone (575) 525–4421; address 1800 Marquess Street, Las Cruces, NM 88005 or by email *michaelsmith@blm.gov* and to have your name added to the mailing list. Persons who use a telecommunications device for the deaf (TDD) may call the Federal Information Relay Service (FIRS) at 1–(800) 877–8339 to contact the above individual during normal business hours. The FIRS is available 24 hours a day, 7 days a week, to leave a message or question with the above individual. You will receive a reply during normal business hours.

SUPPLEMENTARY INFORMATION: The BLM Las Cruces District Office has received a Mine Plan of Operations (Mine Plan) from the New Mexico Copper Corp. to re-start the Copper Flat Mine located in Sierra County, New Mexico. The proposed mine is located approximately 4 miles north-northeast of the town of Hillsboro, New Mexico. Lands involved in the mine include parts of the following sections:

New Mexico Principal Meridian

T. 15 S., R. 6 W.,
Sec. 31.
T. 15 S., R. 7 W.,
Secs. 25, 26, 35 and 36.

Mining, ore processing, and related activities would occur on both private land and public domain administered by the BLM. The proponent currently holds active mining claims over public domain land included in the proposed operation. The estimated project duration is 27 years from site construction to mine reclamation and closure. Mining at the existing open pit would be completed using standard multiple-bench methods. The pit would eventually widen to approximately 2,500 by 2,500 feet and deepen to 900 feet. Ore from the pit would be drilled, blasted, loaded and hauled to a planned processing facility immediately east of the pit. At this facility, the ore would be crushed and ground and copper and molybdenum minerals would be separated and concentrated using standard flotation techniques. Mineral concentrates would be transported by truck and rail to be processed offsite; onsite smelting or refining is not included in this proposal. Waste rock created during operations would be banked primarily on public domain land, and tailings would be disposed of into an expanded, existing tailings impoundment. Water for the proposed operation would be obtained from a well field located on BLM-administered land approximately 8 miles east of the mine in:

New Mexico Principal Meridian

T. 15 S., R. 5 W.,
Secs. 30 and 31.

Water would be piped to the proposed operation through an existing pipeline which roughly parallels the existing highway (New Mexico State Route 152). The total estimated disturbance on public domain land would be 745 acres. Reclamation would consist of removing processing equipment from Federal land, and restoring and seeding waste rock dumps and other disturbed areas. The BLM and the New Mexico Department of Energy, Minerals and Natural Resources would bond the proponent for site reclamation prior to granting authorization.

The purpose of the public scoping process is to determine relevant issues that will influence the scope of the environmental analysis, including alternatives, and guide the process for developing the EIS. At present, the BLM has identified the following preliminary issues:

1. Water use and effects on surface and subsurface hydrology;
2. Water quality effects and water quality protection;
3. Traffic;
4. Cultural Resources and Native American Religious Concerns;

5. Threatened, Endangered and Special Status Species;

6. Livestock grazing; and

7. Reclamation and post-mining land use.

The BLM will utilize and coordinate the NEPA commenting process to satisfy the public involvement process for Section 106 of the National Historic Preservation Act (NHPA) (16 U.S.C. 470f) as provided for in 36 CFR 800.2(d)(3). Native American tribal consultations will be conducted in accordance with policy, and tribal concerns will be given due consideration, including impacts on Indian trust assets. Federal, State, and local agencies, along with other stakeholders that may be interested or affected by the BLM's decision on this project are invited to participate in the scoping process and, if eligible, may request or be requested by the BLM to participate as a cooperating agency.

Before including your address, phone number, email address, or other personal identifying information in your comment, you should be aware that your entire comment—including your personal identifying information—may be made publicly available at any time. While you can ask us in your comment to withhold your personal identifying information from public review, we cannot guarantee that we will be able to do so.

Authority: 40 CFR 1501.7.

Jesse Juen,

Associate State Director.

[FR Doc. 2012–128 Filed 1–6–12; 8:45 am]

BILLING CODE 4310–VC–P

DEPARTMENT OF THE INTERIOR

Bureau of Land Management

[LLNVS00560.L58530000.ES0000.241A; N–84625; 12–08807; MO# 4500025699; TAS: 14X5232]

Notice of Realty Action: Classification for Lease and/or Subsequent Conveyance for Recreation and Public Purposes of Public Land in Clark County, NV

AGENCY: Bureau of Land Management, Interior.

ACTION: Notice of Realty Action.

SUMMARY: In accordance with Section 7 of the Taylor Grazing Act and Executive Order Number 6910, the Bureau of Land Management (BLM) has examined and found suitable for classification for lease and/or subsequent conveyance under the provisions of the Recreation and Public Purposes (R&PP) Act, as amended, approximately 7.5 acres of public land in the City of Las Vegas, Clark County, Nevada. The State of Nevada proposes to use the land for a State office building.

DATES: Interested parties may submit written comments regarding the proposed classification of the land for lease and/or subsequent conveyance of the land, and the environmental assessment (EA), until February 23, 2012.

ADDRESSES: Send written comments to the BLM Las Vegas Field Manager, 4701 N. Torrey Pines Drive, Las Vegas, Nevada 89130, or email: *DDickey@blm.gov.*

FOR FURTHER INFORMATION CONTACT: Dorothy Jean Dickey, (702) 515–5119, or *DDickey@blm.gov.* Persons who use a telecommunications device for the deaf (TDD) may call the Federal Information Relay Service (FIRS) at 1 (800) 877–8339 to contact the above individual during normal business hours. The FIRS is available 24 hours a day, 7 days a week, to leave a message or question with the above individual. You will receive a reply during normal business hours.

SUPPLEMENTARY INFORMATION: The State of Nevada has filed an application to develop the following described land as a State office building with related facilities near Flamingo Road and El Capitan Way in Las Vegas:

Mount Diablo Meridian

T. 21 S., R. 60 E.,
Sec. 17, E½SW¼SW¼SE¼, and SW¼SW¼SW¼SE¼.

The area described contains 7.5 acres, more or less, in Clark County.

The State office building will consist of approximately 60,000 square feet of office and support space. Related facilities include a parking lot, landscaping, lighting, utilities, and ancillary equipment. Additional detailed information pertaining to this application, plan of development, and site plan is in case file N–84625, which is located in the BLM Las Vegas Field Office at the above address.

The land is not required for any Federal purpose. The lease and/or subsequent conveyance are consistent with the BLM Las Vegas Resource Management Plan dated October 5, 1998, and would be in the public interest. The State of Nevada, a qualified applicant under the R&PP Act, has not applied for more than the 640-acre limitation for public purpose uses in a year, and has submitted a statement in compliance with the regulations at 43 CFR 2741.4(b).

The lease and/or subsequent conveyance of the public land shall be subject to valid existing rights. Subject to limitations prescribed by law and regulations, prior to patent issuance, a holder of any Right-of-Way within the lease area may be given the opportunity to amend the Right-of-Way for conversion to a new term, including perpetuity, if applicable.

The lease and/or subsequent conveyance, when issued, will be subject to the provisions of the R&PP Act and applicable regulations of the Secretary of the Interior, and will contain the following terms, conditions, and reservations to the United States:

1. A Right-of-Way thereon for ditches or canals constructed by the authority of the United States, Act of August 30, 1890 (43 U.S.C. 945);

2. All minerals shall be reserved to the United States, together with the right to prospect for, mine, and remove such deposits from the same under applicable law and such regulations as the Secretary of the Interior may prescribe;

3. Valid existing rights;

4. Right-of-Way N–59691 for paved road and drainage, spandrels, bus turnouts, curb, gutter, sidewalks, streetlights, pipe conduit, and concrete lining, granted to Clark County, its successors or assigns, pursuant to the Act of October 21, 1976 (43 U.S.C. 1761);

5. Right-of-Way N–60971 for a 16-inch, underground natural gas pipeline and construction staging area, granted to Southwest Gas Corporation, its successors or assigns, pursuant to the Act of February 25, 1920, as amended (30 U.S.C. 185 sec. 28);

6. Right-of-Way N–74286 for two transformers, and underground electrical lines with related appurtenances, granted to Nevada Power Company, its successors or assigns, pursuant to the Act of October 21, 1976 (43 U.S.C. 1761); and

7. Right-of-Way N–88267 for multiple natural gas pipelines with below and above ground appurtenances granted to Southwest Gas Corporation, its successors or assigns, pursuant to the Act of February 25, 1920, as amended (30 U.S.C. 185 sec. 28);

8. An appropriate indemnification clause protecting the United States from claims arising out of the lessee's/patentee's use, occupancy, or occupations on the leased/patented lands.

Upon publication of this notice in the **Federal Register**, the land described above will be segregated from all other forms of appropriation under the public land laws, including the general mining laws, except for lease and/or subsequent conveyance under the R&PP Act, leasing

1-17-2012

Huey, Greg, NMENV

From: maxyeh@windstream.net
Sent: Tuesday, January 17, 2012 6:07 PM
To: Huey, Greg, NMENV

Greg, now that the EIS process is getting under way, I assume the NMCC has decided on their methods. Did they go with dry tailings, or are they sticking with the old tailings pond and dam? I'm also curious what your department thinks about the mine pit being listed as a well. You can't very well hold them to kinds of protections wells necessitate to prevent ground water pollution, but then it's hardly normal to have trucks and equipment driving around inside a well. Apparently Quintana did it so they could appropriate water from the pit without going through a dewatering permit.
Max

1-17-2012

Agenda
COPPER FLAT MINE NEPA
Site Visit

January 17, 2012 at the Copper Flat Mine 11:00 AM to 4 PM
Directions are attached.

Kickoff Meeting

January 18, 2011 – 8:00 AM to 12:00
Organ Mountain Conference Room
BLM Las Cruces District, 1800 Marquess Street, Las Cruces, NM

Purpose of Meeting: Begin the process for conducting an environmental analysis and documentation for the Copper Flat Mine Plan of Operation in the Las Cruces District.

Welcome/Introductions: Doug Haywood, BLM Project Manager

1. BLM
2. Mangi Environmental
3. NMCC
4. Cooperating Agencies

Roles, Responsibilities, and Communications:

1. MOU, New Mexico Copper Corporation, Bureau of Land Management, Cooperating Agencies (MMD, NMED, OSE, NMDGF)
2. Review Team Members & Time Requirements

<u>BLM Actions/Concerns:</u>
Federal Register Notice of Intent (BLM): Douglas Haywood

Purpose & Need Statement (BLM): Jennifer Montoya

NEPA Analysis Discussion: Does BLM have any requirements, guidance documents? Jennifer Montoya

EIS & Data Report Formats: Jennifer Montoya

Public Participation Plan (BLM/Mangi): Douglas Haywood

1) Scoping letter
2) Public contact list by Mangi
3) Public Meetings
4) Comment Database by Mangi
5) Public/internal websites by Mangi/BLM

Mining Plan of Operations Status: Michael Smith

NEPA Analysis/Alternatives: Jennifer Montoya

1) No Action Alternative: 40 CFR part 1502.14 (d) requires that the alternative of no action be included in an Environmental Impact Statement. Due to the mining claimants' rights under the US mining laws, choosing the No Action Alternative is outside the authority of the authorized officer if it is a reasonable and legally compliant plan of operations.
2) Plan of Operations Proposed Action
3) Discussion of other alternatives to be considered or dismissed

NMCC Actions/Concerns:
Detailed Project Description to be provided: Jens Deichmann

Project Data Reports/Status of Availability: Jens Deichmann

Known Issues: Jens Deichmann
1) Ground and surface water use and possible contamination.

Potential Issues: Jens Deichmann
1) Air Quality degradation from emissions
2) Traffic control
3) Road construction standards
4) Ore transport 1) on BLM Roads 2) State Highways

Specific Discussion topics/questions: David Henney
1) Items to be provided by Mangi
    A) EIS Preparation Plan
    B) Action Plan
    C) Consultation support to BLM
    D) Scoping Meeting support to BLM
    E) Agency meeting support to BLM
    F) Public information support to BLM
    G) Planning Record File Scheme & Responsibility
2) Schedule

BLM Deciding Official Requirements: (What do we need for the final document package?)

Information Exchange: Mangi/BLM/NMCC/All

Information Mangi Requests from BLM:
- Any BLM style guide and style sheet for the EIS
- Applicable statutes, regulations, Executive Orders, BLM manuals, and handbook that will control or guide the preparation of the analysis
- Relevant GIS information applicable to the project area
- Significant project issues
- Contact list
- Visual aid examples expected for the scoping meetings
- Mailer/newsletter example
- News release example
- Project address/mailing list

- Recommended agency contact names to obtain relevant baseline information
- Applicable background information for the project site
- Applicable background information for the cumulative effects analysis

Information Mangi requests from NMCC

- Data Reports
- Electronic File versions of Plan of Operation
- Known references/studies/citations
- Consultation conducted to date
- Access issues to site

Monthly COOP Meeting

January 18, 2011 – 1:00 pM to 3:00

Organ Mountain Conference Room

BLM Las Cruces District, 1800 Marquess Street, Las Cruces, NM

1-18-2012

BUREAU OF LAND MANAGEMENT
MEETING/EVENT

Copper Flat Kick Off

DATE 1 / 18 / 2012 START TIME 8 00 am/pm FINISH TIME _____ am/pm

NAME	ORGANIZATION / Title	PHONE	E-MAIL
Jennifer Montoya	BLM-NEPA Coordinator	575-525-4316	jamontoya@blm.gov
Douglas Haywood	BLM - Project Manager	575-525-4498	dhaywood@blm.gov
Jens Deichmann	NMCC	505-684-2536	jdeichmann@thenmcresources.gov
Bernard Pleau	Public Participation SME	505-250-5872	bpleau@Q.com
Dave Hennney	Mangi Env. / PM	402-305-1279	dhennney2@cox.net
Mark Nelson	CDMSmith - Mangi Team	605-578 9739	nelsonmr@cdmsmith.com
Lee Wilson	- - Mangi	505 988-9811	lwa@lwasfi.com
Joseph Navarro	LCDO - BLM	525-525-4300	joe_navarro@nm.blm.gov
Michael Smith	LCDO BLM	575-525-4421	michael.smith@blm.gov
EDWARD SEUM	BLM, LCDO	575 525 4313	ESEUM@NM.BLM.GOV
Joe Sanchez	BLM - LCDO	575-525-4391	Joe_Sanchez@nm.blm.gov
Kevin Myers	NMOSE-Hydrology	505-827-3521	Kevin.myers@state.nm.us
Kurt Vollbrecht	NMED - GWQB	505-827-0195	Kurt.Vollbrecht@State.nm.us
DJ Ennis	NM - Mining & Minerals	505-476-3434	david.ennis@state.nm.us
Cheryl S. Thacker	NMOSE - Water rights	575-524-6161 x1019	cheryl.thacker@state.nm.us
Norma Perez	NMENV - AQB	505-476-5564	norma.perez@state.nm.us
PAT MATHIS	NM Game & Fish	575-532-2100	patrick.mathis@state.nm.us

1-31-2012

PDF

Huey, Greg, NMENV

From: Zack Gorstein [zgorstein@themacresourcesgroup.com]
Sent: Tuesday, January 31, 2012 5:53 PM
To: Zack Gorstein
Subject: THEMAC Announces a 56% Increase in Recently Updated Measured & Indicated Resource Estimate
Attachments: 20120131 Resource Update MAC.pdf

Please find attached a news release regarding the Copper Flat Mine. If you are interested in gaining any further information for this release please contact Zack Gorstein at 505-234-6285.

Thank you.

Kind regards,

--
Zack Gorstein
Project / Sustainability Analyst
Copper Flat Mine
THEMAC Resources Group, Ltd
2425 San Pedro Dr. NE, Suite 100
Albuquerque, NM 87110

Office: 505-883-2510
Mobile: 843-412-8021
Fax: 505-881-4616
www.themacresourcesgroup.com

This e-mail and any attachment may be confidential and privileged or otherwise protected from disclosure. It is solely intended for the person(s) named above. If you are not the intended recipient, any reading, use, disclosure, copying or distribution of all or parts of this e-mail or associated attachments is strictly prohibited. If you are not an intended recipient, please notify the sender immediately by replying to this message or by telephone and delete this e-mail and any attachments permanently from your system.

THEMAC RESOURCES GROUP LIMITED

Suite 2000 - 1066 West Hastings Street
Vancouver, BC - Canada V6E 3X2
T (+1) 604 806-6110 F (+1) 604 806-6112
TSXV: MAC

THEMAC Resources Group Limited Announces a 56% increase in Recently Updated Measured & Indicated Resource Estimate

Vancouver, British Colombia – January 31, 2012 – THEMAC Resources Group Ltd. (TSXV:MAC) ("THEMAC" or the "Company") today announced the completion of an updated National Instrument 43-101 (NI43-101) resource estimate of its 100% owned Copper Flat project located in Sierra County, New Mexico, prepared by M3 Engineering & Technology Corporation (M3) and Independent Mining Company (IMC), both located in Tucson, Arizona.

The recently completed resource estimate reflects the results of a previously announced drilling completed in 2010 and 2011; the re-assay of 2,969 historical pulps to obtain gold and silver values and continued geotechnical and engineering design studies.

Highlights

- The total Measured and Indicated Resource increased by 56% to 1,005,891,000 pounds of contained copper from the previously reported 645,000,000 pounds of contained copper.
- The total Resource (indicated and inferred) of 153,000 Ktons, of which 107,000 was indicated, that was reported in the 2010 Preliminary Economic Analysis (PEA) has been increased to 202,303 Ktons of which 194,097 Ktons is now measured and indicated resources.
- Only 8,206 Ktons remain classified as Inferred Resources.
- The re-analysis of 2,969 pulps of historical drill samples has permitted IMC to factor both gold and silver values into approximately half of the current resource model. As a result, additional re-assaying of historical pulps is planned with the intent to increase contained gold and silver.

The resource estimate summarized in the table below was prepared under the supervision of John M. Marek, P.Eng., President of Independent Mining Consultants of Tucson, Arizona who is an Independent Qualified Person as defined under NI 43-101, and reviewed by Raymond Irwin, P. Geo. , a Qualified Person for the Company. The subject resource classifications were assigned in conformance with NI 43-101 and its standards and guidelines.

"I am extremely pleased with the progress that is being made on the evaluation of the Copper Flat deposit and the results of the recently completed resource update. The continuing enhancement of the resource from the recent drilling is extremely positive for the economic viability of the copper flat project; and, the recent recovery in the commodity prices may also be expected to add substantially to the value of the resource" said Andre J. Douchane, CEO. "Having a copper resource that now contains a billion pounds puts the Copper Flat Project in a much different league than when it only had 645 million pounds of copper scheduled to be processed. Equally as exciting, we've added 430,000 ounces of gold and 9 million ounces of silver to the resource."

Assumptions

- The mineral resource is based on the application of the floating cone algorithm to the block model to establish the component of the deposit that has "reasonable prospects of economic extraction." The mineral resources are therefore contained within a computer-generated open pit geometry.
- Slightly different metal prices were used in the November 2011 resource estimate as compared to the June 30, 2010 study, comprising part of the PEA undertaken by SRK Consulting Inc.
- The cutoff grade reflects the estimated cost to process the ore plus site general and administrative expenses which total $7.25/ton.
- Ktons is equivalent to 1,000 short tons, and a short ton is equivalent to 2,000 lbs.
- Copper and molybdenum grades are dry weight.
- Gold and silver values are reported in Troy ounce/short ton.
- Gold and silver values were not available at the time of this study in the outer edges of the deposit so the inferred grades for gold and silver are respectively shown as zero or near zero.

January 2012 Updated NI 43-101 Resource:

Classification	Tonnage and Grade				
	Ktons	Cu %	Mo %	Au Oz/t	Ag Oz/t
Measured	41,236	0.33	0.011	0.003	0.07
Indicated	152,861	0.24	0.007	0.002	0.04
Measured + Indicated	194,097	0.26	0.008	0.002	0.05
Inferred	8,206	0.23	0.004	0	0.01

"Along with moving forward with engineering, definitive metallurgical test work and final mill design, we are also finalizing a spring drill program to bring the comparatively higher grade core that was described in earlier work up to NI 43-101 standards," said Ray Irwin, VP Exploration. "As the orebody is still open, the spring drilling program is viewed with optimistic anticipation."

Location and Project History

The Copper Flat project hosts a Laramide porphyry copper-molybdenum deposit containing recoverable gold and silver credits located in the Las Animas Mining District of Sierra County, NM, approximately 150 miles (242 km) south of Albuquerque, NM and 20 miles (32 km) southwest of Truth or Consequences, NM.

The Copper Flat project consists of 26 wholly owned patented mining claims, 184 unpatented mining claims and 29 placer mining claims totaling 4,241.2 acres or 1,717 ha.

This advanced stage exploration/development project operated for a short period of time in 1982 (March –June 1982) by Quintana Minerals Corporation before operations were curtailed due to falling

copper prices. During this brief period of production, the Copper Flat mine produced 1.48 Mst of ore yielding 7.4 Mlbs. of copper, 2,301 ounces of gold and 55,966 ounces of silver.

About THEMAC Resources Group Limited

THEMAC is a copper development company with a strong management team and as of May 18, 2011, a 100% ownership interest in the Copper Flat copper-molybdenum-gold-silver project in New Mexico, USA. *We are committed to bringing the closed copper mine, Copper Flat, in Sierra County, New Mexico back into production with innovation and a sustainable approach to mining development and production, local economic opportunities and the best reclamation practices for our unique environment.* The Company is listed on the TSX Venture Exchange (ticker: MAC) and has issued share capital of 74,117,622 common shares (fully diluted share capital 136,423,241).

For more information please visit www.themacresourcesgroup.com or review the Company's filings on SEDAR (www.sedar.com).

Forward Looking Statements

This news release may contain certain information that constitutes forward-looking statements. Forward-looking statements are frequently characterized by words such as "plan," "expect," "project," "intend," "believe," "anticipate" and other similar words, or statements that certain events or conditions "may" or "will" occur, including statements regarding planned work on the Copper Flat Property. Forward-looking statements are based on the opinions and estimates of management at the date the statements are made, and are subject to a variety of risks and uncertainties and other factors that could cause actual events or results to differ materially from those projected in the forward-looking statements. These factors include the inherent risks involved in the exploration and development of mineral properties, the uncertainties involved in interpreting drilling results and other geological data, fluctuating metal prices, the availability of funds to complete work programs and studies, and other factors described above. The Company disclaims any obligation to update or revise any forward-looking statements if circumstances or management's estimates or opinions should change. The reader is cautioned not to place undue reliance on forward-looking statements.

For further information contact:

THEMAC Resources Group Limited
Andre J. Douchane, President & Chief Executive Officer
(+1) 416 671 8089 or (+1) 520 850 7529

Neither the TSX Venture Exchange (the "TSXV") nor its Regulation Services Provider (as that term is defined in the policies of the TSXV) has reviewed, nor do they accept responsibility for the adequacy or accuracy of, this release.

2-3-2012

United States Department of the Interior

BUREAU OF LAND MANAGEMENT
Las Cruces District Office
1800 Marquess Street
Las Cruces, New Mexico 88005
www.blm.gov/nm

TAKE PRIDE IN AMERICA

In Reply Refer To:
1793 (L0000)

GROUND WATER
FEB 20 2012
BUREAU

February 3, 2012

Dear Interested Party:

The Bureau of Land Management (BLM) Las Cruces District invites you to participate in the identification of issues to determine the scope for an Environmental Impact Statement (EIS) concerning the planned construction, operation, and mine reclamation of the Copper Flat Mine in Sierra County, New Mexico.

New Mexico Copper Corporation (NMCC) submitted a Mining Plan of Operations to the BLM for mining and processing copper and other minerals at the Copper Flat mine in central Sierra County. The proposed mine is located approximately 4 miles north-northeast of the town of Hillsboro, New Mexico. Mining, ore processing and related activities will occur on both private and BLM lands.

As the EIS process begins, the BLM's goal is to reach out and involve the public. The first opportunity for you to participate will be at the upcoming open houses for public scoping. The purpose of the public scoping process is to discover relevant issues that will influence the scope of the environmental analysis, including alternatives to the proposed action, and guide the process for developing the EIS.

Participants will have an opportunity to talk with resource and planning specialists, and are encouraged to provide comments on the scope of the EIS and on potential alternatives, to share issues and concerns, and to ask questions. BLM will consider these comments in determining the scope of the EIS, including alternatives to the proposed action.

The open house format also will allow the BLM, NMCC, and State agencies to provide information about the EIS process, the proposed action, as well as information regarding the development, operation, and mine reclamation for the Copper Flat mining claims. The public scoping open houses will be:

FEBRUARY 22, 2012 7-9 P.M.
HILLSBORO COMMUNITY CENTER
ELENORE ST.
HILLSBORO, NEW MEXICO

FEBRUARY 23, 2012 7-9 P.M.
TRUTH OR CONSEQUENCES CIVIC AND CONVENTION CENTER
400 WEST FOURTH
TRUTH OR CONSEQUENCES, NEW MEXICO

Your thoughts, ideas, and comments are important to us throughout the process. Please attend the scoping open houses or send us your written comments on the enclosed comment form before the scoping period ends, which is March 9, 2012.

You may also submit comments using any of the following methods:

EMAIL: BLM_NM_LCDO_Comments@blm.gov

FAX: 1(703) 760-4899

TOLL-FREE NUMBER: 1(866) 760-1421

MAIL:
Copper Flat Mine
C/O Mangi Environmental Group
7927 Jones Branch Drive
Mclean VA 22102

Also if you wish to be removed from the mailing list, please let us know by checking the box on the comment form. Otherwise your name will be retained on the list and you will receive information on the Copper Flat project in the future. Informational materials like this letter will be available on the Copper Flat website at www.cuflateis.com.

BLM will provide you an opportunity later in the process to review the Draft EIS, which is scheduled for release in January 2013. During the public review period, BLM will conduct public meetings to accept comments on the adequacy of the Draft EIS. Written comments will also be accepted during the review period.

If you have any questions, please contact Mike Smith at 575-525-4421.

Sincerely,

Bill Childress
District Manager

1 Enclosure

Copper Flat Mine
Environmental Impact Statement

BLM WANTS TO HEAR FROM YOU!
SCOPING COMMENT FORM

Please return this form by **MARCH 9, 2012**. Additional sheets may be attached if more space is needed. Fold the form so the address is showing and tape or staple the edges together to mail it. **POSTAGE is required.**

Name

Address

City State Zip

Organization (if applicable)

Add to Mailing List ☐ YES ☐ NO

PLEASE PRINT

PLEASE READ CAREFULLY

Before including your address, phone number, email address, or other personal identifying information in your comment, you should be aware that your entire comment – including your personal identifying information – may be made publicly available at any time. While you can ask us in your comment to withhold your personal identifying information from public review, we cannot guarantee that we will be able to do so. All submissions from organizations or businesses, and from individuals identifying themselves as representatives or officials of organizations or businesses, are available for public inspection in their entirety.

2-6-2012

Huey, Greg, NMENV

From: Erica Earhart [EEarhart@mangi.com]
Sent: Monday, February 06, 2012 6:44 PM
To: Dominguez, Dora, EDD; dhaywood@blm.gov; egarland@zianet.com; ELindsey@torcnm.org; erica.sichler@mail.house.gov; eshort_55@yahoo.com; Evelyn.Renfro@torcnm.org; Martinez, Fernando, EMNRD; Frances.Sanchez@torcnm.org; Freddie.Torres@torcnm.org; gerald.lafont@cityofelephantbutte.com; Huey, Greg, NMENV; gbneal@hotspringsld.com; bartoosandandgravel@windstream.net; Morales, Howie; ikeandmary@windstream.net; jpc@sierracountynm.gov; gerijay@valornet.com; jeanette_lyman@tomudall.senate.gov; jcox@sierracountynm.gov; phfss@torchousing.org
Subject: Copper Flat EIS Scoping
Attachments: SCOPING_LTR_CopperFlatEIS_FEB2012.pdf; scoping_commentform.pptx

Dear Interested Party,
This email retransmits the scoping letter for the Copper Flat EIS because a comment form was omitted from the previous mailing. Please read the attached scoping letter and use the attached comment sheet for all input.
Thank
you.

United States Department of the Interior

BUREAU OF LAND MANAGEMENT
Las Cruces District Office
1800 Marquess Street
Las Cruces, New Mexico 88005
www.blm.gov/nm

TAKE PRIDE IN AMERICA

In Reply Refer To:
1793 (L0000)

February 3, 2012

Dear Interested Party:

The Bureau of Land Management (BLM) Las Cruces District invites you to participate in the identification of issues to determine the scope for an Environmental Impact Statement (EIS) concerning the planned construction, operation, and mine reclamation of the Copper Flat Mine in Sierra County, New Mexico.

New Mexico Copper Corporation (NMCC) submitted a Mining Plan of Operations to the BLM for mining and processing copper and other minerals at the Copper Flat mine in central Sierra County. The proposed mine is located approximately 4 miles north-northeast of the town of Hillsboro, New Mexico. Mining, ore processing and related activities will occur on both private and BLM lands.

As the EIS process begins, the BLM's goal is to reach out and involve the public. The first opportunity for you to participate will be at the upcoming open houses for public scoping. The purpose of the public scoping process is to discover relevant issues that will influence the scope of the environmental analysis, including alternatives to the proposed action, and guide the process for developing the EIS.

Participants will have an opportunity to talk with resource and planning specialists, and are encouraged to provide comments on the scope of the EIS and on potential alternatives, to share issues and concerns, and to ask questions. BLM will consider these comments in determining the scope of the EIS, including alternatives to the proposed action.

The open house format also will allow the BLM, NMCC, and State agencies to provide information about the EIS process, the proposed action, as well as information regarding the development, operation, and mine reclamation for the Copper Flat mining claims. The public scoping open houses will be:

FEBRUARY 22, 2012 7-9 P.M.
HILLSBORO COMMUNITY CENTER
ELENORE ST.
HILLSBORO, NEW MEXICO

FEBRUARY 23, 2012 7-9 P.M.
TRUTH OR CONSEQUENCES CIVIC AND CONVENTION CENTER
400 WEST FOURTH
TRUTH OR CONSEQUENCES, NEW MEXICO

Your thoughts, ideas, and comments are important to us throughout the process. Please attend the scoping open houses or send us your written comments on the enclosed comment form before the scoping period ends, which is March 9, 2012.

You may also submit comments using any of the following methods:

EMAIL: BLM_NM_LCDO_Comments@blm.gov

FAX: 1(703) 760-4899

TOLL-FREE NUMBER: 1(866) 760-1421

MAIL:
Copper Flat Mine
C/O Mangi Environmental Group
7927 Jones Branch Drive
Mclean VA 22102

Also if you wish to be removed from the mailing list, please let us know by checking the box on the comment form. Otherwise your name will be retained on the list and you will receive information on the Copper Flat project in the future. Informational materials like this letter will be available on the Copper Flat website at www.cuflateis.com.

BLM will provide you an opportunity later in the process to review the Draft EIS, which is scheduled for release in January 2013. During the public review period, BLM will conduct public meetings to accept comments on the adequacy of the Draft EIS. Written comments will also be accepted during the review period.

If you have any questions, please contact Mike Smith at 575-525-4421.

Sincerely,

Bill Childress
District Manager

1 Enclosure

2-7-2012

NEW MEXICO
ENVIRONMENT DEPARTMENT

Ground Water Quality Bureau

SUSANA MARTINEZ
Governor

JOHN SANCHEZ
Lieutenant Governor

1190 St. Francis Drive, P.O. Box 5469
Santa Fe, New Mexico 87502-5469
Phone (505) 827-2900 Fax (505) 827-2965
www.nmenv.state.nm.us

CERTIFIED MAIL – RETURN RECEIPT REQUESTED

February 7, 2012

J. Steven Raugust, PG
New Mexico Copper Corporation
2425 San Pedro Drive NE, Suite 100
Albuquerque, NM 87110

RE: Amendment Approval: Site-Wide Stage 1 Abatement Plan Proposal for the Copper Flat Mine Facility

Dear Mr. Raugust:

The New Mexico Environment Department (NMED) has reviewed the "Amendment to the Stage 1 Abatement Plan Proposal for the Copper Flat Mine" (Proposal), dated October 14, 2011 for the Copper Flat Mine Facility. On January 27, 2012 a meeting was held between NMED and the New Mexico Copper Corporation (NMCC) to discuss the Proposal (Meeting). NMED hereby approves the additional work plan presented in the Proposal as described below.

The Proposal is based on the identified contaminants of concern at the site and the need for further characterization within three specific areas: the pit lake, waste rock piles, and tailings impoundment facility.

Four piezometer nests have been installed in the area surrounding the pit lake. The proposed investigation includes collection of four quarters of water quality and water level data from the pit lake and surrounding piezometer nests. A revised water balance for the area will be developed using these data in conjunction with on-site climate data. Additionally, an analysis of the pit lake chemistry will be conducted to determine if there are issues with meeting the applicable surface water quality standards at closure.

Materials tests are being performed on samples collected from the existing waste rock piles. The Proposal includes comparison of results from the waste rock characterization to water quality results obtained from surface water runoff samples, down gradient wells, and the pit area piezometer nests. Historical surface and ground water quality data will be statistically evaluated for significant increases in sulfate and TDS to determine if changes are attributable to the waste rock piles or other influences. NMCC is currently working to gain access to wells on U.S.

Bureau of Land Management (BLM) property. Once access is obtained, water quality samples from GWQ-1, GWQ-3, GWQ-5R, and GWQ-8 will be used to help make this evaluation.

The Proposal proposes to install one or two new monitoring wells down gradient of the known extent of the sulfate plume at the tailings impoundment facility. The first well would be installed east of existing well GWQ94-21. During the Meeting it was determined that this well shall be drilled using methods that provide for determination of the uppermost water table during drilling. This well shall be screened from five feet above the water table to thirty-five feet below the water table. If this first monitoring well does not define the eastward extent of the sulfate plume, a second well will be drilled east of the first proposed monitoring well.

Four additional quarters of data collection are proposed to complete the investigation; however, initiation of this effort is conditional on obtaining access to BLM property. Upon resolution of access issues, NMCC shall initiate collection of all necessary data.

If you have any questions, please contact Greg Huey at (505) 827-1046.

Sincerely,

Mary Ann Menetrey
Program Manager
Ground Water Quality Bureau

MAM:gmh

cc: Kurt Vollbrecht, GWQB MECS
Chris Eustice, EMNRD Mining and Minerals Division
James Bearzi, Bureau Chief, NMED SWQB

2-10-2012

Huey, Greg, NMENV

From: Zack Gorstein [zgorstein@themacresourcesgroup.com]
Sent: Friday, February 10, 2012 8:50 AM
To: Zack Gorstein
Cc: Ann Carpenter
Subject: THEMAC Resources Announces Plans for the 2012 Copper Flat Exploration and Drilling Program
Attachments: 20120209 2012 Drilling PR MAC.pdf

Please find attached a press release on THEMAC Resources' 2012 Exploration and Drilling program.

If you have any questions, please do not hesitate to contact me at zgorstein@themacresourcesgroup.com.

Kind regards,

--
Zack Gorstein
Project / Sustainability Analyst
Copper Flat Mine
THEMAC Resources Group, Ltd
2425 San Pedro Dr. NE, Suite 100
Albuquerque, NM 87110

Office: 505-883-2510
Mobile: 843-412-8021
Fax: 505-881-4616
www.themacresourcesgroup.com

This e-mail and any attachment may be confidential and privileged or otherwise protected from disclosure. It is solely intended for the person(s) named above. If you are not the intended recipient, any reading, use, disclosure, copying or distribution of all or parts of this e-mail or associated attachments is strictly prohibited. If you are not an intended recipient, please notify the sender immediately by replying to this message or by telephone and delete this e-mail and any attachments permanently from your system.

THEMAC RESOURCES GROUP LIMITED

Suite 2000 - 1066 West Hastings Street
Vancouver, BC - Canada V6E 3X2
T (+1) 604 806-6110 F (+1) 604 806-6112
TSXV: MAC

THEMAC Resources Announces Plans for the 2012 Copper Flat Exploration and Drilling Program

Vancouver, British Colombia – February 9, 2012 – THEMAC Resources Group Limited (TSXV:MAC) ("THEMAC" or the "Company") today announced details of its 2012 exploration and drilling program at the Copper Flat copper project, New Mexico.

As stated in the Company's update NI43-101 resource statement filed February 2, 2012 on SEDAR, the Copper Flat deposit currently contains a Measured and Indicated Resource totaling 194,097 Ktons averaging 0.26% copper, 0.008% molybdenum, 0.002 Oz/t gold and 0.05 Oz/t silver. Additionally, the deposit contains an Inferred Resource totaling 8,206 Ktons at a similar, but slightly lower average grade.

Proposed 2012 Exploration and Drilling Program

The 2012 Copper Flat drilling program will consist of up to 20 angled and vertical core holes totaling approximately 22,000 feet (6,700 meters), which is scheduled to commence during April. The proposed drilling program is designed to accomplish the following:

1) Increase the existing resources by extending known moderate to higher grade mineralization in all directions. The results of this extensional drilling will also be used to optimize the shape and orientation of the final pit design in the upcoming pre-feasibility study.
2) Upgrade additional Inferred Resources to the Indicated category.
3) Further evaluate and better define deeper (> 1,000 feet below the surface), higher grade (>0.50%) copper mineralization.
4) Further evaluate the structurally controlled gold and silver mineralization within and proximal to the Copper Flat deposit.

In addition to and in conjunction with the planned exploration and definition drilling, three to six steeply inclined core holes will be drilled to obtain additional geotechnical information, which will aid in the final pit design to be used in the upcoming feasibility study.

"The spring drilling program that is planned for Copper Flat will greatly improve our knowledge of what controls the precious metal deposition and to what extent the gold and silver occurs:" said Andre Douchane, CEO of THEMAC. "We accomplished a lot during 2011, starting from the filing of the draft plan of operations in 2010 to publishing the projects Notice of Intent in the US Federal Register this January which officially began the Environmental Impact Statement process; and, along the way we got the agency cooperating agreement in place and completed and funded the agreement to reimburse the BLM. The 2012 spring drilling program is just another key step toward final design and production."

Other work that may be undertaken during the 2012 exploration program includes the continued re-logging of historical core; and, in addition to the 2969 pulps re-assayed in 2011 it is planned to assay 4,000 more pulps from historical drilling to confirm copper and molybdenum grades as well as obtain needed gold and silver data in an effort to increase contained precious metals. Additionally, work will be directed toward updating the existing geologic map and undertaking geological reconnaissance and prospecting.

The advanced stage Copper Flat project is the site of a Laramide porphyry copper-molybdenum deposit containing recoverable gold and silver credits located in the Las Animas Mining District of Sierra County, NM, approximately 150 miles (242 kilometers) south of Albuquerque, NM and 20 miles (32 kilometers) southwest of Truth or Consequences, NM.

The Copper Flat project consists of 26 wholly-owned patented mining claims, 184 unpatented mining claims and 29 placer mining claims totaling 4,241 acres (1,717 hectares).

About THEMAC Resources Group Limited

THEMAC is a copper development company with a strong management team and as of May 18, 2011, a 100% ownership interest in the Copper Flat copper-molybdenum-gold-silver project in New Mexico, USA. *We are committed to bringing the closed copper mine, Copper Flat, in Sierra County, New Mexico back into production with innovation and a sustainable approach to mining development and production, local economic opportunities and the best reclamation practices for our unique environment.* The Company is listed on the TSX Venture Exchange (ticker: MAC) and has issued share capital of 74,117,622 common shares (fully diluted share capital 136,423,241).

For more information please visit www.themacresourcesgroup.com or review the Company's filings on SEDAR (www.sedar.com).

Forward-Looking Statements

This news release may contain certain information that constitutes forward-looking statements. Forward-looking statements are frequently characterized by words such as "plan," "expect," "project," "intend," "believe," "anticipate" and other similar words, or statements that certain events or conditions "may" or "will" occur, including statements regarding planned work on the Copper Flat Property. Forward-looking statements in this news release include statements regarding the nature, purpose, timing, amount and expected results of the Company's 2012 exploration and other work programs. Forward-looking statements are based on the assumptions, opinions and estimates of management at the date the statements are made. The assumptions made by the Company in preparing the forward looking statements in this news release, which may prove to be incorrect, include: that new drilling will identify new resources and upgrade or better define existing resources. The forward looking statements made in this press release are subject to a variety of risks and uncertainties and other factors that could cause actual events or results to differ materially from those projected in the forward-looking statements. These factors include the inherent risks involved in the exploration and development of mineral properties, the uncertainties involved in interpreting drilling results and other geological data, fluctuating metal prices, the availability of funds to complete work programs and studies, and other factors described above. The Company disclaims any obligation to update or revise any forward-looking statements if circumstances or management's estimates or opinions should change. The reader is cautioned not to place undue reliance on forward-looking statements.

For further information contact:

THEMAC Resources Group Limited
Andre J. Douchane, President & Chief Executive Officer
(+1) 416 671 8089 or (+1) 520 850 7529

Neither the TSX Venture Exchange (the "TSXV") nor its Regulation Services Provider (as that term is defined in the policies of the TSXV) has reviewed, nor do they accept responsibility for the adequacy or accuracy of this release.

2-12-2012

Huey, Greg, NMENV

From: Erica Earhart [EEarhart@mangi.com]
Sent: Friday, February 03, 2012 8:19 PM
To: Dominguez, Dora, EDD; dhaywood@blm.gov; egarland@zianet.com; ELindsey@torcnm.org; erica.sichler@mail.house.gov; eshort_55@yahoo.com; Evelyn.Renfro@torcnm.org; Martinez, Fernando, EMNRD; Frances.Sanchez@torcnm.org; Freddie.Torres@torcnm.org; gerald.lafont@cityofelephantbutte.com; Huey, Greg, NMENV; gbneal@hotspringsld.com; bartoosandandgravel@windstream.net; Morales, Howie; ikeandmary@windstream.net; jpc@sierracountynm.gov; gerijay@valornet.com; jeanette_lyman@tomudall.senate.gov; jcox@sierracountynm.gov; phfss@torchousing.org
Subject: Copper Flat EIS Scoping
Attachments: SCOPING_LTR_CopperFlatEIS_FEB2012.pdf

Dear Interested Party,
Please review the Copper Flat Mine EIS scoping letter attached.
Thank you.

United States Department of the Interior

BUREAU OF LAND MANAGEMENT
Las Cruces District Office
1800 Marquess Street
Las Cruces, New Mexico 88005
www.blm.gov/nm

TAKE PRIDE IN AMERICA

In Reply Refer To:
1793 (L0000)

February 3, 2012

Dear Interested Party:

The Bureau of Land Management (BLM) Las Cruces District invites you to participate in the identification of issues to determine the scope for an Environmental Impact Statement (EIS) concerning the planned construction, operation, and mine reclamation of the Copper Flat Mine in Sierra County, New Mexico.

New Mexico Copper Corporation (NMCC) submitted a Mining Plan of Operations to the BLM for mining and processing copper and other minerals at the Copper Flat mine in central Sierra County. The proposed mine is located approximately 4 miles north-northeast of the town of Hillsboro, New Mexico. Mining, ore processing and related activities will occur on both private and BLM lands.

As the EIS process begins, the BLM's goal is to reach out and involve the public. The first opportunity for you to participate will be at the upcoming open houses for public scoping. The purpose of the public scoping process is to discover relevant issues that will influence the scope of the environmental analysis, including alternatives to the proposed action, and guide the process for developing the EIS.

Participants will have an opportunity to talk with resource and planning specialists, and are encouraged to provide comments on the scope of the EIS and on potential alternatives, to share issues and concerns, and to ask questions. BLM will consider these comments in determining the scope of the EIS, including alternatives to the proposed action.

The open house format also will allow the BLM, NMCC, and State agencies to provide information about the EIS process, the proposed action, as well as information regarding the development, operation, and mine reclamation for the Copper Flat mining claims. The public scoping open houses will be:

FEBRUARY 22, 2012 7-9 P.M.
HILLSBORO COMMUNITY CENTER
ELENORE ST.
HILLSBORO, NEW MEXICO

FEBRUARY 23, 2012 7-9 P.M.
TRUTH OR CONSEQUENCES CIVIC AND CONVENTION CENTER
400 WEST FOURTH
TRUTH OR CONSEQUENCES, NEW MEXICO

Your thoughts, ideas, and comments are important to us throughout the process. Please attend the scoping open houses or send us your written comments on the enclosed comment form before the scoping period ends, which is March 9, 2012.

You may also submit comments using any of the following methods:

EMAIL: BLM_NM_LCDO_Comments@blm.gov

FAX: 1(703) 760-4899

TOLL-FREE NUMBER: 1(866) 760-1421

MAIL:
Copper Flat Mine
C/O Mangi Environmental Group
7927 Jones Branch Drive
Mclean VA 22102

Also if you wish to be removed from the mailing list, please let us know by checking the box on the comment form. Otherwise your name will be retained on the list and you will receive information on the Copper Flat project in the future. Informational materials like this letter will be available on the Copper Flat website at www.cuflateis.com.

BLM will provide you an opportunity later in the process to review the Draft EIS, which is scheduled for release in January 2013. During the public review period, BLM will conduct public meetings to accept comments on the adequacy of the Draft EIS. Written comments will also be accepted during the review period.

If you have any questions, please contact Mike Smith at 575-525-4421.

Sincerely,

Bill Childress
District Manager

1 Enclosure

2-17-2012

Huey, Greg, NMENV

From: Zack Gorstein [zgorstein@themacresourcesgroup.com]
Sent: Friday, February 17, 2012 1:56 PM
To: Zack Gorstein
Subject: THEMAC Resources Scoping Meeting Notification
Attachments: THEMAC_Scoping Meeting Notification.pdf

The Copper Flat Mine is pleased to announce the schedule for the Bureau of Land Management Scoping Meetings. These meetings give the community an opportunity to comment on the opening of the Copper Flat Mine.

The Scoping Meetings will be held on February 22 at 7 pm at the Hillsboro community center, and February 23 at 7 pm at the TorC Civic and Convention Center.

Please see the attached notice for more information, and feel free to contact me with any questions.

Kind regards,

--
Zack Gorstein
Project / Sustainability Analyst
Copper Flat Mine
THEMAC Resources Group, Ltd
2425 San Pedro Dr. NE, Suite 100
Albuquerque, NM 87110

Office: 505-883-2510
Mobile: 843-412-8021
Fax: 505-881-4616
www.themacresourcesgroup.com

This e-mail and any attachment may be confidential and privileged or otherwise protected from disclosure. It is solely intended for the person(s) named above. If you are not the intended recipient, any reading, use, disclosure, copying or distribution of all or parts of this e-mail or associated attachments is strictly prohibited. If you are not an intended recipient, please notify the sender immediately by replying to this message or by telephone and delete this e-mail and any attachments permanently from your system.

The Copper Flat Mine

Bureau of Land Management Scoping Meetings

The Copper Flat Mine is pleased to announce the schedule for the Bureau of Land Management Scoping Meetings.

These meetings give the community an opportunity to comment on the opening of the Copper Flat Mine.

Please join us on the following days:

FEB. 22 2012
7 pm to 9 pm

Hillsboro Community Center
Elenore Street,
Hillsboro,
NM 88042
575-895-3300

FEB. 23 2012
7 pm to 9 pm

Truth or Consequences Civic and Convention Center
400 West Fourth,
Truth or Consequences,
NM 87901
575-894-6673

For more information please visit **www.cuflateis.com**
or call toll free **866-760-1421**

We look forward to seeing you.

LEARN MORE ABOUT THE COPPER FLAT MINE AT
www.themacresourcesgroup.com

OR CALL ZACK GORSTEIN, PROJECT & SUSTAINABILITY ANALYST AT
505-234-6285

THEMAC RESOURCES

02318

This letter retransmits the scoping letter for the Copper Flat Mine Environmental Impact Statement because a comment form was omitted from the previous mailing.

New Mexico Environment Department
Mining and Environmental Compliance Section
c/o Greg Lucas
1190 St. Francis Dr.
Santa Fe, NM 87505

GROUND WATER
FEB 20 2012
BUREAU

$ 000.45
02 1P
0003976093 FEB 06 2012
MAILED FROM ZIP CODE 22102

2-20-2012

POFed

THEMAC RESOURCES

February 20, 2012

Mr. Chris Eustice
Senior Environmental Engineer
Mining and Minerals Division,
Mining Act Reclamation Program
Wendell Chino Building
1220 South St Francis Drive
Santa Fe, New Mexico 87505

Re: Transmission of DRAFT Baseline Data Report for Copper Flat Mine, Sierra County, New Mexico

Dear Chris,

Per your request, New Mexico Copper Corporation (NMCC) is pleased to provide you with one hard copy of the DRAFT Baseline Data Report (BDR) for the Copper Flat Mine. This DRAFT document is an informal submission, CONFIDENTIAL and not for public release. If you would like to review this report and provide comments that would improve the final version of this report, please do so by March 21, 2012.

Per independent requests from the other agencies with executed Cooperating Agency Memoranda of Understanding with the Bureau of Land Management, the DRAFT is being provided to the NMED Ground Water Bureau (1 Copy), Department of Game and Fish (1 Copy), and the NMED Air Quality Bureau (1 Copy). For each of these agencies, the same qualifications of an informal submission, CONFIDENTIAL, and not for public release apply.

NMCC is in the process of preparing a Permit Application Package and any questions or comments you might have upon review of the DRAFT Baseline Data Report would assist us in improving the quality of the final report, which will be included in the Permit Application Package. If you do not wish to provide comments now, you will have an opportunity to do so when NMCC submits the Final Baseline Data Report.

Thank you for your time. It is a pleasure working with you.

Best regards,
New Mexico Copper Corporation

J. Steven Raugust, CEG
Permitting Manager – Engineering

Katie Emmer
Project Scientist

Cc: Mr. Greg Huey, NMED Groundwater Bureau, Mining Environmental Compliance Section
Ms. Rachel Jankowitz, State of New Mexico Department of Game and Fish
Ms. Norma Perez, NMED Air Quality Bureau

Note: The DRAFT BDR is the same as the final version submitted with PAP on July 18, 2012

March 9, 2012

State of New Mexico
Energy, Minerals and Natural Resources Department

Susana Martinez
Governor

John Bemis
Cabinet Secretary

Brett F. Woods, Ph.D.
Deputy Cabinet Secretary

Fernando Martinez, Director
Mining and Minerals Division

March 9, 2012

Mr. Kurt Vollbrecht, Mining Act Team Leader
Mining Environmental Compliance Section
Groundwater Quality Bureau
New Mexico Environment Department
Post Office Box 26110
Santa Fe, NM 87502

GROUND WATER
MAR 13 2012
BUREAU

RE: Request for Review and Comment, Permit Modification 12-1 to Minimal Impact Exploration Permit Application, Copper Flat Exploration 2 Project, Permit No. SI025EM

Dear Mr. Vollbrecht:

The New Mexico Mining and Minerals Division (MMD) received an application requesting a modification to Minimal Impact Exploration Permit No. SI025EM for the Copper Flat Exploration 2 Project located in Sierra County, NM from New Mexico Copper Corporation. A copy of the application is enclosed pursuant to 19.10.4.406.C.3 NMAC.

MMD requests that you review this application and provide comments to MMD no later than 20 days after your receipt of this letter.

Please contact me at (505) 476-3438, or via email at chris.eustice@state.nm.us with any questions or comments you may have regarding the application or this request.

Sincerely,

Chris Eustice, Permit Lead
Mining Act Reclamation Program

Enclosures

cc: Mine File SI025EM

THEMAC
RESOURCES

RECEIVED
MARP
FEB 2 : 2012
MINING & MINERALS DIVISION

February 16, 2012

Mr. Chris Eusctice
Permit Lead, MMD
1220 South St. Francis Drive
Santa Fe, NM 87505

RE: Copper Flat Exploration 2(SI025EM) Permit Modification Request #2

Dear Chris,

New Mexico Copper Corporation (a wholly-owned subsidiary of THEMAC Resources Group) proposes to modify the Copper Flat Exploration 2 Minimal Impact Permit #SI025EM. We intend add 18 drill locations, accommodating 20 holes, to our permit, while relinquishing 6 un-drilled holes (on 4 un-disturbed sites) from the existing permit.

In 2011, we drilled 16 holes for a total of 15,451 downhole feet, comprising 1.93 acres (14 drill pads, 60' x 100' ea.) permitted surface disturbance. Downhole reclamation was completed immediately after drilling. We are requesting release of this portion of Financial Assurance, and have attached Plugging Records as submitted to the Office of the State Engineer.

Furthermore, we would like to abandon the previous modification (9 additional holes on existing sites) which we submitted on August 4, 2011. Those additional holes will no longer be required.

Roads and Overland Access

Nearly all of the proposed drill sites in this modification have been located on or adjacent to existing 2-wheel-drive navigable roads.

Three sites, listed below, will require some minor surface improvement (i.e., new road). Widths of 10' will be generous to accommodate our equipment, and these very short road segments will not need to accommodate two vehicles passing.

Site	Length of Road Required
24	80 feet
30	50 feet
CNI-5	100 feet

Total Road Length: 230 ft
Disturbance Area: 0.05 ac

THEMAC RESOURCES

Drill Pads

We will be constructing pads of no greater than 30' by 60'. Our current drill program will employ a Boart Longyear LF 70 truck-mounted core rig requiring minimal auxiliary equipment. Drill pipe will be staged on a pipe truck immediately behind the rig. This will greatly decrease the area of surface disturbance.

Drill sites which were permitted under the 2011 permit but which will be drilled in 2012 (detailed below) were not prepared or disturbed ahead of time, and will now be constructed to the 30' by 60' size. For this reason, our area of disturbance will be significantly decreased.

Drill Sites

The following drill sites, approved in 2011, were drilled in 2011. We have no further drilling activities planned for these sites. Downhole reclamation was completed on all holes. We will apply for bond release upon completion of surface reclamation.

All coordinates are given in UTM meters, NAD 83 Zone 13 S (un-surveyed).

Site	NMCC Hole Name	UTM N (m)	UTM E (m)	Hole Length (ft)
C	CF-11-13	3650933	263097	1,200
D	CF-11-14	3650903	263097	1,200
E	CF-11-06	3650899	263257	1,177
H	CF-11-01	3650838	263240	310
	CF-11-01B			1,111
J-1/J-2	CF-11-07	3650774	263360	109
	CF-11-04			812
K	CF-11-03	3650751	263077	1,154
Q	CF-11-11	3650653	263341	1,198
R-1/R-2	CF-11-05	3650625	263249	1,200
	CF-11-09			1,200
S	CF-11-08	3650596	263187	1,200
NE-F	CF-11-02	3651004	263305	1,097
JK-9	CF-11-12	3650812	263384	1,200
JK-16	CF-11-10	3650673	263144	106
	CF-11-10B			1,177

Downhole Disturbance: 15,451 ft
Surface Disturbance: 1.93 ac

THEMAC RESOURCES

The following drill sites, approved in 2011, have not been drilled, but we wish to retain them under our permit, and drill them during 2012. In some cases, these hole locations will be adjusted <100'. We will be re-naming the sites to fit with this year's drill program designations, as outlined below. The intended hole lengths have been updated.

Site	UTM N	UTM E	Hole Length	New Site Name
A	3650973	263112	1,050	CNI-6
B	3650951	263316	1,050	CNI-1
I	3650782	263024	1,050	CNI-5
P	3650653	263097	1,050	CNI-4
T	3650606	262998	1,050	3
JK-1	3650981	263152	1,050	7
JK-5	3650949	263401	1,100	20
JK-6	3650919	263346	1,050	16
JK-8	3650883	263462	1,050	CNI-2
(B)	3650883	263462	1,050	22
JK-10	3650680	263447	1,050	CNI-3
JK-14	3650596	263111	1,200	5A

Proposed Downhole Disturbance: 13,100 ft
Proposed Surface Disturbance: 0.45 ac

The following drill sites, approved in 2011, have not been drilled or disturbed, but we wish to retain them under our permit. However, they represent a later phase of drilling, and we do not wish to bond for downhole disturbance at this time. (Permitted surface disturbance *is* included in our Financial Assurance calculation below.)

Site	UTM N	UTM E
NE-C	3651081	263261
NE-G	3650993	263188
F	3650866	263347
G	3650845	263026
L	3650742	263410
M	3650712	263327
O	3650681	263404
U	3650413	263145

THEMAC RESOURCES

JK-2	3651032	263214
JK-4	3651050	263305
JK-7	3650872	263398
JK-11	3650652	263387
JK-12, V	3650563	263241
JK-13	3650566	263050
JK-15	3650638	263035

Proposed Downhole Disturbance: 0 ft
Proposed Surface Disturbance: 0.62 ac

The following drill sites, approved in 2011, have not been drilled or disturbed, and we wish to relinquish them from our permit:

Site	UTM N	UTM E
NE-B	3651112	263285
NE-D, JK-3	3651053	263215
NE-E	3651022	263199
N-1, N-2	3650690	263060

We wish to add the following drill sites to our permit through this modification:

Site		UTM N	UTM E	Hole Length
1		3650689	262989	1,200
2		3650802	262989	1,100
4		3650607	263050	1,100
	(A)	3650607	263050	2,000
4B		3650730	263050	1,050
5		3650516	263100	1,050
6		3650691	263111	1,500
9		3650954	263172	1,050
11		3650619	263233	1,500
13		3650741	263233	1,500
17		3650588	263370	1,050
18		3650611	263415	1,100
21		3650651	263477	1,200
	(B)	3650651	263477	1,200

THEMAC
RESOURCES

23	3650575	263536	1,050
24	3651010	263616	1,050
25A	3650598	263587	1,050
30	3650840	262928	1,050
31	3650818	263579	1,050
8A	3650575	263171	1,200

Proposed Downhole Disturbance: 24,050 ft
Proposed Surface Disturbance: 0.74 ac

In summary, given the MMD's approval of this modification, our permitted drill sites will stand:

Site	UTM N	UTM E	Hole Length	Comment
C	3650933	263097	1,200	Drilled 2011
D	3650903	263097	1,200	Drilled 2011
E	3650899	263257	1,177	Drilled 2011
H	3650838	263240	310	Drilled 2011
(B)			1,111	Drilled 2011
J-1/J-2	3650774	263360	109	Drilled 2011
(B)	3650774	263360	812	Drilled 2011
K	3650751	263077	1,154	Drilled 2011
Q	3650653	263341	1,198	Drilled 2011
R-1/R-2	3650625	263249	1,200	Drilled 2011
(B)			1,200	Drilled 2011
S	3650596	263187	1,200	Drilled 2011
NE-F	3651004	263305	1,097	Drilled 2011
JK-9	3650812	263384	1,200	Drilled 2011
JK-16	3650673	263144	106	Drilled 2011
(B)			1,177	Drilled 2011
CNI-6	3650973	263112	1,050	Formerly A
CNI-1	3650951	263316	1,050	Formerly B
CNI-5	3650782	263024	1,050	Formerly I
CNI-4	3650653	263097	1,050	Formerly P
3	3650606	262998	1,050	Formerly T
7	3650981	263152	1,050	Formerly JK-1
20	3650949	263401	1,100	Formerly JK-5
16	3650919	263346	1,050	Formerly JK-6
CNI-2	3650883	263462	1,050	Formerly JK-8 (AKA 22)
(22)			1,050	Formerly JK-8 (AKA Site 22)

THEMAC
RESOURCES

CNI-3	3650680	263447	1,050	Formerly JK-10
5A	3650596	263111	1,500	Formerly JK-14
NE-C	3651081	263261	No Downhole Bond	Permitted 2011
NE-G	3650993	263188	No Downhole Bond	Permitted 2011
F	3650866	263347	No Downhole Bond	Permitted 2011
G	3650845	263026	No Downhole Bond	Permitted 2011
L	3650742	263410	No Downhole Bond	Permitted 2011
M	3650712	263327	No Downhole Bond	Permitted 2011
O	3650681	263404	No Downhole Bond	Permitted 2011
U	3650413	263145	No Downhole Bond	Permitted 2011
JK-2	3651032	263214	No Downhole Bond	Permitted 2011
JK-4	3651050	263305	No Downhole Bond	Permitted 2011
JK-7	3650872	263398	No Downhole Bond	Permitted 2011
JK-11	3650652	263387	No Downhole Bond	Permitted 2011
JK-12, V	3650563	263241	No Downhole Bond	Permitted 2011
JK-13	3650566	263050	No Downhole Bond	Permitted 2011
JK-15	3650638	263035	No Downhole Bond	Permitted 2011
1	3650689	262989	1,200	New Site
2	3650802	262989	1,100	New Site
4	3650607	263050	1,100	New Site
(A)			2,000	(Site 4)
4B	3650730	263050	1,050	New Site
5	3650516	263100	1,050	New Site
6	3650691	263111	1,500	New Site
9	3650954	263172	1,050	New Site
11	3650619	263233	1,500	New Site
13	3650741	263233	1,500	New Site
17	3650588	263370	1,050	New Site
18	3650611	263415	1,100	New Site
21	3650651	263477	1,200	New Site
(B)			1,200	(Site 21)
23	3650575	263536	1,050	New Site
24	3651010	263616	1,050	New Site
25A	3650598	263587	1,050	New Site
30	3650840	262928	1,050	New Site
31	3650818	263579	1,050	New Site
8A	3650575	263171	1,200	New Site

The attached map shows our intended project disposition.

THEMAC RESOURCES

Financial Assurance

The following factors were used to estimate Financial Assurance:

Existing Disturbance under Permit SI025EM

Surface (Drill Pads)		1.93 ac	
Downhole		15,451 ft	@ $6.50/ft = $100,431.50*

* This amount will not be included in the final Financial Assurance figure, as downhole reclamation is complete

Proposed Additional Disturbance

Surface			
	Road	0.05 ac	
	Drill Pads	1.81 ac	
Downhole		37,150 ft	@ $6.50/ft = $241,475

Total Bond Disturbance

Surface	**3.79 ac**	**@ $5,400.00 First Acre** **$3,300.00 Subsequent Acres** **Total = $14,607**
Downhole	**$37,150 ft**	**@ $6.50/ft = $241,475**

Total Financial Assurance, 2012:	**$256,082.00**
2011 Financial Assurance:	$394,082.00

NMCC will be requesting a reduction of our Financial Assurance bond in the amount of $138,000.00 to reflect our decreased surface and downhole disturbance forecasts, as well as the completed downhole reclamation (abandonment) of 15,451 ft drilled in 2011.

I have enclosed a check for the $250 permit modification fee.

THEMAC
RESOURCES

Thanks once again for all of your assistance during this process. Your ready knowledge of regulations has been a tremendous help in composing these modifications. Please don't hesitate to contact me with any questions or for any more information I can provide.

Best regards,

Andrew Feltman
Project Geologist
New Mexico Copper Corporation – Copper Flat Mine
(A Wholly Owned Subsidiary of THEMAC Resources Group, Ltd.)
Office: 505.872.0297
Mobile: 251.591.5251
www.themacresourcesgroup.com

NE-C
JK-1
JK-2
NE-F
NE-D
CNI-6
7
9
CNI-1
20
C
D
E
16
CNI-2
22
JK-7
30
O
JK-9
31
2
CNI-5
J-1 / J-2
J-1 / J-2
K
L
13
4B
M
1
6
JK-16
JK-16
O
CNI-3
CNI-4
Q
JK-11
21B
21
R-1 / R-2
11
R-1 / R-2
3
4A
4
5A
S
18
25A
17
8A
23
JK-12
5
U
New Sites, 2012
2011 Permitted, Not Drilled
2011 Permitted, No Hole Bond
2011 Drilled
New Road, 2012
0
100
200
400
Feet
Coordinate System: NAD 1983 UTM Zone 13N
Projection: Transverse Mercator
Datum: North American 1983
False Easting: 500,000.0000
False Northing: 0.0000
Central Meridian: -105.0000
Scale Factor: 0.9996
Latitude Of Origin: 0.0000
Units: Meter
N
Minimal Impact Permit SI02EM Modification
THEMAC Resource Group, Ltd
Copper Flat Mine
2/16/2012
APF

3-16-2012

THEMAC RESOURCES

March 16, 2012

Doug Haywood
Program Manager
Bureau of Land Management
Las Cruces District Office
1800 Marquess Street
Las Cruces, NM 88005

Re: Revised and More Detailed Scoping Comments, Copper Flat Mine, Sierra County New Mexico

Doug,

The purpose of this letter is to submit revised and more detailed scoping comments from NMCC in regards to the proposed Copper Flat Mine. This letter provides the list of specific alternatives being considered by NMCC in the design process. These are alternatives that need to be included as part of the EIS process. They are:

Tailings Deposition Method:
NMCC is evaluating a different tailings deposition method versus the conventional tailings storage facility described in the MPO. The method under evaluation is referred to as dry-stack tailings deposition or paste tailings deposition. The two names are sometimes used interchangeably depending on the amount of retained moisture in the tailings at the time of deposition. The method differs from conventional tailings deposition in terms of the method of construction, overall water consumption, erosion control methods, air quality control methods and the general footprint of the tailings storage facility. Additionally, impacts to project economics as well as the overall feasibility of the method are key issues in the assessment of this alternative.

Tailings Storage Facility Design:
NMCC is evaluating the utilization of a single synthetic liner and under drain system for the Copper Flat Mine. The current design incorporates two synthetic liners and two under drain systems. Evaluations by multiple engineering firms are underway to compare containment and process water collection effectiveness as well as long-term structural stability of the two designs. Assuming the evaluations are favorable to the single synthetic liner design, NMCC would like to consider this alternative.

Mining and Processing Rate:
NMCC is evaluating an increase in the processing rate. The current rate for ore processing in the MPO is 17,500 short tons per day. Processing rates up to 25,000 short tons per day are being evaluated. There would also be a corresponding increase in the mining rate. The total tons of ore processed over the life of the mine would remain about the same as that in the MPO. The footprint of the processing plant,

tailings storage facility and pit area would also remain about the same as that in the MPO. This is an important alternative with regards to project economics and feasibility.

Waste Rock Disposal:
Recent geotechnical data and analysis has determined that the pit slopes will need to be constructed at a lesser angle in some areas of the pit than presented in the MPO. This is necessary to allow the safe mining of the ore body. One result of this new determination is an increase in the amount of waste rock that will need to be mined and placed in the waste rock disposal area. NMCC continues efforts in the collection of geotechnical data and the analysis of the pit slopes. As these efforts go forward, the volume of material in the waste rock disposal area will be impacted. This alternative is necessary to provide for the safe and economic mining of the resource.

Thank you for your time. We look forward to working with you in this process and invite any questions you might have regarding these alternatives. We will of course provide additional information to the BLM as the engineering studies are completed.

Sincerely,

NEW MEXICO COPPER CORPORATION

Jens Deichmann
Permitting Manager

Copper Flat Mine EIS
Alternatives Development Outline

1. **Regulatory Framework**
   a. **Alternatives**
      i. CEQ regulations (40 CFR 1502.14) – rigorously explore and objectively evaluate all reasonable alternatives
         1. CEQ 40 Questions (2a) – reasonable alternatives include those that are practical or feasible from the technical and economic standpoint and using common sense, rather than simply desirable from the standpoint of the applicant
      ii. DOI NEPA regulations (43 CFR 46.415) – reasonable alternatives that meet the purpose and need of the proposed action and address one or more significant issues related to the proposed action
         1. 43 CFR 46.420 – reasonable alternatives are technically and economically practical or feasible and meet the purpose and need of the proposed action
      iii. BLM NEPA Handbook – alternatives may need to reflect the decision space and authority of other agencies if decisions are being made by more than one agency
   b. **Purpose and Need**
      i. CEQ regulations (40 CFR 1502.13) – briefly specify the underlying purpose and need to which the agency is responding in proposing the alternatives including the proposed action.
      ii. DOI NEPA regulations (43 CFR 46.420) – consider the needs and goals of the parties involved in the application as well as the public interest
         1. needs and goals of parties involved may be described as background information
         2. BLM's purpose and need for action will determine the range of alternatives
      iii. BLM NEPA Handbook – purpose and need statement for an externally generated action must describe the BLM purpose and need, not the external proponent's purpose and need
      iv. Surface Management regulations (43 CFR 3809) – in response to actions authorized by mining laws, prevent unnecessary and undue degradation of public lands, reclaim disturbed areas, and coordinate with state agencies to avoid duplication

2. **Draft Purpose and Need Statement**
   a. **Need** – allow NMCC reasonable access to public land to conduct mining activities permitted under the general mining laws
   b. **Purpose** – approve an MPO that prevents unnecessary and undue degradation of public lands and reclaims disturbed areas

3. **Alternatives Development**
   a. **No Action**
   b. **Proposed Action** – MPO as presented by NMCC *(discussion below is preliminary draft descriptions subject to change)*
      i. Components – separate activities or facilities of the action
         1. Construction (Site Preparation)

2. Exploration (Access and Sampling)
3. Operation (Extraction and Processing)
4. Reclamation (Closure and Monitoring)

ii. Elements – actions that comprise the components
1. Construction – tailings impoundment, waste rock disposal, haul roads, access roads, fencing and exclusionary devices, stormwater diversion, topsoil salvage, plant area (mill and processing facilities, administration/ancillary facilities), water supply network
2. Exploration – access roads, drill pads, staging areas
3. Operation – open pit, ore processing, dewatering, tailings impoundment process, power source and consumption, water source and consumption, schedule, transport, operating plans
4. Reclamation – remove equipment and facilities, stabilize pit walls, stabilize tailing impoundment walls, recontour disturbed areas, revegetate disturbed areas, alleviate potential for acid rock drainage, remove roads, plug drill holes, abandon wells, monitor pit water and groundwater

c. Process to Identify Alternatives

i. Consider planning, feasibility, and engineering studies prepared by NMCC
ii. Consider options to or different means of implementing components and elements of MPO
iii. Consider operational and environmental issues identified by agencies
1. *TBD from agency input*
2. *TBD from agency input*

iv. Consider operational and environmental issues identified from scoping process
1. *TBD from scoping comments*
2. *TBD from scoping comments*
3. *TBD from scoping comments*

d. Alternative 1

i. Xxxx
ii. Xxxx
iii. Xxxx

e. Alternative 2

i. Xxxx
ii. Xxxx
iii. Xxxx

4. Process to Screen Alternatives for Analysis or Elimination

a. Screening Process – could be a one-step or two-step process depending on the number and complexity of alternatives to be screened

i. One-step Process: Qualitative evaluation based on general criteria; general criteria focus on alternative meeting purpose and need and being reasonable (i.e., technically and economically practical or feasible to implement)
1. *TBD general criterion*
2. *TBD general criterion*

3. *TBD general criterion*

ii. Two-step Process: 1st step as described above; 2nd step consists of qualitative and quantitative evaluation based on specific criteria; specific criteria are subsets of general criteria and assigned weights based on relative importance and feasibility of criteria in identifying a reasonable alternative

1. *TBD specific criterion*
2. *TBD specific criterion*
3. *TBD specific criterion*

b. Decision Matrix – tabulate the outcome of the screening process to indicate alternative carried forward to analysis and alternatives eliminated from analysis

i. One-step Process: qualitatively rate alternatives as positive, negative, or neutral against the general criteria; alternatives with a net positive rating will be analyzed, net negative or net neutral will be eliminated

ii. Two-step Process: 1st step as described above; assign values to alternatives based on likelihood of meeting specific criteria; calculate score and rank alternatives; eliminate low ranking alternatives

3-20-2012

Copper Flat Mine EIS
Alternatives Development Outline

Circa 3-20-2012

1. **Regulatory Framework**
   a. **Alternatives**
      i. CEQ regulations (40 CFR 1502.14) – rigorously explore and objectively evaluate all reasonable alternatives
         1. CEQ 40 Questions (2a) – reasonable alternatives include those that are practical or feasible from the technical and economic standpoint and using common sense, rather than simply desirable from the standpoint of the applicant
      ii. DOI NEPA regulations (43 CFR 46.415) – reasonable alternatives that meet the purpose and need of the proposed action and address one or more significant issues related to the proposed action
         1. 43 CFR 46.420 – reasonable alternatives are technically and economically practical or feasible and meet the purpose and need of the proposed action
      iii. BLM NEPA Handbook – alternatives may need to reflect the decision space and authority of other agencies if decisions are being made by more than one agency
   b. **Purpose and Need**
      i. CEQ regulations (40 CFR 1502.13) – briefly specify the underlying purpose and need to which the agency is responding in proposing the alternatives including the proposed action.
      ii. DOI NEPA regulations (43 CFR 46.420) – consider the needs and goals of the parties involved in the application as well as the public interest
         1. needs and goals of parties involved may be described as background information
         2. BLM's purpose and need for action will determine the range of alternatives
      iii. BLM NEPA Handbook – purpose and need statement for an externally generated action must describe the BLM purpose and need, not the external proponent's purpose and need
      iv. Surface Management regulations (43 CFR 3809) – in response to actions authorized by mining laws, prevent unnecessary and undue degradation of public lands, reclaim disturbed areas, and coordinate with state agencies to avoid duplication

2. **Draft Purpose and Need Statement**
   a. **Need** – ~~allow~~ authorize NMCC reasonable access to public land to conduct mining activities permitted under the general mining laws
   b. **Purpose** – approve an MPO that prevents unnecessary and undue degradation of public lands and reclaims disturbed areas

3. **Alternatives Development**
   a. **No Action**
   b. **Proposed Action** – MPO as presented by NMCC *(discussion below is preliminary draft descriptions subject to change)*
      i. Components – separate activities or facilities of the action
         1. Construction (Site Preparation)

02340

2. Exploration (Access and Sampling)
3. Operation (Extraction and Processing)
4. Reclamation (Closure and Monitoring)

ii. Elements – actions that comprise the components
1. Construction – tailings impoundment, waste rock disposal, haul roads, access roads, fencing and exclusionary devices, stormwater diversion, topsoil salvage, plant area (mill and processing facilities, administration/ancillary facilities), water supply network **(water pump testing?)**
2. Exploration – access roads, drill pads, staging areas
3. Operation – open pit, ore processing, dewatering, tailings impoundment process, power source and consumption, water source and consumption, schedule, transport, operating plans
4. Reclamation – remove equipment and facilities, stabilize pit walls, stabilize tailing impoundment walls, recontour disturbed areas, revegetate disturbed areas, alleviate potential for acid rock drainage, remove roads, plug drill holes, abandon wells, monitor pit water and groundwater

c. Process to Identify Alternatives

i. Consider planning, feasibility, and engineering studies prepared by NMCC
ii. Consider options to or different means of implementing components and elements of MPO
iii. Consider operational and environmental issues identified by agencies
1. *TBD from agency input*
2. *TBD from agency input*

iv. Consider operational and environmental issues identified from scoping process
1. *TBD from scoping comments*
2. *TBD from scoping comments*
3. *TBD from scoping comments*

d. Alternative 1

i. Xxxx
ii. Xxxx
iii. Xxxx

e. Alternative 2

i. Xxxx
ii. Xxxx
iii. Xxxx

4. Process to Screen Alternatives for Analysis or Elimination

a. Screening Process – could be a one-step or two-step process depending on the number and complexity of alternatives to be screened

i. One-step Process: Qualitative evaluation based on general criteria; general criteria focus on alternative meeting purpose and need and being reasonable (i.e., technically and economically practical or feasible to implement)
1. *TBD general criterion*

2. *TBD general criterion*
3. *TBD general criterion*

ii. Two-step Process: 1st step as described above; 2nd step consists of qualitative and quantitative evaluation based on specific criteria; specific criteria are subsets of general criteria and assigned weights based on relative importance and feasibility of criteria in identifying a reasonable alternative

1. *TBD specific criterion*
2. *TBD specific criterion*
3. *TBD specific criterion*

b. Decision Matrix – tabulate the outcome of the screening process to indicate alternatives carried forward to analysis and alternatives eliminated from analysis

i. One-step Process: qualitatively rate alternatives as positive, negative, or neutral against the general criteria; alternatives with a net positive rating will be analyzed, net negative or net neutral will be eliminated

ii. Two-step Process: 1st step as described above; assign values to alternatives based on likelihood of meeting specific criteria; calculate score and rank alternatives; eliminate low ranking alternatives

Purpose and Need

Background

The New Mexico Copper Corporation (NMCC) submitted a Mine Plan of Operation (MPO) to the Las Cruces District Office (LCDO) on November 4, 2011. The MPO proposes to reestablish a poly-metallic mine and processing facility in Sierra County, New Mexico. Mining, ore processing, and related activities would occur on both private land and public land administered by the BLM. Mill concentrate would be transported by truck to rail facilities where it would be shipped to a smelter in Arizona, or port facilities for processing overseas.

Agency Purpose and Need

The purpose of the proposed action is to provide NMCC authorization to conduct mining activities leading to the extraction of copper ore.

The need for the BLM to authorize this project is established under the General Mining Law of 1872, as amended. Under the law, persons are entitled to reasonable access to explore for and develop mineral deposits on public domain land. As the federal agency responsible for managing mineral rights and access on certain federal lands, the BLM must ensure that NMCC's proposal complies with BLM Surface Management Regulation (43 CFR 3809), the Mining and Mineral Policy Act of 1979 (as amended) and Federal Land Policy and Management Act of 1976.

NMCC #	Agency #	Comment
45	SWQB	The introductory paragraph to Section 8, Surface Water, includes the statement "Numerous ephemeral tributaries feed into the Rio Grande from the west, but none contribute perennial flow to the Rio Grande." Lack of perennial flow to the Rio Grande does not negate the fact that both Las Animas Creek and Percha Creek include perennial reaches that support fisheries and water quality must be protected as required under §20.6.4.103 of the New Mexico Administrative Code (NMAC). This paragraph should be reworded to acknowledge the important contribution of these waters of the State as a natural resource.
46		Section 8.1, Surface Water Characteristics of Site and Vicinity. During the joint agency inspection that was conducted on October 26, 2010 (Inspection), Grayback Arroyo exhibited surface water pools and small flows along a reach of several hundred yards that did not appear to be the result of direct precipitation. In addition, there is significant riparian vegetation indicating that Grayback Arroyo should be classified as an intermittent water of the State pursuant to §20.6.4.98 NMAC. The SAP should acknowledge this classification rather than describing Grayback Arroyo as an ephemeral channel.
47		Section 8.2, Historical Data: This section states that "Surface water at the Site was most recently investigated by ABC (1996), who collected flow and water quality from Percha Creek and Las Animas Creek." In 2004, the SWQB conducted a water quality survey that included Las Animas Creek and Percha Creek. These data are available from the State through a public records request.
48		Section 8.6.1.2, Water Quality Sampling: As observed during the Inspection, set up and placement of the automated samplers appeared adequate. SWQB staff did suggest to the applicant that stream sample collection targeting the rising limb of the hydro graph would be preferred since research indicates that the first surge of storm runoff is likely to carry the most pollutants.
49		Section 9 of the SAP states that the Rio Grande is the only significant surface water resource in the area. This statement is questionable since perennial reaches of the tributaries originating from the eastern side of the Black Range provide important sources of surface water to residents west of the Rio Grande and provide unique riparian and wildlife habitat year round. The SAP then states that Las Animas Creek and Percha Creek are intermittent streams. As previously discussed, these streams contain perennial reaches that support fisheries and should be acknowledged as such.

50	GWQB	Section 7.4 of the SAP proposes to review the existing geochemical data prior to determining the locations for collection of additional samples for identification of ore and waste rock zones within the proposed pit outlines. A phased approach is proposed that will contribute to a sampling program focused on the main material types within the proposed pit outlines, with more samples being collected from the material types with the greatest predicted tonnage. NMED agrees that this phased approach is an efficient methodology for identification of geologic strata but requests that addendums to the approved SAP be submitted for agency approval at developmental intervals prior to moving forward with the proceeding stage of geochemical sampling.
51		Section 7.4.2 states that "exploration drilling is currently ongoing in the expansion areas." During the Inspection, a map of the proposed exploration drilling areas was discussed, but at this time no minimal impact exploration application has been submitted for NMED review. Such an application is necessary before exploratory drilling may proceed.
52		Section 7.4.3 mentions "a number of field tests" that may be used to determine the geochemistry of specific material types prior to moving on with standard static testing. These field tests should be identified and described in the requested addendum to the SAP for geochemical sampling.
53		Section 8.6.2.1 discusses using five profiles and two tie lines to determine Pit Lake depth; however, Figure 8-2 shows eight profile lines. This discrepancy should be resolved.
54		Section 9.1.1 cites Figure 9-2 as depicting three aquifers: the crystalline bedrock aquifer, the Santa Fe Group aquifer system, and the Quaternary alluvial aquifer. Figure 9-2 does not provide any reference to the crystalline bedrock aquifer and does not function as a "conceptual model" of the Site ground water flow system as the title suggests. This figure should be replaced with an appropriately designed diagram.

55		Section 9.1.2.1 states that ground water elevation data are derived from wells greater than 4,000 feet distance from the Pit Lake, but then states confidently that the ground water gradients in the area are toward the Pit Lake. The section also references Figure 9-6 as demonstrating ground water gradients toward the Pit Lake; however, the vertical scales on opposite sides of this diagram are not coordinated: the scale on the left side of the figure is approximately 80 feet to one inch, while the scale on the right side of the figure is approximately 5 feet to one inch. This gross discrepancy in scale negates the effectiveness of this figure as a tool in ground water gradient interpretation. In addition, the figure, circa 1998, shows the Pit Lake elevation at 5,436.5 ft amsl, while the text in the section reported the Pit Lake elevation at 5,442 ft amsl in 1997 and 5,444 ft amsl in 2010. The section concludes by stating that the Pit Lake elevation remains below the pre-mining water level elevation of 5,500 to 5,540 ft amsl. This is in contradiction to the Preliminary Environmental Impact Statement (BLM, 1999) cited previously in the section, which describes pre-mining ground elevation as 5,500 to 5,540 ft amsl.
56		Figure 9-9 shows well EIW as the closest monitoring well to the Pit Lake. However, the SAP does not include water depths in this well or Pit Lake elevations in the monitoring network. A denser monitoring well field may be necessary to delineate a local ground water divide, and the SAP should require that Pit Lake elevation measurements be taken at the same time as water level measurements in adjacent ground water monitoring wells to better define the potentiometric surface across the Site. Statements regarding site-wide ground water levels should be re-evaluated pending a more thorough hydrological investigation.

57		Section 9.1.3 states that concentrations of total dissolved solids (TDS) and sulfate down-gradient of the Pit Lake have increased gradually over time and suggests that impacts to water quality in the vicinity of the Pit Lake may be naturally occurring. However, Figure 15 from Raugust (2003) shows an increase in TDS from approximately 550 mg/L to almost 1,000 mg/L between 1996 and 1998 in well GWQ-96-23A. Further review of Raugust (2003) reveals conflicting statements regarding wells in location to the Pit Lake. In the "Study Area Investigations" section, the manuscript states that "Prior to 1996, only one well was available for sampling groundwater in the vicinity of the pit lake. This monitoring well, GWQ-4, is located approximately one-half mile east of the existing pit." However, in the "Conclusions" section the manuscript references water quality collected from monitoring well GWQ-5 in 1981. NMED recommends that, rather than adopt conclusions from references not submitted for agency review, NMCC provide appropriate data and develop conclusions based on the analysis of those data.
58		'Section 9.1.5 references the MMD Guidance Document for Part 6 New Mining Operations, stating that the SAP must include supporting material to justify the use of historic data NMED requests that, regardless of justification, an inventory of all existing data be compiled and reported prior to validation and possible exclusion of these data.
59		Section 9.3 proposes reducing the number of wells monitored for water quality parameters after the initial four quarters of data collection. NMCC should be aware that under NMED abatement plan requirements and the discharge plan permitting process these wells will require separate evaluation by NMED prior to being removed from any approved sampling plan.
60		Section 9.4.2 discusses the possible need for installation of additional monitoring wells. New well drilling and installation must meet NMED and NM OSE requirements. New well locations should be proposed to NMED under a Stage One Abatement Plan and/or Discharge Plan proposal. In addition, this section references Table 9-4 for a summary of previous pumping tests and resulting aquifer characteristics. This table does not provide sufficient information to determine the source or validity of the data provided and the SAP should provide for agency review a summary of the individual aquifer tests used to compile these data prior to determination as to the adequacy of the existing data to support the hydrologic impact analysis.

61		Section 9.7 references Figure 9-9 to provide locations of the wells proposed for sampling in Table 9-2. Well GWQ-12 at the southern end of the tailing disposal facility is not proposed for water quality sampling. As previously stated, well EIW is also not included in the SAP. NMCC should provide justification with supporting data as to why these and other available wells are excluded from the SAP.
62		During the Inspection, a previously identified well was located adjacent to the lower Greyback Arroyo downstream of the tailing dam. It was supposed that this well may be the McCravey-Greyback well. A data review should be conducted for this well and justification for or against its inclusion in the SAP should be included. Furthermore, this well was open to the environment and efforts should be made to properly secure it with an appropriate cap.

Resolution	Notes
Section 8.1.1 now includes the statement: "Both Las Animas and Percha Creeks have perennial reaches that support fisheries."	
Grayback is discussed in Section 8.1.2.3, Greenhorn Arroyo Drainage Basin	
Data was requested and received from SWQB, but NMCC didn't reference because there is no flow data in published reports. See Sec 8.1.2.1.2, 8.1.2.2.2.	
Auto samplers were set to turn on every 15 minutes through monsoon season, however there was not enough runoff generated in precipitation events in 2011 to trigger a sample collection.	
Corrected or removed as applicable.	

See Section 7.5 for Geochemical Characterization	
All exploration drilling has properly permitted and documented through MMD and OSE.	
See Section 7.5 for Geochemical Characterization	
See Figure 8-8	
See Figure 8-11 for the current Conceptual Model of the site and surrounds.	

See Figure 8-16 and Discussion in Section 8.1.2.3.4	
See Figure 8-16 and Discussion in Section 8.1.2.3.4. Figure 8-14 presents Regional 2011 groundwater elevation contours and Table 8-17 presents a Summary of 2011 Water Level Measurements Used.	

Table 8-19 presents Identified Dissolved Constituents of Concern for the Pit Lake. Appendix 8-E presents Pit Lake Analytical Results.	
The BDR does compile historic data in tables and appedices of Section 8.	
NMCC's Stage I AP was submitted under separate cover. NMED approved this plan in February 2012.	
NMCC maintains communication with NMED and the NM OSE regarding new wells and obtains proper permits prior to drilling new wells.	

See Section 8.2.4 for Groundwater Data. See Section 8.2.4.1.3 for Well Selection Rationale.	
See Section 8.2.4 for Groundwater Data. See Section 8.2.4.1.3 for Well Selection Rationale. In addtion, the subject well in this discussion is not actually McGravey-Grayback, but is GWQ-1. Currently, this well is under a Right-of-Way access request by NMCC to the BLM. This ROW is still in process and once granted, NMCC plans to rehabilitate the well including a proper well head. For the baseline data, this well was not included due to it's unmaitained condition.	

3-20-13

THEMAC RESOURCES GROUP LIMITED

Suite 2000 - 1066 West Hastings Street
Vancouver, BC - Canada V6E 3X2
T (+1) 604 806-6110 F (+1) 604 806-6112
TSXV: MAC

THEMAC Resources Announces a Design Milling Rate Increase up to 25,000 TPD at Copper Flat

Vancouver, British Colombia – March 20, 2012 – THEMAC Resources Group Limited (TSXV:MAC) ("THEMAC" or the "Company") today announced that the ongoing metallurgical testing program being conducted in connection with the preparation of the preliminary feasibility study for the Copper Flat Property, has confirmed an enhanced processing plant size based upon existing plant infrastructure and ore characteristics. The test work, being conducted at the directive of Tucson-based M3 Engineering and Technology Corporation, has also presented encouraging results in the area of optimized copper, molybdenum and gold recoveries.

Highlights:

- Existing infrastructure includes foundations from existing crushing and grinding equipment. To take advantage of these structures, and meet the processing plant needs, grinding test work conducted by Hazen Research, Inc. was completed on a large core sample from Copper Flat. The resulting data was modeled and interpreted by Control Systems Services. These results indicate that the grinding circuit proposed will, if installed and operating at full capacity, be capable of processing approximately 25,000 short tons per day (tpd). This represents a designed increase, utilizing the currently installed foundations, of 8,000 tpd over the milling rate originally anticipated in the Company's preliminary assessment previously announced in July, 2010.
- Ongoing test work at Mineral Advisory Group R&D, LLC for the flotation of ore types shows very encouraging preliminary results. This has the potential to enhance the historical 90 percent mill recoveries for copper and silver. Future work will focus on finalizing reagent suites and directing specific reagent types toward improving molybdenum recovery rates over historical test work. Test parameters are also in place to investigate gold recovery improvements in the flotation process.
- Results from a mineralogy review for gold deportment by G & T Resources Ltd. of the mineralization at Copper Flat have been received. The Automatic Digital Image System review indicates that an opportunity exists to increase gold recovery through gravity separation. A test protocol is in progress with FL Smith Knelson Concentrators to fully quantify the increase in gold recoveries.
- Settling and rheological characterization tests are scheduled with Pocock International, Inc. to validate the sizing of process equipment and previous test work completed in this area.

"Initial metallurgical test work results for Copper Flat are very exciting," said Andre J. Douchane, CEO. "Increasing design throughput from 17,500 tpd, from our June 2010 PEA, to 25,000 tpd, while keeping

the same mill foundation footprint, is a real win for the project. This potential increase in throughput will impact the project's payback of capital expenditures and profitability in a very positive way. The enhanced gold recovery potential seen in these test results is also very encouraging, leading us to believe that gold will be a major contributor to the project's economics."

The continuing metallurgical test work is scheduled to be completed during second quarter of 2012, in time to be included in the Copper Flat prefeasibility study.

About THEMAC Resources Group Limited

THEMAC is a copper development company with a strong management team and as of May 18, 2011, a 100% ownership interest in the Copper Flat copper-molybdenum-gold-silver project in New Mexico, USA. *We are committed to bringing the closed copper mine, Copper Flat, in Sierra County, New Mexico back into production with innovation and a sustainable approach to mining development and production, local economic opportunities and the best reclamation practices for our unique environment.* The Company is listed on the TSX Venture Exchange (ticker: MAC) and has issued share capital of 74,117,622 common shares (fully diluted share capital 136,423,241).

For more information please visit www.themacresourcesgroup.com or review the Company's filings on SEDAR (www.sedar.com).

Forward Looking Statements

This news release may contain certain information that constitutes forward-looking statements. Forward-looking information and statements are frequently characterized by words such as "plan," "expect," "project," "intend," "believe," "anticipate" and other similar words, or statements that certain events or conditions "may" or "will" occur, including statements regarding: the expected throughput capacity of the mill and the effect that will have on payback and profitability; expected enhanced recoveries of copper, gold and silver based on test results; and timing of completion of test work. The forward-looking information and statements made in this press release are based on the opinions and estimates of, and assumptions made by, management at the date the statements are made. Forward-looking information and statements are subject to a variety of risks and uncertainties and other factors that could cause actual events or results to differ materially from those projected in the forward-looking statements. These factors include the inherent risks involved in the exploration and development of mineral properties, the uncertainties involved in interpreting test results and other geological and technical data, fluctuating metal prices, the ability to obtain necessary permits and approvals the availability of funds to complete work programs and studies, and other factors described above. The Company disclaims any obligation to update or revise any forward-looking statements if circumstances or management's estimates or opinions should change, except as required by applicable law. The reader is cautioned not to place undue reliance on forward-looking statements.

For further information contact:

THEMAC Resources Group Limited
Andre J. Douchane, Chief Executive Officer (+1) 416 671 8089 or (+1) 520 850 7529

Neither the TSX Venture Exchange (the "TSXV") nor its Regulation Services Provider (as that term is defined in the policies of the TSXV) has reviewed, nor do they accept responsibility for the adequacy or accuracy of this release.

3-23-2012

Vollbrecht, Kurt, NMENV

From: Menzie, David, NMENV
Sent: Friday, March 23, 2012 11:32 AM
To: Vollbrecht, Kurt, NMENV
Subject: RE: Cu Flat

Kurt,

They are jurisdictional under NM State Standards and likely jurisdictional under the federal CWA but the Corps and I have not always agreed on what should be jurisdictional under the CWA

David Menzie, Geologist
NM Environment Department
Surface Water Quality Bureau
Watershed Protection Section
Silver City Field Office
3082 32nd St., By-Pass Road, Ste.D
Silver City, NM 88061
Phone (575) 956-1548
david.menzie@state.nm.us

From: Vollbrecht, Kurt, NMENV
Sent: Friday, March 23, 2012 11:25 AM
To: Menzie, David, NMENV
Subject: Cu Flat

Hi Dave,

There was a question raised at the Cu Flat NEPA meeting Wednesday regarding the wetlands that now exists in Grayback Arroyo on the mine site. The question was whether or not the wetlands is jurisdictional?

You may not know the answer, but let me know what you do know and I will pass the info along...I'm still trying to come up to speed on the site in a general sense. Game and Fish Rachel indicated you had talked about it in the field at some point in time.

Kurt Vollbrecht, Geologist
New Mexico Environment Department
Ground Water Quality Bureau
Mining Environmental Compliance Section
(505) 827-0195

3-31-2012

Proposed Copper Flat Copper Mine
Bureau of Land Management
Las Cruces District

Environmental Impact Statement

Scoping Report
March 2012

Sierra County, New Mexico

Table of Contents

1.0 Introduction 1
2.0 Project Description 1
3.0 Notification of Scoping Meetings 2
3.1 Tribal Consultation 3
4.0 Public Scoping Meetings 3
4.1 Purpose 3
4.2 Public Scoping Meeting Materials 3
4.3 Collection of Comments 7
4.4 Summary of Comments 7
4.4.1 Issues Identified During Scoping 7
4.4.2 Regulatory (G-01) 14
4.4.3 Water Quality (PI-04a) 15
4.4.4 Support Project (CS) 15
4.4.5 Need Jobs or Job Creation (SI-06d) 16
4.4.6 Water (PI-04) 17
4.4.7 Surface Water (PI-04d) 18
4.4.8 Requests (R) 19
4.4.9 Water Quantity (PI-04b) 19
4.4.10 Groundwater (PI-04c) 20
4.4.11 Socioeconomics (SI-06) 21
4.5 NMCC Public Meeting Comments 22
5.0 Issues or Alternatives Excluded from Analysis in the EIS 23

Appendices (in separate volume)

Appendix A: Notice of Intent
Appendix B: Public Meeting Newspaper Notices
Appendix C: Press Release and List of Television Stations, Radio Stations, and Newspapers
Appendix D: Letter Sent to Agencies
Appendix E: Agency and Public Scoping Meetings Sign-In Sheets
Appendix F: Public Scoping Meeting Materials
Appendix G: Public Scoping Comment Form
Appendix H: Coded Comments

Tables

Table 1 – Newspapers and Dates of Public Notices 3
Table 2 – Summary of Scoping Comments Received 8

Figures

Figure 1 – Scoping Meeting at the Hillsboro Community Center 5
Figure 2 – Scoping Meeting at the Truth or Consequences Civic/Convention Center 6

02361

List of Acronyms and Abbreviations

ANP	Acid Neutralizing Potential
BLM	Bureau of Land Management
CFR	Code of Federal Regulations
DEIS	Draft Environmental Impact Statement
EIS	Environmental Impact Statement
EPA	Environmental Protection Agency
FEIS	Final Environmental Impact Statement
GHG	Green House Gases
I -	Interstate
LCDO	Las Cruces District Office
MBTA	Migratory Bird Treaty Act
MPO	Mining Plan of Operations
NEPA	National Environmental Policy Act
NM	New Mexico
NMCC	New Mexico Copper Corporation
NOI	Notice of Intent
PAG	Potentially Acid-Generating
SAP	Sampling and Analysis Plan
THPO	Tribal historic Preservation Officers
TorC	Truth or Consequences

1.0 Introduction

The New Mexico Copper Corporation (NMCC) submitted a Mining Plan of Operations (MPO) to the Bureau of Land Management Las Cruces District Office (BLM LCDO) proposing to re-start mining operations at the Copper Flat Mine located in Sierra County, New Mexico. As identified in the MPO, the Proposed Action is to re-establish a poly-metallic mine and processing facility at the Copper Flat site. The proposed mine is located approximately four miles north-northeast of the town of Hillsboro, New Mexico within portions of Township 15 South; Range 6 and 7 West; and Sections 25, 26, 31, 35, and 36.

Mining, ore processing, and related activities would occur on both private land and public domain administered by the BLM. The proponent currently holds active mining claims over public domain land included in the proposed operation. NMCC proposes a mine permit area encompassing all five sections which would be divided between public lands (745 acres) and private estate (841 acres). At full development the pit would be approximately 2,500 by 2,500 feet and 900 feet deep. The BLM LCDO will prepare an environmental impact statement (EIS) to assess the restart, development, and operations of Copper Flat at the existing mine site in Sierra County. The entire project is also subject to the regulatory jurisdiction of the State of New Mexico.

This report describes the Proposed Project, agency and public scoping meetings and materials, and summarizes substantive public comments received during the public scoping period held from January 9, 2012 through March 9, 2012. In addition, a separate volume includes eight appendices of supplemental information as follows:

- Appendix A: Notice of Intent
- Appendix B: Public Meeting Newspaper Notices
- Appendix C: Press Release and List of Television Stations, Radio Stations, and Newspapers
- Appendix D: Letter Sent to Agencies
- Appendix E: Agency and Public Scoping Meetings Sign-In Sheets
- Appendix F: Public Scoping Meeting Materials
- Appendix G: Public Scoping Comment Form
- Appendix H: Coded Comments

2.0 Project Description

New Mexico Copper Corporation submitted a Plan of Operations to the BLM LCDO proposing to restart the Copper Flat Mine located in Sierra County, New Mexico. The Proposed Action identified in the MPO is to re-establish a poly-metallic mine and processing facility at the Copper Flat site. The proposed mine is located approximately four miles north-northeast of the town of Hillsboro, New Mexico. Lands involved in the mine would include parts of the following: Township 15 South, Range 6 and 7 West, and Sections 25, 26, 31, 35, and 36. Total surface disturbance associated with the MPO would be 1,586 acres, which would be divided between public lands (745 acres) and private estate (841 acres). The existing pit would eventually be enlarged to 2,500 feet by 2,500 feet and would reach an ultimate depth of 900 feet. This would mean that the proposed pit would disturb an additional 17 acres of mostly private

02363

land. No smelting of copper ore would occur on-site. Mill concentrate would be transported by truck approximately 40 miles on State Route 152 and Interstate 25 (I-25) to rail facilities in Rincon, New Mexico, where it would be shipped to a smelter in Arizona or port facilities. NMCC currently projects an operational life of 17 years and an additional 15 for reclamation and post-closure monitoring.

- Mine development includes baseline data gathering, initial site development and construction, which would be conducted to facilitate mine construction and operation.
- Mine operation consists of the activities related to production of copper ore from the mine, and transport of the ore offsite for mineral processing. The production phase would last approximately 17 years.
- Mine reclamation is designed to remove surface facilities, re-contour the disturbed area, replace stockpiled soil, and establish vegetation suitable for the post-mining land use of grazing and recreation.

The BLM LCDO issued a Notice of Intent (NOI) in the *Federal Register* on January 9, 2011 to prepare an EIS for this project in compliance with the National Environmental Policy Act (NEPA), and the Council on Environmental Quality's regulations for implementing NEPA (40 Code of Federal Regulations (CFR) Parts 1500–1508). Exploration and mining activities on BLM-administered lands are controlled by the regulations of the Secretary of the Interior contained in 43 CFR, Subparts 3715 and 3809 and for Wilderness Study Areas, 43 CFR, Subpart 3802. These regulations require mining operations to protect public health, prevent unnecessary or undue degradation of the land, and minimize adverse environmental effects on BLM surface resources.

To provide agencies and the public with a general understanding of the proposed Copper Flat Mine project – pursuant to Section 102 (2) (c) of NEPA – the EIS will evaluate the environmental impacts of the proposed Plan of Operations and determine whether to approve the Plan as proposed or to require additional mitigation measures to minimize impacts to the environment, in accordance with BLM regulations.

3.0 Notification of Scoping Meetings

As noted above, an NOI was published in the *Federal Register* on January 9, 2012, informing the public of BLM's intent to prepare an EIS. The notice also explained public scoping meetings would be held with 15 days prior notification in local media. These local media ads notified the public that the public scoping meetings would be held in Hillsboro and Truth or Consequences on February 22nd and 23rd, 2012, respectively. A copy of the NOI and administrative memorandum are provided in Appendix A.

Notices were printed in local newspapers in the weeks preceding the public scoping meetings, including an advertisement that identified the meeting times and locations. A list of the names of the publications and dates of these advertisements and legal notices are included in Table 1. Copies of the newspaper advertisements and legal notices are included in Appendix B.

Table 1 – Newspapers and Dates of Public Notices

Newspaper	Publication Dates	Location
Albuquerque Journal	2/7/2012	Albuquerque, New Mexico (NM)
The Herald	2/7/2012	Truth or Consequences, NM
Las Cruces Sun-News	2/7/2012	Las Cruces, NM
Las Cruces Bulletin	2/10/2012	Las Cruces, NM
Sierra County Sentinel	2/10/2012	Truth or Consequences, NM

3.1 Tribal Consultation

Tribal leaders and Tribal Historic Preservation Officers (THPOs) received letters with similar information provided to the agencies as well as information on the National Historic Preservation Act (NHPA) Section 106 consultation process. Tribal consultations are pending more project details.

4.0 Public Scoping Meetings

The BLM LCDO conducted two public scoping meetings with an open-house followed by a presentation and public comment session. The first was held from 7-9 p.m. on Wednesday, February 22nd in Hillsboro, NM at the Hillsboro Community Center on Elenore Street; the second was held from 7-9 p.m. on Thursday, February 23rd in Truth or Consequences, NM at the Truth or Consequences Civic/Convention Center on 500 West Fourth. Photos from each open house meeting are shown on the next pages.

4.1 Purpose

The purpose of the public scoping meetings was to provide the public with information regarding the proposed project; answer questions; identify concerns regarding the potential environmental impacts that may result from development and operation of the project; and gather information to determine the scope of issues to be addressed in the EIS.

4.2 Public Scoping Meeting Materials

The open-house portion of the meeting was used to encourage discussion and information sharing and to ensure that the public had opportunities to speak with representatives of the U.S. Bureau of Land Management, Las Cruces District Office; State of New Mexico; and New Mexico Copper Corporation. Several display stations with exhibits, maps and other informational materials were staffed by representatives of the BLM LCDO, State of New Mexico Minerals and Mining Division, State of New Mexico Environment Department, NMCC, and Mangi Environmental Group to answer questions. Additionally, BLM and NMCC provided fact sheets and informational materials at the meetings. Information stations at the public scoping meetings included the following:

- Sign-in and Welcome table
- Project Overview, Purpose and Need
- General Copper Flat information
- Two "Parallel Processes – NEPA/EIS and New Mexico Permit Reviews" Posters

- "Cause-and-Effect-Questions" © Diagram

Sign-in sheets (Appendix E) and comment forms (Appendix G) were made available to all scoping meeting attendees. Attendees were invited to write comments and questions directly on the Cause-and-Effect-Questions diagram, which is included in Appendix F.

Figure 1 – Scoping Meeting at the Hillsboro Community Center

Figure 2 – Scoping Meeting at the Truth or Consequences Civic/Convention Center

4.3 Collection of Comments

Public comments were submitted via comment forms, letters, emails, faxes, website, a 1-800 number, and orally during the meetings to a court recorder. All comments were delivered to either the BLM LCDO or Mangi Environmental Group. A summary of the public comments received and organized by category is provided below. Appendix H is a copy of every comment received with the coding (mark-up of issues raised). Each commenter was assigned a two-part code: commenter's initials followed by a number assigned in consecutive sequence. For example, the first commenter with initials AC would be AC01 and the second person with the same initials would be AC02 and so on. Appendix H has the comments in order of commenter code. The exception is that any comments made during the public meetings are at the end of Appendix H because they contain multiple people's comments.

An Access database was created to allow for viewing the issues raised by a commenter or all the commenters that raised that issue. Due to Access's limitation to 255 characters including spaces, the actual commenter's words may have been abbreviated to fit the space limitation without losing the intent.

4.4 Summary of Comments

A total of 115 submissions were received during the scoping comment period from 94 commenters. The transcript from each scoping meeting was considered a single submission. The vast majority of submissions voiced concerns or raised issues on more than one topic. Multiple people provided more than one submission. Some people utilized multiple methods to provide the same submission (e.g. email and hard copy). These duplicate submissions are being kept on file, but the comments in the submission were only considered once in this document. Public comments were submitted via letter, email, fax, the 1-800 number, website, and comment forms distributed at the public scoping meetings and by mail as well as oral comments dictated at the public meetings and recorded in the meeting transcripts by the court recorder (also included in Appendix H). Submissions include those made by private citizens, elected officials, government agencies, and entities and representatives of non-governmental organizations. No form letters were received.

4.4.1 Issues Identified During Scoping

Following is a summary of issues identified through the scoping process which will be addressed in the EIS relative to the resource topic area (Table 2). Because water was a known major issue, separate codes were created for main aspects, such as water rights, water quality, and groundwater, to better understand specifically what the public's concerns regarding water were. The general water code was reserved for other concerns, such as hydrology. A similar situation exists with biological resources and socioeconomics. There is overlap between the codes when the commenter voiced more than one issue in that sentence(s) and due to the interplay between the NEPA aspects.

02369

Table 2 – Summary of Scoping Comments Received

Resource Area	No. of Commenters	No. of Comments	Summary of Issues
Alternative (A)	7	45	Consideration of less water-intensive option(s) and alternatives plans for accidents or dust management. Concern for lack of alternatives in NOI and water treatment issues. Suggestions by NMCC and EPA (RS01) about alternatives' parameters, such as less than 24 hour schedule.
Biological Resources (BI) (e.g. nature, environment, etc.)	16	29	Need for environmental studies and environmental protection, especially from wastes. Concerns about harming the environment.
Threatened and Endangered Species (BI-01)	5	13	Provided information on these species. Concerns about the Chiricahua Leopard Frog (Endangered), common Blackhawk, and bald eagle (both NM Threatened). Do Biological Assessment.
Wildlife (BI-02)	18	94	Impacts from nighttime operation, exposure to waste products particularly water (pit and tailings). Impacts from reduced water quantity. MW01 listed ways to handle the pit. Harm restoration of blacktailed prairie dog and bolson tortoise. Increases in road kill. Need for monitoring.
Vegetation (BI-03)	19	54	Grayback Arroyo is a distinct vegetation type. Concerns for the Arizona sycamores, especially along Animas Creek. Water quantity impacts to vegetation, especially riparian habitat. Reduction of population/capacity. Impacts to irrigated crops. Impacts from spills/leaks. Concerns with noxious weeds/exotic plants.
Avian and Migratory Species (BI-04)	3	5	Migratory Bird Treaty Act (MBTA), interruption of migratory patterns due to dust or noise.
Oppose Project (CO)	19	29	General opposition to the project, citing irresponsibility to allow mine, water, and/or other environmental concerns.
Support Project (CS)	25	39	General support of the project, citing new jobs and capital, and positive experience(s) with NMCC.
Successful Mining Earlier (CS-01)	5	6	Statements that the mine worked well earlier.

Resource Area	No. of Commenters	No. of Comments	Summary of Issues
General and/or Data on Resources (G)	17	65	Requests for new data (as opposed to reliance on 1999 EIS) and missing data in MPO and other NMCC reports. Provided/requested data on different resource areas. Issues with earlier Alta groundwater data. Suggestions by Environmental Protection Agency (EPA) on scope and content. Proponent requests to limit analysis and required new information as well as to include data forthcoming.
Regulatory (permitting, laws, etc.) (G-01)	20	116	Concerns regarding regulatory constraints; and requests to follow regulation to the maximum. Questions/concerns about the 1872 Mining Act, necessary permits/conditions of permits. Noting NM Mining and Minerals Division does not allow mines requiring perpetual care. Questions/concerns about water rights and bonding. Suggestions for additional cooperating agencies.
Cumulative Impacts (G-02)	8	31	Questions regarding interactive impacts with other mining interests, water use, and climate change. Regulations and suggestions provided from EPA.
Possible Mitigation (M)	8	37	Pit and wildlife mitigations suggested, monitoring to allow for corrective actions, and request for mitigation plan or description in EIS. Several suggestions by EPA.
Operations (designs, processes, etc.) (OI)	17	122	Various questions regarding operation activities and design, the processing location of the copper, and plans for scenarios like accidents.
Suggested Operations (OI-01)	7	144	Suggestions for various aspects of the design, such as possibility of treated water re-injection for waste management and water resue.
Physical Resources (PI)	1	3	Requests to collect data and disclose impacts to geochemical and physical environment.
Geology and Sediment Conditions (PI-01)	9	38	Concerns with current status including contamination of soil, ability of soil to handle wastes. Requests for studies. Concerns about faults, erosion, and soil pollution. Suggestions from EPA on scope.
Mineral Resources (PI-02)	9	25	Questions about mining claims, release of minerals, such as uranium, from rocks, and contamination.

Resource Area	No. of Commenters	No. of Comments	Summary of Issues
Wetland Resources (PI-03)	3	12	Concerns about existing wetland conditions, potential impacts to water, and wastes on wetlands. Many EPA suggestions.
Water (e.g. general hydrology or water concerns) (PI-04)	27	78	Concerns about general water impacts, specifically from waste management activities and spills. Request to provide baseline data and studies. Suggestions by EPA on scope.
Water quality (PI-04a)	22	133	Concerns about water contamination mostly from spills and waste management, especially the tailing pond.
Water quantity (PI-04b)	36	146	Concerns about water levels with regards to shortages during droughts. Cone of depression concerns. Questions regarding duration and quantity of water withdrawal.
Groundwater (PI-04c)	40	168	Concerns about other wells and water table, groundwater contamination, and cone of depression. Impacts to geothermal forces of hot springs.
Surface Water (PI-04d)	29	98	Concerns about "pumping" impacts to surface water and to quality and quantity of run-off. Many citing concerns over Animas and Percha Creeks, Caballo Reservoir, and Rio Grande River.
Water Rights (PI-04e)	13	58	Concerns about impacts to existing water rights/pumping before the completion of EIS. Many questioned validity of NMCC's water rights and requested ruling from Office of State Engineer.
Air Quality (PI-05)	14	59	Questions on the types and sources of pollution as well as potentially affected areas. Many concerns about dust, especially from piles and tailings; dust's contaminants; and visual quality, such as nighttime sky. Several mentioned regulations and permits.
Sustainability (PI-06)	5	8	Questions about recycling wastes, existing minerals, and water quantity. Desire to become resource independent.
Climate Change (PI-08)	6	10	Concerns that the project would exacerbate climate change issues, specifically drought and temperature, greenhouse gas emissions, and insistence that climate change be included in impact analysis.
Requests (e.g. general requests for the process or for the EIS) (R)	30	158	Requests ranged from studies, to process, to analysis. See Section 4.4.8 for details.

Resource Area	No. of Commenters	No. of Comments	Summary of Issues
Request Draft EIS (R-01)	2	2	Two requested copies of the Draft Environmental Impact Statement (DEIS).
Request General Data (R-03)	9	17	General informational questions and requests for modeling and studies on hydrology and specific socioeconomic resources.
Request Scoping Period Reinitiation (R-04)	1	1	Felt the scoping meetings were more town hall events than scoping meetings.
Request Substantial EIS Review Period (R-05)	1	1	The public needs time to share concerns with any new information in the MPO.
Speed up Process (R-06)	7	8	Requests to utilize existing data to expedite EIS process. Requests to expedite the process to start this mine.
Recreation and Tourism (SI-01)	10	30	One commenter discussed positive tourism related to mining. Concerns about hot springs and reservoir impacts, adverse impacts to tourism, such as attractiveness of area to tourists, e.g. impacts to buildings and Scenic Byway. Impacts to birding tourism.
Visual Resources (SI-02)	7	14	Concerns that mine would generally degrade visual quality, especially due to nighttime activities (light) and dust. Scenic Byway and other road impacts.
Noise and Vibrations (SI-03)	9	18	Concerns that blasting and vibrations as well as their impacts to structures. Impacts to people and animals. Cause traffic noise pollution and nuisances; especially from nighttime activities. Based on modeling, may need to limit activities.
Transportation and Traffic (SI-04)	15	64	Questions about actual amounts of traffic, congestion, road closures, road capacities, cost of road maintenance and improvements, risks and prevention of accidents, and transportation routes/methods of transferring load. Importance of NM152. Road closures concerns. Request for traffic study.
Socioeconomics (e.g. costs and quality of life) (SI-06)	59	266	Questions about changes to quality of life and economy. Further details included in Section 4.4.11.

Resource Area	No. of Commenters	No. of Comments	Summary of Issues
Human Health and Safety (SI-06a)	18	67	Concerns about exposures to hazards including hazardous chemicals and wastes, and general accidents including transportation incidents; and requests to identify and address risks/hazards. Questions about long-term health issues for workers and community; as well as the relationship between clean water and air and the public health.
Environmental Justice (SI-06b)	7	7	Discussion about poverty and welfare. EPA commented about following Executive Order 12898.
Need Jobs or Job Creation (SI-06d)	25	51	Several stated the community need for jobs.
Concern for Job Loss (SI-06e)	3	7	Concerns that the mining activity would cause for a decrease in other jobs, such as tourism or farming, and could preclude other jobs in the future due to water usage. Concerns over impacts over potential for project to go bankrupt.
Tax Base (small or need to expand) (SI-06f)	6	6	Area needs a larger tax base. They believe the project will help this.
Tax Revenue Increase (SI-06g)	10	27	Comments support the positive benefits the project's tax revenues would provide, such as improved infrastructure.
Historical Issues (SI-07)	2	2	Concerns about the "historical" sycamores.
Public Services and Infrastructure (SI-09)	19	54	Concerns about the capacity and responsibility for the cost of needed improvements and maintenance of infrastructure, such as roads and health care services. Concerns about degradation of water infrastructure. Also, positive statements of infrastructure improvements.
Land Use (including reclamation) (SI-10)	19	44	Concerns about conflicting land uses (agriculture, tourism, spaceport, etc.), reclamation and post-mine uses, and property values. Questions regarding quantity of disturbed land. Positives of and suggestions offered for mine reclamation.
Range and Livestock (SI-10a)	1	9	Water use and waste management impacts to ranching.

Resource Area	No. of Commenters	No. of Comments	Summary of Issues
Protected Areas (National Parks, etc.) (SI-11)	1	1	National Park Service noted no comment on project.
Wilderness Areas (SI-11b)	1	1	Concern about the Gila Wilderness.
Waste Management (SI-12)	15	99	Several expressed about the tailings pond concerns, especially its liner and stock piles. Questions on impacts from chemicals, spills and releases, such as from rocks, and lifespan/extent of these contaminants. Other inquired about plans for monitoring and responses/clean-up as well as post-mine risks. Several concerns about transportation of materials. Several recommendations made by EPA.
Hazardous Materials and Waste (SI-12a)	6	129	Questions about the potential risks of substances, including quantities and methods of cleaning up and disposal; requests for studies; and some post- operational concerns, including liner. Molybdenum and copper exposure issues. Some suggestions from EPA.
Cultural Resources (SI-13)	9	14	Concern for cultural resource damage and deterioration, especially from blasting and traffic at and around mining site. Requests to identify cultural resources and avoid them. Some general guidance from EPA.
Artifacts (SI-13)	4	4	Concerns that mining activities, especially blasting, would harm artifacts at and near the mine.
Total	704	2766	

Codes were designed in the database anticipating issues that evolved during similar mining projects. Some codes representing issues were not raised during the scoping process but may become relevant during the draft comments. There were two late comments, which brought up no new issues.

In light of the number of comments and breadth of topics, the below is a summary of the top ten issues by number of commenters in ascending order. Because water was a known major issue, separate codes were created for main aspects, such as water rights, water quality, and groundwater, to better understand specifically what the public's concerns regarding water were. The general water code was reserved for other concerns, such as hydrology. A similar situation exists with biological resources and socioeconomics. There is overlap between the codes when the commenter voiced more than one issue in that sentence(s) and due to the interplay between the NEPA aspects. Please note that the Selected Example Comments Subsection consists of comments or summarized comments collected during the scoping process.

4.4.2 Regulatory (G-01)

Summary

116 comments regarding regulatory issues from 20 different commenters were received during the scoping period. Many questioned the validity of the 1872 Mining Act, claiming it is outdated and no longer addresses modern issues. Commenters questioning the use of unpatented mining claims. Some comments were concerned with EPA regulations of the mine like how often the mine would be inspected. Some comments expressed that due to conflicts with other resource concerns, the NMCC should not be granted a mining permit. Some commenters felt that mining regulation would constrain economic progress, and as such, the NMCC should be exempt from permitting and regulations in light of the current economic situation. Several requested that the NMCC apply for state and federal permits to regulate water use, air quality control measures, Department of Transportation safety regulations, and hazardous materials regulations. Some commenters were unsure of the need for a new EIS is mandated since the 1999 EIS was stopped due to copper prices and not because a final decision was made.

Selected Example Comments:

- For hazardous products stored on the Copper Flat Mine site, will there be an EPA inspector on site at all times or might EPA be doing inspections periodically?
- We also are very concerned that the subdivisions of governments being consulted and participating in this process does not apparently include NM Department of Transportation.
- Since the various owners of the rights NMCC has acquired have failed to use the water for over 29 years, the rights must be considered invalid. Besides the law of forfeiture for non-use, non-use is grounds for a charge of abandonment.
- The EIS should identify water bodies in the analysis area that have been placed on the New Mexico 303(d) list.
- The DEIS should analyze the ability of the mine to comply with future National Pollutant Discharge Elimination System requirements. The DEIS monitoring program should also be analyzed to determine if it is compatible with future permits.
- I am concerned that with no regular monitoring following the reclamation phase of the Copper Flat mine, a leakage or a breach could get into the local ground water and contaminate it with toxins.

4.4.3 Water Quality (PI-04a)

Summary

133 comments regarding water quality from 22 different commenters were received during the scoping period. These comments mainly raised concerns about mining practices polluting the ground water through seepage or nonpoint source pollution. Several commenters posed questions regarding the water treatment and management of the open-water pit. There was also some concern that the open pit would attract wildlife that may then consume contaminated water. The use of pit water to control dust was addressed in terms of impacts to air quality and potential pollution, where the water would be sprayed. Others concerns included the potentially indirect water quality impacts to the local population, wildlife, and agriculture.

Selected Example Comments:

- What are all the potential sources of water pollution at the mine, potential contamination pathways, vulnerable communities and environments, and means to prevent such pollution?
- How will surface water run-on and run-off be controlled and minimized?
- What will the quality of the pit water be?
- The EIS should present historic water quality data for the existing pit lake, including uranium concentration, in tabular form, and modeled predictions of future pit lake water quality.
- Pit water is high in total dissolved solids and sulfate concentrations and sometimes higher than allowable in copper concentration and acidity so as to be possibly toxic to wildlife.
- We have clean, wonderful water, and I would hate to see it depleted and polluted by any mining operation.
- The pit violates all well regulations designed to prevent groundwater contamination through the well. It is not sealed from surface water runoff, having no barrier protecting groundwater from oil and gas drippings from trucks & mining equipment, etc.
- Pit water will be acidic and contain metals, including uranium. If used for dust control, as planned, will airborne dust that will be entrained by the strong regional winds contravene the Clean Air Act?
- What are the short and long term costs to Sierra County residents for health issues relating to air and water pollution from Copper Flat?
- Why should the monitoring of water quality around the tailings impoundment last for only 12 years? The threat of water pollution from that impoundment is perpetual. How long do synthetic impoundment liners last? How long has the existing liner been in place?

4.4.4 Support Project (CS)

Summary

39 comments were received from 25 commenters that support the project. These commenters addressed past mining operations and their experience(s) with both Quintana and NMCC. Many

02377

commenters spoke positively of past mining as a good source of jobs and use of the land. Several complimented NMCC on their public involvement.

Selected Example Comments:

- The production well and a lot of the pipeline leading to the mine is on my ranch. When Quintana Minerals developed these, it was a win-win situation for both of us and they never did anything here without first consulting me. It has been the same with NMCC.
- This part of Sierra County has been a mining and ranching area for 150 years. This is the best and most productive multiple-use for this land.
- America runs on mining and minerals. The American people need copper. The American people need gold and other precious minerals.
- I too grew up with a little rock hound in me [like her father], a love for the mining industry and a respect for the value it could offer to our area. This is mining county. It is a wonderful way to grow up. It is our right.
- She knows that NMCC has put a lot of money and thought into the project. I understand fully what they have to go through to prove not only to NMCC that this is the right step, but to BLM, Sierra County, and all the environmental & wacko people here.
- We see the mine going into operation as a positive, not just because of the economic impact it will have but the reclamation of the currently disturbed land.
- I was pleasantly surprised to see your timeline as you spoke tonight on what needs to be done. I hope that we continue to move aggressively, because we do need jobs, we need economic development in our communities, and we strongly support it.
- I feel that the Copper Flat Mine will face various hurdles to achieve their project and I support their effort.

4.4.5 Need Jobs or Job Creation (SI-06d)

Summary

51 comments from 25 commenters addressed the need for jobs and job creation in Sierra County. Many commenters were concerned with the current economy in Sierra County. Several comments argued that young people and families were leaving the area because they could not find work and were not hopeful about the growth of existing businesses and services. Some were also interested in the increased taxes and tax base that the mine would bring to the community, and increased revenue at local businesses. However, some were concerned that the trade-off between current mining activities and other, more permanent, developments and use of water would not be enough to sustain the community long-term.

Selected Example Comments:

- The private sector companies are struggling to provide jobs and services. Not a week or month goes by without someone asking for a job.
- Lack of local opportunities for youth with and without college. Copper Flat will provide training & jobs for those with little or no experience. Give Mine Safety and Health Administration training and certification
- Downtown Truth or Consequences (TorC) was either boarded up or art galleries. There is nothing for the young people, except fast food. Little young families since no place for

them to work unless city, county, or state or phone company where established people with few openings.

- The reclamation of the Copper Flat Mine would generate economic development within Sierra County. This project would also generate much-needed employment opportunities for the citizens of our County.
- The job situation is linked to water. And the creation of jobs by the mining industry is relatively inefficient. That is almost all the other industries create more jobs for the same amount of water.
- Groesbeck, Texas is a town half the size of TorC but has brand new infrastructure. The money came from taxes from the mine - the thing that's going to help our community. Not only to provide jobs, but to provide a tax base and much needed county services.
- Job creation and tax revenues in the community. Employing local people in a variety of direct and indirectly related jobs, as well as generating significant tax revenues, would offer important economic benefits to Sierra County and its communities.

4.4.6 Water (PI-04)

Summary

78 comments from 27 commenters concerned water. Water issues are connected to the local economy in terms of water rights and water quantity, and many commenters were concerned with the amount of water proposed to be used by the mine and impacts to groundwater and stream levels. There are many concerns with water quality and quantity and how this will affect the people, plants, and animals in the area. Several comments requested information on how water would specifically be used, treated, and monitored during the mining processes. The pit and the pit water were also mentioned, with concerns about potential runoff and how the water will be treated before used to control dust. Commenters expressed concerns about mining operations either polluting local wells or lowering the water table to the point of rendering the local wells useless.

Selected Example Comments:

- How would the design of pits, ponds, and lagoons prevent leakage, overflow, and access by birds and other wildlife, etc.?
- Holding pond for water from the pit may pollute ground water.
- Using pit water for dust control spreads the concentration of metals on the land surface susceptible for migration.
- What is the extent, nature and cause of existing pollution at the site, what reclamation is currently underway, and how will this impact the proposed?
- We think serious geological, hydrological, and biological studies are needed for this alternative treatment of the pit waters as surface water.
- My concerns are about the acute and chronic health effects to our local communities, which include those nearby and downwind or downstream from the site and along the transportation corridor.
- The NOI states that the "total estimated disturbance on public domain land would be 745 acres" When mine's air and water pollutants dispersal is included, how much public land

is "disturbed"? What about along the shipping route for the concentrates? These numbers need to be made public.

- There is known contamination from existing tailings, the nature of the pit as a flow through or hydraulic sink has not been adequately proven and the extent of existing contamination appears to be downplayed in the SAP submittal.
- Channeling water is stealing water from all the roots of the sycamores.

4.4.7 Surface Water (PI-04d)

Summary

98 comments from 29 commenters concerned surface water, mainly focused on water quantity and water quality. Commenters are concerned that mining operations would reduce stream levels and pollute surface water areas, which can affect wildlife, plants, and livestock operations. There is concern that the aquifer would be permanently affected by mining activities and this drawdown would affect surface water over the long term.

Selected Example Comments:

- What is existing quality of surface water?
- How would surface water run-on and run-off be controlled and minimized?
- Cone of depression at the mine might lower surface water levels in the Animas Creek watershed.
- Disruption of surface waters and a complete system of seeps, seasonal seeps, springs, natural seasonal ponds, etc. might affect the Animas Creek watershed system.
- What will the cumulative impact of the Mine's use of water be, including the drawdown caused by its production wells and evaporation from the open pit?
- The effect of prolonged pumping at projected consumption levels on existing residential and commercial wells in the area is a huge concern of ours.
- The EIS should include rigorous hydrologic modeling that details the probability, extent, and intensity of potential drawdown impacts on surface aquatic and riparian habitat.
- There are a few small perennial and intermittent riparian areas in Grayback Arroyo that are believed result from alterations in stream flow associated with the previous mine development.
- The watershed drains into the Rio Grande River, which is crucial for downstream farming and agriculture livelihoods.
- Use of water from the pit lake would, then, require an application to the Office of State Engineer for appropriation of surface water and a review of the effects upon the whole system of surface waters in the area.
- Contamination from spoil piles will continue to infiltrate or runoff into the pit lake after mining is discontinued. The contaminated water is dangerous to wildlife and ranch stock and will contribute acid mine drainage to the groundwater.

4.4.8 Requests (R)

Summary

30 commenters provided 158 requests, ranging from requests for specific data to operational suggestions. Some commenters specifically utilized the word request while others used wording that indicated they were requesting something to be done. Many requested surveys and resource analysis plans for topics such as historical water quality and regime, wildlife surveys, socioeconomic reports and projections, and reclamation plans. Some commenters were concerned about the longevity of the mine and the possibility for copper prices to drop and for the mine to bankrupt. Many commenters were interested in the progress of the EIS and mine and requested their names be added to the mailing list.

Selected Example Comments:

- I request that the BLM take immediate action to prevent pre-EIS completion pumping, and that they make NMCC provide a bond equal to any potential damage to the surrounding wells or aquifers to ensure they will not do any massive pumping.
- Proposal that no water be used until mine permit is issued, after hydrology study is complete, and that the NMCC must bond water use for several million dollars.
- If it is unavoidable to initiate activity during this general bird breeding season due to MBTA, nest surveys should be conducted by a qualified biologist, and actions taken to avoid destruction or disturbance of breeding birds.
- Request for an analysis of risk reduction in the use of double liners.
- Since NMCC has stated that it can operate the mine as long as copper prices stay above $3 a pound, we also would like a Monte Carlo estimate of the possibility of that historically exceptional price level enduring for the 17-year projected mine lifetime.
- Can you send me the declarations of the pre-basin water rights owned by Frost and Gray and NMCC? Or can you just tell me what uses they can put the water to?
- Hillsboro Water requests of BLM that a fully scoped and funded Social Impact Assessment be included in the EIS with particular emphasis on the social and economic disruption of the Cu Flat proposal on the water supply of Hillsboro.
- Lack of specificity in Plan of Operation makes any adequate EIS impossible. Alternative: redo Plan after having decided on chemicals, dams, linings, water, etc.

4.4.9 Water Quantity (PI-04b)

Summary

146 comments from 36 commenters were concerned with water quantity. Commenters were concerned that the water use of the mine coupled with potential water pollution would affect the amount of safe drinking water available to the people, agriculture, plants, and wildlife of Sierra County. Several comments asked how they can be assured that the amount of water proposed to be used would not affect the amount of water available for other uses or permanently deplete the aquifer.

Selected Example Comments:

- How will you be able to ensure fresh drinking water for all those residents during these droughts?
- Copper Flat's groundwater withdrawals will affect Hillsboro Water's water supply both in terms of the quantity of the water available and in terms of the water available.
- Hillsboro Water requests of BLM that a predictive assessment and modeling protocol be developed which will determine when the water supply will be stressed to the point of endangering the safety, welfare, and livelihood of the members of Hillsboro Water.
- The required amount of water needed to extract ore from this open pit mine is reason enough to prohibit this operation from being permitted.
- With the effects of climate change and forecasts for long-term drought in this desert location means that the aquifer that supplies water to Hillsboro and surrounding rural communities could be depleted making this part of Sierra County uninhabitable.
- Because water will undoubtedly become increasingly limited in Sierra County, the large proposed rate of pumping by the mine has the potential of serious impacts on native vegetation and wildlife species.
- Replenishment of those waters removed by dewatering, through injections into the ground away from the pit, is equally uncertain since the area is highly fractured. Thus dewatering may profoundly affect the water levels in Hillsboro, only three miles away.
- Our small Mutual Domestic system here in Hillsboro is very concerned of losing our water supply. Okay we've heard "it's not been proven yet." What is their plan if we do run out?

4.4.10 Groundwater (PI-04c)

Summary

168 comments from 40 commenters were about groundwater. Commenters were concerned that mining activities might either reduce available groundwater or pollute the groundwater, which in turn would affect the community and environment. There is also concern about the development of a cone of depression if mining operations pull water from the aquifer, and how this would affect wells, surface water, and wildlife. Some commenters questioned water use during droughts and water conservation practices in general to maintain the groundwater.

Selected Example Comments:

- My concern is for the groundwater that will be flowing from this mine after use that could contaminate drinking water for residents east of the mine site to the river.
- What are the most likely contaminants that could inadvertently be released into groundwater, and in what amount?
- Cone of depression at the mine might reduce well production in the area generally and at Hillsboro specifically.
- What will be the rate and extent of drawdown caused by the Mine's operations, and how will this drawdown impact existing water users, water rights, surface flows, and springs, etc.?

- Reduction of streamflow by lowering of groundwater table in Las Animas and Percha Creeks could damage or eliminate deciduous riparian forests that provide essential habitat for virtually all wildlife species in the region.
- Sierra County's groundwater water supply is diminishing from drought but use. Uses in county need to conserve water, which is supported by New Mexico laws & regulations that allow legal challenge of water use on grounds of water conservation.
- Sometimes the cottonwoods lose their leaves in July for lack of groundwater. Years ago when Copper Flat first opened, the wells were pumping sand within three months.
- In the March 1999 Preliminary Final Environmental Impact Statement for the Copper Flat Project page 4-12, last paragraph, it is stated "Private wells in the Palomas Basin may experience a drawdown of 2 to 10 feet during groundwater withdrawal." Note that all of this is for a 10 year period of pumping, not 17.
- While NMCC may now be making an effort to update data, they are a long way from disproving 1998 Daniel D. Stephens & Associates' findings and adequately filling data gaps needed to provide comprehensive characterization to assure protection of aquifers, streams, and other public land resources.

4.4.11 Socioeconomics (SI-06)

Summary

266 comments from 59 commenters concerned socioeconomics. The comments addressed the current state of Sierra County's economy and the pressing need for jobs and increased tax revenue. Some commenters suggested using the mine as a source of tourism as well. However, other commenters were concerned that the presence of the mine and mining operations might negatively impact current tourism revenue that depends on the quality of the environment and surface water recreation. Several comments requested information how the community might be compensated for potential problems associated with mining such as loss of land use and water (both quality and quantity). Information was also requested on how the loss of land and water use might affect the economy. Some commenters stated that the mine is an economic opportunity and there may not be other economic opportunities as large in the future for the area.

Selected Example Comments:

- Will there be compensation to the residents and their livestock when water becomes not usable?
- No other operation of this sort, with the large number of opportunities that Copper Flat will provide has existed in Sierra County for many decades, and none is likely in the foreseeable future.
- When the mine is in operation, I plan to include the location as a stop on four itineraries for group tours. Visitors can learn about the copper mining process and how useful copper is in our daily life.
- Opportunities for positive effects to Sierra County's economy, like many rural western counties with large federal and state land holdings, are rare and cannot be squandered.
- Hillsboro Water requests of BLM that a fully scoped and funded Social Impact Assessment be included in the EIS with particular emphasis on the social and economic disruption of the Copper Flat proposal on the water supply of Hillsboro.

- Damage to tourism is a cultural and aesthetic quality of life issue.
- Provide indemnification for preventing other claim holders from working their claims.
- Draining on electrical grid might have negative repercussions in Hillsboro.
- How will the long-term post-mining value of the land and environment be preserved? What are the post-mining land uses?
- Without a tax base our infrastructure will continue to degrade, we may not be able to improve healthcare, etc.

4.5 NMCC Public Meeting Comments

Although NMCC's meetings were not part of the NEPA process, NMCC provided a list of concerns. Any of the concerns that were not raised by the public during the scoping period are below.

- How to avoid human error and inspectors.
- Use existing structure to minimize disturbance.
- Use building color that matches or is compatible with the natural environment.
- Potential impact from permanent engineering structure on stream channel post-closure.
- Post-closure activities could take more than 10 years, what is the time table?
- Issues that power lines, especially to production wells, will be used by birds.
- What is the neutralization process, and are there enough neutralizers in the rock, i.e. Calcite, feldspar, dolomite? What are the byproducts from, for instance, the reaction of iron compounds/materials with neutralizers?
- Exceeding acid rock evaluation and future volume increases-need geochemical evaluation, and evaluation of biological (acid bacteria) that use or survive on acid producing area
- EIS should avoid use of "approximate" and/or "approximately" as it shows uncertainty, and thus need to evaluate this uncertainty (%) and confidence level of the evaluation.
- Assumptions should be supported by "methods" and "literatures", etc.
- How will EIS address post-closure impacts of channel diversion and road constructions? Indirect effect on ephemeral water and flood plain-ecosystem should be described in the EIS.
- Use of particle trap and other controls to reduce emissions and air pollutants, use of trap controls that reduce 80% of the particles and new equipments and vehicles.
- Greenhouse Gases.
- Mercury air emissions and air pollutants need to be considered because of the elderly community near the mine.
- Potential future hot spots in the mine to Cabala Lake, such as seepage release into the environment.
- What is the deficit (for neutralizer rocks), and are these rocks used in the area for water resources?
- Identify various receptors for air quality analyses and radius of the impact(s).
- Kinetic testing for waste rock to evaluate acid neutralizing potential, i.e. is it 1:1, 2:1, or 3:1 ratio ([Acid Neutralizing Potential] ANP: [Potentially Acid-Generating] PAG).

02384

5.0 Issues or Alternatives Excluded from Analysis in the EIS

The Council on Environmental Quality and the National Environmental Policy Act requires an agency to: "...identify and eliminate from detailed study issues which are not significant or which have been covered by prior environmental review (Sec. 1506.3)..." Non-significant issues are those that are: 1) outside the scope of the proposed action; 2) already decided by law, regulation, BLM Land Use Plans, or other higher level decision; 3) irrelevant to the decision to be made; or 4) conjectural and not supported by scientific or factual evidence.

The issues and alternatives that can be excluded from further analysis are one of the elements for an alternatives development meeting held on March 21, 2012. That meeting will provide a systematic basis for determining and supporting the elimination these issues and alternatives.

Comparison of Alternatives Used in other Projects

Project EISs discussed:
Copper Flat DEIS, 1996
Rosemont Mine EIS, Pima County AZ, Sept 2011
NorthMet EIS, St Louis County MN, Oct 2009
Emigrant Mine EIS, Elko County, NV, Dec 2010
Betze Pit Expansion EIS, Carlin, NV, Aug 2008

Alternatives Assessed

- Reduced Stripping Ratio (1996 Copper Flat DEIS). This alternative was based upon a different economic analysis that allowed for the mining of lower grade ore from the result of using a lower stripping ratio and still be profitable. They would use 3 dump sites, reduce the size of the disposal area, create a shallower pit and fewer trucks would be needed.
- Consolidated Waste Rock Disposal (1996 Copper Flat DEIS). This alternative allowed for all waste rock disposal to be deposited upon a single site thereby alleviating some additional machinery and truck.
- Phased Tailings (Rosemont EIS). The Phased Tailings Alternative incorporates a waste rock perimeter buttress that would completely surround the dry-stack tailings
- Barrel Alternative (Rosemont EIS). Places all of the tailings in different location (upper Barrel Canyon & lower portion of Wasp Canyon)
- Scholefield-McCleary Alternative (Rosemont EIS). Places all of the tailings in different location (Combination of Scholefield & McCleary Canyons)
- Use of Dual Mine Pits (NorthMet EIS)
- Mine Site Reactive Runoff as Make-up Water (NorthMet EIS)
- Development of an in-pit engineered stream channel as a permanent diversion of an existing intermittent stream channel (Emigrant Mine EIS).
- Use of the Rain Mine office and maintenance complex vs. construction of a new complex at the Emigrant Mine site (Emigrant Mine EIS).
- Regrading backfilled areas to eliminate terraces and avoid trapezoidal shaped features (Emigrant Mine EIS).
- Installation of surface water control structures to address material handling procedures, spill prevention and response, and sediment and erosion control (Emigrant Mine EIS).
- Coordination between Newmont, BLM, and local ranchers to reduce effects of mining on grazing management including development of water sources for livestock; installation of cattle guards, and new fenced corridors to accommodate movement of livestock between allotments (Emigrant Mine EIS).
- Bazza Waste Rock Facility – use of an alternate site (Betze Pit Expansion EIS).

Alternatives Eliminated from Consideration:

- Tailings Impoundment Lining (1996 Copper Flat DEIS). Lining alternatives would have technical and/or economic constraints that could potentially increase the level of impacts. Alternative was not technically or economically feasible or effective in avoiding or minimizing impacts.
- Pit Backfill (1996 Copper Flat DEIS). Two types considered – sequential and post operational. Sequential eliminated because of configuration of pit. Post Operational eliminated because it would add an additional 850,000 man hours to the end of the project making it economically unfeasible.
- Mining Other Locations (Rosemont EIS).
- Utilizing Alternative Mining Methods (Rosemont EIS).
- Mining Ore Using Shafts & Adits (Rosemont EIS).
- Reducing Pit Size (Rosemont EIS).
- In Situ Leaching (Rosemont EIS).
- Hi Temp/Hi Pressure Leaching (Rosemont EIS).
- Traditional Slurry Tailings (Rosemont EIS).
- Pit Configuration Allowing Continuous Backfill (Rosemont EIS).
- Partial/Complete Pit Backfill (Rosemont EIS).
- Waste Rock & Tailings Reconfigure/Relocation (Rosemont EIS).
- Relocating Waste Rock and Tailings to Existing Mines (Rosemont EIS).
- Avoiding Placement in Drainages (Rosemont EIS).
- Deposit Tailings on the Northwestern Slope of the Santa Rita Mountains (Rosemont EIS).
- Using a Natural Backfill Configuration (Rosemont EIS).
- Modifying the Life of the Mine (Rosemont EIS).
- Alternative Water Supplies (Rosemont EIS).
- Alternative Transportation (Rosemont EIS).
- Land Exchange or Purchase (Rosemont EIS).
- In-pit reactive waste rock disposal (NorthMet EIS)
- Off-site non-reactive waste rock disposal (NorthMet EIS)
- In-pit tailings disposal (NorthMet EIS)
- Chemical modification of reactive waste rock stockpiles (NorthMet EIS)
- Co-disposal of reactive waste rock and tailings on a lined tailings basin (NorthMet EIS)
- Pretreatment of Mine Site reactive runoff and discharge to publicly owned treatment works (NorthMet EIS)
- Pretreatment of tailings basin process water and discharge (NorthMet EIS)
- Use existing Heap Leach Facility at nearby Rain Mine (Emigrant Mine EIS)
- Modified Waste Rock facility (Betze Pit Expansion EIS).
- Offsite Waste Rock facility (Betze Pit Expansion EIS).
- Underground mining (Betze Pit Expansion EIS).
- Reduced Tailings facility (Betze Pit Expansion EIS).

DV-03
6.1 ac
AN-06
2.4 ac
AN-10
3.5 ac
WRD-03
32.3 ac
WRD-01
2.6 ac
AN-07
70.7 ac
WRD-02
18.4 ac
SEDIMENT
COLLECITON
PONDS (5)
FRESH
WATER
STORAGE
AN-03
3 ac
PIT-01
117.9 ac
GM-01
3.9 ac
WRD-04
123.2 ac
STKP-01
33.2 ac
Low
Grade ore
AN-09
69.2 ac
AN-01
43.9 ac
TAILINGS
THICKNER
MILL
MINE
SHOP
ADMIN
BUILDING
DV-01
4.6 ac
DV-02
35.8 ac
AN-12
6.1 ac
HR-01
36.6 ac
GM-02
10 ac
AN-04
11.2 ac
GM-03
13.4 ac
AN-02
16.7 ac
RD-01
10.8 ac
TLNG-01
545.5 ac
AN-05
46.8 ac
27
26
25
30
29
34
35
36
31
32
2
1
6
5
T15S/R7W
T15S/R6W
T16S/R7W
T16S/R6W

N

Feet
0 600 1,200 2,400
1 inch = 1,200 feet

EXPLANATION

Public | Plant Facilities | Waste Rock | Tailings | Pit | Diversion | Access Road
Mine Boundary | Pond | Topsoil Stockpile | Ore Stockpile | Haul Road | Ancillary

IF THE ABOVE BAR DOES NOT SCALE 1 INCH, THE DRAWING SCALE IS ALTERED

DESIGN: -	DRAWN: -	REVIEWED: -
CHECKED: -	APPROVED: -	DATE: 12/1/2010

FILE NAME: P:\GO_Fig3-01_PropFacilities_JQG_20101123

NEW MEXICO COPPER CORPORATION

COPPER FLAT MINE

DRAWING TITLE: **PROPOSED FACILITY LAYOUT**

DRAWING NO. **FIGURE 3-1** | SHEET 4 OF 28 | REVISION NO. **A**

JOB NO. **191000-03**

4-5-2012

Vollbrecht, Kurt, NMENV

From: Katie Emmer [kemmer@themacresourcesgroup.com]
Sent: Thursday, April 05, 2012 9:27 AM
To: Vollbrecht, Kurt, NMENV; Myers, Kevin, OSE; Steve Raugust
Cc: dweston@bhinc.com; Steve Finch (sfinch@shomaker.com); Anthony Hom (ahom@blm.gov); Johnson, Mike S., OSE; Mendoza, Andrea J., OSE; Jens Deichmann
Subject: RE: Hydrogeologic Analysis of NMCC Proposed Pumping Test

Kurt,

Thanks for your feedback. We'll discuss your suggestions about mentioning the NPDES permit and NOI process in this report; it is discussed in the EA itself as well. We are incorporating NMOSE comments as well.

As you know, the NPDES permit draft was published for public comment by the EPA on March 31; we'll see how that process moves forward. We remain committed to the plan to collect ground water data from the production wells and use it to submit an NOI to NMED prior to any potential discharge to the gravel quarry as we discussed in our emails with you in December 2011. Of course, we won't be doing any of this until we receive a right of way grant from the BLM.

Thanks again. We're always available to discuss any questions or concerns you might have regarding our plans and status. We'll of course stay in touch as things develop.

Katie

From: Vollbrecht, Kurt, NMENV [mailto:kurt.vollbrecht@state.nm.us]
Sent: Wednesday, April 04, 2012 6:26 PM
To: Katie Emmer; Myers, Kevin, OSE; Steve Raugust
Cc: dweston@bhinc.com; Steve Finch (sfinch@shomaker.com); Anthony Hom (ahom@blm.gov); Johnson, Mike S., OSE; Mendoza, Andrea J., OSE; Jens Deichmann
Subject: [BULK] RE: Hydrogeologic Analysis of NMCC Proposed Pumping Test
Importance: Low

HI Katie,

I have no substantive comments on what is included in the Hydrogeologic Analysis. OSE is the appropriate agency to review and comment on the details of the pump test.

Something I didn't see is a discussion of the process for acquiring an NPDES permit or submittal of a Notice of Intent to NMED for the proposed discharge locations. Perhaps this is covered elsewhere and not intended to be within the scope of this document. As a standalone document it might be prudent to at least mention how/where that is being addressed.

Let me know if you have any questions.

Kurt Vollbrecht, Geologist
New Mexico Environment Department
Ground Water Quality Bureau
Mining Environmental Compliance Section
(505) 827-0195

From: Katie Emmer [mailto:kemmer@themacresourcesgroup.com]
Sent: Tuesday, April 03, 2012 4:03 PM
To: Myers, Kevin, OSE; Steve Raugust

Cc: dweston@bhinc.com; Steve Finch (sfinch@shomaker.com); Vollbrecht, Kurt, NMENV; Anthony Hom (ahom@blm.gov); Johnson, Mike S., OSE; Mendoza, Andrea J., OSE; Jens Deichmann
Subject: RE: Hydrogeologic Analysis of NMCC Proposed Pumping Test

Kevin,

Thank you for your quick response. We will incorporate these clarifications into our *Hydrogeologic Analysis of NMCC Proposed Pumping Test* once all comments from BLM and NMED are received. As Steve Raugust communicated to you and others yesterday we plan send a letter to NMOSE with a description of our workplan for the proposed pumping test along with the finalized report as soon as it is ready; we'll copy BLM on it at that time so that they are aware.

We appreciate the time you've taken to review and provide feedback on our report and your willingness to work with us and other agencies in these efforts.

Best regards,

Katie Emmer
Project Scientist
Copper Flat Mine
THEMAC Resources Group, Ltd.

Mobile: 505.400.7925
Office phone: 505.830.6916

From: Myers, Kevin, OSE [mailto:kevin.myers@state.nm.us]
Sent: Tuesday, April 03, 2012 3:19 PM
To: Katie Emmer; Steve Raugust
Cc: dweston@bhinc.com; Steve Finch (sfinch@shomaker.com); Vollbrecht, Kurt, NMENV; Anthony Hom (ahom@blm.gov); Johnson, Mike S., OSE; Mendoza, Andrea J., OSE
Subject: [BULK] RE: Hydrogeologic Analysis of NMCC Proposed Pumping Test
Importance: Low

Katie and Steve,

As requested by NMCC, OSE Hydrology Bureau(OSE) review focused on Section 1.4 of *revised Hydrogeologic Analysis of NMCC Proposed Pumping Test* dated March 27, 2012 (Revised Report). OSE provides the following comments:

Comment 1: Overall, the Revised Report Section 1.4 provides an adequate description of proposed monitoring of MW-11, which will be a focus for discerning if the aquifer test has drawdown at this location prior to any impact of Las Animas Creek. As indicated, Las Animas Creek flows will not be the sole basis for stopping test. Observed or measured creek flows may be part of other relevant observations and measurements that may be used to evaluate the progress of the aquifer test.

Comment 2: OSE recommends adding sentence that requires, at a minimum, qualitative observations for Las Animas Creek flows near monitoring well nest of MW-9, MW-10, and MW-11. As written, Section 1.4 mentions monitoring Las Animas Creek only if water is flowing enough to place a transducer. As would be important for higher flows with quantitative measurements, qualitative observations of no flow or low flow would be equally important to document throughout pre-test, pumping and recovery phases.

Comment 3: OSE recommends that NMCC and JSAI exchange contact information with emails and phone numbers prior to the 2-week pre-test data collection phase. NMCC and JSAI should contact both OSE Hydrology Bureau and District IV.

OSE Hydrology will be the primary contact for the aquifer test and OSE District IV will be copied on daily email correspondence.

As a clarification, OSE Hydrology Bureau provides technical support to Water Rights Division, which includes district offices.

If you have any questions about the above comments, contact me.

Kevin Myers, Hydrologist
Hydrology Bureau - NM OSE
P.O. Box 25102
Santa Fe, NM 87504-5102
Ph: (505) 827-3521
Fax: (505) 476-0220

http://www.ose.state.nm.us/

From: Katie Emmer [mailto:kemmer@themacresourcesgroup.com]
Sent: Wednesday, March 28, 2012 9:05 AM
To: Vollbrecht, Kurt, NMENV; Myers, Kevin, OSE; Anthony Hom (ahom@blm.gov)
Cc: 'Denise Weston'; Steve Finch (sfinch@shomaker.com); Steve Raugust
Subject: Hydrogeologic Analysis of NMCC Proposed Pumping Test

Kevin and Kurt,

This morning we submitted to BLM the revised Hydrogeologic report regarding the setting and proposed pumping test and wanted to share it with you as well (see attached). This revision addresses comments and presents the monitoring plan we discussed in our March 16th meeting with BLM in Las Cruces. We have proposed that BLM review this report by April 4th and are hoping to schedule a call on April 5th to cover any responses they may have. If you have time and inclination, it would be great if you could take a look at this and see if you are comfortable as well. If we are successful in setting a time for a call on April 5th, we would invite you to participate if you have time.

Kevin – BLM and NMCC are both interested in dialoging with you further regarding how the monitoring during the pumping test will work. We've attempted to document it here in this report (Section 1.4), but we will be following this up with a letter to you directly so we can work something out in writing soon.

I imagine I may see you both in the interagency meeting this afternoon at 2, but I wanted to send this to you so that you have it.

Best regards,

Katie Emmer
Project Scientist
Copper Flat Mine
THEMAC Resources Group, Ltd.

Mobile: 505.400.7925
Office phone: 505.830.6919
www.themacresourcesgroup.com

4-24-13

Shore, Lawrence, NMENV

From: Shore, Lawrence, NMENV
Sent: Tuesday, April 24, 2012 2:41 PM
To: Vollbrecht, Kurt, NMENV
Subject: Copper Flat Job

Kurt,
I have filed all the loose correspondence I could find and organized them in the blue case folder 001 #7. I selected 23 documents that were related to the Stage 1 Abatement Plan, PDFed them and sent them to Bruce Frederick at the Environmental Law Center. They should keep him busy for awhile.

Larry Shore
Geologist
New Mexico Environment Department
Ground Water Quality Bureau
Mining Environmental Compliance Section (MECS)
505-827-2797



NEW MEXICO
ENVIRONMENT DEPARTMENT

Office of General Counsel

SUSANA MARTINEZ
Governor
JOHN A. SANCHEZ
Lieutenant Governor

Harold Runnels Building
1190 Saint Francis Drive (87505)
PO Box 5469, Santa Fe, NM 87502-5469
Phone (505) 827-2855 Fax (505) 827-1628
www.nmenv.state.nm.us
Ryan Flynn, General Counsel

DAVE MARTIN
Cabinet Secretary
BUTCH TONGATE
Deputy Secretary

April 23, 2012

VIA E-MAIL

Bruce Frederick
bfrederick@nmelc.org

Re: Request to Inspect Public Records

Dear Mr. Frederick:

On April 23, 2012, this office received a request for public information. You request information pertaining to: Cooper Flat Mine-Documents associated with Stage 1 Abatement Plan. (See attached request).

I forwarded your request to the bureau on April 23, 2012. The bureau will respond by May 8, 2012.

Should you have any questions, please contact the Ground Water Quality Bureau at (505) 827-0652.

Sincerely,

Melissa Y. Mascareñas
New Mexico Environment Department
Department Public Records Custodian

cc: Jerry Schoeppner, Acting Chief, Ground Water Quality Bureau

NEW MEXICO ENVIRONMENT DEPARTMENT
INSPECTION OF PUBLIC RECORD REQUEST FORM

Please fill out the following information:

1. Date: 4/23/12
2. Requestor's Name: Bruce Frederick
3. Requestor's Address: 1405 Luisa St. #5, SF, NM 87505
4. Phone No.: (505) 989-9022
5. Company Being Represented: NMELC
6. Address: Same
7. Document or File being requested to be reviewed or copied (please describe the records in sufficient detail to enable Department personnel to reasonably identify & locate the records:

Copper Flat mine - Documents associated w/ Stage 1 Abatement plan, in e-format if possible.

8. NMED Bureau where Document/File can be found (if known): Ground Water

Signature

The cost for copying by NMED is as indicated on Attachment A. Please send this request to:

Melissa Y. Mascareñas
Inspection of Public Records Officer
1190 St. Francis Drive, Ste. N-4050
Santa Fe, New Mexico 87505
or fax: (505) 827-1628

Revised 7/05/11

Vollbrecht, Kurt, NMENV

From: Vollbrecht, Kurt, NMENV
Sent: Monday, May 14, 2012 9:04 AM
To: Steve Raugust; Ennis, David, EMNRD
Cc: Shepherd, Holland, EMNRD; Eustice, Chris, EMNRD; Katie Emmer
Subject: RE: Copper Flat - Auto-Sampling & Surface Water

Steve,

DJ and I discussed this prior to his email response to you and had agreement on the path forward as presented, so consider his email to be a "joint response".

Let me know if you have any further questions.

Kurt

From: Steve Raugust [sraugust@themacresourcesgroup.com]
Sent: Friday, May 11, 2012 8:56 AM
To: Ennis, David, EMNRD
Cc: Shepherd, Holland, EMNRD; Eustice, Chris, EMNRD; Vollbrecht, Kurt, NMENV; Katie Emmer
Subject: RE: Copper Flat - Auto-Sampling & Surface Water

Thanks David,

NMCC will wait for a response from NMED, but with MMD's blessing and NMED concurrence, NMCC would propose to disable the auto-samplers in Las Animas and Percha Creeks. However, we will wait to hear from NMED to do that. We would leave them where they are or dismantle them and store until such time as the mine is operational and it makes since to re-activate them.

With respect to Greenhorn/Grayback arroyo system, the best path forward would be to keep the auto-samplers operational at least through the technical review of the BDR. Perhaps we will get lucky and catch an opportunistic sample in SWQ-1, 2, or 3 that might supplement the baseline data. However, I would argue that the surface baseline data in Grayback Arroyo is not insufficient and here is why:

- Surface water in Grayback Arroyos at the SWQ-1, 2, and 3 locations were checked each quarter from August 2010 to April 2011; specifically, August 2010, October 2010, January 2011 and April 2011.
- If the location was not dry or defensible data could not be obtained (static or stagnant water), the locations were sampled and that data presented in Appendix 8-C
- In addition, NMCC was asked by MMD to collect a sediment sample in each drainage, Grayback, Percha, and Las Animas. This was done and actually two sediment samples were collected from Grayback and the results of these samples are located in Appendix 8-D.

I would argue that this meets the minimum requirements as described in the MMD Guidance document. That said, a conservative path forward would be to maintain the auto-samplers through the formal technical review of the BDR, which would allow them NMED and MMD the opportunity to review the data in more detail and provide some guidance to NMCC should the data still be deemed insufficient at that time. I think that what this exercise is telling me is that the BDR needs to do a better job of explaining that we evaluated each location each quarter and when we had flow and collect a defensible sample, we did including sediment samples. A table in the text and the suggested denotation of dry or no flow per sampling event in Appendix 8-C would help clarify this. Guidance is a flexible concept, but we would welcome MMD/NMED advise if the surface water characterization is insufficient, because in my opinion it does meet the guidance recommendations.

NMCC will proceed on this path unless we hear differently from NMED. That path would be temporarily disable the auto-samplers in Perch and Las Animas Creeks, but maintain the auto-samplers in Grayback Arroyo at least through the technical review of the BDR.

Let me know if anyone has any issues with this plan.

From: Ennis, David, EMNRD [mailto:David.Ennis@state.nm.us]
Sent: Thursday, May 10, 2012 4:18 PM
To: Steve Raugust
Cc: Shepherd, Holland, EMNRD; Eustice, Chris, EMNRD; Vollbrecht, Kurt, NMENV
Subject: [BULK] Copper Flat - Auto-Sampling & Surface Water
Importance: Low

Steve,

MMD has reviewed both the SAP and the draft BDR with respect to the issue you raised the other day regarding continued surface water sampling. In short, MMD is of the opinion that additional surface water sampling of the Greenhorn Basin is needed in order to satisfy the requirements of the BDR. At this time, the SWQ data points do not appear to have met the minimum requirement of quarterly sampling over the course of a 12 month period. While it is understood that the SWQ locations have been largely dry (especially SWQ-1), MMD's opinion is that additional attempts to collect surface water samples are warranted from this surface water basin. As such, it is recommended that the opportunistic and/or auto-sampling program continue at the SWQ locations. MMD also recommends that Appendix 8-C be modified to reflect when these sampling locations were checked by NMCC and were found to be dry. While dry, it remains valid baseline data as it demonstrates baseline conditions, at least to some extent.

In contrast, the sampling results from Las Animas and Percha Creeks appear to adequately meet the requirements of the BDR. Therefore it is at the discretion of NMCC whether to continue the opportunistic/auto-sampling program in these locations.

If you have any questions, please let me know.

Thanks,
DJ

DJ Ennis, P.G.
Mining and Minerals Division / 1220 S. St. Francis Drive / Santa Fe, NM 87505
(505) 476-3434 / david.ennis@state.nm.us

Vollbrecht, Kurt, NMENV

From: Powell, Richard, NMENV
Sent: Thursday, May 31, 2012 7:44 AM
To: Vollbrecht, Kurt, NMENV
Subject: RE: NM water quality standards for Coppr Flat pit lake

Who are they?

Here's how the coal mining regulations define impoundment:

IMPOUNDMENT - means a closed basin, naturally formed or artificially built, which is dammed or excavated for the retention of water or sediment.

And how they define permanent diversion:

PERMANENT DIVERSION - means a diversion remaining after surface coal mining and reclamation operations are completed which has been approved for retention by the director and other appropriate state and federal agencies.

So I guess if you creatively combine the two, you have:

PERMANENT IMPOUNDMENT - means a closed basin, naturally formed or artificially built, which is dammed or excavated for the retention of water or sediment remaining after mining and reclamation operations are completed, which has been approved for retention by the director and other appropriate state and federal agencies.

Or the non-coal mining regulations define impoundment:

"Impoundment" means a basin constructed for the retention of water or sediment, but does not include impoundments for process solutions or tailings.

So if you creatively combine these, you have:

PERMANENT IMPOUNDMENT - means a basin constructed for the retention of water or sediment remaining after mining and reclamation operations are completed, which has been approved for retention by the director and other appropriate state and federal agencies.

I personally prefer combination of the two:

PERMANENT IMPOUNDMENT - means a basin, naturally formed or artificially built, which is dammed or excavated for the retention of water or sediment remaining after mining and reclamation operations are completed, which has been approved for retention by the director and other appropriate state and federal agencies.

From: Vollbrecht, Kurt, NMENV
Sent: Wednesday, May 30, 2012 5:15 PM
To: Powell, Richard, NMENV
Subject: RE: NM water quality standards for Coppr Flat pit lake

Now they want me to define "permanent impoundment"...

Kurt Vollbrecht, Geologist
New Mexico Environment Department
Ground Water Quality Bureau
Mining Environmental Compliance Section
(505) 827-0195

From: Powell, Richard, NMENV
Sent: Wednesday, May 30, 2012 9:58 AM
To: Vollbrecht, Kurt, NMENV
Subject: RE: NM water quality standards for Coppr Flat pit lake

And all other permanent impoundments (not actively used for treatment) as well. Our regulations allow for a Use Attainability Analysis (UAA) which may result in a change to the designated use(s). See 20.6.4.15 NMAC.

From: Vollbrecht, Kurt, NMENV
Sent: Thursday, May 24, 2012 11:43 AM
To: Powell, Richard, NMENV
Subject: RE: NM water quality standards for Coppr Flat pit lake

This question just came up during a discussion for copper rules closure requirements. Would the statement below apply to an and all pit lakes at copper mines?

Kurt Vollbrecht, Geologist
New Mexico Environment Department
Ground Water Quality Bureau
Mining Environmental Compliance Section
(505) 827-0195

From: Powell, Richard, NMENV
Sent: Tuesday, May 15, 2012 9:06 AM
To: Vollbrecht, Kurt, NMENV
Subject: RE: NM water quality standards for Coppr Flat pit lake

As a permanent impoundment, we would consider this an unclassified perennial water with designated uses of warmwater aquatic life, livestock watering, wildlife habitat and primary contact as specified in 20.6.4.99 NMAC (*Standards for Interstate and Intrastate Surface Waters, New Mexico Water Quality Control Commission, 20.6.4 New Mexico Administrative Code)* as amended through January 14, 2011 (NMWQS) http://www.nmcpr.state.nm.us/nmac/parts/title20/20.006.0004.htm. Applicable water quality criteria for these uses is specified in 20.6.4.900 NMAC.

From: Vollbrecht, Kurt, NMENV
Sent: Tuesday, May 15, 2012 8:47 AM
To: Powell, Richard, NMENV
Subject: FW: NM water quality standards for Coppr Flat pit lake

Hi Rich-can you provide an answer to this? My guess is he is asking about standards after closure.

Let me know what information is necessary to respond...thanks.

Kurt Vollbrecht, Geologist
New Mexico Environment Department
Ground Water Quality Bureau

Mining Environmental Compliance Section
(505) 827-0195

From: Nelson, Mark [mailto:NelsonMR@cdmsmith.com]
Sent: Monday, May 14, 2012 4:57 PM
To: Vollbrecht, Kurt, NMENV
Subject: NM water quality standards for Coppr Flat pit lake

Hi Kurt-

Which New Mexico water quality standards apply to the Copper Flat pit lake?

To save you time, I could also look up the standards, if you can help with the use designations that apply to the pit lake.

Thanks
Mark

Mark R. Nelson, PG | Project Hydrogeologist/Geochemist, Mining Project Specialist
CDM Smith |12445 Misty Meadows Rd. | Nemo, SD 57759 | T: 605.578.9739 | Cell: 605.390.9042
nelsonmr@cdmsmith.com

United States Department of the Interior

BUREAU OF LAND MANAGEMENT
Las Cruces District Office
1800 Marquess Street
Las Cruces, New Mexico 88005
www.blm.gov/nm

TAKE PRIDE IN AMERICA

In Reply Refer To:

2800 (L0310)

JUN 7 2012

Dear Interested Party:

The Bureau of Land Management (BLM) received a right-of-way application from the New Mexico Copper Corporation (NMCC), to construct, operate, maintain, and terminate existing water facility infrastructure and new temporary water facility infrastructure approximately 11 miles east of Hillsboro, New Mexico (see enclosed vicinity map). The NMCC is proposing a pumping test on existing water facility infrastructure and collecting data on aquifer properties to establish aquifer baseline data. Objectives of the pumping test include:

- Evaluating the current conditions of wells used for pumping
- Determine potential aquifer boundary conditions
- Gather data on aquifer properties in the vicinity of existing wells
- Obtain a better understanding of the interaction of the wells when pumped as a well field (two wells at the same time).

Existing water facility infrastructure is located on public land identified on the enclosed project area figure (PW-1, PW-2, PW-3, PW-4, and ancillary connecting pipelines). Two alternatives for temporary water facility infrastructure would be located on public land as identified below, and on the enclosed project area figure.

Alternative A: A temporary above-ground pipeline (Temporary Pipeline Corridor) from the existing water facilities would be used in conjunction with the associated infiltration area (within an existing but un-used gravel quarry) located on state land for the purpose of transporting test water to the infiltration area.

Alternative B: A temporary above-ground pipeline would extend from the existing water facilities to Greyback Arroyo for the purpose of transporting test water to Greyback Arroyo.

To comply with the National Environmental Policy Act (NEPA), the BLM has analyzed the environmental effects of this proposed action in an environmental assessment (EA). The EA will be posted on the BLM's website for a 30-day review and public comment by early June 2012 at http://www.blm.gov/nm/st/en/fo/Las_Cruces_District_Office.html.

If you have any questions or comments regarding this proposed project, or if you need additional information, please contact Anthony Hom at (575) 525-4331, or Douglas Haywood at (575) 525-4498.

Sincerely,

David L. Wallace
Assistant District Manager
Division of Multi-Resources

2 Enclosures



Figure 1. Vicinity Map



Figure 2: Project Area with Proposed Alternatives

Vollbrecht, Kurt, NMENV

From: Vollbrecht, Kurt, NMENV
Sent: Tuesday, June 19, 2012 10:23 AM
To: Eustice, Chris, EMNRD
Cc: Shepherd, Holland, EMNRD; Menzie, David, NMENV
Subject: Copper Flat Exploration Modification
Attachments: Copper Flat Exp 2.pdf

Chris,

NMED has reviewed the proposed modification to the Copper Flat Minimal Impact Exploration project (permit mod 12-2 to SI025EM). NMED initially submitted comments dated February 3, 2011 (attached). The proposed modification will not result in any additional impacts or concerns and the previous NMED comments are still applicable. Let me know if you have any questions.

Thanks,

Kurt Vollbrecht, Geologist
New Mexico Environment Department
Ground Water Quality Bureau
Mining Environmental Compliance Section
(505) 827-0195

State of New Mexico
Energy, Minerals and Natural Resources Department

Susana Martinez
Governor

John Bemis
Cabinet Secretary

Brett F. Woods, Ph.D.
Deputy Cabinet Secretary

Fernando Martinez, Director
Mining and Minerals Division

June 8, 2012

GROUND WATER
JUN 13 2012
BUREAU

Mr. Kurt Vollbrecht, Mining Act Team Leader
Mining Environmental Compliance Section
Groundwater Quality Bureau
New Mexico Environment Department
Post Office Box 26110
Santa Fe, NM 87502

RE: Request for Review and Comment, Permit Modification 12-2 to Minimal Impact Exploration Permit No. SI025EM, Copper Flat Exploration 2 Project

Dear Mr. Vollbrecht:

The New Mexico Mining and Minerals Division (MMD) received an application requesting a modification to Minimal Impact Exploration Permit No. SI025EM for the Copper Flat Exploration 2 Project located in Sierra County, NM from New Mexico Copper Corporation. A copy of the application is enclosed pursuant to 19.10.4.406.C.3 NMAC.

MMD requests that you review this application and provide comments to MMD no later than 20 days after your receipt of this letter.

Please contact me at (505) 476-3438, or via email at chris.eustice@state.nm.us with any questions or comments you may have regarding the application or this request.

Sincerely,

Chris Eustice, Permit Lead
Mining Act Reclamation Program

Enclosures

cc: Mine File SI025EM

THEMAC RESOURCES

June 1, 2012

Mr. Chris Eusctice
Permit Lead, MMD
1220 South St. Francis Drive
Santa Fe, NM 87505

RE: Copper Flat Exploration 2 (SI025EM) Permit Modification Request #3 - REVISION

Dear Chris,

New Mexico Copper Corporation (a wholly-owned subsidiary of THEMAC Resources Group) proposes to further modify the Copper Flat Exploration 2 Minimal Impact Permit #SI025EM. The following letter replaces my letter of May 15 and further expands our modification request.

We intend to:

(1) Add 7 drill locations (accommodating 7 holes)
(2) Deepen one already-permitted hole by 900'
(3) Relocate one permitted hole and deepen by 50'

The modifications are as follows:

Site	UTM N (m)	UTM E (m)	Length (ft)	Comment
JK-12	3650563	263241	2,000	Deepen permitted hole by 900'
9	3650965	263252	1,100	Relocate permitted hole to new location, deepen 50'
17	3650588	263370	1,500	New Site (previously dropped from Modification 2)
B	3650542	263340	2,000	New Site
E	3650945	263543	1,200	New Site
X	3650425	263589	500	New Site
8B	3650665	263175	1,500	New Site
W6	3650978	263066	1,200	New Site
SQ	3650637	263341	1,500	New Site

(Site 17 was previously included in Modification #2, but later dropped by NMCC)

The attached map shows the location of sites involved in this modification as well as sites already approved under Permit SI025EM.

THEMAC RESOURCES

Roads and Overland Access

All of the proposed drill sites in this modification are located on existing 2-wheel-drive navigable roads (see accompanying aerial photograph map). This modification will involve no new road or overland travel.

Drill Pads

We will construct pads of no greater than 30' by 60'. Our current drill program employs a track-mounted core rig requiring minimal auxiliary equipment.

Ownership

All land affected by this modification consists of patented claims held by New Mexico Copper Corporation.

Disturbance

Existing Permitted Disturbance (Modification 2)

Surface (Drill Pads & Roads)	2.95 ac
Downhole	35,350 ft

Proposed Additional Disturbance (Modification 3)

Surface (7 Drill Pads, 30' x 60')	0.29 ac
Downhole	10,350 ft

Total Permitted Disturbance (Upon Approval of Modification 3)

Surface (Drill Pads)	3.24 ac
Downhole	45,700 ft

THEMAC RESOURCES

Financial Assurance

To date, 12 holes have been drilled and abandoned in 2012 (see attached map). Drill plugging records have been submitted to the Office of the State Engineer. Those holes are:

Site	Permit Depth
3	1,050
5A	1,500
7	1,050
20	1,200
L	1,200
16	1,050
JK-7	1,200
JK-11	1,200
23	1,050
24	1,050
13	1,500
5	1,050

Total Downhole: 14,100 ft

We ask that the F.A. currently posted for these completed & reclaimed holes be deemed sufficient to cover our proposed modifications. A comparison follows

Proposed disturbance:

Downhole: 10,350 feet @ $6.50/ft = $67,275

Surface: 0.29 acres @ $3,300/ac = $957

Total: $68,232

Reclaimed disturbance (2012):

14,100 feet @ $6.50/ft = $91,650

The current bond posted for this permit is $241,710.
This modification represents an increase of F.A. liability of $68,232. However, the reclamation already completed represents an F.A. liability of $91,650. In the interest of expedience, we request that, upon approval of Modification 3, we be permitted to proceed with activities without modifying the F.A.

We are actively drilling under our approved permit, and hope to receive approval of this additional modification as quickly as possible so as to include these modifications in our current drilling campaign. Please contact me if there is anything else I can provide, or anything I can do to facilitate the review process. The $250 permit modification fee was submitted with the original Modification 3 request.

Also, please note that our office address has changed. Our new office address is:

2424 Louisiana Boulevard NE, Suite 301
Albuquerque, NM 87110

Thanks once again for all of your current and past assistance.

Best regards,

Andrew Feltman
Project Geologist
New Mexico Copper Corporation – Copper Flat Mine
(A Wholly Owned Subsidiary of THEMAC Resources Group, Ltd.)
Office: 505.872.0297
Mobile: 251.591.5251
www.themacresourcesgroup.com

NE-F
W6
CNI-5
7
9
CNI-1
20
E
24
C
D
E
16
CNI-2
JK-7
H
H
JK-9
CNI-6
J-1 / J-2
J-1 / J-2
K
4B
13
L
1
6
JK-16
JK-16
CNI-4
8B
CNI-3
Q
SQ
JK-11
21
R-1 / R-2
R-1 / R-2
11
3
4
5A
S
8A
17
25A
28
JK-12
B
5
X
Drilled 2011
Modification 1
Modification 2
Modification 3
N
S
0
100
200
400
Feet
Copper Flat Exploration 2
(SI025EM) Permit Modification 3
THEMAC Resource Group, Ltd
Copper Flat Mine
6/1/2012
APF



Holes Drilled & Plugged in 2012

0 100 200 400 Feet

Coordinate System: NAD 1983 UTM Zone 13N
Projection: Transverse Mercator
Datum: North American 1983
False Easting: 500,000.0000
False Northing: 0.0000
Central Meridian: -105.0000
Scale Factor: 0.9996
Latitude Of Origin: 0.0000
Units: Meter

N
S

Holes Drilled & Plugged in 2012	
THEMAC Resource Group, Ltd Copper Flat Mine	6/1/2012
	APF

Shore, Lawrence, NMENV

From: Vollbrecht, Kurt, NMENV
Sent: Thursday, June 21, 2012 12:05 PM
To: Shore, Lawrence, NMENV
Subject: FW: Notice of Intent from NMCC
Attachments: NMCC_NOI_6_20_12.pdf

Here is the email from NMCC.

If the water quality is as expected, I would think "No DP Required" would suffice, but it is up to Jerry whether we issue temporary permission or not...

Kurt Vollbrecht, Geologist
New Mexico Environment Department
Ground Water Quality Bureau
Mining Environmental Compliance Section
(505) 827-0195

From: Katie Emmer [mailto:kemmer@themacresourcesgroup.com]
Sent: Thursday, June 21, 2012 10:19 AM
To: Vollbrecht, Kurt, NMENV
Cc: Steve Raugust; Jens Deichmann
Subject: Notice of Intent from NMCC

Hi Kurt,

As we discussed, I am submitting NMCC's Notice of Intent for proposed discharge from the pumping test at two possible locations. As you suggested, I am sending this electronically only, but if you'd like a hard copy I will put that in the mail no problem.

The two discharge locations are referred to as Alternative A and Alternative B. Alternative A is an inactive gravel quarry on state land; Alternative B is a location south of the production wells in Grayback Arroyo. As we've been issued an NPDES permit for the Grayback Arroyo location and it is much closer to the wells, it is our preferred option; however this decision is subject to BLM concurrence. This discharge would not occur without the right of way grant we've applied for with the BLM and is subject to other permits. The public comment period for the Environmental Assessment the BLM completed on these proposed actions ends on July 9, 2012. We are hopeful for a decision from BLM in July.

The NPDES for the proposed discharge was issued by EPA on May 31, 2012 and will be effective, assuming no appeals, on July 1, 2012. If you don't have a copy of that permit and would like one please let me know, I'd be happy to provide it.

If you have any questions or other data requests, please let me know.

Thank you,

Katie Emmer
Project Scientist
THEMAC RESOURCES
Copper Flat Mine

7-1-12 NMC003101

New Mexico Environment Department
Ground Water Quality Bureau

Ground Water Quality Bureau – Pollution Prevention Section
Notice of Intent

1. **Name and mailing address of person proposing to discharge:**

New Mexico Copper Corporation
Jens Deichmann
2424 Louisiana Blvd NE, Suite 301
Albuquerque, NM 87110

Work Phone: 505-830-6920
Cell Phone: 505-681-2536
Fax: 505-881-4616
Email: jdeichmann@themacresourcesgroup.com

2. **Name of facility:**

Copper Flat Production Well Field

3. **Physical location of discharge (if applicable, give street address, township, range, section, distance from closest town or landmark, directions to facility, location map):**

Two possible locations:
A: inactive gravel quarry near the intersection of I-25 and NM HWY 152 east of the Copper Flat Production Wells, see "Infiltration Area" connected to Production Wells by "Alternative A" in attached Figure 2: Northern portion of T16S, R5W, Section 2, lots 1 and 3, inclusive.
Or B: South of Copper Flat Production Wells in Grayback arroyo, see "Alternative B" in attached Figure 2, Latitude 32° 57' 42" North, Longitude 107° 22' 22" West T15S, R5W, Section 31, SW1/4NE1/4

4. **Type of operation generating the discharge (e.g., truck wash, food processing plant, restaurant, etc.):**

Pumping test at Copper Flat Production Well field, lasting approximately 16 days. Some discharge may occur prior to pumping test.

5. **Source(s) of the discharge. Describe how the wastewater, sludge, or other discharges processed and/or disposed at your facility are generated. Identify all sources. Attach additional pages if needed:**

Groundwater from Copper Flat Production Wells: likely PW-1 and PW-3, although PW-2 could be used if conditions at PW-1 or PW-3 preclude their use

6. **Expected contaminants in the discharge (e.g., nitrate-nitrogen, metals, organic compounds, salts, etc.) Include estimated concentration if known, and copies of results of laboratory analyses, if available:**

No contaminants will be discharged. See attached laboratory analysis from PW-1 and PW-3, May 2012.

7. **Describe all components of wastewater processing, treatment, storage, and disposal system (e.g., grease interceptor, lagoon, septic tank/leachfield, etc.) Include sizes, site layout map, plans and specifications, etc. if available:**

No processing or treatment is needed or planned. Water may be stored temporarily in above ground temporary mobile tanks prior to discharge.

8. **Estimated maximum daily discharge volume in gallons per day (or other units):**

The average daily discharge would be 9.4 acre feet per day. Maximum discharge would be 13.2 acre feet per day. Total discharge will not exceed 150 acre feet.

9. **Estimated depth to ground water (ft):** At A, unused gravel quarry: 60 ft below ground surface. At B, Grayback arroyo: greater than 250 ft below ground level.

Signature: _____ **Date:** 6/20/12

Printed name: Jens Deichmann **Title:** Project Manager

Please return this form to:
NMED Ground Water Quality Bureau
P.O. Box 5469
Santa Fe, New Mexico 87502-5469

Telephone: 505-827-2900
Fax: 505-827-2965

300' - 1000'

Copper Flat Production
Well Data

Well Name	Date	Boron	Barium	Beryllium	Bicarbonate	Cadmium	Calcium	Chloride (mg/L)	Chromium	Cobalt	Copper	Fluoride	Iron	Lead	Magnesium	Uranium	Arsenic	Vanadium
		.75	1.0	NA	NA	.01	NA	250	.05	.05	1	1.6	1.0	.05	NA	.03		
PW-1																		
	12/23/1975				144.6		22	16.3				0.46			2.8			
	8/14/1981						28				<0.05		0.2	<0.02	4			
	8/2/1994																	
	5/1/2012	0.065	0.011	<0.002	150	<0.002	36	32	<0.006	<0.006	<0.006	1	0.04	<0.005	3.1	.0032	.0033	ND
PW-2																		
	1/15/1976				153.1		21	17				0.66			3.4			
	11/27/1984					<0.005					<0.05		<0.1					
	8/2/1994	<0.1	<0.1	<0.002		<0.0005	60		<0.025	<0.05	<0.025		0.062	<0.005	8.4			
PW-3																		
	1/27/1976				158		23	24.1				0.64			2.7			
	8/14/1981						16				-0.05		0.31	<0.02	1			
	8/2/1994																	
	5/2/2012	0.095	0.0078	<0.002	120	<0.002	20	50	0.006	<0.006	<0.006	1.9	0.065	<0.005	1	.0013	.0074	ND
PW-4																		
	8/2/1994	<0.1	<0.1	<0.002		<0.0005	21		<0.025	<0.05	<0.025		<0.05	<0.005	1.7			
		OK	OK	-	-	OK	-	OK	OK	OK	OK		OK	OK	~			

Well Name	Date	Manganese	Mercury	Molybdenum	Nickel	Nitrate	Potassium (mg/L)	Selenium	Silver	Sodium	Sulfate	TDS	Thallium	Zinc	pH	CN
		.2	.002	1.0	.2	10.0	NA	.05	.05	NA	600	1000	NA	10.	6-9	
PW-1																
	12/23/1975					3.5	4.5			38	10	217			7.8	
	8/14/1981									53				<0.05		
	8/2/1994															
	5/1/2012	0.0024	<0.0002	<0.008	<0.01	0.59	3.4	<0.001	<0.005	58	28	294	<0.001	0.024	8.02	ND
PW-2																
	1/15/1976					3.5	4.3			39	<5	257			8.1	
	11/27/1984	<0.05	<0.001					<0.005								
	8/2/1994	0.032	<0.001		<0.05		3.4	<0.005	<0.025	46			<0.005	<0.05		
PW-3																
	1/27/1976					2.6	5.1			44	<5	243			8	
	8/14/1981									87				0.19		
	8/2/1994															
	5/2/2012	0.0026	<0.0002	<0.008	<0.01	0.7	3.3	<.001	<0.005	81	26	303	<0.001	0.021	8.03	ND
PW-4																
	8/2/1994	<0.03	<0.001	<0.05	<0.05		3.5	<0.005	<0.025	73			<0.005	<0.05		
		OK	OK	OK	OK	OK	-	OK	OK	~	OK	OK	—	OK	OK	

Pump PW-1 3 days then PW-3 +
Blend - pumped @ similar rates
PW-2 as backup

PW-1 looks good (Straight)
PW-3 had sandy tube in it

1. **Name and mailing address of person proposing to discharge:**

New Mexico Copper Corporation
Jens Deichmann
2424 Louisiana Blvd NE, Suite 301
Albuquerque, NM 87110

Work Phone: 505-830-6920
Cell Phone: 505-681-2536
Fax: 505-881-4616
Email: jdeichmann@themacresourcesgroup.com

2. **Name of facility:**

Copper Flat Production Well Field

3. **Physical location of discharge (if applicable, give street address, township, range, section, distance from closest town or landmark, directions to facility, location map):**

Two possible locations:
A: inactive gravel quarry near the intersection of I-25 and NM HWY 152 east of the Copper Flat Production Wells, see "Infiltration Area" connected to Production Wells by "Alternative A" in attached Figure 2: Northern portion of T16S, R5W, Section 2, lots 1 and 3, inclusive.
Or B: South of Copper Flat Production Wells in Grayback arroyo, see "Alternative B" in attached Figure 2, Latitude 32° 57' 42" North, Longitude 107° 22' 22" West T15S, R5W, Section 31, SW1/4NE1/4

4. **Type of operation generating the discharge (e.g., truck wash, food processing plant, restaurant, etc.):**

Pumping test at Copper Flat Production Well field, lasting approximately 16 days. Some discharge may occur prior to pumping test.

5. **Source(s) of the discharge. Describe how the wastewater, sludge, or other discharges processed and/or disposed at your facility are generated. Identify all sources. Attach additional pages if needed:**

Groundwater from Copper Flat Production Wells: likely PW-1 and PW-3, although PW-2 could be used if conditions at PW-1 or PW-3 preclude their use

6. **Expected contaminants in the discharge (e.g., nitrate-nitrogen, metals, organic compounds, salts, etc.) Include estimated concentration if known, and copies of results of laboratory analyses, if available:**

No contaminants will be discharged. See attached laboratory analysis from PW-1 and PW-3, May 2012.

7. **Describe all components of wastewater processing, treatment, storage, and disposal system (e.g., grease interceptor, lagoon, septic tank/leachfield, etc.) Include sizes, site layout map, plans and specifications, etc. if available:**

No processing or treatment is needed or planned. Water may be stored temporarily in above ground temporary mobile tanks prior to discharge.

8. **Estimated maximum daily discharge volume in gallons per day (or other units):**

The average daily discharge would be 9.4 acre feet per day. Maximum discharge would be 13.2 acre feet per day. Total discharge will not exceed 150 acre feet.

9. **Estimated depth to ground water (ft):** At A, unused gravel quarry: 60 ft below ground surface. At B, Grayback arroyo: greater than 250 ft below ground level.

Signature: _____ **Date:** 6/20/12

Printed name: Jens Deichmann **Title:** Project Manager

Please return this form to:
NMED Ground Water Quality Bureau
P.O. Box 5469
Santa Fe, New Mexico 87502-5469

Telephone: 505-827-2900
Fax: 505-827-2965

Copper Flat Production
Well Data

Well Name	Date	Boron	Barium	Beryllium	Bicarbonate	Cadmium	Calcium	Chloride	Chromium	Cobalt	Copper	Fluoride	Iron	Lead	Magnesium
		(mg/L)													
PW-1															
	12/23/1975				144.6		22	16.3				0.46			2.8
	8/14/1981						28				<0.05		0.2	<0.02	4
	8/2/1994														
	5/1/2012	0.065	0.011	<0.002	150	<0.002	36	32	<0.006	<0.006	<0.006	1	0.04	<0.005	3.1
PW-2															
	1/15/1976				153.1		21	17				0.66			3.4
	11/27/1984					<0.005					<0.05		<0.1		
	8/2/1994	<0.1	<0.1	<0.002		<0.0005	60		<0.025	<0.05	<0.025		0.062	<0.005	8.4
PW-3															
	1/27/1976				158		23	24.1				0.64			2.7
	8/14/1981						16				-0.05		0.31	<0.02	1
	8/2/1994														
	5/2/2012	0.095	0.0078	<0.002	120	<0.002	20	50	0.006	<0.006	<0.006	1.9	0.065	<0.005	1
PW-4															
	8/2/1994	<0.1	<0.1	<0.002		<0.0005	21		<0.025	<0.05	<0.025		<0.05	<0.005	1.7

Well Name	Date	Manganese	Mercury	Molybdenum	Nickel	Nitrate	Potassium	Selenium	Silver	Sodium	Sulfate	TDS	Thallium	Zinc	pH
							(mg/L)								
PW-1															
	12/23/1975					3.5	4.5			38	10	217			7.8
	8/14/1981									53				<0.05	
	8/2/1994														
	5/1/2012	0.0024	<0.0002	<0.008	<0.01	0.59	3.4	<0.001	<0.005	58	28	294	<0.001	0.024	8.02
PW-2															
	1/15/1976					3.5	4.3			39	<5	257			8.1
	11/27/1984	<0.05	<0.001					<0.005							
	8/2/1994	0.032	<0.001		<0.05		3.4	<0.005	<0.025	46			<0.005	<0.05	
PW-3															
	1/27/1976					2.6	5.1			44	<5	243			8
	8/14/1981									87				0.19	
	8/2/1994														
	5/2/2012	0.0026	<0.0002	<0.008	<0.01	0.7	3.3	<.001	<0.005	81	26	303	<0.001	0.021	8.03
PW-4															
	8/2/1994	<0.03	<0.001	<0.05	<0.05		3.5	<0.005	<0.025	73			<0.005	<0.05	



Figure 1. Vicinity Map



Figure 2: Project Area with Proposed Alternatives

HALL
ENVIRONMENTAL
ANALYSIS
LABORATORY

Hall Environmental Analysis Laboratory
4901 Hawkins NE
Albuquerque, NM 87109
TEL: 505-345-3975 FAX: 505-345-4107
Website: www.hallenvironmental.com

May 14, 2012

Katie Emmer
New Mexico Copper Corp
2425 San Pedro Dr NE Ste 100
Albuquerque, New Mexico 87109
TEL: (505) 400-7925
FAX

RE: Cu Flat OrderNo.: 1205153

Dear Katie Emmer:

Hall Environmental Analysis Laboratory received 1 sample(s) on 5/3/2012 for the analyses presented in the following report.

These were analyzed according to EPA procedures or equivalent. To access our accredited tests please go to www.hallenvironmental.com or the state specific web sites. See the sample checklist and/or the Chain of Custody for information regarding the sample receipt temperature and preservation. Data qualifiers or a narrative will be provided if the sample analysis or analytical quality control parameters require a flag. All samples are reported as received unless otherwise indicated.

Please don't hesitate to contact HEAL for any additional information or clarifications.

Sincerely,

Andy Freeman
Laboratory Manager
4901 Hawkins NE
Albuquerque, NM 87109

NM Copper
May 1, 2012

Analytical Parameter	Analysis Method	Lab Detection Limit (mg/L unless noted)
Thallium	EPA Method 200.7	0.01
~~Titanium~~	~~EPA Method 200.7~~	~~0.005~~
Uranium	EPA Method 200.8	0.01
Vanadium	EPA Method 200.7	0.005
Zinc	EPA Method 200.7	0.005
Solids		
Total Suspended Solids (TSS)	SM 2540D	1.0 µg/L
Total Dissolved Solids (TDS)	SM 2540C	10
Alkalinity		
Alkalinity, total (as $CaCO_3$)	SM 2320B	20
Carbonate	SM 2320B	20
Bicarbonate	SM 2320B	20
Other		
pH	150.1	12.45
Specific Conductance	120.1	0.01 µS/cm
Cyanide	Kelada-01	0.005

Note: NA = not applicable as sample will not be analyzed for a given parameter.

NM Copper
May 1, 2012

Table 9-3

Analytical Parameters and Analysis Methods for Groundwater Samples

Analytical Parameter	Analysis Method	Lab Detection Limit (mg/L unless noted)
Anions		
Fluoride	EPA Method 300.0	0.1
Chloride	EPA Method 300.0	0.1
Nitrogen, Nitrite (as N)	EPA Method 300.0	0.1
Nitrogen, Nitrate (as N)	EPA Method 300.0	0.1
Sulfate	EPA Method 300.0	0.5
Dissolved Metals		
Aluminum	EPA Method 200.7	0.02
Antimony	EPA Method 200.8	0.005
Arsenic	EPA Method 200.8	0.02
Barium	EPA Method 200.7	0.002
Beryllium	EPA Method 200.7	0.002
Boron	EPA Method 200.7	0.04
Cadmium	EPA Method 200.7	0.002
Calcium	EPA Method 200.7	0.50
Chromium	EPA Method 200.7	0.006
Cobalt	EPA Method 200.7	0.006
Copper	EPA Method 200.7	0.0003
Iron	EPA Method 200.7	0.02
Lead	EPA Method 200.7	0.005
Magnesium	EPA Method 200.7	0.50
Manganese	EPA Method 200.7	0.002
Mercury	EPA Method 7470 CVAA	0.0002
Molybdenum	EPA Method 200.7	0.008
Nickel	EPA Method 200.7	0.01
Potassium	EPA Method 200.7	1.0
Selenium	EPA Method 200.8	0.02
Silicon	EPA Method 200.7	0.08
Silver	EPA Method 200.7	0.005
Sodium	EPA Method 200.7	0.5

Chain-of-Custody Record

Client: New Mexico Copper Corp

Mailing Address: 2425 San Pedro Dr NE Suite 100, ABQ NM

Phone #: 505.400.7925

email or Fax#:

QA/QC Package:
☐ Standard ☐ Level 4 (Full Validation)

Accreditation
☐ NELAP ☐ Other _____
☐ EDD (Type) _____

Turn-Around Time:
☐ Standard ☒ Rush Need Results by May 11 via email

Project Name: CoFlat

Project #: Production Well Sampling

Project Manager: Katie Emmer

Sampler: CMC

On Ice: ☒ Yes ☐ No

Sample Temperature: 3°

HALL ENVIRONMENTAL ANALYSIS LABORATORY

www.hallenvironmental.com

4901 Hawkins NE - Albuquerque, NM 87109

Tel. 505-345-3975 Fax 505-345-4107

Analysis Request

Date	Time	Matrix	Sample Request ID	Container Type and #	Preservative Type	HEAT No 1205076	BTEX + MTBE + TMB's (8021)	BTEX + MTBE + TPH (Gas only)	TPH Method 8015B (Gas/Diesel)	TPH (Method 418.1)	EDB (Method 504.1)	8310 (PNA or PAH)	RCRA 8 Metals	Anions (F,Cl,NO_3,NO_2,PO_4,SO_4)	8081 Pesticides / 8082 PCB's	8260B (VOA)	8270 (Semi-VOA)	see enclosed list				Air Bubbles (Y or N)
5-1-12	1400	H_2O	PW-1	500		-001												X				
				125	H_2SO_4	-001																
				125	HNO_3 + filter	-001																
				500	HNO_3	-001																
				500	NaOH	-001																

Date:	Time:	Relinquished by:	Received by:	Date	Time
5/1/12	14:30			5/1/2012	14:30
5/2/12	07:50			05/02/12	0730

Remarks:
Please email results to: Katie Emmer
kemmer@themacresourcesgroup.com
Please add Hardness, per Katie. dr 5/3

If necessary, samples submitted to Hall Environmental may be subcontracted to other accredited laboratories. This serves as notice of this possibility. Any sub-contracted data will be clearly notated on the analytical report.

HALL ENVIRONMENTAL ANALYSIS LABORATORY

Hall Environmental Analysis Laboratory
4901 Hawkins NE
Albuquerque, NM 87109
TEL: 505-345-3975 FAX: 505-345-4107
Website: www.hallenvironmental.com

Sample Log-In Check List

Client Name: NEW MEXICO COPPER CORP Work Order Number: 1205076

Received by/date: AT 05/02/12

Logged By: Anne Thorne 5/2/2012 7:30:00 AM

Completed By: Anne Thorne 5/2/2012

Reviewed By: AT 05/02/12

Chain of Custody

1. Were seals intact?	Yes ☐	No ☐	Not Present ☑
2. Is Chain of Custody complete?	Yes ☑	No ☐	Not Present ☐
3. How was the sample delivered?	Client		

Log In

4. Coolers are present? (see 19. for cooler specific information)	Yes ☑	No ☐	NA ☐
5. Was an attempt made to cool the samples?	Yes ☑	No ☐	NA ☐
6. Were all samples received at a temperature of >0° C to 6.0°C	Yes ☑	No ☐	NA ☐
7. Sample(s) in proper container(s)?	Yes ☑	No ☐	
8. Sufficient sample volume for indicated test(s)?	Yes ☑	No ☐	
9. Are samples (except VOA and ONG) properly preserved?	Yes ☑	No ☐	
10. Was preservative added to bottles?	Yes ☐	No ☑	NA ☐
11. VOA vials have zero headspace?	Yes ☑	No ☐	No VOA Vials ☐
12. Were any sample containers received broken?	Yes ☐	No ☑	
13. Does paperwork match bottle labels? (Note discrepancies on chain of custody)	Yes ☑	No ☐	
14. Are matrices correctly identified on Chain of Custody?	Yes ☑	No ☐	
15. Is it clear what analyses were requested?	Yes ☑	No ☐	
16. Were all holding times able to be met? (If no, notify customer for authorization.)	Yes ☑	No ☐	

# of preserved bottles checked for pH: 1

(<2 or >12 unless noted)

Adjusted? _____

Checked by: AT 05/02/12

Special Handling (if applicable)

17. Was client notified of all discrepancies with this order? Yes ☐ No ☐ NA ☑

Person Notified: _____ Date _____

By Whom: _____ Via: ☐ eMail ☐ Phone ☐ Fax ☐ In Person

Regarding: _____

Client Instructions: _____

18. Additional remarks:

19. Cooler Information

Cooler No	Temp °C	Condition	Seal Intact	Seal No	Seal Date	Signed By
1	3.4	Good	Not Present			

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: **1205076**

14-May-12

Client: New Mexico Copper Corp

Project: Cu Flat

Sample ID **MB-1800**	SampType: **MBLK**	TestCode: **SM 2540D: TSS**
Client ID: **PBW**	Batch ID: **1800**	RunNo: **2570**
Prep Date: **5/3/2012**	Analysis Date: **5/3/2012**	SeqNo: **71656** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Suspended Solids	ND	4.0								

Sample ID **LCS-1800**	SampType: **LCS**	TestCode: **SM 2540D: TSS**
Client ID: **LCSW**	Batch ID: **1800**	RunNo: **2570**
Prep Date: **5/3/2012**	Analysis Date: **5/3/2012**	SeqNo: **71657** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Suspended Solids	93	4.0	96.60	0	96.3	82.9	110			

Sample ID **1205034-001BDUP**	SampType: **DUP**	TestCode: **SM 2540D: TSS**
Client ID: **BatchQC**	Batch ID: **1800**	RunNo: **2570**
Prep Date: **5/3/2012**	Analysis Date: **5/3/2012**	SeqNo: **71663** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Suspended Solids	ND	4.0						0	15	

Qualifiers:

*/X	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
E	Value above quantitation range	H	Holding times for preparation or analysis exceeded
J	Analyte detected below quantitation limits	ND	Not Detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Detection Limit

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: **1205076**

14-May-12

Client: New Mexico Copper Corp

Project: Cu Flat

Sample ID **MB-1832**	SampType: **MBLK**	TestCode: **SM2540C MOD: Total Dissolved Solids**
Client ID: **PBW**	Batch ID: **1832**	RunNo: **2634**
Prep Date: **5/7/2012**	Analysis Date: **5/8/2012**	SeqNo: **73329** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Total Dissolved Solids	ND	20.0								

Sample ID **LCS-1832**	SampType: **LCS**	TestCode: **SM2540C MOD: Total Dissolved Solids**
Client ID: **LCSW**	Batch ID: **1832**	RunNo: **2634**
Prep Date: **5/7/2012**	Analysis Date: **5/8/2012**	SeqNo: **73330** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Total Dissolved Solids	1,020	20.0	1,000	0	102	80	120			

Sample ID **1205078-002GMS**	SampType: **MS**	TestCode: **SM2540C MOD: Total Dissolved Solids**
Client ID: **BatchQC**	Batch ID: **1832**	RunNo: **2634**
Prep Date: **5/7/2012**	Analysis Date: **5/8/2012**	SeqNo: **73337** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Total Dissolved Solids	4,890	20.0	1,000	3,791	110	80	120			

Sample ID **1205078-002GMSD**	SampType: **MSD**	TestCode: **SM2540C MOD: Total Dissolved Solids**
Client ID: **BatchQC**	Batch ID: **1832**	RunNo: **2634**
Prep Date: **5/7/2012**	Analysis Date: **5/8/2012**	SeqNo: **73338** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Total Dissolved Solids	4,930	20.0	1,000	3,791	114	80	120	0.733	20	

Qualifiers:

*/X	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
E	Value above quantitation range	H	Holding times for preparation or analysis exceeded
J	Analyte detected below quantitation limits	ND	Not Detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Detection Limit

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: **1205076**

14-May-12

Client: New Mexico Copper Corp

Project: Cu Flat

Sample ID	**1205005-001A MS**	SampType:	**MS**		TestCode:	**SM2320B: Alkalinity**				
Client ID:	**BatchQC**	Batch ID:	**R2560**		RunNo:	**2560**				
Prep Date:		Analysis Date:	**5/3/2012**		SeqNo:	**71221**	Units:	**mg/L CaCO3**		
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Total Alkalinity (as CaCO3)	ND	20	80.00	0	0	62.6	110			S

Sample ID	**1205005-001A MSD**	SampType:	**MSD**		TestCode:	**SM2320B: Alkalinity**				
Client ID:	**BatchQC**	Batch ID:	**R2560**		RunNo:	**2560**				
Prep Date:		Analysis Date:	**5/3/2012**		SeqNo:	**71222**	Units:	**mg/L CaCO3**		
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Total Alkalinity (as CaCO3)	ND	20	80.00	0	0	59.9	111	0	10	S

Sample ID	**1205120-001B MS**	SampType:	**MS**		TestCode:	**SM2320B: Alkalinity**				
Client ID:	**BatchQC**	Batch ID:	**R2560**		RunNo:	**2560**				
Prep Date:		Analysis Date:	**5/3/2012**		SeqNo:	**71242**	Units:	**mg/L CaCO3**		
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Total Alkalinity (as CaCO3)	360	20	80.00	299.4	70.9	62.6	110			

Sample ID	**1205120-001B MSD**	SampType:	**MSD**		TestCode:	**SM2320B: Alkalinity**				
Client ID:	**BatchQC**	Batch ID:	**R2560**		RunNo:	**2560**				
Prep Date:		Analysis Date:	**5/3/2012**		SeqNo:	**71243**	Units:	**mg/L CaCO3**		
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Total Alkalinity (as CaCO3)	350	20	80.00	299.4	67.1	59.9	111	0.869	10	

Qualifiers:

*/X	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
E	Value above quantitation range	H	Holding times for preparation or analysis exceeded
J	Analyte detected below quantitation limits	ND	Not Detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Detection Limit

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: **1205076**

14-May-12

Client: New Mexico Copper Corp

Project: Cu Flat

Sample ID	1205005-001A DUP	SampType:	DUP		TestCode:	SM4500-H+B: pH				
Client ID:	BatchQC	Batch ID:	R2560		RunNo:	2560				
Prep Date:		Analysis Date:	5/3/2012		SeqNo:	71363	Units:	pH units		
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
pH	3.92	1.68						0.762		H

Sample ID	1205120-001B DUP	SampType:	DUP		TestCode:	SM4500-H+B: pH				
Client ID:	BatchQC	Batch ID:	R2560		RunNo:	2560				
Prep Date:		Analysis Date:	5/3/2012		SeqNo:	71373	Units:	pH units		
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
pH	7.73	1.68						0.645		H

Qualifiers:

*/X	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
E	Value above quantitation range	H	Holding times for preparation or analysis exceeded
J	Analyte detected below quantitation limits	ND	Not Detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Detection Limit

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: **1205076**

14-May-12

Client: New Mexico Copper Corp

Project: Cu Flat

Sample ID	**1205170-001D**	SampType:	**DUP**	TestCode:	**EPA 120.1: Specific Conductance**				
Client ID:	**BatchQC**	Batch ID:	**R2646**	RunNo:	**2646**				
Prep Date:		Analysis Date:	**5/7/2012**	SeqNo:	**73516**	Units:	**µmhos/cm**		

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Conductivity	610	0.010						0	20	

Qualifiers:

*/X	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
E	Value above quantitation range	H	Holding times for preparation or analysis exceeded
J	Analyte detected below quantitation limits	ND	Not Detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Detection Limit

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: **1205076**

14-May-12

Client: New Mexico Copper Corp

Project: Cu Flat

Sample ID	**1205066-002AMSD**	SampType:	**MSD**		TestCode:	**EPA Method 300.0: Anions**				
Client ID:	**BatchQC**	Batch ID:	**R2544**		RunNo:	**2544**				
Prep Date:		Analysis Date:	**5/2/2012**		SeqNo:	**70853**	Units:	**mg/L**		
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Nitrogen, Nitrate (As N)	3.0	0.10	2.500	0.5059	98.7	82.8	116	10.2	20	
Sulfate	47	0.50	10.00	36.66	101	80.5	119	2.50	20	

Qualifiers:

*/X	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
E	Value above quantitation range	H	Holding times for preparation or analysis exceeded
J	Analyte detected below quantitation limits	ND	Not Detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Detection Limit

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: **1205076**

14-May-12

Client: New Mexico Copper Corp

Project: Cu Flat

Sample ID **1205079-001AMSD**	SampType: **MSD**	TestCode: **EPA Method 300.0: Anions**
Client ID: **BatchQC**	Batch ID: **R2544**	RunNo: **2544**
Prep Date:	Analysis Date: **5/2/2012**	SeqNo: **70810** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Nitrogen, Nitrite (As N)	1.2	0.10	1.000	0	122	77.6	111	4.14	20	S
Nitrogen, Nitrate (As N)	2.4	0.10	2.500	0	95.5	82.8	116	2.38	20	

Sample ID **MB**	SampType: **MBLK**	TestCode: **EPA Method 300.0: Anions**
Client ID: **PBW**	Batch ID: **R2544**	RunNo: **2544**
Prep Date:	Analysis Date: **5/2/2012**	SeqNo: **70849** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Fluoride	ND	0.10								
Chloride	ND	0.50								
Nitrogen, Nitrite (As N)	ND	0.10								
Nitrogen, Nitrate (As N)	ND	0.10								
Sulfate	ND	0.50								

Sample ID **LCS**	SampType: **LCS**	TestCode: **EPA Method 300.0: Anions**
Client ID: **LCSW**	Batch ID: **R2544**	RunNo: **2544**
Prep Date:	Analysis Date: **5/2/2012**	SeqNo: **70850** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Fluoride	0.50	0.10	0.5000	0	99.0	90	110			
Chloride	4.7	0.50	5.000	0	94.2	90	110			
Nitrogen, Nitrite (As N)	0.98	0.10	1.000	0	98.0	90	110			
Nitrogen, Nitrate (As N)	2.5	0.10	2.500	0	98.3	90	110			
Sulfate	9.6	0.50	10.00	0	95.7	90	110			

Sample ID **1205066-002AMS**	SampType: **MS**	TestCode: **EPA Method 300.0: Anions**
Client ID: **BatchQC**	Batch ID: **R2544**	RunNo: **2544**
Prep Date:	Analysis Date: **5/2/2012**	SeqNo: **70852** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Fluoride	1.1	0.10	0.5000	0.5616	101	72.9	113			
Nitrogen, Nitrite (As N)	0.93	0.10	1.000	0	92.7	77.6	111			
Nitrogen, Nitrate (As N)	3.3	0.10	2.500	0.5059	111	82.8	116			
Sulfate	48	0.50	10.00	36.66	113	80.5	119			

Sample ID **1205066-002AMSD**	SampType: **MSD**	TestCode: **EPA Method 300.0: Anions**
Client ID: **BatchQC**	Batch ID: **R2544**	RunNo: **2544**
Prep Date:	Analysis Date: **5/2/2012**	SeqNo: **70853** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Fluoride	1.0	0.10	0.5000	0.5616	93.8	72.9	113	3.52	20	
Nitrogen, Nitrite (As N)	0.79	0.10	1.000	0	78.5	77.6	111	16.5	20	

Qualifiers:

- */X Value exceeds Maximum Contaminant Level.
- E Value above quantitation range
- J Analyte detected below quantitation limits
- R RPD outside accepted recovery limits
- B Analyte detected in the associated Method Blank
- H Holding times for preparation or analysis exceeded
- ND Not Detected at the Reporting Limit
- RL Reporting Detection Limit

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: **1205076**

14-May-12

Client: New Mexico Copper Corp

Project: Cu Flat

Sample ID **MB** SampType: **MBLK** TestCode: **EPA Method 300.0: Anions**

Client ID: **PBW** Batch ID: **R2544** RunNo: **2544**

Prep Date: Analysis Date: **5/2/2012** SeqNo: **70797** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Fluoride	ND	0.10								
Chloride	ND	0.50								
Nitrogen, Nitrite (As N)	ND	0.10								
Nitrogen, Nitrate (As N)	ND	0.10								
Sulfate	ND	0.50								

Sample ID **LCS** SampType: **LCS** TestCode: **EPA Method 300.0: Anions**

Client ID: **LCSW** Batch ID: **R2544** RunNo: **2544**

Prep Date: Analysis Date: **5/2/2012** SeqNo: **70798** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Fluoride	0.47	0.10	0.5000	0	93.8	90	110			
Chloride	4.6	0.50	5.000	0	92.9	90	110			
Nitrogen, Nitrite (As N)	0.93	0.10	1.000	0	92.9	90	110			
Nitrogen, Nitrate (As N)	2.4	0.10	2.500	0	97.4	90	110			
Sulfate	9.5	0.50	10.00	0	94.8	90	110			

Sample ID **1205075-001BMS** SampType: **MS** TestCode: **EPA Method 300.0: Anions**

Client ID: **BatchQC** Batch ID: **R2544** RunNo: **2544**

Prep Date: Analysis Date: **5/2/2012** SeqNo: **70800** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Fluoride	0.68	0.10	0.5000	0.1911	98.1	72.9	113			
Nitrogen, Nitrite (As N)	1.0	0.10	1.000	0	101	77.6	111			
Nitrogen, Nitrate (As N)	2.5	0.10	2.500	0	99.9	82.8	116			

Sample ID **1205075-001BMSD** SampType: **MSD** TestCode: **EPA Method 300.0: Anions**

Client ID: **BatchQC** Batch ID: **R2544** RunNo: **2544**

Prep Date: Analysis Date: **5/2/2012** SeqNo: **70801** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Fluoride	0.65	0.10	0.5000	0.1911	90.9	72.9	113	5.39	20	
Nitrogen, Nitrite (As N)	0.90	0.10	1.000	0	90.2	77.6	111	10.8	20	
Nitrogen, Nitrate (As N)	2.3	0.10	2.500	0	91.3	82.8	116	8.94	20	

Sample ID **1205079-001AMS** SampType: **MS** TestCode: **EPA Method 300.0: Anions**

Client ID: **BatchQC** Batch ID: **R2544** RunNo: **2544**

Prep Date: Analysis Date: **5/2/2012** SeqNo: **70809** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Nitrogen, Nitrite (As N)	1.3	0.10	1.000	0	127	77.6	111			S
Nitrogen, Nitrate (As N)	2.4	0.10	2.500	0	97.8	82.8	116			

Qualifiers:

- */X Value exceeds Maximum Contaminant Level.
- E Value above quantitation range
- J Analyte detected below quantitation limits
- R RPD outside accepted recovery limits
- B Analyte detected in the associated Method Blank
- H Holding times for preparation or analysis exceeded
- ND Not Detected at the Reporting Limit
- RL Reporting Detection Limit

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: **1205076**

14-May-12

Client: New Mexico Copper Corp

Project: Cu Flat

Sample ID	**MB-1862**	SampType: **MBLK**			TestCode: **EPA Method 245.1: Mercury**					
Client ID:	**PBW**	Batch ID: **1862**			RunNo: **2669**					
Prep Date:	**5/9/2012**	Analysis Date: **5/9/2012**			SeqNo: **74223**		Units: **mg/L**			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Mercury	ND	0.00020								

Sample ID	**LCS-1862**	SampType: **LCS**			TestCode: **EPA Method 245.1: Mercury**					
Client ID:	**LCSW**	Batch ID: **1862**			RunNo: **2669**					
Prep Date:	**5/9/2012**	Analysis Date: **5/9/2012**			SeqNo: **74224**		Units: **mg/L**			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Mercury	0.0049	0.00020	0.005000	0	97.4	80	120			

Sample ID	**1204854-004AMS**	SampType: **MS**			TestCode: **EPA Method 245.1: Mercury**					
Client ID:	**BatchQC**	Batch ID: **1862**			RunNo: **2669**					
Prep Date:	**5/9/2012**	Analysis Date: **5/9/2012**			SeqNo: **74226**		Units: **mg/L**			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Mercury	0.0049	0.00020	0.005000	0	97.2	75	125			

Sample ID	**1204854-004AMSD**	SampType: **MSD**			TestCode: **EPA Method 245.1: Mercury**					
Client ID:	**BatchQC**	Batch ID: **1862**			RunNo: **2669**					
Prep Date:	**5/9/2012**	Analysis Date: **5/9/2012**			SeqNo: **74227**		Units: **mg/L**			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Mercury	0.0049	0.00020	0.005000	0	97.1	75	125	0.0957	20	

Qualifiers:

*/X	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
E	Value above quantitation range	H	Holding times for preparation or analysis exceeded
J	Analyte detected below quantitation limits	ND	Not Detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Detection Limit

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: **1205076**

14-May-12

Client: New Mexico Copper Corp

Project: Cu Flat

Sample ID **LCS**	SampType: **LCS**	TestCode: **EPA 200.8: Dissolved Metals**
Client ID: **LCSW**	Batch ID: **R2629**	RunNo: **2629**
Prep Date:	Analysis Date: **5/8/2012**	SeqNo: **73283** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Antimony	0.023	0.0010	0.02500	0	92.8	85	115			
Arsenic	0.023	0.0010	0.02500	0	93.1	85	115			
Thallium	0.023	0.0010	0.02500	0	92.9	85	115			

Sample ID **MB**	SampType: **MBLK**	TestCode: **EPA 200.8: Dissolved Metals**
Client ID: **PBW**	Batch ID: **R2629**	RunNo: **2629**
Prep Date:	Analysis Date: **5/8/2012**	SeqNo: **73284** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Antimony	ND	0.0010								
Arsenic	ND	0.0010								
Thallium	ND	0.0010								

Sample ID **LCS**	SampType: **LCS**	TestCode: **EPA 200.8: Dissolved Metals**
Client ID: **LCSW**	Batch ID: **R2708**	RunNo: **2708**
Prep Date:	Analysis Date: **5/10/2012**	SeqNo: **75447** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Selenium	0.026	0.0010	0.02500	0	104	85	115			
Uranium	0.025	0.0010	0.02500	0	99.2	85	115			

Sample ID **MB**	SampType: **MBLK**	TestCode: **EPA 200.8: Dissolved Metals**
Client ID: **PBW**	Batch ID: **R2708**	RunNo: **2708**
Prep Date:	Analysis Date: **5/10/2012**	SeqNo: **75448** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Selenium	ND	0.0010								
Uranium	ND	0.0010								

Qualifiers:

*/X	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
E	Value above quantitation range	H	Holding times for preparation or analysis exceeded
J	Analyte detected below quantitation limits	ND	Not Detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Detection Limit

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: **1205076**

14-May-12

Client: New Mexico Copper Corp

Project: Cu Flat

Sample ID	1205193-005EMSD	SampType:	MSD		TestCode:	EPA Method 200.7: Dissolved Metals				
Client ID:	BatchQC	Batch ID:	R2670		RunNo:	2670				
Prep Date:		Analysis Date:	5/9/2012		SeqNo:	74186	Units:	mg/L		
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Magnesium	390	5.0	250.0	124.9	106	70	130	0.684	20	
Sodium	460	5.0	250.0	192.5	106	70	130	0.966	20	

Sample ID	MB	SampType:	MBLK		TestCode:	EPA Method 200.7: Dissolved Metals				
Client ID:	PBW	Batch ID:	R2670		RunNo:	2670				
Prep Date:	5/9/2012	Analysis Date:	5/9/2012		SeqNo:	74215	Units:	mg/L		
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Boron	ND	0.040								
Calcium	ND	1.0								
Iron	ND	0.020								
Magnesium	ND	1.0								
Potassium	ND	1.0								
Sodium	ND	1.0								

Sample ID	LCS	SampType:	LCS		TestCode:	EPA Method 200.7: Dissolved Metals				
Client ID:	LCSW	Batch ID:	R2670		RunNo:	2670				
Prep Date:		Analysis Date:	5/9/2012		SeqNo:	74216	Units:	mg/L		
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Boron	0.51	0.040	0.5000	0	101	85	115			
Calcium	54	1.0	50.00	0	107	85	115			
Iron	0.47	0.020	0.5000	0.004190	93.2	85	115			
Magnesium	54	1.0	50.00	0	109	85	115			
Potassium	53	1.0	50.00	0	106	85	115			
Sodium	54	1.0	50.00	0	107	85	115			

Qualifiers:

*/X	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
E	Value above quantitation range	H	Holding times for preparation or analysis exceeded
J	Analyte detected below quantitation limits	ND	Not Detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Detection Limit

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: **1205076**

14-May-12

Client: New Mexico Copper Corp

Project: Cu Flat

Sample ID **MB**	SampType: **MBLK**	TestCode: **EPA Method 200.7: Dissolved Metals**
Client ID: **PBW**	Batch ID: **R2622**	RunNo: **2622**
Prep Date:	Analysis Date: **5/8/2012**	SeqNo: **72991** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Aluminum	ND	0.020								
Barium	ND	0.0020								
Beryllium	ND	0.0020								
Cadmium	ND	0.0020								
Chromium	ND	0.0060								
Cobalt	ND	0.0060								
Copper	ND	0.0060								
Lead	ND	0.0050								
Manganese	ND	0.0020								
Molybdenum	ND	0.0080								
Nickel	ND	0.010								
Silicon	ND	0.080								
Silver	ND	0.0050								
Vanadium	ND	0.050								
Zinc	ND	0.010								

Sample ID **LCS**	SampType: **LCS**	TestCode: **EPA Method 200.7: Dissolved Metals**
Client ID: **LCSW**	Batch ID: **R2622**	RunNo: **2622**
Prep Date:	Analysis Date: **5/8/2012**	SeqNo: **72992** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Aluminum	0.52	0.020	0.5000	0	105	85	115			
Barium	0.49	0.0020	0.5000	0	98.9	85	115			
Beryllium	0.52	0.0020	0.5000	0	103	85	115			
Cadmium	0.50	0.0020	0.5000	0	99.2	85	115			
Chromium	0.49	0.0060	0.5000	0	98.5	85	115			
Cobalt	0.47	0.0060	0.5000	0	94.9	85	115			
Copper	0.50	0.0060	0.5000	0	99.9	85	115			
Lead	0.50	0.0050	0.5000	0	99.3	85	115			
Manganese	0.48	0.0020	0.5000	0	96.9	85	115			
Molybdenum	0.49	0.0080	0.5000	0.002030	98.4	85	115			
Nickel	0.47	0.010	0.5000	0	93.9	85	115			
Silicon	2.6	0.080	2.500	0	104	85	115			
Silver	0.094	0.0050	0.1000	0	94.1	85	115			
Vanadium	0.52	0.050	0.5000	0	104	85	115			
Zinc	0.50	0.010	0.5000	0	101	85	115			

Sample ID **1205193-005EMS**	SampType: **MS**	TestCode: **EPA Method 200.7: Dissolved Metals**
Client ID: **BatchQC**	Batch ID: **R2622**	RunNo: **2622**
Prep Date:	Analysis Date: **5/8/2012**	SeqNo: **73030** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual

Qualifiers:

- */X Value exceeds Maximum Contaminant Level.
- E Value above quantitation range
- J Analyte detected below quantitation limits
- R RPD outside accepted recovery limits
- B Analyte detected in the associated Method Blank
- H Holding times for preparation or analysis exceeded
- ND Not Detected at the Reporting Limit
- RL Reporting Detection Limit

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: **1205076**

14-May-12

Client: New Mexico Copper Corp

Project: Cu Flat

Sample ID **1205193-005EMS** SampType: **MS** TestCode: **EPA Method 200.7: Dissolved Metals**
Client ID: **BatchQC** Batch ID: **R2622** RunNo: **2622**
Prep Date: Analysis Date: **5/8/2012** SeqNo: **73030** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Aluminum	0.54	0.020	0.5000	0	107	70	130			
Barium	0.52	0.0020	0.5000	0.02182	98.9	70	130			
Zinc	0.54	0.010	0.5000	0.03785	101	70	130			

Sample ID **1205193-005EMSD** SampType: **MSD** TestCode: **EPA Method 200.7: Dissolved Metals**
Client ID: **BatchQC** Batch ID: **R2622** RunNo: **2622**
Prep Date: Analysis Date: **5/8/2012** SeqNo: **73031** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Aluminum	0.53	0.020	0.5000	0	106	70	130	1.33	20	
Barium	0.51	0.0020	0.5000	0.02182	97.2	70	130	1.71	20	
Zinc	0.53	0.010	0.5000	0.03785	98.0	70	130	2.48	20	

Sample ID **1205193-005EMS** SampType: **MS** TestCode: **EPA Method 200.7: Dissolved Metals**
Client ID: **BatchQC** Batch ID: **R2670** RunNo: **2670**
Prep Date: Analysis Date: **5/9/2012** SeqNo: **74182** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Potassium	56	1.0	50.00	4.808	102	70	130			

Sample ID **1205193-005EMSD** SampType: **MSD** TestCode: **EPA Method 200.7: Dissolved Metals**
Client ID: **BatchQC** Batch ID: **R2670** RunNo: **2670**
Prep Date: Analysis Date: **5/9/2012** SeqNo: **74183** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Potassium	57	1.0	50.00	4.808	104	70	130	2.44	20	

Sample ID **1205193-005EMS** SampType: **MS** TestCode: **EPA Method 200.7: Dissolved Metals**
Client ID: **BatchQC** Batch ID: **R2670** RunNo: **2670**
Prep Date: Analysis Date: **5/9/2012** SeqNo: **74185** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Iron	4.5	0.10	2.500	2.034	99.6	70	130			
Magnesium	390	5.0	250.0	124.9	107	70	130			
Sodium	460	5.0	250.0	192.5	107	70	130			

Sample ID **1205193-005EMSD** SampType: **MSD** TestCode: **EPA Method 200.7: Dissolved Metals**
Client ID: **BatchQC** Batch ID: **R2670** RunNo: **2670**
Prep Date: Analysis Date: **5/9/2012** SeqNo: **74186** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Iron	4.6	0.10	2.500	2.034	101	70	130	1.03	20	

Qualifiers:

- */X Value exceeds Maximum Contaminant Level.
- E Value above quantitation range
- J Analyte detected below quantitation limits
- R RPD outside accepted recovery limits
- B Analyte detected in the associated Method Blank
- H Holding times for preparation or analysis exceeded
- ND Not Detected at the Reporting Limit
- RL Reporting Detection Limit

Analytical Report
Lab Order **1205076**
Date Reported: **5/14/2012**

Hall Environmental Analysis Laboratory, Inc.

CLIENT: New Mexico Copper Corp
Client Sample ID: PW-1
Project: Cu Flat
Collection Date: 5/1/2012 2:00:00 PM
Lab ID: 1205076-001 **Matrix:** AQUEOUS **Received Date:** 5/2/2012 7:30:00 AM

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
EPA METHOD 300.0: ANIONS						Analyst: **BRM**
Fluoride	1.0	0.10		mg/L	1	5/2/2012 12:52:03 PM
Chloride	32	10		mg/L	20	5/2/2012 1:03:17 PM
Nitrogen, Nitrite (As N)	ND	0.10		mg/L	1	5/2/2012 12:52:03 PM
Nitrogen, Nitrate (As N)	0.59	0.10		mg/L	1	5/2/2012 12:52:03 PM
Sulfate	28	0.50		mg/L	1	5/2/2012 12:52:03 PM
EPA METHOD 200.7: DISSOLVED METALS						Analyst: **ELS**
Aluminum	ND	0.020		mg/L	1	5/8/2012 8:02:55 AM
Barium	0.011	0.0020		mg/L	1	5/8/2012 8:02:55 AM
Beryllium	ND	0.0020		mg/L	1	5/8/2012 8:02:55 AM
Boron	0.065	0.040		mg/L	1	5/9/2012 8:36:51 AM
Cadmium	ND	0.0020		mg/L	1	5/8/2012 8:02:55 AM
Calcium	36	1.0		mg/L	1	5/9/2012 8:36:51 AM
Chromium	ND	0.0060		mg/L	1	5/8/2012 8:02:55 AM
Cobalt	ND	0.0060		mg/L	1	5/8/2012 8:02:55 AM
Copper	ND	0.0060		mg/L	1	5/8/2012 8:02:55 AM
Iron	0.040	0.020		mg/L	1	5/9/2012 8:36:51 AM
Lead	ND	0.0050		mg/L	1	5/8/2012 8:02:55 AM
Magnesium	3.1	1.0		mg/L	1	5/9/2012 8:36:51 AM
Manganese	0.0024	0.0020		mg/L	1	5/8/2012 8:02:55 AM
Molybdenum	ND	0.0080		mg/L	1	5/8/2012 8:02:55 AM
Nickel	ND	0.010		mg/L	1	5/8/2012 8:02:55 AM
Potassium	3.4	1.0		mg/L	1	5/9/2012 8:36:51 AM
Silicon	17	0.40		mg/L	5	5/8/2012 8:06:09 AM
Silver	ND	0.0050		mg/L	1	5/8/2012 8:02:55 AM
Sodium	58	1.0		mg/L	1	5/9/2012 8:36:51 AM
Vanadium	ND	0.050		mg/L	1	5/8/2012 8:02:55 AM
Zinc	0.024	0.010		mg/L	1	5/8/2012 8:02:55 AM
EPA 200.8: DISSOLVED METALS						Analyst: **SNV**
Antimony	ND	0.0010		mg/L	1	5/8/2012 1:15:26 PM
Arsenic	0.0033	0.0010		mg/L	1	5/8/2012 1:15:26 PM
Selenium	ND	0.0010		mg/L	1	5/10/2012 2:28:58 PM
Thallium	ND	0.0010		mg/L	1	5/8/2012 1:15:26 PM
Uranium ✓	0.0032	0.0010		mg/L	1	5/10/2012 2:28:58 PM
EPA METHOD 245.1: MERCURY						Analyst: **ELS**
Mercury	ND	0.00020		mg/L	1	5/9/2012 11:59:45 AM
SM2340B: HARDNESS						Analyst: **ELS**
Hardness (As CaCO3)	100	6.6		mg/L	1	5/9/2012
EPA 120.1: SPECIFIC CONDUCTANCE						Analyst: **DBD**
Conductivity	450	0.010		µmhos/cm	1	5/7/2012 12:31:49 PM

Qualifiers:

*/X	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
E	Value above quantitation range	H	Holding times for preparation or analysis exceeded
J	Analyte detected below quantitation limits	ND	Not Detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Detection Limit
S	Spike Recovery outside accepted recovery limits		

HALL ENVIRONMENTAL ANALYSIS LABORATORY

Hall Environmental Analysis Laboratory
4901 Hawkins NE
Albuquerque, NM 87109
TEL: 505-345-3975 FAX: 505-345-4107
Website: www.hallenvironmental.com

May 14, 2012

Katie Emmer

New Mexico Copper Corp
2425 San Pedro Dr NE Ste 100
Albuquerque, New Mexico 87109
TEL: (505) 400-7925
FAX

RE: Cu Flat OrderNo.: 1205076

Dear Katie Emmer:

Hall Environmental Analysis Laboratory received 1 sample(s) on 5/2/2012 for the analyses presented in the following report.

These were analyzed according to EPA procedures or equivalent. To access our accredited tests please go to www.hallenvironmental.com or the state specific web sites. See the sample checklist and/or the Chain of Custody for information regarding the sample receipt temperature and preservation. Data qualifiers or a narrative will be provided if the sample analysis or analytical quality control parameters require a flag. All samples are reported as received unless otherwise indicated.

Please don't hesitate to contact HEAL for any additional information or clarifications.

Sincerely,

Andy Freeman
Laboratory Manager
4901 Hawkins NE
Albuquerque, NM 87109

Hall Environmental Analysis Laboratory, Inc.

CLIENT: New Mexico Copper Corp
Client Sample ID: PW-1
Project: Cu Flat
Collection Date: 5/1/2012 2:00:00 PM
Lab ID: 1205076-001
Matrix: AQUEOUS
Received Date: 5/2/2012 7:30:00 AM

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
SM4500-H+B: PH						Analyst: **JLF**
pH	8.02	1.68	H	pH units	1	5/3/2012 1:22:52 PM
SM2320B: ALKALINITY						Analyst: **JLF**
Bicarbonate (As CaCO3)	150	20		mg/L CaCO3	1	5/3/2012 1:22:52 PM
Carbonate (As CaCO3)	ND	2.0		mg/L CaCO3	1	5/3/2012 1:22:52 PM
Total Alkalinity (as CaCO3)	150	20		mg/L CaCO3	1	5/3/2012 1:22:52 PM
SM2540C MOD: TOTAL DISSOLVED SOLIDS						Analyst: **KS**
Total Dissolved Solids	294	20.0		mg/L	1	5/8/2012 3:12:00 PM
SM 2540D: TSS						Analyst: **KS**
Suspended Solids	ND	4.0		mg/L	1	5/3/2012 5:30:00 PM

Qualifiers:

*/X	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
E	Value above quantitation range	H	Holding times for preparation or analysis exceeded
J	Analyte detected below quantitation limits	ND	Not Detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Detection Limit
S	Spike Recovery outside accepted recovery limits		

Anatek Labs, Inc.

1282 Alturas Drive • Moscow, ID 83843 • (208) 883-2839 • Fax (208) 882-9246 • email moscow@anateklabs.com
504 E Sprague Ste. D • Spokane WA 99202 • (509) 838-3999 • Fax (509) 838-4433 • email spokane@anateklabs.com

Client:	HALL ENVIRONMENTAL ANALYSIS LAB	**Batch #:**	120503026
Address:	4901 HAWKINS NE SUITE D ALBUQUERQUE, NM 87109	**Project Name:**	1205076
Attn:	ANDY FREEMAN		

Analytical Results Report

Sample Number	120503026-001	**Sampling Date**	5/1/2012	**Date/Time Received**	5/3/2012	12:24 PM
Client Sample ID	1205076-001D / PW-1	**Sampling Time**	2:00 PM	**Extraction Date**		
Matrix	Water	**Sample Location**				
Comments						

Parameter	Result	Units	PQL	Analysis Date	Analyst	Method	Qualifier
Cyanide	ND	mg/L	0.01	5/11/2012	CRW	EPA 335.4	

Authorized Signature

John Coddington, Lab Manager

MCL EPA's Maximum Contaminant Level
ND Not Detected
PQL Practical Quantitation Limit

This report shall not be reproduced except in full, without the written approval of the laboratory.
The results reported relate only to the samples indicated.
Soil/solid results are reported on a dry-weight basis unless otherwise noted.

Certifications held by Anatek Labs ID: EPA:ID00013; AZ:0701; CO:ID00013; FL(NELAP):E87893; ID:ID00013; IN:C-ID-01; KY:90142; MT:CERT0028; NM: ID00013; OR:ID200001-002; WA:C595
Certifications held by Anatek Labs WA: EPA:WA00169; ID:WA00169; WA:C585; MT:Cert0095



Figure 1. Vicinity Map



Figure 2: Project Area with Proposed Alternatives

Analytical Report
Lab Order **1205153**
Date Reported: **5/14/2012**

Hall Environmental Analysis Laboratory, Inc.

CLIENT: New Mexico Copper Corp
Project: Cu Flat
Lab ID: 1205153-001 **Matrix:** AQUEOUS

Client Sample ID: PW-3
Collection Date: 5/2/2012 2:30:00 PM
Received Date: 5/3/2012 8:35:00 AM

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
EPA METHOD 300.0: ANIONS						Analyst: **BRM**
Fluoride	1.9	0.10		mg/L	1	5/3/2012 12:04:13 PM
Chloride	50	10		mg/L	20	5/3/2012 12:41:28 PM
Nitrogen, Nitrite (As N)	ND	0.10		mg/L	1	5/3/2012 12:04:13 PM
Nitrogen, Nitrate (As N)	0.70	0.10		mg/L	1	5/3/2012 12:04:13 PM
Sulfate	26	0.50		mg/L	1	5/3/2012 12:04:13 PM
EPA METHOD 200.7: DISSOLVED METALS						Analyst: **ELS**
Aluminum	ND	0.020		mg/L	1	5/8/2012 8:09:23 AM
Barium	0.0078	0.0020		mg/L	1	5/8/2012 8:09:23 AM
Beryllium	ND	0.0020		mg/L	1	5/8/2012 8:09:23 AM
Boron	0.095	0.040		mg/L	1	5/9/2012 8:40:03 AM
Cadmium	ND	0.0020		mg/L	1	5/8/2012 8:09:23 AM
Calcium	20	1.0		mg/L	1	5/9/2012 8:40:03 AM
Chromium	0.0060	0.0060		mg/L	1	5/8/2012 8:09:23 AM
Cobalt	ND	0.0060		mg/L	1	5/8/2012 8:09:23 AM
Copper	ND	0.0060		mg/L	1	5/8/2012 8:09:23 AM
Iron	0.065	0.020		mg/L	1	5/9/2012 8:40:03 AM
Lead	ND	0.0050		mg/L	1	5/8/2012 8:09:23 AM
Magnesium	1.0	1.0		mg/L	1	5/9/2012 8:40:03 AM
Manganese	0.0026	0.0020		mg/L	1	5/8/2012 8:09:23 AM
Molybdenum	ND	0.0080		mg/L	1	5/8/2012 8:09:23 AM
Nickel	ND	0.010		mg/L	1	5/8/2012 8:09:23 AM
Potassium	3.3	1.0		mg/L	1	5/9/2012 8:40:03 AM
Silicon	21	0.40		mg/L	5	5/8/2012 8:12:46 AM
Silver	ND	0.0050		mg/L	1	5/8/2012 8:09:23 AM
Sodium	81	1.0		mg/L	1	5/9/2012 8:40:03 AM
Vanadium	ND	0.050		mg/L	1	5/8/2012 8:09:23 AM
Zinc	0.021	0.010		mg/L	1	5/8/2012 8:09:23 AM
EPA 200.8: DISSOLVED METALS						Analyst: **SNV**
Antimony	ND	0.0010		mg/L	1	5/8/2012 1:19:22 PM
Arsenic	0.0074	0.0010		mg/L	1	5/8/2012 1:19:22 PM
Selenium	ND	0.0010		mg/L	1	5/10/2012 2:32:54 PM
Thallium	ND	0.0010		mg/L	1	5/8/2012 1:19:22 PM
Uranium	0.0013	0.0010		mg/L	1	5/10/2012 2:32:54 PM
EPA METHOD 245.1: MERCURY						Analyst: **ELS**
Mercury	ND	0.00020		mg/L	1	5/9/2012 12:01:31 PM
SM2340B: HARDNESS						Analyst: **ELS**
Hardness (As CaCO3)	53	6.6		mg/L	1	5/9/2012
EPA 120.1: SPECIFIC CONDUCTANCE						Analyst: **DBD**
Conductivity	460	0.010		µmhos/cm	1	5/7/2012 12:36:13 PM

Qualifiers:

*/X	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
E	Value above quantitation range	H	Holding times for preparation or analysis exceeded
J	Analyte detected below quantitation limits	ND	Not Detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Detection Limit
S	Spike Recovery outside accepted recovery limits		

Hall Environmental Analysis Laboratory, Inc.

CLIENT: New Mexico Copper Corp
Client Sample ID: PW-3
Project: Cu Flat
Collection Date: 5/2/2012 2:30:00 PM
Lab ID: 1205153-001 **Matrix:** AQUEOUS **Received Date:** 5/3/2012 8:35:00 AM

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
SM4500-H+B: PH						Analyst: **JLF**
pH	8.03	1.68	H	pH units	1	5/3/2012 5:14:04 PM
SM2320B: ALKALINITY						Analyst: **JLF**
Bicarbonate (As CaCO3)	120	20		mg/L CaCO3	1	5/3/2012 5:14:04 PM
Carbonate (As CaCO3)	ND	2.0		mg/L CaCO3	1	5/3/2012 5:14:04 PM
Total Alkalinity (as CaCO3)	120	20		mg/L CaCO3	1	5/3/2012 5:14:04 PM
SM2540C MOD: TOTAL DISSOLVED SOLIDS						Analyst: **KS**
Total Dissolved Solids	303	20.0		mg/L	1	5/8/2012 3:12:00 PM
SM 2540D: TSS						Analyst: **KS**
Suspended Solids	ND	4.0		mg/L	1	5/4/2012 4:36:00 PM

Qualifiers:

*/X	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
E	Value above quantitation range	H	Holding times for preparation or analysis exceeded
J	Analyte detected below quantitation limits	ND	Not Detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Detection Limit
S	Spike Recovery outside accepted recovery limits		

Anatek Labs, Inc.

1282 Alturas Drive • Moscow, ID 83843 • (208) 883-2839 • Fax (208) 882-9246 • email moscow@anateklabs.com
504 E Sprague Ste. D • Spokane WA 99202 • (509) 838-3999 • Fax (509) 838-4433 • email spokane@anateklabs.com

Client:	HALL ENVIRONMENTAL ANALYSIS LAB	**Batch #:**	120504004
Address:	4901 HAWKINS NE SUITE D ALBUQUERQUE, NM 87109	**Project Name:**	1205153
Attn:	ANDY FREEMAN		

Analytical Results Report

Sample Number	120504004-001	**Sampling Date**	5/2/2012	**Date/Time Received**	5/4/2012	10:18 AM
Client Sample ID	1205153-001D / PW-3	**Sampling Time**	2:30 PM			
Matrix	Water	**Sample Location**				
Comments						

Parameter	Result	Units	PQL	Analysis Date	Analyst	Method	Qualifier
Cyanide	ND	mg/L	0.01	5/8/2012	CRW	EPA 335.4	

Authorized Signature

John Coddington, Lab Manager

MCL	EPA's Maximum Contaminant Level
ND	Not Detected
PQL	Practical Quantitation Limit

This report shall not be reproduced except in full, without the written approval of the laboratory.
The results reported relate only to the samples indicated.
Soil/solid results are reported on a dry-weight basis unless otherwise noted.

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: **1205153**

14-May-12

Client: New Mexico Copper Corp

Project: Cu Flat

Sample ID **MB**	SampType: **MBLK**	TestCode: **EPA Method 200.7: Dissolved Metals**
Client ID: **PBW**	Batch ID: **R2622**	RunNo: **2622**
Prep Date:	Analysis Date: **5/8/2012**	SeqNo: **72991** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Aluminum	ND	0.020								
Barium	ND	0.0020								
Beryllium	ND	0.0020								
Cadmium	ND	0.0020								
Chromium	ND	0.0060								
Cobalt	ND	0.0060								
Copper	ND	0.0060								
Lead	ND	0.0050								
Manganese	ND	0.0020								
Molybdenum	ND	0.0080								
Nickel	ND	0.010								
Silicon	ND	0.080								
Silver	ND	0.0050								
Vanadium	ND	0.050								
Zinc	ND	0.010								

Sample ID **LCS**	SampType: **LCS**	TestCode: **EPA Method 200.7: Dissolved Metals**
Client ID: **LCSW**	Batch ID: **R2622**	RunNo: **2622**
Prep Date:	Analysis Date: **5/8/2012**	SeqNo: **72992** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Aluminum	0.52	0.020	0.5000	0	105	85	115			
Barium	0.49	0.0020	0.5000	0	98.9	85	115			
Beryllium	0.52	0.0020	0.5000	0	103	85	115			
Cadmium	0.50	0.0020	0.5000	0	99.2	85	115			
Chromium	0.49	0.0060	0.5000	0	98.5	85	115			
Cobalt	0.47	0.0060	0.5000	0	94.9	85	115			
Copper	0.50	0.0060	0.5000	0	99.9	85	115			
Lead	0.50	0.0050	0.5000	0	99.3	85	115			
Manganese	0.48	0.0020	0.5000	0	96.9	85	115			
Molybdenum	0.49	0.0080	0.5000	0.002030	98.4	85	115			
Nickel	0.47	0.010	0.5000	0	93.9	85	115			
Silicon	2.6	0.080	2.500	0	104	85	115			
Silver	0.094	0.0050	0.1000	0	94.1	85	115			
Vanadium	0.52	0.050	0.5000	0	104	85	115			
Zinc	0.50	0.010	0.5000	0	101	85	115			

Sample ID **1205193-005EMS**	SampType: **MS**	TestCode: **EPA Method 200.7: Dissolved Metals**
Client ID: **BatchQC**	Batch ID: **R2622**	RunNo: **2622**
Prep Date:	Analysis Date: **5/8/2012**	SeqNo: **73030** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual

Qualifiers:

- */X Value exceeds Maximum Contaminant Level.
- E Value above quantitation range
- J Analyte detected below quantitation limits
- R RPD outside accepted recovery limits
- B Analyte detected in the associated Method Blank
- H Holding times for preparation or analysis exceeded
- ND Not Detected at the Reporting Limit
- RL Reporting Detection Limit

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: **1205153**

14-May-12

Client: New Mexico Copper Corp

Project: Cu Flat

Sample ID **1205193-005EMS** SampType: **MS** TestCode: **EPA Method 200.7: Dissolved Metals**
Client ID: **BatchQC** Batch ID: **R2622** RunNo: **2622**
Prep Date: Analysis Date: **5/8/2012** SeqNo: **73030** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Aluminum	0.54	0.020	0.5000	0	107	70	130			
Barium	0.52	0.0020	0.5000	0.02182	98.9	70	130			
Zinc	0.54	0.010	0.5000	0.03785	101	70	130			

Sample ID **1205193-005EMSD** SampType: **MSD** TestCode: **EPA Method 200.7: Dissolved Metals**
Client ID: **BatchQC** Batch ID: **R2622** RunNo: **2622**
Prep Date: Analysis Date: **5/8/2012** SeqNo: **73031** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Aluminum	0.53	0.020	0.5000	0	106	70	130	1.33	20	
Barium	0.51	0.0020	0.5000	0.02182	97.2	70	130	1.71	20	
Zinc	0.53	0.010	0.5000	0.03785	98.0	70	130	2.48	20	

Sample ID **1205193-005EMS** SampType: **MS** TestCode: **EPA Method 200.7: Dissolved Metals**
Client ID: **BatchQC** Batch ID: **R2670** RunNo: **2670**
Prep Date: Analysis Date: **5/9/2012** SeqNo: **74182** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Potassium	56	1.0	50.00	4.808	102	70	130			

Sample ID **1205193-005EMSD** SampType: **MSD** TestCode: **EPA Method 200.7: Dissolved Metals**
Client ID: **BatchQC** Batch ID: **R2670** RunNo: **2670**
Prep Date: Analysis Date: **5/9/2012** SeqNo: **74183** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Potassium	57	1.0	50.00	4.808	104	70	130	2.44	20	

Sample ID **1205193-005EMS** SampType: **MS** TestCode: **EPA Method 200.7: Dissolved Metals**
Client ID: **BatchQC** Batch ID: **R2670** RunNo: **2670**
Prep Date: Analysis Date: **5/9/2012** SeqNo: **74185** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Iron	4.5	0.10	2.500	2.034	99.6	70	130			
Magnesium	390	5.0	250.0	124.9	107	70	130			
Sodium	460	5.0	250.0	192.5	107	70	130			

Sample ID **1205193-005EMSD** SampType: **MSD** TestCode: **EPA Method 200.7: Dissolved Metals**
Client ID: **BatchQC** Batch ID: **R2670** RunNo: **2670**
Prep Date: Analysis Date: **5/9/2012** SeqNo: **74186** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Iron	4.6	0.10	2.500	2.034	101	70	130	1.03	20	

Qualifiers:

- */X Value exceeds Maximum Contaminant Level.
- E Value above quantitation range
- J Analyte detected below quantitation limits
- R RPD outside accepted recovery limits
- B Analyte detected in the associated Method Blank
- H Holding times for preparation or analysis exceeded
- ND Not Detected at the Reporting Limit
- RL Reporting Detection Limit

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: **1205153**

14-May-12

Client: New Mexico Copper Corp

Project: Cu Flat

Sample ID	1205193-005EMSD	SampType:	MSD		TestCode:	EPA Method 200.7: Dissolved Metals				
Client ID:	BatchQC	Batch ID:	R2670		RunNo:	2670				
Prep Date:		Analysis Date:	5/9/2012		SeqNo:	74186	Units:	mg/L		
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Magnesium	390	5.0	250.0	124.9	106	70	130	0.684	20	
Sodium	460	5.0	250.0	192.5	106	70	130	0.966	20	

Sample ID	MB	SampType:	MBLK		TestCode:	EPA Method 200.7: Dissolved Metals				
Client ID:	PBW	Batch ID:	R2670		RunNo:	2670				
Prep Date:	5/9/2012	Analysis Date:	5/9/2012		SeqNo:	74215	Units:	mg/L		
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Boron	ND	0.040								
Calcium	ND	1.0								
Iron	ND	0.020								
Magnesium	ND	1.0								
Potassium	ND	1.0								
Sodium	ND	1.0								

Sample ID	LCS	SampType:	LCS		TestCode:	EPA Method 200.7: Dissolved Metals				
Client ID:	LCSW	Batch ID:	R2670		RunNo:	2670				
Prep Date:		Analysis Date:	5/9/2012		SeqNo:	74216	Units:	mg/L		
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Boron	0.51	0.040	0.5000	0	101	85	115			
Calcium	54	1.0	50.00	0	107	85	115			
Iron	0.47	0.020	0.5000	0.004190	93.2	85	115			
Magnesium	54	1.0	50.00	0	109	85	115			
Potassium	53	1.0	50.00	0	106	85	115			
Sodium	54	1.0	50.00	0	107	85	115			

Qualifiers:

- */X Value exceeds Maximum Contaminant Level.
- E Value above quantitation range
- J Analyte detected below quantitation limits
- R RPD outside accepted recovery limits
- B Analyte detected in the associated Method Blank
- H Holding times for preparation or analysis exceeded
- ND Not Detected at the Reporting Limit
- RL Reporting Detection Limit

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: **1205153**

14-May-12

Client: New Mexico Copper Corp

Project: Cu Flat

Sample ID **LCS**	SampType: **LCS**	TestCode: **EPA 200.8: Dissolved Metals**
Client ID: **LCSW**	Batch ID: **R2629**	RunNo: **2629**
Prep Date:	Analysis Date: **5/8/2012**	SeqNo: **73283** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Antimony	0.023	0.0010	0.02500	0	92.8	85	115			
Arsenic	0.023	0.0010	0.02500	0	93.1	85	115			
Thallium	0.023	0.0010	0.02500	0	92.9	85	115			

Sample ID **MB**	SampType: **MBLK**	TestCode: **EPA 200.8: Dissolved Metals**
Client ID: **PBW**	Batch ID: **R2629**	RunNo: **2629**
Prep Date:	Analysis Date: **5/8/2012**	SeqNo: **73284** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Antimony	ND	0.0010								
Arsenic	ND	0.0010								
Thallium	ND	0.0010								

Sample ID **LCS**	SampType: **LCS**	TestCode: **EPA 200.8: Dissolved Metals**
Client ID: **LCSW**	Batch ID: **R2708**	RunNo: **2708**
Prep Date:	Analysis Date: **5/10/2012**	SeqNo: **75447** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Selenium	0.026	0.0010	0.02500	0	104	85	115			
Uranium	0.025	0.0010	0.02500	0	99.2	85	115			

Sample ID **MB**	SampType: **MBLK**	TestCode: **EPA 200.8: Dissolved Metals**
Client ID: **PBW**	Batch ID: **R2708**	RunNo: **2708**
Prep Date:	Analysis Date: **5/10/2012**	SeqNo: **75448** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Selenium	ND	0.0010								
Uranium	ND	0.0010								

Qualifiers:

*/X	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
E	Value above quantitation range	H	Holding times for preparation or analysis exceeded
J	Analyte detected below quantitation limits	ND	Not Detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Detection Limit

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: **1205153**

14-May-12

Client: New Mexico Copper Corp

Project: Cu Flat

Sample ID	**MB-1862**	SampType:	**MBLK**	TestCode:	**EPA Method 245.1: Mercury**					
Client ID:	**PBW**	Batch ID:	**1862**	RunNo:	**2669**					
Prep Date:	**5/9/2012**	Analysis Date:	**5/9/2012**	SeqNo:	**74223**	Units:	**mg/L**			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Mercury	ND	0.00020								

Sample ID	**LCS-1862**	SampType:	**LCS**	TestCode:	**EPA Method 245.1: Mercury**					
Client ID:	**LCSW**	Batch ID:	**1862**	RunNo:	**2669**					
Prep Date:	**5/9/2012**	Analysis Date:	**5/9/2012**	SeqNo:	**74224**	Units:	**mg/L**			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Mercury	0.0049	0.00020	0.005000	0	97.4	80	120			

Sample ID	**1204854-004AMS**	SampType:	**MS**	TestCode:	**EPA Method 245.1: Mercury**					
Client ID:	**BatchQC**	Batch ID:	**1862**	RunNo:	**2669**					
Prep Date:	**5/9/2012**	Analysis Date:	**5/9/2012**	SeqNo:	**74226**	Units:	**mg/L**			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Mercury	0.0049	0.00020	0.005000	0	97.2	75	125			

Sample ID	**1204854-004AMSD**	SampType:	**MSD**	TestCode:	**EPA Method 245.1: Mercury**					
Client ID:	**BatchQC**	Batch ID:	**1862**	RunNo:	**2669**					
Prep Date:	**5/9/2012**	Analysis Date:	**5/9/2012**	SeqNo:	**74227**	Units:	**mg/L**			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Mercury	0.0049	0.00020	0.005000	0	97.1	75	125	0.0957	20	

Qualifiers:

*/X	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
E	Value above quantitation range	H	Holding times for preparation or analysis exceeded
J	Analyte detected below quantitation limits	ND	Not Detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Detection Limit

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: **1205153**

14-May-12

Client: New Mexico Copper Corp

Project: Cu Flat

Sample ID **MB**	SampType: **MBLK**	TestCode: **EPA Method 300.0: Anions**
Client ID: **PBW**	Batch ID: **R2561**	RunNo: **2561**
Prep Date:	Analysis Date: **5/3/2012**	SeqNo: **71254** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Fluoride	ND	0.10								
Chloride	ND	0.50								
Nitrogen, Nitrite (As N)	ND	0.10								
Nitrogen, Nitrate (As N)	ND	0.10								
Sulfate	ND	0.50								

Sample ID **LCS**	SampType: **LCS**	TestCode: **EPA Method 300.0: Anions**
Client ID: **LCSW**	Batch ID: **R2561**	RunNo: **2561**
Prep Date:	Analysis Date: **5/3/2012**	SeqNo: **71255** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Fluoride	0.48	0.10	0.5000	0	95.5	90	110			
Chloride	4.8	0.50	5.000	0	96.2	90	110			
Nitrogen, Nitrite (As N)	0.98	0.10	1.000	0	98.2	90	110			
Nitrogen, Nitrate (As N)	2.5	0.10	2.500	0	101	90	110			
Sulfate	9.8	0.50	10.00	0	97.5	90	110			

Sample ID **1205153-001AMS**	SampType: **MS**	TestCode: **EPA Method 300.0: Anions**
Client ID: **PW-3**	Batch ID: **R2561**	RunNo: **2561**
Prep Date:	Analysis Date: **5/3/2012**	SeqNo: **71257** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Fluoride	2.4	0.10	0.5000	1.941	84.8	72.9	113			
Nitrogen, Nitrite (As N)	0.96	0.10	1.000	0	96.5	77.6	111			
Nitrogen, Nitrate (As N)	3.3	0.10	2.500	0.7031	102	82.8	116			
Sulfate	37	0.50	10.00	26.34	106	80.5	119			

Sample ID **1205153-001AMSD**	SampType: **MSD**	TestCode: **EPA Method 300.0: Anions**
Client ID: **PW-3**	Batch ID: **R2561**	RunNo: **2561**
Prep Date:	Analysis Date: **5/3/2012**	SeqNo: **71258** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Fluoride	2.4	0.10	0.5000	1.941	84.1	72.9	113	0.155	20	
Nitrogen, Nitrite (As N)	0.92	0.10	1.000	0	92.4	77.6	111	4.30	20	
Nitrogen, Nitrate (As N)	3.1	0.10	2.500	0.7031	97.9	82.8	116	3.36	20	
Sulfate	37	0.50	10.00	26.34	102	80.5	119	1.04	20	

Sample ID **1205167-005AMS**	SampType: **MS**	TestCode: **EPA Method 300.0: Anions**
Client ID: **BatchQC**	Batch ID: **R2561**	RunNo: **2561**
Prep Date:	Analysis Date: **5/3/2012**	SeqNo: **71285** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual

Qualifiers:

- */X Value exceeds Maximum Contaminant Level.
- E Value above quantitation range
- J Analyte detected below quantitation limits
- R RPD outside accepted recovery limits
- B Analyte detected in the associated Method Blank
- H Holding times for preparation or analysis exceeded
- ND Not Detected at the Reporting Limit
- RL Reporting Detection Limit

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: **1205153**

14-May-12

Client: New Mexico Copper Corp

Project: Cu Flat

Sample ID	1205167-005AMS	SampType:	MS		TestCode:	EPA Method 300.0: Anions				
Client ID:	BatchQC	Batch ID:	R2561		RunNo:	2561				
Prep Date:		Analysis Date:	5/3/2012		SeqNo:	71285	Units:	mg/L		
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Nitrogen, Nitrite (As N)	0.94	0.10	1.000	0	94.4	77.6	111			

Sample ID	1205167-005AMSD	SampType:	MSD		TestCode:	EPA Method 300.0: Anions				
Client ID:	BatchQC	Batch ID:	R2561		RunNo:	2561				
Prep Date:		Analysis Date:	5/3/2012		SeqNo:	71286	Units:	mg/L		
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Nitrogen, Nitrite (As N)	0.94	0.10	1.000	0	94.4	77.6	111	0.0232	20	

Sample ID	MB	SampType:	MBLK		TestCode:	EPA Method 300.0: Anions				
Client ID:	PBW	Batch ID:	R2561		RunNo:	2561				
Prep Date:		Analysis Date:	5/4/2012		SeqNo:	71314	Units:	mg/L		
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Fluoride	ND	0.10								
Chloride	ND	0.50								
Nitrogen, Nitrite (As N)	ND	0.10								
Nitrogen, Nitrate (As N)	ND	0.10								
Sulfate	ND	0.50								

Sample ID	LCS	SampType:	LCS		TestCode:	EPA Method 300.0: Anions				
Client ID:	LCSW	Batch ID:	R2561		RunNo:	2561				
Prep Date:		Analysis Date:	5/4/2012		SeqNo:	71315	Units:	mg/L		
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Fluoride	0.51	0.10	0.5000	0	101	90	110			
Chloride	4.7	0.50	5.000	0	93.9	90	110			
Nitrogen, Nitrite (As N)	0.96	0.10	1.000	0	96.1	90	110			
Nitrogen, Nitrate (As N)	2.5	0.10	2.500	0	98.0	90	110			
Sulfate	9.5	0.50	10.00	0	94.7	90	110			

Sample ID	1205174-001BMS	SampType:	MS		TestCode:	EPA Method 300.0: Anions				
Client ID:	BatchQC	Batch ID:	R2561		RunNo:	2561				
Prep Date:		Analysis Date:	5/4/2012		SeqNo:	71317	Units:	mg/L		
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Fluoride	1.4	0.10	0.5000	0.9876	91.1	72.9	113			
Chloride	14	0.50	5.000	8.329	103	78	107			
Nitrogen, Nitrite (As N)	0.96	0.10	1.000	0	95.8	77.6	111			
Nitrogen, Nitrate (As N)	6.0	0.10	2.500	3.372	106	82.8	116			
Sulfate	45	0.50	10.00	35.20	102	80.5	119			

Qualifiers:

- */X Value exceeds Maximum Contaminant Level.
- E Value above quantitation range
- J Analyte detected below quantitation limits
- R RPD outside accepted recovery limits
- B Analyte detected in the associated Method Blank
- H Holding times for preparation or analysis exceeded
- ND Not Detected at the Reporting Limit
- RL Reporting Detection Limit

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: **1205153**

14-May-12

Client: New Mexico Copper Corp

Project: Cu Flat

Sample ID **1205174-001BMSD** SampType: **MSD** TestCode: **EPA Method 300.0: Anions**

Client ID: **BatchQC** Batch ID: **R2561** RunNo: **2561**

Prep Date: Analysis Date: **5/4/2012** SeqNo: **71318** Units: **mg/L**

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Fluoride	1.4	0.10	0.5000	0.9876	90.1	72.9	113	0.330	20	
Chloride	13	0.50	5.000	8.329	103	78	107	0.0337	20	
Nitrogen, Nitrite (As N)	0.96	0.10	1.000	0	95.7	77.6	111	0.0653	20	
Nitrogen, Nitrate (As N)	6.0	0.10	2.500	3.372	106	82.8	116	0.00611	20	
Sulfate	45	0.50	10.00	35.20	101	80.5	119	0.199	20	

Qualifiers:

- */X Value exceeds Maximum Contaminant Level.
- E Value above quantitation range
- J Analyte detected below quantitation limits
- R RPD outside accepted recovery limits
- B Analyte detected in the associated Method Blank
- H Holding times for preparation or analysis exceeded
- ND Not Detected at the Reporting Limit
- RL Reporting Detection Limit

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: **1205153**

14-May-12

Client: New Mexico Copper Corp

Project: Cu Flat

Sample ID	**1205170-001D**	SampType:	**DUP**	TestCode:	**EPA 120.1: Specific Conductance**				
Client ID:	**BatchQC**	Batch ID:	**R2646**	RunNo:	**2646**				
Prep Date:		Analysis Date:	**5/7/2012**	SeqNo:	**73516**	Units:	**µmhos/cm**		

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Conductivity	610	0.010						0	20	

Qualifiers:

*/X	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
E	Value above quantitation range	H	Holding times for preparation or analysis exceeded
J	Analyte detected below quantitation limits	ND	Not Detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Detection Limit

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: **1205153**

14-May-12

Client: New Mexico Copper Corp

Project: Cu Flat

Sample ID	**1205005-001A DUP**	SampType: **DUP**			TestCode: **SM4500-H+B: pH**					
Client ID:	**BatchQC**	Batch ID: **R2560**			RunNo: **2560**					
Prep Date:		Analysis Date: **5/3/2012**			SeqNo: **71363**		Units: **pH units**			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
pH	3.92	1.68						0.762		H

Sample ID	**1205120-001B DUP**	SampType: **DUP**			TestCode: **SM4500-H+B: pH**					
Client ID:	**BatchQC**	Batch ID: **R2560**			RunNo: **2560**					
Prep Date:		Analysis Date: **5/3/2012**			SeqNo: **71373**		Units: **pH units**			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
pH	7.73	1.68						0.645		H

Qualifiers:

*/X	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
E	Value above quantitation range	H	Holding times for preparation or analysis exceeded
J	Analyte detected below quantitation limits	ND	Not Detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Detection Limit

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: **1205153**

14-May-12

Client: New Mexico Copper Corp

Project: Cu Flat

Sample ID **1205005-001A MS**	SampType: **MS**	TestCode: **SM2320B: Alkalinity**							
Client ID: **BatchQC**	Batch ID: **R2560**	RunNo: **2560**							
Prep Date:	Analysis Date: **5/3/2012**	SeqNo: **71221**	Units: **mg/L CaCO3**						
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Total Alkalinity (as CaCO3)	ND	20	80.00	0	0	62.6	110			S

Sample ID **1205005-001A MSD**	SampType: **MSD**	TestCode: **SM2320B: Alkalinity**							
Client ID: **BatchQC**	Batch ID: **R2560**	RunNo: **2560**							
Prep Date:	Analysis Date: **5/3/2012**	SeqNo: **71222**	Units: **mg/L CaCO3**						
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Total Alkalinity (as CaCO3)	ND	20	80.00	0	0	59.9	111	0	10	S

Sample ID **1205120-001B MS**	SampType: **MS**	TestCode: **SM2320B: Alkalinity**							
Client ID: **BatchQC**	Batch ID: **R2560**	RunNo: **2560**							
Prep Date:	Analysis Date: **5/3/2012**	SeqNo: **71242**	Units: **mg/L CaCO3**						
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Total Alkalinity (as CaCO3)	360	20	80.00	299.4	70.9	62.6	110			

Sample ID **1205120-001B MSD**	SampType: **MSD**	TestCode: **SM2320B: Alkalinity**							
Client ID: **BatchQC**	Batch ID: **R2560**	RunNo: **2560**							
Prep Date:	Analysis Date: **5/3/2012**	SeqNo: **71243**	Units: **mg/L CaCO3**						
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Total Alkalinity (as CaCO3)	350	20	80.00	299.4	67.1	59.9	111	0.869	10	

Qualifiers:

- */X Value exceeds Maximum Contaminant Level.
- E Value above quantitation range
- J Analyte detected below quantitation limits
- R RPD outside accepted recovery limits
- B Analyte detected in the associated Method Blank
- H Holding times for preparation or analysis exceeded
- ND Not Detected at the Reporting Limit
- RL Reporting Detection Limit

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: **1205153**

14-May-12

Client: New Mexico Copper Corp

Project: Cu Flat

Sample ID	**MB-1832**	SampType: **MBLK**			TestCode: **SM2540C MOD: Total Dissolved Solids**				
Client ID:	**PBW**	Batch ID: **1832**			RunNo: **2634**				
Prep Date:	**5/7/2012**	Analysis Date: **5/8/2012**			SeqNo: **73329**	Units: **mg/L**			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Total Dissolved Solids	ND	20.0								

Sample ID	**LCS-1832**	SampType: **LCS**			TestCode: **SM2540C MOD: Total Dissolved Solids**				
Client ID:	**LCSW**	Batch ID: **1832**			RunNo: **2634**				
Prep Date:	**5/7/2012**	Analysis Date: **5/8/2012**			SeqNo: **73330**	Units: **mg/L**			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Total Dissolved Solids	1,020	20.0	1,000	0	102	80	120			

Sample ID	**1205078-002GMS**	SampType: **MS**			TestCode: **SM2540C MOD: Total Dissolved Solids**				
Client ID:	**BatchQC**	Batch ID: **1832**			RunNo: **2634**				
Prep Date:	**5/7/2012**	Analysis Date: **5/8/2012**			SeqNo: **73337**	Units: **mg/L**			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Total Dissolved Solids	4,890	20.0	1,000	3,791	110	80	120			

Sample ID	**1205078-002GMSD**	SampType: **MSD**			TestCode: **SM2540C MOD: Total Dissolved Solids**				
Client ID:	**BatchQC**	Batch ID: **1832**			RunNo: **2634**				
Prep Date:	**5/7/2012**	Analysis Date: **5/8/2012**			SeqNo: **73338**	Units: **mg/L**			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Total Dissolved Solids	4,930	20.0	1,000	3,791	114	80	120	0.733	20	

Qualifiers:

- */X Value exceeds Maximum Contaminant Level.
- E Value above quantitation range
- J Analyte detected below quantitation limits
- R RPD outside accepted recovery limits
- B Analyte detected in the associated Method Blank
- H Holding times for preparation or analysis exceeded
- ND Not Detected at the Reporting Limit
- RL Reporting Detection Limit

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: **1205153**

14-May-12

Client: New Mexico Copper Corp

Project: Cu Flat

Sample ID	MB-1808	SampType:	MBLK	TestCode:	SM 2540D: TSS					
Client ID:	PBW	Batch ID:	1808	RunNo:	2606					
Prep Date:	5/4/2012	Analysis Date:	5/4/2012	SeqNo:	72551	Units:	mg/L			

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Suspended Solids	ND	4.0								

Sample ID	LCS-1808	SampType:	LCS	TestCode:	SM 2540D: TSS					
Client ID:	LCSW	Batch ID:	1808	RunNo:	2606					
Prep Date:	5/4/2012	Analysis Date:	5/4/2012	SeqNo:	72552	Units:	mg/L			

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Suspended Solids	94	4.0	96.60	0	97.3	82.9	110			

Sample ID	1205122-001BDUP	SampType:	DUP	TestCode:	SM 2540D: TSS					
Client ID:	BatchQC	Batch ID:	1808	RunNo:	2606					
Prep Date:	5/4/2012	Analysis Date:	5/4/2012	SeqNo:	72556	Units:	mg/L			

Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Suspended Solids	ND	4.0						0	15	

Qualifiers:

*/X	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
E	Value above quantitation range	H	Holding times for preparation or analysis exceeded
J	Analyte detected below quantitation limits	ND	Not Detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Detection Limit

Chain-of-Custody Record

Client: NMCC

Mailing Address: 2425 San Pedro NE Ste. 100
Albuquerque, NM

Phone #: 505.400.1925

email or Fax#:

QA/QC Package:
☐ Standard ☐ Level 4 (Full Validation)

Accreditation
☐ NELAP ☐ Other _____
☐ EDD (Type) _____

Turn-Around Time: Need Results May 11
☐ Standard ☒ Rush

Project Name: Cu Flat

Project #: Production Well Sampling

Project Manager: Katie Kemmer

Sampler: CMC

On Ice: ☐ Yes ☐ No

Sample Temperature: 1.7

HALL ENVIRONMENTAL ANALYSIS LABORATORY
www.hallenvironmental.com
4901 Hawkins NE - Albuquerque, NM 87109
Tel. 505-345-3975 Fax 505-345-4107

Date	Time	Matrix	Sample Request ID	Container Type and #	Preservative Type	HEAL No. 1205135
5.2.12	14:30	H_2O	PW-3	500	none	-001
				125	H_2SO_4	-001
				125	HNO_3 filter	-001
				500	HNO_3	-001
				500	NaOH	-001

Analysis Request

BTEX + MTBE + TMB's (8021)	BTEX + MTBE + TPH (Gas only)	TPH Method 8015B (Gas/Diesel)	TPH (Method 418.1)	EDB (Method 504.1)	8310 (PNA or PAH)	RCRA 8 Metals	Anions (F,Cl,NO_3,NO_2,PO_4,SO_4)	8081 Pesticides / 8082 PCB's	8260B (VOA)	8270 (Semi-VOA)	See attached list					Air Bubbles (Y or N)
											X					
											X					

Date	Time	Relinquished by	Received by	Date	Time
5-3-12	8:35			05/03/12	0835
Date:	Time:	Relinquished by:	Received by:	Date	Time

Remarks: Please add Hardness per Andy of Kahn
Need Results by May 11 5/3
Please email to: Kemmer@themacresourcesgroup.com

If necessary, samples submitted to Hall Environmental may be subcontracted to other accredited laboratories. This serves as notice of this possibility. Any sub-contracted data will be clearly notated on the analytical report.

02467

HALL ENVIRONMENTAL ANALYSIS LABORATORY

Hall Environmental Analysis Laboratory
4901 Hawkins NE
Albuquerque, NM 87109
TEL: 505-345-3975 FAX: 505-345-4107
Website: www.hallenvironmental.com

Sample Log-In Check List

Client Name: NEW MEXICO COPPER CORP Work Order Number: 1205153

Received by/date: AT 05/03/12

Logged By: **Anne Thorne** 5/3/2012 8:35:00 AM Anne Thorne

Completed By: **Anne Thorne** 5/3/2012 Anne Thorne

Reviewed By: AT 05/03/12

Chain of Custody

1. Were seals intact?	Yes ☐	No ☐	Not Present ☑
2. Is Chain of Custody complete?	Yes ☑	No ☐	Not Present ☐
3. How was the sample delivered?	Client		

Log In

4. Coolers are present? (see 19. for cooler specific information)	Yes ☑	No ☐	NA ☐
5. Was an attempt made to cool the samples?	Yes ☑	No ☐	NA ☐
6. Were all samples received at a temperature of >0° C to 6.0°C	Yes ☑	No ☐	NA ☐
7. Sample(s) in proper container(s)?	Yes ☑	No ☐	
8. Sufficient sample volume for indicated test(s)?	Yes ☑	No ☐	
9. Are samples (except VOA and ONG) properly preserved?	Yes ☑	No ☐	
10. Was preservative added to bottles?	Yes ☐	No ☑	NA ☐
11. VOA vials have zero headspace?	Yes ☐	No ☐	No VOA Vials ☑
12. Were any sample containers received broken?	Yes ☐	No ☑	
13. Does paperwork match bottle labels? (Note discrepancies on chain of custody)	Yes ☑	No ☐	
14. Are matrices correctly identified on Chain of Custody?	Yes ☑	No ☐	
15. Is it clear what analyses were requested?	Yes ☑	No ☐	
16. Were all holding times able to be met? (If no, notify customer for authorization.)	Yes ☑	No ☐	

# of preserved bottles checked for pH: 3 1 (<2 or >12 unless noted)

Adjusted? _____

Checked by: AT 05/03/12

Special Handling (if applicable)

17. Was client notified of all discrepancies with this order? Yes ☐ No ☐ NA ☑

Person Notified: _____ Date _____

By Whom: _____ Via: ☐ eMail ☐ Phone ☐ Fax ☐ In Person

Regarding: _____

Client Instructions: _____

18. Additional remarks:

19. **Cooler Information**

Cooler No	Temp °C	Condition	Seal Intact	Seal No	Seal Date	Signed By
1	1.6	Good	Not Present			

Table 9-3

Analytical Parameters and Analysis Methods for Groundwater Samples

Analytical Parameter	Analysis Method	Lab Detection Limit (mg/L unless noted)
Anions		
Fluoride	EPA Method 300.0	0.1
Chloride	EPA Method 300.0	0.1
Nitrogen, Nitrite (as N)	EPA Method 300.0	0.1
Nitrogen, Nitrate (as N)	EPA Method 300.0	0.1
Sulfate	EPA Method 300.0	0.5
Dissolved Metals		
Aluminum	EPA Method 200.7	0.02
Antimony	EPA Method 200.8	0.005
Arsenic	EPA Method 200.8	0.02
Barium	EPA Method 200.7	0.002
Beryllium	EPA Method 200.7	0.002
Boron	EPA Method 200.7	0.04
Cadmium	EPA Method 200.7	0.002
Calcium	EPA Method 200.7	0.50
Chromium	EPA Method 200.7	0.006
Cobalt	EPA Method 200.7	0.006
Copper	EPA Method 200.7	0.0003
Iron	EPA Method 200.7	0.02
Lead	EPA Method 200.7	0.005
Magnesium	EPA Method 200.7	0.50
Manganese	EPA Method 200.7	0.002
Mercury	EPA Method 7470 CVAA	0.0002
Molybdenum	EPA Method 200.7	0.008
Nickel	EPA Method 200.7	0.01
Potassium	EPA Method 200.7	1.0
Selenium	EPA Method 200.8	0.02
Silicon	EPA Method 200.7	0.08
Silver	EPA Method 200.7	0.005
Sodium	EPA Method 200.7	0.5

Analytical Parameter	Analysis Method	Lab Detection Limit (mg/L unless noted)
Thallium	EPA Method 200.7	0.01
~~Titanium~~	~~EPA Method 200.7~~	~~0.005~~
Uranium	EPA Method 200.8	0.01
Vanadium	EPA Method 200.7	0.005
Zinc	EPA Method 200.7	0.005
Solids		
Total Suspended Solids (TSS)	SM 2540D	1.0 µg/L
Total Dissolved Solids (TDS)	SM 2540C	10
Alkalinity		
Alkalinity, total (as $CaCO_3$)	SM 2320B	20
Carbonate	SM 2320B	20
Bicarbonate	SM 2320B	20
Other		
pH	150.1	12.45
Specific Conductance	120.1	0.01 µS/cm
Cyanide	Kelada-01	0.005

Note: NA = not applicable as sample will not be analyzed for a given parameter.

Vollbrecht, Kurt, NMENV

From: Hom, Anthony [ahom@blm.gov]
Sent: Wednesday, June 27, 2012 10:53 AM
To: Katie Emmer; Denise Weston (dweston@bhinc.com)
Cc: Smith, Michael A; Seum, Edward R; Vollbrecht, Kurt, NMENV; Haywood, Doug; Jens Deichmann (jdeichmann@themacresourcesgroup.com)
Subject: RE: Shapefiles For BLM

Katie/Denise,
We met this morning, and we've determined that, so long as NMCC does not have to do any new ground disturbing activity to use the existing well (Greyback Well), we can probably CX and amend the monitoring well ROW to authorize its use. If it needs to be drilled, or cleared in any way we won't be able to do this.

The 2 new wells will need to be addressed in the EIS, as it is clear that these are needed for the discharge permit/abatement plan. BLM would amend the monitoring well ROW to include the two new wells, after the ROD is signed.

For the location of the 3 wells, whatever Doug directs you to do will be sufficient for me.

All of the monitoring wells on BLM will remain authorized under ROW, even after the MPO is approved.

Thanks, and if you have any questions, just give me a call.

Anthony Hom
Realty Specialist
US Bureau of Land Management
Las Cruces District Office
Las Cruces, New Mexico
Office: 575-525-4331
Cell: 575-202-8841

From: Katie Emmer [mailto:kemmer@themacresourcesgroup.com]
Sent: Wednesday, June 27, 2012 8:56 AM
To: Hom, Anthony
Subject: RE: Shapefiles For BLM

Thanks. I had a conversation with Kurt Vollbrecht yesterday afternoon so he gave me a head's up about some of the things BLM has to consider as well as NMED's position. We appreciate your time and will look forward to hearing from you.

From: Hom, Anthony [mailto:ahom@blm.gov]
Sent: Wednesday, June 27, 2012 8:55 AM
To: Katie Emmer; Haywood, Doug; Smith, Michael A
Cc: 'Denise Weston'; Jens Deichmann
Subject: RE: Shapefiles For BLM

Katie,
I'm actually here...just not an early bird like Doug (his day is usually ½ over when I get in) – ha, ha!

We're going to meet with Edward today about how to proceed with authorization of these monitoring wells. We'll give you some rational direction, hopefully by end of the day.

Thanks.

Anthony Hom
Realty Specialist
US Bureau of Land Management
Las Cruces District Office
Las Cruces, New Mexico
Office: 575-525-4331
Cell: 575-202-8841

From: Katie Emmer [mailto:kemmer@themacresourcesgroup.com]
Sent: Wednesday, June 27, 2012 8:26 AM
To: Haywood, Doug; Smith, Michael A; Hom, Anthony
Cc: 'Denise Weston'; Jens Deichmann
Subject: FW: Shapefiles For BLM

Hi Doug,

Thanks for the head's up about Anthony being out and you being gone from this afternoon through July 3. I've attached a pdf of a map that shows the wells we're interested in, as well as the associated shapefiles we sent Anthony.

We're interested in establishing the BLM land ownership line near Proposed Wells A and B in T15S R6W, Section 31 and near GWQ-3 in T15S R7W Section 25. The attached pdf map is a little busy but it does show these three wells. I hope this is helpful. Please call me with any questions or concerns.

Thank you for your assistance.

Katie
505-400-7925

No virus found in this message.
Checked by AVG - www.avg.com
Version: 2012.0.2180 / Virus Database: 2437/5096 - Release Date: 06/27/12

Vollbrecht, Kurt, NMENV

From: Katie Emmer [kemmer@themacresourcesgroup.com]
Sent: Tuesday, July 03, 2012 2:42 PM
To: Hom, Anthony; Haywood, Doug; Dave Henney
Cc: Jens Deichmann; Smith, Michael A; Denise Weston (dweston@bhinc.com); Vollbrecht, Kurt, NMENV; Steve Raugust
Subject: RE: Stage 1 Abatement
Attachments: 28 June 2012 Coop Agency Mtg Notes.pdf

Hello All,

I've attached our meeting notes from the cooperating agency meeting on 28 June; this may help fill in some gaps on topics that Dave Henney couldn't hear over the phone.

I'd also like to clarify what we understand to be our current position on the Stage I Abatement Plan.

As noted in the meeting notes, the NMED approved a Stage I Abatement Plan that calls for one or two new monitoring wells to the east of the existing tailing dam to characterize the eastern extent of a known ground water plume. (The Stage I also calls for characterization work at the pit lake and in surrounding wells, for which NMCC does not need BLM access because the wells are on private land, and for characterization work down gradient of existing waste rock piles. NMCC would need BLM access to one well (GWQ-3) to complete monitoring down gradient of waste rock piles according to the plan).

During the meeting, we discussed BLM's latest email that stated that the proposed monitoring wells are clearly tied to the abatement plan and the discharge permit and therefore "the 2 new wells will need to be addressed in the EIS" and not drilled until after the ROD comes out.

Kurt Vollbrecht had spoken with Mike Smith about this topic. Kurt indicated that the NMED sees the proposed wells as necessary but not urgent. If the BLM would prefer to wait to drill these wells until after the ROD comes out, NMED could wait now and then would likely make these wells a condition of a discharge permit in addition to monitoring wells for Stage I characterization once access is secured. Kurt indicated that he sees NMCC as responsible for this characterization and abatement whether the mine is built or not and also said the wells do not affect the NMED's ability to issue the discharge permit.

Kurt indicated that he will look at the other two pieces of the Stage I Abatement Plan (monitoring at and around the pit lake and monitoring down gradient from waste rock piles) and communicate with NMCC if/how NMED might want these pieces to proceed even while the proposed monitoring wells are delayed. yes

We left the meeting with the understanding that the drilling of these monitoring wells will be postponed but we may receive directive from NMED on going forward on other characterization work, or all characterization work may be postponed. If NMED would like the other characterization work to proceed, NMCC would approach BLM about an amendment to an existing right of way to monitor wells to allow ground water monitoring at GWQ-3, hopefully through a categorical exclusion. We do not know if or how Mangi might go about addressing the proposed monitoring wells in the EIS process.

I hope these clarifications on our understanding as well as the attached meeting notes elucidate the current status of the Stage I Abatement Plan work. We do not plan to request access to drill proposed monitoring wells east of the tailing dam at this time. If directed by NMED, we may request access to GWQ-3 for groundwater monitoring in the future.

If you have any questions or corrections, please let us know.

Best regards,

Katie Emmer
Project Scientist
THEMAC
RESOURCES
Copper Flat Mine

Mobile: 505.400.7925
Office phone: 505.830.6919
www.themacresourcesgroup.com

From: Hom, Anthony [mailto:ahom@blm.gov]
Sent: Tuesday, July 03, 2012 9:10 AM
To: Haywood, Doug; Dave Henney
Cc: Jens Deichmann; Smith, Michael A; Katie Emmer; Denise Weston (dweston@bhinc.com); Vollbrecht, Kurt, NMENV (kurt.vollbrecht@state.nm.us)
Subject: RE: Stage 1 Abatement

Dave/Doug,
NMCC is formulating a proposal to amend an existing BLM ROW grant (which currently covers about 10 existing monitoring wells), to add a few more ground water monitoring wells. The three monitoring wells they're proposing to add are required by NMED to: 1) monitor existing conditions of the groundwater as relates to some existing tailings 2) monitor during mining operation 3) be used in the abatement plan.

BLM has only had pre-application discussions with NMCC about these, so aside from well locations, this is all I know. I've cc'd NMCC, and Kurt Vollbrecht with NMED to correct this explanation, if needed.

Hope this helps. Thanks.

Anthony Hom
Realty Specialist
US Bureau of Land Management
Las Cruces District Office
Las Cruces, New Mexico
Office: 575-525-4331
Cell: 575-202-8841

From: Haywood, Doug
Sent: Tuesday, July 03, 2012 7:35 AM
To: Dave Henney
Cc: Hom, Anthony; jdeichmann@themacresourcesgroup.com
Subject: RE: Stage 1 Abatement

Dave,

I will have Anthony get with you on this.

Thanks,
Douglas Haywood
BLM Project Manager
575-525-4498

Vollbrecht, Kurt, NMENV

From: Katie Emmer [kemmer@themacresourcesgroup.com]
Sent: Tuesday, July 03, 2012 2:42 PM
To: Hom, Anthony; Haywood, Doug; Dave Henney
Cc: Jens Deichmann; Smith, Michael A; Denise Weston (dweston@bhinc.com); Vollbrecht, Kurt, NMENV; Steve Raugust
Subject: RE: Stage 1 Abatement
Attachments: 28 June 2012 Coop Agency Mtg Notes.pdf

Hello All,

I've attached our meeting notes from the cooperating agency meeting on 28 June; this may help fill in some gaps on topics that Dave Henney couldn't hear over the phone.

I'd also like to clarify what we understand to be our current position on the Stage I Abatement Plan.

As noted in the meeting notes, the NMED approved a Stage I Abatement Plan that calls for one or two new monitoring wells to the east of the existing tailing dam to characterize the eastern extent of a known ground water plume. (The Stage I also calls for characterization work at the pit lake and in surrounding wells, for which NMCC does not need BLM access because the wells are on private land, and for characterization work down gradient of existing waste rock piles. NMCC would need BLM access to one well (GWQ-3) to complete monitoring down gradient of waste rock piles according to the plan).

During the meeting, we discussed BLM's latest email that stated that the proposed monitoring wells are clearly tied to the abatement plan and the discharge permit and therefore "the 2 new wells will need to be addressed in the EIS" and not drilled until after the ROD comes out.

Kurt Vollbrecht had spoken with Mike Smith about this topic. Kurt indicated that the NMED sees the proposed wells as necessary but not urgent. If the BLM would prefer to wait to drill these wells until after the ROD comes out, NMED could wait now and then would likely make these wells a condition of a discharge permit in addition to monitoring wells for Stage I characterization once access is secured. Kurt indicated that he sees NMCC as responsible for this characterization and abatement whether the mine is built or not and also said the wells do not affect the NMED's ability to issue the discharge permit.

Kurt indicated that he will look at the other two pieces of the Stage I Abatement Plan (monitoring at and around the pit lake and monitoring down gradient from waste rock piles) and communicate with NMCC if/how NMED might want these pieces to proceed even while the proposed monitoring wells are delayed.

We left the meeting with the understanding that the drilling of these monitoring wells will be postponed but we may receive directive from NMED on going forward on other characterization work, or all characterization work may be postponed. If NMED would like the other characterization work to proceed, NMCC would approach BLM about an amendment to an existing right of way to monitor wells to allow ground water monitoring at GWQ-3, hopefully through a categorical exclusion. We do not know if or how Mangi might go about addressing the proposed monitoring wells in the EIS process.

I hope these clarifications on our understanding as well as the attached meeting notes elucidate the current status of the Stage I Abatement Plan work. We do not plan to request access to drill proposed monitoring wells east of the tailing dam at this time. If directed by NMED, we may request access to GWQ-3 for groundwater monitoring in the future.

If you have any questions or corrections, please let us know.

Best regards,

Katie Emmer
Project Scientist
THEMAC RESOURCES
Copper Flat Mine

Mobile: 505.400.7925
Office phone: 505.830.6919
www.themacresourcesgroup.com

From: Hom, Anthony [mailto:ahom@blm.gov]
Sent: Tuesday, July 03, 2012 9:10 AM
To: Haywood, Doug; Dave Henney
Cc: Jens Deichmann; Smith, Michael A; Katie Emmer; Denise Weston (dweston@bhinc.com); Vollbrecht, Kurt, NMENV (kurt.vollbrecht@state.nm.us)
Subject: RE: Stage 1 Abatement

Dave/Doug,
NMCC is formulating a proposal to amend an existing BLM ROW grant (which currently covers about 10 existing monitoring wells), to add a few more ground water monitoring wells. The three monitoring wells they're proposing to add are required by NMED to: 1) monitor existing conditions of the groundwater as relates to some existing tailings 2) monitor during mining operation 3) be used in the abatement plan.

BLM has only had pre-application discussions with NMCC about these, so aside from well locations, this is all I know. I've cc'd NMCC, and Kurt Vollbrecht with NMED to correct this explanation, if needed.

Hope this helps. Thanks.

Anthony Hom
Realty Specialist
US Bureau of Land Management
Las Cruces District Office
Las Cruces, New Mexico
Office: 575-525-4331
Cell: 575-202-8841

From: Haywood, Doug
Sent: Tuesday, July 03, 2012 7:35 AM
To: Dave Henney
Cc: Hom, Anthony; jdeichmann@themacresourcesgroup.com
Subject: RE: Stage 1 Abatement

Dave,

I will have Anthony get with you on this.

Thanks,
Douglas Haywood
BLM Project Manager
575-525-4498

THEMAC RESOURCES

Cooperating Agencies Meeting, June 28, 2012
Attendance:
MMD: DJ Ennis, Holland Shepherd
NMCC: Jens Deichmann, Steve Raugust, Katie Emmer
NMED: Kurt Vollbrecht
NMOSE: Kevin Meyers
One the phone: Mangi- David Henney, NM Air Quality Bureau: Elizabeth Bisby Kehn

1. EIS D.Henney: Mangi is working on the affected environment, Mangi Specialists have contacted their BLM counterparts.
   A call with LWA is scheduled for 9 July
   Mangi is internally working to minimize overlap between groundwater, surface water, geology and other topics to cover everything just once.
   Received response to Data Validation Report, reviewing.
   EA106 report was received in May, Kathy indicated they are waiting for some revisions but they will write it up as they have it now and revise as necessary
   DBSA has been talking to NMOSE about water rights, something is still under review, a question of quantity with a difference of about 1,000 AF
   K.Meyers: Understands there is some change from the declaration and a field check that added about 900 AF, check with district IV
   S.Raugust: This is a difference that has to do with ownership, all of the water right is under LRG 4652, it's just Frost and Gray had 6,462 AF/Yr and HydroResources had about 1,019 AF/Yr (922 for LRG 4652 and 97 for LRG 4654) the LRG 4652 points of diversion were unzipped after Quintana and NMCC has recombined the LRG 4652 declarations through purchases, but the total should be around 7,481AF.
   D.Henney: if you could clarify with J.Kutz or P.Shuh at DBSA
   J.Deichmann: Asks for DH to get clarity on how NMCC should contact DBSA, should BLM be on the call?
   D.Henney: That's good, I will check on that.
2. Traffic Analysis:
   D.Henney asks if SS needs to withdraw his request for information from the NMDOT or will DW do that? SS sent DW a list of analyses he wants. J.Deichmann: Believes this list is covered with the possible exception of an accident analysis.
   D.Henney: Notes they asked for additional information on blasting, JD confirms we will get back to him on that when we get it from E.Fidler
   D.Henney: Said some of the figures they have for the EA2 JSAI report are flawed: Figure 4, 5; also the MPO seems to be missing all of the figures for chapter 3 as well as Figure 5-2.
   J.Deichmann: We are working on a modification of the MPO to show the pit geometry and other details with a 25,000 TPD throughput. MPO should not be missing info for Chapter 3 because the MPO was checked page by page. Henney to check to make sure LWA has the correct version of the MPO.

3. Tours:
   JDeichmann: tours occurred on June 12, 13, 14 with good turnouts and conversations. Only two attended the NGO tour on June 12, Sally Smith of GRIP and Dan Lorimier of the Sierra Club. About 50 attended the two public tours. The Hillsboro Water Authority was there and John Hawley answered a lot of good water questions on one of the tours, able to show why dewatering the pit could not adversely impact Hillsboro wells.
   Additional tours will be scheduled next quarter.
4. NMOSE Cooperating Agency Agreement
   K.Meyers: we do have an executed agreement; this was sent to BLM on or near June 11. KM will send to NMCC
   J.Deichmann: We will provide the BDR, any other documents we may have not shared yet.
5. EA#2
   KLE gives update on EA2, the public comment period will end 9 July. BLM will select Alternative A or B.
   KV: Has NMCC NOI and believes they will do a temporary permission; however they only give permission for 120 days so he will wait until he understands from NMCC that a ROW has been obtained and the pumping test is imminent.
6. NPDES permit
   The NPDES will be effective on 1 July
7. NMOSE permits
   SR: Our WR-04 permit to repair/deepen our production wells was submitted in February and we have been advised by Andrea Mendoza that it has been passed to John Romero. This permit is straight forward and routine and we do not understand why this is taking so long. This permit is quickly becoming time critical.
   KM: Will send an email to AM and copy JR to inquire.
   LRG 15291 came in response to NMCC's submission of a permit with 19 conditions, most of which NMCC is aware of and on board about. Condition 19 is concerning to NMCC because it is not anything we have heard about previously. We'd like to clarify and be sure that this condition:
      - Is making the decision to shut the test down a mutual decision with NMOSE and NMCC
      - Define what "suggests a potential impact" actually means – this is too fuzzy
      - Calls for concerned owners of other wells have to collect a trend of data points before a decision to shut the test off can be made

   NMCC would also like to understand what the intention of assigning a 2nd water right number to this permit may be
   KM: You may be sending a letter to state aggrievance, or you may just be sending a letter to clarify your position. He does not know if NMOSE would amend the permit and put the letter in the file or actually re-issue the permit.
   KM: There are a lot of factors that could cause other well owners to perceive an impact.
   Discussion of "impairment" at NMOSE
   NMOSE would be concerned by depletions to the stream, senior water users.
   SR: this model will provide the tools to evaluate potential impacts.
   HS: MMD needs to see the water balance.
8. Stage I Abatement Plan
   KE: Summary of Stage I status: The NMED approved a Stage I abatement plan that calls for one or two new monitoring wells to the east of the existing tailing dam to characterize the eastern extent of a known ground water plume. These wells are on BLM land and NMCC has approached

BLM about applying for a Right of way grant to drill them. BLM has called KV about this proposed action with some concerns.

KV: The BLM concern was that approving a series of actions was going to appear "pre-decisional" and they asked KV if the proposed monitoring wells are time critical. KV told BLM that these wells are necessary but not urgent. The wells would be monitored during operations and since the new tailings dam proposed would take out the existing monitoring wells east of the existed dam, these wells will become tied to the discharge permit during operations. KV left the decision to BLM.

KE: The BLM sent an email stating that the monitoring wells are clearly tied to the abatement plan and the discharge permit and therefore "the 2 new wells will need to be addressed in the EIS" and not drilled until after the ROD comes out. This reasoning surprised us, because we understood from NMED that the wells are necessary for abatement regardless of whether the mine is complete and that Kurt does not consider the abatement plan wells as necessary to issue the discharge permit.

KV: The wells don't affect our ability to issue the discharge permit, but they will likely be a condition of it.

SR: We could monitor the pit and waste rock with a CX from BLM to access the last well proposed for monitoring for which we do not have access. SR is resistant to monitoring at the dam to collect information we already have.

KV: We probably want data from the wells that exist east of the dam before they are taken out.

JD: Kurt, could you email BLM and clarify your position?

KV: I could call or respond to this email

SR: Once we finish the PAP, Golder is tasked with updating the Discharge permit with updated waste management, spill prevention, closure and other associated plans.

KM: You have wells that will be removed with the dam extension, be sure to put in P & A reports with the NMOSE

SR: We've retroactively permitted the wells we have on BLM lands in anticipation of turning in P/A reports. We need to do a similar group retroactive well permit on those left on private lands. Monitoring wells did not require permits at the times when these wells were installed and need file numbers prior to abandonment. NMCC is aware of the OSE well abandonment procedures.

9. MORP:

   SR: The MORP is imminent.

   Public notice: DJE: Public notice goes to the "long list" at submission, and public notice is required again once deemed complete. DJE will get the list to JD. MMD usually sees photocopied certified mail stubs, 4 to a sheet + the affidavits of certification from the newspaper as proof of public notice.

10. Closure/Closeout Plan

    SR: Question re: the difference between the Closure and Closeout Plans

    DJE: Existing mines in Part 5 must submit a Closeout Plan, new mines in Part 6 submit a Reclamation Plan

    KV: NMED our rules call for a Closure Plan for the Discharge Permit.

    KM: Freeport submits a Closure/Closeout Plan to cover both MMD and NMED with the same document because Part 5 applies to them.

11. Air Quality

    JD: Class one is doing our permit application and modeling, this has been held up in a wait for the prefeasibility study. We believe we will still be a minor source. Sent a message to P. Wise to

ask when to request a pre-application meeting. Confirmed with EBK that she will be the one to attend that meeting, not Norma.

12. Next meeting: August 16 at 14:00

Last question from DHenney: There was a public comment asking if the mine would impact nearby springs, do you know of any beyond the hot springs in TorC?
SR: There are warm springs west of the mine. Your geologist can look at this and see the mine is in the Animas Uplift and that those warm springs are fed by water from the Black Range to the west. The mine will not impact them.

From: Dave Henney [mailto:dhenney@mangi.com]
Sent: Thursday, June 28, 2012 3:52 PM
To: Haywood, Doug; jdeichmann@themacresourcesgroup.com
Subject: Stage 1 Abatement

It was difficult or impossible to hear some of the Cooperators meeting attendees if they weren't close to the microphone. So, I was aware of some discussion under the topic of Stage 1 Abatement rlated to ROW access for monitoring wells on BLM property. Further, that BLM has indicated a discussion related to this needs to be in the EIS and some needed action cannot occur until after the ROD is signed. I didn't get enough of the detail at that point to have an understanding and am wondering if there is a document, letter. Email, or ??? that could help me understand what may have to be added to the EIS.

Thanks

Dave

No virus found in this message.
Checked by AVG - www.avg.com
Version: 2012.0.2193 / Virus Database: 2437/5108 - Release Date: 07/03/12

PUBLIC NOTICE

GROUND WATER
JUL 20 2012
BUREAU

COPPER MINE PROJECT
New Mexico Copper Corporation
2424 Louisiana NE, Suite 301
Albuquerque, NM 87110

New Mexico Copper Corporation (NMCC), a wholly-owned subsidiary of THEMAC Resources Group, Ltd., is proposing re-establishment of a poly-metallic mine and processing facility located near Hillsboro, New Mexico. The proposed Project would consist of an open pit mine, flotation mill, tailing storage facility, waste rock disposal area, a low-grade ore stockpile, and ancillary facilities. In most respects, the facilities, disturbance and operations would be similar to the former operation.

The Project is located in Sierra County, New Mexico, approximately 22 miles southwest of Truth or Consequences and five miles northeast of Hillsboro. The general area can be reached by traveling south 15 miles from Truth or Consequences on Interstate Highway 25, then 10 miles west on New Mexico Highway 152. The Project area lies two miles west-northwest from Highway 152. The project area encompasses all or parts of Township 15 South, Range 7 West, Sections, 25, 26, 27, 35, & 36; Township 15 South, Range 6 West, Sections 25, 26, 27, 30, 31, 32, 33, & 34; Township 15 South, Range 5 West, Sections 30 & 31; and Township 16 South, Range 6 West, Section 6.

A Permit Application Package (PAP) consisting of a Baseline Data Report and a Mine Operations and Reclamation Plan (MORP) has been prepared in compliance with 19.10.6 NMAC New Mexico Mining Commission Rules for new mines, and submitted for review to the Mining and Minerals Division (MMD) of the New Mexico Energy, Minerals and Natural Resources Department.

The application is available for public inspection at the MMD Office in Santa Fe, NM, the Hillsboro, NM Public Library, and the Truth or Consequences, NM Public Library. It may also be viewed on the MMD website at www.emnrd.state.nm.us/MMD/MARP/MARPMain Page.htm, by clicking on the Pending Permit Applications link. Interested persons may submit written comments and/or a request for a public hearing on the application to the MMD Director at:

New Mexico Mining and Minerals Division
Fernando Martinez, Division Director
1220 South St. Francis Drive
Santa Fe, New Mexico 87505
(505) 476-3400

All interested persons may submit written comments regarding the application to the Director. Written comments must be received by the Director prior to the close of the hearing record following any public hearing that is held. If no public hearing is held, written comments will be considered only if they are received by the Director within 60 days after the newspaper publication of the notice of the application or within 60 days after the person filing the comment received notice of the application, whichever is later.

Any interested party may request a public hearing on the application. Such a request must be made within thirty (30) days of the date of the newspaper publication of the notice of the application unless the Director determines a longer period in which to make the request is appropriate and such period is specified in the published notice. If a hearing is timely requested, the Director shall set a hearing unless the request is clearly frivolous. The Director may hold a public hearing absent any request. Title 19, Chapter 10 NMAC regulations for public notice and hearing may be viewed at http://www.nmcpr.state.nm.us/nmac/_title19/T19C010.htm.

NOTA PUBLICA

COPPER MINE PROJECT
New Mexico Copper Corporation
2424 Louisiana NE, Suite 301
Albuquerque, NM 87110

La Corporación del Cobre de Nuevo México (NMCC), un filial de entera propiedad del Grupo de Recursos de THEMAC, S.a., propone restablecimiento de una facilidad polietileno-metálico de mina y procesamiento ubicó cerca de Hillsboro, Nuevo México. El Proyecto propuesto consistiría en una mina abierta de hoyo, molino de flotación, siguiendo instalación de almacenaje, área de disposición de piedra de desecho, una reservas de baja calidad de mineral, y las facilidades adicionales. En la mayoría de los respeto, las facilidades, el alboroto y las operaciones serían semejantes a la operación anterior. El Proyecto es ubicado en el Condado de Sierra, Nuevo México, aproximadamente 22 suroeste de millas de la Verdad o Consecuencias y de cinco noreste de millas de Hillsboro. El área general puede ser alcanzada viajes al sur 15 millas de la Verdad o Consecuencias en la Carretera Interestatal 25, entonces 10 oeste de millas en la Carretera de Nuevo México 152. El área del Proyecto está dos oesnoroeste de millas de la Carretera 152. El área del proyecto abarca todo o las partes de Municipio 15 del sur, la Gama 7 Occidental, las Secciones, 25, 26, 27, 35, & 36; Municipio 15 del sur, la Gama 6 Occidental, las Secciones 25, 26, 27, 30, 31, 32, 33, & 34; Municipio 15 del sur, la Gama 5 Occidental, las Secciones 30 & 31; y el Municipio 16 del sur, la Gama 6 Occidental, la Sección 6.

Un Paquete de la Aplicación del Permiso (PAPILLA) consistiendo en un Informe de Datos de Línea de fondo y un Mío Operaciones y Recuperación Planean (MORP) ha sido preparado en conformidad con NMAC 19.10.6 Nuevo México que Mina Reglas de Comisión para nuevas minas, y sometido para la revisión a la Minería y la División de Minerales (MMD) de la Energía de Nuevo México, los Minerales y el Departamento Natural de Recursos.

La aplicación está disponible para la inspección pública en la Oficina de MMD en Santa Fe, en NM, en el Hillsboro, en NM Biblioteca pública, y en la Verdad o las Consecuencias, NM Biblioteca pública. También puede ser visto en el sitio web de MMD en Página.htm de www.emnrd.state.nm.us/MMD/MARP/MARPMain Page.htm, para hacer clic en las Aplicaciones Pendientes de Permiso ligan. Las personas interesadas pueden someterse comentarios escritos y/o una petición para una audición del público en la aplicación al Director de MMD en:

New Mexico Mining and Minerals Division
Fernando Martinez, Division Director
1220 South St. Francis Drive
Santa Fe, New Mexico 87505
(505) 476-3400

Todas las personas interesadas pueden someterse comentarios escritos con respecto a la aplicación al Director. Los comentarios escritos deben ser recibidos por el Director antes del fin del registro de oído que sigue cualquier audición del público que es tenido. Si ninguna audición pública es tenida, es escrita comentarios serán considerados sólo si son recibidos por el Director dentro de 60 días después de la publicación periodística de la nota de la aplicación o dentro de 60 días después de la persona que archiva el comentario nota recibida de la aplicación, el que es más tarde.

Algún partido interesado puede solicitar una audición del público en la aplicación. Tal petición debe ser hecha dentro de treinta (30) días de la fecha de la publicación periodística de la nota de la aplicación a menos que el Director determine un período más largo en el que hacer la petición es apropiado y tal período es especificado en la nota publicada. Si una audición es oportuna solicitado, el Director pondrá una audición a menos que la petición sea claramente frívola. El Director puede tener una audición del público ausente cualquier petición. El título 19, el Capítulo 10 regulaciones de NMAC para la nota y el oído públicos pueden ser vistas en http://www.nmcpr.state.nm.us/nmac/_title19/T19C010.htm.

State of New Mexico
ENVIRONMENT DEPARTMENT

Ground Water Quality Bureau

Harold Runnels Building
1190 Saint Francis Drive, PO Box 5469
Santa Fe, NM 87502-5469
Telephone (505) 827-2855 Fax (505) 827-2965
www.nmenv.state.nm.us

SUSANA MARTINEZ
Governor
JOHN A. SANCHEZ
Lieutenant Governor



CERTIFIED MAIL—RETURN RECEIPT REQUESTED

August 13, 2012

Mr. Jens Deichmann
New Mexico Copper Corporation
2424 Louisiana Blvd, Suite 301
Albuquerque, NM 87110

RE: Temporary Permission to Discharge, Copper Flat Production Well field Pump Test

Dear Mr. Deichmann:

The New Mexico Environment Department ("NMED") received a "Notice of Intent" ("NOI") from New Mexico Copper Corporation (NMCC) dated June 20, 2012. This NOI proposes to discharge up to 150 acre feet of water from a pump test of approximately 16 days duration. Two locations are proposed for the discharge, including an unused gravel quarry or directly to Grayback Arroyo pursuant to NPDES Permit No. NM0031101. The location of the proposed gravel quarry discharge is several hundred yards west of I-25 in Section 2, T16S, R5W. Depth to ground water beneath the gravel quarry is approximately 60 feet below ground surface (bgs). The proposed location of the discharge in Grayback Arroyo is several miles further to the west in Section 31, T15S, R5W. Depth to ground water beneath the Grayback Arroyo discharge location is approximately 250 feet bgs.

NMCC is proposing to discharge water from 2 to 3 production wells (PW-1 and PW-3 primary, PW-2 backup) associated with the proposed Copper Flat Mine. The production wells were previously used in conjunction with mining and milling operations at the Copper Flat Mine in the early 1980's. Water quality data from that time frame indicates that ground water standards as set forth in Section 20.6.2.3103 NMAC of the Water Quality Control Commission Regulations (WQCC) were met. Recent ground water quality data shows that fluoride levels in well PW-3 slightly exceeds the ground water standard for fluoride. The discharge from the pump test will blend water from two wells (PW-1 and PW-3) and the final water quality discharged is not expected to exceed WQCC standards. Furthermore, the first aquifer present beneath both discharge

locations is the same aquifer from which the water is being withdrawn. NMCC shall provide NMED with the results of any sampling required pursuant to their NPDES permit.

NMED has determined that a Discharge Permit is not required for this discharge as described in the NOI, and grants permission to NMCC to discharge pump test water in accordance with 20.6.2.3106.B NMAC, which states: "[F]or good cause shown the secretary [of the New Mexico Environment Department] may allow such person to discharge without a discharge permit for a period not to exceed 120 days." The period of this Temporary Permission begins on the first day of discharge and ends 120 consecutive days thereafter. NMCC, or its representative, shall notify NMED of the beginning and ending dates of discharge under this Temporary Permission.

NMCC is advised that nothing in this Temporary Permission shall be construed in any way as relieving NMCC of its obligation to comply with all applicable federal, state, and local laws, regulations, permits, or orders (20.6.2 NMAC). Additionally the approval of this Temporary Permission to discharge does not relieve NMCC of liability if the discharge should result in actual pollution of surface or ground water that may be actionable under other laws and/or regulations (20.6.2.3109 NMAC).

Please contact Kurt Vollbrecht at (505) 827-0195 if you have any questions.

Sincerely,

Jerry Schoeppner, Chief
Ground Water Quality Bureau
New Mexico Environment Department

JS:kv

copies:
Chris Eustice, MMD
Rich Powell, NMED SWQB
Anthony Hom, BLM Las Cruces District Office, 1800 Marquess Street Las Cruces, NM 88005

Cooperating Agencies - NMCC Meeting
16 August 2012
MMD Conference room
Call in: 760-984-1000, PIN 1087 467

1. EIS status
2. Briefing on recent mine tours - Jens - Ladder Ranch
3. ROWs - Update on EA#2 ROW /aquifer test – new schedule - Katie
4. Impact of delayed aquifer test – revised EIS schedule - Jens
5. Well rehab approval in advance of aquifer test – Awaiting OSE approval - Katie
6. Stage 1 Abatement Plan status – ROW issue - Steve
7. Submittal of MORP, public notice - Steve
8. Foundation excavations – awaiting approval
9. Air quality permit application - Jens
10. Traffic analysis and road condition assessment - Jens
11. Next meeting date

Next Mtg

Sept. 24 @ 1:00 - 3:00

8-16-12 Copper Flat Monthly Mtg

- Pump Test EA
  - FONSI posted on BLM website
  - Allowed 30 day protest period
    - ends Aug 27
  - Comments on FONSI are posted online w/ BLM response
  - Possibly have ROW Sept 15, start well rehab Sept. 17
  - Final report Dec. 21?

- ROD for EIS - Dec. 2013
  DEIS Feb 2013

- Stage I
  proceed w/ monitoring as proposed
  - Pit Lake + Waste Rock
  - Evaluate TI plan - need to make certain have clean valid data set since we will lose these wells

- MORP - will come to NMED for comment next week
  - EE will be short summary that references EIS - Manji will draft

- Foundations... BLM permitting issues
  - may need to re-cover?

State of New Mexico
Energy, Minerals and Natural Resources Department

Susana Martinez
Governor

John Bemis
Cabinet Secretary

Brett F. Woods, Ph.D.
Deputy Cabinet Secretary

Fernando Martinez, Director
Mining and Minerals Division

August 22, 2012

Mr. Jens Deichmann, Project Manager
New Mexico Copper Corporation
2424 Louisiana Blvd., NE, Suite 301
Albuquerque, New Mexico 87110

Re: New Mine Permit Application Determined Administratively Complete; New Mexico Copper Corporation, Permit No. SI027RN, Copper Flat Mine, Sierra County, New Mexico

Dear Mr. Deichmann,

Pursuant to Part 19.10.6.605.A of the New Mexico Mining Act Rules the New Mexico Mining and Minerals Division (MMD) has determined that an application for a New Mine Permit submitted to MMD, on July 17, 2012, by New Mexico Copper Corporation (NMCC) is administratively complete. The New Mine Permit Application proposes to disturb up to 1270 acres of federal and private surface lands within the permit boundaries proposed for development of an open pit copper mine located approximately 5 miles northeast of the community of Hillsboro, in Sierra County New Mexico.

Pursuant to Part 19.10.6.605.B of the New Mexico Mining Act Rules NMCC shall, within 30 days receipt of this letter, in a form approved by the Director of MMD, give public notice of the application pursuant to 19.10.9 of the New Mexico Mining Act Rules. Therefore, and pursuant to 10.10.9.903.I of the New Mexico Mining Act Rules, NMCC shall provide to the Director of MMD timely proof that the notice of this determination has been provided to everyone who has indicated to the applicant in writing that they desire information regarding the application, and to a list maintained by the Director of individuals and organizations who have requested notice of applications.

MMD will now distribute the application to other reviewing agencies and begin technically reviewing the application. If you have any questions, please contact me at 505-476-3437 or Chris Eustice of my staff at 505-476-3438.

Sincerely,

Holland Shepherd, Program Manager
Mining Act Reclamation Program (MARP)
Mining and Minerals Division

Cc: Fernando Martinez, Director, MMD
Chris Eustice, Permit Lead, MMD/MARP
Mine File (SI027RN)